

Section 114 Information Collection Request Emissions Test Report

Holcim (US) Inc.
Ravena Cement Plant
EPA Registry ID: 110070733606
1916 Rte 9W
Ravena, NY 12143
Report No. M234506C





**Section 114 Information Collection Request
Emissions Test Report**

**Holcim (US) Inc.
Ravena Cement Plant
EPA Registry ID: 110070733606
1916 Rte 9W
Ravena, NY 12143**

**Report Submittal Date:
April 8, 2024**

© Copyright 2024
All rights reserved in
Mostardi Platt

Report No. M234506C

TABLE OF CONTENTS

1.0 INTRODUCTION	1
2.0 TEST REQUIREMENTS	2
3.0 QA SPECIFICATIONS AND PROCESS DIAGRAM	4
Table 3-1 QA/QC Specifications.....	4
Figure 3-2 Process Flow Diagram	5
4.0 TEST PROCEDURES	6
4.1 Method 1 Sample and Velocity Traverse Determination	6
4.2 Method 2 Volumetric Flow Rate Determination	6
4.3 Method 3A Oxygen (O ₂) and Carbon Dioxide (CO ₂) Determination.....	6
4.4 Method 26A Hydrogen Fluoride (HF) and Chlorine (Cl ₂) Determination	7
4.5 Method 320 Speciated Flue Gas Concentration Determinations	7
5.0 TEST RESULTS SUMMARIES.....	9
6.0 CERTIFICATION.....	17
APPENDICES	
Appendix A – Plant Operating Data.....	19
Appendix B – Test Section Diagrams.....	32
Appendix C – Sample Train Diagrams	35
Appendix D – Calculation Nomenclature and Formulas.....	39
Appendix E – Laboratory Sample Analysis	49
Appendix F – Reference Method Test Data	58
Appendix G – Calibration Data	93
Appendix H – Gas Cylinder Certifications	123

1.0 INTRODUCTION

Mostardi Platt conducted an air emissions test program for Holcim (US) Inc. at the Ravena Cement Plant located in Ravena, New York. All testing was performed as described in the *Code of Federal Regulations*, Title 40, Part 60, Appendix A (40CFR60), Methods 1, 2, 3A, 4, 26A, and 40CFR63, Appendix A, (40CFR63) Method 320.

The Holcim US Ravena Cement Plant includes a single Kiln (Main Kiln) ~2,000,000 TPY preheater/pre-calciner having an in-line raw mill. Ravena operates a KHD Pyroclone low NO_x precalciner. The kiln system employs a SNCR as needed to control NO_x, has a baghouse fabric filtration, and a wet scrubber system. Emissions exhaust to a common stack. Emission testing was performed at the common stack testing location used for all compliance testing. This site-specific plan calls for testing in these two operational scenarios (mill on and off), as directed in EPA's Request and instructions.

This test program was completed to satisfy the requirements of the United States Environmental Protection Agency (USEPA) Section 114 Information Collection Request for Portland Cement Manufacturing facilities.

The identification of individuals associated with the test program is summarized below:

Location	Address	Contact
Test Coordinator	Holcim (US) Inc. Ravena Cement Plant 1916 US9W Ravena, NY 12143	Alicia Prioleau Area Environmental and Public Affairs Manager (518) 821-9785 Alicia.prioleau@holcim.com
Test Company Representative	Mostardi Platt 888 Industrial Drive Elmhurst, IL 60126	Eric Ehlers VP, Field Operations (630) 993-2100 eehlers@mp-mail.com

2.0 TEST REQUIREMENTS

Testing was performed at the kiln stack. The following table presents a list of the parameters tested, the applicable methodologies utilized, and average test results:

Source	Parameter Tested	Test Results	Method/Regulation Citation
Main Kiln Stack Mill On	Hydrogen Fluoride (HF)	≤ 0.10 ppmvw	USEPA Method 320, 40CFR63, Appendix A
		≤ 0.28 ppmvd @7% O ₂	
		≤ 0.19 lb/hr	
		≤ 0.0010 lb/ton clinker	
	HF ¹	≤ 0.12 ppmvd	Method 26A, 40CFR60, Appendix A
		≤ 0.31 ppmvd @7% O ₂	
		≤ 0.21 lb/hr	
		≤ 0.0011 lb/ton clinker	
	Chlorine (Cl ₂) ¹	≤ 0.03 ppmvd	USEPA Method 26A, 40CFR60, Appendix A
		≤ 0.09 ppmvd @7% O ₂	
		≤ 0.21 lb/hr	
		≤ 0.0011 lb/ton clinker	
	Hydrogen Cyanide (HCN)	1.22 ppmvw	USEPA Method 320, 40CFR63, Appendix A
		3.44 ppmvd @7% O ₂	
		3.17 lb/hr	
		0.0159 lb/ton clinker	
	Oxygen (O ₂)	15.5 % (dry)	USEPA Method 3A, 40CFR60, Appendix A
	Carbon Dioxide (CO ₂)	8.8 % (dry)	USEPA Method 320, 40CFR63, Appendix A
	Moisture (H ₂ O)	9.0 %	USEPA Method 320, 40CFR63, Appendix A
	Cyclonic Flow Determination	PASS	USEPA Method 1, 40CFR60, Appendix A, Section 11.4
	Three-point O ₂ Stratification Determination	< 5 %	USEPA Method 3A, 40CFR60, Appendix A and Method 7E, Section 8.1.2

¹ HF and Cl₂ Method 26A results are reported as the average from Train A and Train B.

Source	Parameter Tested	Test Results	Method/Regulation Citation
Main Kiln Stack Mill Off	Hydrogen Fluoride (HF)	≤ 0.10 ppmvw	USEPA Method 320, 40CFR63, Appendix A
		≤ 0.20 ppmvd @7% O ₂	
		≤ 0.14 lb/hr	
		≤ 0.0007 lb/ton clinker	
	HF ²	≤ 0.17 ppmvd	Method 26A, 40CFR60, Appendix A
		≤ 0.29 ppmvd @7% O ₂	
		≤ 0.21 lb/hr	
		≤ 0.0010 lb/ton clinker	
	Chlorine (Cl ₂) ²	≤ 0.05 ppmvd	USEPA Method 26A, 40CFR60, Appendix A
		≤ 0.08 ppmvd @7% O ₂	
		≤ 0.21 lb/hr	
		≤ 0.0010 lb/ton clinker	
	Hydrogen Cyanide (HCN)	1.52 ppmvw	USEPA Method 320, 40CFR63, Appendix A
		3.08 ppmvd @7% O ₂	
		2.90 lb/hr	
		0.0139 lb/ton clinker	
	Oxygen (O ₂)	13.0 % (dry)	USEPA Method 3A, 40CFR60, Appendix A
	Carbon Dioxide (CO ₂)	12.9 % (dry)	USEPA Method 320, 40CFR63, Appendix A
	Moisture (H ₂ O)	12.9 %	USEPA Method 320, 40CFR63, Appendix A
	Cyclonic Flow Determination	PASS	USEPA Method 1, 40CFR60, Appendix A, Section 11.4
	Three-point O ₂ Stratification Determination	< 5 %	USEPA Method 3A, 40CFR60, Appendix A and Method 7E, Section 8.1.2


² HF and Cl₂ Method 26A results are reported as the average from Train A and Train B.

3.0 QA SPECIFICATIONS AND PROCESS DIAGRAM

Table 3-1 QA/QC Specifications

Parameter	Method	QA/QC Specification	Acceptance Criteria	Actual Result
HCN	320	Method Detection Limit	0.5 ppm	0.2 ppmvw
		SNR	>2500 at 64 scans	2864 (Run 1 Average)
		S Beam	>0.9	1.003 (Run 1 Average)
		Direct HCN Analysis	±5% of tag value	+0.1%
		Dynamic Spike Analysis	≤10% of total sample volume	9.9%
			Spike gas ~twice native concentration or 3-4 ppm addition to native concentration	+4 ppm
			≤±20% of expected value or ≤±0.5 ppm, whichever is less restrictive	≤±20% of expected value
Cl ₂	26A	Residuals	≤±0.3 ppm, or ≤±5% of measured value, whichever is less restrictive	≤±0.3 ppm
		Detection Limit	300 µg	150 µg
		Paired Train Agreement	≤10% Relative Deviation or ≤0.2 ppm, whichever is less restrictive.	≤10% Relative Deviation

Figure 3-2 Process Flow Diagram



4.0 TEST PROCEDURES

All testing, sampling, analytical, and calibration procedures used for this test program were performed as described in the Title 40, *Code of Federal Regulations*, Part 60, Appendix A (40CFR60), Methods 1, 2, 3A, 4, 26A, and 40CFR63, Appendix A, Method 320; and the latest revisions thereof. Where applicable, the *Quality Assurance Handbook for Air Pollution Measurement Systems*, Volume III, Stationary Source Specific Methods, United States Environmental Protection Agency (USEPA) 600/R-94/038c, September 1994 was used to supplement procedures in addition to the appended "Draft General Test Plan".

4.1 Method 1 Sample and Velocity Traverse Determination

Sample points for testing are determined using USEPA Test Method 1, 40CFR60, Appendix A. The characteristics of the measurement location is summarized below.

Sample Point Selection

Test Location	Stack Diameter	Upstream Diameters	Downstream Diameters	Test Parameter	Number of Sampling Points
Main Kiln Stack	17.708'	3.3 Diameters	8.8 Diameters	HF/Cl ₂ (26A)	12
				O ₂ (3A)	3 (stratification)
				HCN/HF/O ₂ (320/3A)	1

A cyclonic flow check was performed in accordance with Section 11.4, which demonstrated it meets the criteria of an average value of less than 20° and therefore is considered to be a suitable testing location for flow rate measurements.

4.2 Method 2 Volumetric Flow Rate Determination

The gas velocity and volumetric flowrate were determined using Method 2, 40CFR60, Appendix A, as an integrated part of the HF/Cl₂ sampling system.

Velocity pressures were determined by traversing the duct with wind tunnel calibrated S-type pitot tube. Temperatures were measured using K-type thermocouples with calibrated digital temperature indicators. The molecular weight and moisture content of the gases were also determined to permit the calculation of the volumetric flowrate.

4.3 Method 3A Oxygen (O₂) and Carbon Dioxide (CO₂) Determination

O₂ and CO₂ concentrations were determined in accordance with Method 3A, 40CFR60, Appendix A and Method 320, 40CFR63, Appendix A, respectively. A Servomex analyzer was used to determine O₂ concentrations while the MKS 2030 analyzer was used to determine CO₂ concentrations. The O₂ instrument has a paramagnetic detector and operates in a nominal range of 0-25%.

A list of calibration gases used and the results of all calibration and other required quality assurance checks are found in the appendix of this report. Copies of calibration gas certifications are also appended.

4.4 Method 26A Hydrogen Fluoride (HF) and Chlorine (Cl₂)

Determination

HF and Cl₂ concentrations and emission rates were determined in accordance with Method 26A, 40CFR60, Appendix A. Paired sampling trains were used to collect the samples. A total of twelve (12) test points were sampled per run on at Main Kiln stack location. The sample was extracted isokinetically from the gas stream and passed through dilute sulfuric acid (0.1N H₂SO₄). HF was collected in the dilute acid. Cl₂ was collected in the dilute sodium hydroxide (0.1N NaOH) solution. The sample train consisted of a Teflon coated nozzle, a heated borosilicate glass probe liner, a Teflon® filter placed on the outlet of the glass probe liner, and six impingers. The first two impingers contained the 0.1N H₂SO₄, the third remained empty (and was recovered with the first two impingers), the fourth and fifth impingers contained the 0.1N NaOH, while the sixth impinger contained silica gel to absorb any remaining moisture. A de-ionized water rinse was performed on each set of impingers, and samples were stored in Nalgene sample containers for transport. The 0.1N H₂SO₄ impinger catch samples were analyzed for HF while the 0.1N NaOH impinger catch samples were analyzed for Cl₂. A method detection limit (MDL) of 150 µg was determined for both HF and Cl₂ using the "Definition and Procedure for the Determination of the Method Detection Limit, Revision 2". All equipment used was calibrated in accordance with the specifications of the method. Calibration data is appended.

Hand recorded field data sheets were reviewed and scans are retained on the Mostardi Platt network. Copies of this data is available upon request.

4.5 Method 320 Speciated Flue Gas Concentration Determinations

The sampling procedures for HCN and HF were performed in accordance with USEPA Method 320, 40CFR63, Appendix A. Data was continuously recorded with a data logging system throughout sampling, with brief interruption to properly label reference spectra.

The average gas effluent concentrations were determined from the average gas concentration displayed by the MKS 2030 analyzer.

All sampling system components were heated to 375°F +/- 25°F, including: stainless steel sample probe, stainless steel calibration tee, in line glass fiber particulate filter, Teflon® sample line, heated head sample pump, and FTIR detector cell. The sample pump distributes the gas sample to the instrument at a steady sample flow rate (+/- 10%). All components of the sampling system are constructed of stainless steel, glass, or Teflon®.

FTIR technology works on the principle that most gases absorb infrared light. This is true for all compounds except for homonuclear diatomic molecules and noble gases such as: N₂, O₂, H₂, He, Ne, and Ar. Vibrations, stretches, bends, and rotations within the bonds of a molecule determine the infrared absorption distinctiveness. The absorption creates a "fingerprint" which is unique for each given compound. The quantity of infrared light absorbed is proportional to the gas concentration. Most compounds have absorbencies at different infrared frequencies, thus allowing the simultaneous analysis of multiple compounds at one time. The FTIR software compares each sample spectrum to a user-selected list of calibration references and concentration data is generated.

FTIR data was collected using an MKS MultiGas 2030 FTIR spectrometer. Data was generated at 0.5 cm^{-1} . Each Spectra was derived from the coaddition of 62-64 scans with a new data point generated approximately every minute. HCN analyte spiking assured the ability of the FTIR to quantify HCN in the presence of effluent gas. All analyte spikes were introduced using an instrument grade stainless steel rotameter. All QA/QC procedures were within the acceptance criteria allowance of the applicable methodology and the "General Test Plan."

5.0 TEST RESULTS SUMMARIES

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Test Method: 26A - Combined Trains

Source Condition	Mill On	Mill On	Mill On	
Date	1/30/24	1/30/24	1/30/24	
Start Time	8:15	9:50	11:25	
End Time	9:30	11:05	12:40	
	Run 1	Run 2	Run 3	Average
Stack Conditions				
Average Gas Velocity, ft/sec	49.127	48.491	48.922	48.847
Gas Volumetric Flow Rate, acfm	725,933	716,534	722,909	721,792
Gas Volumetric Flow Rate, dscfm	571,763	558,443	561,458	563,888
Gas Volumetric Flow Rate, scfm	621,649	613,805	617,215	617,556
Average %CO ₂ by volume, dry basis	8.8	8.9	8.8	8.8
Average %O ₂ by volume, dry basis	15.6	15.4	15.5	15.5
Clinker production, ton/hr	198.7	199.1	199.6	199.1
Hydrogen Fluoride (HF) Emissions				
ppm ≤	0.12	≤ 0.12	≤ 0.12	≤ 0.12
ppm@7%O ₂ ≤	0.32	≤ 0.31	≤ 0.31	≤ 0.31
lb/hr ≤	0.22	≤ 0.21	≤ 0.21	≤ 0.21
lb/ton of clinker ≤	0.0011	≤ 0.0011	≤ 0.0011	≤ 0.0011
Chlorine (Cl₂) Emissions				
ppm ≤	0.03	≤ 0.04	≤ 0.03	≤ 0.03
ppm@7%O ₂ ≤	0.09	≤ 0.09	≤ 0.09	≤ 0.09
lb/hr ≤	0.21	≤ 0.22	≤ 0.21	≤ 0.21
lb/ton of clinker ≤	0.0011	≤ 0.0011	≤ 0.0011	≤ 0.0011

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Test Method: 26A - A Train

Source Condition	Mill On	Mill On	Mill On	
Date	1/30/24	1/30/24	1/30/24	
Start Time	8:15	9:50	11:25	
End Time	9:30	11:05	12:40	
	Run 1A	Run 2A	Run 3A	Average
Stack Conditions				
Average Gas Temperature, °F	152.3	151.1	154.6	152.7
Flue Gas Moisture, percent by volume	9.1%	8.9%	9.4%	9.1%
Average Flue Pressure, in. Hg	29.71	29.71	29.71	29.71
Gas Sample Volume, dscf	47.397	46.444	46.672	46.838
Average Gas Velocity, ft/sec	49.158	48.137	48.672	48.656
Gas Volumetric Flow Rate, acfm	726,395	711,309	719,217	718,974
Gas Volumetric Flow Rate, dscfm	565,178	556,249	555,941	559,123
Gas Volumetric Flow Rate, scfm	621,960	610,290	613,560	615,270
Average %CO ₂ by volume, dry basis	8.8	8.9	8.8	8.8
Average %O ₂ by volume, dry basis	15.6	15.4	15.5	15.5
Isokinetic Variance	101.0	100.6	101.1	100.9
Hydrogen Fluoride (HF) Emissions				
ug of sample collected	≤ 150.00	≤ 150.00	≤ 150.00	≤ 150.00
ppm	≤ 0.13	≤ 0.14	≤ 0.14	≤ 0.14
Chlorine (Cl₂) Emissions				
ug of sample collected	≤ 150.00	≤ 150.00	≤ 150.00	≤ 150.00
ppm	≤ 0.04	≤ 0.04	≤ 0.04	≤ 0.04

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Test Method: 26A - B Train

Source Condition	Mill On	Mill On	Mill On	
Date	1/30/24	1/30/24	1/30/24	
Start Time	8:15	9:50	11:25	
End Time	9:30	11:05	12:40	
	Run 1B	Run 2B	Run 3B	Average
Stack Conditions				
Average Gas Temperature, °F	152.2	153.0	153.6	152.9
Flue Gas Moisture, percent by volume	6.9%	9.2%	8.7%	8.3%
Average Flue Pressure, in. Hg	29.71	29.71	29.71	29.71
Gas Sample Volume, dscf	59.687	59.025	59.460	59.391
Average Gas Velocity, ft/sec	49.095	48.844	49.172	49.037
Gas Volumetric Flow Rate, acfm	725,471	721,759	726,601	724,610
Gas Volumetric Flow Rate, dscfm	578,347	560,637	566,975	568,653
Gas Volumetric Flow Rate, scfm	621,338	617,319	620,870	619,842
Average %CO ₂ by volume, dry basis	8.8	8.9	8.8	8.8
Average %O ₂ by volume, dry basis	15.6	15.4	15.5	15.5
Isokinetic Variance	99.1	101.1	100.7	100.3
Hydrogen Fluoride (HF) Emissions				
ug of sample collected	≤ 150.00	≤ 150.00	≤ 150.00	≤ 150.00
ppm	≤ 0.11	≤ 0.11	≤ 0.11	≤ 0.11
Chlorine (Cl₂) Emissions				
ug of sample collected	≤ 150.00	≤ 150.00	≤ 150.00	≤ 150.00
ppm	≤ 0.03	≤ 0.03	≤ 0.03	≤ 0.03

Holcim (US) Inc. Ravena Cement Plant Kiln 3 Common Stack Mill On Reference Method Test Data									
Test No.	Date	Start Time	End Time	O2 % (dry)	Moisture %	HCN ppmvw	HCN ppmvd @ 7% O2	HF ppmvw	HF ppmvd @ 7% O2
1	1/30/2024	8:15	9:13	15.6	9.1%	1.20	3.46	≤ 0.10	≤ 0.29
2	1/30/2024	9:50	10:49	15.4	9.0%	1.25	3.48	≤ 0.10	≤ 0.28
3	1/30/2024	11:25	12:24	15.5	8.9%	1.20	3.37	≤ 0.10	≤ 0.28
Average				15.5	9.0%	1.22	3.44	≤ 0.10	≤ 0.28

Test No.	Date	Start Time	End Time	Volumetric Flow, DSCFM	Clinker Production, ton/hr	HCN lb/hr	HCN lb/ton	HF lb/hr	HF lb/ton
1	1/30/2024	8:15	9:13	571,763	198.7	3.17	0.0159	≤ 0.20	≤ 0.0010
2	1/30/2024	9:50	10:49	558,443	199.1	3.23	0.0162	≤ 0.19	≤ 0.0010
3	1/30/2024	11:25	12:24	561,458	199.6	3.12	0.0156	≤ 0.19	≤ 0.0010
Average				563,888	199.1	3.17	0.0159	≤ 0.19	≤ 0.0010

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Test Location: Kiln 3 Common Stack
Test Method: 26A - Combined Trains

Source Condition	Mill Off	Mill Off	Mill Off	
Date	1/31/24	1/31/24	1/31/24	
Start Time	8:20	9:55	11:40	
End Time	9:35	11:10	12:55	
	Run 1	Run 2	Run 3	Average
Stack Conditions				
Average Gas Velocity, ft/sec	35.107	37.767	36.763	36.546
Gas Volumetric Flow Rate, acfm	518,775	558,068	543,244	540,029
Gas Volumetric Flow Rate, dscfm	381,066	410,454	390,056	393,858
Gas Volumetric Flow Rate, scfm	429,553	458,531	445,593	444,559
Average %CO ₂ by volume, dry basis	12.9	12.9	12.9	12.9
Average %O ₂ by volume, dry basis	12.9	12.9	13.1	13.0
Clinker production, ton/hr	209.0	208.7	209.6	209.1
Hydrogen Fluoride (HF) Emissions				
ppm ≤	0.17	≤ 0.16	≤ 0.17	≤ 0.17
ppm@7%O ₂ ≤	0.30	≤ 0.28	≤ 0.30	≤ 0.29
lb/hr ≤	0.20	≤ 0.21	≤ 0.21	≤ 0.21
lb/ton of clinker ≤	0.0010	≤ 0.0010	≤ 0.0010	≤ 0.0010
Chlorine (Cl₂) Emissions				
ppm ≤	0.05	≤ 0.05	≤ 0.05	≤ 0.05
ppm@7%O ₂ ≤	0.08	≤ 0.08	≤ 0.09	≤ 0.08
lb/hr ≤	0.20	≤ 0.21	≤ 0.21	≤ 0.21
lb/ton of clinker ≤	0.0010	≤ 0.0010	≤ 0.0010	≤ 0.0010

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Test Method: 26A - A Train

Source Condition	Mill Off	Mill Off	Mill Off	
Date	1/31/24	1/31/24	1/31/24	
Start Time	8:20	9:55	11:40	
End Time	9:35	11:10	12:55	
	Run 1A	Run 2A	Run 3A	Average
Stack Conditions				
Average Gas Temperature, °F	173.7	178.5	179.9	177.4
Flue Gas Moisture, percent by volume	11.9%	10.2%	12.0%	11.4%
Average Flue Pressure, in. Hg	29.73	29.73	29.73	29.73
Gas Sample Volume, dscf	34.329	35.506	34.075	34.637
Average Gas Velocity, ft/sec	35.305	38.209	36.968	36.827
Gas Volumetric Flow Rate, acfm	521,701	564,608	546,272	544,194
Gas Volumetric Flow Rate, dscfm	380,477	416,526	393,964	396,989
Gas Volumetric Flow Rate, scfm	431,948	463,934	447,874	447,919
Average %CO ₂ by volume, dry basis	12.9	12.9	12.9	12.9
Average %O ₂ by volume, dry basis	12.9	12.9	13.1	13.0
Isokinetic Variance	108.7	102.7	104.2	105.2
Hydrogen Fluoride (HF) Emissions				
ug of sample collected	≤ 150.00	≤ 150.00	≤ 150.00	≤ 150.00
ppm	≤ 0.19	≤ 0.18	≤ 0.19	≤ 0.18
Chlorine (Cl₂) Emissions				
ug of sample collected	≤ 150.00	≤ 150.00	≤ 150.00	≤ 150.00
ppm	≤ 0.05	≤ 0.05	≤ 0.05	≤ 0.05

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Test Method: 26A - B Train

Source Condition	Mill Off	Mill Off	Mill Off	
Date	1/31/24	1/31/24	1/31/24	
Start Time	8:20	9:55	11:40	
End Time	9:35	11:10	12:55	
	Run 1B	Run 2B	Run 3B	Average
Stack Conditions				
Average Gas Temperature, °F	173.6	178.6	179.3	177.2
Flue Gas Moisture, percent by volume	10.7%	10.8%	12.9%	11.5%
Average Flue Pressure, in. Hg	29.73	29.73	29.73	29.73
Gas Sample Volume, dscf	40.927	43.214	41.870	42.004
Average Gas Velocity, ft/sec	34.909	37.324	36.558	36.264
Gas Volumetric Flow Rate, acfm	515,848	551,528	540,215	535,864
Gas Volumetric Flow Rate, dscfm	381,654	404,382	386,147	390,728
Gas Volumetric Flow Rate, scfm	427,158	453,127	443,312	441,199
Average %CO ₂ by volume, dry basis	12.9	12.9	12.9	12.9
Average %O ₂ by volume, dry basis	12.9	12.9	13.1	13.0
Isokinetic Variance	103.0	102.6	104.1	103.2
Hydrogen Fluoride (HF) Emissions				
ug of sample collected	≤ 150.00	≤ 150.00	≤ 150.00	≤ 150.00
ppm	≤ 0.16	≤ 0.15	≤ 0.15	≤ 0.15
Chlorine (Cl₂) Emissions				
ug of sample collected	≤ 150.00	≤ 150.00	≤ 150.00	≤ 150.00
ppm	≤ 0.04	≤ 0.04	≤ 0.04	≤ 0.04

Holcim (US) Inc. Ravena Cement Plant Kiln 3 Common Stack Mill Off Reference Method Test Data									
Test No.	Date	Start Time	End Time	O2 % (dry)	Moisture %	HCN ppmvw	HCN ppmvd @ 7% O2	HF ppmvw	HF ppmvd @ 7% O2
1	1/31/2024	8:20	9:18	12.9	12.8%	1.46	2.92	≤ 0.10	≤ 0.20
2	1/31/2024	9:55	10:54	12.9	12.8%	1.52	3.04	≤ 0.10	≤ 0.20
3	1/31/2024	11:40	12:39	13.1	13.1%	1.59	3.27	≤ 0.10	≤ 0.21
Average				13.0	12.9%	1.52	3.08	≤ 0.10	≤ 0.20


Test No.	Date	Start Time	End Time	Volumetric Flow, DSCFM	Clinker Production, ton/hr	HCN lb/hr	HCN lb/ton	HF lb/hr	HF lb/ton
1	1/31/2024	8:20	9:18	381,066	209.0	2.68	0.0128	≤ 0.14	≤ 0.0007
2	1/31/2024	9:55	10:54	410,454	208.7	3.01	0.0144	≤ 0.15	≤ 0.0007
3	1/31/2024	11:40	12:39	390,056	209.6	3.00	0.0143	≤ 0.14	≤ 0.0007
Average				393,859	209.1	2.90	0.0139	≤ 0.14	≤ 0.0007

6.0 CERTIFICATION

Mostardi Platt is pleased to have been of service to Holcim (US) Inc. If you have any questions regarding this test report, please do not hesitate to contact us at 630-993-2100.

As project manager, I hereby certify that this test report represents a true and accurate summary of emissions test results and the methodologies employed to obtain those results, and the test program was performed in accordance with the methods specified in this test report.

MOSTARDI PLATT


Eric L. Ehlers

Project Manager


Chet A. Gutwein

Quality Assurance

APPENDICES

Appendix A – Plant Operating Data

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/30/2024 08:15	196.0
01/30/2024 08:16	202.5
01/30/2024 08:17	200.3
01/30/2024 08:18	199.3
01/30/2024 08:19	193.8
01/30/2024 08:20	209.5
01/30/2024 08:21	194.0
01/30/2024 08:22	199.8
01/30/2024 08:23	197.0
01/30/2024 08:24	203.5
01/30/2024 08:25	197.5
01/30/2024 08:26	202.9
01/30/2024 08:27	195.0
01/30/2024 08:28	201.5
01/30/2024 08:29	195.4
01/30/2024 08:30	195.3
01/30/2024 08:31	199.2
01/30/2024 08:32	201.7
01/30/2024 08:33	198.7
01/30/2024 08:34	196.9
01/30/2024 08:35	200.2
01/30/2024 08:36	197.4
01/30/2024 08:37	203.0
01/30/2024 08:38	196.1
01/30/2024 08:39	202.8
01/30/2024 08:40	193.1
01/30/2024 08:41	202.9
01/30/2024 08:42	200.3
01/30/2024 08:43	203.5
01/30/2024 08:44	197.1
01/30/2024 08:45	205.8
01/30/2024 08:46	196.9
01/30/2024 08:47	204.4
01/30/2024 08:48	196.3
01/30/2024 08:49	200.4
01/30/2024 08:50	201.3
01/30/2024 08:51	202.4
01/30/2024 08:52	200.5
01/30/2024 08:53	198.5
01/30/2024 08:54	196.4
01/30/2024 08:55	197.8
01/30/2024 08:56	195.1

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/30/2024 08:57	203.0
01/30/2024 08:58	197.8
01/30/2024 08:59	198.5
01/30/2024 09:00	203.0
01/30/2024 09:01	196.5
01/30/2024 09:02	201.1
01/30/2024 09:03	194.1
01/30/2024 09:04	203.8
01/30/2024 09:05	191.5
01/30/2024 09:06	201.2
01/30/2024 09:07	194.4
01/30/2024 09:08	201.6
01/30/2024 09:09	196.1
01/30/2024 09:10	201.8
01/30/2024 09:11	194.3
01/30/2024 09:12	199.1
01/30/2024 09:13	193.0
01/30/2024 09:14	200.4
01/30/2024 09:15	195.1
01/30/2024 09:16	200.7
01/30/2024 09:17	194.8
01/30/2024 09:18	200.4
01/30/2024 09:19	196.0
01/30/2024 09:20	195.4
01/30/2024 09:21	195.3
01/30/2024 09:22	196.4
01/30/2024 09:23	198.5
01/30/2024 09:24	197.1
01/30/2024 09:25	200.6
01/30/2024 09:26	194.0
01/30/2024 09:27	200.6
01/30/2024 09:28	194.6
01/30/2024 09:29	201.2
Average	198.7

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/30/2024 09:50	201.7
01/30/2024 09:51	197.5
01/30/2024 09:52	196.4
01/30/2024 09:53	195.4
01/30/2024 09:54	200.6
01/30/2024 09:55	198.7
01/30/2024 09:56	199.6
01/30/2024 09:57	199.5
01/30/2024 09:58	201.4
01/30/2024 09:59	195.9
01/30/2024 10:00	200.8
01/30/2024 10:01	197.2
01/30/2024 10:02	201.9
01/30/2024 10:03	196.3
01/30/2024 10:04	199.8
01/30/2024 10:05	200.7
01/30/2024 10:06	203.7
01/30/2024 10:07	201.4
01/30/2024 10:08	199.2
01/30/2024 10:09	202.4
01/30/2024 10:10	193.1
01/30/2024 10:11	203.9
01/30/2024 10:12	197.4
01/30/2024 10:13	199.3
01/30/2024 10:14	198.1
01/30/2024 10:15	200.6
01/30/2024 10:16	194.4
01/30/2024 10:17	207.8
01/30/2024 10:18	196.0
01/30/2024 10:19	202.1
01/30/2024 10:20	197.9
01/30/2024 10:21	205.0
01/30/2024 10:22	197.0
01/30/2024 10:23	208.1
01/30/2024 10:24	195.7
01/30/2024 10:25	199.6
01/30/2024 10:26	196.3
01/30/2024 10:27	198.2
01/30/2024 10:28	196.5
01/30/2024 10:29	195.5
01/30/2024 10:30	198.1
01/30/2024 10:31	200.0

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/30/2024 10:32	196.2
01/30/2024 10:33	197.6
01/30/2024 10:34	200.3
01/30/2024 10:35	196.4
01/30/2024 10:36	200.4
01/30/2024 10:37	193.7
01/30/2024 10:38	201.5
01/30/2024 10:39	192.9
01/30/2024 10:40	200.3
01/30/2024 10:41	190.9
01/30/2024 10:42	200.2
01/30/2024 10:43	191.9
01/30/2024 10:44	200.5
01/30/2024 10:45	193.2
01/30/2024 10:46	198.3
01/30/2024 10:47	194.8
01/30/2024 10:48	198.3
01/30/2024 10:49	193.7
01/30/2024 10:50	202.4
01/30/2024 10:51	195.1
01/30/2024 10:52	207.2
01/30/2024 10:53	198.6
01/30/2024 10:54	199.5
01/30/2024 10:55	203.4
01/30/2024 10:56	202.1
01/30/2024 10:57	205.4
01/30/2024 10:58	201.4
01/30/2024 10:59	206.8
01/30/2024 11:00	196.0
01/30/2024 11:01	208.9
01/30/2024 11:02	195.3
01/30/2024 11:03	200.8
01/30/2024 11:04	196.3
Average	199.1

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/30/2024 11:25	192.6
01/30/2024 11:26	196.2
01/30/2024 11:27	196.9
01/30/2024 11:28	201.9
01/30/2024 11:29	196.4
01/30/2024 11:30	202.4
01/30/2024 11:31	198.1
01/30/2024 11:32	199.0
01/30/2024 11:33	193.8
01/30/2024 11:34	203.3
01/30/2024 11:35	196.9
01/30/2024 11:36	204.7
01/30/2024 11:37	197.2
01/30/2024 11:38	201.1
01/30/2024 11:39	196.7
01/30/2024 11:40	204.1
01/30/2024 11:41	197.1
01/30/2024 11:42	200.3
01/30/2024 11:43	203.7
01/30/2024 11:44	200.6
01/30/2024 11:45	201.4
01/30/2024 11:46	199.7
01/30/2024 11:47	202.1
01/30/2024 11:48	199.4
01/30/2024 11:49	203.3
01/30/2024 11:50	195.0
01/30/2024 11:51	203.3
01/30/2024 11:52	193.1
01/30/2024 11:53	200.6
01/30/2024 11:54	194.9
01/30/2024 11:55	201.3
01/30/2024 11:56	196.9
01/30/2024 11:57	200.7
01/30/2024 11:58	195.8
01/30/2024 11:59	202.3
01/30/2024 12:00	195.2
01/30/2024 12:01	198.5
01/30/2024 12:02	196.8
01/30/2024 12:03	194.3
01/30/2024 12:04	197.8
01/30/2024 12:05	196.1
01/30/2024 12:06	199.4

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/30/2024 12:07	196.0
01/30/2024 12:08	201.2
01/30/2024 12:09	197.6
01/30/2024 12:10	201.6
01/30/2024 12:11	196.5
01/30/2024 12:12	202.2
01/30/2024 12:13	196.3
01/30/2024 12:14	201.9
01/30/2024 12:15	195.5
01/30/2024 12:16	204.7
01/30/2024 12:17	200.4
01/30/2024 12:18	202.3
01/30/2024 12:19	199.1
01/30/2024 12:20	200.7
01/30/2024 12:21	202.6
01/30/2024 12:22	200.7
01/30/2024 12:23	205.4
01/30/2024 12:24	199.3
01/30/2024 12:25	202.1
01/30/2024 12:26	204.4
01/30/2024 12:27	203.7
01/30/2024 12:28	203.4
01/30/2024 12:29	200.6
01/30/2024 12:30	202.6
01/30/2024 12:31	201.2
01/30/2024 12:32	202.8
01/30/2024 12:33	200.6
01/30/2024 12:34	197.0
01/30/2024 12:35	201.3
01/30/2024 12:36	197.4
01/30/2024 12:37	204.0
01/30/2024 12:38	196.1
01/30/2024 12:39	201.3
Average	199.6

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/31/2024 08:20	206.2
01/31/2024 08:21	213.2
01/31/2024 08:22	206.8
01/31/2024 08:23	211.9
01/31/2024 08:24	212.0
01/31/2024 08:25	207.5
01/31/2024 08:26	211.4
01/31/2024 08:27	206.7
01/31/2024 08:28	214.6
01/31/2024 08:29	203.7
01/31/2024 08:30	212.9
01/31/2024 08:31	205.9
01/31/2024 08:32	212.0
01/31/2024 08:33	205.4
01/31/2024 08:34	209.3
01/31/2024 08:35	204.6
01/31/2024 08:36	210.3
01/31/2024 08:37	206.0
01/31/2024 08:38	210.7
01/31/2024 08:39	207.2
01/31/2024 08:40	209.7
01/31/2024 08:41	206.8
01/31/2024 08:42	210.4
01/31/2024 08:43	205.8
01/31/2024 08:44	207.0
01/31/2024 08:45	209.0
01/31/2024 08:46	206.7
01/31/2024 08:47	206.8
01/31/2024 08:48	205.7
01/31/2024 08:49	208.1
01/31/2024 08:50	205.6
01/31/2024 08:51	208.4
01/31/2024 08:52	205.4
01/31/2024 08:53	211.6
01/31/2024 08:54	205.5
01/31/2024 08:55	210.8
01/31/2024 08:56	207.9
01/31/2024 08:57	210.9
01/31/2024 08:58	206.4
01/31/2024 08:59	211.4
01/31/2024 09:00	206.1
01/31/2024 09:01	211.6
01/31/2024 09:02	206.0
01/31/2024 09:03	210.0

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/31/2024 09:04	208.9
01/31/2024 09:05	214.1
01/31/2024 09:06	208.3
01/31/2024 09:07	211.8
01/31/2024 09:08	212.9
01/31/2024 09:09	214.1
01/31/2024 09:10	215.9
01/31/2024 09:11	216.7
01/31/2024 09:12	212.6
01/31/2024 09:13	208.3
01/31/2024 09:14	213.5
01/31/2024 09:15	204.5
01/31/2024 09:16	210.2
01/31/2024 09:17	202.2
01/31/2024 09:18	210.3
01/31/2024 09:19	201.8
01/31/2024 09:20	211.8
01/31/2024 09:21	204.5
01/31/2024 09:22	211.4
01/31/2024 09:23	203.6
01/31/2024 09:24	212.1
01/31/2024 09:25	204.3
01/31/2024 09:26	212.2
01/31/2024 09:27	207.6
01/31/2024 09:28	210.7
01/31/2024 09:29	209.8
01/31/2024 09:30	210.3
01/31/2024 09:31	212.3
01/31/2024 09:32	208.1
01/31/2024 09:33	210.0
01/31/2024 09:34	211.3
Average	209.0

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/31/2024 09:55	207.5
01/31/2024 09:56	206.9
01/31/2024 09:57	208.2
01/31/2024 09:58	208.1
01/31/2024 09:59	208.8
01/31/2024 10:00	208.8
01/31/2024 10:01	205.1
01/31/2024 10:02	210.5
01/31/2024 10:03	205.0
01/31/2024 10:04	214.2
01/31/2024 10:05	203.7
01/31/2024 10:06	208.0
01/31/2024 10:07	201.3
01/31/2024 10:08	208.6
01/31/2024 10:09	202.1
01/31/2024 10:10	205.8
01/31/2024 10:11	200.4
01/31/2024 10:12	207.6
01/31/2024 10:13	201.3
01/31/2024 10:14	208.6
01/31/2024 10:15	207.2
01/31/2024 10:16	208.2
01/31/2024 10:17	207.0
01/31/2024 10:18	206.1
01/31/2024 10:19	210.8
01/31/2024 10:20	209.3
01/31/2024 10:21	212.2
01/31/2024 10:22	208.6
01/31/2024 10:23	211.6
01/31/2024 10:24	205.3
01/31/2024 10:25	215.6
01/31/2024 10:26	206.9
01/31/2024 10:27	212.4
01/31/2024 10:28	207.0
01/31/2024 10:29	216.7
01/31/2024 10:30	206.9
01/31/2024 10:31	218.5
01/31/2024 10:32	209.0
01/31/2024 10:33	221.1
01/31/2024 10:34	206.6
01/31/2024 10:35	215.8
01/31/2024 10:36	209.3
01/31/2024 10:37	208.2
01/31/2024 10:38	209.4



Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/31/2024 10:39	209.7
01/31/2024 10:40	210.2
01/31/2024 10:41	204.5
01/31/2024 10:42	207.2
01/31/2024 10:43	207.1
01/31/2024 10:44	208.2
01/31/2024 10:45	204.6
01/31/2024 10:46	207.8
01/31/2024 10:47	204.1
01/31/2024 10:48	207.1
01/31/2024 10:49	202.4
01/31/2024 10:50	208.4
01/31/2024 10:51	208.6
01/31/2024 10:52	212.1
01/31/2024 10:53	207.5
01/31/2024 10:54	213.8
01/31/2024 10:55	205.4
01/31/2024 10:56	210.8
01/31/2024 10:57	208.7
01/31/2024 10:58	213.5
01/31/2024 10:59	209.2
01/31/2024 11:00	209.8
01/31/2024 11:01	206.6
01/31/2024 11:02	208.4
01/31/2024 11:03	208.8
01/31/2024 11:04	209.1
01/31/2024 11:05	212.6
01/31/2024 11:06	208.3
01/31/2024 11:07	213.1
01/31/2024 11:08	211.1
01/31/2024 11:09	213.7
Average	208.7

Date/Time	KILN: CLINKER_PROD_TONS (TON) Expression Value
01/31/2024 11:40	210.7
01/31/2024 11:41	204.8
01/31/2024 11:42	212.3
01/31/2024 11:43	207.7
01/31/2024 11:44	216.6
01/31/2024 11:45	209.8
01/31/2024 11:46	219.1
01/31/2024 11:47	210.8
01/31/2024 11:48	214.7
01/31/2024 11:49	208.9
01/31/2024 11:50	216.3
01/31/2024 11:51	206.1
01/31/2024 11:52	214.4
01/31/2024 11:53	209.5
01/31/2024 11:54	212.0
01/31/2024 11:55	212.7
01/31/2024 11:56	213.4
01/31/2024 11:57	211.0
01/31/2024 11:58	207.0
01/31/2024 11:59	211.4
01/31/2024 12:00	215.1
01/31/2024 12:01	213.4
01/31/2024 12:02	207.1
01/31/2024 12:03	211.4
01/31/2024 12:04	203.6
01/31/2024 12:05	207.6
01/31/2024 12:06	201.7
01/31/2024 12:07	216.3
01/31/2024 12:08	202.3
01/31/2024 12:09	211.1
01/31/2024 12:10	203.6
01/31/2024 12:11	208.3
01/31/2024 12:12	203.9
01/31/2024 12:13	209.2
01/31/2024 12:14	207.9
01/31/2024 12:15	208.8
01/31/2024 12:16	207.9
01/31/2024 12:17	210.0
01/31/2024 12:18	208.9
01/31/2024 12:19	206.5
01/31/2024 12:20	213.8
01/31/2024 12:21	206.5
01/31/2024 12:22	212.9
01/31/2024 12:23	206.9

01/31/2024 12:24	211.2
01/31/2024 12:25	207.8
01/31/2024 12:26	214.5
01/31/2024 12:27	206.0
01/31/2024 12:28	216.9
01/31/2024 12:29	206.5
01/31/2024 12:30	220.7
01/31/2024 12:31	207.3
01/31/2024 12:32	216.8
01/31/2024 12:33	209.4
01/31/2024 12:34	211.9
01/31/2024 12:35	211.0
01/31/2024 12:36	206.5
01/31/2024 12:37	210.7
01/31/2024 12:38	210.2
01/31/2024 12:39	211.4
01/31/2024 12:40	211.0
01/31/2024 12:41	206.2
01/31/2024 12:42	206.8
01/31/2024 12:43	206.7
01/31/2024 12:44	206.2
01/31/2024 12:45	205.7
01/31/2024 12:46	204.8
01/31/2024 12:47	209.4
01/31/2024 12:48	205.5
01/31/2024 12:49	211.6
01/31/2024 12:50	205.0
01/31/2024 12:51	211.1
01/31/2024 12:52	201.9
01/31/2024 12:53	212.5
01/31/2024 12:54	202.6
Average	209.6

Appendix B – Test Section Diagrams

STRATIFICATION TEST FOR ROUND DUCTS



Job: Holcim (US) Inc.
Ravena Cement Plant
Ravena, New York

Test Location: Common Stack

Stack Diameter: 17.708 Feet


Stack Area: 246.280 Square Feet

No. Sample Points: 3

Distance from Inside Wall
To Traverse Point:

1. 83.3 % of diameter
2. 50.0 % of diameter
3. 16.7 % of diameter

EQUAL AREA TRAVERSE FOR ROUND DUCTS



Project: Holcim (US) Inc.
Ravena Cement Plant
Ravena, New York

Test Location: Common Stack

Stack Diameter: 17.708 Feet


Stack Area: 246.280 Square Feet

No. Points Across Diameter: 6


No. of Ports: 4

Appendix C – Sample Train Diagrams


USEPA Method 2 – Type S Pitot Tube Manometer Assembly



USEPA Method 320 – Vapor Phase Organic and Inorganic Emissions by Extractive Fourier Transform Infrared (FTIR) Spectroscopy Sample Train Diagram



USEPA Method 26A – HF and Cl₂ Sample Train Diagram



Appendix D – Calculation Nomenclature and Formulas

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Test Location: Kiln 3 Common Stack
Date: 1/30/24

Sample Calculations

$$(15.73 \% - 0.09 \%) \times \frac{\text{O2 \% (dry)} \quad 11.92 \%}{12.04 \% - 0.09 \%} = 15.61 \%$$

$$C_{\text{gas}} = (C - C_o) \times \frac{C_{\text{ma}}}{C_m - C_o}$$

where:

C_{gas} = Effluent gas concentration, dry basis, ppm or %

C = Average gas concentration indicated by gas analyzer, dry basis, ppm or %

C_o = Average of initial and final system calibration bias check responses for the zero gas, ppm or %

C_m = Average of initial and final system calibration bias check responses for the upscale calibration gas, ppm or %

C_{ma} = Actual concentration of the upscale calibration gas, ppm or %

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Project #: M234506
 Test Location: Kiln 3 Common Stack
 Date: 1/30/24

FTIR Sample Calculations

Direct Recovery % of Calibration Transfer Standard

$$DR_{cts} = \frac{D_{cts}}{Cma} \times 100$$

$$Cma = \underline{100.0}$$

$$D_{cts} = \underline{97.5}$$

$$DR_{cts} = \underline{97.5\%}$$

Recovery % with Calibration Transfer Standard System Purge

$$R_{cts} = \frac{Sys_{cts}}{D_{cts}} \times 100$$

$$Sys_{cts} = \underline{97.8}$$

$$D_{cts} = \underline{97.5}$$

$$R_{cts} = \underline{100\%}$$

Direct Recovery % of Analyte Spike Gas

SF6

$$DR_{sf6} = \frac{D_{sf6}}{Cma} \times 100$$

$$Cma = \underline{5.0}$$

$$D_{sf6} = \underline{4.9}$$

$$DR_{sf6} = \underline{97\%}$$

HCN

$$DR_{asg} = \frac{D_{asg}}{Cma} \times 100$$

$$Cma = \underline{49.7}$$

$$D_{asg} = \underline{49.8}$$

$$DR_{asg} = \underline{100.1\%}$$

Dilution Factor for Analyte Spiking

$$DF = \frac{Spk_{sf6}}{D_{sf6}}$$

$$Spk_{sf6} = \underline{0.486}$$

$$D_{sf6} = \underline{4.860}$$

$$DF = \underline{0.100}$$

Recovery % for Analyte Spike With HCN

$$R_x = \frac{Spk_x}{(N_x \times (1-DF) + D_{asg} \times DF)}$$

$$Spk_x = \underline{5.7}$$

$$N_x = \underline{1.3}$$

$$DF = \underline{0.100}$$

$$D_{asg} = \underline{49.8}$$

$$R_x = \underline{93.8} \quad \%$$

where:

DR_{cts} = Recovery % of the calibration transfer standard directly to the analyzer

Cma = certified concentration of calibration gas, ppm

D_{cts} = Concentration of the calibration transfer standard gas directly to the analyzer, ppm

R_{cts} = Recovery % of the calibration transfer standard through the sampling system

Sys_{cts} = Concentration of the calibration transfer standard gas through the system, ppm

DF = Dilution Factor of analyte spike gas

Spk_{sf6} = SF6 concentration in effluent during spiking

Spk_x = Analyte concentration in effluent during spiking

D_{asg} = Concentration of the analyte spike gas directly to the analyzer, ppm

D_{sf6} = Concentration of the SF6 directly to the analyzer, ppm

R_x = Recovery % of the analyte spike gas

N_x = Native effluent (HCN) concentration prior to analyte spike

MOSTARDI PLATT

Moisture Calculations

$$V_{wc(std)} = \frac{(V_f - V_i)\rho_w RT_{std}}{P_{std}M_w} = 0.04707(V_f - V_i)$$

$$V_{wsg(std)} = \frac{(W_f - W_i)\rho_w RT_{std}}{P_{std}M_w} = 0.04715(W_f - W_i)$$

$$V_{m(std)} = 17.64 V_m Y \frac{P_{bar} + \frac{\Delta H}{13.6}}{T_m}$$

$$B_{ws} = \frac{V_{wc(std)} + V_{wsg(std)}}{V_{wc(std)} + V_{wsg(std)} + V_{m(std)}}$$

Where:

B_{ws} = Water vapor in gas stream, proportion by volume

M_w = Molecular weight of water, 18.015 lb/lb-mole

P_{bar} = Barometric pressure at the testing site, in. Hg

P_{std} = Standard absolute pressure, 29.92 in. Hg

R = Ideal gas constant, $0.048137 \text{ (in. Hg)(ft}^3\text{)/(g-mole)(}^\circ\text{R)} =$
 $[21.8348 \text{ (in. Hg)(ft}^3\text{)/(lb-mole)(}^\circ\text{R)}]/453.592 \text{ g-mole/lb-mole}$

T_m = Absolute average dry gas meter temperature, $^\circ\text{R}$

T_{std} = Standard absolute temperature, 528 $^\circ\text{R}$

V_f = Final volume of condenser water, ml

V_i = Initial volume of condenser water, ml

V_m = Dry gas volume measured by dry gas meter, dcf

$V_{m(std)}$ = Dry gas volume measured by dry gas meter, corrected to standard conditions, scf

$V_{wc(std)}$ = Volume of condensed water vapor, corrected to standard conditions, scf

$V_{wsg(std)}$ = Volume of water vapor collected in silica gel, corrected to standard conditions, scf

W_f = Final weight of silica gel, g

W_i = Initial weight of silica gel, g

Y = Dry gas meter calibration factor

ΔH = Average pressure exerted on dry gas meter outlet by gas sample bag, in. H_2O

ρ_w = Density of water, 0.9982 g/ml

13.6 = Specific gravity of mercury (Hg)

17.64 = T_{std}/P_{std}

0.04707 = ft^3/ml 0.04715 = ft^3/g

MOSTARDI PLATT

Volumetric Flow Nomenclature

- A = Cross-sectional area of stack or duct, ft²
- Bws = Water vapor in gas stream, proportion by volume
- Cp = Pitot tube coefficient, dimensionless
- Md = Dry molecular weight of gas, lb/lb-mole
- Ms = Molecular weight of gas, wet basis, lb/lb-mole
- Mw = Molecular weight of water, 18.0 lb/lb-mole
- Pbar = Barometric pressure at testing site, in. Hg
- Pg = Static pressure of gas, in. Hg (in. H₂O/13.6)
- DH = Static pressure of gas, in. H₂O
- Ps = Absolute pressure of gas, in. Hg = Pbar + Pg
- Pstd = Standard absolute pressure, 29.92 in. Hg
- Acfm = Actual volumetric gas flow rate
- Scfm = Volumetric gas flow rate, corrected to standard conditions
- Dscfm = Standard volumetric flow rate, corrected to dry conditions
- R = Ideal gas constant, 21.85 in. Hg-ft³/°R-lb-mole
- Ts = Average stack gas temperature, °F
- Tm = Average dry gas meter temperature, °F
- Tstd = Standard absolute temperature, 528°R
- vs = Gas velocity, ft/sec
- Vm(std) = Volume of gas sampled, corrected to standard conditions, scf
- Vw(std) = Volume of water vapor in gas sample, corrected to standard conditions, scf
- Vlc = Volume of liquid collected
- Y = Dry gas meter calibration factor
- Δp = Velocity head of gas, in. H₂O
- K1 = 17.647 °R/in. Hg
- %EA = Percent excess air
- %CO₂ = Percent carbon dioxide by volume, dry basis
- %O₂ = Percent oxygen by volume, dry basis
- %N₂ = Percent nitrogen by volume, dry basis
- 0.264 = Ratio of O₂ to N₂ in air, v/v
- 0.28 = Molecular weight of N₂ or CO, divided by 100
- 0.32 = Molecular weight of O₂ divided by 100
- 0.44 = Molecular weight of CO₂ divided by 100
- 13.6 = Specific gravity of mercury (Hg)

MOSTARDI PLATT

Volumetric Air Flow Calculations

$$Vm (std) = 17.647 \times Vm \times \left[\frac{\left(P_{bar} + \left[\frac{DH}{13.6} \right] \right)}{(460 + Tm)} \right] \times Y$$

$$Vw (std) = 0.0471 \times Vlc$$

$$Bws = \left[\frac{Vw (std)}{Vw (std) + Vm (std)} \right]$$

$$Md = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + [0.28 \times (100 - \%CO_2 - \%O_2)]$$

$$Ms = Md \times (1 - Bws) + (18 \times Bws)$$

$$Vs = \sqrt{\frac{(Ts + 460)}{Ms \times Ps}} \times \sqrt{DP} \times Cp \times 85.49$$

$$Acfm = Vs \times Area (of stack or duct) \times 60$$

$$Scfm = Acfm \times 17.647 \times \left[\frac{Ps}{(460 + Ts)} \right]$$

$$Scfh = Scfm \times 60 \frac{min}{hr}$$

$$Dscfm = Scfm \times (1 - Bws)$$

MOSTARDI PLATT

Isokinetic Calculation Formulas

$$1. V_{w(std)} = V_{lc} \left(\frac{\rho_w}{M_w} \right) \left(\frac{RT_{std}}{P_{std}} \right) = K_2 V_{lc}$$

$$2. V_{m(std)} = V_m Y \left(\frac{T_{std}}{T_m} \right) \left(\frac{(P_{bar} + (\frac{\Delta H}{13.6}))}{P_{std}} \right) = K_1 V_m Y \frac{(P_{bar} + (\frac{\Delta H}{13.6}))}{T_m}$$

$$3. B_{ws} = \frac{V_{w(std)}}{(V_{m(std)} + V_{w(std)})}$$

$$4. M_d = 0.44(\%CO_2) + 0.32(\%O_2) + 0.28(\%N_2)$$

$$5. M_s = M_d(1 - B_{ws}) + 18.0(B_{ws})$$

$$6. C_a = \frac{m_a}{V_a \rho_a}$$

$$7. W_a = C_a V_{aw} \rho_a$$

$$8. C_{acf} = 15.43 K_i \left(\frac{m_n P_s}{V_{w(std)} + V_{m(std)} T_s} \right)$$

$$9. C_s = (15.43 \text{ grains/gram}) (m_n / V_{m(std)})$$

$$10. v_s = K_p C_p \sqrt{\frac{\Delta P T_s}{P_s M_s}}$$

$$11. Q_{acfm} = v_s A (60_{\text{sec/min}})$$

$$12. Q_{sd} = (3600_{\text{sec/hr}})(1 - B_{ws}) v_s \left(\frac{T_{std} P_s}{T_s P_{std}} \right) A$$

$$13. E (\text{emission rate, lbs/hr}) = Q_{std} (C_s / 7000 \text{ grains/lb})$$

$$14. IKV = \frac{T_s V_{m(std)} P_{std}}{T_{std} v_s \theta A_n P_s 60(1 - B_{ws})} = K_4 \frac{T_s V_{m(std)}}{P_s v_s A_n \theta (1 - B_{ws})}$$

$$15. \%EA = \left(\frac{\%O_2 - (0.5 \%CO)}{0.264 \%N_2 - (\%O_2 - 0.5 \%CO)} \right) \times 100$$

MOSTARDI PLATT

Isokinetic Nomenclature

- A = Cross-sectional area of stack or duct, square feet
A_n = Cross-sectional area of nozzle, square feet
B_{ws} = Water vapor in gas stream, by volume
C_a = Acetone blank residue concentration, g/g
C_{act} = Concentration of particulate matter in gas stream at actual conditions, gr/acf
C_p = Pitot tube coefficient
C_s = Concentration of particulate matter in gas stream, dry basis, corrected to standard conditions, gr/dscf
IKV = Isokinetic sampling variance, must be 90.0 % ≤ IKV ≤ 110.0%
M_d = Dry molecular weight of gas, lb/lb-mole
M_s = Molecular weight of gas, wet basis, lb/lb-mole
M_w = Molecular weight of water, 18.0 lb/lb-mole
m_a = Mass of residue of acetone after evaporation, grams
P_{bar} = Barometric pressure at testing site, inches mercury
P_g = Static pressure of gas, inches mercury (inches water/13.6)
P_s = Absolute pressure of gas, inches mercury = P_{bar} + P_g
P_{std} = Standard absolute pressure, 29.92 inches mercury
Q_{acfm} = Actual volumetric gas flow rate, acfm
Q_{sd} = Dry volumetric gas flow rate corrected to standard conditions, dscfh
R = Ideal gas constant, 21.85 inches mercury cubic foot/°R-lb-mole
T_m = Dry gas meter temperature, °R
T_s = Gas temperature, °R
T_{std} = Absolute temperature, 528°R
V_a = Volume of acetone blank, ml
V_{aw} = Volume of acetone used in wash, ml
W_a = Weight of residue in acetone wash, grams
m_n = Total amount of particulate matter collected, grams
V_{1c} = Total volume of liquid collected in impingers and silica gel, ml
V_m = Volume of gas sample as measured by dry gas meter, dcf
V_{m(std)} = Volume of gas sample measured by dry gas meter, corrected to standard conditions, dscf
V_s = Gas velocity, ft/sec
V_{w(std)} = Volume of water vapor in gas sample, corrected to standard conditions, scf
Y = Dry gas meter calibration factor
ΔH = Average pressure differential across the orifice meter, inches water
Δp = Velocity head of gas, inches water
ρ_a = Density of acetone, 0.7855 g/ml (average)
ρ_w = Density of water, 0.002201 lb/ml
θ = Total sampling time, minutes
K₁ = 17.647 °R/in. Hg
K₂ = 0.04707 ft³/ml
K₄ = 0.09450/100 = 0.000945
K_p = Pitot tube constant, $85.49 \frac{ft}{sec} \left[\frac{(lb/lb-mole)(in. Hg)}{(°R)(in. H_2O)} \right]^{1/2}$
%EA = Percent excess air
%CO₂ = Percent carbon dioxide by volume, dry basis
%O₂ = Percent oxygen by volume, dry basis
%CO = Percent carbon monoxide by volume, dry basis
%N₂ = Percent nitrogen by volume, dry basis
0.264 = Ratio of O₂ to N₂ in air, v/v
28 = Molecular weight of N₂ or CO
32 = Molecular weight of O₂
44 = Molecular weight of CO₂
13.6 = Specific gravity of mercury (Hg)

MOSTARDI PLATT

Calculations for Hydrogen Fluoride By Method 26 or 26A

Concentration

$$\frac{\text{lbs HF}}{\text{dscf}} = \frac{\mu\text{g HF in sample}}{4.536 \times 10^8 \times \text{dscf}}$$

where:

$$4.536 \times 10^8 = \mu\text{g/lb}$$

dscf = Volume of gas sampled

$$\mu\text{g/lb HF} = \mu\text{g F} \times \frac{20.008}{19.000}$$

Parts Per Million

$$\text{ppm HF} = \frac{\text{lbs HF}}{\text{dscf}} \div \frac{20.008}{385 \times 10^6}$$

where:

385 = Volume of 1 lb mole of gas at 68°F and 29.92 in. Hg

106 = Conversion of ppm v/v

Emission Rate

$$\text{lbs HF /dscf} \times \text{dscfm} \times 60 \text{ min/hr} = \text{lbs/hr HF}$$

MOSTARDI PLATT

Pollutant Concentration Correction 7% for Percent Oxygen

$$C_{adj} = C_d \frac{20.9 - 7\%}{20.9 - \%O_2}$$

where:

C_{adj} = Pollutant concentration corrected to percent O_2

$20.9 - 7\%$ = Percent O_2 , the defined O_2 correction value, percent

20.9 = Percent O_2 in air

$\%O_2$ = Measured O_2 concentration dry basis, percent

C_d = Pollutant concentration measured, dry basis, ppm.

Appendix E- Laboratory Sample Analysis

Chain-of-Custody Form						
Project Number: M234506				Date Results Required:		
Client: Holcim (US) Cement				TAT Required:		
Plant/Test Location: Ravenna/Main Kiln Stack				Project Supervisor: EE		
Sample Number	Sample Date	Sample Point Identification	# of Conts	Sub Lab	Analysis Required	Volume, mls
001	1/30/24	#1A M26A H2SO4 Mill on	1		HF	
002	1/30/24	#1A M26A NaOH Mill on	1		Cl ₂	
003	1/30/24	#1B M26A H2SO4 Mill on	1		HF	
004	1/30/24	#1B M26A NaOH Mill on	1		Cl ₂	
005	1/30/24	#2A M26A H2SO4 Mill on	1		HF	
006	1/30/24	#2A M26A NaOH Mill on	1		Cl ₂	
007	1/30/24	#2B M26A H2SO4 Mill on	1		HF	
008	1/30/24	#2B M26A NaOH Mill on	1		Cl ₂	
009	1/30/24	#3A M26A H2SO4 Mill on	1		HF	
010	1/30/24	#3A M26A NaOH Mill on	1		Cl ₂	
011	1/30/24	#3B M26A H2SO4 Mill on	1		HF	
012	1/30/24	#3B M26A NaOH Mill on	1		Cl ₂	
013	1/30/24	A Train Blank H2SO4 Mill on	1		HF	
014	1/30/24	A Train Blank NaOH Mill on	1		Cl ₂	
015	1/31/24	#1A M26A H2SO4 Mill off	1		HF	
016	1/31/24	#1A M26A NaOH Mill off	1		Cl ₂	
017	1/31/24	#1B M26A H2SO4 Mill off	1		HF	
018	1/31/24	#1B M26A NaOH Mill off	1		Cl ₂	
019	1/31/24	#2A M26A H2SO4 Mill off	1		HF	
020	1/31/24	#2A M26A NaOH Mill off	1		Cl ₂	
Delivered to Lab by: Date/Time:		Received by: Date/Time:		Processed by: Date/Time:		

Laboratory Notes:

Chain-of-Custody Form						
Project Number: M234506				Date Results Required:		
Client: Holcim (US) Cement				TAT Required:		
Plant/Test Location: Ravenna/Main Kiln Stack				Project Supervisor: EE		
Sample Number	Sample Date	Sample Point Identification	# of Conts	Sub Lab	Analysis Required	Volume, mls
021	1/31/24	#2B M26A H2SO4 Mill off	1		HF	
022	1/31/24	#2B M26A NaOH Mill off	1		Cl ₂	
023	1/31/24	#3A M26A H2SO4 Mill off	1		HF	
024	1/31/24	#3A M26A NaOH Mill off	1		Cl ₂	
025	1/31/24	#3B M26A H2SO4 Mill off	1		HF	
026	1/31/24	#3B M26A NaOH Mill off	1		Cl ₂	
027	1/30/24	B Train Blank H2SO4 Mill off	1		HF	
028	1/30/24	B Train Blank NaOH Mill off	1		Cl ₂	
029	1/30/24	DI Reagent Blank	1		HF/Cl ₂	
030	1/30/24	H2SO4 Reagent Blank	1		HF	
031	1/30/24	NaOH Reagent Blank	1		Cl ₂	
Delivered to Lab by: Date/Time:		Received by: Date/Time:		Processed by: Date/Time:		

Laboratory Notes:

Main Kiln-Mill Off

Client: Holcim	Analysis Date: 2/26/2024
Facility: Ravena	Analysis Location: Elmhurst
Test Location: Main Kiln-Mill Off	Analyst: JMG
Project Number: M234506	
Method: 26A	
Date Samples Received: 2/5/2024	

Train A

Sampling Date		1/31/2024	1/31/2024	1/31/2024	1/31/2024		
	UNITS	M26A DI Blank	M26A H2SO4 Blank	M26A H2SO4-R1	M26A H2SO4-R1 Dup	RDL	MDL
Sulfuric Acid Volume	ml	172	226	361	361		
Hydrofluoric Acid	ug	<150	<150	<150	<150	150	15

Sampling Date		1/31/2024	1/31/2024				
	UNITS	M26A- H2SO4 R2	M26A- H2SO4 R3			RDL	MDL
Sulfuric Acid Volume	ml	300	345				
Hydrofluoric Acid	ug	<150	<150			150	15

Train B

Sampling Date		1/31/2024	1/31/2024	1/31/2024	1/31/2024		
	UNITS	M26A DI Blank	M26A H2SO4 Blank	M26A H2SO4-R1	M26A H2SO4-R1 Dup	RDL	MDL
Sulfuric Acid Volume	ml	172	226	361	361		
Hydrofluoric Acid	ug	<150	<150	<150	<150	150	15

Sampling Date		1/31/2024	1/31/2024				
	UNITS	M26A- H2SO4 R2	M26A- H2SO4 R3			RDL	MDL
Sulfuric Acid Volume	ml	384	380				
Hydrofluoric Acid	ug	<150	<150			150	15

Client:	Holcim	Analysis Date:	2/26/2024										
Facility:	Ravena	Analysis Location:	Elmhurst										
Test Location:	Main Kiln-Mill Off	Analyst:	JMG										
Project Number:	M234506												
Method:	26A												
Date Samples Received:	2/5/2024												
Standard ppm HF	Area	Response Factor	Calculated Value	Slope of Regression Curve									
1	0.2139	0.2139	0.95	0.2253									
2	0.4332	0.2166	1.92										
5	1.1237	0.2247	4.99	Response Factor Ave									
8	1.8439	0.2305	8.19	0.2250									
10	2.3932	0.2393	10.62										
Lot Number	Ricca 830603B												
	R ²	0.9989											
Sample Number	Sample Date	Sample ID	Sample Area	PPM F	PPM X Dilution Factor	Dilution Factor	Total ml	mg F in soln	mg HF in soln	mg HF in soln avg	ug HF in soln		
029	1/31/2024	DI Reagent Blank	0.0036	0.0160	0.0160	1	172	0.0027	0.0029				
029	1/31/2024	DI Reagent Blank	0.0018	0.0080	0.0080	1	172	0.0014	0.0014	0.0022	2.171465421		
030	1/31/2024	H2SO4 Reagent Blank	0.0028	0.0124	0.0124	1	226	0.0028	0.0030				
030	1/31/2024	H2SO4 Reagent Blank	0.0038	0.0169	0.0169	1	226	0.0038	0.0040	0.0035	3.487250023		
015	1/31/2024	Test 1A H2SO4 Imp	0.0229	0.1017	0.1017	1	361	0.0367	0.0387				
015	1/31/2024	Test 1A H2SO4 Imp	0.0248	0.1101	0.1101	1	361	0.0397	0.0419	0.0403	40.25837974		
015	1/31/2024	Test 1A H2SO4 Imp	0.0245	0.1088	0.1088	1	361	0.0393	0.0414				
015	1/31/2024	Test 1A H2SO4 Imp	0.0235	0.1043	0.1043	1	361	0.0377	0.0397	0.0405	40.5115771		
019	1/31/2024	Test 2A H2SO4 Imp	0.0096	0.0426	0.0426	1	300	0.0128	0.0135				
019	1/31/2024	Test 2A H2SO4 Imp	0.0117	0.0519	0.0519	1	300	0.0156	0.0164	0.0149	14.93934543		
023	1/31/2024	Test 3A H2SO4 Imp	0.0239	0.1061	0.1061	1	345	0.0366	0.0386				
023	1/31/2024	Test 3A H2SO4 Imp	0.0279	0.1239	0.1239	1	345	0.0427	0.0450	0.0418	41.78107077		
					Expected Value	% Difference							
		Run 1 H2SO4 Spike W/ 2ppm	0.2209	0.9807	1.0145								
Lot Number: Thermo 21-191JKS		Run 1 H2SO4 Spike W/ 2ppm	0.2169	0.9629	1.0145	4.21%							
CCV ppm F	Area	PPM F											
1 ppm ICV	0.2386	1.0592											
5 ppm CCV	1.1537	5.1217											
5 ppm CCV	1.1391	5.0569											
5 ppm CCV	1.1364	5.0449											
5 ppm CCV	1.1283	5.0089											
Standard ppm F	Area	Difference											
1	0.2068	1.72%											
2	0.4337	0.06%											
5	1.1254	0.08%											
8	1.8928	1.29%											
10	2.4171	0.49%											

Client:	Holcim	Analysis Date:	2/26/2024									
Facility:	Ravena	Analysis Location:	Elmhurst									
Test Location:	Main Kiln-Mill Off	Analyst:	JMG									
Project Number:	M234506											
Method:	26A											
Date Samples Received:	2/5/2024											
Standard ppm HF	Area	Response Factor	Calculated Value	Slope of Regression Curve								
1	0.2139	0.2139	0.95	0.2253								
2	0.4332	0.2166	1.92									
5	1.1237	0.2247	4.99	Response Factor Ave								
8	1.8439	0.2305	8.19	0.2250								
10	2.3932	0.2393	10.62									
Lot Number	Ricca 8209004											
	R ²	0.9989										
Sample Number	Sample Date	Sample ID	Sample Area	PPM F	PPM X Dilution Factor	Dilution Factor	Total ml	mg F in soln	mg HF in soln	mg HF in soln avg	ug HF in soln	
029	1/31/2024	DI Reagent Blank	0.0036	0.0160	0.0160	1	172	0.0027	0.0029			
029	1/31/2024	DI Reagent Blank	0.0018	0.0080	0.0080	1	172	0.0014	0.0014	0.0022	2.171465421	
030	1/31/2024	H2SO4 Reagent Blank	0.0028	0.0124	0.0124	1	226	0.0028	0.0030			
030	1/31/2024	H2SO4 Reagent Blank	0.0038	0.0169	0.0169	1	226	0.0038	0.0040	0.0035	3.487250023	
017	1/31/2024	Test 1B H2SO4 Imp	0.0111	0.0493	0.0493	1	361	0.0178	0.0187			
017	1/31/2024	Test 1B H2SO4 Imp	0.0105	0.0466	0.0466	1	361	0.0168	0.0177	0.0182	18.2302097	
017	1/31/2024	Test 1B H2SO4 Imp	0.0105	0.0466	0.0466	1	361	0.0168	0.0177			
017	1/31/2024	Test 1B H2SO4 Imp	0.0110	0.0488	0.0488	1	361	0.0176	0.0186	0.0181	18.14581058	
021	1/31/2024	Test 2B H2SO4 Imp	0.0210	0.0932	0.0932	1	384	0.0358	0.0377			
021	1/31/2024	Test 2B H2SO4 Imp	0.0196	0.0870	0.0870	1	384	0.0334	0.0352	0.0364	36.44919735	
025	1/31/2024	Test 3B H2SO4 Imp	0.0147	0.0653	0.0653	1	380	0.0248	0.0261			
025	1/31/2024	Test 3B H2SO4 Imp	0.0171	0.0759	0.0759	1	380	0.0288	0.0304	0.0283	28.25149456	
CCV ppm F	Area	PPM F										
1 ppm ICV	0.2386	1.0592										
5 ppm CCV	1.1537	5.1217										
5 ppm CCV	1.1391	5.0569										
5 ppm CCV	1.1364	5.0449										
5 ppm CCV	1.1283	5.0089										
Standard ppm F	Area	Difference										
1	0.2068	1.72%										
2	0.4337	0.06%										
5	1.1254	0.08%										
8	1.8928	1.29%										
10	2.4171	0.49%										

Main Kiln-Mill Off

Client: Holcim	Analysis Date: 2/26/2024
Facility: Ravena	Analysis Location: Elmhurst
Test Location: Main Kiln-Mill Off	Analyst: JMG
Project Number: M234506	
Method: 26A	
Date Samples Received: 2/5/2024	

Train A

Sampling Date		1/31/2024	1/31/2024	1/31/2024	1/31/2024		
	UNITS	M26A DI Blank	M26A NaOH Blank	M26A NaOH-R1	M26A NaOH-R1 Dup	RDL	MDL
Sodium Hydroxide Volume	ml	172	223	245	245		
Chlorine	ug	<150	<150	<150	<150	150	15

Sampling Date		1/31/2024	1/31/2024				
	UNITS	M26A- NaOH R2	M26A- NaOH R3			RDL	MDL
Sodium Hydroxide Volume	ml	209	249				
Chlorine	ug	<150	<150			150	15

Train B

Sampling Date		1/31/2024	1/31/2024	1/31/2024	1/31/2024		
	UNITS	M26A DI Blank	M26A NaOH Blank	M26A NaOH-R1	M26A NaOH-R1 Dup	RDL	MDL
Sodium Hydroxide Volume	ml	172	223	214	214		
Chlorine	ug	<150	<150	<150	<150	150	15

Sampling Date		1/31/2024	1/31/2024				
	UNITS	M26A- NaOH R2	M26A- NaOH R3			RDL	MDL
Sodium Hydroxide Volume	ml	238	249				
Chlorine	ug	<150	<150			150	15

Client:	Holcim	Analysis Date:	2/26/2024							
Facility:	Ravena	Analysis Location:	Elmhurst Lab							
Test Location:	Main Kiln-Mill Off	Analyst:	JMG							
Project Number:	M234506									
Method:	26A									
Date Samples Received:	2/5/2024									
Standard ppm Cl	Area	Response Factor	Calculated Value	Slope of Regression Curve						
1	0.1189	0.1189	0.94	0.1270						
2	0.2477	0.1239	1.95							
5	0.6397	0.1279	5.04	Response Factor Ave						
8	1.0453	0.1307	8.23	0.1270						
10	1.3356	0.1336	10.51							
Lot Number	Ricca 830603B									
	R²	0.9996								
Sample Number	Sample Date	Sample ID	Sample Area	PPM Cl	PPM X Dilution Factor	Dilution Factor	Total ml	mg Cl in soln	ug Cl2 in soln	ug Cl2 in soln
029	1/31/2024	DI Reagent Blank	0.0019	0.0150	0.0150	1	172	0.0026		
029	1/31/2024	DI Reagent Blank	0.0007	0.0055	0.0055	1	172	0.0009	0.0018	1.760226855
031	1/31/2024	NaOH Reagent Blank	0.0067	0.0527	0.0527	1	223	0.0118		
031	1/31/2024	NaOH Reagent Blank	0.0068	0.0535	0.0535	1	223	0.0119	0.0118	11.84964881
016	1/31/2024	Test 1A NaOH Imp	0.0072	0.0567	0.0567	1	245	0.0139		
016	1/31/2024	Test 1A NaOH Imp	0.0039	0.0307	0.0307	1	245	0.0075	0.0107	10.7042418
016	1/31/2024	Test 1A NaOH Imp	0.0027	0.0213	0.0213	1	245	0.0052		
016	1/31/2024	Test 1A NaOH Imp	0.0039	0.0307	0.0307	1	245	0.0075	0.0064	6.364684314
020	1/31/2024	Test 2A NaOH Imp	0.0046	0.0362	0.0362	1	209	0.0076		
020	1/31/2024	Test 2A NaOH Imp	0.0046	0.0362	0.0362	1	209	0.0076	0.0076	7.568345701
024	1/31/2024	Test 3A NaOH Imp	0.0038	0.0299	0.0299	1	249	0.0074		
024	1/31/2024	Test 3A NaOH Imp	0.0030	0.0236	0.0236	1	249	0.0059	0.0067	6.664615634
					Expected Value	% Difference				
		Run 1 H2SO4 Spike W/ 2ppm	0.1023	0.8053	0.9968					
		Run 1 H2SO4 Spike W/ 2ppm	0.1014	0.7982	0.9968	19.57%				
CCV ppm Cl	Area	PPM Cl								
5 ppm ICV	0.6506	5.1217								
5 ppm CCV	0.6395	5.0343								
5 ppm CCV	0.6387	5.0280								
5 ppm CCV	0.6452	5.0792								
5 ppm CCV	0.6458	5.0839								

Client:	Holcim	Analysis Date:	2/26/2024							
Facility:	Ravena	Analysis Location:	Elmhurst Lab							
Test Location:	Main Kiln-Mill Off	Analyst:	JMG							
Project Number:	M234506									
Method:	26A									
Date Samples Received:	2/5/2024									
Standard ppm Cl	Area	Response Factor	Calculated Value	Slope of Regression Curve						
1	0.1189	0.1189	0.94	0.1270						
2	0.2477	0.1239	1.95							
5	0.6397	0.1279	5.04	Response Factor Ave						
8	1.0453	0.1307	8.23	0.1270						
10	1.3356	0.1336	10.51							
Lot Number	Ricca 8209004									
	R²	0.9996								
Sample Number	Sample Date	Sample ID	Sample Area	PPM Cl	PPM X Dilution Factor	Dilution Factor	Total ml	mg Cl in soln	mg Cl2 in soln avg	ug Cl2 in soln
029	1/31/2024	DI Reagent Blank	0.0019	0.0150	0.0150	1	172	0.0026		
029	1/31/2024	DI Reagent Blank	0.0007	0.0055	0.0055	1	172	0.0009	0.0018	1.760226855
031	1/31/2024	NaOH Reagent Blank	0.0067	0.0527	0.0527	1	223	0.0118		
031	1/31/2024	NaOH Reagent Blank	0.0068	0.0535	0.0535	1	223	0.0119	0.0118	11.84964881
018	1/31/2024	Test 1B NaOH Imp	0.0063	0.0496	0.0496	1	214	0.0106		
018	1/31/2024	Test 1B NaOH Imp	0.0050	0.0394	0.0394	1	214	0.0084	0.0095	9.518292893
018	1/31/2024	Test 1B NaOH Imp	0.0069	0.0543	0.0543	1	214	0.0116		
018	1/31/2024	Test 1B NaOH Imp	0.0074	0.0583	0.0583	1	214	0.0125	0.0120	12.04527331
022	1/31/2024	Test 2B NaOH Imp	0.0111	0.0874	0.0874	1	238	0.0208		
022	1/31/2024	Test 2B NaOH Imp	0.0105	0.0827	0.0827	1	238	0.0197	0.0202	20.23473662
026	1/31/2024	Test 3B NaOH Imp	0.0055	0.0433	0.0433	1	249	0.0108		
026	1/31/2024	Test 3B NaOH Imp	0.0071	0.0559	0.0559	1	249	0.0139	0.0123	12.34914073
CCV ppm Cl	Area	PPM Cl								
5 ppm ICV	0.6506	5.1217								
5 ppm CCV	0.6395	5.0343								
5 ppm CCV	0.6387	5.0280								
5 ppm CCV	0.6452	5.0792								

Appendix F - Reference Method Test Data

Client: Holcim (US) Inc.
Facility: Ravena Cement Plant
Test Location: Kiln 3 Common Stack
Project #: M234506
Test Method: 26A
Test Engineer: PPP
Test Technician: LPH

	<u>Run 1A</u>	<u>Run 2A</u>	<u>Run 3A</u>
Meter ID:	CM43	CM43	CM43
Pitot ID:	S8-058	S8-058	S8-058
Nozzle Diameter (Inches):	0.250	0.250	0.250
Meter Calibration Date:	1/19/2024	1/19/2024	1/19/2024
Meter Calibration Factor (Y):	0.994	0.994	0.994
Meter Orifice Setting (Delta H):	1.788	1.788	1.788
Nozzle Kit ID Number and Material:	Glass #1 865	Glass #1 865	Glass #1 865

Leak Checks

Pre Pitot Leak Check	0.0	@	3.4	"H ₂ O	0.0	@	3.3	"H ₂ O	0.0	@	3.5	"H ₂ O
Post Pitot Leak Check	0.0	@	3.2	"H ₂ O	0.0	@	3.4	"H ₂ O	0.0	@	3.2	"H ₂ O
Pre Nozzle Leak Check	0.0018	@	13	"Hg	0.0000	@	12	"Hg	0.0000	@	13	"Hg
Post Nozzle Leak Check	0.0000	@	11	"Hg	0.0000	@	12	"Hg	0.0000	@	11	"Hg
Pitot Tube Coefficient:	0.834											
Probe Length (Feet):	7.0											
Probe Liner Material:	Glass											
Sample Plane:	Horizontal											
Port Length (Inches):	12.00											
Port Size (Diameter, Inches):	4.00											
Port Type:	Flange											
Duct Shape:	Circular											
Diameter (Feet):	17.708											
Duct Area (Square Feet):	246.280											
Upstream Diameters:	3.3											
Downstream Diameters:	8.8											
Number of Ports Sampled:	4											
Number of Points per Port:	3											
Minutes per Point:	5.0											
Minutes per Reading:	5.0											
Total Number of Traverse Points:	12											
Test Length (Minutes):	60											
Train Type:	Anderson Box											
Source Condition:	Mill on											
Moisture Balance ID:	S10-31											
# of Runs	3											

Run 1A - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill on

Date: 1/30/24
 Start Time: 8:15
 End Time: 9:30

DRY GAS METER CONDITIONS

ΔH : 2.02 in. H₂O
 Meter Temperature, T_m: 73.8 °F
 Sqrt ΔP : 0.817 in. H₂O
 Stack Temperature, T_s: 152.3 °F
 Meter Volume, V_m: 48.488 ft³
 Meter Volume, V_{mstd}: 47.397 dscf
 Meter Volume, V_{wstd}: 4.762 wscf
 Isokinetic Variance: 101.0 %I
 Test Length: 60.00 in mins.
 Nozzle Diameter: 0.250 in inches
 Barometric Pressure: 29.60 in Hg

STACK CONDITIONS

Static Pressure: 1.50 in. H₂O
 Flue Pressure (Ps): 29.71 in. Hg. abs.
 Carbon Dioxide: 8.75 %
 Oxygen: 15.61 %
 Nitrogen: 75.64 %
 Gas Weight dry, Md: 30.024 lb/lb mole
 Gas Weight wet, Ms: 28.927 lb/lb mole
 Excess Air: --- %
 Gas Velocity, Vs: 49.158 fps
 Volumetric Flow: 726,395 acfm
 Volumetric Flow: 565,178 dscfm
 Volumetric Flow: 621,960 scfm

MOISTURE DETERMINATION

Initial Impinger Content: 3457.1 ml Silica Initial Wt. 861.1 grams
 Final Impinger Content: 3548.9 ml Silica Final Wt. 870.4 grams
 Impinger Difference: 91.8 ml Silica Difference: 9.3 grams
 Total Water Gain: 101.1 Moisture, Bws: 0.091 Supersaturation Value, Bws: 0.270

Port- Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	8:15:00	0.64	1.90	154.272	153	70	70	5	261	260	43
1-2	8:20:00	0.69	2.10	158.570	154	70	70	4	266	260	41
1-3	8:25:00	0.60	1.80	162.410	155	71	71	4	252	258	44
	8:30:00			166.145							
2-1	8:35:00	0.69	2.10	166.145	155	73	73	4	256	258	44
2-2	8:40:00	0.70	2.10	170.310	153	73	73	5	260	264	46
2-3	8:45:00	0.65	1.90	174.430	151	74	74	5	253	262	48
	8:50:00			178.338							
3-1	8:55:00	0.68	2.10	178.338	151	75	75	5	252	261	47
3-2	9:00:00	0.69	2.10	182.530	151	75	75	5	257	264	49
3-3	9:05:00	0.66	2.00	186.640	151	75	75	5	256	261	50
	9:10:00			190.564							
4-1	9:15:00	0.67	2.00	190.564	152	76	76	5	254	261	45
4-2	9:20:00	0.70	2.20	194.830	151	77	77	4	254	261	47
4-3	9:25:00	0.64	1.90	198.970	151	77	77	4	266	262	48
	9:30:00			202.760							

Total 1:00:00 48.488 73.8 73.8
 Average 2.02 152.3 73.8 5
 Min 1.80 151.0 70.0 4
 Max 2.20 155.0 77.0 5

Impinger Weight Sheet - Run 1A

Client:	Holcim (US) Inc.	Scale Calibration Check Date:	<u>1/30/2024</u>
Facility:	Ravena Cement Plant	Scale Calibration Check (see <u>QS-6.05C</u> for procedure)	
Test Location:	Kiln 3 Common Stack	must be within $\pm 0.5g$ of certified mass	
Project #:	M234506	<u>Certified Weight, grams</u>	<u>Result, grams</u>
Date:	1/30/2024	200	<u>200.0</u>
Test Method:	26A		
Weighed/Measured By:	EE	500	<u>500.0</u>
Balance ID:	S10-31	700	<u>700.0</u>

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	821.2	783.7	37.5
0.1N H2SO4	707.8	672.5	35.3
Empty	611.5	596.8	14.7
0.1N NaOH	648.8	645.6	3.2
0.1N NaOH	759.6	758.5	1.1
Silica Gel	870.4	861.1	9.3

<u>3,548.9</u> Liquid Final	<u>3,457.1</u> Liquid Initial	<u>91.8</u> Liquid Gain
<u>870.4</u> Silica Final	<u>861.1</u> Silica Initial	<u>9.3</u> Silica Gain

Run 2A - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill on

Date: 1/30/24
 Start Time: 9:50
 End Time: 11:05

DRY GAS METER CONDITIONS				STACK CONDITIONS			
ΔH:	1.96	In. H ₂ O		Static Pressure	1.50	in. H ₂ O	
Meter Temperature, Tm:	77.5	°F		Flue Pressure (Ps):	29.71	in. Hg. abs.	
Sqrt ΔP:	0.801	In. H ₂ O		Carbon Dioxide:	8.91	%	
Stack Temperature, Ts:	151.1	°F		Oxygen:	15.42	%	
Meter Volume, Vm:	47.847	ft ³		Nitrogen:	75.7	%	
Meter Volume, Vmstd:	46.444	dscf		Gas Weight dry, Md:	30.042	lb/lb mole	
Meter Volume, Vwstd:	4.512	wscf		Gas Weight wet, Ms:	28.976	lb/lb mole	
Isokinetic Variance:	100.6	%I		Excess Air:	---	%	
Test Length:	60.00	in mins.		Gas Velocity, Vs:	48.137	fps	
Nozzle Diameter:	0.250	in inches		Volumetric Flow:	711,309	acfm	
Barometric Pressure:	29.60	in Hg		Volumetric Flow:	556,249	dscfm	
				Volumetric Flow:	610,290	scfm	

MOISTURE DETERMINATION					
Initial Impinger Content:	3501.8	ml	Silica Initial Wt.	870.4	grams
Final Impinger Content:	3591.9	ml	Silica Final Wt.	876.1	grams
Impinger Difference:	90.1	ml	Silica Difference:	5.7	grams
Total Water Gain:	95.8		Moisture, Bws:	0.089	
			Supersaturation Value, Bws:	0.262	

Port- Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	9:50:00	0.64	1.90	203.750	151	78	78	4	264	255	45
1-2	9:55:00	0.67	2.10	207.830	147	78	78	5	252	263	46
1-3	10:00:00	0.62	2.00	211.940	127	78	78	5	259	260	48
	10:05:00			215.873							
2-1	10:10:00	0.61	1.80	215.873	154	78	78	5	261	259	46
2-2	10:15:00	0.69	2.10	219.930	153	78	78	5	269	262	49
2-3	10:20:00	0.62	1.90	223.910	154	78	78	5	263	258	51
	10:25:00			227.739							
3-1	10:30:00	0.63	1.90	227.739	155	77	77	5	255	260	50
3-2	10:35:00	0.67	2.00	231.740	155	77	77	5	253	261	50
3-3	10:40:00	0.62	1.90	235.860	153	77	77	5	263	261	50
	10:45:00			239.643							
4-1	10:50:00	0.62	1.90	239.643	153	77	77	5	266	260	52
4-2	10:55:00	0.70	2.10	243.640	155	77	77	5	254	260	53
4-3	11:00:00	0.62	1.90	247.830	156	77	77	5	251	260	53
	11:05:00			251.597							
Total	1:00:00			47.847		77.5	77.5				
Average			1.96		151.1	77.5		5			
Min			1.80		127.0	77.0		4			
Max			2.10		156.0	78.0		5			

Impinger Weight Sheet - Run 2A

Client: Holcim (US) Inc. Facility: Ravena Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/30/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/30/2024</u> Scale Calibration Check (see QS-6.05C for procedure) must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	710.6	686.2	24.4
0.1N H2SO4	786.2	745.3	40.9
Empty	667.5	650.7	16.8
0.1N NaOH	739.8	733.2	6.6
0.1N NaOH	687.8	686.4	1.4
Silica Gel	876.1	870.4	5.7

<u>3,591.9</u> Liquid Final	<u>3,501.8</u> Liquid Initial	<u>90.1</u> Liquid Gain
<u>876.1</u> Silica Final	<u>870.4</u> Silica Initial	<u>5.7</u> Silica Gain

Run 3A - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill on

Date: 1/30/24
 Start Time: 11:25
 End Time: 12:40

DRY GAS METER CONDITIONS				STACK CONDITIONS			
ΔH:	1.92	In. H ₂ O		Static Pressure	1.50	in. H ₂ O	
Meter Temperature, Tm:	66.8	°F		Flue Pressure (Ps):	29.71	in. Hg. abs.	
Sqrt ΔP:	0.807	In. H ₂ O		Carbon Dioxide:	8.83	%	
Stack Temperature, Ts:	154.6	°F		Oxygen:	15.45	%	
Meter Volume, Vm:	47.132	ft ³		Nitrogen:	75.72	%	
Meter Volume, Vmstd:	46.672	dscf		Gas Weight dry, Md:	30.031	lb/lb mole	
Meter Volume, Vwstd:	4.837	wscf		Gas Weight wet, Ms:	28.901	lb/lb mole	
Isokinetic Variance:	101.1	%I		Excess Air:	---	%	
Test Length:	60.00	in mins.		Gas Velocity, Vs:	48.672	fps	
Nozzle Diameter:	0.250	in inches		Volumetric Flow:	719,217	acfm	
Barometric Pressure:	29.60	in Hg		Volumetric Flow:	555,941	dscfm	
				Volumetric Flow:	613,560	scfm	

MOISTURE DETERMINATION					
Initial Impinger Content:	3440.7	ml	Silica Initial Wt.	870.4	grams
Final Impinger Content:	3536.1	ml	Silica Final Wt.	877.7	grams
Impinger Difference:	95.4	ml	Silica Difference:	7.3	grams
Total Water Gain:	102.7		Moisture, Bws:	0.094	
			Supersaturation Value, Bws:	0.285	

Port-Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	11:25:00	0.60	1.80	251.857	154	69	69	5	253	260	38
1-2	11:30:00	0.67	2.00	255.740	155	69	69	5	255	257	40
1-3	11:35:00	0.63	1.70	259.790	155	68	68	5	263	259	44
	11:40:00			263.525							
2-1	11:45:00	0.66	2.00	263.525	154	67	67	5	257	261	45
2-2	11:50:00	0.69	2.00	267.620	155	67	67	5	260	261	45
2-3	11:55:00	0.63	1.90	271.740	154	67	67	5	262	260	45
	12:00:00			275.385							
3-1	12:05:00	0.67	2.00	275.385	154	66	66	5	264	260	45
3-2	12:10:00	0.70	2.00	279.460	155	66	66	5	260	259	46
3-3	12:15:00	0.63	1.90	283.720	155	67	67	5	257	259	47
	12:20:00			287.284							
4-1	12:25:00	0.64	1.90	287.284	154	66	66	5	254	260	48
4-2	12:30:00	0.68	2.00	291.340	155	65	65	5	251	262	48
4-3	12:35:00	0.62	1.80	295.370	155	65	65	5	254	259	49
	12:40:00			298.989							
Total	1:00:00			47.132		66.8	66.8				
Average			1.92		154.6	66.8		5			
Min			1.70		154.0	65.0		5			
Max			2.00		155.0	69.0		5			

Impinger Weight Sheet - Run 3A

Client: Holcim (US) Inc. Facility: Ravena Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/30/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/30/2024</u> Scale Calibration Check (see QS-6.05C for procedure) must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	801.5	767.4	34.1
0.1N H2SO4	709.3	672.4	36.9
Empty	613.7	601.8	11.9
0.1N NaOH	652.9	641.8	11.1
0.1N NaOH	758.7	757.3	1.4
Silica Gel	877.7	870.4	7.3

<u>3,536.1</u> Liquid Final	<u>3,440.7</u> Liquid Initial	<u>95.4</u> Liquid Gain
<u>877.7</u> Silica Final	<u>870.4</u> Silica Initial	<u>7.3</u> Silica Gain

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Test Location: Kiln 3 Common Stack
Project #: M234506
Test Method: 26A
Test Engineer: CMB
Test Technician: LPH

	<u>Run 1B</u>	<u>Run 2B</u>	<u>Run 3B</u>
Meter ID:	CM13	CM13	CM13
Pitot ID:	S8-059	S8-059	S8-059
Nozzle Diameter (Inches):	0.280	0.280	0.280
Meter Calibration Date:	1/16/2024	1/16/2024	1/16/2024
Meter Calibration Factor (Y):	0.987	0.987	0.987
Meter Orifice Setting (Delta H):	1.516	1.516	1.516
Nozzle Kit ID Number and Material:	GLASS #1	GLASS #1	GLASS #1

Leak Checks

Pre Pitot Leak Check	0.0	@	7.0	"H ₂ O	0.0	@	7.0	"H ₂ O	0.0	@	7.0	"H ₂ O
Post Pitot Leak Check	0.0	@	7.0	"H ₂ O	0.0	@	7.0	"H ₂ O	0.0	@	7.0	"H ₂ O
Pre Nozzle Leak Check	0.0000	@	10	"Hg	0.0000	@	10	"Hg	0.0000	@	10	"Hg
Post Nozzle Leak Check	0.0000	@	10	"Hg	0.0000	@	10	"Hg	0.0000	@	10	"Hg
Pitot Tube Coefficient:	0.839											
Probe Length (Feet):	7.0											
Probe Liner Material:	Glass											
Sample Plane:	Horizontal											
Port Length (Inches):	12.00											
Port Size (Diameter, Inches):	4.00											
Port Type:	Flange											
Duct Shape:	Circular											
Diameter (Feet):	17.708											
Duct Area (Square Feet):	246.280											
Upstream Diameters:	3.3											
Downstream Diameters:	8.8											
Number of Ports Sampled:	4											
Number of Points per Port:	3											
Minutes per Point:	5.0											
Minutes per Reading:	5.0											
Total Number of Traverse Points:	12											
Test Length (Minutes):	60											
Train Type:	Anderson Box											
Source Condition:	Mill on											
Diluent Model/Serial Number:	Servomex Single											
Moisture Balance ID:	S10-31											
# of Runs	3											

Run 1B - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill on

Date: 1/30/24
 Start Time: 8:15
 End Time: 9:30

DRY GAS METER CONDITIONS

ΔH : 2.65 in. H₂O
 Meter Temperature, Tm: 73.7 °F
 Sqrt ΔP : 0.815 in. H₂O
 Stack Temperature, Ts: 152.2 °F
 Meter Volume, Vm: 61.384 ft³
 Meter Volume, Vmstd: 59.687 dscf
 Meter Volume, Vwstd: 4.437 wscf
 Isokinetic Variance: 99.1 %I
 Test Length: 60.00 in mins.
 Nozzle Diameter: 0.280 in inches
 Barometric Pressure: 29.60 in Hg

STACK CONDITIONS

Static Pressure: 1.50 in. H₂O
 Flue Pressure (Ps): 29.71 in. Hg. abs.
 Carbon Dioxide: 8.75 %
 Oxygen: 15.61 %
 Nitrogen: 75.64 %
 Gas Weight dry, Md: 30.024 lb/lb mole
 Gas Weight wet, Ms: 29.192 lb/lb mole
 Excess Air: --- %
 Gas Velocity, Vs: 49.095 fps
 Volumetric Flow: 725,471 acfm
 Volumetric Flow: 578,347 dscfm
 Volumetric Flow: 621,338 scfm

MOISTURE DETERMINATION

Initial Impinger Content: 3680.6 ml Silica Initial Wt. 849.6 grams
 Final Impinger Content: 3760.2 ml Silica Final Wt. 864.2 grams
 Impinger Difference: 79.6 ml Silica Difference: 14.6 grams
 Total Water Gain: 94.2 Moisture, Bws: 0.069 Supersaturation Value, Bws: 0.269

Port- Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	8:15:00	0.65	2.60	12.438	153	69	65	5	257	259	40
1-2	8:20:00	0.68	2.70	17.450	154	68	66	5	257	258	37
1-3	8:25:00	0.63	2.50	22.550	155	70	67	5	260	255	40
	8:30:00			27.450							
2-1	8:35:00	0.70	2.80	27.450	155	74	68	5	263	260	41
2-2	8:40:00	0.71	2.80	32.700	153	76	68	5	260	262	41
2-3	8:45:00	0.62	2.50	37.950	152	79	70	5	259	260	43
	8:50:00			42.900							
3-1	8:55:00	0.67	2.70	42.900	151	79	71	5	261	258	46
3-2	9:00:00	0.68	2.70	48.050	151	81	71	5	264	262	46
3-3	9:05:00	0.63	2.50	53.250	151	85	73	5	256	260	47
	9:10:00			58.300							
4-1	9:15:00	0.68	2.70	58.300	151	82	74	5	260	259	44
4-2	9:20:00	0.70	2.80	63.550	150	82	74	5	257	258	44
4-3	9:25:00	0.62	2.50	68.850	150	83	74	5	256	267	45
	9:30:00			73.822							

Total 1:00:00 61.384 77.3 70.1
 Average 2.65 152.2 73.7 5
 Min 2.50 150.0 65.0 5
 Max 2.80 155.0 85.0 5

Impinger Weight Sheet - Run 1B

Client: Holcim (US) Inc. Facility: Ravenna Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/30/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/30/2024</u> Scale Calibration Check (see QS-6.05C for procedure) must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	781.1	743.1	38.0
0.1N H2SO4	782.7	742.6	40.1
Empty	660.2	638.5	21.7
0.1N NaOH	791.1	776.2	14.9
0.1N NaOH	745.1	780.2	-35.1
Silica Gel	864.2	849.6	14.6

<u>3,760.2</u> Liquid Final	<u>3,680.6</u> Liquid Initial	<u>79.6</u> Liquid Gain
<u>864.2</u> Silica Final	<u>849.6</u> Silica Initial	<u>14.6</u> Silica Gain

Run 2B - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill on

Date: 1/30/24
 Start Time: 9:50
 End Time: 11:05

DRY GAS METER CONDITIONS				STACK CONDITIONS			
ΔH:	2.63	In. H ₂ O		Static Pressure	1.50	in. H ₂ O	
Meter Temperature, Tm:	79.1	°F		Flue Pressure (Ps):	29.71	in. Hg. abs.	
Sqrt ΔP:	0.806	In. H ₂ O		Carbon Dioxide:	8.91	%	
Stack Temperature, Ts:	153.0	°F		Oxygen:	15.42	%	
Meter Volume, Vm:	61.322	ft ³		Nitrogen:	75.7	%	
Meter Volume, Vmstd:	59.025	dscf		Gas Weight dry, Md:	30.042	lb/lb mole	
Meter Volume, Vwstd:	5.968	wscf		Gas Weight wet, Ms:	28.937	lb/lb mole	
Isokinetic Variance:	101.1	%I		Excess Air:	---	%	
Test Length:	60.00	in mins.		Gas Velocity, Vs:	48.844	fps	
Nozzle Diameter:	0.280	in inches		Volumetric Flow:	721,759	acfm	
Barometric Pressure:	29.60	in Hg		Volumetric Flow:	560,637	dscfm	
				Volumetric Flow:	617,319	scfm	

MOISTURE DETERMINATION					
Initial Impinger Content:	3572.5	ml	Silica Initial Wt.	835.5	grams
Final Impinger Content:	3684.9	ml	Silica Final Wt.	849.8	grams
Impinger Difference:	112.4	ml	Silica Difference:	14.3	grams
Total Water Gain:	126.7		Moisture, Bws:	0.092	
			Supersaturation Value, Bws:	0.274	

Port-Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	9:50:00	0.67	2.70	75.453	151	79	75	5	266	257	53
1-2	9:55:00	0.71	2.90	80.650	151	84	75	5	250	259	57
1-3	10:00:00	0.61	2.50	86.000	152	88	76	5	260	261	55
	10:05:00			90.950							
2-1	10:10:00	0.62	2.50	90.950	155	84	75	5	264	260	53
2-2	10:15:00	0.65	2.60	95.950	154	85	75	5	260	260	54
2-3	10:20:00	0.64	2.60	101.050	153	86	75	5	270	259	55
	10:25:00			106.150							
3-1	10:30:00	0.65	2.60	106.150	155	83	74	5	260	261	53
3-2	10:35:00	0.69	2.80	111.250	155	84	74	5	260	259	53
3-3	10:40:00	0.60	2.50	116.500	142	86	75	5	260	260	53
	10:45:00			121.450							
4-1	10:50:00	0.69	2.80	121.450	156	81	75	5	260	258	49
4-2	10:55:00	0.67	2.70	126.700	156	81	74	5	260	261	50
4-3	11:00:00	0.61	2.40	131.850	156	81	74	5	260	258	50
	11:05:00			136.775							

Total	1:00:00			61.322		83.5	74.8				
Average			2.63		153.0	79.1		5			
Min			2.40		142.0	74.0		5			
Max			2.90		156.0	88.0		5			

Impinger Weight Sheet - Run 2B

Client: Holcim (US) Inc. Facility: Ravena Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/30/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/30/2024</u> <u>Scale Calibration Check (see QS-6.05C for procedure)</u> must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	712.8	686.7	26.1
0.1N H2SO4	807.2	758.2	49.0
Empty	667.9	645.0	22.9
0.1N NaOH	765.2	753.8	11.4
0.1N NaOH	731.8	728.8	3.0
Silica Gel	849.8	835.5	14.3

<u>3,684.9</u> Liquid Final	<u>3,572.5</u> Liquid Initial	<u>112.4</u> Liquid Gain
<u>849.8</u> Silica Final	<u>835.5</u> Silica Initial	<u>14.3</u> Silica Gain

Run 3B - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill on

Date: 1/30/24
 Start Time: 11:25
 End Time: 12:40

DRY GAS METER CONDITIONS				STACK CONDITIONS			
	ΔH :	2.58	In. H ₂ O	Static Pressure	1.50	in. H ₂ O	
Meter Temperature, Tm:	63.0	°F		Flue Pressure (Ps):	29.71	in. Hg. abs.	
	Sqrt ΔP :	0.812	In. H ₂ O	Carbon Dioxide:	8.83	%	
Stack Temperature, Ts:	153.6	°F		Oxygen:	15.45	%	
Meter Volume, Vm:	59.939	ft ³		Nitrogen:	75.72	%	
Meter Volume, Vmstd:	59.460	dscf		Gas Weight dry, Md:	30.031	lb/lb mole	
Meter Volume, Vwstd:	5.652	wscf		Gas Weight wet, Ms:	28.986	lb/lb mole	
Isokinetic Variance:	100.7	%		Excess Air:	---	%	
	Test Length:	60.00	in mins.	Gas Velocity, Vs:	49.172	fps	
	Nozzle Diameter:	0.280	in inches	Volumetric Flow:	726,601	acfm	
	Barometric Pressure:	29.60	in Hg	Volumetric Flow:	566,975	dscfm	
				Volumetric Flow:	620,870	scfm	

MOISTURE DETERMINATION

Initial Impinger Content:	3606.5	ml	Silica Initial Wt.	864.2	grams
Final Impinger Content:	3714.5	ml	Silica Final Wt.	876.2	grams
Impinger Difference:	108.0	ml	Silica Difference:	12.0	grams
Total Water Gain:	120.0		Moisture, Bws:	0.087	
			Supersaturation Value, Bws:	0.278	

Port- Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	11:25:00	0.66	2.60	39.750	154	67	67	5	260	258	39
1-2	11:30:00	0.68	2.70	44.800	154	68	64	5	260	259	43
1-3	11:35:00	0.63	2.50	49.900	155	69	63	5	260	261	43
	11:40:00			54.800							
2-1	11:45:00	0.67	2.60	54.800	153	65	61	5	260	260	44
2-2	11:50:00	0.70	2.80	59.850	148	65	60	5	259	259	44
2-3	11:55:00	0.62	2.40	65.000	151	66	60	5	261	261	46
	12:00:00			69.850							
3-1	12:05:00	0.68	2.60	69.850	155	63	58	5	260	259	48
3-2	12:10:00	0.71	2.80	74.900	155	64	58	5	260	259	48
3-3	12:15:00	0.63	2.40	80.050	154	64	58	5	260	260	48
	12:20:00			84.900							
4-1	12:25:00	0.65	2.50	84.900	154	67	57	5	260	260	54
4-2	12:30:00	0.68	2.60	89.850	155	67	57	5	260	261	55
4-3	12:35:00	0.61	2.40	94.900	155	68	57	5	260	261	56
	12:40:00			99.689							

Total	1:00:00			59.939		66.1	60.0				
Average			2.58		153.6	63.0		5			
Min			2.40		148.0	57.0		5			
Max			2.80		155.0	69.0		5			

Impinger Weight Sheet - Run 3B

Client: Holcim (US) Inc. Facility: Ravena Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/30/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/30/2024</u> <u>Scale Calibration Check (see QS-6.05C for procedure)</u> must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	766.6	726.0	40.6
0.1N H2SO4	781.2	738.5	42.7
Empty	658.5	644.7	13.8
0.1N NaOH	765.6	757.5	8.1
0.1N NaOH	742.6	739.8	2.8
Silica Gel	876.2	864.2	12.0

<u>3,714.5</u> Liquid Final	<u>3,606.5</u> Liquid Initial	<u>108.0</u> Liquid Gain
<u>876.2</u> Silica Final	<u>864.2</u> Silica Initial	<u>12.0</u> Silica Gain

Client: Holcim (US) Inc.
 Facility: Ravena Cement Plant
 Project #: M234506
 Test Location: Kiln 3 Common Stack
 Date: 1/30/24

Run 1								Analyzer Data
Spectrum	Time	FTIR Data				Cell Temp	Pressure	O2 % (dry)
		H2O %	CO2 % (wet)	HCN ppmvw	HF ppmvw			
RUN 1_000233.LAB	8:15	9.04	7.84	1.13	≤ 0.10	190.88	0.99	15.71
RUN 1_000234.LAB	8:16	9.06	8.08	1.41	≤ 0.10	190.93	0.99	15.65
RUN 1_000235.LAB	8:17	9.09	8.33	1.32	≤ 0.10	190.85	0.99	15.46
RUN 1_000236.LAB	8:18	9.05	8.06	1.18	≤ 0.10	190.84	0.99	15.58
RUN 1_000237.LAB	8:19	9.02	8.10	1.30	≤ 0.10	190.87	0.99	15.61
RUN 1_000238.LAB	8:20	9.00	7.89	1.26	≤ 0.10	190.83	0.99	15.70
RUN 1_000239.LAB	8:21	9.01	7.93	1.36	≤ 0.10	190.88	0.99	15.70
RUN 1_000240.LAB	8:22	8.98	7.91	1.28	≤ 0.10	190.87	0.99	15.69
RUN 1_000241.LAB	8:23	8.97	7.95	1.26	≤ 0.10	190.84	0.99	15.67
RUN 1_000242.LAB	8:24	8.98	8.09	1.36	≤ 0.10	190.78	0.99	15.65
RUN 1_000243.LAB	8:25	9.04	7.98	1.27	≤ 0.10	190.86	0.99	15.61
RUN 1_000244.LAB	8:26	9.01	7.77	1.15	≤ 0.10	190.84	0.99	15.73
RUN 1_000245.LAB	8:27	9.01	7.99	1.26	≤ 0.10	190.85	0.99	15.70
RUN 1_000246.LAB	8:28	9.05	7.92	1.24	≤ 0.10	190.80	0.99	15.69
RUN 1_000247.LAB	8:29	9.03	8.03	1.04	≤ 0.10	190.83	0.99	15.65
RUN 1_000248.LAB	8:30	9.05	7.94	1.22	≤ 0.10	190.85	0.99	15.66
RUN 1_000249.LAB	8:31	9.04	7.87	1.32	≤ 0.10	190.85	0.99	15.68
RUN 1_000250.LAB	8:32	9.05	7.92	1.11	≤ 0.10	190.84	0.99	15.74
RUN 1_000251.LAB	8:33	9.05	7.94	1.08	≤ 0.10	190.79	0.99	15.71
RUN 1_000252.LAB	8:34	9.04	7.85	1.38	≤ 0.10	190.81	0.99	15.72
RUN 1_000253.LAB	8:35	9.03	7.99	1.29	≤ 0.10	190.76	0.99	15.74
RUN 1_000254.LAB	8:36	9.04	7.96	1.25	≤ 0.10	190.75	0.99	15.70
RUN 1_000255.LAB	8:37	9.01	7.78	1.18	≤ 0.10	190.75	0.99	15.71
RUN 1_000256.LAB	8:38	9.01	7.91	1.21	≤ 0.10	190.73	0.99	15.77
RUN 1_000257.LAB	8:39	8.82	8.00	1.10	≤ 0.10	190.75	0.99	15.74
RUN 1_000258.LAB	8:40	8.87	7.85	1.17	≤ 0.10	190.70	0.99	15.69
RUN 1_000259.LAB	8:41	9.08	8.00	1.26	≤ 0.10	190.77	0.99	15.76
RUN 1_000260.LAB	8:42	9.10	7.85	1.12	≤ 0.10	190.76	0.99	15.73
RUN 1_000261.LAB	8:43	9.07	7.97	1.23	≤ 0.10	190.77	0.99	15.79
RUN 1_000262.LAB	8:44	9.05	7.90	1.20	≤ 0.10	190.74	0.99	15.77
RUN 1_000263.LAB	8:45	9.06	7.97	1.35	≤ 0.10	190.71	0.99	15.74
RUN 1_000264.LAB	8:46	9.07	7.80	1.18	≤ 0.10	190.76	0.99	15.75
RUN 1_000265.LAB	8:47	9.13	7.86	1.12	≤ 0.10	190.74	0.99	15.76
RUN 1_000266.LAB	8:48	9.07	7.93	1.27	≤ 0.10	190.75	0.99	15.81
RUN 1_000267.LAB	8:49	9.03	8.04	0.99	≤ 0.10	190.75	0.99	15.79
RUN 1_000268.LAB	8:50	9.01	7.99	1.14	≤ 0.10	190.79	0.99	15.78
RUN 1_000269.LAB	8:51	9.04	8.08	1.31	≤ 0.10	190.76	0.99	15.76
RUN 1_000270.LAB	8:52	9.01	8.00	1.14	≤ 0.10	190.75	0.99	15.74
RUN 1_000271.LAB	8:53	9.05	7.96	1.05	≤ 0.10	190.73	0.99	15.71
RUN 1_000272.LAB	8:54	9.08	7.96	1.33	≤ 0.10	190.84	0.99	15.75
RUN 1_000273.LAB	8:55	9.09	8.04	1.03	≤ 0.10	190.79	0.99	15.78
RUN 1_000274.LAB	8:56	9.10	8.09	1.20	≤ 0.10	190.74	0.99	15.78
RUN 1_000275.LAB	8:57	9.08	8.02	1.17	≤ 0.10	190.79	0.99	15.74
RUN 1_000276.LAB	8:58	9.07	8.06	1.27	≤ 0.10	190.74	0.99	15.72
RUN 1_000277.LAB	8:59	9.09	8.00	1.23	≤ 0.10	190.68	0.99	15.74
RUN 1_000278.LAB	9:00	9.10	7.98	1.23	≤ 0.10	190.74	0.99	15.73
RUN 1_000279.LAB	9:01	9.10	7.92	1.16	≤ 0.10	190.75	0.99	15.75
RUN 1_000280.LAB	9:02	9.10	7.94	1.15	≤ 0.10	190.75	0.99	15.77
RUN 1_000281.LAB	9:03	9.13	7.93	1.23	≤ 0.10	190.85	0.99	15.76
RUN 1_000282.LAB	9:04	9.12	7.94	0.94	≤ 0.10	190.80	0.99	15.79
RUN 1_000283.LAB	9:05	9.12	8.06	1.12	≤ 0.10	190.84	0.99	15.78
RUN 1_000284.LAB	9:06	9.09	7.84	1.04	≤ 0.10	190.86	0.99	15.82
RUN 1_000285.LAB	9:07	9.07	7.98	1.15	≤ 0.10	190.83	0.99	15.78
RUN 1_000286.LAB	9:08	9.10	8.03	1.15	≤ 0.10	190.80	0.99	15.82
RUN 1_000287.LAB	9:09	9.12	8.06	1.08	≤ 0.10	190.84	0.99	15.87
RUN 1_000288.LAB	9:10	9.14	7.90	1.13	≤ 0.10	190.82	0.99	15.78
RUN 1_000289.LAB	9:11	9.14	7.85	1.09	≤ 0.10	190.82	0.99	15.79
RUN 1_000290.LAB	9:12	9.14	7.84	1.26	≤ 0.10	190.85	0.99	15.78
RUN 1_000291.LAB	9:13	9.07	7.92	1.25	≤ 0.10	190.88	0.99	15.83
RUN 1_000292.LAB	9:14	8.82	7.96	1.19	≤ 0.10	190.81	0.99	15.88
Average		9.05	7.96	1.20	≤ 0.10	190.80	0.99	15.73

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Project #: M234506
 Test Location: Kiln 3 Common Stack
 Date: 1/30/24

Run 2								Analyzer Data O2 % (dry)
Spectrum	Time	H2O %	CO2 % (wet)	HCN ppmvw	HF ppmvw	Cell Temp	Pressure	
RUN 2_000376.LAB	9:50	8.97	8.0	1.22	≤ 0.10	190.6	0.99	15.49
RUN 2_000377.LAB	9:51	8.96	8.2	1.42	≤ 0.10	190.6	0.99	15.37
RUN 2_000378.LAB	9:52	8.99	8.4	1.34	≤ 0.10	190.6	0.99	15.28
RUN 2_000379.LAB	9:53	9.02	8.2	1.31	≤ 0.10	190.6	0.99	15.37
RUN 2_000380.LAB	9:54	8.86	8.0	1.27	≤ 0.10	190.6	0.99	15.45
RUN 2_000381.LAB	9:55	8.70	8.1	1.38	≤ 0.10	190.6	0.99	15.43
RUN 2_000382.LAB	9:56	8.64	8.0	1.16	≤ 0.10	190.6	0.99	15.48
RUN 2_000383.LAB	9:57	8.86	8.4	1.22	≤ 0.10	190.6	0.99	15.38
RUN 2_000384.LAB	9:58	8.93	8.2	1.32	≤ 0.10	190.6	0.99	15.38
RUN 2_000385.LAB	9:59	8.87	8.2	1.34	≤ 0.10	190.6	0.99	15.37
RUN 2_000386.LAB	10:00	9.05	7.9	1.19	≤ 0.10	190.6	0.99	15.48
RUN 2_000387.LAB	14:57	9.10	8.1	1.28	≤ 0.10	190.6	0.99	15.46
RUN 2_000388.LAB	14:58	9.05	8.1	1.28	≤ 0.10	190.7	0.99	15.45
RUN 2_000389.LAB	14:59	9.02	8.0	1.06	≤ 0.10	190.7	0.99	15.46
RUN 2_000390.LAB	15:00	9.04	8.0	1.44	≤ 0.10	190.7	0.99	15.51
RUN 2_000391.LAB	15:01	9.00	8.2	1.17	≤ 0.10	190.6	0.99	15.45
RUN 2_000392.LAB	15:02	9.00	8.0	1.25	≤ 0.10	190.7	0.99	15.41
RUN 2_000393.LAB	15:03	8.97	8.1	1.06	≤ 0.10	190.7	0.99	15.54
RUN 2_000394.LAB	15:04	8.88	8.3	1.32	≤ 0.10	190.6	0.99	15.37
RUN 2_000395.LAB	15:05	8.86	8.5	1.29	≤ 0.10	190.5	0.99	15.32
RUN 2_000396.LAB	15:06	8.90	8.4	1.30	≤ 0.10	190.8	0.99	15.23
RUN 2_000397.LAB	15:07	8.94	8.3	1.21	≤ 0.10	190.5	0.99	15.29
RUN 2_000398.LAB	15:08	9.01	8.4	1.39	≤ 0.10	190.6	0.99	15.32
RUN 2_000399.LAB	15:09	9.04	8.2	1.26	≤ 0.10	190.5	0.99	15.31
RUN 2_000400.LAB	15:10	9.01	7.8	1.36	≤ 0.10	190.6	0.99	15.54
RUN 2_000401.LAB	15:11	9.03	8.2	1.24	≤ 0.10	190.4	0.99	15.70
RUN 2_000402.LAB	15:12	9.04	8.1	1.16	≤ 0.10	190.6	0.99	15.49
RUN 2_000403.LAB	15:13	9.05	8.1	1.36	≤ 0.10	190.5	0.99	15.51
RUN 2_000404.LAB	15:14	9.00	8.1	1.36	≤ 0.10	190.5	0.99	15.53
RUN 2_000405.LAB	15:15	9.05	8.1	1.23	≤ 0.10	190.5	0.99	15.52
RUN 2_000406.LAB	15:16	9.07	8.0	1.29	≤ 0.10	190.6	0.99	15.50
RUN 2_000407.LAB	15:17	9.02	8.1	1.30	≤ 0.10	190.5	0.99	15.52
RUN 2_000408.LAB	15:18	9.05	7.9	1.21	≤ 0.10	190.4	0.99	15.53
RUN 2_000409.LAB	15:19	9.10	8.1	1.25	≤ 0.10	190.5	0.99	15.56
RUN 2_000410.LAB	15:20	9.07	8.0	1.17	≤ 0.10	190.5	0.99	15.51
RUN 2_000411.LAB	15:21	9.09	8.1	1.27	≤ 0.10	190.5	0.99	15.53
RUN 2_000412.LAB	15:22	9.09	8.1	1.24	≤ 0.10	190.5	0.99	15.49
RUN 2_000413.LAB	15:23	9.09	8.2	1.29	≤ 0.10	190.5	0.99	15.48
RUN 2_000414.LAB	15:24	9.11	8.0	1.14	≤ 0.10	190.5	0.99	15.44
RUN 2_000415.LAB	15:25	9.05	8.2	1.27	≤ 0.10	190.5	0.99	15.48
RUN 2_000416.LAB	15:26	9.07	8.1	1.24	≤ 0.10	190.5	0.99	15.51
RUN 2_000417.LAB	15:27	9.06	8.1	1.35	≤ 0.10	190.5	0.99	15.45
RUN 2_000418.LAB	15:28	9.02	8.1	1.29	≤ 0.10	190.5	0.99	15.49
RUN 2_000419.LAB	15:29	8.72	8.2	1.22	≤ 0.10	190.5	0.99	15.49
RUN 2_000420.LAB	15:30	8.82	8.1	1.13	≤ 0.10	190.5	0.99	15.45
RUN 2_000421.LAB	15:31	8.89	8.0	1.17	≤ 0.10	190.5	0.99	15.45
RUN 2_000422.LAB	15:32	9.20	8.0	1.22	≤ 0.10	190.5	0.99	15.44
RUN 2_000423.LAB	15:33	9.20	8.1	1.18	≤ 0.10	190.5	0.99	15.51
RUN 2_000424.LAB	15:34	9.19	8.0	1.26	≤ 0.10	190.5	0.99	15.49
RUN 2_000425.LAB	15:35	9.14	8.0	1.13	≤ 0.10	190.5	0.99	15.47
RUN 2_000426.LAB	15:36	9.13	8.0	1.30	≤ 0.10	190.6	0.99	15.51
RUN 2_000427.LAB	15:37	9.11	8.1	1.31	≤ 0.10	190.5	0.99	15.54
RUN 2_000428.LAB	15:38	9.10	8.1	1.19	≤ 0.10	190.5	0.99	15.54
RUN 2_000429.LAB	15:39	9.10	8.1	1.25	≤ 0.10	190.4	0.99	15.48
RUN 2_000430.LAB	15:40	9.10	8.0	1.24	≤ 0.10	190.5	0.99	15.50
RUN 2_000431.LAB	15:41	9.10	8.1	1.26	≤ 0.10	190.5	0.99	15.53
RUN 2_000432.LAB	15:42	9.07	7.9	1.09	≤ 0.10	190.5	0.99	15.46
RUN 2_000433.LAB	15:43	9.07	7.9	1.14	≤ 0.10	190.5	0.99	15.48
RUN 2_000434.LAB	15:44	9.10	7.9	1.12	≤ 0.10	190.5	0.99	15.53
RUN 2_000435.LAB	15:45	9.11	7.9	1.29	≤ 0.10	190.5	0.99	15.54
Average		9.01	8.11	1.25	≤ 0.10	190.55	0.99	15.46

Client: Holcim (US) Inc.
Facility: Ravena Cement Plant
Project #: M234506
Test Location: Kiln 3 Common Stack
Date: 1/30/24

Run 3

Spectrum	Time	H2O %	FTIR Data		HF ppmvw	Cell Temp	Pressure	Analyzer Data O2 % (dry)
			CO2 % (wet)	HCN ppmvw				
RUN 3_000510.LAB	11:25	8.92	8.2	1.19	≤ 0.10	190.5	0.99	15.30
RUN 3_000511.LAB	11:26	8.91	8.0	1.02	≤ 0.10	190.4	0.99	15.36
RUN 3_000512.LAB	11:27	8.89	8.1	1.17	≤ 0.10	190.4	0.99	15.37
RUN 3_000513.LAB	11:28	8.88	7.9	1.27	≤ 0.10	190.5	0.99	15.38
RUN 3_000514.LAB	11:29	8.86	8.1	1.28	≤ 0.10	190.5	0.99	15.39
RUN 3_000515.LAB	11:30	8.86	8.1	1.20	≤ 0.10	190.5	0.99	15.37
RUN 3_000516.LAB	11:31	8.84	8.0	1.07	≤ 0.10	190.4	0.99	15.33
RUN 3_000517.LAB	11:32	8.85	8.0	1.13	≤ 0.10	190.5	0.99	15.38
RUN 3_000518.LAB	11:33	8.82	8.0	1.09	≤ 0.10	190.4	0.99	15.37
RUN 3_000519.LAB	11:34	8.85	7.9	1.04	≤ 0.10	190.5	0.99	15.40
RUN 3_000520.LAB	11:35	8.86	8.1	1.15	≤ 0.10	190.5	0.99	15.39
RUN 3_000521.LAB	11:36	8.86	8.0	1.16	≤ 0.10	190.5	0.99	15.36
RUN 3_000522.LAB	11:37	8.88	8.1	1.32	≤ 0.10	190.5	0.99	15.37
RUN 3_000523.LAB	11:38	8.91	8.0	1.16	≤ 0.10	190.4	0.99	15.35
RUN 3_000524.LAB	11:39	8.91	8.1	1.18	≤ 0.10	190.4	0.99	15.33
RUN 3_000525.LAB	11:40	8.92	8.0	1.22	≤ 0.10	190.6	0.99	15.32
RUN 3_000526.LAB	11:41	8.95	8.1	1.22	≤ 0.10	190.6	0.99	15.35
RUN 3_000527.LAB	11:42	8.96	8.1	1.19	≤ 0.10	190.5	0.99	15.33
RUN 3_000528.LAB	11:43	8.96	8.2	1.24	≤ 0.10	190.6	0.99	15.32
RUN 3_000529.LAB	11:44	8.93	8.1	1.22	≤ 0.10	190.7	0.99	15.24
RUN 3_000530.LAB	11:45	8.95	8.0	1.12	≤ 0.10	190.6	0.99	15.29
RUN 3_000531.LAB	11:46	8.77	8.1	1.21	≤ 0.10	190.6	0.99	15.31
RUN 3_000532.LAB	11:47	8.61	8.1	1.18	≤ 0.10	190.6	0.99	15.33
RUN 3_000533.LAB	11:48	8.53	8.1	1.05	≤ 0.10	190.6	0.99	15.29
RUN 3_000534.LAB	11:49	8.68	8.1	1.23	≤ 0.10	190.6	0.99	15.31
RUN 3_000535.LAB	11:50	8.98	8.1	1.29	≤ 0.10	190.6	0.99	15.31
RUN 3_000536.LAB	11:51	8.97	8.1	1.29	≤ 0.10	190.6	0.99	15.30
RUN 3_000537.LAB	11:52	8.95	8.0	1.19	≤ 0.10	190.6	0.99	15.28
RUN 3_000538.LAB	11:53	8.96	8.0	1.15	≤ 0.10	190.6	0.99	15.32
RUN 3_000539.LAB	11:54	8.97	8.2	1.26	≤ 0.10	190.6	0.99	15.31
RUN 3_000540.LAB	11:55	8.95	8.1	1.14	≤ 0.10	190.7	0.99	15.32
RUN 3_000541.LAB	11:56	8.93	8.0	1.23	≤ 0.10	190.5	0.99	15.27
RUN 3_000542.LAB	11:57	8.96	8.4	1.30	≤ 0.10	190.6	0.99	15.32
RUN 3_000543.LAB	11:58	8.95	8.3	1.26	≤ 0.10	190.6	0.99	15.32
RUN 3_000544.LAB	11:59	8.94	8.2	1.04	≤ 0.10	190.6	0.99	15.15
RUN 3_000545.LAB	12:00	8.92	8.1	1.20	≤ 0.10	190.6	0.99	15.21
RUN 3_000546.LAB	12:01	8.92	8.1	1.24	≤ 0.10	190.6	0.99	15.25
RUN 3_000547.LAB	12:02	8.92	7.9	1.31	≤ 0.10	190.7	0.99	15.31
RUN 3_000548.LAB	12:03	8.93	8.1	1.34	≤ 0.10	190.7	0.99	15.32
RUN 3_000549.LAB	12:04	8.90	8.0	1.20	≤ 0.10	190.7	0.99	15.36
RUN 3_000550.LAB	12:05	8.92	8.1	1.13	≤ 0.10	190.6	0.99	15.33
RUN 3_000551.LAB	12:06	8.95	8.0	1.17	≤ 0.10	190.6	0.99	15.33
RUN 3_000552.LAB	12:07	8.96	7.9	1.06	≤ 0.10	190.6	0.99	15.32
RUN 3_000553.LAB	12:08	8.99	8.0	1.23	≤ 0.10	190.6	0.99	15.33
RUN 3_000554.LAB	12:09	9.02	8.0	1.11	≤ 0.10	190.6	0.99	15.33
RUN 3_000555.LAB	12:10	9.03	7.9	1.11	≤ 0.10	190.6	0.99	15.36
RUN 3_000556.LAB	12:11	9.07	8.1	1.26	≤ 0.10	190.6	0.99	15.35
RUN 3_000557.LAB	12:12	9.08	8.0	1.39	≤ 0.10	190.7	0.99	15.41
RUN 3_000558.LAB	12:13	9.09	8.0	1.28	≤ 0.10	190.6	0.99	15.35
RUN 3_000559.LAB	12:14	9.05	8.0	1.23	≤ 0.10	190.7	0.99	15.37
RUN 3_000560.LAB	12:15	9.04	8.0	1.29	≤ 0.10	190.6	0.99	15.36
RUN 3_000561.LAB	12:16	9.00	8.0	1.15	≤ 0.10	190.6	0.99	15.40
RUN 3_000562.LAB	12:17	9.01	8.0	1.26	≤ 0.10	190.7	0.99	15.37
RUN 3_000563.LAB	12:18	8.98	7.9	1.21	≤ 0.10	190.6	0.99	15.38
RUN 3_000564.LAB	12:19	8.98	7.9	1.08	≤ 0.10	190.7	0.99	15.37
RUN 3_000565.LAB	12:20	8.98	7.9	1.25	≤ 0.10	190.7	0.99	15.36
RUN 3_000566.LAB	12:21	8.98	8.1	1.30	≤ 0.10	190.7	0.99	15.40
RUN 3_000567.LAB	12:22	8.98	8.1	1.25	≤ 0.10	190.7	0.99	15.42
RUN 3_000568.LAB	12:23	8.68	8.0	1.38	≤ 0.10	190.7	0.99	15.42
RUN 3_000569.LAB	12:24	8.74	8.0	1.30	≤ 0.10	190.7	0.99	15.33
Average		8.92	8.04	1.20	≤ 0.10	190.59	0.99	15.34

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Test Location: Kiln 3 Common Stack
Project #: M234506
Test Method: 26A
Test Engineer: FJD
Test Technician: LPH

	<u>Run 1A</u>	<u>Run 2A</u>	<u>Run 3A</u>
Meter ID:	CM43	CM43	CM43
Pitot ID:	S8-058	S8-058	S8-058
Nozzle Diameter (Inches):	0.250	0.250	0.250
Meter Calibration Date:	1/19/2024	1/19/2024	1/19/2024
Meter Calibration Factor (Y):	0.994	0.994	0.994
Meter Orifice Setting (Delta H):	1.788	1.788	1.788
Nozzle Kit ID Number and Material:	Glass #1 865	Glass #1 865	Glass #1 865

Leak Checks

Pre Pitot Leak Check	0.0	@	3.5	"H ₂ O	0.0	@	3.5	"H ₂ O	0.0	@	3.5	"H ₂ O
Post Pitot Leak Check	0.0	@	3.5	"H ₂ O	0.0	@	3.5	"H ₂ O	0.0	@	3.5	"H ₂ O
Pre Nozzle Leak Check	0.0000	@	14	"Hg	0.0000	@	14	"Hg	0.0000	@	14	"Hg
Post Nozzle Leak Check	0.0000	@	14	"Hg	0.0000	@	14	"Hg	0.0000	@	14	"Hg
Pitot Tube Coefficient:	0.834											
Probe Length (Feet):	7.0											
Probe Liner Material:	Glass											
Sample Plane:	Horizontal											
Port Length (Inches):	12.00											
Port Size (Diameter, Inches):	4.00											
Port Type:	Flange											
Duct Shape:	Circular											
Diameter (Feet):	17.708											
Duct Area (Square Feet):	246.280											
Upstream Diameters:	3.3											
Downstream Diameters:	8.8											
Number of Ports Sampled:	4											
Number of Points per Port:	3											
Minutes per Point:	5.0											
Minutes per Reading:	5.0											
Total Number of Traverse Points:	12											
Test Length (Minutes):	60											
Train Type:	Anderson Box											
Source Condition:	Mill OFF											
Moisture Balance ID:	S10-31											
# of Runs	3											

Run 1A - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill OFF

Date: 1/31/24
 Start Time: 8:20
 End Time: 9:35

DRY GAS METER CONDITIONS

ΔH: 0.94 in. H₂O
 Meter Temperature, Tm: 50.2 °F
 Sqrt ΔP: 0.578 in. H₂O
 Stack Temperature, Ts: 173.7 °F
 Meter Volume, Vm: 33.630 ft³
 Meter Volume, Vmstd: 34.329 dscf
 Meter Volume, Vwstd: 4.644 wscf
 Isokinetic Variance: 108.7 %I
 Test Length: 60.00 in mins.
 Nozzle Diameter: 0.250 in inches
 Barometric Pressure: 29.62 in Hg

STACK CONDITIONS

Static Pressure 1.50 in. H₂O
 Flue Pressure (Ps): 29.73 in. Hg. abs.
 Carbon Dioxide: 12.86 %
 Oxygen: 12.93 %
 Nitrogen: 74.21 %
 Gas Weight dry, Md: 30.575 lb/lb mole
 Gas Weight wet, Ms: 29.076 lb/lb mole
 Excess Air: --- %
 Gas Velocity, Vs: 35.305 fps
 Volumetric Flow: 521,701 acfm
 Volumetric Flow: 380,477 dscfm
 Volumetric Flow: 431,948 scfm

MOISTURE DETERMINATION

Initial Impinger Content: 3641.1 ml Silica Initial Wt. 876.2 grams
 Final Impinger Content: 3734.1 ml Silica Final Wt. 881.8 grams
 Impinger Difference: 93.0 ml Silica Difference: 5.6 grams
 Total Water Gain: 98.6 Moisture, Bws: 0.119 Supersaturation Value, Bws: 0.446

Port- Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	8:20:00	0.25	0.70	366.610	169	52	49	4	270	266	42
1-2	8:25:00	0.23	0.64	369.990	164	49	49	4	260	260	49
1-3	8:30:00	0.21	0.53	371.380	164	50	49	4	260	261	50
	8:35:00			373.670							
2-1	8:40:00	0.36	1.00	373.670	178	50	50	4	260	260	53
2-2	8:45:00	0.34	0.95	376.500	176	50	50	3	260	260	45
2-3	8:50:00	0.32	0.89	378.930	176	50	50	3	260	260	45
	8:55:00			381.930							
3-1	9:00:00	0.41	1.14	381.230	175	50	50	2.5	260	260	44
3-2	9:05:00	0.38	1.05	384.600	174	50	50	2.5	259	259	45
3-3	9:10:00	0.36	1.00	387.550	174	50	50	2.5	260	260	45
	9:15:00			390.520							
4-1	9:20:00	0.42	1.17	390.520	178	51	51	2.5	265	261	51
4-2	9:25:00	0.40	1.11	393.610	178	51	51	2.5	266	261	51
4-3	9:30:00	0.38	1.05	396.430	178	51	51	2.5	265	261	51
	9:35:00			399.540							

Total 1:00:00 33.630 50.3 50.0
 Average 0.94 173.7 50.2 3
 Min 0.53 164.0 49.0 3
 Max 1.17 178.0 52.0 4

Impinger Weight Sheet - Run 1A

Client: Holcim (US) Inc. Facility: Ravena Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/31/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/31/2024</u> <u>Scale Calibration Check (see QS-6.05C for procedure)</u> must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	811.9	745.5	66.4
0.1N H2SO4	759.8	736.5	23.3
Empty	648.9	648.1	0.8
0.1N NaOH	759.4	757.9	1.5
0.1N NaOH	754.1	753.1	1.0
Silica Gel	881.8	876.2	5.6

<u>3,734.1</u> Liquid Final	<u>3,641.1</u> Liquid Initial	<u>93.0</u> Liquid Gain
<u>881.8</u> Silica Final	<u>876.2</u> Silica Initial	<u>5.6</u> Silica Gain

Run 2A - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill OFF

Date: 1/31/24
 Start Time: 9:55
 End Time: 11:10

DRY GAS METER CONDITIONS				STACK CONDITIONS		
ΔH:	1.09	In. H ₂ O		Static Pressure	1.50	in. H ₂ O
Meter Temperature, Tm:	55.8	°F		Flue Pressure (Ps):	29.73	in. Hg. abs.
Sqrt ΔP:	0.626	In. H ₂ O		Carbon Dioxide:	12.85	%
Stack Temperature, Ts:	178.5	°F		Oxygen:	12.92	%
Meter Volume, Vm:	35.150	ft ³		Nitrogen:	74.2	%
Meter Volume, Vmstd:	35.506	dscf		Gas Weight dry, Md:	30.573	lb/lb mole
Meter Volume, Vwstd:	4.041	wscf		Gas Weight wet, Ms:	29.288	lb/lb mole
Isokinetic Variance:	102.7	%I		Excess Air:	---	%
Test Length:	60.00	in mins.		Gas Velocity, Vs:	38.209	fps
Nozzle Diameter:	0.250	in inches		Volumetric Flow:	564,608	acfm
Barometric Pressure:	29.62	in Hg		Volumetric Flow:	416,526	dscfm
				Volumetric Flow:	463,934	scfm

MOISTURE DETERMINATION					
Initial Impinger Content:	3426.5	ml	Silica Initial Wt.	847.6	grams
Final Impinger Content:	3501.7	ml	Silica Final Wt.	858.2	grams
Impinger Difference:	75.2	ml	Silica Difference:	10.6	grams
Total Water Gain:	85.8		Moisture, Bws:	0.102	
			Supersaturation Value, Bws:	0.497	

Port-Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	9:55:00	0.37	1.03	399.711	180	55	55	2	251	260	50
1-2	10:00:00	0.35	0.98	403.000	180	55	55	2	251	259	51
1-3	10:05:00	0.33	0.92	405.890	180	55	55	2	251	260	50
	10:10:00			408.370							
2-1	10:15:00	0.42	1.17	408.370	179	56	56	1.5	262	260	52
2-2	10:20:00	0.40	1.11	411.400	179	56	56	1.5	262	260	52
2-3	10:25:00	0.38	1.06	414.290	179	56	56	1.5	262	260	52
	10:30:00			417.010							
3-1	10:35:00	0.46	1.28	417.010	178	56	56	1.5	255	259	52
3-2	10:40:00	0.44	1.23	420.060	178	56	56	1.5	255	259	52
3-3	10:45:00	0.42	1.17	422.980	178	56	56	1.5	255	259	52
	10:50:00			426.310							
4-1	10:55:00	0.40	1.11	426.310	177	56	56	1.5	255	259	52
4-2	11:00:00	0.38	1.05	429.000	177	56	56	1.5	255	259	52
4-3	11:05:00	0.36	1.00	431.920	177	56	56	1.5	255	259	52
	11:10:00			434.861							

Total	1:00:00			35.150		55.8	55.8				
Average			1.09		178.5	55.8		2			
Min			0.92		177.0	55.0		2			
Max			1.28		180.0	56.0		2			

Impinger Weight Sheet - Run 2A

Client: Holcim (US) Inc. Facility: Ravenna Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/31/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/31/2024</u> <u>Scale Calibration Check (see QS-6.05C for procedure)</u> must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	815.7	765.7	50.0
0.1N H2SO4	683.8	663.1	20.7
Empty	603.0	599.8	3.2
0.1N NaOH	648.3	647.6	0.7
0.1N NaOH	750.9	750.3	0.6
Silica Gel	858.2	847.6	10.6

<u>3,501.7</u> Liquid Final	<u>3,426.5</u> Liquid Initial	<u>75.2</u> Liquid Gain
<u>858.2</u> Silica Final	<u>847.6</u> Silica Initial	<u>10.6</u> Silica Gain

Run 3A - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill OFF

Date: 1/31/24
 Start Time: 11:40
 End Time: 12:55

DRY GAS METER CONDITIONS				STACK CONDITIONS		
ΔH:	0.99	In. H ₂ O		Static Pressure	1.50	in. H ₂ O
Meter Temperature, Tm:	57.4	°F		Flue Pressure (Ps):	29.73	in. Hg. abs.
Sqrt ΔP:	0.603	In. H ₂ O		Carbon Dioxide:	12.89	%
Stack Temperature, Ts:	179.9	°F		Oxygen:	13.12	%
Meter Volume, Vm:	33.851	ft ³		Nitrogen:	73.99	%
Meter Volume, Vmstd:	34.075	dscf		Gas Weight dry, Md:	30.587	lb/lb mole
Meter Volume, Vwstd:	4.663	wscf		Gas Weight wet, Ms:	29.072	lb/lb mole
Isokinetic Variance:	104.2	%I		Excess Air:	---	%
Test Length:	60.00	in mins.		Gas Velocity, Vs:	36.968	fps
Nozzle Diameter:	0.250	in inches		Volumetric Flow:	546,272	acfm
Barometric Pressure:	29.62	in Hg		Volumetric Flow:	393,964	dscfm
				Volumetric Flow:	447,874	scfm

MOISTURE DETERMINATION					
Initial Impinger Content:	3641.1	ml	Silica Initial Wt.	881.8	grams
Final Impinger Content:	3732.1	ml	Silica Final Wt.	889.8	grams
Impinger Difference:	91.0	ml	Silica Difference:	8.0	grams
Total Water Gain:	99.0		Moisture, Bws:	0.120	
			Supersaturation Value, Bws:	0.513	

Port-Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	11:40:00	0.36	0.98	440.010	179	55	55	2	263	257	47
1-2	11:45:00	0.33	0.90	443.010	179	56	56	2	265	258	50
1-3	11:50:00	0.31	0.84	445.960	179	56	56	2	268	261	50
	11:55:00			448.380							
2-1	12:00:00	0.40	1.09	448.380	180	58	58	2	258	260	52
2-2	12:05:00	0.38	1.04	451.520	180	58	58	2	259	260	52
2-3	12:10:00	0.36	0.98	453.990	180	58	58	2	260	260	52
	12:15:00			456.810							
3-1	12:20:00	0.44	1.20	456.810	181	59	59	1.5	265	260	55
3-2	12:25:00	0.41	1.12	459.760	181	59	59	1.5	265	260	55
3-3	12:30:00	0.39	1.06	462.940	180	59	59	1.5	266	260	55
	12:35:00			465.780							
4-1	12:40:00	0.35	0.95	465.780	180	57	57	1.5	262	260	57
4-2	12:45:00	0.33	0.90	467.950	180	57	57	1.5	263	260	57
4-3	12:50:00	0.31	0.84	471.010	180	57	57	1.5	263	260	57
	12:55:00			473.861							

Total	1:00:00			33.851		57.4	57.4				
Average			0.99		179.9	57.4		2			
Min			0.84		179.0	55.0		2			
Max			1.20		181.0	59.0		2			

Impinger Weight Sheet - Run 3A

Client: Holcim (US) Inc. Facility: Ravenna Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/31/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/31/2024</u> Scale Calibration Check (see QS-6.05C for procedure) must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	794.2	736.8	57.4
0.1N H2SO4	771.5	746.6	24.9
Empty	650.5	644.7	5.8
0.1N NaOH	767.9	765.7	2.2
0.1N NaOH	748.0	747.3	0.7
Silica Gel	889.8	881.8	8.0

<u>3,732.1</u> Liquid Final	<u>3,641.1</u> Liquid Initial	<u>91.0</u> Liquid Gain
<u>889.8</u> Silica Final	<u>881.8</u> Silica Initial	<u>8.0</u> Silica Gain

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Test Location: Kiln 3 Common Stack
Project #: M234506
Test Method: 26A
Test Engineer: PPP
Test Technician: LPH

	<u>Run 1B</u>	<u>Run 2B</u>	<u>Run 3B</u>
Meter ID:	CM13	CM13	CM13
Pitot ID:	S8-058	S8-058	S8-058
Nozzle Diameter (Inches):	0.280	0.280	0.280
Meter Calibration Date:	1/16/2024	1/16/2024	1/16/2024
Meter Calibration Factor (Y):	0.987	0.987	0.987
Meter Orifice Setting (Delta H):	1.516	1.516	1.516
Nozzle Kit ID Number and Material:	Glass #1 822	Glass #1 822	Glass #1 822

Leak Checks

Pre Pitot Leak Check	0.0	@	3.3	"H ₂ O	0.0	@	3.2	"H ₂ O	0.0	@	3.3	"H ₂ O
Post Pitot Leak Check	0.0	@	3.4	"H ₂ O	0.0	@	3.3	"H ₂ O	0.0	@	3.2	"H ₂ O
Pre Nozzle Leak Check	0.0000	@	13	"Hg	0.0015	@	12	"Hg	0.0000	@	14	"Hg
Post Nozzle Leak Check	0.0000	@	12	"Hg	0.0000	@	10	"Hg	0.0000	@	12	"Hg
Pitot Tube Coefficient:	0.834											
Probe Length (Feet):	7.0											
Probe Liner Material:	Glass											
Sample Plane:	Horizontal											
Port Length (Inches):	12.00											
Port Size (Diameter, Inches):	4.00											
Port Type:	Flange											
Duct Shape:	Circular											
Diameter (Feet):	17.708											
Duct Area (Square Feet):	246.280											
Upstream Diameters:	3.3											
Downstream Diameters:	8.8											
Number of Ports Sampled:	4											
Number of Points per Port:	3											
Minutes per Point:	5.0											
Minutes per Reading:	5.0											
Total Number of Traverse Points:	12											
Test Length (Minutes):	60											
Train Type:	Anderson Box											
Source Condition:	Mill OFF											
Moisture Balance ID:	S10-31											
# of Runs	3											

Run 1B - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill OFF

Date: 1/31/24
 Start Time: 8:20
 End Time: 9:35

DRY GAS METER CONDITIONS

ΔH: 1.25 in. H₂O
 Meter Temperature, Tm: 57.2 °F
 Sqrt ΔP: 0.573 in. H₂O
 Stack Temperature, Ts: 173.6 °F
 Meter Volume, Vm: 40.900 ft³
 Meter Volume, Vmstd: 40.927 dscf
 Meter Volume, Vwstd: 4.880 wscf
 Isokinetic Variance: 103.0 %I
 Test Length: 60.00 in mins.
 Nozzle Diameter: 0.280 in inches
 Barometric Pressure: 29.62 in Hg

STACK CONDITIONS

Static Pressure 1.50 in. H₂O
 Flue Pressure (Ps): 29.73 in. Hg. abs.
 Carbon Dioxide: 12.86 %
 Oxygen: 12.93 %
 Nitrogen: 74.21 %
 Gas Weight dry, Md: 30.575 lb/lb mole
 Gas Weight wet, Ms: 29.235 lb/lb mole
 Excess Air: --- %
 Gas Velocity, Vs: 34.909 fps
 Volumetric Flow: 515,848 acfm
 Volumetric Flow: 381,654 dscfm
 Volumetric Flow: 427,158 scfm

MOISTURE DETERMINATION

Initial Impinger Content: 3640.6 ml Silica Initial Wt. 839.6 grams
 Final Impinger Content: 3728.0 ml Silica Final Wt. 855.8 grams
 Impinger Difference: 87.4 ml Silica Difference: 16.2 grams
 Total Water Gain: 103.6 Moisture, Bws: 0.107 Supersaturation Value, Bws: 0.446

Port- Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	8:20:00	0.27	1.00	140.712	168	52	48	4	250	250	34
1-2	8:25:00	0.25	0.94	143.840	164	55	48	4	257	261	35
1-3	8:30:00	0.22	0.83	146.930	164	58	48	4	261	260	36
	8:35:00			149.529							
2-1	8:40:00	0.37	1.40	149.529	176	60	48	4	260	261	37
2-2	8:45:00	0.35	1.30	153.340	178	63	49	4	260	262	37
2-3	8:50:00	0.30	1.10	156.850	178	63	49	4	260	261	33
	8:55:00			159.844							
3-1	9:00:00	0.40	1.50	159.844	177	64	50	4	260	260	38
3-2	9:05:00	0.36	1.30	163.720	177	64	50	4	260	259	38
3-3	9:10:00	0.33	1.30	167.360	175	65	60	4	260	259	39
	9:15:00			170.587							
4-1	9:20:00	0.43	1.60	170.587	175	65	60	4	262	260	40
4-2	9:25:00	0.37	1.40	174.630	176	65	61	4	260	261	40
4-3	9:30:00	0.33	1.30	178.340	175	66	61	4	260	261	41
	9:35:00			181.612							

Total 1:00:00 40.900 61.7 52.7
 Average 1.25 173.6 57.2 4
 Min 0.83 164.0 48.0 4
 Max 1.60 178.0 66.0 4

Impinger Weight Sheet - Run 1B

Client: Holcim (US) Inc. Facility: Ravena Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/31/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/31/2024</u> Scale Calibration Check (see QS-6.05C for procedure) must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	784.3	743.1	41.2
0.1N H2SO4	776.7	742.6	34.1
Empty	646.1	638.5	7.6
0.1N NaOH	779.1	776.2	2.9
0.1N NaOH	741.8	740.2	1.6
Silica Gel	855.8	839.6	16.2

<u>3,728.0</u> Liquid Final	<u>3,640.6</u> Liquid Initial	<u>87.4</u> Liquid Gain
<u>855.8</u> Silica Final	<u>839.6</u> Silica Initial	<u>16.2</u> Silica Gain

Run 2B - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill OFF

Date: 1/31/24
 Start Time: 9:55
 End Time: 11:10

DRY GAS METER CONDITIONS				STACK CONDITIONS			
ΔH:	1.37	In. H ₂ O		Static Pressure	1.50	in. H ₂ O	
Meter Temperature, Tm:	57.8	°F		Flue Pressure (Ps):	29.73	in. Hg. abs.	
Sqrt ΔP:	0.611	In. H ₂ O		Carbon Dioxide:	12.85	%	
Stack Temperature, Ts:	178.6	°F		Oxygen:	12.92	%	
Meter Volume, Vm:	43.229	ft ³		Nitrogen:	74.2	%	
Meter Volume, Vmstd:	43.214	dscf		Gas Weight dry, Md:	30.573	lb/lb mole	
Meter Volume, Vwstd:	5.209	wscf		Gas Weight wet, Ms:	29.220	lb/lb mole	
Isokinetic Variance:	102.6	%I		Excess Air:	---	%	
Test Length:	60.00	in mins.		Gas Velocity, Vs:	37.324	fps	
Nozzle Diameter:	0.280	in inches		Volumetric Flow:	551,528	acfm	
Barometric Pressure:	29.62	in Hg		Volumetric Flow:	404,382	dscfm	
				Volumetric Flow:	453,127	scfm	

MOISTURE DETERMINATION					
Initial Impinger Content:	3600.6	ml	Silica Initial Wt.	893.1	grams
Final Impinger Content:	3704.5	ml	Silica Final Wt.	899.8	grams
Impinger Difference:	103.9	ml	Silica Difference:	6.7	grams
Total Water Gain:	110.6		Moisture, Bws:	0.108	
			Supersaturation Value, Bws:	0.498	

Port-Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	9:55:00	0.36	1.30	187.416	179	59	52	4	261	259	33
1-2	10:00:00	0.34	1.30	191.120	179	59	52	4	260	259	35
1-3	10:05:00	0.30	1.10	194.560	179	60	53	4	260	253	34
	10:10:00			197.523							
2-1	10:15:00	0.43	1.60	197.523	179	61	53	4	260	251	35
2-2	10:20:00	0.40	1.50	201.410	178	61	53	4	261	253	35
2-3	10:25:00	0.35	1.30	205.340	178	61	53	4	260	254	35
	10:30:00			208.543							
3-1	10:35:00	0.45	1.60	208.543	179	63	54	4	260	250	36
3-2	10:40:00	0.42	1.50	212.620	179	64	54	4	259	254	36
3-3	10:45:00	0.39	1.40	216.530	179	64	53	4	260	258	37
	10:50:00			220.027							
4-1	10:55:00	0.39	1.40	220.027	178	64	55	4	260	259	38
4-2	11:00:00	0.35	1.30	223.810	178	65	55	4	259	260	38
4-3	11:05:00	0.31	1.10	227.470	178	65	55	4	260	261	39
	11:10:00			230.645							

Total	1:00:00			43.229		62.2	53.5				
Average			1.37		178.6	57.8		4			
Min			1.10		178.0	52.0		0			
Max			1.60		179.0	65.0		4			

Impinger Weight Sheet - Run 2B

Client: Holcim (US) Inc. Facility: Ravenna Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/31/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/31/2024</u> <u>Scale Calibration Check (see QS-6.05C for procedure)</u> must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	815.3	745.6	69.7
0.1N H2SO4	783.1	755.3	27.8
Empty	650.5	646.3	4.2
0.1N NaOH	707.4	705.9	1.5
0.1N NaOH	748.2	747.5	0.7
Silica Gel	899.8	893.1	6.7

<u>3,704.5</u> Liquid Final	<u>3,600.6</u> Liquid Initial	<u>103.9</u> Liquid Gain
<u>899.8</u> Silica Final	<u>893.1</u> Silica Initial	<u>6.7</u> Silica Gain

Run 3B - Method 26A

Client: Holcim (US) Inc.
 Facility: Ravenna Cement Plant
 Test Location: Kiln 3 Common Stack
 Source Condition: Mill OFF

Date: 1/31/24
 Start Time: 11:40
 End Time: 12:55

DRY GAS METER CONDITIONS				STACK CONDITIONS		
ΔH :	1.28	In. H ₂ O		Static Pressure	1.50	in. H ₂ O
Meter Temperature, Tm:	60.6	°F		Flue Pressure (Ps):	29.73	in. Hg. abs.
Sqrt ΔP :	0.595	In. H ₂ O		Carbon Dioxide:	12.89	%
Stack Temperature, Ts:	179.3	°F		Oxygen:	13.12	%
Meter Volume, Vm:	42.115	ft ³		Nitrogen:	73.99	%
Meter Volume, Vmstd:	41.870	dscf		Gas Weight dry, Md:	30.587	lb/lb mole
Meter Volume, Vwstd:	6.198	wscf		Gas Weight wet, Ms:	28.964	lb/lb mole
Isokinetic Variance:	104.1	%I		Excess Air:	---	%
Test Length:	60.00	in mins.		Gas Velocity, Vs:	36.558	fps
Nozzle Diameter:	0.280	in inches		Volumetric Flow:	540,215	acfm
Barometric Pressure:	29.62	in Hg		Volumetric Flow:	386,147	dscfm
				Volumetric Flow:	443,312	scfm

MOISTURE DETERMINATION					
Initial Impinger Content:	3573.4	ml	Silica Initial Wt.	855.8	grams
Final Impinger Content:	3694.6	ml	Silica Final Wt.	866.2	grams
Impinger Difference:	121.2	ml	Silica Difference:	10.4	grams
Total Water Gain:	131.6		Moisture, Bws:	0.129	
			Supersaturation Value, Bws:	0.507	

Port-Point No.	Clock Time	Velocity Head Δp in. H ₂ O	Orifice ΔH in. H ₂ O	Actual Meter Vol. ft ³	Stack Temp °F	Meter Temp Inlet °F	Meter Temp Outlet °F	Pump Vacuum "Hg	Probe Temp °F	Filter Exit Temp °F	Impinger Exit Temp °F
1-1	11:40:00	0.35	1.30	232.539	179	61	54	4	260	260	34
1-2	11:45:00	0.33	1.20	236.020	179	62	55	4	260	258	34
1-3	11:50:00	0.30	1.10	239.530	189	63	55	4	260	259	35
	11:55:00			242.564							
2-1	12:00:00	0.41	1.50	242.564	179	63	55	4	260	260	36
2-2	12:05:00	0.37	1.30	246.370	179	64	56	4	261	259	36
2-3	12:10:00	0.34	1.20	249.910	178	64	57	4	260	260	36
	12:15:00			253.343							
3-1	12:20:00	0.43	1.50	253.343	178	64	58	4	263	260	37
3-2	12:25:00	0.38	1.40	257.430	178	64	58	4	262	260	37
3-3	12:30:00	0.33	1.20	260.910	179	65	59	4	262	260	38
	12:35:00			264.274							
4-1	12:40:00	0.36	1.30	264.274	178	66	59	4	260	260	39
4-2	12:45:00	0.34	1.30	267.990	178	67	59	4	260	263	39
4-3	12:50:00	0.32	1.10	271.520	178	67	59	4	260	262	39
	12:55:00			274.654							

Total	1:00:00			42.115		64.2	57.0				
Average			1.28		179.3	60.6		4			
Min			1.10		178.0	54.0		4			
Max			1.50		189.0	67.0		4			

Impinger Weight Sheet - Run 3B

Client: Holcim (US) Inc. Facility: Ravena Cement Plant Test Location: Kiln 3 Common Stack Project #: M234506 Date: 1/31/2024 Test Method: 26A Weighed/Measured By: EE Balance ID: S10-31	Scale Calibration Check Date: <u>1/31/2024</u> <u>Scale Calibration Check (see QS-6.05C for procedure)</u> must be within $\pm 0.5g$ of certified mass <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left; border-bottom: 1px solid black;"><u>Certified Weight, grams</u></th> <th style="text-align: left; border-bottom: 1px solid black;"><u>Result, grams</u></th> </tr> <tr> <td style="text-align: center;">200</td> <td style="text-align: center; border-bottom: 1px solid black;">200.0</td> </tr> <tr> <td style="text-align: center;">500</td> <td style="text-align: center; border-bottom: 1px solid black;">500.0</td> </tr> <tr> <td style="text-align: center;">700</td> <td style="text-align: center; border-bottom: 1px solid black;">700.0</td> </tr> </table>	<u>Certified Weight, grams</u>	<u>Result, grams</u>	200	200.0	500	500.0	700	700.0
<u>Certified Weight, grams</u>	<u>Result, grams</u>								
200	200.0								
500	500.0								
700	700.0								

IMPINGER	FINAL	INITIAL	GAIN
CONTENTS	MLS / GRAMS	MLS / GRAMS	MLS / GRAMS
0.1N H2SO4	757.5	696.5	61.0
0.1N H2SO4	799.0	754.1	44.9
Empty	664.9	652.7	12.2
0.1N NaOH	768.7	764.7	4.0
0.1N NaOH	704.5	705.4	-0.9
Silica Gel	866.2	855.8	10.4

<u>3,694.6</u> Liquid Final	<u>3,573.4</u> Liquid Initial	<u>121.2</u> Liquid Gain
<u>866.2</u> Silica Final	<u>855.8</u> Silica Initial	<u>10.4</u> Silica Gain

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Test Location: Kiln 3 Common Stack
Date: 1/31/24

Run 1								Analyzer Data O2 % (dry)
Spectrum	Time	H2O %	CO2 % (wet)	HCN ppmvw	HF ppmvw	Cell Temp	Pressure	
RUN 1_000373.LAB	8:20	12.54	11.15	1.55	≤ 0.10	190.97	0.99	13.09
RUN 1_000374.LAB	8:21	12.67	11.39	1.49	≤ 0.10	190.97	0.99	12.90
RUN 1_000375.LAB	8:22	12.76	11.37	1.50	≤ 0.10	190.89	0.99	12.87
RUN 1_000376.LAB	8:23	12.92	11.33	1.47	≤ 0.10	190.95	0.99	12.85
RUN 1_000377.LAB	8:24	13.08	11.49	1.37	≤ 0.10	190.97	0.99	12.78
RUN 1_000378.LAB	8:25	13.22	11.47	1.42	≤ 0.10	190.97	0.99	12.70
RUN 1_000379.LAB	8:26	13.13	11.69	1.43	≤ 0.10	190.98	0.99	12.72
RUN 1_000380.LAB	8:27	13.27	11.55	1.45	≤ 0.10	190.93	0.99	12.64
RUN 1_000381.LAB	8:28	13.09	11.64	1.41	≤ 0.10	191.01	0.99	12.77
RUN 1_000382.LAB	8:29	13.17	11.25	1.47	≤ 0.10	190.91	0.99	12.77
RUN 1_000383.LAB	8:30	13.14	11.30	1.48	≤ 0.10	190.93	0.99	12.92
RUN 1_000384.LAB	8:31	13.10	11.33	1.50	≤ 0.10	190.84	0.99	12.96
RUN 1_000385.LAB	8:32	13.05	11.10	1.37	≤ 0.10	191.04	0.99	12.97
RUN 1_000386.LAB	8:33	12.99	11.06	1.33	≤ 0.10	190.98	0.99	13.10
RUN 1_000387.LAB	8:34	13.01	11.05	1.47	≤ 0.10	190.98	0.99	13.07
RUN 1_000388.LAB	8:35	12.89	10.95	1.35	≤ 0.10	190.93	0.99	13.10
RUN 1_000389.LAB	8:36	12.83	10.78	1.57	≤ 0.10	190.98	0.99	13.13
RUN 1_000390.LAB	8:37	12.78	10.76	1.32	≤ 0.10	191.01	0.99	13.23
RUN 1_000391.LAB	8:38	12.60	10.99	1.49	≤ 0.10	190.91	0.99	13.25
RUN 1_000392.LAB	8:39	12.66	11.14	1.42	≤ 0.10	190.93	0.99	13.20
RUN 1_000393.LAB	8:40	12.55	10.99	1.23	≤ 0.10	190.94	0.99	13.07
RUN 1_000394.LAB	8:41	12.45	10.88	1.31	≤ 0.10	190.94	0.99	13.14
RUN 1_000395.LAB	8:42	11.78	11.12	1.27	≤ 0.10	190.85	0.99	13.15
RUN 1_000396.LAB	8:43	11.91	11.12	1.41	≤ 0.10	191.01	0.99	13.09
RUN 1_000397.LAB	8:44	11.85	11.28	1.38	≤ 0.10	190.95	0.99	13.05
RUN 1_000398.LAB	8:45	12.26	11.14	1.44	≤ 0.10	190.98	0.99	12.98
RUN 1_000399.LAB	8:46	12.13	11.36	1.48	≤ 0.10	190.94	0.99	12.90
RUN 1_000400.LAB	8:47	12.20	11.43	1.30	≤ 0.10	191.05	0.99	12.88
RUN 1_000401.LAB	8:48	12.87	11.40	1.48	≤ 0.10	190.94	0.99	12.78
RUN 1_000402.LAB	8:49	13.01	11.30	1.41	≤ 0.10	190.96	0.99	12.74
RUN 1_000403.LAB	8:50	13.12	11.65	1.49	≤ 0.10	190.97	0.99	12.73
RUN 1_000404.LAB	8:51	13.21	11.48	1.50	≤ 0.10	190.91	0.99	12.73
RUN 1_000405.LAB	8:52	13.15	11.46	1.44	≤ 0.10	190.91	0.99	12.65
RUN 1_000406.LAB	8:53	13.19	11.33	1.38	≤ 0.10	190.96	0.99	12.70
RUN 1_000407.LAB	8:54	13.05	11.33	1.35	≤ 0.10	190.93	0.99	12.75
RUN 1_000408.LAB	8:55	13.18	11.22	1.58	≤ 0.10	190.91	0.99	12.87
RUN 1_000409.LAB	8:56	13.09	11.28	1.55	≤ 0.10	190.95	0.99	12.94
RUN 1_000410.LAB	8:57	13.25	11.19	1.39	≤ 0.10	190.92	0.99	12.93
RUN 1_000411.LAB	8:58	13.19	11.17	1.47	≤ 0.10	190.94	0.99	12.93
RUN 1_000412.LAB	8:59	13.17	10.98	1.52	≤ 0.10	190.95	0.99	12.99
RUN 1_000413.LAB	9:00	13.07	10.98	1.37	≤ 0.10	190.97	0.99	13.05
RUN 1_000414.LAB	9:01	12.94	11.02	1.47	≤ 0.10	190.97	0.99	13.18
RUN 1_000415.LAB	9:02	12.88	10.87	1.43	≤ 0.10	190.96	0.99	13.20
RUN 1_000416.LAB	9:03	12.84	10.93	1.38	≤ 0.10	190.93	0.99	13.24
RUN 1_000417.LAB	9:04	12.79	10.96	1.46	≤ 0.10	190.96	0.99	13.28
RUN 1_000418.LAB	9:05	12.77	11.08	1.60	≤ 0.10	190.94	0.99	13.28
RUN 1_000419.LAB	9:06	12.80	11.05	1.48	≤ 0.10	190.93	0.99	13.28
RUN 1_000420.LAB	9:07	12.81	10.95	1.46	≤ 0.10	190.94	0.99	13.23
RUN 1_000421.LAB	9:08	12.84	11.01	1.41	≤ 0.10	190.96	0.99	13.13
RUN 1_000422.LAB	9:09	12.82	11.04	1.48	≤ 0.10	190.97	0.99	13.15
RUN 1_000423.LAB	9:10	12.77	11.14	1.57	≤ 0.10	190.92	0.99	13.20
RUN 1_000424.LAB	9:11	12.82	11.08	1.53	≤ 0.10	191.06	0.99	13.16
RUN 1_000425.LAB	9:12	12.82	11.33	1.51	≤ 0.10	191.02	0.99	13.13
RUN 1_000426.LAB	9:13	12.81	11.24	1.60	≤ 0.10	190.95	0.99	13.10
RUN 1_000427.LAB	9:14	12.87	11.35	1.64	≤ 0.10	190.92	0.99	13.11
RUN 1_000428.LAB	9:15	12.90	11.44	1.55	≤ 0.10	191.00	0.99	13.00
RUN 1_000429.LAB	9:16	12.98	11.42	1.62	≤ 0.10	190.98	0.99	13.03
RUN 1_000430.LAB	9:17	12.95	11.31	1.59	≤ 0.10	190.99	0.99	12.94
RUN 1_000431.LAB	9:18	12.96	11.31	1.61	≤ 0.10	191.03	0.99	12.91
RUN 1_000432.LAB	9:19	12.89	11.25	1.52	≤ 0.10	190.98	0.99	12.87
Average		12.85	11.21	1.46	≤ 0.10	190.96	0.99	12.99

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Test Location: Kiln 3 Common Stack
Date: 1/31/24

Run 2								
FTIR Data								
Spectrum	Time	H2O %	CO2 % (wet)	HCN ppmvw	HF ppmvw	Cell Temp	Pressure	Analyzer Data O2 % (dry)
RUN 2_000508.LAB	9:55	12.85	11.2	1.39	≤ 0.10	191.0	0.99	13.15
RUN 2_000509.LAB	9:56	12.78	11.1	1.59	≤ 0.10	190.9	0.99	13.14
RUN 2_000510.LAB	9:57	12.86	11.4	1.44	≤ 0.10	190.9	0.99	12.97
RUN 2_000511.LAB	9:58	12.87	11.2	1.45	≤ 0.10	191.0	0.99	12.97
RUN 2_000512.LAB	9:59	12.95	11.4	1.50	≤ 0.10	190.9	0.99	12.85
RUN 2_000513.LAB	10:00	12.92	11.4	1.55	≤ 0.10	191.0	0.99	12.91
RUN 2_000514.LAB	10:01	12.35	11.4	1.44	≤ 0.10	191.0	0.99	12.85
RUN 2_000515.LAB	10:02	12.17	11.3	1.57	≤ 0.10	190.9	0.99	12.84
RUN 2_000516.LAB	10:03	12.67	11.4	1.62	≤ 0.10	190.9	0.99	12.83
RUN 2_000517.LAB	10:04	12.84	11.5	1.61	≤ 0.10	190.9	0.99	12.80
RUN 2_000518.LAB	10:05	12.89	11.6	1.65	≤ 0.10	190.9	0.99	12.73
RUN 2_000519.LAB	10:06	12.91	11.4	1.53	≤ 0.10	191.0	0.99	12.80
RUN 2_000520.LAB	10:07	12.91	11.3	1.56	≤ 0.10	191.0	0.99	12.83
RUN 2_000521.LAB	10:08	12.90	11.4	1.47	≤ 0.10	190.8	0.99	12.82
RUN 2_000522.LAB	10:09	12.98	11.4	1.64	≤ 0.10	190.9	0.99	12.80
RUN 2_000523.LAB	10:10	13.04	11.2	1.47	≤ 0.10	190.9	0.99	12.85
RUN 2_000524.LAB	10:11	13.01	11.3	1.51	≤ 0.10	190.9	0.99	12.93
RUN 2_000525.LAB	10:12	12.98	11.2	1.49	≤ 0.10	190.9	0.99	12.91
RUN 2_000526.LAB	10:13	12.95	11.2	1.44	≤ 0.10	191.0	0.99	12.90
RUN 2_000527.LAB	10:14	12.91	11.3	1.60	≤ 0.10	190.9	0.99	12.96
RUN 2_000528.LAB	10:15	12.89	11.0	1.42	≤ 0.10	190.9	0.99	12.93
RUN 2_000529.LAB	10:16	12.83	10.9	1.57	≤ 0.10	191.1	0.99	13.15
RUN 2_000530.LAB	10:17	12.83	10.9	1.46	≤ 0.10	191.0	0.99	13.19
RUN 2_000531.LAB	10:18	12.78	10.8	1.36	≤ 0.10	191.0	0.99	13.16
RUN 2_000532.LAB	10:19	12.81	11.0	1.52	≤ 0.10	191.1	0.99	13.32
RUN 2_000533.LAB	10:20	12.83	10.8	1.44	≤ 0.10	191.0	0.99	13.12
RUN 2_000534.LAB	10:21	12.78	10.8	1.55	≤ 0.10	191.0	0.99	13.26
RUN 2_000535.LAB	10:22	12.72	11.2	1.60	≤ 0.10	191.0	0.99	13.29
RUN 2_000536.LAB	10:23	12.68	11.2	1.48	≤ 0.10	191.0	0.99	13.23
RUN 2_000537.LAB	10:24	12.70	11.4	1.43	≤ 0.10	190.9	0.99	13.09
RUN 2_000538.LAB	10:25	12.71	11.2	1.57	≤ 0.10	190.9	0.99	12.97
RUN 2_000539.LAB	10:26	12.69	11.2	1.52	≤ 0.10	190.9	0.99	12.92
RUN 2_000540.LAB	10:27	12.70	11.3	1.44	≤ 0.10	190.9	0.99	12.94
RUN 2_000541.LAB	10:28	12.72	11.3	1.59	≤ 0.10	191.0	0.99	12.95
RUN 2_000542.LAB	10:29	12.71	11.3	1.60	≤ 0.10	190.9	0.99	12.98
RUN 2_000543.LAB	10:30	12.72	11.2	1.44	≤ 0.10	191.0	0.99	12.93
RUN 2_000544.LAB	10:31	12.71	11.2	1.48	≤ 0.10	190.9	0.99	12.97
RUN 2_000545.LAB	10:32	12.77	11.2	1.42	≤ 0.10	191.0	0.99	13.01
RUN 2_000546.LAB	10:33	12.84	11.2	1.51	≤ 0.10	191.1	0.99	12.96
RUN 2_000547.LAB	10:34	12.85	11.2	1.57	≤ 0.10	190.9	0.99	12.93
RUN 2_000548.LAB	10:35	12.65	11.4	1.54	≤ 0.10	190.9	0.99	12.93
RUN 2_000549.LAB	10:36	12.28	11.3	1.59	≤ 0.10	191.0	0.99	12.97
RUN 2_000550.LAB	10:37	12.19	11.5	1.62	≤ 0.10	190.9	0.99	12.93
RUN 2_000551.LAB	10:38	12.22	11.4	1.44	≤ 0.10	191.0	0.99	12.97
RUN 2_000552.LAB	10:39	12.81	11.4	1.57	≤ 0.10	191.0	0.99	12.90
RUN 2_000553.LAB	10:40	12.84	11.2	1.62	≤ 0.10	191.0	0.99	12.91
RUN 2_000554.LAB	10:41	12.81	11.2	1.74	≤ 0.10	191.0	0.99	12.88
RUN 2_000555.LAB	10:42	12.82	11.2	1.46	≤ 0.10	190.9	0.99	13.03
RUN 2_000556.LAB	10:43	12.84	11.1	1.67	≤ 0.10	191.0	0.99	13.00
RUN 2_000557.LAB	10:44	12.83	11.2	1.46	≤ 0.10	190.9	0.99	13.03
RUN 2_000558.LAB	10:45	12.81	11.2	1.57	≤ 0.10	191.0	0.99	13.05
RUN 2_000559.LAB	10:46	12.80	11.1	1.48	≤ 0.10	191.0	0.99	13.05
RUN 2_000560.LAB	10:47	12.77	11.0	1.48	≤ 0.10	191.0	0.99	13.03
RUN 2_000561.LAB	10:48	12.81	11.0	1.50	≤ 0.10	191.0	0.99	13.06
RUN 2_000562.LAB	10:49	12.78	11.1	1.57	≤ 0.10	190.9	0.99	13.09
RUN 2_000563.LAB	10:50	12.76	11.2	1.55	≤ 0.10	190.9	0.99	13.11
RUN 2_000564.LAB	10:51	12.76	11.1	1.45	≤ 0.10	191.0	0.99	13.12
RUN 2_000565.LAB	10:52	12.78	11.0	1.54	≤ 0.10	191.1	0.99	13.13
RUN 2_000566.LAB	10:53	12.80	11.0	1.52	≤ 0.10	190.9	0.99	13.05
RUN 2_000567.LAB	10:54	12.80	11.0	1.46	≤ 0.10	191.0	0.99	13.10
Average		12.77	11.21	1.52	≤ 0.10	190.96	0.99	12.99


Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Test Location: Kiln 3 Common Stack
Date: 1/31/24

Run 3

Spectrum	Time	FTIR Data				Cell Temp	Pressure	Analyzer Data O2 % (dry)
		H2O %	CO2 % (wet)	HCN ppmvw	HF ppmvw			
RUN 3_000650.LAB	11:40	12.94	11.0	1.46	≤ 0.10	190.9	0.99	13.31
RUN 3_000651.LAB	11:41	12.92	11.1	1.38	≤ 0.10	190.9	0.99	13.21
RUN 3_000652.LAB	11:42	12.98	11.2	1.59	≤ 0.10	191.0	0.99	13.21
RUN 3_000653.LAB	11:43	12.97	11.1	1.48	≤ 0.10	191.0	0.99	13.20
RUN 3_000654.LAB	11:44	13.00	11.2	1.57	≤ 0.10	191.0	0.99	13.24
RUN 3_000655.LAB	11:45	13.00	11.0	1.50	≤ 0.10	191.0	0.99	13.29
RUN 3_000656.LAB	11:46	12.99	11.1	1.50	≤ 0.10	191.0	0.99	13.30
RUN 3_000657.LAB	11:47	13.02	11.1	1.51	≤ 0.10	191.0	0.99	13.28
RUN 3_000658.LAB	11:48	13.01	11.1	1.78	≤ 0.10	190.9	0.99	13.25
RUN 3_000659.LAB	11:49	13.06	11.5	1.74	≤ 0.10	191.0	0.99	13.13
RUN 3_000660.LAB	11:50	13.07	11.2	1.56	≤ 0.10	191.0	0.99	13.35
RUN 3_000661.LAB	11:51	13.04	11.0	1.55	≤ 0.10	191.0	0.99	13.47
RUN 3_000662.LAB	11:52	13.02	11.1	1.66	≤ 0.10	190.9	0.99	13.41
RUN 3_000663.LAB	11:53	13.01	11.0	1.53	≤ 0.10	190.9	0.99	13.45
RUN 3_000664.LAB	11:54	13.07	11.1	1.52	≤ 0.10	191.0	0.99	13.38
RUN 3_000665.LAB	11:55	12.66	11.2	1.57	≤ 0.10	191.0	0.99	13.36
RUN 3_000666.LAB	11:56	12.39	11.3	1.66	≤ 0.10	190.9	0.99	13.24
RUN 3_000667.LAB	11:57	12.30	11.4	1.61	≤ 0.10	190.9	0.99	13.13
RUN 3_000668.LAB	11:58	12.50	11.6	1.57	≤ 0.10	190.9	0.99	13.04
RUN 3_000669.LAB	11:59	13.05	11.3	1.58	≤ 0.10	191.0	0.99	13.10
RUN 3_000670.LAB	12:00	13.11	11.4	1.57	≤ 0.10	191.0	0.99	13.10
RUN 3_000671.LAB	12:01	13.15	11.3	1.60	≤ 0.10	190.9	0.99	13.11
RUN 3_000672.LAB	12:02	13.17	11.3	1.54	≤ 0.10	190.9	0.99	13.14
RUN 3_000673.LAB	12:03	13.24	11.2	1.72	≤ 0.10	191.0	0.99	13.12
RUN 3_000674.LAB	12:04	13.16	11.7	1.56	≤ 0.10	190.9	0.99	13.05
RUN 3_000675.LAB	12:05	13.30	11.4	1.65	≤ 0.10	191.0	0.99	13.01
RUN 3_000676.LAB	12:06	13.24	11.3	1.69	≤ 0.10	190.9	0.99	13.06
RUN 3_000677.LAB	12:07	13.20	11.4	1.62	≤ 0.10	190.8	0.99	13.13
RUN 3_000678.LAB	12:08	13.27	11.7	1.56	≤ 0.10	190.9	0.99	13.06
RUN 3_000679.LAB	12:09	13.23	11.4	1.50	≤ 0.10	190.9	0.99	12.98
RUN 3_000680.LAB	12:10	13.24	11.3	1.64	≤ 0.10	190.9	0.99	13.08
RUN 3_000681.LAB	12:11	13.23	11.1	1.42	≤ 0.10	190.8	0.99	13.12
RUN 3_000682.LAB	12:12	13.22	11.1	1.62	≤ 0.10	190.9	0.99	13.17
RUN 3_000683.LAB	12:13	13.19	10.9	1.58	≤ 0.10	190.8	0.99	13.20
RUN 3_000684.LAB	12:14	13.17	11.2	1.62	≤ 0.10	190.9	0.99	13.35
RUN 3_000685.LAB	12:15	13.28	11.0	1.48	≤ 0.10	190.8	0.99	13.26
RUN 3_000686.LAB	12:16	13.16	11.0	1.61	≤ 0.10	190.8	0.99	13.32
RUN 3_000687.LAB	12:17	13.27	10.9	1.60	≤ 0.10	190.9	0.99	13.32
RUN 3_000688.LAB	12:18	13.15	10.9	1.68	≤ 0.10	190.8	0.99	13.38
RUN 3_000689.LAB	12:19	13.29	11.0	1.50	≤ 0.10	190.8	0.99	13.35
RUN 3_000690.LAB	12:20	13.15	11.1	1.54	≤ 0.10	190.9	0.99	13.38
RUN 3_000691.LAB	12:21	13.24	11.0	1.62	≤ 0.10	190.9	0.99	13.33
RUN 3_000692.LAB	12:22	13.10	11.0	1.59	≤ 0.10	190.8	0.99	13.37
RUN 3_000693.LAB	12:23	13.28	11.2	1.68	≤ 0.10	190.8	0.99	13.32
RUN 3_000694.LAB	12:24	13.14	11.1	1.62	≤ 0.10	190.8	0.99	13.34
RUN 3_000695.LAB	12:25	13.26	11.0	1.61	≤ 0.10	190.7	0.99	13.28
RUN 3_000696.LAB	12:26	13.16	11.0	1.66	≤ 0.10	190.7	0.99	13.29
RUN 3_000697.LAB	12:27	13.23	11.2	1.70	≤ 0.10	190.7	0.99	13.30
RUN 3_000698.LAB	12:28	13.19	11.3	1.51	≤ 0.10	190.8	0.99	13.27
RUN 3_000699.LAB	12:29	13.21	11.1	1.70	≤ 0.10	190.7	0.99	13.24
RUN 3_000700.LAB	12:30	13.21	11.5	1.70	≤ 0.10	190.8	0.99	13.19
RUN 3_000701.LAB	12:31	13.07	11.1	1.69	≤ 0.10	190.8	0.99	13.23
RUN 3_000702.LAB	12:32	12.78	11.5	1.54	≤ 0.10	190.8	0.99	13.14
RUN 3_000703.LAB	12:33	12.75	11.3	1.46	≤ 0.10	190.8	0.99	13.24
RUN 3_000704.LAB	12:34	13.23	11.4	1.74	≤ 0.10	190.8	0.99	13.13
RUN 3_000705.LAB	12:35	13.27	11.2	1.55	≤ 0.10	190.8	0.99	13.18
RUN 3_000706.LAB	12:36	13.20	11.3	1.65	≤ 0.10	190.8	0.99	13.11
RUN 3_000707.LAB	12:37	13.20	11.3	1.58	≤ 0.10	190.9	0.99	13.17
RUN 3_000708.LAB	12:38	13.22	11.3	1.55	≤ 0.10	190.8	0.99	13.17
RUN 3_000709.LAB	12:39	13.26	11.3	1.65	≤ 0.10	190.8	0.99	13.14
Average		13.09	11.20	1.59	≤ 0.10	190.87	0.99	13.22

Appendix G - Calibration Data

Dry Gas Meter/Control Module Calibration Diagram



Meter Box Calibration

Dry Gas Meter Calibration Data

Dry Gas Meter No. CM13
 Standard Meter No. 366118
 Standard Meter (Y) 0.99950

Date: January 16, 2024
 Calibrated By: HH
 Barometric Pressure: 29.37

Run Number	Orifice Setting in H ₂ O Chg (H)	Standard Meter Gas Volume vr	Dry Gas Meter Gas Volume vd	Standard Meter Temp. F° tr	Dry Gas Meter Inlet Temp. F° tdi	Dry Gas Meter Outlet Temp. F° tdo	Dry Gas Meter Avg. Temp. F° td	Time Min	Time Sec	Y	Chg (H)
Final		66.921	85.720	59	60	58					
Initial		61.879	80.657	60	59	55					
Difference	1 0.20	5.042	5.063	60	60	57	58	18	4	0.992	1.453
Final		71.948	90.840	59	64	60					
Initial		66.921	85.720	59	60	58					
Difference	2 0.50	5.027	5.120	59	62	59	61	11	23	0.983	1.440
Final		77.048	96.032	60	63	63					
Initial		71.948	90.840	59	64	60					
Difference	3 0.70	5.100	5.192	60	64	62	63	9	57	0.986	1.494
Final		82.130	101.215	60	64	63					
Initial		77.048	96.032	60	63	63					
Difference	4 0.90	5.082	5.183	60	64	63	63	8	48	0.984	1.514
Final		87.381	106.580	60	67	63					
Initial		82.130	101.215	60	64	63					
Difference	5 1.20	5.251	5.365	60	66	63	64	7	57	0.983	1.540
Final		61.879	80.657	60	59	55					
Initial		56.788	75.623	61	55	54					
Difference	6 2.00	5.091	5.034	61	57	55	56	6	8	0.997	1.655

Average **0.987** **1.516**

Stack Temperature Sensor Calibration			
Temperature ID :	100769	Name :	HH
Ambient Temperature, °F :	56.3	Date :	January 16, 2024

Temperature Calibrator			
Model # :	CL23A	Certification Date:	May 2, 2023
Serial # :	T-285668	Expiration Date:	May 2, 2024

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

Reference Source Temperature (°F)	Test Thermometer Temperature (°F)	Temperature Difference %
0	0	0.0
250	250	0.0
600	598	0.2
1200	1201	0.1

$$\frac{(\text{Ref. Temp., } ^\circ\text{F} + 460) - (\text{Test Therm. Temp., } ^\circ\text{F} + 460)}{\text{Ref. Temp., } ^\circ\text{F} + 460} * 100 \leq 1.5 \%$$

Meter Box Calibration

Dry Gas Meter Calibration Data

Dry Gas Meter No. CM13
 Standard Meter No. 16541852
 Standard Meter (Y) 1.00440

Date: February 3, 2024
 Calibrated By: JVC
 Barometric Pressure: 29.41

Run Number	Orifice Setting in H ₂ O Chg (H)	Standard Meter Gas Volume vr	Dry Gas Meter Gas Volume vd	Standard Meter Temp. F° tr	Dry Gas Meter Inlet Temp. F° tdi	Dry Gas Meter Outlet Temp. F° tdo	Dry Gas Meter Avg. Temp. F° td	Time Min	Time Sec	Y	Chg (H)
Final		103.544	11.599	53	65	61					
Initial		97.210	5.118	52	61	59					
Difference	1 0.20	6.334	6.481	53	63	60	62	23	1	0.998	1.428
Final		11.744	20.042	53	68	63					
Initial		3.845	11.921	53	63	61					
Difference	2 0.50	7.899	8.121	53	66	62	64	18	32	0.996	1.485
Final		20.124	28.690	54	66	63					
Initial		11.970	20.280	54	65	63					
Difference	3 0.70	8.154	8.410	54	66	63	64	16	24	0.992	1.532
Final		28.044	36.872	54	69	63					
Initial		20.465	29.049	54	64	63					
Difference	4 0.90	7.579	7.823	54	67	63	65	13	39	0.991	1.578
Final		35.394	44.458	55	73	64					
Initial		28.164	36.992	54	65	63					
Difference	5 1.20	7.230	7.466	55	69	64	66	10	58	0.992	1.491
Final		97.158	105.061	52	69	59					
Initial		90.142	97.927	53	60	58					
Difference	6 2.00	7.016	7.134	53	65	59	62	8	40	1.000	1.650

Average **0.995** **1.527**

Stack Temperature Sensor Calibration			
Temperature ID :	100769	Name :	JVC
Ambient Temperature, °F :	57	Date :	February 3, 2024

Temperature Calibrator			
Model # :	CL23A	Certification Date:	May 2, 2023
Serial # :	T-285668	Expiration Date:	May 2, 2024

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

Reference Source Temperature (°F)	Test Thermometer Temperature (°F)	Temperature Difference %
0	0	0.0
250	250	0.0
600	598	0.2
1200	1201	0.1

$$\frac{(\text{Ref. Temp., } ^\circ\text{F} + 460) - (\text{Test Therm. Temp., } ^\circ\text{F} + 460)}{\text{Ref. Temp., } ^\circ\text{F} + 460} * 100 \leq 1.5 \%$$

Meter Box Calibration

Dry Gas Meter Calibration Data

Dry Gas Meter No. CM43
Standard Meter No. 366118
Standard Meter (Y) 0.99950

Date: January 19, 2024
Calibrated By: HGS1
Barometric Pressure: 29.49

Run Number	Orifice Setting in H ₂ O Chg (H)	Standard Meter Gas Volume vr	Dry Gas Meter Gas Volume vd	Standard Meter Temp. F° tr	Dry Gas Meter Inlet Temp. F° tdi	Dry Gas Meter Outlet Temp. F° tdo	Dry Gas Meter Avg. Temp. F° td	Time Min	Time Sec	Y	Chg (H)
Final		15.578	31.760	62	64	64					
Initial		10.302	26.451	61	63	63					
Difference	1 0.20	5.276	5.309	62	64	64	64	20	37	0.997	1.715
Final		36.955	53.349	62	64	64					
Initial		31.225	47.562	61	64	64					
Difference	2 0.50	5.730	5.787	62	64	64	64	14	17	0.993	1.744
Final		31.225	47.562	61	64	64					
Initial		25.945	42.230	62	64	64					
Difference	3 0.70	5.280	5.332	62	64	64	64	11	15	0.993	1.783
Final		20.763	37.005	62	64	64					
Initial		15.578	31.760	62	64	64					
Difference	4 0.90	5.185	5.245	62	64	64	64	9	46	0.990	1.795
Final		25.945	42.230	62	65	65					
Initial		20.763	37.005	62	64	64					
Difference	5 1.20	5.182	5.225	62	65	65	65	8	34	0.993	1.842
Final		10.302	26.451	61	63	63					
Initial		5.012	21.152	61	63	63					
Difference	6 2.00	5.290	5.299	61	63	63	63	6	47	0.997	1.845

Average **0.994** **1.788**

Stack Temperature Sensor Calibration			
Temperature ID :	100769	Name :	HGS1
Ambient Temperature, °F :	57.9	Date :	January 19, 2024

Temperature Calibrator			
Model # :	CL23A	Certification Date:	May 2, 2023
Serial # :	T-285668	Expiration Date:	May 2, 2024

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

Reference Source Temperature (°F)	Test Thermometer Temperature (°F)	Temperature Difference %
0	1	0.2
250	251	0.1
600	601	0.1
1200	1205	0.3

$$\frac{(\text{Ref. Temp., } ^\circ\text{F} + 460) - (\text{Test Therm. Temp., } ^\circ\text{F} + 460)}{\text{Ref. Temp., } ^\circ\text{F} + 460} * 100 \leq 1.5 \%$$

Ref. Temp., °F + 460

Meter Box Calibration

Dry Gas Meter Calibration Data

Dry Gas Meter No. CM43
Standard Meter No. 366118
Standard Meter (Y) 0.99950

Date: February 3, 2024
Calibrated By: JVC
Barometric Pressure: 29.41

Run Number	Orifice Setting in H ₂ O Chg (H)	Standard Meter Gas Volume vr	Dry Gas Meter Gas Volume vd	Standard Meter Temp. F° tr	Dry Gas Meter Inlet Temp. F° tdi	Dry Gas Meter Outlet Temp. F° tdo	Dry Gas Meter Avg. Temp. F° td	Time Min	Time Sec	Y	Chg (H)
Final		103.672	8.128	55	60	60					
Initial		98.279	2.724	55	58	58					
Difference	1 0.20	5.393	5.404	55	59	59	59	22	46	1.005	1.975
Final		11.028	15.533	55	61	61					
Initial		3.872	8.342	55	60	60					
Difference	2 0.50	7.156	7.191	55	61	61	61	18	22	1.004	1.820
Final		18.446	22.978	55	61	61					
Initial		11.196	15.708	55	61	61					
Difference	3 0.70	7.250	7.270	55	61	61	61	15	45	1.007	1.823
Final		26.100	30.672	56	62	62					
Initial		18.674	23.209	55	62	62					
Difference	4 0.90	7.426	7.463	56	62	62	62	14	14	1.005	1.825
Final		32.989	37.605	56	63	63					
Initial		26.246	30.819	56	62	62					
Difference	5 1.20	6.743	6.786	56	63	63	63	10	59	1.003	1.759
Final		98.230	102.664	55	58	58					
Initial		91.299	95.755	55	57	57					
Difference	6 2.00	6.931	6.909	55	58	58	58	8	58	1.003	1.860

Average **1.004** **1.844**

Stack Temperature Sensor Calibration			
Temperature ID :	100769	Name :	JVC
Ambient Temperature, °F :	57	Date :	February 3, 2024

Temperature Calibrator			
Model # :	CL23A	Certification Date:	May 2, 2023
Serial # :	T-285668	Expiration Date:	May 2, 2024

Primary Standards Directly Traceable National Institute of Standards and Technology (NIST)

Reference Source Temperature (°F)	Test Thermometer Temperature (°F)	Temperature Difference %
0	1	0.2
250	252	0.3
600	602	0.2
1200	1206	0.4

$$\frac{(\text{Ref. Temp., } ^\circ\text{F} + 460) - (\text{Test Therm. Temp., } ^\circ\text{F} + 460)}{\text{Ref. Temp., } ^\circ\text{F} + 460} * 100 \leq 1.5 \%$$

Ref. Temp., °F + 460



Airflow Sciences Corporation

Probe Calibration for Method 2

Data Collection and Analysis

Date: 9/21/2023
Temperature (°F): 72.6
Pressure ("Hg): 29.48
Personnel: wgj
Probe: S8-058-A

Wind Tunnel Target DP [I.W.C]	Wind Tunnel Actual DP [I.W.C]	S-Probe DP [I.W.C.]	C _p	C _{p(avg)}	C _p -C _{p(avg)}	σ _{max}	
0.81	0.81	1.15	0.831	0.832	0.000	0.000	Pass
0.81	0.81	1.15	0.832		0.000		
0.81	0.81	1.15	0.832		0.000		
1.81	1.82	2.55	0.837	0.837	0.000	0.001	Pass
1.81	1.82	2.55	0.837		0.000		
1.81	1.82	2.55	0.838		0.001		



Airflow Sciences Corporation

Probe Calibration for Method 2

Data Collection and Analysis

Date: 9/21/2023
Temperature (°F): 72.6
Pressure ("Hg): 29.48
Personnel: wgj
Probe: S8-058-B

Wind Tunnel Target DP [I.W.C]	Wind Tunnel Actual DP [I.W.C]	S-Probe DP [I.W.C.]	C _p	C _{p(avg)}	C _p -C _{p(avg)}	σ _{max}	
0.81	0.81	1.15	0.833	0.833	0.000	0.000	Pass
0.81	0.81	1.15	0.832		0.000		
0.81	0.81	1.15	0.833		0.000		
1.81	1.82	2.56	0.835	0.836	0.000	0.000	Pass
1.81	1.83	2.56	0.836		0.000		
1.81	1.83	2.56	0.836		0.000		



Airflow Sciences Corporation

Probe Calibration for Method 2

Wind Tunnel Facility: Airflow Sciences Corporation
 Wind Tunnel Location: Livonia, MI
 Probe Type: S-Type Pitot
 Probe ID: S8-058-A
 Probe Calibration Date: 09/21/23
 Test Point Location: center
 Ambient Temperature (°F): 72.6
 Barometric Pressure ("Hg): 29.48

Repetition	Nominal Low Velocity Setting (ft/s)	Calibration Pitot		Tested Probe		Calculated C _p
		DP _{std} ("H ₂ O)	Temperature (°F)	DP ("H ₂ O)	Yaw Angle (°)	
1	60	0.81	72.6	1.15	0	0.83
2	60	0.81	72.6	1.15	0	0.83
3	60	0.81	72.6	1.15	0	0.83
Average (C _{p(avg-low)})						0.83

Repetition	Nominal High Velocity Setting (ft/s)	Calibration Pitot		Tested Probe		Calculated C _p
		DP _{std} ("H ₂ O)	Temperature (°F)	DP ("H ₂ O)	Yaw Angle (deg)	
1	90	1.82	72.6	2.55	0	0.84
2	90	1.82	72.6	2.55	0	0.84
3	90	1.82	72.6	2.55	0	0.84
Average (C _{p(avg-high)})						0.84

$$\% \text{ Difference} = \frac{C_{p(\text{avg-low})} - C_{p(\text{avg-high})}}{C_{p(\text{avg-low})}} \times 100\% = \underline{-0.67\%} \quad \text{Pass}$$

Note: (1) The percent difference between the low and high velocity setting C_p values shall be within +/- 3 %.
 (2) If calibrating a 3-D probe for this method, the pitch angle setting must be 0°.

$$C_p = \underline{0.834}$$



Airflow Sciences Corporation

Probe Calibration for Method 2

Wind Tunnel Facility: Airflow Sciences Corporation
 Wind Tunnel Location: Livonia, MI
 Probe Type: S-Type Pitot
 Probe ID: S8-058-B
 Probe Calibration Date: 09/21/23
 Test Point Location: center
 Ambient Temperature (°F): 72.6
 Barometric Pressure ("Hg): 29.48

Repetition	Nominal Low Velocity Setting (ft/s)	Calibration Pitot		Tested Probe		Calculated C_p
		DP _{std} ("H ₂ O)	Temperature (°F)	DP ("H ₂ O)	Yaw Angle (°)	
1	60	0.81	72.6	1.15	0	0.83
2	60	0.81	72.6	1.15	0	0.83
3	60	0.81	72.6	1.15	0	0.83
Average ($C_{p(avg-low)}$)						0.83

Repetition	Nominal High Velocity Setting (ft/s)	Calibration Pitot		Tested Probe		Calculated C_p
		DP _{std} ("H ₂ O)	Temperature (°F)	DP ("H ₂ O)	Yaw Angle (deg)	
1	90	1.82	72.6	2.56	0	0.84
2	90	1.83	72.6	2.56	0	0.84
3	90	1.83	72.6	2.56	0	0.84
Average ($C_{p(avg-high)}$)						0.84

$$\% \text{ Difference} = \frac{C_{p(avg-low)} - C_{p(avg-high)}}{C_{p(avg-low)}} \times 100\% = \underline{-0.37\%} \quad \text{Pass}$$


Note: (1) The percent difference between the low and high velocity setting C_p values shall be within +/- 3 %.
 (2) If calibrating a 3-D probe for this method, the pitch angle setting must be 0°.

$$C_p = \underline{0.834}$$




Airflow Sciences Corporation

Probe Inspection for Method 2G



α_1	0.4 (°)	Pass
α_2	0.5 (°)	Pass
β_1	0.3 (°)	Pass
β_2	0.3 (°)	Pass
D_t	0.375 (")	Pass
P_a	0.474 (")	Pass
P_b	0.474 (")	Pass
z	<0.02 (")	Pass
w	0.007 (")	Pass



Certification

I certify that Type S probe ID **S8-058** meets or exceeds all specifications, criteria, and applicable design features.

Certified by: W Jambeck

Date: 9/21/2023



Airflow Sciences Corporation

Probe Calibration for Method 2

Data Collection and Analysis

Date: 9/21/2023
Temperature (°F): 72.8
Pressure ("Hg): 29.48
Personnel: wgj
Probe: S8-059-A

Wind Tunnel Target DP [I.W.C]	Wind Tunnel Actual DP [I.W.C]	S-Probe DP [I.W.C.]	C _p	C _{p(avg)}	C _p -C _{p(avg)}	σ _{max}	
0.81	0.81	1.13	0.838	0.838	0.000	0.000	Pass
0.81	0.81	1.14	0.837		0.000		
0.81	0.81	1.14	0.838		0.000		
1.81	1.81	2.51	0.840	0.840	0.000	0.000	Pass
1.81	1.81	2.51	0.840		0.000		
1.81	1.81	2.51	0.840		0.000		



Airflow Sciences Corporation

Probe Calibration for Method 2

Data Collection and Analysis

Date: 9/21/2023
Temperature (°F): 73.1
Pressure ("Hg): 29.47
Personnel: wgj
Probe: S8-059-B

Wind Tunnel Target DP [I.W.C]	Wind Tunnel Actual DP [I.W.C]	S-Probe DP [I.W.C.]	C _p	C _{p(avg)}	C _p -C _{p(avg)}	σ _{max}	
0.81	0.81	1.16	0.828	0.828	0.000	0.000	Pass
0.81	0.81	1.16	0.828		0.000		
0.81	0.81	1.16	0.828		0.000		
1.81	1.81	2.58	0.829	0.829	0.000	0.000	Pass
1.81	1.81	2.58	0.829		0.000		
1.81	1.81	2.58	0.829		0.000		



Airflow Sciences Corporation

Probe Calibration for Method 2

Wind Tunnel Facility: Airflow Sciences Corporation
 Wind Tunnel Location: Livonia, MI
 Probe Type: S-Type Pitot
 Probe ID: S8-059-A
 Probe Calibration Date: 09/21/23
 Test Point Location: center
 Ambient Temperature (°F): 72.8
 Barometric Pressure ("Hg): 29.48

Repetition	Nominal Low Velocity Setting (ft/s)	Calibration Pitot		Tested Probe		Calculated C _p
		DP _{std} ("H ₂ O)	Temperature (°F)	DP ("H ₂ O)	Yaw Angle (°)	
1	60	0.81	72.8	1.13	0	0.84
2	60	0.81	72.8	1.14	0	0.84
3	60	0.81	72.8	1.14	0	0.84
Average (C _{p(avg-low)})						0.84

Repetition	Nominal High Velocity Setting (ft/s)	Calibration Pitot		Tested Probe		Calculated C _p
		DP _{std} ("H ₂ O)	Temperature (°F)	DP ("H ₂ O)	Yaw Angle (deg)	
1	90	1.81	72.8	2.51	0	0.84
2	90	1.81	72.8	2.51	0	0.84
3	90	1.81	72.8	2.51	0	0.84
Average (C _{p(avg-high)})						0.84

$$\% \text{ Difference} = \frac{C_{p(\text{avg-low})} - C_{p(\text{avg-high})}}{C_{p(\text{avg-low})}} \times 100\% = \underline{-0.30\%} \quad \text{Pass}$$

Note: (1) The percent difference between the low and high velocity setting C_p values shall be within +/- 3 %.
 (2) If calibrating a 3-D probe for this method, the pitch angle setting must be 0°.

$$C_p = \underline{0.839}$$



Airflow Sciences Corporation

Probe Calibration for Method 2

Wind Tunnel Facility: Airflow Sciences Corporation
 Wind Tunnel Location: Livonia, MI
 Probe Type: S-Type Pitot
 Probe ID: S8-059-B
 Probe Calibration Date: 09/21/23
 Test Point Location: center
 Ambient Temperature (°F): 73.1
 Barometric Pressure ("Hg): 29.47

Repetition	Nominal Low Velocity Setting (ft/s)	Calibration Pitot		Tested Probe		Calculated C _p
		DP _{std} ("H ₂ O)	Temperature (°F)	DP ("H ₂ O)	Yaw Angle (°)	
1	60	0.81	73.1	1.16	0	0.83
2	60	0.81	73.1	1.16	0	0.83
3	60	0.81	73.1	1.16	0	0.83
Average (C _{p(avg-low)})						0.83

Repetition	Nominal High Velocity Setting (ft/s)	Calibration Pitot		Tested Probe		Calculated C _p
		DP _{std} ("H ₂ O)	Temperature (°F)	DP ("H ₂ O)	Yaw Angle (deg)	
1	90	1.81	73.1	2.58	0	0.83
2	90	1.81	73.1	2.58	0	0.83
3	90	1.81	73.1	2.58	0	0.83
Average (C _{p(avg-high)})						0.83

$$\% \text{ Difference} = \frac{C_{p(\text{avg-low})} - C_{p(\text{avg-high})}}{C_{p(\text{avg-low})}} \times 100\% = \underline{-0.17\%} \quad \text{Pass}$$


Note: (1) The percent difference between the low and high velocity setting C_p values shall be within +/- 3 %.
 (2) If calibrating a 3-D probe for this method, the pitch angle setting must be 0°.

$$C_p = \underline{0.829}$$




Airflow Sciences Corporation

Probe Inspection for Method 2G



α_1	0.9 ($^\circ$)	Pass
α_2	0.5 ($^\circ$)	Pass
β_1	0.7 ($^\circ$)	Pass
β_2	0.9 ($^\circ$)	Pass
D_t	0.375 (")	Pass
P_a	0.471 (")	Pass
P_b	0.471 (")	Pass
z	<0.02 (")	Pass
w	0.005 (")	Pass



Certification

I certify that Type S probe ID **S8-059** meets or exceeds all specifications, criteria, and applicable design features.

Certified by: W Jambeck

Date: 9/21/2023


Nozzle Calibration

Date: 2/22/2024

Nozzle ID No.: 201

Analyst: RB

Material/Type: Glass



0.281 1

0.280 2

0.279 3

0.280 4

Valid Data

Average

0.280


Nozzle Calibration

Date: 12/26/2019

Nozzle ID No.: 865

Analyst: JRK

Material/Type: Glass



0.251 1

0.252 2

0.251 3

0.252 4

Valid Data

Average

0.251

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Operating Condition: Mill On

Test Location: Kiln 3 Common Stack
Date: 1/30/2024
Operator: A. Benninghoff
FTIR s/n: 00612

System Leak Check: 0.0 mL/min

Nitrogen (Zero) Direct to FTIR

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
N2_000002.LAB	1/30/24	7:12:45	0.0	0.0	0.0	191.2	0.99	0.1	0.0	-0.002
N2_000003.LAB	1/30/24	7:12:53	0.0	0.0	0.0	191.2	0.99	0.1	0.0	-0.002
N2_000004.LAB	1/30/24	7:13:01	0.0	0.0	-0.1	191.2	0.99	0.0	0.2	-0.003
N2_000005.LAB	1/30/24	7:13:09	0.0	0.0	0.0	191.2	0.99	0.0	-0.4	-0.001
N2_000006.LAB	1/30/24	7:13:16	0.0	0.0	0.0	191.2	0.99	0.1	-0.3	0.001
N2_000007.LAB	1/30/24	7:13:24	0.0	0.0	-0.2	191.3	0.99	0.0	0.2	0.003
N2_000008.LAB	1/30/24	7:13:32	0.0	0.0	-0.1	191.3	0.99	0.1	0.2	-0.004
N2_000009.LAB	1/30/24	7:13:40	0.0	0.0	0.0	191.3	0.99	0.1	-0.2	-0.001

Calibration Transfer Standard (CTS), Direct to FTIR

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
CTS DIR_000043.LAB	1/30/24	7:18:59	0.0	0.0	-0.3	191.2	0.99	97.4	0.0	-0.002	97.4%
CTS DIR_000044.LAB	1/30/24	7:19:06	0.0	0.0	-0.2	191.2	0.99	97.4	0.3	-0.005	97.4%
CTS DIR_000045.LAB	1/30/24	7:19:14	0.0	0.0	0.0	191.2	0.99	97.6	0.3	-0.018	97.6%
CTS DIR_000046.LAB	1/30/24	7:19:22	0.0	0.0	0.0	191.2	0.99	97.9	1.1	-0.016	97.9%
CTS DIR_000047.LAB	1/30/24	7:19:30	0.0	0.0	-0.2	191.2	0.99	97.5	0.0	-0.013	97.6%
CTS DIR_000048.LAB	1/30/24	7:19:38	0.0	0.0	-0.1	191.2	0.99	97.3	-0.1	-0.014	97.3%
CTS DIR_000049.LAB	1/30/24	7:19:46	0.0	0.0	0.0	191.2	0.99	97.6	-0.2	-0.010	97.6%
Average								97.5			97.5%

Analyte Spike Gas (HCN) Direct to FTIR

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % HCN
HCN DIR_000084.LAB	1/30/24	7:25:12	0.0	0.0	0.0	191.0	0.99	-0.5	49.6	4.875	99.8%
HCN DIR_000085.LAB	1/30/24	7:25:20	0.0	0.0	-0.1	191.0	0.99	0.0	49.8	4.858	100.2%
HCN DIR_000086.LAB	1/30/24	7:25:28	0.0	0.0	0.0	191.0	0.99	-0.4	50.4	4.864	101.3%
HCN DIR_000087.LAB	1/30/24	7:25:36	0.0	0.0	-0.2	191.0	0.99	-0.2	50.0	4.858	100.5%
HCN DIR_000088.LAB	1/30/24	7:25:44	0.0	0.0	-0.2	191.0	0.99	-0.3	49.7	4.842	100.0%
HCN DIR_000089.LAB	1/30/24	7:25:51	0.0	0.0	-0.1	191.0	0.99	-0.2	49.3	4.866	99.2%
HCN DIR_000090.LAB	1/30/24	7:25:59	0.0	0.0	0.1	191.0	0.99	-0.3	49.6	4.861	99.7%
HCN DIR_000091.LAB	1/30/24	7:26:07	0.0	0.0	-0.2	191.0	0.99	-0.1	49.6	4.853	99.8%
Average									49.8	4.860	100.1%

CTS, System Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
ETHYLENE REMOTE_000100.LAB	1/30/24	7:27:52	0.1	0.0	-0.1	191.0	0.99	97.4	0.4	-0.009	97.5%
ETHYLENE REMOTE_000101.LAB	1/30/24	7:27:59	0.0	0.0	-0.2	191.0	0.99	97.3	0.3	-0.001	97.3%
ETHYLENE REMOTE_000102.LAB	1/30/24	7:28:07	0.0	0.0	0.0	191.1	0.99	97.8	0.4	-0.007	97.8%
ETHYLENE REMOTE_000103.LAB	1/30/24	7:28:15	0.0	0.0	-0.2	191.1	0.99	97.6	0.2	-0.006	97.6%
ETHYLENE REMOTE_000104.LAB	1/30/24	7:28:23	0.0	0.0	-0.1	191.1	0.99	97.7	0.5	-0.005	97.7%
ETHYLENE REMOTE_000105.LAB	1/30/24	7:28:31	0.0	0.0	0.1	191.1	0.99	97.8	0.3	-0.016	97.8%
ETHYLENE REMOTE_000106.LAB	1/30/24	7:28:39	0.0	0.0	0.0	191.1	0.99	97.5	-0.1	-0.014	97.5%
ETHYLENE REMOTE_000107.LAB	1/30/24	7:28:47	0.0	0.0	0.0	191.1	0.99	97.4	0.0	-0.005	97.4%

Response Time Test

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Response Time (sec)
ETHYLENE REMOTE_000097.LAB	1/30/24	7:27:28	1.7	0.1	-0.1	191.1	0.99	11.2	13.1	-0.050	-
ETHYLENE REMOTE_000098.LAB	1/30/24	7:27:36	0.3	0.0	-0.1	191.1	0.99	93.8	0.9	-0.003	15.687
ETHYLENE REMOTE_000099.LAB	1/30/24	7:27:44	0.1	0.0	0.2	191.0	0.99	97.3	0.3	-0.016	23.687
ETHYLENE REMOTE_000100.LAB	1/30/24	7:27:52	0.1	0.0	-0.1	191.0	0.99	97.4	0.4	-0.009	
ETHYLENE REMOTE_000101.LAB	1/30/24	7:27:59	0.0	0.0	-0.2	191.0	0.99	97.3	0.3	-0.001	
ETHYLENE REMOTE_000102.LAB	1/30/24	7:28:07	0.0	0.0	0.0	191.1	0.99	97.8	0.4	-0.007	
ETHYLENE REMOTE_000103.LAB	1/30/24	7:28:15	0.0	0.0	-0.2	191.1	0.99	97.6	0.2	-0.006	
ETHYLENE REMOTE_000104.LAB	1/30/24	7:28:23	0.0	0.0	-0.1	191.1	0.99	97.7	0.5	-0.005	
ETHYLENE REMOTE_000105.LAB	1/30/24	7:28:31	0.0	0.0	0.1	191.1	0.99	97.8	0.3	-0.016	

Client: Holcim (US) Inc.
Facility: Ravena Cement Plant
Project #: M234506
Operating Condition: Mill On

Test Location: Kiln 3 Common Stack
Date: 1/30/2024
Operator: A. Benninghoff
FTIR s/n: 00612

Pre 1 Native Effluent Prior to Analyte Spike

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
NATIVE_000160.LAB	1/30/24	7:38:19	9.0	7.8	0.0	191.0	0.99	0.3	1.1	0.003
NATIVE_000161.LAB	1/30/24	7:38:26	9.1	7.8	-0.2	191.0	0.99	0.3	1.4	-0.007
NATIVE_000162.LAB	1/30/24	7:38:34	9.0	7.8	-0.3	191.0	0.99	0.5	1.4	0.003
									1.3	-0.001

Pre 1 Effluent Spike Using Analyte

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Dilution Factor	Recovery % HCN
PRE 1 SPIKE_000192.LAB	1/30/24	7:43:02	8.1	7.2	-0.1	190.9	0.99	0.4	5.7	0.486	0.100	93.8%
PRE 1 SPIKE_000193.LAB	1/30/24	7:43:10	8.1	7.2	-0.2	190.9	0.99	0.1	5.8	0.482	0.099	94.9%
PRE 1 SPIKE_000194.LAB	1/30/24	7:43:18	8.1	7.2	-0.1	190.9	0.99	0.3	5.7	0.488	0.100	92.4%
PRE 1 SPIKE_000195.LAB	1/30/24	7:43:26	8.1	7.3	-0.1	190.9	0.99	0.1	6.1	0.481	0.099	101.1%
PRE 1 SPIKE_000196.LAB	1/30/24	7:43:34	8.1	7.3	-0.2	191.0	0.99	0.2	5.6	0.487	0.100	90.8%
PRE 1 SPIKE_000197.LAB	1/30/24	7:43:41	8.1	7.3	-0.3	191.0	0.99	0.3	5.8	0.471	0.097	96.6%
PRE 1 SPIKE_000198.LAB	1/30/24	7:43:49	8.1	7.3	-0.2	191.0	0.99	0.2	5.8	0.481	0.099	95.9%
PRE 1 SPIKE_000199.LAB	1/30/24	7:43:57	8.2	7.2	-0.2	191.0	0.99	0.3	6.0	0.485	0.100	99.1%

Native Effluent Prior to Analyte Spike

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
RUN 1_000302.LAB	1/30/24	9:27:49	9.1	8.0	-0.2	190.8	0.99	0.3	1.2	0.000
RUN 1_000303.LAB	1/30/24	9:28:52	9.1	7.8	-0.2	190.9	0.99	0.3	1.1	0.001
RUN 1_000304.LAB	1/30/24	9:29:55	9.1	8.0	-0.2	190.7	0.99	0.3	1.1	-0.004
									1.1	-0.001

Effluent Spike Using Analyte

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Dilution Factor	Recovery % HCN
P RUN 1 SPIKE_000322.LAB	1/30/24	9:33:59	8.3	7.2	-0.1	190.7	0.99	0.1	5.8	0.473	0.097	98.1%
P RUN 1 SPIKE_000323.LAB	1/30/24	9:34:06	8.2	7.2	-0.1	190.7	0.99	0.2	5.4	0.467	0.096	93.4%
P RUN 1 SPIKE_000324.LAB	1/30/24	9:34:14	8.3	7.2	-0.1	190.7	0.99	0.1	6.0	0.461	0.095	105.0%
P RUN 1 SPIKE_000325.LAB	1/30/24	9:34:22	8.2	7.3	-0.1	190.7	0.99	0.2	5.7	0.468	0.096	97.8%
P RUN 1 SPIKE_000326.LAB	1/30/24	9:34:30	8.2	7.3	-0.1	190.7	0.99	0.2	5.6	0.467	0.096	96.7%
P RUN 1 SPIKE_000327.LAB	1/30/24	9:34:38	8.2	7.2	-0.3	190.7	0.99	0.1	5.3	0.475	0.098	89.5%
P RUN 1 SPIKE_000328.LAB	1/30/24	9:34:45	8.2	7.2	-0.1	190.6	0.99	0.3	6.1	0.473	0.097	103.1%
P RUN 1 SPIKE_000329.LAB	1/30/24	9:34:53	8.2	7.2	-0.2	190.7	0.99	0.1	5.9	0.457	0.094	102.7%

CTS, System Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
P RUN 1 CTS_000337.LAB	1/30/24	9:36:47	0.1	0.0	-0.1	190.7	0.99	97.6	0.3	-0.014	97.6%
P RUN 1 CTS_000338.LAB	1/30/24	9:36:55	0.1	0.0	-0.1	190.7	0.99	97.4	0.4	-0.008	97.4%
P RUN 1 CTS_000339.LAB	1/30/24	9:37:03	0.0	0.0	0.1	190.7	0.99	97.5	0.5	-0.016	97.5%
P RUN 1 CTS_000340.LAB	1/30/24	9:37:11	0.1	0.0	0.1	190.7	0.99	97.4	0.2	-0.010	97.4%
P RUN 1 CTS_000341.LAB	1/30/24	9:37:19	0.0	0.0	0.0	190.7	0.99	97.7	0.8	-0.012	97.7%
P RUN 1 CTS_000342.LAB	1/30/24	9:37:26	0.0	0.0	-0.1	190.7	0.99	97.2	0.4	-0.013	97.2%
P RUN 1 CTS_000343.LAB	1/30/24	9:37:34	0.0	0.0	-0.1	190.7	0.99	97.6	0.2	-0.019	97.6%
P RUN 1 CTS_000344.LAB	1/30/24	9:37:42	0.0	0.0	-0.1	190.7	0.99	97.4	0.2	-0.017	97.4%

Client: Holcim (US) Inc.
Facility: Ravena Cement Plant
Project #: M234506
Operating Condition: Mill On

Test Location: Kiln 3 Common Stack
Date: 1/30/2024
Operator: A. Benninghoff
FTIR s/n: 00612

Native Effluent Prior to Analyte Spike

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
RUN 2_000445.LAB	1/30/24	11:02:39	9.0	8.0	-0.2	190.4	0.99	0.5	0.1	-0.006
RUN 2_000446.LAB	1/30/24	11:03:41	9.0	8.1	-0.1	190.4	0.99	0.4	-0.1	-0.007
RUN 2_000447.LAB	1/30/24	11:04:45	9.0	8.1	-0.2	190.5	0.99	0.5	0.1	-0.004
									0.0	-0.006

Effluent Spike Using Analyte

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Dilution Factor	Recovery % HCN
POST RUN 2 SPIKE_000460.LAB	1/30/24	11:08:00	8.2	7.4	-0.2	190.5	0.99	0.3	4.4	0.438	0.090	97.4%
POST RUN 2 SPIKE_000461.LAB	1/30/24	11:08:08	8.2	7.5	-0.1	190.4	0.99	0.3	4.6	0.434	0.089	102.9%
POST RUN 2 SPIKE_000462.LAB	1/30/24	11:08:15	8.2	7.4	-0.2	190.4	0.99	0.6	4.5	0.444	0.091	98.0%
POST RUN 2 SPIKE_000463.LAB	1/30/24	11:08:23	8.2	7.4	-0.1	190.4	0.99	0.5	4.6	0.439	0.090	101.7%
POST RUN 2 SPIKE_000464.LAB	1/30/24	11:08:31	8.2	7.5	-0.1	190.4	0.99	0.5	4.5	0.444	0.091	99.7%
POST RUN 2 SPIKE_000465.LAB	1/30/24	11:08:39	8.2	7.5	-0.1	190.5	0.99	0.5	4.1	0.443	0.091	90.1%
POST RUN 2 SPIKE_000466.LAB	1/30/24	11:08:47	8.2	7.4	-0.2	190.5	0.99	0.5	4.1	0.440	0.091	90.0%
POST RUN 2 SPIKE_000467.LAB	1/30/24	11:08:55	8.2	7.4	-0.3	190.5	0.99	0.5	4.4	0.449	0.092	95.5%

CTS, System Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
POST RUN 2 CTS_000474.LAB	1/30/24	11:10:34	0.1	0.0	-0.1	190.4	0.99	97.3	-0.9	-0.019	99.7%
POST RUN 2 CTS_000475.LAB	1/30/24	11:10:42	0.1	0.0	0.0	190.4	0.99	97.3	-1.1	-0.005	99.8%
POST RUN 2 CTS_000476.LAB	1/30/24	11:10:50	0.1	0.0	0.0	190.5	0.99	97.6	-0.8	-0.011	100.1%
POST RUN 2 CTS_000477.LAB	1/30/24	11:10:57	0.0	0.0	0.1	190.5	0.99	97.9	-0.6	-0.009	100.4%
POST RUN 2 CTS_000478.LAB	1/30/24	11:11:05	0.1	0.0	-0.1	190.5	0.99	97.4	-0.5	-0.019	99.9%
POST RUN 2 CTS_000479.LAB	1/30/24	11:11:13	0.0	0.0	0.0	190.6	0.99	98.2	-0.9	-0.006	100.6%
POST RUN 2 CTS_000480.LAB	1/30/24	11:11:21	0.0	0.0	0.0	190.7	0.99	97.6	-1.1	-0.019	100.0%
POST RUN 2 CTS_000481.LAB	1/30/24	11:11:29	0.0	0.0	0.0	190.7	0.99	97.7	-0.7	-0.020	100.2%

Native Effluent Prior to Analyte Spike

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
RUN 3_000523.LAB	1/30/24	11:39:26	8.9	8.0	-0.2	190.4	0.99	0.6	0.2	-0.002
RUN 3_000524.LAB	1/30/24	11:40:28	8.9	8.1	-0.1	190.4	0.99	0.6	0.2	-0.005
RUN 3_000525.LAB	1/30/24	11:41:31	8.9	8.0	-0.1	190.6	0.99	0.5	0.2	-0.005
									0.2	-0.004

Effluent Spike Using Analyte

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Dilution Factor	Recovery % HCN
POST RUN 3 SPIKE_000591.LAB	1/30/24	12:42:29	8.2	7.3	-0.1	190.7	0.99	0.6	4.9	0.477	0.098	96.3%
POST RUN 3 SPIKE_000592.LAB	1/30/24	12:42:37	8.2	7.2	-0.3	190.7	0.99	0.6	4.9	0.478	0.098	97.2%
POST RUN 3 SPIKE_000593.LAB	1/30/24	12:42:45	8.2	7.3	-0.2	190.7	0.99	0.3	4.7	0.486	0.100	90.9%
POST RUN 3 SPIKE_000594.LAB	1/30/24	12:42:53	8.1	7.2	-0.1	190.7	0.99	0.3	5.2	0.484	0.100	101.7%
POST RUN 3 SPIKE_000595.LAB	1/30/24	12:43:01	8.1	7.2	-0.3	190.8	0.99	0.3	5.0	0.468	0.096	101.2%
POST RUN 3 SPIKE_000596.LAB	1/30/24	12:43:09	8.1	7.2	-0.2	190.7	0.99	0.5	4.2	0.480	0.099	82.7%
POST RUN 3 SPIKE_000597.LAB	1/30/24	12:43:16	8.1	7.3	-0.1	190.7	0.99	0.5	5.1	0.493	0.101	97.6%
POST RUN 3 SPIKE_000598.LAB	1/30/24	12:43:24	8.1	7.3	-0.1	190.6	0.99	0.5	5.0	0.481	0.099	98.8%

CTS, System Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
POST RUN 3 CTS_000603.LAB	1/30/24	12:44:53	0.1	0.0	0.0	190.8	0.99	97.7	-0.9	-0.010	100.1%
POST RUN 3 CTS_000604.LAB	1/30/24	12:45:01	0.1	0.0	0.0	190.8	0.99	97.5	-1.1	-0.011	100.0%
POST RUN 3 CTS_000605.LAB	1/30/24	12:45:09	0.1	0.0	0.0	190.8	0.99	97.9	-0.8	-0.010	100.3%
POST RUN 3 CTS_000606.LAB	1/30/24	12:45:17	0.1	0.0	-0.1	190.8	0.99	97.4	-0.9	-0.011	99.9%
POST RUN 3 CTS_000607.LAB	1/30/24	12:45:25	0.0	0.0	-0.1	190.8	0.99	97.4	-0.7	-0.006	99.8%
POST RUN 3 CTS_000608.LAB	1/30/24	12:45:32	0.0	0.0	0.0	190.8	0.99	97.5	-1.0	-0.023	100.0%
POST RUN 3 CTS_000609.LAB	1/30/24	12:45:40	0.0	0.0	0.0	190.8	0.99	97.6	-0.7	-0.006	100.1%
POST RUN 3 CTS_000610.LAB	1/30/24	12:45:48	0.0	0.0	0.1	190.8	0.99	98.1	-0.8	-0.014	100.6%

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Operating Condition: Mill On

Test Location: Kiln 3 Common Stack
Date: 1/30/2024
Operator: A. Benninghoff
FTIR s/n: 00612

Post Test CTS, Direct Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
CTS DIRECT_000778.LAB	1/30/24	15:01:11	0.0	0.0	0.0	190.9	0.99	97.1	-1.0	-0.008	99.5%
CTS DIRECT_000779.LAB	1/30/24	15:01:19	0.0	0.0	0.0	190.9	0.99	97.1	-0.7	-0.009	99.6%
CTS DIRECT_000780.LAB	1/30/24	15:01:28	0.0	0.0	-0.1	190.9	0.99	97.3	-0.5	-0.020	99.8%
CTS DIRECT_000781.LAB	1/30/24	15:01:35	0.0	0.0	0.1	190.9	0.99	97.3	-1.0	-0.023	99.8%
CTS DIRECT_000782.LAB	1/30/24	15:01:43	0.0	0.0	0.0	190.9	0.99	97.4	-0.5	-0.024	99.9%
CTS DIRECT_000783.LAB	1/30/24	15:01:51	0.0	0.0	-0.1	190.9	0.99	96.9	-0.5	-0.009	99.4%
CTS DIRECT_000784.LAB	1/30/24	15:01:59	0.0	0.0	0.0	190.8	0.99	97.3	-1.0	-0.009	99.7%
CTS DIRECT_000785.LAB	1/30/24	15:02:06	0.0	0.0	0.0	190.8	0.99	97.3	-0.9	-0.018	99.8%
Average								97.2			

Post Test N2, Direct Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
ZERO GAS 126 DIR_000786.LAB	1/30/24	15:05:28	0.0	0.0	-0.1	190.8	0.99	0.2	-0.7	0.002
ZERO GAS 126 DIR_000787.LAB	1/30/24	15:07:34	0.0	0.0	0.0	190.7	0.99	0.1	-0.9	0.000
ZERO GAS 126 DIR_000788.LAB	1/30/24	15:09:39	0.0	0.0	0.0	190.9	0.99	0.1	-0.9	0.002

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Operating Condition: Mill Off

Test Location: Kiln 3 Common Stack
Date: 1/31/2024
Operator: A. Benninghoff
FTIR s/n: 612

System Leak Check: 0.0 mL/min

Nitrogen (Zero) Direct to FTIR

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
BACKGROUND_000023.LAB	1/31/24	6:51:56	0.1	0.0	0.0	191.0	0.99	0.1	-0.1	-0.002
BACKGROUND_000024.LAB	1/31/24	6:52:04	0.1	0.0	-0.1	190.9	0.99	0.3	0.1	0.006
BACKGROUND_000025.LAB	1/31/24	6:52:11	0.1	0.0	-0.1	191.0	0.99	0.1	0.2	0.004
BACKGROUND_000026.LAB	1/31/24	6:52:19	0.1	0.0	0.0	191.0	0.99	0.3	-0.4	-0.008
BACKGROUND_000027.LAB	1/31/24	6:52:27	0.1	0.0	0.0	191.0	0.99	0.2	-0.3	0.012
BACKGROUND_000028.LAB	1/31/24	6:52:35	0.1	0.0	0.0	190.9	0.99	0.1	0.2	-0.005
BACKGROUND_000029.LAB	1/31/24	6:52:43	0.1	0.0	0.0	191.0	0.99	0.2	-0.2	0.007
BACKGROUND_000030.LAB	1/31/24	6:52:51	0.1	0.0	0.0	191.0	0.99	0.0	0.1	-0.008
BACKGROUND_000031BKG.LAB	1/31/24	6:55:10	0.0	0.0	0.0	191.0	0.99	0.0	0.0	0.000

Calibration Transfer Standard (CTS), Direct to FTIR

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
CTS DIRECT_000033.LAB	1/31/24	6:56:09	0.0	0.0	0.0	191.0	0.99	97.0	-0.1	-0.016	97.0%
CTS DIRECT_000034.LAB	1/31/24	6:56:17	0.0	0.0	0.0	191.0	0.99	96.8	0.4	-0.017	96.8%
CTS DIRECT_000035.LAB	1/31/24	6:56:25	0.0	0.0	0.0	191.1	0.99	97.2	0.0	-0.013	97.2%
CTS DIRECT_000036.LAB	1/31/24	6:56:33	0.0	0.0	0.0	191.0	0.99	97.3	-0.3	-0.021	97.3%
CTS DIRECT_000037.LAB	1/31/24	6:56:41	0.0	0.0	0.1	191.0	0.99	97.1	0.1	-0.020	97.1%
CTS DIRECT_000038.LAB	1/31/24	6:56:49	0.0	0.0	-0.1	191.0	0.99	97.2	-0.2	-0.010	97.2%
CTS DIRECT_000039.LAB	1/31/24	6:56:57	0.0	0.0	0.0	191.0	0.99	97.2	0.3	-0.007	97.2%
Average								97.1			97.1%

Analyte Spike Gas (HCN) Direct to FTIR

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % HCN
HCN DIRECT_000046.LAB	1/31/24	6:58:14	0.0	0.0	0.0	191.0	0.99	-0.5	49.0	4.818	98.6%
HCN DIRECT_000047.LAB	1/31/24	6:58:21	0.0	0.0	-0.2	190.9	0.99	-0.3	49.1	4.829	98.8%
HCN DIRECT_000048.LAB	1/31/24	6:58:29	0.0	0.0	0.0	190.9	0.99	-0.3	49.5	4.818	99.5%
HCN DIRECT_000049.LAB	1/31/24	6:58:37	0.0	0.0	-0.1	191.0	0.99	-0.2	49.3	4.808	99.1%
HCN DIRECT_000050.LAB	1/31/24	6:58:45	0.0	0.0	-0.1	190.9	0.99	-0.3	49.4	4.841	99.4%
HCN DIRECT_000051.LAB	1/31/24	6:58:53	0.0	0.0	0.0	191.0	0.99	-0.2	49.5	4.821	99.5%
HCN DIRECT_000052.LAB	1/31/24	6:59:01	0.0	0.0	0.0	191.0	0.99	-0.3	49.1	4.831	98.7%
HCN DIRECT_000053.LAB	1/31/24	6:59:09	0.0	0.0	0.1	191.0	0.99	-0.5	49.6	4.823	99.8%
Average									49.3	4.824	99.2%

CTS, System Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
CTS REMOTE_000280.LAB	1/31/24	7:35:05	0.1	0.0	-0.1	190.9	0.99	97.1	0.5	-0.012	97.1%
CTS REMOTE_000281.LAB	1/31/24	7:35:14	0.1	0.0	0.0	190.9	0.99	97.2	-0.1	-0.018	97.2%
CTS REMOTE_000282.LAB	1/31/24	7:35:21	0.1	0.0	0.0	190.9	0.99	97.1	0.4	-0.020	97.1%
CTS REMOTE_000283.LAB	1/31/24	7:35:29	0.1	0.0	-0.1	190.9	0.99	97.1	0.4	-0.007	97.1%
CTS REMOTE_000284.LAB	1/31/24	7:35:37	0.1	0.0	0.0	190.9	0.99	97.0	0.0	-0.009	97.0%
CTS REMOTE_000285.LAB	1/31/24	7:35:45	0.1	0.0	0.0	191.0	0.99	97.3	0.2	-0.008	97.3%
CTS REMOTE_000286.LAB	1/31/24	7:35:53	0.1	0.0	0.0	191.0	0.99	97.1	0.1	-0.011	97.1%
CTS REMOTE_000287.LAB	1/31/24	7:36:01	0.1	0.0	-0.1	191.0	0.99	97.6	0.5	-0.004	97.6%

Response Time Test

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Response Time (sec)
CTS REMOTE_000276.LAB	1/31/24	7:34:34	0.6	0.1	-0.1	190.9	0.99	0.6	0.2	-0.006	-
CTS REMOTE_000277.LAB	1/31/24	7:34:42	0.3	0.0	0.1	190.9	0.99	79.7	0.3	-0.023	15.859
CTS REMOTE_000278.LAB	1/31/24	7:34:50	0.2	0.0	0.0	190.9	0.99	97.0	0.3	-0.022	23.859
CTS REMOTE_000279.LAB	1/31/24	7:34:58	0.1	0.0	0.0	190.9	0.99	97.0	0.2	-0.011	
CTS REMOTE_000280.LAB	1/31/24	7:35:05	0.1	0.0	-0.1	190.9	0.99	97.1	0.5	-0.012	
CTS REMOTE_000281.LAB	1/31/24	7:35:14	0.1	0.0	0.0	190.9	0.99	97.2	-0.1	-0.018	
CTS REMOTE_000282.LAB	1/31/24	7:35:21	0.1	0.0	0.0	190.9	0.99	97.1	0.4	-0.020	
CTS REMOTE_000283.LAB	1/31/24	7:35:29	0.1	0.0	-0.1	190.9	0.99	97.1	0.4	-0.007	
CTS REMOTE_000284.LAB	1/31/24	7:35:37	0.1	0.0	0.0	190.9	0.99	97.0	0.0	-0.009	

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Operating Condition: Mill Off

Test Location: Kiln 3 Common Stack
Date: 1/31/2024
Operator: A. Benninghoff
FTIR s/n: 612

Pre 1 Native Effluent Prior to Analyte Spike

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
NATIVE_000314.LAB	1/31/24	7:41:23	12.6	11.4	-0.2	190.9	0.99	0.4	1.5	-0.011
NATIVE_000315.LAB	1/31/24	7:41:30	12.5	11.3	-0.2	191.0	0.99	0.6	1.4	-0.008
NATIVE_000316.LAB	1/31/24	7:41:38	12.5	11.2	-0.1	191.0	0.99	0.7	1.3	0.001
									1.4	-0.006

Pre 1 Effluent Spike Using Analyte

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Dilution Factor	Recovery % HCN
PRE 1 SPIKE_000325.LAB	1/31/24	7:43:29	11.1	9.8	-0.2	191.0	0.99	0.4	5.5	0.463	0.096	90.7%
PRE 1 SPIKE_000326.LAB	1/31/24	7:43:37	11.1	9.8	-0.2	191.0	0.99	0.4	6.1	0.470	0.097	99.6%
PRE 1 SPIKE_000327.LAB	1/31/24	7:43:45	11.0	9.9	-0.1	191.0	0.99	0.7	5.8	0.468	0.097	94.9%
PRE 1 SPIKE_000328.LAB	1/31/24	7:43:53	11.1	9.9	-0.2	191.0	0.99	0.4	5.3	0.469	0.097	87.9%
PRE 1 SPIKE_000329.LAB	1/31/24	7:44:01	11.1	9.8	-0.2	191.0	0.99	0.4	5.9	0.470	0.097	97.5%
PRE 1 SPIKE_000330.LAB	1/31/24	7:44:08	11.1	9.8	-0.2	190.9	0.99	0.5	5.5	0.471	0.098	90.3%
PRE 1 SPIKE_000331.LAB	1/31/24	7:44:16	11.0	9.8	-0.2	190.9	0.99	0.4	5.8	0.476	0.099	93.8%
PRE 1 SPIKE_000332.LAB	1/31/24	7:44:24	11.0	9.9	-0.2	190.9	0.99	0.4	5.5	0.475	0.098	89.1%

Native Effluent Prior to Analyte Spike

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
RUN 1_000442.LAB	1/31/24	9:32:58	12.7	11.0	-0.2	190.9	0.99	0.5	1.4	-0.003
RUN 1_000443.LAB	1/31/24	9:34:01	12.7	11.0	-0.1	191.0	0.99	0.5	1.5	-0.009
RUN 1_000444.LAB	1/31/24	9:35:03	12.7	10.9	-0.2	190.9	0.99	0.5	1.5	-0.004
									1.5	-0.006

Effluent Spike Using Analyte

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Dilution Factor	Recovery % HCN
POST RUN 1 SPIKE_000459.LAB	1/31/24	9:37:53	11.5	10.1	-0.1	190.9	0.99	0.3	6.0	0.443	0.092	101.9%
POST RUN 1 SPIKE_000460.LAB	1/31/24	9:38:01	11.5	10.1	-0.2	190.9	0.99	0.6	5.4	0.452	0.094	91.3%
POST RUN 1 SPIKE_000461.LAB	1/31/24	9:38:08	11.5	10.2	-0.2	190.9	0.99	0.5	5.8	0.451	0.094	98.0%
POST RUN 1 SPIKE_000462.LAB	1/31/24	9:38:16	11.6	10.3	-0.2	191.0	0.99	0.3	5.6	0.442	0.092	95.3%
POST RUN 1 SPIKE_000463.LAB	1/31/24	9:38:24	11.5	10.3	-0.2	191.0	0.99	0.3	5.6	0.442	0.092	95.7%
POST RUN 1 SPIKE_000464.LAB	1/31/24	9:38:32	11.5	10.3	-0.2	191.0	0.99	0.3	5.9	0.449	0.093	99.1%
POST RUN 1 SPIKE_000465.LAB	1/31/24	9:38:40	11.5	10.2	-0.2	190.9	0.99	0.5	5.3	0.446	0.092	90.1%
POST RUN 1 SPIKE_000466.LAB	1/31/24	9:38:48	11.5	10.2	-0.2	191.0	0.99	0.4	5.8	0.453	0.094	97.8%

CTS, System Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
POST RUN 1 CTS_000473.LAB	1/31/24	9:40:34	0.0	0.0	0.1	191.0	0.99	96.9	-0.1	-0.004	97.0%
POST RUN 1 CTS_000474.LAB	1/31/24	9:40:42	0.0	0.1	0.0	191.0	0.99	96.8	0.3	-0.011	96.8%
POST RUN 1 CTS_000475.LAB	1/31/24	9:40:50	0.0	0.0	0.0	191.0	0.99	96.7	0.4	-0.019	96.7%
POST RUN 1 CTS_000476.LAB	1/31/24	9:40:58	0.0	0.0	0.1	191.0	0.99	97.6	0.1	-0.015	97.6%
POST RUN 1 CTS_000477.LAB	1/31/24	9:41:06	0.0	0.0	0.0	191.0	0.99	97.0	0.3	-0.019	97.0%
POST RUN 1 CTS_000478.LAB	1/31/24	9:41:13	0.0	0.0	0.0	191.0	0.99	97.0	0.5	-0.020	97.0%
POST RUN 1 CTS_000479.LAB	1/31/24	9:41:21	0.0	0.0	-0.1	190.9	0.99	97.2	0.1	-0.016	97.2%
POST RUN 1 CTS_000480.LAB	1/31/24	9:41:29	0.0	0.0	0.0	191.0	0.99	97.3	0.5	-0.015	97.3%

Client: Holcim (US) Inc.
Facility: Ravena Cement Plant
Project #: M234506
Operating Condition: Mill Off

Test Location: Kiln 3 Common Stack
Date: 1/31/2024
Operator: A. Benninghoff
FTIR s/n: 612

Native Effluent Prior to Analyte Spike

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
RUN 2_000578.LAB	1/31/24	11:08:47	12.9	11.2	-0.1	191.0	0.99	0.5	0.4	-0.006
RUN 2_000579.LAB	1/31/24	11:09:50	12.9	11.2	-0.2	191.0	0.99	0.5	0.5	-0.003
RUN 2_000580.LAB	1/31/24	11:10:53	12.9	11.3	-0.2	191.1	0.99	0.5	0.3	-0.006
									0.4	-0.005

Effluent Spike Using Analyte

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Dilution Factor	Recovery % HCN
POST RUN 2 SPIKE_000588.LAB	1/31/24	11:12:45	11.8	10.2	-0.2	191.0	0.99	0.6	4.9	0.489	0.101	92.4%
POST RUN 2 SPIKE_000589.LAB	1/31/24	11:12:53	11.8	10.2	-0.2	191.0	0.99	0.4	4.6	0.490	0.102	85.8%
POST RUN 2 SPIKE_000590.LAB	1/31/24	11:13:00	11.7	10.3	-0.2	190.9	0.99	0.3	4.8	0.494	0.102	89.6%
POST RUN 2 SPIKE_000591.LAB	1/31/24	11:13:08	11.7	10.2	-0.1	191.0	0.99	0.3	5.0	0.486	0.101	94.2%
POST RUN 2 SPIKE_000592.LAB	1/31/24	11:13:16	11.7	10.0	-0.1	190.9	0.99	0.5	5.2	0.486	0.101	97.2%
POST RUN 2 SPIKE_000593.LAB	1/31/24	11:13:24	11.6	10.0	-0.2	190.9	0.99	0.4	4.8	0.484	0.100	91.5%
POST RUN 2 SPIKE_000594.LAB	1/31/24	11:13:32	11.6	10.2	-0.2	190.9	0.99	0.3	4.7	0.495	0.103	87.8%
POST RUN 2 SPIKE_000595.LAB	1/31/24	11:13:40	11.6	10.3	-0.1	190.9	0.99	0.4	5.0	0.486	0.101	95.2%

CTS, System Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
POST RUN 2 CTS_000603.LAB	1/31/24	11:15:05	0.1	0.0	0.0	191.0	0.99	96.7	-0.5	-0.012	99.5%
POST RUN 2 CTS_000604.LAB	1/31/24	11:15:13	0.1	0.1	0.1	190.9	0.99	97.0	-0.5	-0.003	99.9%
POST RUN 2 CTS_000605.LAB	1/31/24	11:15:21	0.0	0.1	0.0	190.9	0.99	97.1	-0.5	-0.014	100.0%
POST RUN 2 CTS_000606.LAB	1/31/24	11:15:29	0.0	0.0	-0.1	190.9	0.99	97.1	-1.1	-0.020	100.0%
POST RUN 2 CTS_000607.LAB	1/31/24	11:15:36	0.0	0.1	0.0	191.0	0.99	97.2	-1.0	-0.011	100.1%
POST RUN 2 CTS_000608.LAB	1/31/24	11:15:45	0.0	0.0	-0.1	191.0	0.99	97.0	-1.3	-0.014	99.9%
POST RUN 2 CTS_000609.LAB	1/31/24	11:15:52	0.0	0.0	0.0	190.9	0.99	97.3	-1.1	-0.020	100.2%
POST RUN 2 CTS_000610.LAB	1/31/24	11:16:00	0.0	0.0	0.1	190.9	0.99	97.1	-0.9	-0.018	100.0%

Native Effluent Prior to Analyte Spike

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
RUN 3_000720.LAB	1/31/24	12:53:15	13.3	11.1	-0.2	190.8	0.99	0.5	0.6	-0.004
RUN 3_000721.LAB	1/31/24	12:54:18	13.1	11.0	-0.2	190.9	0.99	0.4	0.5	-0.003
RUN 3_000722.LAB	1/31/24	12:55:21	13.2	11.1	-0.2	190.9	0.99	0.4	0.5	-0.004
									0.5	-0.004

Effluent Spike Using Analyte

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Dilution Factor	Recovery % HCN
POST RUN 3 SPIKE_000733.LAB	1/31/24	12:57:22	11.9	10.0	-0.2	190.9	0.99	0.5	5.0	0.475	0.098	93.9%
POST RUN 3 SPIKE_000734.LAB	1/31/24	12:57:30	11.8	10.0	-0.2	190.9	0.99	0.2	5.1	0.477	0.099	95.1%
POST RUN 3 SPIKE_000735.LAB	1/31/24	12:57:38	11.8	10.0	-0.2	190.9	0.99	0.4	4.8	0.471	0.098	89.9%
POST RUN 3 SPIKE_000736.LAB	1/31/24	12:57:45	11.8	10.0	-0.2	190.9	0.99	0.0	4.9	0.472	0.098	92.9%
POST RUN 3 SPIKE_000737.LAB	1/31/24	12:57:54	11.8	10.1	-0.1	190.9	0.99	0.5	5.0	0.476	0.099	93.3%
POST RUN 3 SPIKE_000738.LAB	1/31/24	12:58:01	11.9	10.1	-0.2	190.9	0.99	0.6	5.5	0.462	0.096	105.0%
POST RUN 3 SPIKE_000739.LAB	1/31/24	12:58:09	11.8	10.1	-0.1	190.9	0.99	0.5	5.2	0.468	0.097	98.3%
POST RUN 3 SPIKE_000740.LAB	1/31/24	12:58:17	11.8	9.9	-0.3	190.9	0.99	0.3	5.2	0.465	0.096	99.4%

CTS, System Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
POST RUN 3 CTS_000747.LAB	1/31/24	12:59:34	0.1	0.1	0.0	190.7	0.99	96.8	-0.5	-0.009	99.7%
POST RUN 3 CTS_000748.LAB	1/31/24	12:59:42	0.1	0.0	0.0	190.7	0.99	97.0	-0.4	-0.005	99.8%
POST RUN 3 CTS_000749.LAB	1/31/24	12:59:50	0.0	0.0	0.1	190.8	0.99	97.1	-0.7	-0.017	100.0%
POST RUN 3 CTS_000750.LAB	1/31/24	12:59:57	0.0	0.0	0.0	190.8	0.99	97.2	-0.4	-0.027	100.1%
POST RUN 3 CTS_000751.LAB	1/31/24	13:00:05	0.0	0.0	0.1	190.8	0.99	97.4	-0.5	-0.006	100.3%
POST RUN 3 CTS_000752.LAB	1/31/24	13:00:14	0.0	0.0	-0.1	190.8	0.99	97.1	-0.5	-0.014	100.0%
POST RUN 3 CTS_000753.LAB	1/31/24	13:00:21	0.0	0.0	0.0	190.8	0.99	97.2	-0.9	-0.016	100.1%
POST RUN 3 CTS_000754.LAB	1/31/24	13:00:29	0.0	0.0	0.0	190.8	0.99	97.1	-0.5	-0.017	100.0%

Client: Holcim (US) Inc.
Facility: Ravenna Cement Plant
Project #: M234506
Operating Condition: Mill Off

Test Location: Kiln 3 Common Stack
Date: 1/31/2024
Operator: A. Benninghoff
FTIR s/n: 612

Post Test CTS, Direct Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet	Recovery % Ethylene
POST RUN 3 CTS DIRECT_000777.LAB	1/31/24	13:05:42	0.0	0.0	-0.1	190.8	0.99	97.7	-0.5	-0.022	100.6%
POST RUN 3 CTS DIRECT_000778.LAB	1/31/24	13:05:50	0.0	0.0	0.0	190.8	0.99	97.6	-1.2	-0.017	100.5%
POST RUN 3 CTS DIRECT_000779.LAB	1/31/24	13:05:58	0.0	0.0	-0.2	190.8	0.99	97.7	-1.3	-0.004	100.6%
POST RUN 3 CTS DIRECT_000780.LAB	1/31/24	13:06:06	0.0	0.0	0.0	190.8	0.99	97.6	-0.2	-0.013	100.6%
POST RUN 3 CTS DIRECT_000781.LAB	1/31/24	13:06:13	0.0	0.0	-0.1	190.8	0.99	97.7	-0.7	-0.007	100.6%
POST RUN 3 CTS DIRECT_000782.LAB	1/31/24	13:06:21	-0.1	0.0	-0.1	190.9	0.99	97.5	-0.6	-0.015	100.4%
POST RUN 3 CTS DIRECT_000783.LAB	1/31/24	13:06:29	-0.1	0.0	0.0	190.9	0.99	97.8	-0.9	-0.012	100.7%
POST RUN 3 CTS DIRECT_000784.LAB	1/31/24	13:06:37	-0.1	0.0	0.0	190.8	0.99	97.7	-0.7	-0.013	100.6%
Average								97.7			

Post Test N2, Direct Purge

Spectrum	Date	Time	H2O% %v	CO2 %v wet	HF ppmv wet	FTIR Gas Cell Temperature deg C	FTIR Gas Cell Pressure atm	Ethylene ppmv wet	HCN ppmv wet	SF6 ppmv wet
128 SCAN N2_000786.LAB	1/31/24	13:12:09	-0.1	0.0	0.0	190.7	0.99	0.1	-0.8	0.001
128 SCAN N2_000787.LAB	1/31/24	13:14:15	-0.1	0.0	0.0	190.7	0.99	0.0	-0.9	0.001
128 SCAN N2_000788.LAB	1/31/24	13:16:20	-0.1	0.0	0.0	190.8	0.99	0.0	-0.8	-0.001

Appendix H - Gas Cylinder Certifications

CERTIFICATE OF ANALYSIS

Grade of Product: EPA PROTOCOL STANDARD

Part Number:	E02NI88E15A3424	Reference Number:	54-402837999-1
Cylinder Number:	CC400459	Cylinder Volume:	146.0 CF
Laboratory:	124 - Chicago (SAP) - IL	Cylinder Pressure:	2015 PSIG
PGVP Number:	B12023	Valve Outlet:	590
Gas Code:	O2,BALN	Certification Date:	Sep 12, 2023

Expiration Date: Sep 12, 2031

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a mole/mole basis unless otherwise noted. The results relate only to the items tested. The report shall not be reproduced except in full without approval of the laboratory. Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS

Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
OXYGEN	12.00 %	11.92 %	G1	+/- 0.5% NIST Traceable	09/12/2023
NITROGEN	Balance				

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
NTRM	11060620	CC340439	14.93 % OXYGEN/NITROGEN	+/- 0.2%	Nov 02, 2028

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
O2-1 HORIBA MPA-510 3VUYL9NR	Paramagnetic	Aug 31, 2023

Triad Data Available Upon Request



Signature on file

Project No. M20230901
Main Kiln Stack

124 of 128

©Mostardi P Page 1 of 1

CERTIFICATE OF ANALYSIS

Grade of Product: PRIMARY STANDARD

Part Number:	X02NI99P15AD524	Reference Number:	141-402876934-1
Cylinder Number:	CC497358	Cylinder Volume:	144.4 CF
Laboratory:	124 - Stryker (SAP) - OH	Cylinder Pressure:	2015 PSIG
Analysis Date:	Oct 24, 2023	Valve Outlet:	350
Lot Number:	141-402876934-1		

Expiration Date: Oct 24, 2031

Primary Standard Gas Mixtures are traceable to N.I.S.T. weights and/or N.I.S.T. Gas Mixture reference materials.

ANALYTICAL RESULTS

Component	Req Conc	Actual Concentration (Mole %)	Analytical Uncertainty
ETHYLENE	100.0 PPM	99.99 PPM	+/- 1%
NITROGEN	Balance		



Signature on file

CERTIFICATE OF ANALYSIS

Grade of Product: CERTIFIED STANDARD-SPEC

Customer:	MOSTARDI PLATT	Reference Number:	160-402841763-1
Part Number:	X03NI99C15AC0W8	Cylinder Volume:	144.4 CF
Cylinder Number:	CC768249	Cylinder Pressure:	2015 PSIG
Laboratory:	124 - Plumsteadville - PA	Valve Outlet:	350SS
Analysis Date:	Sep 11, 2023		
Lot Number:	160-402841763-1		

Expiration Date: Mar 11, 2024

Product composition verified by direct comparison to calibration standards traceable to N.I.S.T. weights and/or N.I.S.T. Gas Mixture reference materials.

ANALYTICAL RESULTS

Component	Req Conc	Actual Concentration (Mole %)	Analytical Uncertainty
SULFUR HEXAFLUORIDE	5.000 PPM	5.022 PPM	+/- 5%
HYDROGEN CYANIDE	50.00 PPM	49.72 PPM	+/- 5%
NITROGEN	Balance		



Signature on file

CERTIFICATE OF ANALYSIS

Grade of Product: EPA PROTOCOL STANDARD

Part Number:	E02NI78E15A0124	Reference Number:	54-402139852-1
Cylinder Number:	EB0061546	Cylinder Volume:	146.3 CF
Laboratory:	124 - Chicago (SAP) - IL	Cylinder Pressure:	2015 PSIG
PGVP Number:	B12021	Valve Outlet:	590
Gas Code:	O2,BALN	Certification Date:	Jun 22, 2021

Expiration Date: Jun 22, 2029

Certification performed in accordance with "EPA Traceability Protocol for Assay and Certification of Gaseous Calibration Standards (May 2012)" document EPA 600/R-12/531, using the assay procedures listed. Analytical Methodology does not require correction for analytical interference. This cylinder has a total analytical uncertainty as stated below with a confidence level of 95%. There are no significant impurities which affect the use of this calibration mixture. All concentrations are on a mole/mole basis unless otherwise noted. The results relate only to the items tested. The report shall not be reproduced except in full without approval of the laboratory. Do Not Use This Cylinder below 100 psig, i.e. 0.7 megapascals.

ANALYTICAL RESULTS

Component	Requested Concentration	Actual Concentration	Protocol Method	Total Relative Uncertainty	Assay Dates
OXYGEN	22.00 %	22.57 %	G1	+/- 1.0% NIST Traceable	06/22/2021
NITROGEN	Balance				

CALIBRATION STANDARDS

Type	Lot ID	Cylinder No	Concentration	Uncertainty	Expiration Date
------	--------	-------------	---------------	-------------	-----------------

ANALYTICAL EQUIPMENT

Instrument/Make/Model	Analytical Principle	Last Multipoint Calibration
O2-1 HORIBA MPA-510 3VUYL9NR	Paramagnetic	Jun 14, 2021

Triad Data Available Upon Request



Signature on file

END OF THE REPORT