

Note: This is a reference cited in AP 42, *Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

13 ~~AW~~
ESS
Truck & Bus Group
Fort Wayne Assembly
General Motors Corporation
12200 Lafayette Center Road
Roanoke, Indiana 46783-9668

March 17, 1993

CERTIFIED MAIL P 360 683 547
RETURN RECEIPT REQUESTED

Mr. Ed Surla, Chief
Enforcement Section
Office of Air Management
Indiana Department of Environmental Management
105 South Meridian Street
P. O. Box 6015
Indianapolis, Indiana 46225-6015

RECEIVED
MAR 23 1993

State of Indiana
Department of Environmental Management
Office of Air Management

Dear Mr. Surla:

General Motors Fort Wayne Assembly Plant located at 12200 Lafayette Center Road, Roanoke, Indiana, is submitting results of compliance stack testing pursuant to 40 CFR 60.8 and continuous emissions monitor and opacity monitor certification pursuant to 40 CFR 60.13. Testing was conducted on February 2 and February 3, 1993, for natural gas/oil-fired boiler #4.

Please contact me at (219) 673-2480 should you have questions relative to the test results.

Sincerely,

Kim Kurtz-Seslar

Kim Kurtz-Seslar
Environmental Engineer

219-673-2505

#4TSTRLT/kks



Clean Air Engineering

500 W. Wood St. • Palatine, IL 60067 • 708-991-3300

RECEIVED

MAR 23 1993

State of Indiana
Department of Environmental Management
Office of Air Management


**REPORT ON
COMPLIANCE TESTING
Including Continuous Emissions Monitor and
Continuous Opacity Monitor Certification**

**Performed for:
GENERAL MOTORS CORPORATION
NORTH AMERICAN TRUCK PLATFORMS
FORT WAYNE ASSEMBLY PLANT
ROANOKE, INDIANA**

**CAE Project No: 6520
March 16, 1993**

CONTENTS

1. SUMMARY	
INTRODUCTION	1-1
SUMMARY OF TEST RESULTS	1-2
Table 1 - RATA, Carbon Dioxide	1-3
Table 2 - RATA, Nitrogen Oxides	1-4
Table 3 - EPA Method 7E, Nitrogen Oxides, Natural Gas	1-5
Table 4 - EPA Methods 7E and 9, Nitrogen Oxides and Opacity, Oil	1-6
2. DESCRIPTION OF INSTALLATION	2-1
3. SUMMARY OF PROCEDURES	
SAMPLING PROCEDURES	3-1
Figure 1 - EPA Methods 1 and 2 Sampling Apparatus	3-3
Figure 2 - EPA Method 3 Sampling Apparatus	3-4
Figure 3 - EPA Method 4 Sampling Apparatus	3-5
Figure 4 - EPA Method 7E Sampling Apparatus	3-6
Figure 5 - RATA Sampling Point Locations	3-7
Figure 6 - Velocity Traverse Point Locations	3-8
ANALYTICAL PROCEDURES	3-9
EPA Method 7E	3-9
QUALITY CONTROL PROCEDURES	3-9
4. COMMENTS	4-1
5. APPENDIX	
NOMENCLATURE	5-1
SAMPLE CALCULATIONS	5-2
PARAMETERS	5-3
CALIBRATION DATA	5-4
FIELD DATA	5-5
MONITOR DATA	5-6
PERTINENT CERTIFICATIONS	5-7
6. CONTINUOUS EMISSIONS MONITOR CERTIFICATION.....	6-1
7. CONTINUOUS OPACITY MONITOR CERTIFICATION.....	7-1



SUMMARY

1-1

INTRODUCTION

Clean Air Engineering was contracted by General Motors Corporation to perform monitor certification testing and to determine levels of nitrogen oxides and visible emissions at their facility located in Roanoke, Indiana for compliance purposes.

The testing took place at the Boiler #4 Stack on February 2 and 3, 1993.
Coordinating the field testing were:

219-673-2480 B. Smid - General Motors Corporation
K. Kurtz-Seslar - General Motors Corporation
G. Santorilla - General Motors Corporation
S. Bailey - pH Environmental Service
J. Bojan - Clean Air Engineering

To the best of our knowledge, the data presented in this report are accurate and complete.

Respectfully submitted,

CLEAN AIR ENGINEERING



Patrick Sheehy
Project Manager



David Perkins
Manager, Technical Communications



SUMMARY OF TEST RESULTS

1-2

Relative Accuracy

The carbon dioxide monitor at the Boiler #4 Stack demonstrated a relative accuracy of 5.0 percent based on CO₂ (percent, wet) over nine runs on February 2, 1993.

The nitrogen oxides monitor at the Boiler #4 Stack demonstrated a relative accuracy of 8.2 percent based on lb/mmBtu NO_x over nine runs on February 2, 1993.

Nitrogen Oxides


The nitrogen oxides concentration at the Boiler #4 Stack averaged 64 ppm over three runs on February 2, 1993. This corresponds to an average emission rate of 20.35 lb/hr and 0.087 lb/mmBtu. Natural gas was used as fuel during these three runs.

The nitrogen oxides concentration at the Boiler #4 Stack averaged 71 ppm over three runs on February 3, 1993. This corresponds to an average emission rate of 22.49 lb/hr and 0.094 lb/mmBtu. No. 2 Fuel Oil was used as fuel for these three runs.

Opacity

The opacity at the Boiler #4 Stack ranged from 0 percent to 10 percent, and averaged 5 percent over three runs on February 3, 1993.

The test conditions and results of analysis are presented in Tables 1 through 4 on pages 1-3 through 1-6.




SUMMARY OF TEST RESULTS Table 1

1-3


**EPA Method 3
Carbon Dioxide, Relative Accuracy
Boiler #4 Stack**

Run No.	Start Time	CO2 RM (percent, wet)	CO2 CEM (percent, wet)	Difference (percent, wet)
1 *	10:00 AM	7.5	8.5	-1.0
2 *	10:30 AM	7.6	8.4	-0.8
3	11:45 AM	7.8	8.3	-0.5
4 *	12:15 PM	7.7	8.3	-0.6
5	12:45 PM	7.7	8.2	-0.5
6	1:15 PM	7.8	7.8	0.0
7	1:45 PM	7.8	7.8	0.0
8	2:30 PM	7.5	7.8	-0.3
9	3:00 PM	7.5	7.8	-0.3
10	3:30 PM	7.6	7.8	-0.2
11	4:00 PM	7.6	7.8	-0.2
12	4:30 PM	7.6	7.7	-0.1
Average		7.7	7.9	-0.2
Total		68.9	71.0	-2.1

Standard Deviation 0.1898
Confidence Coefficient 0.1459
Relative Accuracy 5.0%




RM = Reference Method (Clean Air Engineering Data)
CEM = Continuous Emissions Monitoring Method (General Motors Corporation.)
* Indicates that the run was not included in the calculations.




SUMMARY OF TEST RESULTS - Table 2

**EPA Method 7E
Nitrogen Oxides, Relative Accuracy
Boiler #4 Stack**

Run No.	Start Time	NOx RM (lb/mmBtu)	NOx CEM (lb/mmBtu)	Difference (lb/mmBtu)
1 *	12:25	0.091	0.073	0.018
2 *	13:35	0.084	0.074	0.010
3	14:45	0.085	0.076	0.009
4 *	16:20	0.087	0.077	0.010
5	16:47	0.086	0.078	0.008
6	17:48	0.082	0.079	0.003
7	18:17	0.081	0.081	0.000
8	18:44	0.084	0.081	0.003
9	19:11	0.085	0.079	0.006
10	19:40	0.085	0.079	0.006
11	20:06	0.085	0.080	0.005
12	20:35	0.082	0.081	0.001
Average		0.084	0.079	0.005
Total		0.755	0.714	0.041
Standard Deviation		0.0030		
Confidence Coefficient		0.0023		
Relative Accuracy		8.2%		



RM = Reference Method (Clean Air Engineering Data)
CEM = Continuous Emissions Monitoring Method (General Motors Corporation.)
* Indicates that the run was not included in the calculations.




SUMMARY OF TEST RESULTS - Table 3

1-5

EPA Method 7E
Nitrogen Oxides
Boiler #4 Stack, Natural Gas, Compliance Runs

Run No.	1	2	3	Average
Date (1993)	February 2	February 2	February 2	
Start Time (approx.)	12:25	13:35	14:45	
Stop Time (approx.)	13:25	14:35	15:45	
<u>Gas Conditions</u>				
Temperature (° F)	362	363	363	363
Moisture (volume %)	15.4	16.9	15.2	15.8
O ₂ (dry volume %)	4.8	4.2	4.6	4.5
CO ₂ (dry volume %)	8.9	9.2	9.2	9.1
<u>Volumetric Flow Rate</u>				
acfm	84,060	83,930	84,040	84,010
dscfm	45,060	44,150	45,050	44,750
<u>Nitrogen Oxides Results</u>				
ppm	65	63	63	64
lb/dscf	7.76E-06	7.47E-06	7.50E-06	7.58E-06
lb/hr	20.99	19.80	20.27	20.35
lb/mmBtu	0.091	0.084	0.085	0.087



SUMMARY OF TEST RESULTS - Table 1

**EPA Methods 7E and 9
Nitrogen Oxides and Opacity
Boiler #4 Stack, No. 2 Fuel Oil, Compliance Runs**

Run No.	1	2	3	Average
Date (1993)	February 3	February 3	February 3	
Start Time (approx.)	9:36	10:47	11:58	
Stop Time (approx.)	10:36	11:47	12:58	
<u>Gas Conditions</u>				
Temperature (° F)	370	375	374	373
Moisture (volume %)	12.5	12.6	11.8	12.3
O ₂ (dry volume %)	3.4	3.6	3.2	3.4
CO ₂ (dry volume %)	12.6	13.0	12.8	12.8
<u>Volumetric Flow Rate</u>				
acfm	80,550	81,680	81,210	81,150
dscfm	44,000	44,280	44,490	44,260
<u>Nitrogen Oxides Results</u>				
ppm	76	69	68	71
lb/dscf	9.04E-06	8.29E-06	8.08E-06	8.47E-06
lb/hr	23.88	22.04	21.56	22.49
lb/mmBtu	0.102	0.091	0.090	0.094
<u>Opacity</u>				
Minimum Reading	0	0	0	0
Maximum Reading	10	5	10	10
Average	5	5	5	5




DESCRIPTION OF INSTALLATION

General Motors Corporation's North American Truck Platforms Fort Wayne Assembly Plant, located in Roanoke, Indiana, assembles light-duty pickup trucks. GM operates a Riley Stoker boiler designated as Boiler #4. It is rated at 200,000 lbs steam per hour, and can run on natural gas or No. 2 fuel oil. The boiler uses flue gas recirculation and is vented through one of three flues in a radial brick chimney. A Lear Siegler In-Situ Continuous Emissions Monitor is installed on a flare within the stack. It reads on a wet basis with carbon dioxide as the diluent gas.

The testing reported in this document was performed at the Boiler #4 Stack.

A schematic of the process is shown below.



SUMMARY OF PROCEDURES

3-1

SAMPLING PROCEDURES

The sampling followed procedures as detailed in U.S. Environmental Protection Agency (EPA) Methods 1, 2, 3, 4, 7E and 9. These methods are titled:

- Method 1 — "Sample and Velocity Traverses for Stationary Sources;"
- Method 2 — "Determination of Stack Gas Velocity and Volumetric Flow Rate (Type S Pitot Tube);"
- Method 3 — "Gas Analysis for the Determination of Dry Molecular Weight;"
- Method 4 — "Determination of Moisture Content in Stack Gases;"
- Method 7E - "Determination of Nitrogen Oxides Emissions from Stationary Sources (Instrumental Analyzer Procedure);"
- Method 9 — "Visual Determination of the Opacity of Emissions from Stationary Sources."

These methods appear in detail in Title 40 of the Code of Federal Regulations (CFR), Part 60, Appendix A.

Referenced with the above methods was U.S. EPA Performance Specification 2. This specification is titled: "Specifications and test procedures for SO₂ and NO_x continuous emission monitoring systems in stationary sources."

This specification appears in detail in Title 40 of the CFR, Part 60, Appendix B.

The sampling apparatus are shown in Figures 1 through 3 on pages 3-3 through 3-5. All equipment was calibrated at the Clean Air Engineering laboratory prior to shipment to the job site.



SUMMARY OF PROCEDURES (Continued)

3-2

Sampling Locations

The Boiler #4 Stack has four ports, two of which were traversed. Six points were traversed in each port. The traverse point locations are shown in Figure 5 on page 3-7. The first three runs of the RATA performed on February 2, 1993 at the Boiler #4 Stack were 60 minutes in duration. These runs, in addition to the runs performed on February 3, 1993, were used to determine compliance with emissions standards.


For relative accuracy testing, three points were sampled in a single port of the Boiler #4 Stack. The sampling time per point was seven minutes for a total sampling time of 21 minutes. The sampling locations are shown in Figure 4 on page 3-6.



SUMMARY OF PROCEDURES - Figure 1

3-3


The EPA Methods 1 and 2 sampling apparatus is shown.



SUMMARY OF PROCEDURES - Figure 2

3-4

The EPA Methods 3 and 4 sampling apparatus is shown.




Impinger Contents

- 1) 100 ml distilled water
- 2) 100 ml distilled water
- 3) empty
- 4) 300 g silica gel

SUMMARY OF PROCEDURES - Figure 3

The EPA Method 7E sampling apparatus is shown.


3-5



SUMMARY OF PROCEDURES - Figure 4

3-6


The cross section of the Boiler #4 Stack shows RATA sampling point locations.



SUMMARY OF PROCEDURES - Figure 5

The cross section of the Boiler #4 Stack shows traverse point locations.

3-7



<u>TRAVERSE POINT</u>	<u>PORT TO POINT DISTANCE (IN)</u>
1	65.0
2	58.0
3	47.9
4	20.1
5	10.0
6	3.0

SUMMARY OF PROCEDURES

3-8

ANALYTICAL PROCEDURES

Continuous Emissions Monitoring

Nitrogen Oxides

The nitrogen oxides emission rate was determined using procedures detailed in EPA Method 7E. A sample was extracted continuously from the flue gas stream, and a portion was conveyed to a TECO chemiluminescent nitrogen oxides analyzer.

Before and after each run, the monitor was zeroed and calibrated with a certified calibration gas. These calibrations were used to correct the raw data for zero and calibration drift occurring during the test runs.

QUALITY CONTROL PROCEDURES

Quality control procedures for all aspects of field sampling; sample preservation and holding time; reagent quality; analytical method; analyst training and safety; and instrument cleaning, calibration and safety were followed. These procedures are generally consistent with EPA guidelines documented in "Quality Assurance Manuals for Air Pollution Measurement Systems," Vol 3, "Stationary Source Specific Methods" (EPA-600/4-77-027b).



COMMENTS

The times on the reference method data were ten minutes ahead of the plant CEM data.

No other deviations from standard U.S. EPA testing procedures were noted.

The S-Type Pitot was visually inspected before use and it was determined that no calibration was needed.

4-1



APPENDIX

NOMENCLATURE	5-1
SAMPLE CALCULATIONS	5-2
PARAMETERS	5-3
CALIBRATION DATA	5-4
FIELD DATA	5-5
MONITOR DATA	5-6
PERTINENT CERTIFICATIONS	5-7

GENERAL MOTORS CORPORATION
CAE Project No: 6520

NOMENCLATURE

5-1

Nomenclature

A	-	absorbance
A _n	-	cross sectional area of nozzle (ft ²)
A _s	-	cross sectional area of stack (ft ²)
B _{wo}	-	proportion of water vapor in the gas stream by volume
B _{ws}	-	proportion of water vapor in the gas stream by volume at saturated conditions
C _p	-	pitot tube coefficient (dimensionless)
D _f	-	dilution factor
F _d	-	ratio of dry gas generated to gross calories (dscf/MBtu)
F _c	-	ratio of gas generated
GCV	-	gross calorific value of fuel (Btu/lb)
$\overline{DH}$	-	average pressure drop across meter box orifice (in. H ₂ O)
$\sqrt{DP}$	-	average square roots of velocity heads of stack gas ($\sqrt{\text{in. H}_2\text{O}}$)
DH@	-	meter orifice calibration coefficient (in. H ₂ O)
%I	-	percent of isokinetic sampling (acceptable: $90 \leq \%I \leq 110\%$)
K _p	-	pitot tube constant: $85.49 \text{ (ft/sec)} \frac{\sqrt{(\text{lb/lb-mole})(\text{in. Hg})}}{\sqrt{(^{\circ}\text{R})(\text{in. H}_2\text{O})}}$
K _c	-	spectrophotometer calibration factor
M _d	-	dry molecular weight of stack gas (lb/lb-mole)
M _s	-	molecular weight of stack gas, wet basis (lb/lb-mole)
M _n	-	total amount of particulate matter collected (gm)
mmBtu	-	millions of British Thermal Units (Btu)
N	-	normality of titrant (meq/ml)
P _b	-	barometric pressure (in. Hg)
P _f	-	final absolute pressure of flask (in. Hg)
P _i	-	initial absolute pressure of flask (in. Hg)
P _s	-	absolute stack gas pressure (in. Hg)
Q _a	-	volumetric flow rate, actual conditions
Q _{std}	-	volumetric flow rate, standard conditions, dry basis
std	-	standard conditions, 29.92 in. Hg, 68°F
T _f	-	final absolute temperature of flask (°R)
T _i	-	initial temperature of flask (°R)

T_m	-	average dry gas meter temperature ($^{\circ}\text{F}$)
T_s	-	average stack temperature ($^{\circ}\text{F}$)
T_{std}	-	absolute temperature, standard conditions (528°R)
Q	-	total sampling time (min)
V_a	-	volume of aliquot (ml)
V_f	-	volume of flask (ml)
V_{lc}	-	total volume of liquid collected in impingers and silica gel (ml)
V_m	-	volume of gas sample through the dry gas meter at meter conditions (ft^3)
V_{mstd}	-	volume of gas sample through the dry gas meter, standard conditions (ft^3)
V_{sc}	-	volume of flask sample, standard conditions (ml)
V_{soln}	-	total volume of solution (ml)
V_t	-	volume of titrant used to titrate aliquot (ml)
V_{tb}	-	volume of titrant used to titrate blank (ml)
V_{wstd}	-	volume of water collected, standard conditions (ft^3)
V_s	-	stack gas velocity (ft/sec)
Y_d	-	gas meter correction factor (dimensionless)

Nomenclature

CAL GAS	actual concentration of the upscale calibration gas
CAL I	initial system calibration bias check response for the upscale calibration gas, ppm
CAL F	final system calibration bias check response for the upscale calibration gas, ppm
ZERO I	initial system calibration bias check response for the zero gas, ppm
ZERO F	final system calibration bias check response for the zero gas, ppm
ppm	measured concentration as parts per million in the gas stream
ppm (drift calibrated)	concentration calibrated for drift as per Eq. 6C-1 of EPA Method 6C
DRE	destruction removal efficiency

GENERAL MOTORS CORPORATION
CAE Project No: 6520

SAMPLE CALCULATIONS

5-2

SAMPLE CALCULATIONS - RUN 1, BOILER #4 STACK
(Note: results are taken from computer analysis)

1. Volume of water collected

$$\begin{aligned}V_{\text{wstd}} &= (0.04707 \text{ ft}^3/\text{ml}) (V_{\text{lc}}) \\&= (0.04707) (117) \\&= 5.507 \text{ wscf}\end{aligned}$$

2. Volume of gas metered, standard conditions

$$\begin{aligned}V_{\text{mstd}} &= \frac{(17.64 \text{ }^\circ\text{R}/\text{in. Hg}) (V_{\text{m}}) \left[P_{\text{b}} + \frac{\text{DH}}{13.6} \right] (Y_{\text{d}})}{(460 + T_{\text{m}})} \\&= \frac{(17.64) (32.08) \left[29.56 + \frac{1.0}{13.6} \right] (1.0054)}{(460 + 96)} \\&= 30.34 \text{ dscf}\end{aligned}$$

3. Stack pressure (in. Hg)

$$\begin{aligned}P_{\text{s}} &= P_{\text{b}} + \left(\frac{\text{STATIC P}}{13.6} \right) \\&= 29.56 + \left(\frac{-0.65}{13.6} \right) \\&= 29.51\end{aligned}$$

4. Moisture content

$$\begin{aligned}B_{\text{wo}} &= \frac{V_{\text{wstd}}}{V_{\text{mstd}} + V_{\text{wstd}}} \\&= \frac{5.507}{30.34 + 5.507} \\&= 0.1536 \\&= 15.4 \%\end{aligned}$$

5. Molecular weight of dry gas stream (lb/lb mole)

$$\begin{aligned}M_{\text{d}} &= 0.44(\% \text{CO}_2) + 0.32(\% \text{O}_2) + 0.28(\% \text{CO} + \% \text{N}_2) \\&= 0.44(8.9) + 0.32(4.8) + 0.28(86.3) \\&= 29.61\end{aligned}$$

6. Molecular weight of stack gas (lb/lb mole)

$$\begin{aligned}M_{\text{s}} &= M_{\text{d}} (1 - B_{\text{wo}}) + 18(B_{\text{wo}}) \\&= 29.61 (1 - 0.1536) + 18(0.1536) \\&= 27.83\end{aligned}$$

SAMPLE CALCULATIONS (Continued)

7. Velocity of stack gas

$$\begin{aligned}V_s &= K_p C_p (DP)^{\frac{1}{2}} \frac{[T_s + 460]^{\frac{1}{2}}}{[(M_s) (P_s)]^{\frac{1}{2}}} \\&= 85.49 (0.84) (0.774) \frac{[362 + 460]^{\frac{1}{2}}}{[(27.83) (29.51)]^{\frac{1}{2}}} \\&= 55.59 \text{ ft/sec}\end{aligned}$$

8. Total flow of stack gas

$$\begin{aligned}Q_a &= (60) (A_s) (V_s) \\&= (60) (25.2) (55.59) \\&= 84,060 \text{ acfm}\end{aligned}$$

$$\begin{aligned}Q_{std} &= \frac{Q_a P_s (17.64^\circ \text{R/in. Hg}) (1 - B_{wo})}{T_s + 460} \\&= \frac{(84,060) (29.51) (17.64) (1 - 0.1536)}{362 + 460} \\&= 45,060 \text{ dscfm}\end{aligned}$$

9. Carbon Dioxide

$$\begin{aligned}\% \text{CO}_2 \text{ wet} &= (\% \text{CO}_2 \text{ dry}) (1 - B_{wo}) \\&= (8.9) (1 - 0.1536) \\&= 7.5\end{aligned}$$

SAMPLE CALCULATIONS (Continued)

10. Method 7E - Nitrogen Oxides

$$\begin{aligned}\text{ppm}_{\text{drift calibrated}} &= (C_{\text{avg}} - C_o) \frac{C_{\text{ma}}}{(C_m - C_o)} \\ &= (65 - (-0.2)) \frac{211.9}{(212.3 - (-0.2))} \\ &= 65\end{aligned}$$

- C_{avg} = Average gas concentration indicated by gas analyzer, dry basis, ppm.
 C_o = Average of initial and final system calibration bias check responses for the zero gas, ppm.
 C_m = Average of initial and final system calibration bias check responses for upscale calibration gas, ppm.
 C_{ma} = Actual concentration of the upscale calibration gas, ppm.

$$\begin{aligned}\text{lb/dscf} &= \left(\frac{(\text{ppm}_{\text{drift calibrated}}) (\text{MW})}{385.3 \times 10^6} \right) \\ &= \left(\frac{(65) (46)}{385.3 \times 10^6} \right) \\ &= 7.76 \times 10^{-6}\end{aligned}$$

$$\begin{aligned}\text{lb/hr} &= (\text{lb/dscf})(\text{dscfm})(60) \\ &= (7.76 \times 10^{-6})(45,060)(60) \\ &= 20.99\end{aligned}$$

$$\begin{aligned}\text{lb/mmBtu} &= \frac{(\text{lb/dscf})(F_c)(100)}{\% \text{ CO}_2, \text{ dry}} \\ &= \frac{(7.76 \times 10^{-6})(1,040^*)(100)}{8.9} \\ &= 0.091\end{aligned}$$

* 1,040 is the standard F_c factor for natural gas.

SAMPLE CALCULATIONS (Continued)

11. Standard deviation of difference between NOx lb/MBtu monitor and NOx lb/MBtu reference method

$$\begin{aligned} \text{Sdev} &= \sqrt{\frac{\sum_{i=1}^n d_i^2 - \frac{(\sum_{i=1}^n d_i)^2}{n}}{n-1}} \\ &= \sqrt{\frac{0.000261 - \frac{0.001681}{9}}{9-1}} \\ &= 0.0030 \end{aligned}$$

$\sum_{i=1}^n d_i^2$ = sum of difference squared
 $\sum_{i=1}^n d_i$ = sum of differences
 n = number of data sets

12. Confidence coefficient

$$\begin{aligned} \text{cc} &= (t_{0.975}) \left(\frac{\text{Sdev}}{\sqrt{n}} \right) \\ &= (2.306) \left(\frac{0.0030}{\sqrt{9}} \right) \\ &= 0.0023 \end{aligned}$$

$t_{0.975}$ = t-value (see table)

<u>n</u>	<u>$t_{0.975}$ value</u>	<u>n</u>	<u>$t_{0.975}$ value</u>	<u>n</u>	<u>$t_{0.975}$ value</u>
2	12.706	7	2.447	12	2.201
3	4.303	8	2.365	13	2.179
4	3.182	9	2.306	14	2.160
5	2.776	10	2.262	15	2.145
6	2.571	11	2.228	16	2.131

13. Relative accuracy

$$\begin{aligned} \text{RA} &= 100 \left(\frac{|\text{Davg}| + |\text{cc}|}{\text{reference method average or applicable emission standard}} \right) \\ &= 100 \left(\frac{|0.0046| + |0.0023|}{0.084} \right) \\ &= 8.2 \text{ percent} \end{aligned}$$

$|\text{Davg}|$ = absolute value of the mean of the differences
 $|\text{cc}|$ = absolute value of the confidence coefficient

PARAMETERS

GENERAL MOTORS CORPORATION
 CAE Project No: 6520
 Boiler #4 Stack, Natural Gas, Compliance Runs

VELOCITY AND MOISTURE PARAMETERS

Run No.	1	2	3
Date (1993)	February 2	February 2	February 2
Start Time (approx.)	12:23	13:33	14:44
Stop Time (approx.)	13:23	14:34	15:44
O ₂ (dry volume %)	4.8	4.2	4.6
CO ₂ (dry volume %)	8.9	9.2	9.2
Pb	29.56	29.56	29.56
STATIC P	-0.65	-0.65	-0.65
Cp	0.84	0.84	0.84
As	25.2	25.2	25.2
Vlc	117	132	117
Vm	32.08	32.30	32.29
DH	1.00	1.00	1.00
Yd	1.0054	1.0054	1.0054
Tm	96	95	93
Θ	60	60	60

CALCULATED RESULTS

Vwstd	5.507	6.213	5.507
Vmstd	30.34	30.58	30.68
Ps	29.51	29.51	29.51
Ts	362	363	363
Bwo	0.1536	0.1689	0.1522
DP1/2	0.774	0.770	0.774
Md	29.61	29.64	29.66
Ms	27.83	27.67	27.88
Vs	55.59	55.51	55.58
Qa (acfm)	84,060	83,930	84,040
Qstd (dscfm)	45,060	44,150	45,050

GENERAL MOTORS CORPORATION
 CAE Project No: 6520
 Boiler #4 Stack, Natural Gas, RATA Runs

MOISTURE PARAMETERS

Run No's.	4&5	6&7	8&9	10&11	12
Date (1993)	February 2	February 2	February 2	February 2	February 2
Start Time (approx.)	16:18	17:46	18:42	19:40	20:34
Stop Time (approx.)	17:03	18:31	19:27	20:25	20:54
Pb	29.56	29.56	29.56	29.56	29.56
Vlc	119	125	124	116	55
Vm	31.03	31.18	30.95	30.74	15.09
DH	1.50	1.50	1.50	1.50	2.00
Yd	1.0054	1.0054	1.0054	1.0054	1.0054
Tm	95	97	96	97	96

CALCULATED RESULTS

Vwstd	5.60	5.88	5.84	5.46	2.59
Vmstd	29.41	29.45	29.28	29.06	14.30
Bwo	0.1600	0.1665	0.1662	0.1582	0.1533

GENERAL MOTORS CORPORATION
CAE Project No: 6520
Boiler #4 Stack, Natural Gas

CARBON DIOXIDE AND MOISTURE PARAMETERS

Run No.	%CO2 Dry	Bwo	%CO2 wet
1	8.9	0.1536	7.5
2	9.2	0.1689	7.6
3	9.2	0.1522	7.8
4	9.2	0.1600	7.7
5	9.2	0.1600	7.7
6	9.4	0.1665	7.8
7	9.4	0.1665	7.8
8	9.0	0.1662	7.5
9	9.0	0.1662	7.5
10	9.0	0.1582	7.6
11	9.0	0.1582	7.6
12	9.0	0.1533	7.6

GENERAL MOTORS CORPORATION
 CAE Project No: 6520
 Boiler #4 Stack, Natural Gas, Compliance Runs

NITROGEN OXIDES PARAMETERS

RUN NO.	1	2	3
Date (1993)	February 2	February 2	February 2
Start Time (approx)	12:25	13:35	14:45
Stop Time (approx)	13:25	14:35	15:45
%CO2, dry	8.9	9.2	9.2
Fc	1,040	1,040	1,040
dscfm	45,060	44,150	45,050
ZERO I	0.0	-0.4	0.0
CAL I	212.0	212.5	209.0
ZERO F	-0.4	0.0	-0.2
CAL F	212.5	215.0	216.5
ppm	65	63	63
CAL GAS	211.9	211.9	211.9
ppm (drift calibrated)	65	63	63
lb/dscf	7.76E-06	7.47E-06	7.50E-06
lb/hr	20.99	19.80	20.27
lb/mmBtu	0.091	0.084	0.085

GENERAL MOTORS CORPORATION
CAE Project No: 6520
Boiler #4 Stack, Natural Gas, RATA Runs

NITROGEN OXIDES PARAMETERS

RUN NO.	4	5	6	7	8
Date (1993)	February 2	February 2	February 2	February 2	February 2
Start Time (approx)	16:20	16:47	17:48	18:17	18:44
Stop Time (approx)	16:41	17:08	18:09	18:38	19:05
% CO2, dry	9.2	9.2	9.4	9.4	9.0
Fc	1,040	1,040	1,040	1,040	1,040
ZERO I	-0.2	0.0	-0.2	0.0	-0.1
CAL I	209.5	213.5	213.5	210.0	212.0
ZERO F	0.0	-0.2	0.0	-0.2	-0.4
CAL F	213.5	213.5	218.0	212.0	214.0
ppm	64	64	63	61	61
CAL GAS	211.9	211.9	211.9	211.9	211.9
ppm (drift calibrated)	64	64	62	61	61
lb/dscf	7.66E-06	7.59E-06	7.40E-06	7.32E-06	7.27E-06
lb/mmBtu	0.087	0.086	0.082	0.081	0.084

RUN NO.	9	10	11	12
Date (1993)	February 2	February 2	February 2	February 2
Start Time (approx)	19:11	19:40	20:06	20:35
Stop Time (approx)	19:32	20:01	20:27	20:56
% CO2, dry	9.0	9.0	9.0	9.0
Fc	1,040	1,040	1,040	1,040
ZERO I	-0.4	-0.2	-0.2	0.0
CAL I	214.0	215.0	209.0	210.0
ZERO F	-0.2	-0.2	0.0	-0.2
CAL F	215.0	218.0	210.0	209.0
ppm	62	63	61	59
CAL GAS	211.9	211.9	211.9	211.9
ppm (drift calibrated)	61	61	62	60
lb/dscf	7.34E-06	7.32E-06	7.37E-06	7.13E-06
lb/mmBtu	0.085	0.085	0.085	0.082

GENERAL MOTORS CORPORATION

CAE Project No: 6250

Boiler #4 Stack, No. 2 Fuel Oil, Compliance Runs

VELOCITY AND MOISTURE PARAMETERS

Run No.	1	2	3
Date (1993)	February 3	February 3	February 3
Start Time (approx.)	9:36	10:47	11:58
Stop Time (approx.)	10:36	11:47	12:58
O ₂ (dry volume %)	3.4	3.6	3.2
CO ₂ (dry volume %)	12.6	13.0	12.8
Pb	29.41	29.41	29.41
STATIC P	-0.65	-0.65	-0.65
Cp	0.84	0.84	0.84
As	25.2	25.2	25.2
Vlc	90	90	84
Vm	31.53	31.32	31.53
DH	1.0	1.0	1.0
Yd	1.0054	1.0054	1.0054
Tm	94	95	99
Θ	60	60	60

CALCULATED RESULTS

Vwstd	4.236	4.236	3.954
Vmstd	29.78	29.49	29.51
Ps	29.36	29.36	29.36
Ts	370	375	374
Bwo	0.1245	0.1256	0.1181
DP1/2	0.747	0.755	0.752
Md	30.15	30.22	30.18
Ms	28.64	28.69	28.74
Vs	53.27	54.02	53.71
Qa (acfm)	80,550	81,680	81,210
Qstd (dscfm)	44,000	44,280	44,490

GENERAL MOTORS CORPORATION
CAE Project No: 6520
Boiler #4 Stack, No. 2 Fuel Oil, Compliance Runs

NITROGEN OXIDES PARAMETERS

RUN NO.	1	2	3
Date (1993)	February 3	February 3	February 3
Start Time (approx)	9:36	10:47	11:58
Stop Time (approx)	10:36	11:47	12:58
%CO ₂ , dry	12.6	13.0	12.8
Fc	1,420	1,420	1,420
dscfm	44,000	44,280	44,490
ZERO I	0.2	1.0	1.5
CAL I	210.0	213.0	215.0
ZERO F	1.0	1.5	1.0
CAL F	213.0	215.0	212.0
ppm	76	71	69
CAL GAS	211.9	211.9	211.9
ppm (drift calibrated)	76	69	68
lb/dscf	9.04E-06	8.29E-06	8.08E-06
lb/hr	23.88	22.04	21.56
lb/mmBtu	0.102	0.091	0.090

GENERAL MOTORS CORPORATION
 CAE Project No: 6520
 Boiler #4 Stack, No. 2 Fuel Oil
 February 3, 1993
 Run 1, 9:35

Visible Emissions Parameters

	seconds			
	0	5	10	15
	5	10	5	5
	10	5	5	5
	5	5	10	5
	5	10	5	5
	5	10	5	5
	5	10	5	5
	5	5	5	5
	5	10	5	5
	10	5	5	5
	5	5	5	5
	5	10	5	5
	5	5	5	5
	5	5	5	5
	5	10	5	5
	5	5	5	5
	5	5	5	5
	5	5	5	5
	5	5	5	5
	5	5	5	5
	5	5	5	5
	5	5	0	5
	5	5	5	0
	5	5	5	10
	5	5	5	5
	5	5	10	5
	5	5	5	10
	5	5	5	5
	5	5	5	5
	5	5	5	5

minutes

Average

5

	seconds			
	0	5	10	15
	5	5	5	5
	5	5	5	5
	5	10	5	5
	5	5	5	5
	5	5	10	5
	5	5	5	5
	5	5	10	5
	5	5	5	5
	5	5	5	5
	5	5	5	5
	0	5	5	5
	5	5	5	0
	5	5	5	5
	5	5	5	5
	5	5	5	5
	5	5	5	5
	0	0	5	5
	0	5	5	5
	5	5	5	5
	5	0	5	5
	0	0	5	5
	5	0	0	0
	5	5	5	5
	5	5	5	0
	0	5	0	5
	5	5	0	5
	5	5	5	0
	0	5	5	5
	5	5	5	5

minutes

Average

5

Minimum Reading 0
 Maximum Reading 10
 Total Average 5

GENERAL MOTORS CORPORATION
 CAE Project No: 6520
 Boiler #4 Stack, No. 2 Fuel Oil
 February 3, 1993
 Run 2, 10:45

Visible Emissions Parameters

	seconds			
	15	20	45	60
minutes	5	5	5	5
	5	5	5	5
	5	5	5	5
	5	5	0	5
	5	5	5	0
	5	5	5	5
	5	5	5	5
	5	5	0	5
	5	5	5	5
	0	5	5	5
	5	5	0	5
	5	5	5	5
	0	5	5	5
	5	5	5	0
	5	5	5	0
	5	5	5	5
	5	5	5	5
	5	5	0	5
	5	5	0	5
	5	5	0	5
	5	5	5	5
	0	0	5	5
	5	5	5	5
	0	5	0	5
	5	5	0	5
	5	0	5	5

Average

5

	seconds			
	15	20	45	60
minutes	5	5	5	5
	5	5	5	0
	5	5	5	5
	0	0	0	5
	0	5	0	5
	0	0	5	0
	5	0	0	5
	5	5	0	5
	0	5	0	5
	0	5	5	5
	0	5	0	5
	0	0	5	5
	0	0	0	0
	5	5	0	0
	5	0	0	5
	0	5	5	0
	0	5	0	0
	0	0	5	0
	5	0	0	5
	0	5	5	5
	5	5	5	5
	5	0	0	5
	5	5	5	5
	5	5	5	5
	5	5	5	5
	0	5	5	5
	0	5	5	5
	0	5	5	5

Average

5

Minimum Reading 0
 Maximum Reading 5
 Total Average 5

CALIBRATION DATA

1290 COMBERMERE STREET, TROY, MICHIGAN 48064 (313) 689-2950

Customer:

C A E INSTRUMENT RENTAL
246 WOODWORK LANE
PALATINE IL 60067

Our Project # : 539892

Your P.O. # : 6017-71500

Expiration Date : 2-3-94

Cylinder Number : ALM-022594

Cylinder Pressure : 1900 psig

1 of 1 Component(s)

CERTIFICATE OF ANALYSIS - EPA PROTOCOL GASES

PERFORMED ACCORDING TO SECTION 3.0.4

Certified Per Traceability Procedure # 81

Protocol # 1

File # FD-4295

Certified Accuracy 1 % N25 Traceable

INSTRUMENTATION

LAST CALIBRATION DATE

INSTRUMENT/SERIAL #

6-25-92

BECKMAN 950

270-0828798

REFERENCE STD

SRM # (CRM #)	CYLINDER NUMBER	CONC.
1685	ALM-008716	250.3 PPM
1684	ALM-010464	95.25 PPM

ANALYZED CYLINDER

COMPONENT	CERTIFIED CONC.
NITRIC DIOXIDE	135.0 PPM

BALANCE GAS : NITROGEN

NITROGEN DIOXIDE

0.00 PPM (FROM SECOND ANALYSIS)

FIRST ANALYSIS

DATE : 7-27-92

SECOND ANALYSIS

DATE : 9-3-92

TEST GAS (mV)	REFERENCE GAS CONC.	TEST GAS (mV)	RESULTS PPM
0.00	250.3 PPM 100.00	53.90	134.9
0.00	100.00	53.90	134.9
0.00	100.00	53.90	134.9

CALCULATED RESULTS 134.9

AVERAGE : 134.9 PPM

TEST GAS (mV)	REFERENCE GAS CONC.	TEST GAS (mV)	RESULTS PPM
54.00	250.3 PPM 100.00	54.00	135.2
54.00	100.00	54.00	135.2
54.00	100.00	54.00	135.2

CALCULATED RESULTS 135.2

AVERAGE : 135.2 PPM

TEST GAS (mV)	REFERENCE GAS CONC.	TEST GAS (mV)	RESULTS PPM
100.00	250.3 PPM 100.00	100.00	250.3
100.00	100.00	100.00	250.3
100.00	100.00	100.00	250.3

135.2 PPM NDx

ANALYTICAL PRINCIPLE

CHEMILUMINESCENCE

CALIBRATION CURVE 1st DEGREE

SRM # (CRM #)	CONC. PPM	SPLIT PT (%)	DVM (mV)	FITTED VALUE	PERCENT ERROR
1685	250.3	100	100.00	250.3	0.00
1684	95.26	38	38.05	95.24	-0.02
	0.0000	0	0.00	0.0000	0.00
	0	0	0.00	0.00	0.00
	0	0	0.00	0.00	0.00
	0	0	0.0000	0.0000	0.00
	0	0	0.00	0.00	0.00
1685	250.3	HIGH	100.00	250.3	0.00
1684	95.26	LOW	38.05	95.24	-0.02

1 SH19 - GAS MANUFACTURER'S INTERNAL STANDARD

Analyst : L. Dora

Approved By : L. Shapiro

The only liability of this Company for gas which fails to comply with this analysis shall be replacement thereof by the Company without extra cost.

Customer: C A E INSTRUMENT RENTAL 216 WOODWORK LANE PALATINE IL 60067
Our Project #: 539892
Your P.O. #: 6017-71500
Expiration Date: 2-10-94
Cylinder Number: ALM-030328
Cylinder Pressure: 1900 psig
1 of 1 Component(s)

1111 CERTIFICATE OF ANALYSIS - EPA PROTOCOL BASES PERFORMED ACCORDING TO SECTION 3.0.4
Certified For Traceability Procedure # 61
Protocol # 1
File # PO-4296
Certified Accuracy 1% NBS Traceable
INSTRUMENTATION
INSTR/MODEL/SERIAL # 9511
LAST CALIBRATION DATE 6-25-92
ANALYTICAL PRINCIPLE CHERILLUMINESCENCE

FIRST ANALYSIS				SECOND ANALYSIS				DATE: 8-3-92				DATE: 8-10-92			
ANALYZED CYLINDER				REFERENCE STD				REFERENCE				REFERENCE			
COMPONENT	CERTIFIED CONC.	SRM # (CRM #)	CYLINDER NUMBER	CONC.	SRM # (CRM #)	CYLINDER NUMBER	CONC.	ZERO GAS (mV)	TEST GAS (mV)	RESULTS PPM	RESULTS PPM	ZERO GAS (mV)	TEST GAS (mV)	RESULTS PPM	RESULTS PPM
NITRIC OXIDE	211.9 PPM	1685	ALM-099715	250.3 PPM	1685	ALM-099715	250.3 PPM	0.00	84.50	212.3	211.5	0.00	84.50	212.3	211.5
BALANCE GAS: NITROGEN		1684	ALM-010464	95.26 PPM	1684	ALM-010464	95.26 PPM	0.00	84.50	212.3	211.5	0.00	84.50	212.3	211.5
NITROGEN DIOXIDE	0.00 PPM (FROM SECOND ANALYSIS)							0.00	84.50	212.3	211.5	0.00	84.50	212.3	211.5
CALCULATED RESULTS				CALCULATED RESULTS				CALCULATED RESULTS				CALCULATED RESULTS			
212.3				211.5				211.5				211.5			
AVERAGE: 212.3 PPM				AVERAGE: 211.5 PPM				AVERAGE: 211.5 PPM				AVERAGE: 211.5 PPM			

Pyrometer Calibration Data Sheet

Pyrometer #: F-84

Office: PALATINE

Calibrated By: IL

Date: 12-23-92

Recalibration Due: 5-93

Battery Replaced: Yes ☐ No ☒

Calibration Reference Setting	Pyrometer Reading
50°F	50°
100°F	100°
150°F	150°
200°F	200°
250°F	250°
300°F	300°
350°F	351°
400°F	401°
450°F	450°
500°F	501°
550°F	500°
600°F	600°

Calibration Reference Information (from calibration seal on reference)


Reference Used: Digimite Other: _____

Serial Number: 029129

Calibrated By: EIL Date Calibrated: 3-13-92

Calibration Report Number: 350884

A copy of the original
couldn't reach IL



6' Probe Pn10

DATE

9/28/90

PITOT NUMBER

9/28/90-3

TYPE S PITOT TUBE INSPECTION DATA

Pitot tube assembly level? ☒ yes ☐ no

Pitot tube openings damaged? ☐ yes (explain below) ☒ no

$\alpha_1 = 1^\circ (<10^\circ)$, $\alpha_2 = 1^\circ (<10^\circ)$, $\beta_1 = 2^\circ (<5^\circ)$

$\beta_2 = 1^\circ (<5^\circ)$

$\gamma = 2^\circ$, $\epsilon = 1^\circ$, $A = .724$ cm (in.)

$Z = A \sin \gamma = .025$ cm (in.); < 0.32 cm ($< 1/8$ in.),

$W = A \sin \epsilon = .012$ cm (in.); < 0.02 cm ($< 1/32$ in.)

$P_a = .360$ cm (in.) $P_b = .364$ cm (in.)

$P = \frac{(P_a + P_b)}{2} = .362$

$D_t = .250$ cm (in.)

$\frac{P}{D_t} = 1.44$ (> 1.05 and ≤ 1.50)

COMMENTS:

Calibration required? ☒ yes ☐ no

Calibrated by: J-Z

METER BOX FULL TEST CALIBRATION

Date: 1-14-92

Operator: D Rybarski

Meter Box No.: D	Meter Box ΔH@: 19599	Meter Box Yd: 10054	Barometric Pressure: 29.15
------------------	----------------------	---------------------	----------------------------

Standard Meter Gas Volume ft ³				Meter Box Gas Volume ft ³				Std. Meter Temperature °F			Meter Box Temperature °F			Time ₀	Yd	ΔH@		
Q	ΔH	ΔP	Yds	Initial	Final	Vds Net	Initial	Final	Vds Net	In	Out	Tds Avg	In				Out	Tds Avg
36	1.5	-2.0	10000	Ø	5.003	5.003	652.108	652.306	5.198	63	63	63	98	92	95	13.38	10149	1.9166
36	1.5	-2.0	10000	Ø	5.005	5.005	652.306	662.506	5.2	63	63	63	99	93	96	13.41	10167	1.9202
64	1.5	-2.5	10000	Ø	10.006	10.006	665.208	675.712	10.534	63	63	63	104	92	98	15.37	10032	1.8867
64	1.5	-2.5	10000	Ø	10.002	10.002	675.712	686.282	10.54	63	63	63	104	94	99	15.36	10040	1.8824
86	3.0	-3.1	10000	Ø	10.007	10.007	636.446	636.446	10.524	63	63	63	104	90	97	11.40	9972	2.0791
86	3.0	-3.1	10000	Ø	10.008	10.008	636.446	647.017	10.571	63	63	63	106	92	99	11.41	9964	2.0749

Nomenclature

Barometric Pressure
Flow Rate (cfm)
Orifice Pressure Differential ("H₂O)
Inlet Pressure Differential ("H₂O)
Volume Dry Gas Meter (ft³)
Volume Dry Standard (ft³)
Meter Correction Factor (unitless)
Standard Meter Correction Factor (unitless)
Orifice Pressure Differential that gave 0.75 cfm
of air at 70°F and 29.92 "Hg ("H₂O)

Calculations

$$Yd = (Yds) \left[\frac{Vds}{Vd} \right] \left[\frac{Td + 460}{Tds + 460} \right] \left[\frac{Pb + \Delta P/13.6}{Pb + \Delta P/13.6} \right]$$

$$\Delta H@ = \frac{0.0317 \Delta H}{Pb(Td + 460)} \left[\frac{(Tds + 460)^2}{(Vds)(Yds)} \right]$$

$$Q = \frac{17.64 (Vds)(Pb)}{(Tds + 460)0}$$

Vacuum Gauge Calibration

Standard (ftHg)	Vacuum Gauge
5	5.2
10	10.2
15	15.3
20	20.1
25	25.3
27.2	MAX

Thermometer Calibration

Standard	Inlet	Outlet
40	40	40
60	60	60
80	80	80
100	100	100
120	120	120
140	140	140

POST TEST CALIBRATION CHECK

Client/Owner: General Motors Project Number: 6520
 Operator: A. KUBERA Date: 2-9-93

Meter Box No.: <u>D</u>	Meter Box Vacuum: <u>3</u>	Meter Box Yd: <u>1.0054</u>	Barometric Press.: <u>29.44</u>
-------------------------	----------------------------	-----------------------------	---------------------------------

Q	ΔH	ΔP	Yds	Standard Meter Gas Volume ft ³			Meter Box Gas Volume ft ³			Std. Meter Temperature °F			Meter Box Temperature °F			Time 0	Yd	ΔH@
				Initial	Final	Vds Net	Initial	Final	Vd Net	In	Out	Tds Avg	In	Out	Td Avg			
57	1.3	20	1.0000	0	10.001	10.001	676.121	686.629	10.508	64	64	64	90	82	86	17.28	9835	2.1015
57	1.3	20	1.0000	0	10.001	10.001	686.629	697.207	10.578	64	64	64	100	84	93	17.34	9895	2.0893
57	1.3	20	1.0000	0	10.001	10.001	647.207	707.840	10.633	64	64	64	100	86	94	17.36	9862	2.0904

Nomenclature

Pb	Barometric Pressure
Q	Flow Rate (cfm)
ΔH	Orifice Pressure Differential ("H ₂ O)
ΔP	Inlet Pressure Differential ("H ₂ O)
Vd	Volume Dry Gas Meter (ft ³)
Vds	Volume Dry Standard (ft ³)
Yd	Meter Correction Factor (unitless)
Yds	Standard Meter Correction Factor (unitless)
ΔH@	Orifice Pressure Differential that gave 0.75 cfm of air at 70°F and 29.92 "Hg ("H ₂ O)

Calculations

Yd	=	(Yds)	$\left[\frac{Vds}{Vd} \right]$	$\left[\frac{Td + 460}{Tds + 460} \right]$	$\left[\frac{Pb + \Delta P/13.6}{Pb + \Delta H/13.6} \right]$
ΔH@	=		$\frac{0.0317 \Delta H}{Pb (Td + 460)}$	$\left[\frac{(Tds + 460)^0}{(Vds) (Yds)} \right]^2$	
Q	=		$\frac{17.64 (Vds) (Pb)}{(Tds + 460)^0}$		



FIELD DATA

Orsat Readings

Page 1 of 1


Client <u>GENERAL MOTORS</u>	Project Number <u>6520</u>
Plant <u>BUS + TRUCK</u>	Unit <u>4</u>
Date <u>2-2-93</u>	Fuel Type <u>NATURAL GAS</u>
Orsat ID <u>05</u>	Leak Check? <u>OK</u>

$$F_o = \frac{20.9 - \%O_2}{\%CO_2}$$

$F_o = 1.083 \text{ to } 1.230$
(for bituminous coal)

Run Number	Location	Bag ID	Trial	Percent CO ₂	Percent CO ₂ + O ₂	Percent O ₂	F _o	Sample Time	Analysis Time	Analyst
1	STACK	R1	1	9.0	13.8	4.8		12:25	13:30	JB
			2	8.8	13.6	4.8				
			3	8.8	13.6	4.8				
			Avg.	8.9		4.8				
2	STACK	R2	1	9.4	13.6	4.2		13:35	14:40	JB
			2	9.0	13.2	4.2				
			3	9.2	13.4	4.2				
			Avg.	9.2		4.2				
3	STACK	R3	1	9.2	13.8	4.6		14:45	15:50	JR
			2	9.2	13.8	4.6				
			3	9.2	13.8	4.6				
			Avg.	9.2		4.6				
4/5	STACK	R4/5	1	9.2	14.0	4.8		40 min	17:15	JB
			2	9.2	14.0	4.8				
			3	9.2	14.0	4.8				
			Avg.	9.2		4.8				
6/7	STACK	R6/7	1	9.4	14.0	4.6		40 min	18:40	JB
			2	9.4	14.0	4.6				
			3	9.4	14.0	4.6				
			Avg.	9.4		4.6				
8/9	STACK	R7/8	1	9.0	14.0	5.0		40 min	19:35	JB
			2	9.0	14.0	5.0				
			3	9.0	14.0	5.0				
			Avg.	9.0		5.0				
10/11	STACK	R10/11	1	8.6	14.4	5.58		40 min	20:30	JB
			2	8.4	14.0	5.6				
			3	8.4	14.0	5.6				
			Avg.	8.5		5.7				
12	STACK	R12	1	9.0	14.0	5.0		20 min	21:00	JB
			2	9.0	14.0	5.0				
			3	9.0	14.0	5.0				
			Avg.	9.0		5.0				

REDID ANOTHER BALL.
#15 TOO LOW CO₂




Orsat Readings

Page 1 of 1

Client <u>GM</u>	Project Number <u>6520</u>	$F_o = \frac{20.9 - \%O_2}{\%CO_2}$ $F_o = 1.083 \text{ to } 1.230$ (for bituminous coal)
Plant <u>ROANOKE</u>	Unit <u>4</u>	
Date <u>2-3-93</u>	Fuel Type <u>OIL</u>	
Orsat ID <u>05</u>	Leak Check? <u>OK</u>	

Run Number	Location	Bag ID	Trial	Percent CO ₂	Percent CO ₂ + O ₂	Percent O ₂	F _o	Sample Time	Analysis Time	Analyst
1	STACK	1	1	12.6	16.0	3.4		1 HR	10:40	JB
			2	12.6	16.0	3.4				
			3	12.6	16.0	3.4				
			Avg.	(12.6)		(3.4)				
2	STACK	2	1	13.0	16.6	3.6		1 HR	11:50	JB
			2	13.0	16.6	3.6				
			3	13.0	16.6	3.6				
			Avg.	(13.0)		(3.6)				
3	STACK	3	1	12.8	16.0	3.2		1 HR	13:00	JB
			2	12.8	16.0	3.2				
			3	12.8	16.0	3.2				
			Avg.	(12.8)		(3.2)				
			1							
			2							
			3							
			Avg.							
			1							
			2							
			3							
			Avg.							
			1							
			2							
			3							
			Avg.							
			1							
			2							
			3							
			Avg.							
			1							
			2							
			3							
			Avg.							



Moisture Determination Field Data Sheet


Page 1 of 1

Ambient Temp. (°F)	60	Bar. Press. (in. Hg)	29.56
Assumed Moisture (%)			

Heater Box Setting	Probe Heater Setting
Probe Length 3'	Probe Number
Probe Material SS	

IGS Bag ID Number	R19Relin	
% O ₂		
H ₂ O (ml)	38	
Total V _{ic}	472	
	% CO ₂	
	Silica Gel (gm)	41

Start Time: 11:27	AM	PM	Stop Time: 11:42	AM	PM
-------------------	----	----	------------------	----	----



(98)

Location: Stack Run: 1-3

Moisture Determination Field Data Sheet

Page 1 of 1

Client <u>CMA</u>	Project Number <u>6520</u>
Plant <u>Eck Weyer IN</u>	Unit <u>Boiler #4</u>
Date <u>2/2/93</u>	Inlet/outlet/stack <u>(stack)</u>
Meter Operator <u>K.S.</u>	
Probe Operator <u>J.B.</u>	

Sample Box Number <u>-</u>
Pyrometer Number <u>F84</u>
Meter Box Number <u>D</u>
Meter ΔH@ <u>1.9599</u> Meter Yd <u>1.0059</u>

Leak Rate Before: <u>✓</u> cc/m cf/m @ <u>"Hg</u>
Leak Rate After: <u>✓</u> cc/m cf/m @ <u>"Hg</u>

Schematic of Testing Location

First point all the way IN OUT Method 4

Area (ft²) 25.2 Port Len. (in.) 6.5 Gas Flow OUT

Filter Material

Ambient Temp. (°F) <u>60</u>	Bar. Press. (in. Hg) <u>29.56</u>
Assumed Moisture (%) <u>22</u>	
Heater Box Setting <u>-</u>	Probe Heater Setting <u>-</u>
Probe Length <u>7'</u>	Probe Number <u>9-28-90-3</u>
Probe Material <u>SS</u>	
IGS Bag ID Number <u>-</u>	
% O₂ <u>-</u>	% CO₂ <u>-</u>
H₂O (ml) <u>-</u>	Silica Gel (gm) <u>-</u>
Total Vc <u>-</u>	
Start Time: <u>12:30</u> AM <u>PM</u>	Stop Time: <u>12:35</u> AM <u>PM</u>
<u>1:50</u> <u>PM</u>	<u>1:54</u> <u>PM</u>
<u>3:08</u> <u>PM</u>	<u>3:13</u> <u>PM</u>

Traverse Point Number	Min/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. Tg (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H₂O)	Initial Volume		Gas Sample Temperature at Dry Gas Meter		Probe Temp. Tp (°F)	Notes
						Gas Sample Volume Vm	Circle one: (L) (ft³)	Inlet Tm (°F)	Outlet Tmad (°F)		
1.1	.58	364	.59	.59	361			.18	360		
2	.66	364	.63	.63	360			.64	360		
3	.69	364	.70	.70	363			.71	363		
4	.67	364	.61	.61	363			.69	365		
5	.56	364	.56	.56	363			.58	365		
6	.52	355	.48	.48	363			.44	361		
7.1	.51	361	.52	.52	362			.55	363		
2	.64	362	.67	.67	363			.67	363		
3	.66	363	.72	.72	363			.71	365		
4	.65	365	.65	.65	363			.70	364		
5	.60	363	.54	.54	363			.58	368		
6	.47	355	.48	.48	363			.48	364		
Average	(.774)	(362)	(.770)	(.770)	(363)			(.774)	(363)		
Total											

Location: Stack Run: 1Moisture Determination
Field Data SheetPage 1 of 1

Client	GM			Project Number	6520
Plant	Port Wayne IN			Unit	Baker 4-1
Date	2/2/93			Inlet/outlet/stack	
Meter Operator	K.S.				
Probe Operator	K.S.				

Sample Box Number	K0		
Pyrometer Number	F84		
Meter Box Number	D		
Meter ΔH@	1.9599	Meter Yd	1.0051

Leak Rate Before:	-001	cc/m	@	15	"Hg
Leak Rate After:	.002	cc/m	@	15	"Hg

Ambient Temp. (°F)	66	Bar. Press. (in. Hg)	29.56
Assumed Moisture (%)	22		

Heater Box Setting	—	Probe Heater Setting	—
Probe Length	3'	Probe Number	—
Probe Material	SS		

IGS Bag ID Number	R1		
% O ₂	4.8	% CO ₂	3.9
H ₂ O (ml)	109	Silica Gel (gm)	8
Total V _e	117		

Start Time: 12:23 AM (PM) Stop Time: 1:23 AM (PM)

Schematic of Testing Location

↑ N

2

First point all the way IN OUT Method 4

Area (ft²) 25.2 Port Len. (in.) 6.5 Gas Flow IN OUT

Filter Material

Traverse Point Number	Min/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. T _s (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume		Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)	Notes
						Gas Sample Volume V _m (ft ³)	Circle one: (L) (ft ³)	Inlet T _{m in} (°F)	Outlet T _{m out} (°F)		
1-1	5	2	N/A	46	1.0	299.11		93	88	N/A	
2	10	2		48	1.0	301.77		100	89		
3	15	2		50	1.0	304.41		104	89		
4	20	2		50	1.0	307.21		104	89		
5	25	2		52	1.0	309.85		105	89		
6	30	2		54	1.0	312.43		105	89		
2-1	35	2		54	1.0	315.12		104	88		
2	40	2		54	1.0	317.78		105	88		
3	45	2		56	1.0	320.55		104	88		
4	50	2		56	1.0	323.12		104	88		
5	55	2		56	1.0	325.81		104	88		
6	60	2	✓	58	1.0	328.45		104	88	✓	
Average					(1.0)						
Total						32.08					

Moisture Determination Field Data Sheet

Location: Stack Run: 2

Page 1 of 1

Client <u>CMA</u>	Project Number <u>6520</u>
Plant <u>Port Kemps JAL</u>	Unit <u>Boiler #1</u>
Date <u>2/2/93</u>	Inlet/Outlet/Stack <u>(stack)</u>
Meter Operator <u>K.S.</u>	
Probe Operator <u>K.S.</u>	

Sample Box Number <u>K6</u>	Meter Yd <u>1.0054</u>
Pyrometer Number <u>F64</u>	
Meter Box Number <u>D</u>	

Leak Rate Before: <u>.002</u> cc/m @ <u>15</u> "Hg
Leak Rate After: <u>.001</u> cc/m @ <u>12</u> "Hg

Schematic of Testing Location

First point all the way IN OUT Method 4

Area (ft²)	Port Len. (in.)	Gas Flow IN OUT
<u>25.2</u>	<u>6.5</u>	<u>OUT</u>

Filter Material

Ambient Temp. (°F)	Bar. Press. (in. Hg)
<u>60</u>	<u>29.56</u>
Assumed Moisture (%)	
<u>22</u>	

Heater Box Setting	Probe Heater Setting
<u>3'</u>	<u>-</u>
Probe Length	Probe Number
<u>SS</u>	<u>-</u>

IGS Bag ID Number	% O₂	% CO₂
<u>R2</u>	<u>4.2</u>	<u>9.2</u>
H₂O (ml)	Silica Gel (gm)	
<u>116</u>	<u>16</u>	
Total Vc		
<u>132</u>		

Start Time: <u>1:33</u> AM	Stop Time: <u>2:34</u> AM
----------------------------	---------------------------

Traverse Point Number	Mig/pt	Clock Time	Pump Vacuum (in. Hg)	Stack Temp. Ts (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H₂O)	Initial Volume	Gas Sample Temperature at Dry Gas Meter		Probe Temp. Tp (°F)	Notes
							Gas Sample Volume Vm (ft³)	Inlet Tm in (°F)	Outlet Tm out (°F)		
							Circle one: (L) (ft³)				
	5		2	N/A	56	1.0	331.48	96	87	N/A	
	10		2		52	1.0	334.17	101	88		
	15		2		52	1.0	336.87	104	88		
	20		2		52	1.0	339.57	104	88		
	25		2		52	1.0	342.27	104	88		
	30		2		50	1.0	344.95	104	88		
	35		2		50	1.0	347.65	103	88		
	40		2		50	1.0	350.35	102	88		
	45		2		50	1.0	353.04	102	88		
	50		2		50	1.0	355.72	103	88		
	55		2		50	1.0	358.41	102	88		
	60		2		50	1.0	361.08	103	88		
							(95)				
Average											
Total							32.30				



Location: Stack Run: 3

Moisture Determination Field Data Sheet

Page of

Client <u>GM</u>	Project Number <u>6520</u>
Plant <u>Fort Wayne IN</u>	Unit <u>Bs. 1er 4</u>
Date <u>2/2/93</u>	Inlet/outlet <u>stack</u>
Meter Operator <u>K.S.</u>	
Probe Operator <u>K.S.</u>	

Sample Box Number <u>110</u>
Pyrometer Number <u>F-8-1</u>
Meter Box Number <u>D</u>
Meter $\Delta H@$ <u>1.9599</u> Meter γ_d <u>1.0054</u>

Leak Rate Before: <u>.002</u> cc/m @ <u>13</u> "Hg
Leak Rate After: <u>.002</u> cc/m @ <u>13</u> "Hg

Schematic of Testing Location

First point all the way IN OUT Method 4

Area (ft ²)	Port Len. (in.)	Gas Flow IN OUT
<u>25.2</u>	<u>6.5</u>	<u>OUT</u>

Filter Material

Ambient Temp. (°F)	<u>60</u>	Bar. Press. (in. Hg)	<u>29.56</u>
Assumed Moisture (%)			

Heater Box Setting	<u> </u>	Probe Heater Setting	<u> </u>
Probe Length	<u>3'</u>	Probe Number	<u> </u>
Probe Material	<u>SS</u>		

IGS Bag ID Number	<u>123</u>
% O ₂	<u>4.6</u>
H ₂ O (ml)	<u>113</u>
Total V _c	<u>117</u>
% CO ₂	<u>9.2</u>
Silica Gel (gm)	<u>4</u>

Start Time: <u>2:44</u> AM	Stop Time: <u>3:44</u> AM
----------------------------	---------------------------

Traverse Point Number	Min/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. T _s (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume Gas Sample Volume V _m Circle one: (L) (ft ³)	Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)	Notes
							Inlet T _{m in} (°F)	Outlet T _{m out} (°F)		
	5	2	N/A	52	1.0	364.15	95	86	N/A	
	10	2		52	1.0	367.07	100	86		
	15	2		52	1.0	369.52	101	86		
	20	2		52	1.0	372.20	102	87		
	25	2		50	1.0	374.88	101	87		
	30	2		50	1.0	377.57	101	87		
	35	2		50	1.0	380.26	100	87		
	40	2		50	1.0	382.94	100	86		
	45	2		50	1.0	385.62	100	87		
	50	2		50	1.0	388.28	100	86		
	55	2		52	1.0	390.95	100	86		
	60	2		52	1.0	393.64	100	86		
Average					<u>(1.0)</u>					
Total						<u>(32.29)</u>				



Run: 4-5

Moisture Determination Field Data Sheet

Page _____ of _____

Client	GA	Project Number	6520
Plant	Fort Wayne IN	Unit	Bouler #4
Date	2/2/93	Inlet/Outlet/Stack	
Meter Operator	KS.		
Probe Operator	KS		

Sample Box Number	K6
Pyrometer Number	F-821
Meter Box Number	D
Meter $\Delta H @$	1.9599
Meter Yd	1.0054

Leak Rate Before:	.001 cc/m @ 10	"Hg
Leak Rate After:	.003 cc/m @ 13	"Hg

Ambient Temp. (°F)	60	Bar. Press. (in. Hg)	29.56
Assumed Moisture (%)			

Heater Box Setting	Probe Heater Setting
Probe Length 3'	Probe Number
Probe Material SS	

IGS Bag ID Number	74
% O ₂	4.8
% CO ₂	9.2
H ₂ O (ml)	112
Silica Gel (gm)	7
Total V _c	119

Start Time: 4:18 AM Stop Time: 5:03 AM

Schematic of Testing Location		First point all the way IN OUT		Method 4
	Area (ft ²)	Port Len. (in.)	Gas Flow IN OUT	
	25.2	6.5		
Filter Material				

Traverse Point Number	Mips/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. T _s (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume Gas Sample Volume V _m Circle one: (L) (ft ³)	Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)		Notes
							Inlet T _{m in} (°F)	Outlet T _{m out} (°F)			
	5	2	N/A	44	1.5	397.58	92	84	N/A		
	10	2		44	1.5	401.04	102	84			
	15	2		46	1.5	404.59	105	86			
	20	2		46	1.5	407.94	106	86			
	25	2		48	1.5	411.38	106	87			
	30	2		48	1.5	414.83	106	87			
	35	2		50	1.5	418.26	106	88			
	40	2		50	1.5	421.70	106	88			
	45	2		50	1.5	425.14	106	88			
Average					(1.5)						
Total						(31.03)					

Location: Stack Run: 8-1


Moisture Determination Field Data Sheet

Client GM Project Number 6520
Plant Folt Wayne IN Unit Boiler #4
Date 2/2/93 Inlet/outlet stack
Meter Operator K.S.
Probe Operator K.S.

Sample Box Number K0
Pyrometer Number E-84
Meter Box Number D
Meter $\Delta H @$ 1.9599 Meter Y_d 1.0054

Leak Rate Before: 1.006 cc/m @ 13 °Hg
Leak Rate After: 1.001 cc/m @ 13 °Hg

Schematic of Testing Location



First point all the way IN OUT Method 4
Area (ft²) 25.2 Port Len. (in.) 6.5 Gas Flow IN OUT
Filter Material

Ambient Temp. (°F) 60 Bar. Press. (in. Hg) 29.56
Assumed Moisture (%) 16.62

Heater Box Setting - Probe Heater Setting -
Probe Length 3' Probe Number -
Probe Material SS

IGS Bag ID Number R8-9
% O₂ 5.0 % CO₂ 9.0
H₂O (ml) 108 Silica Gel (gm) 16
Total V_e 124

Start Time: 6:42 AM PM Stop Time: 7:27 AM PM

Traverse Point Number	Mgd/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp, T _s (°F)	Bath Temp, (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume Gas Sample Volume V _m Circle one: (L) (ft ³)	Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)	Notes
							Inlet T _{m in} (°F)	Outlet T _{m out} (°F)		
5		2	N/A	46	1.5	457.63 461.10	96	88	N/A	
10		2		44	1.5	464.55	102	88		
15		2		48	1.5	467.99	105	88		
20		2		50	1.5	471.42	106	88		
25		2		50	1.5	474.85	106	88		
30		2		50	1.5	478.28	106	88		
35		2		50	1.5	481.71	106	89		
40		2		50	1.5	485.15	106	89		
45		2		52	1.5	488.58	105	89		
Average										
Total										

(96)

(30.95)

(1.5)

Moisture Determination Field Data Sheet

Page 1 of _____

Ambient Temp. (°F)	60	Bar. Press. (in. Hg)	29.56
Assumed Moisture (%)	15.81		

Heater Box Setting	—	Probe Heater Setting	—
Probe Length	3'	Probe Number	
Probe Material	SS		

IGS Bag ID Number	R 10-11	
% O ₂	5.7	% CO ₂ 8.5
H ₂ O (ml)	106	Silica Gel (gm) 10
Total V _{ic}	116	

Start Time: 7:40	AM / PM	Stop Time: 8:25	AM / PM
------------------	---------	-----------------	---------

Schematic of Testing Location		Method 4
	Port Len. (in.) <u>6.5</u>	Gas Flow <u>IN</u> <u>OUT</u>
Area (ft ²) <u>25.2</u>	Filter Material	

Client	GM	Project Number	6520
Plant	5014 Wayne IN	Unit	Biller #4
Date	2/2/93	Inlet/Outlet	stack
Meter Operator	KS		
Probe Operator			

Sample Box Number	K0
Pyrometer Number	F-84
Meter Box Number	0
Meter $\Delta H @$	1.9599
Meter Y_0	1.0054

Leak Rate Before: ∞	cc/m ci/m @ 13	"Hg
Leak Rate After: ∞	cc/m ci/m @ 13	"Hg

Traverse Point Number	Min/ppt Σ Clock Time	Pump Vacuum (in. Hg)	Stack Temp. T _s (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume Gas Sample Volume V _m Circle one: (L) (ft ³)	Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)	Notes
							Inlet T _{m in} (°F)	Outlet T _{m out} (°F)		
	5	2	N/A	44	1.5	492.51	94	86	N/A	
	10	2		44	1.5	495.95	104	88		
	15	2		46	1.5	499.36	106	89		
	20	2		44	1.5	502.76	106	89		
	25	2		46	1.5	506.17	106	89		
	30	2		46	1.5	509.56	106	89		
	35	2		48	1.5	512.95	106	90		
	40	2		48	1.5	516.35	106	90		
	45	2	✓	48	1.5	519.79	106	89	↓	
Average					(1.5)				(97)	
Total						(30.74)				

Moisture Determination Field Data Sheet

Location: stack Run: 8

Client	Carl	Project Number	6529
Plant	Felt Wayne IN	Unit	Boiler #4
Date	2/2/93	Inlet/outlet	stack
Meter Operator	K.S.		
Probe Operator	K.S.		

Sample Box Number	K6	"Hg
Pyrometer Number	F.84	"Hg
Meter Box Number	D	
Meter ΔH@	1.9599	Meter Y _d
		1.0054
Leak Rate Before:	0.01	cc/m @ 15
Leak Rate After:		cc/m cfm @

Schematic of Testing Location		Method 4	
	First point all the way IN	OUT	
Area (ft ²)	25.2	Port Len. (in.)	6.5
Filter Material		Gas Flow	IN OUT

Ambient Temp. (°F)	60	Bar. Press. (in. Hg)	29.56
Assumed Moisture (%)	15.34		

Heater Box Setting	—	Probe Heater Setting	—
Probe Length	3'	Probe Number	—
Probe Material	SS		

IGS Bag ID Number	R12		
% O ₂	5	% CO ₂	9
H ₂ O (ml)	53	Silica Gel (gm)	2
Total V _{ic}	55		

Start Time:	8:34 AM	Stop Time:	8:54 AM
-------------	---------	------------	---------

[illegible]

Moisture Determination Field Data Sheet

Page 1 of 1

Location: Slack Run: 1-30.1

Client: CMA Project Number: 6520
 Plant: Fort Wayne IU Unit: 3-2-1
 Date: 2/3/93 Inlet/outlet: stack
 Meter Operator: KS
 Probe Operator: JB

Sample Box Number: —
 Pyrometer Number: F81
 Meter Box Number: D
 Meter ΔH @ 1.9599 Meter Yd: 1.0054

Leak Rate Before: ✓ cc/m cf/m @ "Hg
 Leak Rate After: ✓ cc/m cf/m @ "Hg

Schematic of Testing Location



First point all the way IN OUT Method 4
 Area (ft²): 25.2 Port Len. (in.): 6.5 Gas Flow: IN OUT
 Filter Material: —

Heater Box Setting: — Probe Heater Setting: —
 Probe Length: 7' Probe Number: 9-22-90-2
 Probe Material: SS

IGS Bag ID Number: —
 % O₂: — % CO₂: —
 H₂O (ml): — Silica Gel (gm): —
 Total Vc: —

Start Time: 9:47 AM/PM Stop Time: 9:51 AM/PM
 10:54 PM 12:05 PM

Traverse Point Number	Min/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. T _s (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume		Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)	Notes
						Gas Sample Volume V _m (ft³)	Circle one: (L) (ft³)	Inlet T _{inlet} (°F)	Outlet T _{outlet} (°F)		
1-1	.50	371	.52	372				.48	372		
2	.62	370	.61	373				.59	373		
3	.65	370	.67	375				.63	374		
4	.64	370	.63	373				.63	375		
5	.57	370	.59	377				.56	376		
6	.37	370	.41	378				.40	372		
2-1	.51	370	.48	375				.49	373		
2	.58	370	.51	377				.61	374		
3	.67	370	.63	376				.66	375		
4	.65	370	.66	377				.67	376		
5	.57	370	.63	374				.61	377		
6	.41	370	.51	377				.50	377		
Average	(.747)	(370)	(.755)	(375)				(.752)	(374)		
Total											

Location: Slick Run: 1-0-1

Moisture Determination Field Data Sheet

Client	C.A	Project Number	6520
Plant	Port Wayne IV	Unit #	4 Boiler
Date	2/3/93	Inlet/outlet/stack	
Meter Operator	KS		
Probe Operator	KS		

Sample Box Number	86
Pyrometer Number	-
Meter Box Number	1
Meter ΔH@	17599
Meter Yc	1.0054

Leak Rate Before:	001	cc/m @ 14	"Hg
Leak Rate After:	001	cc/m @ 15	"Hg

Schematic of Testing Location

First point all the way IN OUT Method 4

Area (ft²)	25.2	Port Len. (in.)	6.5	Gas Flow	IN OUT
Filter Material					


Ambient Temp. (°F)	61	Bar. Press. (in. Hg)	29.41
Assumed Moisture (%)	12.47		

Heater Box Setting	-	Probe Heater Setting	-
Probe Length	3'	Probe Number	-
Probe Material	SS		

IGS Bag ID Number	R10
% O ₂	3.4
H ₂ O (ml)	80
Total Vc	90
% CO ₂	12.6
Silica Gel (gm)	10

Start Time:	7:36 AM	Stop Time:	8:36 AM
-------------	---------	------------	---------

Traverse Point Number	Min/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. Ts (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Gas Sample Temperature at Dry Gas Meter		Probe Temp. Tp (°F)	Notes
						Initial Volume Gas Sample Volume Vm Circle one: (L) (ft³)	Inlet Tm in (°F)	Outlet Tm out (°F)	
5		2	N/A	34	1.0	538.80	94	85	N/A
10		2		38	1.0	541.81	100	86	
15		2		42	1.0	544.08	103	86	
20		2		44	1.0	546.72	103	87	
25		2		46	1.0	549.34	102	86	
30		2		46	1.0	551.94	101	88	
35		2		48	1.0	554.55	100	88	
40		2		50	1.0	557.17	100	88	
45		2		50	1.0	559.78	100	88	
50		2		52	1.0	562.38	100	88	
55		2		54	1.0	564.95	100	88	
60		2		56	1.0	567.58	100	87	
						(94)			
Average						(31.53)			
Total									



Moisture Determination Field Data Sheet


Location: Stack Run: 2.01

Client	<u>GA</u>	Project Number	<u>6520</u>
Plant	<u>Fort Wayne IN</u>	Unit #	<u>4</u>
Date	<u>2/3/93</u>	Inlet/Outlet/Stack	<u>Stack</u>
Meter Operator	<u>KS</u>		
Probe Operator	<u>KS</u>		

Sample Box Number	<u>KC</u>
Pyrometer Number	<u>-</u>
Meter Box Number	<u>D</u>
Meter $\Delta H @$	<u>1.9599</u>
Meter Y_d	<u>1.0054</u>

Leak Rate Before:	<u>.001</u>	cc/m @	<u>15</u>	"Hg
Leak Rate After:	<u>.003</u>	cc/m @	<u>18</u>	"Hg

Schematic of Testing Location



First point all the way IN	OUT	Method 4
Area (ft ²)	Port Len. (in.)	Gas Flow
<u>25.2</u>	<u>6.5</u>	<u>IN</u>
Filter Material		


Ambient Temp. (°F)	<u>61</u>	Bar. Press. (in. Hg)	<u>29.41</u>
Assumed Moisture (%)	<u>12.58</u>		

Heater Box Setting	<u>-</u>	Probe Heater Setting	<u>-</u>
Probe Length	<u>3'</u>	Probe Number	<u>-</u>
Probe Material	<u>SS</u>		

IGS Bag ID Number	<u>K20</u>
% O ₂	<u>3.6</u>
H ₂ O (ml)	<u>81</u>
Total V _c	<u>90</u>
% CO ₂	<u>13.0</u>
Silica Gel (gm)	<u>9</u>

Start Time:	<u>10:47 AM</u>	Stop Time:	<u>11:47 AM</u>
-------------	-----------------	------------	-----------------

Traverse Point Number	Mig/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. T _s (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume Gas Sample Volume V _m Circle one: (L) (ft ³)	Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)	Notes
							Inlet T _m in (°F)	Outlet T _m out (°F)		
5	2	2	N/A	50	1.0	570.70	92	85	N/A	
10	2	2		50	1.0	513.37	98	86		
15	2	2		54	1.0	515.88	102	86		
20	2	2		56	1.0	578.45	103	86		
25	2	2		56	1.0	581.10	104	87		
30	2	2		56	1.0	583.80	105	87		
35	2	2		56	1.0	586.33	105	88		
40	2	2		58	1.0	588.94	106	88		
45	2	2		54	1.0	591.56	106	88		
50	2	2		54	1.0	594.17	106	89		
55	2	2		50	1.0	596.78	107	90		
60	2	2		50	1.0	599.39	106	90		
Average										
Total										



Location: stack Run: 301

Moisture Determination Field Data Sheet

Client GM Project Number 6520
Plant Fort Wayne IN Unit # 4 Boiler
Date 2/3/95 Inlet/outlet/stack stack
Meter Operator KS
Probe Operator KS

Sample Box Number K0
Pyrometer Number —
Meter Box Number D
Meter $\Delta H @$ 1.9599 Meter Y_d 1.0058

Leak Rate Before: 0.01 cc/m @ 17 "Hg
Leak Rate After: 0.03 cc/m @ 14 "Hg

Schematic of Testing Location

First point all the way IN OUT Method 4

Area (ft²) 25.2 Port Len. (in.) 6.5 Gas Flow IN OUT

Filter Material —



Ambient Temp. (°F) 61 Bar. Press. (in. Hg) 29.41
Assumed Moisture (%) 11.82

Heater Box Setting — Probe Heater Setting —
Probe Length 3' Probe Number —
Probe Material SS

IGS Bag ID Number 123
% O₂ 3.2 % CO₂ 12.8
H₂O (ml) 82 Silica Gel (gm) 2
Total V_g 84

Start Time: 11:58 AM / PM Stop Time: 12:58 AM / PM

Traverse Point Number	Min/pt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. T _s (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume Gas Sample Volume V _m (L) (ft ³)	Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)	Notes
							Inlet T _{m in} (°F)	Outlet T _{m out} (°F)		
	5	2	N/A	48	1.0	602.05	99	90	N/A	
	10	2		44	1.0	605.49	106	90		
	15	2		46	1.0	608.13	107	91		
	20	2		46	1.0	610.74	108	91		
	25	2		46	1.0	613.34	108	91		
	30	2		48	1.0	615.96	107	91		
	35	2		46	1.0	618.62	107	91		
	40	2		46	1.0	621.25	107	91		
	45	2		48	1.0	623.88	107	91		
	50	2		50	1.0	626.50	107	91		
	55	2		50	1.0	629.11	107	91		
	60	2		50	1.0	631.70	107	91		
Average							(99)			
Total						31.53				

Run: 4-50:1

Location: Sidack

Project Number 6526
Unit Bunk 4
evstack

75001 P.

14	Hg
15	Hg

Moisture Determination Field Data Sheet

Page 1 of 1

Ambient Temp. (°F)	61	Bar. Press. (in. Hg)	29.41
Assumed Moisture (%)			

Heater Box Setting	--	Probe Heater Setting	--
Probe Length	3'	Probe Number	--
Probe Material	SS		

IGS Bag ID Number		12450
% O ₂		
% CO ₂		
H ₂ O (ml)	53	
Silica Gel (gm)		5
Total V _{ic}	58	

Start Time: 1:57	AM	Stop Time: 2:27	AM
------------------	----	-----------------	----

Schematic of Testing Location			
	First point all the way IN		Method 4
	Area (ft ²)	Port Len. (in.)	Gas Flow IN OUT
25.2	6.5		
Filter Material			

Traverse Point Number	Min/ppt Clock Time	Pump Vacuum (in. Hg)	Stack Temp. T _s (°F)	Bath Temp. (°F)	Orifice Setting ΔH (in. H ₂ O)	Initial Volume Gas Sample V _m Circle one: (L) (ft ³)	Gas Sample Temperature at Dry Gas Meter		Probe Temp. T _p (°F)	Notes
							Inlet T _{m in} (°F)	Outlet T _{m out} (°F)		
	5	3	N/A	41	1.5	632.50 635.88	97	90	N/A	
	16	2		42	1.5	639.23	109	92	/	
	15	3		48	1.5	642.52	112	92	/	
	26	3		50	1.5	645.83	112	93	/	
	25	3		52	1.5	649.16	112	93	/	
	30	3		52	1.5	651.95	112	94	/	
	35									stirred at 29:20
	40									
	45									
Average					(1.5)					
Total						(19.45)			(102)	

Visual Emissions Observation Form

Run 1

Client/Owner GM DATED NICHOLLA

Plant: First 1/2 mile Unit: 4 Observer's name: _____ Project Number: 6520

Observation Date: 2/3/93 Certified by: Carl Kuntz Date Certified: 10/17/92

Source/Process: CIL Feed Boiler Start time: 9:35 am Stop time: 10:35 am

Control Equipment: VINE

Operating Mode: 200,000 lb/term

Describe emission point:
Tall and round, red white striped brick stack

Emission point height above ground level (feet): 250'

Emission point height above relative to observer (feet): 250'

Distance to emission point: _____

Distance to emission point from observer: _____

Describe emission (Color, etc): _____

Continuous Fugitive Intermittent

Water vapor present? No Yes

If yes, is plume attached or detached? _____

Point where opacity was determined: diameter from exit

Describe background: clear blue sky

Sky conditions: clear

Wind speed: 0-9 Wind direction: _____

Ambient temperature: _____

Relative humidity: 74%

Comments: _____

Layout sketch of source:

Range of opacity: 0 % to 10 %

Observer's Signature: David Nicholls

Date: _____

	0	15	30	45	60	0	15	30	45	60
0	5	10	5	5	5	30	5	5	5	5
1	10	5	5	5	5	31	5	5	5	5
2	5	5	10	5	5	32	5	10	5	5
3	5	10	5	5	5	33	5	5	5	5
4	5	10	10	5	5	34	5	5	10	5
5	5	10	10	5	5	35	5	5	5	5
6	5	5	5	5	5	36	5	5	10	5
7	5	10	5	5	5	37	5	5	5	5
8	10	5	5	5	5	38	5	5	5	5
9	5	5	5	5	5	39	5	5	5	5
10	5	10	5	5	5	40	0	5	5	5
11	5	5	5	5	5	41	5	5	5	0
12	5	5	5	5	5	42	5	5	5	5
13	5	10	5	5	5	43	5	5	5	5
14	5	5	5	5	5	44	5	5	5	5
15	5	5	5	10	5	45	5	5	5	5
16	5	5	5	5	5	46	5	5	5	5
17	5	5	5	5	5	47	0	0	5	5
18	5	5	5	5	5	48	0	5	5	5
19	5	5	5	5	5	49	5	5	5	5
20	5	5	5	5	5	50	5	0	5	5
21	5	5	0	5	5	51	0	0	5	5
22	5	5	5	0	5	52	5	0	0	0
23	5	5	5	10	5	53	5	5	5	5
24	5	5	5	5	5	54	5	5	5	0
25	5	5	10	5	5	55	0	5	0	5
26	5	5	5	10	5	56	5	5	0	5
27	5	5	5	5	5	57	5	5	5	0
28	5	5	5	5	5	58	0	5	5	5
29	5	5	5	5	5	59	5	5	5	5

gray check

Visual Emissions Observation Form

Run 2


DAVID NABRALLA

Client/Owner: GM	Observer's name: DAVID NABRALLA	Project Number: 6520
Plant: Fort Wayne Unit: 4	Certified by: Carl Huntz	Date Certified: 10/7/92
Observation Date: 2/3/93	Start time: 10:45	Stop time: 11:45
Source/Process: Oil Fired Boiler		
Control Equipment: NONE		
Operating Mode: 200,000 lb steam		
Describe emission point: Tall, round, red white stripe, Brick stack		
Emission point height above ground level (feet): 250'		
Emission point height above relative to observer (feet): 250'		
Distance to emission point:		
Distance to emission point from observer: 900'		
Describe emission (Color, etc):		
☒ Continuous ☐ Fugitive ☐ Intermittent		
Water vapor present? ☒ No ☐ Yes		
If yes, is plume attached or detached?		
Point, where opacity was determined: Diameter from exit		
Describe background: Blue/white sky		
Sky conditions: 10% overcast		
Wind speed: 0-5 Wind direction:		
Ambient temperature: 45 40 ON		
Relative humidity: 80%		
Comments:		
Layout sketch of source:		
Range of opacity: 0 % to 5 %		
Observer's Signature: David Nabralle		
Date: 2/3/93		

0	15	30	45	60	0	15	30	45	60
0	5	5	5	5	30	5	5	5	5
1	5	5	5	5	31	5	5	5	0
2	5	5	5	5	32	5	5	5	5
3	5	5	0	5	33	0	0	0	5
4	5	5	5	0	34	0	5	0	5
5	5	5	5	0	35	0	0	5	0
6	5	5	5	5	36	5	0	0	5
7	5	5	5	5	37	5	5	0	5
8	5	5	0	5	38	0	5	0	5
9	5	5	5	5	39	0	5	5	5
10	0	5	5	5	40	0	5	0	5
11	5	5	0	5	41	0	5	0	0
12	5	5	0	0	42	0	0	5	5
13	5	5	5	5	43	0	0	0	0
14	0	5	5	5	44	0	0	0	0
15	5	0	5	5	45	5	5	0	0
16	5	5	5	0	46	5	0	0	5
17	5	5	5	5	47	0	5	5	0
18	0	5	5	5	48	0	5	0	0
19	5	5	5	5	49	0	0	5	0
20	5	5	5	5	50	5	0	0	5
21	5	5	0	5	51	0	5	5	5
22	5	5	0	5	52	5	5	5	5
23	5	5	0	5	53	5	0	0	5
24	5	5	5	5	54	5	5	0	5
25	0	0	5	5	55	5	5	5	5
26	5	5	5	5	56	5	5	5	5
27	0	5	0	5	57	5	5	5	5
28	5	5	0	5	58	0	5	5	5
29	5	0	5	5	59	0	5	5	5

Visual Emissions Observation Form


Run 3

Client/Owner GM Observer's name: DAVID NASRALLA Project Number: 6520 DN
 Plant: Fert Wayne Unit: 4 Certified by: Carl Hantz Date Certified: 10/7/12
 Observation Date: 2/3/93 Start time: 11:55 Stop time: 12:55
 Source/Process: Oil Fuel Boilers
 Control Equipment: None
 Operating Mode: 200000 lb/hr steam
 Describe emission point:
TALL, round, red + white striped brick stack.
 Emission point height above ground level (feet): 250
 Emission point height above relative to observer (feet): 250
 Distance to emission point:
 Distance to emission point from observer:
 Describe emission (Color, etc):
 Continuous ☒ Fugitive ☐ Intermittent ☐
 Water vapor present? No Yes ☐
 If yes, is plume attached or detached?
 Point where opacity was determined:
1 diameter from exit
 Describe background:
white
 Sky conditions: 20% overcast
 Wind speed: 5-10 Wind direction: SSE
 Ambient temperature: 41°F
 Relative humidity: 80%
 Comments:
 Layout sketch of source:

 Range of opacity: 0 % to 5 %
 Observer's Signature: David Nasralla
 Date: Feb 3, 1993

	0	15	30	45	60	0	15	30	45	60
0	5	5	0	5	30	5	0	5	5	
1	5	5	5	5	31	5	5	5	5	
2	5	5	5	5	32	5	5	5	5	
3	5	5	5	5	33	5	0	0	5	
4	5	5	5	5	34	0	5	0	5	
5	5	5	0	5	35	5	0	0	0	
6	5	5	5	5	36	5	0	5	5	
7	5	5	5	5	37	5	5	5	5	
8	5	5	5	5	38	0	0	5	5	
9	5	0	0	5	39	0	5	5	5	
10	5	5	5	5	40	5	0	5	5	
11	5	5	5	5	41	5	5	5	5	
12	0	5	0	0	42	5	0	0	5	
13	5	5	5	5	43	0	5	5	0	
14	5	5	5	5	44	5	5	5	5	
15	5	5	5	5	45	5	5	0	0	
16	5	5	5	5	46	5	5	5	5	
17	0	5	5	0	47	5	5	5	5	
18	0	5	5	5	48	5	5	5	5	
19	5	5	0	5	49	5	5	5	5	
20	5	5	5	0	50	5	5	5	5	
21	5	0	5	5	51	5	5	5	5	
22	5	5	5	5	52	5	5	5	5	
23	5	5	5	5	53	5	5	5	5	
24	5	5	5	5	54	5	5	5	5	
25	5	5	5	5	55	5	5	5	5	
26	5	5	0	5	56	5	5	5	5	
27	5	5	5	5	57	5	5	5	5	
28	5	5	5	5	58	5	5	5	5	
29	0	5	5	5	59	5	5	5	5	

GENERAL MOTORS CORPORATION
CAE Project No: 6520
Boiler #4 Stack, Natural Gas
February 2, 1993

NITROGEN OXIDES (PPM)




GENERAL MOTORS CORPORATION

CAE Project No: 6520

Boiler #4 Stack, Natural Gas


February 2, 1993

NITROGEN OXIDES (PPM)




GENERAL MOTORS CORPORATION
CAE Project No: 6520
Boiler #4 Stack, Natural Gas
February 2, 1993

NITROGEN OXIDES (PPM)




GENERAL MOTORS CORPORATION
CAE Project No: 6520
Boiler #4 Stack, Natural Gas
February 2, 1993

NITROGEN OXIDES (PPM)




GENERAL MOTORS CORPORATION
CAE Project No: 6520
Boiler #4 Stack, Oil
February 3, 1993

NITROGEN OXIDES (PPM)



GENERAL MOTORS CORPORATION
CAE Project No: 6520
Boiler #4 Stack, Oil
February 3, 1993

NITROGEN OXIDES (PPM)



GENERAL MOTORS CORPORATION
CAE Project No: 6520

MONITOR DATA

5-6

- Run 1 - 1 Hour TEST.

Use PgUp and PgDn keys to display other parameters.
Press the ENTER key to update the screen.

Press the ENTER key to display other parameters.
IM Specified Average Report MMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMM More Above MM;
Start Time: Tue Feb 2 12:14:40 1993 End Time: Tue Feb 2 13:14:50 1993
Unit #4 Gasit 12:25 Start

12:25 START

Unit	Value	Unit
Unit #4 Opacity	1.900	%
Unit #4 O2	0.000	%
Unit #4 CO2	8.495	%
Unit #4 CO ppm	217.583	ppm
Unit #4 SO2 ppm	3.650	ppm
Unit #4 NO ppm	50.083	ppm
Unit #4 Fuel Input	218.123	MMBtu/Hr
Unit #4 SO2 Emission Rate	0.007	Lbs/mmBTU
Unit #4 CO Emission Rate	0.193	Lbs/mmBTU
Unit #4 NOx Emission Rate	0.073	Lbs/mmBTU
Unit #4 SO2 Mass Emission	1.616	Lbs/Hr
Unit #4 CO Mass Emission	42.152	Lbs/Hr
Unit #4 NOx Mass Emission	15.938	Lbs/Hr

[illegible]

Run 2 - 1 Hour

Use PgUp and PgDn keys to display other parameters.
Press the ENTER key to display the next screen.

Press the ENTER key to update the screen.

IM Specified Average Report MMM More Above MM;
Start Time: Tue Feb 2 ~~14~~¹³:00 1993 End Time: Tue Feb 2 ~~14~~¹³:20 1993 :

Start Time: Tue Feb 2 14:00:00 1993 End Time: Tue Feb 2 14:05:20 1993

Unit	Value	Unit
Unit #4 Opacity	1.900	%
Unit #4 O2	0.000	%
Unit #4 CO2	8.359	%
Unit #4 CO ppm	213.721	ppm
Unit #4 SO2 ppm	3.459	ppm
Unit #4 NO ppm	50.197	ppm
Unit #4 Fuel Input	218.189	MMBtu/Hr
Unit #4 SO2 Emission Rate	0.007	Lbs/mmBTU
Unit #4 CO Emission Rate	0.193	Lbs/mmBTU
Unit #4 NOx Emission Rate	0.074	Lbs/mmBTU
Unit #4 SO2 Mass Emission	1.556	Lbs/Hr
Unit #4 CO Mass Emission	42.099	Lbs/Hr
Unit #4 NOx Mass Emission	16.240	Lbs/Hr

[illegible]

Help 33 Main Menu 33 Print 33 Previous 3
DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY

'DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY

Press the ENTER key to update the screen.

Start Time: Tue Feb 2 14:30:30 1993 End Time: Tue Feb 2 14:40:40 1993

Unit	Value	Unit
Unit #4 Opacity	16.20	%
Unit #4 O2	16.41	%
Unit #4 CO2	0.000	%
Unit #4 CO ppm	8.285	%
Unit #4 SO2 ppm	157.600	ppm
Unit #4 NO ppm	3.050	ppm
	51.550	ppm
Unit #4 Fuel Input		
Unit #4 SO2 Emission Rate	218.205	MMBtu/Hr
Unit #4 CO Emission Rate	0.006	Lbs/mmBTU
Unit #4 NOx Emission Rate	0.144	Lbs/mmBTU
Unit #4 SO2 Mass Emission	0.077	Lbs/mmBTU
Unit #4 CO Mass Emission	1.385	Lbs/Hr
Unit #4 NOx Mass Emission	31.319	Lbs/Hr
	16.827	Lbs/Hr

[illegible]

RA - Ruw #1 - 21-min.

Press the ENTER key to update the screen.

Start Time: Tue Feb 2 ~~14:30~~:30 1993 End Time: Tue Feb 2 ~~14:50~~:50 1993 :

```

MMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMMM More Below MM<
ZLF1 DDDDDDDDDDDDD?ZLF2 DDDDDDDDDDDDD?ZLF3 DDDDDDDDDDDDD?ZLF4 DDDDDDDDDDDDD?
3      Help      33 Main Menu    33 Print      33 Previous  3
DDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY

```

- Run #2 - 21 min

Press the ENTER key to update the screen.

Start Time: Tue Feb 2 ~~11:34~~:40 1993 End Time: Tue Feb 2 ~~11:59~~:10 1993 :

[illegible]

3 Help 33 Main Menu 33 Print 33 Previous 3

DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY

Run #3 21 MIN

Press the ENTER key to update the screen.

Start Time: Tue Feb 2 08:40:40 1993 End Time: Tue Feb 2 14:00:00 1993

Unit #4 Fuel Input	159.050	MMBtu/Hr	:
Unit #4 SO2 Emission Rate	0.007	Lbs/mmBTU	:
Unit #4 CO Emission Rate	0.194	Lbs/mmBTU	:
Unit #4 NOx Emission Rate	0.081	Lbs/mmBTU	:
Unit #4 SO2 Mass Emission	1.055	Lbs/Hr	:
Unit #4 CO Mass Emission	30.806	Lbs/Hr	:
Unit #4 NOx Mass Emission	12.927	Lbs/Hr	:

```

/ ~~~~~ More Below MM<
EF1 DDDDDDDDDDDDD?ZDF2 DDDDDDDDDDDDD?ZDF3 DDDDDDDDDDDDD?ZDF4 DDDDDDDDDDDDD?
3      Help      33 Main Menu  33 Print      33 Previous  3
( DDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY

```

Row #4 - 21 min

Press the ENTER key to update the screen.
Specified Average Report MMM More Above MM;
Start Time: Tue Feb 2 18:00:40 1993 End Time: Tue Feb 2 18:27:00 1993 :
Unit #4 Capacity 18.000

Unit	Value	Unit	Value
Unit #4 Opacity	1.778	%	19:05
Unit #4 O2	0.000	%	
Unit #4 CO2	7.794	%	
Unit #4 CO ppm	200.778	ppm	
Unit #4 SO2 ppm	3.000	ppm	
Unit #4 NO ppm	51.111	ppm	
Unit #4 Fuel Input	159.050	MMBtu/Hr	
Unit #4 SO2 Emission Rate	0.007	Lbs/mmBTU	
Unit #4 CO Emission Rate	0.194	Lbs/mmBTU	
Unit #4 NOx Emission Rate	0.081	Lbs/mmBTU	
Unit #4 SO2 Mass Emission	1.055	Lbs/Hr	
Unit #4 CO Mass Emission	30.806	Lbs/Hr	
Unit #4 NOx Mass Emission	12.927	Lbs/Hr	

```

12.927 Cbs/Hr
:
:
1 DDDDDDDDDDDDD?ZF2 DDDDDDDDDDDDD?ZF3 DDDDDDDDDDDDD?ZF4 DDDDDDDDDDDDD? More Below MM<
3 Help 33 Main Menu 33 Print 33 Previous 3
6 DDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDY
-

```

- Run 5 - 21 min

IM Specified Average Report MMM More Above MM;
: Start Time: Tue Feb 2 ~~19:00~~:40 1993 End Time: Tue Feb 2 19:~~00~~~~40~~ 1993 :
: Unit #4 Opacity 19.11

Unit	Value	Unit
Unit #4 Opacity	1.790	%
Unit #4 O2	0.000	%
Unit #4 CO2	7.795	%
Unit #4 CO ppm	197.800	ppm
Unit #4 SO2 ppm	2.350	ppm
Unit #4 NO ppm	49.650	ppm
Unit #4 Fuel Input	159.050	MMBtu/Hr
Unit #4 SO2 Emission Rate	0.005	Lbs/mmBTU
Unit #4 CO Emission Rate	0.191	Lbs/mmBTU
Unit #4 NOx Emission Rate	0.079	Lbs/mmBTU
Unit #4 SO2 Mass Emission	0.827	Lbs/Hr
Unit #4 CO Mass Emission	30.383	Lbs/Hr
Unit #4 NOx Mass Emission	12.557	Lbs/Hr

Run 6 - 21 min

Press the ENTER key to update the screen.
e Report M

End Time: Tue Feb 2 ~~1993~~:30 1993

19.40

20:01

Run 7. 21 min

Press the ENTER key to update the screen.

Start Time: Tue Feb 2 ~~12:58~~:10 1993 End Time: Tue Feb 2 ~~12:58~~:40 1993

20:27

[illegible]

Run #8 - 21 min

Press the ENTER key to update the screen.

3DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY@DDDDDDDDDDDDDDDDDDY

Run #9 - 21 min

GENERAL MOTORS CORPORATION
CAE Project No: 6520

PERTINENT CERTIFICATIONS

5-7

VISIBLE EMISSIONS EVALUATION

This is to certify that

David Nasralla

did complete a course in the opacity method of determining visible emissions from sources as specified by Federal Reference Method "9" conducted by Carl Koontz & Associates of Nashville, Tennessee.

Carl Koontz
Course Moderator

Valparaiso, IN
Location

CARL KOONTZ & ASSOCIATES
of Nashville, Tennessee

This is to acknowledge that
DAVID NASRALLA
successfully participated in Visible Emissions
training on October 7, 1992
and is qualified to evaluate Visible Emissions
for a period of six (6) months from the date of
certification.

Carl Koontz
Instructor

GENERAL MOTORS CORPORATION
CAE Project No: 6520

CONTINUOUS EMISSIONS MONITOR CERTIFICATION

6-1

SM 8100 NO MONITOR
EX 4700 CO2 MONITOR
ZERO & CALIBRATION DRIFT REPORT

MAR 9 1993

FORT WAYNE ASSEMBLY
ROANOKE, INDIANA

UNIT 4 STACK

SM 8100 S/N 0361063
EX 4700 S/N 0360057

PREPARED FOR:

FORT WAYNE ASSEMBLY
12200 LAFAYETTE CENTER ROAD
ROANOKE, INDIANA 46783

MARCH 3, 1993

APPROVED BY:

Sullivan C. Bailey

TABLE OF CONTENTS

PAGE NUMBER

1.	INTRODUCTION	1
2.	INSTALLATION	1
3.	SUMMARY	1
4.	RESULTS	1
	A. CALIBRATION DRIFT TEST PERIOD.	1
	B. ZERO DRIFT AND CALIBRATION DRIFT	1 & 2
5.	TABLE 1 - PERFORMANCE TEST RESULTS	3
7.	LOG OF OPERATIONS	6
8.	TABLE 2 - ZERO & SPAN CAL. DRIFT TEST (NO)	7
9.	TABLE 3 - ZERO & SPAN CAL. DRIFT TEST (CO2)	8
10.	FIELD DATA	

I. INTRODUCTION

pH Environmental, Inc. was contracted by Fort Wayne Assembly to prepare a performance evaluation on a Lear Siegler SM8100 S/N 0361063 and Lear Siegler EX4700A S/N 0360057 with the Unicon 700 control unit S/N 0360064. The installations were made on Unit 4 Stack located at the Fort Wayne Assembly facility located in Roanoke, Indiana. The Calibration Drift test was performed in accordance with the emission monitoring requirements as promulgated on May 25, 1983, by the Environmental Protection Agency.* The Calibration Drift tests were conducted on February 19, 1993 throughout February 25, 1993. The instruments operated continuously throughout the calibration drift test period without maintenance or service.

II. INSTALLATION DESCRIPTION

The instruments were installed at the Fort Wayne Assembly plant on the Unit 4 Stack located at the Roanoke, Indiana facility. Further installation information can be obtained from the affected facility. The initial startup of the instruments was on December 16, 1992.

III. SUMMARY

Test results of the performance evaluation are presented on the following page. The test results clearly show that the Lear Siegler SM8100 Stack Gas Monitor and the Lear Siegler EX4700A are in conformance with Nitric Oxide and Carbon Dioxide requirements of the Performance Specifications 2 and 3- Performance Specifications and Specifications Test Procedures for Monitors of NO and CO2 from Stationary Sources.

IV. RESULTS

CALIBRATION DRIFT TEST PERIOD

The instruments operated continuously from February 19, 1993 through February 25, 1993 for a period of 168 hours. Federal Register specifications require a minimum operational period of 168 hours. Please see follow page titled " Log of Operations."

ZERO DRIFT and CALIBRATION DRIFT

Zero drift and calibration drift were tested in accordance with Paragraph 6 of Performance Specification 2 & 3. The SM8100 and EX4700A are designed to provide automatically timed zero and span calibration checked at selectable intervals throughout the calibration drift test period.

*Federal Register, Vol.48, No.102, May 25, 1983, 40 CFR 60 Appendix B.

ZERO DRIFT and CALIBRATION DRIFT cont'

Data for the zero and calibration drift tests were taken from the computer printout data of the instrument output during the period from February 19, 1993 throughout February 25, 1993. No adjustments were made during the 168 hour period calibration drift period since the drift limits were not exceeded. The CEMS calibration did not drift or deviate from any reference value by more than 2.5 percent of the span value for NO or by 0.5 percent of the CO2 reference. Please refer to the following pages for the results.

ZERO DRIFT & CALIBRATION DRIFT PERFORMANCE TEST RESULTS

	<u>EPA SPECIFICATIONS</u>	<u>RESULTS</u>
I. SM8100		NOX
Calibration Drift Test	ALL CD'S <2.5% OF SPAN VALUE	
ZERO DRIFT		.000%
SPAN DRIFT		.975%
II. EX4700A		CO2
Calibration Drift Test	ALL CD'S <0.5% OF SPAN VALUE	
ZERO DRIFT		.431%
SPAN DRIFT		.215%

LOG OF OPERATIONS

I. SM8100 (NO)

Date of Manufacture March 21, 1986

Initial Start-up December 16, 1992

	<u>DATE</u>	<u>TIME</u>
Start of CDTP	February 19, 1993	0705
End of CDTP	February 25, 1993	0705

II. EX4700A (CO2)

Date of Manufacture March 18, 1986

Initial Start-up December 16, 1992

	<u>DATE</u>	<u>TIME</u>
Start of CDTP	February 19, 1993	0705
End of CDTP	February 25, 1993	0705

TABLE 2

ZERO AND SPAN CALIBRATION DRIFT TEST

CUSTOMER: FORT WAYNE ASSEMBLY
12200 LAFAYETTE CENTER ROAD
ROANOKE, IN.

DATE: 3-3-93

INST S/N: 0361063

INST. LOCATION: UNIT 4 STACK

MODEL: LEAR SIEGLER SM8100

ANALYZER RANGE: 0 - 375 PPM
TEST PARAMETER: NO

OPERATOR: SULLIVAN C. BAILEY

INST. RANGE: 0 - 375 PPM
ZERO SETTING: 0

READING NUMBER	DATE	TIME	ZERO READING		ZERO DRIFT	
			INITIAL A	FINAL B	C=B-A	
DAY 1	02-19-93	0705	0	0	0	0
DAY 2	02-20-93	0705	0	0	0	0
DAY 3	02-21-93	0705	0	0	0	0
DAY 4	02-22-93	0705	0	0	0	0
DAY 5	02-23-93	0705	0	0	0	0
DAY 6	02-24-93	0705	0	0	0	0
DAY 7	02-25-93	0705	0	0	0	0
ARITHMETIC MEAN:					.000	0
CONFIDENCE COEF.					.000	
ZERO DRIFT:					.000	

UPSCALE VALUE 120 PPM

READING NUMBER	DATE	TIME	UPSCALE CAL READING		UPSCALE	CAL	
			INITIAL D	FINAL E	DRIFT F=E-D	DRIFT G=F-C	
DAY 1	02-19-93	0705	120	121	1	1	1
DAY 2	02-20-93	0705	120	120	0	0	0
DAY 3	02-21-93	0705	120	121	1	1	1
DAY 4	02-22-93	0705	120	120	0	0	0
DAY 5	02-23-93	0705	120	119	-1	-1	1
DAY 6	02-24-93	0705	120	119	-1	-1	1
DAY 7	02-25-93	0705	120	119	-1	-1	1
ARITHMETIC MEAN:						-.143	5
CONFIDENCE COEF:						.832	
CAL DRIFT:						.975	

TABLE 3

ZERO AND SPAN CALIBRATION DRIFT TEST

CUSTOMER: FORT WAYNE ASSEMBLY
12200 LAFAYETTE CENTER ROAD
ROANOKE, IN.

DATE: 3-3-93

INST S/N: 0360057

INST. LOCATION: UNIT 4 STACK

MODEL: LEAR SIEGLER EX4700A

ANALYZER RANGE: 0-20%
TEST PARAMETER: CO2

OPERATOR: SULLIVAN C. BAILEY

INST. RANGE: 0 - 20%
ZERO SETTING: 0

READING NUMBER	DATE	TIME	ZERO READING		ZERO DRIFT	
			INITIAL A	FINAL B	C=B-A	
DAY 1	02-19-93	0705	0	0	0	0
DAY 2	02-20-93	0705	0	0	0	0
DAY 3	02-21-93	0705	0	0	0	0
DAY 4	02-22-93	0705	0	.4	.4	.16
DAY 5	02-23-93	0705	0	.6	.6	.36
DAY 6	02-24-93	0705	0	.3	.3	.09
DAY 7	02-25-93	0705	0	.2	.2	.04
ARITHMETIC MEAN:					.214	.65
CONFIDENCE COEF.					.216	
ZERO DRIFT:					.431	

UPSCALE VALUE 16.8 %

READING NUMBER	DATE	TIME	UPSCALE CAL READING		UPSCALE DRIFT		CAL DRIFT	
			INITIAL D	FINAL E	F=E-D	G=F-C		
DAY 1	02-19-93	0705	16.8	16.7	0	0	0	
DAY 2	02-20-93	0705	16.8	16.8	0	0	0	
DAY 3	02-21-93	0705	16.8	16.8	0	0	0	
DAY 4	02-22-93	0705	16.8	16.8	0	-.16	.0256	
DAY 5	02-23-93	0705	16.8	16.8	0	-.36	.1296	
DAY 6	02-24-93	0705	16.8	16.8	0	-.09	.0081	
DAY 7	02-25-93	0705	16.8	16.8	0	-.04	.0016	
ARITHMETIC MEAN:						-.093	.1649	
CONFIDENCE COEF:						.122		
CAL DRIFT:						.215		

10. FIELD DATA

--- CEMS Calibration Report ---
General Motors

From 00:00 2/19/93 Through 23:59 2/19/93

Parameter	End Time	---Zero Calibration---				---Span Calibration---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:05	0.0	0.0	0.0	0.0	121.0	120.0	1.0	0.3
CO2 Unit #4	07:05	0.0	0.0	0.0	0.0	16.7	16.8	-0.1	-0.5
CO Unit #4	07:05	10.0	0.0	10.0	1.0	640.0	665.0	-25.0	-2.5
SO2 Unit #4	07:05	1.0	0.0	1.0	0.3	101.0	100.0	1.0	0.3
Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/20/93 Through 23:59 2/20/93

Parameter	End Time	---Zero Calibration---				---Span Calibration---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:05	0.0	0.0	0.0	0.0	120.0	120.0	0.0	0.0
CO2 Unit #4	07:05	0.0	0.0	0.0	0.0	16.8	16.8	0.0	0.0
CO Unit #4	07:05	0.0	0.0	0.0	0.0	655.0	665.0	-10.0	-1.0
SO2 Unit #4	07:05	1.0	0.0	1.0	0.3	101.0	100.0	1.0	0.3
Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/21/93 Through 23:59 2/21/93

Parameter	End Time	---Zero Calibration---				--- Span Calibration ---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:05	0.0	0.0	0.0	0.0	121.0	120.0	1.0	0.3
CO2 Unit #4	07:05	0.0	0.0	0.0	0.0	16.8	16.8	0.0	0.0
CO Unit #4	07:05	0.0	0.0	0.0	0.0	669.0	665.0	4.0	0.4
SO2 Unit #4	07:05	0.0	0.0	0.0	0.0	101.0	100.0	1.0	0.3
Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/23/93 Through 23:59 2/23/93

Parameter	End Time	---Zero Calibration---				--- Span Calibration ---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:04	0.0	0.0	0.0	0.0	119.0	120.0	-1.0	-0.3
CO2 Unit #4	07:04	0.6	0.0	0.6	3.0	16.8	16.8	0.0	0.0
CO Unit #4	07:04	35.0	0.0	35.0	3.5	651.0	665.0	-14.0	-1.4
SO2 Unit #4	07:04	1.0	0.0	1.0	0.3	100.0	100.0	0.0	0.0
Opac #4	07:05	0.0	0.0	0.0	0.0	35.0	34.6	0.4	0.4
NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/24/93 Through 23:59 2/24/93

		---Zero Calibration---					--- Span Calibration ---				
		End			drift	drift			drift	drift	
P	Parameter	Time	Value	Std.	(abs)	(%FS)	Value	Std.	(abs)	(%FS)	
C	NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
C	CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
C	CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
D	SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
E	Opac #3	00:00	No Zero Cal Today				No Span Cal Today				
	NO Unit #4	07:04	0.0	0.0	0.0	0.0	119.0	120.0	-1.0	-0.3	
C	CO2 Unit #4	07:04	0.3	0.0	0.3	1.5	16.8	16.8	0.0	0.0	
S	CO Unit #4	07:04	34.0	0.0	34.0	3.4	640.0	665.0	-25.0	-2.5	
	SO2 Unit #4	07:04	1.0	0.0	1.0	0.3	101.0	100.0	1.0	0.3	
	Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3	
C	NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
C	CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
C	CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
D	SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
E	Opac #5	00:00	No Zero Cal Today				No Span Cal Today				

--- CEMS Calibration Report ---
General Motors

From 00:00 2/25/93 Through 23:59 2/25/93

Parameter	End Time	---Zero Calibration---				---Span Calibration---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:04	0.0	0.0	0.0	0.0	119.0	120.0	-1.0	-0.3
CO2 Unit #4	07:04	0.2	0.0	0.2	1.0	16.8	16.8	0.0	0.0
CO Unit #4	07:04	0.0	0.0	0.0	0.0	646.0	665.0	-19.0	-1.9
SO2 Unit #4	07:04	0.0	0.0	1.0	0.3	101.0	100.0	1.0	0.3
Opac #4	07:04	1.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
NO Unit #5	07:05	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

GENERAL MOTORS CORPORATION
CAE Project No: 6520

CONTINUOUS OPACITY MONITOR CERTIFICATION

7-1

RM 4200 OPACITY
CERTIFICATION REPORT

FORT WAYNE ASSEMBLY
ROANOKE, INDIANA

UNIT 4 STACK MONITOR
RM 4200 S/N 15603804

PREPARED FOR:

FORT WAYNE ASSEMBLY
12200 LAFAYETTE CENTER ROAD
ROANOKE, INDIANA 46783

MARCH 3, 1993

APPROVED BY:

Sullivan C Bailey

TABLE OF CONTENTS

	PAGE NUMBER
1. INTRODUCTION	1
2. INSTALLATION	1
3. ALIGNMENT	1
4. SUMMARY	1
5. DISCUSSION OF RESULTS	2
A. OPTICAL DESIGN PARAMETERS.	2
B. CALIBRATION ERROR.	3
C. ZERO AND SPAN CALIBRATION DRIFT.	3
D. RESPONSE TIME.	3
E. CONDITIONING PERIOD.	4
F. OPERATING TEST PERIOD.	4
6. TABLE 1 - PERFORMANCE TEST RESULTS	5
7. NOTICE OF FIELD CERTIFICATION.	6
8. TABLE 2 - ZERO & SPAN CALIBRATION DRIFT TEST	7
A. FIELD DATA	
9. NOTICE OF FACTORY CERTIFICATION	

1. INTRODUCTION:

pH Environmental Service was contracted by Fort Wayne Assembly to prepare a performance evaluation on a Lear Siegler RM 4200 Opacity Monitor S/N 15603804 . The installation was on the Unit 4 stack. Zero and Calibration drift, calibration error, and response time were quantified. The certification was performed in accordance with the emission monitoring requirements as promulgated on March 30, 1983, by the Environmental Protection Agency.* Field test were performed continuously throughout the conditioning period and the operational test period without maintenance or service.

2. INSTALLATION DESCRIPTION AND START-UP:

The instrument is installed on the Unit 4 Stack located at the Roanoke, In. facility. The instrument is designed so an operator can swing open the transceiver and retroreflector to gain access to the external optics for cleaning. Further installation information can be obtained from the affected facility.

3. ALIGNMENT:

The RM 4200 is equipped with an optical window on the case side. Viewing through an optical bull's eye through the window, it is possible to verify and, if necessary, adjust the instrument alignment at any time during operation. Using the alignment window, an operator sights across the stack to the reflector. By turning the alignment bolts located on the flange as mounting hardware, an operator can center the reflector in the light beam using the bull's eye target as a guide. When using the alignment target, the operator must position the mode switch to "align." When the light spot is within the outer bull's eye ring the instrument is aligned for optimum accuracy.

4. SUMMARY:

Test results of the Performance Evaluation are presented on Page 5. These results are based on data obtained at Lear Siegler's production facility located at Englewood, CO and during normal operation following installation at the affected facility. Documentation and test data are found in the Appendix.

These results indicate that Lear Siegler RM 4200 Opacity Monitors are in conformance with all requirements of "Performance Specifications 1 - Performance Specifications Test Procedures for Monitors of Opacity from Stationary Sources."

* Federal Register, Vol.48, No 62, Part II, March 30, 1983, 40 CFR 60, Appendix B.

5. DISCUSSION OF RESULTS:

A. Optical Design Parameters. Paragraph 6.5 of performance Specification 1 pertaining to transmissometer systems specifies that one analyzer from each month's production must be tested by the manufacturer and shown to meet certain design specifications projections, and optical alignment sight. The serial number and production date (final testing) of the instrument used for this purpose is provided on the " Notice of Factory Certification" in the Appendix.

The detector, lamp, and filter used in the RM 4200 Transmissiometer are manufactured by a single supplier. In order to provide more accurate and meaningful data, the spectral response parameters have been determined from a composite spectral response curve of three components determined at the instrument manufacture facility, rather than separate curves for each component. The peak and mean spectral response values are given:

Peak Spectral Response 580.0 nm

Mean Spectral Response 584.16 nm

Percent Response Below 4.00%
400nm/above 700nm

Federal Register specifications require that the peak and mean spectral response fall between 500nm and 600nm, with response at any wavelength below 400nm or above 700nm less than 10 percent of the peak response.

To measure the angle of view for the RM 4200 transceiver was set up, calibrated, and placed on a gimballed test fixture facing a small light source at the other end of the monitor path length. The detector output of the subject transceiver was measured and recorded at the gimbal zero at 1/2 degree increments up, to the right, and to the left.

The angle of view and the angle of projection test results are given below:

Angle of View 4.0 degrees

Angle of Projection 3.0 degrees

Federal Register specifications require that both the angle of view and the angle of projection be no greater than 5 degrees. Additional test data are to be found in the Appendix.

Optical alignment was checked and found to be accordance with Paragraph 6.4 of Performance Specification 1.

B. Calibration Error. The Calibration Error Test was performed in accordance with Paragraph 7.1.4 of the referenced specifications at Lear Siegler facility prior to shipment. Low, Mid and High range calibration filter were used. Fifteen nonconsecutive tests were made with the calibration filters using the three calibration filters (Five readings with each filter). The calibration error is represented by the sum of the mean differences plus 95% confidence interval expressed as a percentage of the known filter value. The initial certification of the neutral density filter was performed by National Bureau of standards. The results are shown on page 5. The test results are a 0.80% error at the low range, 0.80% at the mid range, and 1.417% at the high range. Federal Register specifications limit the allowable error to 3%.

C. Zero Drift and Calibration Drift. Zero Drift and Calibration Drift were tested in accordance with Paragraph 7.4 of Performance Specification 1. The RM 4200 Opacity Monitor is designed to provide automatically timed zero and span calibration checks every twenty-four hours throughout both the conditioning test period and operational test period. The zero value is determined by mechanically simulating a clear stack condition, thereby producing a zero condition that checks the analyzer, internal mirrors, and all electronic circuitry including the radiation source and detector assembly. The span of the system is checked with a calibration filter equivalent to an upscale opacity condition.

Data for the zero and calibration drift were taken from the field data of the instrument output during the period from February 19 through February 25, 1993. Adjustments were not made during the drift test. Twenty-four (24) hour results were calculated by taking the difference between consecutive calibration readings. Results of the zero and calibration drift test are:

T e s t	DRIFT IN % SPAN
Zero Drift (24 hours)	.000%
Calibration Drift (24 hours)	.349%

The drift is represented as an error term of the mean drift plus 95% confidence interval of the drift terms, expressed as percentage of opacity. Refer to Table II (page 7) for test results.

Federal Register specifications direct the twenty-four (24) calibration drift to be less than or equal to 2% opacity.

D. Response Time. Instrument response time was tested on March 13, 1986 in accordance with Paragraph 7.1.5 Performance Specification 1. Five upscale and five down scale readings were recorded. The average response time was 5.00 seconds. Federal Register specifications limit the response time to 10 seconds or less.

E. Conditioning Period. The RM 4200 transmissometer system was operated in accordance with Paragraph 7.3 for an initial 168 hour conditioning period from February 12 through February 18, 1993.

F. Operational Period. The operational period is defined as a "minimum period of time over which the continuous monitoring system is expected to operate within certain performance specifications without unscheduled maintenance, repair, or adjustment."

The instrument operated continuously in accordance with Paragraph 7.4 from February 19 through February 25, 1993 for a total of 168 hours. Federal Register specification requires a minimum operational period of 168 hours.

T A B L E 1
 PERFORMANCE TEST RESULTS
 RM 4200 S/N 15603804

	RESULTS	EPA SPECIFICATIONS
PEAK SPECTRAL RESPONSE	580.0 nm	>500 - <600 nm
MEAN SPECTRAL REAPONSE	584.16 nm	>500 - <600 nm
PERCENT RESPONSE BELOW 400 nm - ABOVE 700 nm	4.0 %	< 10 %
ANGLE OF VIEW, DEGREES	4.0	< 5.0
ANGLE OF PROJECTION, DEGREES	3.0	< 5.0
CALIBRATION ERROR: LOW	0.80 %	< 3 %
MID	0.80 %	< 3 %
HIGH	1.417 %	< 3 %
CONDITIONING PERIOD	168 HOURS	168 HOURS
OPERATIONAL TEST PERIOD	168 HOURS	168 HOURS
ZERO DRIFT (24 HOUR)	0.000 %	< 2 %
SPAN DRIFT (24 HOUR)	0.349 %	< 2 %
RESPONSE TIME	5.00 seconds	< 10 seconds

NOTICE OF FIELD CERTIFICATION

RM 4200

Certification is hereby given that the Lear Siegler visible emission monitoring system described below has been tested and satisfactorily evaluated in accordance with EPA on-site testing requirements, CFR, Title 40; Part 60, Appendix B, Specification 1, as promulgated in the March 1983 Federal Register, No.62, Vol.48, Part II. The instrument drift and calibration drift (24 hour) have been evaluated in accordance with Paragraph 7.4 and have been shown to meet specification. Copies of the attached certified test data can be submitted to the appropriate regulatory agency in compliance with Source Performance Monitoring requirements. Additional copies are available, by request, from pH Environmental Service.

In addition to the above field performance test data, several factory performance tests must be performed to verify design specifications, calibration error, and response time as defined in the reference specification (Paragraph 7). The factory performance test data should be reviewed before commencing with Field Performance Tests.

CUSTOMER: FORT WAYNE ASSEMBLY LOCATION: ROANOKE, IN.

TRANSMISSOMETER MODEL: RM 4200 S/N: 15603804

REFLECTOR MODEL: RM 4200 S/N: 15603804

OPACITY MEASUREMENT RANGE (Stack Exit): 0-100%

OPACITY RECORDER OUTPUT LEVEL: TO UNICON 700, RECORDED AT D.A.S.

CERTIFICATIONS	RESULTS	STANDARDS
ZERO DRIFT (24 HOUR)	.000 OPACITY	<2.0% OPACITY
CALIBRATION DRIFT (24 HOUR)	.349 OPACITY	<2.0% OPACITY
CONDITIONING PERIOD	168 HOUR	168 HOUR
OPERATIONAL TEST PERIOD	168 HOUR	168 HOUR

TEST PERFORMED BY: Sullivan & Bailey DATE: 2-27-93

TEST REVIEWED BY: Sullivan & Bailey DATE: 3-3-93

T A B L E 2

ZERO AND SPAN CALIBRATION DRIFT TEST

CUSTOMER: FORT WAYNE ASSEMBLY
12200 LAFAYETTE CENTER ROAD
ROANOKE, IN.

DATE: 3-3-93

INST S/N:15603804

INST. LOCATION: UNIT 4 STACK

MODEL: LEAR SIEGLER RM4200

ANALYZER RANGE: 0 - 100 %
TEST PARAMETER: OPACITY

OPERATOR: SULLIVAN C. BAILEY

INST. RANGE: 0 - 100%
ZERO SETTING: 0

READING NUMBER	DATE	TIME	ZERO READING		ZERO DRIFT C=B-A	
			INITIAL A	FINAL B		
DAY 1	02-19-93	0705	0	0	0	0
DAY 2	02-20-93	0705	0	0	0	0
DAY 3	02-21-93	0705	0	0	0	0
DAY 4	02-22-93	0705	0	0	0	0
DAY 5	02-23-93	0705	0	0	0	0
DAY 6	02-24-93	0705	0	0	0	0
DAY 7	02-25-93	0705	0	0	0	0
ARITHMETIC MEAN:					.000	0
CONFIDENCE COEF.					.000	
ZERO DRIFT:					.000	

UPSCALE VALUE 34.6%

READING NUMBER	DATE	TIME	UPSCALE CAL READING		UPSCALE DRIFT F=E-D	CAL DRIFT G=F-C	
			INITIAL D	FINAL E			
DAY 1	02-19-93	0705	34.6	34.9	.3	.3	.09
DAY 2	02-20-93	0705	34.6	34.9	.3	.3	.09
DAY 3	02-21-93	0705	34.6	34.9	.3	.3	.09
DAY 4	02-22-93	0705	34.6	34.9	.3	.3	.09
DAY 5	02-23-93	0705	34.6	35	.4	.4	.16
DAY 6	02-24-93	0705	34.6	34.9	.3	.3	.09
DAY 7	02-25-93	0705	34.6	34.9	.3	.3	.09
ARITHMETIC MEAN:						.314	.7
CONFIDENCE COEF:						.035	
CAL DRIFT:						.349	

A. FIELD DATA

--- CEMS Calibration Report ---
General Motors

From 00:00 2/19/93 Through 23:59 2/19/93

Parameter	End Time	---Zero Calibration---				--- Span Calibration ---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:05	0.0	0.0	0.0	0.0	121.0	120.0	1.0	0.3
CO2 Unit #4	07:05	0.0	0.0	0.0	0.0	16.7	16.8	-0.1	-0.5
CO Unit #4	07:05	10.0	0.0	10.0	1.0	640.0	665.0	-25.0	-2.5
SO2 Unit #4	07:05	1.0	0.0	1.0	0.3	101.0	100.0	1.0	0.3
Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/20/93 Through 23:59 2/20/93

Parameter	End Time	---Zero Calibration---				---Span Calibration---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
O2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
O2 Unit #3	00:00	No Zero Cal Today				No Span Cal Today			
Opac #3	00:00	0.0	0.0	0.0	0.0	120.0	120.0	0.0	0.0
NO Unit #4	07:05	0.0	0.0	0.0	0.0	16.8	16.8	0.0	0.0
O2 Unit #4	07:05	0.0	0.0	0.0	0.0	655.0	665.0	-10.0	-1.0
CO Unit #4	07:05	0.0	0.0	0.0	0.0	101.0	100.0	1.0	0.3
SO2 Unit #4	07:05	1.0	0.0	1.0	0.3	34.9	34.6	0.3	0.3
Opac #4	07:05	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
O2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/21/93 Through 23:59 2/21/93

Parameter	End Time	---Zero Calibration---				--- Span Calibration ---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:05	0.0	0.0	0.0	0.0	121.0	120.0	1.0	0.3
CO2 Unit #4	07:05	0.0	0.0	0.0	0.0	16.8	16.8	0.0	0.0
CO Unit #4	07:05	0.0	0.0	0.0	0.0	669.0	665.0	4.0	0.4
SO2 Unit #4	07:05	0.0	0.0	0.0	0.0	101.0	100.0	1.0	0.3
Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/22/93 Through 23:59 2/22/93

Parameter	End Time	---Zero Calibration---				--- Span Calibration ---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:05	0.0	0.0	0.0	0.0	120.0	120.0	0.0	0.0
CO2 Unit #4	07:05	0.4	0.0	0.4	2.0	16.8	16.8	0.0	0.0
CO Unit #4	07:05	30.0	0.0	30.0	3.0	663.0	665.0	-2.0	-0.2
SO2 Unit #4	07:05	0.0	0.0	0.0	0.0	100.0	100.0	0.0	0.0
Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/23/93 Through 23:59 2/23/93

Parameter	End Time	---Zero Calibration---				---Span Calibration---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:04	0.0	0.0	0.0	0.0	119.0	120.0	-1.0	-0.3
CO2 Unit #4	07:04	0.6	0.0	0.6	3.0	16.8	16.8	0.0	0.0
CO Unit #4	07:04	35.0	0.0	35.0	3.5	651.0	665.0	-14.0	-1.4
SO2 Unit #4	07:04	1.0	0.0	1.0	0.3	100.0	100.0	0.0	0.0
Opac #4	07:05	0.0	0.0	0.0	0.0	35.0	34.6	0.4	0.4
NO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/24/93 Through 23:59 2/24/93

Parameter	End Time	---Zero Calibration---				--- Span Calibration ---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
NO Unit #3:	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3:	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3:	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3:	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4:	07:04	0.0	0.0	0.0	0.0	119.0	120.0	-1.0	-0.3
CO2 Unit #4:	07:04	0.3	0.0	0.3	1.5	16.8	16.8	0.0	0.0
CO Unit #4:	07:04	34.0	0.0	34.0	3.4	640.0	665.0	-25.0	-2.5
SO2 Unit #4:	07:04	1.0	0.0	1.0	0.3	101.0	100.0	1.0	0.3
Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
NO Unit #5:	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5:	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5:	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5:	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

--- CEMS Calibration Report ---
General Motors

From 00:00 2/25/93 Through 23:59 2/25/93

Parameter	End Time	---Zero Calibration---				---Span Calibration---			
		Value	Std.	drift (abs)	drift (%FS)	Value	Std.	drift (abs)	drift (%FS)
IO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #3	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #3	00:00	No Zero Cal Today				No Span Cal Today			
NO Unit #4	07:04	0.0	0.0	0.0	0.0	119.0	120.0	-1.0	-0.3
CO2 Unit #4	07:04	0.2	0.0	0.2	1.0	16.8	16.8	0.0	0.0
IO Unit #4	07:04	0.0	0.0	0.0	0.0	646.0	665.0	-19.0	-1.9
SO2 Unit #4	07:04	1.0	0.0	1.0	0.3	101.0	100.0	1.0	0.3
Opac #4	07:05	0.0	0.0	0.0	0.0	34.9	34.6	0.3	0.3
IO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
CO Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
SO2 Unit #5	00:00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Opac #5	00:00	No Zero Cal Today				No Span Cal Today			

9. NOTICE OF FACTORY CERTIFICATION

NOTICE OF FACTORY CERTIFICATION - RM41/RM4100

Certification is hereby given that the Lear Siegler Visible Emission Monitoring System described below has been tested and satisfactorily evaluated in accordance with EPA requirements, CFR, Title 40, Part 60, Appendix B, Specification 1, as promulgated in the March 30, 1983 Federal Register, Vol. 48, No. 62. Calibration error and response time has been evaluated according to procedures defined in paragraph seven and have been shown to meet specification. Design specifications, which include peak spectral response, mean spectral response, angle of view, angle of projection and optical alignment sight, meet stated requirements. Copies of the attached certified data can be submitted to the appropriate regulatory agency in compliance with source performance monitoring requirements. Additional copies are available, by request, from LSI.

In addition to the above factory test data, additional on-site operational performance tests must be performed as defined in the referenced specification (Para. 8.2) to complete specified EPA source performance monitoring requirements.

Customer HONEYWELL / GM Location: ROANOKE, IND.

Transmissometer Model RM4200 S/N 15603804

Reflector Model RM 4200 S/N 15603804

Converter Model UNION 700 S/N 0360064 Output 4-20 mA

Separation Distance, Transceiver Flange to Reflector Flange 6 ft.
6 in.

* Recorder Model N/A S/N _____

- * If recorder is supplied with opacity monitoring system, transmissometer and recorder are to be kept together as a system.

<u>CERTIFICATION TEST</u>	<u>EPA SPECIFICATION</u>	<u>RESULTS</u>
Performance Specifications		
Calibration error % opacity	<u><3</u> % Low	<u>.8</u> % Low
Calibration error % opacity	<u><3</u> % Mid	<u>.8</u> % Mid
Calibration error % opacity	<u><3</u> % High	<u>1.417</u> % High
Response Time	<u><10</u> Seconds	<u>5.0</u> Seconds

FACTORY CERTIFICATION

RM41

SPECTRAL RESPONSE

For the purposes of demonstrating conformance with the spectral response requirements, a composite spectral response curve (Data Sheet 1.1) of the Tungsten light source shaping filter and photodetector was obtained from Lear Siegler's facility. This curve shows the peak spectral response of the tested unit. The curve also shows a relative response less than 10 percent of peak response above 700nm and below 400nm. Data Sheet 1.2 shows calculation of the mean spectral response of the tested unit. All of the above parameters are well within the referenced specification (Paragraph 6.1). These parameters are primarily a function of basic optical component design and are not subject to any significant variation within the basic RM41/4100 design.

ANGLE-OF-VIEW AND ANGLE-OF-PROJECTION

Procedure: Place the transceiver on the Gimballed test fixture and set both vertical and horizontal readings at zero. With the transceiver mounted on the Gimballed head, set up and calibrate the RM41 measurement system for 3 meter pathlength and span (range) to be used in the installation. Replace the reflector unit with a second transceiver unit.

Angle-of-View Record the detector output of the subject transceiver at the Gimbal zero setting and at every 1/2 degree increment up to 2.5 degrees up, down, to the left and to the right of zero. Record the results on Data Sheet 1.3. Record the lowest angle in each direction which results in a detector output of zero. Add the two vertical readings, add the two horizontal readings and record the greater of the two sums as the system angle-of-view on Data Sheet 1.3 and on the Notice of Certification.

Angle-of-Projection Record the output of the secondary transceiver (at reflector location) with the subject transceiver at the Gimbal zero setting and at every 1/2 degree increments up to 2.5 degrees up, down, to the right and to the left of zero. Record the results on Data Sheet 1.3. Record the lowest angle in each direction which results in a detector output of zero. Add the two vertical readings, add the two horizontal readings, and record the greater of the two sums and the system angle of projection on Data Sheet 1.3 and on the Notice of Certification. Also record the date of testing.

CALIBRATION ERROR AND RESPONSE TIME TESTS

The calibration error test and the response time test must be performed prior to installation of the opacity monitoring system on the stack. The results of these tests reflect the stack installation parameters and the entire continuous monitoring system (transceiver, control unit, and data recorder). It is, therefore, required that the instrument system be set up for the monitor pathlength and full scale span to be used in the installation.

CALIBRATION ERROR TEST

Procedure: Set up and calibrate the RM41 measurement system for the monitor pathlength and span (range) to be used in the installation. Place the calibration filter assembly into the transmissometer path midway between the transceiver and the reflector. Position the filter assembly so that the projected beam passes unobstructed through the frame at an angle of 3 degrees to the normal of the filter surfaces. The 3 degree angle is important since a lesser angle may result in unwanted surface reflections and a greater angle can result in a significant neutral density error. Alternately insert the low, mid, and high range neutral density filters (the values of which must be determined from Table 1.A) into the light path according to the following sequence: low, high, mid, high, low, mid, high, mid, low, high, mid, low, mid, high and low. This sequence yields five non-consecutive readings of each filter (a total of 15 readings). Record the measurement system output readings in percent opacity on Data Sheet 1.4. Subtract the known filter opacity value from the value shown by the measurement system for each of the 15 readings and record the differences. Use the arithmetic sum of these difference values to calculate the mean difference and the 95 percent confidence interval of the five readings at each test filter value using the equations on Data Sheet 1.5. Record the sum (in percent opacity) of the mean difference and the 95 percent confidence interval for each of the three test filters on the Data Sheet and on the Notice of Certification. Also record the date of testing.

RESPONSE TIME TEST

Using the apparatus and configuration described in the calibration error test, insert the high range filter into the transmissometer path five times. Record the upscale and downscale time intervals required for the system to respond to 95 percent of the final (stable) high range filter and zero values on Data Sheet 1.5. Calculate the mean of the ten response time values and record it on the Data Sheet and on the Notice of Certification. Also record the date of testing.

OPTICAL ALIGNMENT SIGHT TEST

Procedures: Place the transceiver on the Gimballed test fixture and set both horizontal and vertical readings at zero. With the transceiver mounted on the Gimballed head, set up and calibrate the RM41/4100 measurement system for an 8 meter pathlength (26'-3"). Establish zero current and record as reference value before starting misalignment procedure.

Rotational Misalignment: Place a neutral density filter close to 10% opacity in light path and record transceiver output. Using the horizontal adjustment, slowly rotate transceiver until the transceiver output changes 2% opacity. Check the alignment bulls-eye and verify it indicates misalignment. Return horizontal reading to zero; alignment zero should result in same zero current as initially determined.

Lateral Misalignment: Place a neutral density filter close to 10% opacity light path and record transceiver output. Slowly move reflector stand laterally until the transceiver output changes 2% opacity. Check the transceiver alignment bulls-eye and verify it indicates misalignment.

FACTORY CERTIFICATION

DOCUMENTATION

RM41/4100

Effective Date: September 1983

NOTICE OF CERTIFICATION AND TABULATED RESULTS

NOTES ON:

CALIBRATION FILTER SELECTION

SPECTRAL RESPONSE

ANGLE OF VIEW

ANGLE OF PROJECTION

CALIBRATION ERROR TEST

RESPONSE TIME TEST

OPTICAL ALIGNMENT SIGHT TEST

CERTIFICATION DATA:

DATA SHEET 1.1 RM41/4100 COMPOSITE SPECTRAL RESPONSE CURVE

DATA SHEET 1.2 MEAN SPECTRAL RESPONSE CALCULATIONS

DATA SHEET 1.3 ANGLE OF PROJECTION, ANGLE OF VIEW & OPTICAL
ALIGNMENT

DATA SHEET 1.4 CALCULATION FORM

DATA SHEET 1.5 RESPONSE TIME TEST

RECORDER TRACES OF CALIBRATION ERROR TEST AND RESPONSE TIME TESTS

Design Specifications

In accordance with Paragraph 6.5 of the referenced specifications, one analyzer from each month's production was tested per Sections 6.1 through 6.4 and satisfactorily met all Design Specifications of Section 5. Listed below are the results of the monthly unit tested for Design Specifications:

TEST UNIT S/N 1530600C Date of Test 3/3/86

EPA SPECIFICATION

RESULTS

Peak Spectral Response	<u>500-600 nm</u>	<u>580 nm</u>
Mean Spectral Response	<u>500-600 nm</u>	<u>584.16 nm</u>
Angle of View	<u>≤5 degrees</u>	<u>4.0 degrees</u>
Angle of Projection	<u>≤5 degrees</u>	<u>3.0 degrees</u>

Optical Alignment



Pass



Fail

Test Performed By: Mark Higgins Date 3/13/86

Test Reviewed By: [Signature] Date 3/13/86

RM 41/4220 SPECTRAL RESPONSE DATA SHEET

SERIAL # 15506006

OPERATOR MARK HIGGINS

DATE MARCH 3, 1966

A	B	C	D	E	F	G	H
400 nm	0.00	0.00	0.00	1.69	0.00	0.00	0.00
420 nm	0.00	0.00	0.00	1.49	0.00	0.00	0.00
440 nm	0.00	0.00	0.00	1.25	0.00	0.00	0.00
460 nm	0.18	0.00	0.18	1.12	0.00	0.00	0.00
480 nm	0.47	0.00	0.47	1.06	0.00	0.00	18.60
500 nm	1.00	0.00	1.00	1.00	0.00	0.10	48.80
520 nm	1.97	0.00	1.97	1.00	1.00	0.20	160.40
540 nm	3.17	0.00	3.17	1.02	1.97	2.40	208.70
560 nm	4.22	0.00	4.22	1.04	3.23	0.60	350.60
580 nm	4.61	0.00	4.61	1.08	4.47	0.90	501.10
600 nm	4.17	0.00	4.17	1.12	4.98	1.00	500.20
620 nm	3.25	0.00	3.25	1.14	4.67	0.94	562.80
640 nm	2.14	0.00	2.14	1.19	3.71	0.74	461.30
660 nm	1.20	0.01	1.19	1.23	2.85	0.51	327.30
680 nm	0.66	0.00	0.57	1.23	1.46	0.29	194.00
700 nm	0.42	0.00	0.22	1.25	0.72	0.14	55.70
					0.28	0.06	30.60

TOTALS 5.97 3486.60

MEAN RESPONSE = 504.10


PEAK RESPONSE = 580

SYMBOLS:

- A = Monochromator setting
 - B = Test Output of the subject unit
 - C = Dark Output of the subject unit
 - D = Difference
 - E = Multiplier
 - F = Largest product from equation $D \times E$
 - G = Relative transmission $(D \times E / F)$
 - H = Product of $G \times A$
- Peak Response = Monochromator setting where $G = 1$

SPECTRAL RESPONSE

MARCH 1966



— S/N 15506006

DATA SHEET 1.3

INSTRUMENT S/N 15506006 DATE: 313 182 OPERATOR: MARK HIGGINS

ANGLE-OF-PROJECTION TEST

DIRECTION	ANGLE 0.0	0.5	1.0	1.5	2.0	2.5	LOWEST WITH ZERO READING
UP	20.00	15.43	4.35	0.00	0.00	0.00	A 1.5
DOWN	20.00	9.05	0.10	0.00	0.00	0.00	B 1.5
LEFT	20.00	9.01	0.41	0.00	0.00	0.00	C 1.5
RIGHT	20.00	14.15	2.47	0.00	0.00	0.00	D 1.5

VERTICAL ANGLE-OF-PROJECTION (A+B) = 3.0

HORIZONTAL ANGLE-OF-PROJECTION (C+D) = 3.0

SYSTEM ANGLE-OF-PROJECTION (GREATER OF THE TWO) = 3.0

ANGLE-OF-VIEW TEST

DIRECTION	ANGLE 0.0	0.5	1.0	1.5	2.0	2.5	LOWEST WITH ZERO READING
UP	20.00	19.41	11.68	0.43	0.00	0.00	A 2.0
DOWN	20.00	19.05	11.44	0.57	0.00	0.00	B 2.0
LEFT	20.00	19.58	17.77	7.27	0.00	0.00	C 2.0
RIGHT	20.00	19.39	15.48	2.92	0.00	0.00	D 2.0

VERTICAL ANGLE-OF-VIEW (A+B) = 4.0

HORIZONTAL ANGLE-OF-VIEW (C+D) = 4.0

SYSTEM ANGLE-OF-VIEW (GREATER OF THE TWO) = 4.0

OPTICAL ALIGNMENT SIGHT TEST

ROTATIONAL ALIGNMENT

☒ Pass

☐ Fail

LATERAL ALIGNMENT

☒ Pass

☐ Fail

CALIBRATION FILTER SELECTION

To calculate which neutral density filters to use, multiply the full scale value (in percent opacity) by 0.2, 0.6, and 0.9 for the low, mid, and high filter values respectively, to obtain the simulated stack-exit opacity ($OP_{stack\ exit}$). Then calculate the filter values in optical density using the following equation:

$$O.D. \text{ filter} = \left(\frac{0.5}{OPLR} \right) \left(\log_{10} 1 - \frac{OP_{stack\ exit}}{100} \right)$$

Where:

$$OPLR = \frac{\text{Stack exit ID}}{2 (\text{Installation ID})} = \frac{.5}{5'6''}$$

$$\text{Stack exit ID} = \frac{5'6''}{5'6''}$$

$$\text{Installation ID} = \frac{5'6''}{5'6''}$$

Record the three calculated filter values in optical density in Table 1A.

TABLE 1A

Low Filter .097 O.D.

Mid Filter .398 O.D.

High Filter 1.000 O.D.

Select the filter values which most closely match the calculated values and record their optical density values in Table 1B.

Then calculate the corresponding stack exit opacity ($OP_{stack\ exit}$) for each filter using the following equation and record the resultant stack exit opacity values in the last column below.

$$OP_{stack\ exit} = 100 \left[1 - 10^{(-2 \text{ O.D.}) (OPLR)} \right]$$

Where O.D. is the optical density of the calibration filter.

Table 1B shows the actual filters used.

TABLE 1B

Low Filter	<u>.132</u>	O.D.	<u>26.2</u>	% Opacity	<u> </u>	S/N
Mid Filter	<u>.412</u>	O.D.	<u>60.4</u>	% Opacity	<u> </u>	S/N
High Filter	<u>.99</u>	O.D.	<u>99.5</u>	% Opacity	<u> </u>	S/N

DATA SHEET 1.4

CALIBRATION ERROR TEST

Instrument S/N 1-203804 Date: 3/13/86 Operator: MARK HIGGINS
 Analyser Range 0-100 % Opacity OPLR Value 5

LOW FILTER 26.2 % Opacity

Filter	Reading
1 Zero	0
2 Low	27.0
3 High	90.6
4 Mid	61.2
5 High	91.0
6 Low	27.0
7 Mid	61.2
8 High	91.1
9 Mid	61.2
10 Low	27.0
11 High	91.1
12 Mid	61.2
13 Low	27.0
14 Mid	61.2
15 High	91.0
16 Low	27.0
17 Zero	0

Inst. Reading	Diff (Xi)	(Xi) ²
27.0	.8	.64
27.0	.8	.64
27.0	.8	.64
27.0	.8	.64
27.0	.8	.64
ΣXi = 4.0		ΣXi² = 3.2

Mean Diff = .8
 C.I. = 0
 Cal Error = .8

MID FILTER 60.4 % Opacity

Inst. Reading	Diff (Xi)	(Xi) ²
61.2	.8	.64
61.2	.8	.64
61.2	.8	.64
61.2	.8	.64
61.2	.8	.64
ΣXi = 4.0		ΣXi² = 3.2

Mean Diff = .8
 C.I. = 0
 Cal Error = .8

HIGH FILTER 89.8 % Opacity

Inst. Reading	Diff (Xi)	(Xi) ²
90.6	.8	.64
91.0	1.2	1.44
91.1	1.3	1.69
91.1	1.3	1.69
91.0	1.2	1.44
ΣXi = 5.8		ΣXi² = 6.9

Mean Diff = 1.16
 C.I. = .257
 Cal Error = 1.417

Mean Diff = [ΣX_i] / 5

C.I. = $0.2776 \sqrt{5(\Sigma X_i^2) - (\Sigma X_i)^2}$

Cal Error = Mean Diff + C.I.


C.I. = Confidence Interval

RM 41 / 4200 CERTIFICATION

RECORDER TRACES

S/N: 1560384

DATE: 3/13/80



RESPONSE TIME TEST

Date of Test 3/13/86 Operator MARK HIGGINS

Span Filter .45 % Opacity Instrument S/N 15603804

Analyzer Range 0-100 % Opacity

Upscale

1	<u>5.0</u>	seconds
2	<u>5.0</u>	seconds
3	<u>5.0</u>	seconds
4	<u>5.0</u>	seconds
5	<u>5.0</u>	seconds

Downscale

1	<u>5.0</u>	seconds
2	<u>5.0</u>	seconds
3	<u>5.0</u>	seconds
4	<u>5.0</u>	seconds
5	<u>5.0</u>	seconds

Average Response 5.0 seconds