

Note: This is a reference cited in *AP 42, Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/


The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP-42 Section Number: 1.8

Reference Number: 47

Title: Atlantic Sugar Association Particulate
Emissions Test Report Boiler #5

January 1991



Eastmount Engineering

Environmental Consultants — Air Quality Specialists

DSW1-ASA9

ATLANTIC SUGAR ASSOCIATION
COMPLIANCE PARTICULATE EMISSIONS TEST REPORT
BOILER #5

PREPARED FOR:

Atlantic Sugar Association
P.O. Box 1570
Belle Glade, Florida 33430

CONCERNING:

Particulate Emissions Testing
Atlantic Sugar Association
Boiler #5
Belle Glade, Florida Facility
January 10, 1991

PREPARED BY:

Sean MacKay
Project Director
Eastmount Engineering, Inc.
420 Main Street
Walpole, MA 02081

Sean MacKay

Sean MacKay
Project Director

28 FEB 91

Date

TABLE OF CONTENTS

- 1.0 COMPENDIUM
- 2.0 STACK SCHEMATIC
- 3.0 TRAVERSE POINT LOCATION & SAMPLING TIME PER POINT
- 4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES
- 5.0 QUALITY CONTROL PROCEDURES

APPENDIX

- I COMPUTER INPUT SHEETS
- II ISOKINETIC CALCULATION SHEETS
- III ENTHALPY CALCULATION SHEETS
- IV HEAT INPUT CALCULATION SHEETS
- V EMISSION CALCULATION SHEETS
- VI NOMENCLATURE SHEETS
- VII FIELD DATA SHEETS - UNIT OPERATING CONDITIONS
- VIII FIELD DATA SHEETS - STACK TESTING
- IX EQUIPMENT CALIBRATION SHEETS

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

1.0 COMPENDIUM

Eastmount Engineering Inc., conducted a Compliance Particulate Emissions Test Program on Unit #5 at Altatic Sugar Association's Belle Glade, Florida facility on January 10, 1991. The test program consisted of a series of three EPA Method 5 test runs.

All testing was conducted in strict accordance with the Environmental Protection Agency Reference Methods 1 through 5 as found in the Federal Register (40 CFR 60) as amended and were consistent with the State of Florida Department of Environmental Regulation's guidelines.

The purpose of this test was to determine compliance with the rules of the Department of Environmental Regulation (DER), Chapter 17-2.600 Air Pollution, Section 2.05 Prohibitive Acts, Subsection 6, Stationary Sources, Table II, Emission Limiting Standards.

During testing the boiler was burning bagasse as fuel. Boiler No. 5 is rated at 135,000 pounds of steam per hour. Results of the test program indicate Boiler No. 5 to be in compliance with the Florida DER emission standards. The following table summarizes the emission results, emission standards and boiler operating conditions.

RUN#	DATE	EMISSION RATE		ALLOWABLE		LOAD #/HR	% OF 135 KPH
		#/MMBtu	#/HR	#MMBtu	#/HR		
1	01-10-91	.137	29.32	.150	32.20	112702	83.5%
2	01-10-91	.126	27.93	.150	33.35	116900	86.6%
3	01-10-91	.155	34.02	.150	32.93	115300	85.4%
3 RUN AVG.		.139	30.42	.150	32.83	114967	85.2%

S. Joseph Mercadante, President, was in charge of and responsible for all stack testing including operating the meter box. Sean MacKay, Project Director, performed Method 9 testing (results may be found in Appendix VIII of this report), sample recovery and conducted all calculations. Bryan Gibson performed Orsat analysis. Mark Wescott positioned the probe at the proper traverse points and Michael Mercadante assisted where required. Mr. E. Perez was responsible for boiler operations and acquisition of all pertinent process data. Mr. Ajaya Satyal of the Palm Beach County Department of Health and Mr. Sherell Culliver of the Florida Department of Environmental Regulation observed the stack testing and boiler operations.


Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

2.0 STACK SCHEMATIC

ATLANTIC SUGAR ASSOCIATION
UNIT # 5
BELLE GLADE, FLORIDA FACILITY

The following is a schematic of the stack which services Boiler #5 at Atlantic Sugar Association's Belle Glade, Florida facility.

Defined are the sampling port locations, interior stack dimensions and distances from the ports to the nearest upstream and downstream interferences.




DISTANCE UPSTREAM FROM FLOW DISTURBANCE (A)	14.7'
DISTANCE DOWNSTREAM FROM FLOW DISTURBANCE (B)	50.3'
DIAMETER OF PORT SLEEVE (C)	3.5"
LENGTH OF PORT SLEEVE (D)	1.6"
NUMBER OF PORTS	2
INTERNAL DIAMETER OF STACK AT SAMPLING PORTS	5.5'

Drawing not to scale

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

ATLANTIC SUGAR ASSOCIATION
UNIT # 5
BELLE GLADE, FLORIDA FACILITY



Minimum number of traverse points for particulate traverses.

Distance A = 14.2' or 2.6 diameters.

Distance B = 59.3' or 10.7 diameters.

In accordance with Method 1, 12 traverse points are needed.

In order to sample for a minimum of one hour and draw at least 30 cubic feet, each traverse point was sampled for 5.0 minutes.

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

ATLANTIC SUGAR ASSOCIATION
UNIT # 5
BELLE GLADE, FLORIDA FACILITY

DIAMETER OF STACK: 5.5 FEET
PORT SLEEVE LENGTH: 1.6 INCHES

TRAVERSE POINT	DISTANCE % OF DIAMETER	DISTANCE (INCHES)	PROBE MARK (INCHES)
1	4.4	2.9	4.6
2	14.6	9.7	11.4
3	29.6	19.8	21.4
4	70.4	47.0	48.6
5	85.4	57.0	58.6
6	95.6	65.3	65.4

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES

The following is a description of the sampling train and specifications of particulate collection media used in the tests.

1. EMISSION SAMPLING EQUIPMENT

The specific train used during this test is one manufactured by Research Appliance Company (RAC). The design specifications of this train meets all the requirements of Environmental Protection Agency's Method 5 as found in the Federal Regulations under Section 40 CFR 60 as amended. The following is a description of the individual pieces of equipment used:

Nozzle - The nozzle was of seamless stainless steel tubing construction of the button hook design. A range of sizes suitable for isokinetic sampling was available. All nozzles were calibrated before testing. A nozzle calibration sheet may be found in the calibration section of this report.

Probe - An 10 foot steel probe with a stainless steel liner was used.

Heating System - The filter temperature was maintained by enclosing the filter in a hot box capable of maintaining the temperature at $248^{\circ}\text{F} \pm 25^{\circ}\text{F}$. This temperature was monitored by use of a thermocouple in the hot box.

Pitot Tube - A type S pitot tube attached to the probe was used to monitor the stack gas velocity. Since the pitot tube meets all the dimensional criteria set forth in Method 2 of 40 CFR 60, a coefficient of 0.84 has been used.

Filter Holder - A borosilicate glass type filter holder with frit support was used.

Condenser - Four impingers connected in series, with ground glass leak-free fittings were used as the condenser. The first, third and fourth impingers were of the Greenburg-Smith design, modified by replacing the tip with a 1/2" glass tube extending to about 1/2" from the bottom of the flask. The second impinger was of the Greenburg-Smith design with the standard tip.

Metering System - A vacuum gauge, micromanometer, inclined manometer, leak-free pump, calibrated thermocouples and a calibrated dry gas meter were the basic components used to meter the dry gas through the system.

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Gas Density Determination - An ORSAT type combustion analyzer, capable of measuring CO₂, O₂ and CO was used to determine the molecular weight of the flue gas. An integrated proportional sample was taken at each of the traverse points in order to assure that the total test span was covered. The ORSAT analysis was conducted immediately following each test run.

2. SAMPLING AND ANALYTICAL PROCEDURES

All sampling and analytical procedures were conducted in strict accordance with the methods prescribed in Methods 1 through 5 of the Code of Federal Regulations as found in 40 CFR 60 as amended. The following is the sequence of events that occur both prior to and during the actual stack test.

Traverse Points - The traverse points were calculated in accordance with Method 1 and the probe was marked accordingly.

Static Pressure - The static pressure was checked and recorded.

Preliminary Traverse - A preliminary traverse was conducted. Readings included the pressure drops and stack gas temperatures.

Nomograph - Once all of the above information had been obtained, the nomograph was set up for the actual test to correlate the isokinetic relationships.

Barometric Pressure - Barometric pressure was obtained by use of an aneroid barometer at the test site.

Sampling Train Set-Up

- (a) The pre-weighed filter was placed in the filter holder and visually checked.
- (b) 100 ml of water was placed in the first two impingers.
- (c) Approximately 200 grams of silica gel was placed in the fourth impinger. (Exact weights were logged on the field data sheets).
- (d) Crushed ice was placed around the impingers.
- (e) Once assembly of the entire train was completed, the probe and heater box were turned on.

Pre-test Leak Check - Once the heater box was at the desired temperature for testing, the system was leak checked at 15 inches of vacuum. A leakage rate of less than 0.02 CFM had to be achieved before testing commenced.

Final Check - Once everything was ready to go, the plant was checked to assure that it was running at desired capacity.

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Sampling - Isokinetic sampling as described in Method 5 then took place.

Post-test Leak Check - Upon completion of each test run, the system was leak checked at the highest vacuum recorded during that run. All leak checks were less than 0.02 CFM and considered acceptable.

Sample Recovery - Because of the importance of proper sample recovery procedures, details of the sample recovery can be found in the Quality Control Procedures Section of this report.

Isokinetics - Once all sample recovery was completed and the amount of moisture collected had been determined, calculations were conducted to determine the percent isokinetics of the test run.

Operating Data Sheets - All pertinent operating data were logged throughout the testing period by plant personnel.

5.0 QUALITY CONTROL PROCEDURES

The following is a description of the procedures used for maintaining the integrity of samples collected, including the chain of custody and quality control assurance of filters and acetone wash.

Pre-test preparation consisted of the filters being desiccated at $68 \pm 10^\circ\text{F}$ at ambient pressure for at least twenty four (24) hours. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved ± 0.5 mg change from the previous weighing. These pre-marked filters were then put into petri dishes and sealed. All filters used during testing were put into a carrying case for transport to the job site. A list of the filters and tare weights was available prior to testing.

After each test run, the filter and any particles which may have adhered to the filter holder gasket were carefully removed from the filter holder and placed into its identified petri dish container. This container was then labeled with the run number and date.

Taking care to see that particulate on the outside of the probe or other exterior surface did not get into the sample, particulate matter from the probe liner, nozzle, probe fittings, and front half of the filter holder were acetone washed into a sample container. This container was then sealed. The run number, date, and a mark indicating the level of the acetone wash in the bottle was recorded on the bottle.

Both the petri dish containing the filter and the bottle containing the acetone wash were transported to Eastmount Engineering's laboratory.

Once at the laboratory, each filter was weighed and then put back into its individual container. The container was then placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved ± 0.5 mg change from the previous weighing.

The levels marked on the bottles containing the acetone wash were checked to confirm that no leakage occurred during transport. The contents were then transferred into a pre-weighed beaker and evaporated to dryness. Once this had been accomplished, the beaker was placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the beaker was re-weighed until a constant weight of ± 0.5 mg change from the previous weighing was achieved.

All calculations were conducted in strict accordance with 40 CFR 60 (See Calculation Sheets in report).

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

APPENDIX I

COMPUTER INPUT SHEETS

INPUT DATA SHEET

PLANT: ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-1
DATE : 01-10-91

Ds (FT)	5.5							
Dn (IN)	.257							
FILTER#	3623	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
		PT	HEAD	ROOT	H	IN	OUT	TEMP
PIT COEFF	.84							
		A1	.36	.60	1.01	83	80	158
IMP-1 (INT)	100	2	.44	.66	1.23	87	81	159
		3	.44	.66	1.23	93	82	158
IMP-2 (INT)	100	4	.46	.68	1.29	96	83	158
		5	.47	.69	1.32	101	85	158
IMP-3 (INT)	0	6	.44	.66	1.23	103	86	156
IMP-4 (INT)	500.0	B1	.47	.69	1.32	81	81	158
		2	.65	.81	1.82	88	81	158
IMP-1 (FIN)	379	3	.60	.77	1.68	98	82	157
		4	.74	.86	2.07	104	84	158
IMP-2 (FIN)	127	5	.60	.77	1.68	108	85	155
		6	.30	.55	.84	110	87	156
IMP-3 (FIN)	2							
IMP-4 (FIN)	510.3							
% CO2	13.9							
% O2	5.9							
% CO	1.4							
P BAR	29.99							
P STK	-.30							
NO. PTS	12							
TEST LNGTH	60							
END METER	139.920							
INT METER	103.200							
BEGIN TIME:	10:45							
END TIME:	13:05							
AVERAGE			.50	.70	1.39	96.0	83.1	157.4

INPUT DATA SHEET

PLANT: ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-2
DATE : 01-10-91

Ds (FT)	5.5							
Dn (IN)	.250							
FILTER#	3619	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		A1	.34	.58	.88	78	78	158
IMP-1 (INT)	100	2	.40	.63	1.04	83	79	159
		3	.42	.65	1.09	87	79	158
IMP-2 (INT)	100	4	.50	.71	1.30	89	80	158
		5	.50	.71	1.30	92	81	157
IMP-3 (INT)	0	6	.36	.60	.84	92	82	157
IMP-4 (INT)	500.0	B1	.42	.65	1.09	86	82	158
		2	.50	.71	1.30	93	83	158
IMP-1 (FIN)	375	3	.55	.74	1.43	97	84	157
		4	.46	.68	1.20	100	86	157
IMP-2 (FIN)	126	5	.30	.55	.78	100	87	158
		6	.30	.55	.78	98	87	159
IMP-3 (FIN)	0							
IMP-4 (FIN)	513.7							
% CO2	14.3							
% O2	5.5							
% CO	.0							
P BAR	29.98							
P STK	-.30							
NO. PTS	12							
TEST LNTH	60							
END METER	175.695							
INT METER	142.400							
BEGIN TIME:	16:05							
END TIME:	17:10							
AVERAGE			.42	.65	1.09	91.3	82.3	157.8

INPUT DATA SHEET

PLANT: ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-3
DATE : 01-10-91

Ds (FT) 5.5

Dn (IN) .250

FILTER# 3618

PIT COEFF .84

		TRAV PT	VEL HEAD	SQ ROOT	DELTA H	DRYGAS IN	DRYGAS OUT	STACK TEMP
		A1	.46	.68	1.06	84	83	159
IMP-1 (INT)	100	2	.54	.73	1.24	90	84	158
		3	.73	.85	1.68	94	84	158
IMP-2 (INT)	100	4	.76	.87	1.75	98	85	158
		5	.64	.80	1.47	101	86	159
IMP-3 (INT)	0	6	.65	.81	1.49	102	88	158

IMP-4 (INT)	500.0	B1	.53	.73	1.22	97	87	159
		2	.67	.82	1.54	101	89	159
IMP-1 (FIN)	398	3	.64	.80	1.47	102	89	159
		4	.61	.78	1.40	102	90	158
IMP-2 (FIN)	128	5	.55	.74	1.27	103	90	161
		6	.48	.69	1.10	103	90	159

IMP-3 (FIN) 2

IMP-4 (FIN) 511.7

% CO2 13.1

% O2 6.9

% CO .0

P BAR 29.98

P STK -.30

NO. PTS 12

TEST LNTH 60

END METER 212.834

INT METER 175.949

BEGIN TIME: 18:00

END TIME: 19:05

AVERAGE .61 .78 1.39 98.1 87.1 158.8

APPENDIX II

ISOKINETIC CALCULATION SHEETS

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 5

RUN #: COMP-1
DATE : 01-10-91

TS (°F) = 157.4	% CO2 = 13.9	VM (CF) = 36.720
TS (°R) = 617.4	% O2 = 5.9	DELTA H (ABS) = 30.09
TM (°F) = 89.5	% CO = 1.4	PS (ABS) = 29.97
TM (°R) = 549.5	% N2 = 78.8	SQRT DELTA P = .700226
VI(TOT) = 318.3	CP = .84	AREA NOZZLE = .000360

Y = .9863

VM STD	= 17.64	$\frac{(VM)(Y)(DELTA H ABS)}{(TM)}$	= 34.98	DSCF
VW STD	= .04707 (VI TOT)		= 14.98	CF
BWO	=	$\frac{VW STD}{VW STD + VM STD}$	= .300	
BWO	=	MOISTURE FROM STEAM TABLES	= .303	
VI TOT	=	ADJUSTED TO SATURATION VOLUME	= N/A	ML
1-BWO	=	1 - BWO	= .700	
Md (DRY)	=	$.44 (\% CO2) + .32 (\% O2) + .28 (\% CO) + .28 (\% N2)$	= 30.46	LBS/LB MOLE
Ms (WET)	=	$MD (1-BWO) + 18 (BWO)$	= 26.72	LBS/LB MOLE
G	=	SQRT (TS / PS / MS)	= .88	
VS	=	85.49(CP)(G)(SQRT DELTA P)	= 44.2	FPS
H	=	0.002669 (VI TOT)	= .85	
J	=	(DELTA H ABS)(VM)(Y) / (TM)	= 1.98	
K	=	(H) + (J)	= 2.83	
% ISO	=	$\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$	= 101.9	

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 5

RUN #: COMP-2
DATE : 01-10-91

TS (`F)=	157.8	% CO2=	14.3	VM (CF)	=	33.295
TS (`R)=	617.8	% O2=	5.5	DELTA H (ABS)=		30.06
TM (`F)=	86.8	% CO=	0	PS (ABS)	=	29.96
TM (`R)=	546.8	% N2=	80.2	SQRT DELTA P =		.645693
VI(TOT)=	314.7	CP=	.84	AREA NOZZLE	=	.000341

Y = .9863

VM STD = 17.64 $\frac{(VM)(Y)(DELTA H ABS)}{(TM)}$ = 31.85 DSCF

VW STD = .04707 (VI TOT) = 14.81 CF

BWO = $\frac{VW STD}{VW STD + VM STD}$ = .317

BWO = MOISTURE FROM STEAM TABLES = .306

VI TOT = ADJUSTED TO SATURATION VOLUME= 302.9 ML

1-BWO = 1 - BWO = .694

Md (DRY) = $\frac{.44 (\% CO2) + .32 (\% O2) + .28 (\% CO) + .28 (\% N2)}{}$ = 30.51 LBS/LB MOLE

Ms (WET) = $\frac{MD (1-BWO) + 18 (BWO)}{}$ = 26.90 LBS/LB MOLE

G = $SQRT (TS / PS / MS)$ = .88

VS = $85.49 (CP) (G) (SQRT DELTA P)$ = 40.6 FPS

H = $0.002669 (VI TOT)$ = .81

J = $(DELTA H ABS) (VM) (Y) / (TM)$ = 1.81

K = $(H) + (J)$ = 2.61

% ISO = $\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$ = 108.2

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 5

RUN #: COMP-3
DATE : 01-10-91

TS (°F) = 158.8 % CO2 = 13.1 VM (CF) = 36.885
 TS (°R) = 618.8 % O2 = 6.9 DELTA H (ABS) = 30.08
 TM (°F) = 92.6 % CO = 0 PS (ABS) = 29.96
 TM (°R) = 552.6 % N2 = 80 SQRT DELTA P = .775625
 VI(TOT) = 339.7 CP = .84 AREA NOZZLE = .000341

Y = .9863

VM STD = 17.64 (VM)(Y)(DELTA H ABS) / (TM) = 34.94 DSCF
 VW STD = .04707 (VI TOT) = 15.99 CF
 BWO = $\frac{VW STD}{VW STD + VM STD}$ = .314
 BWO = MOISTURE FROM STEAM TABLES = .313
 VI TOT = ADJUSTED TO SATURATION VOLUME = 338.7 ML
 1-BWO = 1 - BWO = .687
 Md (DRY) = $\frac{.44 (\% CO2) + .32 (\% O2) + .28 (\% CO) + .28 (\% N2)}{100}$ = 30.37 LBS/LB MOLE
 Ms (WET) = $\frac{MD (1-BWO) + 18 (BWO)}{100}$ = 26.52 LBS/LB MOLE
 G = $\sqrt{TS / PS / MS}$ = .88
 VS = $85.49 (CP) (G) (\sqrt{DELTA P})$ = 49.2 FPS
 H = $0.002669 (VI TOT)$ = .90
 J = $(DELTA H ABS) (VM) (Y) / (TM)$ = 1.98
 K = (H) + (J) = 2.88
 % ISO = $\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$ = 98.8

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

APPENDIX III

ENTHALPY CALCULATION SHEETS

ENTHALPY CALCULATION SHEET

PLANT : ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-1
DATE : 01-10-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	205	480	250
	200	480	250
	205	480	250
	200	480	250
	250	500	250
	240	490	250
	230	490	250
AVERAGE	218.6 PSIG	485.7	250.0
P ABS =	233.3 PSIA		1266.9 1266.0
ENTHALPY @	500 'F AND	220 PSIA =	1267.5
ENTHALPY @	400 'F AND	220 PSIA =	1256.7
ENTHALPY @	485.7 'F AND	220 PSIA =	1266.0
ENTHALPY OF FEED WATER =		218.48	
AVERAGE ENTHALPY =		1047.5 BTU/LB OF STEAM	

ENTHALPY CALCULATION SHEET

PLANT : ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-2
DATE : 01-10-91

STEAM
PRESSURE

STEAM
TEMPERATURE

FEED WATER
TEMPERATURE

200
220
220
210

480
480
480
470
470

250
250
250
250
250

AVERAGE	212.5 PSIG	476.0	250.0
---------	------------	-------	-------

P ABS = 227.2 PSIA

ENTHALPY @ 500 'F AND 225 PSIA = 1267.1

ENTHALPY @ 400 'F AND 225 PSIA = 1256.2

ENTHALPY @ 476.0 'F AND 225 PSIA = 1264.5

ENTHALPY OF FEED WATER = 218.48

AVERAGE ENTHALPY = 1046.0 BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-3
DATE : 01-10-91

STEAM
PRESSURE

STEAM
TEMPERATURE

FEED WATER
TEMPERATURE

190
230
230
210
200

480
480
490
500
480

250
250
250
250
250

AVERAGE

212.0 PSIG

486.0

250.0

P ABS =

226.7 PSIA

ENTHALPY @

500

'F AND

225

PSIA =

1267.1

ENTHALPY @

400

'F AND

225

PSIA =

1256.2

ENTHALPY @

486.0

'F AND

225

PSIA =

1265.6

ENTHALPY OF FEED WATER =

218.48

AVERAGE ENTHALPY =

1047.1

BTU/LB OF STEAM

APPENDIX IV

HEAT INPUT CALCULATION SHEETS

HEAT INPUT CALCULATION SHEET

PLANT: ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-1
DATE: 01-10-91

	STEAM INTEGRATOR READINGS				TIME		INTEGRATOR FACTOR
	FIRST HALF	SECOND HALF	FIRST HALF	SECOND HALF			
END	6896	8743	11:20	13: 5			100
BEGIN	6229	8189	10:45	12: 35			LBS/HR STEAM
NET	667	554	X	100	/	65	MINS = 112708

112708 LBS/HR STEAM / 55% EFF. = 204923 EQUIV.

204923 LBS/HR STEAM X 1047 BTU/LB = 214.7 BTU(e6)/HR

	OIL INTEGRATOR READINGS		TIME		GALS/HR
END		0	13: 5		
BEGIN		0	10: 45		
NET		0	GALLONS	65	MINS = 0 GPH

0 GPH X 150,000 BTU/GAL (EST) = 0 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	214.7	-	0	X	.15	=	32.2	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	32.2	LBS/HR

HEAT INPUT CALCULATION SHEET

PLANT: ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-2
DATE: 01-10-91

	STEAM INTEGRATOR READINGS		TIME		INTEGRATOR FACTOR
	-----		----		-----
END	3181		17: 5		100
BEGIN	2012		16: 5		LBS/HR STEAM
	----		----		-----
NET	1169	X	100 / 60	MINS =	116900

116900 LBS/HR STEAM / 55% EFF. = 212545 EQUIV.

212545 LBS/HR STEAM X 1046 BTU/LB = 222.3 BTU(e6)/HR

	OIL INTEGRATOR READINGS		TIME		GALS/HR
	-----		----		-----
END	0		17: 5		
BEGIN	0		16: 5		
	----		----		
NET	0	GALLONS	60	MINS =	0 GPH

0 GPH X 150,000 BTU/GAL (EST) = 0 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	222.3	-	0	X	.15	=	33.3	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	33.3	LBS/HR

EMISSION CALCULATION SHEET

PLANT: ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-1
DATE: 01-10-91

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
NO. :	3623	5	3752	9
FINAL:	.8142	70.304	.6402	72.5769
TARE :	.6156	70.2966	.6398	72.5766
NET :	.1986	.0074	.0004	.0003/200ML

VOLUME OF RINSE 325

WEIGHT = 206.00
RESIDUE = - .49

Mn = 205.51 Mg AS = 23.8 SQ FT

Qs = $3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$ = 2263757 DSCFH

CS = $(2.205 \times 10^{-6})(Mn) / (VM \text{ STD})$ = $1.295e^{-5}$ LBS/SCF

CS' = $0.0154 (Mn) / (VM \text{ STD})$ = .09 GRAINS / SCF

PMR = (QS) (CS) = 29.32 LBS/HR

LOAD= MILLIONS OF BTU / HOUR INPUT = 214.7 BTU e6 / HR

CS = LBS / MILLION BTU = .137 LBS / BTu e6

ALLOWABLE = 32.20 LBS/HR

= .150 LBS / BTu e6

EMISSION CALCULATION SHEET

PLANT: ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-2
DATE: 01-10-91

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
NO. :	3619	6	3752	9
FINAL:	.8072	69.8778	.6402	72.5769
TARE :	.6185	69.8705	.6398	72.5766
NET :	.1887	.0073	.0004	.0003/200ML

WEIGHT = 196.00
RESIDUE = .42

Mn = 195.58 Mg AS = 23.8 SQ FT

Qs = $3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$ = 2062486 DSCFH

CS = $(2.205 \times 10^{-6})(Mn) / (VM \text{ STD})$ = $1.354e-5$ LBS/SCF

CS' = $0.0154 (Mn) / (VM \text{ STD})$ = .09 GRAINS/SCF

PMR = $(QS)(CS)$ = 27.93 LBS/HR

LOAD= MILLIONS OF BTU / HOUR INPUT = 222.3 BTU e6 / HR

CS = LBS / MILLION BTu = .126 LBS/BTu e6

ALLOWABLE = 33.35 LBS/HR

= .150 LBS/BTu e6

EMISSION CALCULATION SHEET

PLANT: ATLANTIC
LOCATION: UNIT 5

RUN #: COMP-3
DATE: 01-10-91

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
NO. :	3618	7	3752	9
FINAL:	.8303	72.5337	.6402	72.5769
TARE :	.6189	72.5263	.6398	72.5766
NET :	.2114	.0074	.0004	.0003/200ML

WEIGHT = 218.80
RESIDUE = .32

VOLUME OF RINSE 215

Mn = 218.48 Mg AS = 23.8 SQ FT

Qs = $3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$ = 2466754 DSCFH

Aug = 2,264,332

CS = $(2.205 \times 10^{-6})(Mn) / (VM STD)$ = 1.379e-5 LBS/SCF

CS' = $0.0154 (Mn) / (VM STD)$ = .10 GRAINS/SCF

PMR = (QS) (CS) = 34.02 LBS/HR Aug =

LOAD= MILLIONS OF BTU / HOUR INPUT

= 219.5 BTU e6 / HR

CS = LBS / MILLION BTu

= .155 LBS/BTu e6

ALLOWABLE

= 32.93 LBS/HR

= .150 LBS/BTu e6

APPENDIX VI

NOMENCLATURE SHEETS

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

NOMENCLATURE SHEET

PARTICULATE EMISSION TEST

Ar	Acetone residue - result of Blank evaporation.
AREA NOZZLE	Area of the nozzle in square feet.
AS	Area of the stack in square feet.
BDL	Below detectable limits
BWO	The amount of moisture in the flue gas.
% CO	Percent of carbon monoxide in the flue gas.
% CO2	Percent of carbon dioxide in the flue gas.
Cp	Pitot tube coefficient.
CS	The concentration in the stack in pounds per standard cubic foot.
Cs'	The concentration in the stack in grains per standard cubic foot.
DELTA H	The meter orifice differential.
DELTA H(ABS)	The meter orifice differential, absolute conditions in inches of mercury.
Dn (IN)	Diameter of the nozzle in inches.
DRY GAS IN	Temperature of the dry gas meter inlet degrees Farenheight.
DRY GAS OUT	Temperature of the dry gas meter outlet degrees Farenheight.
Ds (FT)	Diameter of the stack in feet.
E	The emission rate in pounds per million Btu derived by using F-Factor.
E (Heat Input)	The emission rate in pounds per million Btu derived by use of calculated heat input.
END METER	The dry gas meter reading at the end of the test.
F factor	The theoretical amount of air in dry standard cubic feet (DSCF) needed to combust a million Btu's worth of fuel.

NOMENCLATURE (cont'd)

Filter Catch	The amount of particulate captured on the filter during testing.
INT METER	The dry gas meter reading at the beginning of the test.
Md (DRY)	The dry molecular weight of the flue gas in pounds per pound mole.
MN	The amount of particulate collected by washing the nozzle, probe, and front half of the glassware, reported in milligrams.
MN'	The milligrams of particulate collected minus the blank.
Ms (WET)	Wet or actual molecular weight of the flue gas in pounds per pound mole.
% N2	The percent of nitrogen in the flue gas.
NO PTS	Number of traverse points.
% O2	Percent of oxygen in the flue gas.
P BAR	Barometric pressure at test location.
P STK	Static pressure of the stack in inches of water.
PMR	The emission rate in pounds per hour.
PS (ABS)	Absolute pressure conditions in the stack in inches of mercury.
Qs	The volumetric flow rate of the flue gas in dry standard cubic feet per hour.
SQ ROOT	The square root of each velocity head measurement.
SQRT DELTA P	The average of the square roots of the measured pressure drops.
Stack Temp or TS (°F)	The temperature of the stack in degrees Fahrenheit.
TS (°R)	The temperature of the stack in degrees Rankine.
T (Hot Box)	Temperature around the filter box, degrees Fahrenheit.
TM (°F)	Average temperature of the dry gas meter in degrees Fahrenheit.

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

NOMENCLATURE (cont'd)

TM (°R)	Average temperature of the dry gas meter in degrees Rankine.
VEL HEAD	The pressure drop measured across the pitot tubes.
VI (TOT)	The amount of water collected in the impingers in milliliters.
VM (CF)	The volume sampled through the dry gas meter in cubic feet.
VM STD	Volume sampled through the dry gas meter corrected to standard conditions.
VS	Velocity of the stack gas in feet per second.
VW STD	The amount of moisture collected, converted to standard cubic feet.
Y	Meter box calibration factor.
o	Sampling time in minutes.

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

APPENDIX VII

FIELD DATA SHEETS - UNIT OPERATING CONDITIONS

BOILER DATA SHEET

ATLANTIC SUGAR

UNIT # ~~3~~ 5

RUN #: RUN 1

DATE: 01/10/91

stop
↓

start
↓

TIME	10 ⁴⁵ AM	11 ⁰⁰ AM	11 ¹⁵ AM	11 ²⁰ AM	12 ³⁵ PM	12 ⁵⁰ PM	1 ⁰⁵ PM
STEAM PRESSURE	205	200	205	200	250	240	230
STEAM TEMPERATURE	480	480	480	480	500	490	490
STEAM INTEGRATOR	6229	6496	6781	6896	8189	8486	8742
FUEL OIL PRESSURE	-	-	-	-	-	-	-
FUEL OIL TEMPERATURE	-	-	-	-	-	-	-
FUEL OIL INTEGRATOR	-	-	-	-	-	-	-
FEED WATER TEMPERATURE	250	250	250	250	250	250	250
% O ₂	0.5	1.5	2	2	2.5	2	1.5
SCRUBBER DIFFERENTIAL	7	8	8	8	8	8	8

READINGS TAKEN BY: [Signature]

BOILER DATA SHEET

ATLANTIC SUGAR
UNIT #

RUN #: 475-2

DATE: 01/10/97

TIME	4 ⁰⁵ _{PM}	4 ²⁰ _{PM}	4 ³⁵ _{PM}	4 ⁵⁰ _{PM}	5 ⁰⁵
STEAM PRESSURE	200	220	220	210	3181
STEAM TEMPERATURE	480	480	480	470	470
STEAM INTEGRATOR	2012	2305	2584	2875	3181
FUEL OIL PRESSURE	-	-	-	-	-
FUEL OIL TEMPERATURE	-	-	-	-	-
FUEL OIL INTEGRATOR	-	-	-	-	-
FEED WATER TEMPERATURE	250	250	250	250	250
% O2	15	3	2	3	2
SCRUBBER DIFFERENTIAL	8	8	8	8	8

READINGS TAKEN BY: 

BOILER DATA SHEET

ATLANTIC SUGAR
UNIT #

RUN #:

RUN-3

DATE:

01/10/91

TIME	6 ⁰⁰ _{PM}	6 ¹⁵ _{PM}	6 ³⁰ _{PM}	6 ⁴⁵ _{PM}	7 ⁰⁰ _{PM}
STEAM PRESSURE	190	230	230	510	200
STEAM TEMPERATURE	480	500	490	480	480
STEAM INTEGRATOR	4150	4436	4728	5001	5303
FUEL OIL PRESSURE	-	-	-	-	-
FUEL OIL TEMPERATURE	-	-	-	-	-
FUEL OIL INTEGRATOR	-	-	-	-	-
FEED WATER TEMPERATURE	250	250	250	250	250
% O2	2	3.5	3	1.5	2.5
SCRUBBER DIFFERENTIAL	8	8	8	8	8

READINGS TAKEN BY:

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

APPENDIX VIII

FIELD DATA SHEETS - STACK TESTING

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>ATLANTIC</u>	Run #:	<u>COMP-1</u>
Location:	<u>UNIT 5</u>	Date:	<u>10 JAN 91</u>
Ds (ft):	<u>5.5</u>	No. Points:	<u>12</u>
Dn (in):	<u>.257</u>	Test Length:	<u>60</u>
Filter #:	<u>3623</u>	End Meter Reading:	<u>139.920</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>103.200</u>
P bar:	<u>29.99</u>	Begin Time:	<u>10.45</u>
P stack:	<u>-.3</u>	End Time:	<u>13.05</u>

IMP-1 (INT)	<u>100 ML</u>	IMP-1 (FINAL)	<u>379</u>
IMP-2 (INT)	<u>100 ML</u>	IMP-2 (FINAL)	<u>127</u>
IMP-3 (INT)	<u>0 ML</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0 g</u>	IMP-4 (FINAL)	<u>510.3</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>13.9</u>	<u> </u>	<u> </u>
% O ₂	<u>5.9</u>	<u> </u>	<u> </u>
% CO	<u>1.4</u>	<u> </u>	<u> </u>

Project Director:	<u>S. MACKAY</u>	Field Laboratory:	<u>Mackay</u>
Meter Box Operator:	<u>J. MERCHANT</u>	Chain of Custody:	<u>Mackay</u>
Probe Operator:	<u>M. WESCOTT</u>	Plant Coordinator:	<u> </u>
^{3A} Erst Analyst:	<u>B. GIBSON</u>	Agency Rep:	<u>Satya / Culliver</u>

Comments:

TRAVERSE DATA SHEET

Page 1 of 1

Sampling time per point: 5

Plant: ATLANTIC

Run #: Comp - 1

Location: UNIT #5

Date: 10 JAN 91

029

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
			<u>103.200</u>						
<u>A1</u>	<u>.36</u>	<u>1.01</u>	<u>106.0</u>	<u>83</u>	<u>80</u>	<u>268</u>	<u>65</u>	<u>158</u>	<u>8.0</u>
<u>2</u>	<u>.44</u>	<u>1.23</u>	<u>108.8</u>	<u>87</u>	<u>81</u>	<u>238</u>	<u>63</u>	<u>159</u>	<u>8.5</u>
<u>3</u>	<u>.44</u>	<u>1.23</u>	<u>111.6</u>	<u>93</u>	<u>82</u>	<u>260</u>	<u>63</u>	<u>158</u>	<u>9.0</u>
<u>4</u>	<u>.46</u>	<u>1.29</u>	<u>114.6</u>	<u>96</u>	<u>83</u>	<u>263</u>	<u>64</u>	<u>158</u>	<u>10.0</u>
<u>5</u>	<u>.47</u>	<u>1.32</u>	<u>117.7</u>	<u>101</u>	<u>85</u>	<u>266</u>	<u>65</u>	<u>158</u>	<u>12.0</u>
<u>6</u>	<u>.47</u>	<u>1.23</u>	<u>120.635</u>	<u>103</u>	<u>86</u>	<u>255</u>	<u>65</u>	<u>156</u>	<u>12.0</u>
<u>B1</u>	<u>.47</u>	<u>1.82</u>	<u>123.6</u>	<u>81</u>	<u>81</u>	<u>225</u>	<u>65</u>	<u>158</u>	<u>10.0</u>
<u>2</u>	<u>.65</u>	<u>1.82</u>	<u>126.9</u>	<u>88</u>	<u>81</u>	<u>261</u>	<u>67</u>	<u>158</u>	<u>13.0</u>
<u>3</u>	<u>.60</u>	<u>1.68</u>	<u>130.3</u>	<u>98</u>	<u>82</u>	<u>262</u>	<u>68</u>	<u>157</u>	<u>14.0</u>
<u>4</u>	<u>.74</u>	<u>2.07</u>	<u>133.9</u>	<u>104</u>	<u>84</u>	<u>257</u>	<u>69</u>	<u>158</u>	<u>15.0</u>
<u>5</u>	<u>.60</u>	<u>1.68</u>	<u>137.4</u>	<u>108</u>	<u>85</u>	<u>262</u>	<u>68</u>	<u>155</u>	<u>14.0</u>
<u>6</u>	<u>.30</u>	<u>0.84</u>	<u>139.920</u>	<u>110</u>	<u>87</u>	<u>255</u>	<u>67</u>	<u>156</u>	<u>9.0</u>

Relationship: 2.8

Box #: 3 Y: 9863 Delta H: 1.90

Start Time: 10.45 End Time: 13.05

Pre Leak Ck: .005 CFM @ 15 "Hg

Mid Leak Ck: CFM @ "Hg (Vol:)

Post Leak Ck: .005 CFM @ 15 "Hg

Pitot Leak Ck: 9000 @ 5 "H2O

Box Oper: Probe Oper:

Stopped test during
Part Change - Progen
with ~~scabber~~ Becken
Feeder.
11:23
Re start @ 12:35

Visible Emission Observation Form

SOURCE NAME			OBSERVATION DATE		START TIME		STOP TIME					
ATLANTIC SUGAR			10 JAN 91		1000							
ADDRESS			SEC	0	15	30	45	SEC	0	15	30	45
P.O. DRAWER B			MIN					MIN				
CITY			1	5	5	5	5	31				
Belle Glade			2	5	5	5	5	32				
STATE			3	5	5	5	5	33				
F/4			4	5	5	5	5	34				
ZIP			5	5	5	5	5	35				
33430			6	5	5	5	5	36				
PHONE			7	5	5	5	5	37				
SOURCE ID NUMBER			8	5	5	5	5	38				
PROCESS EQUIPMENT			9	5	5	5	5	39				
BAGASSE BOILER			10	5	5	5	5	40				
OPERATING MODE			11	5	5	5	5	41				
CONTROL EQUIPMENT			12	5	5	5	5	42				
IMPIGEMENT SCRUBBER			13	5	5	5	5	43				
OPERATING MODE			14	5	5	5	5	44				
DESCRIBE EMISSION POINT			15	5	5	5	5	45				
START			16	5	5	5	5	46				
STOP			17	5	5	5	5	47				
HEIGHT ABOVE GROUND LEVEL			18	5	5	5	5	48				
START 100' STOP			19	5	5	5	5	49				
HEIGHT RELATIVE TO OBSERVER			20	5	5	5	5	50				
START 100' STOP			21	5	5	5	5	51				
DISTANCE FROM OBSERVER			22	5	5	5	5	52	5	5	5	5
START 300 STOP			23	5	5	5	5	53	5	5	5	5
DIRECTION FROM OBSERVER			24	5	5	5	5	54	5	5	5	5
START South STOP			25	5	5	5	5	55	5	5	5	5
DESCRIBE EMISSIONS			26	5	5	5	5	56	5	5	5	5
START STEAM PLUME STOP STEAM PLUME			27	5	5	5	5	57	5	5	5	5
EMISSION COLOR			28	5	5	5	5	58	5	5	5	5
START Lt Blue STOP Same			29	5	5	5	5	59	5	5	5	5
PLUME TYPE: CONTINUOUS ☒			30	5	5	5	5	60	5	5	5	5
FUGITIVE ☐ INTERMITTENT ☐												
WATER DROPLETS PRESENT: NO ☐ YES ☒												
IF WATER DROPLET PLUME: ATTACHED ☒ DETACHED ☐												
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED												
START 2' ABOVE STACK STOP												
DESCRIBE BACKGROUND												
START PC Sky STOP PC Sky												
BACKGROUND COLOR												
START Blue STOP												
WIND SPEED												
START 10-15 STOP												
WIND DIRECTION												
START East STOP												
AMBIENT TEMP.												
START 76 STOP												
WET BULB TEMP.												
RH, percent												
Source Layout Sketch												
Draw North Arrow												
AVERAGE OPACITY FOR HIGHEST PERIOD			NUMBER OF READINGS ABOVE % WERE									
RANGE OF OPACITY READINGS			MINIMUM MAXIMUM									
OBSERVER'S NAME (PRINT)			SEAN MACKAY									
OBSERVER'S SIGNATURE			DATE									
ORGANIZATION			EASTMOUNT ENGINEERING									
I HAVE RECEIVED A COPY OF THESE OPACITY OBSERVATIONS			CERTIFIED BY									
SIGNATURE			DATE									
TITLE			VERIFIED BY									
DATE			DATE									



EASTMOUNT ENGINEERING, INC.
ENVIRONMENTAL ENGINEERS
AIR QUALITY SPECIALISTS

Quality Assurance Handbook M9-4.2

ADDITIONAL COMMENTS
STOP TEST @ 11:20, BROKEN CONVEYOR
Restart @ 12:35, STARTED RAINING
@ 12:37

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>ATLANTIC</u>	Run #:	<u>COMP-2</u>
Location:	<u>UNIT #5</u>	Date:	<u>10 JAN 91</u>
Ds (ft):	<u>5.5</u>	No. Points:	<u>12</u>
Dn (in):	<u>.250</u>	Test Length:	<u>60</u>
Filter #:	<u>3619</u>	End Meter Reading:	<u>175.695</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>142.400</u>
P bar:	<u>29.98</u> <u>-.3</u>	Begin Time:	<u>1605</u>
P stack:	<u>-.3</u>	End Time:	<u>1710</u>

IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>375</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>126</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>0</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>513.7</u>

	TEST 1	TEST 2	TEST 3
% CO2	<u>14.3</u>	<u> </u>	<u> </u>
% O2	<u>5.5</u>	<u> </u>	<u> </u>
% CO	<u>0</u>	<u> </u>	<u> </u>

Project Director:	<u>S. Mac Kay</u>	Field Laboratory:	<u>Mac Kay / Mercadante</u>
Meter Box Operator:	<u>S.J. Mercadante</u>	Chain of Custody:	<u>Mac Kay</u>
Probe Operator:	<u>M. Wescott</u>	Plant Coordinator:	<u>E. Perez</u>
Orsat Analyst:	<u>B. Gibson</u>	Agency Rep:	<u>SATYA / COLLIVER</u>

Comments:

TRAVERSE DATA SHEET

Page 1 of 1

Sampling time per point: 5

Plant: AT/ANT, C

Run #: Comp - 2

Location: UNIT 5

Date: 10 JAN 91

[illegible]

Relationship: 2.6
Box #: 3 Y: 9863 Delta H_e: 1.90
Start Time: 16:05 End Time: 17:08
Pre Leak Ck: 1.005 CFM @ 17 "Hg
Mid Leak Ck: 9.00 CFM @ 5 "Hg (Vol:)
Post Leak CK: 0.00 CFM @ 5 "Hg
Pitot Leak CK: 9.00 @ 5 "H₂O
Box Oper: Smt Probe Oper: HW

Visible Emission Observation Form

SOURCE NAME ATLANTIC SUGAR			OBSERVATION DATE					START TIME 1605		STOP TIME 1710		
ADDRESS BRAWER B			SEC MIN	0	15	30	45	SEC MIN	0	15	30	45
CITY Belle Glade STATE FLA ZIP 33430			1	5	5	5	5	31				
PHONE			2	5	5	5	5	32	RAIN			
SOURCE ID NUMBER			3	5	5	5	5	33				
PROCESS EQUIPMENT BAGASSE BOILER			4	5	5	5	5	34				
OPERATING MODE			5	5	10	10	5	35				
CONTROL EQUIPMENT IMPINGEMENT SCRUBBER			6	5	5	5	5	36				
OPERATING MODE			7	5	5	5	5	37	5	5	5	5
DESCRIBE EMISSION POINT START STEAM PLUME STOP SAME			8	5	5	5	5	38	5	5	5	5
HEIGHT ABOVE GROUND LEVEL START 100' STOP			9	5	5	5	5	39	5	5	5	5
HEIGHT RELATIVE TO OBSERVER START 100' STOP			10	5	5	5	5	40	5	5	5	5
DISTANCE FROM OBSERVER START 300' STOP			11	10	5	10	5	41	5	5	5	5
DIRECTION FROM OBSERVER START NORTH STOP			12	5	5	5	5	42	5	5	5	5
DESCRIBE EMISSIONS START STEAM PLUME STOP			13	5	5	5	5	43	5	5	5	5
EMISSION COLOR START WHITE STOP			14	5	5	5	5	44	5	5	5	5
PLUME TYPE: CONTINUOUS ☒ FUGITIVE ☐ INTERMITTENT ☐			15	5	10	5	5	45	5	5	5	5
WATER DROPLETS PRESENT: NO ☐ YES ☒			16	5	5	5	5	46	5	5	5	5
IF WATER DROPLET PLUME: ATTACHED ☒ DETACHED ☐			17	5	5	5	5	47	5	5	5	5
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED START 2' ABOVE STACK STOP SAME			18	5	10	5	5	48	5	5	5	5
DESCRIBE BACKGROUND START CLOUDS STOP CLOUDY			19	5	10	5	5	49	5	5	5	5
BACKGROUND COLOR START WHITE STOP			20					50	5	10	10	5
SKY CONDITIONS START CL STOP			21	RAIN				51	5	5	5	5
WIND SPEED START 10-15 STOP			22					52	5	5	5	5
WIND DIRECTION START EAST STOP			23					53	5	5	5	5
AMBIENT TEMP. START 78 STOP			24					54	5	5	5	5
WET BULB TEMP. RH, percent			25					55	5	5	5	5
			26					56	5	5	5	5
			27					57	5	10	5	5
			28					58	5	5	5	5
			29					59	5	5	5	5
			30					60	5	5	5	5
Source Layout Sketch Draw North Arrow Sun → Wind → Plume and Stack ← Observers Position 140° Sun Location Line			AVERAGE OPACITY FOR HIGHEST PERIOD				NUMBER OF READINGS ABOVE % WERE					
			RANGE OF OPACITY READINGS				MAXIMUM					
			MINIMUM									
			OBSERVER'S NAME (PRINT) SEAN MAC KAY									
COMMENTS PLUME ROLLING OVER ON ITSELF			OBSERVER'S SIGNATURE Sean Mac Kay				DATE 10 JAN 91					
			ORGANIZATION EAST MOUNT ENGINEERING									
I HAVE RECEIVED A COPY OF THESE OPACITY OBSERVATIONS			CERTIFIED BY PKS, DEP				DATE					
SIGNATURE			VERIFIED BY				DATE					
TITLE												
DATE												

Quality Assurance Handbook M9-4.2

EASTMOUNT ENGINEERING, INC.
ENVIRONMENTAL ENGINEERS
AIR QUALITY SPECIALISTS



FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>ATLANTIC</u>	Run #:	<u>COMP-3</u>
Location:	<u>UNIT 5</u>	Date:	<u>10 JAN 91</u>
Ds (ft):	<u>5.5</u>	No. Points:	<u>12</u>
Dn (in):	<u>.250</u>	Test Length:	<u>60 min</u>
Filter #:	<u>3618</u>	End Meter Reading:	<u>212.834</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>175.949</u>
P bar:	<u>29.98</u>	Begin Time:	<u>18:00</u>
P stack:	<u>-.3</u>	End Time:	<u>19:05</u>
IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>398</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>128</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0 g</u>	IMP-4 (FINAL)	<u>511.7</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>13.1</u>	_____	_____
% O ₂	<u>6.9</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>MacKay</u>
Meter Box Operator:	<u>M. Mercadante</u>	Chain of Custody:	<u>MacKay</u>
Probe Operator:	<u>M. Wescott</u>	Plant Coordinator:	<u>E. Perez</u>
Orsat Analyst:	<u>S.J. Mercadante</u>	Agency Rep:	<u>Smyth/Culliver</u>

Comments:

TRAVERSE DATA SHEET

Page 1 of 1

Sampling time per point: 5

Plant: ATLANTIC

Run #: Comp - 3

Location: UNIT 5

Date: 10 JAN 91

[illegible]Relationship: 2.3

Box #: 3 Y: 1986 Delta H#: 196

Start Time: 1200 End Time: 1905

Pre Leak Ck: .005 CFM @ 15 "Hg
Mid Leak Ck: _____ CFM @ _____ "Hg (Vol: _____)

Mid Leak CK: _____ CFM @ _____ "Hg
Post Leak CK: 1.0 CFM @ 2 "Hg

Pitot Leak CK: 9000 @ 5 "H2O

Box Oper: M Y Probe Oper: MW

Atlantic Sugar Association - Boiler #5
Particulate Emissions Test Report

APPENDIX IX

EQUIPMENT CALIBRATION SHEETS

POST
METER BOX CALIBRATION SHEET

BOX #: 3
PRES BAR: 30.04

DATE: 2-11-91
VACUUM: 15IN HG

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	10.00	10.198	1.40	.103	30.14	16.22
2	10.00	10.336	1.40	.103	30.14	16.24
3	10.00	10.406	1.40	.103	30.14	16.26

RUN #	TEMP WET (`F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H @
1	66.0	85.3	74.0	79.7	1.003	1.99
2	66.0	90.7	79.3	85.0	.9990	1.98
3	66.0	93.3	83.0	88.2	.9981	1.97
AVERAGE					1.000	1.98

PRE CAL Y = .9863 % DIFFERENCE = 1.36 %

ALLOWABLE = 5.00 %

FORMULAS:

Y=

DELTA H @=

$$Y = \frac{(V w) (P b) (T d)}{(V d) (P b \text{ ABS}) (T w)} \times \frac{0.0317 (\text{DELTA H})}{(P b) (T d)} \times \left[\frac{(T w) (\text{TIME})^2}{(V w)} \right]$$

JIM JARDIN

CALIBRATION BY: _____

METER BOX CALIBRATION SHEET

BOX NUMBER: #3
PRESS BAR : 30.20

DATE: 16 NOV 90
DUE: 16 MAY 91

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	5	5.084	.50	.0368	30.24	11.99
2	5	5.137	1.00	.0735	30.27	8.97
3	10	10.410	1.50	.1103	30.31	15.46
4	10	10.506	2.00	.1471	30.35	13.57
5	10	10.671	3.00	.2206	30.42	11.08
6	10	10.777	4.00	.2941	30.49	9.69

RUN #	TEMP WET (°F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H @
1	74.0	79.4	88.2	83.8	1.000	1.58
2	74.0	96.8	82.5	89.6	.9994	1.75
3	74.0	101.3	85.5	93.4	.9918	1.94
4	74.0	103.8	88.3	96.0	.9862	1.98
5	74.0	108.3	90.5	99.4	.9745	1.97
6	74.0	110.3	91.5	100.9	.9652	2.00
AVERAGE					.9863	1.87

FORMULAS:

Y=

DELTA H @=

$$\frac{(V w) (P b) (T d)}{(V d) (P b \text{ ABS}) (T w)} \quad \frac{0.0317 (\text{DELTA H})}{(P b) (T d)} \quad * \quad \left[\frac{(T w) (\text{TIME})^2}{(V w)} \right]$$

CALIBRATION BY:

MIKE RIDGE

THERMOCOUPLE CALIBRATION SHEET -----

SET #: METER BOX #3

DATE: 6-20-87

REFERENCE MERCURY/GLASS

STANDARD ('F)	THERMOCOUPLE ('F)	% DEVIATION OF ABSOLUTE
32	33	.20
67	70	.57
212	215	.45
MAXIMUM % DEVIATION		.57
ALLOWABLE % DEVIATION		1.50

SET #: METER BOX #3

DATE: 6-20-87

STANDARD ('F)	THERMOCOUPLE ('F)	% DEVIATION OF ABSOLUTE
32	29	.61
73	70	.56
212	211	.15
MAXIMUM % DEVIATION		.61
ALLOWABLE		1.50

G. ZWILLING

CALIBRATION BY: _____

NOZZLE CALIBRATION SHEET

PROJECT NAME: ATLANTIC #5

PROJECT NUMBER: 90-104

POINT# NOZZLE# 1/4-2 NOZZLE # 1/4-3 NOZZLE# _____ NOZZLE # _____

1 .256 .249 _____

2 .258 .251 _____

3 .257 .250 _____

AVG. .257 .250 _____

Sean MacKay
CALIBRATED BY:

10 JAN 91
DATE:

THERMOCOUPLE CALIBRATION SHEET

SET #: 8.5' - 7

DATE: 07/07/89

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE (ABSOLUTE)
87	86	.18
212	211	.15
415	420	.57
	MAXIMUM	.57
	ALLOWABLE	1.50

CALIBRATION BY:

S. MacKay

THERMOCOUPLE CALIBRATION SHEET

SET #: 8.5' - 6

DATE: 07/07/89

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE (ABSOLUTE)
87	86	.18
212	211	.15
430	436	.67
	MAXIMUM	.67
	ALLOWABLE	1.50

CALIBRATION BY:

S. MacKay

7-18A

DATE 10/3/91 FLORIDA DEPARTMENT OF ENVIRONMENTAL REGULATION
PARTICULATE STACK TEST VERIFICATION
EPA METHOD 5

FACILITY NAME: OKEELANTA

APIS # 0005

COMPANY CONDUCTING TEST: EASTMOUNT ENG

TEST DATE 1/10/1991

SOURCE DESCRIPTION: BOILER5

STACK TEST DATA SUMMATION

	RUN1	RUN2	RUN3
1.H2O (VOL.MEAS.),ML	308	301	328
2.H2O (MASS MEAS.),GM	10.3	13.7	11.7
3.M'N PARTICULATE WEIGHT, GM	.2055	.1956	.2184
4.V'M VOLUME METERED,CF	36.72	33.295	36.88
5.Y DRY GAS MTR. CALIB.FCTR.	.9863	.9863	.9863
6.RDP AVG SQR D.P-SAMPLING	.7	.65	.78
7.DH AVG DELTA H,IN.H2O	1.39	1.09	1.39
8.T'M AVG MTR. TEMP,DEG.F	89.5	86.8	92.6
9.T'S AVG STACK TEMP,DEG.F	157.4	157.8	158.8
10.P'SG STACK PRESS,'HG(GAUGE)	.3	.3	.3
11.P'B BAROMETRIC PRESS,'HG	29.99	29.98	29.98
13.D'N ACTUAL NOZZLE DIAM,IN	.257	.25	.25
14.T ACTUAL SAMPLE TIME,MIN	60	60	60
15.C'P PITOT TUBE COEFFICIENT	.84	.84	.84
23.S/T VALUE:SAMPLE PTS/TOT PTS	1	1	1

RUN	VOLUME SAMPLED DSCF	MOISTURE CONTENT PERCENT	STACK VEL FPS	FLOW RATE DSCF/H	PERCENT ISO- KINETIC	ACTUAL EMISS LB/HR	ALLOW EMISS LB/HR
1	34.99	29.95	44.16	2,293,977	100.79	29.701	32.670
2	31.85	30.25	41.06	2,121,417	104.82	28.722	32.670
3	34.93	30.99	49.39	2,521,064	96.75	34.746	32.670
MEAN	33.92	30.40	44.87	2,312,152	100.79	31.056	32.670

SUMMARY

GENERAL:

REVIEWED BY RAISA
ACTUAL A 'S = 23.8 SQ FT
LAMINAR FLOW ASSUMED (<10 DEG YAW) (OR <20 DER)
ALL REQUIRED LEAK TESTS ACCEPTABLE
ASSUMED M 'D=30.0 (COMBUSTION GASES)

COMMENT.....

RUN 1 :

ACTUAL A 'N = .0003602 SQ FT
P 'S = 30.29 IN HG
OVERSATURATED CONDITIONS: SATURATION MOISTURE ASSUMED/GIVEN PG.1

COMMENT.....

RUN 2 :

ACTUAL A 'N = .0003409 SQ FT
P 'S = 30.28 IN HG
OVERSATURATED CONDITIONS: SATURATION MOISTURE ASSUMED/GIVEN PG.1

COMMENT.....

RUN 3 :

ACTUAL A 'N = .0003409 SQ FT
P 'S = 30.28 IN HG
OVERSATURATED CONDITIONS: SATURATION MOISTURE ASSUMED/GIVEN PG.1

COMMENT.....

53

avg
23.8

Jan 1-10-91

Heat Value

214.7 222.3 219.5

INPUT SHEET - REV:09/13/83 - PAGE 2 OF 2

ENTER THE FOLLOWING:

	RUN1	RUN2	RUN3
1. H2O COLLECTED (ONLY VOL. MEASURED), ML:	318.3	314.7	339.7
2. H2O COLLECTED (WEIGHED PART ONLY), GM:	—	—	—
3. M'N PARTICULATE WEIGHT, GM:	2055	1955	2184
4. V'M VOLUME METERED, CF:	36.720	33.295	36.885
5. Y DRY GAS METER CAL FACTOR:	9863	9863	9863
6. RDP AVG SQR DELTA P (WHEN SAMPLING):	70	65	78
7. DH' AVG DELTA H, IN H2O:	1.39	1.09	1.39
8. T'M AVG METER TEMP, DEG F:	89.5	86.8	92.6
9. T'S AVG STACK TEMP, DEG F:	157.4	157.8	158.8
10. P'S* STACK PRESS, *IN(.....):	29.97	29.96	29.96
11. P'B BAROMETRIC PRESS, IN HG:	29.98	29.98	29.98
12. D'N ACTUAL NOZZLE DIAMETER, IN.:	25.7	25.0	25.0
14. T ACTUAL SAMPLE TIME, MIN:	60	60	60
15. C'P PITOT TUBE COEFFICIENT:	84	84	84

OPTION ENTRIES:

17. ORSAT/FYRITE - %CO2:	214.7		
18. ORSAT/FYRITE - %O2:	222.3		
20. ORSAT/FYRITE (FOR C'S @ 50% A.A. CO2):	219.5		
19. SPECIFIC M'D ENTRIES:	656.5		
23. CYCLONIC (10-20 DEG) - AVG COS(YAW):			
26. CYC.(>20) - AVG(SQR D.P X COS(YAW)):			
24. PROCESS WT SOURCE - T/HR:			
22. LB/TON REGULATED - T/HR:			
27. LB/* REGULATED (* AS DEFINED) - */HR:			
29. LAM&CYC(20) - VAL(SAMPLE PTS/TOT PTS):			

214.7
222.3
219.5
656.5
3 1 656.5 1218.8
5 26 24 25

5303
4150

1153 X 100
115,300

Lbs/Hr → 209636

212 — PSIG
486 — Temp

218.25 MBTU

500 —
250

1041

run 1

$$\begin{array}{r} 279 \\ 37 \\ \hline 308 \end{array}$$

10.3

$$\begin{array}{r} 2 \\ 275 \\ \hline 26 \\ \hline 301 \end{array}$$

13.7

$$\begin{array}{r} 3 \\ 298 \\ \hline 28 \\ \hline 328 \end{array}$$

11.7