

Note: This is a reference cited in *AP 42, Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/


The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP-42 Section Number: 1.8

Reference Number: 51

Title: Okeelanta Corporation Compliance
Particulate Emissions Test Report
Boiler #10

January 1992



Eastmount Engineering

Environmental Consultants — Air Quality Specialists

Rib-39
OSWI-004

OKEELANTA CORPORATION
COMPLIANCE PARTICULATE EMISSIONS TEST REPORT
BOILER #10

PREPARED FOR:

Okeelanta Corporation
Okeelanta Sugar Division
South Bay, Florida 33493

CONCERNING:


Particulate Emissions Testing
Okeelanta Corporation
Boiler #10
South Bay Florida Facility
January, 29, 30 & 31, 1992

PREPARED BY:

Sean M. MacKay
Project Director
Eastmount Engineering, Inc.
420 Main Street
Walpole, MA 02081

I hereby certify that the information presented in this report is accurate and true to the best of my knowledge.


Sean M. MacKay
Project Director


Date

39

STACK TEST REVIEW DATA INPUT FORM

EPA-51

TEST DATE: January 29, 92

South Bay

FACILITY: O Keelanta Corporation Sugar APIS #: 0005

DESCRIPTION: Boiler 10

TESTING FIRM: Eastmont Engineering, Inc

PERMIT EMISSION LIMIT: 0.2 LB/MMBTU OR 38.18 LB/HR 38.18

AVERAGE HEAT INPUT: 190.53 MMBTU/HR

A's (AREA OF STACK): 44.2 FT²

39.8 } Average
38.3 } 38.13
36.3 }

comp-1, 2, 3

01-29-92

Heat input

198.9

191.4

181.3

MEASURED PARAMETERS

	Run-1	Run-2	Run-3
1. H2O impingers (V'i), milliliters	<u>242</u>	<u>232</u>	<u>243</u>
2. H2O filter, grams	<u>18.5</u>	<u>16.8</u>	<u>14.8</u>
3. M'n (particulate weight), grams	<u>.1375</u>	<u>.1407</u>	<u>.1432</u>
4. V'm (gas volume metered), FT ³	<u>50.88</u>	<u>50.05</u>	<u>48.86</u>
5. Y (dry gas calibration factor)	<u>.9911</u>	<u>.9911</u>	<u>.9911</u>
6. RDP (average square root dP)	<u>.89</u>	<u>.88</u>	<u>.85</u>
7. dH (average delta H), inches H2O	<u>2.55</u>	<u>2.49</u>	<u>2.80</u>
8. T'm (average meter temperature), F	<u>97.5</u>	<u>99.4</u>	<u>97.1</u>
9. T's (average stack temperature), F	<u>141.8</u>	<u>140.5</u>	<u>141.8</u>
10. P's (stack pressure, abs.) inches Hg	<u>29.95</u> <u>30.00</u>	<u>30.03</u> <u>30.08</u>	<u>29.95</u> <u>30.00</u>
11. P'b (barometric pressure, abs.) inches Hg	<u>30.00</u>	<u>30.08</u>	<u>30.00</u>
13. D'n (nozzle dia.), inches	<u>.260</u>	<u>.280</u>	<u>.260</u>
14. Sample Time, minutes	<u>60</u>	<u>60</u>	<u>60</u>
15. C'p (pitot tube coefficient)	<u>.84</u>	<u>.84</u>	<u>.84</u>
23. S/T (sample pts./total pts.)	<u>1.00</u>	<u>1.0</u>	<u>1.0</u>

STACK TEST REVIEW DATA INPUT FORM

TEST DATE: January 29, 2031, 1992

43
CT-10R-2
CT-10R-1
01-31-92

FACILITY: Okeelanta Corpor. South Bay APIS #: _____

DESCRIPTION: Boiler 10

TESTING FIRM: East mount

PERMIT EMISSION LIMIT: 0.2 LB/MMBTU OR 38.01 LB/HR

AVERAGE HEAT INPUT: 186.63 MMBTU/HR

A's (AREA OF STACK): 44.2 FT²

37.6
+56.1
38.6 } 37.3

191.2
188
180.7 } 186.63

MEASURED PARAMETERS

	Run-1	Run-2	Run-3
1. H2O impingers (V'i), milliliters	204	210	179
2. H2O filter, grams	13.5	13.0	12.1
3. M'n (particulate weight), grams	.1339	.1413	.0982
4. V'm (gas volume metered), FT ³	45.408	56.408	43.84
5. Y (dry gas calibration factor)	.9911	.9911	.9911
6. RDP (average square root dP)	.79	.82	.78
7. dH (average delta H), inches H2O	1.99	2.13	1.84
8. T'm (average meter temperature), F	93.4	94.5	97.1
9. T's (average stack temperature), F	139.3	138.8	136.6
10. P's (stack pressure, abs.) inches Hg	29.89 29.94	29.90 29.95	29.89 29.96
11. P'b (barometric pressure, abs.) inches Hg	29.94	29.95	29.96
13. D'n (nozzle dia.), inches	.260	.265	.260
14. Sample Time, minutes	60	60	60
15. C'p (pitot tube coefficient)	.84	.84	.84
23. S/T (sample pts./total pts.)	1.0	1.0	1.0

TABLE OF CONTENTS

- 1.0 COMPENDIUM
- 2.0 STACK SCHEMATIC
- 3.0 TRAVERSE POINT LOCATIONS & SAMPLING TIME PER POINT
- 4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES
- 5.0 QUALITY CONTROL PROCEDURES

APPENDIX

- I COMPUTER INPUT SHEETS
- II ISOKINETIC CALCULATION SHEETS
- III ENTHALPY CALCULATION SHEETS
- IV HEAT INPUT CALCULATION SHEETS
- V PARTICULATE EMISSION CALCULATION SHEETS
- VI NOMENCLATURE SHEETS
- VII FIELD DATA SHEETS - UNIT OPERATING CONDITIONS
- VIII FIELD DATA SHEETS - STACK TESTING
- IX LABORATORY RESULTS
- X EQUIPMENT CALIBRATION SHEETS
- XI PAGE 202, 203 FROM CONTROL ROOM LOG BOOK

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

1.0 COMPENDIUM

Eastmount Engineering conducted a Compliance Particulate Emissions Test Program on Unit #10 at Okeelanta Corporation's South Bay, Florida facility on January 29, 30 and 31, 1992. The test program was an EPA first class audit and consisted of two series of three EPA Method 5 test runs.

All testing was conducted in strict accordance with the Environmental Protection Agency's Reference Methods 1 through 5 as found in the Federal Register (40 CFR 60) as amended and were consistent with the State of Florida Department of Environmental Regulation's guidelines.

The purpose of this test was to determine compliance with the rules of the Department of Environmental Regulation, Chapter 17-2.600 Air Pollution, Section 2.05 Prohibitive Acts, Subsection 6, Stationary Sources, Table II, Emission Limiting Standards.

While testing the boiler was burning bagasse as fuel. Boiler #10 has a maximum rated capacity of 125,000 pounds of steam per hour. During run #3 of the first series of tests, performed on January 30, 1992, soot blowers No. 1 and No. 2 for Boiler No. 10 were stuck in the open position. Considering this malfunction, The steam flow production is directly affected by the loss of heat in the economizer due to the excess air used to blow soot off the economizer tubes. It is the opinion of Okeelanta corporation and Eastmount Engineering that the process conditions of run #3 were not normal operating procedures. The malfunction in the soot blower is recorded in the control room log book and is presented in Appendix XI of this report.

Results of the test program are presented in the table on the following page which summarizes the emission results, the emission standards, and the boiler operating conditions. The data for run #3 is included in the summary table for reporting purposes however, it is not included in the average for the test series. The two averages that are presented represent runs 1,2, and 1R and runs 1,2,1R,2R and 3R.

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

1.0 COMPENDIUM (cont)

SUMMARY OF RESULTS
COMPLIANCE PARTICULATE TESTING
UNIT NO. 10

RUN #	DATE	EMISSION RATE		ALLOWABLE		LOAD	% OF
		LB/MMBtu	LB/HR	LB/MMBtu	LB/HR	LB/HR-125	KPPH
1	01-29-92	.194	38.51	.20	39.78	97,754	78.2%
2	01-29-92	.207	39.70	.20	38.28	93,600	74.9%
3*	01-30-92	.219	39.77	.20	36.26	88,645	70.4%
1R	01-31-92	.196	37.49	.20	38.24	93,138	74.5%
2R	01-31-92	.180	33.86	.20	37.60	91,754	73.4%
3R	01-31-92	.160	28.87	.20	36.13	88,062	70.4%
AVERAGE							
RUNS 1,2 & 1R		.199	38.57	.20	38.78	94,831	75.9%
AVERAGE RUNS							
1,2,1R,2R & 3R		.187	35.69	.20	38.01	92,862	74.3%

* - represents run with soot blowers stuck open

Sean MacKay, Project Director, was in charge of and responsible for all stack testing, conducted all calculations and maintained chain of custody of all samples. Brian Gibson operated the meter box and assisted in the field laboratory. Pat Wildman located the probe at the proper traverse point locations and assisted where required. Michael Wayt of South Florida Environmental Services performed the analysis on all filters and washes. Mr. Kenneth Tucker of the Florida Department of Environmental Regulation observed the stack testing and boiler operations as well as Mr. Ajay Satyel and Mr. Jeff Koerner of the Palm Beach County Public Health Unit. Mr. Alberto Padrone was the boiler room superintendent and acted as liaison between Okeelanta Corporation and the Florida DER and county. Mr. George Devane was responsible for boiler operations and acquisition of all pertinent process data.


Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

2.0 STACK SCHEMATIC

OKEELANTA CORPORATION
Boiler #10
South Bay, Florida Facility

The following is a schematic of the stack which services Boiler #10 at Okeelanta Corporation's South Bay, Florida facility.

Defined are the sampling port locations, interior stack dimensions and distances from the ports to the nearest upstream and downstream interferences.




DISTANCE UPSTREAM FROM FLOW DISTURBANCE (A)	4'
DISTANCE DOWNSTREAM FROM FLOW DISTURBANCE (B)	16'
DIAMETER OF PORT SLEEVE (C)	4"
LENGTH OF PORT SLEEVE (D)	3.5"
NUMBER OF PORTS	2
INTERNAL DIAMETER OF STACK AT SAMPLING PORTS	7.5'

SCHEMATIC NOT TO SCALE

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

3.0 TRAVERSE POINT LOCATIONS AND SAMPLING TIME PER POINT

OKEELANTA CORPORATION
Boiler #10
South Bay, Florida Facility



Minimum number of traverse points for particulate traverses.

Distance A = 4' or 0.5 diameters.

Distance B = 16' or 2.1 diameters.

In accordance with Method 1, 24 traverse points are needed.

In order to sample for a minimum of one hour and draw at least 30 cubic feet, each traverse point was sampled for 2.5 minutes.

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

3.0 TRAVERSE POINT LOCATIONS AND SAMPLING TIME PER POINT (cont)

OKEELANTA CORPORATION
Boiler #10
South Bay, Florida Facility

DIAMETER OF STACK: 7.5 FEET
PORT SLEEVE LENGTH: 3.5 INCHES

TRAVERSE POINT	DISTANCE % OF DIAMETER	DISTANCE (INCHES)	PROBE MARKING (INCHES)
1	2.1	1.9	5.4
2	6.7	6.0	9.5
3	11.8	10.6	14.1
4	17.7	15.9	19.4
5	25.0	22.5	26.0
6	35.6	32.0	35.5
7	64.4	57.9	61.5
8	75.0	67.5	71.0
9	82.3	74.1	77.6
10	88.2	79.4	82.9
11	93.3	84.0	87.5
12	97.9	88.1	91.6

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES

The following is a description of the sampling train and specifications of particulate collection media used in the tests.

4.1 EMISSION SAMPLING EQUIPMENT

The specific train used during this test is one manufactured by Research Appliance Company (RAC). The design specifications of this train meets all the requirements of Environmental Protection Agency's Method 5 as found in the Federal Regulations under Section 40 CFR 60 as amended. The following is a description of the individual pieces of equipment used:

Nozzle - The nozzle was of seamless stainless steel tubing construction of the button hook design. A range of sizes suitable for isokinetic sampling was available. All nozzles were calibrated before testing. A nozzle calibration sheet may be found in the calibration section of this report.

Probe - An 10 foot steel probe with a stainless steel liner was used.

Heating System - The filter temperature was maintained by enclosing the filter in a hot box capable of maintaining the temperature at $248^{\circ}\text{F} \pm 25^{\circ}\text{F}$. This temperature was monitored by use of a thermocouple in the hot box.

Pitot Tube - A type S pitot tube attached to the probe was used to monitor the stack gas velocity. Since the pitot tube meets all the dimensional criteria set forth in Method 2 of 40 CFR 60, a coefficient of 0.84 has been used.

Filter Holder - A borosilicate glass type filter holder with frit support was used.

Condenser - Four impingers connected in series, with ground glass leak-free fittings were used as the condenser. The first, third and fourth impingers were of the Greenburg-Smith design, modified by replacing the tip with a 1/2" glass tube extending to about 1/2" from the bottom of the flask. The second impinger was of the Greenburg-Smith design with the standard tip.

Metering System - A vacuum gauge, micromanometer, inclined manometer, leak-free pump, calibrated thermocouples and a calibrated dry gas meter were the basic components used to meter the dry gas through the system.

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Gas Density Determination - An ORSAT type combustion analyzer, capable of measuring CO₂, O₂ and CO was used to determine the molecular weight of the flue gas. An integrated proportional sample was taken at each of the traverse points in order to assure that the total test span was covered. The ORSAT analysis was conducted immediately following each test run.

4.2 SAMPLING AND ANALYTICAL PROCEDURES

All sampling and analytical procedures were conducted in strict accordance with the methods prescribed in Methods 1 through 5 of the Code of Federal Regulations as found in 40 CFR 60 as amended. The following is the sequence of events that occur both prior to and during the actual stack test.

Traverse Points - The traverse points were calculated in accordance with Method 1 and the probe was marked accordingly.

Static Pressure - The static pressure was checked and recorded.

Preliminary Traverse - A preliminary traverse was conducted. Readings included the pressure drops and stack gas temperatures.

Nomograph - Once all of the above information had been obtained, the nomograph was set up for the actual test to correlate the isokinetic relationships.

Barometric Pressure - Barometric pressure was obtained by use of an aneroid barometer at the test site.

Sampling Train Set-Up

- (a) The pre-weighed filter was placed in the filter holder and visually checked.
- (b) 100 ml of water was placed in the first two impingers.
- (c) Approximately 200 grams of silica gel was placed in the fourth impinger. (Exact weights were logged on the field data sheets).
- (d) Crushed ice was placed around the impingers.
- (e) Once assembly of the entire train was completed, the probe and heater box were turned on.

Pre-test Leak Check - Once the heater box was at the desired temperature for testing, the system was leak checked at 15 inches of vacuum. A leakage rate of less than 0.02 CFM had to be achieved before testing commenced.

Final Check - Once everything was ready to go, the plant was checked to assure that it was running at desired capacity.

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Sampling - Isokinetic sampling as described in Method 5 then took place.

Post-test Leak Check - Upon completion of each test run, the system was leak checked at the highest vacuum recorded during that run. All leak checks were less than 0.02 CFM and considered acceptable.

Sample Recovery - Because of the importance of proper sample recovery procedures, details of the sample recovery can be found in the Quality Control Procedures Section of this report.

Isokinetics - Once all sample recovery was completed and the amount of moisture collected had been determined, calculations were conducted to determine the percent isokinetics of the test run.

Operating Data Sheets - All pertinent operating data were logged throughout the testing period by plant personnel.

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

5.0 QUALITY CONTROL PROCEDURES

The following is a description of the procedures used for maintaining the integrity of samples collected, including the chain of custody and quality control assurance of filters and acetone wash.

Pre-test preparation consisted of the filters being desiccated at $68 \pm 10^\circ\text{F}$ at ambient pressure for at least twenty four (24) hours. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved ± 0.5 mg change from the previous weighing. These pre-marked filters were then put into petri dishes and sealed. All filters used during testing were put into a carrying case for transport to the job site. A list of the filters and tare weights was available prior to testing.

After each test run, the filter and any particles which may have adhered to the filter holder gasket were carefully removed from the filter holder and placed into its identified petri dish container. This container was then labeled with the run number and date.

Taking care to see that particulate on the outside of the probe or other exterior surface did not get into the sample, particulate matter from the probe liner, nozzle, probe fittings, and front half of the filter holder were acetone washed into a sample container. This container was then sealed. The run number, date, and a mark indicating the level of the acetone wash in the bottle was recorded on the bottle.

Both the petri dish containing the filter and the bottle containing the acetone wash were transported to Eastmount Engineering's laboratory.

Once at the laboratory, each filter was weighed and then put back into its individual container. The container was then placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved ± 0.5 mg change from the previous weighing.

The levels marked on the bottles containing the acetone wash were checked to confirm that no leakage occurred during transport. The contents were then transferred into a pre-tared beaker and evaporated to dryness. Once this had been accomplished, the beaker was placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the beaker was re-weighed until a constant weight of ± 0.5 mg change from the previous weighing was achieved.

All calculations were conducted in strict accordance with 40 CFR 60 (See Calculation Sheets in report).

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX I

COMPUTER INPUT SHEETS

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-1
DATE : 01-29-92

Ds (FT) 7.5

Dn (IN) .260

FILTER#	4441	TRAV PT	VEL HEAD	SQ ROOT	DELTA H	DRYGAS IN	DRYGAS OUT	STACK TEMP
PIT COEFF	.84							
IMP-1 (INT)	100	A1	1.50	1.22	4.50	84	75	147
		2	1.50	1.22	4.50	90	75	146
		3	1.10	1.05	3.30	102	76	145
IMP-2 (INT)	100	4	1.00	1.00	3.00	107	77	143
		5	.93	.96	2.79	110	78	142
IMP-3 (INT)	0	6	.63	.79	1.89	111	78	141
		7	.34	.58	1.02	109	79	140
IMP-4 (INT)	500.0	8	.34	.58	1.02	106	79	140
		9	.34	.58	1.02	107	80	140
IMP-1 (FIN)	308	10	.47	.69	1.41	108	81	139
		11	.70	.84	2.10	109	81	139
IMP-2 (FIN)	130	12	.88	.94	2.64	114	81	138
IMP-3 (FIN)	4	B1	1.60	1.26	4.80	106	82	140
		2	1.50	1.22	4.50	120	83	142
IMP-4 (FIN)	518.5	3	1.20	1.10	3.60	125	83	142
		4	.99	.99	2.97	129	85	142
% CO2	7.9	5	.69	.83	2.07	125	85	142
		6	.33	.57	.99	123	86	142
% O2	12.5	7	.22	.47	.66	120	86	142
		8	.69	.83	2.07	119	86	142
% CO	0	9	.73	.85	2.19	120	86	142
		10	.85	.92	2.55	123	86	141
P BAR	30.00	11	.85	.92	2.55	124	87	142
		12	.99	.99	2.97	125	88	143
P STK	-.68							
NO. PTS	24							
TEST LNGTH	60							
END METER	74.862							
INT METER	23.982							
BEGIN TIME:	08:00							
END TIME:	09:05							
AVERAGE			.85	.89	2.55	113.2	81.8	141.8

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-2
DATE : 01-29-92

Ds (FT)	7.5							
Dn (IN)	.250							
FILTER#	4442	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		B1	1.70	1.30	5.10	84	79	143
IMP-1 (INT)	100	2	1.50	1.22	4.50	90	80	145
		3	1.30	1.14	3.90	100	80	145
IMP-2 (INT)	100	4	1.10	1.05	3.30	105	81	143
		5	.67	.82	2.01	109	81	141
IMP-3 (INT)	0	6	.47	.69	1.41	109	81	141
		7	.25	.50	.75	108	82	139
IMP-4 (INT)	500.0	8	.35	.59	1.05	108	82	139
		9	.56	.75	1.68	108	82	140
IMP-1 (FIN)	304	10	.72	.85	2.16	112	83	140
		11	.94	.97	2.82	116	83	141
IMP-2 (FIN)	126	12	.98	.99	2.94	120	84	141
IMP-3 (FIN)	2	A1	1.40	1.18	4.20	111	84	140
		2	1.40	1.18	4.20	122	85	140
IMP-4 (FIN)	516.8	3	1.20	1.10	3.60	127	86	140
		4	1.10	1.05	3.30	130	87	140
% CO2	8.8	5	.90	.95	2.70	130	88	139
		6	.65	.81	1.95	128	89	139
% O2	11.5	7	.27	.52	.81	125	88	139
		8	.24	.49	.72	120	88	139
% CO	0	9	.34	.58	1.02	118	88	139
		10	.50	.71	1.50	118	89	139
P BAR	30.08	11	.64	.80	1.92	120	89	140
		12	.76	.87	2.28	123	89	140
P STK	-.68							
NO. PTS	24							
TEST LNGTH	60							
END METER	125.246							
INT METER	75.200							
BEGIN TIME:	10:15							
END TIME:	11:20							
AVERAGE			.83	.88	2.49	114.2	84.5	140.5

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-3
DATE : 01-30-92

Ds (FT)	7.5							
Dn (IN)	.260							
FILTER#	4443	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		A1	1.40	1.18	4.20	78	75	141
IMP-1 (INT)	100	2	1.30	1.14	3.60	86	75	144
		3	1.10	1.05	3.30	91	76	144
IMP-2 (INT)	100	4	.90	.95	2.70	99	77	144
		5	.68	.82	2.04	104	77	145
IMP-3 (INT)	0	6	.36	.60	1.08	104	77	147
		7	.22	.47	.66	103	78	147
IMP-4 (INT)	500.0	8	.36	.60	1.08	104	78	141
		9	.60	.77	1.80	107	78	142
IMP-1 (FIN)	310	10	.76	.87	2.28	111	80	143
		11	.95	.97	2.85	117	81	143
IMP-2 (FIN)	128	12	1.10	1.05	3.30	118	81	143
IMP-3 (FIN)	5	B1	1.10	1.05	3.30	113	83	142
		2	1.10	1.05	3.30	120	83	142
IMP-4 (FIN)	514.8	3	1.10	1.05	3.30	123	84	141
		4	.97	.98	2.91	126	85	140
% CO2	7.9	5	.80	.89	2.40	128	87	140
		6	.54	.73	1.62	127	87	140
% O2	12.5	7	.20	.45	.60	122	87	139
		8	.29	.54	.87	120	88	140
% CO	0	9	.42	.65	1.26	119	87	140
		10	.55	.74	1.65	120	88	138
P BAR	30.00	11	.80	.89	2.40	124	88	138
		12	.93	.96	2.79	127	89	138
P STK	-.68							
NO. PTS	24							
TEST LNTH	60							
END METER	174.856							
INT METER	126.000							
BEGIN TIME:	13:10							
END TIME:	14:12							
AVERAGE			.77	.85	2.30	112.1	82.0	141.8

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-1
DATE : 01-31-92

Ds (FT)	7.5							
Dn (IN)	.260							
FILTER#	4457	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		B1	1.10	1.05	3.30	79	77	139
IMP-1 (INT)	100	2	1.10	1.05	3.30	83	75	139
		3	.85	.92	2.55	93	76	140
IMP-2 (INT)	100	4	.71	.84	2.13	96	76	140
		5	.46	.68	1.38	100	77	140
IMP-3 (INT)	0	6	.27	.52	.81	100	77	141
		7	.21	.46	.63	100	77	141
IMP-4 (INT)	500.0	8	.38	.62	1.14	100	77	139
		9	.53	.73	1.59	104	77	141
IMP-1 (FIN)	280	10	.66	.81	1.98	106	78	141
		11	.82	.91	2.46	111	79	141
IMP-2 (FIN)	120	12	.86	.93	2.58	113	80	141
IMP-3 (FIN)	4	A1	1.10	1.05	3.30	106	80	140
		2	1.05	1.02	3.15	111	81	138
IMP-4 (FIN)	513.5	3	.95	.97	2.85	118	82	139
		4	.85	.92	2.55	120	82	136
% CO2	9.1	5	.72	.85	2.16	121	83	137
		6	.47	.69	1.41	119	83	138
% O2	11.2	7	.24	.49	.72	114	84	138
		8	.22	.47	.66	111	83	139
% CO	0	9	.37	.61	1.11	111	84	139
		10	.46	.68	1.38	112	84	139
P BAR	29.94	11	.73	.85	2.19	115	84	139
		12	.79	.89	2.37	119	84	138
P STK	-.68							
NO. PTS	24							
TEST LGTH	60							
END METER	220.604							
INT METER	175.201							
BEGIN TIME:	09:00							
END TIME:	10:05							
AVERAGE			.66	.79	1.99	106.8	80.0	139.3

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-2
DATE : 01-31-92

Ds (FT)	7.5							
Dn (IN)	.265							
FILTER#	4458	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		B1	1.30	1.14	3.90	81	78	140
IMP-1 (INT)	100	2	1.30	1.14	3.90	90	78	141
		3	1.05	1.02	3.15	96	79	140
IMP-2 (INT)	100	4	.92	.96	2.76	102	78	138
		5	.53	.73	1.59	104	79	138
IMP-3 (INT)	0	6	.31	.56	.93	103	79	139
		7	.24	.49	.72	102	79	139
IMP-4 (INT)	500.0	8	.35	.59	1.05	102	80	138
		9	.52	.72	1.56	103	80	137
IMP-1 (FIN)	286	10	.65	.81	1.95	108	80	138
		11	.84	.92	2.52	111	81	138
IMP-2 (FIN)	122	12	.92	.96	2.76	115	81	139
IMP-3 (FIN)	2	A1	1.30	1.14	3.60	104	81	139
		2	1.30	1.14	3.60	111	82	139
IMP-4 (FIN)	513.0	3	1.10	1.05	3.30	116	83	138
		4	.94	.97	2.82	119	84	139
% CO2	8.6	5	.70	.84	2.10	120	84	139
		6	.42	.65	1.26	116	84	139
% O2	11.7	7	.15	.39	.45	113	84	139
		8	.23	.48	.69	111	84	140
% CO	0	9	.35	.59	1.05	111	84	139
		10	.47	.69	1.41	112	84	138
P BAR	29.95	11	.64	.80	1.92	114	84	139
		12	.69	.83	2.07	116	84	139
P STK	-.68							
NO. PTS	24							
TEST LNTH	60							
END METER	267.504							
INT METER	211.101							
BEGIN TIME:	11:00							
END TIME:	12:05							
AVERAGE			.72	.82	2.13	107.5	81.4	138.8

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-3
DATE : 01-31-92

Ds (FT)	7.5							
Dn (IN)	.260							
FILTER#	4471	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		B1	1.10	1.05	3.08	87	78	138
IMP-1 (INT)	100	2	1.05	1.02	2.94	98	78	138
		3	.89	.94	2.49	106	79	139
IMP-2 (INT)	100	4	.71	.84	1.99	110	80	138
		5	.45	.67	1.26	111	80	137
IMP-3 (INT)	0	6	.27	.52	.76	110	80	138
		7	.18	.42	.50	107	81	137
IMP-4 (INT)	500.0	8	.25	.50	.70	106	81	136
		9	.53	.73	1.48	108	81	138
IMP-1 (FIN)	260	10	.69	.83	1.93	110	81	137
		11	.88	.94	2.46	116	82	136
IMP-2 (FIN)	118	12	.97	.98	2.72	117	83	136
IMP-3 (FIN)	1	A1	1.05	1.02	2.94	109	83	136
		2	1.05	1.02	2.94	116	83	137
IMP-4 (FIN)	512.1	3	.97	.98	2.72	118	84	137
		4	.88	.94	2.46	120	83	136
% CO2	7.9	5	.68	.82	1.90	122	86	137
		6	.42	.65	1.18	119	86	136
% O2	12.5	7	.20	.45	.56	118	86	135
		8	.20	.45	.56	113	86	135
% CO	0	9	.35	.59	.98	111	85	134
		10	.45	.67	1.26	113	86	134
P BAR	29.96	11	.68	.82	1.90	116	86	136
		12	.85	.92	2.38	118	86	137
P STK	-.68							
NO. PTS	24							
TEST LGTH	60							
END METER	311.658							
INT METER	267.821							
BEGIN TIME:	13:05							
END TIME:	14:10							
AVERAGE			.66	.78	1.84	111.6	82.7	136.6

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX II

ISOKINETIC CALCULATION SHEETS

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-1
DATE : 01-29-92

TS (°F)=	141.8	% CO2=	7.9	VM (CF)	=	50.880
TS (°R)=	601.8	% O2=	12.5	DELTA H (ABS)=		30.19
TM (°F)=	97.5	% CO=	0	PS (ABS)	=	29.95
TM (°R)=	557.5	% N2=	79.6	SQRT DELTA P	=	.893508
VI (TOT)=	260.5	CP=	.84	AREA NOZZLE	=	.000369
						Y = .9911
VM STD	=	17.64	$\frac{(VM)(Y)(DELTA H ABS)}{(TM)}$	=	48.17	DSCF
VW STD	=	.04707	(VI TOT)	=	12.26	CF
BWO	=	$\frac{VW STD}{VW STD + VM STD}$		=	.203	
BWO	=	MOISTURE FROM STEAM TABLES			=	.206
VI TOT	=	ADJUSTED TO SATURATION VOLUME=			N/A	ML
1-BWO	=	1 - BWO		=	.797	
Md (DRY)	=	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2)		=	29.76	LBS/LB MOLE
Ms (WET)	=	MD (1-BWO) + 18 (BWO)		=	27.38	LBS/LB MOLE
G	=	SQRT (TS / PS / MS)		=	.86	
VS	=	85.49 (CP) (G) (SQRT DELTA P)		=	55.0	FPS
H	=	0.002669 (VI TOT)		=	.70	
J	=	(DELTA H ABS) (VM) (Y) / (TM)		=	2.73	
K	=	(H) + (J)		=	3.43	
% ISO	=	$\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$		=	94.4	

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-2
DATE : 01-29-92

TS (°F) = 140.5	% CO2 = 8.8	VM (CF) = 50.046
TS (°R) = 600.5	% O2 = 11.5	DELTA H (ABS) = 30.26
TM (°F) = 99.4	% CO = 0	PS (ABS) = 30.03
TM (°R) = 559.4	% N2 = 79.7	SQRT DELTA P = .879446
VI (TOT) = 248.8	CP = .84	AREA NOZZLE = .000341

	(VM) (Y) (DELTA H ABS)	Y = .9911
VM STD = 17.64	----- (TM)	= 47.34 DSCF
VW STD = .04707 (VI TOT)		= 11.71 CF
BWO =	VW STD ----- VW STD + VM STD	= .198
BWO =	MOISTURE FROM STEAM TABLES	= .198
VI TOT =	ADJUSTED TO SATURATION VOLUME	= 248.8 ML
1-BWO =	1 - BWO	= .802
Md (DRY) =	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2) -----	= 29.87 LBS/LB MOLE
Ms (WET) =	MD (1-BWO) + 18 (BWO) -----	= 27.52 LBS/LB MOLE
G =	SQRT (TS / PS / MS)	= .85
VS =	85.49 (CP) (G) (SQRT DELTA P)	= 53.8 FPS
H =	0.002669 (VI TOT)	= .66
J =	(DELTA H ABS) (VM) (Y) / (TM)	= 2.68
K =	(H) + (J)	= 3.35
% ISO =	(TS) (K) (1.667) ----- (TIME) (VS) (PS) (AN)	= 101.3

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-3
DATE : 01-30-92

TS (°F) = 141.8	% CO2 = 7.9	VM (CF) = 48.856
TS (°R) = 601.8	% O2 = 12.5	DELTA H (ABS) = 30.17
TM (°F) = 97.1	% CO = 0	PS (ABS) = 29.95
TM (°R) = 557.1	% N2 = 79.6	SQRT DELTA P = .853301
VI (TOT) = 257.8	CP = .84	AREA NOZZLE = .000369

		Y = .9911
VM STD = 17.64	(VM) (Y) (DELTA H ABS) ----- (TM)	= 46.26 DSCF
VW STD = .04707 (VI TOT)		= 12.13 CF
BWO =	VW STD ----- VW STD + VM STD	= .208
BWO =	MOISTURE FROM STEAM TABLES	= .206
VI TOT =	ADJUSTED TO SATURATION VOLUME	= 254.3 ML
1-BWO =	1 - BWO	= .794
Md (DRY) =	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2) -----	= 29.76 LBS/LB MOLE
Ms (WET) =	MD (1-BWO) + 18 (BWO) -----	= 27.34 LBS/LB MOLE
G =	SQRT (TS / PS / MS)	= .86
VS =	85.49 (CP) (G) (SQRT DELTA P)	= 52.5 FPS
H =	0.002669 (VI TOT)	= .68
J =	(DELTA H ABS) (VM) (Y) / (TM)	= 2.62
K =	(H) + (J)	= 3.30
% ISO =	(TS) (K) (1.667) ----- (TIME) (VS) (PS) (AN)	= 95.1

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-1
DATE : 01-31-92

TS (°F) = 139.3	% CO2 = 9.1	VM (CF) = 45.403
TS (°R) = 599.3	% O2 = 11.2	DELTA H (ABS) = 30.09
TM (°F) = 93.4	% CO = 0	PS (ABS) = 29.89
TM (°R) = 553.4	% N2 = 79.7	SQRT DELTA P = .791706
VI(TOT) = 217.5	CP = .84	AREA NOZZLE = .000369

		Y = .9911
VM STD = 17.64	$\frac{(VM)(Y)(DELTA H ABS)}{(TM)}$	= 43.16 DSCF
VW STD = .04707 (VI TOT)		= 10.24 CF
BWO =	$\frac{VW STD}{VW STD + VM STD}$	= .192
BWO =	MOISTURE FROM STEAM TABLES	= .193
VI TOT =	ADJUSTED TO SATURATION VOLUME	= N/A ML
1-BWO = 1 - BWO		= .808
Md (DRY) =	$\begin{aligned} &.44 (\% CO2) \\ &+.32 (\% O2) \\ &+.28 (\% CO) \\ &+.28 (\% N2) \end{aligned}$	= 29.91 LBS/LB MOLE
Ms (WET) =	$\begin{aligned} &MD (1-BWO) \\ &+ 18 (BWO) \end{aligned}$	= 27.62 LBS/LB MOLE
G =	$SQRT (TS / PS / MS)$	= .85
VS =	$85.49(CP)(G)(SQRT DELTA P)$	= 48.4 FPS
H =	$0.002669 (VI TOT)$	= .58
J =	$(DELTA H ABS)(VM)(Y) / (TM)$	= 2.45
K =	$(H) + (J)$	= 3.03
% ISO =	$\frac{(TS)(K)(1.667)}{(TIME)(VS)(PS)(AN)}$	= 94

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-2
DATE : 01-31-92

TS (°F) = 138.8	% CO2 = 8.6	VM (CF) = 56.403
TS (°R) = 598.8	% O2 = 11.7	DELTA H (ABS) = 30.11
TM (°F) = 94.5	% CO = 0	PS (ABS) = 29.90
TM (°R) = 554.5	% N2 = 79.7	SQRT DELTA P = .816320
VI(TOT) = 223.0	CP = .84	AREA NOZZLE = .000383

		Y = .9911
VM STD = 17.64	(VM) (Y) (DELTA H ABS) ----- (TM)	= 53.54 DSCF
VW STD = .04707	(VI TOT)	= 10.50 CF
BWO =	VW STD ----- VW STD + VM STD	= .164
BWO =	MOISTURE FROM STEAM TABLES	= .191
VI TOT =	ADJUSTED TO SATURATION VOLUME	= N/A ML
1-BWO =	1 - BWO	= .836
Md (DRY) =	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2) -----	= 29.85 LBS/LB MOLE
Ms (WET) =	MD (1-BWO) + 18 (BWO) -----	= 27.91 LBS/LB MOLE
G =	SQRT (TS / PS / MS)	= .85
VS =	85.49 (CP) (G) (SQRT DELTA P)	= 49.7 FPS
H =	0.002669 (VI TOT)	= .60
J =	(DELTA H ABS) (VM) (Y) / (TM)	= 3.04
K =	(H) + (J)	= 3.63
% ISO =	(TS) (K) (1.667) ----- (TIME) (VS) (PS) (AN)	= 106

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-3
DATE: 01-31-92

TS (°F) = 136.6 *Aug = 139* % CO2 = 7.9 VM (CF) = 43.837
 TS (°R) = 596.6 % O2 = 12.5 DELTA H (ABS) = 30.10
 TM (°F) = 97.1 % CO = 0 PS (ABS) = 29.91
 TM (°R) = 557.1 % N2 = 79.6 SQRT DELTA P = .783514
 VI (TOT) = 191.1 CP = .84 AREA NOZZLE = .000369

Y = .9911

VM STD = 17.64 (VM) (Y) (DELTA H ABS) / (TM) = 41.40 DSCF
 VW STD = .04707 (VI TOT) = 9.00 CF
 BWO = $\frac{\text{VW STD}}{\text{VW STD} + \text{VM STD}}$ = .178
 BWO = MOISTURE FROM STEAM TABLES = .180
 VI TOT = ADJUSTED TO SATURATION VOLUME = N/A ML
 1-BWO = 1 - BWO = .822
 Md (DRY) = $\frac{.44 (\% \text{ CO}_2) + .32 (\% \text{ O}_2) + .28 (\% \text{ CO}) + .28 (\% \text{ N}_2)}{1}$ = 29.76 LBS/LB MOLE
 Ms (WET) = $\frac{\text{MD} (1-\text{BWO}) + 18 (\text{BWO})}{1}$ = 27.66 LBS/LB MOLE
 G = $\sqrt{\text{TS} / \text{PS} / \text{MS}}$ = .85
 VS = 85.49 (CP) (G) (SQRT DELTA P) = 47.8 FPS
 H = 0.002669 (VI TOT) = .51
 J = (DELTA H ABS) (VM) (Y) / (TM) = 2.35
 K = (H) + (J) = 2.86
 % ISO = $\frac{(\text{TS}) (K) (1.667)}{(\text{TIME}) (VS) (PS) (AN)}$ = 90

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX III
ENTHALPY CALCULATION SHEETS

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
 LOCATION: UNIT 10

RUN #: COMP-1
 DATE : 01-29-92

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	408	670	260
	348	670	
	343	670	
	354	670	
	348	670	
 AVERAGE	 360.2 PSIG	 670.0	 260.0
 P ABS =	 374.9 PSIA		
 ENTHALPY @	 700 'F AND	 370 PSIA =	 1363.6
ENTHALPY @	600 'F AND	370 PSIA =	1309.1
ENTHALPY @	670.0 'F AND	370 PSIA =	1347.3
 ENTHALPY OF FEED WATER =		 228.76	
AVERAGE ENTHALPY =		1118.5	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-2
DATE : 01-29-92

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	336	670	260
	348	680	
	348	680	
	348	680	
	348	680	
AVERAGE	345.6 PSIG	678.0	260.0
P ABS =	360.3 PSIA		
ENTHALPY @	700 'F AND	360 PSIA =	1365.6
ENTHALPY @	600 'F AND	360 PSIA =	1310.6
ENTHALPY @	678.0 'F AND	360 PSIA =	1353.5
ENTHALPY OF FEED WATER =		228.76	
AVERAGE ENTHALPY =		1124.7	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-3
DATE : 01-30-92

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	348	690	260
	348	700	
	360	680	
	348	670	
	354	670	
AVERAGE	351.6 PSIG	682.0	260.0
P ABS =	366.3 PSIA		
ENTHALPY @	700 'F AND	370 PSIA =	1363.6
ENTHALPY @	600 'F AND	370 PSIA =	1309.1
ENTHALPY @	682.0 'F AND	370 PSIA =	1353.8
ENTHALPY OF FEED WATER =		228.76	
AVERAGE ENTHALPY =		1125.0	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET -----

PLANT : OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-1
DATE : 01-31-92

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	342	680	260
	378	690	
	354	690	
	390	690	
	354	690	
AVERAGE	363.6 PSIG	688.0	260.0
P ABS =	378.3 PSIA		
ENTHALPY @	700 'F AND	380 PSIA =	1364.5
ENTHALPY @	600 'F AND	380 PSIA =	1309.0
ENTHALPY @	688.0 'F AND	380 PSIA =	1357.8
ENTHALPY OF FEED WATER =		228.76	
AVERAGE ENTHALPY =		1129.1	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-2
DATE : 01-31-92

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	354	680	260
	384	690	
	360	680	
	342	680	
	370	690	
 AVERAGE	 362.0 PSIG	 684.0	 260.0
 P ABS =	 376.7 PSIA		
 ENTHALPY @	 700 'F AND	 380 PSIA =	 1364.5
ENTHALPY @	600 'F AND	380 PSIA =	1309.0
ENTHALPY @	684.0 'F AND	380 PSIA =	1355.6
 ENTHALPY OF FEED WATER =		 228.76	
AVERAGE ENTHALPY =		1126.9	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-3
DATE : 01-31-92

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	354	690	260
	354	690	
	354	690	
	354	690	
	342	680	
AVERAGE	351.6 PSIG	688.0	260.0
P ABS =	366.3 PSIA		
ENTHALPY @	700 'F AND	370 PSIA =	1363.6
ENTHALPY @	600 'F AND	370 PSIA =	1309.1
ENTHALPY @	688.0 'F AND	370 PSIA =	1357.1
ENTHALPY OF FEED WATER =		228.76	
AVERAGE ENTHALPY =		1128.3	BTU/LB OF STEAM

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX IV

HEAT INPUT CALCULATION SHEETS

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-1
DATE: 01-29-92

STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
END 847769	9: 5	100
BEGIN 846710	8: 0	LBS/HR STEAM
NET 1059 X 100 / 65	MINS =	97754

97754 LBS/HR STEAM / 55% EFF. = 177734 EQUIV.

177734 LBS/HR STEAM X 1118 BTU/LB = 198.8 BTU(e6)/HR

OIL INTEGRATOR READINGS	TIME	GALS/HR
END 0	9: 5	
BEGIN 0	8: 0	
NET 0 GALLONS	65 MINS =	0 GPH

0 GPH X 150,000 BTU/GAL (EST) = 0 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	198.8	-	0	X	.2	=	39.8	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	39.8	LBS/HR
							.200	LB/MMBTU

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-2
DATE: 01-29-92

	<u>STEAM INTEGRATOR READINGS</u>		<u>TIME</u>		<u>INTEGRATOR FACTOR</u>
END	849961		11: 20		100
BEGIN	848947		10: 15		LBS/HR STEAM
NET	<u>1014</u>	X	<u>100</u>	/ 65 MINS =	<u>93600</u>

93600 LBS/HR STEAM / 55% EFF. = 170182 EQUIV.

170182 LBS/HR STEAM X 1125 BTU/LB = 191.4 BTU(e6)/HR

	<u>OIL INTEGRATOR READINGS</u>		<u>TIME</u>		<u>GALS/HR</u>
END	0		11: 20		
BEGIN	0		10: 15		
NET	<u>0</u>	GALLONS	<u>65</u>	MINS =	0 GPH

0 GPH X 150,000 BTU/GAL (EST) = 0 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	191.4	-	0	X	.2	=	38.3	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	38.3	LBS/HR
							.200	LB/MMBTU

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-3
DATE: 01-30-92

	<u>STEAM INTEGRATOR READINGS</u>		<u>TIME</u>		<u>INTEGRATOR FACTOR</u>
END	869697		14: 12		100
BEGIN	868781		13: 10		LBS/HR STEAM
NET	916	X	100 / 62	MINS =	<u>88645</u>
88645	LBS/HR STEAM	/	55%	EFF. =	161173 EQUIV.
161173	LBS/HR STEAM	X	1125 BTU/LB	=	181.3 BTU(e6)/HR

	<u>OIL INTEGRATOR READINGS</u>		<u>TIME</u>		<u>GALS/HR</u>
END	0		14: 12		
BEGIN	0		13: 10		
NET	0	GALLONS	62	MINS =	0 GPH
0 GPH	X	150,000 BTU/GAL (EST)	=	0	BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	181.3	-	0	X	.2	=	36.3	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	36.3	LBS/HR
							.200	LB/MMBTU

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-1
DATE: 01-31-92

	<u>STEAM INTEGRATOR READINGS</u>		<u>TIME</u>		<u>INTEGRATOR FACTOR</u>
END	886796		10: 5		100
BEGIN	885787		9: 0		<u>LBS/HR STEAM</u>
NET	<u>1009</u>	X	<u>100</u>	/ 65 MINS =	93138
93138	LBS/HR STEAM	/	55% EFF.	=	169343 EQUIV.
169343	LBS/HR STEAM	X	1129 BTU/LB	=	191.2 BTU(e6)/HR

	<u>OIL INTEGRATOR READINGS</u>		<u>TIME</u>		<u>GALS/HR</u>
END	0		10: 5		
BEGIN	0		9: 0		
NET	<u>0</u>		<u>65</u>	MINS =	0 GPH
0 GPH	X 150,000 BTU/GAL (EST)	=	0		BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	191.2	-	0	X	.2	=	38.2	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	38.2	LBS/HR
							.200	LB/MMBTU

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-2
DATE: 01-31-92

	<u>STEAM INTEGRATOR READINGS</u>		<u>TIME</u>		<u>INTEGRATOR FACTOR</u>
END	888583		12: 5		100
BEGIN	887589		11: 0		LBS/HR STEAM
NET	994	X	100	/ 65 MINS =	91754
91754	LBS/HR STEAM	/	55%	EFF. =	166825 EQUIV.
166825	LBS/HR STEAM	X	1127	BTU/LB =	188.0 BTU(e6)/HR

	<u>OIL INTEGRATOR READINGS</u>		<u>TIME</u>		<u>GALS/HR</u>
END	0		12: 5		
BEGIN	0		11: 0		
NET	0	GALLONS	65	MINS =	0 GPH
0 GPH	X	150,000 BTU/GAL (EST)	=	0	BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	188.0	-	0	X	.2	=	37.6	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	37.6	LBS/HR
							.200	LB/MMBTU

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-3
DATE: 01-31-92

	<u>STEAM INTEGRATOR READINGS</u>	<u>TIME</u>	<u>INTEGRATOR FACTOR</u>
END	890528	14: 10	100
BEGIN	889574	13: 5	LBS/HR STEAM
NET	954	X 100 / 65	MINS = 88062

88062 LBS/HR STEAM / 55% EFF. = 160112 EQUIV.

160112 LBS/HR STEAM X 1128 BTU/LB = 180.7 BTU(e6)/HR

	<u>OIL INTEGRATOR READINGS</u>	<u>TIME</u>	<u>GALS/HR</u>
END	0	14: 10	
BEGIN	0	13: 5	
NET	0	GALLONS 65	MINS = 0 GPH

0 GPH X 150,000 BTU/GAL (EST) = 0 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	180.7	-	0	X	.2	=	36.1	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	36.1	LBS/HR
							.200	LB/MMBTU

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX V

PARTICULATE EMISSION CALCULATION SHEETS

PARTICULATE
EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-1
DATE: 01-29-92

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
	-----	-----	-----	-----
NO. :	4441	11	4423	221
FINAL:	.7189	71.6990	.6177	76.7835
TARE :	.5975	71.6809	.6177	76.7822
	-----	-----	-----	-----
NET :	.1214	.0181	.0000	.0013/200ML

WEIGHT =	139.50		VOLUME OF RINSE	300
RESIDUE =	-	1.95		
Mn =	137.55	Mg	AS =	44.2 SQ FT

Qs =	3600 (1-BWO) (VS) (AS) (17.64) (PS) / (TS)	=	6116610	DSCFH
CS =	(2.205 X 10 ⁻⁶) (Mn) / (VM STD)	=	6.297e-6	LBS/SCF
CS' =	0.0154 (Mn) / (VM STD)	=	.04	GRAINS / SCF
PMR =	(QS) (CS)	=	38.51	LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT	=	198.9	BTU e6 / HR
E =	LBS / MILLION BTu	=	.194	LBS / BTu e6
ALLOWABLE		=	39.78	LBS/HR
		=	.20	LBS / BTu e6

PARTICULATE
EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-2
DATE: 01-29-92

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
	-----	-----	-----	-----
NO. :	4442	115	4423	221
FINAL:	.7220	65.4121	.6177	76.7835
TARE :	.5984	65.3930	.6177	76.7822
	-----	-----	-----	-----
NET :	.1236	.0191	.0000	.0013/200ML

WEIGHT = 142.70
RESIDUE = - 1.95

VOLUME OF RINSE 300

Mn = 140.75 Mg AS = 44.2 SQ FT

Qs = 3600 (1-BWO) (VS) (AS) (17.64) (PS) / (TS) = 6055332 DSCFH

CS = (2.205 X 10⁻⁶) (Mn) / (VM STD) = 6.556e-6 LBS/SCF

CS' = 0.0154 (Mn) / (VM STD) = .05 GRAINS / SCF

PMR = (QS) (CS) = 39.70 LBS/HR

LOAD= MILLIONS OF BTU / HOUR INPUT = 191.4 BTU e6 / HR

E = LBS / MILLION BTu = .207 LBS / BTu e6

ALLOWABLE = 38.28 LBS/HR

= .20 LBS / BTu e6

PARTICULATE
EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: COMP-3
DATE: 01-30-92

	SAMPLES		BLANKS		
	FILTER	BEAKER	FILTER	ACETONE	
	-----	-----	-----	-----	
NO. :	4443	204	4423	221	
FINAL:	.7200	77.8755	.6177	76.7835	
TARE :	.5909	77.8601	.6177	76.7822	
	-----	-----	-----	-----	
NET :	.1291	.0154	.0000	.0013/200ML	
WEIGHT =	144.50		VOLUME OF RINSE 200		
RESIDUE =	- 1.30				
Mn =	143.20	Mg	AS =	44.2	SQ FT
Qs =	$3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$		=	5826873	DSCFH
CS =	$(2.205 \times 10^{-6})(Mn) / (VM \text{ STD})$		=	6.826e-6	LBS/SCF
CS' =	$0.0154 (Mn) / (VM \text{ STD})$		=	.05	GRAINS /SCF
PMR =	(QS) (CS)		=	39.77	LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT		=	181.3	BTU e6 / HR
E =	LBS / MILLION BTu		=	.219	LBS/ BTu e6
ALLOWABLE			=	36.26	LBS/HR
			=	.20	LBS/ BTu e6

PARTICULATE
EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-1
DATE: 01-31-92

	SAMPLES		BLANKS		
	FILTER	BEAKER	FILTER	ACETONE	
	-----	-----	-----	-----	
NO. :	4457	206	4423	221	
FINAL:	.7294	77.9223	.6177	76.7835	
TARE :	.6037	77.9125	.6177	76.7822	
	-----	-----	-----	-----	
NET :	.1257	.0098	.0000	.0013/200ML	
WEIGHT =	135.50		VOLUME OF RINSE		240
RESIDUE =	- 1.56				
Mn =	133.94	Mg	AS =	44.2	SQ FT
Qs =	$3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$		=	5478177	DSCFH
CS =	$(2.205 \times 10^{-6})(Mn) / (VM \text{ STD})$		=	6.843e-6	LBS/SCF
CS' =	$0.0154 (Mn) / (VM \text{ STD})$		=	.05	GRAINS /SCF
PMR =	(QS) (CS)		=	37.49	LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT		=	191.2	BTU e6 / HR
E =	LBS / MILLION BTu		=	.196	LBS/ BTu e6
ALLOWABLE			=	38.24	LBS/HR
			=	.20	LBS/ BTu e6

PARTICULATE
EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-2
DATE: 01-31-92

	SAMPLES		BLANKS		
	FILTER	BEAKER	FILTER	ACETONE	
	-----	-----	-----	-----	
NO. :	4458	209	4423	221	
FINAL:	.7335	76.3183	.6177	76.7835	
TARE :	.6088	76.3000	.6177	76.7822	
	-----	-----	-----	-----	
NET :	.1247	.0183	.0000	.0013/200ML	
WEIGHT =	143.00		VOLUME OF RINSE		250
RESIDUE =	- 1.63				
Mn =	141.38	Mg	AS =	44.2	SQ FT
Qs =	$3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$		=	5816246	DSCFH
CS =	$(2.205 \times 10^{-6})(Mn) / (VM \text{ STD})$		=	5.822e-6	LBS/SCF
CS' =	$0.0154 (Mn) / (VM \text{ STD})$		=	.04	GRAINS /SCF
PMR =	(QS) (CS)		=	33.86	LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT		=	188.0	BTU e6 / HR
E =	LBS / MILLION BTu		=	.180	LBS/ BTu e6
ALLOWABLE			=	37.60	LBS/HR
			=	.20	LBS/ BTu e6

PARTICULATE
EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 10

RUN #: CT-10R-3
DATE: 01-31-92

	SAMPLES		BLANKS	
	FILTER -----	BEAKER -----	FILTER -----	ACETONE -----
NO. :	4471	211	4423	221
FINAL:	.6848	79.1400	.6177	76.7835
TARE :	.5948	79.1304	.6177	76.7822
NET :	.0900	.0096	.0000	.0013/200ML
WEIGHT =	99.60	VOLUME OF RINSE 220		
RESIDUE = -	1.43			
Mn =	98.17 Mg	AS =	44.2	SQ FT
Qs =	$3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$		=	5520664 DSCFH
CS =	$(2.205 \times 10^{-6})(Mn) / (VM STD)$		=	5.229e-6 LBS/SCF
CS' =	$0.0154 (Mn) / (VM STD)$		=	.04 GRAINS/SCF
PMR =	(QS) (CS)		=	28.87 LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT		=	180.7 BTU e6 / HR
E =	LBS / MILLION BTu		=	.160 LBS/BTu e6
ALLOWABLE			=	36.13 LBS/HR
			=	.20 LBS/BTu e6

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX VI
NOMENCLATURE SHEETS

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

NOMENCLATURE SHEET

PARTICULATE EMISSIONS TEST

Ar	Acetone residue - result of Blank evaporation.
AREA NOZZLE	Area of the nozzle in square feet.
AS	Area of the stack in square feet.
BDL	Below detectable limits
BWO	The amount of moisture in the flue gas.
% CO	Percent of carbon monoxide in the flue gas.
% CO2	Percent of carbon dioxide in the flue gas.
Cp	Pitot tube coefficient.
CS	The concentration in the stack in pounds per standard cubic foot.
Cs'	The concentration in the stack in grains per standard cubic foot.
DELTA H	The meter orifice differential.
DELTA H (ABS)	The meter orifice differential, absolute conditions in inches of mercury.
Dn (IN)	Diameter of the nozzle in inches.
DRY GAS IN	Temperature of the dry gas meter inlet degrees Farenheight.
DRY GAS OUT	Temperature of the dry gas meter outlet degrees Farenheight.
Ds (FT)	Diameter of the stack in feet.
E	The emission rate in pounds per million Btu derived by using F-Factor.
E (Heat Input)	The emission rate in pounds per million Btu derived by use of calculated heat input.
END METER	The dry gas meter reading at the end of the test.
F factor	The theoretical amount of air in dry standard cubic feet (DSCF) needed to combust a million Btu's worth of fuel.

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

NOMENCLATURE (cont'd)

Filter Catch	The amount of particulate captured on the filter during testing.
INT METER	The dry gas meter reading at the beginning of the test.
Md (DRY)	The dry molecular weight of the flue gas in pounds per pound mole.
MN	The amount of particulate collected by washing the nozzle, probe, and front half of the glassware, reported in milligrams.
MN'	The milligrams of particulate collected minus the blank.
Ms (WET)	Wet or actual molecular weight of the flue gas in pounds per pound mole.
% N2	The percent of nitrogen in the flue gas.
NO PTS	Number of traverse points.
% O2	Percent of oxygen in the flue gas.
P BAR	Barometric pressure at test location.
P STK	Static pressure of the stack in inches of water.
PMR	The emission rate in pounds per hour.
PS (ABS)	Absolute pressure conditions in the stack in inches of mercury.
Qs	The volumetric flow rate of the flue gas in dry standard cubic feet per hour.
SQ ROOT	The square root of each velocity head measurement.
SQRT DELTA P	The average of the square roots of the measured pressure drops.
Stack Temp or TS (°F)	The temperature of the stack in degrees Fahrenheit.
TS (°R)	The temperature of the stack in degrees Rankine.
T (Hot Box)	Temperature around the filter box, degrees Fahrenheit.
TM (°F)	Average temperature of the dry gas meter in degrees Fahrenheit.

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

NOMENCLATURE (cont'd)

TM (°R)	Average temperature of the dry gas meter in degrees Rankine.
VEL HEAD	The pressure drop measured across the pitot tubes.
VI (TOT)	The amount of water collected in the impingers in milliliters.
VM (CF)	The volume sampled through the dry gas meter in cubic feet.
VM STD	Volume sampled through the dry gas meter corrected to standard conditions.
VS	Velocity of the stack gas in feet per second.
VW STD	The amount of moisture collected, converted to standard cubic feet.
Y	Meter box calibration factor.
o	Sampling time in minutes.

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX VII

FIELD DATA SHEETS - UNIT OPERATING CONDITIONS

740
 620
 20
 740
 620
 20

CAPACITY 125,000
 INT. FACTOR 100
 RUN 1 10-1

BOILER 1 10

MULTIPLE COMPARISON TESTING
 DATE 1-29-90
 TESTED BY: EASTMONT 444

TIME	STEAM INTERGRATOR	OIL METER	STEAM PRESS.	TEMP.	REACTING LBS/HR.	FEED WATER PRESS.	TEMP.	BOILER PRESSURE DROP
8:00	846710	1323650	1033202	408	670	97,000	200	260
8:15	846972	X						
8:30	847202							
8:45	847439							
9:05	847769	1323650	1033202	348	670	97,500	610	260
OVERFIRE AIR PRESS. AIR HEATER AIR OUT UNDERGRATE AIR PRESS. WIND BOX PRESSURE FURNACE PRESSURE AIR OUTLET PRESSURE DUST COLLECTOR OUT. SCRUBBER DIFF.								
BOILER TEMPERATURE BOILER OUTLET AIR HEATER GAS OUT AIR HEATER AIR OUT I.D. FAN S.H. STEAM TEMP.								
PANEL SETTINGS FURNACE PRESSURE F.D. FAN PRESSURE BAGASSE FEED UNDERGRATE AIR OVERFIRE AIR								

TEST RESULTS

OIL USED	None	GALES.
TOTAL TEST TIME	65	MIN.
INTERGRATOR TIME	1059	COUNT
INTERGRATOR STEAM	97,274	P.P.H
CHART READING	490,500	TOTAL
CHART AVERAGE	98,100	P.P.H.
I.D. FAN TURBINE	4800	RPM
STACK TEMPERATURE	145	°F
GRATE TEMPERATURE	None	°F
SCRUBBER WATER	1000	G.P.M.

COMMENTS: "A" "B"
 (1) Mill speed 85 F.P.H.
 (2) using no oil burner
 (3) Adjusted chart sh. steam temp @ 8:55

Allowed =

Actual =

PLANT READINGS BY Eastmont 444
 % OF CAPACITY

CAPACITY - 125,000
 INT. FACTOR 100
 RUN 1 10-2

BOILER 1 10

MULTITEST COMPLIANCE TESTING
 DATE: 1-29-92
 TESTED BY: P. J. Stancant Eng

TIME	STEAM INTEGRATOR	OIL METER		STEAM		WEIGHING LBS/HR.	FEED WATER		BOILER PRESSURE DROP			
		WATER	WATER	WATER	WATER		WATER	WATER	OVERFIRE AIR PRESS.	AIR HEATER AIR OUT	UNDERGRATE AIR PRESS.	WIND BOX PRESSURE
10:15	848947	1323650	1033702	336	670	97,500	620	260				
10:20	849204			308	680	97,500	620	260				
10:30	849437			348	680	99,000	610	260				
11:00	849672			348	680	90,000	610	260				
11:20	849961	1323650	1033702	348	680	82,500	610	260				

TEST RESULTS

OIL USED	1040	GALS.
TOTAL TEST TIME	65	MINS.
INTEGRATOR TIME	1014	COUNT
INTEGRATOR STEAM	93,600	P.P.H.
CHART READING	458,500	TOTAL
CHART AVERAGE	94,700	P.P.H.
I.D. FAN TURBINE	6860	RPM
STACK TEMPERATURE	143	°F
GRATE TEMPERATURE	None	°F
SCRUBBER WATER	R5T	

COMMENTS:

47 Mill speed 85 F.S. F.P.H.
 (2) Using no oil burners

Allowed =

Actual =

PLANT READINGS BY Gary Sullivan
 2 OF CAPACITY

26-DE-1

TEST RESULTS

QTY. USED	NO. WE	GALS.
TOTAL TEST TIME	57	MINS.
INTERGATOR TIME	916	COUNT
INTERGATOR STEAM	86, 421	° F
CHART READING	448, 600	TOTAL
CHART AVERAGE	89, 700	° F
I. O. FAN TURNING	4500	RPM
STACK TEMPERATURE	143	° F
GRATE TEMPERATURE	—	° F
SCRUBBER WATER	1000	G. P. M.

ಪ್ರತಿಪಕ್ಷ


REMARKS: "A" 85 "B" 85 F.P.H.
(1) MILE SPEED
(2) USING NO OIL BURNER.
(3)

Handwritten: 26/9/31
D.E.D.
Candace
phys
daily

Flowed = 73 mo 77 H

Actual =

ALL INFORMATION CONTAINED
HEREIN IS UNCLASSIFIED






CHART 125 000
 INT. FACTOR 100
 RUN 1 10-1R

BOTTLE 1 10

COLLECTION CONTINUOUS TESTING
 DATE: 1-31-92
 TESTED BY: E3ST/MOUNT Eng

TIME	STEAM INTEGRATOR	OIL METER	STEAM PRESS.	TEMP.	LOADING LBS/HR.	FEED WATER PRESS.	TEMP.	BOILER PRESSURE DROP
9:00	885787	1323980	342	680	88,500	600	260°	OVERFIRE AIR PRESS. AIR HEATER AIR OUT
9:15	886019		378	690	87,000	650	"	UNDERGRATE AIR PRESS. WIND BOX PRESSURE
9:30	886268		354	680	97,500	620	"	FURNACE PRESSURE AIR OUTLET PRESSURE
9:45	886487		390	690	88,500	650	"	DUST COLLECTOR OUT. SCRUBBER DIFF.
10:05	886796	1323980	354	690	90,000	600	"	
								BOILER TEMPERATURE
								BOILER OUTLET
								AIR HEATER GAS OUT
								AIR HEATER AIR OUT
								H.D. FAN
								S.H. STEAM TEMP.
								680 690 690 680
								PANEL SETTINGS
								FURNACE PRESSURE
								F.D. FAN PRESSURE
								BAGASSE FEED
								UNDERGRATE AIR
								OVERFIRE AIR

TEST RESULTS

OIL USED	NONE	GALS.
TOTAL TEST TIME	65	MINS.
INTEGRATOR TIME	1009	COUNT
INTEGRATOR STEAM	93,138	P.P.H.
CHART READING	451,000	TOTAL
CHART AVERAGE	90,300	P.P.H.
F.D. FAN TURNING	4200	RPM
STACK TEMPERATURE	140	°F
GRATE TEMPERATURE	NONE	°F
SCRUBBER WATER	1000	G.P.H.

COMMENTS:

(1) MILL SPEED 85
 (2) USING NO OIL BURNERS.

"A" "B"

Allowed =

Actual =

PLANT READINGS BY Gregory D. Della
 % OF CAPACITY

K. D. W. C. B. R.
 F.D. FAN
 1/11/92

CURRENT 125,000
INT. FACTOR 100
JUN 1 10-2R

BOILER 1 10

QUALITY CONTROL TESTING
DATE: 1-31-92
TESTED BY: R. J. H. H. H. H. H.

TIME	STEAM INTERGRATOR	OIL METER	STEAM PRESS.	TEMP.	RECYCLING LBS/HR.	FEED WATER PRESS.	TEMP.	BOILER PRESSURE DROP
11:00	887589	1323980	354	680	94,500	600	260	OVERFIRE AIR PRESS. AIR HEATER AIR OUT UNDERGRATE AIR PRESS. WIND BOX PRESSURE FURNACE PRESSURE BLR. OUTLET PRESSURE DUST COLLECTOR OUT. SCRUBBER DIFF.
11:15	887820		384	690	90,000	620	11	
11:30	888039		360	680	88,500	620	11	
11:45	888270		342	680	88,500	600	11	
12:05	888583	1323980	370	690	94,500	620	11	
								BOILER TEMPERATURE
								BOILER OUTLET AIR HEATER GAS OUT AIR HEATER AIR OUT I.D. FAN S.H. STEAM TEMP.
								680 690 680 680
								PANEL SETTINGS
								FURNACE PRESSURE F.D. FAN PRESSURE BAGASSE FEED UNDERGRATE AIR OVERFIRE AIR

TEST RESULTS

OIL USED	ADONIS	GALS.
TOTAL TEST TIME	65	MINS.
INTERGRATOR TIME	994	COUNT
INTERGRATOR STEAM	91,753	P.P.H.
CHART READING	456,000	TOTAL
CHART AVERAGE	91,200	P.P.H.
I.D. FAN TURBINE	4700	RPM
STACK TEMPERATURE	140	°F
GRATE TEMPERATURE	NONE	°F
SCRUBBER WATER	1000	G.P.M.

COMMENTS:

- (1) Mill speed 65 F.P.H.
- (2) Using no oil burners.


"A" "B"

Allowed =

Actual =

R. J. H. H. H. H. H.
F. J. H. H. H. H. H.
9/13/92

PLANT READINGS BY
% OF CAPACITY



Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX VIII

FIELD DATA SHEETS - STACK TESTING

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEELANTA</u>	Run #:	<u>Comp-1</u>
Location:	<u>UNIT 10</u>	Date:	<u>29 JAN 92</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>.260</u>	Test Length:	<u>60 min</u>
Filter #:	<u>4441</u>	End Meter Reading:	<u>48.678 74.862</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>23.982</u>
P bar:	<u>30.00</u>	Begin Time:	<u>08:00</u>
P stack:	<u>- .68</u>	End Time:	<u>09:05</u>
IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>308</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>130</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>4</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>518.5</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>8.1</u>	<u>7.9</u>	<u>8.0</u>
% O ₂	<u>12.4</u>	<u>12.5</u>	<u>12.5</u>
% CO	<u>0</u>	<u>0</u>	<u>0</u>

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>MacKay/GIBSON</u>
Meter Box Operator:	<u>B. GIBSON</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>P. Wiloman</u>	Plant Coordinator:	<u>G. DEWANE</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>K. TUCKER</u>

Comments:

A.J. SATY
JEFF KOERNER

K. Gibson
FDER
01/29/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 1 OF 2

SAMPLING TIME PER POINT 2.5 min

PLANT Okeelanta

RUN # Comp - 1

LOCATION Unit 8 10

DATE 29 JAN 92

23982

TRAV. NO.	DELTA P	DELTA H	METER READING	DGM IN	DGM OUT	HOT BOX	IMPG TEMP	STACK TEMP	VAC
A 1	1.5	4.5	26.8	84	75	260	60	147	8
2	1.5	4.5	29.6	90	75	261	61	146	9
3	1.1	3.3	32.1	102	76	265	63	145	6
4	1.0	3.0	34.4	107	77	265	63	143	5
5	.93	2.79	36.6	110	78	263	63	142	5
6	.63	1.89	38.6	111	78	264	62	141	3
7	.34	1.02	40.1	109	79	263	61	140	2
8	.34	1.02	41.5	106	79	267	61	140	2
9	.34	1.02	43.0	107	80	264	61	140	2
10	.47	1.41	44.5	108	81	261	61	139	2
11	.70	2.10	46.5	109	81	261	61	139	4
12	.88	2.64	48.678	114	81	261	61	138	5

11.2
11.5
12.0
12.5
12.8
12.5

COMMENTS: DELTA P x 3.0 = DELTA H
 BOX # 11 Y = .9911 DELTA H @ = 1.80
 START TIME: 0800
 END TIME: 09:03
 INITIAL LEAK CHECK .002 AT 15 INCHES HG
 FINAL LEAK CHECK .001 AT 15 INCHES HG
 Pre Pito p.d. ± 4.5 in H₂O

K. Tucker
FDER
01/29/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 2 OF 2

SAMPLING TIME PER POINT 2.5

PLANT Okeelanta

RUN # Comp - 1

LOCATION Unit 10

DATE 29 JAN 92

TRAV. NO.	DELTA P	DELTA H	METER READING	DGM IN	DGM OUT	HOT BOX	IMPG TEMP	STACK TEMP	VAC
B 1	1.6	4.8	51.6	106	82	255	60	140	13
2	1.5	4.5	54.5	120	83	255	60	142	12
3	1.2	3.6	57.0	125	83	257	63	142	10
4	.99	2.97	59.5	129	85	256	64	142	7
5	.69	2.07	61.5	125	85	255	64	142	5
6	.33	.99	63.0	123	86	256	64	142	2
7	.22	.66	64.2	120	86	258	64	142	1
8	.69	2.07	66.1	119	86	260	63	142	5
9	.73	2.19	68.2	120	86	263	63	142	5
10	.85	2.55	70.3	123	86	264	63	141	7
11	.85	2.55	72.4	124	87	264	64	142	7
12	.99	2.97	74.862	125	88	266	65	143	9

COMMENTS:

DELTA P * 3.0 = DELTA H

BOX # 11 Y = .9911 DELTA H @ = 1.80

START TIME: 0800

END TIME: 0903

INITIAL LEAK CHECK .002 AT 15 INCHES HG

FINAL LEAK CHECK .001 AT 15 INCHES HG

Pos Pit $\Delta P > \pm 2.6$ in H_2O

K. Jackson
FDERZ
01/29/92

EASTMOUNT ENGINEERING INC. • 420 MAIN STREET • NALPOLE, MA 02081 • (608) 668-9005

Port Change 3 min @ sec

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEE/ANTA</u>	Run #:	<u>Comp-2</u>
Location:	<u>UNIT 10</u>	Date:	<u>29 JAN 92</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>.250</u>	Test Length:	<u>60 MIN</u>
Filter #:	<u>554443 4442</u>	End Meter Reading:	<u>125.246</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>75.200</u>
P bar:	<u>30.08</u>	Begin Time:	<u>10:15</u>
P stack:	<u>-.68</u>	End Time:	<u>11:20</u>

IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>304</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>126</u>
IMP-3 (INT)	<u>0</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>516.8</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>8.8</u>	<u>8.8</u>	<u> </u>
% O ₂	<u>11.5</u>	<u>11.5</u>	<u> </u>
% CO	<u>0</u>	<u>0</u>	<u> </u>

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>MacKay/Gibson</u>
Meter Box Operator:	<u>B. Gibson</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>P. W. IOMAN</u>	Plant Coordinator:	<u>G. DEVANE</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>K. TUCKER</u> FIA DER <u>A.J. Smyth</u> P.B. County <u>JEFF KOERNEQ</u> P.B. County

Comments:

K. Tucker
FDER
1/29/92
Gibson/Smyth

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 1 OF 2

SAMPLING TIME PER POINT 2.5

PLANT Wheelabrator

RUN # Comp - 2

LOCATION Unit 10

DATE 29 JAN 92

75.200

TRAV. NO.	DELTA P	DELTA H	METER READING	DGM IN	DGM OUT	HOT BOX	IMPG TEMP	STACK TEMP	VAC
B 1	1.7	5.1	78.3	84	79	267	59	143	7
2	1.5	4.5	81.1	90	80	266	59	145	6
3	1.3	3.9	83.8	100	80	267	63	145	5
4	1.1	3.3	86.2	105	81	266	65	143	5
5	.67	2.01	88.2	109	81	267	62	141	3
6	.47	1.41	89.9	109	81	264	61	141	2
7	.25	.75	91.1	108	82	260	61	139	2
8	.35	1.05	92.6	108	82	263	60	139	2
9	.56	1.68	94.4	108	82	264	60	140	3
10	.72	2.16	96.3	112	93	264	61	140	3
11	.94	2.82	98.6	116	83	260	61	141	4
12	.98	2.94	100.968	120	84	259	62	141	5

COMMENTS: DELTA P * 3.0 = DELTA H
 BOX # 11 Y = .9911 DELTA H @ - 1.80
 START TIME : 1015
 END TIME :
 INITIAL LEAK CHECK .007 AT 16 INCHES HG
 FINAL LEAK CHECK AT INCHES HG
 Re ± > 4 in H₂O

[Signature]
 1/29
 K. Tucker
 FTER
 2/29/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 2 OF 2

SAMPLING TIME PER POINT

PLANT Okeelanta

RUN # Comp-2

LOCATION Unit 10

DATE 29 JAN 92

[illegible]

COMMENTS:

$$\Delta P \approx \underline{3.0} = \Delta H$$

BOX # 11 Y = .9911 DELTA H # = 1.80

START TIME : ~~900~~ 1015

END TIME :

INITIAL LEAK CHECK .007 AT 15 INCHES HG

FINAL LEAK CHECK 0.005 AT 10 INCHES HG

Post $P_{10} \geq \frac{7}{4}$

EASTMOUNT ENGINEERING INC. • 420 MAIN STREET • NALPOLE, MA 02081 • (508) 668-9005

Port charge 4.0 min

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEE/ANTA</u>	Run #:	<u>comp-3</u>
Location:	<u>UNIT 10</u>	Date:	<u>30 JAN 92</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>.260</u>	Test Length:	<u>60</u>
Filter #:	<u>4443</u>	End Meter Reading:	<u>174,856</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>126.000</u>
P bar:	<u>30.00</u>	Begin Time:	<u>13:10</u>
P stack:	<u>-.68</u>	End Time:	<u>14:12</u>
IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>310</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>128</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>5</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>514.8</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>7.9</u>	<u> </u>	<u> </u>
% O ₂	<u>12.5</u>	<u> </u>	<u> </u>
% CO	<u>0</u>	<u> </u>	<u> </u>

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>MacKay/Gibson</u>
Meter Box Operator:	<u>B. Gibson</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>P. W. IOMAN</u>	Plant Coordinator:	<u>G. DEWANE</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>K. TUCKER FIA DER</u>

Comments:

Mary Satyal

A.J. SATYAL P.B. County
JEFF KOERNER P.B. County

K. TUCKER FDER
01/30/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 1 OF 2

SAMPLING TIME PER POINT 2.5

PLANT Wheelabrator

RUN # Comp-3

LOCATION Unit 10

DATE 30 JAN 92

TRAV. NO.	DELTA P	DELTA H	METER READING	DGM IN	DGM OUT	HOT BOX	IMPG TEMP	STACK TEMP	VAC
A1	1.4	4.2	128.8	78	75	267	68	141	8
2	1.3	3.6	131.3	86	75	262	68	144	7
3	1.1	3.3	133.7	91	76	263	66	144	6
4	.90	2.70	136.1	99	77	263	66	144	5
5	.68	2.04	138.1	104	77	263	66	145	5
6	.36	1.08	139.6	104	77	262	64	147	2
7	.22	.66	140.8	103	78	266	64	147	2
8	.36	1.08	142.3	104	78	266	63	141	2
9	.60	1.80	144.1	107	78	262	62	142	3
10	.76	2.28	146.2	111	80	264	62	143	5
11	.95	2.85	148.4	117	81	266	63	143	7
12	1.1	3.3	150.8	118	81	266	63	143	9

COMMENTS:

DELTA P = 3.0 - DELTA H
 BOX # 11 Y = .9911 DELTA H = 1.80
 START TIME: 1310
 END TIME: 1412
 INITIAL LEAK CHECK .005 AT 18 INCHES HG
 FINAL LEAK CHECK AT INCHES HG
± 4

Handwritten:
 K. Jucker
 FDER
 1/30/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 2 OF 2

SAMPLING TIME PER POINT 2.5

PLANT okeelanta

RUN # Comp - 3

LOCATION Unit 10

DATE 30 JAN 92

TRAV. NO.	DELTA P	DELTA H	METER READING	DGM IN	DGM OUT	HOT BOX	IMPG TEMP	STACK TEMP	VAC
B 1	1.1	3.3	153.3	113	83	257	65	142	9 8
2	1.1	3.3	155.8	120	83	255	64	142	9
3	1.1	3.3	158.2	123	84	256	67	141	10
4	.97	2.91	160.6	126	85	252	68	146	9
5	.80	2.4	162.8	128	87	249	64	140	6
6	.54	1.62	164.6	127	87	252	62	140	4
7	.20	.60	165.7	122	87	252	62	139	2
8	.29	.87	167.0	120	88	264	63	140	2
9	.42	1.26	168.6	119	87	259	62	140	3
10	.55	1.65	170.4	120	88	258	62	138	5
11	.80	2.4	172.6	124	88	262	62	138	8
12	.93	2.79	174.856	127	89	260	63	138	9

12.0

12.2

12.7

12.5

12.5

13.5

COMMENTS:

DELTA P * 3.0 = DELTA H
 BOX # 11 Y = .9911 DELTA H @ = 1.80
 START TIME : 1310
 END TIME : 1413
 INITIAL LEAK CHECK .005 AT 18 INCHES HG
 FINAL LEAK CHECK .000 AT 12 INCHES HG (9)

Wang Satyul
W. Jackson
 FDER
 01/30/92

FIELD DATA SHEET
GENERAL INFORMATION

Plant: <u>OKEE/ANTA</u>	Run #: <u>CT-10R-1</u>
Location: <u>UNIT 10</u>	Date: <u>31 JAN 92</u>
Ds (ft): <u>7.5</u>	No. Points: <u>24</u>
Dn (in): <u>.260</u>	Test Length: <u>60 MIN</u>
Filter #: <u>4457</u>	End Meter Reading: <u>175.201</u>
Cp: <u>.34</u>	Int Meter Reading: <u>220.604</u>
P bar: <u>29.94</u>	Begin Time: <u>09:00</u>
P stack: <u>-.68</u>	End Time: <u>10:05</u>
IMP-1 (INT) <u>100 mL</u>	IMP-1 (FINAL) <u>280</u>
IMP-2 (INT) <u>100 mL</u>	IMP-2 (FINAL) <u>120</u>
IMP-3 (INT) <u>0</u>	IMP-3 (FINAL) <u>4</u>
IMP-4 (INT) <u>500.0g</u>	IMP-4 (FINAL) <u>513.5</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>SM H 9.1</u>	<u> </u>	<u> </u>
% O ₂	<u>SM G+ H.2</u>	<u> </u>	<u> </u>
% CO	<u>0</u>	<u> </u>	<u> </u>

Project Director: <u>S. MacKay</u>	Field Laboratory: <u>S. MacKay/B. Gibson</u>
Meter Box Operator: <u>B. Gibson</u>	Chain of Custody: <u>S. MacKay</u>
Probe Operator: <u>P. W. Loman</u>	Plant Coordinator: <u>G. Devane</u>
Orsat Analyst: <u>S. MacKay</u>	Agency Rep: <u>K. Tucker</u>

Comments:

Eastmount Engineering, Inc. 420 Main Street, Walpole, MA 02081

K. Tucker
FDER
4/13/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 1 OF 3

SAMPLING TIME PER POINT

2.5

PLANT Okeelanta

RUN # CT10R-1

LOCATION Unit 10

DATE 31 JAN 92

175.201

[illegible]

COMMENTS: DELTA P X 3.0 = DELTA H
BOX # 11 Y = .9911 DELTA H @ = 1.80
START TIME : 0900
END TIME : _____
INITIAL LEAK CHECK 1001 AT 15 INCHES HG
FINAL LEAK CHECK _____ AT _____ INCHES HG

K. Jacobson
FDER
01/31/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 2 OF 2

SAMPLING TIME PER POINT

2.5

PLANT Okeelanta

RUN # CT-10R-1

LOCATION Unit 10

DATE 31 JAN 92

TRAV. NO.	DELTA P	DELTA H	METER READING	DGH IN	DGH OUT	TIOT BOX	IMPG TEMP	STACK TEMP	VAC
A 1	1.1	3.3	200.3	106	80	252	60	140	8
2	1.05	3.15	202.7	111	81	255	58	138	8
3	.95	2.85	205.0	118	82	249	59	139	7
4	1.85	2.55	207.3	120	82	249	60	136	7
5	.72	2.16	209.3	121	83	241	60	137	5
6	1.47	1.41	211.1	119	83	256	62	138	4
7	1.24	.72	212.3	114	84	246	63	138	2
8	1.22	.66	213.5	111	83	249	64	139	2
9	.37	1.11	215.0	111	84	249	64	139	2
10	1.46	1.38	216.6	112	84	265	65	139	3
11	.73	2.19	218.5	115	84	261	66	139	6
12	.79	2.37	220.604	119	84	249	68	138	7

12.0

12.7

12.5

11.5

11.5

11.7

COMMENTS: DELTA P = 3.0 = DELTA H
 BOX # 11 Y = .9911 DELTA H = 1.80
 START TIME: 0900
 END TIME: 1003
 INITIAL LEAK CHECK .001 AT 15 INCHES HG
 FINAL LEAK CHECK .015 AT 15 INCHES HG 6

F. J. J. J.
 FDEP
 01/31/92

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEELANTA</u>	Run #:	<u>CP-10R-2</u>
Location:	<u>UNIT 10</u>	Date:	<u>31 JAN 92</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>SM 265 .265</u>	Test Length:	<u>60 min</u>
Filter #:	<u>4458</u>	End Meter Reading:	<u>267.504</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>211.101</u>
P bar:	<u>29.95</u>	Begin Time:	<u>Ø 11:00</u>
P stack:	<u>-.68</u>	End Time:	<u>12:05</u>
IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>286</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>122</u>
IMP-3 (INT)	<u>0</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>513.0</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>8.6</u>	<u> </u>	<u> </u>
% O ₂	<u>11.7</u>	<u> </u>	<u> </u>
% CO	<u>0</u>	<u> </u>	<u> </u>

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>MacKay/Gibson</u>
Meter Box Operator:	<u>B. GIBSON</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>P. W. Yoman</u>	Plant Coordinator:	<u>G. DEVAINE</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>K. TUCKER DER</u> <u>D. Brown P.B County</u>

Comments:

*K. Tucker
FDER
Ø1/31/92*

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 1 OF 2

SAMPLING TIME PER POINT 2.5

PLANT okeelanta

RUN # C-10R-2

LOCATION Unit 10

DATE 31 JAN 92

211.101

TRAV. NO.	DELTA P	DELTA H	METER READING	DGM IN	DGM OUT	HOOT BOX	IMPG TEMP	STACK TEMP	VAC
B 1	1.3	3.9	223.8	81	78	261	63	140	4
2	1.3	3.9	226.4	90	78	255	61	141	4
3	1.05	3.15	228.7	96	79	258	62	140	3
4	.92	2.76	231.0	102	78	251	62	138	3
5	.53	1.59	232.7	104	79	252	63	138	2
6	.31	.93	234.1	103	79	254	63	139	2
7	.24	.72	235.3	102	79	252	62	139	2
8	.35	1.05	236.7	102	80	258	63	138	2
9	.52	1.56	238.5	103	80	258	62	137	2
10	.65	1.95	240.3	108	80	258	62	138	2
11	.84	2.52	242.4	111	81	247	62	138	3
12	.92	2.76	244.701	115	81	253	62	139	4

11.0
11.7
11.5
11.7
12.3
12.0

COMMENTS: DELTA P x 3.0 = DELTA H
 BOX # 11 Y = .77 DELTA H @ = 11
 START TIME : 1100
 END TIME :
 INITIAL LEAK CHECK .005 AT 16 INCHES HG
 FINAL LEAK CHECK AT INCHES HG
 P $\geq \pm 4.5$

*K. Trucken
FDER
01/31/92*

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 2 OF 2
 PLANT Okeelanta
 LOCATION Unit 10

SAMPLING TIME PER POINT 25
 RUN # C-10R-2
 DATE 31 JAN 92

TRAV. NO.	DELTA P	DELTA H	METER READING	DGM IN	DGM OUT	DOT BOX	IMPG TEMP	STACK TEMP	VAC
A 1	1.3	3.6	247.3	104	81	240	60	139	5
2	1.3	3.6	249.8	111	82	248	57	139	6
3	1.1	3.3	252.3	116	83	261	58	138	5
4	.94	2.82	254.6	119	84	254	58	139	5
5	.70	2.10	256.6	120	84	256	59	139	4
6	.42	1.26	258.3	116	84	252	60	139	2
7	.15	.45	259.3	113	84	258	64	139	2
8	.23	.69	260.5	111	84	265	63	140	2
9	.35	1.05	262.0	111	84	256	60	139	2
10	.47	1.41	263.6	112	84	258	60	138	2
11	.64	1.92	265.5	114	84	244	60	139	4
12	.69	2.07	267.504	116	84	260	60	139	4

12.0
12.0
12.0
11.7
11.0
11.0

COMMENTS: DELTA P = 3.0 - DELTA H
 BOX # 11 Y = .9911 DELTA H @ = 1.80
 START TIME : 1100
 END TIME : 12:05
 INITIAL LEAK CHECK .005 AT 16 INCHES HG
 FINAL LEAK CHECK .000 AT 8 INCHES HG (4)(6)
 Final Ppt Leak Check - 9000 P 5" H₂O

For [unclear]
 FDER
 01/31/92

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEELANTA</u>	Run #:	<u>CT-10R-3</u>
Location:	<u>UNIT 10</u>	Date:	<u>31 JAN 92</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>1260</u>	Test Length:	<u>60</u>
Filter #:	<u>4471</u>	End Meter Reading:	<u>311.658</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>267.821</u>
P bar:	<u>29.96</u>	Begin Time:	<u>13:05</u>
P stack:	<u>1.68</u>	End Time:	<u>14:10</u>

IMP-1 (INT)	<u>100 ML</u>	IMP-1 (FINAL)	<u>260</u>
IMP-2 (INT)	<u>100 ML</u>	IMP-2 (FINAL)	<u>118</u>
IMP-3 (INT)	<u>0</u>	IMP-3 (FINAL)	<u>1</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>512.1</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>7.9</u>	<u> </u>	<u> </u>
% O ₂	<u>12.5</u>	<u> </u>	<u> </u>
% CO	<u>0</u>	<u> </u>	<u> </u>

Project Director:	<u>S. McKay</u>	Field Laboratory:	<u>McKay/Gibson</u>
Meter Box Operator:	<u>B. Gibson</u>	Chain of Custody:	<u>S. McKay</u>
Probe Operator:	<u>P. WILDMAN</u>	Plant Coordinator:	<u>G. DEVANE</u>
Orsat Analyst:	<u>S. McKay</u>	Agency Rep:	<u>K. TUCKER FIA DER</u> <u>D. BROWN P.B. County</u>

Comments:

K. J. Gibson
FDER
01/31/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 1 OF 2

SAMPLING TIME PER POINT 2.5

PLANT Okeelanta

RUN # CT-10R-3

LOCATION Unit 10

DATE 31 JAN 92

267.821

TRAV. NO.	DELTA P	DELTA H	METER READING	DGM IN	DGM OUT	HOT BOX	IMPG TEMP	STACK TEMP	VAC
B 1	1.1	3.08	270.2	87	78	255	64	138	4
2	1.05	2.94	272.5	98	78	264	61	138	4
3	.89	2.49	274.7	106	79	263	63	139	3
4	.71	1.99	276.7	110	80	265	64	138	3
5	.45	1.26	278.3	111	80	260	66	137	2
6	.27	.76	279.6	110	80	257	66	138	2
7	.18	.50	280.5	107	81	253	67	137	2
8	.25	.70	281.8	106	81	252	67	136	2
9	.53	1.48	283.4	108	81	256	59	138	2
10	.69	1.93	285.4	110	81	260	58	137	3
11	.88	2.46	287.5	116	82	260	59	136	4
12	.97	2.72	289.7	117	83	263	60	136	5

13.0
11.7
12.0
12.0
12.7
12.5

COMMENTS:

DELTA P = 2.8 - DELTA H

BOX # 11 Y = 9911 DELTA H B = 1.80

START TIME: 1305

END TIME:

INITIAL LEAK CHECK .002 AT 16 INCHES HG

FINAL LEAK CHECK AT INCHES HG

K. Anderson
FDEIR
01/31/92

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

PAGE 2 OF 2
 PLANT Okeelanta
 LOCATION Unit 10

SAMPLING TIME PER POINT 2.5 min
 RUN # CT-10R-3
 DATE 31 JAN. 92

TRAV. NO.	DELTA P	DELTA Δ	METER READING	DGM IN	DGM OUT	HOOT BOX	IMPG TEMP	STACK TEMP	VAC
A 1	1.05	2.94 2.94	292.0	109	83	245	245 245	136	5
2	1.05	2.94	294.4	116	83	253	259 259	137	6
3	.97	2.72	296.7	118	84	240	61	137	6
4	.88	2.46	298.8	120	83	258	62	136	5
5	.68	1.90	300.8	122	86	250	63	137	4
6	.42	1.18	302.1	119	86	268	64	136	3
7	.20	.56	303.7	118	86	265	65	135	2
8	.20	.56	304.7	113	86	251	61	135	2
9	.35	.98	306.1	111	85	261	62	134	2
10	.45	1.26	307.7	113	86	245	62	134	2
11	.68	1.90	309.6	116	86	252	60	136	4
12	.85	2.38	311.658	118	86	264	61	137	6

13.6
12.8
12.5
12.5
13.1
13.3

COMMENTS: DELTA P Δ 2.8 = DELTA H
 BOX # 11 Y = 9911 DELTA H Δ = 1.80
 START TIME: 1305
 END TIME: 1410
 INITIAL LEAK CHECK .002 AT 16 INCHES HG
 FINAL LEAK CHECK .001 AT 7 INCHES HG (5)(6)

K. Jackson
 FDER
 4/31/92

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX IX
LABORATORY RESULTS



South Florida Environmental Services

LABORATORY SUMMARY OF RESULTS

PROJECT NUMBER: 91-102
PROJECT NAME: OKEELANTA CORPORATION
BOILER #10

ANALYST: M. WAYT
ANALYSIS: EPA METHOD 5

FILTER

SAMPLE DESCRIPTION	FILTER #	TEST DATE	TARE WEIGHT (g)	FINAL* WEIGHT (g)
C-1	4441	1-29-92	0.5975	0.7189
C-2	4442	1-29-92	0.5984	0.7220
C-3	4443	1-30-92	0.5909	0.7200
BLANK	4423	1-31-92	0.6177	0.6177

WASH

SAMPLE DESCRIPTION	BKR#	TEST DATE	TARE WEIGHT (g)	FINAL WEIGHT (g)	VOLUME (ml)
C-1	11	1-29-92	71.6809	71.6990	300
C-2	115	1-29-92	65.3930	65.4121	300
C-3	204	1-30-92	77.8601	77.8755	200
BLANK	221	1-31-92	76.7822	76.7835	200

- Filters heated at 220 degrees(F) for 2.5 hours



LABORATORY
SUMMARY OF RESULTS

PROJECT NUMBER: 91-102
PROJECT NAME: OKEELANTA CORPORATION
BOILER #10

ANALYST: M. WAYT
ANALYSIS: EPA METHOD 5

FILTER

SAMPLE DESCRIPTION	FILTER #	TEST DATE	TARE WEIGHT (g)	FINAL* WEIGHT (g)
CT-10R-1	4457	1-31-92	0.6037	0.7294
CT-10R-2	4458	1-31-92	0.6088	0.7335
CT-10R-3	4471	1-31-92	0.5948	0.6848
BLANK	4423	1-31-92	0.6177	0.6177

WASH

SAMPLE DESCRIPTION	BKR#	TEST DATE	TARE WEIGHT (g)	FINAL WEIGHT (g)	VOLUME (ml)
CT-10R-1	206	1-31-92	77.9125	77.9223	240
CT-10R-2	209	1-31-92	76.3000	76.3183	250
CT-10R-3	211	1-31-92	79.1304	79.1400	220
BLANK	221	1-31-92	76.7822	76.7835	200

- Filters heated at 220 degrees(F) for 2.5 hours

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX X
EQUIPMENT CALIBRATION SHEETS

POST
METER BOX CALIBRATION SHEET

BOX #: 11
PRES BAR: 29.77

DATE: 02-07-92
VACUUM: 12 IN HG

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	10.00	10.245	2.00	.147	29.92	13.11
2	10.00	10.553	2.00	.147	29.92	13.10
3	10.00	10.452	2.00	.147	29.92	13.10

RUN #	TEMP WET	TEMP DRY INLET	TEMP DRY OUTLET	TEMP DRY (AVG)	Y	DELTA H @
1	66.0	107.3	70.0	88.7	1.0131	1.85
2	66.0	117.3	75.7	96.5	.99762	1.82
3	66.0	120.7	79.7	100.2	1.0140	1.81
AVERAGE					1.0082	1.82

ACTUAL % DEVIATION = 1.06 %

ALLOWABLE % DEVIATION = 2.0 %

PRE CALIBRATION Y = .9911

ACTUAL % DIFFERENCE = 1.70 %

ALLOWABLE DIFFERENCE = 5.0 %

FORMULAS:

Y=

DELTA H @=

$$\frac{(V w) (P b) (T d)}{(V d) (P b \text{ ABS}) (T w)} = \frac{0.0317 (\text{DELTA H})}{(P b) (T d)} * \left[\frac{(T w) (\text{TIME})}{(V w)} \right]$$

CALIBRATION BY:


Pat Wildman

METER BOX CALIBRATION SHEET

BOX NUMBER: 11
PRESS BAR : 30.19

DATE: 15 OCT 91
DUE: 15 APR 92

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	5	5.168	.50	.0368	30.23	12.48
2	5	5.195	1.00	.0735	30.26	8.97
3	10	10.456	1.50	.1103	30.30	14.83
4	10	10.539	2.00	.1471	30.34	13.28
5	10	10.581	3.00	.2206	30.41	10.82
6	10	10.613	4.00	.2941	30.48	9.50

RUN #	TEMP WET (°F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H @
1	71.0	82.7	76.0	79.3	.9815	1.71
2	69.7	95.3	77.0	86.2	.9900	1.73
3	69.0	107.0	79.0	93.0	.9961	1.75
4	69.0	114.7	82.7	98.7	.9972	1.86
5	69.0	114.3	85.0	99.7	.9926	1.84
6	68.7	114.7	86.3	100.5	.9893	1.89
AVERAGE					.9911	1.80

MAX % DEVIATION .97
ALLOWABLE % DEV 2.00

FORMULAS:

Y=


DELTA H @=

$$Y = \frac{(V w) (P b) (T d)}{(V d) (P b) (ABS) (T w)}$$

$$\Delta H @ = \frac{0.0317 (\Delta H)}{(P b) (T d)} * \left[\frac{(T w) (TIME)^2}{(V w)} \right]$$

CALIBRATION BY:


JEM JARDIN



Sean

Eastmount Engineering

Environmental Consultants — Air Quality Specialists

WET TEST METER CALIBRATION

WET TEST METER:- Model AL-19, Serial No. P-468

BELL PROVER :- Chain Compensated Gasometer
Warren E. Collins Inc.
Serial NO. 2874
Factor 133.2 cc/mm

(Maintained by E.P.A. region 1)

CALIBRATED BY :- Anthony Stratton and Kieran Nolan

DATE CALD. :- March 28 1991

DATE DUE :- March 28 1992

RESULTS :-

-----	RUN #	C.F.M.	% DIFF.
	1	.55	+.31
	2	.55	+.20
	3	.55	+.10
	-----	-----	-----
AVERAGE :-		.55	+.20

NOZZLE CALIBRATION SHEET

PROJECT NAME: ORIELANT Corp PROJECT NUMBER: 91-102

POINT# NOZZLE # 1/4-5 NOZZLE # 1/4-13 NOZZLE # 5/16-14 NOZZLE # 5/16-3

1 .265 .260 .310 .315

2 .264 .258 .310 .314

3 .266 .261 .310 .313

AVG. .265 .260 .310 .314

SEAN MACKAY

CALIBRATED BY:

DEC 9, 1991

DATE:

TRANSCAT

"CAL-LAB"

Certificate of Calibration

TRANSCAT certifies that this instrument has been calibrated to manufacturer's specifications using measurement standards traceable to the National Institute of Standards and Technology (NIST) and as required by The National Research Council of Canada, Division of Physics, within the limitations of the Council's calibrations services. TRANSCAT's calibration system meets or exceeds the requirements of MIL-STD-45662A.

Complete records of all work performed is maintained by TRANSCAT and is available upon request.


TEMPERATURE 68° F.

RELATIVE HUMIDITY OF 59%.

Customer : EASTMONT ENGINEERING
Manufacturer : TRANSHATION
Model Number : 1261
Serial Number : 8277
Description : THERMOCOUPLE CALIBRA
Calibrated : 08/02/91
Date Due : 08/01/92
Repair Number : 17-7047-00

ITEM RECEIVED IN TOLERANCE

ASSETS	MANUFACTURER	MODEL	DESCRIPTION	CALIBRATED	DATE DUE
2485	DATA PRECISION	9200	DC CALIB.	01/02/91	01/03/92
2486	PLUXE	9842A	DM	03/19/91	03/19/92
2471	KAYE	149-4	ICE FT. REP.	03/14/91	03/13/92
2482	NBS	172144-K	STD THERMOCOUPLE	04/19/91	04/19/93


CAL-LAB MANAGER

TEMPERATURE INDICATOR CALIBRATION FORM

INDICATOR S/N: 650 - 6

CAL DATE: 8 AUG 91

REFERENCE S/N:1061-8277

DUE DATE: 8 AUG 92

CHANNEL NO.	REFERENCE SET POINT							
	0	32	200	250	320	600	800	1000
1	0	33	199	249	320	600	800	1000
2	0	32	199	249	320	599	800	1000
3	0	32	199	249	320	599	800	1000
4	0	32	199	249	320	600	800	1001
5	0	32	199	250	320	600	800	1000
6	0	32	199	249	320	599	800	1000
7								
8								
9								
10								

% DIFF: .06

CALIBRATED BY _____ KIERAN NOLAN *KN*

TEMPERATURE INDICATOR CALIBRATION FORM

INDICATOR S/N: 650 - 7

CAL DATE: 13 SEP 91

REFERENCE S/N:1061-8277

DUE DATE: 13 SEP 92

CHANNEL NO.	REFERENCE SET POINT							
	0	32	200	250	320	600	800	1000
1	1	32	199	249	320	599	798	999
2	1	32	200	250	320	599	799	999
3	1	33	200	250	320	599	799	999
4	1	32	200	250	320	599	799	999
5	0	32	199	249	320	600	799	998
6	0	32	199	250	320	599	799	998
7								
8								
9								
10								

% DIFF: .04

CALIBRATED BY _____ KIERAN NOLAN *KN*

THERMOCOUPLE CALIBRATION SHEET

SET #: METER BOX 11-IN

DATE: 08-11-86

STANDARD ('F)	THERMOCOUPLE ('F)	% DEVIATION OF ABSOLUTE
34	29	1.01
211	210	.15
404	403	.12
	MAXIMUM	1.01
	ALLOWABLE	1.50

SET #: METER BOX 11-OUT

DATE: 08-11-86

STANDARD ('F)	THERMOCOUPLE ('F)	% DEVIATION OF ABSOLUTE
34	28	1.21
211	210	.15
404	401	.35
	MAXIMUM	1.21
	ALLOWABLE	1.50

CALIBRATION BY:

G. ZWILLING

THERMOCOUPLE CALIBRATION SHEET

TC #: RAC - 2 - 170

DATE: 1/11/91

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE (ABSOLUTE)
32.0	32	.00
516.2	519	.29
212	213	.15
	MAXIMUM	.29
	ALLOWABLE	1.50

CALIBRATION BY:

Kieran Nolan

KIERAN NOLAN


THERMOCOUPLE CALIBRATION SHEET

SET #: 7.75' - 9

DATE 3/6/91

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE (ABSOLUTE)
32	32	.00
212	213	.15
466	479	1.43
	MAXIMUM	1.43
	ALLOWABLE	1.50

CALIBRATION BY:


KIERAN NOLAN

THERMOCOUPLE CALIBRATION SHEET

SET #: 8.5' - 6

DATE: 07/07/89

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE (ABSOLUTE)
87	86	.18
212	211	.15
430	436	.67
	MAXIMUM	.67
	ALLOWABLE	1.50

CALIBRATION BY:

S. MacKay

THERMOCOUPLE CALIBRATION SHEET

TC #: 4THIMP-210

DATE: 2/27/91

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE (ABSOLUTE)
32.0	32	.00
157.1	157	.02
212	214	.30
	MAXIMUM	.30
	ALLOWABLE	1.50

CALIBRATION BY:


KIERAN NOLAN

Okeelanta Corporation - Boiler #10
Particulate Emissions Test Report

APPENDIX XI

PAGES 202, 203 FROM CONTROL ROOM LOG BOOK

1-29-92

11:00 - 7:00

11:00 PM - BLOW SOOT ON BLR. =

" " 5285-ALBERTO RODRIGUEZ - DID NOT REPORT TO WORK. = (CHANGED SHIFT)

" " 4843-ALFONSO PRUITT - WORKED 8 HRS. = O.F.A. =

NOTE - 4735-ORLANDO RODRIGUEZ - WORKED 8 HRS. W.C.P.O.

" " 4920-JOSE F. RODRIGUEZ - WORKED 8 HRS. U.T.N.C.P.

" " 4973-ANGEL MARIO CRESPO - WORKED 8 HRS. O.C.L.

" " 7304-JUAN GALVAN - WORKED 8 HRS. B.C.L. =

12:00 AM - CLEANED STOKER GRATE #5 BLR. =

12:10 " A.M. 4L STOP = 12:15 START.

1:30 " CLEANED FURNACES = #6 BLR. + 5 = #4 BLR. + 4.

3:00 " START CLEANING FURNACES #1-2-3-4-5
ON #10 BOILER = 5:00 AM. = FINISH =

" " W.C. PLANT PLUGGED-UP = 3:40 OK. BACK TO OPERATION

NOTE - 5472-ANGULO GARCIA - DID NOT REPORT TO WORK. (SICK)

4:45 " A.M. 4L STOP - START: 6:30 =

5:30 AM - 2 1/2 BUCKETS - (100 LBS.) CAUSTIC SODA -

" 1 BUCKET (40 LBS.) # 227-

" 1 GALLON # 219

" 1 CUP # 271 =

W.C. LOGS = 35 (6)

O. USED = 3661-

G.M. READ = 06740434 =

J.M.A.

1-30-92

7-3

Blow Soot on Boilers @

Cleaned Grate Ashes Boiler 5 @

Alfonso pruit# did not work this shift ^{change} shift

Alberto Rodrigue worked B.F.M. 8 hrs

Soot Blowers # 1-2 Boiler 10 is stuck in open

Position - in # 1 the Valve Turns But the Hammer

it not work.

Note

203

#10

(43)

Started P.T. # 10-3 @ 1-1/2

Added 2 1/2 Bucket Caustic Soda

1 1 (HOL) 227

1 Gal # 219

1 Cup # 271

6744875

4,441 Gal.

40 Loads 2 1/2

②

Note

Main ~~line~~ line to Soot Blower North + South Side
 is closed ~~at~~ At Drum because the Soot Blower Supply
 Valve will not close completely. So when the
 Soot is Blown those Valves will have to Be
 OPEN in order to Blow Soot on that Side # 10
 And Close Back when Finished

P.T. # 10-3

Finished P.T. # 10-3

1-30-92

3-11

Blew soot a blrs.

Cleaned Grate ashes # 5 blrs.

Manuel Herrera did not report to worked injured

Laura Trevino 8 hrs. P.L.O.

Cleaned Furnaces # 10-3 6-3 4-2 4-3 blrs.

Added # 204 10 lb.

Felip Carrillo did not report to worked sick

Jose Precides, w.c. P.L.O.

Cleaned All ashes hopper

Albiro Camelo did not report to worked death in the Family

R. Lopez 8 hrs. B.F.M.

C. Perez 4 hrs. w.c. plant

Jose Rodriguez 4 hrs. w.c. plant

~~Added~~ Cleaned burners # 5 3+4

Added 2 1/2 Bucket Caustic soda 100 lb.

1 " # 227 40 lb.

1 Gal. # 219