

Note: This is a reference cited in *AP 42, Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/


The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP-42 Section Number: 1.8

Reference Number: 61

Title: Okeelanta Corporation Particulate
Emissions Test Reprot Boiler #11

December 1990



Eastmount Engineering

Environmental Consultants — Air Quality Specialists

OKEELANTA CORPORATION
COMPLIANCE PARTICULATE EMISSIONS TEST REPORT
BOILER #11

PREPARED FOR:


Okeelanta Corporation
Okeelanta Sugar Division
South Bay, Florida 33493

CONCERNING:

Particulate Emissions Testing
Okeelanta Corporation
Boiler #11
South Bay Florida Facility
December 6 & 7, 1990

PREPARED BY:

Sean MacKay
Project Director
Eastmount Engineering, Inc.
420 Main Street
Walpole, MA 02081


Sean MacKay
Project Director

11 FEB 91
Date

TABLE OF CONTENTS

- 1.0 COMPENDIUM
- 2.0 STACK SCHEMATIC
- 3.0 TRAVERSE POINT LOCATION & SAMPLING TIME PER POINT
- 4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES
- 5.0 QUALITY CONTROL PROCEDURES

APPENDIX

- I COMPUTER INPUT SHEETS
- II ISOKINETIC CALCULATION SHEETS
- III ENTHALPY CALCULATION SHEETS
- IV HEAT INPUT CALCULATION SHEETS
- V EMISSION CALCULATION SHEETS
- VI NOMENCLATURE SHEETS
- VII FIELD DATA SHEETS - UNIT OPERATING CONDITIONS
- VIII FIELD DATA SHEETS - STACK TESTING
- IX EQUIPMENT CALIBRATION SHEETS

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

1.0 COMPENDIUM

Eastmount Engineering Inc., conducted a Compliance Particulate Emissions Test Program on Unit # 11 at Okeelanta Corporation's South Bay, Florida facility on December 6 and 7, 1990. The test program consisted of a series of three EPA Method 5 test runs. A series of four Method 5 tests were performed on December 4 and 5, 1991. Due to upsets in facility operations during the tests these numbers are not reported under this cover but are available upon request.

All testing was conducted in strict accordance with the Environmental Protection Agency Reference Methods 1 through 5 as found in the Federal Register (40 CFR 60) as amended and were consistent with the State of Florida Department of Environmental Regulation's guidelines.

The purpose of this test was to determine compliance with the rules of the Department of Environmental Regulation (DER), Chapter 17-2.600 Air Pollution, Section 2.05 Prohibitive Acts, Subsection 6, Stationary Sources, Table II, Emission Limiting Standards.

During testing the boiler was burning bagasse and oil as fuel. Boiler No. 11 is rated at 125,000 pounds of steam per hour. Results of the test program indicate Boiler No. 11 to be in compliance with the Florida DER emission standard. The following table summarizes the emission results, emission standards and boiler operating conditions.

RUN#	DATE	EMISSION RATE		ALLOWABLE		LOAD	% OF 125 KPH
		#/MMBtu	#/HR	#MMBtu	#/HR	#/HR	
1A	12-6-90	.149	37.54	.193	48.48	123415	98.7%
2A	12-7-90	.184	46.91	.192	49.02	123514	98.8%
3A	12-7-90	.215	55.00	.193	49.54	124029	99.2%
3 RUN AVG.		.183	46.48	.193	49.01	123652	98.9%

Sean MacKay, Project Director, was in charge of and responsible for all stack testing, conducted all calculations and maintained chain of custody of all samples. Kieran Nolan operated the meter box and performed the field laboratory aspects of the program. Mark Wescott located the probe at the proper traverse point locations and assisted where required. Mr. Kenneth Tucker of the Florida Department of Environmental Regulation observed the stack testing and boiler operations. Mr. A. Padrone was the boiler room superintendent. Mr. George Devane was responsible for boiler operation and acquisition of all pertinent process data.


Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

2.0 STACK SCHEMATIC

OKEELANTA CORPORATION
UNIT #11
SOUTH BAY, FLORIDA FACILITY

The following is a schematic of the stack which services Boiler #11 at Okeelanta Corporation's South Bay, Florida facility.

Defined are the sampling port locations, interior stack dimensions and distances from the ports to the nearest upstream and downstream interferences.



DISTANCE UPSTREAM FROM FLOW DISTURBANCE (A)	4'
DISTANCE DOWNSTREAM FROM FLOW DISTURBANCE (B)	16'
DIAMETER OF PORT SLEEVE (C)	4"
LENGTH OF PORT SLEEVE (D)	3.5"
NUMBER OF PORTS	2
INTERNAL DIAMETER OF STACK AT SAMPLING PORTS	7.5'

Drawing not to scale

PB GOLF course

685


3885

PDN
KCPUR

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

OKEELANTA CORPORATION
UNIT #11
SOUTH BAY, FLORIDA FACILITY



Minimum number of traverse points for particulate traverses.

Distance A = 4' or 0.5 diameters.

Distance B = 16' or 2.1 diameters.

In accordance with Method 1, 24 traverse points are needed.

In order to sample for a minimum of one hour and draw at least 30 cubic feet, each traverse point was sampled for 2.5 minutes.

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

OKEELANTA CORPORATION
UNIT #11
SOUTH BAY, FLORIDA FACILITY

DIAMETER OF STACK: 7.5 FEET
PORT SLEEVE LENGTH: 3 INCHES

TRAVERSE POINT	DISTANCE % OF DIAMETER	DISTANCE (INCHES)	PROBE MARK (INCHES)
1	2.1	1.9	5.4
2	6.7	6.0	9.5
3	11.8	10.6	14.1
4	17.7	15.9	19.4
5	25.0	22.5	26.0
6	35.6	32.0	35.5
7	64.4	57.9	61.5
8	75.0	67.5	71.0
9	82.3	74.1	77.6
10	88.2	79.4	82.9
11	93.3	84.0	87.5
12	97.9	88.1	91.6

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES

The following is a description of the sampling train and specifications of particulate collection media used in the tests.

1. EMISSION SAMPLING EQUIPMENT

The specific train used during this test is one manufactured by Research Appliance Company (RAC). The design specifications of this train meets all the requirements of Environmental Protection Agency's Method 5 as found in the Federal Regulations under Section 40 CFR 60 as amended. The following is a description of the individual pieces of equipment used:

Nozzle - The nozzle was of seamless stainless steel tubing construction of the button hook design. A range of sizes suitable for isokinetic sampling was available. All nozzles were calibrated before testing. A nozzle calibration sheet may be found in the calibration section of this report.

Probe - An 10 foot steel probe with a stainless steel liner was used.

Heating System - The filter temperature was maintained by enclosing the filter in a hot box capable of maintaining the temperature at $248^{\circ}\text{F} \pm 25^{\circ}\text{F}$. This temperature was monitored by use of a thermocouple in the hot box.

Pitot Tube - A type S pitot tube attached to the probe was used to monitor the stack gas velocity. Since the pitot tube meets all the dimensional criteria set forth in Method 2 of 40 CFR 60, a coefficient of 0.84 has been used.

Filter Holder - A borosilicate glass type filter holder with frit support was used.

Condenser - Four impingers connected in series, with ground glass leak-free fittings were used as the condenser. The first, third and fourth impingers were of the Greenburg-Smith design, modified by replacing the tip with a $1/2$ " glass tube extending to about $1/2$ " from the bottom of the flask. The second impinger was of the Greenburg-Smith design with the standard tip.

Metering System - A vacuum gauge, micromanometer, inclined manometer, leak-free pump, calibrated thermocouples and a calibrated dry gas meter were the basic components used to meter the dry gas through the system.

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Gas Density Determination - An ORSAT type combustion analyzer, capable of measuring CO₂, O₂ and CO was used to determine the molecular weight of the flue gas. An integrated proportional sample was taken at each of the traverse points in order to assure that the total test span was covered. The ORSAT analysis was conducted immediately following each test run.

2. SAMPLING AND ANALYTICAL PROCEDURES

All sampling and analytical procedures were conducted in strict accordance with the methods prescribed in Methods 1 through 5 of the Code of Federal Regulations as found in 40 CFR 60 as amended. The following is the sequence of events that occur both prior to and during the actual stack test.

Traverse Points - The traverse points were calculated in accordance with Method 1 and the probe was marked accordingly.

Static Pressure - The static pressure was checked and recorded.

Preliminary Traverse - A preliminary traverse was conducted. Readings included the pressure drops and stack gas temperatures.

Nomograph - Once all of the above information had been obtained, the nomograph was set up for the actual test to correlate the isokinetic relationships.

Barometric Pressure - Barometric pressure was obtained by use of an aneroid barometer at the test site.

Sampling Train Set-Up

- (a) The pre-weighed filter was placed in the filter holder and visually checked.
- (b) 100 ml of water was placed in the first two impingers.
- (c) Approximately 200 grams of silica gel was placed in the fourth impinger. (Exact weights were logged on the field data sheets).
- (d) Crushed ice was placed around the impingers.
- (e) Once assembly of the entire train was completed, the probe and heater box were turned on.

Pre-test Leak Check - Once the heater box was at the desired temperature for testing, the system was leak checked at 15 inches of vacuum. A leakage rate of less than 0.02 CFM had to be achieved before testing commenced.

Final Check - Once everything was ready to go, the plant was checked to assure that it was running at desired capacity.

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Sampling - Isokinetic sampling as described in Method 5 then took place.

Post-test Leak Check - Upon completion of each test run, the system was leak checked at the highest vacuum recorded during that run. All leak checks were less than 0.02 CFM and considered acceptable.

Sample Recovery - Because of the importance of proper sample recovery procedures, details of the sample recovery can be found in the Quality Control Procedures Section of this report.

Isokinetics - Once all sample recovery was completed and the amount of moisture collected had been determined, calculations were conducted to determine the percent isokinetics of the test run.

Operating Data Sheets - All pertinent operating data were logged throughout the testing period by plant personnel.

5.0 QUALITY CONTROL PROCEDURES

The following is a description of the procedures used for maintaining the integrity of samples collected, including the chain of custody and quality control assurance of filters and acetone wash.

Pre-test preparation consisted of the filters being desiccated at $68 \pm 10^\circ\text{F}$ at ambient pressure for at least twenty four (24) hours. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved ± 0.5 mg change from the previous weighing. These pre-marked filters were then put into petri dishes and sealed. All filters used during testing were put into a carrying case for transport to the job site. A list of the filters and tare weights was available prior to testing.

After each test run, the filter and any particles which may have adhered to the filter holder gasket were carefully removed from the filter holder and placed into its identified petri dish container. This container was then labeled with the run number and date.

Taking care to see that particulate on the outside of the probe or other exterior surface did not get into the sample, particulate matter from the probe liner, nozzle, probe fittings, and front half of the filter holder were acetone washed into a sample container. This container was then sealed. The run number, date, and a mark indicating the level of the acetone wash in the bottle was recorded on the bottle.

Both the petri dish containing the filter and the bottle containing the acetone wash were transported to Eastmount Engineering's laboratory.

Once at the laboratory, each filter was weighed and then put back into its individual container. The container was then placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved ± 0.5 mg change from the previous weighing.

The levels marked on the bottles containing the acetone wash were checked to confirm that no leakage occurred during transport. The contents were then transferred into a pre-tared beaker and evaporated to dryness. Once this had been accomplished, the beaker was placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the beaker was re-weighed until a constant weight of ± 0.5 mg change from the previous weighing was achieved.

All calculations were conducted in strict accordance with 40 CFR 60 (See Calculation Sheets in report).

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX I
COMPUTER INPUT SHEETS

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-1a
DATE : 12-06-90

Ds (FT) 7.5

Dn (IN) .305

FILTER#	3780	TRAV PT	VEL HEAD	SQ ROOT	DELTA H	DRYGAS IN	DRYGAS OUT	STACK TEMP
PIT COEFF	.84							
		A1	.63	.79	3.53	77	75	152
IMP-1 (INT)	100	2	.70	.84	3.92	82	77	153
		3	.66	.81	3.70	83	78	153
IMP-2 (INT)	100	4	.61	.78	3.42	87	78	154
		5	.56	.75	3.14	91	80	153
IMP-3 (INT)	0	6	.44	.66	2.46	89	78	154
		7	.40	.63	2.24	89	80	154
IMP-4 (INT)	500.0	8	.38	.62	2.13	88	80	153
		9	.45	.67	2.52	90	81	153
IMP-1 (FIN)	370	10	.48	.69	2.69	90	83	154
		11	.54	.73	3.02	91	85	153
IMP-2 (FIN)	156	12	.57	.75	3.14	92	83	155
		B1	1.00	1.00	5.60	88	83	153
IMP-3 (FIN)	3	2	1.10	1.05	6.16	92	83	154
		3	1.10	1.05	6.16	94	84	153
IMP-4 (FIN)	529.0	4	1.05	1.02	5.88	95	85	153
		5	.92	.96	5.15	96	86	154
% CO2	10.7	6	.64	.80	3.58	94	85	154
		7	.20	.45	1.12	96	87	154
% O2	9.5	8	.12	.35	.67	94	86	154
		9	.11	.33	.62	96	87	155
% CO	0	10	.11	.33	.62	93	86	154
		11	.12	.35	.67	92	87	153
P BAR	30.08	12	.11	.33	.62	90	87	153
P STK	.2							
NO. PTS	24							
TEST LNTH	60							
END METER	662.137							
	.201							
INT METER	614.600							
BEGIN TIME:	12:15							
END TIME:	13:20							
AVERAGE			.54	.70	3.03	90.4	82.7	153.5

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-2a
DATE :12-07-90

Ds (FT) 7.5

Dn (IN) .250

FILTER#	3779	TRAV PT	VEL HEAD	SO ROOT	DELTA H	DRYGAS IN	DRYGAS OUT	STACK TEMP
PIT COEFF	.84	A1	.55	.74	1.38	81	77	156
IMP-1 (INT)	100	2	.60	.77	1.50	81	77	156
		3	.63	.79	1.58	82	79	158
IMP-2 (INT)	100	4	.60	.77	1.50	83	79	158
		5	.53	.73	1.33	86	79	156
IMP-3 (INT)	0	6	.45	.67	1.13	85	80	156
		7	.33	.57	.83	88	80	157
IMP-4 (INT)	500.0	8	.35	.59	.88	91	82	156
		9	.38	.62	.95	86	80	156
IMP-1 (FIN)	309	10	.43	.66	1.08	88	82	156
		11	.41	.64	1.03	88	83	160
IMP-2 (FIN)	143	12	.39	.62	.98	87	82	157
		B1	1.00	1.00	2.50	86	82	156
IMP-3 (FIN)	3	2	1.05	1.02	2.63	89	84	156
		3	1.05	1.02	2.63	89	85	156
IMP-4 (FIN)	513.2	4	1.05	1.02	2.67	88	84	157
		5	.85	.92	2.13	91	83	158
% CO2	11.5	6	.57	.75	1.43	92	85	158
		7	.18	.42	.45	90	85	157
% O2	8.7	8	.08	.28	.20	88	85	156
		9	.06	.24	.15	87	84	156
% CO	0	10	.07	.26	.18	86	84	156
		11	.08	.28	.20	85	84	157
P BAR	30.09	12	.10	.32	.25	85	83	156

P STK .2

NO. PTS 24

TEST LNPTH 60

END METER 693.926

.144

INT METER 662.468

BEGIN TIME: 09:40

END TIME: 10:50

AVERAGE		.49	.66	1.23	86.8	82.0	156.7
---------	--	-----	-----	------	------	------	-------

INPUT DATA SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-3a
DATE : 12-07-90

Ds (FT)	7.5							
Dn (IN)	.250							
FILTER#	3778	TRAV	VEL	SO	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		A1	.51	.71	1.33	80	79	157
IMP-1 (INT)	100	2	.55	.74	1.43	83	80	160
		3	.59	.77	1.53	84	80	157
IMP-2 (INT)	100	4	.55	.74	1.43	85	81	160
		5	.52	.72	1.35	89	81	157
IMP-3 (INT)	0	6	.45	.67	1.17	88	82	155
		7	.37	.61	.96	92	83	155
IMP-4 (INT)	500.0	8	.40	.63	1.04	86	84	155
		9	.46	.68	1.20	87	84	156
IMP-1 (FIN)	310	10	.48	.69	1.25	89	84	156
		11	.50	.71	1.30	90	83	156
IMP-2 (FIN)	136	12	.51	.71	1.33	94	86	155
		B1	1.05	1.02	2.73	88	84	156
IMP-3 (FIN)	4	2	1.05	1.02	2.73	90	86	156
		3	1.08	1.04	2.81	91	87	155
IMP-4 (FIN)	514.0	4	1.05	1.02	2.73	92	88	156
		5	.90	.95	2.34	96	87	156
% CO2	11.6	6	.63	.79	1.64	93	87	155
		7	.23	.48	.60	92	86	156
% O2	8.6	8	.09	.30	.23	89	87	156
		9	.08	.28	.21	90	86	155
% CO	0	10	.05	.22	.13	87	85	155
		11	.10	.32	.26	87	85	155
P BAR	30.09	12	.04	.20	.10	87	86	155
P STK	.2							
NO. PTS	24							
TEST LGTH	60							
END METER	726.972							
	.263							
INT METER	694.180							
BEGIN TIME:	12:00							
END TIME:	13:10							
AVERAGE			.51	.67	1.33	88.7	84.2	156.0

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX I1
ISOKINETIC CALCULATION SHEETS

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-1a
DATE: 12-06-90

TS (°F) = 153.5	% CO2 = 10.7	VM (CF) = 47.336
TS (°R) = 613.5	% O2 = 9.5	DELTA H (ABS) = 30.30
TM (°F) = 86.5	% CO = 0	PS (ABS) = 30.09
TM (°R) = 546.5	% N2 = 79.8	SORT DELTA P = .698097
VI(TOT) = 358.0	CP = .84	AREA NOZZLE = .000507
		Y = 1.001
VM STD = 17.64	(VM)(Y)(DELTA H ABS) ----- (TM)	= 46.34 DSCF
VW STD = .04707 (VI TOT)		= 16.85 CF
BWO =	VW STD ----- VW STD + VM STD	= .267
BWO =	MOISTURE FROM STEAM TABLES	= .274
VI TOT =	ADJUSTED TO SATURATION VOLUME	= N/A ML
1-BWO = 1 - BWO		= .733
Md (DRY) =	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2) -----	= 30.09 LBS/LB MOLE
Ms (WET) =	MD (1-BWO) + 18 (BWO) -----	= 26.87 LBS/LB MOLE
G =	SORT (TS / PS / MS)	= .87
VS =	85.49(CP)(G)(SORT DELTA P)	= 43.7 FPS
H =	0.002669 (VI TOT)	= .96
J =	(DELTA H ABS)(VM)(Y) / (TM)	= 2.63
K =	(H) + (J)	= 3.58
% ISO =	(TS) (K) (1.667) ----- (TIME) (VS) (PS) (AN)	= 91.6

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-2a
DATE :12-07-90

TS (°F)= 156.7	% CO2= 11.5	VM (CF) = 31.314	
TS (°R)= 616.7	% O2= 8.7	DELTA H (ABS)= 30.18	
TM (°F)= 84.4	% CO= 0	PS (ABS) = 30.10	
TM (°R)= 544.4	% N2= 79.8	SQRT DELTA P = .656382	
VI(TOT)= 268.2	CP= .84	AREA NOZZLE = .000341	
		Y = 1.001	
VM STD = 17.64	$\frac{(VM)(Y)(DELTA H ABS)}{(TM)}$	= 30.66	DSCF
VW STD = .04707	(VI TOT)	= 12.62	CF
BWO =	$\frac{VW STD}{VW STD + VM STD}$	= .292	
BWO =	MOISTURE FROM STEAM TABLES	= .296	
VI TOT =	ADJUSTED TO SATURATION VOLUME=	N/A	ML
1-BWO =	1 - BWO	= .708	
Md (DRY) =	$\begin{aligned} &.44 (\% CO2) \\ &+.32 (\% O2) \\ &+.28 (\% CO) \\ &+.28 (\% N2) \end{aligned}$	= 30.19	LBS/LB MOLE
Ms (WET) =	$\begin{aligned} &MD (1-BWO) \\ &+ 18 (BWO) \end{aligned}$	= 26.63	LBS/LB MOLE
G =	$SQRT (TS / PS / MS)$	= .88	
VS =	$85.49(CP)(G)(SQRT DELTA P)$	= 41.3	FPS
H =	$0.002669 (VI TOT)$	= .72	
J =	$(DELTA H ABS)(VM)(Y) / (TM)$	= 1.74	
K =	$(H) + (J)$	= 2.45	
% ISO =	$\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$	= 99.1	

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-3a
DATE: 12-07-90

TS (°F) = 156.0 *Avg = 155* % CO2 = 11.6 *Avg = 8.9* VM (CF) = 32.529
TS (°R) = 616.0 % O2 = 8.6 DELTA H (ABS) = 30.19
TM (°F) = 86.5 % CO = 0 PS (ABS) = 30.10
TM (°R) = 546.5 % N2 = 79.8 SQRT DELTA P = .668685
VI(TOT) = 264.0 CP = .84 AREA NOZZLE = .000341

Y = 1.001

VM STD = 17.64 $\frac{(VM)(Y)(DELTA H ABS)}{(TM)}$ = 31.73 DSCF

VW STD = .04707 (VI TOT) = 12.43 CF

BWO = $\frac{VW STD}{VW STD + VM STD}$ = .281

BWO = MOISTURE FROM STEAM TABLES = .291

VI TOT = ADJUSTED TO SATURATION VOLUME = N/A ML

1-BWO = 1 - BWO = .719

Md (DRY) = $\frac{.44 (\% CO2) + .32 (\% O2) + .28 (\% CO) + .28 (\% N2)}{}$ = 30.20 LBS/LB MOLE

Ms (WET) = $\frac{MD (1-BWO) + 18 (BWO)}{}$ = 26.77 LBS/LB MOLE

G = $\sqrt{TS / PS / MS}$ = .87

VS = 85.49(CP)(G)(SQRT DELTA P) = 42.0 FPS

H = 0.002669 (VI TOT) = .70

J = $\frac{(DELTA H ABS)(VM)(Y)}{(TM)}$ = 1.80

K = (H) + (J) = 2.50

% ISO = $\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$ = 99.4

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX III
ENTHALPY CALCULATION SHEETS

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
 LOCATION: UNIT 11

RUN #: COMP-1a
 DATE : 12-06-90

STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
350	700	260
370	700	
360	690	
330	610	
340	660	

AVERAGE 350.0 PSIG 672.0 260.0

P ABS = 364.7 PSIA

ENTHALPY @ 700 'F AND 360 PSIA = 1364.1

ENTHALPY @ 600 'F AND 360 PSIA = 1309.9

ENTHALPY @ 672.0 'F AND 360 PSIA = 1348.9

ENTHALPY OF FEED WATER = 228.65

AVERAGE ENTHALPY = 1120.3 BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-2a
DATE : 12-07-90

	STEAM PRESSURE		STEAM TEMPERATURE		FEED WATER TEMPERATURE
	340		700		260
	355		700		
	330		690		
	350		700		
	365		700		
	360				
AVERAGE	350.0	PSIG	698.0		260.0
P ABS =	364.7	PSIA			
ENTHALPY @	700	'F AND	360	PSIA =	1364.1
ENTHALPY @	600	'F AND	360	PSIA =	1309.9
ENTHALPY @	698.0	'F AND	360	PSIA =	1363.0
ENTHALPY OF FEED WATER =					228.65
AVERAGE ENTHALPY =					1134.4 BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-3a
DATE : 12-07-90

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	360	700	260
	360	700	
	350	700	
	345	700	
	355	700	
	340	700	
AVERAGE	351.7 PSIG	700.0	260.0
P ABS =	366.4 PSIA		
ENTHALPY @	700 'F AND	360 PSIA =	1364.1
ENTHALPY @	600 'F AND	360 PSIA =	1309.9
ENTHALPY @	700.0 'F AND	360 PSIA =	1364.1
ENTHALPY OF FEED WATER =		228.65	
AVERAGE ENTHALPY =		1135.5	BTU/LB OF STEAM

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX IV
HEAT INPUT CALCULATION SHEETS

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-1a
DATE : 12-06-90

	STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
	-----	----	-----
END	881572	13: 20	100
BEGIN	880235	12: 15	LBS/HR STEAM
	-----	-----	-----
NET	1337 X 100 / 65 MINS =		123415

123415 LBS/HR STEAM / 55% EFF. = 224392 EQUIV.

224392 LBS/HR STEAM X 1120 BTU/LB = 251.4 BTU(e6)/HR

	OIL INTEGRATOR READINGS	TIME	GALS/HR
	-----	----	-----
END	877780	13: 20	
BEGIN	877650	12: 15	
	---	-----	
NET	130 GALLONS	65 MINS =	120 GPH

120 GPH X 150,000 BTU/GAL (EST) = 18 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	251.4	-	18	X	.2	=	46.7	LBS/HR
OIL			18	X	.1	=	1.8	LBS/HR
TOTAL						=	48.5	LBS/HR
						=	.193	#/MBtu

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-2a
DATE: 12-07-90

	STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
	-----	----	-----
END	907519	10: 50	100
BEGIN	906078	9: 40	LBS/HR STEAM
	-----	-----	-----
NET	1441	X 100 / 70	MINS = 123514

123514 LBS/HR STEAM / 55% EFF. = 224571 EQUIV.

224571 LBS/HR STEAM X 1134 BTU/LB = 254.7 BTU(e6)/HR

	OIL INTEGRATOR READINGS	TIME	GALS/HR
	-----	----	-----
END	878170	10: 50	
BEGIN	878020	9: 40	
	---	-----	
NET	150	GALLONS 70	MINS = 128.571 GPH

128.5714 GPH X 150,000 BTU/GAL (EST) = 19.286 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	254.7	-	19	X	.2	=	47.1	LBS/HR
OIL			19	X	.1	=	1.9	LBS/HR
TOTAL						=	49.0	LBS/HR
							.192	#/MMBtu

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-3a
DATE: 12-07-90

	STEAM INTEGRATOR READINGS		TIME		INTEGRATOR FACTOR
END	910262		13: 10		100
BEGIN	908815		12: 0		LBS/HR STEAM
NET	1447	X	100	/ 70	MINS = 124029

124029 LBS/HR STEAM / 55% EFF. = 225506 EQUIV.

225506 LBS/HR STEAM X 1135 BTU/LB = 256.1 BTU(e6)/HR

Aug = 254.1

	OIL INTEGRATOR READINGS		TIME		GALS/HR
END	878430		13: 10		
BEGIN	878300		12: 0		
NET	130	GALLONS	70	MINS =	111.429 GPH

111.4286 GPH X 150,000 BTU/GAL (EST) = 16.714 BTU(e6)/HR

*Aug = 18.000
Total = 272.07*

ALLOWABLE EMISSIONS

BAGASSE	256.1	-	17	X	.2	=	47.9	LBS/HR
OIL			17	X	.1	=	1.7	LBS/HR
TOTAL						=	49.5	LBS/HR
						=	.193	#/MMBtu

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX V
EMISSION CALCULATION SHEETS

EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-1a
DATE: 12-06-90

	FILTER	BEAKER	BLANKS	
			FILTER	ACETONE
NO. :	3780	5	3777	9
FINAL:	.7950	70.3204	.6444	72.5770
TARE :	.6386	70.2968	.6442	72.5759
NET :	.1564	.0236	.0002	.0011/200ML

WEIGHT = 180.00
RESIDUE = .96
VOLUME OF RINSE 174

Mn = 179.04 Mg AS = 44.2 SQ FT

Qs = 3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS) = 4407016 DSCFH

CS = (2.205 X 10⁻⁶) (Mn) / (VM STD) = 8.519e-6 LBS/SCF

CS' = 0.0154 (Mn) / (VM STD) = .06 GRAINS / SCF

PMR = (QS) (CS) = 37.54 LBS/HR

LOAD= MILLIONS OF BTU / HOUR INPUT = 251.4 BTU e6 / HR

CS = LBS / MILLION BTU = .149 LBS/ BTU e6

ALLOWABLE = 48.48 LBS/HR

= .193 LBS/ BTU e6

EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-2a
DATE: 12-07-90

	SAMPLES		BLANKS		
	FILTER	BEAKER	FILTER	ACETONE	
	-----	-----	-----	-----	
NO. :	3779	6	3777	EE220	
FINAL:	.7517	69.9221	.6444	72.5770	
TARE :	.6390	69.8710	.6442	72.5759	
	-----	-----	-----	-----	
NET :	.1127	.0511	.0002	.0011	/200ML

VOLUME OF RINSE 210

WEIGHT = 163.80
RESIDUE = - 1.15

Mn = 162.65 Mg AS = 44.2 SQ FT

$Q_s = 3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS) = 4010100$ DSCFH

$CS = (2.205 \times 10^{-6})(Mn) / (VM STD) = 1.170e-5$ LBS/SCF

$CS' = 0.0154 (Mn) / (VM STD) = .08$ GRAINS / SCF

$PMR = (QS) (CS) = 46.91$ LBS/HR

LOAD= MILLIONS OF BTU / HOUR INPUT = 254.7 BTU e6 / HR

$CS = LBS / MILLION BTu = .184$ LBS / BTu e6

ALLOWABLE = 49.02 LBS/HR

= .192 LBS / BTu e6

EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 11

RUN #: COMP-3a
DATE: 12-07-90

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
NO. :	3778	7	3777	9
FINAL:	.7663	72.5956	.6444	72.5770
TARE :	.6426	72.5270	.6442	72.5759
NET :	.1237	.0686	.0002	.0011/200ML

VOLUME OF RINSE 174

WEIGHT = 192.30
RESIDUE = .96

Mn = 191.34 Mg AS = 44.2 SQ FT

Qs = $3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$ = 4136387 DSCFH

CS = $(2.205 \times 10^{-6})(Mn) / (VM \text{ STD})$ = 1.330e-5 LBS/SCF

CS' = $0.0154 (Mn) / (VM \text{ STD})$ = .09 GRAINS/SCF

PMR = (QS) (CS) = 55.00 LBS/HR

LOAD= MILLIONS OF BTU / HOUR INPUT = 256.1 BTU e6 / HR

CS = LBS / MILLION BTu = .215 LBS/BTu e6

ALLOWABLE = 49.54 LBS/HR

= .193 LBS/BTu e6

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX VI
NOMENCLATURE SHEETS

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

NOMENCLATURE SHEET
PARTICULATE EMISSION TEST

Ar	Acetone residue - result of Blank evaporation.
AREA NOZZLE	Area of the nozzle in square feet.
AS	Area of the stack in square feet.
BDL	Below detectable limits
BWO	The amount of moisture in the flue gas.
% CO	Percent of carbon monoxide in the flue gas.
% CO ₂	Percent of carbon dioxide in the flue gas.
Cp	Pitot tube coefficient.
CS	The concentration in the stack in pounds per standard cubic foot.
CS'	The concentration in the stack in grains per standard cubic foot.
DELTA H	The meter orifice differential.
DELTA H (ABS)	The meter orifice differential, absolute conditions in inches of mercury.
Da (IN)	Diameter of the nozzle in inches.
DRY GAS IN	Temperature of the dry gas meter inlet degrees Fahrenheit.
DRY GAS OUT	Temperature of the dry gas meter outlet degrees Fahrenheit.
Ds (FT)	Diameter of the stack in feet.
E	The emission rate in pounds per million Btu derived by using F-Factor.
E (Heat Input)	The emission rate in pounds per million Btu derived by use of calculated heat input.
END METER	The dry gas meter reading at the end of the test.
F factor	The theoretical amount of air in dry standard cubic feet (DSCF) needed to combust a million Btu's worth of fuel.

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

NOMENCLATURE (cont'd)

Filter Catch	The amount of particulate captured on the filter during testing.
INT METER	The dry gas meter reading at the beginning of the test.
Md (DRY)	The dry molecular weight of the flue gas in pounds per pound mole.
MN	The amount of particulate collected by washing the nozzle, probe, and front half of the glassware, reported in milligrams.
MN'	The milligrams of particulate collected minus the blank.
Ms (WET)	Wet or actual molecular weight of the flue gas in pounds per pound mole.
% N2	The percent of nitrogen in the flue gas.
NO PTS	Number of traverse points.
% O2	Percent of oxygen in the flue gas.
P BAR	Barometric pressure at test location.
P STK	Static pressure of the stack in inches of water.
PMR	The emission rate in pounds per hour.
PS (ABS)	Absolute pressure conditions in the stack in inches of mercury.
Qs	The volumetric flow rate of the flue gas in dry standard cubic feet per hour.
SQ ROOT	The square root of each velocity head measurement.
SQRT DELTA P	The average of the square roots of the measured pressure drops.
Stack Temp or TS (°F)	The temperature of the stack in degrees Fahrenheit.
TS (°R)	The temperature of the stack in degrees Rankine.
T (Hot Box)	Temperature around the filter box, degrees Fahrenheit.
TM (°F)	Average temperature of the dry gas meter in degrees Fahrenheit.

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report


NOMENCLATURE (cont'd)

TM (°R)	Average temperature of the dry gas meter in degrees Rankine.
VEL HEAD	The pressure drop measured across the pitot tubes.
VI (TOT)	The amount of water collected in the impingers in milliliters.
VM (CF)	The volume sampled through the dry gas meter in cubic feet.
VM STD	Volume sampled through the dry gas meter corrected to standard conditions.
VS	Velocity of the stack gas in feet per second.
VW STD	The amount of moisture collected, converted to standard cubic feet.
Y	Meter box calibration factor.
o	Sampling time in minutes.


Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX VII

FIELD DATA SHEETS - UNIT OPERATING CONDITIONS



WATERMAN
FISCHER
CO.
150000165



WATERMAN
FISCHER
CO.
150000165

CAPACITY 125,000
INT. FACTOR 100
RUN 11-2R

BOILER # 11

POLLUTION COMPLIANCE TESTING
DATE: 12-7-90
TESTED BY: Gastmeyer eas

TIME	STEAM INTERGRATOR	OIL METER		STEAM		WEIGHING READING LBS/HR.	FEED WATER		BOILER PRESSURE DROP				CO ₂
		NORTH	SOUTH	PRESS.	TEMP.		PRESS.	TEMP.	OVERFIRE AIR PRESS.	AIR HEATER AIR OUT	UNDERGRATE AIR PRESS.	WIND BOX PRESSURE	
9:40	906078	728670	878020	340	700	124,500	600	260"					
9:58	906381			355	700	124,500	620	"				.8 .8 .8 .8	
10:10	906715			330	690	120,000	600	"				.25 .25 .25 .25	
10:25	907006			350	700	124,500	630	"					
10:40	907309			365	700	123,000	650	"					
10:50	907519	728670	878170	360	700	124,500	660	"					
									BOILER TEMPERATURE				
									BOILER OUTLET				
									AIR HEATER GAS OUT				
									AIR HEATER AIR OUT				
									I.D. FAN	500	500	495	495
									S.H. STEAM TEMP.	700	700	690	700
									PANEL SETTINGS				
									FURNACE PRESSURE				
									F.D. FAN PRESSURE				
									BAGASSE FEED	60	60	60	60
									UNDERGRATE AIR				
									OVERFIRE AIR				

TEST RESULTS

OIL USED	150	GALS.
TOTAL TEST TIME	70	MINS.
INTERGRATOR TIME	1441	COUNT
INTERGRATOR STEAM	123,514	P.P.H.
CHART AVERAGE	741,000	TOTAL
I.D. FAN TURBINE	4800	RPM
STACK TEMPERATURE	156	°F
GRATE TEMPERATURE	NA	°F
SCRUBBER WATER	800	G.P.H.

COMMENTS:

"A" "B"
(1) Mill speed 25 25 F.P.H.
(2) using one oil burner at minimum.
(3) Instrument dept. working on 200/350 station.

Allowed = 49.22

Actual = 46.91

PLANT READINGS BY George Park
% OF CAPACITY

CAPACITY 125,000
INT. FACTOR 100
RUN # 11-3A

BOILER # 11


POLLUTION COMPLIANCE TESTING
DATE: 12-7-90
TESTED BY: GASTHOUT INC

TIME	STEAM INTERGRATOR	OIL METER		STEAM		CHART READING LBS/HR.	FEED WATER		BOILER PRESSURE DROP		CO ₂
		NORTH	SOUTH	PRESS.	TEMP.		PRESS.	TEMP.	OVERFIRE AIR PRESS.	AIR HEATER AIR OUT	
12:00	908815	728670	878300	360	700	123,000	680	260			
12:15	909116			360	700	118,500	710	"			
12:30	909417			350	700	120,000	700	"			
12:45	909732			345	700	126,000	680	"			
1:00	910046			355	700	124,500	670	"			
1:10	910262	728670	878430	340	700	124,500	600	"			
BOILER TEMPERATURE BOILER OUTLET AIR HEATER GAS OUT AIR HEATER AIR OUT I.D. FAN S.H. STEAM TEMP. PANEL SETTINGS FURNACE PRESSURE F.D. FAN PRESSURE BAGASSE FEED UNDERGRATE AIR OVERFIRE AIR 											

TEST RESULTS				COMMENTS	
OIL USED	130	GALS.		"A"	"B"
TOTAL TEST TIME	70	MINS.		(1) Mill speed 75	55 F.P.H.
INTERGRATOR TIME	1447	COUNT		(2) using one oil burner at minimum	
INTERGRATOR STEAM	124,029	P.P.H		(3) Ins. dept- working on 250/300 station	
CHART READING	736,500	TOTAL			
CHART AVERAGE	122,750	P.P.H.			
I.D. FAN TURBINE	4800	RPM			
STACK TEMPERATURE	160	°F			
GRATE TEMPERATURE	N.A.	°F			
SCRUBBER WATER	800	G.P.M.			

Allowed = 49.54
Actual = 55.00

PLANT READINGS BY George D. Miller
% OF CAPACITY



Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX VIII
FIELD DATA SHEETS - STACK TESTING

FIELD DATA SHEET

GENERAL INFORMATION

Plant:	<u>CKEELANTA</u>	Run #:	<u>Comp-1A</u>
Location:	<u>UNIT 11</u>	Date:	<u>6 DEC 90</u>
Ds (ft):	<u>7.50</u>	No. Points:	<u>24</u>
Dn (in):	<u>.305</u>	Test Length:	<u>60</u>
Filter #:	<u>3780</u>	End Meter Reading:	<u>662.137</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>614.600</u>
P bar:	<u>30.08</u>	Begin Time:	<u>12:15</u>
P stack:	<u>.2</u>	End Time:	<u>13:20</u>

IMP-1 (INT)

100 mL

IMP-1 (FINAL)

1370

IMP-2 (INT)

100 mL

IMP-2 (FINAL)

156

IMP-3 (INT)

0 mL

IMP-3 (FINAL)

3

IMP-4 (INT)

500 mL

IMP-4 (FINAL)

529

TEST 1

TEST 2

TEST 3

% CO2

10.7

% O2

9.5

% CO

0

Project Director:

SEAN MacKay

Field Laboratory:

S. MacKay

Meter Box Operator:

K. Nolan

Chain of Custody:

S. MacKay

Probe Operator:

M. Wescott

Plant Coordinator:

G. DEUANG

Orsat Analyst:

S. MacKay

Agency Rep:

K. TUCKER

Comments:

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

Page 1 of 2

Sampling time per point: 2 1/2 min

Plant: CKEELANTA

Run #: COMP-5 JA

Location: UNIT 11

Date: 12-6-90

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
			614.600						
9.7 1	-63	3.53	616.89	77	75	228	53	152	8
2	-70	3.92	619.20	82	77	230	51	153	10
3	-66	3.70	621.55	83	78	257	49	153	10
9.7 4	-61	2.42	623.38	87	78	269	51	154	10
5	-56	3.14	626.13	91	80	248	54	153	9
6	-44	2.46	627.09	89	78	237	55	154	9
9.4 7	-40	2.24	629.80	89	80	234	58	154	6
8	-38	2.13	631.59	88	80	233	57	153	5
9	-45	2.52	633.57	90	81	237	56	153	5
10	-48	2.69	635.46	90	83	241	60	154	6
9.7 11	-54	3.02	637.54	91	85	239	58	153	8
12	-57	3.19	639.610	92	83	230	58	155	8

Comments: DELTA P = 5.6 DELTA H
 BOX # 4 ; Y = 1.001 , DELTA H @ 2.03
 START TIME : 12.15
 STOP TIME : 13.20
 INITIAL LEAK CHECK 0.000 AT 15 INCHES HG
 FINAL LEAK CHECK 1.0 AT 14 INCHES HG
 Pilot LEAK CHK - 9000 @ 5" H₂O

FIELD DATA SHEET **TRAVERSE POINT INFORMATION**

Page 2 of 2

Sampling time per point: 2 1/2 min

Plant: C KEELANDTIA

Run #: COMP - 3 / A

Location: UNIT 11

Date: 12-6-90

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hol Box	Impg Temp	Stack Temp	Vac
			639.811						
B1	1.0	5.6	642.20	88	83	265	54	153	14
2	1.1	6.16	644.74	92	83	251	51	154	14
98 3	1.1	6.16	647.11	94	84	236	51	153	14
4	1.05	5.88	649.52	95	85	229	52	153	14
5	.92	5.15	651.85	96	86	229	50	154	14
6	.64	3.58	654.23	94	85	234	50	154	14
9.2 7	.20	1.12	656.30	96	87	242	51	154	14
8	.12	.67	658.05	94	86	247	5.7	154	13
9	.11	.62	659.23	96	87	251	60	155	2
10	.11	.62	660.20	93	86	251	57	154	1
9.2 11	.12	.67	661.18	92	87	246	57	153	1
12	.11	.62	662.137	90	87	258	60	153	1

Comments: DELTA P * _____ = DELTA H
 BOX # _____ ; Y = _____ , DELTA H @ _____
 START TIME : _____
 STOP TIME : 1:20 pm
 INITIAL LEAK CHECK .000 AT 14 INCHES HG
 FINAL LEAK CHECK _____ AT _____ INCHES HG

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEELANT4</u>	Run #:	<u>comp 11-2A</u>
Location:	<u>UNIT 11</u>	Date:	<u>7 DEC 90</u>
Ds (ft):	<u>7.5 FT</u>	No. Points:	<u>24</u>
Dn (in):	<u>.250</u>	Test Length:	<u>60 min</u>
Filter #:	<u>3779</u>	End Meter Reading:	<u>693.926</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>662.468</u>
P bar:	<u>30.09</u>	Begin Time:	<u>9:40</u>
P stack:	<u>.2</u>	End Time:	<u>10:50</u>

IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>309 mL</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>143.0 mL</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>3.0 mL</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>513.2 g</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>11.5</u>	<u> </u>	<u> </u>
% O ₂	<u>8.7</u>	<u> </u>	<u> </u>
% CO	<u>0</u>	<u> </u>	<u> </u>

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>S. MacKay</u>
Meter Box Operator:	<u>K. Nolan</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>M. Wescott</u>	Plant Coordinator:	<u>G. Devane</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>K. Tucker</u>

Comments:

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

Page 1 of 2

Sampling time per point: 2 1/2 min

Plant: OKEELANTA

Run #: LCMP - 2A

Location: UNIT 11

Date: 12-7-90

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Slack Temp	Vac
0.2%			662.468						
1	-55	1.38	664.03	81	77	225	59	156	1
2	.60	1.50	665.56	81	77	241	55	156	1
8.6	3	-63	667.16	82	77	264	56	158	1
4	.60	1.50	668.77	83	77	270	57	158	1
5	-53	1.33	670.17	86	74	254	60	156	1
6	.45	1.13	671.68	85	80	247	60	156	1
7	.33	.83	672.79	88	80	238	63	157	1
8.8	8	-35	673.96	91	82	238	63	156	1
9	-38	.95	675.16	86	80	247	62	156	1
10	-43	1.08	676.46	88	82	243	61	156	1
11	.41	1.03	677.67	88	83	248	61	160	1
8.6	12	.39	678.716	87	82	248	62	157	1

Comments: DELTA P = 2.50 DELTA H
 BOX # 40 ; Y = 1.001 , DELTA H @ 2.03
 START TIME : 9.40
 STOP TIME : _____
 INITIAL LEAK CHECK .000 AT 15 INCHES HG
 FINAL LEAK CHECK _____ AT _____ INCHES HG

FIELD DATA SHEET

TRAVERSE POINT INFORMATION

Page 2 of 2

Sampling time per point: 2 1/2 min

Plant: CKEELANTA

Run #: COMP - 2A

Location: UNIT 11

Date: 12-7-90

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
			679.060						
B1	1.0	2.5	681.01	86	82	243	63	156	2
2	1.05	2.63	682.92	89	84	246	57	156	2
9.1 3	1.05	2.67	684.05	89	85	244	59	156	2
4	1.05	2.67	686.81	88	84	252	62	157	3
5	.85	2.13	688.67	91	83	260	65	158	3
6	-.57	1.43	690.28	92	85	261	68	158	3
8.7 7	-.18	-.45	691.23	90	85	265	68	157	3
8	-.08	-.20	691.80	88	85	247	66	156	1
9	-.06	-.15	692.27	87	84	250	63	156	1
10	-.07	-.18	692.75	86	84	255	62	156	1
11	-.08	-.20	693.31	85	84	265	62	157	1
8.8 12	-.10	-.25	693.92	85	83	251	60	156	1

Comments: DELTA P * 2.5 = DELTA H
 BOX # _____ ; Y = _____ , DELTA H @ _____
 START TIME : _____
 STOP TIME : 10.50
 INITIAL LEAK CHECK .0 AT 15 INCHES HG
 FINAL LEAK CHECK .000 AT 5 INCHES HG

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>CREE/ANTA</u>	Run #:	<u>(Camp-34</u>
Location:	<u>UNIT 11</u>	Date:	<u>7 DEC 90</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>.250</u>	Test Length:	<u>60 min</u>
Filter #:	<u>3778</u>	End Meter Reading:	<u>726.972</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>694.180</u>
P bar:	<u>30.09</u>	Begin Time:	<u>12:00</u>
P stack:	<u>.2</u>	End Time:	<u>13:00</u>
IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>310 mL</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>136 mL</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>4 mL</u>
IMP-4 (INT)	<u>500.0 g</u>	IMP-4 (FINAL)	<u>514 g</u>

	TEST 1	TEST 2	TEST 3
% CO ₂	<u>11.6</u>	<u> </u>	<u> </u>
% O ₂	<u>3.6</u>	<u> </u>	<u> </u>
% CO	<u> </u>	<u> </u>	<u> </u>

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>S. MacKay</u>
Meter Box Operator:	<u>L. Nolan</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>M. Wescott</u>	Plant Coordinator:	<u>G. Devane</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>K. Tucker</u>

Comments:

FIELD DATA SHEET **TRAVERSE POINT INFORMATION**

Page 1 of 2

Sampling time per point: 2 1/2 MIN

Plant: OKEELANTA

Run #: COMA-3A

Location: UNIT 11

Date: 12-7-90

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
0.2%			594.180						
1	.51	1.33	695.78	80	79	266	62	157	1
2	.55	1.43	697.27	83	80	267	57	160	1
7.4									
3	.59	1.53	698.80	84	80	260	60	157	1
4	.55	1.43	700.34	85	81	267	59	160	1
5	.52	1.35	701.54	89	81	266	60	157	1
9.5									
6	.45	1.17	703.23	86	82	258	62	155	1
7	.37	.96	704.47	92	83	230	63	155	1
8	.40	1.04	705.71	86	84	251	65	155	1
9	.46	1.20	707.06	87	84	228	65	156	1
10	.48	1.25	708.46	89	84	255	62	156	1
8.8									
11	.50	1.30	709.90	90	83	251	63	156	1
12	.51	1.33	711.315	94	86	232	66	155	1

Comments: DELTA P = 2.6 DELTA H
 BOX # 4 ; Y = 1.001 , DELTA H @ 2.03
 START TIME : 12:00
 STOP TIME : 3:10
 INITIAL LEAK CHECK 0 AT 15 INCHES HG
 FINAL LEAK CHECK 0 AT 6 INCHES HG

FIELD DATA SHEET **TRAVERSE POINT INFORMATION**

Page 2 of 2

Sampling time per point: 2 1/2 min

Plant: OKEELANTA

Run #: Comp

Location: UNIT 11

Date: 12-7-90

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Slack Temp	Vac
0.1			711.578						
B1	1.05	2.73	713.95	88	88	256	58	156	5
2	1.05	2.73	716.05	90	86	240	65	156	5
3	1.08	2.81	718.0	91	87	260	61	155	6
9.9 4	1.05	2.73	720.11	92	88	242	62	156	6
5	.90	2.34	721.87	96	87	239	65	156	6
6	.63	1.64	723.62	93	87	242	64	155	5
7	.23	.60	724.62	92	86	262	65	156	4
9.1 8	.09	.234	725.22	89	87	264	61	156	2
9	.08	.21	725.78	90	86	260	63	155	1
10	.05	.13	726.26	87	85	260	62	155	1
11	.10	.26	726.65	87	85	259	62	155	1
7.6 12	.04	.10	726.972	87	86	250	66	155	1

Comments: DELTA P * _____ = DELTA H
 BOX # _____ ; Y = _____ , DELTA H @ _____
 START TIME : _____
 STOP TIME : _____
 INITIAL LEAK CHECK _____ AT _____ INCHES HG
 FINAL LEAK CHECK -000 AT 6 INCHES HG

Okeelanta Corporation - Boiler # 11
Particulate Emissions Test Report

APPENDIX IX
EQUIPMENT CALIBRATION SHEETS

METER BOX CALIBRATION SHEET

BOX NUMBER: 4
PRESS BAR : 30.04

DATE: 10 SEPT 1990
DUE: 10 MAR 1991

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	5	5.037	.50	.0368	30.08	13.80
2	5	5.043	1.00	.0735	30.11	9.55
3	10	10.190	1.50	.1103	30.15	15.34
4	10	10.273	2.00	.1471	30.19	13.46
5	10	10.330	3.00	.2206	30.26	11.69
6	10	10.400	4.00	.2941	30.33	9.64

RUN #	TEMP WET (°F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H @
1	69.3	82.3	77.3	79.8	1.011	2.02
2	69.7	83.7	78.3	81.0	1.010	2.00
3	70.0	86.7	80.3	83.5	1.003	1.93
4	70.0	89.3	82.7	86.0	.9979	1.97
5	69.3	91.7	83.3	87.5	.9940	2.21
6	69.0	94.7	85.3	90.0	.9900	1.99
AVERAGE					1.001	2.03

MAX % DEVIATION 1.10
ALLOWABLE % DEV 2.00

FORMULAS:

$$Y = \frac{(V W) (P b) (I d)}{(V d) (P b \text{ ABS}) (T w)}$$

$$\text{DELTA H @} = \frac{0.0317 (\text{DELTA H})}{(P b) (T d)} * \left[\frac{(T w) (\text{TIME})^2}{(V w)} \right]$$

CALIBRATION BY:

SCOTT LAWTON

From Computer Disc
BLT
12-Feb-90

NOZZLE CALIBRATION SHEET

PROJECT NAME: OKEEELANTA

PROJECT NUMBER: 90-102

POINT# NOZZLE# 5/16-3 NOZZLE # 5/16-14 NOZZLE# 1/4-3 NOZZLE # 1/4-1

1 .316 .313 .251 .250

2 .314 .312 .249 .251

3 .315 .311 .250 .251

AVG. .315 .312 .250 .251

SEAN McHAY
CALIBRATED BY:

3 DEC 90
DATE:

NOZZLE CALIBRATION SHEET

PROJECT NAME: OKEE/ANTA

PROJECT NUMBER: 90 102

POINT# NOZZLE# 19/04-1 NOZZLE # 1/4-2 NOZZLE# _____ NOZZLE # _____

1 .305 .256 _____

2 .305 .258 _____

3 .305 .257 _____

AVG. .305 .257 _____

SEAN MacFARLANE
CALIBRATED BY:

3 DEC 90
DATE:

THERMOCOUPLE CALIBRATION SHEET

SET #: 8'-1

DATE: 10-25-85

REFERENCE MERCURY/GLASS

STANDARD ('F)	THERMOCOUPLE ('F)	ABSOLUTE OF % DEVIATION
74	72	.37
210	205	.75
400	409	1.05
MAXIMUM DEVIATION		1.05
ALLOWABLE		1.50


SET #: 8.5'-1

DATE: 11-15-85

STANDARD ('F)	THERMOCOUPLE ('F)	ABSOLUTE OF % DEVIATION
66	63	.57
170	170	0
211.5	215	.52
MAXIMUM DEVIATION		.57
ALLOWABLE		1.50

G. ZWILLING

CALIBRATION BY: _____



12 gm

Silica 12 mg mat

500 gm
5/12 gm

water 8p

1 gm = 1 ml = 12 ml

* 3-24-2
nit input
253 ← load

APIS 0005

49

Facility: Okelanta Corporation
49.

INPUT SHEET - REV: 09/13/83 - PAGE 2 OF 2

ENTER THE FOLLOWING:

	RUN1	RUN2	RUN3
1. H2O COLLECTED (ONLY VOL. MEASURED), ML:	329	250.0	250.0
2. H2O COLLECTED (WEIGHED PART ONLY), GM:	2.9	13.2	14.9
3. M'N PARTICULATE WEIGHT, GM:	179	162	191
4. V'M VOLUME METERED, CF:	47.336	31.314	32.529
5. Y DRY GAS METER CAL FACTOR:	1.001	1.001	1.001
✓ 6. RDP AVG SOR DELTA P (WHEN SAMPLING):	0.7	0.66	0.7
✓ 7. DH AVG DELTA H, IN H2O:	3.03	1.23	1.33
8. T'M AVG METER TEMP, DEG F:	86.5	84.4	86.5
✓ 9. T'S AVG STACK TEMP, DEG F:	153.5	156.7	156
10. P'S* STACK PRESS, *IN(.....):	2	2	2
11. P'B BAROMETRIC PRESS, IN HG:	30.08	30.09	30.09
13. D'N ACTUAL NOZZLE DIAMETER, IN.:	305	25	25
14. T ACTUAL SAMPLE TIME, MIN:	60	60	60
15. C'P PITOT TUBE COEFFICIENT:	0.84	0.84	0.84
OPTION ENTRIES:			
17. ORSAT/FYRITE - ZCO2:	10.7		
18. ORSAT/FYRITE - ZO2:	9.5		
20. ORSAT/FYRITE (FOR C'S @ 50% E.A.)-ZCO:			
19. SPECIFIC M'D ENTRIES:			
20. CYCLONIC (10-20 DEG) - AVG COS(YAW):			
26. CYC.()20] - AVG(SOR D.P X COS(YAW)):			
21. PROCESS WT SOURCE - T/HR:			
22. LB/TON REGULATED - T/HR:			
27. LB/* REGULATED (* AS DEFINED) - */HR:			
23. LAM&CYC(20)-VAL(SAMPLE PTS/T PTS):	1	1	1