

## TABLE OF CONTENTS

|                                         |    |
|-----------------------------------------|----|
| I. SUMMARY OF RESULTS .....             | 4  |
| II. INTRODUCTION .....                  | 6  |
| III. AMMONIA DATA .....                 | 8  |
| IV. HYDROCARBON DATA .....              | 11 |
| V. SULFUR EMISSIONS .....               | 16 |
| A. Results .....                        | 17 |
| B. Sulfur Analysis .....                | 18 |
| VI. RELATIVE ACCURACY .....             | 19 |
| A. Results .....                        | 20 |
| B. Reference Method & CEM Data .....    | 23 |
| C. Reference Method Results .....       | 25 |
| VII. EMISSION FACTORS (lbs/MMBtu) ..... | 37 |
| VIII. FUEL GAS ANALYSIS .....           | 39 |
| IX. METHODS & EQUATIONS .....           | 41 |

**TABLE OF CONTENTS**  
**(Continued)**

**APPENDICES**

|                                                 |     |
|-------------------------------------------------|-----|
| I. OPERATIONAL DATA (Supplied by Destec) .....  | 57  |
| II. RAW DATA .....                              | 59  |
| A. ST-1B Field Data (NH <sub>3</sub> ) .....    | 60  |
| B. 350.3 Lab Analysis (NH <sub>3</sub> ) .....  | 68  |
| C. Hydrocarbon Chromatograms .....              | 71  |
| D. Instrument Strip Charts .....                | 75  |
| III. QUALITY ASSURANCE .....                    | 83  |
| A. Chain of Custody .....                       | 84  |
| B. Calibration Gas Certificates .....           | 85  |
| C. Hydrocarbon Calibrations & Linearities ..... | 89  |
| IV. CORRESPONDENCE .....                        | 100 |

**RECEIVED**

MAY 28 1993

SAN JUAN VALLEY UNIFIED  
APCD—SOUTHERN REGION

# SUMMARY OF RESULTS

S-0172-0001-04

## SUMMARY OF SOURCE TEST RESULTS

COMPANY: DESTEC - LIVE OAK COGEN

APCD #: 4213001 (B)

TEST DATE: APRIL 22, 1993

UNIT #: TURBINE OUTLET

| EMISSIONS                | gr/scf                              | @12%CO2 | ppm                                    | ppm @15% O2                 | lb/ MMBtu                   | lb/hr                       | lb/day                         | Permit Limits        |
|--------------------------|-------------------------------------|---------|----------------------------------------|-----------------------------|-----------------------------|-----------------------------|--------------------------------|----------------------|
| NH3                      |                                     |         | 3.82<br>2.66<br><u>3.91</u>            | 4.17<br>2.97<br><u>4.27</u> |                             | 2.37<br>1.65<br><u>2.42</u> |                                |                      |
| Mean:                    |                                     |         | 3.46                                   | 3.88                        |                             | 2.15                        | 52                             | 20 ppm               |
| SULFUR                   |                                     |         |                                        |                             |                             |                             |                                |                      |
| Mean:                    |                                     |         | 1.36                                   |                             |                             | 0.044                       | 1.05                           | 11.0 lb/hr as sulfur |
| NOx (dry)<br>(RUNS 1-12) |                                     |         |                                        |                             |                             |                             |                                |                      |
| Mean:                    |                                     |         | 2.6                                    | 2.8                         | 0.0105                      | 4.3                         | 103                            | 0.0135 lb/hr SO2     |
| CO<br>(RUNS 1-12)        |                                     |         |                                        |                             |                             |                             |                                |                      |
| Mean:                    |                                     |         | 2.7                                    | 2.9                         |                             | 2.7                         | 66                             | 11.0 lb/hr           |
| NMHC                     |                                     |         |                                        |                             |                             |                             |                                |                      |
|                          |                                     |         | 0.06                                   |                             |                             | 0.037                       | 0.9                            | 5.37 lb/hr           |
| RELATIVE ACCURACY        | % RA<br>Related to Reference Method |         | % RA<br>Related to Applicable Standard |                             | PERMIT LIMITS               |                             |                                |                      |
|                          |                                     |         |                                        |                             | Related to Reference Method |                             | Related to Applicable Standard |                      |
| NOx                      | 6.65                                |         | NA                                     |                             | 20 %                        |                             | 10 %                           |                      |
| CO                       | 4.39                                |         | NA                                     |                             | 10 %                        |                             | 5 %                            |                      |
| O2                       | 1.13                                |         | NA                                     |                             | 20 %                        |                             | 10 %                           |                      |

For San Joaquin Unified APCD Use Only:

1/ Emission limit as sulfur = (lb/hr SO2/2) + (lb/hr SO4/3)

*Q. P. W.*

# PRODUCTION

## INTRODUCTION

On April 22, 1993, Petro Chem Environmental Services, Inc. (PCES) performed a series of emission source tests for Destec Operating Company at their Live Oak Limited Cogeneration Facility located in Bakersfield, California. The unit tested was one 48.5 MW GE LM-5000 gas fired turbine. Determination of concentrations (ppm) and emissions (lbs/hr) of ammonia, sulfur, NMHC, NO<sub>x</sub>, CO, O<sub>2</sub>, from the exhaust of the turbine and relative accuracy testing was performed for NO<sub>x</sub>, CO, and O<sub>2</sub> using the following procedures:

| PARAMETERS                                                            | METHOD                                                                              | # TEST RUNS    |
|-----------------------------------------------------------------------|-------------------------------------------------------------------------------------|----------------|
| Ammonia                                                               | BAAQMD ST-1B                                                                        | 3 - 30 minute  |
| Sulfur                                                                | Fuel Analysis / Fuel Rates<br>EAS Labs                                              | 1              |
| NMHC                                                                  | EPA Method 18; (modified)<br>C <sub>1</sub> - C <sub>6+</sub>                       | 3              |
| NO <sub>x</sub>                                                       | EPA Method 20;<br>Chemiluminescent Analyzer<br>equipped with<br>Molydenum Convertor | 12 - 30 minute |
| CO                                                                    | EPA Method 10;<br>Gas Filter<br>Correlation Analyzer                                | 12 - 30 minute |
| O <sub>2</sub>                                                        | EPA Method 20;<br>Fuel Cell Analyzer                                                | 12 - 30 minute |
| Molecular Weight<br>O <sub>2</sub> , CO <sub>2</sub> , N <sub>2</sub> | EPA Method 3; Orsat                                                                 | 2              |
| Volume Flow<br>DSCFM                                                  | EPA Method 2 & 4;<br>Pitot Tube Traverse<br>and Condensation Train                  | 2              |
| Relative Accuracy<br>NO <sub>x</sub> / CO / O <sub>2</sub>            | Title 40 CFR Performance<br>Spec II, III, IV                                        | 9 - 30 minute  |

All sampling was performed by Doug Towne and Scott Davis of Petro Chem Environmental Services, Inc. The hydrocarbons and fuel gas analyses were performed by Terry Rowles of PCES. Scott Kicker of Destec Operating Company supervised the testing. Glenn Sliter of San Joaquin Valley Unified APCD, Southern Region, was present and witnessed the testing.

# MONIA DATA

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN  
 DATE : 4-22-93  
 PROJECT : 027-488

METHOD 1-4  
 FIELD DATA @ 60° F

|                                           | RUN #: | 1       | 2       | 3       |         |
|-------------------------------------------|--------|---------|---------|---------|---------|
|                                           | TIME : | 1400    | 1530    | 1728    | AVERAGE |
| Vm (dry gas sampled)                      |        | 28.931  | 30.695  | 28.826  |         |
| Y (meter calib. factor)                   |        | 1.00976 | 1.00976 | 1.00976 |         |
| P bar (Barometric pressure)               |        | 29.5    | 29.5    | 29.5    |         |
| P static (stack pressure, " H2O)          |        | -0.37   | -0.37   | -0.37   |         |
| Delta H (differential meter press, " H2O) |        | 0.57    | 0.57    | 0.57    |         |
| Tm (meter temperature, R°)                |        | 535.3   | 532.3   | 534.1   |         |
| Vol H2O mls                               |        | 107.7   | 122.1   | 118.9   |         |
| Vm(std),dscf                              |        | 28.02   | 29.90   | 27.98   | 28.63   |
| Bws-H2O vapor                             |        | 0.1515  | 0.1595  | 0.1649  |         |
| MF-moisture factor                        |        | 0.8485  | 0.8405  | 0.8351  |         |
| % CO2                                     |        | 3.1     | 3.0     | 3.1     |         |
| % O2                                      |        | 15.5    | 15.6    | 15.5    |         |
| % N2                                      |        | 81.4    | 81.4    | 81.4    |         |
| Md-MW stk gas,dry                         |        | 29.12   | 29.10   | 29.12   | 29.11   |
| Ms-MW stk gas,wet                         |        | 27.43   | 27.33   | 27.28   | 27.35   |
| Cp-pitot tube                             |        | 0.831   | 0.831   | 0.831   |         |
| Avg sq rt ^p                              |        | 1.06    | 0.98    |         |         |
| T stack, R°                               |        | 731     | 730     |         |         |
| Stack area,ft2                            |        | 94.315  | 94.315  | 94.315  |         |
| Vs-fps                                    |        | 71.81   | 65.98   |         |         |
| Qstd-dscfm                                |        | 241599  | 220219  |         | 230909  |
| Sample time                               |        | 48      | 48      | 48      |         |



COMPANY : DESTEC  
UNIT : LIVE OAK COGEN - TURBINE OUTLET  
DATE : 4-22-93  
PROJECT : 027-488

**AMMONIA (NH3)**  
**EPA 350.3 / BAAQMD ST 1-B**

|                    | Run - 1 | Run - 2 | Run - 3 | AVERAGE     |
|--------------------|---------|---------|---------|-------------|
| NH3 (mg/L)         | 4.73    | 3.64    | 4.73    |             |
| Sample Volume (ml) | 460     | 445     | 470     |             |
| Total NH3 (mg)     | 2.18    | 1.62    | 2.22    |             |
| Vm, acf (sampled)  | 28.931  | 30.695  | 28.826  |             |
| delta-H            | 0.57    | 0.57    | 0.57    |             |
| Meter Temp, °F     | 75.3    | 72.3    | 74.1    |             |
| % O2               | 15.5    | 15.6    | 15.5    |             |
| Vstd,dscf =        | 28.02   | 29.90   | 27.98   |             |
| DSCFM =            | 230909  | 230909  | 230909  |             |
| ppm NH3 =          | 3.82    | 2.66    | 3.91    | <u>3.46</u> |
| ppm NH3 @ 15% O2 = | 4.17    | 2.97    | 4.27    | <u>3.80</u> |
| lbs/hr NH3 =       | 2.37    | 1.65    | 2.42    | <u>2.15</u> |

**Calculations:**

$$Vstd = \frac{(17.38 * Vm * (Pb + (H/13.6)) * MC)}{Tm}$$

Pbar..... 29.5  
Meter Coeff..... 1.00976

$$ppm NH3 = \frac{mg * 836}{Vstd * MW}$$

**Where:**

Vstd = Corrected sample volume, SDCF @ 60°F & 29.92 in Hg  
Vm = Uncorrectd meter volume, ft3  
Tm = Absolute meter temperature in °R  
Pb = Barometric pressure, in. Hg  
17.38 = A constant correcting to 60°F & 29.92 in. Hg (520 R/29.92" Hg)  
MC = Dry gas meter calibration coefficient  
mg = Total wt. of NH3 in the impinger catch (in mg)  
836 = A constant derived from the molar gas volume and  
correcting to 60F and 29.92 inches Hg.  
delta-H = Pressure differential at meter orifice  
MW = Molecular weight of ammonia, 17 gm/mole

# COCARBON DATA

COMPANY : DESTEC  
UNIT : LIVE OAK COGEN  
DATE : 4-22-93  
PROJECT : 027-488

**HYDROCARBON RESULTS  
CORRECTED FOR METHOD BLANK**

|                      |     |                                         |                |             |                     |             |
|----------------------|-----|-----------------------------------------|----------------|-------------|---------------------|-------------|
| RUN No.: 1           |     | average of pitot tube velocity profiles |                |             |                     |             |
| DSCFM: 230909        |     | BLANK                                   | ppm<br>- BLANK | lb/hr       | ppm<br>(as Methane) | lb/hr       |
| Methane (C1)         | *ND | 0.05                                    | 1.47           | 0.86        | 1.47                | 0.86        |
| Ethane (C2)          | *ND | 0.03                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Propane (C3)         | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Butane (C4)          | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Pentane (C5)         | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Hexane (C6)          |     | 0.02                                    | 0.02           | 0.06        | 0.12                | 0.07        |
| <u>Total</u>         |     |                                         | <u>1.49</u>    | <u>0.92</u> | <u>1.59</u>         | <u>0.93</u> |
| <u>Total</u>         |     |                                         |                |             |                     |             |
| <u>(non methane)</u> |     |                                         | <u>0.02</u>    | <u>0.06</u> | <u>0.12</u>         | <u>0.07</u> |

|                      |     |                                         |                |             |                     |             |
|----------------------|-----|-----------------------------------------|----------------|-------------|---------------------|-------------|
| RUN No.: 2           |     | average of pitot tube velocity profiles |                |             |                     |             |
| DSCFM: 230909        |     | BLANK                                   | ppm<br>- BLANK | lb/hr       | ppm<br>(as Methane) | lb/hr       |
| Methane (C1)         | *ND | 0.05                                    | 1.42           | 0.83        | 1.42                | 0.83        |
| Ethane (C2)          | *ND | 0.03                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Propane (C3)         | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Butane (C4)          | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Pentane (C5)         | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Hexane (C6)          |     | 0.02                                    | 0.01           | 0.03        | 0.06                | 0.04        |
| <u>Total</u>         |     |                                         | <u>1.43</u>    | <u>0.86</u> | <u>1.48</u>         | <u>0.86</u> |
| <u>Total</u>         |     |                                         |                |             |                     |             |
| <u>(non methane)</u> |     |                                         | <u>0.01</u>    | <u>0.03</u> | <u>0.06</u>         | <u>0.04</u> |

|                      |     |                                         |                |             |                     |             |
|----------------------|-----|-----------------------------------------|----------------|-------------|---------------------|-------------|
| RUN No.: 3           |     | average of pitot tube velocity profiles |                |             |                     |             |
| DSCFM: 230909        |     | BLANK                                   | ppm<br>- BLANK | lb/hr       | ppm<br>(as Methane) | lb/hr       |
| Methane (C1)         | *ND | 0.05                                    | 1.40           | 0.82        | 1.40                | 0.82        |
| Ethane (C2)          | *ND | 0.03                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Propane (C3)         | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Butane (C4)          | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Pentane (C5)         | *ND | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| Hexane (C6)          |     | 0.02                                    | 0.00           | 0.00        | 0.00                | 0.00        |
| <u>Total</u>         |     |                                         | <u>1.40</u>    | <u>0.82</u> | <u>1.40</u>         | <u>0.82</u> |
| <u>Total</u>         |     |                                         |                |             |                     |             |
| <u>(non methane)</u> |     |                                         | <u>0.00</u>    | <u>0.00</u> | <u>0.00</u>         | <u>0.00</u> |

\*ND - Non detect in sample blank, used detection limit

COMPANY : DESTEC  
UNIT : LIVE OAK COGEN - TURBINE OUTLET  
DATE : 4-22-93  
PROJECT : 027-488

### HYDROCARBON RESULTS UNCORRECTED


| RUN No.: 1             |      | DSCFM: 230909 average of pitot tube velocity profiles |       |                     |                       |
|------------------------|------|-------------------------------------------------------|-------|---------------------|-----------------------|
|                        |      | ppm                                                   | lb/hr | ppm<br>(as Methane) | lb/hr<br>(as Methane) |
| Methane                | (C1) | 1.52                                                  | 0.89  | 1.52                | 0.89                  |
| Ethane                 | (C2) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Propane                | (C3) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Butane                 | (C4) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Pentane                | (C5) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Hexane                 | (C6) | 0.04                                                  | 0.13  | 0.24                | 0.14                  |
| <u>Total</u>           |      | 1.56                                                  | 1.01  | 1.76                | 1.03                  |
| Total<br>(non methane) |      | 0.04                                                  | 0.13  | 0.24                | 0.14                  |

---

| RUN No.: 2             |      | DSCFM: 230909 average of pitot tube velocity profiles |       |                     |                       |
|------------------------|------|-------------------------------------------------------|-------|---------------------|-----------------------|
|                        |      | ppm                                                   | lb/hr | ppm<br>(as Methane) | lb/hr<br>(as Methane) |
| Methane                | (C1) | 1.47                                                  | 0.86  | 1.47                | 0.86                  |
| Ethane                 | (C2) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Propane                | (C3) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Butane                 | (C4) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Pentane                | (C5) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Hexane                 | (C6) | 0.03                                                  | 0.09  | 0.18                | 0.11                  |
| <u>Total</u>           |      | 1.50                                                  | 0.95  | 1.65                | 0.96                  |
| Total<br>(non methane) |      | 0.03                                                  | 0.09  | 0.18                | 0.11                  |

---

| RUN No.: 3             |      | DSCFM: 230909 average of pitot tube velocity profiles |       |                     |                       |
|------------------------|------|-------------------------------------------------------|-------|---------------------|-----------------------|
|                        |      | ppm                                                   | lb/hr | ppm<br>(as Methane) | lb/hr<br>(as Methane) |
| Methane                | (C1) | 1.45                                                  | 0.85  | 1.45                | 0.85                  |
| Ethane                 | (C2) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Propane                | (C3) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Butane                 | (C4) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Pentane                | (C5) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| Hexane                 | (C6) | 0.00                                                  | 0.00  | 0.00                | 0.00                  |
| <u>Total</u>           |      | 1.45                                                  | 0.85  | 1.45                | 0.85                  |
| Total<br>(non methane) |      | 0.00                                                  | 0.00  | 0.00                | 0.00                  |



**PETRO  
CHEM  
ENVIRONMENTAL  
SERVICES, INC.**

3207 Antonino Avenue  
Bakersfield, California 93308  
(805) 327-7300  
FAX (805) 327-3459

COMPANY : DESTEC OPERATING  
DATE : 4-22-93  
PROJECT : 027-488

DATE RECEIVED : 4-23-93  
DATE ANALYZED : 4-24-93  
DATE REPORTED: 4-28-93

**EPA METHOD 18  
HYDROCARBON ANALYSIS REPORT**

UNIT : LIVE OAK COGEN

| CONSTITUENT | RUN # 1<br>ppm(v/v) | RUN # 2<br>ppm(v/v) | RUN # 3<br>ppm(v/v) |
|-------------|---------------------|---------------------|---------------------|
| METHANE     | 1.52                | 1.47                | 1.45                |
| ETHANE      | ND                  | ND                  | ND                  |
| PROPANE     | ND                  | ND                  | ND                  |
| BUTANE      | ND                  | ND                  | ND                  |
| PENTANE     | ND                  | ND                  | ND                  |
| HEXANES+    | 0.04                | 0.03                | ND                  |
| TOTAL       | 1.56                | 1.50                | 1.45                |
| NON-METHANE | 0.04                | 0.03                | 0.00                |

UNIT : HC SAMPLE BLANK

| CONSTITUENT | ppm(v/v) |
|-------------|----------|
| METHANE     | ND       |
| ETHANE      | ND       |
| PROPANE     | ND       |
| BUTANE      | ND       |
| PENTANE     | ND       |
| HEXANES+    | 0.02     |
| TOTAL       | 0.02     |
| NON-METHANE | 0.02     |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN  
 DATE : 4-22-93  
 PROJECT : 027-488

# HYDROCARBON RESULTS @ 60°F

|                        |      | DETECTION LIMITS |                     |
|------------------------|------|------------------|---------------------|
|                        |      | ppm              | ppm<br>(as Methane) |
| Methane                | (C1) | 0.05             | 0.05                |
| Ethane                 | (C2) | 0.03             | 0.06                |
| Propane                | (C3) | 0.02             | 0.06                |
| Butane                 | (C4) | 0.02             | 0.08                |
| Pentane                | (C5) | 0.02             | 0.10                |
| Hexane                 | (C6) | 0.02             | 0.12                |
| Total                  |      | 0.16             | 0.47                |
| Total<br>(non methane) |      | 0.11             | 0.42                |

# AIR EMISSIONS

COMPANY : DESTEC  
UNIT : LIVE OAK COGEN - TURBINE OUTLET  
DATE : 4-22-93  
PROJECT : 027-488

### SULFUR EMISSION RESULTS

| TIME      | TS, ppm | AVERAGE<br>MSCFH | AVERAGE<br>SCFH | FUEL<br>SCFM | SULFUR |         |
|-----------|---------|------------------|-----------------|--------------|--------|---------|
|           |         |                  |                 |              | LBS/HR | LBS/DAY |
| 1300-2145 | 1.30    | 403.55           | 403550          | 6726         | 0.044  | 1.06    |

EQUATION:

SCFM = SCFH ( 1/60 )

SULFUR LBS/HR = TS ppm \* 32 \* SCFM \* 1.581 \* 10<sup>-7</sup>

MW SULFUR = 32



# ANALYSIS REPORT SHEET

## Sulfur Compounds by GC/FPD

Client: Petro Chem  
 Site: 027-488  
 Can #: Tedlar

Lab #: 31460-1  
 Date Sampled: 4-22-93  
 Date Analyzed: 4-24-93

| Compound          | MDL<br>ug/m3 | Concentration<br>ug/m3 | Concentration<br>ppbv |
|-------------------|--------------|------------------------|-----------------------|
| Hydrogen Sulfide  | 77.0         | 1300                   | 960                   |
| Carbonyl Sulfide  | 77.0         | 2100                   | 870                   |
| Methyl Mercaptan  | 77.0         | not detected           | not detected          |
| Dimethyl Sulfide  | 77.0         | not detected           | not detected          |
| Carbon Disulfide  | 38.5         | not detected           | not detected          |
| Total Sulfur, H2S |              |                        | 1300                  |

# ATIVE ACCURACY

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

ANALYZER NOx

# RELATIVE ACCURACY RESULTS

PPMvd

| RUN #   | REFERENCE<br>METHOD | CEM<br>DATA | DIFFERENCE |
|---------|---------------------|-------------|------------|
| 1       | 2.44                | 2.63        | -0.19      |
| 2       | 2.57                | 2.33        | 0.24       |
| 3       | 2.58                | 2.33        | 0.25       |
| 4       | 2.56                | 2.47        | 0.09       |
| 5       | 2.65                | 2.50        | 0.15       |
| 6       | 2.50                | 2.47        | 0.03       |
| 7       | 2.61                | 2.47        | 0.14       |
| 8       | 2.82                | 2.83        | -0.01      |
| 9       | 2.77                | 2.53        | 0.24       |
| 10      | 2.35                | 2.37        | -0.02      |
| 11      | 2.43                | 2.33        | 0.10       |
| 12      | 2.31                | 2.63        | -0.32      |
| AVERAGE | 2.55                | 2.49        | 0.06       |

## RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD

$t$  = 2.201  
 .975

STANDARD DEVIATION = 0.18

CONFIDENCE COEFFICIENT = 0.11

REFERENCE METHOD = 2.55

RELATIVE ACCURACY = 6.65

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

ANALYZER CO

# RELATIVE ACCURACY RESULTS

PPMvd

| RUN #   | REFERENCE<br>METHOD | CEM<br>DATA | DIFFERENCE |        |
|---------|---------------------|-------------|------------|--------|
| 1 *     | 2.80                | 3.27        | -0.47      |        |
| 2       | 2.63                | 2.66        | -0.03      |        |
| 3       | 2.71                | 2.66        | 0.05       |        |
| 4       | 2.66                | 2.90        | -0.24      |        |
| 5       | 2.54                | 2.60        | -0.06      |        |
| 6       | 2.58                | 2.47        | 0.11       |        |
| 7       | 2.59                | 2.53        | 0.06       |        |
| 8 *     | 2.51                | 3.10        | -0.59      |        |
| 9       | 2.67                | 2.50        | 0.17       |        |
| 10      | 2.75                | 2.63        | 0.12       |        |
| 11      | 2.80                | 2.70        | 0.10       |        |
| 12      | 2.76                | 3.07        | -0.31      |        |
| AVERAGE |                     | 2.669       | 2.672      | -0.003 |

## RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD

$t$   
 .975 = 2.262

STANDARD DEVIATION = 0.16

CONFIDENCE COEFFICIENT = 0.11

REFERENCE METHOD = 2.67

RELATIVE ACCURACY = 4.39

\* Runs 1 & 8 were excluded from all averages and calculations.

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

ANALYZER O2

# RELATIVE ACCURACY RESULTS

PPMvd

| RUN #   | REFERENCE<br>METHOD | CEM<br>DATA | DIFFERENCE |      |
|---------|---------------------|-------------|------------|------|
| 1       | 15.46               | 15.50       | -0.04      |      |
| 2       | 15.53               | 15.40       | 0.13       |      |
| 3       | 15.53               | 15.40       | 0.13       |      |
| 4       | 15.69               | 15.40       | 0.29       |      |
| 5       | 15.55               | 15.40       | 0.15       |      |
| 6       | 15.48               | 15.40       | 0.08       |      |
| 7       | 15.48               | 15.40       | 0.08       |      |
| 8       | 15.53               | 15.40       | 0.13       |      |
| 9       | 15.58               | 15.40       | 0.18       |      |
| 10      | 15.56               | 15.40       | 0.16       |      |
| 11      | 15.52               | 15.40       | 0.12       |      |
| 12      | 15.51               | 15.40       | 0.11       |      |
| AVERAGE |                     | 15.54       | 15.41      | 0.13 |

## RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD

$t$   
 .975 = 2.201

STANDARD DEVIATION = 0.08

CONFIDENCE COEFFICIENT = 0.05

REFERENCE METHOD = 15.54

RELATIVE ACCURACY = 1.13

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

# PCES REFERENCE METHOD SUMMARY

| RUN #   | TIME      | %O2   | NOx  |                 |        | CO   |                 |        |
|---------|-----------|-------|------|-----------------|--------|------|-----------------|--------|
|         |           |       | ppm  | ppm @<br>15% O2 | lbs/hr | ppm  | ppm @<br>15% O2 | lbs/hr |
| 1       | 1300-1330 | 15.46 | 2.44 | 2.65            | 4.09   | 2.80 | 3.04            | 2.86   |
| 2       | 1345-1415 | 15.53 | 2.57 | 2.83            | 4.32   | 2.63 | 2.89            | 2.68   |
| 3       | 1430-1500 | 15.53 | 2.58 | 2.84            | 4.33   | 2.71 | 2.98            | 2.77   |
| 4       | 1515-1545 | 15.69 | 2.56 | 2.90            | 4.29   | 2.66 | 3.01            | 2.72   |
| 5       | 1600-1630 | 15.55 | 2.65 | 2.92            | 4.44   | 2.54 | 2.81            | 2.60   |
| 6       | 1645-1715 | 15.48 | 2.50 | 2.72            | 4.19   | 2.58 | 2.80            | 2.63   |
| 7       | 1730-1800 | 15.48 | 2.61 | 2.84            | 4.39   | 2.59 | 2.81            | 2.64   |
| 8       | 1815-1845 | 15.53 | 2.82 | 3.10            | 4.74   | 2.51 | 2.76            | 2.57   |
| 9       | 1900-1930 | 15.58 | 2.77 | 3.07            | 4.65   | 2.67 | 2.95            | 2.72   |
| 10      | 1945-2015 | 15.56 | 2.35 | 2.60            | 3.94   | 2.75 | 3.04            | 2.81   |
| 11      | 2030-2100 | 15.52 | 2.43 | 2.67            | 4.08   | 2.80 | 3.07            | 2.85   |
| 12      | 2115-2145 | 15.51 | 2.31 | 2.53            | 3.88   | 2.76 | 3.02            | 2.82   |
| AVERAGE |           | 15.54 | 2.55 | 2.81            | 4.28   | 2.67 | 2.93            | 2.72   |

COMPANY : DESTEC  
UNIT : LIVE OAK COGEN - TURBINE OUTLET  
DATE : 4-22-93  
PROJECT : 027-488

**DESTEC CEM DATA SUMMARY**

| <b>RUN #</b>   | <b>TIME</b> | <b>%O2</b>  | <b>NOx<br/>ppm</b> | <b>CO<br/>ppm</b> |
|----------------|-------------|-------------|--------------------|-------------------|
| 1              | 1300-1330   | 15.5        | 2.63               | 3.27              |
| 2              | 1345-1415   | 15.4        | 2.33               | 2.66              |
| 3              | 1430-1500   | 15.4        | 2.33               | 2.66              |
| 4              | 1515-1545   | 15.4        | 2.47               | 2.90              |
| 5              | 1600-1630   | 15.4        | 2.50               | 2.60              |
| 6              | 1645-1715   | 15.4        | 2.47               | 2.47              |
| 7              | 1730-1800   | 15.4        | 2.47               | 2.53              |
| 8              | 1815-1845   | 15.4        | 2.83               | 3.10              |
| 9              | 1900-1930   | 15.4        | 2.53               | 2.50              |
| 10             | 1945-2015   | 15.4        | 2.37               | 2.63              |
| 11             | 2030-2100   | 15.4        | 2.33               | 2.70              |
| 12             | 2115-2145   | 15.4        | 2.63               | 3.07              |
| <b>AVERAGE</b> |             | <b>15.4</b> | <b>2.49</b>        | <b>2.76</b>       |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #1  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          |                |         |        |              |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| TIME INTERVAL              |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 01:00 PM                   | - | 01:10 PM | 15.50          | 2.41    | 2.85   | 72.4         | 14.8   | 21.4  |
| 01:10 PM                   | - | 01:20 PM | 15.45          | 2.46    | 2.79   | 72.4         | 14.9   | 21.2  |
| 01:20 PM                   | - | 01:30 PM | 15.43          | 2.46    | 2.76   | 72.5         | 14.9   | 21.1  |
| Averages:                  |   |          | 15.46          | 2.44    | 2.80   | 72.4         | 14.9   | 21.2  |

| Calibration Data   |      |      |      |
|--------------------|------|------|------|
|                    | O2   | NOx  | CO   |
| INITIAL zero       | 10   | 10   | 10   |
| INITIAL span       | 94   | 51.1 | 90.2 |
| FINAL zero         | 10   | 10   | 10   |
| FINAL span         | 94.6 | 51.1 | 90.3 |
| ZERO DRIFT %/ppm   | 0.00 | 0.00 | 0.00 |
| CALIB. DRIFT %/ppm | 0.15 | 0.00 | 0.03 |
| ZERO DRIFT %fs     | 0.00 | 0.00 | 0.00 |
| CALIB. DRIFT %fs   | 0.60 | 0.00 | 0.10 |
| CAL GAS value      | 20.9 | 20.6 | 20.1 |
| FULL SCALE RANGE   | 25   | 50   | 25   |

|                                                 |       |      |        |        |       |
|-------------------------------------------------|-------|------|--------|--------|-------|
| DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE) |       |      |        |        |       |
|                                                 | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| NOx values:                                     | 15.46 | 2.44 | 8.03   | 2.65   | 4.09  |

|            |       |      |        |        |       |
|------------|-------|------|--------|--------|-------|
|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| CO values: | 15.46 | 2.80 | 9.22   | 3.04   | 2.86  |



COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #2  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          |                |         |        |              |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| TIME INTERVAL              |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 01:45 PM                   | - | 01:55 PM | 15.53          | 2.49    | 2.71   | 72.5         | 14.9   | 20.9  |
| 01:55 PM                   | - | 02:05 PM | 15.55          | 2.51    | 2.60   | 72.7         | 14.8   | 20.6  |
| 02:05 PM                   | - | 02:15 PM | 15.52          | 2.72    | 2.57   | 72.7         | 15.1   | 20.6  |
| Averages:                  |   |          | 15.53          | 2.57    | 2.63   | 72.6         | 14.9   | 20.7  |

| Calibration Data   |      |       |      |
|--------------------|------|-------|------|
|                    | O2   | NOx   | CO   |
| INITIAL zero       | 10   | 10    | 10   |
| INITIAL span       | 94   | 51.1  | 90.3 |
| FINAL zero         | 10   | 9.9   | 10.1 |
| FINAL span         | 94.4 | 50.8  | 90.6 |
| ZERO DRIFT %/ppm   | 0.00 | -0.05 | 0.03 |
| CALIB. DRIFT %/ppm | 0.10 | -0.15 | 0.08 |
| ZERO DRIFT %fs     | 0.00 | -0.10 | 0.10 |
| CALIB. DRIFT %fs   | 0.40 | -0.30 | 0.30 |
| CAL GAS value      | 20.9 | 20.6  | 20.1 |
| FULL SCALE RANGE   | 25   | 50    | 25   |

|                                                 |       |      |        |        |       |
|-------------------------------------------------|-------|------|--------|--------|-------|
| DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE) |       |      |        |        |       |
|                                                 | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| NOx values:                                     | 15.53 | 2.57 | 8.58   | 2.83   | 4.32  |

|            |       |      |        |        |       |
|------------|-------|------|--------|--------|-------|
|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| CO values: | 15.53 | 2.63 | 8.77   | 2.89   | 2.68  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #3  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          |                |         |        |              |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| TIME INTERVAL              |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 02:30 PM                   | - | 02:40 PM | 15.56          | 2.50    | 2.74   | 72.6         | 14.9   | 21.0  |
| 02:40 PM                   | - | 02:50 PM | 15.53          | 2.53    | 2.72   | 72.6         | 14.8   | 21.0  |
| 02:50 PM                   | - | 03:00 PM | 15.52          | 2.71    | 2.67   | 72.7         | 15.0   | 20.9  |
| Averages:                  |   |          | 15.53          | 2.58    | 2.71   | 72.6         | 14.9   | 21.0  |

| Calibration Data   |      |       |       |
|--------------------|------|-------|-------|
|                    | O2   | NOx   | CO    |
| INITIAL zero       | 10   | 10    | 10    |
| INITIAL span       | 94   | 51.1  | 90.2  |
| FINAL zero         | 10   | 10    | 9.9   |
| FINAL span         | 94.4 | 50.6  | 90.6  |
| ZERO DRIFT %/ppm   | 0.00 | 0.00  | -0.03 |
| CALIB. DRIFT %/ppm | 0.10 | -0.25 | 0.10  |
| ZERO DRIFT %fs     | 0.00 | 0.00  | -0.10 |
| CALIB. DRIFT %fs   | 0.40 | -0.50 | 0.40  |
| CAL GAS value      | 20.9 | 20.6  | 20.1  |
| FULL SCALE RANGE   | 25   | 50    | 25    |

DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE)

|             | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
|-------------|-------|------|--------|--------|-------|
| NOx values: | 15.53 | 2.58 | 8.61   | 2.84   | 4.33  |

|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
|------------|-------|------|--------|--------|-------|
| CO values: | 15.53 | 2.71 | 9.04   | 2.98   | 2.77  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #4  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          |                |         |        |              |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| TIME INTERVAL              |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 03:15 PM                   | - | 03:25 PM | 15.65          | 2.56    | 2.66   | 72.9         | 15.1   | 20.6  |
| 03:25 PM                   | - | 03:35 PM | 15.70          | 2.56    | 2.63   | 73.1         | 15.1   | 20.4  |
| 03:35 PM                   | - | 03:45 PM | 15.72          | 2.56    | 2.68   | 73.2         | 15.1   | 20.5  |
| Averages:                  |   |          | 15.69          | 2.56    | 2.66   | 73.1         | 15.1   | 20.5  |

| Calibration Data   |      |      |       |
|--------------------|------|------|-------|
|                    | O2   | NOx  | CO    |
| INITIAL zero       | 10   | 10   | 10    |
| INITIAL span       | 94   | 51.1 | 90.5  |
| FINAL zero         | 10   | 10   | 9.9   |
| FINAL span         | 94   | 51.1 | 90.3  |
| ZERO DRIFT %/ppm   | 0.00 | 0.00 | -0.02 |
| CALIB. DRIFT %/ppm | 0.00 | 0.00 | -0.05 |
| ZERO DRIFT %fs     | 0.00 | 0.00 | -0.10 |
| CALIB.DRIFT %fs    | 0.00 | 0.00 | -0.20 |
| CAL GAS value      | 20.9 | 20.6 | 20.1  |
| FULL SCALE RANGE   | 25   | 50   | 25    |

|                                                 |       |      |        |        |       |
|-------------------------------------------------|-------|------|--------|--------|-------|
| DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE) |       |      |        |        |       |
|                                                 | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| NOx values:                                     | 15.69 | 2.56 | 8.79   | 2.90   | 4.29  |

|            |       |      |        |        |       |
|------------|-------|------|--------|--------|-------|
|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| CO values: | 15.69 | 2.66 | 9.14   | 3.01   | 2.72  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #5  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          |                |         |        |              |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| TIME INTERVAL              |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 04:00 PM                   | - | 04:10 PM | 15.54          | 2.56    | 2.58   | 72.4         | 15.1   | 20.4  |
| 04:10 PM                   | - | 04:20 PM | 15.56          | 2.68    | 2.55   | 72.4         | 15.3   | 20.5  |
| 04:20 PM                   | - | 04:30 PM | 15.56          | 2.70    | 2.50   | 72.3         | 15.3   | 20.5  |
| Averages:                  |   |          | 15.55          | 2.65    | 2.54   | 72.4         | 15.2   | 20.5  |

| Calibration Data   |       |       |      |
|--------------------|-------|-------|------|
|                    | O2    | NOx   | CO   |
| INITIAL zero       | 10    | 10    | 10   |
| INITIAL span       | 94    | 51.1  | 90.3 |
| FINAL zero         | 10    | 10    | 10   |
| FINAL span         | 93.7  | 51    | 90.9 |
| ZERO DRIFT %/ppm   | 0.00  | 0.00  | 0.00 |
| CALIB. DRIFT %/ppm | -0.07 | -0.05 | 0.15 |
| ZERO DRIFT %fs     | 0.00  | 0.00  | 0.00 |
| CALIB.DRIFT %fs    | -0.30 | -0.10 | 0.60 |
| CAL GAS value      | 20.9  | 20.6  | 20.1 |
| FULL SCALE RANGE   | 25    | 50    | 25   |

|                                                 |       |      |        |        |       |
|-------------------------------------------------|-------|------|--------|--------|-------|
| DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE) |       |      |        |        |       |
|                                                 | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| NOx values:                                     | 15.55 | 2.65 | 8.87   | 2.92   | 4.44  |

|            |       |      |        |        |       |
|------------|-------|------|--------|--------|-------|
|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| CO values: | 15.55 | 2.54 | 8.52   | 2.81   | 2.60  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #6  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          |                |         |        |              |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| TIME INTERVAL              |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 04:45 PM                   | - | 04:55 PM | 15.44          | 2.55    | 2.57   | 72.0         | 15.1   | 20.3  |
| 04:55 PM                   | - | 05:05 PM | 15.48          | 2.48    | 2.63   | 72.0         | 15.0   | 20.6  |
| 05:05 PM                   | - | 05:15 PM | 15.51          | 2.46    | 2.54   | 72.0         | 15.0   | 20.3  |
| Averages:                  |   |          | 15.48          | 2.50    | 2.58   | 72.0         | 15.0   | 20.4  |

| Calibration Data   |       |      |      |
|--------------------|-------|------|------|
|                    | O2    | NOx  | CO   |
| INITIAL zero       | 10    | 10   | 10   |
| INITIAL span       | 94    | 51.1 | 90.3 |
| FINAL zero         | 10    | 10   | 10   |
| FINAL span         | 93.6  | 51.2 | 90.5 |
| ZERO DRIFT %/ppm   | 0.00  | 0.00 | 0.00 |
| CALIB. DRIFT %/ppm | -0.10 | 0.05 | 0.05 |
| ZERO DRIFT %fs     | 0.00  | 0.00 | 0.00 |
| CALIB. DRIFT %fs   | -0.40 | 0.10 | 0.20 |
| CAL GAS value      | 20.9  | 20.6 | 20.1 |
| FULL SCALE RANGE   | 25    | 50   | 25   |

DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE)

|             | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
|-------------|-------|------|--------|--------|-------|
| NOx values: | 15.48 | 2.50 | 8.24   | 2.72   | 4.19  |

|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
|------------|-------|------|--------|--------|-------|
| CO values: | 15.48 | 2.58 | 8.51   | 2.80   | 2.63  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #7  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          |                |         |        |              |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| TIME INTERVAL              |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 05:30 PM                   | - | 05:40 PM | 15.44          | 2.60    | 2.59   | 72.0         | 15.2   | 20.4  |
| 05:40 PM                   | - | 05:50 PM | 15.48          | 2.63    | 2.63   | 72.0         | 15.3   | 20.6  |
| 05:50 PM                   | - | 06:00 PM | 15.51          | 2.61    | 2.54   | 72.0         | 15.3   | 20.3  |
| Averages:                  |   |          | 15.48          | 2.61    | 2.59   | 72.0         | 15.3   | 20.4  |

| Calibration Data   |       |       |      |
|--------------------|-------|-------|------|
|                    | O2    | NOx   | CO   |
| INITIAL zero       | 10    | 10    | 10   |
| INITIAL span       | 94    | 51.1  | 90.3 |
| FINAL zero         | 10    | 10.3  | 10   |
| FINAL span         | 93.6  | 50.9  | 90.5 |
| ZERO DRIFT %/ppm   | 0.00  | 0.15  | 0.00 |
| CALIB. DRIFT %/ppm | -0.10 | -0.10 | 0.05 |
| ZERO DRIFT %fs     | 0.00  | 0.30  | 0.00 |
| CALIB.DRIFT %fs    | -0.40 | -0.20 | 0.20 |
| CAL GAS value      | 20.9  | 20.6  | 20.1 |
| FULL SCALE RANGE   | 25    | 50    | 25   |

|                                                 |       |      |        |        |       |
|-------------------------------------------------|-------|------|--------|--------|-------|
| DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE) |       |      |        |        |       |
|                                                 | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| NOx values:                                     | 15.48 | 2.61 | 8.63   | 2.84   | 4.39  |

|            |       |      |        |        |       |
|------------|-------|------|--------|--------|-------|
|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| CO values: | 15.48 | 2.59 | 8.54   | 2.81   | 2.64  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #8  
 NOx/CO/O2 DATA

| TIME INTERVAL |          | Stack Gas Measurement Data<br>CONCENTRATIONS |         |        | % FULL SCALE |        |       |
|---------------|----------|----------------------------------------------|---------|--------|--------------|--------|-------|
| BEGIN         | END      | O2:%                                         | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 06:15 PM      | 06:25 PM | 15.52                                        | 2.76    | 2.54   | 72.5         | 15.4   | 20.2  |
| 06:25 PM      | 06:35 PM | 15.56                                        | 2.81    | 2.53   | 72.9         | 15.3   | 20.3  |
| 06:35 PM      | 06:45 PM | 15.50                                        | 2.91    | 2.47   | 72.9         | 15.3   | 20.2  |
| Averages:     |          | 15.53                                        | 2.82    | 2.51   | 72.8         | 15.3   | 20.2  |

| Calibration Data   |      |       |      |
|--------------------|------|-------|------|
|                    | O2   | NOx   | CO   |
| INITIAL zero       | 10   | 10    | 10   |
| INITIAL span       | 94   | 51.1  | 90.3 |
| FINAL zero         | 10.2 | 9.9   | 10.1 |
| FINAL span         | 94.5 | 50.6  | 90.6 |
| ZERO DRIFT %/ppm   | 0.05 | -0.05 | 0.03 |
| CALIB. DRIFT %/ppm | 0.12 | -0.25 | 0.08 |
| ZERO DRIFT %fs     | 0.20 | -0.10 | 0.10 |
| CALIB. DRIFT %fs   | 0.50 | -0.50 | 0.30 |
| CAL GAS value      | 20.9 | 20.6  | 20.1 |
| FULL SCALE RANGE   | 25   | 50    | 25   |

|                                                 |       |      |        |        |       |
|-------------------------------------------------|-------|------|--------|--------|-------|
| DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE) |       |      |        |        |       |
|                                                 | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| NOx values:                                     | 15.53 | 2.82 | 9.41   | 3.10   | 4.74  |

|            |       |      |        |        |       |
|------------|-------|------|--------|--------|-------|
|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| CO values: | 15.53 | 2.51 | 8.37   | 2.76   | 2.57  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #9  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          |                |         |        |              |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| TIME INTERVAL              |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 07:00 PM                   | - | 07:10 PM | 15.58          | 2.84    | 2.57   | 72.6         | 15.6   | 20.3  |
| 07:10 PM                   | - | 07:20 PM | 15.58          | 2.76    | 2.74   | 72.6         | 15.3   | 21.1  |
| 07:20 PM                   | - | 07:30 PM | 15.58          | 2.72    | 2.69   | 72.6         | 15.1   | 21.0  |
| Averages:                  |   |          | 15.58          | 2.77    | 2.67   | 72.6         | 15.3   | 20.8  |

| Calibration Data   |      |       |      |
|--------------------|------|-------|------|
|                    | O2   | NOx   | CO   |
| INITIAL zero       | 10   | 10    | 10   |
| INITIAL span       | 94   | 51.1  | 90.3 |
| FINAL zero         | 10   | 9.9   | 10.1 |
| FINAL span         | 94   | 50.8  | 90.5 |
| ZERO DRIFT %/ppm   | 0.00 | -0.05 | 0.03 |
| CALIB. DRIFT %/ppm | 0.00 | -0.15 | 0.05 |
| ZERO DRIFT %fs     | 0.00 | -0.10 | 0.10 |
| CALIB.DRIFT %fs    | 0.00 | -0.30 | 0.20 |
| CAL GAS value      | 20.9 | 20.6  | 20.1 |
| FULL SCALE RANGE   | 25   | 50    | 25   |

DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE)

|             | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
|-------------|-------|------|--------|--------|-------|
| NOx values: | 15.58 | 2.77 | 9.32   | 3.07   | 4.65  |

|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
|------------|-------|------|--------|--------|-------|
| CO values: | 15.58 | 2.67 | 8.96   | 2.95   | 2.72  |



COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #10  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 07:45 PM                   | - | 07:55 PM | 15.55          | 2.38    | 2.79   | 72.5         | 14.8   | 21.2  |
| 07:55 PM                   | - | 08:05 PM | 15.56          | 2.38    | 2.77   | 72.6         | 14.9   | 21.2  |
| 08:05 PM                   | - | 08:15 PM | 15.58          | 2.28    | 2.69   | 72.7         | 14.8   | 21.0  |
| Averages:                  |   |          | 15.56          | 2.35    | 2.75   | 72.6         | 14.8   | 21.1  |

| Calibration Data   |      |       |      |
|--------------------|------|-------|------|
|                    | O2   | NOx   | CO   |
| INITIAL zero       | 10   | 10    | 10   |
| INITIAL span       | 94   | 51.1  | 90.3 |
| FINAL zero         | 10   | 9.9   | 10   |
| FINAL span         | 94.1 | 51.5  | 90.6 |
| ZERO DRIFT %/ppm   | 0.00 | -0.05 | 0.00 |
| CALIB. DRIFT %/ppm | 0.02 | 0.20  | 0.08 |
| ZERO DRIFT %fs     | 0.00 | -0.10 | 0.00 |
| CALIB.DRIFT %fs    | 0.10 | 0.40  | 0.30 |
| CAL GAS value      | 20.9 | 20.6  | 20.1 |
| FULL SCALE RANGE   | 25   | 50    | 25   |

|                                                 |       |      |        |        |       |
|-------------------------------------------------|-------|------|--------|--------|-------|
| DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE) |       |      |        |        |       |
|                                                 | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| NOx values:                                     | 15.56 | 2.35 | 7.87   | 2.60   | 3.94  |

|            |       |      |        |        |       |
|------------|-------|------|--------|--------|-------|
|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| CO values: | 15.56 | 2.75 | 9.22   | 3.04   | 2.81  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #11  
 NOx/CO/O2 DATA

| Stack Gas Measurement Data |   |          | CONCENTRATIONS |         |        | % FULL SCALE |        |       |
|----------------------------|---|----------|----------------|---------|--------|--------------|--------|-------|
| BEGIN                      | - | END      | O2:%           | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 08:30 PM                   | - | 08:40 PM | 15.54          | 2.40    | 2.85   | 72.4         | 14.9   | 21.4  |
| 08:40 PM                   | - | 08:50 PM | 15.51          | 2.48    | 2.75   | 72.2         | 15.3   | 21.1  |
| 08:50 PM                   | - | 09:00 PM | 15.51          | 2.41    | 2.79   | 72.1         | 15.4   | 21.3  |
| Averages:                  |   |          | 15.52          | 2.43    | 2.80   | 72.2         | 15.2   | 21.3  |

| Calibration Data   |       |      |      |
|--------------------|-------|------|------|
|                    | O2    | NOx  | CO   |
| INITIAL zero       | 10    | 10   | 10   |
| INITIAL span       | 94    | 51.1 | 90.3 |
| FINAL zero         | 10    | 10   | 10   |
| FINAL span         | 93.7  | 51.8 | 90.5 |
| ZERO DRIFT %/ppm   | 0.00  | 0.00 | 0.00 |
| CALIB. DRIFT %/ppm | -0.07 | 0.35 | 0.05 |
| ZERO DRIFT %fs     | 0.00  | 0.00 | 0.00 |
| CALIB.DRIFT %fs    | -0.30 | 0.70 | 0.20 |
| CAL GAS value      | 20.9  | 20.6 | 20.1 |
| FULL SCALE RANGE   | 25    | 50   | 25   |

|                                                 |       |      |        |        |       |
|-------------------------------------------------|-------|------|--------|--------|-------|
| DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE) |       |      |        |        |       |
|                                                 | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| NOx values:                                     | 15.52 | 2.43 | 8.09   | 2.67   | 4.08  |

|            |       |      |        |        |       |
|------------|-------|------|--------|--------|-------|
|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
| CO values: | 15.52 | 2.80 | 9.30   | 3.07   | 2.85  |

COMPANY : DESTEC  
 UNIT : LIVE OAK COGEN - TURBINE OUTLET  
 DATE : 4-22-93  
 PROJECT : 027-488

RUN #12  
 NOx/CO/O2 DATA

| TIME INTERVAL |          | Stack Gas Measurement Data<br>CONCENTRATIONS |         |        | % FULL SCALE |        |       |
|---------------|----------|----------------------------------------------|---------|--------|--------------|--------|-------|
| BEGIN         | END      | O2:%                                         | NOx:ppm | CO:ppm | O2%fs        | NOx%fs | CO%fs |
| 09:15 PM      | 09:25 PM | 15.49                                        | 2.55    | 2.72   | 72.2         | 15.2   | 20.9  |
| 09:25 PM      | 09:35 PM | 15.51                                        | 2.23    | 2.75   | 72.2         | 14.8   | 21.1  |
| 09:35 PM      | 09:45 PM | 15.54                                        | 2.16    | 2.81   | 72.2         | 14.9   | 21.4  |
| Averages:     |          | 15.51                                        | 2.31    | 2.76   | 72.2         | 15.0   | 21.1  |

| Calibration Data   |       |      |      |
|--------------------|-------|------|------|
|                    | O2    | NOx  | CO   |
| INITIAL zero       | 10    | 10   | 10   |
| INITIAL span       | 94    | 51.1 | 90.3 |
| FINAL zero         | 10    | 10   | 10   |
| FINAL span         | 93.7  | 51.8 | 90.5 |
| ZERO DRIFT %/ppm   | 0.00  | 0.00 | 0.00 |
| CALIB. DRIFT %/ppm | -0.07 | 0.35 | 0.05 |
| ZERO DRIFT %fs     | 0.00  | 0.00 | 0.00 |
| CALIB. DRIFT %fs   | -0.30 | 0.70 | 0.20 |
| CAL GAS value      | 20.9  | 20.6 | 20.1 |
| FULL SCALE RANGE   | 25    | 50   | 25   |

DSCFM = 230730 (AVERAGE OF PITOT TUBE TRAVERSE)

|             | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
|-------------|-------|------|--------|--------|-------|
| NOx values: | 15.51 | 2.31 | 7.69   | 2.53   | 3.88  |

|            | %O2   | ppm  | @ 3%O2 | @15%O2 | lb/hr |
|------------|-------|------|--------|--------|-------|
| CO values: | 15.51 | 2.76 | 9.18   | 3.02   | 2.82  |

# EMISSION FACTORS (lbs/MMBtu)


COMPANY : DESTEC  
UNIT : LIVE OAK COGEN - TURBINE OUTLET  
DATE : 4-22-93  
PROJECT : 027-488

NO<sub>x</sub>, LBS/MMBTU & EPA F FACTOR @ 60°F

| RUN     | PPM  | %O <sub>2</sub> | LBS/MMBTU |
|---------|------|-----------------|-----------|
| #1      | 2.44 | 15.46           | 0.00967   |
| #2      | 2.57 | 15.53           | 0.01032   |
| #3      | 2.58 | 15.53           | 0.01036   |
| #4      | 2.56 | 15.69           | 0.01059   |
| #5      | 2.65 | 15.55           | 0.01068   |
| #6      | 2.50 | 15.48           | 0.00995   |
| #7      | 2.61 | 15.48           | 0.01038   |
| #8      | 2.82 | 15.53           | 0.01132   |
| #9      | 2.77 | 15.58           | 0.01123   |
| #10     | 2.35 | 15.56           | 0.00949   |
| #11     | 2.43 | 15.52           | 0.00974   |
| #12     | 2.31 | 15.51           | 0.00924   |
| AVERAGE | 2.61 | 15.54           | 0.01050   |

EPA F FACTOR @ 60°F 8511

# EL GAS ANALYSIS



**PETRO  
CHEM  
ENVIRONMENTAL  
SERVICES, INC.**

3207 Antonino Avenue  
Bakersfield, California 93308  
(805) 327-7300  
FAX (805) 327-3459

COMPANY : DESTEC OPERATING COMPANY  
UNIT : LIVE OAK COGEN  
DATE : 4-22-93  
PROJECT : 027-488

DATE RECEIVED : APRIL 23,1993  
DATE ANALYZED : APRIL 23,1993  
DATE REPORTED: APRIL 26,1993

**FUEL GAS ANALYSIS**

| CONSTITUENT     | MOLE %  | WT. %   | CHONS Wt. % |       |
|-----------------|---------|---------|-------------|-------|
| CARBON DIOXIDE  | 1.414   | 3.573   | CARBON      | 72.45 |
| OXYGEN          | 0.009   | 0.016   | HYDROGEN    | 23.29 |
| NITROGEN        | 1.026   | 1.650   | OXYGEN      | 2.61  |
| CARBON MONOXIDE | 0.000   | 0.000   | NITROGEN    | 1.65  |
|                 |         |         | SULFUR      | 0.00  |
|                 |         |         | H/C         | 0.321 |
| METHANE         | 92.485  | 85.175  |             |       |
| ETHANE          | 4.220   | 7.284   |             |       |
| PROPANE         | 0.698   | 1.767   |             |       |
| ISOBUTANE       | 0.057   | 0.190   |             |       |
| N-BUTANE        | 0.053   | 0.178   |             |       |
| ISOPENTANE      | 0.013   | 0.054   |             |       |
| N-PENTANE       | 0.009   | 0.036   |             |       |
| HEXANES+        | 0.016   | 0.077   |             |       |
| TOTALS:         | 100.000 | 100.000 |             |       |

|                                           |          |
|-------------------------------------------|----------|
| SPECIFIC GRAVITY (AIR = 1)                | 0.6015   |
| SPECIFIC VOLUME, cu.ft./lb.               | 21.79    |
| GROSS CALORIFIC VALUE (DRY), BTU/cu.ft.   | 1033.87  |
| GROSS CALORIFIC VALUE (WET), BTU/cu.ft.   | 1013.55  |
| GROSS CALORIFIC VALUE (DRY), BTU/lb.      | 22524.78 |
| NET CALORIFIC VALUE (DRY), BTU/cu.ft.     | 932.43   |
| NET CALORIFIC VALUE (WET), BTU/cu.ft.     | 914.10   |
| COMPRESSABILITY FACTOR "Z" @ 60° F, 1 ATM | 0.9977   |
| EXPANSION FACTOR (DSCF/CF)                | 8.80     |

|                                      |      |
|--------------------------------------|------|
| EPA "F" FACTOR @ 68° F (DSCF/MM BTU) | 8641 |
| EPA "F" FACTOR @ 60° F (DSCF/MM BTU) | 8511 |

ASTM METHODS D-1945-81 & D-3588-91

  
Terry Rowles  
Laboratory Manager

## IS AND EQUATIONS



## **SAMPLING AND ANALYTIC PROCEDURES**

REF: EPA Code of Federal Regulations, Title 40, Part 60, Appendix A. EPA Method 1, 2, 3, & 4

### **EPA Method 1: Sampling and Velocity Traverses for Stationary Sources**

Prior to the source test a site assessment was performed in order to locate sample points for obtaining the best representative measurements of pollution concentrations and volumetric flow rates. EPA Method 1 takes into account duct area, straight run and cyclonic or stratified flow pattern.

### **EPA Method 2: Velocity and Volumetric Flow Rates**

A computer was used in selection of suitable sample/traverse points. The calibrated pitot tube was connected to a magnehelic gauge and leak checked. A temperature and  $\Delta P$  was recorded at each traverse point and a duct static pressure was measured and recorded. A volume flow rate was calculated from the measured required traverse points.

### **EPA Method 3: % CO<sub>2</sub>, % O<sub>2</sub>, Dry Molecular Weight**

Concurrent with each particulate sampling, an integrated gas sample was withdrawn from the summation of the traverse points through the train and collected at the outlet of the meter into a sample bag. The contents of the sample bladder were analyzed by Orsat for fixed gas composition.

### **EPA Method 4: Percent Water**

Tare weights of the charged individual impingers were recorded. After sampling, the final weights were recorded. Percent water was calculated from the weight of water collected and the dry gas volume sampled.

## EPA METHOD 2 STACK GAS VELOCITY AND VOLUMETRIC FLOWRATE

Average Stack Gas Velocity  
Eq. 2-6 & Eq. 2-9

$$P_g = \frac{\text{Static Pressure, } H_2O}{13.6}$$

$$P_s = P_{bar} + P_g$$

$$V_s = K_p C_p (\sqrt{\Delta P})_{avg} \sqrt{\frac{T_{s(avg)}}{P_s M_s}}$$

Average Stack Gas Dry Volumetric Flow Rate  
Eq. 2-10

$$Q_{std} = 60 (1 - B_{ws}) v_s A \left[ \frac{T_{std}}{T_{s(avg)}} \right] \left[ \frac{P_s}{P_{std}} \right]$$

$$\frac{Q_{std}}{MF} = \text{SCFM}$$

## EPA METHOD 3 DRY MOLECULAR WEIGHT OF STACK GAS Eq. 3-2

$$M_d = 0.44 (\% CO_2) + 0.320 (\% O_2) + 0.280 (\% N_2 + \% CO)$$

Wet Molecular Weight of Stack Gas

$$M_s = M_d (1 - B_{ws}) + 18 (B_{ws})$$

**EPA METHOD 4**  
**DETERMINATION OF MOISTURE CONTENT IN STACK GASES**

Volume of Water Vapor Condensed  
 Eq. 4-1

$$V_{wc (std)} = \frac{(V_f - V_i) \rho_w RT_{std}}{P_{std} M_w} = K_1 (V_f - V_i)$$

Where:  $K_1 = 0.04646 \frac{ft^3}{ml} @ 520^\circ R$

Volume of Water Vapor Collected in Silica Gel  
 Eq. 4-2

$$V_{wsg (std)} = \frac{(W_f - W_i) RT_{std}}{P_{std} M_w (453.6 \text{ g/lb})}$$

$$= K_2 (W_f - W_i)$$

Where:  $K_2 = 0.04651 \frac{ft^3}{g} @ 520^\circ R$

**EPA METHOD 4**  
**DETERMINATION OF MOISTURE CONTENT IN STACK GASES**  
 (continued)

Sample Gas Volume  
 Eq. 4-3

$$V_{m (std)} = V_m Y \left[ \frac{(P_m) (T_{std})}{(P_{std}) (T_m)} \right]$$

$$= K_3 Y \frac{V_m P_m}{T_m}$$

Where:  $K_3 = 17.38 \frac{^{\circ} R}{in. Hg} @ 520 ^{\circ} R$

Moisture Content  
 Eq. 4-4

$$B_{ws} = \frac{V_{wc (std)} + V_{wsg (std)}}{V_{wc (std)} + V_{wsg (std)} + V_m (std)}$$

$$B_{ws} \times 100 = \% H_2 O \text{ in gas stream}$$

$$MF = 1 - B_{ws}$$

## NOMENCLATURE

- A** = Cross-sectional area of stack (ft<sup>2</sup>)  
**A<sub>n</sub>** = Cross-sectional area of nozzle, (ft<sup>2</sup>)  
**B<sub>wa</sub>** = Proportion of water vapor, by volume, in the gas stream  
**C<sub>a</sub>** = Acetone blank residue concentration, (mg/g)  
**C<sub>p</sub>** = Pitot tube coefficient, dimensionless  
**C<sub>s</sub>** = Concentration of particulate matter in stack gas, dry basis corrected to standard conditions, (gr/dscf)  
**C<sub>SO2</sub>** = Concentration of sulfur dioxide dry basis corrected to standard conditions, (lb/dscf)  
**C<sub>H2SO4</sub>** = Sulfuric acid (including SO<sub>3</sub>) concentration, corrected to standard conditions, (lb/dscf)  
**ΔH** = Average pressure differential across the orifice meter, (in H<sub>2</sub>O)  
**K<sub>p</sub>** = Pitot tube constant,  $85.49 \frac{\text{ft}[(\text{lb/lb-mole})(\text{in Hg})]^{1/2}}{\text{sec}[(^{\circ}\text{R})(\text{in H}_2\text{O})]}$   
**L<sub>p</sub>** = Leakage rate observed during the post-test leak check, (cfm)  
**L<sub>a</sub>** = Maximum acceptable leakage rate, (0.02 cfm or 4% of average sampling rate, whichever is less)  
**L<sub>i</sub>** = Individual leakage rate observed during the leak check conducted prior to the <sup>n</sup>th component change, (cfm)  
**M<sub>a</sub>** = Mass of residue of acetone after evaporation, mg  
**M<sub>d</sub>** = Molecular weight of stack gas, dry basis, (lb/lb-mole)  
**M<sub>n</sub>** = Total weight of particulate matter collected, mg  
**M<sub>s</sub>** = Molecular weight of stack gas, wet basis, (lb/lb-mole)  
**M<sub>w</sub>** = Molecular weight of water, 18 lb/lb-mole  
**N** = Normality of barium perchlorate titrant, (milliequivalents/ml)  
**ΔP** = Velocity head of stack gas, (in H<sub>2</sub>O)  
**P<sub>bar</sub>** = Barometric pressure at measurement site (in Hg)  
**P<sub>g</sub>** = Stack static pressure, (in Hg)  
**P<sub>m</sub>** = Absolute pressure at the dry gas meter, (P<sub>bar</sub> + ΔH/13.6)  
**P<sub>s</sub>** = Absolute stack gas pressure, (inches Hg)  
**P<sub>(std)</sub>** = Standard absolute pressure, 29.92 in Hg  
**Q<sub>(std)</sub>** = Dry volumetric stack gas flow rate, standard conditions, (dscfm)  
**R** = Ideal gas constant, 21.85 (in Hg) (ft<sup>3</sup>)/(lb-mole)(°R)  
**t<sub>s</sub>** = Stack temperature, (°F)  
**T<sub>m</sub>** = Absolute temperature at meter, (°R)  
**T<sub>(std)</sub>** = Standard absolute temperature, (520°R)  
**T<sub>s</sub>** = Absolute stack temperature, (460° + t<sub>s</sub>)  
**V<sub>a</sub>** = Volume of sample aliquot titrated, (ml)  
**V<sub>ab</sub>** = Volume of acetone blank, ml  
**V<sub>m</sub>** = Dry gas volume measured by dry gas meter, (dcf)  
**V<sub>m(std)</sub>** = Dry gas volume measured by dry gas meter, corrected to standard conditions, (dscf)  
**V<sub>wc(std)</sub>** = Volume of water vapor condensed corrected to standard conditions, (scf)  
**V<sub>wsg(std)</sub>** = Volume of water vapor collected in silica gel corrected to standard conditions (scf)

## NOMENCLATURE

(continued)

|                  |   |                                                                                                                                           |
|------------------|---|-------------------------------------------------------------------------------------------------------------------------------------------|
| $V_{ic}$         | = | Volume of water vapor condensed in impingers and silica gel, (ml)                                                                         |
| $V_f$            | = | Final volume of condensed water, ml                                                                                                       |
| $V_i$            | = | Initial volume of condensed water, ml                                                                                                     |
| $v_s$            | = | Average stack gas velocity, (ft/sec)                                                                                                      |
| $V_{soln}$       | = | Total volume of solution in which the sulfur dioxide sample is contained (ml)                                                             |
| $V_t$            | = | Volume of barium perchlorate titrant used for the sample, (ml)                                                                            |
| $V_{tb}$         | = | Volume of barium perchlorate titrant used for the blank, (ml)                                                                             |
| $W_f$            | = | Final weight of silica gel or silica gel plus impinger, (g)                                                                               |
| $W_i$            | = | Initial weight of silica gel or silica gel plus impinger, (g)                                                                             |
| $Y$              | = | Dry gas meter calibration factor                                                                                                          |
| $\rho_w$         | = | Density of water, (0.002202 lb/ml @ 60°F)                                                                                                 |
| $\rho_a$         | = | Density of acetone, (g/ml)(see bottle label)                                                                                              |
| MF               | = | Moisture factor                                                                                                                           |
| %CO <sub>2</sub> | = | Percent CO <sub>2</sub> by volume (dry basis)                                                                                             |
| %O <sub>2</sub>  | = | Percent O <sub>2</sub> by volume (dry basis)                                                                                              |
| %CO              | = | Percent CO by volume (dry basis)                                                                                                          |
| %N <sub>2</sub>  | = | Percent N <sub>2</sub> by volume (dry basis)                                                                                              |
| 0.264            | = | Ratio of O <sub>2</sub> to N <sub>2</sub> in air v/v                                                                                      |
| 0.280            | = | Molecular weight of N <sub>2</sub> or CO, divided by 100                                                                                  |
| 0.320            | = | Molecular weight of O <sub>2</sub> , divided by 100                                                                                       |
| 0.440            | = | Molecular weight of CO <sub>2</sub> , divided by 100                                                                                      |
| 60               | = | Conversion factor, (sec/min)                                                                                                              |
| 18.0             | = | Molecular weight of water, (lb/lb-mole)                                                                                                   |
| 32.03            | = | Equivalent weight of sulfur dioxide                                                                                                       |
| $\theta$         | = | Total sampling time (min)                                                                                                                 |
| $\theta_i$       | = | Sampling time interval, between two successive component changes, beginning with the interval between the first and second changes, (min) |
| $\theta_1$       | = | Sampling time interval, from the run beginning until first component change, (min)                                                        |
| $\theta_p$       | = | Sampling time interval, from the final (n <sup>th</sup> ) component change until the end of the sampling run, (min)                       |

## **CONTINUOUS EMISSION MONITORING SYSTEM (CEMS)**

Reference: Manual of Procedures; ST-13A, ST-19A, Jan 1982, State of California, Air Resources Board, Test Methods 1-100, June 1979.  
EPA CFR Title 40, Pt. 60, Appendix A, Method 3A, 6C, 7E, & 10.

### **Instrument Summary**

A constant sample of flue gas was extracted, dried, filtered and delivered to an instrument manifold system for distribution to one or more analyzers. Instrument results are recorded on an analog strip chart recorder. System calibration checks are performed as well as calibration checks at the beginning and end of each test run. Final data reduction includes zero and calibration drift corrections.

### **Sample Conditioning System**

Consists of a borosilicate glass tube or 316 grade stainless steel probe fitted with a cindered stainless steel or pyrex glass wool particulate filter. The probe is fitted with a teflon (TFE) sample line which connects to a water condensation system located at the source. The condensation system consists of three 500-ml short stem glass impingers connected in a series, immersed in an ice bath. The gas is delivered to the instrument trailer with a teflon line (3/8" O.D.) through an in-line Balston particulate filter drawn by a teflon-coated diaphragm pump. The sample system is leak checked prior to sampling by plugging the end of the sample probe and adjusting the sample pump to its maximum rate (approximately 22" Hg). The manifold is by-passed and the leak rate monitored through a gas meter or low range flow meter.

### **Manifold System**

Sample gas is delivered to each analyzer through a five way valve and regulated with a needle valve flow meter. Manifold pressure is controlled by a back pressure regulator which is typically set at three psi. Zero gas ( $N_2$ ) and calibrated gases are delivered to the analyzers using the same five way valve and flow meter. All manifold parts are glass, stainless steel, or teflon materials.

### **Analog Strip Chart Data Reduction**

Analog recordings consists of averaged time increments as shown on the data pages (typically 5, 10, or 20 minute increments). Data for each increment was recorded at an average percent of full scale. The readings were then compared with the zero and calibration readings for calculation of the average concentration for each time increment. Any deviation of the zero and calibration readings from the start to the end of a test period was corrected by calculating apparent zero and calibration readings for the mid-point of each time increment. The average concentrations were then calculated from the sample readings and the apparent zero and span readings.

## **SOURCE TEST PROCEDURE BAAQMD ST-1B AMMONIA, INTEGRATED SAMPLING**

### **1. Applicability**

- 1.1 This method is used to quantify emissions of ammonia.

### **2. Principle**

- 2.1 Sample gas is drawn through a solution of 0.1 N hydrochloric acid which absorbs the ammonia. The ammonia is then analyzed according to Analytical Procedure EPA 350.3.

### **3. Range**

- 3.1 The minimum measurable concentration of ammonia is 1 ppm at the sample volume specified in this procedure.
- 3.2 Elevated concentrations of ammonia may be determined by increasing the concentration of the absorbing reagent, hydrochloric acid solution. The concentration of reagent to be used may be determined by stoichiometry, allowing a 50% excess.

### **4. Interference**

- 4.1 See EPA Method 350.3.

### **5. Apparatus**

- 5.1 Probe - The probe is constructed of borosilicate glass tubing fitted with a glass wool filter in the nozzle.
- 5.2 Condensers - Use three Greenberg-Smith impingers as absorber/condensers. The final impinger has a thermometer attached to the inlet stem.
- 5.3 Cooling system - Use an ice bath to contain the impingers.
- 5.4 Sample pump - Use a leak-free vacuum pump capable of maintaining a 14.3 liter/min (0.5 CFM) flow rate at 15 inches of mercury. The pump must have a flow control valve and vacuum gauge attached to the inlet.
- 5.5 Silica gel tube - Use approximately 500cc of silica gel (with a Drierite indicator) to insure that the gas entering the dry test meter is dry.
- 5.6 Dry test meter - Use a dry gas test meter accurate within + 2% of the true volume and equipped with a thermometer to measure the outlet temperature.



**SOURCE TEST PROCEDURE BAAQMD ST-1B**  
**AMMONIA, INTEGRATED SAMPLING**  
(continued)

5.7 Connections - Use Teflon tubing in making all connections that come in contact with the sample. Vinyl tubing is acceptable for all other connections.

5.8 Barometer - Use a barometer that is accurate to within + 0.2 inches of mercury.

5.9 Rotameter - Use a calibrated rotameter to measure the sampling rate.

**6. Reagents**

6.1 Hydrochloric acid, 0.1N. Dissolve 7.30 ml concentrated HCl in sufficient water to make a 1.0 liter solution.

**7. Pre-test Procedures**

7.1 Add 100 ml of the HCl solution to each of two impingers.

7.2 Stopper the impingers.

7.3 Retain 100 ml of the HCl solution to analyze as a blank.

7.4 Assemble the sampling train as shown in Figure IV-4.

7.5 Leak-test the sampling train by starting the pump, plugging the probe, and adjusting the pump inlet vacuum to 10 inches Hg. The leak rate must not exceed 0.6 liter/min (0.02 CFM) through the dry test meter. Before stopping the pump, carefully release the plug in the sample probe to avoid back flow of the impinger solution.

7.6 Record the initial dry test meter reading and barometric pressure on the sampling data sheet.

7.7 If there is evidence of concentration stratification, select the sampling traverse points according to ST-18. Otherwise, sample at a single point.

**8. Sampling**

8.1 Each test run shall be of thirty minute duration when testing emissions from continuous operations. Each test run at batch process operation shall be for 90% of the batch time or thirty minutes, whichever is less.

8.2 Position the probe at the sampling point and start the pump.

8.3 Sample at a constant rate of 14.3 liter/min (0.5 CEM) during the test as determined by the rotameter. Use the rotameter only to establish the initial sampling rate. Then remove it from the system.

# **SOURCE TEST PROCEDURE BAAQMD ST-1B** **AMMONIA, INTEGRATED SAMPLING** (continued)

8.4 Record the following information at five minute intervals.

- A. Dry test meter temperature
- B. Impinger outlet temperature
- C. Dry test meter volume

8.5 Add ice as necessary to maintain impinger temperatures at 7 °C (45 °F) or less.

8.6 At the conclusion of each run, stop the pump, remove the probe from the stack, record the final meter reading. Point the probe upward and purge the sample train with ambient air.


8.7 Take three consecutive samples.

## 9. Post-test Procedures

9.1 Stopper the impingers until they are analyzed.

9.2 Individually analyze the hydrochloric acid solutions and blank for total ammonia content according to analytical procedure Lab 1.

## Sampling Diagram



**NITROGEN, AMMONIA**  
**Method 350.3**  
**Potentiometric, Ion Selective Electrode**

**1. Scope and Application**

- 1.1 This method is applicable to the measurement of ammonia-nitrogen in drinking, surface and saline waters, domestic and industrial wastes.
- 1.2 This method covers the range from 0.03 to 1400 mg NH<sub>3</sub>-N/li. Color and turbidity have no effect on the measurements, thus, distillation may not be necessary.

**2. Summary of Method**

- 2.1 The ammonia is determined potentiometrically using an ion selective ammonia electrode and a pH meter having an expanded millivolt scale or specific ion meter.
- 2.2 The ammonia electrode uses a hydrophobic gas-permeable membrane to separate the sample solution from an ammonia chloride internal solution. Ammonia in the sample diffuses through the membrane and alters the pH of the internal solution, which is sensed by a pH electrode. The constant level of chloride in the internal solution is sensed by a chloride selective ion electrode which acts as the reference electrode.

**3. Sample Handling and Preservation**

- 3.1 Samples may be preserved with 2 ml of conc. H<sub>2</sub>SO<sub>4</sub> per liter and stored at 4°C.

**4. Interferences**

- 4.1 Volatile amines act as a positive interference.
- 4.2 Mercury interferes by forming a strong complex with ammonia. Thus the samples cannot be preserved with mercuric chloride.

**5. Apparatus**

- 5.1 Electrometer (pH meter) with expanded mV scale or a specific ion meter.
- 5.2 Ammonia selective electrode, such as Orion Model 95-10 or EIL Model 8002-2.
- 5.3 Magnetic stirrer, thermally insulated, and Teflon-coated stirring bar.

**NITROGEN, AMMONIA**  
**Method 350.3**  
(continued)

**6. Reagents**

- 6.1 Distilled water: Special precautions must be taken to insure that the distilled water is free of ammonia. This is accomplished by passing distilled water through an ion exchange column containing a strongly acidic cation exchange resin mixed with a strongly basic anion exchange resin.
- 6.2 Sodium hydroxide, 10N: Dissolve 400 g of sodium hydroxide in 800 ml of distilled water. Cool and dilute to 1 liter with distilled water (6.1)
- 6.3 Ammonia chloride, stock solution: 1.0 ml = 1.0 mg  $\text{NH}_3\text{-N}$ . Dissolve 3.819 g  $\text{NH}_4\text{Cl}$  in water and bring to volume in a 1 liter volumetric flask using distilled water (6.1)
- 6.4 Ammonia chloride, standard solution: 1.0 ml = 0.01 mg  $\text{NH}_3\text{-N}$ . Dilute 10.0 ml of the stock solution (6.3) to 1 liter with distilled water (6.1) in a volumetric flask.

NOTE 1: When analyzing saline waters, standards must be made up in synthetic ocean water (SOW); found in Nitrogen, Ammonia: Calorimetric, Automated Phenate Method (350.1)

**7. Procedures**

- 7.1 Preparation of standards: Prepare a series of standard solutions covering the concentration range of the samples by diluting either the stock or standard solutions of ammonium chloride.
- 7.2 Calibration of electrometer: Place 100 ml of each standard solution in clean 150 ml beakers. Immerse electrode into standard of lowest concentration and add 1 ml of 10N sodium hydroxide solution while mixing. Keep electrode in the solution until a stable reading is obtained.
- 7.3 Repeat this procedure with the remaining standards, going from lowest to highest concentration. Using semilogarithmic graph paper, plot the concentration of ammonia in mg  $\text{NH}_3\text{-N/l.}$  on the log axis vs. the electrode potential developed in the standard on the linear axis, starting with the lowest concentration at the bottom of the scale.
- 7.4 Calibration of a specific ion meter: Follow the directions of the manufacturer for the operation of the instrument.

**NITROGEN, AMMONIA**  
**Method 350.3**  
(continued)

7.5 Sample measurement: Follow the procedure in (7.2) for 100 ml of sample in 150 ml beakers. Record the stabilized potential of each unknown sample and convert the potential reading to the ammonia concentration using the standard curve. If a specific ion meter is used, read the ammonia level directly in mg  $\text{NH}_3\text{-N/l}$ .

8. Precision and Accuracy

8.1 In a single laboratory (EMSL), using surface water samples at concentrations of 1.00, 0.77, 0.19 and 0.13 mg  $\text{NH}_3\text{-N/l}$ , standard deviations were +0.038, +0.017, +0.007 and +0.003 respectively.

8.2 In a single laboratory (EMSL), using surface water samples at concentrations of 0.19 and 0.13 mg  $\text{NH}_3\text{-N/l}$ , recoveries were 96% and 91%, respectively.

**BIBLIOGRAPHY**

1. Booth, R.L., and Thomas, R.F., "Selective Electrode Determination of Ammonia in Water and Wastes", *Envir. Sci. Technology*, 7, p. 523-526 (1973).
2. Banwart, W.L., Bremner, J.M., and Tabatabai, M.A., "Determination of Ammonia in Soil Extracts and Water Samples by an Ammonia Electrode", *Comm. Soil Sci. Plant.*, 3, p. 449 (1952).
3. Midgley, D., and Torrance, K., "The Determination of Ammonia in Condensed Steam and Boiler Feed-Water with a Potentiometric Ammonia Probe", *Analyst* 97, p. 626-633 (1972)

**RELATIVE ACCURACY**  
**Code of Federal Regulations, 40 CFR, Pt. 60, App. B, Spec. 2**

**Arithmetic Mean of the Differences,  $\bar{d}$**   
**Eq. 8.1**

Where:  $n$  = Number of data points

$$\bar{d} = \frac{1}{n} \sum_{i=1}^n d_i$$

**Standard deviation of the differences,  $S_d$**   
**Eq. 8.2**

$$S_d = \left( \frac{\sum_{i=1}^n d_i^2 - \frac{\left( \sum_{i=1}^n d_i \right)^2}{n}}{n-1} \right)^{1/2}$$

**Confidence Coefficient, CC**  
**Eq. 8.3**

$$CC = t_{0.975} \left( \frac{S_d}{\sqrt{n}} \right)$$

$t_{0.975}$  = t value Table (40 CFR, pg. 1043)

**Relative Accuracy, RA**  
**Eq. 8.4**

$$RA = \frac{\left| \bar{d} \right| + \left| CC \right|}{\overline{RM}} \times 100$$

Where:  $\left| \bar{d} \right|$  = Absolute value of the mean of differences (from Eq. 8.1)  
RM = Average from reference method

## HYDROCARBON EMISSIONS TESTING EPA METHOD 18 - FID ANALYSIS

### SAMPLING PROCEDURES

The sample was drawn via evacuated cannister through a stainless steel/teflon probe into a tedlar bag. Each sample bag was evacuated, and then filled.

### ANALYTICAL PROCEDURES

The contents of the tedlar bag was analyzed by gas chromatography. The gas chromatograph was calibrated with an appropriate standard for each carbon #, before and after each set of samples are analyzed. The sample is speciated by carbon #-C<sub>1</sub>, C<sub>2</sub>, C<sub>3</sub>, C<sub>4</sub>, C<sub>5</sub>, and C<sub>6+</sub> backflush.

### SYMBOL IDENTIFICATION

i = carbon #; i = 1 to 6+

s = refers to standard for that carbon #

Rx<sub>i</sub> = response factor for C<sub>i</sub>

MW = molecular weight - g/mole

DSCFM = Average volume flow rate of unit tested

### EQUATIONS

$$Rx_i = \frac{Area_{std}}{ppm_{std}}$$

$$Sample\ ppm_i = \frac{1}{Rx_i} \times Area_i$$

$$Sample\ ppm\ (as\ C_1) = Sample\ ppm \times \#\ of\ Carbons$$

$$\frac{lbs}{hr_i} = ppm_i \times MW_i \times DSCFM \times 1.581 \times 10^{-7}$$

$$Total\ non-methane\ \frac{lbs}{hr} = \sum \frac{6+}{2} \frac{lbs}{hr_i}$$

Note 1: If lbs/hr as methane is required, MW will equal 16.0 (MW of methane, CH<sub>4</sub>)

Note 2: # of carbons: ethane = 2, propane = 3, etc...

# APPENDIX I OPERATIONAL DATA (Supplied by Destec)





## APPENDIX II RAW DATA

COMPANY: Desiec  
 UNIT : Live Oak Cochen  
 DATE : 4.22.93  
 PROJECT : 027-488

### ON-SITE DATA

|                                                     | RUN #1    | RUN #2    | RUN #3    |
|-----------------------------------------------------|-----------|-----------|-----------|
| TIME:                                               | 1400-1454 | 1530-1626 | 1728-1816 |
| Vm, Dry sampled gas volume, dcf                     | 28.931    | 30.695    | 28.826    |
| Y, Meter calibration factor (Met# <u>1.009760</u> ) | 1.009760  | 1.009760  | 1.009760  |
| Pbar, Barometric Pressure, "Hg                      | 29.5      | 29.5      | 29.5      |
| Pstatic Stack static pressure, "Hg                  | -.37      | -.37      | -.37      |
| ΔH, Differential meter pressure, "H2O               | .57       | .57       | .57       |
| Tm, Meter temperature, °F                           | 75.3      | 72.3      | 74.1      |

| CONTENTS                | RUN #1     |       |        | RUN #2                 |       |        | RUN #3                 |       |        |
|-------------------------|------------|-------|--------|------------------------|-------|--------|------------------------|-------|--------|
|                         | FINAL      | TARE  | NET    | FINAL                  | TARE  | NET    | FINAL                  | TARE  | NET    |
| 0.1N HCL                | 692.2      | 553.7 | 138.5  | 711.6                  | 555.8 | 155.8  | 705.6                  | 555.8 | 149.8  |
| 0.1N HCL                | 593.2      | 591.5 | 1.7    | 626.1                  | 623.4 | 2.7    | 600.0                  | 597.6 | 2.4    |
| DRY                     | 497.3      | 496.5 | .8     | 485.1                  | 485.0 | .1     | 497.3                  | 496.5 | .8     |
| SG                      | 842.3      | 835.8 | 6.5    | 793.2                  | 786.6 | 6.6    | 848.3                  | 842.3 | 6.0    |
|                         |            |       |        |                        |       |        |                        |       |        |
| (LW)                    | (0.1N HCL) |       | (39.8) |                        |       | (43.1) |                        |       | (40.1) |
| Vic, volume of H2O, gms |            |       | 107.7  | 0.1N HCL rinse = 114.2 |       | 122.1  | 0.1N HCL rinse = 142.2 |       | 118.9  |
|                         |            |       |        |                        |       |        |                        |       |        |

0.1N HCL rinse = 149.5

|                                        | RUN #1 | RUN #2 | RUN #3 |
|----------------------------------------|--------|--------|--------|
| CO2, % Dry Volume                      | 3.1    | 3.0    | 3.1    |
| O2, % Dry Volume                       | 15.5   | 15.6   | 15.5   |
| N2, % Dry Volume                       |        |        |        |
| + Cp, Pitot Tube Coefficient (# _____) | .831   | .831   | .831   |
| ΔP, Avg P, "H2O                        | 1.130  | 0.952  | /      |
| Ts, Stack temperature, °F              | 271    | 270    | /      |
| As, Stack Area, sq.ft.                 | 94.31  | 94.31  | 94.31  |
| Ds, Stack diameter, inches             | 131.5  | 131.5  | 131.5  |
| Dn, Nozzle diameter, inches            | /      | /      | /      |
| Dur, Sampling time, min                | 48     | 48     | 48     |
| % ISO Mini iso                         |        |        |        |

Filter # \_\_\_\_\_  
 Filter tare weights, gms \_\_\_\_\_

Additional Comments: \_\_\_\_\_

METHOD 1-4/ST-1B RUN # 1

| COMPANY: <u>Destec</u><br>UNIT: <u>Live OIL</u><br>DATE: <u>4/22/93</u><br>PROJECT: <u>027-488</u><br>TECH: <u>SAD</u><br>PUMP #: <u></u><br>METER BOX#: <u>1004</u><br>METER COEFF: <u>1.009760</u><br>PROBE #: <u>KS' initial Cp:</u> |                  |               |                       | PRE / POST TEST LEAK CHECK<br>LEAK RATE: <u>2.02</u> cfm<br>VACUUM: <u>10</u> "Hg |                                |            |                                 | AMBIENT TEMP, °F: <u>70</u><br>Pbar: <u></u><br>STATIC PRESSURE ("Hg): <u></u><br>ASSUMED MOISTURE, %: <u></u><br>NOZZLE ID#: <u></u><br>AVG. CALIB. NOZZLE DIAM. ("): <u></u><br>PROBE LINER MATERIAL: <u></u><br>FILTER #: <u></u> |            |                 |                                                   |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|---------------|-----------------------|-----------------------------------------------------------------------------------|--------------------------------|------------|---------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|-----------------|---------------------------------------------------|
| DUCT DIAM. ("): <u>131.5</u>                                                                                                                                                                                                            |                  |               |                       |                                                                                   |                                |            |                                 |                                                                                                                                                                                                                                      |            |                 |                                                   |
| TRAVERSE<br>PT. NUMBER                                                                                                                                                                                                                  | TIME<br>(e) min. | VACUUM<br>"Hg | STACK TEMP<br>(Ts) °F | VELOCITY<br>HEAD<br>( $\Delta$ Ps)/in. H2O                                        | PRESSURE<br>DIFFERENTIAL, "H2O |            | GAS SAMPLE<br>VOLUME<br>(cu.ft) | GAS SAMPLE TEMP.                                                                                                                                                                                                                     |            | TEMP. °F<br>BOX | TEMP OF GAS<br>EXIT CONDENSER<br>OR LAST IMPINGER |
|                                                                                                                                                                                                                                         |                  |               |                       |                                                                                   | RATE                           | $\Delta$ H |                                 | INLET, °F                                                                                                                                                                                                                            | OUTLET, °F |                 |                                                   |
| 8                                                                                                                                                                                                                                       | 1400             | 2             | 270                   | 1.75                                                                              | 0.60                           | 0.57       | 208.000                         | 79                                                                                                                                                                                                                                   | 67         |                 | 60                                                |
| 7                                                                                                                                                                                                                                       | 03               | 2             | 271                   | 1.60                                                                              | 0.6                            | 0.57       | 209.8                           | 79                                                                                                                                                                                                                                   | 66         |                 | 61                                                |
| 6                                                                                                                                                                                                                                       | 06               | 2             | 270                   | 1.25                                                                              | 0.6                            | 0.57       | 211.6                           | 81                                                                                                                                                                                                                                   | 68         |                 | 61                                                |
| 5                                                                                                                                                                                                                                       | 09               | 2             | 274                   | 1.0                                                                               | 0.6                            | 0.57       | 213.4                           | 82                                                                                                                                                                                                                                   | 68         |                 | 61                                                |
| 4                                                                                                                                                                                                                                       | 12               | 2             | 269                   | 0.75                                                                              | 0.6                            | 0.57       | 215.2                           | 83                                                                                                                                                                                                                                   | 69         |                 | 61                                                |
| 3                                                                                                                                                                                                                                       | 15               | 2             | 267                   | 0.90                                                                              | 0.6                            | 0.57       | 217.0                           | 83                                                                                                                                                                                                                                   | 70         |                 | 61                                                |
| 2                                                                                                                                                                                                                                       | 18               | 2             | 267                   | 0.90                                                                              | 0.6                            | 0.57       | 218.8                           | 85                                                                                                                                                                                                                                   | 70         |                 | 61                                                |
| 1                                                                                                                                                                                                                                       | 21               | 2             | 266                   | 0.90                                                                              | 0.6                            | 0.57       | 220.6                           | 86                                                                                                                                                                                                                                   | 70         |                 | 61                                                |
| PC                                                                                                                                                                                                                                      | 14:24            |               |                       |                                                                                   |                                |            | 222.481                         |                                                                                                                                                                                                                                      |            |                 |                                                   |
| AVG (75.4)                                                                                                                                                                                                                              |                  |               |                       |                                                                                   |                                |            |                                 |                                                                                                                                                                                                                                      |            |                 |                                                   |

METHOD 1-4 | ST-1B RUN # 1

| COMPANY: <u>Destec</u><br>UNIT: <u>Live Oak</u><br>DATE: <u>4/22/93</u><br>PROJECT: <u>027-488</u><br>TECH: <u>SAD</u><br>PUMP #: _____<br>METER BOX#: <u>1004</u><br>METER COEFF: <u>1,009760</u><br>PROBE #: <u>K' Initial</u> Cp: _____ |                  |               |                       | PRE / POST TEST LEAK CHECK<br>LEAK RATE: <u>&lt; 0.005</u> cfm<br>VACUUM: <u>5</u> "Hg |                                |            |                                  | AMBIENT TEMP, °F: _____<br>Pbar: _____<br>STATIC PRESSURE ("Hg): _____<br>ASSUMED MOISTURE, %: _____<br>NOZZLE ID#: _____<br>AVG. CALIB. NOZZLE DIAM. ("): _____<br>PROBE LINER MATERIAL: _____<br>FILTER #: _____<br>DUCT DIAM. ("): _____ |            |               |       |                                                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|---------------|-----------------------|----------------------------------------------------------------------------------------|--------------------------------|------------|----------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|---------------|-------|---------------------------------------------------|
| TRAVERSE<br>PT. NUMBER                                                                                                                                                                                                                     | TIME<br>(s) min. | VACUUM<br>"Hg | STACK TEMP<br>(Ts) °F | VELOCITY<br>HEAD<br>( $\Delta$ Ps) in. H2O                                             | PRESSURE<br>DIFFERENTIAL, "H2O |            | GAS SAMPLE<br>VOLUME<br>(cu. ft) | GAS SAMPLE TEMP.                                                                                                                                                                                                                            |            | FILTER HOLDER |       | TEMP OF GAS<br>EXIT CONDENSER<br>OR LAST IMPINGER |
|                                                                                                                                                                                                                                            |                  |               |                       |                                                                                        | RATE                           | $\Delta$ H |                                  | AT DRY GAS METER<br>INLET, °F                                                                                                                                                                                                               | OUTLET, °F | TEMP, °F      | PROBE |                                                   |
| 6                                                                                                                                                                                                                                          | 1430             | 2             | 272                   | 1.30                                                                                   | 0.6                            | 0.57       | 222.481                          | 78                                                                                                                                                                                                                                          | 70         |               |       | 61                                                |
| 7                                                                                                                                                                                                                                          | 33               | 2             | 273                   | 1.15                                                                                   | 0.6                            | 0.57       | 224.2                            | 80                                                                                                                                                                                                                                          | 70         |               |       |                                                   |
| 6                                                                                                                                                                                                                                          | 36               | 2             | 273                   | 1.05                                                                                   | 0.6                            | 0.57       | 226.0                            | 81                                                                                                                                                                                                                                          | 70         |               |       | 63                                                |
| 5                                                                                                                                                                                                                                          | 39               | 2             | 275                   | 1.0                                                                                    | 0.6                            | 0.57       | 227.8                            | 82                                                                                                                                                                                                                                          | 70         |               |       |                                                   |
| 4                                                                                                                                                                                                                                          | 42               | 2             | 273                   | 1.0                                                                                    | 0.6                            | 0.57       | 229.6                            | 82                                                                                                                                                                                                                                          | 70         |               |       | 63                                                |
| 3                                                                                                                                                                                                                                          | 45               | 2             | 273                   | 1.25                                                                                   | 0.6                            | 0.57       | 231.4                            | 81                                                                                                                                                                                                                                          | 69         |               |       |                                                   |
| 2                                                                                                                                                                                                                                          | 48               | 2             | 273                   | 1.4                                                                                    | 0.6                            | 0.57       | 233.2                            | 81                                                                                                                                                                                                                                          | 69         |               |       | 63                                                |
| 1                                                                                                                                                                                                                                          | 51               | 2             | 273                   | 1.10                                                                                   | 0.6                            | 0.57       | 235.0                            | 81                                                                                                                                                                                                                                          | 68         |               |       |                                                   |
| EUR                                                                                                                                                                                                                                        | 14:54            |               |                       |                                                                                        |                                |            | 236.931                          |                                                                                                                                                                                                                                             |            |               |       |                                                   |
| AVG                                                                                                                                                                                                                                        | 48 min           |               | 271                   | 1.130                                                                                  |                                | 0.57       | 236.931                          |                                                                                                                                                                                                                                             |            |               |       | (75.3)                                            |

METHOD 1-4 / ST-1B RUN # 2

| COMPANY: <u>Destec</u><br>UNIT: <u>Live OAK</u><br>DATE: <u>4/22/93</u><br>PROJECT: <u>027-488</u><br>TECH: <u>SAC</u><br>PUMP #: _____<br>METER BOX#: <u>1004</u><br>METER COEFF: <u>1.006760</u> |               |            |                    | PRE / POST TEST LEAK CHECK<br>LEAK RATE: <u>&lt; 0.02</u> cfm<br>VACUUM: <u>7</u> "Hg |                             |      |                           | AMBIENT TEMP, °F: <u>65</u><br>Pbar: _____<br>STATIC PRESSURE ("Hg): _____<br>ASSUMED MOISTURE, %: _____<br>NOZZLE ID#: _____<br>AVG. CALIB. NOZZLE DIAM. ("): _____<br>PROBE LINER MATERIAL: _____<br>FILTER #: _____ |            |               |           |                                             |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|------------|--------------------|---------------------------------------------------------------------------------------|-----------------------------|------|---------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|---------------|-----------|---------------------------------------------|
| PROBE #: <u>15</u> Initial Cp: _____                                                                                                                                                               |               |            |                    | DUCT DIAM. ("): _____                                                                 |                             |      |                           | GAS SAMPLE TEMP.                                                                                                                                                                                                       |            |               |           |                                             |
| TRAVERSE PT. NUMBER                                                                                                                                                                                | TIME (s) min. | VACUUM "Hg | STACK TEMP (Ts) °F | VELOCITY HEAD (Δ Ps) in. H2O                                                          | PRESSURE DIFFERENTIAL, "H2O |      | GAS SAMPLE VOLUME (cu.ft) | GAS SAMPLE TEMP.                                                                                                                                                                                                       |            | FILTER HOLDER |           | TEMP OF GAS EXIT CONDENSER OR LAST IMPINGER |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       | RATE                        | Δ H  |                           | AT DRY GAS METER INLET, °F                                                                                                                                                                                             | OUTLET, °F | TEMP, °F      | PROBE BOX |                                             |
| 8                                                                                                                                                                                                  | 1530          | 2          | 270                | 1.25                                                                                  | 0.6                         | 0.57 | 237.505                   | 68                                                                                                                                                                                                                     | 66         |               |           | 61                                          |
| 7                                                                                                                                                                                                  | 33            | 2          | 273                | 1.0                                                                                   | 0.6                         | 0.57 | 239.3                     | 78                                                                                                                                                                                                                     | 66         |               |           | 61                                          |
| 6                                                                                                                                                                                                  | 36            | 2          | 271                | 1.0                                                                                   | 0.6                         | 0.57 | 241.1                     | 78                                                                                                                                                                                                                     | 66         |               |           | 61                                          |
| 5                                                                                                                                                                                                  | 39            | 2          | 272                | 1.15                                                                                  | 0.6                         | 0.57 | 243.9                     | 78                                                                                                                                                                                                                     | 66         |               |           | 64                                          |
| 4                                                                                                                                                                                                  | 42            | 2          | 271                | 0.9                                                                                   | 0.6                         | 0.57 | 245.7                     | 78                                                                                                                                                                                                                     | 66         |               |           | 64                                          |
| 3                                                                                                                                                                                                  | 45            | 2          | 271                | 1.0                                                                                   | 0.6                         | 0.57 | 247.5                     | 78                                                                                                                                                                                                                     | 67         |               |           | 64                                          |
| 2                                                                                                                                                                                                  | 48            | 2          | 270                | 1.1                                                                                   | 0.6                         | 0.57 | 249.3                     | 78                                                                                                                                                                                                                     | 66         |               |           | 64                                          |
| 1                                                                                                                                                                                                  | 51            | 2          | 268                | 1.05                                                                                  | 0.6                         | 0.57 | 251.1                     | 78                                                                                                                                                                                                                     | 66         |               |           | 64                                          |
| PC                                                                                                                                                                                                 | 1554          |            |                    |                                                                                       |                             |      | 253.917                   |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
|                                                                                                                                                                                                    |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           |                                             |
| AVG                                                                                                                                                                                                |               |            |                    |                                                                                       |                             |      |                           |                                                                                                                                                                                                                        |            |               |           | (71.4)                                      |



METHOD

ST-1B

REV#

3

| COMPANY: <u>Dexter</u><br>UNIT: <u>Live Oak</u><br>DATE: <u>4/22/93</u><br>PROJECT: <u>027-488</u><br>TECH: <u>SAD</u><br>PUMP #:<br>METER BOX#: <u>1004</u><br>METER COEFF: <u>1.002760</u> |                  |               |                       | PRE / POST TEST LEAK CHECK<br>LEAK RATE: <u>20.01</u> / <u>0.005</u> cfm<br>VACUUM: <u>10</u> / <u>5</u> "Hg |                                |      |                                  | AMBIENT TEMP. °F: <u>60</u><br>Pbar:<br>STATIC PRESSURE ("Hg):<br>ASSUMED MOISTURE, %:<br>NOZZLE ID#:<br>AVG. CALIB. NOZZLE DIAM. ("):<br>PROBE LINER MATERIAL:<br>FILTER #:<br>DUCT DIAM. ("): |            |                           |                                                   |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|---------------|-----------------------|--------------------------------------------------------------------------------------------------------------|--------------------------------|------|----------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|---------------------------|---------------------------------------------------|
| TRAVERSE<br>PT. NUMBER                                                                                                                                                                       | TIME<br>(e) min. | VACUUM<br>"Hg | STACK TEMP<br>(Ts) °F | VELOCITY<br>HEAD<br>(Δ Ps)/m. H2O                                                                            | PRESSURE<br>DIFFERENTIAL, "H2O |      | GAS SAMPLE<br>VOLUME<br>(cu. ft) | GAS SAMPLE TEMP.                                                                                                                                                                                |            | FILTER HOLDER<br>TEMP. °F | TEMP OF GAS<br>EXIT CONDENSER<br>OR LAST IMPINGER |
|                                                                                                                                                                                              |                  |               |                       |                                                                                                              | RATE                           | Δ H  |                                  | INLET, °F                                                                                                                                                                                       | OUTLET, °F |                           |                                                   |
| START                                                                                                                                                                                        | 1728             | 2             |                       |                                                                                                              | 0.6                            | 0.57 | 263.8                            | 70                                                                                                                                                                                              | 66         |                           | 61                                                |
|                                                                                                                                                                                              | 34               | 2             |                       |                                                                                                              | 0.6                            | 0.57 | 272.9                            | 81                                                                                                                                                                                              | 67         |                           | 61                                                |
|                                                                                                                                                                                              | 40               | 2             |                       |                                                                                                              | 0.6                            | 0.57 | 276.5                            | 83                                                                                                                                                                                              | 68         |                           | 65                                                |
|                                                                                                                                                                                              | 46               | 2             |                       |                                                                                                              | 0.6                            | 0.57 | 280.1                            | 83                                                                                                                                                                                              | 68         |                           | 63                                                |
|                                                                                                                                                                                              | 52               | 2             |                       |                                                                                                              | 0.6                            | 0.57 | 283.7                            | 83                                                                                                                                                                                              | 67         |                           |                                                   |
|                                                                                                                                                                                              | 58               | 2             |                       |                                                                                                              | 0.6                            | 0.57 | 287.3                            | 82                                                                                                                                                                                              | 68         |                           |                                                   |
|                                                                                                                                                                                              | 1864             | 2             |                       |                                                                                                              | 0.6                            | 0.57 | 290.9                            | 82                                                                                                                                                                                              | 68         |                           |                                                   |
|                                                                                                                                                                                              | 10               | 2             |                       |                                                                                                              | 0.6                            | 0.57 | 294.5                            | 81                                                                                                                                                                                              | 68         |                           |                                                   |
| Finish                                                                                                                                                                                       | 1816             |               |                       |                                                                                                              |                                |      | 298.154                          |                                                                                                                                                                                                 |            |                           |                                                   |
| AVG                                                                                                                                                                                          |                  |               |                       |                                                                                                              |                                | .57  | 28.826                           |                                                                                                                                                                                                 |            |                           | 74.1                                              |



|                  |     |
|------------------|-----|
| COMPANY: Dester  |     |
| UNIT: Live Oak   |     |
| DATE: 4/22/93    |     |
| PROJECT: 027-488 |     |
| TECH: SAD        |     |
| PUMP #:          |     |
| METER BOX#:      |     |
| METER COEFF:     |     |
| PROBE #:         | Cp: |

|              |                |
|--------------|----------------|
| TECH:        |                |
| PUMP #:      | TOTAL 147.5    |
| METER BOX#:  | COUPLING 16.0  |
| METER COEFF: | DIAMETER 131.5 |
| PROBE #:     | AREA 94.31     |
|              | Co:            |

## Rated Total MMBtu/HR

|             |          |
|-------------|----------|
| $\Delta p$  | Vel      |
| Ts          | DSCFM    |
| Static      | MMBtu/hr |
| Pbar        | % Thr    |
| MW(wet)     |          |
| %H2O        |          |
| %O2         |          |
| °F. (@ 60°) |          |

**Additional Data:**

Diameters before disturb \_\_\_\_\_ After \_\_\_\_\_  
# of points, total \_\_\_\_\_

# VELOCITY TRAVERSE

EPA Method 20

COMPANY: Destec

UNIT: Kive Oak

DATE: 4/22/93

PROJECT: 027-488

TECH: SAD

PUMP #:

METER BOX#:

METER COEFF:

PROBE #:

TOTAL 162.5  
COUPLING 31.0  
DIAMETER 131.5  
AREA 94.31

Cp:

## VELOCITY DATA

| TRAVERSE POINTS |         | Ts, °F |     | ΔP      |     | Ts, °F |         | ΔP  |                                            | Rated Total MMBtu/HR |          |
|-----------------|---------|--------|-----|---------|-----|--------|---------|-----|--------------------------------------------|----------------------|----------|
| W/O             | W/COUPL | NO.    | W/O | W/COUPL | NO. | W/O    | W/COUPL | NO. | W/O                                        | W/COUPL              | NO.      |
|                 | 82.5    | 1      |     | 147.3   |     |        | 18      |     | ΔP                                         |                      | Vel      |
|                 | 35.6    | 2      |     | 11.0    |     |        | 15      |     | Ts                                         |                      | DSCFM    |
|                 | 39.0    | 3      |     | 154.5   |     |        | 20      |     | Static                                     |                      | MMBtu/hr |
|                 | 42.5    | 4      |     | 157.9   |     |        | 21      |     | Pbar                                       |                      | % Thr    |
|                 | 46.8    | 5      |     | 161.0   |     |        | 22      |     | MW(wet)                                    |                      |          |
|                 | 50.3    | 6      |     |         |     |        |         |     | %H2O                                       |                      |          |
|                 | 54.7    | 7      |     |         |     |        |         |     | %O2                                        |                      |          |
|                 | 59.7    | 8      |     |         |     |        |         |     | °F, (@ 60°)                                |                      |          |
|                 | 65.4    | 9      |     |         |     |        |         |     | Additional Data:                           |                      |          |
|                 | 72.5    | 10     |     |         |     |        |         |     |                                            |                      |          |
|                 | 82.7    | 11     |     |         |     |        |         |     | Diameters before disturb _____ After _____ |                      |          |
|                 | 110.8   | 12     |     |         |     |        |         |     |                                            |                      |          |
|                 | 121.0   | 13     |     |         |     |        |         |     | # of points, total _____                   |                      |          |
|                 | 128.1   | 14     |     |         |     |        |         |     |                                            |                      |          |
|                 | 133.8   | 15     |     |         |     |        |         |     |                                            |                      |          |
|                 | 138.8   | 16     |     |         |     |        |         |     |                                            |                      |          |
|                 | 143.2   | 17     |     |         |     |        |         |     |                                            |                      |          |

# LABORATORY ANALYSIS

## EPA METHOD 350.3 - AMMONIA ANALYSIS

COMPANY: Destec

PROJECT: 027-488

LOCATION/UNIT: Live Oak Cogen

DATE TESTED: 4/22/93

ANALYST: DGS

### STANDARDIZATION:


| mg/L $\text{NH}_4\text{Cl}$ | mV    | SLOPE |
|-----------------------------|-------|-------|
| 0.1                         | 96.8  | 65.6  |
| 1.0                         | 31.2  | 41.6  |
| 10.0                        | -30.4 | 41.8  |
| 100.0                       | -92.2 |       |

| SAMPLE # | mV    | N mg/L | df | N mg/L | NH3 mg/L | SAMPLE VOL. | T. mg      |
|----------|-------|--------|----|--------|----------|-------------|------------|
| 1        | -6.9  | 3.9    | —  | 3.9    | 4.73     | 460 ml      | 2.2 (2.17) |
| 2        | 0     | 3.0    | —  | 3.0    | 3.64     | 445 ml      | 1.6        |
| 3        | -6.3  | 3.9    | —  | 3.9    | 4.73     | 470 ml      | 2.2 (2.23) |
| Blank    | 126.6 | 4.1    |    |        |          | 265 ml      |            |
|          |       |        |    |        |          |             |            |
|          |       |        |    |        |          |             |            |
|          |       |        |    |        |          |             |            |
|          |       |        |    |        |          |             |            |
|          |       |        |    |        |          |             |            |
|          |       |        |    |        |          |             |            |
|          |       |        |    |        |          |             |            |
|          |       |        |    |        |          |             |            |


Method 350.3  $\text{NH}_3$  Analysis

46 6010

K·E SEMI-LOGARITHMIC 4 CYCLES X 70 DIVISIONS  
KEUFFEL & ESSER CO. MADE IN U.S.A.




Method 350.3 NH<sub>3</sub> Analysis



DESTEC/WZI LIVE OAK COGEN  
 4-22-93 PROJECT # 027-488  
 HC SAMPLE BLANK

16:34:14



CHROMATOGRAM 8 MEMORIZED  
 PKNO TIME AREA MK

| PKNO         | TIME             | AREA           | MK |
|--------------|------------------|----------------|----|
| 1            | 2.683            | 218            |    |
| <del>2</del> | <del>9.555</del> | <del>124</del> |    |
| 3            | 8.982            | 222            | V  |

IDNO

CONC

NAME

C-6+

~~C-5~~

C-5


} not a peak  
run

TOTAL

1760


0

DESTEC/WZI LIVE OAK COGEN  
 4-22-93 PROJECT # 027-488  
 HC SAMPLE # 1



| CHROMATOGRAM | 9     | MEMORIZED |    |      |      |      |
|--------------|-------|-----------|----|------|------|------|
| PKNO         | TIME  | AREA      | MK | IDNO | CONC | NAME |
| 1            | 2.532 | 302       |    |      |      |      |
| 2            | 2.692 | 438       | V  | 6    |      | C-6+ |
| 3            | 2.979 | 738       |    | 1    |      | C-1  |
| 4            | 3.07  | 1970      | V  | 1    |      | C-1  |
| TOTAL        |       | 3349      |    |      | 0    |      |

DESTEC/WZI LIVE OAK COGEN  
 4-22-93 PROJECT # 027-488  
 HC SAMPLE # 2




| CHROMATOGRAM 10<br>PKNO | TIME  | MEMORIZED<br>AREA | MK | IDNO | CONC | NAME |
|-------------------------|-------|-------------------|----|------|------|------|
| 1                       | 2.67  | 356               |    | 6    |      | C-6+ |
| 2                       | 2.977 | 847               |    | 1    |      | C-1  |
| 3                       | 3.072 | 1759              |    | 1    |      | C-1  |
| TOTAL                   |       | 2961              |    |      | 0    |      |




DESTEC/WZI LIVE OAK COGEN  
 4-22-93 PROJECT # 027-488  
 HC SAMPLE # 3


17:38:57




| CHROMATOGRAM | 11    | MEMORIZED |             |      |      |      |
|--------------|-------|-----------|-------------|------|------|------|
| PKNO         | TIME  | AREA      | MK          | IDNO | CONC | NAME |
| 1            | 2.978 | 849       | } 2575<br>V | 1    |      | C-1  |
| 2            | 3.072 | 1726      |             | 1    |      | C-1  |
| TOTAL        |       | 2575      |             |      | 0    |      |





















## APPENDIX III QUALITY ASSURANCE

# PETRO CHEM ENVIRONMENTAL SERVICES, INC.

## CHAIN OF CUSTODY RECORD

### MAIN OFFICE

313 Daniels Lane  
Bakersfield, CA 93307  
(805) 327-7300 FAX (805) 327-3459

### LAB OFFICE

3207 Antonino Avenue  
Bakersfield, CA 93308  
(805) 631-9332 FAX (805) 327-0860

### ANALYSIS REQUEST

| LABORATORY<br><i>EAS</i>  |                    |                |     | LAB ID#                                   |          |          | <i>Low Range Total Sulfur as H<sub>2</sub>S</i> |  |  |  |  |  |  |  |  |  |  |  |                         |
|---------------------------|--------------------|----------------|-----|-------------------------------------------|----------|----------|-------------------------------------------------|--|--|--|--|--|--|--|--|--|--|--|-------------------------|
| COMPANY<br><i>Deste</i>   |                    |                |     | LOCATION/UNIT<br><i>Live Oak Cogen</i>    |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
| PROJECT<br><i>027-488</i> |                    |                |     | SAMPLED BY<br><i>DCI</i>                  |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
| METHOD                    |                    |                |     | DELIVER REPORT TO:<br><i>Terry Rowles</i> |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  | PCES PO#<br><i>3086</i> |
| SAMPLE ID#                | SAMPLE DESCRIPTION | SAMPLE DATE    | Liq | Filter                                    | Gas      |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
| <i>Bag</i>                | <i>Fuel Gas</i>    | <i>4/22/93</i> |     |                                           | <i>X</i> | <i>X</i> |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |
|                           |                    |                |     |                                           |          |          |                                                 |  |  |  |  |  |  |  |  |  |  |  |                         |

|                     |                |              |      |
|---------------------|----------------|--------------|------|
| COMMENTS:           |                |              |      |
| RELINQUISHED BY:    | DATE           | RECEIVED BY: | DATE |
| <i>D. Smallwood</i> | <i>4/22/93</i> |              |      |
| RELINQUISHED BY:    | DATE           | RECEIVED BY: | DATE |
|                     |                |              |      |
| RELINQUISHED BY:    | DATE           | RECEIVED BY: | DATE |
|                     |                |              |      |

**PETRO CHEM ENVIRONMENTAL SERVICES, INC.**  
**DRY GAS METER CALIBRATION**

|             |         |                  |           |
|-------------|---------|------------------|-----------|
| DATE:       | 4-12-93 | AMBIENT TEMP °F: | 61        |
| TECH:       | BDM     | BAROMETRIC Pbar: | 30.06     |
| METER I.D.# | 1004    | TEST METER ID#:  | S5M104564 |
|             |         | TEST METER Mcf:  | 1.023     |

| APPROXIMATE CFM                    |         | 0.75     | 0.50     | 0.30     |
|------------------------------------|---------|----------|----------|----------|
| STD TEST METER<br>VOLUME CF        | INITIAL | 0.00     | 0.00     | 0.00     |
|                                    | FINAL   | 7.44     | 10.01    | 10.01    |
|                                    | TOTAL   | 7.44     | 10.01    | 10.01    |
| FIELD GAS METER<br>VOLUME CF       | INITIAL |          |          |          |
|                                    | FINAL   | 165.40   | 185.40   | 197.40   |
|                                    | TOTAL   | 172.82   | 185.40   | 207.79   |
| STD TEST METER<br>TEMP (°F)        |         |          |          |          |
|                                    |         | 62.0     | 61.0     | 62.0     |
|                                    |         |          |          |          |
| FIELD GAS METER<br>TEMP (°F)       | IN      | 71.0     | 75.0     | 74.0     |
|                                    | OUT     | 55.0     | 60.0     | 65.0     |
|                                    | AVERAGE | 63.0     | 67.5     | 69.5     |
| STD TEST METER<br>PRESSURE ("H2O)  |         |          |          |          |
|                                    |         | -0.60    | -0.30    | -0.15    |
|                                    |         |          |          |          |
| FIELD GAS METER<br>PRESSURE ("H2O) |         |          |          |          |
|                                    |         | 0.73     | 0.32     | 0.09     |
|                                    |         |          |          |          |
| FIELD GAS METER, Mcf               |         | 1.025891 | 1.003864 | 0.999526 |

|                    |          |     |        |
|--------------------|----------|-----|--------|
| FIELD AVERAGE Mcf: | 1.009760 | H@: | 0.7246 |
|--------------------|----------|-----|--------|

PETRO CHEM ENVIRONMENTAL SERVICES, INC.  
PITOT TUBE CALIBRATION

PITOT TUBE ID. # 13'IN  
DATE: 4-30-93  
CALIBRATED BY: RJK

| "A" SIDE CALIBRATION |                                   |                                   |       |                            |
|----------------------|-----------------------------------|-----------------------------------|-------|----------------------------|
| RUN #                | $\Delta$ Pstd<br>cm H2O (in. H2O) | $\Delta$ P(s)<br>cm H2O (in. H2O) | Cp(s) | DEVIATION<br>Cp(s) - Cp(A) |
| 1                    | 0.280                             | 0.400                             | 0.828 | 0.002                      |
| 2                    | 0.280                             | 0.405                             | 0.823 | -0.003                     |
| 3                    | 0.285                             | 0.410                             | 0.825 | -0.001                     |
| Cp (SIDE A)          |                                   |                                   | 0.826 |                            |

| "B" SIDE CALIBRATION |                                   |                                   |       |                            |
|----------------------|-----------------------------------|-----------------------------------|-------|----------------------------|
| RUN #                | $\Delta$ Pstd<br>cm H2O (in. H2O) | $\Delta$ P(s)<br>cm H2O (in. H2O) | Cp(s) | DEVIATION<br>Cp(s) - Cp(B) |
| 1                    | 0.270                             | 0.380                             | 0.834 | -0.001                     |
| 2                    | 0.270                             | 0.385                             | 0.829 | -0.006                     |
| 3                    | 0.275                             | 0.380                             | 0.842 | 0.007                      |
| Cp (SIDE B)          |                                   |                                   | 0.835 |                            |

|                             |        |       |
|-----------------------------|--------|-------|
| Cp (SIDE A) - Cp (SIDE B) = | -0.009 | 0.831 |
|-----------------------------|--------|-------|

$$Cp = .99 * \Delta Pstd / \Delta P(s)$$



542234

Airco Special Gases  
Union Landing & River Roads  
P.O. Drawer No. 272  
Riverton  
New Jersey 08077  
Telephones: Marketing: 609-829-7878  
Prod. & Admin.: 609-829-7914  
International: 609-829-7917

## CERTIFICATE OF ANALYSIS - EPA PROTOCOL GAS MIXTURE

CUSTOMER: Bakersfield Welding Supply Sausalito CACYLINDER #: CG:69805CYLINDER PRESSURE: 1000 psigLABORATORY: Riverton NJCERTIFICATION DATE: 3/5/93EXPIRATION DATE: 9/5/93REFERENCE #: 30963

| MIXTURE<br>COMPONENT | ACTUAL MIXTURE<br>CONCENTRATION | AIRCO INTERMEDIATE STANDARD |          |           |
|----------------------|---------------------------------|-----------------------------|----------|-----------|
|                      |                                 | CYLINDER #                  | CONC.    | NIST SRM# |
| Carbon Monoxide      | 20.1 ppm                        | CG:62780                    | 24.7 ppm | 1678C     |

BALANCE GAS: Nitric Oxide, Sulfur Dioxide, Nitrogen

## GAS ANALYZER:

MAKE: Beckman MODEL: 866 SERIAL#: 1000049PRINCIPAL: Non-Dispersive InfraredLAST MULTIPOINT CALIBRATION DATE: 11/3/92

R=REFERENCE STANDARD

Z=ZERO GAS

S=SAMPLE GAS

1ST ANALYSIS: DATE 2/26/93 ANALYST A. Lattanze

|                 |              |              |                          |
|-----------------|--------------|--------------|--------------------------|
| 1) Z <u>000</u> | R <u>243</u> | S <u>197</u> | CONC (1) <u>20.0 ppm</u> |
| 2) R <u>243</u> | Z <u>000</u> | S <u>197</u> | CONC (2) <u>20.0 ppm</u> |
| 3) R <u>243</u> | S <u>197</u> | Z <u>000</u> | CONC (3) <u>20.0 ppm</u> |
|                 |              |              | AVE CONC <u>20.0 ppm</u> |

2ND ANALYSIS: DATE 3/5/93 ANALYST A. Lattanze

|                 |              |              |                          |
|-----------------|--------------|--------------|--------------------------|
| 1) Z <u>000</u> | R <u>240</u> | S <u>195</u> | CONC (1) <u>20.1 ppm</u> |
| 2) R <u>240</u> | Z <u>000</u> | S <u>195</u> | CONC (2) <u>20.1 ppm</u> |
| 3) R <u>240</u> | S <u>195</u> | Z <u>000</u> | CONC (3) <u>20.1 ppm</u> |
|                 |              |              | AVE CONC <u>20.1 ppm</u> |

THIS CALIBRATION STANDARD HAS BEEN CERTIFIED VERSUS EPA TRACEABILITY  
PROTOCOL NO. 1, PROCEDURE G1, AND ANALYSES PERFORMED PER SECTION 3.0.4.

CERTIFIED CONCENTRATION: Carbon Monoxide=20.1ppm, Nitric Oxide=20.6ppm, Sulfur Dioxide=20.0 ppmAPPROVED BY J. Lino Nitrogen=Balance  
LABORATORY MANAGER



542234

Airco Special Gases  
Union Landing & River Roads  
P.O. Drawer No. 272  
Riverton  
New Jersey 08077  
Telephones: Marketing: 609-829-7878  
Prod. & Admin.: 609-829-7914  
International: 609-829-7917

## CERTIFICATE OF ANALYSIS - EPA PROTOCOL GAS MIX

CUSTOMER: Bakersfield Welding Supply Sausalito CACYLINDER #: CC-69805CERTIFICATION DATE: 3/5/93CYLINDER PRESSURE: 1000 psigEXPIRATION DATE: 9/5/93LABORATORY: Riverton NJREFERENCE #: 30963

| MIXTURE<br>COMPONENTS | ACTUAL MIXTURE<br>CONCENTRATION | AIRCO INTERMEDIATE STANDARD |          |           |
|-----------------------|---------------------------------|-----------------------------|----------|-----------|
|                       |                                 | CYLINDER #                  | CONC.    | NIST SRM# |
| <i>Nitric Oxide</i>   | 20.6 ppm                        | CC:95054                    | 18.7 ppm | 2629A     |
| <i>Sulfur Dioxide</i> | 20.0 ppm                        | CC:15382                    | 25.8 ppm | 1693A     |

BALANCE GAS: Carbon Monoxide, NitrogenCOMPONENT 1 GAS ANALYSIS PROCEDURE ChemiluminescenceMAKE/MODEL/SER#: Beckman, 952, 0100204LAST MULTIPOINT CALIBRATION DATE: 2/2/93COMPONENT 2 GAS ANALYSIS PROCEDURE Non-Dispersive InfraredMAKE/MODEL/SER#: Beckman, 865, 0103986LAST MULTIPOINT CALIBRATION DATE: 2/2/93

R=REFERENCE STANDARD. Z=ZERO GAS S=SAMPLE GAS

1ST COMPONENT Nitric Oxide

|               |             |                |             |                    |             |          |                 |
|---------------|-------------|----------------|-------------|--------------------|-------------|----------|-----------------|
| 1ST ANALYSIS: | DATE        | <u>2/26/93</u> | ANALYST     | <u>A. Lattanze</u> |             |          |                 |
| 1) Z          | <u>0000</u> | R              | <u>1535</u> | S                  | <u>1680</u> | CONC (1) | <u>20.5 ppm</u> |
| 2) R          | <u>1535</u> | Z              | <u>0000</u> | S                  | <u>1680</u> | CONC (2) | <u>20.5 ppm</u> |
| 3) R          | <u>1535</u> | S              | <u>1680</u> | Z                  | <u>0000</u> | CONC (3) | <u>20.5 ppm</u> |
|               |             |                |             |                    |             | AVE CONC | <u>20.5 ppm</u> |

|               |             |               |             |                    |             |          |                 |
|---------------|-------------|---------------|-------------|--------------------|-------------|----------|-----------------|
| 2ND ANALYSIS: | DATE        | <u>3/5/93</u> | ANALYST     | <u>A. Lattanze</u> |             |          |                 |
| 1) Z          | <u>0000</u> | R             | <u>1500</u> | S                  | <u>1650</u> | CONC (1) | <u>20.6 ppm</u> |
| 2) R          | <u>1500</u> | Z             | <u>0000</u> | S                  | <u>1650</u> | CONC (2) | <u>20.6 ppm</u> |
| 3) R          | <u>1500</u> | S             | <u>1650</u> | Z                  | <u>0000</u> | CONC (3) | <u>20.6 ppm</u> |
|               |             |               |             |                    |             | AVE CONC | <u>20.6 ppm</u> |

2ND COMPONENT Sulfur Dioxide

|               |             |                |             |                    |             |          |                 |
|---------------|-------------|----------------|-------------|--------------------|-------------|----------|-----------------|
| 1ST ANALYSIS: | DATE        | <u>2/26/93</u> | ANALYST     | <u>A. Lattanze</u> |             |          |                 |
| 1) Z          | <u>0000</u> | R              | <u>2520</u> | S                  | <u>1950</u> | CONC (1) | <u>20.0 ppm</u> |
| 2) R          | <u>2520</u> | Z              | <u>0000</u> | S                  | <u>1950</u> | CONC (2) | <u>20.0 ppm</u> |
| 3) R          | <u>2520</u> | S              | <u>1950</u> | Z                  | <u>0000</u> | CONC (3) | <u>20.0 ppm</u> |
|               |             |                |             |                    |             | AVE CONC | <u>20.0 ppm</u> |


|               |             |               |             |                    |             |          |                 |
|---------------|-------------|---------------|-------------|--------------------|-------------|----------|-----------------|
| 2ND ANALYSIS: | DATE        | <u>3/5/93</u> | ANALYST     | <u>A. Lattanze</u> |             |          |                 |
| 1) Z          | <u>0000</u> | R             | <u>2410</u> | S                  | <u>1870</u> | CONC (1) | <u>20.0 ppm</u> |
| 2) R          | <u>2410</u> | Z             | <u>0000</u> | S                  | <u>1870</u> | CONC (2) | <u>20.0 ppm</u> |
| 3) R          | <u>2410</u> | S             | <u>1870</u> | Z                  | <u>0000</u> | CONC (3) | <u>20.0 ppm</u> |
|               |             |               |             |                    |             | AVE CONC | <u>20.0 ppm</u> |

THIS CALIBRATION STANDARD HAS BEEN CERTIFIED VERSUS EPA TRACEABILITY  
PROTOCOL NO. 1, PROCEDURE G1, AND ANALYSES PERFORMED PER SECTION 3.0.4.  
CERTIFIED CONCENTRATION: Nitric Oxide=20.6ppm, Sulfur Dioxide=20.0ppm, Carbon Monoxide=20.1ppm, Nitrogen=Balance

APPROVED BY J. S. Sca  
A member of The BOC Group LABORATORY MANAGER

-88-

Petro Chem Environmental Services, Inc.



**PETRO  
CHEM  
ENVIRONMENTAL  
SERVICES, INC.**

3207 Antonino Avenue  
Bakersfield, California 93308  
(805) 327-7300  
FAX (805) 327-3459


COMPANY : DESTEC OPERATING  
DATE : 4-22-93  
PROJECT : 027-488

DATE RECEIVED : 4-23-93  
DATE ANALYZED : 4-24-93  
DATE REPORTED: 4-28-93

**EPA METHOD 18  
LOW RANGE HYDROCARBON ANALYSIS  
CALIBRATION DATA AND STATISTICS**


**METHANE**

| CONC.<br>(ppmv) | AREA<br>COUNTS | RESPONSE<br>FACTOR<br>ppmv/AC |
|-----------------|----------------|-------------------------------|
| 0.413           | 753            | 5.48E-04                      |
| 0.825           | 1515           | 5.45E-04                      |
| 4.125           | 7134           | 5.78E-04                      |
| 8.25            | 14258          | 5.79E-04                      |
| AVERAGE RF      |                | 5.62E-04                      |
| STD. DEVIATION  |                | 1.60E-05                      |
| RSD%            |                | 2.85%                         |




**ETHANE**

| CONC.<br>(ppmv) | AREA<br>COUNTS | RESPONSE<br>FACTOR<br>ppmv/AC |
|-----------------|----------------|-------------------------------|
| 0.413           | 1433           | 2.88E-04                      |
| 0.825           | 3018           | 2.73E-04                      |
| 4.125           | 14282          | 2.89E-04                      |
| 8.25            | 29337          | 2.81E-04                      |
| AVERAGE RF      |                | 2.83E-04                      |
| STD. DEVIATION  |                | 6.27E-06                      |
| RSD%            |                | 2.22%                         |







**PETRO  
CHEM  
ENVIRONMENTAL  
SERVICES, INC.**

3207 Antonino Avenue  
Bakersfield, California 93308  
(805) 327-7300  
FAX (805) 327-3459


COMPANY: DESTEC OPERATING  
DATE : 4-22-93  
PROJECT : 027-488

DATE RECEIVED : 4-23-93  
DATE ANALYZED : 4-24-93  
DATE REPORTED: 4-28-93

**EPA METHOD 18  
LOW RANGE HYDROCARBON ANALYSIS  
CALIBRATION DATA AND STATISTICS**


**PROPANE**


| CONC.<br>(ppmv) | AREA<br>COUNTS | RESPONSE<br>FACTOR<br>ppmv/AC |
|-----------------|----------------|-------------------------------|
| 0.413           | 2198           | 1.88E-04                      |
| 0.825           | 4507           | 1.83E-04                      |
| 4.125           | 21237          | 1.94E-04                      |
| 8.25            | 43237          | 1.91E-04                      |
| AVERAGE RF      |                | 1.89E-04                      |
| STD. DEVIATION  |                | 4.10E-06                      |
| RSD%            |                | 2.17%                         |



**BUTANE**

| CONC.<br>(ppmv) | AREA<br>COUNTS | RESPONSE<br>FACTOR<br>ppmv/AC |
|-----------------|----------------|-------------------------------|
| 0.413           | 2826           | 1.46E-04                      |
| 0.825           | 5953           | 1.39E-04                      |
| 4.125           | 28314          | 1.46E-04                      |
| 8.25            | 57502          | 1.43E-04                      |
| AVERAGE RF      |                | 1.43E-04                      |
| STD. DEVIATION  |                | 3.00E-06                      |
| RSD%            |                | 2.09%                         |





**PETRO  
CHEM  
ENVIRONMENTAL  
SERVICES, INC.**

3207 Antonino Avenue  
Bakersfield, California 93308  
(805) 327-7300  
FAX (805) 327-3459


COMPANY: DESTEC OPERATING  
DATE : 4-22-93  
PROJECT : 027-488

DATE RECEIVED : 4-23-93  
DATE ANALYZED : 4-24-93  
DATE REPORTED: 4-28-93

**EPA METHOD 18  
LOW RANGE HYDROCARBON ANALYSIS  
CALIBRATION DATA AND STATISTICS**


**PENTANE**


| CONC.<br>(ppmv) | AREA<br>COUNTS | RESPONSE<br>FACTOR<br>ppmv/AC |
|-----------------|----------------|-------------------------------|
| 0.37            | 2792           | 1.33E-04                      |
| 0.74            | 6699           | 1.10E-04                      |
| 3.7             | 32699          | 1.13E-04                      |
| 7.4             | 66274          | 1.12E-04                      |
| AVERAGE RF      |                | 1.17E-04                      |
| STD. DEVIATION  |                | 9.04E-06                      |
| RSD%            |                | 7.73%                         |



**HEXANE**

| CONC.<br>(ppmv) | AREA<br>COUNTS | RESPONSE<br>FACTOR<br>ppmv/AC |
|-----------------|----------------|-------------------------------|
| 0.38            | 4233           | 8.98E-05                      |
| 0.76            | 8763           | 8.67E-05                      |
| 3.8             | 39423          | 9.64E-05                      |
| 7.6             | 79851          | 9.52E-05                      |
| AVERAGE RF      |                | 9.20E-05                      |
| STD. DEVIATION  |                | 3.94E-06                      |
| RSD%            |                | 4.28%                         |





**PETRO  
CHEM  
ENVIRONMENTAL  
SERVICES, INC.**

3207 Antonino Avenue  
Bakersfield, California 93308  
(805) 327-7300  
FAX (805) 327-3459

COMPANY: DESTEC OPERATING  
DATE : 4-22-93  
PROJECT : 027-488

DATE RECEIVED : 4-23-93  
DATE ANALYZED : 4-24-93  
DATE REPORTED: 4-28-93

**EPA METHOD 18  
CALIBRATION DRIFT ANALYSIS**

**POST ANALYSIS CALIBRATION CHECK (0.4ppm STD.)**

| CONSTITUENT | INITIAL<br>RF | POST<br>RF | %DIFF. |
|-------------|---------------|------------|--------|
| METHANE     | 5.48E-04      | 5.30E-04   | 3.34%  |
| ETHANE      | 2.88E-04      | 2.93E-04   | -1.63% |
| PROPANE     | 1.88E-04      | 1.94E-04   | -3.10% |
| BUTANE      | 1.46E-04      | 1.52E-04   | -4.05% |
| PENTANE     | 1.33E-04      | 1.02E-04   | 23.21% |
| HEXANES+    | 8.98E-05      | 9.21E-05   | -2.59% |

**POST ANALYSIS CALIBRATION CHECK (0.8ppm STD.)**

| CONSTITUENT | INITIAL<br>RF | POST<br>RF | %DIFF. |
|-------------|---------------|------------|--------|
| METHANE     | 5.45E-04      | 5.57E-04   | -2.30% |
| ETHANE      | 2.73E-04      | 2.73E-04   | 0.20%  |
| PROPANE     | 1.83E-04      | 1.87E-04   | -1.90% |
| BUTANE      | 1.39E-04      | 1.42E-04   | -2.48% |
| PENTANE     | 1.10E-04      | 1.09E-04   | 1.60%  |
| HEXANES+    | 8.67E-05      | 9.07E-05   | -4.57% |

## EPA METHOD 2 STACK GAS VELOCITY AND VOLUMETRIC FLOWRATE

Average Stack Gas Velocity  
Eq. 2-6 & Eq. 2-9

$$P_g = \frac{\text{Static Pressure, } H_2O}{13.6}$$

$$P_s = P_{bar} + P_g$$

$$V_s = K_p C_p (\sqrt{\Delta P})_{avg} \sqrt{\frac{T_{s(avg)}}{P_s M_s}}$$

Average Stack Gas Dry Volumetric Flow Rate  
Eq. 2-10

$$Q_{std} = 60 (1 - B_{ws}) v_s A \left[ \frac{T_{std}}{T_{s(avg)}} \right] \left[ \frac{P_s}{P_{std}} \right]$$

$$\frac{Q_{std}}{MF} = SCFM$$


## EPA METHOD 3 DRY MOLECULAR WEIGHT OF STACK GAS Eq. 3-2

$$M_d = 0.44 (\% CO_2) + 0.320 (\% O_2) + 0.280 (\% N_2 + \% CO)$$

Wet Molecular Weight of Stack Gas


$$M_s = M_d (1 - B_{ws}) + 18 (B_{ws})$$

SYSTEM BLANK  
UHP NITROGEN



CHROMATOGRAM 3 MEMORIZED  
WARNING NO PEAK


0.4PPM HYDROCARBON STANDARD  
SCOTTY CAN MIX 1 DIL. 1:40



| CHROMATOGRAM 18 |        | MEMORIZED |    | IDNO | CONC | NAME |
|-----------------|--------|-----------|----|------|------|------|
| PKNO            | TIME   | AREA      | MK |      |      |      |
| 1               | 2.667  | 4233      |    | 6    |      | C-6+ |
| 2               | 3.079  | 753       |    | 1    |      | C-1  |
| 3               | 3.627  | 1433      |    | 2    |      | C-2  |
| 4               | 4.774  | 2198      |    | 3    |      | C-3  |
| 5               | 7.453  | 2826      |    | 4    |      | C-4  |
| 6               | 13.408 | 2792      |    | 5    |      | C-5  |
| TOTAL           |        | 14235     |    |      | 0    |      |


0.8PPM HYDROCARBON STANDARD  
SCOTTY CAN MIX 1 DIL 1:20

15:10:51



| CHROMATOGRAM | 5                | MEMORIZED      |    |               |      |                |
|--------------|------------------|----------------|----|---------------|------|----------------|
| PKNO         | TIME             | AREA           | MK | IDNO          | CONC | NAME           |
| 1            | 2.683            | 8763           |    | 6             |      | C-6+           |
| 2            | 3.071            | 1515           |    | 1             |      | C-1            |
| 3            | 3.621            | 3018           |    | 2             |      | C-2            |
| 4            | 4.764            | 4507           |    | 3             |      | C-3            |
| 5            | 7.44             | 5953           |    | 4             |      | C-4            |
| 6            | <del>8.783</del> | <del>999</del> |    | <del>16</del> |      | <del>C-5</del> |
| 7            | 13.39            | 6699           |    | 5             |      | C-5            |
| TOTAL        |                  | 31263          |    |               | 0    |                |


4PPM HYDROCARBON STANDARD  
SCOTTY CAN MIX 1 DIL. 1:4



| CHROMATOGRAM<br>PKNO | 6<br>TIME | MEMORIZED<br>AREA | MK | IDNO | CONC | NAME |
|----------------------|-----------|-------------------|----|------|------|------|
| 1                    | 2.683     | 39423             |    | 6    |      | C-6+ |
| 2                    | 3.072     | 7134              |    | 1    |      | C-1  |
| 3                    | 3.622     | 14282             |    | 2    |      | C-2  |
| 4                    | 4.766     | 21237             |    | 3    |      | C-3  |
| 5                    | 7.441     | 28314             |    | 4    |      | C-4  |
| 6                    | 13.394    | 32699             |    | 5    |      | C-5  |
| TOTAL                |           | 143090            |    |      | 0    |      |




8PPM HYDROCARBON STANDARD  
SCOTTY CAN MIX 1 DIL. 1:1



| CHROMATOGRAM<br>PKNO | 7<br>TIME        | MEMORIZED<br>AREA | MK | IDNO         | CONC | NAME           |
|----------------------|------------------|-------------------|----|--------------|------|----------------|
| 1                    | 2.684            | 79851             |    | 6            |      | C-6+           |
| 2                    | 3.074            | 14258             |    | 1            |      | C-1            |
| 3                    | 3.623            | 29337             |    | 2            |      | C-2            |
| 4                    | 4.768            | 43237             |    | 3            |      | C-3            |
| 5                    | 7.444            | 57502             |    | 4            |      | C-4            |
| 6                    | <del>8.867</del> | <del>218</del>    |    | <del>4</del> |      | <del>C-5</del> |
| 7                    | 13.399           | 66274             |    | 5            |      | C-5            |
| -----                |                  |                   |    |              |      |                |
| TOTAL                |                  | 290675            |    |              | 0    |                |


POST ANALYSIS CALIBRATION CHECK  
 0.4PPM HYDROCARBON STANDARD  
 SCOTTY CAN MIX 1 DIL. 1:40

18:18:02



| CHROMATOGRAM 16 MEMORIZED |        |       |    |      |      |      |
|---------------------------|--------|-------|----|------|------|------|
| PKNO                      | TIME   | AREA  | MK | IDNO | CONC | NAME |
| 1                         | 2.677  | 4126  |    | 6    |      | C-6+ |
| 2                         | 3.073  | 779   |    | 1    |      | C-1  |
| 3                         | 3.621  | 1410  |    | 2    |      | C-2  |
| 4                         | 4.771  | 2132  |    | 3    |      | C-3  |
| 5                         | 7.433  | 2716  |    | 4    |      | C-4  |
| 6                         | 13.417 | 3636  |    | 5    |      | C-5  |
| TOTAL                     |        | 14797 |    |      | 0    |      |

POST ANALYSIS CALIBRATION CHECK  
 0.8PPM HYDROCARBON STANDARD  
 SCOTTY CAN MIX 1 DIL. 1:20



| CHROMATOGRAM | 17    | MEMORIZED |    |      |      |      |
|--------------|-------|-----------|----|------|------|------|
| PKNO         | TIME  | AREA      | MK | IDNO | CONC | NAME |
| 1            | 2.675 | 8380      |    | 6    |      | C-6+ |
| 2            | 3.076 | 1481      |    | 1    |      | C-1  |
| 3            | 3.626 | 3024      |    | 2    |      | C-2  |
| 4            | 4.772 | 4423      |    | 3    |      | C-3  |
| 5            | 7.433 | 5809      |    | 4    |      | C-4  |
| 6            | 13.4  | 6808      |    | 5    |      | C-5  |
| TOTAL        |       | 29924     |    |      | 0    |      |

## APPENDIX IV RESPONDENCE

Gary Fuller  
WZI, Inc.  
March 31, 1993

Project: 027-488  
Live Oak  
Limited Cogen

## **SOURCE TEST PROTOCOL**

### **I. Source Information**

A. Unit                      One 48.5 MW GE LM-5000  
Gas Fired Turbine  
PTO 4213001 B

B. Company                Destec Engineering , Inc.  
Live Oak Limited Cogeneration Facility  
Sec. 23, T28S, R27E  
Kern County, California

C/O Gary Fuller (WZI, Inc.)  
4700 Stockdale Highway  
Bakersfield, California 93309

### **II. Testing Firm**

Petro Chem Environmental Services, Inc.  
313 Daniels Lane  
Bakersfield, California 93307

Attention: Mark Ready

### **III. Regulatory Agency**

San Joaquin Valley Unified APCD  
Southern Region

### **IV. Summary**

Determinations of concentrations (ppm) and  
emissions (lb/hr) of sulfur, NMHC, NOx, CO, NH<sub>3</sub>  
and Spec II, III, IV (NOx, O<sub>2</sub>, CO) relative accuracy,  
from the exhaust of a gas fired Turbine/Generator.

### **V. Testing Date**

April 22 - 23, 1993

Gary Fuller  
WZI, Inc.  
March 31, 1993

Project: 027-488  
Live Oak  
Limited Cogen

### PROPOSAL FOR COMPLIANCE TESTING


Determination of concentrations (ppm) and emissions (lbs/hr) of sulfur, NMHC, NOx, CO, and NH<sub>3</sub> from the exhaust of one 48.5 MW gas fired Turbine/Generator. Relative Accuracy testing will be performed for NOx, O<sub>2</sub> and CO following Title 40 CFR performance Spec II, III and IV; a minimum of nine 30 minute runs will be performed. Fuel sulfur analysis will be performed by EPA Method 20 and 19; EAS Labs of San Luis Obispo will be used (example analysis enclosed). The following Methods will be used:

| Parameters                                                       | Method                                                       | Test Runs Per Turbine            | Permit Limit, lb/hr Per Turbine |
|------------------------------------------------------------------|--------------------------------------------------------------|----------------------------------|---------------------------------|
| Ammonia                                                          | BAAQMD ST-1B                                                 | 3 - 30 minute                    | 20 ppm                          |
| Sulfur                                                           | Fuel Analysis / Fuel Rates                                   | 1                                | *** .29 lb/hr as sulfur         |
| NMHC                                                             | EPA Method 18; (modified) C <sub>1</sub> -C <sub>6</sub> +   | 3                                | ** 5.37 lb/hr                   |
| * NOx                                                            | EPA Method 20; Chemiluminescent Analyzer                     | 9 - 30 minute                    | 6.16 lb/hr<br>.0135 lb/MMBtu    |
| * CO                                                             | EPA Method 10; GFC Analyzer                                  | 9 - 30 minute                    | 11.00 lb/hr                     |
| * O <sub>2</sub>                                                 | EPA Method 20; Fuel Cell Analyzer                            | 9 - 30 minute                    | —                               |
| Molecular Weight O <sub>2</sub> /CO <sub>2</sub> /N <sub>2</sub> | EPA Method 3; Orsat Analysis                                 | 2                                | —                               |
| Volume Flow DSCFM                                                | EPA Method 2 & 4; Pitot Tube Traverse and Condensation Train | 2                                | —                               |
| Relative Accuracy NOx/O <sub>2</sub> /CO                         | Title 40 CFR Performance Spec II, III and IV                 | See above NOx/O <sub>2</sub> /CO | 20%/20%/10%                     |

\* An initial 48 point concentration traverse will be performed to document the point(s) of average concentration. All follow-up runs will be performed at the point(s) of average concentration.


\*\* The Method 18 analysis will be modified to increase sensitivity to 0.2 ppm C<sub>1</sub>-C<sub>6</sub>+. Sample analysis is enclosed.

\*\*\* Emissions as sulfur = (lb/hr SO<sub>2</sub>/s) + lb/hr SO<sub>4</sub>/3.



SAN JOAQUIN VALLEY  
UNITED AIR POLLUTION CONTROL DISTRICT  
SOUTHERN REGION

PERMIT TO OPERATE



Number: 4213001(B)

PERMIT TO OPERATE IS HEREBY GRANTED TO: LIVE OAK LIMITED  
FOR EQUIPMENT LOCATED AT: Sec. 18, T28S, R28E  
EQUIPMENT OR PROCESS DESCRIPTION: One Cogeneration Unit  
OPERATIONAL CONDITIONS LISTED BELOW.

THIS PERMIT BECOMES VOID UPON ANY CHANGE OF OWNERSHIP OR LOCATION. OR ANY ALTERATION.

NOTE: The permittee may be required to provide adequate sampling and testing facilities. Equipment modification requires a new permit.

DAVID L. CROW  
EXECUTIVE DIRECTOR/APCO

REVOCABLE: This permit does not authorize the emission of air contaminants in excess of those allowed by the Rules and Regulations of the S.J.V.U.A.P.C.D.

By: Don M. Adams

For Period: 04-30-92 TO 04-30-93

CONDITIONAL APPROVAL:

Compliance with all conditions of approval imposed by any applicable Authority to Construct is required for life of this equipment unless modified by application.

EQUIPMENT DESCRIPTION: Gas-Fired 48 Megawatt Cogeneration Facility, including the following equipment:

- a. Stewart & Stevenson GE LM-5000 gas turbine generator system, 48 MW capacity.
- b. Heat recovery boiler, 110,000 lb/hr 650 psig steam, 30,000 lbm/hr 200 psig steam.
- c. Inlet air absorption chiller and heat exchanger.
- d. Turbine combustor steam injection system for NOx control.
- e. Selective catalytic reduction (SCR) system (for NOx control) utilizing ammonia as reducing agent.
- f. Engelhard carbon monoxide reactor 236.4 in. wide x 375.5 in. high x 18.0 in. deep with 104 catalyst modules.
- g. Continuously recording monitor for ammonia.
- h. Continuously recording monitors for O and NOx.
- i. Dollinger GP298-GTS-60 turbine lube oil mist eliminator.
- j. Dollinger AE129-660 generator lube oil mist eliminator.

OPERATIONAL CONDITIONS:

1. Gas turbine engine shall be fired exclusively with PUC-regulated quality natural gas. (Rule 220.1-BACT)
2. Gas turbine engine steam injection rate shall be maintained at steam-to-fuel ratio documented to result in compliance with emission limits. (Rule 209)
3. Ammonia injection rate shall be controlled to maintain ammonia "breakthrough" to less than 20 ppmv. (Rule 419)
4. Fuel gas sulfur content shall not exceed 0.25 gr. H2S/100 scf without prior District approval. (Rule 220.1-BACT)

5. SO<sub>2</sub> exhaust stack concentration shall not exceed 0.015% by volume and NO<sub>2</sub> exhaust stack concentration shall not exceed 0.0108% by volume at 15% oxygen on dry basis. (Rule 422)
6. Live Oak Limited shall maintain accurate records of sulfur content in fuel gas and make such records readily available for District inspection upon request. (Rule 422)
7. If steam injection or SCR system is inoperative, gas turbine engine shall be shut down. (Rule 209)
8. Inlet gas temperature to catalyst bed shall be maintained within range recommended by catalyst manufacturer. (Rule 209)
9. Gas turbine engine shall not burn more than 10.28 MM scf/day of natural gas. (Rule 220.1)
10. Temperature of exhaust flow through carbon monoxide reactor shall be no less than 760 deg. F. (Rule 209)
11. All gas turbine engine exhaust shall flow through catalyst bed. (Rule 220.1)
12. Gas turbine engine shall be equipped to burn PUC-regulated natural gas only. (Rule 220.1)
13. Gas turbine engine shall be equipped with continuously recording fuel gas flowmeter. (Rule 209)
14. Gas turbine engine combustor steam injection system shall be equipped with continuously recording steam-to-fuel injection rate monitoring system accurate to within  $\pm 5\%$ . (Rule 422)
15. Gas turbine exhaust shall be equipped with continuously recording O<sub>2</sub>, NO<sub>x</sub> and ammonia monitors. (Rule 209)
16. Circular cross section exhaust stack shall be equipped with permanent provisions to allow collection of stack gas samples consistent with EPA test methods and equipped with flow straighteners, if necessary, to minimize turbulence. (Rule 108.1)
17. Gas temperature at SCR catalyst section inlet shall be monitored by operational temperature indicator. (Rule 209)
18. Ammonia injection grid shall be equipped with operational ammonia flowmeter and injection pressure indicator. (Rule 209)
19. Installed SCR unit shall provide space for additional catalyst if source operation cannot achieve sampling limits. (Rule 209)
20. Gas turbine lube oil system atmospheric vent shall be equipped with aerosol/smoke control provisions. (Rule 209)
21. Live Oak Limited shall comply in full with Rule 422 (New Source Performance Standards) requirements including notification, recordkeeping and monitoring requirements. (Rule 422)
22. Continuous emission monitoring system for NO<sub>x</sub> (as NO<sub>2</sub>), NH<sub>3</sub>, and O<sub>2</sub> serving exhaust gas stream shall conform to Rule 108 specifications. (Rule 108)
23. Continuous emission monitoring systems shall be calibrated and operated according to EPA guidelines as specified in CFR, Part 60, Appendix B. (Rule 108)
24. Audits of monitors shall be conducted semi-annually by independent laboratory in accordance with EPA guidelines, witnessed by District, and reports shall be submitted to District within 30 days of such audit. (Rule 108)
25. Live Oak continuous emission monitoring printouts shall be made readily available for District inspection upon request. (Rule 108)



LIVE OAK LIMITED  
PERMIT #4213001B  
PAGE 3

26. Live Oak Limited shall keep accurate records of daily fuel consumption of gas turbine engine and shall make them readily available for District inspection upon request. (Rule 209)
27. Steam produced at this facility for use in oil-production operations shall be injected only into strata for which all wells are connected to District-authorized well vent vapor control system(s). (Rules 220.1 & 485.1)
28. Noncompliance with emission limit(s) requires immediate shutdown or curtailment to effect compliance. Installation of additional control provisions or increase in emission limit(s) requires modified Authority to Construct before continued operation at non-complying levels. Pursuant to Section 42350 of California Health and Safety Code, a variance from this condition cannot be obtained. (Rule 209)
29. Live Oak Limited shall monitor and records exhaust gas temperature at oxidation catalyst inlet, and if average temperature exceeds 800 deg. F., shall establish catalyst hydrocarbon control satisfies BACT requirement. (Rule 220.1)
30. This Authority to Construct cancels and replaces Authority to Construct #4213001. (Rule 220.1)

#### COMPLIANCE TESTING REQUIREMENTS:

Compliance with all emission sampling limits shall be demonstrated by District-witnessed sample collection by independent testing laboratory within 60 days after start-up of this equipment. Compliance with sulfur compounds emission sampling limits shall be demonstrated by fuel gas sulfur analysis, and compliance with oxides of nitrogen, VOC, carbon monoxide and ammonia emission sampling limits shall be demonstrated by District-witnessed sample collection by independent testing laboratory annually 60 days prior to permit anniversary date. Lube oil vent emission rate shall be tested if five percent opacity or greater visible emissions are exhibited. Official test results and field data shall be submitted to District within 30 days after collection. (Rule 108.1)

#### EMISSION SAMPLING LIMITS: Total for turbine exhaust plus lube oil vent

|                                          |                                                                                                                                                                  |
|------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <u>Particulates (PM-10):</u>             | 2.76 lbm/hr (Rule 220.1)                                                                                                                                         |
| <u>Sulfur Compounds:</u>                 | 0.29 lbm/hr (of SO <sub>2</sub> ) (Rule 220.1)                                                                                                                   |
|                                          | 0.10 lbm/hr (of SO <sub>4</sub> ) (Rule 220.1)                                                                                                                   |
| <u>Oxides of Nitrogen:</u>               | 5.78 lbm/hr (as NO <sub>2</sub> ) (Rule 220.1)                                                                                                                   |
|                                          | 0.0127 lbm/MM Btu (as NO <sub>2</sub> ) (Rule 220.1-BACT req.)                                                                                                   |
| <u>Volatile Organic Compounds (VOC):</u> | 0.58 lbm/hr (including lube oil cooler (accumulating vent(s)) (Rule 220.1)                                                                                       |
|                                          | 0.576 ppmv dry at 15% O <sub>2</sub> (as CH <sub>4</sub> ) (Rule 220.1-BACT req.) (Only if catalyst inlet temperature exceeds 800 deg. F., see special cond. ii) |
| <u>Carbon Monoxide:</u>                  | 10.90 lbm/hr (Rule 220.1)                                                                                                                                        |
| <u>Ammonia:</u>                          | 20.0 ppmv (Rule 419)                                                                                                                                             |

LIVE OAK LIMITED  
PERMIT #4213001B  
GE 4

WARNING:

Failure of carbon monoxide reactor or SCR catalyst to perform as required because of catalyst poisoning or fouling shall not be recognized as basis for Rule 111 enforcement exemption. (Rule 111)

STATE OF CALIFORNIA AIR TOXICS HOT SPOTS REQUIREMENTS:

Facility shall comply with California Health and Safety Code Sections 44300 through 4384. (Rule 208.1)

STATIONARY SOURCE CURTAILMENT PLANS AND TRAFFIC ABATEMENT PLANS:

Facilities expected to emit 100 tons per year or more of carbon monoxide, hydrocarbons, PM-10 or oxides of nitrogen shall comply with SJVUAPCD Rule 613.

RULE 220.1 (NSR) ANALYSIS VALIDATION:

Maximum daily emission rate of all air contaminants from this permit unit shall not exceed the following daily emission limitations:

|                                          |                                                                                                    |
|------------------------------------------|----------------------------------------------------------------------------------------------------|
| <u>Particulates (PM-10):</u>             | 68.29 lbm/day (Rule 220.1)                                                                         |
| <u>Sulfur Compounds:</u>                 | 6.90 lbm/day (of SO <sub>2</sub> ) (Rule 220.1)<br>2.30 lbm/day (of SO <sub>3</sub> ) (Rule 220.1) |
| <u>Oxides of Nitrogen:</u>               | 138.66 lbm/day (as NO <sub>2</sub> ) (Rule 220.1)                                                  |
| <u>Volatile Organic Compounds (VOC):</u> | 14.00 lbm/day (Rule 220.1)                                                                         |
| <u>Carbon Monoxide:</u>                  | 261.36 lbm/day (Rule 220.1)                                                                        |

Compliance with these emission limits shall be verified by source operator on daily basis and written documentation made readily available to District for period of one year.



San Joaquin Valley  
Unified Air Pollution Control District

## PERMIT TO OPERATE

PERMIT NO.: 4213001C

EXPIRATION DATE: APRIL 30, 1993

LEGAL OWNER OR OPERATOR: LIVE OAK LIMITED  
(Destec Energy Incorporated, Managing General Partner)  
MAILING ADDRESS: 4800 Easton Drive, Suite 114  
Bakersfield, California 93309

EQUIPMENT LOCATION: NW/4 Sec. 18, T28S, R28E  
Kern River Oil Field

EQUIPMENT DESCRIPTION:  
Gas-Fired 48 Megawatt Cogeneration Facility

### CONDITIONS

---

1. Stewart & Stevenson GE LM-5000 gas turbine generator system shall have a capacity of no greater than 48 MW and a heat input rating of no greater than 453 MMBtu/hr. (Rule 2010)
2. Turbine shall be equipped with heat recovery boiler, 110,000 lb/hr 650 psig steam, 30,000 lb/hr 200 psig steam. (Rule 2010)
3. Turbine shall be equipped with inlet air absorption chiller and heat exchanger. (Rule 2010)
4. Turbine shall be equipped with turbine combustor steam injection system for NOx control. (Rule 2010)
5. Unfired heat recovery boiler shall be equipped with selective catalytic reduction (SCR) system (for NOx control) utilizing ammonia as reducing agent. (Rule 2010)
6. Unfired heat recovery boiler shall be equipped with Engelhard carbon monoxide reactor 236.4 in. wide x 375.5 in. high x 18.0 in. deep with 104 catalyst modules. (Rule 2010)

(CONDITIONS CONTINUE ON THE NEXT PAGE)

This Permit to Operate remains valid through the permit expiration date listed above, subject to payment of annual permit fees and compliance with permit conditions and all applicable local, state, and federal regulations. This permit is valid only at the location specified above, and becomes void upon any transfer of ownership or location. Any modification of the equipment or operation, as defined in District Rule 220.1, will require a new permit. This permit shall be posted as prescribed in District Rule 2010.

DAVID L. CROW

Executive Director / APCO

Southern Regional Office \* 2700 M Street, Suite 275 \* Bakersfield, California 93301 \* (805) 861-3682 \* FAX (805) 861-2060

7. Unfired heat recovery boiler exhaust shall be equipped with continuously recording monitor for ammonia. (Rule 2010)
8. Unfired heat recovery boiler exhaust shall be equipped with continuously recording monitors for  $O_2$  and  $NO_x$ . (Rule 2010)
9. Turbine lube oil vent shall be equipped with R. K. Chase turbine lube oil vent demister. (Rule 2010)
10. Turbine lube oil reservoir shall be equipped with R. K. Chase turbine lube oil reservoir demister. (Rule 2010)
11. Turbine generator shall be equipped with Dollinger AE129-660 generator lube oil mist eliminator. (Rule 2010)
12. No emission shall cause injury, detriment, nuisance or annoyance or endanger the comfort, repose, health or safety of any persons or have a natural tendency to cause injury or damage to business or property. (Rule 4002)
13. There shall be no odors detectable at or beyond property boundary. (Rule 4002)
14. Gas turbine engine shall be equipped to burn PUC-regulated quality natural gas only. (Rule 220.1)
15. Gas turbine engine shall be equipped with continuously recording fuel gas flowmeter. (Rule 220.1)
16. Gas turbine engine combustor steam injection system shall be equipped with continuously recording steam-to-fuel injection rate monitoring system accurate to within  $\pm 5\%$ . (Rule 422)
17. Gas turbine exhaust shall be equipped with continuously recording  $O_2$ ,  $NO_x$  and ammonia monitors. (Rules 220.1 & 4002)
18. Circular cross section exhaust stack shall be equipped with permanent provisions to allow collection of stack gas samples consistent with EPA test methods and equipped with flow straighteners, if necessary, to minimize turbulence. (Rule 108.1)
19. Gas temperature at SCR catalyst section inlet shall be monitored by operational temperature indicator. (Rule 220.1)
20. Ammonia injection grid shall be equipped with operational ammonia flowmeter and injection pressure indicator. (Rule 220.1)
21. Installed SCR unit shall provide space for additional catalyst if source operation cannot achieve sampling limits. (Rule 220.1)
22. Gas turbine lube oil system atmospheric vent shall be equipped with aerosol/smoke control provisions. (Rule 4001)
23. Gas turbine engine shall be fired exclusively with PUC-regulated quality natural gas. (Rule 220.1 - BACT requirement)
24. Gas turbine engine steam injection rate shall be maintained at steam-to-fuel ratio documented to result in compliance with emission limits. (Rule 220.1)
25. Ammonia injection rate shall be controlled to maintain ammonia "breakthrough" to less than 20 ppmv. (Rule 4002)
26. Fuel gas sulfur content shall not exceed 0.25 gr.  $H_2S$ /100 scf without prior District approval. (Rule 220.1 - BACT requirement)
27.  $SO_2$  exhaust stack concentration shall not exceed 0.015% by volume and  $NO_2$  exhaust stack concentration shall not exceed 0.0108% by volume at 15% oxygen on dry basis. (Rule 422)

28. Live Oak Limited shall maintain accurate records of sulfur content in fuel gas and make such records readily available for District inspection upon request. (Rule 422)
29. If steam injection or SCR system is inoperative, gas turbine engine shall be shut down. (Rule 220.1)
30. Inlet gas temperature to catalyst bed shall be maintained within range recommended by catalyst manufacturer. (Rule 220.1)
31. Gas turbine engine shall not burn more than 10.28 MM scf/day of natural gas. (Rule 220.1)
32. Temperature of exhaust flow through carbon monoxide reactor shall be not less than 760 deg. F. (Rule 220.1)
33. All gas turbine engine exhaust shall flow through catalyst bed. (Rule 220.1)
34. Live Oak Limited shall comply in full with Rule 422 (New Source Performance Standards) requirements including notification, recordkeeping and monitoring requirements. (Rule 422)
35. Continuous emission monitoring system for NO<sub>x</sub> (as NO<sub>2</sub>), NH<sub>3</sub>, and O<sub>2</sub> serving exhaust gas stream shall conform to Rule 1080 specifications. (Rule 1080)
36. Continuous emission monitoring systems shall be calibrated and operated according to EPA guidelines as specified in CFR, Part 60, Appendix B. (Rule 1080)
37. Audits of monitors shall be conducted semiannually by independent laboratory in accordance with EPA guidelines, witnessed by District, and reports shall be submitted to District within 30 days of such audit. (Rule 1080)
38. Live Oak Limited continuous emission monitoring printouts shall be made readily available for District inspection upon request. (Rule 1080)
39. Live Oak Limited shall keep accurate records of daily fuel consumption of gas turbine engine and shall make them readily available for District inspection upon request. (Rule 220.1)
40. Steam produced at this facility for use in oil-production operations shall be injected only into strata for which all wells are connected to District-authorized well vent vapor control system(s). (Rules 220.1 & 465.1)
- ✓ 41. Noncompliance with emission limit(s) requires immediate shutdown or curtailment to effect compliance. Variance from this condition cannot be obtained. (C. H. & S. C. Section 42350)
42. Installation of additional control provisions or increase in emission limit(s) requires modified Authority to Construct before continued operation at non-complying levels. (Rule 220.1)
43. Live Oak Limited shall monitor and record exhaust gas temperature at oxidation catalyst inlet, and if average temperature exceeds 800 deg. F, shall establish catalyst hydrocarbon control satisfies BACT requirement. (Rule 220.1)
44. Failure of carbon monoxide reactor or SCR catalyst to perform as required because of catalyst poisoning or fouling shall not be recognized as basis for Rule 1100 enforcement exemption. (Rule 1100)
45. Emission sampling limits of particulates (PM<sub>10</sub>), total for turbine exhaust ~~plus tube oil vent~~, shall not exceed 0.0061 lbm PM<sub>10</sub>/MMBtu. (Rule 220.1) *MRB*
46. Emission sampling limits of sulfur compounds, total for turbine exhaust ~~plus tube oil vent~~, shall not exceed 0.0006 lbm SO<sub>2</sub>/MMBtu or 0.0002 lbm SO<sub>4</sub>/MMBtu. (Rule 220.1) *MRB*
47. Emission sampling limits of oxides of nitrogen, total for turbine exhaust ~~plus tube oil vent~~, shall not exceed 3.6 ppmv dry at 15% O<sub>2</sub> (as NO<sub>2</sub>). (Rule 220.1) *MRB*

48. Emission sampling limits of volatile organic compounds (VOC), total for turbine exhaust plus lube oil vent, shall not exceed 0.6 ppmv dry at 15% O<sub>2</sub> (as CH<sub>4</sub>). (Rule 220.1-BACT req.) (Only if catalyst inlet temperature exceeds 800 deg. F, see condition 43)
49. Emission sampling limits of carbon monoxide, total for turbine exhaust ~~plus lube oil vent~~ <sup>MRB</sup>, shall not exceed 11 ppmv dry at 15% O<sub>2</sub>. (Rule 220.1)
50. Emission sampling limits of ammonia, total for turbine exhaust ~~plus lube oil vent~~ <sup>MRB</sup>, shall not exceed 20.0 ppmv. (Rule 4002)
51. Emission of each air contaminant from this operation shall not exceed the following:  
(Rule 220.1)

## Pounds Per Calendar Quarter

|                   | <u>IAN - MAR</u> | <u>APR - JUN</u> | <u>JUL - SEP</u> | <u>OCT - DEC</u> |
|-------------------|------------------|------------------|------------------|------------------|
| PM <sub>10</sub>  | 5,966            | 6,032            | 6,099            | 6,099            |
| NO <sub>x</sub> : | 12,479           | 12,618           | 12,757           | 12,757           |
| VOC:              | 1,260            | 1,274            | 1,288            | 1,288            |

52. Compliance with all emission sampling limits shall be demonstrated by District-witnessed sample collection by independent testing laboratory within 60 days after startup of this equipment. Compliance with sulfur compounds emission sampling limits shall be demonstrated by fuel gas sulfur analysis, and compliance with oxides of nitrogen, VOC, carbon monoxide and ammonia emission sampling limits shall be demonstrated by District-witnessed sample collection by independent testing laboratory annually 60 days prior to permit anniversary date. Lube oil vent emission rate shall be tested if five percent opacity or greater visible emissions are exhibited. Official test results and field data shall be submitted to District within 30 days after collection.  
(Rule 108.1)