

TABLE OF CONTENTS

I. SUMMARY OF RESULTS	4
II. INTRODUCTION	8
III. METHOD 5 DATA	11
A. Turbine #1	12
B. Turbine #2	14
IV. HYDROCARBON DATA	16
A. Summary of Hydrocarbon Results (Turbine #1 & #2)	17
B. Turbine #1 Results	
1. Summary	18
2. Turbine #1 Main Stack	19
3. Lube Oil Vent Generator #1	21
4. Lube Oil Vent Turbine #1	24
C. Turbine #2 Results	
1. Summary	27
2. Turbine #2 Main Stack	28
3. Lube Oil Vent Generator #2	30
4. Lube Oil Vent Turbine #2	33
D. Non Condensable Hydrocarbon Detection Limits	36
V. SULFUR EMISSIONS	37
A. Turbine #1 Emissions	38
B. Turbine #2 Emissions	39
VI. RELATIVE ACCURACY	40
A. Turbine #1 RATA	41
B. Turbine #2 RATA	44
C. Destec CEM Summary	47
D. Reference Method Turbine #1	48
E. Reference Method Turbine #2	61

TABLE OF CONTENTS (con't)

VII. EMISSION FACTORS (lbs/MMBtu)	72
A. Turbine #1 - NOx & CO	73
B. Turbine #2 - NOx & CO	74
VIII. FUEL GAS ANALYSIS	75
IX. METHODS & EQUATIONS	79
 APPENDICES	
I. OPERATIONAL DATA (Supplied by Destec)	92
A. CEM Data	93
B. Fuel Data	100
II. RAW DATA	103
A. Method 5 Field Data	104
B. Method 5 Lab Data	116
C. Method 1-4 Field Data	120
D. Method 1-4 Lab Data	136
E. Hydrocarbon Chromatograms	140
F. Instrument Strip Charts	163
III. QUALITY ASSURANCE	175
A. Chain of Custody Records	176
B. Equipment Calibration	182
C. CEM Calibration Gases	186
D. Wet Test Methods Field Blanks	189
E. Hydrocarbon Linearities	197
IV. CORRESPONDENCE	229

SUMMARY OF RESULTS

SUMMARY OF SOURCE TEST RESULTS

COMPANY: **DESTEC - DOUBLE C**

APCD #: 4165001 (B)

TEST DATE: FEBRUARY 9 - 12, 1993 & FEBRUARY 26, 1993

UNIT #: TURBINE #1

EMISSIONS	gr/scf	@12%CO2	ppm	ppm @15% O2	lb/ MMBtu	lb/hr	lb/day	Permit Limits
PARTICULATE	0.00148 0.00114	0.00604 0.00477				1.75 1.39	42.0 33.4	
Mean:	0.00131	0.00541				1.57	37.7	3.12 lb/hr
SULFUR			in fuel < 1.0 as H2S			in exhaust	in exhaust	
Mean:						< 0.0188	< 0.451	0.16 lb/hr
NOx (dry) (RUNS 1-12)								
Mean:			2.48	2.09	0.00761	2.03	48.7	0.0182 lb/MMBtu 4.04 lb/hr
CO (RUNS 1-12)								
Mean:			45.3	38.1	0.0847	22.6	542	27.83 lb/hr
NMHC turbine plus 2 lube oil vents								
Mean:						1.67	40.2	3.12 lb/hr
RELATIVE ACCURACY	% RA Related to Reference Method		% RA Related to Applicable Standard			PERMIT LIMITS		
						Related to Reference Method	Related to Applicable Standard	
	NOx		NA			20 %	NA	
	CO		NA			10 %	NA	
	O2		NA			20 %	NA	

For San Joaquin Unified APCD Use Only:

SUMMARY OF SOURCE TEST RESULTS

COMPANY: **DESTEC - DOUBLE C**

TEST DATE: **FEBRUARY 9 - 12, 1993**

APCD #: **4165002 (B)**

UNIT #: **TURBINE #2**

EMISSIONS	gr/scf	@12%CO2	ppm	ppm @15% O2	lb/ MMBtu	lb/hr	lb/day	Permit Limits
PARTICULATE	0.00129 0.00199	0.00547 0.00822				1.56 2.42	37.4 58.1	
Mean:	0.00164	0.00685				1.99	47.8	3.12 lb/hr
SULFUR			in fuel < 1.0 as H2S			in exhaust	in exhaust	
Mean:						< .01995	< 0.479	0.16 lb/hr
NOx (dry) (RUNS 1-12)								
Mean:			2.94	2.51	0.00915	2.51	60.2	0.0162 lb/MMBtu 4.04 lb/hr
CO (RUNS 1-12)								
Mean:			45.0	38.3	0.08505	23.3	569	27.83 lb/hr
NMHC turbine plus 2 lube oil vents								
Mean:						1.97	47.3	3.12 lb/hr
RELATIVE ACCURACY	% RA Related to Reference Method		% RA Related to Applicable Standard			PERMIT LIMITS		
						Related to Reference Method	Related to Applicable Standard	
	NOx		NA			20 %	NA	
	CO		NA			10 %	NA	
	O2		NA			20 %	NA	

For San Joaquin Unified APCD Use Only:

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINES 1 & 2 AND LUBE OIL VENTS
 DATE : 02-11-93 & 02-26-93
 REPORT : 027-341

SUMMARY OF HYDROCARBONS RESULTS

	gr/scf	ppm	lbs/hr	lbs/day
TURBINE #1				
NON-CONDENSABLE	---	5.78	1.67	40.16
TOTAL HYDROCARBONS	---	---	1.67	40.16
TURBINE #2				
NON-CONDENSABLE	---	6.61	1.97	47.20
TOTAL HYDROCARBONS	---	---	1.97	47.20
LOV GENERATOR 1				
CONDENSABLE	0.01070	---	0.00195	0.0466
NON-CONDENSABLE	---	0.0000	0.0000	0.0000
TOTAL HYDROCARBONS	---	---	0.00195	0.0466
LOV TURBINE 1				
CONDENSABLE	0.02222	---	0.00060	0.0144
NON-CONDENSABLE	---	0.000	0.00000	0.0000
TOTAL HYDROCARBONS	---	---	0.00060	0.0144
LOV GENERATOR 2				
CONDENSABLE	0.00968	---	0.00183	0.0440
NON-CONDENSABLE	---	0.000	0.00000	0.0000
TOTAL HYDROCARBONS	---	---	0.00183	0.0440
LOV TURBINE 2				
CONDENSABLE	0.01516	---	0.00036	0.0085
NON-CONDENSABLE	---	0.907	0.000001	0.0002
TOTAL HYDROCARBONS	---	---	0.00036	0.0087
TOTAL EMISSIONS				
TURBINE #1 + LOVG 1 + LOVT 1			1.67	40.2
TURBINE #2 + LOVG 2 + LOVT 2			1.97	47.3

INTRODUCTION

INTRODUCTION

On February 9-12 and 26, 1993, Petro Chem Environmental Services, Inc. (PCES) performed a series of emission source tests for Destec Operating Company at their Double C Limited Cogeneration Facility located in Kern County, California. The units tested were two 25.0 MW GE LM-2500 gas fired turbine/generators and four lube oil vents; two per turbine.

Determination of concentrations (ppm) and emissions (lbs/hr) of particulate, sulfur, NMHC, NOx, CO, O₂, from the exhaust of the two turbine/generators and relative accuracy testing was performed for NOx, CO, and O₂ using the following procedures:

PARAMETERS	METHOD	# TEST RUNS PER TURBINE
Particulate	EPA Method 5; Gravimetric	2 - 6 hr.
Sulfur	Fuel Analysis / Fuel Rates EAS Labs	1
NMHC	EPA Method 18; (modified) C ₁ - C ₆₊	3
NOx	EPA Method 20; Chemiluminescent Analyzer equipped with Molydenum Convertor	Turbine #1 12 - 30 min. Turbine #2 10 - 30 min.
CO	EPA Method 10; Gas Filter Correlation Analyzer	Turbine #1 12 - 30 min. Turbine #2 10 - 30 min.
O ₂	EPA Method 20; Fuel Cell Analyzer	Turbine #1 12 - 30 min. Turbine #2 10 - 30 min.
Molecular Weight O ₂ , CO ₂ , N ₂	EPA Method 3; Orsat	2
Volume Flow DSCFM	EPA Method 2; Pitot Tube Traverse	2
Relative Accuracy NOx/ CO / O ₂	Title 40 CFR Performance Spec II, III, IV	Turbine #1 12 - 30 min. Turbine #2 10 - 30 min.

Each turbine was equipped with two lube oil vent (LOV) stacks; turbine LOV and generator LOV. Concentrations (ppm, gr/DSCF) and emissions (lb/hr, lb/day) of condensable and non condensable hydrocarbon emissions from the exhaust of the lube oil vent stacks were determined using the following procedures:

PARAMETERS	METHOD	# TEST RUNS/ LUBE OIL VENTS
Condensable Hydrocarbons	EPA Method 4; with Gravimetric Organic Extractions Utilizing CARB Method 5.4.3.1.	3
Non Condensable Hydrocarbons	EPA Method 18; Bag Sample FID Analysis	3
Volume Flow	EPA Method 2; Pitot Tube Or Hot Wire Anemometer	3
Molecular Weight	EPA Method 3; Orsat Analysis	3
% H ₂ O	EPA Method 4; Condensation	3

As per the permit to operate, emissions of hydrocarbons are expressed as the sum of the emissions from the turbine and it's two LOV stacks.

All sampling was performed by Doug Towne, Bob Martin, and Scott Harrison of Petro Chem Environmental Services, Inc. The hydrocarbons, fuel gas, PM, and organic analyses were performed by Terry Rowles of PCES. Scott Kicker of Destec Operating Company supervised the testing. Greg LaFore of San Joaquin Valley Unified APCD, Southern Region, was present and witnessed the testing.

METHOD 5 DATA

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 2/09-10/93
REPORT : 027-341

METHOD 1-5
FIELD DATA @ 60° F

	RUN #:	1	2
	TIME :	1033	840
Vm (dry gas sampled)		190.63	174.97
Y (meter calib. factor)		0.982977	0.982977
P bar (Barometric pressure)		28.49	29.24
P static (stack pressure, " H2O)		-0.7	-0.7
Delta H (differential meter press, " H2O)		0.67	0.61
Tm (meter temperature, R°)		529	527
Vol H2O mls		854.9	785.1
Vm(std),dscf		175.70 ✓	166.10
Bws-H2O vapor		0.1844 ✓	0.1801
MF-moisture factor		0.8156	0.8199
% CO2		3.6	3.5
% O2		13.8	13.9
% N2		82.6	82.6
Md-MW stk gas,dry		29.13	29.12
Ms-MW stk gas,wet		27.08 ✓	27.11
Cp-pitot tube		0.791	0.791
Avg sq rt ^p		1.03	1.05
T stack, R°		728	731
Stack area,ft2		50.004	50.004
Vs-fps		67.82	68.13
Qstd-dscfm		112679 ✓	116311
Area noz,ft2		2.01E-04	2.01E-04
Sample time		360	360
% Isokinetic		107.7	98.6

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 2/09-10/93
 REPORT : 027-341

EPA METHOD 5 DATA

@ 60°F

RUN #1

PARTICULATE RESULTS:	net mg	gr/dscf	gr/scf	gr/dscf @ 12% CO2	lbs/hr
Probe & Nozzle:	11.30	0.00099	0.00081	0.00330	0.958
Filter:	0.50	0.00004	0.00004	0.00015	0.042
Condensables:	8.88	0.00078	0.00063	0.00259	0.752
Total:	20.68	0.00181	0.00148	0.00604	1.752

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1033	1645	13.8	3.6	18.44	175.7	112679

RUN #2

PARTICULATE RESULTS:	net mg	gr/dscf	gr/scf	gr/dscf @ 12% CO2	lbs/hr
Probe & Nozzle:	7.40	0.00069	0.00056	0.00235	0.685
Filter:	0.30	0.00003	0.00002	0.00010	0.028
Condensables:	7.30	0.00068	0.00056	0.00232	0.676
Total:	15.00	0.00139	0.00114	0.00477	1.388

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
840	1453	13.9	3.5	18.01	166.1	116311

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 2/11-12/93
 REPORT : 027-341

METHOD 1-5
 FIELD DATA @ 60° F

	RUN #:	1	2
	TIME :	900	838
Vm (dry gas sampled)		172.78	171.79
Y (meter calib. factor)		0.982977	0.982977
P bar (Barometric pressure)		29.22	29.22
P static (stack pressure, " H2O)		-0.75	-0.75
Delta H (differential meter press, " H2O)		0.58	0.61
Tm (meter temperature, R°)		523	519
Vol H2O mls		725.7	735.4
Vm(std),dscf		165.15	165.49
Bws-H2O vapor		0.1695	0.1711
MF-moisture factor		0.8305	0.8289
% CO2		3.4	3.5
% O2		15	14.9
% N2		81.6	81.6
Md-MW stk gas,dry		29.14	29.16
Ms-MW stk gas,wet		27.25	27.25
Cp-pitot tube		0.791	0.791
Avg sq rt ^p		1.05	1.06
T stack, R°		738	738
Stack area,ft2		50.004	50.004
Vs-fps		68.49	68.94
Qstd-dscfm		117212	117743
Area noz,ft2		2.01E-04	2.01E-04
Sample time		360	360
% Isokinetic		97.3	97.1

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 2/11-12/93
 REPORT : 027-341

EPA METHOD 5 DATA

@ 60°F

RUN #1

PARTICULATE RESULTS:	net mg	gr/dscf	gr/scf	gr/dscf @ 12% CO2	lbs/hr
Probe & Nozzle:	7.30	0.00068	0.00057	0.00240	0.685
Filter:	0.40	0.00004	0.00003	0.00013	0.038
Condensables:	8.92	0.00083	0.00069	0.00294	0.837
Total:	16.62	0.00155	0.00129	0.00547	1.559

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
900	1521	15	3.4	16.95	165.15	117212

RUN #2

PARTICULATE RESULTS:	net mg	gr/dscf	gr/scf	gr/dscf @ 12% CO2	lbs/hr
Probe & Nozzle:	15.70	0.00146	0.00121	0.00501	1.476
Filter:	0.50	0.00005	0.00004	0.00016	0.047
Condensables:	9.55	0.00089	0.00074	0.00305	0.898
Total:	25.75	0.00240	0.00199	0.00822	2.421

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
838	1447	14.9	3.5	17.11	165.49	117743

HYDROCARBON DATA

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINES 1 & 2 AND LUBE OIL VENTS
 DATE : 02-11-93 & 02-26-93
 REPORT : 027-341

SUMMARY OF HYDROCARBONS RESULTS

	gr/scf	ppm	lbs/hr	lbs/day
TURBINE #1				
NON-CONDENSABLE	---	5.78	1.67	40.16
TOTAL HYDROCARBONS	---	---	1.67	40.16
TURBINE #2				
NON-CONDENSABLE	---	6.61	1.97	47.20
TOTAL HYDROCARBONS	---	---	1.97	47.20
LOV GENERATOR 1				
CONDENSABLE	0.01070	---	0.00195	0.0466
NON-CONDENSABLE	---	0.0000	0.0000	0.0000
TOTAL HYDROCARBONS	---	---	0.00195	0.0466
LOV TURBINE 1				
CONDENSABLE	0.02222	---	0.00060	0.0144
NON-CONDENSABLE	---	0.000	0.00000	0.0000
TOTAL HYDROCARBONS	---	---	0.00060	0.0144
LOV GENERATOR 2				
CONDENSABLE	0.00968	---	0.00183	0.0440
NON-CONDENSABLE	---	0.000	0.00000	0.0000
TOTAL HYDROCARBONS	---	---	0.00183	0.0440
LOV TURBINE 2				
CONDENSABLE	0.01516	---	0.00036	0.0085
NON-CONDENSABLE	---	0.907	0.000001	0.0002
TOTAL HYDROCARBONS	---	---	0.00036	0.0087
TOTAL EMISSIONS				
TURBINE #1 + LOVG 1 + LOVT 1			1.67	40.2
TURBINE #2 + LOVG 2 + LOVT 2			1.97	47.3

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1 & LUBE OIL VENTS
 DATE : 02-11-93 & 02-26-93
 REPORT : 027-341

SUMMARY OF HYDROCARBONS RESULTS

	gr/scf	ppm	lbs/hr	lbs/day
TURBINE #1 - MAIN STACK				
BLANK CORRECTED				
NON-CONDENSABLE				
RUN 1		6.68	1.93	46.32
RUN 2		5.44	1.58	37.92
RUN 3		5.23	1.51	36.24
AVERAGE		5.78	1.67	40.16
LOV GENERATOR 1				
CONDENSABLE				
RUN 1	0.00266		0.00051	0.0122
RUN 2	0.02525		0.00460	0.1103
RUN 3	0.00419		0.00073	0.0174
AVERAGE	0.01070		0.00195	0.0466
NON-CONDENSABLE				
RUN 1		0	0	0
RUN 2		0	0	0
RUN 3		0	0	0
AVERAGE		0	0	0
TOTAL HYDROCARBONS	---	---	0.00195	0.0466
LOV TURBINE 1				
CONDENSABLE				
RUN 1	0.01745		0.00047	0.0112
RUN 2	0.02758		0.00075	0.0180
RUN 3	0.02163		0.00059	0.0141
AVERAGE	0.02222		0.00060	0.0144
NON-CONDENSABLE				
RUN 1		0	0	0
RUN 2		0	0	0
RUN 3		0	0	0
AVERAGE		0	0	0
TOTAL HYDROCARBONS	---	---	0.00060	0.0144
TURBINE #1				
TOTAL EMISSIONS			1.67	40.22
MAIN STACK + LOVG + LOVT				

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 02-11-93
REPORT : 027-341

HYDROCARBON RESULTS
CORRECTED FOR METHOD BLANK

RUN No.: 1		114495 average of pitot tube velocity profiles			
		BLANK	ppm - BLANK	lb/hr	ppm (as Methane) lb/hr
Methane (C1)		0.29	67.57	19.57	67.57 19.57
Ethane (C2)		0.00	3.22	1.75	6.44 1.87
Propane (C3)		0.04	0.08	0.06	0.24 0.07
Butane (C4)		0.04	0.00	0.00	0.00 0.00
Pentane (C5)		0.12	0.00	0.00	0.00 0.00
Hexane (C6)		0.94	0.00	0.00	0.00 0.00
<u>Total</u>			<u>70.87</u>	<u>21.38</u>	<u>74.25</u> <u>21.50</u>
Total					
(non methane)			<u>3.30</u>	<u>1.81</u>	<u>6.68</u> <u>1.93</u>

RUN No.: 2					
		BLANK	ppm - BLANK	lb/hr	ppm (as Methane) lb/hr
Methane (C1)		0.29	66.91	19.38	66.91 19.38
Ethane (C2)		0.00	2.66	1.44	5.32 1.54
Propane (C3)		0.04	0.04	0.03	0.12 0.03
Butane (C4)		0.04	0.00	0.00	0.00 0.00
Pentane (C5)		0.12	0.00	0.00	0.00 0.00
Hexane (C6)		0.94	0.00	0.00	0.00 0.00
<u>Total</u>			<u>69.61</u>	<u>20.86</u>	<u>72.35</u> <u>20.95</u>
Total					
(non methane)			<u>2.70</u>	<u>1.48</u>	<u>5.44</u> <u>1.58</u>

RUN No.: 3					
		BLANK	ppm - BLANK	lb/hr	ppm (as Methane) lb/hr
Methane (C1)		0.29	65.77	19.05	65.77 19.05
Ethane (C2)		0.00	2.60	1.41	5.20 1.51
Propane (C3)		0.04	0.01	0.01	0.03 0.01
Butane (C4)		0.04	0.00	0.00	0.00 0.00
Pentane (C5)		0.12	0.00	0.00	0.00 0.00
Hexane (C6)		0.94	0.00	0.00	0.00 0.00
<u>Total</u>			<u>68.38</u>	<u>20.47</u>	<u>71.00</u> <u>20.56</u>
Total					
(non methane)			<u>2.61</u>	<u>1.42</u>	<u>5.23</u> <u>1.51</u>

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 02-11-93
REPORT : 027-341

HYDROCARBON RESULTS UNCORRECTED

UNCORRECTED

RUN No.:		1				
DSCFM:		114495	average of pitot tube velocity profiles			
			ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)		67.86	19.65	67.86	19.65
Ethane	(C2)		2.63	1.43	5.26	1.52
Propane	(C3)		0.12	0.10	0.36	0.10
Butane	(C4)	ND **	0.02	0.02	0.08	0.02
Pentane	(C5)	ND **	0.02	0.03	0.10	0.03
Hexane	(C6)		0.18	0.28	1.08	0.31
<u>Total</u>			<u>70.83</u>	<u>21.51</u>	<u>74.74</u>	<u>21.65</u>
Total						
(non methane)			<u>2.97</u>	<u>1.85</u>	<u>6.88</u>	<u>1.99</u>

RUN No.:		2				
			ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)		67.20	19.46	67.20	19.46
Ethane	(C2)		2.66	1.44	5.32	1.54
Propane	(C3)		0.08	0.06	0.24	0.07
Butane	(C4)	ND **	0.02	0.02	0.08	0.02
Pentane	(C5)	ND **	0.02	0.03	0.10	0.03
Hexane	(C6)		0.09	0.14	0.54	0.16
<u>Total</u>			<u>70.07</u>	<u>21.16</u>	<u>73.48</u>	<u>21.28</u>
Total						
(non methane)			<u>2.87</u>	<u>1.70</u>	<u>6.28</u>	<u>1.82</u>

RUN No.:		3				
			ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)		66.06	19.13	66.06	19.13
Ethane	(C2)		2.60	1.41	5.20	1.51
Propane	(C3)		0.05	0.04	0.15	0.04
Butane	(C4)	ND **	0.02	0.02	0.08	0.02
Pentane	(C5)	ND **	0.02	0.03	0.10	0.03
Hexane	(C6)		0.10	0.16	0.60	0.17
<u>Total</u>			<u>68.85</u>	<u>20.79</u>	<u>72.19</u>	<u>20.91</u>
Total						
(non methane)			<u>2.79</u>	<u>1.65</u>	<u>6.13</u>	<u>1.78</u>

** ND - Not Detected (See detection limits)

COMPANY : DESTEC
 UNIT : DOUBLE C - LUBE OIL VENT GENERATOR 1
 DATE : 02-11-93
 REPORT : 027-341

FIELD DATA @ 60°F

	RUN #:	1	2	3
	TIME:	1058	1145	1234
Vm (dry gas sampled)		24.0	24.05	24.0
Y (meter calib. factor)		0.998954	0.998954	0.998954
P bar (Barometric pressure)		29.22	29.22	29.22
P static (stack pressure, " H2O)		0	0	0
Delta H (differential meter press, " H2O)		0.45	0.59	0.61
Tm (meter temperature, R°)		532.13	532.56	532.06
Vol H2O mls		4.9	5	5.2
Vm(std), dscf		22.91	22.94	22.92
Bws-H2O vapor		0.0098	0.0100	0.0104
MF-moisture factor		0.9902	0.9900	0.9896
% CO2		0	0	0
% O2		20.9	20.9	20.9
% N2		79.1	79.1	79.1
Md-MW stk gas, dry		28.84	28.84	28.84
Ms-MW stk gas, wet		28.73	28.73	28.73
T stack, R°		556.38	555.88	553.13
Stack area, ft2		0.060	0.060	0.060
Vs-fpm, hot wire anemometer		393.75	380.63	371.25
Q-acfm		23.6	22.8	22.3
Qstd-dscfm		22	21	20
Sample time		40	40	40

COMPANY : DESTEC
 UNIT : DOUBLE C - LUBE OIL VENT GENERATOR 1
 DATE : 2-11-93
 REPORT : 027-341

EPA METHOD 4 DATA
 @ 60°F

RUN #1

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	4.00	0.00269	0.00266	0.00051	0.0122

ADDITIONAL DATA:
 TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1058	1138	20.9	0	0.98	22.91	22

RUN #2

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	37.99	0.02550	0.02525	0.00460	0.1103

ADDITIONAL DATA:
 TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1145	1225	20.9	0	1	22.94	21

RUN #3

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	6.30	0.00423	0.00419	0.00073	0.0174

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1234	1314	20.9	0	1.04	22.92	20

COMPANY : DESTEC
UNIT : DOUBLE C - LUBE OIL VENT GENERATOR 1
DATE : 02-11-93
REPORT : 027-341

NON CONDENSABLE
HYDROCARBON RESULTS

RUN No.: 1		DSCFM: 22			
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	2.646	0.000	2.646	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>2.646</u>	<u>0.000</u>	<u>2.646</u>	<u>0.000</u>
Total (non methane)		<u>0.000</u>	<u>0.000</u>	<u>0.000</u>	<u>0.000</u>

RUN No.: 2		DSCFM: 21			
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	2.451	0.000	2.451	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>2.451</u>	<u>0.000</u>	<u>2.451</u>	<u>0.000</u>
Total (non methane)		<u>0.000</u>	<u>0.000</u>	<u>0.000</u>	<u>0.000</u>

RUN No.: 3		DSCFM: 20			
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	2.826	0.0001	2.826	0.0001
Ethane	(C2)	0.000	0.0000	0.000	0.0000
Propane	(C3)	0.000	0.0000	0.000	0.0000
Butane	(C4)	0.000	0.0000	0.000	0.0000
Pentane	(C5)	0.000	0.0000	0.000	0.0000
Hexane	(C6)	0.000	0.0000	0.000	0.0000
<u>Total</u>		<u>2.826</u>	<u>0.0001</u>	<u>2.826</u>	<u>0.0001</u>
Total (non methane)		<u>0.000</u>	<u>0.0000</u>	<u>0.000</u>	<u>0.0000</u>

COMPANY : DESTEC
UNIT : DOUBLE C - LUBE OIL VENT TURBINE 1
DATE : 02-26-93
REPORT : 027-341

FIELD DATA @ 60°F

	RUN #:	1	2	3
	TIME:	1043	1125	1208
Vm (dry gas sampled)		24.12	23.97	24.15
Y (meter calib. factor)		0.982977	0.982977	0.982977
P bar (Barometric pressure)		29.3	29.3	29.3
P static (stack pressure, " H2O)		0	0	0
Delta H (differential meter press, " H2O)		0.6	0.6	0.6
Tm (meter temperature, R°)		519.94	527.81	526.13
Vol H2O mls		11.6	11.8	11.5
Vm(std),dscf		23.26	22.77	23.01
Bws-H2O vapor		0.0226	0.0235	0.0227
MF-moisture factor		0.9774	0.9765	0.9773
% CO2		0	0	0
% O2		20.9	20.9	20.9
% N2		79.1	79.1	79.1
Md-MW stk gas,dry		28.84	28.84	28.84
Ms-MW stk gas,wet		28.59	28.59	28.59
T stack, R°		536.88	534	534
Stack area,ft2		0.060	0.060	0.060
Vs-fpm, hot wire anemometer		53.75	54.125	54.125
Q-acfm		3.23	3.25	3.25
Qstd-dscfm		3.06	3.10	3.10
Sample time		40	40	40

COMPANY : DESTEC
 UNIT : DOUBLE C - LUBE OIL VENT TURBINE 1
 DATE : 02-26-93
 REPORT : 027-341

EPA METHOD 4 DATA
@ 60°F

RUN #1

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	26.96	0.01785	0.01745	0.00047	0.0112

ADDITIONAL DATA:
 TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1043	1123	20.9	0	2.26	23.26	3.06

RUN #2

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	41.76	0.02824	0.02758	0.00075	0.0180

ADDITIONAL DATA:
 TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1125	1205	20.9	0	2.35	22.77	3.10

RUN #3

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	33.07	0.02213	0.02163	0.00059	0.0141

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1208	1248	20.9	0	2.27	23.01	3.10

COMPANY : DESTEC
UNIT : DOUBLE C - LUBE OIL VENT TURBINE 1
DATE : 02-26-93
REPORT : 027-341

NON CONDENSABLE HYDROCARBON RESULTS

RUN No.: 1					
DSCFM: 3.06					
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	3.127	0.000	3.127	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>3.127</u>	<u>0.000</u>	<u>3.127</u>	<u>0.000</u>
Total					
(non methane)		<u>0.000</u>	<u>0.000</u>	<u>0.000</u>	<u>0.000</u>

RUN No.: 2					
DSCFM: 3.10					
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	58.708	0.000	58.708	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>58.708</u>	<u>0.000</u>	<u>58.708</u>	<u>0.000</u>
Total					
(non methane)		<u>0.000</u>	<u>0.000</u>	<u>0.000</u>	<u>0.000</u>

RUN No.: 3					
DSCFM: 3.10					
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	4.887	0.000	4.887	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>4.887</u>	<u>0.000</u>	<u>4.887</u>	<u>0.000</u>
Total					
(non methane)		<u>0.000</u>	<u>0.000</u>	<u>0.000</u>	<u>0.000</u>

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2 & LUBE OIL VENTS
 DATE : 02-11-93 & 02-26-93
 REPORT : 027-341

SUMMARY OF HYDROCARBONS RESULTS

	gr/scf	ppm	lbs/hr	lbs/day
TURBINE #2 - MAIN STACK				
BLANK CORRECTED				
NON-CONDENSABLE				
RUN 1		6.80	2.02	48.48
RUN 2		6.58	1.96	47.04
RUN 3		6.45	1.92	46.08
AVERAGE		6.61	1.97	47.20
LOV GENERATOR 2				
CONDENSABLE				
RUN 1	0.00655		0.00125	0.0301
RUN 2	0.01554		0.00297	0.0713
RUN 3	0.00696		0.00127	0.0305
AVERAGE	0.00968		0.00183	0.0440
NON-CONDENSABLE				
RUN 1		0	0	0
RUN 2		0	0	0
RUN 3		0	0	0
AVERAGE		0	0	0
TOTAL HYDROCARBONS	---	---	0.00183	0.0440
LOV TURBINE 2				
CONDENSABLE				
RUN 1	0.01516		0.00034	0.0081
RUN 2	0.01384		0.00034	0.0081
RUN 3	0.01649		0.00039	0.0094
AVERAGE	0.01516		0.00036	0.0085
NON-CONDENSABLE				
RUN 1		2.720	0.00002	0.0005
RUN 2		0	0	0
RUN 3		0	0	0
AVERAGE		0.906556	0.0000066	0.00016
TOTAL HYDROCARBONS	---	---	0.00036	0.0087
TURBINE #2				
TOTAL EMISSIONS			1.97	47.25
MAIN STACK + LOVG + LOVT				

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #2
DATE : 02-11-93
REPORT : 027-341

HYDROCARBON RESULTS
CORRECTED FOR METHOD BLANK

RUN No.: 1		117478 average of pitot tube velocity profiles				
		BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	0.29	79.18	23.53	79.18	23.53
Ethane	(C2)	0.00	3.22	1.79	6.44	1.91
Propane	(C3)	0.04	0.12	0.10	0.36	0.11
Butane	(C4)	0.04	0.00	0.00	0.00	0.00
Pentane	(C5)	0.12	0.00	0.00	0.00	0.00
Hexane	(C6)	0.94	0.00	0.00	0.00	0.00
<u>Total</u>			<u>82.52</u>	<u>25.42</u>	<u>85.98</u>	<u>25.55</u>
<u>Total</u>						
<u>(non methane)</u>			<u>3.34</u>	<u>1.89</u>	<u>6.80</u>	<u>2.02</u>
RUN No.: 2						
		BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	0.29	79.86	23.73	79.86	23.73
Ethane	(C2)	0.00	3.11	1.73	6.22	1.85
Propane	(C3)	0.04	0.12	0.10	0.36	0.11
Butane	(C4)	0.04	0.00	0.00	0.00	0.00
Pentane	(C5)	0.12	0.00	0.00	0.00	0.00
Hexane	(C6)	0.94	0.00	0.00	0.00	0.00
<u>Total</u>			<u>83.09</u>	<u>25.56</u>	<u>86.44</u>	<u>25.69</u>
<u>Total</u>						
<u>(non methane)</u>			<u>3.23</u>	<u>1.83</u>	<u>6.58</u>	<u>1.96</u>
RUN No.: 3						
		BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	0.29	75.93	22.56	75.93	22.56
Ethane	(C2)	0.00	3.06	1.71	6.12	1.82
Propane	(C3)	0.04	0.11	0.09	0.33	0.10
Butane	(C4)	0.04	0.00	0.00	0.00	0.00
Pentane	(C5)	0.12	0.00	0.00	0.00	0.00
Hexane	(C6)	0.94	0.00	0.00	0.00	0.00
<u>Total</u>			<u>79.10</u>	<u>24.36</u>	<u>82.38</u>	<u>24.48</u>
<u>Total</u>						
<u>(non methane)</u>			<u>3.17</u>	<u>1.79</u>	<u>6.45</u>	<u>1.92</u>

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #2
DATE : 02-11-93
REPORT : 027-341

HYDROCARBON RESULTS
UNCORRECTED

RUN No.: 1		DSCFM: 117478 average of pitot tube velocity profiles			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	79.47	23.62	79.47	23.62
Ethane	(C2)	3.22	1.79	6.44	1.91
Propane	(C3)	0.16	0.13	0.48	0.14
Butane	(C4) ND **	0.02	0.02	0.08	0.02
Pentane	(C5) ND **	0.02	0.03	0.10	0.03
Hexane	(C6)	0.13	0.21	0.78	0.23
<u>Total</u>		<u>83.02</u>	<u>25.80</u>	<u>87.35</u>	<u>25.96</u>
<u>Total</u>					
<u>(non methane)</u>		<u>3.55</u>	<u>2.18</u>	<u>7.88</u>	<u>2.34</u>
RUN No.: 2					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	80.15	23.82	80.15	23.82
Ethane	(C2)	3.11	1.73	6.22	1.85
Propane	(C3)	0.16	0.13	0.48	0.14
Butane	(C4) ND **	0.02	0.02	0.08	0.02
Pentane	(C5) ND **	0.02	0.03	0.10	0.03
Hexane	(C6)	0.13	0.21	0.78	0.23
<u>Total</u>		<u>83.59</u>	<u>25.94</u>	<u>87.81</u>	<u>26.09</u>
<u>Total</u>					
<u>(non methane)</u>		<u>3.44</u>	<u>2.12</u>	<u>7.66</u>	<u>2.28</u>
RUN No.: 3					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	76.22	22.65	76.22	22.65
Ethane	(C2)	3.06	1.71	6.12	1.82
Propane	(C3)	0.15	0.12	0.45	0.13
Butane	(C4) ND **	0.02	0.02	0.08	0.02
Pentane	(C5) ND **	0.02	0.03	0.10	0.03
Hexane	(C6)	0.14	0.22	0.84	0.25
<u>Total</u>		<u>79.61</u>	<u>24.75</u>	<u>83.81</u>	<u>24.91</u>
<u>Total</u>					
<u>(non methane)</u>		<u>3.39</u>	<u>2.10</u>	<u>7.59</u>	<u>2.26</u>

** ND - Not Detected (See detection limits)

COMPANY : DESTEC
 UNIT : DOUBLE C -- LUBE OIL VENT GENERATOR 2
 DATE : 02-11-93
 REPORT : 027-341

FIELD DATA @ 60°F

	RUN #:	1	2	3
	TIME:	1345	1433	1527
Vm (dry gas sampled)		23.99	24.00	24.00
Y (meter calib. factor)		0.998954	0.998954	0.998954
P bar (Barometric pressure)		29.22	29.22	29.22
P static (stack pressure, " H2O)		0	0	0
Delta H (differential meter press, " H2O)		0.60	0.60	0.60
Tm (meter temperature, R°)		527.25	531.63	534.69
Vol H2O mls		6.9	6.2	6
Vm(std),dscf		23.12	22.94	22.81
Bws-H2O vapor		0.0137	0.0124	0.0121
MF-moisture factor		0.9863	0.9876	0.9879
% CO2		0	0	0
% O2		20.9	20.9	20.9
% N2		79.1	79.1	79.1
Md-MW stk gas,dry		28.84	28.84	28.84
Ms-MW stk gas,wet		28.69	28.71	28.71
T stack, R°		538.25	531.63	536
Stack area,ft2		0.060	0.060	0.060
Vs-fpm, hot wire anemometer		351.25	323.13	332.5
Q-acfm		21.1	19.4	20.0
Qstd-dscfm		20	19	19
Sample time		40	40	40

COMPANY : DESTEC
UNIT : DOUBLE C - LUBE OIL VENT GENERATOR 2
DATE : 2-11-93
REPORT : 027-341

EPA METHOD 4 DATA
@ 60°F

RUN #1

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	9.97	0.00664	0.00655	0.00125	0.0301

ADDITIONAL DATA:

TIME						
start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1345	1425	20.9	0	1.37	23.12	22

RUN #2

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	23.44	0.01574	0.01554	0.00297	0.0713

ADDITIONAL DATA:

TIME						
start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1433	1513	20.9	0	1.24	22.94	22

RUN #3

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	10.44	0.00705	0.00696	0.00127	0.0305

ADDITIONAL DATA:

TIME						
start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1527	1607	20.9	0	1.21	22.81	21

COMPANY : DESTEC
UNIT : DOUBLE C - LUBE OIL VENT GENERATOR 2
DATE : 02-11-93
REPORT : 027-341

NON CONDENSABLE
HYDROCARBON RESULTS

RUN No.: 1					
DSCFM: 20					
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	4.504	0.000	4.504	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>4.504</u>	<u>0.000</u>	<u>4.504</u>	<u>0.000</u>
Total					
<u>(non methane)</u>		<u>0.000</u>	<u>0.000</u>	<u>0.000</u>	<u>0.000</u>

RUN No.: 2					
DSCFM: 19					
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	5.809	0.000	5.809	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>5.809</u>	<u>0.000</u>	<u>5.809</u>	<u>0.000</u>
Total					
<u>(non methane)</u>		<u>0.000</u>	<u>0.000</u>	<u>0.000</u>	<u>0.000</u>

RUN No.: 3					
DSCFM: 19					
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	4.516	0.000	4.516	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>4.516</u>	<u>0.000</u>	<u>4.516</u>	<u>0.000</u>
Total					
<u>(non methane)</u>		<u>0.000</u>	<u>0.000</u>	<u>0.000</u>	<u>0.000</u>

COMPANY : DESTEC
 UNIT : DOUBLE C - LUBE OIL VENT TURBINE 2
 DATE : 02-11-93
 REPORT : 027-341

FIELD DATA @ 60°F

	RUN #:	1	2	3
	TIME:	1643	1729	1814
Vm (dry gas sampled)		24.35	24.06	24.00
Y (meter calib. factor)		0.998954	0.998954	0.998954
P bar (Barometric pressure)		29.22	29.22	29.22
P static (stack pressure, " H2O)		0	0	0
Delta H (differential meter press, " H2O)		0.60	0.59	0.60
Tm (meter temperature, R°)		531.5	528.88	527.44
Vol H2O mls		11.2	13.8	10.2
Vm(std),dscf		23.28	23.11	23.12
Bws-H2O vapor		0.0219	0.0270	0.0201
MF-moisture factor		0.9781	0.9730	0.9799
% CO2		0	0	0
% O2		20.9	20.9	20.9
% N2		79.1	79.1	79.1
Md-MW stk gas,dry		28.84	28.84	28.84
Ms-MW stk gas,wet		28.6	28.55	28.62
T stack, R°		543.88	539.25	537.25
Stack area,ft2		0.060	0.060	0.060
Vs-fpm, hot wire anemometer		45.25	49.13	47.63
Q-acfm		2.72	2.95	2.86
Qstd-dscfm		2.54	2.78	2.70
Sample time		40	40	40

COMPANY : DESTEC
 UNIT : DOUBLE C - LUBE OIL VENT TURBINE 2
 DATE : 2-11-93
 REPORT : 027-341

EPA METHOD 4 DATA
 @ 60°F

RUN #1

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	23.43	0.01550	0.01516	0.00034	0.0081

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1643	1723	20.9	0	2.19	23.28	2.54

RUN #2

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	21.34	0.01422	0.01384	0.00034	0.0081

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1729	1809	20.9	0	2.7	23.11	2.78

RUN #3

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	25.26	0.01683	0.01649	0.00039	0.0094

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1814	1854	20.9	0	2.01	23.12	2.7

COMPANY : DESTEC
UNIT : DOUBLE C - LUBE OIL VENT TURBINE 2
DATE : 02-11-93
REPORT : 027-341

NON CONDENSABLE
HYDROCARBON RESULTS

RUN No.:		1			
DSCFM:		2.54			
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	21.880	0.00014	21.880	0.00014
Ethane	(C2)	1.360	0.00002	2.720	0.00002
Propane	(C3)	0.000	0.00000	0.000	0.00000
Butane	(C4)	0.000	0.00000	0.000	0.00000
Pentane	(C5)	0.000	0.00000	0.000	0.00000
Hexane	(C6)	0.000	0.00000	0.000	0.00000
<u>Total</u>		<u>23.240</u>	<u>0.00016</u>	<u>24.600</u>	<u>0.00016</u>
Total (non methane)		1.360	0.00002	2.720	0.00002

RUN No.:		2			
DSCFM:		2.78			
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	14.650	0.000	14.650	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>14.650</u>	<u>0.000</u>	<u>14.650</u>	<u>0.000</u>
Total (non methane)		0.000	0.000	0.000	0.000

RUN No.:		3			
DSCFM:		2.70			
		ppm	lb/hr	ppm as CH4	lb/hr (as Methane)
Methane	(C1)	11.350	0.000	11.350	0.000
Ethane	(C2)	0.000	0.000	0.000	0.000
Propane	(C3)	0.000	0.000	0.000	0.000
Butane	(C4)	0.000	0.000	0.000	0.000
Pentane	(C5)	0.000	0.000	0.000	0.000
Hexane	(C6)	0.000	0.000	0.000	0.000
<u>Total</u>		<u>11.350</u>	<u>0.000</u>	<u>11.350</u>	<u>0.000</u>
Total (non methane)		0.000	0.000	0.000	0.000

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1 & #2
 DATE : 02-11-93
 REPORT : 027-341

HYDROCARBON RESULTS @ 60°F

DETECTION LIMITS		
	ppm	ppm (as Methane)
Methane (C1)	0.05	0.05
Ethane (C2)	0.03	0.06
Propane (C3)	0.02	0.06
Butane (C4)	0.02	0.08
Pentane (C5)	0.02	0.10
Hexane (C6)	0.02	0.12
Total	0.16	0.47
Total (non methane)	0.11	0.42

SULFUR EMISSIONS

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 2-9/10-93
REPORT : 027-341

SUFUR EMISSION RESULTS

DATE	TIME	TS, ppm *	AVG LBS/HR GAS FUEL FLOW	SP VOL CF/LB	AVERAGE SCFH	FUEL SCFM	SULFUR	
							LBS/HR	LBS/DAY
2/9/93	1130-1645	< 1.0	10125.2	22.05	223261	3721	< 0.01883	< 0.452
2/10/93	900-1245	< 1.0	10098.8	22.05	222679	3711	< 0.01878	< 0.451
AVERAGE							< 0.01880	< 0.451

EQUATION:

SCFM = SCFH (1/60)

SULFUR LBS/HR = TS ppm * 32 * SCFM * 1.581 * 10⁻⁷

MW SULFUR = 32

* SEE FUEL ANALYSIS (Page 78)

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 2-11-93
 REPORT : 027-341

SUFUR EMISSION RESULTS

DATE	TIME	TS, ppm *	AVG LBS/HR GAS FUEL FLOW	SP VOL CF/LB	AVERAGE SCFH	FUEL SCFM	SULFUR	
							LBS/HR	LBS/DAY
2/11/93	1015-1815	< 1.0	10736.3	22.04	236628	3944	< 0.01995	< 0.479

EQUATION:

$$\text{SCFM} = \text{SCFH} (1/60)$$

$$\text{SULFUR LBS/HR} = \text{TS ppm} * 32 * \text{SCFM} * 1.581 * 10^{-7}$$

$$\text{MW SULFUR} = 32$$

* SEE FUEL ANALYSIS (Page 78)

RELATIVE ACCURACY

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02/09-10/93
 REPORT : 027-341

ANALYZER NOx

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	1.48	2.24	-0.76
2	3.30	2.26	1.04
3	2.23	2.42	-0.19
4	2.38	2.50	-0.12
5	2.08	2.49	-0.41
6	2.65	2.49	0.16
7	2.84	2.57	0.27
8	2.45	2.50	-0.05
9	2.50	2.50	0.00
10	2.50	2.53	-0.03
11	2.52	2.55	-0.03
12	2.83	2.76	0.07
AVERAGE	2.48	2.48	0.00

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t _{.975}	=	2.201
STANDARD DEVIATION	=	0.42
CONFIDENCE COEFFICIENT	=	0.27
REF METHOD	=	2.5
RELATIVE ACCURACY	=	11.05

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02/09-10/93
 REPORT : 027-341

ANALYZER CO

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	46.5	43.7	2.80
2	45.7	43.0	2.70
3	45.4	43.6	1.80
4	47.0	45.2	1.80
5	48.5	46.2	2.30
6	46.8	46.9	-0.10
7	43.7	42.5	1.20
8	46.3	46.4	-0.10
9	46.0	43.9	2.10
10	44.6	42.6	2.00
11	43.5	40.9	2.60
12	39.9	38.1	1.80
AVERAGE	45.3	43.6	1.74

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t _{.975}	=	2.201
STANDARD DEVIATION	=	0.97
CONFIDENCE COEFFICIENT	=	0.62
REF METHOD	=	45.3
RELATIVE ACCURACY	=	5.20

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02/09-10/93
 REPORT : 027-341

ANALYZER O2

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	14.00	13.92	0.08
2	13.91	13.93	-0.02
3	14.00	13.92	0.08
4	13.90	13.92	-0.02
5	13.83	13.92	-0.09
6	13.90	13.92	-0.02
7	13.86	13.92	-0.06
8	13.88	13.97	-0.09
9	13.95	14.03	-0.08
10	13.70	14.09	-0.39
11	13.68	14.13	-0.45
12	13.98	14.13	-0.15
AVERAGE	13.88	13.98	-0.10

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t .975	=	2.201
STANDARD DEVIATION	=	0.16
CONFIDENCE COEFFICIENT	=	0.10
REF METHOD	=	13.9
RELATIVE ACCURACY	=	1.47

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

ANALYZER NOx

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	2.93	3.01	-0.08
2	3.04	3.00	0.04
3	2.98	3.05	-0.07
4	3.00	3.00	0.00
5	2.72	3.00	-0.28
6	3.00	3.00	0.00
7	2.75	3.00	-0.25
8	3.00	3.00	0.00
9	3.00	3.00	0.00
10	3.00	3.00	0.00
AVERAGE	2.94	3.01	-0.06

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t	=	2.262
.975		
STANDARD DEVIATION	=	0.11
CONFIDENCE COEFFICIENT	=	0.08
REF METHOD	=	2.9
RELATIVE ACCURACY	=	4.90

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

ANALYZER CO

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	42.8	41.0	1.80
2	43.6	41.0	2.60
3	44.4	40.8	3.60
4	45.6	42.2	3.40
5	46.0	42.5	3.50
6	45.2	41.7	3.50
7	44.3	40.3	4.00
8	44.4	40.8	3.60
9	46.2	43.6	2.60
10	47.1	44.0	3.10
AVERAGE	45.0	41.8	3.17

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t .975	=	2.262
STANDARD DEVIATION	=	0.65
CONFIDENCE COEFFICIENT	=	0.47
REF METHOD	=	45.0
RELATIVE ACCURACY	=	8.09

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

ANALYZER O2

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	14.15	14.14	0.01
2	13.98	14.12	-0.14
3	14.20	14.13	0.07
4	14.06	14.13	-0.07
5	13.25	14.16	-0.91
6	14.03	14.13	-0.10
7	14.00	14.12	-0.12
8	14.03	14.13	-0.10
9	13.94	14.12	-0.18
10	14.00	14.12	-0.12
AVERAGE		13.96	14.13
			-0.17

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t _{.975}	=	2.262
STANDARD DEVIATION	=	0.27
CONFIDENCE COEFFICIENT	=	0.19
REF METHOD	=	14.0
RELATIVE ACCURACY	=	2.58

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1 & #2
 DATE : 02/09-10/93
 REPORT : 027-341

CEM DATA SUMMARY

RUN #	TIME	TURBINE #1			TURBINE #2		
		%O2	NOx ppm	CO ppm	%O2	NOx ppm	CO ppm
1	1130-1200	13.92	2.24	43.7	14.14	3.01	41.0
2	1215-1245	13.93	2.26	43.0	14.12	3.00	41.0
3	1300-1330	13.92	2.42	43.6	14.13	3.05	40.8
4	1400-1430	13.92	2.50	45.2	14.13	3.00	42.2
5	1445-1515	13.92	2.49	46.2	14.16	3.00	42.5
6	1535-1605	13.92	2.49	46.9	14.13	3.00	41.7
7	1615-1645	13.92	2.57	42.5	14.12	3.00	40.3
8	900-930	13.97	2.50	46.4	14.13	3.00	40.8
9	1000-1030	14.03	2.50	43.9	14.12	3.00	43.6
10	1045-1115	14.09	2.53	42.6	14.12	3.00	44.0
11	1130-1200	14.13	2.55	40.9			
12	1215-1245	14.13	2.76	38.1			
AVERAGE		13.98	2.48	43.6	14.13	3.01	41.8

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02/09-10/93
 REPORT : 027-341

PCES REFERENCE METHOD SUMMARY

RUN #	TIME	%O2	NOx			CO		
			ppm	ppm @ 15% O2	lbs/hr	ppm	ppm @ 15% O2	lbs/hr
1	1130-1200	14.00	1.48	1.27	1.22	46.5	39.8	23.2
2	1215-1245	13.91	3.30	2.79	2.70	45.7	38.6	22.8
3	1300-1330	14.00	2.23	1.91	1.83	45.4	38.8	22.6
4	1400-1430	13.90	2.38	2.00	1.95	47.0	39.6	23.4
5	1445-1515	13.83	2.08	1.74	1.71	48.5	40.5	24.2
6	1535-1605	13.90	2.65	2.23	2.17	46.8	39.5	23.3
7	1615-1645	13.86	2.84	2.38	2.33	43.7	36.6	21.8
8	900-930	13.88	2.45	2.06	2.01	46.3	39.0	23.1
9	1000-1030	13.95	2.50	2.12	2.05	46.0	39.0	22.9
10	1045-1115	13.70	2.50	2.05	2.05	44.6	36.5	22.2
11	1130-1200	13.68	2.52	2.06	2.06	43.5	35.5	21.7
12	1215-1245	13.98	2.83	2.41	2.32	39.9	34.0	19.9
AVERAGE		13.88	2.48	2.09	2.03	45.3	38.1	22.6

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 02-09-93
REPORT : 027-341

RUN #1
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
11:30 AM	-	11:40 AM	13.98	1.90	46.9	65.8	14.3	57.0
11:40 AM	-	11:50 AM	14.00	1.50	46.2	65.6	14.5	56.5
11:50 AM	-	12:00 PM	14.02	1.05	46.5	65.4	14.6	57.0
Averages:			14.00	1.48	46.5	65.6	14.5	56.8

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.5
FINAL zero	10	10	10
FINAL span	69.2	93	92
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	-0.20	1.50	0.50
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	-0.80	3.00	0.50
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.00	1.48	3.85	1.27	1.22

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.00	46.5	121	39.8	23.2

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 02-09-93
REPORT : 027-341

RUN #2
NOx/CO/O2 DATA

Stack Gas Measurement Data			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
12:15 PM	-	12:25 PM	13.96	2.65	46.1	66.0	14.7	56.1
12:25 PM	-	12:35 PM	13.89	3.35	45.6	66.0	14.9	55.5
12:35 PM	-	12:45 PM	13.89	3.90	45.4	66.3	14.8	55.1
Averages:			13.91	3.30	45.7	66.1	14.8	55.6

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.5
FINAL zero	9.9	10.1	10
FINAL span	71	86.3	91.1
ZERO DRIFT %/ppm	-0.02	0.05	0.00
CALIB. DRIFT %/ppm	0.25	-1.85	-0.40
ZERO DRIFT %fs	-0.10	0.10	0.00
CALIB.DRIFT %fs	1.00	-3.70	-0.40
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)					
NOx values:	%O2	ppm	@ 3%O2	@15%O2	lb/hr
	13.91	3.30	8.45	2.79	2.70

CO values:	%O2	ppm	@ 3%O2	@15%O2	lb/hr
	13.91	45.7	117	38.6	22.8

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02-09-93
 REPORT : 027-341

RUN #3
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
01:00 PM	-	01:10 PM	14.00	2.38	43.5	66.0	14.8	53.5
01:10 PM	-	01:20 PM	14.01	2.30	43.2	66.0	14.7	53.0
01:20 PM	-	01:30 PM	14.00	2.02	49.4	65.9	14.2	59.0
Averages:			14.00	2.23	45.4	66.0	14.6	55.2

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.5
FINAL zero	9.9	10	10
FINAL span	70	90.2	91
ZERO DRIFT %/ppm	-0.02	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.10	-0.50
ZERO DRIFT %fs	-0.10	0.00	0.00
CALIB.DRIFT %fs	0.00	0.20	-0.50
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.00	2.23	5.80	1.91	1.83

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.00	45.4	118	38.8	22.6

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02-09-93
 REPORT : 027-341

RUN #4
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
02:00 PM	-	02:10 PM	13.86	2.46	45.0	65.3	15.0	55.0
02:10 PM	-	02:20 PM	13.89	2.38	48.3	65.1	15.0	58.1
02:20 PM	-	02:30 PM	13.94	2.29	47.6	65.0	15.0	57.2
Averages:			13.90	2.38	47.0	65.1	15.0	56.8

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.5
FINAL zero	9.9	10.2	10
FINAL span	69.2	90.3	91
ZERO DRIFT %/ppm	-0.02	0.10	0.00
CALIB. DRIFT %/ppm	-0.20	0.15	-0.50
ZERO DRIFT %fs	-0.10	0.20	0.00
CALIB.DRIFT %fs	-0.80	0.30	-0.50
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.90	2.38	6.07	2.00	1.95

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.90	47.0	120	39.6	23.4

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 02-09-93
REPORT : 027-341

RUN #5
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
02:45 PM	-	02:55 PM	13.88	2.28	49.0	65.5	14.8	59.0
02:55 PM	-	03:05 PM	13.83	2.10	48.2	65.3	14.9	58.0
03:05 PM	-	03:15 PM	13.80	1.87	48.4	65.2	14.9	58.0
Averages:			13.83	2.08	48.5	65.3	14.9	58.3

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.5
FINAL zero	10	10	9.9
FINAL span	70	91.4	91.1
ZERO DRIFT %/ppm	0.00	0.00	-0.10
CALIB. DRIFT %/ppm	0.00	0.70	-0.40
ZERO DRIFT %fs	0.00	0.00	-0.10
CALIB.DRIFT %fs	0.00	1.40	-0.40
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.83	2.08	5.28	1.74	1.71

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.83	48.5	123	40.5	24.2

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 02-09-93
REPORT : 027-341

RUN #6
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
03:35 PM	-	03:45 PM	13.94	2.50	47.1	65.8	14.8	57.1
03:45 PM	-	03:55 PM	13.89	2.65	47.1	65.7	14.7	57.0
03:55 PM	-	04:05 PM	13.89	2.80	46.2	65.8	14.6	56.0
Averages:			13.90	2.65	46.8	65.8	14.7	56.7

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.5
FINAL zero	10	10	9.9
FINAL span	70.3	88.8	91.3
ZERO DRIFT %/ppm	0.00	0.00	-0.10
CALIB. DRIFT %/ppm	0.07	-0.60	-0.20
ZERO DRIFT %fs	0.00	0.00	-0.10
CALIB. DRIFT %fs	0.30	-1.20	-0.20
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.90	2.65	6.78	2.23	2.17

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.90	46.8	120	39.5	23.3

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02-09-93
 REPORT : 027-341

RUN #7
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
04:15 PM	-	04:25 PM	13.83	2.58	45.3	65.3	14.9	55.3
04:25 PM	-	04:35 PM	13.85	2.83	43.9	65.4	14.9	53.9
04:35 PM	-	04:45 PM	13.90	3.13	41.8	65.6	15.0	51.8
Averages:			13.86	2.84	43.7	65.4	14.9	53.7

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.5
FINAL zero	10	10	10
FINAL span	70	88.5	91.4
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	0.00	-0.75	-0.10
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	0.00	-1.50	-0.10
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.86	2.84	7.22	2.38	2.33

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.86	43.7	111	36.6	21.8

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02-10-93
 REPORT : 027-341

RUN #8
 NOx/CO/O2 DATA

Stack Gas Measurement Data			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
09:00 AM	-	09:10 AM	13.88	2.40	50.9	65.5	14.8	60.8
09:10 AM	-	09:20 AM	13.85	2.50	45.6	65.4	15.0	55.5
09:20 AM	-	09:30 AM	13.93	2.45	42.6	65.7	14.9	52.5
Averages:			13.88	2.45	46.3	65.5	14.9	56.3

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.3
FINAL zero	10	10	10
FINAL span	70	90	91.3
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.00	0.00
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	0.00	0.00	0.00
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.88	2.45	6.25	2.06	2.01

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.88	46.3	118	39.0	23.1

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 2-10-93
REPORT : 027-341

RUN #9
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
10:00 AM	-	10:10 AM	13.95	2.50	46.3	65.8	15.0	56.2
10:10 AM	-	10:20 AM	13.95	2.50	46.3	65.8	15.0	56.2
10:20 AM	-	10:30 AM	13.95	2.50	45.4	65.8	15.0	55.3
Averages:			13.95	2.50	46.0	65.8	15.0	55.9

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.3
FINAL zero	10	10	10
FINAL span	70	90	91.3
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.00	0.00
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	0.00	0.00	0.00
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.95	2.50	6.44	2.12	2.05

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.95	46.0	118	39.0	22.9

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 02-10-93
REPORT : 027-341

RUN #10
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
10:45 AM	-	10:55 AM	13.73	2.50	44.5	64.9	15.0	54.4
10:55 AM	-	11:05 AM	13.70	2.50	44.9	64.8	15.0	54.8
11:05 AM	-	11:15 AM	13.68	2.50	44.5	64.7	15.0	54.4
Averages:			13.70	2.50	44.6	64.8	15.0	54.5

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.3
FINAL zero	10	10	10
FINAL span	70	90	91.3
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.00	0.00
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	0.00	0.00	0.00
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.70	2.50	6.22	2.05	2.05

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.70	44.6	111	36.5	22.2

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02-10-93
 REPORT : 027-341

RUN #11
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
11:30 AM	-	11:40 AM	13.71	2.50	44.3	64.8	15.0	54.2
11:40 AM	-	11:50 AM	13.68	2.50	44.1	64.6	15.0	53.9
11:50 AM	-	12:00 PM	13.64	2.55	42.1	64.4	15.1	51.9
Averages:			13.68	2.52	43.5	64.6	15.0	53.3

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.3
FINAL zero	10	10	10
FINAL span	69.8	90	91.1
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	-0.05	0.00	-0.20
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB. DRIFT %fs	-0.20	0.00	-0.20
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.68	2.52	6.24	2.06	2.06

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.68	43.5	108	35.5	21.7

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #1
DATE : 02-10-93
REPORT : 027-341

RUN #12
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
12:15 PM	-	12:25 PM	13.96	2.84	39.5	65.8	15.7	49.5
12:25 PM	-	12:35 PM	13.99	2.83	39.8	65.8	15.7	49.8
12:35 PM	-	12:45 PM	13.99	2.81	40.3	65.7	15.7	50.3
Averages:			13.98	2.83	39.9	65.8	15.7	49.9

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.3
FINAL zero	9.9	10.1	9.9
FINAL span	69.8	90	91.4
ZERO DRIFT %/ppm	-0.02	0.05	-0.10
CALIB. DRIFT %/ppm	-0.05	0.00	0.10
ZERO DRIFT %fs	-0.10	0.10	-0.10
CALIB.DRIFT %fs	-0.20	0.00	0.10
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112679 (DSCFM by Pitot Tube Traverse)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.98	2.83	7.31	2.41	2.32

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.98	39.9	103	34.0	19.9

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

PCES REFERENCE METHOD SUMMARY

RUN #	TIME	%O2	NOx			CO		
			ppm	ppm @ 15% O2	lbs/hr	ppm	ppm @ 15% O2	lbs/hr
1	1015-1045	14.15	2.93	2.56	2.49	42.8	37.4	22.2
2	1130-1200	13.98	3.04	2.59	2.59	43.6	37.2	22.6
3	1230-1300	14.20	2.98	2.63	2.54	44.4	39.1	23.0
4	1345-1415	14.06	3.00	2.59	2.56	45.6	39.3	23.6
5	1400-1430	13.25	2.72	2.09	2.32	46.0	35.5	23.9
6	1445-1515	14.03	3.00	2.58	2.56	45.2	38.8	23.4
7	1530-1600	14.00	2.75	2.35	2.34	44.3	37.9	23.0
8	1615-1645	14.03	3.00	2.57	2.56	44.4	38.1	23.0
9	1700-1730	13.94	3.00	2.54	2.56	46.2	39.2	24.0
10	1805-1815	14.00	3.00	2.57	2.56	47.1	40.3	24.5
AVERAGE		13.96	2.94	2.51	2.51	45.0	38.3	23.3

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #2
DATE : 02-11-93
REPORT : 027-341

RUN #1
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
10:15 AM	-	10:25 AM	14.20	2.98	43.1	66.8	16.0	53.0
10:25 AM	-	10:35 AM	14.15	2.93	42.6	66.6	16.0	52.6
10:35 AM	-	10:45 AM	14.10	2.88	42.8	66.4	16.0	52.9
Averages:			14.15	2.93	42.8	66.6	16.0	52.8

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.2
FINAL zero	10	10	10
FINAL span	70	90.3	91.4
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.15	0.20
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	0.00	0.30	0.20
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.15	2.93	7.76	2.56	2.49

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.15	42.8	114	37.4	22.2

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

RUN #2
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
11:30 AM	-	11:40 AM	14.00	2.99	44.2	66.0	16.0	54.1
11:40 AM	-	11:50 AM	13.99	3.04	43.4	66.0	16.1	53.2
11:50 AM	-	12:00 PM	13.95	3.09	43.4	65.9	16.2	53.1
Averages:			13.98	3.04	43.6	66.0	16.1	53.5

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90.3	91.4
FINAL zero	10	10	10.1
FINAL span	70.1	90.3	91
ZERO DRIFT %/ppm	0.00	0.00	0.10
CALIB. DRIFT %/ppm	0.02	0.00	-0.40
ZERO DRIFT %fs	0.00	0.00	0.10
CALIB. DRIFT %fs	0.10	0.00	-0.40
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.98	3.04	7.86	2.59	2.59

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.98	43.6	113	37.2	22.6

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

RUN #3
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
12:30 PM	-	12:40 PM	14.19	3.00	44.1	66.8	16.0	53.9
12:40 PM	-	12:50 PM	14.23	3.00	44.2	67.0	16.0	54.1
12:50 PM	-	01:00 PM	14.18	2.95	45.0	66.9	15.9	54.9
Averages:			14.20	2.98	44.4	66.9	16.0	54.3

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10.1
INITIAL span	70	90	91
FINAL zero	10	10	10
FINAL span	70.2	90	91.2
ZERO DRIFT %/ppm	0.00	0.00	-0.10
CALIB. DRIFT %/ppm	0.05	0.00	0.20
ZERO DRIFT %fs	0.00	0.00	-0.10
CALIB.DRIFT %fs	0.20	0.00	0.20
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.20	2.98	7.97	2.63	2.54

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.20	44.4	119	39.1	23.0

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #2
DATE : 02-11-93
REPORT : 027-341

RUN #4
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
01:45 PM	-	01:55 PM	14.05	3.00	45.4	66.2	16.0	55.3
01:55 PM	-	02:05 PM	14.05	3.00	45.5	66.2	16.0	55.3
02:05 PM	-	02:15 PM	14.08	3.00	45.8	66.3	16.0	55.5
Averages:			14.06	3.00	45.6	66.2	16.0	55.4

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.2
FINAL zero	10	10	10
FINAL span	70	90	91
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.00	-0.20
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	0.00	0.00	-0.20
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.06	3.00	7.85	2.59	2.56

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.06	45.6	119	39.3	23.6

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

RUN #5
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
02:00 PM	-	02:10 PM	14.05	2.87	46.1	66.1	15.9	55.9
02:10 PM	-	02:20 PM	14.09	2.70	46.1	66.0	15.9	55.9
02:20 PM	-	02:30 PM	11.60	2.58	45.8	55.8	16.0	55.6
Averages:			13.25	2.72	46.0	62.6	15.9	55.8

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91
FINAL zero	10	10	10
FINAL span	69.3	91	91
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	-0.18	0.50	0.00
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	-0.70	1.00	0.00
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.25	2.72	6.35	2.09	2.32

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.25	46.0	108	35.5	23.9

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #2
DATE : 02-11-93
REPORT : 027-341

RUN #6
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
02:45 PM	-	02:55 PM	14.03	3.00	45.4	66.1	16.0	55.3
02:55 PM	-	03:05 PM	14.05	3.00	45.2	66.2	16.0	55.1
03:05 PM	-	03:15 PM	14.03	3.00	44.9	66.1	16.0	54.8
Averages:			14.03	3.00	45.2	66.1	16.0	55.1

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91.2
FINAL zero	10	10	10
FINAL span	70	90	91.2
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.00	0.00
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	0.00	0.00	0.00
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.03	3.00	7.82	2.58	2.56

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.03	45.2	118	38.8	23.4

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

RUN #7
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
03:30 PM	-	03:40 PM	14.00	2.92	44.4	66.0	16.0	54.2
03:40 PM	-	03:50 PM	14.00	2.75	44.4	66.0	16.0	54.2
03:50 PM	-	04:00 PM	14.00	2.58	44.1	66.0	16.0	54.0
Averages:			14.00	2.75	44.3	66.0	16.0	54.1

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91
FINAL zero	10	10	10.1
FINAL span	70	91	91
ZERO DRIFT %/ppm	0.00	0.00	0.10
CALIB. DRIFT %/ppm	0.00	0.50	0.00
ZERO DRIFT %fs	0.00	0.00	0.10
CALIB.DRIFT %fs	0.00	1.00	0.00
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.00	2.75	7.13	2.35	2.34

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.00	44.3	115	37.9	23.0

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

RUN #8
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
04:15 PM	-	04:25 PM	14.03	3.00	44.7	66.1	16.0	54.5
04:25 PM	-	04:35 PM	14.03	3.00	44.4	66.1	16.0	54.3
04:35 PM	-	04:45 PM	14.03	3.00	44.2	66.1	16.0	54.1
Averages:			14.03	3.00	44.4	66.1	16.0	54.3

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10.1
INITIAL span	70	90	91
FINAL zero	10	10	10
FINAL span	70	90	91.2
ZERO DRIFT %/ppm	0.00	0.00	-0.10
CALIB. DRIFT %/ppm	0.00	0.00	0.20
ZERO DRIFT %fs	0.00	0.00	-0.10
CALIB. DRIFT %fs	0.00	0.00	0.20
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.03	3.00	7.81	2.57	2.56

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.03	44.4	116	38.1	23.0

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

RUN #9
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
05:00 PM	-	05:10 PM	13.88	3.00	45.2	65.5	16.0	55.0
05:10 PM	-	05:20 PM	13.95	3.00	46.5	65.8	16.0	56.4
05:20 PM	-	05:30 PM	14.00	3.00	47.0	66.0	16.0	57.0
Averages:			13.94	3.00	46.2	65.8	16.0	56.1

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	90	91
FINAL zero	10	10	10.3
FINAL span	70	90	91
ZERO DRIFT %/ppm	0.00	0.00	0.30
CALIB. DRIFT %/ppm	0.00	0.00	0.00
ZERO DRIFT %fs	0.00	0.00	0.30
CALIB. DRIFT %fs	0.00	0.00	0.00
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.94	3.00	7.72	2.54	2.56

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.94	46.2	119	39.2	24.0

COMPANY : DESTEC
UNIT : DOUBLE C - TURBINE #2
DATE : 02-11-93
REPORT : 027-341

RUN #10
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
05:45 PM	-	05:55 PM	14.00	3.00	47.0	66.0	16.0	56.8
05:55 PM	-	06:05 PM	14.00	3.00	47.0	66.0	16.0	56.6
06:05 PM	-	06:15 PM	14.00	3.00	47.4	66.0	16.0	56.9
Averages:			14.00	3.00	47.1	66.0	16.0	56.8

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10.3
INITIAL span	70	90	91
FINAL zero	10	10	10.1
FINAL span	70	90	90.7
ZERO DRIFT %/ppm	0.00	0.00	-0.20
CALIB. DRIFT %/ppm	0.00	0.00	-0.30
ZERO DRIFT %fs	0.00	0.00	-0.20
CALIB.DRIFT %fs	0.00	0.00	-0.30
CAL GAS value	15	40	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 117212 (DSCFM by Pitot Tube Traverse)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.00	3.00	7.78	2.57	2.56

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.00	47.1	122	40.3	24.5

EMISSION FACTORS

(lbs/MMBtu)

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1
 DATE : 02-11-93
 REPORT : 027-341

LBS/MMBTU & EPA F FACTOR @ 60°F

NOx

RUN	PPM	%O2	LBS/MMBTU
#1	1.48	14.00	0.00462
#2	3.30	13.91	0.01017
#3	2.23	14.00	0.00696
#4	2.38	13.90	0.00732
#5	2.08	13.83	0.00634
#6	2.65	13.90	0.00815
#7	2.84	13.86	0.00869
#8	2.45	13.88	0.00752
#9	2.50	13.95	0.00775
#10	2.50	13.70	0.00748
#11	2.52	13.68	0.00752
#12	2.83	13.98	0.00881
AVERAGE	2.48	13.88	0.00761

CO

RUN	PPM	%O2	LBS/MMBTU
#1	46.5	14.00	0.08835
#2	45.7	13.91	0.08571
#3	45.4	14.00	0.08626
#4	47.0	13.90	0.08802
#5	48.5	13.83	0.08993
#6	46.8	13.90	0.08765
#7	43.7	13.86	0.08138
#8	46.3	13.88	0.08647
#9	46.0	13.95	0.08677
#10	44.6	13.70	0.08121
#11	43.5	13.68	0.07899
#12	39.9	13.98	0.07559
AVERAGE	45.3	13.88	0.08470

EPA F FACTOR @ 60°F 8502

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #2
 DATE : 02-11-93
 REPORT : 027-341

LBS/MMBTU & EPA F FACTOR @ 60°F


NOx RUN	PPM	%O2	LBS/MMBTU
#1	2.93	14.15	0.00935
#2	3.04	13.98	0.00946
#3	2.98	14.20	0.00958
#4	3.00	14.06	0.00945
#5	2.72	13.25	0.00766
#6	3.00	14.03	0.00941
#7	2.75	14.00	0.00858
#8	3.00	14.03	0.00941
#9	3.00	13.94	0.00928
#10	3.00	14.00	0.00936
AVERAGE	2.94	13.96	0.00915

CO

RUN	PPM	%O2	LBS/MMBTU
#1	42.8	14.15	0.08313
#2	43.6	13.98	0.08260
#3	44.4	14.20	0.08688
#4	45.6	14.06	0.08740
#5	46.0	13.25	0.07883
#6	45.2	14.03	0.08626
#7	44.3	14.00	0.08417
#8	44.4	14.03	0.08473
#9	46.2	13.94	0.08702
#10	47.1	14.00	0.08949
AVERAGE	45.0	13.96	0.08505

EPA F FACTOR @ 60°F 8502

L GAS ANALYSIS



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC DOUBLE "C"
UNIT : TURBINE # 1
DATE : 2-11-93
REPORT : 027-341

DATE RECEIVED : FEBRUARY 12, 1993
DATE ANALYZED : FEBRUARY 13, 1993
DATE REPORTED: FEBRUARY 16, 1993

FUEL GAS ANALYSIS

CONSTITUENT	MOLE %	WT. %	CHONS Wt. %	
CARBON DIOXIDE	0.566	1.446	CARBON	73.75
OXYGEN	0.012	0.022	HYDROGEN	23.86
NITROGEN	0.806	1.311	OXYGEN	1.07
CARBON MONOXIDE	0.000	0.000	NITROGEN	1.31
			SULFUR	0.00
METHANE	93.210	86.867	H/C	0.324
ETHANE	4.507	7.873		
PROPANE	0.740	1.897		
ISOBUTANE	0.066	0.223		
N-BUTANE	0.055	0.184		
ISOPENTANE	0.012	0.051		
N-PENTANE	0.008	0.035		
HEXANES+	0.018	0.089		
TOTALS:	100.000	100.000		

SPECIFIC GRAVITY (AIR = 1)	0.5944
SPECIFIC VOLUME, cu.ft./lb.	22.05
GROSS CALORIFIC VALUE (DRY), BTU/cu.ft.	1047.78
GROSS CALORIFIC VALUE (WET), BTU/cu.ft.	1027.19
GROSS CALORIFIC VALUE (DRY), BTU/lb.	23100.57
NET CALORIFIC VALUE (DRY), BTU/cu.ft.	945.05
NET CALORIFIC VALUE (WET), BTU/cu.ft.	926.48
COMPRESSABILITY FACTOR "Z" @ 60° F, 1 ATM	0.9977

EPA "F" FACTOR @ 68° F (DSCF/MM BTU)	8631
EPA "F" FACTOR @ 60° F (DSCF/MM BTU)	8502

ASTM METHODS D-1945-81 & D-3588-91


Terry Rowles
Laboratory Manager



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC DOUBLE "C"
UNIT : TURBINE # 2
DATE : 2-12-93
REPORT : 027-341

DATE RECEIVED : FEBRUARY 12, 1993
DATE ANALYZED : FEBRUARY 13, 1993
DATE REPORTED : FEBRUARY 16, 1993


FUEL GAS ANALYSIS


CONSTITUENT	MOLE %	WT. %	CHONS Wt. %	
CARBON DIOXIDE	0.555	1.418	CARBON	73.76
OXYGEN	0.012	0.022	HYDROGEN	23.86
NITROGEN	0.818	1.331	OXYGEN	1.05
CARBON MONOXIDE	0.000	0.000	NITROGEN	1.33
			SULFUR	0.00
			H/C	0.323
METHANE	93.153	86.780		
ETHANE	4.556	7.955		
PROPANE	0.746	1.910		
ISOBUTANE	0.067	0.227		
N-BUTANE	0.056	0.189		
ISOPENTANE	0.013	0.053		
N-PENTANE	0.009	0.036		
HEXANES+	0.016	0.080		
TOTALS:	100.000	100.000		

SPECIFIC GRAVITY (AIR = 1)	0.5946
SPECIFIC VOLUME, cu.ft./lb.	22.04
GROSS CALORIFIC VALUE (DRY), BTU/cu.ft.	1048.22
GROSS CALORIFIC VALUE (WET), BTU/cu.ft.	1027.62
GROSS CALORIFIC VALUE (DRY), BTU/lb.	23101.09
NET CALORIFIC VALUE (DRY), BTU/cu.ft.	945.47
NET CALORIFIC VALUE (WET), BTU/cu.ft.	926.89
COMPRESSIBILITY FACTOR "Z" @ 60° F, 1 ATM	0.9977

EPA "F" FACTOR @ 68° F (DSCF/MM BTU)	8632
EPA "F" FACTOR @ 60° F (DSCF/MM BTU)	8502

ASTM METHODS D-1945-81 & D-3586-91


Terry Rowles
Laboratory Manager



ZALCO LABORATORIES, INC.
Analytical & Consulting Services

Petro Chem Environmental Service
3207 Antonino Avenue
Bakersfield, CA 93308

Laboratory No: 34790
Date Received: 2-12-93
Date Reported: 2-17-93
P O #: 49140

Attention: Terry Rowles

Sample: Gas

Sample Description: Destec Operating Company, Double "C" Limited, Job #027-341
34790-1 Fuel Gas Turbine #1
34790-2 Fuel Gas Turbine #2
Sampled by J. K. H. on 2-12-93

Total Sulfur
(ASTM D 3246)

	-1 <u>Result</u>	-2 <u>Result</u>
As H ₂ S, ppm (vol.)	< 1.0	< 1.0
As S, Grains/100 SCF*	< 0.06	< 0.06

* Standard cubic feet (60 °F, 14.7 psia)

JE/tds


Jim Etherton
Lab Operations Manager

4309 Armour Avenue Bakersfield, California 93308

(805) 395-0539

FAX (805) 395-3069

MODELS AND EQUATIONS

EPA Method 2: Velocity and Volumetric Flow Rates

A computer was used in selection of suitable sample/traverse points. The calibrated pitot tube was connected to a magnehelic gauge and leak checked. A temperature and Δ -P was then recorded at each traverse point and a duct static pressure was also measured and recorded. A volume flow rate was calculated from the measured required traverse points.

EPA Method 3: % CO₂, % O₂, Dry Molecular Weight

Concurrent with each particulate sampling, an integrated gas sample was withdrawn from the summation of the traverse points through the train and collected at the outlet of the meter into a sample bag. Then the contents of the sample bladder were analyzed by Orsat for fixed gas composition.

EPA Method 4: Percent Water

Tare weights of the charged individual impingers was recorded. After sampling, the final weights was then recorded. Percent water was calculated from the weight of water collected and the dry gas volume sampled.

EPA Method 5: Particulate Emissions

A series of preliminary measurements was made prior to conducting the particulate test. EPA Methods 1, 2, and 3 was performed to determine location and number of traverse points, average gas velocity, and pressure and gas molecular weight. Percent water was determined by a psychrometric chart or from combustion analysis of the fixed gases. The results of these measurements were entered into the field computer for the purpose of determining an appropriate nozzle size for isokinetic sampling.

The method 5 apparatus was then prepared on-site in the mobile laboratory. The absorption train was charged with freshly prepared chemicals, weighted on a calibrated digital balance to the nearest 0.1 grams, and assembled. The probe was brushed out and rinsed with distilled water and acetone, then the filter holder was charged. The sampling apparatus was sealed and transported to the sampling site where it was assembled and leak tested at 15 inches mercury vacuum.

The probe, filter and impinger line heaters were set at 250 °F and the probe was then positioned into the duct at the first traverse point with the nozzle out of the flow.

The nozzle was positioned into the gas flow and the vacuum pump was started immediately and adjusted to obtain an isokinetic sample rate. A complete traverse was performed while sampling at a minimum of two minutes per sample point. Upon completion of the traverse the vacuum pump was turned off and the probe was transferred into the next sample EPA port where an identical sample-traverse was then performed. Duct conditions (temperature, Δ -P)

Method 5: Continued

and sampling conditions (meter temperature, volume and pressure, probe, filter, sample line, impinger temperatures, and absorption train vacuum) was monitored and recorded regularly for each sample point.

Upon completion of sampling, the apparatus was leak tested at a vacuum greater than the highest observed vacuum. The leak was recorded and the apparatus was then sealed and transported to the mobile laboratory. The heated filter-to-impinger line was rinsed with a known amount of distilled water into the first impinger.

The filter and any loose particulate was carefully removed from the filter holder with tweezers. It was then placed in a labeled petri dish and transported to the P.C.E.S. laboratory. The nozzle, probe, and filter top housing was rinsed and brushed three times with distilled water and acetone. The sample fractions were combined, bottled, labeled, and fluid level marked for transportation to the P.C.E.S. laboratory. Aliquots of distilled water and acetone were similarly treated for blank analysis.

The absorption train was inspected for abnormalities and disassembled. The impingers were weighed on a digital balance for a percent moisture determination. The contents of the impingers were quantitatively transferred into separate bottles, sealed, labeled, and fluid level marked for transportation to the P.C.E.S. laboratory for analysis, if required. Aliquots of the reagent grade impinger contents were saved for blank analysis.

The filter was transferred to an oven and heated at 105 °F for 2-3 hours and then placed in a desiccator for 24 hours. The filter was then weighed on a Mettler digital balance to the nearest 0.01 mg. Additional six hour desiccations and weighings were then performed until the difference between consecutive weighings were less than 0.5 mg or one percent of the total filtrate weight (weighed to a constant weight).

The nozzle/probe/filter top wash was then examined for any leakage during transportation and transferred to a tared evaporation dish. The wash was then evaporated at an elevated temperature, below the boiling point of the wash, with occasional swirling. The dish and wash residue was then desiccated and weighed to a constant weight.

If required by the regulatory agency, the contents of the first impinger were recovered and diluted volumetrically to a known volume. An aliquot of this sample was then evaporated, desiccated, and then weighed to a constant weight.

The net weight of particulate was calculated from the two fractions (three fractions including the impinger contents, if required). Concentrations (gr/DSCF) and emissions (lbs/hr) or other applicable units were then calculated and reported.

EPA METHOD 2
STACK GAS VELOCITY AND VOLUMETRIC FLOWRATE

Average Stack Gas Velocity
Eq. 2-6 & Eq. 2-9

$$P_g = \frac{\text{Static Pressure, H}_2\text{O}}{13.6}$$

$$P_s = P_{\text{bar}} + P_g$$

$$V_s = K_p C_p (\sqrt{\Delta P})_{\text{avg}} \sqrt{\frac{T_s (\text{avg})}{P_s M_s}}$$

Average Stack Gas Dry Volumetric Flow Rate
Eq. 2-10

$$Q_{\text{std}} = 60 (1 - B_{\text{ws}}) V_s A \left(\frac{T_{\text{std}}}{T_s (\text{avg})} \right) \left(\frac{P_s}{P_{\text{std}}} \right)$$

$$\frac{Q_{\text{std}}}{MF} = \text{SCFM}$$

EPA METHOD 3
DRY MOLECULAR WEIGHT OF STACK GAS
Eq. 3-2

$$M_d = 0.44 (\% \text{CO}_2) + 0.320 (\% \text{O}_2) + 0.280 (\% \text{N}_2 + \% \text{CO})$$

Wet Molecular Weight of Stack Gas

$$M_s = M_d (1 - B_{\text{ws}}) + 18 (B_{\text{ws}})$$

EPA METHOD 4
DETERMINATION OF MOISTURE CONTENT IN STACK GASES

Volume of Water Vapor Condensed
Eq. 4-1

$$V_{vc} (std) = \frac{(V_f - V_i) p_v RT_{std}}{P_{std} M_v} = K_1 (V_f - V_i)$$

Where: $K_1 = 0.04646 \frac{ft^3}{ml} @ 520^\circ R$

Volume of Water Vapor Collected in Silica Gel
Eq. 4-2

$$V_{vsg} (std) = \frac{(W_f - W_i) RT_{std}}{P_{std} M_v (453.6 \text{ g/lb})}$$

$$= K_2 (W_f - W_i)$$

Where: $K_2 = 0.04651 \frac{ft^3}{g} @ 520^\circ R$

Sample Gas Volume
Eq. 4-3

$$V_g (std) = V_g \gamma \left(\frac{(P_g) (T_{std})}{(P_{std}) (T_g)} \right)$$

$$= K_3 \gamma \frac{V_g P_g}{T_g}$$

Where: $K_3 = 17.38 \frac{^\circ R}{in. Hg} @ 520^\circ R$

Moisture Content
Eq. 4-4

$$B_{vs} = \frac{V_{vc} (std) + V_{vsg} (std)}{V_{vc} (std) + V_{vsg} (std) + V_g (std)}$$

$$B_{vs} \times 100 = \% H_2 O \text{ in gas stream}$$

$$MF = 1 - B_{vs}$$

EPA METHOD 5
DETERMINATION OF PARTICULATE EMISSIONS FROM STATIONARY SOURCES
 Use in Method 5 and 8 combinations runs

Dry Gas Volume
 Eq. 5-1

$$\begin{aligned}
 V_{\#} (std) &= V_{\#} Y \left(\frac{T_{std}}{T_{\#}} \right) \left[P_{bar} + \frac{\Delta H}{13.6} \right] \\
 &= K_1 V_{\#} Y \left[\frac{P_{bar} + \frac{\Delta H}{13.6}}{T_{\#}} \right] \\
 &= K_1 = 17.38 \frac{R}{in.Hg} @ 520 \cdot R
 \end{aligned}$$

*In case of leak rate beyond allowable limits, correct Eq. 5-1 as follows:
 Case 1 - No component changes made during run.

$$V_{\#} = V_{\#} - (L_p - L_d) \theta$$

Case 2 - One or more component changes made during run.

$$V_{\#} = \left[V_{\#} - (L_1 - L_d) \theta_1 - \sum_{i=2}^n (L_i - L_d) \theta_i - (L_p - L_d) \theta_p \right]$$

Volume of Water Vapor
 Eq. 5-2

$$\begin{aligned}
 V_{vc} (std) &= V_1 c \left(\frac{P_v}{M_v} \right) \left(\frac{RT_{std}}{P_{std}} \right) \\
 &= K_2 V_1 c
 \end{aligned}$$

$$\text{Where: } K_2 = 0.04646 \frac{ft^3}{ml} @ 60 \cdot F$$

Moisture Content
 Eq. 5-3

$$B_{vs} = \frac{V_{vc} (std)}{V_{\#} (std) + V_{vc} (std)}$$

EPA METHOD 5
(con't)

Acetone Blank Concentration
Eq. 5-4

$$C_1 = \frac{M_1}{V_1 \rho_1}$$

Acetone Wash Blank
Eq. 5-5

$$W_1 = C_1 V_{1W} \rho_1$$

Particulate Concentration
Eq. 5-6

$$C_3 = \frac{gr}{dscf} = \left(0.001 \frac{g}{mg} \right) \left(\frac{M_H}{V_H (std)} \right) (15.432)$$

$$gr/dscf (MF) = \frac{gr}{scf}$$

Corrected to 12 % CO₂

$$\frac{gr}{dscf} @ 12\% CO_2 = \frac{\frac{gr}{dscf} \times 12\% CO_2}{\% CO_2 (dry)}$$

Isokinetic Variation
Eq. 5-7 and 5-8

$$\% I = 100 \times \frac{T_s \left[V_1 C K_3 + \frac{V_H}{T_H} \left(P_b + \frac{\Delta H}{13.6} \right) \right]}{60 \theta A_H V_s P_s}$$

Where: $K_3 = 0.002669$

Mass Emission Rate

$$\frac{lbs}{hr} = \frac{gr}{dscf} \times dscfm \times 60 \frac{m}{hr} \times \frac{1 lb}{7000 gr}$$

NOMENCLATURE

(1 of 3)

A	= Cross-sectional area of stack (ft^2)
A_n	= Cross-sectional area of nozzle, (ft^2)
B_{vs}	= Proportion of water vapor, by volume, in the gas stream
C_a	= Acetone blank residue concentration, (mg/g)
C_p	= Pitot tube coefficient, dimensionless
C_s	= Concentration of particulate matter in stack gas, dry basis corrected to standard conditions, (gr/dscf)
C_{SO_2}	= Concentration of sulfur dioxide dry basis corrected to standard conditions, (lb/dscf)
$C_{H_2SO_4}$	= Sulfuric acid (including SO_3) concentration, corrected to standard conditions, (lb/dscf)
ΔH	= Average pressure differential across the orifice meter, (in H_2O)
K_p	= Pitot tube constant, $85.49 \frac{\text{ft} \cdot [(\text{lb}/\text{lb-mole})(\text{in Hg})]^{1/2}}{\text{sec} \cdot (^{\circ}\text{R})(\text{in H}_2\text{O})}$
L_p	= Leakage rate observed during the post-test leak check, (cfm)
L_a	= Maximum acceptable leakage rate, (0.02 cfm or 4% of average sampling rate, whichever is less)
L_i	= Individual leakage rate observed during the leak check conducted prior to the " i^{th} " component change, (cfm)
M_a	= Mass of residue of acetone after evaporation, mg
M_d	= Molecular weight of stack gas, dry basis, (lb/lb-mole)
M_n	= Total weight of particulate matter collected, mg
M_s	= Molecular weight of stack gas, wet basis, (lb/lb-mole)
M_v	= Molecular weight of water, 18 lb/lb-mole
N	= Normality of barium perchlorate titrant, (milliequivalents/ml)
ΔP	= Velocity head of stack gas, (in H_2O)
P_{bar}	= Barometric pressure at measurement site (in Hg)
P_g	= Stack static pressure, (in Hg)
P_a	= Absolute pressure at the dry gas meter, ($P_{bar} + \Delta H/13.6$)

NOMENCLATURE

(2 of 3)

P_s	= Absolute stack gas pressure, (inches Hg)
$P_{(std)}$	= Standard absolute pressure, 29.92 in Hg
$Q_{(std)}$	= Dry volumetric stack gas flow rate, standard conditions, (dscfm)
R	= Ideal gas constant, 21.85 (in Hg) (ft ³)/(lb-mole)(°R)
t_s	= Stack temperature, (°F)
T_m	= Absolute temperature at meter, (°R)
$T_{(std)}$	= Standard absolute temperature, (520°R)
T_s	= Absolute stack temperature, (460° + t_s)
V_a	= Volume of sample aliquot titrated, (ml)
V_{ab}	= Volume of acetone blank, ml
V_m	= Dry gas volume measured by dry gas meter, (dcf)
$V_{m(std)}$	= Dry gas volume measured by dry gas meter, corrected to standard conditions, (dscf)
$V_{vc(std)}$	= Volume of water vapor condensed corrected to standard conditions, (scf)
$V_{vsg(std)}$	= Volume of water vapor collected in silica gel corrected to standard conditions (scf)
V_{ic}	= Volume of water vapor condensed in impingers and silica gel, (ml)
V_f	= Final volume of condensed water, ml
V_i	= Initial volume of condensed water, ml
v_s	= Average stack gas velocity, (ft/sec)
V_{soln}	= Total volume of solution in which the sulfur dioxide sample is contained (ml)
V_t	= Volume of barium perchlorate titrant used for the sample, (ml)
V_{tb}	= Volume of barium perchlorate titrant used for the blank, (ml)
W_f	= Final weight of silica gel or silica gel plus impinger, (g)
W_i	= Initial weight of silica gel or silica gel plus impinger, (g)
Y	= Dry gas meter calibration factor
ρ_w	= Density of water, (0.002202 lb/ml @ 60°F)

NOMENCLATURE

(3 of 3)

ρ_a	= Density of acetone, (g/ml)(see bottle label)
MF	= Moisture factor
%CO ₂	= Percent CO ₂ by volume (dry basis)
%O ₂	= Percent O ₂ by volume (dry basis)
%CO	= Percent CO by volume (dry basis)
%N ₂	= Percent N ₂ by volume (dry basis)
0.264	= Ratio of O ₂ to N ₂ in air v/v
0.280	= Molecular weight of N ₂ or CO, divided by 100
0.320	= Molecular weight of O ₂ , divided by 100
0.440	= Molecular weight of CO ₂ , divided by 100
60	= Conversion factor, (sec/min)
18.0	= Molecular weight of water, (lb/lb-mole)
32.03	= Equivalent weight of sulfur dioxide
θ	= Total sampling time (min)
θ_i	= Sampling time interval, between two successive component changes, beginning with the interval between the first and second changes, (min)
θ_1	= Sampling time interval, from the run beginning until first component change, (min)
θ_p	= Sampling time interval, from the final (n th) component change until the end of the sampling run, (min)

CONTINUOUS EMISSION MONITORING SYSTEM (CEMS)

Reference: Manual of Procedures; ST-13A, ST-19A, Jan 1982, State of California, Air Resources Board, Test Methods 1-100, June 1979.
EPA CFR Title 40, Pt. 60, Appendix A, Method 3A, 6C, 7E, & 10.

Instrument Summary

A constant sample of flue gas was extracted, dried, filtered and delivered to an instrument manifold system for distribution to one or more analyzers. Instrument results are recorded on an analog strip chart recorder. System calibration checks are performed as well as calibration checks at the beginning and end of each test run. Final data reduction includes zero and calibration drift corrections.

Sample Conditioning System

Consists of a borosilicate glass tube or 316 grade stainless steel probe fitted with a cindered stainless steel or pyrex glass wool particulate filter. The probe is fitted with a teflon (TFE) sample line which connects to a water condensation system located at the source. The condensation system consists of three 500-ml short stem glass impingers connected in a series, immersed in an ice bath. The gas is delivered to the instrument trailer with a teflon line (3/8" O.D.) through an in-line Balston particulate filter drawn by a teflon-coated diaphragm pump. The sample system is leak checked prior to sampling by plugging the end of the sample probe and adjusting the sample pump to its maximum rate (approximately 22" Hg). The manifold is by-passed and the leak rate monitored through a gas meter or low range flow meter.

Manifold System

Sample gas is delivered to each analyzer through a five way valve and regulated with a needle valve flow meter. Manifold pressure is controlled by a back pressure regulator which is typically set at three psi. Zero gas (N_2) and calibrated gases are delivered to the analyzers using the same five way valve and flow meter. All manifold parts are glass, stainless steel, or teflon materials.

Analog Strip Chart Data Reduction

Analog recordings consists of averaged time increments as shown on the data pages (typically 5, 10, or 20 minute increments). Data for each increment was recorded at an average percent of full scale. The readings were then compared with the zero and calibration readings for calculation of the average concentration for each time increment. Any deviation of the zero and calibration readings from the start to the end of a test period was corrected by calculating apparent zero and calibration readings for the mid-point of each time increment. The average concentrations were then calculated from the sample readings and the apparent zero and span readings.

EPA METHOD 18
HYDROCARBON EMISSIONS TESTING
FID ANALYSIS

Sampling Procedures

The sample was drawn via evacuated cannister through a stainless steel/teflon probe into a tedlar bag. Each sample bag was evacuated and then filled.

Analytical Procedures

The contents of the tedlar bag are analyzed by gas chromatography. The gas chromatograph is calibrated with an appropriate standard for each carbon #, before and after each set of samples are analyzed. The sample is speciated by carbon #-C₁, C₂, C₃, C₄, C₅, and C₆₊ backflush.

Symbol Identification

i = Carbon #; i = 1 to 6+
s = Refers to standard for that carbon #
Rx_i = Response factor for C_i
MW = Molecular weight - g/mole
DSCFM = Average volume flow rate of unit tested

Equations

$$Rx_i = \frac{Area_{std}}{ppm_{std}}$$

$$Sample\ ppm_i = \frac{1}{Rx_i} \times Area_i$$

$$Sample\ ppm\ (as\ C_1) = Sample\ ppm \times \#\ of\ carbons$$

$$\frac{lbs}{hr_i} = ppm_i \times MW_i \times DSCFM \times 1.581 \times 10^{-7}$$

$$Total\ non-methane\ \frac{lbs}{hr} = \sum_{2}^{6+} \frac{lbs}{hr_i}$$

Note 1: If lbs/hr as methane is required, MW will equal 16.0 (MW of methane)
Note 2: # of carbons: ethane = 2; propane = 3; etc...

APPENDIX I
OPERATIONAL DATA
(Supplied by Destec)

COMPANY : DESTEC
 UNIT : DOUBLE C - TURBINE #1 & #2
 DATE : 02/09-10/93
 REPORT : 027-341

CEM DATA SUMMARY

RUN #	TIME	TURBINE #1			TURBINE #2		
		%O2	NOx ppm	CO ppm	%O2	NOx ppm	CO ppm
1	1130-1200	13.92	2.24	43.7	14.14	3.01	41.0
2	1215-1245	13.93	2.26	43.0	14.12	3.00	41.0
3	1300-1330	13.92	2.42	43.6	14.13	3.05	40.8
4	1400-1430	13.92	2.50	45.2	14.13	3.00	42.2
5	1445-1515	13.92	2.49	46.2	14.16	3.00	42.5
6	1535-1605	13.92	2.49	46.9	14.13	3.00	41.7
7	1615-1645	13.92	2.57	42.5	14.12	3.00	40.3
8	900-930	13.97	2.50	46.4	14.13	3.00	40.8
9	1000-1030	14.03	2.50	43.9	14.12	3.00	43.6
10	1045-1115	14.09	2.53	42.6	14.12	3.00	44.0
11	1130-1200	14.13	2.55	40.9			
12	1215-1245	14.13	2.76	38.1			
AVERAGE		13.98	2.48	43.6	14.13	3.01	41.8

EMISSIONS MONITORING LOG
DOUBLE C - LOG 7 (12HR)

17:25:21

09FEB93

PD

HH:MM:SS	1 BLR1NOX PPMVD AVG	2 BLR1CO PPMVD AVG	3 BLR1NOCR PPMVD AVG	4 BLR1COCR PPMVD AVG	5 BLR1O2 PPMVD AVG	6 9LR2NOX PPMVD AVG	7 BLR2CO PPMVD AVG	8 BLR2NOCR PPMVD AVG	9 BLR2COCR PPMVD AVG	10 BLR2O2 PPMVD AVG	11 XS1932 CALIBR
05:30:00	2.60	35.92	2.365451	31.5	14.30	3.32	40.25	3.1	35.9	14.41	NORM
05:45:00	2.67	34.35	2.439711	30.1	14.32	3.63	37.42	3.3	33.3	14.43	NORM
06:00:00	2.50	38.36	2.266693	33.7	14.32	3.75	39.03	3.3	34.8	14.43	NORM
06:15:00	2.50	38.60	2.264319	33.8	14.32	3.54	38.72	3.3	34.4	14.39	NORM
06:30:00	2.62	37.49	2.384440	32.9	14.32	3.75	37.83	3.3	33.7	14.43	NORM
06:45:00	2.75	37.39	2.512190	32.8	14.32	3.73	38.78	3.3	34.5	14.43	NORM
07:00:00	2.75	37.08	2.519226	32.5	14.33	3.66	38.59	3.3	34.3	14.43	NORM
07:15:00	2.66	37.44	2.423011	32.8	14.32	3.56	38.35	3.3	34.2	14.40	NORM
07:30:00	2.51	38.01	2.279409	33.4	14.32	3.76	38.02	3.3	33.9	14.43	NORM
07:45:00	2.50	37.86	2.267710	33.2	14.32	3.77	37.47	3.3	33.4	14.43	NORM
08:00:00	2.50	37.86	2.271271	33.2	14.32	3.76	37.23	3.3	33.2	14.43	NORM
08:15:00	2.50	38.22	2.271440	33.6	14.33	3.76	37.33	3.3	33.3	14.42	NORM
08:30:00	2.53	40.59	2.155643	34.7	14.16	3.76	34.94	3.3	30.6	14.31	NORM
08:45:00	2.63	41.54	2.144199	34.9	14.03	3.77	35.09	3.3	30.8	14.31	NORM
09:00:00	2.61	42.24	2.131059	35.5	14.02	3.76	35.32	3.3	30.6	14.23	NORM
09:15:00	2.49	43.13	2.019755	36.3	14.02	3.73	35.87	3.2	31.0	14.23	NORM
09:30:00	2.51	40.80	2.034081	34.3	14.02	3.48	38.33	3.0	33.2	14.23	NORM
09:45:00	2.51	38.53	2.027215	32.4	14.01	3.25	38.68	2.8	33.4	14.22	NORM
10:00:00	2.51	37.87	2.035522	31.8	14.01	3.29	38.10	2.8	32.9	14.23	NORM
10:15:00	2.35	41.70	1.865387	34.8	13.95	3.33	38.48	2.8	33.3	14.23	NORM
10:30:00	2.25	44.99	1.754252	37.3	13.89	3.51	37.62	3.0	32.7	14.41	NORM
10:45:00	2.24	45.29	1.755778	37.7	13.90	3.50	37.31	3.2	33.1	14.22	NORM
11:00:00	2.24	44.61	1.757050	37.1	13.90	3.45	38.29	3.0	32.0	14.20	NORM
11:15:00	2.24	44.06	1.759932	36.6	13.92	3.48	37.00	2.8	31.7	14.12	NORM
11:30:00	2.24	44.09	1.762590	36.8	13.92	3.32	37.11	2.8	31.9	14.10	NORM
11:45:00	2.24	43.71	1.763916	36.4	13.92	3.49	37.38	2.8	33.2	14.11	NORM
12:00:00	2.24	43.70	1.760271	36.4	13.93	3.26	38.98	2.8	33.2	14.12	NORM
12:15:00	2.26	43.99	1.772817	36.6	13.93	3.26	38.49	2.8	33.0	14.13	NORM
12:30:00	2.25	43.52	1.760186	36.1	13.93	3.26	38.71	2.8	33.0	14.13	NORM
12:45:00	2.27	43.07	1.787652	35.4	13.93	3.26	38.24	2.8	32.3	14.05	NORM
13:00:00	2.36	42.26	1.883443	35.1	13.93	3.26	38.60	2.8	32.9	14.12	NORM
13:15:00	2.49	41.32	2.009498	34.4	13.92	3.48	37.72	3.0	32.2	14.13	NORM
13:30:00	2.35	43.81	1.872677	38.1	13.92	3.50	37.62	3.0	31.7	14.05	NORM
13:45:00	2.34	43.39	1.863258	40.2	13.92	3.50	37.94	3.0	32.4	14.11	NORM
14:00:00	2.49	43.39	2.012041	36.1	13.92	3.35	39.09	2.8	33.3	14.11	NORM
14:15:00	2.49	44.44	2.013397	37.0	13.92	3.23	40.83	2.7	34.5	14.02	NORM
14:30:00	2.50	45.90	2.013228	38.2	13.92	3.01	42.75	2.5	36.1	14.02	NORM
14:45:00	2.49	45.57	2.013482	37.9	13.92	3.01	42.58	2.5	35.9	14.02	NORM
15:00:00	2.49	46.13	2.015771	38.4	13.92	3.00	42.23	2.5	35.8	14.03	NORM
15:15:00	2.49	46.28	2.016873	38.5	13.91	3.04	41.40	2.6	35.5	14.11	NORM
15:30:00	2.49	46.58	2.013312	39.7	13.92	3.23	41.04	2.7	34.8	14.05	NORM
15:45:00	2.49	47.90	2.017127	39.9	13.92	3.03	41.65	2.6	35.6	14.12	NORM
16:00:00	2.49	46.94	2.013823	38.2	13.92	3.22	40.18	2.7	34.4	14.12	NORM
16:15:00	2.49	46.55	2.019162	36.9	13.92	3.17	39.77	2.7	34.1	14.12	NORM
16:30:00	2.49	46.55	2.010515	36.4	13.92	3.25	40.07	2.8	34.4	14.13	NORM
16:45:00	2.51	47.51	2.152591	34.4	13.92	3.26	39.49	2.8	33.8	14.13	NORM
17:00:00	2.75	38.80	2.263048	32.1	13.92	3.26	39.99	2.8	33.1	14.12	NORM

EMISSIONS MONITORING LOG
DOUBLE C - LOG7 (12HR)

17:25:25

09FEB93

PD

HH:MM:SS

1
BLR1NOX
PPMVD
AVG2
BLR1CO
PPMVD
AVG3
BLR1NOCR
PPMVD
AVG4
BLR1COCR
PPMVD
AVG5
BLR102
PPMVD
AVG6
BLR2NOX
PPMVD
AVG7
BLR2CO
PPMVD
AVG8
BLR2NOCR
PPMVD
AVG9
BLR2COCR
PPMVD
AVG10
BLR202
PPMVD
AVG11
XS1932
CALIBR

12

17:15:00 2.75 37.25 2.261183 30.9 13.93 3.25 41.27 2.8 35.2 14.14 NORM

SUMMARY DATA

AVG 2.47 41.91 2.057946 35.4 14.04 3.42 38.69 3.0 33.5 14.22
 MAX 2.75 48.39 2.519226 40.2 14.33 3.77 42.75 3.3 36.1 14.43
 TMAX 7:00:00 13:45:00 7:00:00 13:45:00 8:15:00 14:30:00 14:30:00 14:30:00 14:30:00 6:45:00
 MIN 2.23 34.35 1.754252 30.1 13.89 3.00 34.94 2.5 30.6 14.02
 TMIN 11:00:00 5:45:00 10:30:00 5:45:00 10:30:00 15:00:00 8:30:00 15:00:00 9:00:00 14:45:00

EMISSIONS MONITORING LOG
DOUBLE C -LOG7 (12HR)

14:01:06

10FEB93

PD

12

11
XS1932
CALIBR

10
BLR202
PPMVD
AVG

9
BLR2COCR
PPMVD
AVG

8
BLR2NOCR
PPMVD
AVG

7
BLR2CO
PPMVD
AVG

6
BLR2NOX
PPMVD
AVG

5
BLR102
PPMVD
AVG

4
BLR1COCR
PPMVD
AVG

3
BLR1NOCR
PPMVD
AVG

2
BLR1CO
PPMVD
AVG

1
BLR1NOX
PPMVD
AVG

NORM

14.22

35.2

2.8

40.73

3.26

14.08

32.5

2.265591

38.34

2.76

SUMMARY DATA

AVG
MAX
TMAX
MIN
TMIN

14.31
14.51
8:00:00
14.19
10:00:00

35.5
37.9
11:30:00
31.9
12:45:00

2.7
3.2
12:30:00
2.5
10:00:00

40.58
43.27
11:30:00
36.42
12:45:00

3.10
3.72
12:30:00
2.75
10:00:00

14.15
14.23
4:30:00
13.92
9:45:00

32.2
40.4
9:45:00
27.1
2:15:00

2.355192
2.520328
5:00:00
1.939562
9:45:00

37.69
48.68
9:45:00
31.35
2:15:00

2.80
3.00
4:00:00
2.37
9:45:00

PD	11FEB93	18:48:03	EMISSIONS MONITORING LOG										LOG #	7	PAGE	2
HH:MM:SS	1	2	3	4	5	6	7	8	9	10	11	12				
	BLR1NOX	BLR1CO	BLR1NOCR	BLR1COCR	BLR102	BLR2NOX	BLR2CO	BLR2NOCR	BLR2COCR	BLR202	XS1932					
	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	CALIBR					
	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG						
18:45:00	3.52	30.21	3.020392	25.3	14.03	3.00	44.49	2.5	38.0	14.13	NORM					
SUMMARY DATA																
AVG	2.66	39.18	2.301064	33.1	14.07	3.12	40.31	2.6	34.6	14.17						
MAX	3.73	51.81	3.237406	42.9	14.33	3.67	44.99	3.3	38.4	14.40						
TMAX	18:00:00	16:30:00	18:00:00	16:30:00	7:15:00	7:30:00	17:45:00	7:30:00	17:45:00	7:30:00						
MIN	1.99	24.50	1.754845	21.4	13.91	3.00	33.44	2.5	29.4	14.10						
TMIN	16:30:00	8:15:00	16:45:00	8:15:00	16:30:00	17:45:00	7:30:00	17:45:00	7:45:00	17:30:00						

EMISSIONS MONITORING LOG
DOUBLE C - LOGS (DAILY)

09FEB93 00:02:33

- 1 GT-1 MNATTS
- 2 GAS FUEL FLOW
- 3 STEAM NOZZLE LOW FLOW ALARM
- 4 TURBINE 1 STEAM : FUEL RATIO
- 5 STEAM CDP LOW FLOW ALARM
- 6 INLET CO CATALYTIC CONVERTER
- 7 SRC REACTOR INLET LOW TEMP SEL
- 8 TOTAL FUEL FLOW TO TURBINE 1
- 9 TOTAL FUEL GAS FLOW TURBINE 2
- 10 CEM SYSTEM IN CALIBRATION
- 11
- 12

HH:MM:SS	1 J11964 MM AVG	2 MIIBX AVG	3 MIIBU AVG	4 WISTOF RATIO AVG	5 MIIBV AVG	6 TE1402 DEG F AVG	7 TI1456 DEG F AVG	8 GT1FGTGT HMPPH AVG	9 GT2FGTGT HMPPH AVG	10 XS1932 CALIBR
01:00:00	22.0	9557.0	17704.0	1.85	20467.2	975.4	739.1	4793.51	0.00	NORM
02:00:00	21.5	9382.2	17151.7	1.83	20368.4	979.9	739.5	14301.65	0.01	NORM
03:00:00	21.2	9280.1	16772.5	1.81	20376.5	981.9	740.2	23698.00	0.02	NORM
04:00:00	21.9	9519.4	17658.0	1.86	20287.0	976.0	740.0	33011.38	0.03	NORM
05:00:00	21.9	9538.3	17712.4	1.86	20260.9	976.5	740.9	42553.02	0.04	NORM
06:00:00	21.9	9397.3	17701.8	1.88	20247.3	977.3	740.9	52031.27	0.05	NORM
07:00:00	22.1	9423.9	17892.6	1.90	20251.1	975.9	740.7	61440.25	0.06	NORM
08:00:00	22.2	9461.9	18031.2	1.91	20261.0	975.3	740.7	70892.93	0.07	NORM
09:00:00	23.0	9834.7	19128.1	1.94	20562.0	982.3	745.6	80469.70	0.08	NORM
10:00:00	23.9	10186.8	20161.3	1.98	20900.2	989.0	750.5	90575.89	0.09	NORM
11:00:00	23.6	10157.6	19828.2	1.95	20721.8	989.9	750.8	100759.3	0.11	NORM
12:00:00	23.5	10133.0	19669.5	1.94	20956.6	990.8	751.1	110914.4	0.12	NORM
13:00:00	23.4	10116.7	19633.9	1.94	20959.9	991.3	751.3	121053.8	0.13	NORM
14:00:00	23.5	10095.5	19742.9	1.96	20939.1	991.0	751.3	131155.8	0.14	NORM
15:00:00	23.7	10151.0	20086.0	1.98	20913.5	990.1	751.3	141295.0	0.15	NORM
16:00:00	23.6	10145.3	19990.9	1.97	20893.8	990.5	751.7	151464.3	0.16	NORM
17:00:00	23.5	10077.1	19569.8	1.94	20822.5	992.1	752.5	161568.0	0.17	NORM
18:00:00	23.8	10196.7	20181.6	1.98	21294.0	990.7	752.9	171697.2	0.18	NORM
19:00:00	24.0	10271.9	20457.0	1.99	21325.3	990.0	753.6	181946.1	0.19	NORM
20:00:00	24.1	10304.7	20646.3	2.00	21285.4	989.8	753.9	192241.7	0.20	NORM
21:00:00	24.1	10309.3	20654.0	2.00	21319.9	990.7	754.3	202564.7	0.21	NORM
22:00:00	23.3	10021.5	19582.3	1.95	20965.5	985.5	750.4	212825.8	0.22	NORM
23:00:00	22.2	9630.1	18144.6	1.88	20207.9	977.5	743.5	222569.7	0.23	NORM
00:00:00	22.2	9637.9	18247.4	1.89	20225.1	976.6	742.5	232220.2	0.24	NORM

SUMMARY DATA 1025.2

AVG	22.9	9867.9	19014.5	1.92	20708.8	984.4	747.0	116997.6	0.12
MAX	24.1	10309.3	20654.0	2.00	21325.3	992.1	754.3	232220.2	0.24
TMAX	20:00:00	21:00:00	20:00:00	20:00:00	19:00:00	17:00:00	21:00:00	0:00:00	0:00:00
MIN	21.2	9280.1	16772.5	1.81	20207.9	975.3	739.1	4793.51	0.00
TMIN	3:00:00	3:00:00	3:00:00	3:00:00	23:00:00	8:00:00	1:00:00	1:00:00	1:00:00

EMISSIONS MONITORING LOG
DOUBLE C - LOG9 (DAILY)

PG 11FEB93 00:02:52

- 1 GT-2 MWATTS
- 2 GAS FUEL FLOW
- 3 STEAM NOZZLE LOW FLOW ALARM
- 4 TURBINE 2 FUEL TO STEAM RATIO
- 5 STEAM CDP LOW FLOW ALARM
- 6 INLT CO CATALYT CONV CO-02-101
- 7 SRC REACTOR INLT LO TEMP SELECT
- 8 COR NOX LEVEL AT STACK 02-101
- 9 COR CO LEVEL AT STACK 02-101
- 10 02 LEVEL AT STACK 02-101
- 11 CEM SYSTEM IN CALIBRATION
- 12

HH:MM:SS	1	2	3	4	5	6	7	8	9	10	11	12
	J12964	M21BX	M21BU	M2STOF	M21BV	TE2402	T12456	BLR2NOCR	BLR2COCR	BLR202	XS1932	
	MM	CS/HK	AVG	RATIO	AVG	DEG F	DEG F	PPMVD	PPMVD	PPMVD	CALIBR	
	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG		
01:00:00	23.7	10297.5	19683.6	1.91	19943.5	971.75	715.2	2.9	31.8	14.33	NORM	
02:00:00	23.9	10344.4	19968.6	1.93	19882.1	971.01	715.3	2.8	33.3	14.30	NORM	
03:00:00	24.0	10383.0	20135.0	1.94	19846.9	970.90	715.4	2.9	34.4	14.36	NORM	
04:00:00	24.2	10453.9	20500.4	1.96	19858.9	970.25	715.7	2.8	35.1	14.32	NORM	
05:00:00	24.3	10478.4	20645.6	1.97	19846.2	970.10	715.8	2.8	35.9	14.32	NORM	
06:00:00	24.4	10509.4	20852.6	1.98	19905.6	969.78	715.9	2.8	36.3	14.31	NORM	
07:00:00	24.4	10523.7	20976.7	1.99	19939.8	969.96	716.0	2.8	36.0	14.32	NORM	
08:00:00	24.2	10480.3	20636.1	1.97	19944.9	970.59	715.6	2.8	35.6	14.37	NORM	
09:00:00	24.7	10666.5	21301.1	2.00	20121.8	977.38	719.4	2.7	33.7	14.26	NORM	
10:00:00	25.1	10800.8	22101.5	2.05	20183.9	973.21	719.5	2.5	36.9	14.20	NORM	
11:00:00	24.9	10753.5	21868.4	2.03	20220.5	972.68	719.0	2.6	37.3	14.31	NORM	
12:00:00	24.8	10701.1	21526.2	2.01	20550.4	973.07	719.0	2.6	36.5	14.32	NORM	
13:00:00	24.7	10608.9	20502.2	1.96	21763.6	971.79	717.8	3.1	32.9	14.32	NORM	
14:00:00	25.2	10852.4	21728.0	2.00	21766.5	970.81	718.6	2.8	35.9	14.23	NORM	
15:00:00	25.0	10753.0	21215.6	1.97	21803.0	967.99	716.9	2.8	35.2	14.22	NORM	
16:00:00	25.0	10701.9	21073.3	1.97	21804.5	967.91	716.8	2.9	35.5	14.26	NORM	
17:00:00	25.0	10703.4	21070.0	1.97	21760.9	967.67	716.6	2.8	35.4	14.25	NORM	
18:00:00	25.1	10734.8	21043.5	1.96	21728.1	967.41	716.8	2.9	36.5	14.29	NORM	
19:00:00	25.1	10753.0	20999.1	1.95	21716.1	966.61	716.6	3.0	35.8	14.28	NORM	
20:00:00	25.1	10757.5	20969.3	1.95	21731.7	966.49	716.5	3.0	36.2	14.29	NORM	
21:00:00	24.4	10514.6	19838.8	1.89	21767.7	968.28	715.5	3.5	31.9	14.32	NORM	
22:00:00	24.1	10395.7	19219.0	1.85	21760.0	969.95	714.9	3.7	29.9	14.32	NORM	
23:00:00	24.2	10450.8	19601.8	1.88	21735.3	970.28	715.2	3.7	30.0	14.32	NORM	
00:00:00	24.6	10584.8	20553.8	1.94	21710.8	968.45	715.2	3.0	34.3	14.33	NORM	

SUMMARY DATA

AVG	24.6	10591.8	20760.8	1.96	20889.3	970.18	716.6	2.9	34.7	14.30	
MAX	25.2	10852.4	22101.5	2.05	21804.5	977.38	719.5	3.7	37.3	14.37	
TMAX	14:00:00	14:00:00	10:00:00	10:00:00	9:00:00	10:00:00	10:00:00	22:00:00	11:00:00	8:00:00	
MIN	23.7	10297.5	19219.0	1.85	19846.2	966.49	714.9	2.5	29.9	14.20	
TMIN	1:00:00	1:00:00	22:00:00	22:00:00	20:00:00	22:00:00	22:00:00	10:00:00	22:00:00	10:00:00	

APPENDIX II RAW DATA

COMPANY: Destec
 UNIT: Double "C" #1
 DATE: 2-9-93
 REPORT: 027-341

ON-SITE DATA

		RUN TIME	#1	#2	#3
Vm	Dry sampled gas volume, dcf		<u>1033-1645</u>	<u>840-1953</u>	
Y	Meter calibration factor (met# <u>1002, 1002</u>)		<u>190.63</u>	<u>174.97</u>	
Pbar	Barometric Pressure, "Hg		<u>.982977</u>	<u>.982977</u>	
Pstatic	Stack static pressure, "Hg		<u>28.49</u>	<u>29.24</u>	
ΔH	Stack static pressure, "Hg		<u>-.70</u>	<u>-.70</u>	
ΔH	Differential meter pressure, "H2O		<u>0.67</u>	<u>0.61</u>	
Tm	Meter temperature, °F		<u>69</u>	<u>67</u>	

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	990.2	579.2	411.0	846.7	553.1	293.6			
H ₂ O	985.8	586.5	369.3	898.1	613.5	284.6			
Dry	586.9	499.5	92.4	696.8	475.3	221.5			
Dry	489.4	487.8	1.6	490.0	484.9	5.1			
Dry	483.4	481.9	1.5	463.9	462.3	1.6			
Silica	873.8	844.6	29.20	806.0	777.3	28.7			
V _{lc} ^{1/2} volume of H ₂ O, gms			<u>854.9</u>			<u>785.1</u>			

		RUN	#1	#2	#3
CO ₂	% Dry Volume		<u>3.6</u>	<u>3.5</u>	
O ₂	% Dry Volume		<u>13.8</u>	<u>13.9</u>	
N ₂	% Dry Volume				
Cp	Pitot tube coefficient (Pit# _____)		<u>.791</u>	<u>.791</u>	
ΔP	Avg P, "H ₂ O		<u>1.064</u>	<u>1.099</u>	
Ts	Stack temperature, °F		<u>268</u>	<u>271</u>	
As	Stack area, sq. ft.				
Ds	Stack diameter, inches		<u>95.75</u>	<u>95.75</u>	
Dn	Nozzle diameter, inches		<u>.192</u>	<u>.193</u>	
Dur	Sampling time, min		<u>360</u>	<u>360</u>	
% Iso	Mini iso				

Filter #	<u>502</u>	<u>503</u>	
Filter tare weights, gms	<u>0.6163</u>	<u>0.6189</u>	

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

METHOD 5		RUN # 1 SW	
COMPANY: <u>Reslec</u> "Double C"			
UNIT: <u>Unit #1</u>			
DATE: <u>2-9-93</u>			
REPORT: <u>027-341</u>			
TECH: <u>DCJ</u>			
PUMP #: <u>CAST</u>			
METER BOX#: <u>1002</u>			
METER HQ: <u>0.85</u> (<u>111.982917</u>)			
PROBE #: <u>Cp: .791</u>			

PRE / POST TEST LEAK CHECK		AMBIENT TEMP, °F: 65°	
		Pbar: 28.49	
		STATIC PRESSURE ("Hg): -3.70	
		ASSUMED MOISTURE, %: 17.5% MWU 27.5	
		NOZZLE ID#:	
LEAK RATE: <.002 / <.001 cfm			
VACUUM: 10 / 5 "Hg			
		AVG. CALIB. NOZZLE DIAM. ("): .192	
		PROBE LINER MATERIAL: Qtz.	
		FILTER #:	
		DUCT DIAM. ("): 95.75	

TRAVERSE PT. NUMBER	TIME (e) min.	VACUUM "Hg	STACK TEMP (Ts) °F	VELOCITY HEAD (Δ Ps) "H2O	PRESSURE DIFFERENTIAL, "H2O		GAS SAMPLE VOLUME (cu. ft.)	GAS SAMPLE AT DRY GAS METER		FILTER HOLDER		TEMP OF GAS EXIT CONDENSER OR LAST IMPINGER
					RATE	Δ H		INLET, °F	OUTLET, °F	TEMP, °F	BOX	
12	13:45.00	2	267	1.10	0.538	0.69	396.50	69	69	243	265	
11	14:00.00	2	265	1.20	0.559	0.75	404.6	64	67	258	256	
10	15	2	268	1.10	0.533	0.69	413.0	64	65	264	255	
9	30	2	270	1.15	0.546	0.72	421.0	68	64	247	256	
8	45	2	272	1.20	0.558	0.74	429.1	70	64	246	259	
7	15:00.00	2	275	1.20	0.556	0.74	437.5	69	64	246	262	
6	15	2	273	1.10	0.533	0.69	445.9	68	64	244	261	
5	30	2	271	1.10	0.537	0.69	453.9	74	65	248	260	
4	45	2	271	1.05	0.525	0.66	461.9	74	65	247	260	
3	16:00.00	2	271	1.05	0.524	0.66	469.8	71	66	250	261	
2	15	2	271	1.05	0.523	0.66	477.6	70	66	250	261	
1	30	2	252	.85	0.475	0.56	485.5	67	65	249	261	
FOI	16:45.00						492.625					
							VM: 190.63					
							SD: 100.29					
							VF: 66.71					
AVG			268	1.064		0.67			69			

METHOD		RUN #	
5		2	
COMPANY: <u>DESTEC - Double "C"</u>			
UNIT: <u>#1</u>			
DATE: <u>2-10-93</u>			
REPORT: <u>027-341</u>			
TECH: <u>RJK</u>			
PUMP #: <u>GAST.</u>			
METER BOX#: <u>CB1002 (0.85)</u>			
METER HQ: <u>MCF = 0.982937</u>			
PROBE #: <u>Cp: 0.791</u>			
PRE/POST TEST LEAK CHECK			
LEAK RATE: <u>< 0.007</u> cfm		AMBIENT TEMP, °F: <u>55°</u>	
VACUUM: <u>10</u> "Hg		Pbar: <u>29.24</u>	
STATIC PRESSURE ("Hg): <u>-1.70</u>		ASSUMED MOISTURE, %: <u>17.5</u>	
NOZZLE ID#: <u>MW WET 27.5</u>		AVG. CALIB. NOZZLE DIAM ("): <u>0.192</u>	
PROBE LINER MATERIAL: <u>Q72.</u>		FILTER #:	
DUCT DIAM ("): <u>95.75</u>		TEMP OF GAS	

TRAVERSE PT. NUMBER <i>S.W. Part</i>	TIME (e) min.	VACUUM "Hg	STACK TEMP (Ts) °F	VELOCITY HEAD (Δ Ps) "H2O	PRESSURE		GAS SAMPLE VOLUME (cu. ft)	GAS SAMPLE TEMP.		FILTER HOLDER		TEMP OF GAS EXIT CONDENSER OR LAST IMPINGER
					RATE	DIFFERENTIAL, "H2O		INLET, °F	OUTLET, °F	PROBE	BOX	
12	8:40	2	267	1.10	0.475	0.60	493.00	55	54	246	250	
11	8:55	2	266	1.10	0.479	0.61	500.2	62	53	261	255	
10	9:10	2	270	1.15	0.490	0.63	507.2	66	55	248	257	
9	9:25	2	273	1.20	0.501	0.65	514.6	68	52	245	258	
8	9:40	2	273	1.20	0.501	0.65	522.2	68	52	250	259	
7	9:55	2	276	1.25	0.514	0.68	529.8	73	58	253	260	
6	10:10	2	277	1.10	0.482	0.61	537.5	73	59	255	260	
5	10:25	2	275	1.00	0.462	0.52	544.7	75	61	254	260	
4	10:40	2	274	1.05	0.474	0.59	551.7	75	62	251	259	
3	10:55	2	274	1.05	0.475	0.59	558.6	75	64	253	260	
2	11:10	2	274	1.05	0.476	0.59	565.7	76	65	255	262	
1	11:25	2	273	0.90	0.441	0.51	572.8	75	66	252	265	
P.C.	11:40						579.55					
							Vol = 86.55					
							Isa = 100.15					
							Vel Fps = 67.57					
AVG	PRELIMINARY AVERAGES		273	1.094	0.61							

COMPANY: DESTEC Double "C"		METHOD		RUN #		2 (Cont.)	
UNIT: #1		PRE/POST TEST LEAK CHECK		AMBIENT TEMP. °F: 67°			
DATE: 2-10-93				Pbar: 29.24			
REPORT: 027-341				STATIC PRESSURE (°Hg): -70			
TECH: RJK				ASSUMED MOISTURE, %: 17.5			
PUMP #: GAST.				NOZZLE ID #: 17W WET 27.5			
METER BOX #: CB1002 (0.85)				AVG. CALIB. NOZZLE DIAM. ("): 0.192			
METER HQ: MCF = 0.982977				PROBE LINER MATERIAL: Q12.			
PROBE #: Cp: 0.791				FILTER #:			
				DUCT DIAM. ("): 95.75			
493.00							
TRAVERSE PT. NUMBER S.E. ADJ.	TIME (e) min.	VACUUM °Hg	STACK TEMP (Ts) °F	VELOCITY HEAD (ΔPs) "H2O	DIFFERENTIAL, "H2O RATE	PRESSURE Δ H	GAS SAMPLE VOLUME (cu.ft)
12	11:53	2	270	1.15	0.496	0.64	579.90
11	12:08	2	268	1.15	0.501	0.64	587.3
10	12:23	2	269	1.20	0.512	0.67	594.7
9	12:38	2	270	1.20	0.512	0.67	602.5
8	12:53	2	268	1.25	0.525	0.69	610.3
7	1:08	2	269	1.35	0.545	0.74	618.2
6	1:23	2	270	1.05	0.478	0.59	626.3
5	1:38	2	270	1.00	0.465	0.57	633.5
4	1:53	2	270	1.00	0.463	0.56	640.5
3	2:08	2	271	1.00	0.461	0.56	647.4
2	2:23	2	270	1.00	0.461	0.56	654.2
1	2:38	2	267	0.95	0.450	0.54	661.2
END	2:53						667.97
							174.97
							ISO = 100.38
							VELFMS = 67.67
AVG			271	1.099		0.61	
							67

COMPANY : Deslec "Double C"
UNIT : #1
DATE : 2-8-93
REPORT : 027-341
RUN # : Initial
PUMP # :
METER BOX# : 1002
METER COEFF. : 0.982977 (41=0.85)
PILOT TUBE# :

[illegible]

COMPANY : Destec
 UNIT : Double 4" unit + 2
 DATE : 2-11-93, 2-12-93
 REPORT : 027-341

ON-SITE DATA

		RUN TIME	#1	#2	#3
Vm	Dry sampled gas volume, dcf		900-1521	338-1997	
Y	Meter calibration factor (met# _____)		172.78	171.79	
Pbar	Barometric Pressure, "Hg		.982977	.982977	
Pstatic	Stack static pressure, "Hg		29.22	29.22	
ΔH	Stack static pressure, "Hg		-1.75	-1.75	
ΔH	Differential meter pressure, "H2O		.58	.61	
Tm	Meter temperature, °F		63	59	

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	937.2	577.0	360.2	930.9	582.0	348.9			
H ₂ O	943.3	597.1	346.2	960.3	593.9	366.4			
Dry	535.7	495.7	40.0	546.9	498.6	48.3			
Dry	489.9	489.3	.6	496.9	496.8	.1			
Silica	866.5	837.7	28.8	861.0	834.0	27.0			
H ₂ O		<-50.1>				<55.3>			
Vlc	volume of H ₂ O, gms								
	725.7			735.4					

		RUN	#1	#2	#3
CO ₂	% Dry Volume		3.4	3.5	
O ₂	% Dry Volume		15.0	14.9	
N ₂	% Dry Volume				
Cp	Pitot tube coefficient (Pit# _____)		.791	.791	
ΔP	Avg P, "H ₂ O		1.105	1.119	
Ts	Stack temperature, °F		278	278	
As	Stack area, sq. ft.		50.00	50.0	
Ds	Stack diameter, inches		95.75	95.75	
Dn	Nozzle diameter, inches		.192	.192	
Dur	Sampling time, min		360	360	
% Iso	Mini iso		100.13	99.73	

Filter #	507	506	
Filter tare weights, gms	0.6148	.6189	

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (Inches) _____ Coupling _____

METHOD 5 RUN # 2

COMPANY: DESTEC "DOUBLE C"
 UNIT: #2 TURBINE OUTLET
 DATE: 2-12-93
 REPORT: 027-341
 TECH: RJK
 PUMP #: GAST (PD-09)
 METER BOX #: CB1002
 METER COEFF: McF = 0.982977
 PILOT TUBE #: 0.791

PRE POST TEST LEAK CHECK

LEAK RATE: < 0.005 cfm
 VACUUM: 10 "Hg

AMBIENT TEMP, °F: 47°
 P-bar: 29.22
 STATIC PRESSURE ("Hg): -0.75
 ASSUMED MOISTURE %: 17.5 PW WET 27.5

AVG. CALIB. NOZZLE DIAM ("): 0.192
 PROBE LINED MATERIAL: Q72.
 FILTER #: 95.75
 DUCT DIAM ("):

TRAVERSE PT. NUMBER SE. PORT	TIME (s) min.	VACUUM "Hg	STACK TEMP (T _s) °F	VELOCITY HEAD (ΔP _s) "H ₂ O	PRESSURE DIFFERENTIAL ΔH rate "H ₂ O ΔH	GAS SAMPLE VOLUME (cu. ft)	GAS SAMPLE TEMP. AT DRY INLET, °F OUTLET, °F	FILTER HOLDER TEMP °F Probe Box	TEMP OF GAS EXIT CONDENSED OR LAST IMPIGN °F
12	8:38	2	280	1.10	0.464 0.59	853.70	47 47	258 246	
11	8:53	2	279	1.10	0.468 0.59	860.8	54 48	258 248	
10	9:08	2	280	1.10	0.468 0.59	867.8	55 49	254 249	
9	9:23	2	281	1.10	0.469 0.59	874.8	56 50	251 252	
8	9:38	2	282	1.15	0.480 0.62	881.6	58 51	250 252	
7	9:53	2	282	1.20	0.492 0.64	888.8	60 52	249 246	
6	10:08	2	279	1.20	0.495 0.65	896.3	62 54	252 246	
5	10:23	2	277	1.10	0.475 0.60	903.7	62 55	255 246	
4	10:38	2	276	1.10	0.477 0.60	910.9	65 56	253 247	
3	10:53	2	277	1.15	0.490 0.63	918.0	67 58	251 245	
2	11:08	2	277	1.10	0.479 0.60	925.2	66 60	250 244	
1	11:23	2	276	0.90	0.433 0.51	932.4	63 60	249 244	
P.C.	11:38					939.2			
AVERAGE									

METHOD 5 RUN 1 2 (cont.)

COMPANY: DESTEC "DOUBLE C"
 UNIT: #2 TURBINE OUTFIT
 DATE: 2-12-93
 REPORT: 027-341
 TECH: RJR
 PUMP #: GAST (PD-09)
 METER BOX #: CB1002
 METER COEFF: $MCF = 0.982997$
 PILOT TUBE #: 0.791

PRE/POST TEST LEAK CHECK
 LEAK RATE: < 0.004 cfm
 VACUUM: 7.5 "Hg

AMBIENT TEMP, °F: 60°
 Pbat: 29.22
 STATIO PRESSURE ("Hg): -0.75
 ASSUMED MOISTURE, %: 17.5 MW WET 27.5
 AVG. CALIB. NOZZLE DIAM ("): 0.192
 PROBE LINE MATERIAL: Q72.
 FILTER #: 95.75
 DUCT DIAM ("): 95.75

85.50 + 86.29

TRAVERSE PT. NUMBER	TIME (s) min.	VACUUM "Hg	STACK TEMP (°s) °F	VELOCITY HEAD (ΔPa) "H ₂ O	PRESSURE DIFFERENTIAL ΔH rate "H ₂ O ΔH	GAS SAMPLE VOLUME (cu. ft)	GAS SAMPLE TEMP. AT DRY INLET, °F	GAS METER OUTLET, °F	FILTER HOLDER TEMP °F	TEMP OF GAS EXIT CONDENSER OR LAST IMPIGNI °F
S.W. PORT										
12	11:47	2	276	1.15	0.488	939.50	60	60	250	248
11	12:02	2	278	1.25	0.507	946.5	61	58	250	251
10	12:17	2	277	1.20	0.497	954.0	61	58	251	250
9	12:32	2	276	1.15	0.488	961.3	62	58	249	252
8	12:47	2	278	1.25	0.508	968.8	62	59	252	254
7	1:02	2	276	1.25	0.509	976.2	63	59	244	249
6	1:17	2	278	1.20	0.499	983.9	64	59	250	249
5	1:32	2	279	1.10	0.478	991.5	64	61	251	247
4	1:47	2	280	1.10	0.477	998.7	64	60	254	249
3	2:02	2	278	1.05	0.468	1005.8	65	61	250	250
2	2:17	2	279	1.05	0.468	1012.8	66	61	249	250
1	2:32	2	278	0.85	0.421	1019.8	65	61	252	249
End	2:47					1025.89				
						Vol = 171.79				
						T50 = 99.73				
						Vel Fps = 9.62				
AVERAGE			278	1.119	0.61			59		

A simple line drawing of a rectangle positioned above an oval. The rectangle is oriented horizontally and the oval is oriented vertically.

COMPANY	:	DESTEC "DOUBLE C"
UNIT	:	#2
DATE	:	2-11-93
REPORT	:	027-341
RUN #	:	VEL INTERNAL
PUMP #	:	GAST.
METER BOX#:	:	CB/002
METERcoeff:	:	0.982977 (0.85)
PITOT TUBE#:	:	C

[illegible]

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Deste

REPORT: 027-341

LOCATION/UNIT: Turbine #1

DATE TESTED: 2/9/93

ANALYST: DGS

RUN # 1

PROBE/NOZZLE/FILTER TOP

VOL-285 ml

DISH # 53 #1	#2	#3	AVERAGE
FINAL (g) <u>77.6804</u>	<u>77.6804</u>		<u>77.6804</u>
TARE (g) <u>77.6693</u>			<u>77.6693</u>
NET (g)			<u>0.0113</u>

FILTER # 502

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6168</u>	<u>0.6167</u>		<u>0.6168</u>
TARE (g) <u>0.6163</u>			<u>0.6163</u>
NET (g)			<u>0.0005</u>

CONDENSABLE (aliquot 250 ml / 1233 ml)

DISH # 64 #1	#2	#3	AVERAGE
FINAL (g) <u>76.8164</u>	<u>76.8177</u>	<u>76.8176</u>	<u>76.8177</u>
TARE (g) <u>76.8159</u>			<u>76.8159</u>
NET (g)			<u>0.0018</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Deste

REPORT: 027-34/

LOCATION/UNIT: Turbine #1

DATE TESTED: 2/10/93

ANALYST: DGS

RUN # 2

PROBE/NOZZLE/FILTER TOP

VOL- 185 ml

DISH # <u>3</u> #1	#2	#3	AVERAGE
FINAL (g) <u>77.6970</u>	<u>77.6987</u> ✓	<u>77.6986</u> ✓	<u>77.6987</u>
TARE (g) <u>77.6913</u>	_____	_____	<u>77.6913</u>
NET (g)			<u>0.0074</u>

FILTER # 503

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6191</u>	<u>0.6192</u>		<u>0.6192</u>
TARE (g) <u>0.6189</u>	_____	_____	<u>0.6189</u>
NET (g)			<u>0.0003</u>

CONDENSABLE (aliquot 250ml / 1141 ml)

DISH # <u>10</u> #1	#2	#3	AVERAGE
FINAL (g) <u>74.8786</u>	<u>74.8795</u> ✓	<u>74.8792</u> ✓	<u>74.8794</u>
TARE (g) <u>74.8778</u>	_____	_____	<u>74.8778</u>
NET (g)			<u>0.0016</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbine #2

DATE TESTED: 2/11/93

ANALYST: DGS

RUN # 1

PROBE/NOZZLE/FILTER TOP

VOL- 254ml

DISH # <u>4^u</u> #1	#2	#3	AVERAGE
FINAL (g) <u>81.4366</u>	<u>81.4376</u> ✓	<u>81.4377</u> ✓	<u>81.4377</u>
TARE (g) <u>81.4304</u>	_____	_____	<u>81.4304</u>
NET (g)			<u>0.0073</u>

FILTER # 507

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6152</u>	<u>0.6151</u>		<u>0.6152</u>
TARE (g) <u>0.6148</u>	_____	_____	<u>0.6148</u>
NET (g)			<u>0.0004</u>

CONDENSABLE (aliquot 250ml / 1115ml)

DISH # <u>62</u> #1	#2	#3	AVERAGE
FINAL (g) <u>90.2237</u>	<u>90.2247</u> ✓	<u>90.2245</u> ✓	<u>90.2246</u>
TARE (g) <u>90.2226</u>	_____	_____	<u>90.2226</u>
NET (g)			<u>0.0020</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbine #2

DATE TESTED: 2/12/93

ANALYST: DGS

RUN # 2

PROBE/NOZZLE/FILTER TOP

VOL- 285 ml

DISH # <u>43</u> #1	#2	#3	AVERAGE
FINAL (g) <u>73.6306</u>	<u>73.6330</u>	<u>73.6325</u>	<u>73.6328</u>
TARE (g) <u>73.6171</u>	_____	_____	<u>73.6171</u>
NET (g)			<u>0.0157</u>

FILTER # 506

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6195</u>	<u>0.6193</u>		<u>0.6194</u>
TARE (g) <u>0.6189</u>	_____	_____	<u>0.6189</u>
NET (g)			<u>0.0005</u>

CONDENSABLE (aliquot 250 ml / 1194 ml)

DISH # <u>12</u> #1	#2	#3	AVERAGE
FINAL (g) <u>76.9014</u>	<u>76.9024</u>	<u>76.9023</u>	<u>76.9024</u>
TARE (g) <u>76.9004</u>	_____	_____	<u>76.9004</u>
NET (g)			<u>0.0020</u>

COMPANY: DesteC DOUBLE C
 UNIT: LOV #1 TURBINE
 DATE: 2-26-93
 REPORT: 001-341

ON-SITE DATA

	RUN TIME	#1	#2	#3
Vm	Dry sampled gas volume, dcf	10:43-11:23 24.12	11:25-12:05 23.97	12:08-12:48 24.15
Y	Meter calibration factor (met# _____)	.999882	.999882	.999882
Pbar	Barometric Pressure, "Hg	29.30	29.30	29.30
Pstatic	Stack static pressure, "Hg			
ΔH	Differential meter pressure, "H2O	.60	.60	.60
Tm	Meter temperature, °F	59.94	67.61	66.13

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	6358.9	581.7	57.2	672.4	617.2	55.2	663.8	605.6	58.20
H ₂ O	560.5	558.7	1.8	635.8	634.2	1.6	566.8	565.0	1.8
CO	486.6	486.1	0.5	495.3	494.9	0.4	534.8	534.5	0.3
Silica (gel)	774.0	769.2	4.8	876.3	871.8	4.5	777.4	773.8	3.6
Line WATER			<52.7>			<49.9>			<52.4>

meCl = V_{iso} = 56.3 volume of H₂O, gms 11.6
 H₂O = 121.1
 H₂O = 2.23%
 meCl = 59.06 H₂O = 113.67 RUN #1 H₂O = 2.30%
 meCl = 56.2 H₂O = 119.8 #2 H₂O = 2.23%
 meCl = 56.2 H₂O = 119.8 #3 H₂O = 2.23%

CO ₂	% Dry Volume			
O ₂	% Dry Volume			
N ₂	% Dry Volume			
Cp	Pitot tube coefficient (Pit# _____)			
ΔP	Avg P, "H ₂ O ft/min	53.75	54.125	54.625
Ts	Stack temperature, °F	70.88	74	74
As	Stack area, sq. ft.			
Ds	Stack diameter, inches			
Dn	Nozzle diameter, inches			
Dur	Sampling time, min			
% Iso	Mini iso			

Filter # _____
 Filter tare weights, gms _____

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

COMPANY : Destec
 UNIT : Double "C" LOV GENERATOR 1
 DATE : 2-11-93
 REPORT : 027-341

ON-SITE DATA

		RUN TIME	#1	#2	#3
Vm	Dry sampled gas volume, dcf		10.58	11.45	12.34
Y	Meter calibration factor (met# _____)		24.0	24.05	24.00
Pbar	Barometric Pressure, "Hg		998954	998954	998954
Pstatic	Stack static pressure, "Hg		29.22	29.22	29.22
ΔH	Differential meter pressure, "H2O				
Tm	Meter temperature, °F		45	59	61
			72.13	72.56	72.06

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H2O	617.8	617.6	.2	612.5	612.5	0.00	615.4	615.1	.3
H2O	554.5	554.0	.5	593.5	593.0	.5	562.5	562.1	.4
Dry	492.8	492.9	<.1>	485.5	485.4	.1	493.2	492.9	.4
Silica	793.4	796.1	4.3	799.1	794.7	4.4	797.5	793.4	4.1

Vlc volume of H2O, gms 4.9 5.0 5.2

		RUN	#1	#2	#3
CO2	% Dry Volume				
O2	% Dry Volume				
N2	% Dry Volume				
Cp	Pitot tube coefficient (Pit# _____)				
ΔP	Avg P, "H2O FT/MIN		393.75	380.63	371.25
Ts	Stack temperature, °F		96.38	95.88	93.13
As	Stack area, sq. ft.				
Ds	Stack diameter, inches		3.75"	3.25"	3.25"
Dn	Nozzle diameter, inches				
Dur	Sampling time, min		40	40	40
% Iso	Mini iso				

Filter # _____
 Filter tare weights, gms _____

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

COMPANY: Destec "Double C" UNIT: Lube Oil Vent GENI DATE: 2-11-93 REPORT: 027-341 TECH: DEJ/BDM PUMP #: GAST METER BOX#: 1003 METER HQ: 1028 PROBE #: _____ Cp: _____				METHOD 4 Condense / NC RUN # 1 AMBIENT TEMP, °F: 60 PRE / POST TEST LEAK CHECK LEAK RATE: <.002 / <.001 cfm VACUUM: 5 / 2 "Hg NOZZLE ID#: _____ AVG. CALIB. NOZZLE DIAM. ("): _____ PROBE LINER MATERIAL: _____ FILTER #: _____ DUCT DIAM ("): 3.25"			
---	--	--	--	---	--	--	--

TRAVERSE PT. NUMBER	TIME (e) min.	VACUUM "Hg	STACK TEMP (Ts) °F	VELOCITY HEAD (Δ Ps) "H2O	PRESSURE DIFFERENTIAL, "H2O		GAS SAMPLE VOLUME (cu. ft)	GAS SAMPLE TEMP. AT DRY GAS METER		FILTER HOLDER TEMP, °F		TEMP OF GAS EXIT CONDENSER OR LAST IMPINGER
					RATE	Δ H		INLET, °F	OUTLET, °F	PROBE	BOX	
0	10:38.0	1	97	375	.6	.45	023.10	70	70			
5		1	99	415	.6	.45	026.3	68	73			
10		1	96	400	.6	.50	029.1	69	74			
15		1	100	400	.6	.40	032.2	69	75			
20		1	96	400	.6	.45	035.0	70	76			
25		1	97	390	.6	.40	038.1	70	76			
30		1	90	400	.6	.45	041.1	70	76			
35		1	96	370	.6	.50	044.1	71	77			
40	11:38.0						047.1					
			96.38	393.75	.6	.45	Nm: 024.00		72.13			
AVG												

COMPANY: Deste "Double C"
WELL: Lube 0.1 Vent GEN 1
DATE: 2-11-93
REPORT: 027-341
TECH: DSW/ADM
PUMP #: GAST
MEIEN BOX#: 1003
MEIEN COEFF: 1.028 (998924)
PILOT TUBE#:

LEAK DATE: <.005 / <.005
VACUUM: 5 / 5

AMBIENT TEMP., °F: 60
 P_{bar}:
 STATIC PRESSURE ("Hg):
 ASSUMED MOISTURE, %:
 AVG. CALIB. NOZZLE DIAM ("):
 PROBE LINE MATERIAL:
 FILTER #:
 DUCT DIAM ("): 3.25"

Petro Chem Environmental Services, Inc.

METHOD 1 Condense/VC RUN # 3

COMPANY: Destec "Double C"

COMPANY: USGR. MADE IN
TUBE OIL Vent GEN 1

DATE: 2-11-93

REF: 027-341

ECU: D01/BOM

PUMP #: 6A3T

REVEN BOX#: 1003

MEIEN coeff: 1.028

DATE WHEN:

PRE / POST TEST LEAK CHECK

LEAK DATE: $<.004$ / $<.001$

LEAK RATE: 5 / 5
VACUUM: 5 / 5

AMBIENT TEMP, °F: 60°

Phar:

STATIC PRESSURE ("10):

ASSUMED MOISTURE, %:

AVG. CALIB. NOZZLE DIAM("):

PHORE I INEN MATERIAL:

FILTER:

DUCT DIAM ("): 3.25"

FT/MIN
VELOCITY

[illegible]

ON-SITE DATA

		RUN TIME	#1	#2	#3
Vm	Dry sampled gas volume, dcf		16.43	17.29	18.14
Y	Meter calibration factor (met# _____)		24.35	24.06	24.0
Pbar	Barometric Pressure, "Hg		29.22	29.22	29.22
Pstatic	Stack static pressure, "Hg				
ΔH	Differential meter pressure, "H2O		.60	.59	.60
Tm	Meter temperature, °F		71.5	68.88	67.44

Y lc **volume of H₂O, gms**

RUN

#1

#2

#3

CO2	% Dry Volume			
O2	% Dry Volume			
N2	% Dry Volume			
Cp	Pitot tube coefficient (Pit# _____)			
ΔP	Avg P, "H2O FT/MIN	45.25	49.13	47.63
Ts	Stack temperature, °F	83.98	79.25	77.25
As	Stack area, sq. ft.			
Ds	Stack diameter, inches			
Dn	Nozzle diameter, inches			
Dur	Sampling time, min	40	40	40
% Iso	Mini iso			

Filter # _____
Filter tare weights, gms _____

CONTROL BOX#:

Hi P_____ Lo P_____ Avg P_____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

METHOD 4 Condense / NC RUN # 1

COMPANY: Destec "Double C"
UNIT: Lube Oil Vent Turbine
DATE: 2-11-93
REPORT: 027-341
TECH: JJJ BDM
PUMP #: GAST
NAME/EN BOX#: 1003
NAME/EN coeff: 1.028 (9989.54)
PILOT TUBE#:

VIII: Lube Oil Vent Turbine 2

DATE: 2.11.93

ИДЕНТИФИКАЦИОННИ БРОЈ: 027-341

TECH: D	BDM
---------	-----

PUMP #: 6AST

METER BOX: 1003

MEIEN (off: 1078 (998954)

PILOT TUBES:

PRE / POST TEST LEAK CHECK

LEAK RATE: $< .002$ / $< .002$ cfm cfm

VACUUM: 5 / 5 " Hg

AMBIENT TEMP, °F: 60°

Index:

STATIO PRESSURE(10):

ASSUMED MOISTURE, %:

AVG. CALIB. NOZZLE DIAM("):

PROBE LINE MATERIAL:

FILTER:

DUCT DIAM ("):

[illegible]

METHOD 4 Condense / NC RUN # 2

COMPANY: Destec "Double C"
UNIT: Lube Oil Vent TURBINEZ-
DATE: 2.11.93
REPORT: 027-341
TECH: DCJ / BDM
PUMP #: GAST
MEIEN BOX#: 1003
MEIEN Coeff: 1.028 (998951)
MOT TUBES:

PRE / POST TEST LEAK CHECK

LEAK RATE:	<.004	<.005	cfm
VACUUM:	5	5	"Hg

AMBIENT TEMP, °F: 60°
 P-bar:
 STATIC PRESSURE("H):
 ASSUMED MOISTURE, %:
 AVG. CALIB. NOZZLE DIAM("):
 PROBE LINER MATERIAL:
 FILTER #:
 DUCT DIAM ("):

[illegible]

METHOD 4 Condense/N RUN 13

COMPANY: Destec "Double C"

UNIT: Lube Oil Vent TURBINE Z

DATE: 2.11.93

NEPONT: 027-341

TECH: 27 / 13DM

PUMP #: CAST

MEIER BOX#: 1003

MEIEN coeff: 1.028 (.998951)

PIOR UBEN:

PRE / POST TEST LEAK CHECK

LEAK RATE: $<.003$ / $<.002$ c/m

"Hg	
VACUUM:	5

AMBIENT TEMP. °F: 60°

Phar:

STATIC PRESSURE ("Hg):

ASSUMED MOISTURE, %:

AVG. CALIB. NOZZLE DIAM("):

PROBE LINER MATERIAL:

FILTER:

DUCT DIAM ("):

$$F_T / m I \omega$$
[illegible]

COMPANY: Destec
 UNIT: WBE OILVENT GENERATOR 2
 DATE: 2-11-93
 REPORT: 087-341

ON-SITE DATA

		<u>RUN</u> TIME	#1	#2	#3
Vm	Dry sampled gas volume, dcf		13'45 23.99	14'33 24.00	15'27 24.00
Y	Meter calibration factor (met# _____)		998954	998954	998954
Pbar	Barometric Pressure, "Hg		29.22	29.22	29.22
Pstatic	Stack static pressure, "Hg		_____	_____	_____
ΔH	Differential meter pressure, "H2O		.60	.60	.60
Tm	Meter temperature, °F		67.25	71.63	74.69

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	645.0	585.2	59.8	664.1	617.0	47.1	655.1	606.7	48.4
H ₂ O	612.1	611.8	.3	587.7	587.3	.4	583.6	583.0	.6
KO	491.2	491.1	.1	476.2	476.0	.2	503.0	502.6	.4
Silicagel	803.0	799.1	3.9	801.8	797.4	4.4	807.3	803.0	4.3
line waste			<57.2>			<45.9>			<47.7>
Vlc	volume of H ₂ O, gms		6.9			6.2			6.0

		<u>RUN</u>	#1	#2	#3
CO ₂	% Dry Volume		_____	_____	_____
O ₂	% Dry Volume		_____	_____	_____
N ₂	% Dry Volume		_____	_____	_____
Cp	Pitot tube coefficient (Pit# _____)		_____	_____	_____
ΔP	Avg P "H ₂ O FT/MIN		351.25	323.13	332.50
Ts	Stack temperature, °F		78.25	71.63	76
As	Stack area, sq. ft.		_____	_____	_____
Ds	Stack diameter, inches		_____	_____	_____
Dn	Nozzle diameter, inches		_____	_____	_____
Dur	Sampling time, min		40	40	40
% Iso	Mini iso		_____	_____	_____

Filter # _____
 Filter tare weights, gms _____

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

METHOD 4 Condense / NC RUN # 3

COMPANY: Destec "Double C"

COMPANY: WESTEC COMPANY
UNIT: Lybe Oil Vent GEN 2

Umf: Lube O.1
DATE: 2.11.93

DATE: 2.11.93
REFNO: 027-341

TECH: DC7 / BDM
 PERONI: 027-341

TECH: DOW /
PUMP #: CAST

PUMP #: GAST
METER BOX#: 1003

MEIEN BOX#: 1003
MEIEN coeff: 1.028

MEIEN COEFF
PIOTUBE#:

PRE / POST TEST LEAK CHECK

LEAK DATE: <.001 / <.001

LEAK DATE:	<.001	<.001
VACUUM:	5	5

FT/miv

[illegible]

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbine #1
Lube Oil Vent GENERATOR 1

DATE TESTED: 2/11/93

ANALYST: DGS

SAMPLE # 1 aliquot - 232 ml

TIN # 8	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.59013</u>	final (g) <u>1.59012</u>	final (g)	<u>1.59013</u>
tare (g) <u>1.58613</u>	tare (g) _____	tare (g) _____	<u>1.58613</u>
NET (g)	NET (g)	NET (g)	<u>0.00400</u>

SAMPLE # 2 aliquot - 232 ml

TIN # 10	#5- 1.61134 ✓	#4- 1.61135 ✓	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.61227</u>	final (g) <u>1.61195</u>	final (g) <u>1.61182</u>	<u>1.61135</u>
tare (g) <u>1.57336</u>	tare (g) _____	tare (g) _____	<u>1.57336</u>
NET (g)	NET (g)	NET (g)	<u>0.03799</u>

SAMPLE # 3 aliquot - 248 ml

TIN # 9	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.58301 ✓</u>	final (g) <u>1.58309</u>	final (g) <u>1.58305 ✓</u>	<u>1.58303</u>
tare (g) <u>1.57673</u>	tare (g) _____	tare (g) _____	<u>1.57673</u>
NET (g)	NET (g)	NET (g)	<u>0.00630</u>

SAMPLE # _____ aliquot - _____

TIN #	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	_____
NET (g)	NET (g)	NET (g)	

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

PROJECT: 027-841

LOCATION/UNIT: Lube Oil Vent
Turbine 1

DATE TESTED: 2/24/93

ANALYST: DGS

SAMPLE # 1

ALIQOT - 234 ml

TIN # 7	#1	#2	#3	AVERAGE
FINAL (g)	1.43177	1.43177		1.43177
TARE (g)	1.40481			1.40481
NET (g)				0.02696

SAMPLE # 2

ALIQOT - 236 ml

TIN # 4	#1	#2	#3	AVERAGE
FINAL (g)	1.42365	1.42365		1.42365
TARE (g)	1.58189			1.58189
NET (g)				0.04176

SAMPLE # 3

ALIQOT - 232 ml

TIN # 8	#1	#2	#3	AVERAGE
FINAL (g)	1.62465	1.62463		1.62464
TARE (g)	1.59167			1.59157
NET (g)				0.03307

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbine #2
Lube Oil Vent Generator 2

DATE TESTED: 2/11/93

ANALYST: DGS

SAMPLE # 1 aliquot - 246 ml

TIN # 11			
# 1	# 2	# 3	AVERAGE
final (g) <u>1.61393</u>	final (g) <u>1.59456</u>	final (g) <u>1.59455</u>	<u>1.59456</u>
tare (g) <u>1.58459</u>	tare (g) _____	tare (g) _____	<u>1.58459</u>
NET (g)	NET (g)	NET (g)	<u>0.00997</u>

SAMPLE # 2 aliquot - 250 ml

TIN # 6			
# 1	# 2	# 3	AVERAGE
final (g) <u>1.62140</u>	final (g) <u>1.62137</u>	final (g) _____	<u>1.62139</u>
tare (g) <u>1.59795</u>	tare (g) _____	tare (g) _____	<u>1.59795</u>
NET (g)	NET (g)	NET (g)	<u>0.02344</u>

SAMPLE # 3 aliquot - 241 ml

TIN # 2			
# 1	# 2	# 3	AVERAGE
final (g) <u>1.58898</u>	final (g) <u>1.58900</u>	final (g) _____	<u>1.58899</u>
tare (g) <u>1.57855</u>	tare (g) _____	tare (g) _____	<u>1.57855</u>
NET (g)	NET (g)	NET (g)	<u>0.01044</u>

SAMPLE # _____ aliquot - _____

TIN #			
# 1	# 2	# 3	AVERAGE
final (g) _____	final (g) _____	final (g) _____	_____
tare (g) _____	tare (g) _____	tare (g) _____	_____
NET (g)	NET (g)	NET (g)	_____

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbine #2
Lube Oil Vent Turbine 2

DATE TESTED: 2/11/93

ANALYST: DGS

SAMPLE # 1

aliquot - 240 ml

TIN # 3			
# 1	# 2	# 3	AVERAGE
final (g) <u>1.43897</u>	final (g) <u>1.43893</u>	final (g)	<u>1.43895</u>
tare (g) <u>1.41552</u>	tare (g) _____	tare (g) _____	<u>1.41552</u>
NET (g)	NET (g)	NET (g)	<u>0.02343</u>

SAMPLE # 2

aliquot - 240 ml

TIN # 5			
# 1	# 2	# 3	AVERAGE
final (g) <u>1.61439</u>	final (g) <u>1.61435</u>	final (g)	<u>1.61437</u>
tare (g) <u>1.59303</u>	tare (g) _____	tare (g) _____	<u>1.59303</u>
NET (g)	NET (g)	NET (g)	<u>0.02134</u>

SAMPLE # 3

aliquot - 239 ml

TIN # 7			
# 1	# 2	# 3	AVERAGE
final (g) <u>1.64205</u>	final (g) <u>1.64204</u>	final (g)	<u>1.64205</u>
tare (g) <u>1.61679</u>	tare (g) _____	tare (g) _____	<u>1.61679</u>
NET (g)	NET (g)	NET (g)	<u>0.02526</u>

SAMPLE # _____

aliquot - _____

TIN #			
# 1	# 2	# 3	AVERAGE
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	_____
NET (g)	NET (g)	NET (g)	



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC OPERATING
DATE : 2-11-93
REPORT : 027-341

DATE RECEIVED : 2-12-93
DATE ANALYZED : 2-12-93
DATE REPORTED: 2-16-93


EPA METHOD 18
HYDROCARBON ANALYSIS REPORT

UNIT : TURBINE # 1

CONSTITUENT	RUN # 1 ppm(v/v)	RUN # 2 ppm(v/v)	RUN # 3 ppm(v/v)
METHANE	67.86	67.20	66.06
ETHANE	2.63	2.66	2.60
PROPANE	0.12	0.08	0.05
BUTANE	ND	ND	ND
PENTANE	ND	ND	ND
HEXANES+	0.09	0.09	0.10
TOTAL	70.70	70.03	68.82
NON-METHANE	2.84	2.83	2.76

UNIT : TURBINE # 2

CONSTITUENT	RUN # 1 ppm(v/v)	RUN # 2 ppm(v/v)	RUN # 3 ppm(v/v)
METHANE	79.47	80.15	76.22
ETHANE	3.22	3.11	3.06
PROPANE	0.15	0.16	0.15
BUTANE	ND	ND	ND
PENTANE	ND	ND	ND
HEXANES+	0.13	0.13	0.14
TOTAL	82.97	83.55	79.57
NON-METHANE	3.50	3.39	3.35



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC OPERATING
DATE : 2-11-93
REPORT : 027-341


DATE RECEIVED : 2-12-93
DATE ANALYZED : 2-12-93
DATE REPORTED: 2-16-93

**EPA METHOD 18
HYDROCARBON ANALYSIS REPORT**

UNIT : HYDROCARBON SAMPLE BLANK


CONSTITUENT	ppm(v/v)
METHANE	0.29
ETHANE	0.00
PROPANE	0.04
BUTANE	0.04
PENTANE	0.12
HEXANES+	0.94
TOTAL	1.43
NON-METHANE	1.14

DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 NORTH TURBINE # 1
 HC SAMPLE # 1



CHROMATOGRAM	10	MEMORIZED				
PKNO	TIME	AREA	NK	IDNO	CONC	NAME
1	2.656	984		6		C-6+
2	3.047	119831		1		C-1
3	3.595	3776		2		C-2
4	3.678	5418	V	2	9194	C-2
5	4.376	340		8		C-3
6	4.712	259		3	599	C-3
TOTAL		130608			0	


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 NORTH TURBINE # 1
 HC SAMPLE # 2



CHROMATOGRAM	11	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.675	972		6		C-6+
2	3.048	118671		1		C-1
3	3.595	3787		2		C-2
4	3.679	5483	V	2	> 9270	C-2
5	4.367	309		8		C-3
6	4.714	110		3	> 419	C-3
7	11.562	157		14		C-5
8	12.043	132		17		C-5
TOTAL		129619			0	


Baseline noise
 (True)

DESTEC, DOUBLE "C"
 2-11-93 REPORT # 027-341
 NORTH TURBINE # 1
 HC SAMPLE # 3




CHROMATOGRAM 13 MEMORIZED						
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.654	1119		6		C-6+
2	3.051	116661		1		C-1
3	3.598	3598		2		C-2
4	3.685	5491	V	2	> 9089	C-2
5	4.73	272		3		C-3
TOTAL		127141			0	

DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 TURBINE # 2
 HC SAMPLE # 1




CHROMATOGRAM 14 MEMORIZED						
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.663	1400		6		C-6+
2	3.047	140332		1		C-1
3	3.599	4265		2		C-2
4	3.685	6991	Y	2	11256	C-2
5	4.398	461		8		C-3
6	4.749	299		3	760	C-3
TOTAL		153748			0	

DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 TURBINE # 2
 HC SAMPLE # 2




CHROMATOGRAM 15		MEMORIZED		IDNO	CONC	NAME
PKNO	TIME	AREA	MK			
1	2.647	1416		6		C-6+
2	3.049	141540		1		C-1
3	3.592	4119		2		C-2
4	3.684	6726	V	2	> 10845	C-2
5	4.365	428		8		C-3
6	4.725	381		3	> 809	C-3
TOTAL		154610			0	

DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 TURBINE # 2
 HC SAMPLE # 3



CHROMATOGRAM 16		MEMORIZED		IDNO	CONC	NAME
PKNO	TIME	AREA	MK			
1	2.654	1511		6		C-6+
2	3.051	134599		1		C-1
3	3.667	10670		2		C-2
4	4.35	480		8		C-3
5	4.717	306		3		C-3
TOTAL		147566			0	


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT GENERATOR 1
 HC SAMPLE # 1



CHROMATOGRAM	10	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.038	476	V	1	2.6457	C-1
2	5.244	438				
TOTAL		913			2.6457	

GROUP(NAME)	CONC
C-1	2.6457
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0

DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT *GENERATOR 1*
 HC SAMPLE # 2




19:05:13

CHROMATOGRAM	11	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.947	115		1	0.6376	C-1
2	3.045	326	V	1	1.8132	C-1
TOTAL		441			2.4508	

GROUP(NAME)	CONC
C-1	2.4508
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT GENERATOR,
 HC SAMPLE # 3



CHROMATOGRAM	12	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.549	222				
2	3.046	508		1	2.8258	C-1
3	3.957	306		7	0.8506	C-2
TOTAL		1036			3.6764	

GROUP(NAME)	CONC
C-1	2.8258
C-2	0.8506
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-26-93 REPORT # 027-341
 LUBE OIL VENT TURBINE
 HC SAMPLE # 1



CHROMATOGRAM	10	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.605	467		6	0.444	C-6+
2	3.054	544		1	3.1271	C-1
TOTAL		1011			3.5711	

GROUP(NAME)	CONC
C-1	3.1271
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0.444


DESTEC DOUBLE "C"
 2-26-93 REPORT # 027-341
 LUBE OIL VENT *TURBINE 1*
 HC SAMPLE # 2



CHROMATOGRAM	11	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.062	994		1	5.7082	C-1
TOTAL		994			5.7082	

GROUP(NAME)	CONC
C-1	5.7082
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-26-93 REPORT # 027-341
 LUBE OIL VENT TURBINE 1
 HC SAMPLE # 3



CHROMATOGRAM	12	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.062	851		1	4.887	C-1
TOTAL		851			4.887	

GROUP(NAME)	CONC
C-1	4.887
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT GENERATOR 2
 HC SAMPLE # 1



CHROMATOGRAM	13	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.045	810		1	4.5039	C-1
2	7.607	64				
3	7.9	52				
4	8.355	81				
TOTAL		1006			4.5039	

GROUP(NAME)	CONC
C-1	4.5039
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT *GENERATOR 2*
 HC SAMPLE # 2



CHROMATOGRAM	14	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.044	1044		1	5.809	C-1
2	6.733	70		10	0.0992	C-4
3	7.125	63		4	0.0884	C-4
TOTAL		1177			5.9966	

GROUP(NAME)	CONC
C-1	5.809
C-2	0
C-3	0
C-4	0.1876
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT *GENERATOR 2*
 HC SAMPLE # 3



CHROMATOGRAM	15	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.048	812		1	4.5156	C-1
		-----			-----	
	TOTAL	812			4.5156	

GROUP(NAME)	CONC
C-1	4.5156
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT TURBINE 2
 HC SAMPLE # 1



CHROMATOGRAM	7	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.038	3933		1	21.8808	C-1
2	3.591	367		2	1.0196	C-2
3	3.863	125	V	7	0.3463	C-2
4	5.658	182		9	0.2576	C-4
5	6.608	232		10	0.3281	C-4
TOTAL		4840			23.8324	

GROUP(NAME)	CONC
C-1	21.8808
C-2	1.366
C-3	0
C-4	0.5857
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT *TURBINE 2*
 HC SAMPLE # 2



CHROMATOGRAM	8	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.039	2634		1	14.6535	C-1
2	3.417	70	V			
3	3.579	205		2	0.5704	C-2
TOTAL		2909			15.2239	

GROUP(NAME)	CONC
C-1	14.6535
C-2	0.5704
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT *TURBINE 2*
 HC SAMPLE # 3



CHROMATOGRAM	9	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.039	2041		1	11.3515	C-1
2	3.579	133		2	0.369	C-2
3	4.996	57				
4	5.299	80				
5	9.173	96				
6	9.582	105				
TOTAL		2511			11.7206	

GROUP(NAME)	CONC
C-1	11.3515
C-2	0.369
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 LUBE OIL VENT
 HC SAMPLE BLANK



CHROMATOGRAM	6	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	3.025	689		1	3.8316	C-1
2	9.833	70				
TOTAL		759			3.8316	

GROUP(NAME)	CONC
C-1	3.8316
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-26-93 REPORT # 027-341
 LUBE OIL VENT # 1 TURBINE
 HC SAMPLE BLANK




CHROMATOGRAM	9	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.533	139				
2	2.958	137		1	0.7898	C-1
3	3.062	330	V	1	1.897	C-1
TOTAL		607			2.6868	


GROUP(NAME)	CONC
C-1	2.6868
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0


DESTEC DOUBLE "C"
 2-11-93 REPORT # 027-341
 TURBINE #'s 1&2
 RC SAMPLE BLANK





CHROMATOGRAM	8	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.654	10368		6		C-6+
2	3.059	515		1		C-1
3	4.791	182		3		C-3
4	7.4	275		4		C-4
5	12.081	312		17		C-5
6	13.344	778		5		C-5 > 1090
TOTAL		12429			0	

















APPENDIX III LIABILITY ASSURANCE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
3207 Antonino Avenue, Bakersfield, CA 93308
(805) 631-9332 FAX (805) 327-0860

CHAIN OF CUSTODY RECORD

Submitted to: ZALCO LABORATORIES

ANALYSIS REQUEST

COMPANY <u>Destec Operating Co</u>		LOCATION/UNIT <u>Double "C" Limited</u>				LOW RANGE TOTAL SULFUR as H ₂ S				
REPORT # <u>027-341</u>		SAMPLER <u>JCH</u>								
METHOD		REPORT ATTN. <u>TERRY ROWLES</u>		PO# <u>49140</u>						
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas					
<u>BAG</u>	<u>FUEL GAS Turbine #1</u>	<u>2/12/93</u>			<u>X</u>	<u>X</u>				
<u>Bag</u>	<u>Fuel Gas Turbine #2</u>	<u>2/12/93</u>			<u>X</u>	<u>X</u>				

COMMENTS:			
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
<u>D. Smallwood</u>	<u>2/12/93</u>	<u>D. Smallwood</u>	<u>2-12-93</u>
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

All meth S condensables

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
3207 Antonino Avenue, Bakersfield, CA 93308
(805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to:

P.C.E.S LABS

ANALYSIS REQUEST

COMPANY <u>DESTEC</u>		LOCATION/UNIT <u>Double "C" TURBINES 1,2</u>				EPA meth S gran method				
REPORT # <u>027-341</u>		SAMPLER <u>John Hinkle / JAMES TAPLIN</u>								
METHOD <u>5</u>		REPORT ATTN. <u>TERRY ROWLES</u>		PO#						
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas					
22	P/N Run#1 TURBINE#1	2-9	X			X				
23	Imp Run#1 TURBINE#1	2-9	X			X				
24	" "	2-9	X			X				
25	" "	2-9	X			X				
26	P/N Run#2 TURBINE#1	2-10	X			X				
27	Imp Run#2 TURBINE#1	2-10	X			X				
28	" " "	2-10	X			X				
29	" " "	2-10	X			X				
30	P/N Run#1 TURBINE#2	2-11	X			X				
31	Imp Run#2 TURBINE#2	2-11	X			X				
32	" " "	2-11	X			X				

COMMENTS:

RELINQUISHED BY: <u>John Hinkle</u>	DATE <u>2-15-93</u>	RECEIVED BY: <u>D. Smallwood</u>	DATE <u>2/16/93</u>
RELINQUISHED BY: <u>/</u>	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

Meth S BLANKS AND FILTERS Fuel gases

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
3207 Antonino Avenue, Bakersfield, CA 93308
(805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: P.C.E.S. LABS

ANALYSIS REQUEST

COMPANY <u>DESTEC</u>		LOCATION/UNIT <u>DESTEC</u>				EPA/Meth S Gravimetric	Cr-Cat by TCD 100 Range 125 by FPD				
REPORT # <u>027-341</u>		SAMPLER <u>John Hinkle / James TAPLIN</u>									
METHOD <u>EPA 5</u>		REPORT ATTN. <u>FERRY LOWES</u>		PO#							
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas						
33	D/N pre-test BLNK	2-9	x			x					
34	Train #1 pre-test BLNK	2-9	x			x					
35	Train #2 pre-test BLNK	2-9	x			x					
36	D/N BLANK	2-11	x			x					
37	Train BLANK	2-11	x			x					
38	FILTER #1 TURBINE #1	2-9		x		x					
39	FILTER #2 TURBINE #1	2-9		x		x					
40	FILTER #1 TURBINE #2	2-9		x		x					
41	FILTER BLANK	2-9-12		x		x					
42	Bomb Turbine 2	2-12			x		x				
43	Bomb TURBINE 1	2-12			x		x				
44	BAG TURBINE 2	2-12			x		x				
45	BAG TURBINE 1	2-12			x		x				

COMMENTS:

RELINQUISHED BY: <u>John K Hinkle</u>	DATE <u>2-15-93</u>	RECEIVED BY: <u>D Smallwood</u>	DATE <u>2/16/93</u>
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

All water samples

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
3207 Antonino Avenue, Bakersfield, CA 93308
(805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: P.C.E.S. LABS

ANALYSIS REQUEST

COMPANY <u>Destec</u>		LOCATION/UNIT <u>TURBINES 1, & 2</u>			
REPORT # <u>027-341</u>		SAMPLER <u>John Hinkle, James TAPUN</u>			
METHOD		REPORT ATTN.		PO#	
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas
14	High pressure steam turbine 2	2-11	X		
15	High pressure feed turbine 2	2-11	X		
16	Low pressure steam turbine 2	2-11	X		
17	Low pressure blowdown turb. 2	2-11	X		
18	Low pressure steam turbine 1	2-11	X		
19	High pressure steam turbine 1	2-11	X		
20	Low pressure Blowdown turbine 1	2-11	X		
21	High pressure feed turbine 1	2-11	X		

COMMENTS: <u>HOLD for further instructions</u>			
RELINQUISHED BY: <u>John Hinkle</u>	DATE <u>2-15-93</u>	RECEIVED BY: <u>D. Smallwood</u>	DATE <u>2/16/93</u>
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

ALL Hydrocarbons

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
3207 Antonino Avenue, Bakersfield, CA 93308
(805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: P.C.E.S. LAOS

ANALYSIS REQUEST

COMPANY		LOCATION/UNIT									
Deater		TURB 1, TURB 2									
REPORT #		SAMPLER									
027-341		John Hinkle									
METHOD		REPORT ATTN.		PO#							
		TERRY ROWLES									
SAMPLE	SAMPLE DESCRIPTION			SAMPLE							
No/ID				DATE	Liq	Filter	Gas				
#1	LUBE OIL VENT #1 TURB 2 H/C 1,2,3			2-11-93			✓	X	X		
#2	LUBE OIL VENT #1 TURB 2 H/C 1,2,3			2-11-93			✓	+	X		
#3	TURBINE 1 & 2 H/C 1,2,3 PLUS BLANK RUN						✓			X	
#4	LUBE OIL VENT #3 TURB 2 H/C 1,2,3			2-11-93			✓	X	X		
5	LUBE OIL VENT #3 RUN 3			2-11	✓						X
6	LUBE OIL VENT #4 RUN 2			2-11	✓						✓
7	LUBE OIL VENT #4 RUN 3			2-11	✓						X
8	LUBE OIL VENT #3 RUN 2			2-11	✓						X
9	LUBE OIL VENT #1 RUN 2			2-11	✓						✓
10	LUBE OIL VENT #1 RUN 3			2-11	✓						X
11	LUBE OIL VENT #3 RUN 1			2-11	✓						X
12	LUBE OIL VENT #4 RUN 1			2-11	✓						X
13	LUBE OIL VENT #1 RUN 1			2-11	✓						X

EPA METH. 17

FID ANALYSIS

ORSAT ANALYSIS

EPA METHOD 3

O2 CO2

EPA Method Modified

CI-17 Low Range

CONDENSABLE HYDROCARBONS

EPA Method 4 with gravimetric detection using Method 14.2

COMMENTS: * 7 TOTAL SAMPLES
** 6 AG SAMPLES
*** Condensables

RELINQUISHED BY: <u>John Hinkle</u>	DATE: <u>2-15-93</u>	RECEIVED BY: <u>R. Smaller</u>	DATE: <u>2/16/93</u>
RELINQUISHED BY:	DATE:	RECEIVED BY:	DATE:
RELINQUISHED BY:	DATE:	RECEIVED BY:	DATE:

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
3207 Antonino Avenue, Bakersfield, CA 93308
(805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: P. C. E. S.

ANALYSIS REQUEST

COMPANY DESTEC		LOCATION/UNIT TURBINE #2					EPA METH 5 CON.				
REPORT # 027-341		SAMPLER RJK									
METHOD		REPORT ATTN.			PO#						
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas						
46	P/N RUN #2 TURBINE #2	2-12				X					
47	IMP. " "	2-12				X					
48	FILTER " "	2-12				X					
49	PROBE BLANK POST	2-12				X					
50	IMP. BLANK POST	2-12				X					

COMMENTS: **PLEASE ADD A FILTER BLANK AS WE DONT HAVE ANY MORE.**

RELINQUISHED BY: RJK	DATE 2-12-93	RECEIVED BY: D Smallwood	DATE 2/15/93
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
DRY GAS METER CALIBRATION

DATE:	1-27-93	AMBIENT TEMP °F:	62
TECH:	BDM	BAROMETRIC Pbar:	29.54
METER I.D.#	1002	TEST METER ID#:	SSM104564
		TEST METER Mct:	1.023

APPROXIMATE CFM			0.75	0.50	0.30
STD TEST METER VOLUME CF	INITIAL		0.00	0.00	0.00
	FINAL		7.41	10.01	10.05
	TOTAL		7.41	10.01	10.05
FIELD GAS METER VOLUME CF	INITIAL		109.20	119.00	130.10
	FINAL		116.69	129.56	140.89
	TOTAL		7.49	10.56	10.79
STD TEST METER TEMP (°F)			62.5	60.0	60.0
FIELD GAS METER TEMP (°F)	IN		69.0	71.0	69.5
	OUT		54.0	60.0	63.0
	AVERAGE		61.5	65.5	66.3
STD TEST METER PRESSURE ("H₂O)			-0.60	-0.30	-0.15
FIELD GAS METER PRESSURE ("H₂O)					
			1.40	0.60	0.21
FIELD GAS METER, Mct			1.006629	0.978514	0.963789

FIELD AVERAGE Mct:	0.982977
---------------------------	-----------------

H@:	1.4324
------------	---------------

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
DRY GAS METER CALIBRATION

DATE:	1-28-93	AMBIENT TEMP °F:	61
TECH:	BDM	BAROMETRIC Pbar:	30.22
METER I.D.#	1003	TEST METER ID#:	S5M104564
		TEST METER Mcf	1.023

APPROXIMATE CFM			.75	0.50	0.30
STD TEST METER VOLUME CF	INITIAL		0.00	0.00	0.00
	FINAL		7.59	10.04	10.01
	TOTAL		7.59	10.04	10.01
FIELD GAS METER VOLUME CF	INITIAL		807.30	815.30	826.50
	FINAL		814.90	825.75	837.19
	TOTAL		7.60	10.45	10.69
STD TEST METER TEMP (°F)			57.0	60.5	61.0
FIELD GAS METER TEMP (°F)	IN		59.0	65.5	66.5
	OUT		60.0	75.0	72.5
	AVERAGE		59.5	70.3	69.0
STD TEST METER PRESSURE ("H2O)			-0.60	-0.30	-0.15
FIELD GAS METER PRESSURE ("H2O)			0.90	0.40	0.18
FIELD GAS METER, Mcf			1.024351	1.000301	0.972209

FIELD AVERAGE Mcf:	0.998954	H@:	0.8432
---------------------------	-----------------	------------	---------------

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
DRY GAS METER CALIBRATION

DATE:	2-25-93	AMBIENT TEMP °F:	62
TECH:	BDM	BAROMETRIC Pbar:	29.54
METER I.D.#	1003	TEST METER ID#:	S5M104564
		TEST METER Mcf	1.023

APPROXIMATE CFM		0.75	0.50	0.30
STD TEST METER VOLUME CF	INITIAL	0.00	0.00	0.00
	FINAL	7.44	10.10	10.01
	TOTAL	7.44	10.10	10.01
FIELD GAS METER VOLUME CF	INITIAL			
	FINAL	29.20	38.40	49.60
	TOTAL	36.73	48.99	60.34
		7.53	10.59	10.74
STD TEST METER TEMP (°F)		61.0	61.5	62.0
FIELD GAS METER TEMP (°F)	IN			
	OUT	68.0	69.0	70.0
	AVERAGE	77.0	76.5	76.0
		72.5	72.8	73.0
STD TEST METER PRESSURE ("H₂O)		-0.60	-0.30	-0.15
FIELD GAS METER PRESSURE ("H₂O)		0.89	0.40	0.18
FIELD GAS METER, Mcf		1.030800	0.995722	0.973123

FIELD AVERAGE Mcf:	0.999882	H@:	0.8795
---------------------------	-----------------	------------	---------------

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
PITOT TUBE CALIBRATION

PITOT TUBE ID. # **P12Q-10**
DATE: **2-4-93**
CALIBRATED BY: **RJK**

"A" SIDE CALIBRATION				
RUN #	Δ Pstd cm H2O (in.H2O)	Δ P(s) cm H2O (in. H2O)	Cp(s)	DEVIATION Cp(s) - Cp(A)
1	0.260	0.415	0.784	-0.007
2	0.265	0.410	0.796	0.005
3	0.270	0.420	0.794	0.003
			Cp (SIDE A)	0.791

"B" SIDE CALIBRATION				
RUN #	Δ Pstd cm H2O (in.H2O)	Δ P(s) cm H2O (in. H2O)	Cp(s)	DEVIATION Cp(s) - Cp(B)
1	0.265	0.415	0.791	0.000
2	0.260	0.410	0.788	-0.003
3	0.270	0.420	0.794	0.003
			Cp (SIDE B)	0.791

Cp (SIDE A) - Cp (SIDE B) =	0.000	0.791
------------------------------------	--------------	--------------

$$Cp = .99 * \Delta P_{std} / \Delta P(s)$$



AIRCO

518655

Airco Electronic Gases
 Union Landing & River Roads
 P.O. Drawer No. 272
 Riverton
 New Jersey 08077
 Telephones: Marketing: 609-829-7878
 Prod. & Admin.: 609-829-7917
 International: 609-829-7917

CERTIFICATE OF ANALYSIS - EPA PROTOCOL GAS MIX

CUSTOMER: Bakersfield Welding SupplyCYLINDER #: CC-17885CYLINDER PRESSURE: 1650 psigLABORATORY: Riverton NJCERTIFICATION DATE: 11/2/92EXPIRATION DATE: 5/2/93REFERENCE #: 24275

MIXTURE COMPONENTS	ACTUAL MIXTURE CONCENTRATION	AIRCO INTERMEDIATE STANDARD CYLINDER #	CONC.	NIST SRM#
Nitric Oxide	40.0 ppm	CC-14977	49.8 ppm	1683B
Carbon Monoxide	39.9 ppm	CC-43310	49.8 ppm	1678C

BALANCE GAS: Nitrogen

COMPONENT 1 GAS ANALYSIS PROCEDURE

MAKE/MODEL/SER#:

LAST MULTIPOINT CALIBRATION DATE:

ChemiluminescenceBeckman, 952, 01002048/3/92

COMPONENT 2 GAS ANALYSIS PROCEDURE

MAKE/MODEL/SER#:

LAST MULTIPOINT CALIBRATION DATE:

Non-Dispersive InfraredHoriba, CO/Analyzer, 562556018/3/92

R=REFERENCE STANDARD

Z=ZERO GAS

S=SAMPLE GAS

1ST COMPONENT Nitric Oxide

1ST ANALYSIS: DATE

10/26/92

ANALYST

A. Lattanze1) Z 0000

R

4550

S

3635

CONC (1)

39.8 ppm2) R 4540

Z

0000

S

3640

CONC (2)

39.9 ppm3) R 4540

S

3630

Z

0000

CONC (3)

39.8 ppm

AVE CONC

39.8 ppm

2ND ANALYSIS: DATE

11/2/92

ANALYST

A. Lattanze1) Z 0000

R

4385

S

3540

CONC (1)

40.2 ppm2) R 4400

Z

0000

S

3535

CONC (2)

40.0 ppm3) R 4410

S

3540

Z

0000

CONC (3)

40.0 ppm

AVE CONC

40.1 ppm2ND COMPONENT Carbon Monoxide

1ST ANALYSIS: DATE

10/26/92

ANALYST

A. Lattanze1) Z 000

R

491

S

393

CONC (1)

39.9 ppm2) R 491

Z

000

S

393

CONC (2)

39.9 ppm3) R 491

S

393

Z

000

CONC (3)

39.9 ppm

AVE CONC

39.9 ppm

2ND ANALYSIS: DATE

11/2/92

ANALYST

A. Lattanze1) Z 000

R

493

S

395

CONC (1)

39.9 ppm2) R 493

Z

000

S

395

CONC (2)

39.9 ppm3) R 493

S

395

Z

000

CONC (3)

39.9 ppm

AVE CONC

39.9 ppm

THIS CALIBRATION STANDARD HAS BEEN CERTIFIED VERSUS EPA TRACEABILITY
 PROTOCOL NO. 1, PROCEDURE G1, AND ANALYSES PERFORMED PER SECTION 3.0.4.
 CERTIFIED CONCENTRATION: Nitric Oxide = 40.0 ppm; Carbon Monoxide = 39.9 pp

APPROVED BY

Nitrogen = Balance

A member of The JOCE LABORATORY MANAGER



512041

Airco Electronic Gases
Union Landing & River Roads
P.O. Drawer No. 272
Riverton
New Jersey 08077
Telephones: Marketing; 609-829-7878
Prod. & Admin.; 609-829-7914
International; 609-829-7917

CERTIFICATE OF ANALYSIS - EPA PROTOCOL GAS MIX

CUSTOMER: Bakersfield Welding (Saugas, CA)
CYLINDER #: CC-77462 CERTIFICATION DATE: 10/12/92
CYLINDER PRESSURE: 1650 psig EXPIRATION DATE: 4/12/93
LABORATORY: Riverton, NJ REFERENCE #: 23698

MIXTURE COMPONENTS	ACTUAL MIXTURE CONCENTRATION	AIRCO INTERMEDIATE STANDARD CYLINDER #	CONC.	NIST SRM#
Nitric Oxide	78.2 ppm	CC-69954	100 ppm	1684B
Carbon Monoxide	81.4 ppm	CC-3138	112 ppm	1679C

BALANCE GAS: Nitrogen

COMPONENT 1 GAS ANALYSIS PROCEDURE Chemiluminescence
MAKE/MODEL/SER#: Beckman, 952, 0100204
LAST MULTIPOINT CALIBRATION DATE: 8/3/92

COMPONENT 2 GAS ANALYSIS PROCEDURE Non-Dispersive Infrared
MAKE/MODEL/SER#: Beckman; 866; 1000049
LAST MULTIPOINT CALIBRATION DATE: 8/3/92
R=REFERENCE STANDARD Z=ZERO GAS S=SAMPLE GAS

1ST COMPONENT Nitric Oxide
1ST ANALYSIS: DATE 10/5/92 ANALYST A. Lattanze
1) Z 0000 R 3690 S 2880 CONC (1) 78.0 ppm
2) R 3690 Z 0000 S 2880 CONC (2) 78.0 ppm
3) R 3690 S 2880 Z 0000 CONC (3) 78.0 ppm
AVE CONC 78.0 ppm
2ND ANALYSIS: DATE 10/12/92 ANALYST A. Lattanze
1) Z 0000 R 3700 S 2900 CONC (1) 78.4 ppm
2) R 3700 Z 0000 S 2900 CONC (2) 78.4 ppm
3) R 3700 S 2900 Z 0000 CONC (3) 78.4 ppm
AVE CONC 78.4 ppm

2ND COMPONENT Carbon Monoxide
1ST ANALYSIS: DATE 10/5/92 ANALYST A. Lattanze
1) Z 000 R 222 S 163 CONC (1) 82.2 ppm
2) R 222 Z 000 S 161 CONC (2) 81.2 ppm
3) R 222 S 163 Z 000 CONC (3) 82.2 ppm
AVE CONC 81.9 ppm
2ND ANALYSIS: DATE 10/12/92 ANALYST A. Lattanze
1) Z 000 R 221 S 160 CONC (1) 81.1 ppm
2) R 222 Z 000 S 160 CONC (2) 80.7 ppm
3) R 222 S 160 Z 000 CONC (3) 80.7 ppm
AVE CONC 80.8 ppm

THIS CALIBRATION STANDARD HAS BEEN CERTIFIED VERSUS EPA TRACEABILITY
PROTOCOL NO. 1, PROCEDURE G1, AND ANALYSES PERFORMED PER SECTION 3.0.4.
CERTIFIED CONCENTRATION: Nitric Oxide = 78.2 ppm; Carbon Monoxide = 81.4 ppm;
Nitrogen = Balance

APPROVED BY J. L. Lattanze
A member of The BOC LABORATORY MANAGER



PETRO CHEM ENVIRONMENTAL SERVICES, INC.

CALIBRATION GAS CERTIFICATE

DATE: 12-2-91
ANALYST: TIM BRENNAN

TANK #: LK-273312
CONTENTS: Oxygen in Nitrogen

	SET #1	SET #2	SET #3
RUN #1	15.0	15.1	15.0
RUN #2	15.0	15.1	15.0
RUN #3	15.1	15.0	15.1
AVERAGE	15.0	15.1	15.0

TOTAL AVERAGE CONCENTRATION 15.0 %O2

Expires: 6-2-93

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbine #1

DATE TESTED: 2/9/93

ANALYST: DGS

RUN # PreTest Blank 2

PROBE/NOZZLE/FILTER TOP

VOL-

DISH # #1	#2	#3	AVERAGE
FINAL (g)			
TARE (g) _____	_____	_____	_____
NET (g)			

FILTER # _____

#1	#2	#3	AVERAGE
FINAL (g)			
TARE (g) _____	_____	_____	_____
NET (g)			

Train 2

CONDENSABLE (aliquot 100 ml / 166 ml)

DISH # <u>43</u> #1	#2	#3	AVERAGE
FINAL (g) <u>78.2228</u>	<u>78.2224</u>		<u>78.2227</u>
TARE (g) <u>78.2225</u>	_____	_____	<u>78.2225</u>
NET (g)			<u>0.0002</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbines #1 & #2

DATE TESTED: 2/11/93

ANALYST: DGS

RUN # Mid-Test Blanks

PROBE/NOZZLE/FILTER TOP

VOL- 185 ml

DISH # <u>16</u> #1	#2	#3	AVERAGE
FINAL (g) <u>76.9192</u>	<u>76.9183</u>	<u>76.9190</u>	<u>76.9191</u>
TARE (g) <u>76.9189</u>	_____	_____	<u>76.9189</u>
NET (g)			<u>0.0002</u>

FILTER # 504

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6207</u>	<u>0.6207</u>		<u>0.6207</u>
TARE (g) <u>0.6208</u>	_____	_____	<u>0.6208</u>
NET (g)			<u>0</u>

CONDENSABLE (aliquot 100 ml / 214 ml)

DISH # <u>50</u> #1	#2	#3	AVERAGE
FINAL (g) <u>77.4978</u>	<u>77.4971</u>	<u>77.4976</u>	<u>77.4977</u>
TARE (g) <u>77.4976</u>	_____	_____	<u>77.4976</u>
NET (g)			<u>0.0001</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbine #2

DATE TESTED: 2/12/93

ANALYST: DGS

RUN # End-Test Blanks

PROBE/NOZZLE/FILTER TOP

VOL- 150 ml

DISH # 40 #1	#2	#3	AVERAGE
FINAL (g) 71.8500	71.8492	71.8498	71.8497
TARE (g) 71.8497	_____	_____	71.8497
NET (g)			0.0002

FILTER # 505

#1	#2	#3	AVERAGE
FINAL (g) 0.6187	0.6187		0.6187
TARE (g) 0.6186	_____	_____	0.6186
NET (g)			0.0001

CONDENSABLE (aliquot 100ml / 209ml)

DISH # 18 #1	#2	#3	AVERAGE
FINAL (g) 65.8824	65.8817	65.8822	65.8823
TARE (g) 65.8830	_____	_____	65.8830
NET (g)			0

PETRO CHEM ENVIRONMENTAL SERVICES LABORATORY

QUALITY CONTROL - METHOD 5

Q A BATCH #: 5-93-0011

DI H₂O FROM ANTONINO AVE

VOLUME (ml): 250 ml

DISH #: <u>27</u>	#3- <u>81.1228</u>	AVERAGE
FINAL WT. (g): <u>81.1213</u>	FINAL WT. (g): <u>81.1228</u>	FINAL WT. (g): <u>81.1228</u>
TARE WT. (g): <u>81.1217</u>	TARE WT. (g): _____	TARE WT. (g): <u>81.1217</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0.0011</u>

DI H₂O FROM DANIELS LN.

VOLUME (ml): 250 ml

DISH #: <u>24</u>	#3- <u>74.5886</u>	AVERAGE
FINAL WT. (g): <u>74.5875</u>	FINAL WT. (g): <u>74.5886</u>	FINAL WT. (g): <u>74.5886</u>
TARE WT. (g): <u>74.5875</u>	TARE WT. (g): _____	TARE WT. (g): <u>74.5875</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0.0011</u>

EMPTY DISH

DISH #: <u>7</u>	#3- <u>65.0509</u>	AVERAGE
FINAL WT. (g): <u>65.0502</u>	FINAL WT. (g): <u>65.0511</u>	FINAL WT. (g): <u>65.0510</u>
TARE WT. (g): <u>65.0504</u>	TARE WT. (g): _____	TARE WT. (g): <u>65.0504</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0.0006</u>

FILTER BLANK

FILTER #: <u>510</u>		AVERAGE
FINAL WT. (g): <u>0.6136</u>	FINAL WT. (g): <u>0.6135</u>	FINAL WT. (g): <u>0.6136</u>
TARE WT. (g): <u>0.6137</u>	TARE WT. (g): _____	TARE WT. (g): <u>0.6137</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0</u>

RECOVERY SAMPLE

VOLUME (ml): 100 ml

DISH #: <u>20</u>	#3- <u>72.3965</u>	AVERAGE
FINAL WT. (g): <u>72.3969</u>	FINAL WT. (g): <u>72.3991</u>	FINAL WT. (g): <u>72.3967</u>
TARE WT. (g): <u>72.3955</u>	TARE WT. (g): _____	TARE WT. (g): <u>72.3955</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0.0012</u>
CONC (g/l): <u>0.01435 g/l</u> Na ₂ SO ₄ WT (g): <u>0.001435 g</u>		% RECOVERY: <u>83.69</u> <u>(0.0012 / 0.001435) 100</u>

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbines 1 & 2

DATE TESTED: 2/11/93

ANALYST: DGS

SAMPLE # MeCl₂ Lab Reagent Blank aliquot - 100 ml

TIN # 4			
# 1	# 2	# 3	AVERAGE
final (g) <u>1.59694</u>	final (g) <u>1.59699</u>	final (g)	<u>1.59698</u>
tare (g) <u>1.59684</u>	tare (g) _____	tare (g) _____	<u>1.59684</u>
NET (g)	NET (g)	NET (g)	<u>0.00014</u>

SAMPLE # Empty aliquot - 0 ml

TIN # /			
# 1	# 2	# 3	AVERAGE
final (g) <u>1.59450</u>	final (g) <u>1.59454</u>	final (g)	<u>1.59452</u>
tare (g) <u>1.59440</u>	tare (g) _____	tare (g) _____	<u>1.59440</u>
NET (g)	NET (g)	NET (g)	<u>0.00012</u>

SAMPLE # _____ aliquot - _____

TIN #			
# 1	# 2	# 3	AVERAGE
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	_____
NET (g)	NET (g)	NET (g)	

SAMPLE # _____ aliquot - _____

TIN #			
# 1	# 2	# 3	AVERAGE
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	_____
NET (g)	NET (g)	NET (g)	

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Turbine #1

DATE TESTED: 2/9/93

ANALYST: DGS

RUN # Pretest Blanks 1

PROBE/NOZZLE/FILTER TOP

VOL- 150 ml

DISH # 47 #1	#2	#3	AVERAGE
FINAL (g) <u>77.2103</u>	<u>77.2096</u>	<u>77.2102</u>	<u>77.2103</u>
TARE (g) <u>77.2096</u>	_____	_____	<u>77.2096</u>
NET (g)			<u>0.0007</u>

FILTER # _____

#1	#2	#3	AVERAGE
FINAL (g)			
TARE (g) _____	_____	_____	_____
NET (g)			

Train 1

CONDENSABLE (aliquot 100ml / 194ml)

DISH # 52 #1	#2	#3	AVERAGE
FINAL (g) <u>77.1684</u>	<u>77.1675</u>	<u>77.1681</u>	<u>77.1683</u>
TARE (g) <u>77.1681</u>	_____	_____	<u>77.1681</u>
NET (g)			<u>0.0002</u>

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Blanks

DATE TESTED: 2/26/93

ANALYST: DHS

SAMPLE # Lab Reagent Blank - Meclz

ALIQOT - 100 ml

TIN # <u>2</u>			
#1	#2	#3	AVERAGE
FINAL (g) <u>1.59123</u>	<u>1.59123</u>		<u>1.59123</u>
TARE (g) <u>1.59120</u>			<u>1.59120</u>
NET (g)			<u>0.00003</u>

SAMPLE # Empty

ALIQOT - 0 ml

TIN # <u>1</u>			
#1	#2	#3	AVERAGE
FINAL (g) <u>1.58967</u>	<u>1.58970</u>		<u>1.58969</u>
TARE (g) <u>1.58972</u>			<u>1.58972</u>
NET (g)			<u>0</u>

SAMPLE # _____

ALIQOT - _____

TIN # _____			
#1	#2	#3	AVERAGE
FINAL (g) _____			
TARE (g) _____			
NET (g) _____			

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

REPORT: 027-341

LOCATION/UNIT: Blanks
LOV TURBINE1

DATE TESTED: 2/24/93

ANALYST: DGS

SAMPLE # Train Blank

ALIQOUT - 200 ml

TIN # <u>6</u>	#1	#2	#3	AVERAGE
FINAL (g)	1.59004	1.59004		1.59004
TARE (g)	<u>1.58974</u>	<u> </u>	<u> </u>	<u>1.58974</u>
NET (g)				<u>0.00030</u>

SAMPLE # H₂O Blanks


ALIQOUT - 200ml

TIN # <u>5</u>	#1	#2	#3	AVERAGE
FINAL (g)	1.60073	1.60077		1.60075
TARE (g)	<u>1.60063</u>	<u> </u>	<u> </u>	<u>1.60063</u>
NET (g)				<u>0.00012</u>

SAMPLE # Field Blank-MeCl₂

ALIQOUT - 180 ml

TIN # <u>3</u>	#1	#2	#3	AVERAGE
FINAL (g)	1.57397	1.57399		1.57398
TARE (g)	<u>1.57340</u>	<u> </u>	<u> </u>	<u>1.57340</u>
NET (g)				<u>0.00058</u>



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC OPERATING
DATE : 2-11-93
REPORT : 027-341

DATE RECEIVED : 2-12-93
DATE ANALYZED : 2-12-93
DATE REPORTED: 2-16-93

EPA METHOD 18
LOW RANGE HYDROCARBON ANALYSIS
CALIBRATION DATA AND STATISTICS

METHANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.413	742	5.57E-04
0.825	1453	5.68E-04
4.125	7236	5.70E-04
8.25	14456	5.71E-04
AVERAGE RF		5.66E-04
STD. DEVIATION		5.70E-06
RSD%		1.01%

ETHANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.413	1415	2.92E-04
0.825	2838	2.91E-04
4.125	14705	2.81E-04
8.25	29176	2.83E-04
AVERAGE RF		2.86E-04
STD. DEVIATION		4.90E-06
RSD%		1.71%



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY: DESTEC OPERATING
DATE : 2-11-93
REPORT : 027-341

DATE RECEIVED : 2-12-93
DATE ANALYZED : 2-12-93
DATE REPORTED: 2-16-93

EPA METHOD 18
LOW RANGE HYDROCARBON ANALYSIS
CALIBRATION DATA AND STATISTICS

PROPANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.413	2077	1.99E-04
0.825	4179	1.97E-04
4.125	21763	1.90E-04
8.25	43211	1.91E-04
AVERAGE RF		1.94E-04
STD. DEVIATION		4.01E-06
RSD%		2.07%

BUTANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.413	2826	1.46E-04
0.825	5652	1.46E-04
4.125	28794	1.43E-04
8.25	57028	1.45E-04
AVERAGE RF		1.45E-04
STD. DEVIATION		1.16E-06
RSD%		0.80%



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY: DESTEC OPERATING
DATE : 2-11-93
REPORT : 027-341

DATE RECEIVED : 2-12-93
DATE ANALYZED : 2-12-93
DATE REPORTED: 2-16-93

EPA METHOD 18
LOW RANGE HYDROCARBON ANALYSIS
CALIBRATION DATA AND STATISTICS

PENTANE







CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.37	3203	1.16E-04
0.74	6628	1.12E-04
3.7	35175	1.05E-04
7.4	69074	1.07E-04
AVERAGE RF		1.10E-04
STD. DEVIATION		4.01E-06
RSD%		3.65%

HEXANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.38	4200	9.05E-05
0.76	8451	8.99E-05
3.8	41640	9.13E-05
7.6	82003	9.27E-05
AVERAGE RF		9.11E-05
STD. DEVIATION		1.03E-06
RSD%		1.14%

COMPANY : DESTEC OPERATING
 UNIT : DOUBLE "C" TURBINES 1 & 2
 DATE : 2-11-93
 REPORT : 027-341

HYDROCARBON CALIBRATION LINEARITY GRAPHS
 ANALYSIS PERFORMED ON 2-12-93





**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY: DESTEC OPERATING
DATE : 2-11-93
REPORT : 027-341

DATE RECEIVED : 2-12-93
DATE ANALYZED : 2-12-93
DATE REPORTED: 2-16-93

**EPA METHOD 18
CALIBRATION DRIFT ANALYSIS**


POST ANALYSIS CALIBRATION CHECK (0.4ppm STD.)

CONSTITUENT	INITIAL RF	POST RF	%DIFF.
METHANE	5.57E-04	5.73E-04	-2.91%
ETHANE	2.92E-04	2.97E-04	-1.87%
PROPANE	1.99E-04	2.08E-04	-4.48%
BUTANE	1.46E-04	1.53E-04	-4.36%
PENTANE	1.16E-04	1.18E-04	-1.94%
HEXANES+	9.05E-05	8.70E-05	3.89%

POST ANALYSIS CALIBRATION CHECK (0.8ppm STD.)


CONSTITUENT	INITIAL RF	POST RF	%DIFF.
METHANE	5.68E-04	5.67E-04	0.14%
ETHANE	2.91E-04	2.88E-04	0.94%
PROPANE	1.97E-04	1.96E-04	0.76%
BUTANE	1.46E-04	1.49E-04	-1.95%
PENTANE	1.12E-04	1.06E-04	5.22%
HEXANES+	8.99E-05	8.86E-05	1.43%

SYSTEM BLANK
UHP NITROGEN




CHROMATOGRAM 2 MEMORIZED
WARNING NO PEAK

0.4PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL. 1:40




PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.658	4200		6		C-6+
2	3.056	742		1		C-1
3	3.606	1415		2		C-2
4	4.741	2077		3		C-3
5	7.409	2826		4		C-4
6	13.345	3203		5		C-5
7	14.181	180				
TOTAL		14643			0	

0.8PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL. 1:20




CHROMATOGRAM 4 MEMORIZED						
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.667	8451		6		C-6+
2	3.05	1453		1		C-1
3	3.605	2838		2		C-2
4	4.747	4179		3		C-3
5	7.408	5652		4		C-4
6	13.341	6628		5		C-5
TOTAL		29200			0	

4PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL 1:4




CHROMATOGRAM	5	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.663	41640		6		C-6+
2	3.058	7236		1		C-1
3	3.606	14705		2		C-2
4	4.746	21763		3		C-3
5	7.412	28794		4		C-4
6	13.353	35175		5		C-5
TOTAL		149312			0	

8PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL. 1:2




CHROMATOGRAM	6	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.675	82003		6		C-6+
2	3.059	14456		1		C-1
3	3.606	29176		2		C-2
4	4.746	43211		3		C-3
5	7.41	57028		4		C-4
6	13.339	69074		5		C-5
TOTAL		294947			0	

POST ANALYSIS' CLLIBRATION CHECK
 0.4PPM HYDROCARBON STANDARD
 SCOTTY CAN MIX 1 DIL. 1:40



CHROMATOGRAM	17	MEMORIZED				
P<NO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.666	4370		6		C-6+
2	3.055	721		1		C-1
3	3.598	1389		2		C-2
4	4.736	1988		3		C-3
5	7.396	2708		4		C-4
6	13.3	3142		5		C-5
7	15.65	288		15		C-5
TOTAL		14606			0	

POST ANALYSIS CALIBRATION CHECK
0.8PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL. 1:20









CHROMATOGRAM 18 MEMORIZED


PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.677	8574		6		C-6+
2	3.053	1455		1		C-1
3	3.598	2865		2		C-2
4	4.736	4211		3		C-3
5	7.396	5544		4		C-4
6	8.77	232		16		C-5
7	11.735	310		17		C-5
8	13.313	6993		5		C-5
TOTAL		30185			0	

COMPANY : DESTEC DOUBLE "C"
 UNIT : LUBE OIL VENTS
 DATE : 2-11-93
 REPORT : 027-341

HYDROCARBON CALIBRATION LINEARITY GRAPHS
 ANALYSIS PERFORMED ON 2-12-93



15PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1



15:24:07

CHROMATOGRAM	2	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.664	16693		6		C-6+
2	3.035	2947	V	1		C-1
3	3.578	5775		2		C-2
4	4.71	8596		3		C-3
5	7.357	11369		4		C-4
6	13.24	13965		5		C-5


TOTAL		59346				

IDENTIFICATION FILE 0
MODE\$ 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.02	0.00559961	16.5
2	C-2	3.57	0.00285702	16.5
3	C-3	4.7	0.00191947	16.5
4	C-4	7.34	0.00145126	16.5
5	C-5	13.23	0.00105976	14.8
6	C-6+	2.66	0.000910568	15.2
7	C-2	3.85	0.00285702	16.5
8	C-3	4.3	0.00191947	16.5
9	C-4	5.7	0.00145126	16.5
10	C-4	6.65	0.00145126	16.5
11	C-5	10.24	0.00105976	14.8
12	C-5	10.59	0.00105976	14.8
13	C-5	12.73	0.00105976	14.8
14	C-5	11.3	0.00105976	14.8
15	C-5	15.43	0.00105976	14.8
16	C-5	8.79	0.00105976	14.8
17	C-5	11.82	0.00105976	14.8

100PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 220




CHROMATOGRAM	3	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.672	106664		6		C-6+
2	3.038	18155	V	1		C-1
3	3.582	36346		2		C-2
4	4.715	53925		3		C-3
5	7.365	71542		4		C-4
6	13.261	86396		5		C-5
TOTAL		373029				

IDENTIFICATION FILE 1
MODE\$ 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.03	0.00556311	101
2	C-2	3.57	0.00277887	101
3	C-3	4.7	0.00185442	100
4	C-4	7.35	0.00141176	101
5	C-5	13.24	0.00114704	99.1
6	C-6+	2.66	0.000937519	100
7	C-2	3.9	0.00277887	101
8	C-3	4.35	0.00185442	100
9	C-4	5.75	0.00141176	101
10	C-4	6.7	0.00141176	101
11	C-5	10.21	0.00114704	101
12	C-5	10.59	0.00114704	99.1
13	C-5	12.71	0.00114704	99.1
14	C-5	11.3	0.00114704	99.1
15	C-5	15.27	0.00114704	99.1
16	C-5	12.19	0.00114704	99.1
17	C-5	11.6	0.00114704	99.1

1000PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 224




CHROMATOGRAM	4	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.665	1092464		6		C-6+
2	3.04	185090	V	1		C-1
3	3.584	369110		2		C-2
4	4.717	548920		3		C-3
5	6.697	810		10		C-4
6	7.365	729210		4		C-4
7	12.027	703				
8	13.255	899180	S	5		C-5
9	14.63	2218	T			
TOTAL		3827705				

IDENTIFICATION FILE 2
MODE\$ 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.03	0.00540277	1000
2	C-2	3.57	0.0027905	1030
3	C-3	4.7	0.00182176	1000
4	C-4	7.35	0.00138506	1010
5	C-5	13.23	0.00113437	1020
6	C-6+	2.66	0.000919938	1005
7	C-2	3.9	0.0027905	1030
8	C-3	4.52	0.00182176	1000
9	C-4	5.94	0.00138506	1010
10	C-4	6.68	0.00138506	1010
11	C-5	10.21	0.00113437	1020
12	C-5	10.59	0.00113437	1020
13	C-5	12.73	0.00113437	1020
14	C-5	12.53	0.00113437	1020
15	C-5	15.21	0.00113437	1020


SYSTEM BLANK
UHP NITROGEN



CHROMATOGRAM	1	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.45	231				
		-----			-----	
	TOTAL	231			0	

GROUP(NAME)	CONC
C-1	0
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0


POST ANALYSIS CALIBRATION CHECK
 15PPM HYDROCARBON STANDARD
 SCOTTY CAN MIX 1



PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.671	16264		6	14.8091	C-6+
2	3.046	2872		1	16.0838	C-1
3	3.583	5675		2	16.2143	C-2
4	4.728	8376	V	3	16.0768	C-3
5	7.383	11220		4	16.2832	C-4
6	13.294	13797	V	5	14.6212	C-5
TOTAL		58204			94.0884	

GROUP(NAME)	CONC
C-1	16.0838
C-2	16.2143
C-3	16.0768
C-4	16.2832
C-5	14.6212
C-6+	14.8091

POST ANALYSIS CALIBRATION CHECK
 100PPM HYDROCARBON STANDARD
 SCOTTY CAN MIX 220









CHROMATOGRAM	17	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.672	106264		6	99.6241	C-6+
2	3.048	18046	V	1	100.3935	C-1
3	3.593	36074		2	100.2438	C-2
4	4.729	53827		3	99.8176	C-3
5	6.433	236				
6	7.384	70581		4	99.6427	C-4
7	13.293	85904		5	98.5352	C-5
TOTAL		370930			598.2569	

GROUP(NAME)	CONC
C-1	100.3935
C-2	100.2438
C-3	99.8176
C-4	99.6427
C-5	98.5352
C-6+	99.6241

COMPANY : DESTEC OPERATING
 UNIT : LUBE OIL VENT #1 TURBINE 1
 DATE : 2-26-93
 REPORT : 027-341


HYDROCARBON CALIBRATION LINEARITY GRAPHS
 ANALYSIS PERFORMED ON 2-27-93



SYSTEM BLANK
UHP NITROGEN


93/02/27

10:45:44



CHROMATOGRAM 1 MEMORIZED
WARNING NO PEAK

15PPM STANDARD
SCOTTY CAN MIX 1




CHROMATOGRAM	2	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.677	16352		6		C-6+
2	3.052	2847		1		C-1
3	3.599	5665		2		C-2
4	4.736	8260		3		C-3
5	7.397	11135		4		C-4
6	13.321	13546		5		C-5
TOTAL		57806				

IDENTIFICATION FILE 0
MODE\$ 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.04	0.00579578	16.5
2	C-2	3.58	0.00291267	16.5
3	C-3	4.72	0.00199749	16.5
4	C-4	7.38	0.00148179	16.5
5	C-5	13.3	0.00109255	14.8
6	C-6+	2.66	0.000929527	15.2
7	C-2	3.85	0.00291267	16.5
8	C-3	4.3	0.00199749	16.5
9	C-4	5.7	0.00148179	16.5
10	C-4	6.65	0.00148179	16.5
11	C-5	10.24	0.00109255	14.8
12	C-5	10.59	0.00109255	14.8
13	C-5	12.73	0.00109255	14.8
14	C-5	11.3	0.00109255	14.8
15	C-5	15.43	0.00109255	14.8
16	C-5	8.79	0.00109255	14.8
17	C-5	11.82	0.00109255	14.8

100PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 220




PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.677	105206		6		C-6+
2	3.054	17581		1		C-1
3	3.601	36075		2		C-2
4	4.74	53689		3		C-3
5	6.448	164				
6	7.403	70563		4		C-4
7	13.328	85164		5		C-5
TOTAL		368443				

IDENTIFICATION FILE 1
MODE\$ 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.04	0.00574471	101
2	C-2	3.59	0.00279969	101
3	C-3	4.72	0.00186259	100
4	C-4	7.39	0.00143134	101
5	C-5	13.31	0.00116364	99.1
6	C-6+	2.66	0.000950515	100
7	C-2	3.9	0.00279969	101
8	C-3	4.35	0.00186259	100
9	C-4	5.75	0.00143134	101
10	C-4	6.66	0.00143134	101
11	C-5	10.21	0.00116364	101
12	C-5	10.59	0.00116364	99.1
13	C-5	12.71	0.00116364	99.1
14	C-5	11.3	0.00116364	99.1
15	C-5	15.27	0.00116364	99.1
16	C-5	12.19	0.00116364	99.1
17	C-5	11.6	0.00116364	99.1

1000PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 224




CHROMATOGRAM	4	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.679	1084699		6		C-6+
2	3.056	182575	V	1		C-1
3	3.603	366221		2		C-2
4	4.741	546122		3		C-3
5	6.731	801		10		C-4
6	7.403	723032		4		C-4
7	12.068	582	V			
8	13.32	888271		5		C-5
9	14.715	3371	V			
TOTAL		3795672				

IDENTIFICATION FILE 2
MODE\$ 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.04	0.0054772	1000
2	C-2	3.59	0.00281251	1030
3	C-3	4.73	0.00183109	1000
4	C-4	7.39	0.0013969	1010
5	C-5	13.3	0.0011483	1020
6	C-6+	2.66	0.000926524	1005
7	C-2	3.9	0.00281251	1030
8	C-3	4.52	0.00183109	1000
9	C-4	5.94	0.0013969	1010
10	C-4	6.71	0.0013969	1010
11	C-5	10.21	0.0011483	1020
12	C-5	10.59	0.0011483	1020
13	C-5	12.73	0.0011483	1020
14	C-5	12.55	0.0011483	1020
15	C-5	15.21	0.0011483	1020


POST ANALYSIS CALIBRATION CHECK
 15PPM HYDROCARBON STANDARD
 SCOTTY CAN MIX 1



CHROMATOGRAM	14	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.67	16676		6	15.5009	C-6+
2	3.063	2919		1	16.919	C-1
3	3.613	5790		2	16.8631	C-2
4	4.755	8572		3	17.1225	C-3
5	7.417	11301		4	16.7462	C-4
6	13.371	13791		5	15.0677	C-5
TOTAL		59049			98.2193	

GROUP(NAME)	CONC
C-1	16.919
C-2	16.8631
C-3	17.1225
C-4	16.7462
C-5	15.0677
C-6+	15.5009

POST ANALYSIS CALIBRATION CHECK
 100PPM HYDROCARBON STANDARD
 SCOTTY CAN MIX 220



CHROMATOGRAM 15 MEMORIZED						
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.672	106850		6	101.5628	C-6+
2	3.065	18030		1	103.5794	C-1
3	3.614	36510		2	102.2167	C-2
4	4.756	54453		3	101.4233	C-3
5	6.746	234		10	0.3355	C-4
6	7.428	71740	V	4	102.6838	C-4
7	13.372	86707		5	100.8948	C-5
TOTAL		374524			612.6962	

GROUP(NAME)	CONC
C-1	103.5794
C-2	102.2167
C-3	101.4233
C-4	103.0193
C-5	100.8948
C-6+	101.5628

APPENDIX IV CORRESPONDENCE



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

313 Daniels Lane
Bakersfield, California 93307
(805) 327-7300
FAX (805) 327-3459

Gary Fuller (WZI)
Double "C" Limited Cogen Facility
January 27, 1993

Units: Two Gas Turbines and
Two Lube Oil Vent Stacks

SOURCE TEST PLAN

I. Source Information:

A. Unit: Two 25.0 MW GE LM-2500
Gas Fired Turbines
PTO 4165001 (B), 4165002 (B)
Two Lube Oil Vent Stacks; one per turbine

B. Company: Destec Engineering, Inc.
Double "C" Limited Cogeneration Facility
Sec. 11, T28S, R27E
Kern County, California

C/O Gary Fuller (WZI, Inc.)
4800 Easton Drive, Suite 114
Bakersfield, California 93309

II. Testing Firm: Petro Chem Environmental Services, Inc.
313 Daniels Lane
Bakersfield, CA 93307

Attention: Tim Brennan

III. Regulatory Agency: San Joaquin Valley Unified APCD
Southern Region

IV. Summary: Determination concentrations (ppm) and
emissions (lb/hr) of particulate, sulfur,
NMHC, NOx, CO and Spec II, III, IV
(NOx, O₃, CO) relative accuracy, from the
exhaust of two gas fired Turbine/Generators.

V. Testing Date: February 9 - 12, 1993

**PROPOSAL FOR COMPLIANCE TESTING
AT TWO TURBINE MAIN STACKS**

Determination of concentrations (ppm) and emissions (lb/hr) of particulate, sulfur, NMHC, NOx and CO from the exhaust of two 25 MW gas fired Turbine/Generators. Relative Accuracy testing will be performed for NOx, O₂ and CO following Title 40 CFR performance Spec II, III and IV; a minimum of nine thirty minute runs will be performed. Fuel sulfur analysis will be performed by EPA Method 20 and 19; EAS Labs of San Luis Obispo will be used (example analysis enclosed). The following methods will be used:

Parameters	Method	# Test Runs Per Turbine	Permit Limit, lb/hr Per Turbine
Particulate	EPA Method 5; Gravimetric	2 - 6 hour	3.12
Sulfur	Fuel Analysis / Fuel Rates	1	*** 0.16 as sulfur
NMHC	EPA Method 18; (modified) C ₁ -C ₆ +	3	** 3.12
* NOx	EPA Method 20; Chemiluminescent Analyzer	9 - 30 min.	4.04 lb/hr 0.0162 lb/MMBtu
* CO	EPA Method 10; GFC Analyzer	9 - 30 min.	27.83
* O ₂	EPA Method 20; Fuel Cell Analyzer	9 - 30 min.	---
Molecular Weight O ₂ /CO ₂ /N ₂	EPA Method 3; Orsat	2	---
Volume Flow DSCFM	EPA Method 2; Pitot Tube Traverse	2	---
Relative Accuracy NOx/O ₂ /CO	Title 40 CFR Performance Spec II/III/IV	See above NOx,O ₂ ,CO	20%/20%/10%

* An initial 48 point concentration traverse will be performed to document the point(s) of average concentration. All follow-up runs will be performed at the point(s) of average concentration.

** Includes emissions from lube oil vent stack. The Method 18 analysis will be modified to increase sensitivity to 0.2 ppm C₁-C₆+. Sample analysis is enclosed.

*** Emissions as sulfur = (lb/hr SO₂/s) + lb/hr SO₄/3)

Gary Fuller (WZI)
Double "C" Limited Cogen Facility
January 27, 1993

Units: Two Gas Turbines and
Two Lube Oil Vent Stacks

**PROPOSAL FOR COMPLIANCE TESTING
AT LUBE OIL VENT STACKS**

Determination of concentrations (ppm, gr/DSCF) and emissions (lb/hr, lb/day) of condensable and non-condensable hydrocarbon emissions from the exhaust of two lube oil vent stacks, one per turbine. The following procedures will be used:

Parameters	Method	# Test Runs/Site
Condensable Hydrocarbons	EPA Method 4; with Gravimetric Organic Extractions Utilizing CARB Method 5.4.3.1	3
Non-Condensable Hydrocarbons	EPA Method 18; Bag Sample FID Analysis	3
Volume Flow	EPA Method 2; Pitot Tube or Hot Wire Anemometer	3
Molecular Weight	EPA Method 3; Orsat Analysis	3
% H ₂ O	EPA Method 4; Condensation	3



KERN COUNTY AIR POLLUTION CONTROL DISTRICT

PERMIT TO OPERATE

Number: 4163001(B)

2700 "M" STREET, SUITE 275
BAKERSFIELD, CA. 93301
TELEPHONE: (805) 861-3882

PERMIT TO OPERATE IS HEREBY GRANTED TO: DOUBLE "C" LIMITED
FOR EQUIPMENT LOCATED AT: Sec. 11, T28S. R27E
Kern Front Lease
EQUIPMENT OR PROCESS DESCRIPTION: 25.0 MW Gas-Fired Turbine Engine
Cogeneration System


OPERATIONAL CONDITIONS LISTED BELOW.

THIS PERMIT BECOMES VOID UPON ANY CHANGE OF OWNERSHIP OR LOCATION, OR ANY ALTERATION.

NOTE: The permittee may be required to provide adequate sampling and testing facilities. Equipment modification requires a new permit.

WILLIAM J. RODDY
AIR POLLUTION CONTROL OFFICER

REVOCABLE: This permit does not authorize the emission of air contaminants in excess of those allowed by the Rules and Regulations of the K.C.A.P.C.D.

By: 

For Period: 02-28-92 TO 02-28-93

CONDITIONAL APPROVAL:

Compliance with all conditions of approval imposed by any applicable Authority to Construct is required for life of this equipment unless modified by application. Equipment authorized by this Permit to Operate shall comply in full with applicable Rule 210.1 requirements.

EQUIPMENT DESCRIPTION:

- a. Winston 120 HB centrifugal separator.
- b. General Electric. Model LM 2500. 250.2 MM BTU/hr input natural gas fired turbine engine.
- c. Continuously recording emission monitors for NOx, CO, and O₂.
- d. 25.0 MW electric generator.

OPERATIONAL CONDITIONS:

1. Gas turbine engine shall be fired exclusively with PUC-regulated quality natural gas. (Rule 210.1)
2. Gas turbine engine steam injection rate shall be maintained at 1.90 - 2.19 steam to fuel ratio documented to result in compliance with emission limits. (Rule 209)
3. Ammonia injection rate shall be controlled to maintain ammonia "break-through" to less than 20 ppmv. (Rule 410)
4. If steam injection, SCR, or catalytic conversion system is inoperative, gas turbine engine shall be shut down. (Rule 209)
Inlet gas temperature to both catalyst beds shall be maintained within the range recommended by catalyst manufacturer. (Rule 209)
5. Gas turbine engine shall not burn more than 5.67 MM scf/day of natural gas. (Rule 209)

7. All gas turbine exhaust shall flow through both catalyst beds. (Rule 209)
8. Handling and storage of collected liquids shall not result in an increase of hydrocarbon emissions. (Rule 210.1)
9. Visible emissions from lube oil system atmospheric vent shall not exceed 20% opacity for more than a total of 3 minutes in any one hour. (Rule 401)

COMPLIANCE TESTING REQUIREMENT:

Compliance with particulates, sulfur compounds, oxides of nitrogen, hydrocarbons and carbon monoxide emission sampling limits shall be demonstrated by District-witnessed sample collection by independent testing laboratory within 60 days after startup and annually within 60 days prior to permit anniversary date, and the official test results, and field data submitted within 30 days after collection. Samples shall be collected during maximum fuel consumption and use of evaporative coolers. (Rule 108.1)

EMISSION SAMPLING LIMITS:

<u>Particulates:</u>	3.12	lbm/hr	(Rule 210.1)
<u>Sulfur Compounds:</u>	0.18	lbm/hr	(of SO ₂) (Rule 210.1)
	0.24	lbm/hr	(of SO ₄) (Rule 210.1)
<u>Oxides of Nitrogen:</u>	4.04	lbm/hr	(as NO ₂) (Rule 210.1)
	0.0162	lbm/MM BTU	(as NO ₂) (Rule 210.1 BACT req't)
<u>Hydrocarbons:</u>	3.12	lbm/hr	(Rule 210.1) (including lube oil cooler/accumulating vents & collected liquids)
<u>Carbon Monoxide:</u>	27.88	lbm/hr	(Rule 210.1)

SPECIAL CONDITIONS:

1. Double "C" Limited shall comply in full with Rule 422 (New Source Performance Standards) requirements including notification, record keeping and monitoring requirements.
2. Continuous emission monitoring system for NO_x (as NO₂), CO and O₂ serving exhaust gas stream shall conform to Rule 108 specifications.
3. Continuous emission monitoring systems shall be calibrated and operated according to EPA guidelines as specified in CRF, Part 60, Appendix B. (Rule 108)
4. Audits of monitors shall be conducted semi-annually by independent laboratory in accordance with EPA guidelines, witnessed by District, and reports shall be submitted to District within 30 days of such audit. (Rule 108)
5. Double "C" Limited continuous emissions monitoring printouts shall be made readily available for District inspection upon request. (Rule 208)

6. Double "C" Limited shall keep accurate records of daily fuel consumption of gas turbine engine and shall make them readily available for District inspection upon request. (Rule 209)
7. Steam produced at this facility for use in oil-production operations shall affect only wells connected to well vent vapor recovery systems KCAPCD #4018106 owned by Cities Service and KCAPCD #4032100 owned by Carrec Oil unless prior District approval is obtained. (Rule 210.1)
8. Double "C" Limited shall provide design details, including but not limited to engineering drawings of SCR and catalytic converter units for District approval prior to installation. (Rule 209)
9. Non-compliance with NOx emission sampling limit shall require: shut-down of gas turbine, down throttling (reduced fuel consumption), or installation of additional SCR catalyst volume - increased emission limits will require modified Authority to Construct before continued operation at such levels pursuant to Section 42350 of California Health & Safety Code, a variance for this condition cannot be obtained. (Rule 209)

RNING:

Failure of catalyst to perform as required because of catalyst poisoning or fouling shall not be recognized as basis for Rule 111 enforcement exemption. (Rule 209)



KERN COUNTY AIR POLLUTION CONTROL DISTRICT

PERMIT TO OPERATE

Number: 4163002(8)

2700 "M" STREET, SUITE 275
BAKERSFIELD, CA. 93301
TELEPHONE: (805) 361-3632

PERMIT TO OPERATE IS HEREBY GRANTED TO: DOUBLE "C" LIMITED
FOR EQUIPMENT LOCATED AT: Sec. 11. T2SS. R27E
Kern Front Lease
EQUIPMENT OR PROCESS DESCRIPTION: 25.0 MW Gas-Fired Turbine Engine
Cogeneration System


OPERATIONAL CONDITIONS LISTED BELOW.

THIS PERMIT BECOMES VOID UPON ANY CHANGE OF OWNERSHIP OR LOCATION, OR ANY ALTERATION.

NOTE: The permittee may be required to provide adequate sampling and testing facilities. Equipment modification requires a new permit.

WILLIAM J. RODOY
AIR POLLUTION CONTROL OFFICER

REVOCABLE: This permit does not authorize the emission of air contaminants in excess of those allowed by the Rules and Regulations of the K.C.A.P.C.D.

By: 

For Period: 02-28-92 TO 02-28-93

CONDITIONAL APPROVAL:

Compliance with all conditions of approval imposed by any applicable Authority to Construct is required for life of this equipment unless modified by application. Equipment authorized by this Permit to Operate shall comply in full with applicable Rule 210.1 requirements.

EQUIPMENT DESCRIPTION:

- Winston 120 HB centrifugal separator.
- General Electric, Model LM 2500, 250.3 MM BTU/hr input natural gas fired turbine engine.
- Continuously recording emission monitors for NOx, CO, and O₂.
- 25.0 MW electric generator.

OPERATIONAL CONDITIONS:

- Gas turbine engine shall be fired exclusively with PUC-regulated quality natural gas. (Rule 210.1)
- Gas turbine engine steam injection rate shall be maintained at 1.62 - 1.74 steam to fuel ratio documented to result in compliance with emission limits. (Rule 209)
- Ammonia injection rate shall be controlled to maintain ammonia "break-through" to less than 20 ppmv. (Rule 410)
- If steam injection, SCR, or catalytic conversion system is inoperative, gas turbine engine shall be shut down. (Rule 209)
Inlet gas temperature to both catalyst beds shall be maintained within the range recommended by catalyst manufacturer. (Rule 209)
- Gas turbine engine shall not burn more than 5.67 MM scf/day of natural gas. (Rule 209)

7. All gas turbine exhaust shall flow through both catalyst beds. (Rule 209)
8. Handling and storage of collected liquids shall not result in an increase of hydrocarbon emissions. (Rule 210.1)
9. Visible emissions from lube oil system atmospheric vent shall not exceed 20% opacity for more than a total of 3 minutes in any one hour. (Rule 401)

COMPLIANCE TESTING REQUIREMENT:

Compliance with particulates, sulfur compounds, oxides of nitrogen, hydrocarbons and carbon monoxide emission sampling limits shall be demonstrated by District-witnessed sample collection by independent testing laboratory within 60 days after startup and annually within 60 days prior to permit anniversary date, and the official test results, and field data submitted within 30 days after collection. Samples shall be collected during maximum fuel consumption and use of evaporative coolers. (Rule 108.1)

EMISSION SAMPLING LIMITS:

<u>Particulates:</u>	3.12	lbm/hr	(Rule 210.1)
<u>Sulfur Compounds:</u>	0.16	lbm/hr	(of SO ₂) (Rule 210.1)
	0.24	lbm/hr	(of SO ₄) (Rule 210.1)
<u>Oxides of Nitrogen:</u>	4.04	lbm/hr	(as NO ₂) (Rule 210.1)
	0.0162	lbm/MM BTU	(as NO ₂) (Rule 210.1 BACT req't)
<u>Hydrocarbons:</u>	3.12	lbm/hr	(Rule 210.1) (including lube oil cooler/accumulating vents & collected liquids)
<u>Carbon Monoxide:</u>	27.83	lbm/hr	(Rule 210.1)

SPECIAL CONDITIONS:

1. Double "C" Limited shall comply in full with Rule 422 (New Source Performance Standards) requirements including notification, record keeping and monitoring requirements.
2. Continuous emission monitoring system for NO_x (as NO₂), CO and O₂ serving exhaust gas stream shall conform to Rule 108 specifications.
3. Continuous emission monitoring systems shall be calibrated and operated according to EPA guidelines as specified in CRF, Part 60, Appendix B. (Rule 108)
4. Audits of monitors shall be conducted semi-annually by independent laboratory in accordance with EPA guidelines, witnessed by District, and reports shall be submitted to District within 30 days of such audit. (Rule 108)
5. Double "C" Limited continuous emissions monitoring printouts shall be made readily available for District inspection upon request. (Rule 208)

6. Double "C" Limited shall keep accurate records of daily fuel consumption of gas turbine engine and shall make them readily available for District inspection upon request. (Rule 209)
7. Steam produced at this facility for use in oil-production operations shall affect only wells connected to well vent vapor recovery systems KCAPCD #4018106 owned by Citicor Service and KCAPCD #4032100 owned by Carrec Oil unless prior District approval is obtained. (Rule 210.1)
8. Double "C" Limited shall provide design details, including but not limited to engineering drawings of SCR and catalytic converter units for District approval prior to installation. (Rule 209)
9. Non-compliance with NOx emission sampling limit shall require: shut-down of gas turbine, down throttling (reduced fuel consumption), or installation of additional SCR catalyst volume - increased emission limits will require modified Authority to Construct before continued operation at such levels pursuant to Section 42350 of California Health & Safety Code, a variance for this condition cannot be obtained. (Rule 209)

WARNING:

Failure of catalyst to perform as required because of catalyst poisoning or fouling shall not be recognized as basis for Rule 111 enforcement exemption. (Rule 209)