

RECEIVED

TABLE OF CONTENTS

APR 7 1993

SAN JOAQUIN VALLEY UNIFIED
APCD—SOUTHERN REGION

I. SUMMARY OF RESULTS	4
II. INTRODUCTION	8
III. METHOD 5 DATA	11
A. Turbine #1	12
B. Turbine #2	14
IV. HYDROCARBON DATA	16
A. Summary of Hydrocarbon Results (Turbine #1 & #2)	17
B. Turbine #1 Results	
1. Summary	18
2. Turbine #1 Main Stack	19
3. Lube Oil Vent Generator #1	21
4. Lube Oil Vent Turbine #1	24
C. Turbine #2 Results	
1. Summary	27
2. Turbine #2 Main Stack	28
3. Lube Oil Vent Generator #2	30
4. Lube Oil Vent Turbine #2	33
D. Non Condensable Hydrocarbon Detection Limits	36
V. SULFUR EMISSIONS	37
A. Emissions	38
B. Sulfur Analysis	40
VI. RELATIVE ACCURACY	47
A. Turbine #1 RATA	48
B. Turbine #2 RATA	51
C. Destec CEM Summary	54
D. Reference Method Turbine #1	55
E. Reference Method Turbine #2	65

TABLE OF CONTENTS
(con't)

VII. EMISSION FACTORS (lbs/MMBtu)	75
A. Turbine #1 - NOx & CO	76
B. Turbine #2 - NOx & CO	77
VIII. FUEL GAS ANALYSIS	78
IX. METHODS & EQUATIONS	81
 APPENDICES	
I. OPERATIONAL DATA (Supplied by Destec)	94
A. CEM Data	95
B. Fuel Data	103
II. RAW DATA	106
A. Method 5 Field Data	107
B. Method 5 Lab Data	119
C. Method 1-4 Field Data	123
D. Method 1-4 Lab Data	139
E. Hydrocarbon Chromatograms	143
F. Instrument Strip Charts	166
III. QUALITY ASSURANCE	178
A. Chain of Custody Records	179
B. Equipment Calibration	187
C. CEM Calibration Gases	190
D. Wet Test Methods Field Blanks	195
E. Hydrocarbon Linearities	202
IV. CORRESPONDENCE	246

SUMMARY OF SOURCE TEST RESULTS

COMPANY: **DESTEC - KERN FRONT**

APCD #: 4166001 (B)

TEST DATE: **FEBRUARY 18-19, 23-26, 1993**

UNIT #: **TURBINE #1**

EMISSIONS	gr/scf	@12%CO2	ppm	ppm @15% O2	lb/ MMBtu	lb/hr	lb/day	Permit Limits
PARTICULATE	0.000691 0.000539	0.003373 0.002627				0.81 0.64	19.44 15.36	
Mean:	0.000615	0.003000				0.73	17.40	3.12 lb/hr
SULFUR			in fuel			in exhaust	in exhaust	
Mean:			2.0			0.0379	0.910	0.16 lb/hr
NOx (dry) (RUNS 1-9)								0.0162 lb/MMBtu
Mean:			2.12	1.81	0.00661	1.73	41.5	4.04 lb/hr
CO (RUNS 1-9)								
Mean:			35.6	30.4	0.06764	17.6	427	27.83 lb/hr
NMHC turbine plus 2 lube oil vents								
Mean:						1.22	29.08	3.12 lb/hr
RELATIVE ACCURACY	% RA Related to Reference Method		% RA Related to Applicable Standard			PERMIT LIMITS		
						Related to Reference Method	Related to Applicable Standard	
NOx	4.77		NA			20 %	NA	
CO	6.07		NA			10 %	NA	
O2	1.29		NA			20 %	NA	

For San Joaquin Unified APCD Use Only:

[Handwritten Signature]
4/20

SUMMARY OF SOURCE TEST RESULTS

COMPANY: **DESTEC - KERN FRONT**

APCD #: 4166002 (B)

TEST DATE: **FEBRUARY 18-19, 23-26, 1993**

UNIT #: **TURBINE #2**

EMISSIONS	gr/scf	@12%CO ₂	ppm	ppm @15% O ₂	lb/ MMBtu	lb/hr	lb/day	Permit Limits
PARTICULATE	0.000865 <u>0.000744</u>	0.004223 <u>0.003648</u>				0.99 <u>0.88</u>	23.76 <u>21.12</u>	
Mean:	0.000805	0.003936				0.94	22.44	3.12 lb/hr
SULFUR			in fuel			in exhaust	in exhaust	
Mean:			1.9			0.0364	0.874	0.16 lb/hr
NO _x (dry) (RUNS 1-9)								0.0182 lb/MMBtu
Mean:			2.82	2.45	0.00893	2.26	54.2	4.04 lb/hr
CO (RUNS 1-9)								
Mean:			40.9	35.4	0.07874	19.9	478	27.83 lb/hr
NMHC turbine plus 2 lube oil vents								
Mean:						1.39	33.33	3.12 lb/hr
RELATIVE ACCURACY	% RA Related to Reference Method		% RA Related to Applicable Standard			PERMIT LIMITS		
						Related to Reference Method	Related to Applicable Standard	
NO _x	9.97		NA			20 %	NA	
CO	0.96		NA			10 %	NA	
O ₂	1.17		NA			20 %	NA	


For San Joaquin Unified APCD Use Only: _____

A. P. d.
4/2

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINES 1 & 2 AND LUBE OIL VENTS
 DATE : 02-18/19, 25-93
 REPORT : 027-343

SUMMARY OF HYDROCARBONS RESULTS

	gr/scf	ppm	lbs/hr	lbs/day
TURBINE #1				
NON-CONDENSABLE	---	4.34	1.21	28.96
TOTAL HYDROCARBONS	---	---	1.21	28.96
TURBINE #2				
NON-CONDENSABLE	---	4.85	1.38	33.20
TOTAL HYDROCARBONS	---	---	1.38	33.20
LOV GENERATOR 1				
CONDENSABLE	0.03755	---	0.00356	0.0854
NON-CONDENSABLE	---	24.56	0.00071	0.0170
TOTAL HYDROCARBONS	---	---	0.00427	0.1024
LOV TURBINE 1				
CONDENSABLE	0.03151	---	0.00068	0.0163
NON-CONDENSABLE	---	12.54	0.00008	0.0018
TOTAL HYDROCARBONS	---	---	0.00076	0.0181
LOV GENERATOR 2				
CONDENSABLE	0.03081	---	0.00323	0.0800
NON-CONDENSABLE	---	21.61	0.00068	0.0163
TOTAL HYDROCARBONS	---	---	0.00391	0.0963
LOV TURBINE 2				
CONDENSABLE	0.02558	---	0.00070	0.0167
NON-CONDENSABLE	---	80.80	0.00063	0.0150
TOTAL HYDROCARBONS	---	---	0.00133	0.0317
TOTAL EMISSIONS				
TURBINE #1 + LOVG 1 + LOVT 1			1.22	29.08
TURBINE #2 + LOVG 2 + LOVT 2			1.39	33.33



INTRODUCTION

On February 23-26, 1992, Petro Chem Environmental Services, Inc. (PCES) performed a series of emission source tests for Destec Operating Company at their Kern Front Limited Cogeneration Facility located in Kern County, California. The units tested were two 25.0 MW GE LM-2500 gas fired turbine/generators and four lube oil vents; two per turbine.

Determination of concentrations (ppm) and emissions (lbs/hr) of particulate, sulfur, NMHC, NOx, CO, O₂, from the exhaust of the two turbine/generators and relative accuracy testing was performed for NOx, CO, and O₂ using the following procedures:

PARAMETERS	METHOD	# TEST RUNS PER TURBINE
Particulate	EPA Method 5; Gravimetric	2 - 6 hr.
Sulfur	Fuel Analysis / Fuel Rates EAS Labs	1
NMHC	EPA Method 18; (modified) C ₁ - C ₈₊	3
NOx	EPA Method 20; Chemiluminescent Analyzer equipped with Molydenum Convertor	Turbine #1 9 - 30 min. Turbine #2 9 - 30 min.
CO	EPA Method 10; Gas Filter Correlation Analyzer	Turbine #1 9 - 30 min. Turbine #2 9 - 30 min.
O ₂	EPA Method 20; Fuel Cell Analyzer	Turbine #1 9 - 30 min. Turbine #2 9 - 30 min.
Molecular Weight O ₂ , CO ₂ , N ₂	EPA Method 3; Orsat	2
Volume Flow DSCFM	EPA Method 2; Pitot Tube Traverse	2
Relative Accuracy NOx/ CO / O ₂	Title 40 CFR Performance Spec II, III, IV	Turbine #1 9 - 30 min. Turbine #2 9 - 30 min.

Each turbine was equipped with two lube oil vent (LOV) stacks; turbine LOV and generator LOV. Concentrations (ppm, gr/DSCF) and emissions (lb/hr, lb/day) of condensable and non condensable hydrocarbon emissions from the exhaust of the lube oil vent stacks were determined using the following procedures:

PARAMETERS	METHOD	# TEST RUNS/ LUBE OIL VENT
Condensable Hydrocarbons	EPA Method 4; with Gravimetric Organic Extractions Utilizing CARB Method 5.4.3.1.	3
Non Condensable Hydrocarbons	EPA Method 18; Bag Sample FID Analysis	3
Volume Flow	EPA Method 2; Pitot Tube Or Hot Wire Anemometer	3
Molecular Weight	EPA Method 3; Orsat Analysis	3
% H ₂ O	EPA Method 4; Condensation	3

As per permit to operate, emissions of hydrocarbons are expressed as the sum of the emissions from the turbine and it's two LOV stacks.

All sampling was performed by Doug Towne and Randall Kastner of Petro Chem Environmental Services, Inc. The hydrocarbons, fuel gas, PM, and organic analyses were performed by Terry Rowles of PCES. The fuel sulfur was analyzed by EAS Labs of San Luis Obispo, California. Gary Fuller of Destec Operating Company supervised the testing. Harvey Lopez of San Joaquin Valley Unified APCD, Southern Region, was present and witnessed the testing.

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

METHOD 1-5
 FIELD DATA @ 60° F

RUN #:	1	2
TIME :	911	835

Vm (dry gas sampled)	173.99	173.61
Y (meter calib. factor)	0.982977	0.982977
P bar (Barometric pressure)	29.04	29.09
P static (stack pressure, " H2O)	-0.85	-0.85
Delta H (differential meter press, " H2O)	0.57	0.6
Tm (meter temperature, R°)	526	519
Vol H2O mls	779.8	779.4
Vm(std),dscf	164.34	166.49
Bws-H2O vapor	0.1806	0.1786
MF-moisture factor	0.8194	0.8214
% CO2	3	3
% O2	14	14
% N2	83	83
Md-MW stk gas,dry	29.04	29.04
Ms-MW stk gas,wet	27.05	27.07
Cp-pitot tube	0.791	0.791
Avg sq rt ^p	0.99	1.01
T stack, R°	723	729
Stack area,ft2	50.528	50.528
Vs-fps	64.43	65.88
Qstd-dscfm	111481	113527
Area noz,ft2	2.10E-04	2.10E-04
Sample time	360	360
% Isokinetic	98.7	98.2

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 02-23/24-93
 REPORT : 027-343

EPA METHOD 5 DATA
 @ 60°F
 RUN #1

PARTICULATE RESULTS:	net mg	gr/dscf	gr/scf	gr/dscf @ 12% CO2	lbs/hr	lbs/day
Probe & Nozzle:	3.70	0.000347	0.000284	0.001387	0.33	7.92
Filter:	0.10	0.000009	0.000008	0.000037	0.01	0.24
Condensables:	5.20	0.000487	0.000399	0.001949	0.47	11.28
Total:	9.00	0.000843	0.000691	0.003373	0.81	19.44

ADDITIONAL DATA:
 TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
901	1523	14	3	18.06	164.34	111481

RUN #2

PARTICULATE RESULTS:	net mg	gr/dscf	gr/scf	gr/dscf @ 12% CO2	lbs/hr	lbs/day
Probe & Nozzle:	2.00	0.000185	0.000152	0.000740	0.18	4.32
Filter:	0.30	0.000028	0.000023	0.000111	0.03	0.72
Condensables:	4.80	0.000444	0.000365	0.001776	0.43	10.32
Total:	7.10	0.000657	0.000539	0.002627	0.64	15.36

ADDITIONAL DATA:
 TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
835	1451	14	3	17.86	166.49	113527

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 2-25/26-93
 REPORT : 027-343

METHOD 1-5
 FIELD DATA @ 60° F

RUN #: 1 2
 TIME : 750 823

Vm (dry gas sampled)	167.98	172.04
Y (meter calib. factor)	0.982977	0.982977
P bar (Barometric pressure)	29.13	29.03
P static (stack pressure, " H2O)	-0.6	-0.6
Delta H (differential meter press, " H2O)	0.57	0.59
Tm (meter temperature, R°)	522	522
Vol H2O mls	762.5	796.1
Vm(std),dscf	160.38	163.70
Bws-H2O vapor	0.1809	0.1843
MF-moisture factor	0.8191	0.8157
% CO2	3	3
% O2	14	14.3
% N2	83	82.7
Md-MW stk gas,dry	29.04	29.05
Ms-MW stk gas,wet	27.04	27.02
Cp-pitot tube	0.791	0.791
Avg sq rt ^p	0.97	0.99
T stack, R°	725	720
Stack area,ft2	50.528	50.528
Vs-fps	62.91	64.16
Qstd-dscfm	108922	111009
Area noz,ft2	2.10E-04	2.10E-04
Sample time	360	360
% Isokinetic	98.6	98.8

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #2
DATE : 02-25/26-93
REPORT : 027-343

EPA METHOD 5 DATA

@ 60°F

RUN #1

PARTICULATE RESULTS:	net mg	gr/dscf	gr/scf	gr/dscf @ 12% CO2	lbs/hr	lbs/day
Probe & Nozzle:	4.90	0.000471	0.000385	0.001882	0.44	10.56
Filter:	0.30	0.000029	0.000024	0.000115	0.03	0.72
Condensables:	5.79	0.000556	0.000456	0.002226	0.52	12.48
Total:	10.99	0.001056	0.000865	0.004223	0.99	23.76

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
750	1401	14	3	18.09	160.38	108922

RUN #2

PARTICULATE RESULTS:	net mg	gr/dscf	gr/scf	gr/dscf @ 12% CO2	lbs/hr	lbs/day
Probe & Nozzle:	3.30	0.000310	0.000253	0.001242	0.30	7.20
Filter:	0.20	0.000019	0.000015	0.000075	0.02	0.48
Condensables:	6.19	0.000583	0.000475	0.002331	0.56	13.44
Total:	9.69	0.000912	0.000744	0.003648	0.88	21.12

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
823	1433	14.3	3	18.43	163.7	111009

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINES 1 & 2 AND LUBE OIL VENTS
 DATE : 02-18/19, 25-93
 REPORT : 027-343

SUMMARY OF HYDROCARBONS RESULTS

	gr/scf	ppm	lbs/hr	lbs/day
TURBINE #1				
NON-CONDENSABLE	----	4.34	1.21	28.96
TOTAL HYDROCARBONS	----	----	1.21	28.96
TURBINE #2				
NON-CONDENSABLE	----	4.85	1.38	33.20
TOTAL HYDROCARBONS	----	----	1.38	33.20
LOV GENERATOR 1				
CONDENSABLE	0.03755	----	0.00356	0.0854
NON-CONDENSABLE	----	24.56	0.00071	0.0170
TOTAL HYDROCARBONS	----	----	0.00427	0.1024
LOV TURBINE 1				
CONDENSABLE	0.03151	----	0.00068	0.0163
NON-CONDENSABLE	----	12.54	0.00008	0.0018
TOTAL HYDROCARBONS	----	----	0.00076	0.0181
LOV GENERATOR 2				
CONDENSABLE	0.03081	----	0.00323	0.0800
NON-CONDENSABLE	----	21.61	0.00068	0.0163
TOTAL HYDROCARBONS	----	----	0.00391	0.0963
LOV TURBINE 2				
CONDENSABLE	0.02558	----	0.00070	0.0167
NON-CONDENSABLE	----	80.80	0.00063	0.0150
TOTAL HYDROCARBONS	----	----	0.00133	0.0317
TOTAL EMISSIONS				
TURBINE #1 + LOVG 1 + LOVT 1			1.22	29.08
TURBINE #2 + LOVG 2 + LOVT 2			1.39	33.33

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1 & LUBE OIL VENTS
 DATE : 02-18/19, 25-93
 REPORT : 027-343

SUMMARY OF HYDROCARBONS RESULTS

	gr/scf	ppm	lbs/hr	lbs/day
TURBINE #1 - MAIN STACK				
BLANK CORRECTED				
NON-CONDENSABLE				
RUN 1		4.82	1.34	32.16
RUN 2		4.20	1.17	28.08
RUN 3		4.00	1.11	26.64
AVERAGE		4.34	1.21	28.96
LOV GENERATOR 1				
CONDENSABLE				
RUN 1	0.04393		0.00380	0.0913
RUN 2	0.03505		0.00335	0.0804
RUN 3	0.03368		0.00352	0.0845
AVERAGE	0.03755		0.00356	0.0854
NON-CONDENSABLE				
RUN 1		16.95	0.00043	0.0103
RUN 2		11.87	0.00033	0.0079
RUN 3		44.87	0.00136	0.0326
AVERAGE		24.56	0.00071	0.0170
TOTAL HYDROCARBONS	---	---	0.00427	0.1024
LOV TURBINE 1				
CONDENSABLE				
RUN 1	0.04024		0.00092	0.0220
RUN 2	0.02909		0.00058	0.0140
RUN 3	0.02520		0.00054	0.0130
AVERAGE	0.03151		0.00068	0.0163
NON-CONDENSABLE				
RUN 1		13.71	0.00009	0.0022
RUN 2		12.65	0.00007	0.0017
RUN 3		11.25	0.00007	0.0017
AVERAGE		12.54	0.00008	0.0018
TOTAL HYDROCARBONS	---	---	0.00076	0.0181
TURBINE #1				
TOTAL EMISSIONS			1.22	29.08
MAIN STACK + LOVG + LOVT				

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #1
DATE : 02-25-93
REPORT : 027-343

HYDROCARBON RESULTS
CORRECTED FOR METHOD BLANK

RUN No.: 1			average of pitot tube velocity profiles				
DSCFM: 109966			BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	*ND	0.05	66.25	18.43	66.25	18.43
Ethane	(C2)	*ND	0.03	2.41	1.26	4.82	1.34
Propane	(C3)	*ND	0.02	0.00	0.00	0.00	0.00
Butane	(C4)	*ND	0.02	0.00	0.00	0.00	0.00
Pentane	(C5)	*ND	0.02	0.00	0.00	0.00	0.00
Hexane	(C6)		0.10	0.00	0.00	0.00	0.00
Total			68.66		19.69	71.07	19.77
Total (non methane)			2.41		1.26	4.82	1.34

RUN No.: 2			BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	*ND	0.05	59.53	16.56	59.53	16.56
Ethane	(C2)	*ND	0.03	2.10	1.10	4.20	1.17
Propane	(C3)	*ND	0.02	0.00	0.00	0.00	0.00
Butane	(C4)	*ND	0.02	0.00	0.00	0.00	0.00
Pentane	(C5)	*ND	0.02	0.00	0.00	0.00	0.00
Hexane	(C6)		0.10	0.00	0.00	0.00	0.00
Total			61.63		17.65	63.73	17.73
Total (non methane)			2.10		1.10	4.20	1.17

RUN No.: 3			BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	*ND	0.05	56.09	15.60	56.09	15.60
Ethane	(C2)	*ND	0.03	2.00	1.04	4.00	1.11
Propane	(C3)	*ND	0.02	0.00	0.00	0.00	0.00
Butane	(C4)	*ND	0.02	0.00	0.00	0.00	0.00
Pentane	(C5)	*ND	0.02	0.00	0.00	0.00	0.00
Hexane	(C6)		0.10	0.00	0.00	0.00	0.00
Total			58.09		16.65	60.09	16.72
Total (non methane)			2.00		1.04	4.00	1.11

*ND - Non detect in sample blank, used detection limit

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #1
DATE : 02-25-93
REPORT : 027-343

HYDROCARBON RESULTS

RUN No.: 1		DSCFM: 109966 average of pitot tube velocity profiles			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	66.30	18.44	66.30	18.44
Ethane	(C2)	2.44	1.27	4.88	1.36
Propane	(C3)	0.00	0.00	0.00	0.00
Butane	(C4)	0.00	0.00	0.00	0.00
Pentane	(C5)	0.00	0.00	0.00	0.00
Hexane	(C6)	0.00	0.00	0.00	0.00
<u>Total</u>		<u>68.74</u>	<u>19.72</u>	<u>71.18</u>	<u>19.80</u>
Total (non methane)		<u>2.44</u>	<u>1.27</u>	<u>4.88</u>	<u>1.36</u>
RUN No.: 2		DSCFM: 109966 average of pitot tube velocity profiles			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	59.58	16.57	59.58	16.57
Ethane	(C2)	2.13	1.11	4.26	1.19
Propane	(C3)	0.00	0.00	0.00	0.00
Butane	(C4)	0.00	0.00	0.00	0.00
Pentane	(C5)	0.00	0.00	0.00	0.00
Hexane	(C6)	0.00	0.00	0.00	0.00
<u>Total</u>		<u>61.71</u>	<u>17.68</u>	<u>63.84</u>	<u>17.76</u>
Total (non methane)		<u>2.13</u>	<u>1.11</u>	<u>4.26</u>	<u>1.19</u>
RUN No.: 3		DSCFM: 109966 average of pitot tube velocity profiles			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	56.14	15.62	56.14	15.62
Ethane	(C2)	2.04	1.06	4.08	1.13
Propane	(C3)	0.00	0.00	0.00	0.00
Butane	(C4)	0.00	0.00	0.00	0.00
Pentane	(C5)	0.00	0.00	0.00	0.00
Hexane	(C6)	0.00	0.00	0.00	0.00
<u>Total</u>		<u>58.18</u>	<u>16.68</u>	<u>60.22</u>	<u>16.75</u>
Total (non methane)		<u>2.04</u>	<u>1.06</u>	<u>4.08</u>	<u>1.13</u>

COMPANY : DESTEC
 UNIT : KERN FRONT - LUBE OIL VENT GENERATOR 1
 DATE : 02-19-93
 REPORT : 027-343

FIELD DATA @ 60°F

	RUN #:	1	2	3
	TIME:	1228	1312	1355
Vm (dry gas sampled)		24.07	23.97	23.93
Y (meter calib. factor)		0.998954	0.998954	0.998954
P bar (Barometric pressure)		29.08	29.08	29.08
P static (stack pressure, " H2O)		0	0	0
Delta H (differential meter press, " H2O)		0.59	0.59	0.59
Tm (meter temperature, R°)		536.7	538.44	536.6
Vol H2O mls		4.7	6.3	7.4
Vm(std),dscf		22.68	22.51	22.55
Bws-H2O vapor		0.0095	0.0128	0.0150
MF-moisture factor		0.990463	0.9872	0.9850
% CO2		0	0	0
% O2		20.7	20.7	20.7
% N2		79.3	79.3	79.3
Md-MW stk gas,dry		28.83	28.83	28.83
Ms-MW stk gas,wet		28.73	28.69	28.67
T stack, R°		557.5	546.5	549.4
Stack area,ft2		0.058	0.058	0.058
Vs-fpm, hot wire anemometer		189.1	214.4	224
Q-acfm		11	12	13
Qstd-dscfm		10	11	12
Sample time		40	40	40

COMPANY : DESTEC
UNIT : KERN FRONT - LUBE OIL VENT GENERATOR 1
DATE : 02-19-93
REPORT : 027-343

EPA METHOD 4 DATA
@ 60°F

RUN #1

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	65.31	0.04435	0.04393	0.00380	0.0913

ADDITIONAL DATA:
TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1228	1308	20.7	0	0.95	22.68	10

RUN #2

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	51.90	0.03551	0.03505	0.00335	0.0804

ADDITIONAL DATA:
TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1312	1352	20.7	0	1.28	22.51	11

RUN #3

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	50.07	0.03419	0.03368	0.00352	0.0845

ADDITIONAL DATA:

TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1355	1435	20.7	0	1.5	22.55	12

COMPANY : DESTEC
UNIT : KERN FRONT - LUBE OIL VENT GENERATOR 1
DATE : 02-19-93
REPORT : 027-343

NON CONDENSABLE
HYDROCARBON RESULTS

RUN No.: 1					
DSCFM: 10					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	2.59	0.00007	2.59	0.00007
Ethane	(C2)	0.00	0.00000	0.00	0.00000
Propane	(C3)	0.40	0.00003	1.19	0.00003
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.55	0.00006	2.76	0.00007
Hexane	(C6)	2.17	0.00029	13.00	0.00033
<u>Total</u>		<u>5.70</u>	<u>0.00045</u>	<u>19.54</u>	<u>0.00049</u>
Total					
(non methane)		<u>3.12</u>	<u>0.00039</u>	<u>16.95</u>	<u>0.00043</u>
RUN No.: 2					
DSCFM: 11					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	3.54	0.00010	3.54	0.00010
Ethane	(C2)	0.00	0.00000	0.00	0.00000
Propane	(C3)	0.00	0.00000	0.00	0.00000
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.06	0.00001	0.31	0.00001
Hexane	(C6)	1.93	0.00029	11.56	0.00032
<u>Total</u>		<u>5.53</u>	<u>0.00039</u>	<u>15.41</u>	<u>0.00043</u>
Total					
(non methane)		<u>1.99</u>	<u>0.00030</u>	<u>11.87</u>	<u>0.00033</u>
RUN No.: 3					
DSCFM: 12					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	1.75	0.00005	1.75	0.00005
Ethane	(C2)	0.00	0.00000	0.00	0.00000
Propane	(C3)	0.43	0.00004	1.28	0.00004
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.36	0.00005	1.79	0.00005
Hexane	(C6)	6.97	0.00114	41.80	0.00127
<u>Total</u>		<u>9.50</u>	<u>0.00127</u>	<u>46.62</u>	<u>0.00142</u>
Total					
(non methane)		<u>7.75</u>	<u>0.00122</u>	<u>44.87</u>	<u>0.00136</u>

COMPANY : DESTEC
 UNIT : KERN FRONT - LUBE OIL VENT TURBINE #1
 DATE : 02-18-93
 REPORT : 027-343

FIELD DATA @ 60°F

	RUN #:	1	2	3
	TIME:	1554	1642	1728
Vm (dry gas sampled)		23.99	24.02	24.04
Y (meter calib. factor)		0.998954	0.998954	0.998954
P bar (Barometric pressure)		29.14	29.14	29.14
P static (stack pressure, " H2O)		0	0	0
Delta H (differential meter press, " H2O)		0.59	0.59	0.59
Tm (meter temperature, R°)		531.9	532.8	531.3
Vol H2O mls		19.7	17.6	18.7
Vm(std),dscf		22.85	22.84	22.93
Bws-H2O vapor		0.0385	0.0346	0.0365
MF-moisture factor		0.961487	0.9654	0.9635
% CO2		0	0	0
% O2		20.9	20.9	20.9
% N2		79.1	79.1	79.1
Md-MW stk gas,dry		28.84	28.84	28.84
Ms-MW stk gas,wet		28.42	28.47	28.44
T stack, R°		546.6	545	543.6
Stack area,ft2		0.058	0.058	0.058
Vs-fpm, hot wire anemometer		47.8	42	45
Q-acfm		2.75	2.42	2.59
Qstd-dscfm		2.55	2.25	2.42
Sample time		40	40	40

COMPANY : DESTEC
 UNIT : KERN FRONT - LUBE OIL VENT TURBINE 1
 DATE : 02-18-93
 REPORT : 027-343

EPA METHOD 4 DATA
@ 60°F

RUN #1

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	62.10	0.04185	0.04024	0.00092	0.0220

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1554	1634	20.9	0	3.85	22.85	2.55

RUN #2

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	44.69	0.03013	0.02909	0.00058	0.0140

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1642	1722	20.9	0	3.46	22.84	2.25

RUN #3

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	38.95	0.02616	0.02520	0.00054	0.0130

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1728	1808	20.9	0	3.65	22.93	2.42

COMPANY : DESTEC
UNIT : KERN FRONT - LUBE OIL VENT TURBINE 1
DATE : 02-18-93
REPORT : 027-343

NON CONDENSABLE
HYDROCARBON RESULTS

RUN No.: 1					
DSCFM: 2.55					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	67.71	0.00044	67.71	0.00044
Ethane	(C2)	2.60	0.00003	5.21	0.00003
Propane	(C3)	0.31	0.00001	0.94	0.00001
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.21	0.00001	1.06	0.00001
Hexane	(C6)	1.09	0.00004	6.51	0.00004
<u>Total</u>		<u>71.92</u>	<u>0.00052</u>	<u>81.42</u>	<u>0.00053</u>
Total					
(non methane)		4.21	0.00008	13.71	0.00009
RUN No.: 2					
DSCFM: 2.25					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	70.40	0.00040	70.40	0.00040
Ethane	(C2)	2.63	0.00003	5.26	0.00003
Propane	(C3)	0.38	0.00001	1.15	0.00001
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.06	0.00000	0.31	0.00000
Hexane	(C6)	0.99	0.00003	5.92	0.00003
<u>Total</u>		<u>74.46</u>	<u>0.00047</u>	<u>83.04</u>	<u>0.00047</u>
Total					
(non methane)		4.06	0.00007	12.65	0.00007
RUN No.: 3					
DSCFM: 2.42					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	63.06	0.00039	63.06	0.00039
Ethane	(C2)	2.18	0.00003	4.37	0.00003
Propane	(C3)	0.19	0.00000	0.58	0.00000
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.07	0.00000	0.34	0.00000
Hexane	(C6)	0.99	0.00003	5.95	0.00004
<u>Total</u>		<u>66.50</u>	<u>0.00045</u>	<u>74.31</u>	<u>0.00045</u>
Total					
(non methane)		3.44	0.00006	11.25	0.00007

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2 & LUBE OIL VENTS
 DATE : 02-18/19, 25-93
 REPORT : 027-343

SUMMARY OF HYDROCARBONS RESULTS

	gr/scf	ppm	lbs/hr	lbs/day
TURBINE #2 - MAIN STACK				
BLANK CORRECTED				
NON-CONDENSABLE				
RUN 1		5.96	1.70	40.80
RUN 2		4.24	1.21	29.04
RUN 3		4.34	1.24	29.76
AVERAGE		4.85	1.38	33.20
LOV GENERATOR 2				
CONDENSABLE				
RUN 1	0.03311		0.00372	0.0893
RUN 2	0.03141		0.00379	0.0909
RUN 3	0.02792		0.00218	0.0523
AVERAGE	0.03081		0.00323	0.0800
NON-CONDENSABLE				
RUN 1		9.63	0.00032	0.0077
RUN 2		36.77	0.00130	0.0312
RUN 3		18.43	0.00042	0.0101
AVERAGE		21.61	0.00088	0.0183
TOTAL HYDROCARBONS	----	----	0.00391	0.0963
LOV TURBINE 2				
CONDENSABLE				
RUN 1	0.02405		0.00066	0.0158
RUN 2	0.02239		0.00059	0.0141
RUN 3	0.03030		0.00084	0.0202
AVERAGE	0.02558		0.00070	0.0167
NON-CONDENSABLE				
RUN 1		103.86	0.00082	0.0197
RUN 2		100.74	0.00076	0.0182
RUN 3		37.79	0.00030	0.0072
AVERAGE		80.80	0.00063	0.0150
TOTAL HYDROCARBONS	----	----	0.00133	0.0317
TURBINE #2				
TOTAL EMISSIONS			1.39	33.33
MAIN STACK + LOVG + LOVT				

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #2
DATE : 02-25-93
REPORT : 027-343

**HYDROCARBON RESULTS
CORRECTED FOR METHOD BLANK**

RUN No.:		1	average of pitot tube velocity profiles				
DSCFM:		112504	BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	*ND	0.05	79.61	22.66	79.61	22.66
Ethane	(C2)	*ND	0.03	2.98	1.59	5.96	1.70
Propane	(C3)	*ND	0.02	0.00	0.00	0.00	0.00
Butane	(C4)	*ND	0.02	0.00	0.00	0.00	0.00
Pentane	(C5)	*ND	0.02	0.00	0.00	0.00	0.00
Hexane	(C6)		0.10	0.00	0.00	0.00	0.00
Total				82.59	24.25	85.57	24.35
Total (non methane)				2.98	1.59	5.96	1.70

RUN No.:		2	BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	*ND	0.05	16.28	4.63	16.28	4.63
Ethane	(C2)	*ND	0.03	2.12	1.13	4.24	1.21
Propane	(C3)	*ND	0.02	0.00	0.00	0.00	0.00
Butane	(C4)	*ND	0.02	0.00	0.00	0.00	0.00
Pentane	(C5)	*ND	0.02	0.00	0.00	0.00	0.00
Hexane	(C6)		0.10	0.00	0.00	0.00	0.00
Total				18.40	5.76	20.52	5.84
Total (non methane)				2.12	1.13	4.24	1.21

RUN No.:		3	BLANK	ppm - BLANK	lb/hr	ppm (as Methane)	lb/hr
Methane	(C1)	*ND	0.05	16.95	4.82	16.95	4.82
Ethane	(C2)	*ND	0.03	2.17	1.16	4.34	1.24
Propane	(C3)	*ND	0.02	0.00	0.00	0.00	0.00
Butane	(C4)	*ND	0.02	0.00	0.00	0.00	0.00
Pentane	(C5)	*ND	0.02	0.00	0.00	0.00	0.00
Hexane	(C6)		0.10	0.00	0.00	0.00	0.00
Total				19.12	5.98	21.29	6.06
Total (non methane)				2.17	1.16	4.34	1.24

*ND - Non detect in sample blank, used detection limit

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 02-25-93
 REPORT : 027-343

HYDROCARBON RESULTS

RUN No.: 1		DSCFM: 112504 average of pitot tube velocity profiles			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	79.66	22.67	79.66	22.67
Ethane	(C2)	3.01	1.61	6.02	1.71
Propane	(C3)	0.00	0.00	0.00	0.00
Butane	(C4)	0.00	0.00	0.00	0.00
Pentane	(C5)	0.00	0.00	0.00	0.00
Hexane	(C6)	0.00	0.00	0.00	0.00
<u>Total</u>		<u>82.67</u>	<u>24.28</u>	<u>85.68</u>	<u>24.38</u>
Total (non methane)		3.01	1.61	6.02	1.71

RUN No.: 2		DSCFM: 112504 average of pitot tube velocity profiles			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	57.38	16.33	57.38	16.33
Ethane	(C2)	2.15	1.15	4.30	1.22
Propane	(C3)	0.00	0.00	0.00	0.00
Butane	(C4)	0.00	0.00	0.00	0.00
Pentane	(C5)	0.00	0.00	0.00	0.00
Hexane	(C6)	0.00	0.00	0.00	0.00
<u>Total</u>		<u>59.53</u>	<u>17.48</u>	<u>61.68</u>	<u>17.55</u>
Total (non methane)		2.15	1.15	4.30	1.22

RUN No.: 3		DSCFM: 112504 average of pitot tube velocity profiles			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	59.73	17.00	59.73	17.00
Ethane	(C2)	2.20	1.17	4.40	1.25
Propane	(C3)	0.00	0.00	0.00	0.00
Butane	(C4)	0.00	0.00	0.00	0.00
Pentane	(C5)	0.00	0.00	0.00	0.00
Hexane	(C6)	0.00	0.00	0.00	0.00
<u>Total</u>		<u>61.93</u>	<u>18.17</u>	<u>64.13</u>	<u>18.25</u>
Total (non methane)		2.20	1.17	4.40	1.25

COMPANY : DESTEC
 UNIT : KERN FRONT - LUBE OIL VENT GENERATOR 2
 DATE : 02-19-93
 REPORT : 027-343

FIELD DATA @ 60°F

	RUN #:	1	2	3
	TIME:	959	1042	1125
Vm (dry gas sampled)		24.11	24.04	24.07
Y (meter calib. factor)		0.998954	0.998954	0.998954
P bar (Barometric pressure)		29.08	29.08	29.08
P static (stack pressure, " H2O)		0	0	0
Delta H (differential meter press, " H2O)		0.59	0.59	0.59
Tm (meter temperature, R°)		532.2	526.3	527.6
Vol H2O mls		3.4	1.8	5.1
Vm(std),dscf		22.91	23.10	23.07
Bws-H2O vapor		0.0068	0.0036	0.0102
MF-moisture factor		0.993152	0.9964	0.9898
% CO2		0	0	0
% O2		20.8	20.8	20.8
% N2		79.2	79.2	79.2
Md-MW stk gas,dry		28.83	28.83	28.83
Ms-MW stk gas,wet		28.76	28.79	28.72
T stack, R°		557.5	546.5	746.9
Stack area,ft2		0.058	0.058	0.058
Vs-fpm, hot wire anemometer		256.3	270	224
Q-acfm		15	16	13
Qstd-dscfm		13	14	9
Sample time		40	40	40

COMPANY : DESTEC
 UNIT : KERN FRONT - LUBE OIL VENT GENERATOR 2
 DATE : 02-19-93
 REPORT : 027-343

EPA METHOD 4 DATA
 @ 60°F

RUN #1

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	49.60	0.03334	0.03311	0.00372	0.0893

ADDITIONAL DATA:
 TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
959	1039	20.8	0	0.68	22.91	13

RUN #2

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	47.29	0.03153	0.03141	0.00379	0.0909

ADDITIONAL DATA:
 TIME

start	finish	%O2	%CO2	%H2O	Vm(std)	DSCFM
1042	1122	20.8	0	0.36	23.1	14

RUN #3

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	42.25	0.02820	0.02792	0.00218	0.0523

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1125	1205	20.8	0	1.02	23.07	9

COMPANY : DESTEC
UNIT : KERN FRONT - LUBE OIL VENT GENERATOR 2
DATE : 02-19-93
REPORT : 027-343

NON CONDENSABLE
HYDROCARBON RESULTS

RUN No.: 1		DSCFM: 13			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	5.57	0.00018	5.57	0.00018
Ethane	(C2)	0.00	0.00000	0.00	0.00000
Propane	(C3)	0.00	0.00000	0.00	0.00000
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.00	0.00000	0.00	0.00000
Hexane	(C6)	1.60	0.00028	9.63	0.00032
<u>Total</u>		<u>7.17</u>	<u>0.00047</u>	<u>15.19</u>	<u>0.00050</u>
Total (non methane)		1.60	0.00028	9.63	0.00032

RUN No.: 2		DSCFM: 14			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	9.77	0.00035	9.77	0.00035
Ethane	(C2)	0.34	0.00002	0.68	0.00002
Propane	(C3)	0.00	0.00000	0.00	0.00000
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.00	0.00000	0.00	0.00000
Hexane	(C6)	6.02	0.00115	36.09	0.00128
<u>Total</u>		<u>16.12</u>	<u>0.00151</u>	<u>46.54</u>	<u>0.00165</u>
Total (non methane)		6.36	0.00117	36.77	0.00130

RUN No.: 3		DSCFM: 9			
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	14.14	0.00032	14.14	0.00032
Ethane	(C2)	0.60	0.00003	1.20	0.00003
Propane	(C3)	0.00	0.00000	0.00	0.00000
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.28	0.00003	1.39	0.00003
Hexane	(C6)	2.64	0.00032	15.84	0.00036
<u>Total</u>		<u>17.66</u>	<u>0.00070</u>	<u>32.57</u>	<u>0.00074</u>
Total (non methane)		3.52	0.00038	18.43	0.00042

COMPANY : DESTEC
 UNIT : KERN FRONT - LUBE OIL VENT TURBINE 2
 DATE : 02-18-93
 REPORT : 027-343

FIELD DATA @ 60°F

	RUN #:	1	2	3
	TIME:	1022	1112	1207
Vm (dry gas sampled)		24.03	24.04	24
Y (meter calib. factor)		0.998954	0.998954	0.998954
P bar (Barometric pressure)		29.14	29.14	29.14
P static (stack pressure, " H2O)		0	0	0
Delta H (differential meter press, " H2O)		0.59	0.59	0.58
Tm (meter temperature, R°)		522.6	523.3	525.9
Vol H2O mls		13.2	12.5	14.8
Vm(std), dscf		23.3	23.28	23.12
Bws-H2O vapor		0.0256	0.0243	0.0289
MF-moisture factor		0.974354	0.9757	0.9711
% CO2		0	0	0
% O2		20.9	20.9	20.9
% N2		79.1	79.1	79.1
Md-MW stk gas, dry		28.84	28.84	28.84
Ms-MW stk gas, wet		28.56	28.58	28.53
T stack, R°		535.4	532.4	537.4
Stack area, ft2		0.058	0.058	0.058
Vs-fpm, hot wire anemometer		57.1	54.3	58.1
Q-acfm		3.29	3.13	3.35
Qstd-dscfm		3.11	2.98	3.15
Sample time		40	40	40

COMPANY : DESTEC
 UNIT : KERN FRONT - LUBE OIL VENT TURBINE 2
 DATE : 02-18-93
 REPORT : 027-343

EPA METHOD 4 DATA
 @ 60°F

RUN #1

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	37.34	0.02468	0.02405	0.00066	0.0158

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1022	1102	20.9	0	2.56	23.3	3.11

RUN #2

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	34.69	0.02295	0.02239	0.00059	0.0141

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1112	1152	20.9	0	2.43	23.28	2.98

RUN #3

CONDENSABLE HYDROCARBONS:	net mg	gr/dscf	gr/scf	lbs/hr	lbs/day
RESULTS:	46.84	0.03120	0.03030	0.00084	0.0202

ADDITIONAL DATA:

TIME		%O2	%CO2	%H2O	Vm(std)	DSCFM
start	finish					
1207	1247	20.9	0	2.89	23.12	3.15

COMPANY : DESTEC
UNIT : KERN FRONT - LUBE OIL VENT TURBINE 2
DATE : 02-18-93
REPORT : 027-343

NON CONDENSABLE
HYDROCARBON RESULTS

RUN No.: 1					
DSCFM: 3.11					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	307.38	0.00242	307.38	0.00242
Ethane	(C2)	11.47	0.00017	22.95	0.00018
Propane	(C3)	1.92	0.00004	5.75	0.00005
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.00	0.00000	0.00	0.00000
Hexane	(C6)	12.53	0.00053	75.16	0.00059
<u>Total</u>		<u>333.30</u>	<u>0.00316</u>	<u>411.24</u>	<u>0.00324</u>
Total					
(non methane)		<u>25.92</u>	<u>0.00074</u>	<u>103.86</u>	<u>0.00082</u>
RUN No.: 2					
DSCFM: 2.98					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	306.58	0.00231	306.58	0.00231
Ethane	(C2)	11.40	0.00016	22.80	0.00017
Propane	(C3)	1.75	0.00004	5.25	0.00004
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.00	0.00000	0.00	0.00000
Hexane	(C6)	12.12	0.00049	72.69	0.00055
<u>Total</u>		<u>331.85</u>	<u>0.00300</u>	<u>407.33</u>	<u>0.00307</u>
Total					
(non methane)		<u>25.27</u>	<u>0.00069</u>	<u>100.74</u>	<u>0.00076</u>
RUN No.: 3					
DSCFM: 3.15					
		ppm	lb/hr	ppm (as Methane)	lb/hr (as Methane)
Methane	(C1)	348.73	0.00278	348.73	0.00278
Ethane	(C2)	13.47	0.00020	26.95	0.00021
Propane	(C3)	2.17	0.00005	6.50	0.00005
Butane	(C4)	0.00	0.00000	0.00	0.00000
Pentane	(C5)	0.24	0.00001	1.20	0.00001
Hexane	(C6)	0.52	0.00002	3.15	0.00003
<u>Total</u>		<u>365.13</u>	<u>0.00306</u>	<u>386.52</u>	<u>0.00308</u>
Total					
(non methane)		<u>16.40</u>	<u>0.00028</u>	<u>37.79</u>	<u>0.00030</u>

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1 & #2
 DATE : 02-25-93
 REPORT : 027-343

HYDROCARBON RESULTS @ 60°F

		DETECTION LIMITS	
		ppm	ppm (as Methane)
Methane	(C1)	0.05	0.05
Ethane	(C2)	0.03	0.06
Propane	(C3)	0.02	0.06
Butane	(C4)	0.02	0.08
Pentane	(C5)	0.02	0.10
Hexane	(C6)	0.02	0.12
Total		0.16	0.47
Total (non methane)		0.11	0.42

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

SUFUR EMISSION RESULTS

DATE	TIME	TS, ppm	AVG LBS/HR GAS FUEL FLOW	SP VOL CF/LB	AVERAGE SCFH	FUEL SCFM	SULFUR	
							LBS/HR	LBS/DAY
2/23/93	1430-1645	2.0	10078.6	22.07	222435	3707	0.03751	0.900
2/24/93	915-1345	2.0	10296.1	22.07	227235	3787	0.03832	0.920
AVERAGE							0.03792	0.910

EQUATION:

SCFM = SCFH (1/60)

SULFUR LBS/HR = TS ppm * 32 * SCFM * 1.581 * 10⁻⁷

MW SULFUR = 32

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 2-25/26-93
 REPORT : 027-343

SUFUR EMISSION RESULTS

DATE	TIME	TS, ppm	AVG LBS/HR GAS FUEL FLOW	SP VOL CF/LB	AVERAGE SCFH	FUEL SCFM	SULFUR	
							LBS/HR	LBS/DAY
2/25/93	930-1600	1.9	10301.2	22.06	227244	3787	0.03641	0.874

EQUATION:

$SCFM = SCFH (1/60)$

$SULFUR\ LBS/HR = TS\ ppm * 32 * SCFM * 1.581 * 10^{-7}$

$MW\ SULFUR = 32$



Environmental Analytical Service, Inc.

March 9, 1993

Reference Number: 30728

Terry Rowles
Petro Chem Environmental Services, Inc.
3207 Antonino Avenue
Bakersfield, CA 93308

Dear Terry,

Enclosed is the analytical report for the samples which were received by Environmental Analytical Service on January 23, 1993 for your project location Kern Front #1 and #2.

If you have any questions on the report or the analytical data please contact myself or Vivian Longacre at (805) 541-3666.

Sincerely,

Steven D. Hoyt, Ph.D.
Laboratory Director

SDH/jd
enclosures

ANALYSIS REPORT SHEET

Sulfur Compounds by GC/FPD

Client: Petro Chem Lab #: 30730
 Site: Kern Front Fuel Gas #1 Date Sampled: 2-22-93
 Can #: Tedlar Date Analyzed: 2-23-93

Compound	MDL ug/m3	Concentration ug/m3	Concentration ppbv
Hydrogen Sulfide	110	390	280
Carbonyl Sulfide	110	1600	660
Methyl Mercaptan	110	450	230
Dimethyl Sulfide	110	not detected	not detected
Carbon Disulfide	55	not detected	not detected
Total Sulfur, H2S *			2000

* Includes above listed compounds plus all quantifiable peaks.

2000
~~1000,000,000~~
 2 ppm.

ANALYSIS REPORT SHEET

Sulfur Compounds by GC/FPD

Client: Petro Chem	Lab #: 30731
Site: Kern Front Fuel Gas #2	Date Sampled: 2-22-93
Can #: Tedlar	Date Analyzed: 2-23-93

Compound	MDL ug/m3	Concentration ug/m3	Concentration ppbv
Hydrogen Sulfide	110	300	210
Carbonyl Sulfide	110	1600	650
Methyl Mercaptan	110	not detected	not detected
Dimethyl Sulfide	110	not detected	not detected
Carbon Disulfide	55	not detected	not detected
Total Sulfur, H2S *			1900


* Includes above listed compounds plus all quantifiable peaks.

*IDENTIFIER STD 12 13 14 0.3ML

Sulfur Gas Standard

*INVALID SYSTEM COMMAND

* RUN # 258 FEB 23, 1993 23:47:49
START



STOP

Closing signal file M:SIGNAL .BNC

RUN# 258 FEB 23, 1993 23:47:49

IDENTIFIER : STD 12, 13,
SIGNAL FILE: M:SIGNAL.BNC
AREA%

RT	AREA	TYPE	WIDTH	AREA%
1.716	707352	SPH	.018	8.75139
1.951	1055068	SHB	.029	13.05335
4.195	538907	BB	.030	6.66739
6.968	509136	PB	.032	6.29906
7.252	5272272	SBB	.036	65.22883

TOTAL AREA=8082736
MUL FACTOR=1.0000E+00

INVALID SYSTEM COMMAND

* RUN # 248 FEB 23, 1993 18:40:25
START

BLANK

1.867

TIMETABLE STOP

Closing signal file M:SIGNAL .BNC

RUN# 248 FEB 23, 1993 18:40:25

IDENTIFIER : : LANK ZERO

SIGNAL FILE: M:SIGNAL.BNC

AREA%

RT	AREA	TYPE	WIDTH	AREA%
1.867	2297	I P8	.182	100.00000

TOTAL AREA= 2297


MUL FACTOR=1.0000E+00

GC/FPD
Capillary Column

Sample 30728

*IDENTIFIER: 307/28 1.36ML

* RUN # 250 FEB 23, 1993 19:49:40
START



STOP

Closing signal file M:SIGNAL .BNC

RUN# 250 FEB 23, 1993 19:49:40

IDENTIFIER : : 307728 1.3


SIGNAL FILE: M:SIGNAL.BNC

AREA%

RT AREA TYPE WIDTH AREA%

Sample 30730

RUN # 253 FEB 23, 1993 21:10:05
START



END OF SIGNAL

Closing signal file M:SIGNAL .BNA

RUN# 253 FEB 23, 1993 21:10:05

IDENTIFIER : : 330730 1.3
SIGNAL FILE: M:SIGNAL.BNA
AREA%

RT	AREA	TYPE	WIDTH	AREA%
.587	610	PV	.027	.11980
1.455	274606	PB	.215	53.92933
1.620	6521	PV	.070	1.28065
1.784	12425	VV	.085	2.44012
1.909	100523	VV	.029	19.74152
2.835	9526	VV	.121	1.87079
2.362	1160	VV	.047	.22781
2.663	1135	VV	.059	.22290
2.865	12465	PV	.046	2.44798
3.331	1359	PV	.083	.26689
3.474	819	VP	.032	1.60004

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 02-23/24-93
 REPORT : 027-343

ANALYZER NOx

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	1.88	2.05	-0.17
2	2.01	1.98	0.03
3	2.08	2.05	0.03
4	2.23	2.07	0.16
5	2.37	2.29	0.08
6	2.48	2.44	0.04
7	2.25	2.12	0.13
8	1.89	2.05	-0.16
9	1.88	2.04	-0.16
AVERAGE	2.119	2.121	-0.002

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
$t_{.975}$	=	2.306
STANDARD DEVIATION	=	0.13
CONFIDENCE COEFFICIENT	=	0.10
REF METHOD	=	2.1
RELATIVE ACCURACY	=	4.77

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 02-23/24-93
 REPORT : 027-343

ANALYZER CO

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	36.7	36.42	0.28
2	37.3	37.65	-0.35
3	36.3	36.25	0.05
4	35.4	35.67	-0.27
5	32.6	32.81	-0.21
6	31.5	29.47	2.03
7	36.4	33.98	2.42
8	38.1	35.53	2.57
9	36.5	33.40	3.10
AVERAGE	35.6	34.58	1.07

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t _{.975}	=	2.306
STANDARD DEVIATION	=	1.42
CONFIDENCE COEFFICIENT	=	1.09
REF METHOD	=	35.6
RELATIVE ACCURACY	=	6.07

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 02-23/24-93
 REPORT : 027-343

ANALYZER O2

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	13.85	14.13	-0.28
2	14.01	14.12	-0.11
3	14.03	14.12	-0.09
4	14.04	14.12	-0.08
5	14.06	14.12	-0.06
6	14.04	14.12	-0.08
7	13.95	14.12	-0.17
8	13.96	14.12	-0.16
9	13.99	14.12	-0.13
AVERAGE	13.99	14.12	-0.13

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t .975	=	2.306
STANDARD DEVIATION	=	0.07
CONFIDENCE COEFFICIENT	=	0.05
REF METHOD	=	13.99
RELATIVE ACCURACY	=	1.29

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 02-25/26-93
 REPORT : 027-343

ANALYZER NOx

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	2.57	2.71	-0.14
2	2.84	2.66	0.18
3	3.22	2.80	0.42
4	2.81	2.73	0.08
5	2.85	2.80	0.05
6	2.52	2.80	-0.28
7	2.53	2.80	-0.27
8	3.37	2.80	0.57
9	2.66	2.80	-0.14
AVERAGE	2.82	2.77	0.05

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
$t_{.975}$	=	2.306
STANDARD DEVIATION	=	0.30
CONFIDENCE COEFFICIENT	=	0.23
REF METHOD	=	2.82
RELATIVE ACCURACY	=	9.97

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 02-25/26-93
 REPORT : 027-343

ANALYZER CO

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE
1	45.50	45.32	0.18
2	43.10	43.24	-0.14
3	41.40	40.45	0.95
4	40.90	41.29	-0.39
5	39.90	40.05	-0.15
6	39.70	39.43	0.27
7	38.60	38.50	0.10
8	39.00	39.27	-0.27
9	39.60	39.38	0.22
AVERAGE	40.86	40.77	0.09

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t _{.975}	=	2.306
STANDARD DEVIATION	=	0.40
CONFIDENCE COEFFICIENT	=	0.31
REF METHOD	=	40.86
RELATIVE ACCURACY	=	0.96

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 02-25/26-93
 REPORT : 027-343

ANALYZER O2

RELATIVE ACCURACY RESULTS

PPMvd

RUN #	REFERENCE METHOD	CEM DATA	DIFFERENCE	
1	14.04	14.23	-0.19	
2	14.03	14.22	-0.19	
3	14.11	14.23	-0.12	
4	14.12	14.22	-0.10	
5	14.08	14.22	-0.14	
6	14.13	14.23	-0.10	
7	14.09	14.22	-0.13	
8	14.09	14.23	-0.14	
9	14.19	14.22	-0.03	
AVERAGE		14.10	14.22	-0.13

RELATIVE ACCURACY RELATED TO THE REFERENCE METHOD		
t _{.975}	=	2.306
STANDARD DEVIATION	=	0.05
CONFIDENCE COEFFICIENT	=	0.04
REF METHOD	=	14.10
RELATIVE ACCURACY	=	1.17

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1 & #2
 DATE : 02-23/26-93
 REPORT : 027-343

CEM DATA SUMMARY

RUN #	TURBINE #1			TURBINE #2		
	%O2	NOx ppm	CO ppm	%O2	NOx ppm	CO ppm
1	14.13	2.05	36.42	14.23	2.71	45.32
2	14.12	1.98	37.65	14.22	2.66	43.24
3	14.12	2.05	36.25	14.23	2.80	40.45
4	14.12	2.07	35.67	14.22	2.73	41.29
5	14.12	2.29	32.81	14.22	2.80	40.05
6	14.12	2.44	29.47	14.23	2.80	39.43
7	14.12	2.12	33.98	14.22	2.80	38.50
8	14.12	2.05	35.53	14.23	2.80	39.27
9	14.12	2.04	33.40	14.22	2.80	39.38
	14.12	2.12	34.58	14.22	2.77	40.77

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 02-23/24-93
 REPORT : 027-343

PCES REFERENCE METHOD SUMMARY

RUN #	TIME	%O2	NOx			CO		
			ppm	ppm @ 15% O2	lbs/hr	ppm	ppm @ 15% O2	lbs/hr
1	1430-1500	13.85	1.88	1.58	1.54	36.7	30.7	18.3
2	1530-1600	14.01	2.01	1.73	1.65	37.3	32.0	18.6
3	1615-1645	14.03	2.08	1.79	1.70	36.3	31.2	18.1
4	915-945	14.04	2.23	1.92	1.82	35.4	30.5	17.6
5	1015-1045	14.06	2.37	2.05	1.94	32.6	28.1	16.2
6	1100-1130	14.04	2.48	2.13	2.03	31.5	27.1	15.7
7	1145-1215	13.95	2.25	1.91	1.84	36.4	30.9	18.1
8	1230-1300	13.96	1.89	1.61	1.55	38.1	32.3	19.0
9	1315-1345	13.99	1.88	1.61	1.54	36.5	31.2	18.2
AVERAGE		13.99	2.12	1.81	1.73	35.6	30.4	17.8

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

RUN #1
 NOx/CO/O2 DATA

TIME INTERVAL		Stack Gas Measurement Data CONCENTRATIONS			% FULL SCALE		
BEGIN	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
02:30 PM	02:40 PM	13.90	1.88	36.7	65.7	13.8	46.6
02:40 PM	02:50 PM	13.85	1.90	36.8	65.7	13.9	46.7
02:50 PM	03:00 PM	13.79	1.87	36.7	65.7	13.9	46.7
Averages:		13.85	1.88	36.7	65.7	13.9	46.7

Calibration Data			
	O2	NOx	CO
INITIAL zero	9.8	10	9.8
INITIAL span	70	45.2	91.4
FINAL zero	10.05	10	9.8
FINAL span	70.4	45.4	91.5
ZERO DRIFT %/ppm	0.06	0.00	0.00
CALIB. DRIFT %/ppm	0.10	0.10	0.10
ZERO DRIFT %fs	0.25	0.00	0.00
CALIB.DRIFT %fs	0.40	0.20	0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.85	1.88	4.78	1.58	1.54

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.85	36.7	93.2	30.7	18.3

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

RUN #2
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
03:30 PM	-	03:40 PM	14.05	1.92	37.6	66.1	13.8	47.6
03:40 PM	-	03:50 PM	13.99	2.01	37.8	65.7	13.9	47.8
03:50 PM	-	04:00 PM	14.00	2.11	36.5	65.6	14.0	46.5
Averages:			14.01	2.01	37.3	65.8	13.9	47.3

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	9.9
INITIAL span	70	45.4	91.5
FINAL zero	10	10	9.9
FINAL span	69.5	45.1	91.5
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	-0.13	-0.15	0.00
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	-0.50	-0.30	0.00
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.01	2.01	5.24	1.73	1.65

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.01	37.3	97.0	32.0	18.6

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

RUN #3
 NOx/CO/O2 DATA

TIME INTERVAL			Stack Gas Measurement Data CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
04:15 PM	-	04:25 PM	14.06	2.01	36.7	66.3	14.0	46.7
04:25 PM	-	04:35 PM	14.00	2.06	36.8	66.2	14.0	46.7
04:35 PM	-	04:45 PM	14.02	2.16	35.5	66.4	14.1	45.4
Averages:			14.03	2.08	36.3	66.3	14.0	46.3

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.4	91.4
FINAL zero	10	10.1	9.8
FINAL span	70.4	45	91.5
ZERO DRIFT %/ppm	0.00	0.05	-0.20
CALIB. DRIFT %/ppm	0.10	-0.20	0.10
ZERO DRIFT %fs	0.00	0.10	-0.20
CALIB. DRIFT %fs	0.40	-0.40	0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.03	2.08	5.42	1.79	1.70

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.03	36.3	94.6	31.2	18.1

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #1
DATE : 2-23/24-93
REPORT : 027-343

RUN #4
NOx/CO/O2 DATA

TIME INTERVAL		Stack Gas Measurement Data CONCENTRATIONS			% FULL SCALE		
BEGIN	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
09:15 AM	09:25 AM	14.03	2.18	35.1	66.1	14.3	45.0
09:25 AM	09:35 AM	14.05	2.21	35.7	66.2	14.2	45.4
09:35 AM	09:45 AM	14.05	2.30	35.5	66.2	14.2	45.1
Averages:		14.04	2.23	35.4	66.2	14.2	45.2

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.4	91.4
FINAL zero	9.9	10	9.8
FINAL span	70.1	44.9	91.1
ZERO DRIFT %/ppm	-0.02	0.00	-0.20
CALIB. DRIFT %/ppm	0.02	-0.25	-0.30
ZERO DRIFT %fs	-0.10	0.00	-0.20
CALIB.DRIFT %fs	0.10	-0.50	-0.30
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.04	2.23	5.82	1.92	1.82

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.04	35.4	92.4	30.5	17.6

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #1
DATE : 2-23/24-93
REPORT : 027-343

RUN #5
NOx/CO/O2 DATA

Stack Gas Measurement Data			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
10:15 AM	-	10:25 AM	14.05	2.30	33.6	66.2	14.6	43.7
10:25 AM	-	10:35 AM	14.09	2.39	32.0	66.3	14.7	42.1
10:35 AM	-	10:45 AM	14.05	2.42	32.2	66.1	14.7	42.3
Averages:			14.06	2.37	32.6	66.2	14.7	42.7

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.4	91.5
FINAL zero	9.9	10	10
FINAL span	70	45.2	91.6
ZERO DRIFT %/ppm	-0.02	0.00	0.00
CALIB. DRIFT %/ppm	0.00	-0.10	0.10
ZERO DRIFT %fs	-0.10	0.00	0.00
CALIB.DRIFT %fs	0.00	-0.20	0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.06	2.37	6.21	2.05	1.94

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.06	32.6	85.4	28.1	16.2

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

RUN #6
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
11:00 AM	-	11:10 AM	14.03	2.41	31.8	66.1	14.8	41.8
11:10 AM	-	11:20 AM	14.01	2.51	31.4	66.0	14.9	41.3
11:20 AM	-	11:30 AM	14.07	2.51	31.3	66.2	14.8	41.2
Averages:			14.04	2.48	31.5	66.1	14.8	41.4

Calibration Data			
	O2	NOx	CO
INITIAL zero	9.9	10	10
INITIAL span	70	45.4	91.4
FINAL zero	10	10.1	9.8
FINAL span	69.8	45	91.5
ZERO DRIFT %/ppm	0.02	0.05	-0.20
CALIB. DRIFT %/ppm	-0.05	-0.20	0.10
ZERO DRIFT %fs	0.10	0.10	-0.20
CALIB. DRIFT %fs	-0.20	-0.40	0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.04	2.48	6.47	2.13	2.03

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.04	31.5	82.1	27.1	15.7

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

RUN #7
 NOx/CO/O2 DATA

TIME INTERVAL		Stack Gas Measurement Data CONCENTRATIONS			% FULL SCALE		
BEGIN	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
11:45 AM	11:55 AM	13.95	2.31	33.3	65.8	14.5	43.3
11:55 AM	12:05 PM	13.95	2.16	38.1	65.9	13.9	48.1
12:05 PM	12:15 PM	13.96	2.26	37.9	66.0	13.8	48.0
Averages:		13.95	2.25	36.4	65.9	14.1	46.5

Calibration Data			
	O2	NOx	CO
INITIAL zero	9.8	10	10
INITIAL span	70	45.4	91.4
FINAL zero	9.9	10	10
FINAL span	70.1	44.5	91.5
ZERO DRIFT %/ppm	0.02	0.00	0.00
CALIB. DRIFT %/ppm	0.02	-0.45	0.10
ZERO DRIFT %fs	0.10	0.00	0.00
CALIB.DRIFT %fs	0.10	-0.90	0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.95	2.25	5.79	1.91	1.84

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.95	36.4	93.8	30.9	18.1

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

RUN #8
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
12:30 PM	-	12:40 PM	13.94	1.96	38.2	65.7	14.0	48.2
12:40 PM	-	12:50 PM	13.95	1.89	38.0	65.6	14.0	48.1
12:50 PM	-	01:00 PM	13.99	1.82	38.1	65.6	14.0	48.3
Averages:			13.96	1.89	38.1	65.6	14.0	48.2

Calibration Data			
	O2	NOx	CO
INITIAL zero	9.9	10	10
INITIAL span	70	45.4	91.4
FINAL zero	9.7	10	10
FINAL span	69.8	45.8	91.7
ZERO DRIFT %/ppm	-0.05	0.00	0.00
CALIB. DRIFT %/ppm	-0.05	0.20	0.30
ZERO DRIFT %fs	-0.20	0.00	0.00
CALIB.DRIFT %fs	-0.20	0.40	0.30
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.96	1.89	4.88	1.61	1.55

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.96	38.1	98.1	32.3	19.0

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 2-23/24-93
 REPORT : 027-343

RUN #9
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
01:15 PM	-	01:25 PM	13.97	1.95	37.1	65.8	14.0	47.1
01:25 PM	-	01:35 PM	14.00	1.87	36.4	65.8	14.0	46.3
01:35 PM	-	01:45 PM	14.01	1.83	36.1	65.7	14.1	46.0
Averages:			13.99	1.88	36.5	65.8	14.0	46.5

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.4	91.4
FINAL zero	10	10.1	9.8
FINAL span	69.6	45.8	91.5
ZERO DRIFT %/ppm	0.00	0.05	-0.20
CALIB. DRIFT %/ppm	-0.10	0.20	0.10
ZERO DRIFT %fs	0.00	0.10	-0.20
CALIB. DRIFT %fs	-0.40	0.40	0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 112504 (AVERAGE OF PITOT TUBE TRAVERSE)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	13.99	1.88	4.88	1.61	1.54

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	13.99	36.5	94.6	31.2	18.2

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 02-25/26-93
 REPORT : 027-343

PCES REFERENCE METHOD SUMMARY

RUN #	TIME	%O2	NOx			CO		
			ppm	ppm @ 15% O2	lbs/hr	ppm	ppm @ 15% O2	lbs/hr
1	930-1000	14.04	2.57	2.21	2.06	45.5	39.1	22.1
2	1015-1045	14.03	2.84	2.44	2.27	43.1	37.1	21.0
3	1100-1130	14.11	3.22	2.79	2.57	41.4	35.9	20.1
4	1145-1215	14.12	2.81	2.45	2.25	40.9	35.6	19.9
5	1230-1300	14.08	2.85	2.47	2.28	39.9	34.5	19.4
6	1315-1345	14.13	2.52	2.20	2.02	39.7	34.6	19.3
7	1400-1430	14.09	2.53	2.19	2.02	38.6	33.5	18.8
8	1445-1515	14.09	3.37	2.92	2.70	39.0	33.8	19.0
9	1530-1600	14.19	2.66	2.34	2.13	39.6	34.8	19.3
AVERAGE		14.10	2.82	2.45	2.26	40.9	35.4	19.9

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 2-25/26-93
 REPORT : 027-343

RUN #1
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
09:30 AM	-	09:40 AM	14.03	2.60	45.5	66.1	15.3	55.6
09:40 AM	-	09:50 AM	14.05	2.59	45.0	66.1	15.4	54.8
09:50 AM	-	10:00 AM	14.04	2.52	45.9	66.0	15.4	55.5
Averages:			14.04	2.57	45.5	66.1	15.4	55.3

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.4	91.8
FINAL zero	9.9	10	9.8
FINAL span	69.9	45.8	91.2
ZERO DRIFT %/ppm	-0.02	0.00	-0.20
CALIB. DRIFT %/ppm	-0.02	0.20	-0.60
ZERO DRIFT %fs	-0.10	0.00	-0.20
CALIB.DRIFT %fs	-0.10	0.40	-0.60
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.04	2.57	6.71	2.21	2.06

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.04	45.5	119	39.1	22.1

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #2
DATE : 2-25/26-93
REPORT : 027-343

RUN #2
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
10:15 AM	-	10:25 AM	14.03	2.69	43.9	66.1	15.3	53.8
10:25 AM	-	10:35 AM	14.05	2.86	42.6	66.1	15.4	52.3
10:35 AM	-	10:45 AM	14.02	2.98	42.9	65.9	15.4	52.4
Averages:			14.03	2.84	43.1	66.0	15.4	52.8

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.4	91.5
FINAL zero	10	10	9.9
FINAL span	69.8	44.7	90.9
ZERO DRIFT %/ppm	0.00	0.00	-0.10
CALIB. DRIFT %/ppm	-0.05	-0.35	-0.60
ZERO DRIFT %fs	0.00	0.00	-0.10
CALIB.DRIFT %fs	-0.20	-0.70	-0.60
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.03	2.84	7.41	2.44	2.27

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.03	43.1	112	37.1	21.0

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 2-25/26-93
 REPORT : 027-343

RUN #3
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
11:00 AM	-	11:10 AM	14.08	2.92	41.9	66.3	15.6	51.8
11:10 AM	-	11:20 AM	14.11	3.23	41.1	66.4	15.7	50.8
11:20 AM	-	11:30 AM	14.12	3.50	41.1	66.4	15.7	50.6
Averages:			14.11	3.22	41.4	66.4	15.7	51.1

Calibration Data			
	O2	NOx	CO
INITIAL zero	9.9	10	10
INITIAL span	70	45.4	91.4
FINAL zero	9.8	10.1	9.9
FINAL span	70	43.7	90.9
ZERO DRIFT %/ppm	-0.02	0.05	-0.10
CALIB. DRIFT %/ppm	0.00	-0.85	-0.50
ZERO DRIFT %fs	-0.10	0.10	-0.10
CALIB.DRIFT %fs	0.00	-1.70	-0.50
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.11	3.22	8.48	2.79	2.57

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.11	41.4	109	35.9	20.1

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #2
DATE : 2-25/26-93
REPORT : 027-343

RUN #4
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
11:45 AM	-	11:55 AM	14.10	2.83	40.6	66.4	15.7	50.6
11:55 AM	-	12:05 PM	14.14	2.76	41.1	66.5	15.6	51.0
12:05 PM	-	12:15 PM	14.12	2.84	40.9	66.4	15.8	50.7
Averages:			14.12	2.81	40.9	66.4	15.7	50.8

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.4	91.4
FINAL zero	9.9	10.2	9.9
FINAL span	70	45.3	91.3
ZERO DRIFT %/ppm	-0.02	0.10	-0.10
CALIB. DRIFT %/ppm	0.00	-0.05	-0.10
ZERO DRIFT %fs	-0.10	0.20	-0.10
CALIB.DRIFT %fs	0.00	-0.10	-0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.12	2.81	7.42	2.45	2.25

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.12	40.9	108	35.6	19.9

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #2
DATE : 2-25/26-93
REPORT : 027-343

RUN #5
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
12:30 PM	-	12:40 PM	14.09	2.84	39.8	66.4	15.7	49.8
12:40 PM	-	12:50 PM	14.09	2.85	40.0	66.5	15.7	50.0
12:50 PM	-	01:00 PM	14.06	2.87	40.0	66.5	15.7	50.0
Averages:			14.08	2.85	39.9	66.5	15.7	49.9

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.5	91.5
FINAL zero	10.2	10.1	10
FINAL span	70.1	45.3	91.4
ZERO DRIFT %/ppm	0.05	0.05	0.00
CALIB. DRIFT %/ppm	0.02	-0.10	-0.10
ZERO DRIFT %fs	0.20	0.10	0.00
CALIB.DRIFT %fs	0.10	-0.20	-0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.08	2.85	7.49	2.47	2.28

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.08	39.9	104.8	34.5	19.4

COMPANY : DESTEC
UNIT : KERN FRONT - TURBINE #2
DATE : 2-25/26-93
REPORT : 027-343

RUN #6
NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
01:15 PM	-	01:25 PM	14.12	2.70	39.8	66.5	15.6	49.8
01:25 PM	-	01:35 PM	14.14	2.44	39.9	66.6	15.4	49.9
01:35 PM	-	01:45 PM	14.13	2.42	39.4	66.6	15.7	49.4
Averages:			14.13	2.52	39.7	66.6	15.6	49.7

Calibration Data			
	O2	NOx	CO
INITIAL zero	9.9	10	10
INITIAL span	70	45.4	91.5
FINAL zero	10	10	10
FINAL span	70	46.4	91.4
ZERO DRIFT %/ppm	0.02	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.50	-0.10
ZERO DRIFT %fs	0.10	0.00	0.00
CALIB.DRIFT %fs	0.00	1.00	-0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.13	2.52	6.66	2.20	2.02

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.13	39.7	105	34.6	19.3

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 2-25/26-93
 REPORT : 027-343

RUN #7
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
02:00 PM	-	02:10 PM	14.10	2.71	38.2	66.4	15.7	48.2
02:10 PM	-	02:20 PM	14.10	2.58	38.3	66.4	15.9	48.2
02:20 PM	-	02:30 PM	14.08	2.30	39.4	66.3	15.8	49.3
Averages:			14.09	2.53	38.6	66.4	15.8	48.6

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.5	91.5
FINAL zero	10	10	10
FINAL span	70	46.9	91.3
ZERO DRIFT %/ppm	0.00	0.00	0.00
CALIB. DRIFT %/ppm	0.00	0.69	-0.20
ZERO DRIFT %fs	0.00	0.00	0.00
CALIB.DRIFT %fs	0.00	1.40	-0.20
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.09	2.53	6.65	2.19	2.02

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.09	38.6	102	33.5	18.8

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 2-25/26-93
 REPORT : 027-343

RUN #8
 NOx/CO/O2 DATA

Stack Gas Measurement Data								
TIME INTERVAL			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
02:45 PM	-	02:55 PM	14.12	2.88	39.6	66.7	15.2	49.6
02:55 PM	-	03:05 PM	14.09	3.36	38.8	67.0	15.0	48.9
03:05 PM	-	03:15 PM	14.06	3.89	38.7	67.3	14.9	48.9
Averages:			14.09	3.37	39.0	67.0	15.0	49.1

Calibration Data			
	O2	NOx	CO
INITIAL zero	9.8	10	10
INITIAL span	70	45.4	91.4
FINAL zero	10	9.5	10
FINAL span	71.1	42.4	91.6
ZERO DRIFT %/ppm	0.05	-0.25	0.00
CALIB. DRIFT %/ppm	0.27	-1.49	0.20
ZERO DRIFT %fs	0.20	-0.50	0.00
CALIB.DRIFT %fs	1.10	-3.00	0.20
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)					
	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.09	3.37	8.87	2.92	2.70

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.09	39.0	103	33.8	19.0

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 2-25/26-93
 REPORT : 027-343

RUN #9
 NOx/CO/O2 DATA

Stack Gas Measurement Data			CONCENTRATIONS			% FULL SCALE		
BEGIN	-	END	O2:%	NOx:ppm	CO:ppm	O2%fs	NOx%fs	CO%fs
03:30 PM	-	03:40 PM	14.12	2.79	39.1	66.4	15.7	49.1
03:40 PM	-	03:50 PM	14.20	2.66	39.4	66.6	15.6	49.3
03:50 PM	-	04:00 PM	14.26	2.53	40.4	66.7	15.5	50.3
Averages:			14.19	2.66	39.6	66.6	15.6	49.6

Calibration Data			
	O2	NOx	CO
INITIAL zero	10	10	10
INITIAL span	70	45.4	91.4
FINAL zero	10	10.1	9.8
FINAL span	69.6	45.8	91.5
ZERO DRIFT %/ppm	0.00	0.05	-0.20
CALIB. DRIFT %/ppm	-0.10	0.20	0.10
ZERO DRIFT %fs	0.00	0.10	-0.20
CALIB. DRIFT %fs	-0.40	0.40	0.10
CAL GAS value	15	17.61	81.4
FULL SCALE RANGE	25	50	100

DSCFM = 109966 (AVERAGE OF PITOT TUBE TRAVERSE)

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
NOx values:	14.19	2.66	7.10	2.34	2.13

	%O2	ppm	@ 3%O2	@15%O2	lb/hr
CO values:	14.19	39.6	106	34.8	19.3

EMISSION FACTORS (lbs/MMBtu)

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1
 DATE : 02-23/24-93
 REPORT : 027-343

LBS/MMBTU & EPA F FACTOR @ 60°F

NOx

RUN	PPM	%O2	LBS/MMBTU
#1	1.88	13.85	0.00574
#2	2.01	14.01	0.00628
#3	2.08	14.03	0.00652
#4	2.23	14.04	0.00700
#5	2.37	14.06	0.00746
#6	2.48	14.04	0.00779
#7	2.25	13.95	0.00697
#8	1.89	13.96	0.00587
#9	1.88	13.99	0.00586
AVERAGE	2.12	13.99	0.00661

CO

RUN	PPM	%O2	LBS/MMBTU
#1	36.7	13.85	0.06825
#2	37.3	14.01	0.07098
#3	36.3	14.03	0.06928
#4	35.4	14.04	0.06766
#5	32.6	14.06	0.06249
#6	31.5	14.04	0.06021
#7	36.4	13.95	0.06867
#8	38.1	13.96	0.07198
#9	36.5	13.99	0.06926
AVERAGE	35.6	13.99	0.06764

EPA F FACTOR @ 60°F 8503

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #2
 DATE : 02-25/26-93
 REPORT : 027-343

LBS/MMBTU & EPA F FACTOR @ 60°F

NOx


RUN	PPM	%O2	LBS/MMBTU
#1	2.57	14.04	0.00807
#2	2.84	14.03	0.00890
#3	3.22	14.11	0.01022
#4	2.81	14.12	0.00893
#5	2.85	14.08	0.00900
#6	2.52	14.13	0.00802
#7	2.53	14.09	0.00800
#8	3.37	14.09	0.01066
#9	2.66	14.19	0.00854
AVERAGE	2.82	14.10	0.00893

CO

RUN	PPM	%O2	LBS/MMBTU
#1	45.5	14.04	0.08696
#2	43.1	14.03	0.08226
#3	41.4	14.11	0.07994
#4	40.9	14.12	0.07910
#5	39.9	14.08	0.07671
#6	39.7	14.13	0.07689
#7	38.6	14.09	0.07432
#8	39.0	14.09	0.07509
#9	39.6	14.19	0.07738
AVERAGE	40.9	14.10	0.07874

EPA F FACTOR @ 60°F 8503

GAS ANALYSIS



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC OPERATING
UNIT : KERN FRONT # 1
DATE : 2-22-93
PROJECT : 027-343

DATE RECEIVED : FEBRUARY 19, 1993
DATE ANALYZED : FEBRUARY 23, 1993
DATE REPORTED: FEBRUARY 25, 1993

FUEL GAS ANALYSIS


CONSTITUENT	MOLE %	WT. %	CHONS Wt. %	
CARBON DIOXIDE	0.604	1.547	CARBON	73.61
OXYGEN	0.008	0.016	HYDROGEN	23.83
NITROGEN	0.871	1.419	OXYGEN	1.14
CARBON MONOXIDE	0.000	0.000	NITROGEN	1.42
			SULFUR	0.00
METHANE	93.327	87.059	H/C	0.324
ETHANE	4.308	7.532		
PROPANE	0.726	1.862		
ISOBUTANE	0.065	0.221		
N-BUTANE	0.053	0.179		
ISOPENTANE	0.012	0.050		
N-PENTANE	0.008	0.032		
HEXANES+	0.017	0.083		
TOTALS:	100.000	100.000		

SPECIFIC GRAVITY (AIR = 1)	0.5938
SPECIFIC VOLUME, cu.ft./lb.	22.07
GROSS CALORIFIC VALUE (DRY), BTU/cu.ft.	1044.88
GROSS CALORIFIC VALUE (WET), BTU/cu.ft.	1024.36
GROSS CALORIFIC VALUE (DRY), BTU/lb.	23058.55
NET CALORIFIC VALUE (DRY), BTU/cu.ft.	942.39
NET CALORIFIC VALUE (WET), BTU/cu.ft.	923.88
COMPRESSIBILITY FACTOR "Z" @ 60° F, 1 ATM	0.9978

EPA "F" FACTOR @ 68° F (DSCF/MM BTU)	8632
EPA "F" FACTOR @ 60° F (DSCF/MM BTU)	8503

ASTM METHODS D-1945-81 & D-3588-91


Terry Rowles
Laboratory Manager



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC OPERATING
UNIT : KERN FRONT # 2
DATE : 2-22-93
PROJECT : 027-343

DATE RECEIVED : FEBRUARY 19, 1993
DATE ANALYZED : FEBRUARY 23, 1993
DATE REPORTED : FEBRUARY 25, 1993

FUEL GAS ANALYSIS

CONSTITUENT	MOLE %	WT. %	CHONS Wt. %	
CARBON DIOXIDE	0.610	1.560	CARBON	73.59
OXYGEN	0.014	0.025	HYDROGEN	23.83
NITROGEN	0.873	1.421	OXYGEN	1.16
CARBON MONOXIDE	0.000	0.000	NITROGEN	1.42
			SULFUR	0.00
METHANE	93.313	87.030	H/C	0.324
ETHANE	4.311	7.536		
PROPANE	0.725	1.860		
ISOBUTANE	0.065	0.221		
N-BUTANE	0.053	0.179		
ISOPENTANE	0.012	0.050		
N-PENTANE	0.008	0.032		
HEXANES+	0.017	0.085		
TOTALS :	100.000	100.000		

SPECIFIC GRAVITY (AIR = 1) 0.5939
SPECIFIC VOLUME, cu.ft./lb. 22.06
GROSS CALORIFIC VALUE (DRY), BTU/cu.ft. 1044.79
GROSS CALORIFIC VALUE (WET), BTU/cu.ft. 1024.27
GROSS CALORIFIC VALUE (DRY), BTU/lb. 23052.39
NET CALORIFIC VALUE (DRY), BTU/cu.ft. 942.30
NET CALORIFIC VALUE (WET), BTU/cu.ft. 923.79
COMPRESSABILITY FACTOR "Z" @ 60° F, 1 ATM 0.9978

EPA "F" FACTOR @ 68° F (DSCF/MM BTU) 8632
EPA "F" FACTOR @ 60° F (DSCF/MM BTU) 8503

ASTM METHODS D-1945-81 & D-3586-91


Terry Rowles
Laboratory Manager

IS AND EQUATIONS


SAMPLING AND ANALYTIC PROCEDURES

REF: EPA Code of Federal Regulations, Title 40, Part 60, Appendix A.
Method 1, 2, 3, 4, and 5

Sampling Apparatus

The sampling apparatus consisted of a nozzle, a heater wrapped probe, and a heated filter holder (see data sheets for type of nozzle, probe, and filter). The filter was connected to a heated teflon filter-to-impinger line. A series of impingers (see data sheet for type and contents) was connected in tandem and immersed in an ice bath. Following the absorption train was a gas pump, dry test meter, and a calibrated restriction orifice fitted with a magnehelic differential pressure gauge. A type 'S' pitot tube and temperature probe was then positioned alongside the probe terminating at the sample nozzle for the purpose of monitoring duct conditions throughout the test.

Sampling Diagram



EPA Method 1: Sampling and Velocity Traverses for Stationary Sources

Prior to the source test a site assessment was performed in order to locate sample points for obtaining the best representative measurements of pollution concentrations and volumetric flow rates. EPA Method 1 takes into account duct area, straight run and cyclonic or stratified flow patterns.

EPA Method 2: Velocity and Volumetric Flow Rates

A computer was used in selection of suitable sample/traverse points. The calibrated pitot tube was connected to a magnehelic gauge and leak checked. A temperature and Δ -P was then recorded at each traverse point and a duct static pressure was also measured and recorded. A volume flow rate was calculated from the measured required traverse points.

EPA Method 3: % CO₂, % O₂, Dry Molecular Weight

Concurrent with each particulate sampling, an integrated gas sample was withdrawn from the summation of the traverse points through the train and collected at the outlet of the meter into a sample bag. Then the contents of the sample bladder were analyzed by Orsat for fixed gas composition.

EPA Method 4: Percent Water

Tare weights of the charged individual impingers was recorded. After sampling, the final weights was then recorded. Percent water was calculated from the weight of water collected and the dry gas volume sampled.

EPA Method 5: Particulate Emissions

A series of preliminary measurements was made prior to conducting the particulate test. EPA Methods 1, 2, and 3 was performed to determine location and number of traverse points, average gas velocity, and pressure and gas molecular weight. Percent water was determined by a psychrometric chart or from combustion analysis of the fixed gases. The results of these measurements were entered into the field computer for the purpose of determining an appropriate nozzle size for isokinetic sampling.

The method 5 apparatus was then prepared on-site in the mobile laboratory. The absorption train was charged with freshly prepared chemicals, weighted on a calibrated digital balance to the nearest 0.1 grams, and assembled. The probe was brushed out and rinsed with distilled water and acetone, then the filter holder was charged. The sampling apparatus was sealed and transported to the sampling site where it was assembled and leak tested at 15 inches mercury vacuum.

The probe, filter and impinger line heaters were set at 250 °F and the probe was then positioned into the duct at the first traverse point with the nozzle out of the flow.

The nozzle was positioned into the gas flow and the vacuum pump was started immediately and adjusted to obtain an isokinetic sample rate. A complete traverse was performed while sampling at a minimum of two minutes per sample point. Upon completion of the traverse the vacuum pump was turned off and the probe was transferred into the next sample EPA port where an identical sample-traverse was then performed. Duct conditions (temperature, Δ -P)

Method 5: Continued

and sampling conditions (meter temperature, volume and pressure, probe, filter, sample line, impinger temperatures, and absorption train vacuum) was monitored and recorded regularly for each sample point.

Upon completion of sampling, the apparatus was leak tested at a vacuum greater than the highest observed vacuum. The leak was recorded and the apparatus was then sealed and transported to the mobile laboratory. The heated filter-to-impinger line was rinsed with a known amount of distilled water into the first impinger.

The filter and any loose particulate was carefully removed from the filter holder with tweezers. It was then placed in a labeled petri dish and transported to the P.C.E.S. laboratory. The nozzle, probe, and filter top housing was rinsed and brushed three times with distilled water and acetone. The sample fractions were combined, bottled, labeled, and fluid level marked for transportation to the P.C.E.S. laboratory. Aliquots of distilled water and acetone were similarly treated for blank analysis.

The absorption train was inspected for abnormalities and disassembled. The impingers were weighed on a digital balance for a percent moisture determination. The contents of the impingers were quantitatively transferred into separate bottles, sealed, labeled, and fluid level marked for transportation to the P.C.E.S. laboratory for analysis, if required. Aliquots of the reagent grade impinger contents were saved for blank analysis.

The filter was transferred to an oven and heated at 105 °F for 2-3 hours and then placed in a desiccator for 24 hours. The filter was then weighed on a Mettler digital balance to the nearest 0.01 mg. Additional six hour desiccations and weighings were then performed until the difference between consecutive weighings were less than 0.5 mg or one percent of the total filtrate weight (weighed to a constant weight).

The nozzle/probe/filter top wash was then examined for any leakage during transportation and transferred to a tared evaporation dish. The wash was then evaporated at an elevated temperature, below the boiling point of the wash, with occasional swirling. The dish and wash residue was then desiccated and weighed to a constant weight.

If required by the regulatory agency, the contents of the first impinger were recovered and diluted volumetrically to a known volume. An aliquot of this sample was then evaporated, desiccated, and then weighed to a constant weight.

The net weight of particulate was calculated from the two fractions (three fractions including the impinger contents, if required). Concentrations (gr/DSCF) and emissions (lbs/hr) or other applicable units were then calculated and reported.

EPA METHOD 2
STACK GAS VELOCITY AND VOLUMETRIC FLOWRATE

Average Stack Gas Velocity
Eq. 2-6 & Eq. 2-9

$$P_g = \frac{\text{Static Pressure, H}_2\text{O}}{13.6}$$

$$P_s = P_{bar} + P_g$$

$$V_s = K_p C_p (\sqrt{\Delta P})_{avg} \sqrt{\frac{T_s (avg)}{P_s M_s}}$$

Average Stack Gas Dry Volumetric Flow Rate
Eq. 2-10

$$Q_{std} = 60 (1 - B_{vs}) V_s A \left(\frac{T_{std}}{T_s (avg)} \right) \left(\frac{P_s}{P_{std}} \right)$$

$$\frac{Q_{std}}{MF} = SCFM$$

EPA METHOD 3
DRY MOLECULAR WEIGHT OF STACK GAS
Eq. 3-2

$$M_d = 0.44 (\% CO_2) + 0.320 (\% O_2) + 0.280 (\% N_2 + \% CO)$$

Wet Molecular Weight of Stack Gas

$$M_s = M_d (1 - B_{vs}) + 18 (B_{vs})$$

EPA METHOD 4
DETERMINATION OF MOISTURE CONTENT IN STACK GASES

Volume of Water Vapor Condensed
Eq. 4-1

$$V_{vc} (std) = \frac{(V_f - V_i) P_v R T_{std}}{P_{std} M_v} = K_1 (V_f - V_i)$$

Where: $K_1 = 0.04646 \frac{ft^3}{ml} @ 520^\circ R$

Volume of Water Vapor Collected in Silica Gel
Eq. 4-2

$$V_{vsg} (std) = \frac{(W_f - W_i) R T_{std}}{P_{std} M_v (453.6 \text{ g/lb})}$$

$$= K_2 (W_f - W_i)$$

Where: $K_2 = 0.04651 \frac{ft^3}{g} @ 520^\circ R$

Sample Gas Volume
Eq. 4-3

$$V_{\#} (std) = V_{\#} \gamma \left(\frac{(P_{\#}) (T_{std})}{(P_{std}) (T_{\#})} \right)$$

$$= K_3 \gamma \frac{V_{\#} P_{\#}}{T_{\#}}$$

Where: $K_3 = 17.38 \frac{^\circ R}{in. Hg} @ 520^\circ R$

Moisture Content
Eq. 4-4

$$B_{vs} = \frac{V_{vc} (std) + V_{vsg} (std)}{V_{vc} (std) + V_{vsg} (std) + V_{\#} (std)}$$

$$B_{vs} \times 100 = \% H_2 O \text{ in gas stream}$$

$$MF = 1 - B_{vs}$$

EPA METHOD 5
DETERMINATION OF PARTICULATE EMISSIONS FROM STATIONARY SOURCES
 Use in Method 5 and 8 combinations runs

Dry Gas Volume
 Eq. 5-1

$$\begin{aligned}
 V_{\#} (std) &= V_{\#} Y \left(\frac{T_{std}}{T_{\#}} \right) \left[P_{bar} + \frac{\Delta H}{13.6} \right] \\
 &= K_1 V_{\#} Y \left[\frac{P_{bar} + \frac{\Delta H}{13.6}}{T_{\#}} \right] \\
 &= K_1 = 17.38 \frac{R}{in.Hg} @ 520 \cdot R
 \end{aligned}$$

*In case of leak rate beyond allowable limits, correct Eq. 5-1 as follows:
 Case 1 - No component changes made during run.

$$V_{\#} = V_{\#} - (L_p - L_d) \theta$$

Case 2 - One or more component changes made during run.

$$V_{\#} = \left[V_{\#} - (L_1 - L_d) \theta_1 - \sum_{i=2}^n (L_i - L_d) \theta_i - (L_p - L_d) \theta_p \right]$$

Volume of Water Vapor
 Eq. 5-2

$$\begin{aligned}
 V_{vc} (std) &= V_1 c \left(\frac{p_v}{M_v} \right) \left(\frac{RT_{std}}{P_{std}} \right) \\
 &= K_2 V_1 c
 \end{aligned}$$

$$\text{Where: } K_2 = 0.04646 \frac{ft^3}{ml} @ 60 \cdot F$$

Moisture Content
 Eq. 5-3

$$B_{vs} = \frac{V_{vc} (std)}{V_{\#} (std) + V_{vc} (std)}$$

**EPA METHOD 5
(con't)**

**Acetone Blank Concentration
Eq. 5-4**

$$C_i = \frac{M_i}{V_i \rho_i}$$

**Acetone Wash Blank
Eq. 5-5**

$$W_i = C_i V_{iw} \rho_i$$

**Particulate Concentration
Eq. 5-6**

$$C_s = \frac{gr}{dscf} = \left(0.001 \frac{g}{mg} \right) \left(\frac{M_n}{V_n (std)} \right) (15.432)$$

$$gr/dscf (MF) = \frac{gr}{scf}$$

Corrected to 12 % CO₂

$$\frac{gr}{dscf} @ 12\% CO_2 = \frac{\frac{gr}{dscf} \times 12\% CO_2}{\% CO_2 (dry)}$$

**Isokinetic Variation
Eq. 5-7 and 5-8**

$$\% I = 100 \times \frac{T_s \left[V_1 C K_3 + \frac{V_1}{T_1} \left(P_1 + \frac{\Delta H}{13.6} \right) \right]}{60 \theta A_n V_s P_s}$$

Where: $K_3 = 0.002669$

Mass Emission Rate

$$\frac{lbs}{hr} = \frac{gr}{dscf} \times dscfm \times 60 \frac{m}{hr} \times \frac{1 lb}{7000 gr}$$

NOMENCLATURE

(1 of 3)

A	= Cross-sectional area of stack (ft ²)
A _n	= Cross-sectional area of nozzle, (ft ²)
B _{vs}	= Proportion of water vapor, by volume, in the gas stream
C _a	= Acetone blank residue concentration, (mg/g)
C _p	= Pitot tube coefficient, dimensionless
C _s	= Concentration of particulate matter in stack gas, dry basis corrected to standard conditions, (gr/dscf)
C _{SO2}	= Concentration of sulfur dioxide dry basis corrected to standard conditions, (lb/dscf)
C _{H2SO4}	= Sulfuric acid (including SO3) concentration, corrected to standard conditions, (lb/dscf)
ΔH	= Average pressure differential across the orifice meter, (in H ₂ O)
K _p	= Pitot tube constant, $85.49 \frac{\text{ft} [(\text{lb/lb-mole})(\text{in Hg})]^{1/2}}{\text{sec} [(^{\circ}\text{R}) (\text{in H}_2\text{O})]}$
L _p	= Leakage rate observed during the post-test leak check, (cfm)
L _a	= Maximum acceptable leakage rate, (0.02 cfm or 4% of average sampling rate, whichever is less)
L _i	= Individual leakage rate observed during the leak check conducted prior to the "i th " component change, (cfm)
M _a	= Mass of residue of acetone after evaporation, mg
M _g	= Molecular weight of stack gas, dry basis, (lb/lb-mole)
M _n	= Total weight of particulate matter collected, mg
M _s	= Molecular weight of stack gas, wet basis, (lb/lb-mole)
M _w	= Molecular weight of water, 18 lb/lb-mole
N	= Normality of barium perchlorate titrant, (milliequivalents/ml)
ΔP	= Velocity head of stack gas, (in H ₂ O)
P _{bar}	= Barometric pressure at measurement site (in Hg)
P _g	= Stack static pressure, (in Hg)
P _a	= Absolute pressure at the dry gas meter, (P _{bar} + ΔH/13.6)

NOMENCLATURE

(2 of 3)

P_s	= Absolute stack gas pressure, (inches Hg)
$P_{(std)}$	= Standard absolute pressure, 29.92 in Hg
$Q_{(std)}$	= Dry volumetric stack gas flow rate, standard conditions, (dscfm)
R	= Ideal gas constant, 21.85 (in Hg) (ft ³)/(lb-mole)(°R)
t_s	= Stack temperature, (°F)
T_a	= Absolute temperature at meter, (°R)
$T_{(std)}$	= Standard absolute temperature, (520°R)
T_s	= Absolute stack temperature, (460° + t_s)
V_a	= Volume of sample aliquot titrated, (ml)
V_{ab}	= Volume of acetone blank, ml
V_n	= Dry gas volume measured by dry gas meter, (dcf)
$V_{n(std)}$	= Dry gas volume measured by dry gas meter, corrected to standard conditions, (dscf)
$V_{wc(std)}$	= Volume of water vapor condensed corrected to standard conditions, (scf)
$V_{wsg(std)}$	= Volume of water vapor collected in silica gel corrected to standard conditions (scf)
V_{ic}	= Volume of water vapor condensed in impingers and silica gel, (ml)
V_f	= Final volume of condensed water, ml
V_i	= Initial volume of condensed water, ml
V_s	= Average stack gas velocity, (ft/sec)
V_{soln}	= Total volume of solution in which the sulfur dioxide sample is contained (ml)
V_t	= Volume of barium perchlorate titrant used for the sample, (ml)
V_{tb}	= Volume of barium perchlorate titrant used for the blank, (ml)
W_f	= Final weight of silica gel or silica gel plus impinger, (g)
W_i	= Initial weight of silica gel or silica gel plus impinger, (g)
Y	= Dry gas meter calibration factor
ρ_w	= Density of water, (0.002202 lb/ml @ 60°F)

NOMENCLATURE

(3 of 3)

ρ_a	= Density of acetone, (g/ml)(see bottle label)
MF	= Moisture factor
%CO ₂	= Percent CO ₂ by volume (dry basis)
%O ₂	= Percent O ₂ by volume (dry basis)
%CO	= Percent CO by volume (dry basis)
%N ₂	= Percent N ₂ by volume (dry basis)
0.264	= Ratio of O ₂ to N ₂ in air v/v
0.280	= Molecular weight of N ₂ or CO, divided by 100
0.320	= Molecular weight of O ₂ , divided by 100
0.440	= Molecular weight of CO ₂ , divided by 100
60	= Conversion factor, (sec/min)
18.0	= Molecular weight of water, (lb/lb-mole)
32.03	= Equivalent weight of sulfur dioxide
θ	= Total sampling time (min)
θ_i	= Sampling time interval, between two successive component changes, beginning with the interval between the first and second changes, (min)
θ_1	= Sampling time interval, from the run beginning until first component change, (min)
θ_p	= Sampling time interval, from the final (n th) component change until the end of the sampling run, (min)

CONTINUOUS EMISSION MONITORING SYSTEM (CEMS)

Reference: Manual of Procedures; ST-13A, ST-19A, Jan 1982, State of California, Air Resources Board, Test Methods 1-100, June 1979.
EPA CFR Title 40, Pt. 60, Appendix A, Method 3A, 6C, 7E, & 10.

Instrument Summary

A constant sample of flue gas was extracted, dried, filtered and delivered to an instrument manifold system for distribution to one or more analyzers. Instrument results are recorded on an analog strip chart recorder. System calibration checks are performed as well as calibration checks at the beginning and end of each test run. Final data reduction includes zero and calibration drift corrections.

Sample Conditioning System

Consists of a borosilicate glass tube or 316 grade stainless steel probe fitted with a cindered stainless steel or pyrex glass wool particulate filter. The probe is fitted with a teflon (TFE) sample line which connects to a water condensation system located at the source. The condensation system consists of three 500-ml short stem glass impingers connected in a series, immersed in an ice bath. The gas is delivered to the instrument trailer with a teflon line (3/8" O.D.) through an in-line Balston particulate filter drawn by a teflon-coated diaphragm pump. The sample system is leak checked prior to sampling by plugging the end of the sample probe and adjusting the sample pump to its maximum rate (approximately 22" Hg). The manifold is by-passed and the leak rate monitored through a gas meter or low range flow meter.

Manifold System

Sample gas is delivered to each analyzer through a five way valve and regulated with a needle valve flow meter. Manifold pressure is controlled by a back pressure regulator which is typically set at three psi. Zero gas (N₂) and calibrated gases are delivered to the analyzers using the same five way valve and flow meter. All manifold parts are glass, stainless steel, or teflon materials.

Analog Strip Chart Data Reduction

Analog recordings consists of averaged time increments as shown on the data pages (typically 5, 10, or 20 minute increments). Data for each increment was recorded at an average percent of full scale. The readings were then compared with the zero and calibration readings for calculation of the average concentration for each time increment. Any deviation of the zero and calibration readings from the start to the end of a test period was corrected by calculating apparent zero and calibration readings for the mid-point of each time increment. The average concentrations were then calculated from the sample readings and the apparent zero and span readings.

EPA METHOD 18
HYDROCARBON EMISSIONS TESTING
FID ANALYSIS

Sampling Procedures

The sample was drawn via evacuated cannister through a stainless steel/teflon probe into a tedlar bag. Each sample bag was evacuated and then filled.

Analytical Procedures

The contents of the tedlar bag are analyzed by gas chromatography. The gas chromatograph is calibrated with an appropriate standard for each carbon #, before and after each set of samples are analyzed. The sample is speciated by carbon #-C₁, C₂, C₃, C₄, C₅, and C₆₊ backflush.

Symbol Identification

i = Carbon #; i = 1 to 6+
s = Refers to standard for that carbon #
Rx_i = Response factor for C_i
MW = Molecular weight - g/mole
DSCFM = Average volume flow rate of unit tested

Equations

$$Rx_i = \frac{Area_{std}}{ppm_{std}}$$

$$Sample\ ppm_i = \frac{1}{Rx_i} \times Area_i$$

$$Sample\ ppm\ (as\ C_1) = Sample\ ppm \times \# \ of\ carbons$$

$$\frac{lbs}{hr_i} = ppm_i \times MW_i \times DSCFM \times 1.581 \times 10^{-7}$$

$$Total\ non-methane\ \frac{lbs}{hr} = \sum_{i=2}^{6+} \frac{lbs}{hr_i}$$

Note 1: If lbs/hr as methane is required, MW will equal 16.0 (MW of methane)
Note 2: # of carbons: ethane = 2; propane = 3; etc...

APPENDIX I
OPERATIONAL DATA
(Supplied by Destec)

COMPANY : DESTEC
 UNIT : KERN FRONT - TURBINE #1 & #2
 DATE : 02-23/26-93
 REPORT : 027-343

CEM DATA SUMMARY

RUN #	TURBINE #1			TURBINE #2		
	%O2	NOx ppm	CO ppm	%O2	NOx ppm	CO ppm
1	14.13	2.05	36.42	14.23	2.71	45.32
2	14.12	1.98	37.65	14.22	2.66	43.24
3	14.12	2.05	36.25	14.23	2.80	40.45
4	14.12	2.07	35.67	14.22	2.73	41.29
5	14.12	2.29	32.81	14.22	2.80	40.05
6	14.12	2.44	29.47	14.23	2.80	39.43
7	14.12	2.12	33.98	14.22	2.80	38.50
8	14.12	2.05	35.53	14.23	2.80	39.27
9	14.12	2.04	33.40	14.22	2.80	39.38
	14.12	2.12	34.58	14.22	2.77	40.77

EMISSIONS MONITORING LOG1
KERN FRONT - LOG8 (12HR)

16:56:01

23FEB93

PD

1 NOX LEVEL AT STACK 01-101
2 CO LEVEL AT STACK 01-101
3 COR NOX LEVEL AT STACK 01-101
4 COR CO LEVEL AT STACK 01-101
5 O2 LEVEL AT STACK 01-101
6 NOX LEVEL AT STACK 02-101
7 CO LEVEL AT STACK 02-101
8 COR NOX LEVEL AT STACK 02-101
9 COR CO LEVEL AT STACK 02-101
10 O2 LEVEL AT STACK 02-101
11 CEM SYSTEM IN CALIBRATION
12

HH:MM:SS 1 BLR1NOX PPMVD AVG 2 BLR1CO PPMVD AVG 3 BLR1NOCR PPMVD AVG 4 BLR1COCR PPMVD AVG 5 BLR1O2 PPMVD AVG 6 BLR2NOX PPMVD AVG 7 BLR2CO PPMVD AVG 8 BLR2NOCR PPMVD AVG 9 BLR2COCR PPMVD AVG 10 BLR2O2 PPMVD AVG 11 XS1932 CALIB 12

05:00:00	1.36	30.50	1.1	27.3	14.42	2.05	36.56	1.8	33.0	14.47	NORMAL
05:15:00	1.53	30.46	1.3	27.3	14.42	2.05	36.72	1.8	32.9	14.43	NORMAL
05:30:00	1.54	29.98	1.3	26.9	14.42	2.18	34.21	1.9	30.8	14.48	NORMAL
05:45:00	1.54	30.47	1.3	27.3	14.42	2.15	35.77	1.9	32.2	14.47	NORMAL
06:00:00	1.54	30.25	1.3	27.1	14.42	2.04	39.99	1.8	35.8	14.42	NORMAL
06:15:00	1.34	31.00	1.1	27.7	14.42	2.04	39.42	1.8	35.3	14.43	NORMAL
06:30:00	1.52	30.55	1.3	27.4	14.43	2.04	38.29	1.8	34.3	14.43	NORMAL
06:45:00	1.54	30.36	1.3	27.2	14.43	2.04	37.52	1.8	33.6	14.42	NORMAL
07:00:00	1.53	30.15	1.3	27.0	14.42	2.04	37.51	1.8	33.6	14.43	NORMAL
07:15:00	1.54	30.38	1.3	27.2	14.43	2.05	37.46	1.8	33.8	14.48	NORMAL
07:30:00	1.52	30.67	1.3	27.5	14.43	2.05	38.11	1.8	34.5	14.52	NORMAL
07:45:00	1.34	30.95	1.1	27.7	14.43	2.05	37.72	1.8	34.2	14.53	NORMAL
08:00:00	1.52	30.55	1.3	27.4	14.43	2.05	36.57	1.8	33.1	14.49	NORMAL
08:15:00	1.52	30.28	1.3	27.1	14.43	2.05	36.58	1.8	33.4	14.43	NORMAL
08:30:00	1.52	30.66	1.3	27.5	14.43	2.04	37.26	1.8	34.3	14.43	NORMAL
08:45:00	9.62	19.73	3.2	17.2	8.24	2.04	38.27	1.8	34.3	14.43	CALIB
09:00:00	10.39	16.35	3.4	14.1	7.80	2.04	38.27	1.8	34.3	14.43	CALIB
09:15:00	7.10	24.36	2.6	20.9	10.20	2.04	38.27	1.8	34.3	14.43	NORMAL
09:30:00	13.28	17.55	4.0	13.2	5.61	2.04	38.27	1.8	34.3	14.43	NORMAL
09:45:00	1.54	34.62	1.3	31.0	14.43	2.05	41.75	1.8	37.4	14.44	NORMAL
10:00:00	2.28	33.47	1.5	29.5	13.86	2.05	42.03	1.8	37.7	14.44	NORMAL
10:15:00	3.23	30.38	1.7	27.2	13.20	2.04	40.82	1.9	36.5	14.48	NORMAL
10:30:00	1.79	35.31	1.5	31.6	14.42	2.19	40.32	2.0	36.5	14.52	NORMAL
10:45:00	1.78	33.76	1.5	30.4	14.43	2.30	39.96	2.0	36.1	14.48	CALIB
11:00:00	1.79	34.80	1.5	31.1	14.43	2.30	39.27	2.0	35.1	14.43	CALIB
11:15:00	2.22	32.47	2.0	28.7	14.34	2.30	39.27	2.0	35.1	14.43	NORMAL
11:30:00	2.29	32.32	2.0	28.0	14.21	2.35	39.01	2.1	34.8	14.41	NORMAL
11:45:00	2.29	33.03	2.0	28.2	14.12	2.80	38.46	2.5	33.4	14.22	NORMAL
12:00:00	2.29	31.73	2.0	27.3	14.16	2.80	36.42	2.5	32.0	14.31	NORMAL
12:15:00	2.29	30.32	2.0	26.2	14.17	2.80	35.71	2.6	31.1	14.22	NORMAL
12:30:00	2.29	29.65	2.0	25.5	14.15	2.59	41.20	2.3	35.8	14.23	NORMAL
12:45:00	2.29	29.50	2.0	25.4	14.18	2.55	40.63	2.3	34.9	14.16	NORMAL
13:00:00	2.29	29.03	2.0	25.0	14.17	2.74	39.56	2.5	34.3	14.22	NORMAL
13:15:00	2.29	28.38	2.1	24.5	14.17	2.55	41.59	2.3	36.0	14.21	NORMAL
13:30:00	2.29	28.30	2.0	25.7	14.17	2.55	41.26	2.3	35.3	14.22	NORMAL
13:45:00	2.05	33.97	1.8	29.1	14.12	2.54	42.39	2.3	36.3	14.14	NORMAL
14:00:00	2.05	35.95	1.8	30.8	14.12	2.55	42.73	2.3	36.6	14.14	NORMAL
14:15:00	2.05	35.68	1.8	30.5	14.12	2.55	41.59	2.3	36.2	14.23	NORMAL
14:30:00	2.05	36.18	1.8	31.0	14.13	2.55	44.25	2.3	38.4	14.21	NORMAL
14:45:00	2.05	36.18	1.8	31.0	14.13	2.55	44.25	2.3	38.4	14.13	NORMAL
15:00:00	2.05	36.95	1.8	31.4	14.13	2.54	42.34	2.3	36.7	14.13	NORMAL
15:15:00	2.05	36.77	1.8	31.5	14.12	2.55	42.72	2.3	36.6	14.14	NORMAL

Turn # 1

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100

15:30:00 2.05 37.29 1.8 31.9 14.12 2.54 42.83 2.3 37.2 NORMAL
 15:45:00 1.98 38.03 1.7 32.5 14.12 2.55 43.02 2.3 38.2 NORMAL
 16:00:00 1.97 37.26 1.7 31.9 14.12 2.55 43.52 2.3 37.8 NORMAL
 16:15:00 2.04 36.49 1.8 31.3 14.12 2.55 41.72 2.3 36.2 NORMAL
 16:30:00 2.04 36.75 1.8 31.4 14.12 2.55 41.25 2.3 35.8 NORMAL

second 1/2 of pur # 1 turbine # 1

PD	23FEB93	16:56:06	EMISSIONS MONITORING LOG1 KERN FRONT - LOG8 (12HR)												LOG #	8	PAGE	2
HH:MM:SS	1	2	3	4	5	6	7	8	9	10	11	12						
	BLR1NOX	BLR1CO	BLR1NOCR	BLR1COCR	BLR1O2	BLR2NOX	BLR2CO	BLR2NOCR	BLR2COCR	BLR2O2	XS1932							
	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	CALIB							
	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG								
16:45:00	2.05	35.74	1.8	30.6	14.12	2.55	38.03	2.3	33.0	14.23	NORMAL							

SUMMARY DATA

AVG	2.59	31.55	1.8	27.6	13.72	2.31	39.55	2.1	35.0	14.35	
MAX	13.28	38.03	4.0	32.5	14.43	2.80	44.25	2.6	38.4	14.53	
TMAX	9:30:00	15:45:00	9:30:00	15:45:00	11:00:00	12:00:00	14:45:00	12:30:00	14:45:00	7:45:00	
MIN	1.34	16.35	1.1	13.2	5.61	2.04	34.21	1.8	30.8	14.13	
TMIN	7:45:00	9:00:00	6:15:00	9:30:00	9:30:00	6:00:00	5:30:00	6:00:00	5:30:00	15:00:00	

EMISSIONS MONITORING LOG1
KERN FRONT - LOG8 (12HR)

15:16:46

24FEB93

1 NOX LEVEL AT STACK 01-101
2 CO LEVEL AT STACK 01-101
3 COR NOX LEVEL AT STACK 01-101
4 COR CO LEVEL AT STACK 01-101
5 O2 LEVEL AT STACK 01-101
6 NOX LEVEL AT STACK 02-101
7 CO LEVEL AT STACK 02-101
8 COR NOX LEVEL AT STACK 02-101
9 COR CO LEVEL AT STACK 02-101
10 O2 LEVEL AT STACK 02-101
11 CEM SYSTEM IN CALIBRATION
12

12

HH:MM:SS

1	2	3	4	5	6	7	8	9	10	11
BLRINOX	BLRICO	BLRINOCR	BLRICOCR	BLR102	BLR2NOX	BLR2CO	BLR2NOCR	BLR2COCR	BLR202	XS1932
PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	CALIB
AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	
03:30:00	41.13	1.5	35.2	14.12	2.54	58.14	2.3	49.8	14.13	NORMAL
03:45:00	41.34	2.3	35.4	14.12	2.53	57.56	2.3	49.3	14.12	NORMAL
04:00:00	48.25	3.8	41.0	14.07	2.54	54.98	2.3	47.1	14.13	NORMAL
04:15:00	55.33	2.6	46.7	14.03	2.55	55.57	2.3	47.6	14.12	NORMAL
04:30:00	55.06	1.3	46.5	14.03	2.55	54.11	2.3	46.3	14.12	NORMAL
04:45:00	54.92	1.3	46.4	14.02	2.55	57.06	2.3	48.9	14.13	NORMAL
05:00:00	55.09	1.3	46.5	14.02	2.54	56.06	2.3	48.0	14.12	NORMAL
05:15:00	55.85	1.3	47.1	14.03	2.54	54.94	2.3	47.1	14.12	NORMAL
05:30:00	56.89	1.3	48.0	14.03	2.54	55.79	2.3	47.8	14.13	NORMAL
05:45:00	48.54	1.6	41.3	14.08	2.39	59.17	2.2	50.7	14.12	NORMAL
06:00:00	42.00	1.7	35.9	14.12	2.80	41.80	2.6	36.3	14.23	NORMAL
06:15:00	41.51	1.8	35.5	14.12	2.79	41.25	2.5	35.8	14.23	NORMAL
06:30:00	41.31	1.8	35.3	14.12	2.80	41.87	2.6	36.3	14.22	NORMAL
06:45:00	40.18	1.7	34.4	14.12	2.81	41.34	2.5	35.9	14.22	NORMAL
07:00:00	38.43	1.8	32.9	14.12	2.81	42.66	2.6	36.9	14.23	NORMAL
07:15:00	38.29	1.8	32.7	14.13	2.81	42.72	2.5	37.1	14.23	NORMAL
07:30:00	38.44	1.8	32.9	14.13	2.80	41.76	2.5	36.2	14.22	NORMAL
07:45:00	38.75	1.8	33.1	14.12	2.79	43.47	2.4	37.3	14.15	NORMAL
08:00:00	38.75	1.8	33.1	14.12	2.80	42.33	2.5	36.7	14.23	NORMAL
08:15:00	38.48	1.8	32.9	14.12	2.80	41.27	2.6	35.8	14.22	NORMAL
08:30:00	38.06	1.8	32.6	14.12	2.80	41.01	2.5	35.6	14.23	NORMAL
08:45:00	37.45	1.8	32.1	14.12	2.81	39.93	2.5	34.7	14.23	NORMAL
09:00:00	36.99	1.8	31.7	14.12	2.81	39.03	2.5	33.9	14.23	NORMAL
09:15:00	36.64	1.8	31.4	14.12	3.03	37.49	2.6	32.6	14.23	NORMAL
09:30:00	35.80	1.8	30.6	14.12	3.05	35.56	2.8	31.2	14.31	NORMAL
09:45:00	35.54	1.8	30.4	14.12	3.05	37.76	2.6	32.8	14.24	NORMAL
10:00:00	35.07	1.8	30.0	14.12	3.05	36.56	2.8	32.2	14.31	NORMAL
10:15:00	34.64	1.9	29.6	14.12	3.06	34.93	2.6	30.4	14.24	NORMAL
10:30:00	33.41	2.0	28.2	14.12	3.08	34.73	2.8	30.6	14.32	NORMAL
10:45:00	32.20	2.0	27.5	14.12	3.05	34.17	2.8	30.1	14.32	CALIB
11:00:00	31.80	2.0	27.2	14.12	3.05	34.02	2.8	30.0	14.33	NORMAL
11:15:00	30.18	2.2	25.8	14.12	3.29	29.19	2.8	25.7	14.32	NORMAL
11:30:00	28.76	2.2	24.7	14.12	3.33	29.73	2.8	25.9	14.26	NORMAL
11:45:00	28.76	2.0	24.4	14.11	3.30	32.14	2.8	28.3	14.32	NORMAL
12:00:00	32.69	1.9	28.0	14.12	3.30	29.07	2.8	25.6	14.32	NORMAL
12:15:00	35.26	1.8	30.1	14.12	2.57	46.49	2.3	39.0	14.13	NORMAL
12:30:00	35.58	1.8	30.4	14.12	2.54	46.59	2.3	40.1	14.13	NORMAL
12:45:00	35.03	1.8	30.9	14.12	2.55	44.59	2.3	38.7	14.20	NORMAL
13:00:00	35.02	1.8	29.9	14.12	2.55	43.58	2.3	37.8	14.22	NORMAL
13:15:00	34.92	1.8	29.8	14.12	2.54	45.57	2.3	39.1	14.13	NORMAL
13:30:00	33.55	1.8	28.3	14.12	2.55	40.61	2.3	36.2	14.22	NORMAL
13:45:00	33.14	1.8	28.4	14.12	2.55	42.91	2.3	37.2	14.22	NORMAL

EMISSIONS MONITORING LOG1
KERN FRONT - LOG8 (12HR)

16:09:22

26FEB93

PD

1 NOX LEVEL AT STACK 01-101
2 CO LEVEL AT STACK 01-101
3 COR NOX LEVEL AT STACK 01-101
4 COR CO LEVEL AT STACK 01-101
5 02 LEVEL AT STACK 01-101
6 NOX LEVEL AT STACK 02-101
7 CO LEVEL AT STACK 02-101
8 COR NOX LEVEL AT STACK 02-101
9 COR CO LEVEL AT STACK 02-101
10 02 LEVEL AT STACK 02-101
11 CEM SYSTEM IN CALIBRATION
12

HH:MM:SS	1	2	3	4	5	6	7	8	9	10	11	12
	BLR1NOX PPMVD AVG	BLR1CO PPMVD AVG	BLR1NOCR PPMVD AVG	BLR1COCR PPMVD AVG	BLR102 PPMVD AVG	BLR2NOX PPMVD AVG	BLR2CO PPMVD AVG	BLR2NOCR PPMVD AVG	BLR2COCR PPMVD AVG	BLR202 PPMVD AVG	XS1932 CALIB	
04:15:00	0.84	34.46	0.6	28.7	13.95	1.59	44.07	1.3	37.3	14.05	NORMAL	
04:30:00	0.91	37.58	0.7	31.4	13.93	1.53	48.65	1.3	40.8	13.97	NORMAL	
04:45:00	0.53	50.47	0.5	42.0	13.93	1.34	52.56	1.1	44.1	13.99	NORMAL	
05:00:00	0.53	49.80	0.5	41.5	13.92	1.42	51.87	1.2	43.5	13.96	NORMAL	
05:15:00	0.54	49.09	0.5	40.9	13.92	1.36	49.59	1.1	41.8	14.01	NORMAL	
05:30:00	0.54	47.42	0.5	39.5	13.93	1.48	46.03	1.2	38.8	14.02	NORMAL	
05:45:00	0.53	46.80	0.5	39.0	13.92	1.54	43.74	1.3	36.9	14.03	NORMAL	
06:00:00	0.53	47.18	0.5	39.3	13.92	1.54	40.75	1.3	34.4	14.04	NORMAL	
06:15:00	0.53	47.07	0.5	39.2	13.92	1.54	41.19	1.3	34.8	14.04	NORMAL	
06:30:00	0.53	47.36	0.5	39.4	13.92	1.54	42.52	1.3	36.0	14.05	NORMAL	
06:45:00	0.53	46.34	0.5	38.6	13.92	1.54	42.59	1.3	36.0	14.03	NORMAL	
07:00:00	0.53	46.92	0.5	39.0	13.92	1.54	43.82	1.3	37.2	14.09	NORMAL	
07:15:00	0.52	46.91	0.5	39.0	13.92	1.53	43.42	1.3	36.7	14.04	NORMAL	
07:30:00	0.53	47.50	0.5	39.5	13.92	1.54	43.65	1.3	37.2	14.09	NORMAL	
07:45:00	0.52	48.51	0.5	40.3	13.92	1.52	45.02	1.3	38.1	14.04	NORMAL	
08:00:00	0.50	50.68	0.5	42.2	13.92	1.33	48.46	1.1	40.9	14.02	NORMAL	
08:15:00	0.32	50.05	0.3	41.6	13.92	1.31	47.54	1.1	40.1	14.02	NORMAL	
08:30:00	0.52	49.37	0.5	41.1	13.92	1.32	46.03	1.1	38.9	14.02	NORMAL	
08:45:00	0.34	49.12	0.4	40.9	13.92	1.30	46.15	1.1	39.0	14.02	NORMAL	
09:00:00	0.30	49.34	0.3	41.0	13.92	1.29	46.32	1.0	39.1	14.03	CALIB	
09:15:00	0.41	49.39	0.4	41.1	13.93	1.29	46.32	1.0	39.1	14.03	NORMAL	
09:30:00	1.80	49.46	1.5	41.3	14.02	2.20	45.79	2.0	39.4	14.15	NORMAL	
09:45:00	1.77	51.92	1.5	43.8	14.02	2.77	45.20	2.5	39.3	14.23	NORMAL	
10:00:00	1.79	52.02	1.5	43.9	14.02	2.65	45.43	2.4	39.5	14.22	NORMAL	
10:15:00	1.79	49.34	1.5	41.6	14.02	2.56	45.53	2.3	39.6	14.22	NORMAL	
10:30:00	1.80	50.10	1.5	42.3	14.02	2.61	43.91	2.4	38.1	14.22	NORMAL	
10:45:00	1.80	49.44	1.5	41.7	14.02	2.70	42.57	2.5	37.0	14.22	NORMAL	
11:00:00	1.80	48.66	1.5	41.1	14.03	2.80	42.80	2.6	37.0	14.22	NORMAL	
11:15:00	1.80	47.08	1.5	39.8	14.03	2.80	40.93	2.6	35.9	14.22	NORMAL	
11:30:00	1.80	47.66	1.5	40.3	14.03	2.80	39.96	2.5	34.7	14.23	NORMAL	
11:45:00	1.80	47.89	1.5	40.3	14.03	2.80	39.91	2.6	34.6	14.22	NORMAL	
12:00:00	1.80	48.16	1.5	40.7	14.03	2.73	40.91	2.5	35.5	14.22	NORMAL	
12:15:00	1.79	49.05	1.5	41.5	14.04	2.72	41.67	2.5	36.2	14.22	NORMAL	
12:30:00	1.79	48.22	1.5	40.7	14.04	2.77	40.61	2.5	35.3	14.22	NORMAL	
12:45:00	1.80	46.01	1.5	39.3	14.11	2.80	40.19	2.5	34.9	14.22	NORMAL	
13:00:00	1.79	47.03	1.5	39.7	14.02	2.80	39.90	2.5	34.6	14.22	NORMAL	
13:15:00	1.80	46.37	1.5	39.2	14.03	2.80	39.29	2.5	34.1	14.22	NORMAL	
13:30:00	1.79	46.85	1.5	39.5	14.02	2.80	39.95	2.5	34.7	14.23	NORMAL	
13:45:00	1.79	46.42	1.5	39.2	14.03	2.80	38.90	2.5	33.8	14.23	NORMAL	
14:00:00	1.79	47.28	1.5	40.0	14.03	2.80	38.79	2.5	33.7	14.22	NORMAL	
14:15:00	1.79	44.79	1.5	38.2	14.10	2.80	37.98	2.5	33.0	14.22	NORMAL	
14:30:00	1.79	46.66	1.5	39.5	14.10	2.80	39.01	2.5	33.8	14.22	NORMAL	

14:45:00 1.79 47.59 1.5 40.2 14.02 2.80 39.76 2.5 34.5 14.22 NORMAL

15:00:00 1.80 46.53 1.5 39.1 14.02 2.80 39.30 2.5 34.1 14.23 NORMAL

15:15:00 1.79 45.94 1.5 39.2 14.09 2.80 39.23 2.5 34.0 14.22 NORMAL

15:30:00 1.79 47.41 1.5 40.0 14.07 2.80 39.09 2.5 33.9 14.22 NORMAL

15:45:00 1.79 46.93 1.5 39.7 14.02 2.80 39.15 2.5 34.0 14.22 NORMAL

88.2 = KQ

88.5 = 0

22.41 = 02

Run #9

PD 26FEB93 16:09:27 EMISSIONS MONITORING LOG1 KERN FRONT - LOG8 (12HR) LOG # 8 PAGE 2

HH:MM:SS	1	2	3	4	5	6	7	8	9	10	11	12
	BLR1NOX	BLR1CO	BLR1NOCR	BLR1COCR	BLR102	BLR2NOX	BLR2CO	BLR2NOCR	BLR2COCR	BLR202	XS1932	
	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	PPMVD	CALIB	
	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG	AVG		
16:00:00	1.80	46.84	1.5	39.5	14.03	2.80	39.61	2.6	34.4	14.22	NORMAL	

SUMMARY DATA

AVG	1.24	47.56	1.1	39.9	13.99	2.18	43.03	1.9	36.9	14.14	
MAX	1.80	52.02	1.5	43.9	14.11	2.80	52.56	2.6	44.1	14.23	
TMAX	9:30:00	10:00:00	10:30:00	10:00:00	12:45:00	14:15:00	4:45:00	11:45:00	4:45:00	9:45:00	
MIN	0.30	34.46	0.3	28.7	13.92	1.29	37.98	1.0	33.0	13.96	
TMIN	9:00:00	4:15:00	9:00:00	4:15:00	6:30:00	9:00:00	14:15:00	9:00:00	14:15:00	5:00:00	

Record 112
T-1000-02

PG 24FEB93 00:01:17

33

WATER AND FUEL USAGE
KERN FRONT - LOSS (DAILY)

5 RAN MTR CITIES SERV - CURR TOT 9
6 TURBINE 6T-01-101 RUN HOUR MTR 10
7 TURBINE 6T-02-201 RUN HOUR MTR 11
8 12

1 ACTUAL FLOW
2 GAS FUEL FLOW
3 GAS FUEL FLOW
4 RAN MTR FROM CITIES SERVICE

PH:MM:SS	1 PL1970 TSLF MAX	2 W2IBX W2IBX AVG	3 W2IBX W2IBX AVG	4 F11500 GPM AVG	5 F11500 GALS MAX	6 XQ11001 HOURS MAX	7 XQ12001 HOURS MAX	8	9	10	11	12
01:00:00	8930.00	10243.9	10029.6	371.0	2911.2	13.834	45.067					
02:00:00	8930.00	10238.4	10015.0	355.0	2832.6	14.234	45.057					
03:00:00	8930.00	10240.0	10050.7	365.4	345.3	15.834	47.067					
04:00:00	8930.00	10244.2	10040.3	362.5	1036.0	16.834	48.057					
05:00:00	8930.00	10251.2	10023.0	357.0	1365.1	17.834	49.067					
06:00:00	8930.00	10241.3	10051.1	360.5	1726.0	18.834	50.057					
07:00:00	8930.00	10225.8	10057.0	361.1	2037.4	19.834	51.067					
08:00:00	8930.00	10225.8	10014.5	359.9	2448.5	20.834	52.067					
09:00:00	8930.00	10225.8	10004.6	352.4	2891.4	21.834	53.067					
10:00:00	8930.00	10222.3	9987.6	101.8	2903.5	22.834	54.067					
11:00:00	8930.00	10165.0	9863.6	168.6	2999.8	23.834	55.067					
12:00:00	8930.00	10088.5	9752.7	309.5	379.5	24.834	56.067					
13:00:00	8930.00	9914.0	9722.2	306.9	686.7	25.834	57.066					
14:00:00	8930.00	9892.3	9852.9	382.8	1069.3	26.834	58.066					
15:00:00	8930.00	10146.2	9891.7	408.5	1479.1	27.834	59.066					
16:00:00	8930.00	10139.9	9865.2	402.0	1880.6	28.834	60.056					
17:00:00	8930.00	10099.1	9687.1	342.4	2243.5	29.834	61.056					
18:00:00	8930.00	10118.5	9738.4	355.5	2600.2	30.834	62.066					
19:00:00	8930.00	10379.8	10152.2	331.3	2931.9	31.834	63.066					
20:00:00	8930.00	10359.8	10130.9	289.4	2997.9	32.834	64.066					
21:00:00	8930.00	10355.5	10120.8	268.0	509.6	33.834	65.067					
22:00:00	8930.00	10464.7	10309.9	238.4	798.1	34.834	66.067					
23:00:00	8930.00	10524.1	10360.7	288.7	1087.0	35.834	67.067					
00:00:00	8930.00	10589.6	10462.3	288.0	1375.2	36.833	68.067					

SUMMARY DATA AUG = 10078.4 TURBINE 1

AVG	8980.00	10234.5	10013.4	323.2	1830.6	25.334	56.567
SUN	21520.0	245628.5	240321.7	7829.6	4335.3	605.007	1357.595
MAX	8980.00	10589.6	10462.3	408.5	2999.9	36.833	68.067

TURBINE 1 Fuel Flow

25FEB93

15:35:52

2/24

EMISSIONS MONITORING LOG2 KERN FRONT - LOG9 (DAILY)

LOG # 9

PAGI

9 COR CO LEVEL AT STACK 02-101

10 02 LEVEL AT STACK 02-101

11 CEM SYSTEM IN CALIBRATION

5 STEAM CDP LOW FLOW ALARM

6 INLET CO CATALYTIC CONVERTER

7 SRC REACTOR INLET LOW TEMP SEL

8 TOTAL FUEL FLOW TO TURBINE 1

1 GT-1 MWATTS

2 GAS FUEL FLOW

3 STEAM NOZZLE LOW FLOW ALARM

4 TURBINE 1 STEAM : FUEL RATIO

TIME:SS	1 J11964 HM AVG	2 W11BX AVG	3 W11BU AVG	4 W11STOF RATIO AVG	5 W11BV AVG	6 TE1402 DEG F AVG	7 T11456 DEG F AVG	8 GT1FGTOT MMPH AVG	9 BLR2COCR PPMVD AVG	10 BLR202 PPMVD AVG	11 XS1932 CALIB
0:00:00	23.2	10268.2	20209.9	1.97	21054.9	983.0	761.8632	161841.9	36.9	14.15	NORMAL
1:00:00	23.4	10329.7	20473.4	1.98	21010.4	982.0	762.2900	172144.3	38.2	14.12	NORMAL
2:00:00	23.9	10524.5	21359.3	2.03	21017.7	978.9	764.0773	182576.8	42.5	14.12	NORMAL
3:00:00	24.1	10595.3	21811.5	2.06	21019.1	975.4	764.7004	193162.3	49.8	14.12	NORMAL
4:00:00	24.2	10581.6	22045.0	2.08	21020.5	972.7	763.6401	203761.7	44.5	14.13	NORMAL
5:00:00	24.2	10699.5	22097.0	2.08	21023.7	973.4	765.8008	214357.8	40.1	14.12	NORMAL
6:00:00	24.2	10605.8	22117.3	2.09	21004.0	970.1	770.0055	224978.1	44.4	14.13	NORMAL
7:00:00	24.2	10615.9	22128.0	2.08	20993.5	970.6	772.4147	235603.0	45.4	14.13	NORMAL
8:00:00	24.2	10609.0	22426.5	2.11	21101.4	971.1	759.4440	246232.2	43.7	14.12	NORMAL
9:00:00	24.2	10609.1	22253.8	2.10	21052.1	971.3	760.7283	5310.29	41.2	14.13	NORMAL
10:00:00	24.1	10591.1	22235.8	2.10	21053.1	970.7	759.9986	15913.92	44.8	14.10	NORMAL
11:00:00	24.2	10601.6	22219.3	2.09	21029.1	969.2	758.8836	26528.07	46.6	14.12	NORMAL
12:00:00	24.2	10609.8	22219.3	2.10	20981.2	967.7	758.2797	37144.68	47.8	14.12	NORMAL
13:00:00	24.2	10603.1	22232.2	2.11	21030.5	967.1	758.1885	47753.75	42.9	14.12	NORMAL
14:00:00	24.2	10602.4	22345.3	2.12	21087.8	966.4	758.0854	58366.21	40.2	14.12	NORMAL
15:00:00	24.2	10606.7	22493.6	2.12	21087.8	966.4	759.9977	68988.53	23.2	14.22	NORMAL
16:00:00	24.2	10618.9	21860.2	2.06	21267.7	970.6	759.9977	79565.18	29.0	14.17	NORMAL
17:00:00	23.8	10451.8	20496.8	1.96	21348.8	980.4	763.2581	79565.18	28.1	14.21	NORMAL
18:00:00	23.0	10217.4	19350.9	1.89	21332.0	985.7	764.0693	89856.78	27.1	14.27	NORMAL
19:00:00	23.6	10439.8	21129.6	2.02	21324.1	983.8	764.6702	100225.3	32.2	14.22	NORMAL
20:00:00	23.3	10348.2	20672.2	2.00	21325.4	985.0	764.2823	110618.7	37.1	14.19	NORMAL
21:00:00	23.1	10283.8	20314.5	1.98	21325.5	986.1	764.5181	120938.7	26.3	14.05	CALIB
22:00:00	23.2	10323.0	19708.6	1.91	22091.4	982.8	763.1141	131227.8	31.9	14.12	CALIB
23:00:00	23.0	10257.7	18644.2	1.82	22876.7	980.6	761.7185	141594.0	34.5	14.13	NORMAL
24:00:00	22.9	10202.5	18894.8	1.85	22885.1	983.2	762.7180	151718.2			

TURBINE 1 + 10238.6 = 10187.4

SUMMARY DATA

AVG	23.8	10478.6	21230.0	2.02	21302.3	976.2	762.7811	125850.3	38.3	14.14
MAX	24.2	10618.9	22493.6	2.12	22885.1	986.1	772.4147	246232.2	49.8	14.27
THIN	7:00:00	7:00:00	6:00:00	6:00:00	15:00:00	12:00:00	23:00:00	0:00:00	19:00:00	10:00:00
THIN	22:00:00	10202.6	18644.2	1.82	20981.2	966.4	759.0854	5310.29	23.2	14.05
THIN	15:00:00	15:00:00	14:00:00	14:00:00	4:00:00	6:00:00	6:00:00	1:00:00	7:00:00	13:00:00

P3

2/25

WATER AND FUEL USAGE
KERN FRONT - L065 (DAILY)

TIME:MM:SS	1 ACTUAL FLOW				5 RAM WTR CITIES SERV - CURR TOT				9			
	1	2	3	4	5	6	7	8	9	10	11	12
	FG1970	W11BK	W21BK	FI1500	FG1500	XQ11001	XQ12001					
	MSCF	AVG	AVG	SPM	GALS	HOURS	HOURS					
	MAX			AVG	MAX	MAX	MAX					
01:00:00	8980.00	10591.1	10472.6	353.9	1040.0	61.833	3.050					
02:00:00	8980.00	10601.5	10533.2	349.0	1399.1	62.833	4.050					
03:00:00	8980.00	10603.9	10637.3	347.6	1736.8	65.833	5.050					
04:00:00	8980.00	10602.2	10650.5	343.2	2090.1	64.833	6.050					
05:00:00	8980.00	10602.3	10597.2	337.2	2419.7	65.833	7.050					
06:00:00	8980.00	10606.7	10570.0	339.0	2753.8	66.834	8.050					
07:00:00	8980.00	10619.9	9853.5	335.6	2992.7	67.834	9.050					
08:00:00	8980.00	10451.3	10103.3	340.4	435.8	68.834	10.050					
09:00:00	8980.00	10217.4	9950.4	341.4	777.7	69.834	11.050					
10:00:00	8980.00	10439.9	9837.9	344.8	1122.4	70.835	12.050					
11:00:00	8980.00	10348.5	9907.6	344.0	1486.6	71.835	13.050					
12:00:00	8980.00	10283.7	9912.7	345.1	1811.9	72.835	14.050					
13:00:00	8980.00	10323.0	10198.3	347.2	2159.1	73.835	15.050					
14:00:00	8980.00	10257.8	10051.7	197.5	2357.1	74.835	16.050					
15:00:00	8980.00	10202.9	10039.8	302.1	2659.5	75.836	17.050					
16:00:00	8980.00	10326.2	9909.9	300.2	2960.0	76.836	18.050					
17:00:00	8980.00	10091.0	9803.2	297.0	2299.8	77.836	19.050					
18:00:00	8980.00	10211.0	9958.2	295.6	553.0	78.836	20.050					
19:00:00	8980.00	10312.4	10145.0	294.5	947.7	79.836	21.050					
20:00:00	8980.00	10537.9	10471.2	293.0	1141.3	80.837	22.050					
21:00:00	8980.00	10568.1	10472.7	293.3	1434.5	81.837	23.050					
22:00:00	8980.00	10575.7	10514.0	292.1	1725.6	82.837	24.050					
23:00:00	8980.00	10616.7	10472.4	308.2	2035.0	83.837	25.050					
00:00:00	8980.00	10630.4	10530.2	334.5	2369.8	84.838	26.050					

SUMMARY DATA

AVG	8980.00	10442.8	10235.0	320.0	1803.4	73.335	14.550
SUM	215520.0	250622.2	245640.5	7673.8	43281.9	1760.042	349.207
MAX	8980.00	10630.4	10650.6	353.9	2999.8	84.838	26.050

COMPANY: Destec
 UNIT : Turbine Outlet #1
 DATE : 2-23/24-93
 REPORT : 027-343

ON-SITE DATA

2-23-93

2-24-93

		RUN TIME	#1	#2	#3
Vm	Dry sampled gas volume, dcf		0911-1523	08:35-14:51	
Y	Meter calibration factor (met# <u>1002, 1002, _____</u>)		173.99	173.61	
Pbar	Barometric Pressure, "Hg		0.982977	0.982977	
Pstatic	Stack static pressure, "Hg		29.04	29.09	
ΔH	Differential meter pressure, "H2O		-0.85	-0.85	
Tm	Meter temperature, °F		0.57	0.60	
			66	59	

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	909.0	597.8	311.2	941.7	596.5	345.20			
H ₂ O	926.9	593.9	333.0	928.7	590.9	337.80			
KC	642.8	494.4	148.4	604.0	493.9	110.10			
KO	482.9	482.4	.5	482.3	481.8	0.50			
SG	859.9	832.1	27.8	860.7	834.0	26.70			
<LW>			<41.1>			<40.9>			
Vlc	volume of H2O, gms		779.8			779.4			

		RUN	#1	#2	#3
CO2	% Dry Volume		3.0	3.	
O2	% Dry Volume		14.0	14	
N2	% Dry Volume		83.0	83.0	
Cp	Pitot tube coefficient (Pit# _____)		0.791	0.791	
ΔP	Avg P, "H2O		0.964	1.023	
Ts	Stack temperature, °F		263	269	
As	Stack area, sq. ft.		50.53	50.53	
Ds	Stack diameter, inches		96.25	96.25	
Dn	Nozzle diameter, inches		.196	.196	
Dur	Sampling time, min		360	360	
% Iso	Mini iso		100.18	100.03	

Filter #	514	515	
Filter tare weights, gms	0.6168	0.6134	

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

COMPANY: **DESTEC**

UNIT: **KERN FRONT TURBINE #1**

DATE: **2-24-93**

REPORT: **027-343**

TECH: **RJK**

PUMP #: **GAST. (PD-09)**

METER BOX#: **CB 1002 (0.85)**

METER COEFF: **0.982977**

PROBE #: **Cp: 0.791**

METHOD: **5**

RUN # **2 (cont.)**

AMBIENT TEMP, °F: **61°**

Pbar: **29.09**

STATIC PRESSURE (°Hg): **- 0.85**

ASSUMED MOISTURE, %: **18%**

NOZZLE ID#: **17W WET 27.0**

AVG. CALIB. NOZZLE DIAM (°): **0.196**

PROBE LINER MATERIAL: **QTZ.**

FILTER #:

DUCT DIAM (°): **96.25**

PRE / POST TEST LEAK CHECK

LEAK RATE: **< 0.002** cfm

VACUUM: **10** °Hg

TRAVERSE PT. NUMBER N.E.	TIME (e) min.	VACUUM °Hg	STACK TEMP (Ts) °F	VELOCITY HEAD (ΔPs) *H2O	PRESSURE DIFFERENTIAL, °H2O		GAS SAMPLE VOLUME (cu. ft)	GAS SAMPLE TEMP. (AT DRY GAS METER)		FILTER HOLDER / TEMP, °F		TEMP OF GAS EXIT CONDENSER OR LAST IMPINGER
					RATE	Δ H		INLET, °F	OUTLET, °F	PROBE	BOX	
12	11:51	2	270	1.00	0.479	0.59	1062.40	61	61	255	260	
11	12:06	2	270	1.05	0.492	0.62	1069.5	65	60	254	259	
10	12:21	2	270	1.10	0.505	0.65	1076.8	68	59	253	257	
9	12:36	2	270	1.10	0.506	0.65	1084.5	68	61	254	259	
8	12:51	2	269	1.10	0.506	0.65	1092.2	67	61	252	257	
7	13:06	2	269	1.15	0.517	0.67	1099.8	67	61	251	258	
6	13:21	2	268	1.00	0.483	0.60	1107.5	68	60	250	259	
5	13:36	2	267	1.00	0.482	0.60	1114.7	66	61	253	260	
4	13:51	2	266	0.95	0.471	0.57	1121.9	68	60	254	258	
3	14:06	2	265	0.95	0.472	0.57	1128.9	68	61	253	256	
2	14:21	2	265	0.95	0.470	0.57	1136.0	65	61	252	254	
1	14:36	2	260	0.85	0.446	0.52	1143.1	63	61	253	260	
END	14:51						1149.81					
							10L=173.61					
							150=100.03					
							16L Fps=65.95					
AVG			269	1.023		0.60						

COMPANY : Desteer Kern Front
 UNIT : Turbine #2
 DATE : 2-25/26-93
 REPORT : 027-343

ON-SITE DATA

		2-25-93 #1	2-26-93 #2	#3
Vm	Dry sampled gas volume, dcf	7:50-14:01 167.98	8:23-14:33 172.04	
Y	Meter calibration factor (met# 1002, 1002,)	0.982977	0.982977	
Pbar	Barometric Pressure, "Hg	29.13	29.03	
Pstatic	Stack static pressure, "Hg	-0.60	-0.60	
ΔH	Differential meter pressure, "H2O	0.57	0.59	
Tm	Meter temperature, °F	62	62	

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	937.5	596.7	340.8	934.4	601.4	333.0			
H ₂ O	945.0	594.3	350.7	957.5	597.9	359.6			
KO	584.6	493.8	90.8	614.8	494.3	120.5			
KO	482.0	481.3	.7	481.7	481.6	.1			
SG	883.8	861.2	22.6	825.5	799.6	25.9			
<LW>			<43.1>			<43.0>			
Vlc	volume of H ₂ O, gms		762.5			796.1			

		RUN #1	#2	#3
CO ₂	% Dry Volume	3	3	
O ₂	% Dry Volume	14	14.3	
N ₂	% Dry Volume	83	82.7	
Cp	Pitot tube coefficient (Pit#)	0.791	0.791	
ΔP	Avg P, "H ₂ O	0.939	0.979	
Ts	Stack temperature, °F	265	260	
As	Stack area, sq. ft.	50.53	50.53	
Ds	Stack diameter, inches	96.25	96.25	
Dn	Nozzle diameter, inches	.196	.196	
Dur	Sampling time, min	360	360	
% Iso	Mini iso	100.06	99.96	

Filter #	424	425	
Filter tare weights, gms	0.6035	0.6039	

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

5 RUN # 1

METHOD

COMPANY: DESTEC

UNIT: KERN FRONT TURBINE #2

DATE: 2-25-93

REPORT: 027-343

TECH: RJH

PUMP #: GAST (PD-09)

METER BOX#: CB1002 (0.85)

METER COEFF: 0.982977

PROBE #: Cp: 0.791

AMBIENT TEMP, °F: 56°

Pbar: 29.13

STATIC PRESSURE (°Hg): -0.60

ASSUMED MOISTURE, %: 18

NOZZLE ID#: 17W WET 27.0

AVG. CALIB. NOZZLE DIAM. ("): 0.196

PROBE LINER MATERIAL: Q72.

FILTER #:

DUCT DIAM. ("): 96.25

PRE POST TEST LEAK CHECK

LEAK RATE: <0.003 cfm

VACUUM: 10 °Hg

TRAVERSE PT. NUMBER	TIME (g) min. 15/PT.	VACUUM °Hg	STACK TEMP (Ts) °F	VELOCITY HEAD (ΔPs) *H2O	PRESSURE DIFFERENTIAL, °H2O		GAS SAMPLE VOLUME (cu.ft)	GAS SAMPLE TEMP.		FILTER HOLDER		TEMP OF GAS EXIT CONDENSER OR LAST IMPINGER
					RATE	Δ H		INLET, °F	OUTLET, °F	PROBE	BOX	
12	7:50	2	266	1.00	0.476	0.59	151.00	56	56	245	255	
11	8:05	2	267	1.00	0.476	0.59	158.0	58	56	250	259	
10	8:20	2	267	1.00	0.477	0.59	165.2	59	56	256	260	
9	8:35	2	268	0.95	0.465	0.57	172.4	60	56	254	261	
8	8:50	2	267	0.95	0.465	0.57	179.5	60	56	253	261	
7	9:05	2	267	1.05	0.489	0.62	186.5	61	56	251	262	
6	9:20	2	266	1.00	0.478	0.59	193.8	61	57	252	262	
5	9:35	2	265	0.95	0.467	0.57	200.8	62	57	253	262	
4	9:50	2	265	0.75	0.445	0.46	207.8	61	59	254	262	
3	10:05	2	264	0.85	0.443	0.52	214.0	62	58	251	263	
2	10:20	2	264	0.80	0.430	0.49	220.8	62	59	252	263	
1	10:35	2	262	0.95	0.470	0.57	227.3	64	59	253	264	
P.C.	10:50						234.27					
AVG												

5 RUN # 2

METHOD

AMBIENT TEMP, °F: 52°

COMPANY: DESTEC

UNIT: KEAN FRONT TURBINE #2

DATE: 2-26-93

REPORT: 027-343

TECH: RJK

PUMP #: GAST - (PD-09)

METER BOX #: CB1002 (0.85)

METER COEFF: 0.982977

PROBE #: Cp: 0.791

(PRE) POST TEST LEAK CHECK

LEAK RATE: <0.002

VACUUM: 10

Pbar: 29.03

STATIC PRESSURE ("Hg): -0.60

ASSUMED MOISTURE, %: 18%

NOZZLE ID#: MW Wet 27.0

AVG. CALIB. NOZZLE DIAM. ("): 0.196

PROBE LINER MATERIAL: Q7Z

FILTER #:

DUCT DIAM. ("): 96.25

TRAVERSE PT. NUMBER	TIME (e) min.	VACUUM "Hg	STACK TEMP (Ts) °F	VELOCITY HEAD (ΔPs) *H2O	PRESSURE DIFFERENTIAL, "H2O		GAS SAMPLE VOLUME (cu.ft)	GAS SAMPLE TEMP. (AT DRY GAS METER)		FILTER HOLDER /TEMP, °F		TEMP OF GAS EXIT CONDENSER OR LAST IMPINGER
					RATE	Δ H		INLET, °F	OUTLET, °F	PROBE	BOX	
12	8:23	2	257	1.00	0.476	0.59	321.50	52	52	245	243	
11	8:38	2	257	1.05	0.488	0.62	328.6	54	52	248	246	
10	8:53	2	258	1.05	0.489	0.62	335.8	56	51	250	248	
9	9:08	2	259	1.10	0.500	0.65	343.2	55	52	249	247	
8	9:23	2	260	1.15	0.511	0.67	350.9	56	52	251	248	253
7	9:38	2	261	1.15	0.510	0.67	358.6	55	52	250	254	
6	9:53	2	262	1.00	0.476	0.59	366.1	56	52	252	255	
5	10:08	2	262	0.95	0.464	0.57	373.4	56	53	251	256	
4	10:23	2	262	0.90	0.453	0.54	380.2	58	53	253	255	
3	10:38	2	262	0.95	0.467	0.57	387.0	60	54	254	256	
2	10:53	2	261	0.90	0.457	0.55	393.9	64	56	253	257	
1	11:08	2	259	0.85	0.447	0.52	400.7	67	59	252	259	
P.C.	11:23						407.42					
AVG												

METHOD 5 RUN # 26 (cont.)

COMPANY: DESTEC
 UNIT: KERN FRONT TURBINE #2
 DATE: 2-26-93
 REPORT: 027-343
 TECH: RJK
 PUMP #: GAST (PD-09)
 METER BOX #: CB1002 (0.85)
 METER COEFF: 0.982977
 PILOT TUBE #: 0.791

PRE POST TEST LEAK CHECK
 LEAK RATE: < 0.002 cfm
 VACUUM: 7.5 "Hg


AMBIENT TEMP. °F: 65°
 Pbar: 29.93
 STATIC PRESSURE ("Hg): -0.60
 ASSUMED MOISTURE, %: 18
 MW WET 27.0
 AVG. CALIB. NOZZLE DIAM ("): 0.126
 PROBE LINED MATERIAL: Q7Z.
 FILTER #: 96.25
 DIJOT DIAM ("): 96.25

85.92 + 86.12

TRANSVERSE PT. NUMBER	TIME (e) min.	VACUUM "Hg	STACK TEMP (T _g) °F	VELOCITY HEAD (ΔP _g) "H ₂ O	PRESSURE DIFFERENTIAL ΔH rate "H ₂ O ΔH	GAS SAMPLE VOLUME (cu. ft)	GAS SAMPLE TEMP. AT DRY ↓ GAS METER INLET, °F	OUTLET, °F	FILTER HOLDER TEMP °F	TEMP OF GAS EXIT CONDEINER ON LAST IMPIGHT °F
12	11:33	2	260	0.95	0.475	407.70	68	63	252	261
11	11:48	2	260	0.95	0.479	414.7	73	66	251	252
10	12:03	2	261	1.05	0.503	422.0	73	67	250	251
9	12:18	2	262	1.00	0.489	429.5	69	68	249	253
8	12:33	2	263	1.00	0.487	436.9	67	66	251	252
7	12:48	2	262	1.05	0.501	444.2	71	65	253	252
6	13:03	2	261	0.95	0.478	457.8	74	65	252	248
5	13:18	2	261	0.95	0.478	458.9	71	68	251	246
4	13:33	2	260	0.95	0.478	465.9	70	67	250	250
3	13:48	2	260	0.95	0.478	473.2	69	68	252	248
2	14:03	2	260	0.90	0.464	480.4	68	66	253	253
1	14:18	2	259	0.80	0.438	487.4	70	66	255	249
End	14:33					493.82				
						Vol=172.04				
						ISO=99.96				
						VelFs=(4.21)				
AVERAGE			260	0.979	0.59					

VELOCITY TRAVERSE

COMPANY : DESTEC
 UNIT : KERN FRONT TURBINE #2
 DATE : 2-25-83
 REPORT : 027-343
 RUN # : INITIAL VEL. TOTAL : 105.25
 PUMP # : GAST (PD-09) COUPLING : 9.00
 METER BOX# : CR1002 (0.85) DIAMETER : 96.25
 METER coeff: 0.982977 AREA : 50.53
 PITOT TUBE# : 0.791 Cp : 0.791



TRAVERSE POINTS		North East		South East		VELOCITY DATA	
w/b	w/air no.	Ts (°F)	ΔP	Ts (°F)	ΔP	Rated Total MMBTU/hr	
94.2	103.2	12	265	1.00	1.00	ΔP	0.941
89.8	98.8	11	266	1.00	1.00	Ts	264.50
84.9	93.9	10	267	1.05	1.00	Static	0.60
79.2	88.2	9	268	0.95	1.05	Pbar	29.13
72.2	81.2	8	268	0.95	0.95	MW(well)	27.0
62.0	71.0	7	267	1.10	1.10	%H2O	18
34.2	43.2	6	266	1.05	0.95	%O2	
24.1	33.1	5	265	0.90	0.90	F60	
17.1	26.1	4	266	0.75	0.85		
11.4	20.4	3	265	0.85	0.80	Additional Data:	
6.4	15.4	2	263	0.80	0.90		
2.0	11.0	1	261	0.90	0.85		

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Dexter REPORT: 027-343
LOCATION/UNIT: Kern Front Turbine #1 DATE TESTED: 2/23/93
ANALYST: DGS

RUN # 1

PROBE/NOZZLE/FILTER TOP

VOL- 208 ml

DISH # 52 #1	#2	#3	AVERAGE
FINAL (g) 77.1704	77.1704		77.1704
TARE (g) 77.1667			77.1667
NET (g)			0.0037

FILTER # 514

#1	#2	#3	AVERAGE
FINAL (g) 0.6169	0.6169		0.6169
TARE (g) 0.6168			0.6168
NET (g)			0.0001

CONDENSABLE (aliquot 57/ml / 1142 ml)

DISH # 54 #1	#2	#3	AVERAGE
FINAL (g) 79.4056	79.4055		79.4056
TARE (g) 79.4030			79.4030
NET (g)			0.0026

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Desfec

REPORT: 027-343

LOCATION/UNIT: Kern Front Turbine #1

DATE TESTED: 2/24/93

ANALYST: DGS

RUN # 2

PROBE/NOZZLE/FILTER TOP

VOL- 260ml

DISH # <u>66</u> #1	#2	#3	AVERAGE
FINAL (g) <u>82.0678</u>	<u>82.0677</u>		<u>82.0678</u>
TARE (g) <u>82.0658</u>			<u>82.0658</u>
NET (g)			<u>0.0020</u>

FILTER # 515

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6137</u>	<u>0.6136</u>		<u>0.6137</u>
TARE (g) <u>0.6134</u>			<u>0.6134</u>
NET (g)			<u>0.0003</u>

CONDENSABLE (aliquot 588ml / 1176ml)

DISH # <u>18</u> #1	#2	#3	AVERAGE
FINAL (g) <u>65.8830</u>	<u>65.8834</u>		<u>65.8832</u>
TARE (g) <u>65.8808</u>			<u>65.8808</u>
NET (g)			<u>0.0024</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Deste

REPORT: 027-343

LOCATION/UNIT: Kern Front Turbine #2

DATE TESTED: 2/25/93

ANALYST: DGS

RUN # 1

PROBE/NOZZLE/FILTER TOP

VOL- 258 ml

DISH # <u>5</u> #1	#2	#3	AVERAGE
FINAL (g) <u>76.5844</u>	<u>76.5847</u>		<u>76.5846</u>
TARE (g) <u>76.5797</u>			<u>76.5797</u>
NET (g)			<u>0.0049</u>

FILTER # 424

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6038</u>	<u>0.6037</u>		<u>0.6038</u>
TARE (g) <u>0.6035</u>			<u>0.6035</u>
NET (g)			<u>0.0003</u>

CONDENSABLE (aliquot 573 ml / 1145 ml)

DISH # <u>37</u> #1	#2	#3	AVERAGE
FINAL (g) <u>80.6408</u>	<u>80.6410</u>		<u>80.6409</u>
TARE (g) <u>80.6380</u>			<u>80.6380</u>
NET (g)			<u>0.0029</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 027-343

LOCATION/UNIT: Kern Front Turbine #2

DATE TESTED: 2/26/93

ANALYST: DHS

RUN # 2

PROBE/NOZZLE/FILTER TOP

VOL- 194 ml

DISH # <u>24</u> #1	#2	#3	AVERAGE
FINAL (g) <u>74.5914</u>	<u>74.5911</u>		<u>74.5913</u>
TARE (g) <u>74.5880</u>			<u>74.5880</u>
NET (g)			<u>0.0033</u>

FILTER # 425

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6041</u>	<u>0.6040</u>		<u>0.6041</u>
TARE (g) <u>0.6039</u>			<u>0.6039</u>
NET (g)			<u>0.0002</u>

CONDENSABLE (aliquot 594 ml / 1187 ml)

DISH # <u>64</u> #1	#2	#3	AVERAGE
FINAL (g) <u>76.8189</u>	<u>76.8193</u>		<u>76.8191</u>
TARE (g) <u>76.8160</u>			<u>76.8160</u>
NET (g)			<u>0.0031</u>

COMPANY: Deotec Kern Front
 UNIT: Generator #1 LOV
 DATE: 2-19-93
 REPORT: 027-343

ON-SITE DATA

		RUN TIME	#1 12:28-13:08	#2 13:12-13:52	#3 13:55-14:35
Vm	Dry sampled gas volume, dcf		24.07	23.97	23.93
Y	Meter calibration factor (met# <u>1003, 1003, 1003</u>)		.998954	.998954	.998954
Pbar	Barometric Pressure, "Hg		29.08	29.08	29.08
Pstatic	Stack static pressure, "Hg		0	0	0
ΔH	Differential meter pressure, "H2O		.59	.59	.59
Tm	Meter temperature, °F		76.7	78.44	76.6

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	635.7	593.8	41.9	620.8	575.6	45.2	612.5	568.6	43.9
H ₂ O	576.7	576.6	.1	565.4	564.1	1.3	607.9	606.6	1.3
RO	527.5	527.3	.2	485.4	485.1	.3	533.7	533.3	.4
SG	804.3	800.7	3.6	783.7	780.0	3.7	768.9	763.8	5.1
<LW>			<41.1>			<44.2>			<43.3>

Vlc	volume of H ₂ O, gms	H ₂ O - 142.1	MCL - 42.4	RUN	#1	#2	#3
CO ₂	% Dry Volume	0	0	0	0	0	0
O ₂	% Dry Volume	20.7	20.7	20.7	20.7	20.7	20.7
N ₂	% Dry Volume	-	-	-	-	-	-
Cp	Pitot tube coefficient (Pit# _____)	-	-	-	-	-	-
ΔP	Avg P, "H ₂ O (FT/MIN) HOT WIRE ANEMOMETER	189.1	214.4	224.0	189.1	214.4	224.0
Ts	Stack temperature, °F	97.5	86.5	89.4	97.5	86.5	89.4
As	Stack area, sq. ft.	-	-	-	-	-	-
Ds	Stack diameter, inches	3.25	3.25	3.25	3.25	3.25	3.25
Dn	Nozzle diameter, inches	-	-	-	-	-	-
Dur	Sampling time, min	40	40	40	40	40	40
% Iso	Mini iso	-	-	-	-	-	-

Filter # _____
 Filter tare weights, gms _____

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

COMPANY : Destec Kern Front
UNIT : Turbine Unit #1 L.O.V.
DATE : 2-18-93
REPORT : 027-343

ON-SITE DATA

	RUN TIME	#1	#2	#3
Vm	Dry sampled gas volume, dcf	23.99	24.02	24.04
Y	Meter calibration factor (met# <u>1003</u> , <u>1003</u> , <u>1003</u>)	.998954	.998954	.998954
Pbar	Barometric Pressure, "Hg	29.14	29.14	29.14
Pstatic	Stack static pressure, "Hg			
ΔH	Differential meter pressure, "H ₂ O	.59	.59	.59
Tm	Meter temperature, °F	71.8	72.8	71.3

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	647.3	596.0	51.3	629.4	574.9	54.5	622.7	567.9	54.8
H ₂ O	576.3	573.3	3.0	570.8	568.1	2.7	610.7	608.4	2.3
KO	528.6	528.0	.6	486.7	486.3	.4	534.4	533.7	.7
Silica	797.2	791.6	5.6	776.9	771.9	5.0	802.4	795.6	6.8
<LW>			<40.8>			<45.0>			<45.9>

Vic volume of H₂O, gms
A₂O - 136.1
MeCl - 45.0

H₂O - 143.2
MeCl - 42.6
RUN

H₂O - 138.7
MeCl - 42.8
#2

CO ₂	% Dry Volume
O ₂	% Dry Volume
N ₂	% Dry Volume
C _p	Pitot tube coefficient (Pit# _____)
ΔP	Avg P, "H ₂ O (FT/MIN)
T _s	Stack temperature, °F
A _s	Stack area, sq. ft.
D _s	Stack diameter, inches
D _n	Nozzle diameter, inches
Dur	Sampling time, min
% Iso	Mini iso _____

Filter # _____
Filter tare weights, gms _____

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points. total _____

Overall (inches) _____ Coupling _____

METHOD 41 RUN #2

COMPANY: Dwyer Kern Front
UNIT: Turbine #1 101
DATE: 2-18-93
REPORT: 027-343
TECH: Dwyer
PUMP #: 6A5T
MEIEN BOX#: 1003
MEIEN COEFF: 998954 ($\Delta H: 1.028$)
PILOT TUBE#:

PRF / POST TEST LEAK CHECK

LEAK DATE:	<.007	<.004	clm
VACUUM:	11	5	-11g

AMBIENT TEMP, °F:	65
PIBAL:	29.14
STATIC PRESSURE ("10):	
ASSUMED MOISTURE, %:	
AVG. CALIB. NOZZLE DIAM ("):	
PIPORE LINED MATERIAL:	
FW LENT #:	
DWGT DIAM ("):	

$$\frac{F_T}{M_{T10}}$$
[illegible]

COMPANY: Destec Kern Front
 UNIT: Generator #2 L.O.V.
 DATE: 2-19-93
 REPORT: 027-343

ON-SITE DATA

	RUN TIME	#1 9:59-10:39	#2 10:42-11:22	#3 11:25-12:05
Vm Dry sampled gas volume, dcf		24.11	24.04	24.07
Y Meter calibration factor (met# <u>1003</u> , <u>1003</u> , <u>1003</u>)		.998954	.998954	.998954
Pbar Barometric Pressure, "Hg		29.08	29.08	29.08
Pstatic Stack static pressure, "Hg				
ΔH Differential meter pressure, "H2O		.59	.59	.59
Tm Meter temperature, °F		72.2	66.3	67.6

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H2O	638.8	590.3	48.5	627.3	583.3	44.0	612.6	567.9	44.7
H2O	566.2	566.8	<.6>	561.8	562.3	<.5>	603.6	603.2	.4
KO	528.1	528.1	.0	485.1	485.9	<.8>	533.6	533.8	<.2>
SG	800.5	796.7	3.8	780.5	776.9	3.6	763.2	758.4	4.8
<LW>			<48.3>			<44.5>			<44.6>

Vlc volume of H2O, gms
 MeCl - 44.4
 H2O - 128.6

H2O - 148.4
 MeCl - 44.7
 RUN

H2O - 126.9
 MeCl - 42.2
 #2

		#1	#2	#3
CO2 % Dry Volume		0	0	0
O2 % Dry Volume		20.8	20.8	20.8
N2 % Dry Volume				
Cp Pitot tube coefficient (Pit# _____)				
ΔP Avg P, "H2O (FT MIN) HOT WIRE ANEMOMETER		256.3	270.0	286.9
Ts Stack temperature, °F		70.6	69.5	77.3
As Stack area, sq. ft.				
Ds Stack diameter, inches				
Dn Nozzle diameter, inches				
Dur Sampling time, min		40	40	40
% Iso Mini iso				

Filter # _____
 Filter tare weights, gms _____

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

COMPANY : Destec Kern Front
 UNIT : Turbine Unit #2 L.O.V.
 DATE : 2-18-93
 REPORT : 027-343

ON-SITE DATA

		RUN TIME	#1 <u>10:22-11:02</u>	#2 <u>11:12-11:52</u>	#3 <u>12:07-12:47</u>
Vm	Dry sampled gas volume, dcf		<u>24.03</u>	<u>24.04</u>	<u>24.0</u>
Y	Meter calibration factor (met# <u>1003, 1003, 1003</u>)		<u>.998954</u>	<u>.998954</u>	<u>.998954</u>
Pbar	Barometric Pressure, "Hg		<u>29.14</u>	<u>29.14</u>	<u>29.14</u>
Pstatic	Stack static pressure, "Hg		<u>0</u>	<u>0</u>	<u>0</u>
ΔH	Differential meter pressure, "H2O		<u>.59</u>	<u>.59</u>	<u>.58</u>
Tm	Meter temperature, °F		<u>62.6</u>	<u>63.3</u>	<u>65.9</u>

CONTENTS	RUN 1			RUN 2			RUN 3		
	FINAL	TARE	NET	FINAL	TARE	NET	FINAL	TARE	NET
H ₂ O	647.1	590.5	56.60	633.0	576.3	56.7	657.5	607.0	50.5
H ₂ O	569.8	569.2	.6	564.1	563.4	.7	570.0	568.7	1.3
KO	528.0	527.9	.1	486.4	486.4	.0	535.0	535.0	.0
SG	792.3	786.8	5.5	772.5	767.1	5.4	795.8	790.5	5.3
<LW>			<49.6>			<50.3>			<42.3>

Vlc	volume of H ₂ O, gms	<u>13.2</u>	H ₂ O - 175.1 MeCl - 42.6 RUN	<u>12.5</u>	H ₂ O - 142.5 MeCl - 43.3 RUN	<u>14.8</u>
	H ₂ O - 157.9 MeCl - 39.4		#1	#2	#3	

CO ₂	% Dry Volume	<u>0</u>	<u>0</u>	<u>0</u>
O ₂	% Dry Volume	<u>20.9</u>	<u>20.9</u>	<u>20.9</u>
N ₂	% Dry Volume	<u>-</u>	<u>-</u>	<u>-</u>
Cp	Pitot tube coefficient (Pit# _____)	<u>-</u>	<u>-</u>	<u>-</u>
ΔP	Avg P, "H ₂ O (FT/MIN)	<u>57.1</u>	<u>54.3</u>	<u>58.1</u>
Ts	Stack temperature, °F	<u>75.4</u>	<u>72.4</u>	<u>77.4</u>
As	Stack area, sq. ft.	<u>-</u>	<u>-</u>	<u>-</u>
Ds	Stack diameter, inches	<u>3.25</u>	<u>3.25</u>	<u>3.25</u>
Dn	Nozzle diameter, inches	<u>-</u>	<u>-</u>	<u>-</u>
Dur	Sampling time, min	<u>40</u>	<u>40</u>	<u>40</u>
% Iso	Mini iso	<u>-</u>	<u>-</u>	<u>-</u>

Filter # _____
 Filter tare weights, gms _____

INITIALS

CONTROL BOX#:

Hi P _____ Lo P _____ Avg P _____ Duct Temp _____

Diameters before disturb _____ After _____

of points, total _____

Overall (inches) _____ Coupling _____

METHOD 41 RUN # 1

COMPANY: Destec Kava Front
UNIT: Turbine #2 LCV
DATE: 2-18-93
PERIOD: 027-343
TECH: DD
RUMBLE: CAST
MAGNETIC BOX: 103
MAGNETIC COEFF: 998954 (M: 1.02E)
CINOT NUMBER:

PDF / POST TEST / LEAK CHECK

LEAK RATE:	4.001	4.001	cm
VACUUM:	12	5	" Hg

AMBIENT TEMP, °F: 63°
 DATE: 27, 14
 BIATRO PRESSURE (110°F)
 ASSUMED MOISTURE, %:
 AVG. CALIB. NOZZLE DIAM (1°F)
 PROBE LINED MATERIAL:
 FILTER #:
 INLET DIAM (1°F)

$$F_T/M_T$$
[illegible]

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec
LOCATION/UNIT: LOV #1 Generator

REPORT: 027-343
DATE TESTED: 2/19/93
ANALYST: DGS

SAMPLE # 1 aliquot - 221 ml

TIN # 39	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.66221</u>	final (g) <u>1.66220</u>	final (g) _____	<u>1.66221</u>
tare (g) <u>1.59690</u>	tare (g) _____	tare (g) _____	<u>1.59690</u>
NET (g) _____	NET (g) _____	NET (g) _____	<u>0.06531</u>

SAMPLE # 2 aliquot - 224 ml

TIN # 35	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.63793</u>	final (g) <u>1.63797</u>	final (g) _____	<u>1.63795</u>
tare (g) <u>1.58605</u>	tare (g) _____	tare (g) _____	<u>1.58605</u>
NET (g) _____	NET (g) _____	NET (g) _____	<u>0.05190</u>

SAMPLE # 3 aliquot - 222 ml

TIN # 40	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.63557</u>	final (g) <u>1.63468</u> ✓	final (g) <u>1.63464</u> ✓	<u>1.63464</u>
tare (g) <u>1.58459</u>	tare (g) _____	tare (g) _____	<u>1.58459</u>
NET (g) _____	NET (g) _____	NET (g) _____	<u>0.05007</u>

SAMPLE # _____ aliquot - _____

TIN #	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) _____	final (g) _____	final (g) _____	
tare (g) _____	tare (g) _____	tare (g) _____	
NET (g) _____	NET (g) _____	NET (g) _____	

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec
LOCATION/UNIT: LOV #1 Turbine

REPORT: 027-343
DATE TESTED: 2/18/93
ANALYST: DGS

SAMPLE # 1 aliquot - 226 ml

TIN # 43	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.66694</u>	final (g) <u>1.64761</u> ✓	final (g) <u>1.64760</u>	<u>1.64761</u>
tare (g) <u>1.58551</u>	tare (g) _____	tare (g) _____	<u>1.58551</u>
NET (g)	NET (g)	NET (g)	<u>0.06210</u>

SAMPLE # 2 aliquot - 223 ml

TIN # 46	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.65142</u>	final (g) <u>1.65151</u> ✓	final (g) <u>1.65148</u> ✓	<u>1.65150</u>
tare (g) <u>1.60681</u>	tare (g) _____	tare (g) _____	<u>1.60681</u>
NET (g)	NET (g)	NET (g)	<u>0.04469</u>

SAMPLE # 3 aliquot - 222 ml

TIN # 38	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.62888</u>	final (g) <u>1.62056</u> ✓	final (g) <u>1.62053</u> ✓	<u>1.62055</u>
tare (g) <u>1.58160</u>	tare (g) _____	tare (g) _____	<u>1.58160</u>
NET (g)	NET (g)	NET (g)	<u>0.03895</u>

SAMPLE # _____ aliquot - _____

TIN #	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	
NET (g)	NET (g)	NET (g)	

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec
LOCATION/UNIT: LDV #2 Generator

REPORT: 027-343
DATE TESTED: 2/19/93
ANALYST: DGS

SAMPLE # 1 aliquot - 214 ml

TIN # 32	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.63908</u>	final (g) <u>1.63905</u>	final (g)	<u>1.63907</u>
tare (g) <u>1.58947</u>	tare (g) _____	tare (g) _____	<u>1.58947</u>
NET (g)	NET (g)	NET (g)	<u>0.04960</u>

SAMPLE # 2 aliquot - 214 ml

TIN # 36	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.63219</u>	final (g) <u>1.63223</u>	final (g)	<u>1.63221</u>
tare (g) <u>1.58492</u>	tare (g) _____	tare (g) _____	<u>1.58492</u>
NET (g)	NET (g)	NET (g)	<u>0.04729</u>

SAMPLE # 3 aliquot - 218 ml

TIN # 37	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.63198</u>	final (g) <u>1.63195</u>	final (g)	<u>1.63197</u>
tare (g) <u>1.58972</u>	tare (g) _____	tare (g) _____	<u>1.58972</u>
NET (g)	NET (g)	NET (g)	<u>0.04225</u>

SAMPLE # _____ aliquot - _____

TIN #	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	
NET (g)	NET (g)	NET (g)	

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec
LOCATION/UNIT: LOV #2 Turbine

REPORT: 027-343
DATE TESTED: 2/18/93
ANALYST: DGS

SAMPLE # 1

aliquot - 216 ml

TIN # 31	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.62843</u>	final (g) <u>1.62838</u>	final (g)	<u>1.62841</u>
tare (g) <u>1.59107</u>	tare (g) _____	tare (g) _____	<u>1.59107</u>
NET (g)	NET (g)	NET (g)	<u>0.03734</u>

SAMPLE # 2

aliquot - 220 ml

TIN # 30	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.62714</u>	final (g) <u>1.62714</u>	final (g)	<u>1.62715</u>
tare (g) <u>1.59244</u>	tare (g) _____	tare (g) _____	<u>1.59244</u>
NET (g)	NET (g)	NET (g)	<u>0.03469</u>

SAMPLE # 3


aliquot - 214 ml

TIN # 33	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.61820</u>	final (g) <u>1.61819</u>	final (g)	<u>1.61820</u>
tare (g) <u>1.57134</u>	tare (g) _____	tare (g) _____	<u>1.57134</u>
NET (g)	NET (g)	NET (g)	<u>0.04684</u>

SAMPLE # _____

aliquot - _____

TIN #	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	_____
NET (g)	NET (g)	NET (g)	



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC OPERATING
DATE : 2-25-93
REPORT : 027-343

DATE RECEIVED : 2-26-93
DATE ANALYZED : 2-26-93
DATE REPORTED: 3-6-93


EPA METHOD 18
HYDROCARBON ANALYSIS REPORT

UNIT : KERN FRONT TURBINES 1 & 2

CONSTITUENT	INITIAL HC SAMPLE BLANK ppm(v/v)
METHANE	ND
ETHANE	ND
PROPANE	ND
BUTANE	ND
PENTANE	ND
HEXANES+	ND
TOTAL	ND
NON-METHANE	ND

UNIT : KERN FRONT TURBINES 1 & 2

CONSTITUENT	MIDTEST HC SAMPLE BLANK ppm(v/v)
METHANE	ND
ETHANE	ND
PROPANE	ND
BUTANE	ND
PENTANE	ND
HEXANES+	0.10
TOTAL	0.10
NON-METHANE	0.10



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC OPERATING
DATE : 2-25-93
REPORT : 027-343

DATE RECEIVED : 2-26-93
DATE ANALYZED : 2-26-93
DATE REPORTED: 3-9-93

EPA METHOD 18
HYDROCARBON ANALYSIS REPORT


UNIT : KERN FRONT TURBINE # 1

CONSTITUENT	RUN # 1 ppm(v/v)	RUN # 2 ppm(v/v)	RUN # 3 ppm(v/v)
METHANE	66.30	59.58	56.14
ETHANE	2.44	2.13	2.04
PROPANE	ND	ND	ND
BUTANE	ND	ND	ND
PENTANE	ND	ND	ND
HEXANES+	0.07	0.17	0.14
TOTAL	68.82	61.88	58.32
NON-METHANE	2.52	2.30	2.18

UNIT : KERN FRONT TURBINE # 2


CONSTITUENT	RUN # 1 ppm(v/v)	RUN # 2 ppm(v/v)	RUN # 3 ppm(v/v)
METHANE	79.66	57.38	59.73
ETHANE	3.01	2.15	2.20
PROPANE	0.15	0.09	0.06
BUTANE	ND	ND	ND
PENTANE	ND	ND	ND
HEXANES+	0.06	0.02	0.03
TOTAL	82.88	59.64	62.01
NON-METHANE	3.22	2.26	2.28

DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 1 HC SAMPLE # 1



CHROMATOGRAM	8	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.582	816		6		C-6+
2	3.055	115203		1		C-1
3	3.604	3064		2		C-2
4	3.689	5545	V	2		C-2
TOTAL		124627			0	8609


DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 1 HC SAMPLE # 2



CHROMATOGRAM PKNO	9 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.633	1863		6		C-6+
2	3.058	103528		1		C-1
3	3.608	2825		2		C-2
4	3.691	4697	V	2		C-2
TOTAL		112914			0	

Handwritten note: 7522 (next to C-2)


DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 1 HC SAMPLE # 3



CHROMATOGRAM 10 MEMORIZED


PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.606	1540		6		C-6+
2	3.057	97550		1		C-1
3	3.607	2713		2		C-2
4	3.693	4487	V	2		C-2
TOTAL		106290			0	7200

DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 2 HC SAMPLE # 1




CHROMATOGRAM 11		MEMORIZED		IDNO	CONC	NAME
PKNO	TIME	AREA	MK			
1	2.661	722		6		C-6+
2	3.056	138419		1		C-1
3	3.606	3975		2		C-2) 10599
4	3.69	6624	V	2		C-2)
5	4.392	443		8		C-3)
6	4.74	305		3		C-3) 748
TOTAL		150487			0	

DESTEC KERN FRONT
 2-25-93 REPORT # 027-343
 TURBINE # 2 HC SAMPLE # 2




CHROMATOGRAM	12	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.674	266	V	6		C-6+
2	3.057	99696		1		C-1
3	3.695	7587		2		C-2
4	4.392	232		8		C-3
5	4.742	218		3		C-3
TOTAL		107999			0	450

DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 2 HC SAMPLE # 3



CHROMATOGRAM	13	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.564	237				
2	2.633	305	Y	6		C-6+
3	3.056	103779		1		C-1
4	3.692	7743		2		C-2
5	4.371	297		8		C-3
TOTAL		112361			0	


DESTEC KERN FRONT
2-25-93 PROJECT # 027-343
HC SAMPLE BLANK



CHROMATOGRAM 14 MEMORIZED
WARNING NO PEAK

DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 MIDTEST BLANK


18:46:07



CHROMATOGRAM	19	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.649	1105		6		C-6+
		-----			-----	
	TOTAL	1105			0	

DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 1 GENERATOR
 HC SAMPLE # 1


14:03:50



CHROMATOGRAM	13	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.642	2294		6	2.1669	C-6+
2	3.055	441		1	2.5884	C-1
3	4.4	215		8	0.3981	C-3
4	12.145	163		16	0.188	C-5
5	12.311	315		16	0.3632	C-5
TOTAL		3428			5.7047	

GROUP(NAME)	CONC
C-1	2.5884
C-2	0
C-3	0.3981
C-4	0
C-5	0.5513
C-6+	2.1669


DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 1 GENERATOR
 HC SAMPLE # 2



CHROMATOGRAM 14	MEMORIZED					
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.642	2039		6	1.9265	C-6+
2	2.958	183	V	1	1.075	C-1
3	3.04	420	V	1	2.465	C-1
4	4.088	51				
5	15.158	54		15	0.0617	C-5
TOTAL		2747			5.5281	

GROUP(NAME)	CONC
C-1	3.54
C-2	0
C-3	0
C-4	0
C-5	0.0617
C-6+	1.9265

DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 1 GENERATOR
 HC SAMPLE # 3




14:52:57

CHROMATOGRAM 15	MEMORIZED					
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.651	7376		6	6.9674	C-6+
2	3.055	298		1	1.7493	C-1
3	4.213	230		8	0.4265	C-3
4	11.767	310		17	0.3571	C-5
TOTAL		8214			9.5003	

GROUP(NAME)	CONC
C-1	1.7493
C-2	0
C-3	0.4265
C-4	0
C-5	0.3571
C-6+	6.9674


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 1 TURBINE
 HC SAMPLE # 1



CHROMATOGRAM	6	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.651	1149		6	1.0854	C-6+
2	3.053	11534		1	67.7079	C-1
3	3.592	934		2	2.603	C-2
4	4.73	169		3	0.3134	C-3
5	12.278	183		16	0.2111	C-5
TOTAL		13970			71.9208	

GROUP(NAME)	CONC
C-1	67.7079
C-2	2.603
C-3	0.3134
C-4	0
C-5	0.2111
C-6+	1.0854

DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 1 TURBINE
 HC SAMPLE # 2




11:52:37

CHROMATOGRAM PKNO	7 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.627	1045		6	0.9872	C-6+
2	3.054	11992	V	1	70.3967	C-1
3	3.683	945		2	2.6324	C-2
4	4.735	207		3	0.3834	C-3
TOTAL		14189			74.3997	

GROUP(NAME)	CONC
C-1	70.3967
C-2	2.6324
C-3	0.3834
C-4	0
C-5	0
C-6+	0.9872

DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 2 GENERATOR
 HC SAMPLE # 1


15:17:32



CHROMATOGRAM 16 PKNO	TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.642	1699		6	1.6044	C-6+
2	3.058	949		1	5.5684	C-1
3	5.082	60				
4	5.475	111	V			
5	5.533	110				
6	14.508	145	V			
TOTAL		3074			7.1728	

GROUP(NAME)	CONC
C-1	5.5684
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	1.6044


DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 2 GENERATOR
 HC SAMPLE # 2



CHROMATOGRAM	17	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.645	6369		6	6.0158	C-6+
2	3.055	1664		1	9.767	C-1
3	3.611	122		2	0.3399	C-2
TOTAL		8155			16.1228	

GROUP(NAME)	CONC
C-1	9.767
C-2	0.3399
C-3	0
C-4	0
C-5	0
C-6+	6.0158


DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 2 GENERATOR
 HC SAMPLE # 3



PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.642	2795		6	2.6399	C-6+
2	3.057	2409		1	14.1423	C-1
3	3.605	215		2	0.5988	C-2
4	11.766	127		17	0.1463	C-5
5	14.198	161				
6	14.533	71				
7	14.655	62	V			
8	15.53	115		15	0.1326	C-5
TOTAL		5955			17.6598	

GROUP(NAME)	CONC
C-1	14.1423
C-2	0.5988
C-3	0
C-4	0
C-5	0.2788
C-6+	2.6399


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 2 TURBINE
 HC SAMPLE # 1



CHROMATOGRAM	9	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.647	13262		6	12.527	C-6+
2	3.056	52364		1	307.3803	C-1
3	3.605	4118		2	11.4735	C-2
4	4.361	56		8	0.1032	C-3
5	4.745	977		3	1.8123	C-3
TOTAL		70776			333.2962	

GROUP(NAME)	CONC
C-1	307.3803
C-2	11.4735
C-3	1.9155
C-4	0
C-5	0
C-6+	12.527


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 2 TURBINE
 HC SAMPLE # 2



CHROMATOGRAM PKNO	10 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.645	12826		6	12.1153	C-6+
2	3.056	52228		1	306.5854	C-1
3	3.604	4091		2	11.4002	C-2
4	4.744	943		3	1.75	C-3
TOTAL		70089			331.8509	

GROUP(NAME)	CONC
C-1	306.5854
C-2	11.4002
C-3	1.75
C-4	0
C-5	0
C-6+	12.1153


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 2 TURBINE
 HC SAMPLE # 3



CHROMATOGRAM	11	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.646	555		6	0.5243	C-6+
2	3.057	59407		1	348.7268	C-1
3	3.605	4835	V	2	13.4726	C-2
4	4.733	1168		3	2.167	C-3
5	10.000	66		11	0.0764	C-5
6	10.152	142		11	0.1631	C-5
TOTAL		66173			365.1301	


GROUP(NAME)	CONC
C-1	348.7268
C-2	13.4726
C-3	2.167
C-4	0
C-5	0.2396
C-6+	0.5243


DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 1 & # 2
 HC SAMPLE BLANK





CHROMATOGRAM	12	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.648	361		6	0.3413	C-6+
2	3.056	934		1	5.4844	C-1
TOTAL		1296			5.8257	


GROUP(NAME)	CONC
C-1	5.4844
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0.3413














PETRO CHEM ENVIRONMENTAL SERVICES, INC.
 3207 Antonino Avenue, Bakersfield, CA 93308
 (805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: Terry Rowles

ANALYSIS REQUEST

COMPANY <u>Destec</u>		LOCATION/UNIT <u>Kern Front Turbine #2</u>					EPA Method 5/gravimetric				
REPORT # <u>027-343</u>		SAMPLER <u>RJK/DCJ</u>									
METHOD <u>Method 5</u>		REPORT ATTN. <u>Terry Rowles</u>			PO#						
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas						
301	P/N #1 (Run 1)	2/25/93	/			/					
302	Filter #1	"		/		/					
303	Impinger #1A	"	/			/					
304	" #1B	"	/			/					
305	" #1C	"	/			/					
306	P/N #2 (Run 2)	2/26/93	/			/					
307	Filter #2	"		/		/					
308	Impinger #2A	"	/			/					
309	" #2B	"	/			/					
310	" #2C	"	/			/					
311	DI H ₂ O Blank (used to rinse Run #2 only)	"	/			/					
312	Post Test P/N Blank	"	/			/					
313	Post test Method filter blank	"		/		/					

COMMENTS:

RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
<u>D. Towne</u>	<u>2/26/93</u>		
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
CHAIN OF CUSTODY RECORD

MAIN OFFICE
313 Daniels Lane
Bakersfield, CA 93307
(805) 327-7300 FAX (805) 327-3459

LAB OFFICE
3207 Antonino Avenue
Bakersfield, CA 93308
(805) 631-9332 FAX (805) 327-0860

ANALYSIS REQUEST

LABORATORY				LAB ID#			EPA Method 5/bioanalytic	C-6t GC/FID	HOLD ?		
COMPANY Destec		LOCATION/UNIT Kern Front Turbine #2									
REPORT 027-343		SAMPLED BY DCJ/RTK									
METHOD Method 5		DELIVER REPORT TO:		PCES PO#							
SAMPLE ID#	SAMPLE DESCRIPTION		SAMPLE DATE	Liq	Filter	Gas					
401	H/C Midtest Blank		2/25/93			/		/			
402	H/C Mystery Blank		2/24/93			/		/			
403	High Pressure Soft Water 14:58		2/26/93	/			?		/		
404	Low Pressure Feed Water 15:00		"	/			?		/		
405	Low Pressure Steam 15:00		"	/			?		/		
406	L.P. Drum Cont. Standdown 15:03		"	/			?		/		
407	High Pressure Steam 16:34		"	/			?		/		
408	Oxy 16:35		"	/			?		/		

COMMENTS:

RELINQUISHED BY: D. Stone		DATE 2/26/93	RECEIVED BY:		DATE
RELINQUISHED BY:		DATE	RECEIVED BY:		DATE
RELINQUISHED BY:		DATE	RECEIVED BY:		DATE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
 3207 Antonino Avenue, Bakersfield, CA 93308
 (805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: Terry Rowles

ANALYSIS REQUEST

COMPANY <u>Destec</u>		LOCATION/UNIT <u>Kern Front Turbine #1</u>					EPA Method 5/Gas/metric				
REPORT # <u>027-343</u>		SAMPLER <u>RJK/DO7</u>									
METHOD <u>Method 5</u>		REPORT ATTN. <u>Terry Rowles</u>			PO#						
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas						
201	Impinger Mid test Blank	2/24/93	/			/					
202	Filter	"		/		/					
203	P/N	"	/			/					
204	High Pressure Feed Steam Sample	"	/			/					
205	Low Pressure Drum Cont Blowdown	"	/			/					
206	High Pressure Steam	"	/			/					
207	Low Pressure Steam	"	/			/					

COMMENTS:			
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
<u>D. Rowles</u>	<u>2/24/93</u>		
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
 3207 Antonino Avenue, Bakersfield, CA 93308
 (805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: Terry Rowles

ANALYSIS REQUEST

COMPANY Dexter		LOCATION/UNIT Ken Froot Turbine #1					C ₁ -C ₆ + GC/FID				
REPORT # 027-343		SAMPLER RJK / DC7									
METHOD Method 18		REPORT ATTN Terry Rowles			PO#						
SAMPLE NO/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas						
	HC #1	12:00			/	/					
	#2	12:40			/	/					
	#3	13:20			/	/					
	Pretest Field blank				/	/					

COMMENTS: 0.2 ppm v detection limit C₁-C₆+			
RELINQUISHED BY: D. Rowles		DATE 2/24/93	
RECEIVED BY:		DATE	
RELINQUISHED BY:		DATE	
RECEIVED BY:		DATE	
RELINQUISHED BY:		DATE	
RECEIVED BY:		DATE	

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
 3207 Antonino Avenue, Bakersfield, CA 93308
 (805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: Terry Rowles

ANALYSIS REQUEST

COMPANY <u>Destec</u>		LOCATION/UNIT <u>Kern Front Turbine #1</u>				EPA Method 5 Gravimetric				
REPORT # <u>027-343</u>		SAMPLER <u>RSK DCU</u>								
METHOD <u>Method 5</u>		REPORT ATTN. <u>Terry Rowles</u>		PO#						
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas					
101	P/N #1	2/23/93	/			/				
102	Filter #1	"		/		/				
103	Impinger #1A	"	/			/				
103	" #1B	"	/			/				
104	P/N #2	2/24/93	/			/				
105	Filter #2	"		/		/				
106	Impinger #2A	"	/			/				
107	" #2B	"	/			/				
108	" #2C	"	/			/				
109	P/N pretest field blank	2/23/93	/			/				
110	Filter " " "	"		/		/				
111	Impinger " " "	"	/			/				
112	Filter Reagent blank	"	/			/				
113	DI H ₂ O " "	"	/			/				

COMMENTS:

RELINQUISHED BY: <u>D. Rowles</u>	DATE <u>2/24/93</u>	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
 3207 Antonino Avenue, Bakersfield, CA 93308
 (805) 631-9332 FAX (805) 327-0860

CHAIN OF CUSTODY RECORD

Submitted to: EAS

ANALYSIS REQUEST

COMPANY Destec		LOCATION/UNIT Kern Front #1 & #2				Sulfur Specifications	Total Sulfur as H ₂ S				
REPORT # 027-343		SAMPLER RJK									
METHOD		REPORT ATTN. Terry Rowles		PO# 49144							
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas						
Bag Fuel Gas #1		2/22/93			-	-	-				30730
Bag Fuel Gas #2		2/22/93			-	✓	-				30731

COMMENTS:

72 hour holding time from sample date.

RELINQUISHED BY: D Smallwood	DATE 2/22/93	RECEIVED BY: Cox Cox	DATE 2/23/93
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
 3207 Antonino Avenue, Bakersfield, CA 93308
 (805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: Terry Rowles

ANALYSIS REQUEST

COMPANY Destec		LOCATION/UNIT Kern Front Turbine #1					C ₁ -C ₆ +GC/FID				
REPORT # 027-343		SAMPLER DO7									
METHOD Method 18		REPORT ATTN. Terry Rowles			PO#						
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas						
	#1 HC #2	2/23			/	/					
	HC #3	2/23			/	/					
Replacement Samples For Turbine #1											

COMMENTS:			
RELINQUISHED BY: <u>T. Rowles</u>	DATE 2/23/93	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
 3207 Antonino Avenue, Bakersfield, CA 93308
 (805) 327-7300 FAX (805) 327-3459

CHAIN OF CUSTODY RECORD

Submitted to: Terry Rawles

ANALYSIS REQUEST

COMPANY <u>Dostec</u>		LOCATION/UNIT <u>KensFron Turbine #2</u>				<u>C1-C6+GC/FID</u>				
REPORT # <u>027-343</u>		SAMPLER <u>RJK/DC7</u>								
METHOD <u>Method 18</u>		REPORT ATTN. <u>Terry Rawles</u>		PO#						
SAMPLE No/ID	SAMPLE DESCRIPTION	SAMPLE DATE	Liq	Filter	Gas					
	<u>HC #1</u>	<u>2/25</u>			<u>/</u>	<u>/</u>				
	<u>HC #2</u>	<u>"</u>			<u>/</u>	<u>/</u>				
	<u>HC #3</u>	<u>"</u>			<u>/</u>	<u>/</u>				
	<u>Post Test blank</u>	<u>"</u>			<u>/</u>	<u>/</u>				

COMMENTS:			
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
<u>D. Stinson</u>	<u>2/25/93</u>		
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE
RELINQUISHED BY:	DATE	RECEIVED BY:	DATE

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
PITOT TUBE CALIBRATION

PITOT TUBE ID. # **P12Q-10**
DATE: **2-4-93**
CALIBRATED BY: **RJK**

"A" SIDE CALIBRATION				
RUN #	ΔP_{std} cm H₂O (in. H₂O)	$\Delta P(s)$ cm H₂O (in. H₂O)	$C_p(s)$	DEVIATION $C_p(s) - C_p(A)$
1	0.260	0.415	0.784	-0.007
2	0.265	0.410	0.796	0.005
3	0.270	0.420	0.794	0.003
			C_p (SIDE A)	0.791

"B" SIDE CALIBRATION				
RUN #	ΔP_{std} cm H₂O (in. H₂O)	$\Delta P(s)$ cm H₂O (in. H₂O)	$C_p(s)$	DEVIATION $C_p(s) - C_p(B)$
1	0.265	0.415	0.791	0.000
2	0.260	0.410	0.788	-0.003
3	0.270	0.420	0.794	0.003
			C_p (SIDE B)	0.791

C_p (SIDE A) - C_p (SIDE B) =	0.000	0.791
--	--------------	--------------

$$C_p = .99 * \Delta P_{std} / \Delta P(s)$$

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
DRY GAS METER CALIBRATION

DATE:	1-27-93	AMBIENT TEMP °F:	62
TECH:	BDM	BAROMETRIC Pbar:	29.54
METER I.D.#	1002	TEST METER ID#:	SSM104564
		TEST METER Mct:	1.023

APPROXIMATE CFM		0.75	0.50	0.30
STD TEST METER VOLUME CF	INITIAL	0.00	0.00	0.00
	FINAL	7.41	10.01	10.05
	TOTAL	7.41	10.01	10.05
FIELD GAS METER VOLUME CF	INITIAL	109.20	119.00	130.10
	FINAL	116.69	129.56	140.89
	TOTAL	7.49	10.56	10.79
STD TEST METER TEMP (°F)		62.5	60.0	60.0
FIELD GAS METER TEMP (°F)	IN	69.0	71.0	69.5
	OUT	54.0	60.0	63.0
	AVERAGE	61.5	65.5	66.3
STD TEST METER PRESSURE ("H₂O)		-0.60	-0.30	-0.15
FIELD GAS METER PRESSURE ("H₂O)		1.40	0.60	0.21
FIELD GAS METER, Mct		1.006629	0.978514	0.963789

FIELD AVERAGE Mct: **0.982977**

H@: **1.4324**

PETRO CHEM ENVIRONMENTAL SERVICES, INC.
DRY GAS METER CALIBRATION

DATE:	1-28-93	AMBIENT TEMP °F:	61
TECH:	BDM	BAROMETRIC Pbar:	30.22
METER I.D.#	1003	TEST METER ID#:	SEM104564
		TEST METER Mcf:	1.023

APPROXIMATE CFM		.75	0.50	0.30
STD TEST METER VOLUME CF	INITIAL	0.00	0.00	0.00
	FINAL	7.59	10.04	10.01
	TOTAL	7.59	10.04	10.01
FIELD GAS METER VOLUME CF	INITIAL			
		807.30	815.30	826.50
	FINAL	814.90	825.75	837.19
	TOTAL	7.60	10.45	10.69
STD TEST METER TEMP (°F)				
		57.0	60.5	61.0
FIELD GAS METER TEMP (°F)	IN			
		59.0	65.5	65.5
	OUT	60.0	75.0	72.5
	AVERAGE	59.5	70.3	69.0
STD TEST METER PRESSURE ("H₂O)				
		-0.60	-0.30	-0.15
FIELD GAS METER PRESSURE ("H₂O)				
		0.90	0.40	0.18
FIELD GAS METER, Mcf		1.024351	1.000301	0.972209

FIELD AVERAGE Mcf:	0.998954	HQ:	0.8432
---------------------------	-----------------	------------	---------------

SCOTT - MARRIN, INC.

2001 THIRD ST., UNIT H

RIVERSIDE, CALIFORNIA 92507

REPORT OF ANALYSIS

CUSTOMER ORDER NUMBER: 1653/Reanalysis

CYLINDER NUMBER CC37890

COMPONENT CONCENTRATION (v/v)

Carbon Monoxide 6.86 ± 0.14 ppm

Nitric Oxide 7.27 ± 0.15 ppm

Sulfur Dioxide 6.83 ± 0.14 ppm

Nitrogen* Balance

Cylinder pressure: 1600 psig

*Oxygen-free

Replicate	01/03/91	6.87 ppm
Analysis		6.92 ppm
Data On		<u>6.83 ppm</u>
CO:	Mean	6.87 ppm

Expiration Date CO: 07/03/92

Replicate	01/03/91	7.25 ppm
Analysis		7.25 ppm
Data On		<u>7.28 ppm</u>
NO:	Mean	7.26 ppm

Expiration Date NO: 07/03/92



SCOTT-MARRIN, INC.

2001 THIRD ST. • UNIT H • RIVERSIDE, CA 92507
TELEPHONE (714) 784-1240

RECEIVED FEB 14 1991

REPORT OF ANALYSIS
EPA PROTOCOL GAS MIXTURES

PETR01

TO:

RICK WILLIAMS
PETROCHEM ENVIRONMENTAL
3207 ANTONINO AVE.
BAKERSFIELD, CA 93308

DATE : 02/11/91

CUSTOMER ORDER NUMBER: 01138

PAGE 1

COMPONENT		CONCENTRATION (v/v)	REFERENCE STANDARD	ANALYZER MAKE, MODEL, S/N, DETECTION	EXPIRATION DATE	REPLICATE ANALYSIS DATA	
CYLINDER NO.:			CC68780				
Nitric Oxide	17.61 ± 0.35 ppm	GHS Cylinder # CC28863 @ 19.31 ppm	Monitor Labs Model 8440	S/N 136 Continuous Chemiluminescence Last Cal Date: 10/23/90	07/22/91	<u>01/11/91</u>	<u>01/22/91</u>
			17.62 ppm			17.62 ppm	
			17.56 ppm			17.56 ppm	
			<u>17.56 ppm</u>			<u>17.69 ppm</u>	
			Mean: 17.58 ppm			17.63 ppm	
Carbon Monoxide	17.98 ± 0.36 ppm	GHS Cylinder # CC12168 @ 17.73 ppm	Carle Insts Model 8800	S/N 8249 Methanation/FID Gas Chromatography Last Cal Date: 12/24/90	07/29/91	<u>01/22/91</u>	<u>01/29/91</u>
			18.82 ppm			17.99 ppm	
			17.93 ppm			18.18 ppm	
Nitrogen, O2-Free Balance						<u>17.98 ppm</u>	<u>17.93 ppm</u>
Cylinder Pressure: 2000 psig						Mean: 17.95 ppm	18.81 ppm

ppm = umole/mole

% = mole-%

The above analyses were performed in accordance with EPA-1987 Traceability Protocol # 1, Section 3.0.4, Procedure G1.

Analyst:

Mark Monson

M.J. Monson

Approved:

J.T. Marrin
J.T. Marrin

The only liability of this company for gas which fails to comply with this analysis shall be replacement or reanalysis thereof by the company without extra cost.

STANDARD CALIBRATION GASES IN ALUMINUM CYLINDERS



AIRCO

518655

Airco Electronic Gases
Union Landing & River Roads
P.O. Drawer No. 272
Riverton
New Jersey 08077
Telephones: Marketing: 609-829-7878
Prod. & Admin.: 609-829-
International: 609-829-79

CERTIFICATE OF ANALYSIS - EPA PROTOCOL GAS MIX

CUSTOMER: Bakersfield Welding Supply

CYLINDER #: CC-17885

CYLINDER PRESSURE: 1650 psig

LABORATORY: Riverton NJ

CERTIFICATION DATE: 11/2/92

EXPIRATION DATE: 5/2/93

REFERENCE #: 24275

MIXTURE COMPONENTS	ACTUAL MIXTURE CONCENTRATION	AIRCO INTERMEDIATE STANDARD CYLINDER #	CONC.	NIST SRM#
Nitric Oxide	40.0 ppm	CC-14977	49.8 ppm	1683B
Carbon Monoxide	39.9 ppm	CC-43310	49.8 ppm	1678C

BALANCE GAS: Nitrogen

COMPONENT 1 GAS ANALYSIS PROCEDURE

MAKE/MODEL/SER#:

LAST MULTIPOINT CALIBRATION DATE:

Chemiluminescence

Beckman, 952, 0100204

8/3/92

COMPONENT 2 GAS ANALYSIS PROCEDURE

MAKE/MODEL/SER#:

LAST MULTIPOINT CALIBRATION DATE:

Non-Dispersive Infrared

Horiba, CO/Analyzer, 56255601

8/3/92

R=REFERENCE STANDARD

Z=ZERO GAS

S=SAMPLE GAS

1ST COMPONENT

Nitric Oxide

1ST ANALYSIS: DATE

10/26/92

ANALYST

A. Lattanze

1) Z 0000

R

4550

S

3635

CONC (1)

39.8 ppm

2) R 4540

Z

0000

S

3640

CONC (2)

39.9 ppm

3) R 4540

S

3630

Z

0000

CONC (3)

39.8 ppm

AVE CONC

39.8 ppm

2ND ANALYSIS: DATE

11/2/92

ANALYST

A. Lattanze

1) Z 0000

R

4385

S

3540

CONC (1)

40.2 ppm

2) R 4400

Z

0000

S

3535

CONC (2)

40.0 ppm

3) R 4410

S

3540

Z

0000

CONC (3)

40.0 ppm

AVE CONC

40.1 ppm

2ND COMPONENT

Carbon Monoxide

1ST ANALYSIS: DATE

10/26/92

ANALYST

A. Lattanze

1) Z 000

R

491

S

393

CONC (1)

39.9 ppm

2) R 491

Z

000

S

393

CONC (2)

39.9 ppm

3) R 491

S

393

Z

000

CONC (3)

39.9 ppm

AVE CONC

39.9 ppm

2ND ANALYSIS: DATE

11/2/92

ANALYST

A. Lattanze

1) Z 000

R

493

S

395

CONC (1)

39.9 ppm

2) R 493

Z

000

S

395

CONC (2)

39.9 ppm

3) R 493

S

395

Z

000

CONC (3)

39.9 ppm

AVE CONC

39.9 ppm

THIS CALIBRATION STANDARD HAS BEEN CERTIFIED VERSUS EPA TRACEABILITY
PROTOCOL NO. 1, PROCEDURE G1, AND ANALYSES PERFORMED PER SECTION 3.0.4.
CERTIFIED CONCENTRATION: Nitric Oxide = 40.0 ppm; Carbon Monoxide = 39.9 ppm

APPROVED BY [Signature] Nitrogen = Balance

A member of The ACC LABORATORY MANAGER



512041

Airco Electronic Gases
Union Landing & River Roads
P.O. Drawer No. 272
Riverton
New Jersey 08077
Telephones: Marketing: 609-829-7878
Prod. & Admin.: 609-829-7914
International: 609-829-7917

CERTIFICATE OF ANALYSIS - EPA PROTOCOL GAS MIX

CUSTOMER: Bakersfield Welding (Saugas, CA)
CYLINDER #: CC-77462 CERTIFICATION DATE: 10/12/92
CYLINDER PRESSURE: 1650 psig EXPIRATION DATE: 4/12/93
LABORATORY: Riverton, NJ REFERENCE #: 23698

MIXTURE COMPONENTS	ACTUAL MIXTURE CONCENTRATION	AIRCO INTERMEDIATE STANDARD CYLINDER #	CONC.	NIST SRM#
Nitric Oxide	78.2 ppm	CC-69954	100 ppm	1684B
Carbon Monoxide	81.4 ppm	CC-3138	112 ppm	1679C

BALANCE GAS: Nitrogen

COMPONENT 1 GAS ANALYSIS PROCEDURE Chemiluminescence
MAKE/MODEL/SER#: Beckman, 952, 0100204
LAST MULTIPOINT CALIBRATION DATE: 8/3/92

COMPONENT 2 GAS ANALYSIS PROCEDURE Non-Dispersive Infrared
MAKE/MODEL/SER#: Beckman; 866; 1000049
LAST MULTIPOINT CALIBRATION DATE: 8/3/92
R=REFERENCE STANDARD Z=ZERO GAS S=SAMPLE GAS

1ST COMPONENT Nitric Oxide

1ST ANALYSIS: DATE 10/5/92 ANALYST A. Lattanze
1) Z 0000 R 3690 S 2880 CONC (1) 78.0 ppm
2) R 3690 Z 0000 S 2880 CONC (2) 78.0 ppm
3) R 3690 S 2880 Z 0000 CONC (3) 78.0 ppm
AVE CONC 78.0 ppm
2ND ANALYSIS: DATE 10/12/92 ANALYST A. Lattanze
1) Z 0000 R 3700 S 2900 CONC (1) 78.4 ppm
2) R 3700 Z 0000 S 2900 CONC (2) 78.4 ppm
3) R 3700 S 2900 Z 0000 CONC (3) 78.4 ppm
AVE CONC 78.4 ppm

2ND COMPONENT Carbon Monoxide

1ST ANALYSIS: DATE 10/5/92 ANALYST A. Lattanze
1) Z 000 R 222 S 163 CONC (1) 82.2 ppm
2) R 222 Z 000 S 161 CONC (2) 81.2 ppm
3) R 222 S 163 Z 000 CONC (3) 82.2 ppm
AVE CONC 81.9 ppm
2ND ANALYSIS: DATE 10/12/92 ANALYST A. Lattanze
1) Z 000 R 221 S 160 CONC (1) 81.1 ppm
2) R 222 Z 000 S 160 CONC (2) 80.7 ppm
3) R 222 S 160 Z 000 CONC (3) 80.7 ppm
AVE CONC 80.8 ppm

THIS CALIBRATION STANDARD HAS BEEN CERTIFIED VERSUS EPA TRACEABILITY
PROTOCOL NO. 1, PROCEDURE G1, AND ANALYSES PERFORMED PER SECTION 3.0.4.
CERTIFIED CONCENTRATION: Nitric Oxide = 78.2 ppm; Carbon Monoxide = 81.4 ppm
Nitrogen = Balance

APPROVED BY J. L. [Signature]
A member of The AIRCO LABORATORY MANAGER

PETRO CHEM ENVIRONMENTAL SERVICES, INC.

CALIBRATION GAS CERTIFICATE

DATE: 12-2-91
ANALYST: TIM BRENNAN

TANK #: LK-273312
CONTENTS: Oxygen in Nitrogen

	SET #1	SET #2	SET #3
RUN #1	15.0	15.1	15.0
RUN #2	15.0	15.1	15.0
RUN #3	15.1	15.0	15.1
AVERAGE	15.0	15.1	15.0

TOTAL AVERAGE CONCENTRATION

15.0 %O2

Expires: 6-2-93

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 0a7-343

LOCATION/UNIT: Blanks

DATE TESTED: 2/22/93

ANALYST: DGS

RUN # Pre test

PROBE/NOZZLE/FILTER TOP

VOL- 164 ml

DISH # <u>51</u> #1	#2	#3	AVERAGE
FINAL (g) <u>80.0515</u>	<u>80.0516</u>		<u>80.0516</u>
TARE (g) <u>80.0505</u>			<u>80.0505</u>
NET (g)			<u>0.0011</u>

FILTER # 513

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6133</u>	<u>0.6132</u>		<u>0.6133</u>
TARE (g) <u>0.6135</u>			<u>0.6135</u>
NET (g)			<u>0</u>

CONDENSABLE (aliquot 100 ml 1284 ml)

DISH # <u>59</u> #1	#2	#3	AVERAGE
FINAL (g) <u>80.8203</u>	<u>80.8201</u>		<u>80.8202</u>
TARE (g) <u>80.8202</u>			<u>80.8202</u>
NET (g)			<u>0</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Deske

REPORT: 027-343

LOCATION/UNIT: Blanks

DATE TESTED: 2/24/93

ANALYST: DGS

RUN # mid test

PROBE/NOZZLE/FILTER TOP

VOL-234 ml

DISH # <u>50</u> #1	#2	#3	AVERAGE
FINAL (g) <u>77.4980</u>	<u>77.4979</u>		<u>77.4980</u>
TARE (g) <u>77.4964</u>			<u>77.4964</u>
NET (g)			<u>0.0016</u>

FILTER # 517

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6105</u>	<u>0.6104</u>		<u>0.6105</u>
TARE (g) <u>0.6106</u>			<u>0.6106</u>
NET (g)			<u>0</u>

CONDENSABLE (aliquot 100ml / 220ml)

DISH # <u>7</u> #1	#2	#3	AVERAGE
FINAL (g) <u>65.0509</u>	<u>65.0508</u>		<u>65.0509</u>
TARE (g) <u>65.0505</u>			<u>65.0505</u>
NET (g)			<u>0.0004</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Destec

REPORT: 027-343

LOCATION/UNIT: Blanks

DATE TESTED: 2/26/93

ANALYST: DGJ

RUN # Dost Test

PROBE/NOZZLE/FILTER TOP

VOL-205 ml

DISH # <u>62</u> #1	#2	#3	AVERAGE
FINAL (g) <u>90.2265</u>	<u>90.2263</u>		<u>90.2264</u>
TARE (g) <u>90.2258</u>			<u>90.2258</u>
NET (g)			<u>0.0006</u>

FILTER # 426

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6051</u>	<u>0.6051</u>		<u>0.6051</u>
TARE (g) <u>0.6053</u>			<u>0.6053</u>
NET (g)			<u>0</u>

CONDENSABLE (aliquot 100ml / 270ml)

DISH # <u>19</u> #1	#2	#3	AVERAGE
FINAL (g) <u>66.1554</u>	<u>66.1553</u>		<u>66.1554</u>
TARE (g) <u>66.1550</u>			<u>66.1550</u>
NET (g)			<u>0.0004</u>

LABORATORY ANALYSIS
EPA METHOD 5 - PARTICULATE ANALYSIS

COMPANY: Deste

REPORT: 027-343

LOCATION/UNIT: Kern Front

DATE TESTED: 2/23/93

ANALYST: DGS

RUN # Blanks

PROBE/NOZZLE/FILTER TOP				VOL-
DISH #	#1	#2	#3	AVERAGE
FINAL (g)				
TARE (g)				
NET (g)				

FILTER # 516

#1	#2	#3	AVERAGE
FINAL (g) <u>0.6155</u>	<u>0.6154</u>		<u>0.6155</u>
TARE (g) <u>0.6155</u>			<u>0.6155</u>
NET (g)			<u>0</u>

H₂O

CONDENSABLE (aliquot 100ml / 130ml)

DISH #	#1	#2	#3	AVERAGE
#27				
FINAL (g) <u>81.1217</u>	<u>81.1217</u>			<u>81.1218</u>
TARE (g) <u>81.1217</u>				<u>81.1217</u>
NET (g)				<u>0.0001</u>

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

REPORT: 027-343

LOCATION/UNIT: Blanks

DATE TESTED: 2/18/19/93

ANALYST: DHS

SAMPLE # ^{Mellor} Lab Reagent Blank

aliquot - 100 ml

TIN # 44			
# 1	# 2	# 3	AVERAGE
final (g) 1.57544	final (g) 1.57558 ✓	final (g) 1.57559 ✓	1.57559
tare (g) 1.57529	tare (g) _____	tare (g) _____	1.57529
NET (g)	NET (g)	NET (g)	0.00030

SAMPLE # Empty Dish

aliquot - 0 ml

TIN # 34			
# 1	# 2	# 3	AVERAGE
final (g) 1.58753	final (g) 1.58774 ✓	final (g) 1.58770 ✓	1.58772
tare (g) 1.58740	tare (g) _____	tare (g) _____	1.58740
NET (g)	NET (g)	NET (g)	0.00032

SAMPLE # _____

aliquot - _____

TIN #			
# 1	# 2	# 3	AVERAGE
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	_____
NET (g)	NET (g)	NET (g)	

SAMPLE # _____

aliquot - _____

TIN #			
# 1	# 2	# 3	AVERAGE
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	_____
NET (g)	NET (g)	NET (g)	

LABORATORY ANALYSIS
EPA METHOD 5 - ORGANIC ANALYSIS

COMPANY: Destec

REPORT: 027-343

LOCATION/UNIT: Blanks

DATE TESTED: 2/18/19/93

ANALYST: DGS

SAMPLE # D1 H₂O (2/18/93) aliquot - 200 ml

TIN # 42	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.59371</u>	final (g) <u>1.59382</u>	final (g) <u>1.59381</u>	<u>1.59382</u>
tare (g) <u>1.59326</u>	tare (g) _____	tare (g) _____	<u>1.59326</u>
NET (g)	NET (g)	NET (g)	<u>0.00056</u>

SAMPLE # D1 H₂O (2/19/93) aliquot - 200 ml

TIN # 41	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.59734</u>	final (g) <u>1.59749</u>	final (g) <u>1.59747</u>	<u>1.59748</u>
tare (g) <u>1.59706</u>	tare (g) _____	tare (g) _____	<u>1.59706</u>
NET (g)	NET (g)	NET (g)	<u>0.00042</u>

SAMPLE # Field MeCl₂ aliquot - 229 ml

TIN # 45	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g) <u>1.57932</u>	final (g) <u>1.57952</u>	final (g) <u>1.57950</u>	<u>1.57951</u>
tare (g) <u>1.57903</u>	tare (g) _____	tare (g) _____	<u>1.57903</u>
NET (g)	NET (g)	NET (g)	<u>0.00048</u>

SAMPLE # _____ aliquot - _____

TIN #	# 2	# 3	AVERAGE
# 1	# 2	# 3	
final (g)	final (g)	final (g)	
tare (g) _____	tare (g) _____	tare (g) _____	
NET (g)	NET (g)	NET (g)	

PETRO CHEM ENVIRONMENTAL SERVICES LABORATORY

QUALITY CONTROL - METHOD 5

Q A BATCH #: 5-93-0013

DI H₂O FROM ANTONINO AVE

VOLUME (ml): 250 ml

DISH #:		AVERAGE
<u>43</u>		
FINAL WT. (g): <u>78.2221</u>	FINAL WT. (g): <u>78.2218</u>	FINAL WT. (g): <u>78.2220</u>
TARE WT. (g): <u>78.2218</u>	TARE WT. (g): _____	TARE WT. (g): <u>78.2218</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0.0002</u>

DI H₂O FROM DANIELS LN.

VOLUME (ml): 250 ml

DISH #:		AVERAGE
<u>20</u>		
FINAL WT. (g): <u>72.3966</u>	FINAL WT. (g): <u>72.3965</u>	FINAL WT. (g): <u>72.3966</u>
TARE WT. (g): <u>72.3956</u>	TARE WT. (g): _____	TARE WT. (g): <u>72.3956</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0.0010</u>

EMPTY DISH

DISH #:		AVERAGE
<u>65</u>		
FINAL WT. (g): <u>80.9385</u>	FINAL WT. (g): <u>80.9388</u>	FINAL WT. (g): <u>80.9387</u>
TARE WT. (g): <u>80.9386</u>	TARE WT. (g): _____	TARE WT. (g): <u>80.9386</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0.0001</u>


FILTER BLANK

FILTER #:		AVERAGE
<u>530</u>		
FINAL WT. (g): <u>0.6148</u>	FINAL WT. (g): <u>0.6147</u>	FINAL WT. (g): <u>0.6148</u>
TARE WT. (g): <u>0.6148</u>	TARE WT. (g): _____	TARE WT. (g): <u>0.6148</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0</u>

RECOVERY SAMPLE

VOLUME (ml): 100 ml

DISH #:		AVERAGE
<u>12</u>		
FINAL WT. (g): <u>76.9234</u>	FINAL WT. (g): <u>76.9229</u>	FINAL WT. (g): <u>76.9232</u>
TARE WT. (g): <u>76.9003</u>	TARE WT. (g): _____	TARE WT. (g): <u>76.9003</u>
NET WT. (g): _____	NET WT. (g): _____	NET WT. (g): <u>0.0229</u>
CONC (g/l): <u>0.2296 g/l Na₂SO₄</u> WT (g): <u>0.02296 g</u>		% RECOVERY: <u>99.7 %</u> <u>(0.0229 / 0.02296) 100</u>



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY : DESTEC OPERATING
DATE : 2-25-93
REPORT : 027-343

DATE RECEIVED : 2-26-93
DATE ANALYZED : 2-26-93
DATE REPORTED: 3-9-93


EPA METHOD 18
LOW RANGE HYDROCARBON ANALYSIS
CALIBRATION DATA AND STATISTICS

METHANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.413	701	5.89E-04
0.825	1426	5.79E-04
4.125	7301	5.65E-04
8.25	14489	5.69E-04
AVERAGE RF		5.76E-04
STD. DEVIATION		9.27E-06
RSD%		1.61%

ETHANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.413	1447	2.85E-04
0.825	2884	2.86E-04
4.125	14647	2.82E-04
8.25	29285	2.82E-04
AVERAGE RF		2.84E-04
STD. DEVIATION		2.05E-06
RSD%		0.72%



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY: DESTEC OPERATING
DATE : 2-25-93
REPORT : 027-343

DATE RECEIVED : 2-26-93
DATE ANALYZED : 2-26-93
DATE REPORTED: 3-9-93


**EPA METHOD 18
LOW RANGE HYDROCARBON ANALYSIS
CALIBRATION DATA AND STATISTICS**

PROPANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.413	2050	2.01E-04
0.825	4274	1.93E-04
4.125	21507	1.92E-04
8.25	43237	1.91E-04
AVERAGE RF		1.94E-04
STD. DEVIATION		4.22E-06
RSD%		2.17%

BUTANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.413	2712	1.52E-04
0.825	5732	1.44E-04
4.125	28432	1.45E-04
8.25	58664	1.41E-04
AVERAGE RF		1.45E-04
STD. DEVIATION		4.25E-06
RSD%		2.92%



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY: DESTEC OPERATING
DATE : 2-25-93
REPORT : 027-343

DATE RECEIVED : 2-26-93
DATE ANALYZED : 2-26-93
DATE REPORTED: 3-9-93

EPA METHOD 18
LOW RANGE HYDROCARBON ANALYSIS
CALIBRATION DATA AND STATISTICS

PENTANE







CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.37	3461	1.07E-04
0.74	6886	1.07E-04
3.7	34739	1.07E-04
7.4	69824	1.06E-04
AVERAGE RF		1.07E-04
STD. DEVIATION		5.43E-07
RSD%		0.51%


HEXANE

CONC. (ppmv)	AREA COUNTS	RESPONSE FACTOR ppmv/AC
0.38	4424	8.59E-05
0.76	8505	8.94E-05
3.8	41301	9.20E-05
7.6	82301	9.23E-05
AVERAGE RF		8.99E-05
STD. DEVIATION		2.59E-06
RSD%		2.88%

COMPANY : DESTEC OPERATING
 UNIT : KERN FRONT TURBINES 1 & 2
 DATE : 2-25-93
 REPORT : 027-343

HYDROCARBON CALIBRATION LINEARITY GRAPHS
 ANALYSIS PERFORMED ON 2-26-93





**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

3207 Antonino Avenue
Bakersfield, California 93308
(805) 327-7300
FAX (805) 327-3459

COMPANY: DESTEC OPERATING
DATE : 2-25-93
REPORT : 027-343

DATE RECEIVED : 2-26-93
DATE ANALYZED : 2-26-93
DATE REPORTED: 3-9-93

EPA METHOD 18
CALIBRATION DRIFT ANALYSIS

POST ANALYSIS CALIBRATION CHECK (0.4ppm STD.)







CONSTITUENT	INITIAL RF	POST RF	%DIFF.
METHANE	5.89E-04	5.73E-04	2.77%
ETHANE	2.85E-04	2.85E-04	0.07%
PROPANE	2.01E-04	1.88E-04	6.65%
BUTANE	1.52E-04	1.39E-04	8.87%
PENTANE	1.07E-04	1.16E-04	-8.87%
HEXANES+	8.59E-05	8.59E-05	0.00%

POST ANALYSIS CALIBRATION CHECK (0.8ppm STD.)


CONSTITUENT	INITIAL RF	POST RF	%DIFF.
METHANE	5.79E-04	6.07E-04	-4.85%
ETHANE	2.86E-04	2.93E-04	-2.49%
PROPANE	1.93E-04	2.01E-04	-3.96%
BUTANE	1.44E-04	1.53E-04	-6.38%
PENTANE	1.07E-04	1.13E-04	-4.75%
HEXANES+	8.94E-05	9.09E-05	-1.69%

COMPANY : DESTEC OPERATING
UNIT : KERN FRONT LUBE OIL VENTS
DATE : 2-18,19-93
REPORT : 027-343

HYDROCARBON CALIBRATION LINEARITY GRAPHS
ANALYSIS PERFORMED ON 2-22-93




DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 2 HC SAMPLE # 3




CHROMATOGRAM 13 MEMORIZED						
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.564	237				
2	2.633	305	V	6		C-6+
3	3.056	103779		1		C-1
4	3.692	7743		2		C-2
5	4.371	297		8		C-3
TOTAL		112361			0	

DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 1 HC SAMPLE # 1



CHROMATOGRAM	8	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.582	816		6		C-6+
2	3.055	115203		1		C-1
3	3.684	3064		2		C-2
4	3.689	5545	V	2		C-2
TOTAL		124627			0	8609


DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 1 HC SAMPLE # 2



CHROMATOGRAM	9	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.633	1863		6		C-6+
2	3.058	103528		1		C-1
3	3.608	2825		2		C-2
4	3.691	4697	V	2		C-2
TOTAL		112914			0	


7522

DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 1 HC SAMPLE # 3




CHROMATOGRAM 10 MEMORIZED						
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.606	1540		6		C-6+
2	3.057	97550		1		C-1
3	3.607	2713		2		C-2
4	3.693	4487	V	2		C-2
TOTAL		106290			0	7200

DESTEC KERN FRONT
 2-25-93 PROJECT # 027-343
 TURBINE # 2 HC SAMPLE # 1




CHROMATOGRAM 11	MEMORIZED					
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.661	722		6		C-6+
2	3.056	138419		1		C-1
3	3.606	3975		2		C-2) 10599
4	3.69	6624	V	2		C-2
5	4.392	443		8		C-3) 748
6	4.74	305		3		C-3
TOTAL		150487			0	

DESTEC KERN FRONT
 2-25-93 REPORT # 027-343
 TURBINE # 2 HC SAMPLE # 2



CHROMATOGRAM	12	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.674	266	V	6		C-6+
2	3.057	99696		1		C-1
3	3.695	7587		2		C-2
4	4.392	232		8		C-3
5	4.742	218		3		C-3
TOTAL		107999			0	450


DESTEC KERN FRONT
2-25-93 PROJECT # 027-343
HC SAMPLE BLANK



CHROMATOGRAM 14 MEMORIZED
WARNING NO PEAK


DESTEC KERN FRONT
2-25-93 PROJECT # 027-343
MIDTEST BLANK

18:46:07



CHROMATOGRAM	19	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.649	1105		6		C-6+
		-----			-----	
	TOTAL	1105			0	

DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 1 GENERATOR
 HC SAMPLE # 1




14:03:50

CHROMATOGRAM	13	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.642	2294		6	2.1669	C-6+
2	3.055	441		1	2.5884	C-1
3	4.4	215		8	0.3981	C-3
4	12.145	163		16	0.188	C-5
5	12.311	315		16	0.3632	C-5
TOTAL		3428			5.7047	

GROUP(NAME)	CONC
C-1	2.5884
C-2	0
C-3	0.3981
C-4	0
C-5	0.5513
C-6+	2.1669


DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 1 GENERATOR
 HC SAMPLE # 2



CHROMATOGRAM	14	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.642	2039		6	1.9265	C-6+
2	2.958	183	V	1	1.075	C-1
3	3.04	420	V	1	2.465	C-1
4	4.088	51				
5	15.158	54		15	0.0617	C-5
TOTAL		2747			5.5281	

GROUP(NAME)	CONC
C-1	3.54
C-2	0
C-3	0
C-4	0
C-5	0.0617
C-6+	1.9265

DESTEC KERN FRONT
 2-19-93 REPORT # 827-343
 LUBE OIL VENT # 1 GENERATOR
 HC SAMPLE # 3




14:52:57

CHROMATOGRAM	15	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.651	7376		6	6.9674	C-6+
2	3.055	298		1	1.7493	C-1
3	4.213	230		8	0.4265	C-3
4	11.767	310		17	0.3571	C-5
TOTAL		8214			9.5003	

GROUP(NAME)	CONC
C-1	1.7493
C-2	0
C-3	0.4265
C-4	0
C-5	0.3571
C-6+	6.9674


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 1 TURBINE
 HC SAMPLE # 1



CHROMATOGRAM PKNO	6 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.651	1149		6	1.0854	C-6+
2	3.053	11534		1	67.7079	C-1
3	3.592	934		2	2.603	C-2
4	4.73	169		3	0.3134	C-3
5	12.278	183		16	0.2111	C-5
TOTAL		13970			71.9208	

GROUP(NAME)	CONC
C-1	67.7079
C-2	2.603
C-3	0.3134
C-4	0
C-5	0.2111
C-6+	1.0854


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 1 TURBINE
 HC SAMPLE # 2



CHROMATOGRAM PKNO	7 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.627	1045		6	0.9872	C-6+
2	3.054	11992	Y	1	70.3967	C-1
3	3.603	945		2	2.6324	C-2
4	4.735	207		3	0.3834	C-3
TOTAL		14189			74.3997	

GROUP(NAME)	CONC
C-1	70.3967
C-2	2.6324
C-3	0.3834
C-4	0
C-5	0
C-6+	0.9872


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 1 TURBINE
 HC SAMPLE # 3



CHROMATOGRAM PKNO	8 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.651	1050		6	0.9919	C-6+
2	3.055	10743		1	63.0603	C-1
3	3.604	784		2	2.1847	C-2
4	4.727	105		3	0.1945	C-3
5	15.169	60		15	0.0687	C-5
TOTAL		12741			66.5001	

GROUP(NAME)	CONC
C-1	63.0603
C-2	2.1847
C-3	0.1945
C-4	0
C-5	0.0687
C-6+	0.9919


DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 2 GENERATOR
 HC SAMPLE # 1



CHROMATOGRAM 16	MEMORIZED					
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.642	1699		6	1.6044	C-6+
2	3.058	949		1	5.5684	C-1
3	5.082	60				
4	5.475	111	V			
5	5.533	110				
6	14.508	145	V			
TOTAL		3074			7.1728	

GROUP(NAME)	CONC
C-1	5.5684
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	1.6044

DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 2 GENERATOR
 HC SAMPLE # 2



15:42:04


CHROMATOGRAM	17	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.645	6369		6	6.0158	C-6+
2	3.055	1664		1	9.767	C-1
3	3.611	122		2	0.3399	C-2
TOTAL		8155			16.1228	

GROUP (NAME)	CONC
C-1	9.767
C-2	0.3399
C-3	0
C-4	0
C-5	0
C-6+	6.0158

DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 2 GENERATOR
 HC SAMPLE # 3

93/02/22


16:05:22



CHROMATOGRAM 18		MEMORIZED		IDNO	CONC	NAME
PKNO	TIME	AREA	MK			
1	2.642	2795		6	2.6399	C-6+
2	3.057	2409		1	14.1423	C-1
3	3.605	215		2	0.5988	C-2
4	11.766	127		17	0.1463	C-5
5	14.198	161				
6	14.533	71				
7	14.655	62	V			
8	15.53	115		15	0.1326	C-5
TOTAL		5955			17.6598	

GROUP(NAME)	CONC
C-1	14.1423
C-2	0.5988
C-3	0
C-4	0
C-5	0.2788
C-6+	2.6399


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 2 TURBINE
 HC SAMPLE # 1



CHROMATOGRAM	9	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.647	13262		6	12.527	C-6+
2	3.056	52364		1	307.3803	C-1
3	3.605	4118		2	11.4735	C-2
4	4.361	56		8	0.1032	C-3
5	4.745	977		3	1.8123	C-3
TOTAL		70776			333.2962	

GROUP(NAME)	CONC
C-1	307.3803
C-2	11.4735
C-3	1.9155
C-4	0
C-5	0
C-6+	12.527


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 2 TURBINE
 HC SAMPLE # 2



CHROMATOGRAM	10	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.645	12826		6	12.1153	C-6+
2	3.056	52228		1	306.5854	C-1
3	3.604	4091		2	11.4002	C-2
4	4.744	943		3	1.75	C-3
TOTAL		70089			331.8509	

GROUP(NAME)	CONC
C-1	306.5854
C-2	11.4002
C-3	1.75
C-4	0
C-5	0
C-6+	12.1153


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 LUBE OIL VENT # 2 TURBINE
 HC SAMPLE # 3



CHROMATOGRAM	11	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.646	555		6	0.5243	C-6+
2	3.057	59407		1	348.7268	C-1
3	3.605	4835	V	2	13.4726	C-2
4	4.733	1168		3	2.167	C-3
5	10.008	66		11	0.0764	C-5
6	10.152	142		11	0.1631	C-5
TOTAL		66173			365.1301	

GROUP(NAME)	CONC
C-1	348.7268
C-2	13.4726
C-3	2.167
C-4	0
C-5	0.2396
C-6+	0.5243

DESTEC KERN FRONT
 2-19-93 REPORT # 027-343
 LUBE OIL VENT # 1 & # 2
 HC SAMPLE BLANK




CHROMATOGRAM	12	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.648	361		6	0.3413	C-6+
2	3.056	934		1	5.4844	C-1
TOTAL		1296			5.8257	

GROUP(NAME)	CONC
C-1	5.4844
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0.3413


MAIN STACK DACK

SYSTEM BLANK
UHP NITROGEN




CHROMATOGRAM 1 MEMORIZED
WARNING NO PEAK

0.40PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL. 1:40




CHROMATOGRAM	2	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.678	4424		6		C-6+
2	3.051	701		1		C-1
3	3.596	1447		2		C-2
4	3.95	221		7		C-2
5	4.717	2050		3		C-3
6	7.39	2712		4		C-4
7	13.31	3461		5		C-5
TOTAL		15016			0	

0.8PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL. 1:20




CHROMATOGRAM PKNO	TIME	3 MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.668	8505		6		C-6+
2	3.055	1426		1		C-1
3	3.6	2884		2		C-2
4	4.737	4274		3		C-3
5	7.399	5732		4		C-4
6	13.33	6886		5		C-5
TOTAL		29707			0	

4PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL. 1:4




CHROMATOGRAM	4	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.677	41301		6		C-6+
2	3.055	7301		1		C-1
3	3.601	14647		2		C-2
4	4.739	21507		3		C-3
5	7.4	28432		4		C-4
6	13.328	34739		5		C-5
TOTAL		147927			0	

8PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 1 DIL. 1:2




CHROMATOGRAM PKNO	5 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.671	82301		6		C-6+
2	3.055	14489		1		C-1
3	3.602	29285		2		C-2
4	4.74	43237		3		C-3
5	7.405	58664		4		C-4
6	13.336	69824		5		C-5
TOTAL		297799			0	

POST ANALYSIS CALIBRATION CHECK
 0.4PPM HYDROCARBON STANDARD
 SCOTTY CAN MIX 1 DIL. 1:40



CHROMATOGRAM	15	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.678	4424		6		C-6+
2	3.055	721		1		C-1
3	3.604	1448		2		C-2
4	4.738	2196		3		C-3
5	7.398	2976		4		C-4
6	13.317	3179		5		C-5
TOTAL		14943			0	


POST ANALYSIS CALIBRATION CHECK
 0.8PPM HYDROCARBON STANDARD
 SCOTTY CAN MIX 1 DIL. 1:20



CHROMATOGRAM	17	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.671	8364		6		C-6+
2	3.057	1360		1		C-1
3	3.605	2814		2		C-2
4	4.743	4111		3		C-3
5	7.411	5388		4		C-4
6	13.329	6574		5		C-5
TOTAL		28612			0	


LOV QA PACK

SYSTEM BLANK
UHP NITROGEN



CHROMATOGRAM 1 MEMORIZED
WARNING NO PEAK

15PPM HYDROCARBON STANDARD
SCOTT CAN MIX 1




CHROMATOGRAM PKNO	2 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.658	16426		6		C-6+
2	3.049	2863		1		C-1
3	3.595	5737		2		C-2
4	4.732	8499		3		C-3
5	7.391	11271		4		C-4
6	13.292	13550		5		C-5
TOTAL		58347				

IDENTIFICATION FILE 0
MODE\$ 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.03	0.00576419	16.5
2	C-2	3.58	0.00287594	16.5
3	C-3	4.72	0.00194131	16.5
4	C-4	7.37	0.00146388	16.5
5	C-5	13.28	0.00109229	14.8
6	C-6+	2.65	0.00092534	15.2
7	C-2	3.85	0.00287594	16.5
8	C-3	4.3	0.00194131	16.5
9	C-4	5.7	0.00146388	16.5
10	C-4	6.65	0.00146388	16.5
11	C-5	10.24	0.00109229	14.8
12	C-5	10.59	0.00109229	14.8
13	C-5	12.73	0.00109229	14.8
14	C-5	11.3	0.00109229	14.8
15	C-5	15.43	0.00109229	14.8
16	C-5	8.79	0.00109229	14.8
17	C-5	11.82	0.00109229	14.8

100PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 220




CHROMATOGRAM	3	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.668	105865		6		C-6+
2	3.052	17206		1		C-1
3	3.598	36247		2		C-2
4	4.736	53909		3		C-3
5	7.397	71268		4		C-4
6	13.32	85952		5		C-5
7	14.661	148				
TOTAL		370596				

IDENTIFICATION FILE 1
MODE\$ 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.04	0.00587011	101
2	C-2	3.58	0.00278646	101
3	C-3	4.72	0.00185496	100
4	C-4	7.38	0.00141718	101
5	C-5	13.3	0.00115297	99.1
6	C-6+	2.66	0.0009446	100
7	C-2	3.9	0.00278646	101
8	C-3	4.35	0.00185496	100
9	C-4	5.75	0.00141718	101
10	C-4	6.66	0.00141718	101
11	C-5	10.21	0.00115297	101
12	C-5	10.59	0.00115297	99.1
13	C-5	12.71	0.00115297	99.1
14	C-5	11.3	0.00115297	99.1
15	C-5	15.27	0.00115297	99.1
16	C-5	12.19	0.00115297	99.1
17	C-5	11.6	0.00115297	99.1

1000PPM HYDROCARBON STANDARD
SCOTTY CAN MIX 224




CHROMATOGRAM 4		MEMORIZED		IDNO	CONC	NAME
PKNO	TIME	AREA	MK			
1	2.676	1086007		6		C-6+
2	3.053	182088	V	1		C-1
3	3.599	366655		2		C-2
4	4.737	545057		3		C-3
5	6.724	804		10		C-4
6	7.397	722778		4		C-4
7	12.061	604				
8	13.313	888100	SV	5		C-5
9	14.681	2207	T			
TOTAL		3794299				

IDENTIFICATION FILE 2
MODE# 101

WINDOW 3

IDNO	NAME	TIME	FACTOR	CONC
1	C-1	3.04	0.00549186	1000
2	C-2	3.58	0.00280918	1030
3	C-3	4.72	0.00183467	1000
4	C-4	7.38	0.00139739	1010
5	C-5	13.29	0.00114852	1020
6	C-6+	2.66	0.000925408	1005
7	C-2	3.9	0.00280918	1030
8	C-3	4.52	0.00183467	1000
9	C-4	5.94	0.00139739	1010
10	C-4	6.7	0.00139739	1010
11	C-5	10.21	0.00114852	1020
12	C-5	10.59	0.00114852	1020
13	C-5	12.73	0.00114852	1020
14	C-5	12.55	0.00114852	1020
15	C-5	15.21	0.00114852	1020


DESTEC KERN FRONT
 2-18-93 REPORT # 027-343
 HC SAMPLE BLANK



CHROMATOGRAM PKNO	5 TIME	MEMORIZED AREA	MK	IDNO	CONC	NAME
1	2.645	324		6	0.3065	C-6+
2	2.933	136				
3	3.047	393	V	1	2.3089	C-1
4	9.455	56				
TOTAL		911			2.6154	

GROUP(NAME)	CONC
C-1	2.3089
C-2	0
C-3	0
C-4	0
C-5	0
C-6+	0.3065


POST ANALYSIS CALIBRATION CHECK
15PPM HYDROCARBON STANDARD



CHROMATOGRAM	19	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.668	16601		6	15.3613	C-6+
2	3.05	2905		1	16.7461	C-1
3	3.606	5756		2	16.5536	C-2
4	4.747	8542		3	16.5828	C-3
5	7.415	11108		4	16.2601	C-4
6	13.333	13783		5	15.0553	C-5
TOTAL		58695			96.5593	


GROUP(NAME)	CONC
C-1	16.7461
C-2	16.5536
C-3	16.5828
C-4	16.2601
C-5	15.0553
C-6+	15.3613

POST ANALYSIS CALIBRATION CHECK
 100PPM HYDROCARBON STANDARD
 SCOTTY CAN MIX 220



CHROMATOGRAM	20	MEMORIZED				
PKNO	TIME	AREA	MK	IDNO	CONC	NAME
1	2.676	106879		6	100.9578	C-6+
2	3.058	17901		1	105.0785	C-1
3	3.606	36431		2	101.5132	C-2
4	4.746	54303		3	100.7292	C-3
5	7.413	71681		4	101.5843	C-4
6	13.348	86774		5	100.0474	C-5
7	14.696	330				
TOTAL		374297			609.9104	

GROUP(NAME)	CONC
C-1	105.0785
C-2	101.5132
C-3	100.7292
C-4	101.5843
C-5	100.0474
C-6+	100.9578



**PETRO
CHEM
ENVIRONMENTAL
SERVICES, INC.**

313 Daniels Lane
Bakersfield, California 93307
(805) 327-7300
FAX (805) 327-3459

Gary Fuller
WZI, Inc.
January 29, 1993

Units: Kern Front Limited
Two Cogens

SOURCE TEST PLAN

I. Source Information:

- A. Unit: Two 25.0 MW GE LM-2500
Gas Fired Turbines
PTO# 4166001 (B), 4166002 (B)
- B. Company: Destec Engineering, Inc.
Kern Front Limited Cogeneration Facility
Sec. 2-T28S-R27E
Kern County, California
- C/O Gary Fuller (WZI, Inc.)
4800 Easton Drive, Suite 114
Bakersfield, CA 93309

- II. Testing Firm: Petro Chem Environmental Services, Inc.
313 Daniels Lane
Bakersfield, CA 93307
- Attention: Mark Ready

- III. Regulatory Agency: San Joaquin Valley Unified APCD
Southern Region

- IV. Summary: Determination of concentrations (ppm) and
emissions (lb/hr) of particulate, sulfur,
NMHC, NOx, CO and Spec II, III, IV
(NOx, O₂ and CO) relative accuracy, from the
exhaust of two gas fired Turbine/Generators.

- V. Testing Date: February 23 - 26, 1993

**PROPOSAL FOR COMPLIANCE TESTING
AT TWO TURBINE MAIN STACKS**

Determination of concentrations (ppm) and emissions (lb/hr) of particulate, sulfur, NMHC, NOx and CO from the exhaust of two 25 MW gas fired Turbine/Generators. Relative Accuracy testing will be performed for NOx, O₂ and CO following Title 40 CFR performance Spec II, III and IV; a minimum of nine thirty minute runs will be performed. Fuel sulfur analysis will be performed by EPA Method 20 and 19; EAS Labs of San Luis Obispo will be used (example analysis enclosed). The following methods will be used:

Parameters	Method	# Test Runs Per Turbine	Permit Limit, lb/hr Per Turbine
Particulate	EPA Method 5; Gravimetric	2 - 6 hour	3.12
Sulfur	Fuel Analysis / Fuel Rates	1	*** 0.16 as sulfur
NMHC	EPA Method 18; (modified) C ₁ -C ₆ +	3	** 3.12
* NOx	EPA Method 20; Chemiluminescent Analyzer	9 - 30 minute	4.04 lb/hr 0.0162 lb/MMBtu
* CO	EPA method 10; GFC Analyzer	9 - 30 minute	27.83
* O ₂	EPA Method 20; Fuel Cell Analyzer	9 - 30 minute	---
Molecular Weight O ₂ /CO ₂ /N ₂	EPA Method 3; Orsat	2	---
volume Flow DSCFM	EPA Method 2; Pitot Tube Traverse	2	---
Relative Accuracy NOx/O ₂ /CO	Title 40 CFR Performance Spec II/III/IV	See above NOx, O ₂ , CO	20%/20%/10%

* An initial 48 point concentration traverse will be performed to document the point(s) of average concentration. All follow-up runs will be performed at the point(s) of average concentration.

** Includes emission from lube oil vent stack. The Method 18 analysis will be modified to increase sensitivity to 0.2 ppm C₁-C₆+. Sample analysis is enclosed.

*** Emissions as sulfur = (lb/hr SO₂/s) + lb/hr SO₄/3


Gary Fuller (WZI)
Kern Front Limited Cogen Facility
January 29, 1993

Units: Two Gas Turbines and
Four Lube Oil Vent Stacks

**PROPOSAL FOR COMPLIANCE TESTING
LUBE OIL VENT STACKS**

Determination of concentrations (ppm, gr/DSCF) and emissions (lb/hr, lb/day) of condensable and non condensable hydrocarbon emissions from the exhaust of four lube oil vent stacks (two per turbine). The following procedures will be used:

Parameters	Method	# Test Runs/Site
Condensable Hydrocarbons	EPA Method 4; with Gravimetric Organic Extractions Utilizing CARB Method 5.4.3.1	3
Non Condensable Hydrocarbons	EPA Method 18; Bag Sample FID Analysis	3
Volume Flow	EPA Method 2; Pitot Tube or Hot Wire Anemometer	3
Molecular Weight	EPA Method 3; Orsat Analysis	3
% H ₂ O	EPA Method 4; Condensation	3



KERN COUNTY AIR POLLUTION CONTROL DISTRICT

PERMIT TO OPERATE

Number: 4186001(B)

2700 "M" STREET, SUITE 276
BAKERSFIELD, CA. 93301
TELEPHONE: (805) 861-3882

PERMIT TO OPERATE IS HEREBY GRANTED TO:

KERN FRONT LIMITED

FOR EQUIPMENT LOCATED AT:

Sec. 2, T28S, R27E
Kern Front Lease

EQUIPMENT OR PROCESS DESCRIPTION:

25.0 MW Gas-Fired Turbine Engine
Cogeneration System

OPERATIONAL CONDITIONS LISTED BELOW.

THIS PERMIT BECOMES VOID UPON ANY CHANGE OF OWNERSHIP OR LOCATION. OR ANY ALTERATION.

NOTE: The permittee may be required to provide adequate sampling and testing facilities. Equipment modification requires a new permit.

WILLIAM J. RODDY
AIR POLLUTION CONTROL OFFICER

REVOCABLE: This permit does not authorize the emission of air contaminants in excess of those allowed by the Rules and Regulations the K.C.A.P.C.D.

By: W. J. Roddy

For Period: 02-28-92 TO 02-28-93

CONDITIONAL APPROVAL:

Compliance with all conditions of approval imposed by any applicable Authority to Construct is required for life of this equipment unless modified by application. Equipment authorized by this Permit to Operate shall comply in full with applicable Rule 210.1 requirements.

EQUIPMENT DESCRIPTION:

- Winston 120 HB centrifugal separator.
- General Electric, Model LM 2500, 250.3 MW BTU/hr input natural gas fired turbine engine.
- Continuously recording emission monitors for NOx, CO, and O₂.
- 25.0 MW electric generator.

OPERATIONAL CONDITIONS:

- Gas turbine engine shall be fired exclusively with PUC-regulated quality natural gas. (Rule 210.1)
- Gas turbine engine steam injection rate shall be maintained at 1.32 - 1.92 steam to fuel ratio documented to result in compliance with emission limits. (Rule 209)
- Ammonia injection rate shall be controlled to maintain ammonia "break-through" to less than 20 ppmv. (Rule 410)
- If steam injection, SCR, or catalytic conversion system is inoperative, gas turbine engine shall be shut down. (Rule 209)
Inlet gas temperature to both catalyst beds shall be maintained within the range recommended by catalyst manufacturer. (Rule 209)
- Gas turbine engine shall not burn more than 5.87 MM scf/day of natural gas. (Rule 209)

7. All gas turbine exhaust shall flow through both catalyst beds. (Rule 208)
8. Handling and storage of collected liquids shall not result in an increase of hydrocarbon emissions. (Rule 210.1)
9. Visible emissions from lube oil system atmospheric vent shall not exceed 20% opacity for more than a total of 3 minutes in any one hour. (Rule 401)

COMPLIANCE TESTING REQUIREMENT:

Compliance with particulates, sulfur compounds, oxides of nitrogen, hydrocarbons and carbon monoxide emission sampling limits shall be demonstrated by District-witnessed sample collection by independent testing laboratory within 60 days after startup and annually within 60 days prior to permit anniversary date, and the official test results, and field data submitted within 30 days after collection. Samples shall be collected during maximum fuel consumption and use of evaporative coolers. (Rule 108.1)

EMISSION SAMPLING LIMITS:

<u>Particulates:</u>	3.12	lbm/hr	(Rule 210.1)
<u>Sulfur Compounds:</u>	0.16	lbm/hr	(of SO ₂) (Rule 210.1)
	0.24	lbm/hr	(of SO ₄) (Rule 210.1)
<u>Oxides of Nitrogen:</u>	4.04	lbm/hr	(as NO ₂) (Rule 210.1)
	0.0162	lbm/MM BTU	(as NO ₂) (Rule 210.1 BACT req't)
<u>Hydrocarbons:</u>	3.12	lbm/hr	(Rule 210.1) (including lube oil cooler/ accumulating vents & collected liquids)
<u>Carbon Monoxide:</u>	27.88	lbm/hr	(Rule 210.1)

SPECIAL CONDITIONS:

1. Kern Front Limited shall comply in full with Rule 422 (New Source Performance Standards) requirements including notification, record keeping and monitoring requirements.
2. Continuous emission monitoring system for NO_x (as NO₂), CO and O₂ serving exhaust gas stream shall conform to Rule 108 specifications.
3. Continuous emission monitoring systems shall be calibrated and operated according to EPA guidelines as specified in CRF, Part 60, Appendix B. (Rule 108)
4. Audits of monitors shall be conducted semi-annually by independent laboratory in accordance with EPA guidelines, witnessed by District, and reports shall be submitted to District within 30 days of such audit. (Rule 108)
5. Kern Front Limited continuous emissions monitoring printouts shall be made readily available for District inspection upon request. (Rule 208)

KERN FRONT LIMITED

Permit #4186001(B)

Page 3

6. Kern Front Limited shall keep accurate records of daily fuel consumption of gas turbine engine and shall make them readily available for District inspection upon request. (Rule 209)
7. Steam produced at this facility for use in oil-production operations shall affect only wells connected to well vent vapor recovery systems KCAPCD #4019105 & '105 owned by Cities Service and KCAPCD #4032104 & '106 owned by Petro Lewis unless prior District approval is obtained. (Rule 210.1)
8. Kern Front Limited shall provide design details, including but not limited to engineering drawings of SCR and catalytic converter units for District approval prior to installation. (Rule 209)
9. Non-compliance with NOx emission sampling limit shall require: shut-down of gas turbine, down throttling (reduced fuel consumption), or installation of additional SCR catalyst volume - increased emission limits will require modified Authority to Construct before continued operation at such levels pursuant to Section 42350 of California Health & Safety Code. a variance for this condition cannot be obtained. (Rule 209)

RYING:

Failure of catalyst to perform as required because of catalyst poisoning or fouling shall not be recognized as basis for Rule 111 enforcement exemption. (Rule 209)

7. All gas turbine exhaust shall flow through both catalyst beds. (Rule 209)
8. Handling and storage of collected liquids shall not result in an increase of hydrocarbon emissions. (Rule 210.1)
9. Visible emissions from lube oil system atmospheric vent shall not exceed 20% opacity for more than a total of 3 minutes in any one hour. (Rule 401)

COMPLIANCE TESTING REQUIREMENT:


Compliance with particulates, sulfur compounds, oxides of nitrogen, hydrocarbons and carbon monoxide emission sampling limits shall be demonstrated by District-witnessed sample collection by independent testing laboratory within 60 days after startup and annually within 60 days prior to permit anniversary date, and the official test results, and field data submitted within 30 days after collection. Samples shall be collected during maximum fuel consumption and use of evaporative coolers. (Rule 108.1)

EMISSION SAMPLING LIMITS:

<u>Particulates:</u>	3.12	lbm/hr	(Rule 210.1)
<u>Sulfur Compounds:</u>	0.16	lbm/hr	(of SO ₂) (Rule 210.1)
	0.24	lbm/hr	(of SO ₄) (Rule 210.1)
<u>Oxides of Nitrogen:</u>	4.04	lbm/hr	(as NO ₂) (Rule 210.1)
	0.0162	lbm/MM BTU	(as NO ₂) (Rule 210.1 BACT req't)
<u>Hydrocarbons:</u>	3.12	lbm/hr	(Rule 210.1) (including lube oil cooler/accumulating vents & collected liquids)
<u>Carbon Monoxide:</u>	27.88	lbm/hr	(Rule 210.1)

SPECIAL CONDITIONS:

1. Kern Front Limited shall comply in full with Rule 422 (New Source Performance Standards) requirements including notification, record keeping and monitoring requirements.
2. Continuous emission monitoring system for NO_x (as NO₂), CO and O₂ serving exhaust gas stream shall conform to Rule 108 specifications.
3. Continuous emission monitoring systems shall be calibrated and operated according to EPA guidelines as specified in CFR, Part 60, Appendix B. (Rule 108)
4. Audits of monitors shall be conducted semi-annually by independent laboratory in accordance with EPA guidelines, witnessed by District, and reports shall be submitted to District within 30 days of such audit. (Rule 108)
5. Kern Front Limited continuous emissions monitoring printouts shall be made readily available for District inspection upon request. (Rule 208)



KERN COUNTY AIR POLLUTION CONTROL DISTRICT

PERMIT TO OPERATE

Number: 4166002(8)

2700 "M" STREET, SUITE 275
BAKERSFIELD, CA. 93301
TELEPHONE: (805) 387-3822

PERMIT TO OPERATE IS HEREBY GRANTED TO:

KERN FRONT LIMITED

FOR EQUIPMENT LOCATED AT:

Sec. 2. T29S, R27E
Kern Front Lease

EQUIPMENT OR PROCESS DESCRIPTION:

25.0 MW Gas-Fired Turbine Engine
Cogeneration System

OPERATIONAL CONDITIONS LISTED BELOW.

THIS PERMIT BECOMES VOID UPON ANY CHANGE OF OWNERSHIP OR LOCATION, OR ANY ALTERATION.

NOTE: The permittee may be required to provide adequate sampling and testing facilities. Equipment modification requires a new permit.

WILLIAM J. RODDY
AIR POLLUTION CONTROL OFFICER

REVOCABLE: This permit does not authorize the emission of air contaminants in excess of those allowed by the Rules and Regulations the K.C.A.P.C.D.

By: SB

For Period: 02-28-92 TO 02-28-93

CONDITIONAL APPROVAL:

Compliance with all conditions of approval imposed by any applicable Authority to Construct is required for life of this equipment unless modified by application. Equipment authorized by this Permit to Operate shall comply in full with applicable Rule 210.1 requirements.

EQUIPMENT DESCRIPTION:

- a. Winston 120 HB centrifugal separator.
- b. General Electric, Model LM 2500. 250.3 MW BTU/hr input natural gas fired turbine engine.
- c. Continuously recording emission monitors for NOx, CO, and O₂.
- d. 25.0 MW electric generator.

OPERATIONAL CONDITIONS:

1. Gas turbine engine shall be fired exclusively with PUC-regulated quality natural gas. (Rule 210.1)
2. Gas turbine engine steam injection rate shall be maintained at 1.57 - 2.05 steam to fuel ratio documented to result in compliance with emission limits. (Rule 209)
3. Ammonia injection rate shall be controlled to maintain ammonia "break-through" to less than 20 ppmv. (Rule 410)
4. If steam injection, SCR, or catalytic conversion system is inoperative, gas turbine engine shall be shut down. (Rule 209)
Inlet gas temperature to both catalyst beds shall be maintained within the range recommended by catalyst manufacturer. (Rule 209)
5. Gas turbine engine shall not burn more than 5.67 MM scf/day of natural gas. (Rule 209)

6. Kern Front Limited shall keep accurate records of daily fuel consumption of gas turbine engine and shall make them readily available for District inspection upon request. (Rule 209)
7. Steam produced at this facility for use in oil-production operations shall affect only wells connected to well vent vapor recovery systems KCAPCD #4018103 & '106 owned by Cities Service and KCAPCD #4032104 & '106 owned by Petro Lewis unless prior District approval is obtained. (Rule 210.1)
8. Kern Front Limited shall provide design details, including but not limited to engineering drawings of SCR and catalytic converter units for District approval prior to installation. (Rule 209)
9. Non-compliance with NOx emission sampling limit shall require: shut-down of gas turbine, down throttling (reduced fuel consumption), or installation of additional SCR catalyst volume - increased emission limits will require modified Authority to Construct before continued operation at such levels pursuant to Section 42350 of California Health & Safety Code, a variance for this condition cannot be obtained. (Rule 209)

WARNING:

Failure of catalyst to perform as required because of catalyst poisoning or fouling shall not be recognized as basis for Rule 111 enforcement exemption. (Rule 209)