

Note: This is a reference cited in AP 42, *Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

Background Report Reference

AP-42 Section Number: 9.13.2

Background Chapter: 4

Reference Number: 2

Title: Final Report for an Emission
Compliance Test Program at Nestle
Company, Inc., Freehold, NJ

York Services Corporation

York Services Corporation

April 1987

FINAL REPORT
FOR AN
EMISSION COMPLIANCE TEST PROGRAM

AT
NESTLE COMPANY, INC.
FREEHOLD, NEW JERSEY

PREPARED BY

JIM LEHMANN
ENVIRONMENTAL ENGINEER

YORK SERVICES CORPORATION
ONE RESEARCH DRIVE
STAMFORD, CONNECTICUT 06906

* * * * *

TABLE OF CONTENTS

	<u>PAGE NO.</u>
LIST OF FIGURES	i
LIST OF TABLES	ii
1.0 INTRODUCTION	1
2.0 SUMMARY AND DISCUSSION OF TEST RESULTS	1
3.0 SAMPLING LOCATION	1
4.0 SAMPLING AND ANALYTICAL PROCEDURES	1
4.1 Gas Velocity Measurements	4
4.2 Flue Gas Composition	4
4.3 Particulate Emissions	4
5.0 APPENDIX	11
5.1 Field Data Sheets	12
5.1.1 Preliminary Traverse	13
5.1.2 Cyclonic Flow Measurement	15
5.1.3 Particulate	17
5.1.4 Orsat	21
5.2 Complete Emission Calculations	25
5.2.1 Particulate	26
5.3 Process Data	30
5.4 Calibration Data	36
5.4.1 Pretest Calibration	37
5.4.2 Posttest Calibration	43
5.5 Laboratory Data	45
5.6 Calculation Formulae	49

LIST OF FIGURES

	<u>PAGE NO.</u>
Figure 3-1 Sampling Port and Traverse Point Locations	3
Figure 4-1 Integrated Gas Sampling Train and Orsat Analyzer	5
Figure 4-2 Particulate Sampling Train	6

LIST OF TABLES

	<u>PAGE NO.</u>
Table 2-1 Summary of Particulate Emission Test Results	2

1.0 INTRODUCTION

York Services Corporation (YSC) was contracted by the Nestle Company, Inc. to conduct an emission compliance test program on their MEC dryer located in Freehold, New Jersey. The purpose of the test program was to demonstrate compliance with applicable State of New Jersey Department of Environmental Protection regulations for particulate emissions. The test program was conducted during the week of March 23, 1987 and was witnessed by the New Jersey DEP officials.

2.0 SUMMARY AND DISCUSSION OF TEST RESULTS

The results of the emission compliance test program conducted on the MEC dryer are presented in this section. All sampling and analyses were conducted in accordance with methods outlined in 40 CFR 60, Appendix A, Methods 1-5.

Emission Results

Table 2-1 summarizes the particulate emission results. A total of three samples was collected for particulate emission analysis.

3.0 SAMPLING LOCATION

All emission tests and flue gas samples were conducted in the stack which vents the exhaust gases from the unit to the atmosphere. The test ports are located at a point in the stack in accordance with guidelines outlined in EPA Method 1.

The stack is 42 inches in diameter at the test location. The ports are 20 feet, 6 inches (5.8 stack diameters) downstream of the breeching and 84.5 inches (2.0 stack diameters) upstream of the stack exit. At this location, EPA Method 1 requires that 24 traverse points be used to extract a representative sample (Figure 3-1).

4.0 SAMPLING AND ANALYTICAL PROCEDURES

Measurement procedures, sample recovery, handling techniques and laboratory analytical procedures were conducted in accordance with United States Environmental Protection Agency (USEPA) guidelines 1,2,3,5.

TABLE 2-1

SUMMARY OF PARTICULATE TEST RESULTS

MEC DRYER

THE NESTLE COMPANY

FREEHOLD, NEW JERSEY

RUN:	1	2	3	AVERAGE
<u>General Data</u>				
Date	3/25/87	3/25/87	3/25/87	-
Time	10:10-11:27	12:30-1:48	2:45-4:01	
Isokinetic Ratio, %	98.5	103.1	102.2	101.3
Water, % v/v	8.2	8.9	10.8	9.3
<u>Stack Parameters</u>				
Temperature, °F	108	108	108	108
Average Velocity, ft/sec	56.31	53.27	53.87	54.48
<u>Volumetric Flow Rate</u>				
ACFM	32,507	30,753	33,981	32,414
SCFMd	27,830	26,118	28,283	27,411
<u>Gas Composition (dry)</u>				
CO ₂ , % v/v	ND*	ND	ND	ND
O ₂ , % v/v	20.9	20.9	20.9	20.9
N ₂ , % v/v	79.1	79.1	79.1	79.1
<u>Particulates</u>				
Concentration, gr/SCFd	0.0117	0.0127	0.0148	0.0131
Mass Emission Rate: lb/hr	2.78	2.85	3.58	3.07

* None Detected



York Research Corporation

ONE RESEARCH DRIVE, STAMFORD, CONNECTICUT 06906

WORK PLANNING FORM


PROJECT # Y-

CLIENT: NESTLE

SUBJECT:

LOCATION: MEC DRYER OUTLET

NO SCALE / J.L.



4.1 PRELIMINARY VELOCITY MEASUREMENTS

Preliminary velocity and temperature measurements were performed. Gas velocity and temperatures were measured in accordance with guidelines outlined in EPA Method 2. Cyclonic flow determinations were conducted as delineated in EPA Method 1, Section 2.4.

4.2 FLUE GAS CONCENTRATIONS

The gas composition was determined in accordance with EPA Method 3. A gas sample was collected during each particulate test. A sample line was attached to the sampling probe. A gas sample was drawn by a vacuum pump into an evacuated Tedlar bag at a rate proportional to the stack velocity. The contents of the bag were analyzed for O_2 and CO_2 with an Orsat Analyzer® after collection. Figure 4-1 illustrates the sampling train and analyzer.


4.3 PARTICULATE CONCENTRATIONS

Particulate concentrations were determined in accordance with EPA Method 5. This method calls for isokinetic sampling of the flue gas to ensure a representative particulate sample.

Sampling Apparatus

The particulate sampling apparatus consisted of a probe, pitot tube, filter holder, four impingers, dry gas meter, vacuum pump and flow meter, as shown in Figure 4-2. A calibrated nozzle was attached to the sampling end of the probe which had a heated borosilicate glass liner. After passing through the nozzle and probe, the sample was drawn through the tared fiberglass filter which was encased in an oven to maintain a temperature not to exceed 225°F. The sample then passed through the impinger system which was contained in an ice bath.

The first and second impingers were initially filled with a total of 200 ml of distilled water. The third impinger was left dry and the fourth impinger contained 300 g of indicating type silica gel. The temperature at the exit of the last impinger was monitored with a thermometer that measured to the nearest 1°F. A sample line connected the last impingers to the meter box.



INTEGRATED GAS SAMPLING TRAIN and ORSAT ANALYZER




FIGURE 4-1

PARTICULATE SAMPLING TRAIN (Without Cyclone)




FIGURE 4-2

Sampling Procedures

Initial and final leak checks were performed on each sampling train to confirm the presence of a leak-free system (leakage rates did not exceed 0.02 cfm per EPA Standards prior to the runs).

The proper nozzle size was determined using data obtained from the preliminary tests. The probe and filter assemblies were heated to approximately 180°F to prevent condensation.

A programmable calculator was used to correlate all variables such that a direct relationship between Δp and ΔH was made. The sampling rate could then quickly be adjusted when the gas temperature and/or velocity pressure changed.

During the test, the following data were recorded for each traverse point:

- Point designation
- Sampling time (min)
- Clock time sampling commenced at each port
- Dry gas meter reading (V_m , ft³)
- Δp (in H₂O)
- Actual ΔH (in H₂O)
- Stack temperature (t_s , °F)
- Dry gas meter temperature at inlet and outlet (t_m , °F)
- Vacuum gauge reading (in Hg)
- Probe temperature, °F
- Filter exit temperature, °F
- Dry gas temperature at exit of last impinger (°F)

Sample Recovery

At the completion of each run, the samples were recovered in the following manner:

Container No. 1 - The probe and nozzle were brushed and rinsed until clean with nanograde acetone from a polyethylene squeeze bottle. This sample was sealed in a glass sample jar.

Container No. 2 - The filter holder inlet was covered with aluminum foil and transported to the laboratory. In the lab, the front half of the filter holder was brushed and rinsed with acetone into Container 1. The filter was placed in a petri dish for weighing.

Container No. 3 - The silica gel from the fourth impinger was weighed to the nearest 0.1 gram. The net weight was recorded on the field data sheet.

Container No. 4 - A sample of acetone from the field supply (squeeze bottle) was collected in a glass jar.

Additionally, the impinger fluids were grossly examined, the total volume measured and the difference from 200 ml (the initial volume) recorded on the field data sheet. The fluids were discarded.

All glass sample jars had teflon-lined lids. Each sample container was labeled with the date, contents and test number and sealed with tape.

Sample Analysis

Each sample was analyzed in the following manner:

Filter - The filter was removed from its sealed container and placed in a petri dish, heated overnight at 100°C and then desiccated over anhydrous CaSO_4 until cool. Filters were then weighed. The weight was recorded to the nearest 0.1 mg.

Front-half Acetone - The acetone was transferred to a tared beaker. The acetone was evaporated at ambient temperature and pressure, then dried at 60°C for overnight. The beaker was desiccated until cool and weighed. The weight was recorded to the nearest 0.1 mg.

PROJECT NO. 01-4629-00

REVIEW REPORT FORM

PREPARED BY:




JIM LEHMANN
SENIOR PROJECT MANAGER

REVIEWED BY:



ROGER A. KNISKERN
MANAGER EMISSIONS MEASUREMENT

APPROVED BY:



ABRAHAM J. KURTZ
VICE PRESIDENT

Certification of Test Report

I have reviewed the procedures and results of York Services Corporation Test Report No. 01-4629-00 and certify as to its correctness.

SIGNATURE: _____

NAME: Vito J. Fossella _____

NEW JERSEY LICENSE NO.: NJ-16005 _____

DATE: April 23, 1987 _____

Seal

5.0 APPENDIX

5.1 FIELD DATA SHEETS

5.1.1 PRELIMINARY TRAVERSE

YSC

BAROMETRIC PRESSURE, in. Hg. 29.90

STACK PRESSURE, in. Hg. _____

METER BOX I.D. _____

PROBE I.D. _____

CD FACTOR _____

METER TEMPERATURE _____

DISTANCE TO DISTURBANCE:

UPSTREAM

DOWNSTREAM

21% C_x
0% C_{O^2}

Schematic of Port Locations
(Indicate North, Label Ports A,B etc.)

TRAVERSE POINT NUMBER	VELOCITY HEAD (Δp_s), in. H ₂ O	STACK TEMPERATURE (T_s), °F
B-1	1.5	
B-2	1.4	
B-3	1.4	120.
B-4	1.5	
B-5	1.5	
B-6	1.5	
B-7	1.2	
B-8	.91	
B-9	.91	
B-10	.88	
B-11	.82	
B-12	.55	
A-12	.43	
A-1	1.2	
A-2	1.3	
A-3	1.4	
A-4	1.4	120.
A-5	1.4	
A-6	1.4	
A-7	1.2	
A-8	.86	
A-9	.94	
A-10	.84	
A-11	.66	
AVERAGE	1.057	

[illegible]

5.1.2 CYCLONIC FLOW MEASUREMENT

YSC

4pm
24 MAR 07

TW 115°F

TD 116° E

 $\sim 10^{4\frac{1}{2}} \text{ H}_2\text{O}$

VISIBLE H_2O

droplet in
stack, liquid
has running
down stack
walls. J-L

5.1.3 PARTICULATE

1-1995

LEAK RATE B4 K₁₀₀ = 0.016 @ 20" VAC
1.22 x ΔP = ΔH @ 105°F LEAK RATE AFTER T₁₀₀ = 0.020 cfm @ 2" Hg VAC

۱۲۰

JIM LEHMANN

Environmental Engineer

2096 RAC Book

STACK ANALYSIS

Plant: *NES-LE*

Notes: $P_{6.11} = 29.98\%$ H_9

$$\text{stack } p = 0.4'' + 750.7$$
$$d_n = 0.1933$$

start at 10 am
End next morn 12-1/2 hr

not imp. in fact

File. 64326

METER BASE	NUMBER OF POINTS	DRY GAS METER CORRECTION	ORIFICE METER FACTOR
22.20	24	0.976	1.967

TIME (MIN)	DRY GAS METER (FT ³)	PITOT RDG. ("H ₂ O)	ORIFICE RDG. ("H ₂ O)	TEMP. GAS METER		TRAIN VAC. ("Hg)	TEMP. LAST IMPINGER (°F)	STACK PRESSURE ("H ₂ O)	STACK TEMP. (°F)	OVEN BOX TEMP. (°F)
				IN (°F)	OUT (°F)					
3.	24.12	1.15	1.31	64.	64.	64 N.D.	48.	+0.95	118.	224/224.
3.	26.00	1.15	1.31	70.	65.	67.5"	46.		101.	194/192.
3.	28.70	1.15	1.37	73.	65.	69"	44.		101.	192/185.
3.	30.00	1.25	1.57	75.	64.	69.5"			102.	198/196.
3.	32.12	1.2	1.5	78.	66.	72"	45.		105.	225/217.
3.	34.18	1.2	1.5	80.	68.	74"			108.	224/216.
3.	36.08	0.95	1.15	83.	70.	76.5"	48.		109.	186/181.
3.	37.92	0.94	1.15	83.	79.	76.5"			112.	180/164.
3.	39.74	0.90	1.1	84.	71.	77.5"	49.		113.	224/225.
3.	41.45	0.84	1.0	83.	71.	77"	49.		110.	187/177.
3.	42.58	0.84	0.56	83.	72.	77.5"			109.	152/154.
3.	44.05	0.83	0.54	82.	74.	76.5"	49.		109.	167/154.
3.	45.75	0.89	1.0	75.	72.	73.5"	51.		110.	157/155.
3.	47.68	1.00	1.56	78.	71.	74.5"	51.		110.	220/193.
3.	49.64	1.3	1.56	80.	71.	75.5"	51.	+0.60	110.	289/252.
3.	51.37	1.3	1.56	82.	72.	77"	48.		112.	219/208.
3.	53.88	1.2	1.45	83.	74.	77.5"	48.		112.	194/183.
3.	56.00	1.15	1.4	84.	72.	78"	48.		112.	225/213.
3.	58.00	1.05	1.30	86.	73.	79.5"	48.		113.	178/176.
3.	59.95	1.05	1.3	86.	73.	79.5"	52.		112.	210/204.
3.	61.80	0.91	1.1	86.	73.	79.5"	52.		113.	199/178.
3.	63.65	0.97	1.15	86.	74.	80"	55.		112.	190/170.
3.	65.38	0.85	1.0	86.	74.	80.5"	57.		109.	190/176.
3.	66.02	0.89	0.10	86.	75.	80.5"			101.	192/166.

$V_1 = 43.82$	948	1.19
---------------	-------	--------

755

108

JIM LEHMANN
Environmental Engineer

Lehrate DA run 0.014 CFM @ 17" VAC

STACK ANALYSIS

LEHMAN note after test @ 2" VAC = 0.01 CFM

RAC Box 2096

METER BASE	NUMBER OF POINTS	DRY GAS METER CORRECTION	ORIFICE METER FACTOR
67.40	24.	0.976	1.967


Notes: *dn / Phn see hwni*
72 not and Aug. 9.2.
12.1 gm wt 5.6,

Plant: NESTLE
 Location: Ant-hat
 Run No.: TWO
 Date: 25 MAR 87

start ports @ 12:30pm *dn / out probe*

TIME (MIN)	DRY GAS METER (FT ³)	PITOT RDG. ("H ₂ O)	ORIFICE RDG. ("H ₂ O)	TEMP. GAS METER IN (°F)	TEMP. GAS METER OUT (°F)	TRAIN VAC. ("Hg)	TEMP. LAST IMPINGER (°F)	STACK PRESSURE ("H ₂ O)	STACK TEMP. (°F)	OVEN BOX TEMP. (°F)	
3.0	69.44	1.2	1.45	81.	76.	78.2, 2.	48.	+0.65	113.	200/187	197. B-1
3.0	71.65	1.2	1.45	82.	76.	79 "			112.	200/190	200 2
3.0	73.71	1.2	1.45	87.	77.	82 "	48.		111.	163/154.	190. 3
3.0	75.88	1.3	1.55	90.	78.	84 "			106.	191/174.	180. 4
3.0	77.94	1.1	1.32	92.	79.	85.5 "	47.		106.	175/162.	170. 5
3.0	79.92	1.05	1.25	93.	80.	86.5 "			105.	158/131.	183. 6
3.0	81.86	1.02	1.20	93.	81.	87 "	48.		105.	165/148.	185. 7
3.0	83.77	0.95	1.20	93.	81.	87 "			109.	194/177.	189. 8
3.0	85.68	0.95	1.20	93.	81.	87 "	48.		109.	186/168.	196. 9
3.0	87.40	0.78	0.97	93.	81.	87 "			110.	192/170.	192. 10
3.0	88.96	0.62	0.79	93.	82.	87.5 "	49.		105.	184/172.	190. 11
3.0	84.41.	0.18	0.24	92.	83.	87.5 "	50.		101.	186/177.	190. 12
3.0	91.86	1.1	1.32	88.	84.	86 "	51. ^{ice}		107.	179/150.	229. A1 6.1.12P
3.0	93.90	1.1	1.32	90.	84	87 "	50.		111.	219/187.	195. 2
3.0	95.95	1.1	1.32	91.	84.	87.5 "	50.		113.	208/170.	190. 3
3.0	98.10	1.2	1.50	92.	84.	88 "	50.		113.	178/158.	189. 4
3.0	100.24	1.2	1.50	92.	83.	87.5 "	50. ^{ice}		111.	202/195.	184 5
3.0	102.31	1.1	1.38	91.	87.	87 "	47.		108.	200/171.	172. 6
3.0	104.23	0.99	1.25	91.	82.	86.5 "	48.		109.	173/158.	178. 7
3.0	106.08	0.90	1.10	90.	81.	85.5 "	49.		111.	211/197.	172. 8
3.0	108.90	0.87	1.08	90.	81.	85.5 "	49.		113.	206/177.	176. 9
3.0	109.32	0.57	0.70	90.	81.	85.5 "	49.		105.	209/192.	193. 10
3.0	110.93	0.30	0.38	88.	80.	84 "	53.		105.	218/181.	185. 11
3.0	111.75	0.16	0.20	86.	80.	83 "	53.		103.	206/163.	195. 12
	44.35	1.22	1.20			85.5			108.4		

F-111-64329
 6 0 2 9 64330
 7 178. 8 172. 9 176. 10 193. 11 185. 12 195.



Environmental
result

0.005 CFM LEAK RATE @ 18" AC after 1 hr
0.005 @ 2" Hg vac

Plant: Nestle / Fresh Milk
Location: Antlet
Run No.: 3
Date: 25 MARCH

STACK ANALYSIS

Notes:

METER BASE	NUMBER OF POINTS	DRY GAS METER CORRECTION	ORIFICE METER FACTOR
1230	24	0.976	1.967

In/out Probe pt

TIME (MIN)	DRY GAS METER (FT ³)	PITOT RDG. ("H ₂ O)	ORIFICE RDG. ("H ₂ O)	TEMP. GAS METER IN (°F)	TEMP. GAS METER OUT (°F)	TRAIN VAC. ("Hg)	TEMP. LAST IMPINGER (°F)	STACK PRESSURE ("H ₂ O)	STACK TEMP. (°F)	OVEN BOX TEMP. (°F)	
3.0	14.28	1.1	1.32	76.	74.	75 N.D.	48.	40.60	114.	218./214.	202. A-1
3.0	16.19	1.2	1.44	78.	76.	77 "	46.		113.	210./170	208. 2
3.0	18.24	1.2	1.50	84.	76.	80 "	46.		114.	206./188.	200. 3
3.0	20.30	1.2	1.50	85.	76.	80.5 "	46.		115.	183./189.	199. 4
3.0	22.38	1.25	1.52	86.	76.	81 "	45.		115.	173./171.	200. 5
3.0	24.46	1.25	1.55	87.	77.	82 "	45.		113.	178./175.	198. 6
3.0	26.44	1.05	1.30	86.	77.	81.5 "	45. ice.		114.	191./188.	199. 7
3.0	28.38	0.92	1.15	86.	77.	81.5 "	44.		112.	163./164.	192. 8
3.0	30.16	0.92	1.10	86.	77.	81.5 "	44.		111.	176./190.	193. 9
3.0	31.90	0.88	1.06	86.	76.	81 "	43.		110.	220./216.	188. 10
3.0	33.59	0.75	0.93	86.	75.	80.5 "	43.		103.	205./198.	188. 11
3.0	35.02	0.50	0.62	86.	74.	80 "	42.		101.	209./201.	190. 12
3.0	37.05	1.2	1.46	80.	76.	78 "	48.		116.	186./197.	210. B-1
3.0	39.07	1.2	1.46	81.	77.	79 "	48.		115.	211./214.	202. 2
3.0	41.29	1.4	1.73	83.	77.	80 < 1.0	48.		114.	184./176.	198. 3
3.0	43.49	1.3	1.61	83.	77.	80 N.D.	49.		111.	186./172.	190. 4
3.0	45.73	1.4	1.73	83.	77.	80 "	50.		110.	176./168.	183. 5
3.0	47.95	1.35	1.66	83.	77.	80 "	52.		108.	181./186.	185. 6
3.0	49.94	1.1	1.35	84.	76.	80 "	53.		112.	203./211.	178. 7
4.0	51.94	1.1	1.35	84.	76.	80 "	53.		114.	198./185.	186. 8
3.0	53.86	1.0	1.25	84.	76.	80 "	53.		110.	194./201.	191. 9
3.0	55.76	1.0	1.25	84.	76.	80 "	53.		116.	180./176.	183. 10
3.0	57.51	0.83	1.03	84.	76.	80 "	53.		105.	179./186.	187. 11
3.0	59.40	0.83	1.03	84.	74.	81 "	53.		101.	186./179.	196. 12
	47.100	1.07	1.33			80.0			111.4		

2:45:25 PM

File 64322

64323

3:25 PM

5.1.4 ORSAT

DRY MOLECULAR WEIGHT DETERMINATION

YSC

PLANT NESTLE FREEMAN, N.J. COMMENTS: Real

DATE 25 MAR 87

SAMPLING TIME (24hr CLOCK) START ~ 11:02 A

SAMPLING LOCATION Outlet MEC PAYER

SAMPLE TYPE (BAG, INTEGRATED, CONTINUOUS) Bag

ANALYTICAL METHOD ORSAT

AMBIENT TEMPERATURE ~ 70°F

OPERATOR Ch. Z.

RUN GAS	1		2		3		AVERAGE NET VOLUME	MULTIPLIER	MOLECULAR WEIGHT OF STACK GAS (DRY BASIS) M _d , lb/lb-mole
	ACTUAL READING	NET	ACTUAL READING	NET	ACTUAL READING	NET			
CO ₂	N.D.	—	N.D.	—	N.D.	—	—	44/100	—
O ₂ (NET IS ACTUAL O ₂ READING MINUS ACTUAL CO ₂ READING)	20.9	20.9	20.9	20.9	20.9	20.9	20.9	32/100	
CO (NET IS ACTUAL CO READING MINUS ACTUAL O ₂ READING)	20.9	—	20.9	—	20.9	—	—	28/100	
N ₂ (NET IS 100 MINUS ACTUAL CO READING)	79.1	79.1	79.1	79.1	79.1	79.1	79.1	28/100	
TOTAL									28.99

ES-043

64327

ORSAT

Outlet

1

DRY MOLECULAR WEIGHT DETERMINATION

Run 2-

YSC

PLANT NESLE CO. FREDERICK, NJ
 DATE 25 MAR 67
 SAMPLING TIME (24hr CLOCK) Start ~ 1:15 PM
 SAMPLING LOCATION Outlet of M.E.O. dryer
 SAMPLE TYPE (BAG, INTEGRATED, CONTINUOUS) Bag
 ANALYTICAL METHOD Orsat
 AMBIENT TEMPERATURE ~ 70°F
 OPERATOR Spid.

COMMENTS:

RUN GAS	1		2		3		AVERAGE NET VOLUME	MULTIPLIER	MOLECULAR WEIGHT OF STACK GAS (DRY BASIS) M_d , lb/lb-mole
	ACTUAL READING	NET	ACTUAL READING	NET	ACTUAL READING	NET			
CO ₂	—	—	—	—	—	—	—	44/100	—
O ₂ (NET IS ACTUAL O ₂ READING MINUS ACTUAL CO ₂ READING)	21.0	21.0	21.0	21.0	21.0	21.0	21.0	32/100	—
CO (NET IS ACTUAL CO READING MINUS ACTUAL O ₂ READING)	21.0	—	21.0	—	21.0	—	—	28/100	—
N ₂ (NET IS 100 MINUS ACTUAL CO READING)	79.0	79.0	79.0	79.0	79.0	79.0	79.0	28/100	—
TOTAL									29.00

ES-043

64330

Orsat

Orsat

1.2

DRY MOLECULAR WEIGHT DETERMINATION

YSC

PLANT Mellie @ Grubbs H. J. COMMENTS: Run 3
 DATE 25 March 67
 SAMPLING TIME (24-hr CLOCK) 3:30 Start
 SAMPLING LOCATION Mechanics Unit.
 SAMPLE TYPE (BAG, INTEGRATED, CONTINUOUS) Bag
 ANALYTICAL METHOD Orsat
 AMBIENT TEMPERATURE -70°F
 OPERATOR P.L.

RUN GAS	1		2		3		AVERAGE NET VOLUME	MULTIPLIER	MOLECULAR WEIGHT OF STACK GAS (DRY BASIS) M _d , lb/lb-mole
	ACTUAL READING	NET	ACTUAL READING	NET	ACTUAL READING	NET			
CO ₂	—	—	—	—	—	—	—	44/100	
O ₂ (NET IS ACTUAL O ₂ READING MINUS ACTUAL CO ₂ READING)	20.9	20.9	20.9	20.9	20.9	20.9	20.9	32/100	
CO (NET IS ACTUAL CO READING MINUS ACTUAL O ₂ READING)	20.9	—	20.9	—	20.9	—	20.9	28/100	
N ₂ (NET IS 100 MINUS ACTUAL CO READING)	79.1	79.1	79.1	79.1	79.1	79.1	79.1	28/100	
TOTAL									28.99

64323 ORSAT

63

ES-043

5.2 COMPLETE EMISSION CALCULATIONS

5.2.2 PARTICULATE

HP-41 DATA ENTRY FORM

PROGRAM 'STACK'

PARTICULATE
EMISSIONS
(EPA METHOD 5)

Job Number	4629
Plant	NESTLE
Unit	MEC DRYER
Test Location	FREEHOLD, NJ
Test Condition	NORMAL
Test Date	25 MAR 87
Test Number	ONE
Test Engineer	J. LEHMANN
Barometric Pressure (in. Hg)	29.98
ΔH (in. H ₂ O)	1.19
Dry Gas Meter Volume (cf)	* 43.272
Meter Temp (°F)	75.52
Meter Y Factor	0.976
Volume of Water Condensed (ml)	79.2
Stack Temp (°F)	107.96
Average $\sqrt{\Delta P}$	0.4934
Nozzle Diameter (in.)	0.1933
CO ₂ (%)	< 0.01
O ₂ (%)	20.4
N ₂ (%)	79.1
Pitot Tube C _p	0.806
Elapsed Time (min.)	72.0
Static Pressure (in. H ₂ O)	0.575
Type of Stack	CIRCULAR
Stack Diameter (ft.)	3.5
Stack Length (ft.)	N/A
Stack Width (ft.)	N/A
Total Particulate (mg)	31.7
F-Factor	N/A

* Corrected for leak rate in
mass of 0.02 CFM

JOB NUMBER:

4629
PLANT:
NESTLE
UNIT:
MEC DRYER
TEST LOCATION:
FREEHOLD, NJ
TEST CONDITION:
NORMAL
TEST DATE:
25 MAR 87
TEST NO.:
ONE
TEST ENGINEER:
J. LEHMANN

CLX
RUN

RUN

RUN

RUN

RUN

RUN

RUN

RUN

STACK DIAMETER

SELECT ONE OF THE
FOLLOWING CODES:CIRCULAR=1
RECTANGULAR=2

CODE?

1.00 RUN

STK DIA, FT?

3.50 RUN

DATA ENTRY

BAROMETRIC
Pb (IN HG) =
29.98 RUN

DELTA H
DH (IN H₂O) =
1.19 RUN

METER VOL. ^{Corrected}
AVM (FT³) ^{LEAK RATE}
43.272 RUN

METER TEMP.
TM (DEGREE F) =
75.52 RUN

METER Y
FCTR YM =
0.976 RUN

VOL OF H₂O
VM (ML-GM) =
79.20 RUN

STACK TEMP.
TS (DEGREE F) =
107.96 RUN

SQRT AVG.
DELTA P =
0.4934 CLX
RUN

NOZZLE
DIAMETER (IN) =
0.1933 RUN

% CO₂ =
0.01 RUN

% O₂ =
20.90 RUN

% N₂ =
79.10 RUN

PITOT FCTR
CP =
0.806 RUN

ELAPSED
TIME (MIN) =
72.00 RUN

STATIC PRESS.
(IN H₂O) =
0.575 RUN

CALCULATIONS

METER TEMP (R)=535.52
VOL STD=41.83
STACK TEMP (R)=567.96
%MOISTURE=8.18
MW(DRY)=28.84
MW(WET)=27.95
STK PRESS.=30.82
VELOCITY (FPS)=56.31
STK AREA (FT²)=9.62
ISOINETIC (%)=98.53
ACFM=32.586.71
SCFM=27.838.46

DATA ENTRY

PARTICULATE
TOTAL (MG)=

31.70 RUN

F FACTOR-Fd=

0.00 RUN

CALCULATIONS

* NOT APPLICABLE
GR/SCF=0.0117
GR/SCF CORRECTED
TO 12% CO₂=14.0850*
GR/ACF=0.0180
LB/HR=2.7840
LB/SCF=1.6673E-6

HP-41 DATA ENTRY FORM

PROGRAM 'STACK'

Job Number	4629
Plant	NESTLE
Unit	MEC DRYER
Test Location	Freehold, NJ
Test Condition	Normal
Test Date	25MAR87
Test Number	Two
Test Engineer	J. Lehmann
Barometric Pressure (in. Hg)	29.98
ΔH (in. H ₂ O)	1.13
Dry Gas Meter Volume (cf)	43.285
Meter Temp (°F)	85.48
Meter Y Factor	0.976
Volume of Water Condensed (ml)	84.9
Stack Temp (°F)	108.38
Average $\sqrt{\Delta P}$	0.9383
Nozzle Diameter (in.)	0.1933
CO ₂ (%)	20.01
O ₂ (%)	20.9
N ₂ (%)	79.1
Pitot Tube C _p	0.806
Elapsed Time (min.)	72.0
Static Pressure (in. H ₂ O)	0.65
Type of Stack	CIRCULAR
Stack Diameter (ft.)	3.50
Stack Length (ft.)	N/A
Stack Width (ft.)	N/A
Total Particulate (mg)	34.0
F-Factor	N/A

PARTICULATE EMISSIONS
(EPA METHOD 5)

JOB NUMBER:
4629
PLANT:
NESTLE
UNIT:
MEC DRYER
TEST LOCATION:
FREEHOLD
TEST CONDITION:
NORM.
TEST DATE:
25MAR87
TEST NO.:
TWO
TEST ENGINEER:
J. LEHMANN

DATA ENTRY

BAROMETRIC
Pb (IN HG) =
29.98
DELTA H
DH (IN H2O) =
1.13
METER VOL.
AVM (FT3) =
43.285
METER TEMP.
TM (DEGREE F) =
85.48
METER Y
FCTR YM =
0.976
VOL OF H2O
VM (ML-GM) =
84.90
STACK TEMP.
TS (DEGREE F) =
108.38
SORT AVG.
DELTA P =
0.9383
NOZZLE
DIAMETER (IN) =
0.1933
Z CO2 =
0.01
Z O2 =
20.98
Z N2 =
79.10

PITOT FCTR

CP =
0.806 RUN

ELAPSED

TIME (MIN) =
72.00 RUN

STATIC PRESS.

(IN H2O) =
0.65 RUN

STACK DIAMETER

SELECT ONE OF THE
FOLLOWING CODES:

CIRCULAR=1
RECTANGULAR=2

CODE?

1.00 RUN

STK DIA, FT?

3.500 RUN

CALCULATIONS

METER TEMP (R)=545.48
VOL STD=41.07
STACK TEMP (R)=568.38
%MOISTURE=8.87
MW(DRY)=28.84
MW(WET)=27.88
STAK PRESS.=30.03
VELOCITY (FPS)=53.27
STK AREA (FT2)=9.62
ISO KINETIC (Z)=183.03
ACFM=30,753.05
SCFM=26,118.37

DATA ENTRY

PARTICULATE
TOTAL (MG)=
34.00 RUN

F FACTOR-Fd=
0.00 RUN

CALCULATIONS

* NOT APPLICABLE
GR/SCF=0.0127
GR/SCF CORRECTED
TO 12% CO2=15.2982
GR/ACF=0.0108
LB/HR=2.8540
LB/SCF=1.8212E-6

HP-41 DATA ENTRY FORM

PROGRAM 'STACK'

Job Number	4629
Plant	NESTLE
Unit	MEC DRYER
Test Location	Freehold, NJ
Test Condition	NORMAL
Test Date	25 MAR 87
Test Number	THREE
Test Engineer	J. LEHMANN
Barometric Pressure (in. Hg)	29.98
ΔH (in. H ₂ O)	1.38
Dry Gas Meter Volume (cf)	45.970
Meter Temp (°F)	79.98
Meter Y Factor	0.976
Volume of Water Condensed (ml)	113.3
Stack Temp (°F)	107.67
Average $\sqrt{\Delta p}$	1.0335
Nozzle Diameter (in.)	0.1933
CO ₂ (%)	< 0.01
O ₂ (%)	20.9
N ₂ (%)	79.1
Pitot Tube C _p	0.806
Elapsed Time (min.)	72.0
Static Pressure (in. H ₂ O)	0.60
Type of Stack	CIRCULAR
Stack Diameter (ft.)	3.50
Stack Length (ft.)	N/A
Stack Width (ft.)	N/A
X	
Total Particulate (mg)	42.3
F-Factor	N/A

PARTICULATE EMISSIONS
(EPA METHOD 5)

JOB NUMBER:
4629
PLANT:
NESTLE
UNIT:
MEC DRYER
TEST LOCATION:
FREEHOLD, NJ
TEST CONDITION:
NORMAL
TEST DATE:
25MAR87
TEST NO.:
THREE
TEST ENGINEER:
LEHMANN, J.

DATA ENTRY

BAROMETRIC
Pb (IN HG) =
29.98

DELTA H
DH (IN H2O) =
1.38

METER VOL.
AVM (FT3) =
45.970

METER TEMP.
TM (DEGREE F) =
79.98

METER Y
FCTR YM =
0.976

VOL OF H2O
VM (ML-GM) =
113.30

STACK TEMP.
TS (DEGREE F) =
107.67

SORT AVG.
DELTA P =
1.0335

NOZZLE
DIAMETER (IN) =
0.1933

% CO2 =
.01

% O2 =
20.90

% N2 =
79.10

PITOT FCTR
CP =

0.806 RUN

ELAPSED

TIME (MIN) =

72.000000 RUN

STATIC PRESS.

(IN H2O) =

0.60 RUN

STACK DIAMETER

SELECT ONE OF THE
FOLLOWING CODES:

CIRCULAR=1

RECTANGULAR=2

CODE?

1.00 RUN

STK DIA, FT?

3.50 RUN

CALCULATIONS

METER TEMP (R)=539.98

VOL STD=44.10

STACK TEMP (R)=567.67

%MOISTURE=10.79

MM(DRY)=28.84

MM(WET)=27.67

STAK PRESS.=30.02

VELOCITY (FPS)=58.87

STK AREA (FT2)=9.62

ISOKINETIC (Z)=102.20

ACFM=33,981.37

SCFM=28,283.42

DATA ENTRY

PARTICULATE

TOTAL (MG)=

42.30 RUN

F FACTOR-Fd=

0.00 RUN

CALCULATIONS

* Not Applicable

GR/SCF=0.0148

GR/SCF CORRECTED

TO 12% CO2=17.7269 *

GR/ACF=0.0123

LB/HR=3.5813

LB/SCF=2.1103E-6

5.3 PROCESS DATA

THE NESTLÉ COMPANY, INC.

ENGINEERING DIVISION

PLANT: FREEHOLDBY: W. CHOATECKO

JOB: _____


DATE: 11/4/82

DESCRIPTION: _____

SHEET 7 OF 10

REF. DWG. _____

THROUGHPUT VS RPM

At 14 RPM output $\cong$ 5,500#/hr/press

JR 4/15/87

2 presses were feeding into 11 5 11000#

MEC DRYER CONTROL DATA SHEET

SHIFT: 8-4

DATE: 3-25-87

OPERATOR: R. McLeod

SUPERVISOR: S. R.

MEC DRYER CONTROL DATA SHEET											WET SCRUBBER					EXTRACTION STATUS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
TIME	INLET TEMP. (°F)	OUTLET TEMP. (°F)	MOISTURE (%)	WET BIN LEVEL (%)	LIVE BOTTOM SCREWS (% LOAD)	MIXER/BLENDER		PRODUCT USAGE			WET SCRUBBER					"A" SET TO:			"B" SET TO:																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
						CO ₂ (%)	TEMP. (°F)	OIL PLANT	BOILER	DUMP STEER	PUMP PSI	FLOW (GPM)	FLOW Primary	INLET M.I. Press	DISCH M.I. Press	EAST TANK	WEST TANK	WET BIN	EAST TANK	WEST TANK	WET BIN																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
8	660	134	6.2			20	130	X			116	325	125	6.0	4.4																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						</

COMMENTS: (INCLUDE REASONS FOR DOWNTIME, WHEN PERFORMED)

177

Nestle

MEC DRYER CONTROL DATA SHEET

SHIFT: 4-12 DATE: 3/25/87 OPERATOR: W.E. PANKY SUPERVISOR: BAP / JEU

TIME	MEC DRYER CONTROL DATA SHEET										WET SCRUBBER						EXTRACTION STATUS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
	INLET TEMP. (°F)	OUTLET TEMP. (°F)	MOISTURE (%)	WET BIN LEVEL (%)	LIVE BOTTOM SCREWS (% LOAD)	RIBBON BLENDER		PRODUCT USAGE		WET SCRUBBER						"A" SET TO:			"B" SET TO:																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
						CO ₂ (IN)	TEMP. (°F)	OIL PLANT	BOILER	DUMP. STER	PUMP PSI	FLOW (GPH)	FLOW Primary	INLET M.I. Press	DISCH. M.I. Press	EAST TANK	WEST TANK	WET BIN	EAST TANK	WEST TANK	WET BIN																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
4 ⁰⁰	639.2	132.4	12.0	—	—	20	108	X			116	325	125	6.0	4.2		X																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			</

COMMENTS: (INCLUDE REASONS FOR DOWNTIME, IF ANY PERFORMED)

5:00 adding Sumbury grounds to system

All Bin Screens set to 8 RPM. (west tank)

Date: 3-25-87

Operator: *Willard*

Supervisor:

B.A.S.

Shift: 8-4

# 1 VETTER PRESS									
Time	On	RPM	Cone Press	Over. Press	Oil Temp.	Suction Press	Charge Press	Press Cleaned	
8	on	12	-	120	44	5.0	4.5		
9	on	12	-	140	46	5.5	5.5		
10	on	14	-	100	50	5.5	10.5		
11	on	14	-	100	52	6.0	10		
12	on	14	-	90	50	6.0	10		
1	on	14	-	110	56	6.0	10		
2	on	14	-	120	54	6.0	10		
3	on	14	-	100	56	6.0	10		

# 2 VETTER PRESS									
Time	On	RPM	Cone Press	Over. Press	Oil Temp.	Suction Press	Charge Press	Press Cleaned	
	on	12	-	80	40	1.5	13		
	on	12	-	60	42	1.5	13		
	on	14	-	20	44	1.5	13		
	on	14	-	90	44	1.0	13		
	on	14	-	40	44	1.0	13		
	on	14	-	20	46	1.0	13		
	on	14	-	40	48	1.0	13		
	on	14	-	20	48	1.0	13		

# 3 VETTER PRESS									
Time	On	RPM	Cone Press	Over. Press	Oil Temp.	Suction Press	Charge Press	Press Cleaned	
	on	14	-						
	on	14	-						
	on	14	-						
	on	14	-						
	on	14	-						
	on	14	-						
	on	14	-						
	on	14	-						

COMMENTS (include reasons for downtime, M & H Performance)

1 4 1/2

Time	Bin Screws		Unloading Screws		Incline Screws		Truck Screws	
	East Tank	West Tank	East Tank	West Tank	East Tank	West Tank	East Tank	West Tank
8	off	on	off	on	off	on	off	on
9		on	on	on	on	on	on	on
10		on	on	on	on	on	on	on
11		on	on	on	on	on	on	on
12		on	on	on	on	on	on	on
1		on	on	on	on	on	on	on
2		on	on	on	on	on	on	on
3		on	on	on	on	on	on	on

Time	Cycle Time		Blowdown Tank Levels %		Container Transfers	
	"A" Min.	"B" Min.	East	West	Ticket Number	Time
	16-17	16-17	0	60		
	16-17	16-17	0	58		
	16-17	16-17	0	49		
	16-17	16-17	0	48		
	16-17	16-17	0	47		
	16-17	16-17	0	37		
	16-17	16-17	0	30		
	16-17	16-17	0	21		

Date: 3/5/27

Operator: W.E. SAWYER

Supervisor: RVP

Shift: 4:15 - 12:00

Time	# 1 VETTER PRESS									
	On	Off	RPM	Cone Press	Over. Press	Oil Temp.	Suction Press	Charge Press	Press Cleaned	
4:00	ON		14	-	120	60	6.5	9.5		
5:00	ON		14	-	145	58	6	9		
6:00	ON		14	-	140	56	6	9		
7:00	ON		14	-	135	56	6	9		
8:00	ON		14	-	80	48	5	10		
9:00	OFF		-	-	-	-	-	-		
10:00										
11:00										

Time	# 2 VETTER PRESS									
	On	Off	RPM	Cone Press	Over. Press	Oil Temp.	Suction Press	Charge Press	Press Cleaned	
	ON		14	-	85	50	1.5	13		
	ON		14	-	45	50	1.25	12		
	ON		14	-	45	60	1.25	12		
	ON		14	-	30	60	1.5	12		
	ON		14	-	25	45	1.25	13		
	OFF		-	-	-	-	-	-		

Time	# 3 VETTER PRESS									
	On	Off	RPM	Cone Press	Over. Press	Oil Temp.	Suction Press	Charge Press	Press Cleaned	
	ON		14	-	-	-	-	-		
	ON		14	-	-	-	-	-		
	ON		14	-	-	-	-	-		
	ON		14	-	-	-	-	-		
	ON		14	-	-	-	-	-		
	OFF		-	-	-	-	-	-		

COMMENTS (Include reasons for downtime, M & R Performance)

Time	Bin Screws				Unloading Screws				Incline Screws				Truck Screws			
	East Tank	West Tank	East Tank	West Tank	East Tank	West Tank	East Tank	West Tank	East Tank	West Tank	East Tank	West Tank	East Tank	West Tank	East Tank	West Tank
4:00	OFF	ON	OFF	ON	ON	OFF	ON	OFF	ON	OFF	ON	OFF	ON	OFF	ON	OFF
5:00																
6:00																
7:00																
8:00																
9:00																
10:00																
11:00	OFF	ON	OFF	ON	ON	OFF	ON	OFF	ON	OFF	ON	OFF	ON	OFF	ON	OFF

Time	Ext. Cycle Time		Blowdown Tank Levels %		Container Transfers	
	"A" Min.	"B" Min.	East	West	Ticket Number	Time
	25	25	0	15		
	20-25			13		
	20-25			10		
	20-25			6		
	20-25			6		
	20-25			11		
	20-25			16		
	20-25	25	0	27		

5.4 CALIBRATION DATA

5.4.1 PRETEST CALIBRATIONS

York Services

NOZZLE CALIBRATIONS

Date 3/23/87

Calibrated by DRW, KDP

Nozzle diameter Size	D_1	D_2	D_3	D_4	D average
1/8 .125	.125	.125	.126	.001	.125
5/32 .160					
3/16 .1875	.194	.193	.193	.001	.1933
1/4 .250	.250	.251	.252	.002	.251
5/16 .3125	.310	.310	.310	.000	.310
3/8 .375	.378	.377	.377	.001	.377
7/16 .4375					
1/2 .500	.495	.493	.499	.002	.495
5/8 .625					
3/4 .750					
Miscellaneous Diameter					

where: = nozzle diameter measurements in in. tolerance = .001 in.

$D_{1,2,3}$

D_4 = maximum difference in any two measurements = .004 in.

D_{avg} = average of D_1, D_2, D_3

PITOT TUBE CALIBRATION

Pitot Tube Identification Number: "5ft" 4629

Standard Pitot Tube Identification Number: #2

Standard Pitot Tube C_p : 0.99

Calibration Date: 20 MAR 87

Calibrated By: J. L. & K. P.

A-Side Calibration			
Δp_{std} (in. H ₂ O)	⁴⁶²⁹ Δp_s (TEST) (in. H ₂ O)	C_p	Deviation
0.68	1.15	0.761	- 0.045
0.75	1.10	0.817	+ 0.011
0.77	1.10	0.828	+ 0.022
0.75	1.10	0.817	+ 0.011
Average		0.806	$\delta = 0.030$
B-Side Calibration			
Δp_{std} (in. H ₂ O)	Δp_s (in. H ₂ O)	C_p	Deviation
Not checked: only one orientation possible with this Pitot assembly. J.L.			
Average			

$$C_p = C_{p(std)} \sqrt{\frac{\Delta p_{std}}{\Delta p_s}}$$

STACK GAS THERMOCOUPLE CALIBRATION

Identification Number: 544 - 4629

Calibration Date: 23 MAR 67

Calibrated By: J. L.

	Reference Thermometer (°F)	Stack Gas Thermocouple (°F)
Ice Water	33.	34.
Ambient Air	67.	67.
Hot Water	155.	155.
Hot Oil	—	—

DRY GAS METER THERMOMETER CALIBRATION

Identification Number: RAC 1563 & RAC 2096

Calibration Date: 20 MAR 87

Calibrated By: J.L. / K.P.

	Reference Thermometer (°F)	Dry Gas Meter Thermometer (°F)
RAC 1563 — Ambient Air — RAC 2096	67	In 66. Out 67. — — — — — In 66. Out 67
Hot water		

IMPINGER THERMOMETER CALIBRATION

Identification Number: 6 4 8

Calibration Date: 20 MAR 87

Calibrated By: J. L. K. P

	Reference Thermometer (°F)	Impinger Thermometer (°F)
Ice Water		
# 6 — Ambient Air —	67.	66.
# 8		67.

5.4.2 POSTTEST CALIBRATION

POSTTEST CALIBRATION CHECKS

Job No.: 4629

Date: 3 APRIL 87

Client: NESTLE/FREEHOLD, N.J.

Checked By: JL

• Pitot Tube

Pretest pitot tube coefficient 0.806

Any damage to pitot tube prior to start of any test run? NO

Pitot tube coefficient for calculations 0.806

• Stack Thermocouple

Was a pretest temperature correction used? NO

Average stack temperature during test ~ 115°F

Temperature of reference thermometer during recalibration 120°F

Temperature of stack thermocouple during recalibration 119°F

Do values agree within $\pm 1.5\%$? yes

• Impinger Thermometer

Was a pretest Temperature correction used? NO

Posttest reference thermometer reading 67.

Posttest impinger thermometer reading 67.

Do values agree within $\pm 4^{\circ}\text{F}$? yes

• Dry Gas Meter Thermometers

Was a pretest temperature correction used? NO

Posttest thermometer reading at ambient temperature NOT CONDUCTED*

Posttest reference thermometer reading _____

Do they agree within $\pm 10.8^{\circ}\text{F}$? _____

• Dry Gas Meter

Pretest calibration factor, Y 0.976

Posttest calibration factor, Y NOT CONDUCTED*

Is posttest calibration factor within $\pm 5\%$ of pretest factor? _____

* UNIT Suffered irreparable damage subsequent to testing. while lowering unit, the supporting rope broke and unit fell ~ 60 feet to the ground. the unit used has a past history of changing less than 3% per year and 10% during a "before-after" calibration. JL

5.5 LABORATORY DATA



Environmental
Consultants

JIM LEHMANN
Environmental Engineer

York Services Corporation
A Subsidiary of York Research Corporation
Research Drive, Stamford, Connecticut 06906 • Telephone: (203) 325-1371

CHEMICAL ANALYTICAL SERVICES REQUEST

Job No. 01-4629 Client NESTLÉ Date 26 MAR 87 Logged by Jim Lehmann

Sample Number & Type	Parameters to be determined	Chain of Custody
64326 ☐ EPAS ☐ Filter ☐ RY		
64328 ☐ Probe Wash ☐ OUTLET ☐ 1	<i>Net Weight to nearest 0.1 mgm</i>	
64329 ☐ Filter ☐ EPAS ☐ RY		
64321 ☐ GPAS ☐ Outlet ☐ RY		
64322 ☐ Filter ☐ EPAS ☐ OUT ☐ RY		
64324 ☐ Filter ☐ GPAS ☐ OUT ☐ 3		
	<i>Filters maybe oven dried at 100°C, desiccators till cool then weighed. G.L.</i>	

Received by _____ Date _____

Received by _____ Date _____

FINAL DISPOSITION _____

COMMENTS

Record Volumes (approximate) on possible washes for ATONE blank subtraction.

EACH JOB NUMBER MUST APPEAR ON THE WRITTEN REPORT.

RETURN THIS FORM, DULY SIGNED, WITH THE REPORT. COPIES OF THIS FORM MAY BE RETAINED BY YOUR FIRM FOR IN-HOUSE RECORDS.

PARTICULATE ANALYSIS FORM

JOB # 01-4629

Nestle

TYPE OF SAMPLE Particulate / Filters

DATE 4/1/87

Recd. 3/27/87

Net wt to nearest

SAMPLE #	TYPE	GROSS WT.G.	TARE WT.G.	NET WT.G.	VOL. ML.	BLANK G.	RESULTS - 1 mg.	Run
----------	------	-------------	------------	-----------	----------	----------	-----------------	-----

64322	2	0.40634	0.40078	0.00556			5.6 mg	3
-------	---	---------	---------	---------	--	--	--------	---

64326	1	0.39853	0.40642	-0.00789			- 7.9 mg	1
-------	---	---------	---------	----------	--	--	----------	---

64329	2	0.41046	0.40665	0.00381			3.8 mg	2
-------	---	---------	---------	---------	--	--	--------	---

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--

ANALYST A. Harkness

APPROVED BY

J. Lehman

* Filter # 64326 not intact - adhered to rubber gasket.
Scraped and added to acetone.

JOB # 01-4629

TYPE OF SAMPLE Particulate/Acetone

DATE 4/1/87

Rec'd 3/27/87

[illegible]

ANALYST A. Jackson

APPROVED BY

Jim Lehman

5.6 CALCULATION FORMULAE

CALCULATION FORMULAE

PROGRAM 'STACK'

DEFINITIONS

P_s	=	Stack pressure (inches of mercury)
P_b	=	Barometric pressure (inches of mercury)
S_p	=	Static pressure (inches of water)
V_{mstd}	=	Volume of gas sampled (standard cubic feet)
V_m	=	Volume of gas sampled meter conditions (cubic feet)
Y	=	Meter calibration factor
ΔH	=	Average orifice pressure drop (inches of water)
T_m	=	Meter temperature ($^{\circ}F$)
V_{wgas}	=	Volume of water vapor (standard cubic feet)
V_w	=	Volume of water collected (ml)
H_2O	=	Moisture content (vol. %)
MW_d	=	Molecular weight (dry)
MW	=	Molecular weight (wet)
CO_2	=	Carbon Dioxide (vol. %)
O_2	=	Oxygen (vol. %)
N_2	=	Nitrogen (vol. %)
CO	=	Carbon Monoxide (vol. %)
V_s	=	Stack gas velocity (feet per second)
C_p	=	Pitot tube calibration factor
$\sqrt{\Delta p}$	=	Average of square root of Δp
T_s	=	Stack temperature ($^{\circ}F$)
I	=	Isokinetic ratio (%)
$ACFM$	=	Stack gas flow rate (actual cubic feet per minute)
A_s	=	Stack cross-sectional area (square feet)
A_n	=	Nozzle cross-sectional area (square feet)
$SCFM$	=	Stack gas flow rate (standard cubic feet per minute)
M_t	=	Pollutant sample weight (mg)

T_t	=	Test time (minutes)
gr/SCF	=	Emission concentration (grains per standard cubic foot)
gr/ACF	=	Emission concentration (grains per actual cubic foot)
lb/hr	=	Emission rate (pounds per hour)
lb/dscf	=	Emission rate (pounds per dry standard cubic foot)
F_d	=	F-factor
lb/MMBTU	=	Emission rate (pounds per million BTU heat input)

FORMULAE

P_s	=	$P_b + \text{or } - (S_p/13.6)$
V_{mstd}	=	$(V_m)(Y)(17.64)(P_b + \Delta H/13.6)/(T_m + 460)$
V_{wgas}	=	$(0.04707)(V_w)$
H_2O	=	$\left[V_{wgas} / (V_{wgas} + V_{mstd}) \right] (100)$
MW_d	=	$(.44)(CO_2) + (.32)(O_2) + (.28)(N_2 + CO)$
MW	=	$MW_d(1 - H_2O/100) + 18(H_2O/100)$
V_s	=	$85.49(C_p)(\sqrt{\Delta p}) \left[(T_s + 460)/(P_s)(MW) \right]^{1/2}$
I	=	$\frac{(0.09450)(T_s + 460)(V_{mstd})}{(P_s)(V_s)(A_n)(T_t)(1 - (H_2O/100))}$
ACFM	=	$(V_s)(A_s)(60)$
SCFM	=	$(17.64)(ACFM)(P_s/(T_s + 460))(1 - H_2O/100)$
gr/SCF	=	$(M_t)(.0154)/(V_{mstd})$
gr/ACF	=	$(M_t)(.0154)/(V_m)$
gr/SCF @ 12% CO_2	=	$(gr/SCF)(12/CO_2)$
lb/hr	=	$(gr/SCF)(SCFM)(60)/(7000)$
lb/dscf	=	$(gr/SCF)/(7000)$
lb/MMBTU	=	$(lb/dscf)(F_d)(20.9)/(20.9 - O_2)$

#2



York Services Corporation

- Energy and Environmental Systems Engineering
- Atmospheric Sciences Services
- Emission Measurement Services

One Research Drive
Stamford, Connecticut 06906
Telephone (203) 325-1371
TWX 710-474-3947

May 1, 1987

NJDEP
Division of Environmental Quality
CN-027
Trenton, NJ 08625

Attention: Mr. Edward Choromanski

Subject: Nestle Food Corporation
Final Test Report - MEC Dryer-

Dear Mr. Choromanski:

Enclosed please find two copies of the final test report which describes the results of the emission compliance test program conducted on the MEC Dryer at Nestle Foods Corporation in Freehold, NJ.

If you have any questions, or require additional information, please call.

Very truly yours,

A handwritten signature in cursive script, reading 'Roger A. Kniskern', followed by a horizontal line.

Roger A. Kniskern
Manager Emissions Measurement

RK/sb
Enclosures

Let's protect our earth



State of New Jersey
DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF ENVIRONMENTAL QUALITY
CENTRAL REGIONAL OFFICE, AIR PROGRAM
TWIN RIVERS PROFESSIONAL BLDG.
EAST WINDSOR, NJ 08520

MEMORANDUM

TO: Lou Mikolajczyk, Chief

FROM: Joseph N. DePierro, Regional Enforcement Officer


SUBJECT: Nestle Foods, Freehold I.D. # 20004 Stack Test 3-25-87

DATE: April 14, 1987

Attached is a report supplied to me by Mr. Paul Orlando regarding subject matter. I have examined Mr. Orlando's report and concur that an ~~en~~ accurate feed rate was difficult to determine. Furthermore, I do not feel that an extrapolated feed rate is prudent in obtaining process weights in order to determine control efficiency.

Please examine Mr. Orlando's report and discuss it with your staff. It is my position that a more accurate method should be implemented by subject facility in determining feed rate. In addition I feel that a retest must be conducted once accurate feed rates can be determined.

Please advise Mr. Orlando of your findings and recommendations; if any questions arise and feel free to contact this office.


Joseph N. DePierro
Regional Enforcement Officer

nlg

c: P. Orlando
S. Hawthorne



State of New Jersey
DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF ENVIRONMENTAL QUALITY
CENTRAL REGIONAL OFFICE, AIR PROGRAM
TWIN RIVERS PROFESSIONAL BLDG.
EAST WINDSOR, NJ 08520

MEMORANDUM

TO: Joseph N. DePierro
FROM: Paul G. Orlando
SUBJECT: Nestle Foods Stack Test - Conducted on 3-25-87
DATE: April 8, 1987

Stack tests were conducted on Nestle Foods' # 51 rotary dryer (P/CT # 75818, N.J. stack # 050) for particulate emissions. Tests were performed by York Research Corporation. I was in attendance for the purpose of monitoring operating parameters and production rates. Parameters measured for this test were fuel oil feed rate; scrubber liquid flow, dryer exit temperature and coffee grounds feed rate. The coffee grounds feed rate could not be accurately measured during the test period due to a lack of measurement devices. Instead, the feed rate was estimated by measuring the revolutions per minute of the two Vetter presses and then obtaining the weight from a calibration chart of throughput vs R.P.M.. For example, a press conveyor screw speed of 12 R.P.M. would relate to a 4400 pound (dry basis) of coffee throughput. (see 11/4/82 chart attached) This method is a very crude technique for determining coffee throughput. More important, this calibration chart is over four years old! Since coffee ground throughput is the most important parameter measured for determination of scrubber efficiency, I do not feel this method should be accepted by our Department. Instead, I suggest that either the screw conveyors be re-calibrated with representatives of our Department present to insure their validity or the stack test be disapproved until a more accurate technique of determining coffee ground throughput can be developed.

The process operation during the stack test proceeded with minimal downtime. The only occurrence of concern was when the # 2 Vetter press shut down for a period of ten minutes during test # 3. The shut down was caused by excessive moisture content in the coffee grounds being fed to the Vetter presses. This downtime would reduce the amount of coffee

grounds fed to the dryer during this period. In conclusion, I would like to reiterate my opinion that the values for coffee ground feed rate are not accurate and should not be accepted as the actual feed rates for the specified test period. (A summary of the process parameters will follow.)



Paul G. Orlando
Environmental Engineer Trainee

nlg

c. E. Choromanski

Summary of Operating Parameters

	Test # 1	Test # 2	Test # 3	Permit Requirements
Fuel Oil Feed Rate (gal/hr)	6	6	6	120 (max)
Scrubber Flow Rate (gal/hr)	325	325	325	None
Dryer Exit Temp. (°F)	126	126	126	200 (max)
Coffee Grounds Feed Rate (lb/hr) (Dry Basis)	13,000	12,000	10,000*	11,111

• grossly estimated due to downtime of # 2 press

STACK TEST DATA FOR NESTLE FOODS CORP.
Test Conducted on 3-25-87

Scrubber Flow		Coffee Ground		Dryer Exit		Fuel Oil		Comments
		Feed Rate		Temp.	Feed Rate			
Time	GPM	Time	Press #1 (RPM)	Press #2 (RPM)	Time	Temp. (°F)	Time	Gal
	Test	#	1	Started	at	10:10		
10:10	325	10:13	16	16	10:10	128	10:10	29
	325	10:45	16	16	10:47	124		
	325	11:12	16	14	11:10	125	11:10	35
11:24	325	11:24	16	*	11:24	125		
								* Press # 2 Stopped rotating at 11:24 due to excessive moisture in coffee ground feed. Test # 1 was finished at this time. Should not affect results of this test.
Test # 1 finished at 11:24								
	Test	#	2	Started	at	12:30		
12:35	325	12:30	14	14	12:35	126	12:35	45
	325	13:12	14	14	13:12	125		
	325	13:35	14	14	13:37	125		
13:50	325	13:49	14	14	13:50	125	13:37	51
Test # 2 finished at 13:50								
	Test	#	3	Started	at	13:50		
14:52	325	14:48	14	14	14:51	125	14:52	59
	325	15:05	14	**				
	325	15:15	-	17	15:15	125		
	325	15:25	14	17	15:45	125	16:00	65
								** Press # 2 stopped running for a period of 10 minutes during test # 3. This could affect the results of test # 3 since it makes it difficult to determine the actual feed rate for this run.
Test # 3 finished at 16:10								

CALCULATION SHEET

THE NESTLÉ COMPANY, INC.

ENGINEERING DIVISION

PLANT: FREEHOLDBY: W. CHOATECKO


JOB: _____

DATE: 11/4/82

DESCRIPTION: _____

SHEET 7 OF 10

REF. DWG. _____



NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF ENVIRONMENTAL QUALITY
TECHNICAL SERVICES

EMISSION TEST OBSERVATION

1) Company: The Nestle Company, Inc

Address: 61 Jerseyville Ave

City/State: Freehold NJ Phone: (201) 462-1300

DEP ID No. 20004 Plant Contact: Jeff Carter

2) Source being tested: NJ Stack No. 051 Permit/Certificate No. 075818

3) Date of Test(s): 3/25/87

4) Consultant Company conducting tests: YORK Services Corporation

Name(s) of persons conducting tests: Jim Lehmann

Ken Pinkney

Name(s) of all other persons involved in the test program (include all Agency, Company and Contractors and their affiliation).

PERSON

AFFILIATION

Paul Orinade Central Field Office

- 5) Outlet tests conducted for the following pollutants:
- | | |
|---|---|
| ☒ Particulates | ☐ Heavy Metals |
| ☐ Hydrocarbons | ☐ HCL |
| ☐ SO ₂ | ☐ CO |
| ☐ SO ₂ /SO ₃ | ☐ Specific Organics: _____ |
| ☐ NO _x | ☐ Other: _____ |

Were any inlet tests conducted: ☐ Yes ☒ No

If yes, indicate the pollutant tested for. _____

6) How many tests were observed this date: (If more than one date, indicate test runs observed on each date).

DATE

NO. OF TEST RUNS OBSERVED

3/25/87

#1 10:10^{am} - 11:27^{am}

#2 12:30^{pm} - 1:49^{pm}

#3 2:45^{pm} - 4:02^{pm}

- 10) Were any continuous emission monitors used in conjunction with those tests: ☐ Yes ☒ No

If yes, indicate the following information:

POLLUTANT	PRINCIPLE OF MONITOR	NO. OF SPAN GASES	SPAN GAS CONCENTRATIONS
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Strip Chart Speed: _____

Were monitors calibrated prior to each test: ☐ Yes ☐ No

If no, explain why not: _____

- 11) Were tests conducted in accordance with the approved protocol: ☒ Yes ☐ No

If no, indicate difference and reasons for change: _____

Were changes approved: ☐ Yes ☐ No If yes, indicated by whom: _____

If no, indicated reason: _____

- 12) Record and list other pertinent information or problems regarding these tests not previously recorded:

T₁ & T₂ were taken outside the glass and not the actual gas stream temp. ^{was} Run 1 failed leak check. Test will be recalculated. Total vol = Initial total volume (1.007 ^{lit} 72 ^{min}) (see back) Final

- 13) Was company representative notified of any problems regarding the tests: ☒ Yes ☐ No

If yes, indicate company representative: *Jeff Caster - Nestle*

If no, indicate reason: _____

Signature of Observer: *Thomas P. Brown*

Title: *Env. Specialist*

Date: *3/25/87*

Reviewed by: *[Signature]*

Date: *3/26/87*

TEST VOID BECAUSE
PROCESS RATES ARE ESTIMATES

Section 4 Reference ☒

AP-42 Reference ☐

(#2)

Emission Test Report Review Checklist--Short Form

Reviewer: TLAPP
Review Date: 8/18/94

A. Background Information


1. Facility name: NESTLE Food Corp.
Location: Freehold, NJ
2. Source category: Coffee Roasting
3. Test date: MARCH 25, 1987
4. Test sponsor: NESTLE Food Corp.
5. Testing contractor: YORK SERVICES Corp.
6. Purpose of test: COMPLIANCE TEST FOR PM EMISSIONS
7. Pollutants measured (include test method and indicate if valid): TOTAL PM 40 CFR 60, APP. A, METHODS 1-5

8. Process overview: Attach a process description and a block diagram. Identify processes tested with letters from the beginning of the alphabet (A, B, C, etc...) and APC systems with letters from the end of the alphabet (V, W, X, etc...). Also identify test locations with Arabic numerals (1, 2, 3, ...). Using the ID symbols from the diagram, complete the table below.

Test ID	Process	Process ID	Emissions tested		APCD (controlled emissions only)
			Uncontrolled	Controlled	
	ROTARY DRYER (MEC DRYER)	NJ STACK No. 051		scrubber/ demister	ID: Type: Model #:
					ID: Type: Model #:
					ID: Type: Model #:
					ID: Type: Model #:

B. Process Information

1. Provide a brief narrative description of the process and attach process flow diagram. (Note: If the process description provided in the test report is adequate, attach a copy here.)





State of New Jersey
DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF ENVIRONMENTAL QUALITY
CENTRAL REGIONAL OFFICE, AIR PROGRAM
TWIN RIVERS PROFESSIONAL BLDG.
EAST WINDSOR, NJ 08520


MEMORANDUM

TO: Joseph N. DePierro
FROM: Paul G. Orlando
SUBJECT: Nestle Foods Stack Test - Conducted on 3-25-87
DATE: April 8, 1987

Stack tests were conducted on Nestle Foods' # 51 rotary dryer (P/CT # 75818, N.J. stack # 050) for particulate emissions. Tests were performed by York Research Corporation. I was in attendance for the purpose of monitoring operating parameters and production rates. Parameters measured for this test were fuel oil feed rate; scrubber liquid flow, dryer exit temperature and coffee grounds feed rate. The coffee grounds feed rate could not be accurately measured during the test period due to a lack of measurement devices. Instead, the feed rate was estimated by measuring the revolutions per minute of the two Vetter presses and then obtaining the weight from a calibration chart of throughput vs R.P.M.. For example, a press conveyor screw speed of 12 R.P.M. would relate to a 4400 pound (dry basis) of coffee throughput. (see 11/4/82 chart attached) This method is a very crude technique for determining coffee throughput. More important, this calibration chart is over four years old! Since coffee ground throughput is the most important parameter measured for determination of scrubber efficiency, I do not feel this method should be accepted by our Department. Instead, I suggest that either the screw conveyors be re-calibrated with representatives of our Department present to insure their validity or the stack test be disapproved until a more accurate technique of determining coffee ground throughput can be developed.

The process operation during the stack test proceeded with minimal downtime. The only occurrence of concern was when the # 2 Vetter press shut down for a period of ten minutes during test # 3. The shut down was caused by excessive moisture content in the coffee grounds being fed to the Vetter presses. This downtime would reduce the amount of coffee

grounds fed to the dryer during this period. In conclusion, I would like to reiterate my opinion that the values for coffee ground feed rate are not accurate and should not be accepted as the actual feed rates for the specified test period. (A summary of the process parameters will follow.)



Paul G. Orlando
Environmental Engineer Trainee

nlg

c. E. Choromanski

NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF ENVIRONMENTAL QUALITY
TECHNICAL SERVICES

EMISSION TEST OBSERVATION

1) Company: The Nestle Company, Inc

Address: 61 Jerseyville Ave

City/State: Freehold NJ Phone: (201) 462-1300

DEP ID No. 20004 Plant Contact: Jeff Cantor

2) Source being tested: NJ Stack No. 051 Permit/Certificate No. 075818

3) Date of Test(s): 3/25/87

4) Consultant Company conducting tests: YORK Services Corporation

Name(s) of persons conducting tests: Jim Lehmann

Ken Pinckney

Name(s) of all other persons involved in the test program (include all Agency, Company and Contractors and their affiliation).

PERSON	AFFILIATION
<u>Paul Orlando</u>	<u>Central Field Office</u>

5) Outlet tests conducted for the following pollutants:

☒ Particulates	☐ Heavy Metals
☐ Hydrocarbons	☐ HCL
☐ SO ₂	☐ CO
☐ SO ₂ /SO ₃	☐ Specific Organics: <u> </u>
☐ NO _x	☐ Other: <u> </u>

Were any inlet tests conducted: ☐ Yes ☒ No

If yes, indicate the pollutant tested for.

6) How many tests were observed this date: (If more than one date, indicate test runs observed on each date).

DATE	NO. OF TEST RUNS OBSERVED
<u>3/25/87</u>	<u>#1 10:10^{AM} - 11:27^{AM}</u>
	<u>#2 12:30^{PM} - 1:49^{PM}</u>
	<u>#3 2:45^{PM} - 4:02^{PM}</u>

- 10) Were any continuous emission monitors used in conjunction with those tests: ☐ Yes ☒ No

If yes, indicate the following information:

POLLUTANT	PRINCIPLE OF MONITOR	NO. OF SPAN GASES	SPAN GAS CONCENTRATIONS
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Strip Chart Speed: _____

Were monitors calibrated prior to each test: ☐ Yes ☒ No

If no, explain why not: _____

- 11) Were tests conducted in accordance with the approved protocol: ☒ Yes ☐ No

If no, indicate difference and reasons for change: _____

Were changes approved: ☐ Yes ☐ No If yes, indicated by whom: _____

If no, indicated reason: _____

- 12) Record and list other pertinent information or problems regarding these tests not previously recorded:

*T₁ - T₃ were taken outside the glass and ^{were} not the actual gas stream temp temperature. * Run 1 failed leak check. Test will be recalculated. Total vol = Initial total volume (1.0077 ^{min} 72 m (see back) Final*

- 13) Was company representative notified of any problems regarding the tests: ☒ Yes ☐ No

If yes, indicate company representative: *Jeff Cantore - Nestle*

If no, indicate reason: _____

Signature of Observer: *[Signature] P. Brown*

Title: *Env. Specialist*

Date: *3/25/87*

Reviewed by: *[Signature]*

Date: *3/26/87*