

Note: This is a reference cited in AP 42, *Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

PM10 Emissions Sampling
Kirby Forest Products, Silsbee, TX
March 2 - 5, 1992
Armstrong Environmental Inc.
Project W-1159-92

Report Prepared For:
Dr. James Boswell
Louisiana-Pacific Corporation
PO Box 3107
Conroe, TX 77305

Report Prepared March 16, 1992 By:
Armstrong Environmental Inc.
4747 Irving Blvd. #204
Dallas, Texas 75247
(214) 631-0021

TABLE OF CONTENTS

I. INTRODUCTION	Page 1
II. SUMMARY	2 - 7
III. PROCEDURES	8
IV. APPENDICES	
A - CALCULATION SUMMARIES	9 - 61
B - ANALYTICAL SUMMARIES	62 - 92
C - FIELD DATA SHEETS	93 - 107
D - EQUIPMENT CALIBRATIONS	108 - 134
E - CHAIN OF CUSTODY RECORDS	135 - 142

I. INTRODUCTION

A series of tests were performed on the exhaust stacks associated with Dryers #1 - #5 at the Kirby Forest Products facility in Silsbee, TX on March 2 - 5, 1992.

The purpose of this test series was to determine the exhaust emission rate of PM-10 in terms of lbs/hr.

Sampling was performed following procedures detailed in Title 40: Code of Federal Regulations (40:CFR).

Sampling was performed by Tom Armstrong, Larry Whicher, Joe Barrera, Jerry Salinas, Mark Peterson, and Danny Barrera of Armstrong Environmental, Inc. using two NAPP Model 31 Method 5 sampling trains and two Anderson PM10 instack cyclones.

Dryer #4 and 5 were sampled on March 2, Dryer #3 on March 3, and Dryer #1 and 2 on March 5. Three two hour test repetitions were performed on each source, and sampling was performed over an eight hour period each day.

Submitted by:
Armstrong Environmental, Inc.

Tom Armstrong ^{os}

Tom Armstrong
President

TA/os

II. SUMMARY

A series of tests were performed on the exhaust stacks associated with Dryers #1 - #5 on March 2 - 5, 1992 at the Kirby Forest Products facility in Silsbee, TX.

Testing was conducted following procedures detailed in 40:CFR, Parts 51 and 60.

The results of this test series are summarized in Tables 1 - 5 for Dryers #1 - #5, respectively.

Results indicate the following PM10 emission rates:

Repetition	1	2	3
Dryer #1 - 3/5/92	17.42	18.44	17.83
Dryer #2 - 3/5/92	17.16	14.51	11.97
Dryer #3 - 3/3/92	15.41	13.89	14.41
Dryer #4 - 3/2/92	16.39	18.23	17.97
Dryer #5 - 3/2/92	14.95	15.28	16.72

FRONT HAZZ
ONLY

Based on the results of this test series the following comments can be made:

1. At the tests conclusion on Dryer #5, some nozzle damage was noted. Nozzle was reamed and recalibrated on March 3 for Dryer #3.

2. A test series was performed on Dryers #2 and #3 on February 26 and 27, 1992. Due to questions concerning clean-up and sample storage, these runs were rejected and rerun the following week.

SUMMARY OF PM10 EMISSIONS DATA

TABLE: 1

PLANT: Kirby Forest Products, Silsbee, TX

LOCATION: Dryer #1 Exhaust

OPERATOR: Jerry Salinas

TEST DATE: March 5, 1992

REPETITION:

STACK GAS

	1	2	3
Temperature, F	183.5	182.5	181.9
Velocity, fps	80.28	81.85	82.03
Volume Flow, acfm	45244	46131	46233
scfm	31164	32037	31894
scfh	1869819	1922224	1913653
Moisture, %	16.37	15.80	16.43
CO2, %	2.0	2.0	2.0
O2, %	18.0	18.0	18.0

SAMPLE

Start Time, hrs:min	9:49am	12:16pm	2:46pm
Finish Time, hrs:min	11:18am	2:26pm	4:54pm
Volume, scf	44.351	45.399	45.791
Isokinetic Ratio, %	111.60	108.71	110.13
Cyclone Flow, acfm	0.5185	0.5149	0.5228
Cutpoint, D50	10.05	10.09	9.97
Minimum Delta P	1.14	1.13	1.16
Maximum Delta P	2.71	2.69	2.77
Number of Points			
Outside range	0	0	0

CYCLONE CATCH

Sample Weight, mg	6.4	5.85	6.05
Concentration, gr/scf	0.0022	0.0020	0.0020
Emissions, lbs/hr	0.595	0.546	0.557

PM10

Sample Weight, mg	187.4	182.5	193.4
Concentration, gr/scf	0.0652	0.0672	0.0652
Emissions, lbs/hr	17.42	18.44	17.83
	2.2	2.3	2.3

IMPINGERS

Sample Weight, mg	14.4	6.4	10.1
Concentration, gr/scf	0.0050	0.0022	0.0034
Emissions, lbs/hr	1.339	0.597	0.931
	0.17	0.076	0.12

7.9 TON/HR PROC. RATE

2.3 lb/ton

0.12 lb/ton

2.4 lb/ton

SUMMARY OF PM10 EMISSIONS DATA

TABLE: 2

PLANT: Kirby Forest Products, Silsbee, TX

LOCATION: Dryer #2 Exhaust

OPERATOR: Mark Peterson

TEST DATE: March 5, 1992

REPETITION:

STACK GAS

	1	2	3
Temperature, F	177.8	176.9	174.5
Velocity, fps	78.98	81.19	81.07
Volume Flow, acfm	44516	45759	45690
scfm	31196	31786	32375
scfh	1871737	1907150	1942474
Moisture, %	15.66	16.51	15.16
CO2, %	2.0	2.0	2.0
O2, %	18.5	19.0	19.0

SAMPLE

Start Time, hrs:min	9:22am	11:51am	2:12pm
Finish Time, hrs:min	11:24am	1:50pm	4:15pm
Volume, scf	46.352	44.042	44.007
Isokinetic Ratio, %	111.83	105.95	103.6
Cyclone Flow, acfm	0.5425	0.5283	0.5157
Cutpoint, D50	9.69	9.85	10.01
Minimum Delta P	1.11	1.05	1.01
Maximum Delta P	2.67	2.52	2.42
Number of Points			
Outside range	0	0	0

CYCLONE CATCH

Sample Weight, mg	7.65	9.15	5.40
Concentration, gr/scf	0.0027	0.0032	0.0019
Emissions, lbs/hr	0.711	0.873	0.525

PM10

Sample Weight, mg	184.435	152.04	123.05
Concentration, gr/scf	0.0641	0.0533	0.0431
Emissions, lbs/hr	17.16	14.51	11.97
	2.2	1.8	1.5

IMPINGERS

Sample Weight, mg	5.85	3.30	3.00
Concentration, gr/scf	0.0020	0.0012	0.0011
Emissions, lbs/hr	0.544	0.315	0.292
	0.069	0.040	0.037

2.3

1.8

1.5

0.049 lbs/hr

SUMMARY OF PM10 EMISSIONS DATA

TABLE: 3

PLANT: Kirby Forest Products, Silsbee, TX

LOCATION: Dryer #3 Exhaust

OPERATOR: Jerry Salinas

TEST DATE: March 3, 1992

REPETITION:

1

2

3

STACK GAS

Temperature, F	173.8	172.7	172.7
Velocity, fps	76.91	77.21	78.07
Volume Flow, acfm	43346	43509	44002
scfm	30721	30507	31443
scfh	1843270	1830401	1886559
Moisture, %	15.99	17.03	15.44
CO2, %	1.0	1.5	1.0
O2, %	20.0	19.5	19.0

SAMPLE

Start Time, hrs:min	9:10am	11:37am	2:10pm
Finish Time, hrs:min	11:14am	1:45pm	3:27pm
Volume, scf	43.619	43.622	43.596
Isokinetic Ratio, %	107.38	107.21	104.10
Cyclone Flow, acfm	0.5069	0.5083	0.4997
Cutpoint, D50	10.12	10.05	10.22
Minimum Delta P	0.98	0.99	0.95
Maximum Delta P	2.35	2.36	2.26
Number of Points			
Outside range	1	1	1

CYCLONE CATCH

Sample Weight, mg	34.25	22.15	18.35
Concentration, gr/scf	0.0121	0.0078	0.0065
Emissions, lbs/hr	3.19	2.05	1.75

PM10

Sample Weight, mg	165.44	150.195	150.99
Concentration, gr/scf	0.0585	0.0531	0.0534
Emissions, lbs/hr	15.41	13.89	14.41
	2.0	1.8	1.8

IMPINGERS

Sample Weight, mg	6.2	4.5	4.45
Concentration, gr/scf	0.0022	0.0016	0.0016
Emissions, lbs/hr	0.578	0.416	0.424

0.073

0.053

0.054

= 0.046 lbs/hr

2.1

1.9

1.9

2.0

SUMMARY OF PM10 EMISSIONS DATA

TABLE: 4

PLANT: Kirby Forest Products, Silsbee, TX

LOCATION: Dryer #4 Exhaust

OPERATOR: Jerry Salinas

TEST DATE: March 2, 1992

REPETITION:

STACK GAS

	1	2	3
Temperature, F	169.4	169.1	167.9
Velocity, fps	82.50	77.67	84.15
Volume Flow, acfm	46495	43778	47429
scfm	33141	31622	33647
scfh	1988489	1897337	2018799
Moisture, %	16.37	15.29	16.97
CO2, %	2.0	1.0	1.5
O2, %	19.5	19.0	19.0

SAMPLE

	1	2	3
Start Time, hrs:min	10:54am	2:25pm	4:50pm
Finish Time, hrs:min	1:11pm	4:23pm	6:53pm
Volume, scf	44.811	38.709	42.536
Isokinetic Ratio, %	103.42	108.31	102.62
Cyclone Flow, acfm	0.4935	0.4869	0.4998
Cutpoint, D50	10.22	10.33	10.09
Minimum Delta P	1.07	1.03	1.09
Maximum Delta P	2.55	2.47	2.61
Number of Points			
Outside range	1	1	1

CYCLONE CATCH

	1	2	3
Sample Weight, mg	18.45	8.8	19.15
Concentration, gr/scf	0.0064	0.0035	0.0069
Emissions, lbs/hr	1.81	0.951	2.00

PM10

	1	2	3
Sample Weight, mg	167.6	168.675	171.74
Concentration, gr/scf	0.0577	0.0672	0.0623
Emissions, lbs/hr	16.39	18.23	17.97
	2.1	2.3	2.3

IMPINGERS

	1	2	3
Sample Weight, mg	7.6	7.5	8.6
Concentration, gr/scf	0.0026	0.0030	0.0031
Emissions, lbs/hr	0.743	0.811	0.900
	0.094	0.10	0.11

	1	2	3
	2.2	2.4	2.4

= 0.10 lbs/hr

2.3

SUMMARY OF PM10 EMISSIONS DATA

TABLE: 5

PLANT: Kirby Forest Products, Silsbee, TX

LOCATION: Dryer #5 Exhaust

OPERATOR: Larry Whicher

TEST DATE: March 2, 1992

REPETITION:

1

2

3

STACK GAS

Temperature, F	163.4	164.5	161.8
Velocity, fps	80.45	80.39	79.78
Volume Flow, acfm	45340	45308	44962
scfm	32810	32903	33032
scfh	1968607	1974164	1981939
Moisture, %	15.63	15.18	14.56
CO2, %	1.5	1.0	1.5
O2, %	19.5	19.0	19.0

SAMPLE

Start Time, hrs:min	9:45am	1:31pm	4:38pm
Finish Time, hrs:min	12:00pm	3:35pm	6:40pm
Volume, scf	39.299	38.963	39.528
Isokinetic Ratio, %	102.57	100.09	102.07
Cyclone Flow, acfm	0.4555	0.4428	0.4481
Cutpoint, D50	10.76	11.00	10.87
Minimum Delta P	1.01	0.95	0.98
Maximum Delta P	2.41	2.27	2.35
Number of Points			
Outside range	1	1	1

CYCLONE CATCH

Sample Weight, mg	28.2	15.6	24.85
Concentration, gr/scf	0.0111	0.0062	0.0097
Emissions, lbs/hr	3.11	1.74	2.75

PM10

Sample Weight, mg	135.38	136.76	151.29
Concentration, gr/scf	0.0532	0.0542	0.0591
Emissions, lbs/hr	14.95	15.28	16.72
	1.9	1.9	2.1

IMPINGERS

Sample Weight, mg	5.6	4.5	3.45
Concentration, gr/scf	0.0022	0.0018	0.0014
Emissions, lbs/hr	0.618	0.502	0.381
	0.078	0.064	0.048

2.0

2.0

2.1

2.0

0.063 lb/hr

III. PROCEDURES

The procedure for emissions sampling followed USEPA test methods as detailed in Title 40: Code of Federal Regulations. The following methods were used from Part 60, Appendix A;

Method	Title
1	Sample and Velocity Traverses from Stationary Sources
2	Determination of Stack Gas Velocity and Volumetric Flow (Type S Pitot)
3	Gas Analysis for CO ₂ , O ₂ , Excess Air and Dry Molecular Weight
4	Determination of Moisture Content in Stack Gases
5	Determination of Particulate Emissions from Stationary Sources

The following procedures were used from Part 51, Appendix M:

201A	Determination of PM ₁₀ Emissions (Constant Sampling Rate Procedure)
------	--

CO₂ and O₂ were determined using a Fyrite Analyzer

?? QUALITY ??

Sampling was performed using two Napp Model 31 sampling trains equipped with two Anderson Samplers stainless steel instack cyclones. The train was modified slightly from that required in 201A by eliminating the instack filter and using the heated filter from the Method 5 sampling train.

(*)
METHOD
5
FILTER
TEMP

Nozzle #1 (nominal .136 inch diameter) was used on all stacks. Specific nozzle sizes are listed in the field data sheets in Appendix C.

Sampling was targeted for 5.0 minutes at each of 24 points making a total run duration target of 120 minutes. Run lengths varied between 109 minutes and 127 minutes.

Sample clean-up and recovery took place at ground level in a van. Chain of custody forms were maintained throughout, samples being recovered by either Tom Armstrong or Joe Barrera. Samples were stored in the back of the van, transported to Dallas in the same, and analyzed by Joe Barrera March 6, 7 and 8.

APPENDIX A

Kirby
Dryer #1
3/5/92
Repetition 1

CUTPOINT, D50 = 10.05222

CYCLONE FLOW, CU FT/MIN = .5185462

NOZZLE VELOCITY, FT/SEC = 89.58546

MINIMUM NOZZLE VELOCITY, FT/SEC = 67.99365

MAXIMUM NOZZLE VELOCITY, FT/SEC = 104.8564

MINIMUM DELTA P = 1.142784

MAXIMUM DELTA P = 2.717639

Kirby
Dryer #1
3/5/92
Repetition # 1

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 44.3514$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 8.679708$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .163672$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.04$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.23306$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.11088$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 80.28028$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 45244.36$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1869819$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 111.6018$

Kirby
Dryer #1
3/5/92
Repetition # 1

PRESSURE DROP ACROSS ORIFICE, H = .48
METER CO-EFFICIENT, Y = .9689
METER TEMPERATURE, TM = 97.3125
BAROMETRIC PRESSURE, PBAR = 30.03
GAS METER VOLUME, VM = 48.102
LIQUID COLLECTED, VLC = 184.4
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = 1.1
STACK TEMPERATURE, TS = 183.4583
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.262014
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 123.9
AREA OF NOZZLE, AN = 9.647846E-05
CO2 % = 2
O2 % = 18
CO % = 0

Kirby
Dryer #1
3/5/92
Repetition 2

CUTPOINT, D50 = 10.09991

CYCLONE FLOW, CU FT/MIN = .5149572

NOZZLE VELOCITY, FT/SEC = 88.96541

MINIMUM NOZZLE VELOCITY, FT/SEC = 67.49575

MAXIMUM NOZZLE VELOCITY, FT/SEC = 104.1099

MINIMUM DELTA P = 1.129942

MAXIMUM DELTA P = 2.688359

Kirby Forest Products

Dryer #1

3/5/92

Repetition # 2

PRESSURE DROP ACROSS ORIFICE, H = .48

METER CO-EFFICIENT, Y = .9689

METER TEMPERATURE, TM = 96.75

BAROMETRIC PRESSURE, PBAR = 30.03

GAS METER VOLUME, VM = 49.189

LIQUID COLLECTED, VLC = 181

PARTICULATE SAMPLE WEIGHT, MN = 0

STATIC PRESSURE, SP = -.95

STACK TEMPERATURE, TS = 182.5

PITOT CO-EFFICIENT, CP = .84

SQUARE ROOT OF DELTA P, DP = 1.288939

AREA OF STACK, AS = 9.392999

TEST DURATION, T = 126.7

AREA OF NOZZLE, AN = 9.647846E-05

CO2 % = 2

O2 % = 18

CO % = 0

Kirby Forest Products
Dryer #1
3/5/92
Repetition # 2

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 45.39947$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 8.519671$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1580083$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.04$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.29559$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.09985$

STACK GAS VELOCITY, FPS
 $(SGR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 81.85306$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 46130.75$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92)) * AS * V * (1 - BWS) * 3600 = 1922224$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 108.7084$

Kirby
Dryer #1
3/5/92
Repetition 3

CUTPOINT, D50 = 9.972678

CYCLONE FLOW, CU FT/MIN = .5228284

NOZZLE VELOCITY, FT/SEC = 90.32525

MINIMUM NOZZLE VELOCITY, FT/SEC = 68.59787

MAXIMUM NOZZLE VELOCITY, FT/SEC = 105.7511

MINIMUM DELTA P = 1.165301

MAXIMUM DELTA P = 2.769408

Kirby
Dryer #1
3/5/92
Repetition # 3

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 45.79186$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 9.004491$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1643265$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.04$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.22584$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.10096$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 82.03495$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 46233.25$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92)) * AS * V * (1 - BWS) * 3600 = 1913653$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISO KINETIC RATIO, %
 $((VMSTD / 17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 110.1353$

Kirby
Dryer #1
3/5/92
Repetition # 3

PRESSURE DROP ACROSS ORIFICE, $H = .48$
METER CO-EFFICIENT, $Y = .9689$
METER TEMPERATURE, $TM = 91.97916$
BAROMETRIC PRESSURE, $PBAR = 30.03$
GAS METER VOLUME, $VM = 49.189$
LIQUID COLLECTED, $VLC = 191.3$
PARTICULATE SAMPLE WEIGHT, $MN = 0$
STATIC PRESSURE, $SP = .965$
STACK TEMPERATURE, $TS = 181.9583$
PITOT CO-EFFICIENT, $CP = .84$
SQUARE ROOT OF DELTA P, $DP = 1.290719$
AREA OF STACK, $AS = 9.392999$
TEST DURATION, $T = 126.7$
AREA OF NOZZLE, $AN = 9.647846E-05$
 $CO_2 \% = 2$
 $O_2 \% = 18$
 $CO \% = 0$

PM10 CUTPOINT RESULTS

Kirby
Dryer #2
3/5/92

REPETITION 1

CUTPOINT, D50 = 9.68672

CYCLONE FLOW, CU FT/MIN = .542449

NOZZLE VELOCITY, FT/SEC = 88.32245

MINIMUM NOZZLE VELOCITY, FT/SEC = 66.88271

MAXIMUM NOZZLE VELOCITY, FT/SEC = 103.2689

MINIMUM DELTA P = 1.118781

MAXIMUM DELTA P = 2.667204

Kirby
Dryer #2
3/5/92
Repetition # 1

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 44.35954$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 8.237251$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1566113$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.06$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.32788$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.0925$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 78.98909$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 44516.67$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1871737$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN * V / PS * T * (TS + 460) * 1.667 = 111.8349$

Kirby
Dryer #2
3/5/92
Repetition # 1

PRESSURE DROP ACROSS ORIFICE, $H = .56$
METER CO-EFFICIENT, $Y = .9786$
METER TEMPERATURE, $TM = 82.42$
BAROMETRIC PRESSURE, $PBAR = 30.03$
GAS METER VOLUME, $VM = 46.352$
LIQUID COLLECTED, $VLC = 175$
PARTICULATE SAMPLE WEIGHT, $MN = 0$
STATIC PRESSURE, $SP = .85$
STACK TEMPERATURE, $TS = 177.8$
PITOT CO-EFFICIENT, $CP = .84$
SQUARE ROOT OF DELTA P, $DP = 1.249$
AREA OF STACK, $AS = 9.392999$
TEST DURATION, $T = 116.5$
AREA OF NOZZLE, $AN = 1.023689E-04$
 $CO_2 \% = 2$
 $O_2 \% = 18.5$
 $CO \% = 0$

PM10 CUTPOINT RESULTS

Kirby

Dryer #2

3/5/92

REPETITION 2

CUTPOINT, D50 = 9.85229

CYCLONE FLOW, CU FT/MIN = .5282498

NOZZLE VELOCITY, FT/SEC = 86.01052

MINIMUM NOZZLE VELOCITY, FT/SEC = 65.04094

MAXIMUM NOZZLE VELOCITY, FT/SEC = 100.5014

MINIMUM DELTA P = 1.056562

MAXIMUM DELTA P = 2.522698

Kirby
Dryer #2
3/5/92
Repetition # 2

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 44.04175$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 8.707949$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1650806$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.08$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.25091$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.09802$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 81.19288$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 45758.68$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1907150$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISO KINETIC RATIO, %
 $((VMSTD / 17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 105.9511$

Kirby
Dryer #2
3/5/92
Repetition # 2

PRESSURE DROP ACROSS ORIFICE, $H = .502$
METER CO-EFFICIENT, $Y = .9786$
METER TEMPERATURE, $TM = 85.95$
BAROMETRIC PRESSURE, $PBAR = 30.03$
GAS METER VOLUME, $VM = 46.326$
LIQUID COLLECTED, $VLC = 185$
PARTICULATE SAMPLE WEIGHT, $MN = 0$
STATIC PRESSURE, $SP = .925$
STACK TEMPERATURE, $TS = 176.96$
PITOT CO-EFFICIENT, $CP = .84$
SQUARE ROOT OF DELTA P, $DP = 1.283$
AREA OF STACK, $AS = 9.392999$
TEST DURATION, $T = 119.8$
AREA OF NOZZLE, $AN = 1.023689E-04$
 $CO_2 \% = 2$
 $O_2 \% = 19$
 $CO \% = 0$

PM10 CUTPOINT RESULTS

Kirby
Dryer #2
3/5/92
REPETITION 3

CUTPOINT, D50 = 10.01362

CYCLONE FLOW, CU FT/MIN = .515786

NOZZLE VELOCITY, FT/SEC = 83.98114

MINIMUM NOZZLE VELOCITY, FT/SEC = 63.40671

MAXIMUM NOZZLE VELOCITY, FT/SEC = 98.05978

MINIMUM DELTA P = 1.013461

MAXIMUM DELTA P = 2.423921

Kirby
Dryer #2
3/5/92
Repetition # 3

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 44.0074$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 7.865398$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1516286$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.08$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.39996$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.09507$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CF * DF * 85.49 = 81.07115$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 45690.08$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1942474$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN * V / PS * T * (TS + 460) * 1.667 = 103.6071$

Kirby
Dryer #2
3/5/92
Repetition # 3

PRESSURE DROP ACROSS ORIFICE, H = .49
METER CO-EFFICIENT, Y = .9786
METER TEMPERATURE, TM = 82.02
BAROMETRIC PRESSURE, PBAR = 30.03
GAS METER VOLUME, VM = 45.958
LIQUID COLLECTED, VLC = 167.1
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = .885
STACK TEMPERATURE, TS = 174.5
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.287
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 120.2
AREA OF NOZZLE, AN = 1.023689E-04
CO2 % = 2
O2 % = 19
CO % = 0

PM10 CUTPOINT RESULTS

Kirby

Dryer #3

3/3/92

REPETITION 1

CUTPOINT, D50 = 10.114

CYCLONE FLOW, CU FT/MIN = .5068974

NOZZLE VELOCITY, FT/SEC = 82.53388

MINIMUM NOZZLE VELOCITY, FT/SEC = 62.25146

MAXIMUM NOZZLE VELOCITY, FT/SEC = 96.32578

MINIMUM DELTA P = .9833251

MAXIMUM DELTA P = 2.354416

Kirby
Dryer #3
3/3/92
Repetition # 1

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 43.61917$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 8.303148$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1599148$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 28.96$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.20733$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.375$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 76.91234$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 43346.26$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1843270$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 107.3829$

Kirby
Dryer #3
3/3/92
Repetition # 1

PRESSURE DROP ACROSS ORIFICE, H = .38
METER CO-EFFICIENT, Y = 1.0679
METER TEMPERATURE, TM = 95.08
BAROMETRIC PRESSURE, PBAR = 30.3
GAS METER VOLUME, VM = 42.38
LIQUID COLLECTED, VLC = 176.4
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = 1.02
STACK TEMPERATURE, TS = 173.8
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.223
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 121.1
AREA OF NOZZLE, AN = 1.023689E-04
CO2 % = 1
O2 % = 20
CO % = 0

PM10 CUTPOINT RESULTS

Kirby

Dryer #3

3/3/92

REPETITION 2

CUTPOINT, D50 = 10.05457

CYCLONE FLOW, CU FT/MIN = .5082957

NOZZLE VELOCITY, FT/SEC = 82.76157

MINIMUM NOZZLE VELOCITY, FT/SEC = 62.46087

MAXIMUM NOZZLE VELOCITY, FT/SEC = 96.61808

MINIMUM DELTA P = .9856882

MAXIMUM DELTA P = 2.358525

Kirby
Dryer #3
3/3/92
Repetition # 2

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 43.62189$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 8.957421$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1703602$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.02$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.14263$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.36397$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CF * DP * 85.49 = 77.20277$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 43509.93$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1830401$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD / 17.64) + (.002669 * VLC)) / AN * V / PS * T * (TS + 460) * 1.667 = 107.2191$

Kirby
Dryer #3
3/3/92
Repetition # 2

PRESSURE DROP ACROSS ORIFICE, H = .389
METER CO-EFFICIENT, Y = 1.0679
METER TEMPERATURE, TM = 100.1
BAROMETRIC PRESSURE, PBAR = 30.3
GAS METER VOLUME, VM = 42.765
LIQUID COLLECTED, VLC = 190.3
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = .87
STACK TEMPERATURE, TS = 172.7
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.227
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 122.19
AREA OF NOZZLE, AN = 1.023689E-04
CO2 % = 1.5
O2 % = 19.5
CO % = 0

PM10 CUTPOINT RESULTS

Kirby

Dryer #3

3/3/92

REPETITION 3

CUTPOINT, D50 = 10.22124

CYCLONE FLOW, CU FT/MIN = .4997795

NOZZLE VELOCITY, FT/SEC = 81.37494

MINIMUM NOZZLE VELOCITY, FT/SEC = 61.33046

MAXIMUM NOZZLE VELOCITY, FT/SEC = 94.94016

MINIMUM DELTA P = .9451219

MAXIMUM DELTA P = 2.264828

Kirby
Dryer #3
3/3/92
Repetition # 3

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 43.59608$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 7.964244$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1544646$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 28.92$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.23325$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.36691$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CF * DP * 85.49 = 78.07548$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 44001.78$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1886559$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD / 17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 104.1003$

Kirby
Dryer #3
3/3/92
Repetition # 3

PRESSURE DROP ACROSS ORIFICE, H = .389
METER CO-EFFICIENT, Y = 1.0679
METER TEMPERATURE, TM = 101.1
BAROMETRIC PRESSURE, PBAR = 30.3
GAS METER VOLUME, VM = 42.816
LIQUID COLLECTED, VLC = 169.2
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = .91
STACK TEMPERATURE, TS = 172.7
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.243
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 122.02
AREA OF NOZZLE, AN = 1.023689E-04
CO2 % = 1
O2 % = 19
CO % = 0

PM10 CUTPOINT RESULTS

Kirby

Dryer #4

3/2/92

REPETITION 1

CUTPOINT, D50 = 10.22197

CYCLONE FLOW, CU FT/MIN = .4935118

NOZZLE VELOCITY, FT/SEC = 85.26043

MINIMUM NOZZLE VELOCITY, FT/SEC = 64.58584

MAXIMUM NOZZLE VELOCITY, FT/SEC = 99.70416

MINIMUM DELTA P = 1.069274

MAXIMUM DELTA P = 2.548244

Kirby
Dryer #4
3/2/92
Repetition # 1

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 44.81165$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 8.773848$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1637355$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.1$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.28253$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.48824$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 82.49994$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 46495.32$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1988489$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 103.4208$

Kirby
Dryer #4
3/2/92
Repetition # 1

PRESSURE DROP ACROSS ORIFICE, H = .45
METER CO-EFFICIENT, Y = .9786
METER TEMPERATURE, TM = 82.46
BAROMETRIC PRESSURE, PBAR = 30.4
GAS METER VOLUME, VM = 46.271
LIQUID COLLECTED, VLC = 186.4
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = 1.2
STACK TEMPERATURE, TS = 169.4
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.3207
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 127
AREA OF NOZZLE, AN = 9.647846E-05
CO2 % = 2
O2 % = 19.5
CO % = 0

PM10 CUTPOINT RESULTS

Kirby

Dryer #4

3/2/92

REPETITION 2

CUTPOINT, D50 = 10.33894

CYCLONE FLOW, CU FT/MIN = .4869117

NOZZLE VELOCITY, FT/SEC = 84.12019

MINIMUM NOZZLE VELOCITY, FT/SEC = 63.66284

MAXIMUM NOZZLE VELOCITY, FT/SEC = 98.32885

MINIMUM DELTA P = 1.038059

MAXIMUM DELTA P = 2.47635

Kirby
Dryer #4
3/2/92
Repetition # 2

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 38.70949$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 6.989895$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1529538$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 28.92$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.24975$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.48456$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 77.67914$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 43778.41$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1897337$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN * V / PS * T * (TS + 460) * 1.667 = 108.3093$

Kirby
Dryer #4
3/2/92
Repetition # 2

PRESSURE DROP ACROSS ORIFICE, H = .45
METER CO-EFFICIENT, Y = .9786
METER TEMPERATURE, TM = 82.92
BAROMETRIC PRESSURE, PBAR = 30.4
GAS METER VOLUME, VM = 40.004
LIQUID COLLECTED, VLC = 148.5
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = 1.15
STACK TEMPERATURE, TS = 169.1
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.243
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 109.8
AREA OF NOZZLE, AN = 9.647846E-05
CO2 % = 1
O2 % = 19
CO % = 0

PM10 CUTPOINT RESULTS

Kirby
Dryer #4
3/2/92

REPETITION 3

CUTPOINT, D50 = 10.09678

CYCLONE FLOW, CU FT/MIN = .4997969

NOZZLE VELOCITY, FT/SEC = 86.34627

MINIMUM NOZZLE VELOCITY, FT/SEC = 65.4778

MAXIMUM NOZZLE VELOCITY, FT/SEC = 101.0231

MINIMUM DELTA P = 1.095332

MAXIMUM DELTA P = 2.607345

Kirby
Dryer #4
3/2/92
Repetition # 3

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 42.53588$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 8.693829$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1697029$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.13327$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.48088$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DF * 85.49 = 84.15836$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 47429.97$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 2018799$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 102.6166$

Kirby
Dryer #4
3/2/92
Repetition # 3

PRESSURE DROP ACROSS ORIFICE, H = .45
METER CO-EFFICIENT, Y = .9786
METER TEMPERATURE, TM = 78.63
BAROMETRIC PRESSURE, PBAR = 30.4
GAS METER VOLUME, VM = 43.611
LIQUID COLLECTED, VLC = 184.7
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = 1.1
STACK TEMPERATURE, TS = 167.9
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.345
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 119.7
AREA OF NOZZLE, AN = 9.647846E-05
CO2 % = 1.5
O2 % = 19
CO % = 0

PM10 CUTPOINT RESULTS

Kirby

Dryer #5

3/2/92

REPETITION 1

CUTPOINT, D50 = 10.76425

CYCLONE FLOW, CU FT/MIN = .455494

NOZZLE VELOCITY, FT/SEC = 82.74771

MINIMUM NOZZLE VELOCITY, FT/SEC = 62.68462

MAXIMUM NOZZLE VELOCITY, FT/SEC = 96.76732

MINIMUM DELTA P = 1.013685

MAXIMUM DELTA P = 2.415675

Kirby
Dryer #5
3/2/92
Repetition # 1

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 39.2998$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 7.281729$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1563222$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29.02$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.29733$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.37427$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 80.45027$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 45340.17$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1968607$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN / V / PS / T * (TS + 460) * 1.667 = 102.5669$

Kirby
Dryer #5
3/2/92
Repetition # 1

PRESSURE DROP ACROSS ORIFICE, H = .31
METER CO-EFFICIENT, Y = 1.06788
METER TEMPERATURE, TM = 82.5
BAROMETRIC PRESSURE, PBAR = 30.3
GAS METER VOLUME, VM = 37.325
LIQUID COLLECTED, VLC = 154.7
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = 1.01
STACK TEMPERATURE, TS = 163.4
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.292
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 119.34
AREA OF NOZZLE, AN = 9.175021E-05
CO2 % = 1.5
O2 % = 19.5
CO % = 0

PM10 CUTPOINT RESULTS

Kirby

Dryer #5

3/2/92

REPETITION 2

CUTPOINT, D50 = 11.00383

CYCLONE FLOW, CU FT/MIN = .4428131

NOZZLE VELOCITY, FT/SEC = 80.44401

MINIMUM NOZZLE VELOCITY, FT/SEC = 60.83077

MAXIMUM NOZZLE VELOCITY, FT/SEC = 93.99649

MINIMUM DELTA P = .9515411

MAXIMUM DELTA P = 2.271979

Kirby
Dryer #5
3/2/92
Repetition # 2

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 38.96345$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 6.975774$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .1518479$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205^{-06} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 28.92$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.26182$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.36912$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 80.39337$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 45308.1$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1974164$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / (AN/V/PS/T * (TS + 460) * 1.667) = 100.0947$

Kirby
Dryer #5
3/2/92
Repetition # 2

PRESSURE DROP ACROSS ORIFICE, H = .31
METER CO-EFFICIENT, Y = 1.06788
METER TEMPERATURE, TM = 87.96
BAROMETRIC PRESSURE, FBAR = 30.3
GAS METER VOLUME, VM = 37.378
LIQUID COLLECTED, VLC = 148.2
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = .94
STACK TEMPERATURE, TS = 164.5
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.289
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 120.92
AREA OF NOZZLE, AN = 9.175021E-05
CO2 % = 1
O2 % = 19
CO % = 0

PM10 CUTPOINT RESULTS

Kirby

Dryer #5

3/2/92

REPETITION 3

CUTPOINT, D50 = 10.87924

CYCLONE FLOW, CU FT/MIN = .4481804

NOZZLE VELOCITY, FT/SEC = 81.41908

MINIMUM NOZZLE VELOCITY, FT/SEC = 61.61746

MAXIMUM NOZZLE VELOCITY, FT/SEC = 95.17068

MINIMUM DELTA P = .9852299

MAXIMUM DELTA P = 2.350371

Kirby
Dryer #5
3/2/92
Repetition # 3

SAMPLE VOLUME, STANDARD CUBIC FEET
 $((H/13.6) / TM) * Y * VM * 17.64 = 39.52826$

VOLUME OF WATER VAPOR, STANDARD CUBIC FEET
 $VLC * 0.04707 = 6.740424$

FRACTIONAL MOISTURE CONTENT
 $VWSTD / (VMSTD + VWSTD) = .14568$

PARTICULATE CONCENTRATION, GR/SCF DB
 $(MN/VMSTD) * 0.01543 = 0$

PARTICULATE CONCENTRATION, LBS/SCF DB
 $(MN/VMSTD) * 2.205 \times 10^{-6} = 0$

MOLECULAR WEIGHT OF STACK GAS, DRY BASIS
 $(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = 29$

MOLECULAR WEIGHT OF STACK GAS, WET BASIS
 $(MD * (1 - BWS)) + (18 * BWS) = 27.39752$

STACK PRESSURE, INCHES OF MERCURY
 $(SP / 13.6) + PBAR = 30.3625$

STACK GAS VELOCITY, FPS
 $(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = 79.78086$

STACK GAS VOLUME, ACFM
 $V * AS * 60 = 44962.89$

STACK GAS VOLUME, SCFH
 $((528 * PBAR) / (TS + 460) / 29.92) * AS * V * (1 - BWS) * 3600 = 1981939$

PARTICULATE EMISSIONS, LBS/HR
 $CS * QS = 0$

ISOKINETIC RATIO, %
 $((VMSTD/17.64) + (.002669 * VLC)) / AN * V / PS * T * (TS + 460) * 1.667 = 102.0725$

Kirby
Dryer #5
3/2/92
Repetition # 3

PRESSURE DROP ACROSS ORIFICE, H = .31
METER CO-EFFICIENT, Y = 1.0679
METER TEMPERATURE, TM = 81.73001
BAROMETRIC PRESSURE, PBAR = 30.3
GAS METER VOLUME, VM = 37.488
LIQUID COLLECTED, VLC = 143.2
PARTICULATE SAMPLE WEIGHT, MN = 0
STATIC PRESSURE, SP = .85
STACK TEMPERATURE, TS = 161.8
PITOT CO-EFFICIENT, CP = .84
SQUARE ROOT OF DELTA P, DP = 1.285
AREA OF STACK, AS = 9.392999
TEST DURATION, T = 119.85
AREA OF NOZZLE, AN = 9.175021E-05
CO2 % = 1.5
O2 % = 19
CO % = 0

```

5 REM-Method 5 Data Reduction
10 DIM A(100):DIM B(100):DIM C(100):DIM D(100):DIM E(100)
12 DIM F(100):DIM G(100):DIM H(100):DIM I(100):DIM J(100)
14 DIM K(100):DIM L(100):DIM M(100):DIM N(100):DIM O(100)
16 DIM P(100):DIM Q(100):DIM R(100):DIM S(100):DIM T(100)
18 DIM U(100):DIM V(100):DIM W(100):DIM X(100):DIM Y(100)
20 DIM Z(100):DIM AA(100):DIM BB(100):DIM CC(100):DIM DD(100)
22 DIM EE(100):DIM FF(100):DIM GG(100):DIM HH(100):DIM II(100)
24 DIM JJ(100):DIM KK(100):DIM LL(100):DIM MM(100):DIM NN(100)
26 DIM OO(100):DIM PP(100):DIM QQ(100):DIM RR(100):DIM SS(100)
27 DIM NT(100):DIM AB(100)
30 PRINT"Method 5 Calculation Summary"
35 PRINT
40 PRINT"Select one of the following"
45 PRINT"      1. Average Data Sheets"
50 PRINT"      2. Calculate Data Sheets"
55 INPUT TT
60 IF TT = 2 THEN GOTO 500
65 PRINT
70 PRINT"Choose colume to be averaged"
75 PRINT"      1. Stack Temperature"
80 PRINT"      2. Delta H"
85 PRINT"      3. Meter Temperature"
90 PRINT"      4. Delta P"
95 PRINT
100 INPUT UU
110 IF UU > 4 THEN GOTO 70
112 PRINT
113 PRINT"Input Run #":INPUT WW
115 PRINT"Input number of points":INPUT VV
120 PRINT"Input Data"
125 PRINT
130 FOR LL = 1 TO VV
135 INPUT MM(LL)
140 NEXT LL
145 IF UU = 4 THEN GOTO 200
150 FOR LL = 1 TO VV
155 NN(LL) = MM(LL) + NN(LL - 1)
160 NEXT LL
162 PP = NN(VV)/VV
165 IF UU < 4 THEN GOTO 220
200 FOR LL = 1 TO VV
205 OO(LL) = SQR(MM(LL))
210 NN(LL) = OO(LL) + NN(LL - 1)
215 NEXT LL
217 PP = NN(VV)/VV
220 IF UU = 1 THEN I(WW) = PP
225 IF UU = 2 THEN A(WW) = PP
230 IF UU = 3 THEN C(WW) = PP
235 IF UU = 4 THEN K(WW) = PP
240 IF UU = 1 THEN PRINT"Stack Temperature = "I(WW)
245 IF UU = 2 THEN PRINT"Delta H = "A(WW)
250 IF UU = 3 THEN PRINT"Meter Temperature ="C(WW)
255 IF UU = 4 THEN PRINT"Square Root of Delta P = "K(WW)
260 GOTO 35
500 PRINT "Input Run #":INPUT WW
505 PRINT
510 PRINT "Did you average the data sheets on this machine? 1=yes 2=no":INPUT L
L
515 PRINT

```

```

517 PRINT "Input the following"
520 IF LL = 1 THEN GOTO 550
525 PRINT "Delta H":INPUT A(WW)
530 PRINT "Meter Temperature, F":INPUT C(WW)
535 PRINT "Stack Temperature, F":INPUT I(WW)
540 PRINT "Square Root of Delta P":INPUT K(WW)
550 PRINT "Is barometric pressure the same as last run? 1=yes 2=no":INPUT UU
552 IF UU = 1 THEN GOTO 555
553 PRINT "Barometric Pressure, in. H2O":INPUT D
555 PRINT "Are these parameters the same as last run? 1=yes 2=no"
559 PRINT "    1. Test Duration"
561 PRINT "    2. Nozzle Size"
563 PRINT "    3. Meter Co-efficient, Y"
565 PRINT "    4. Pitot Co-efficient, Cp"
567 PRINT "    5. Stack Area, As"
568 INPUT LL
569 IF LL = 1 THEN GOTO 590
572 PRINT "Test Duration, minutes":INPUT M
574 PRINT "Nozzle Diameter, inches":INPUT XX
576 PRINT "Meter Co-efficient, Y":INPUT B
578 PRINT "Pitot Co-efficient, Cp":INPUT J
580 PRINT "Stack Area, Sq. Ft.":INPUT L
590 PRINT "Gas Meter Volume, Cu Ft.":INPUT E(WW)
595 PRINT "Liquid Collected, mls":INPUT F(WW)
600 PRINT "Particulate Sample Weight, mg":INPUT G(WW)
605 PRINT "Static Pressure, in. H2O":INPUT H(WW)
610 PRINT "Percent CO2":INPUT Q(WW)
615 PRINT "Percent O2":INPUT P(WW)
620 PRINT "Percent CO":INPUT Q(WW)
625 R(WW) = (((A(WW)/13.6)+D)/(C(WW)+460)) * B * E(WW) * 17.64
630 S(WW) = F(WW) * .04707
635 T(WW) = S(WW)/(R(WW) + S(WW))
640 U(WW) = (G(WW)/R(WW)) * .01543
645 V(WW) = (G(WW)/R(WW)) * 2.205E-06
650 NT(WW) = 100 - ((Q(WW) + P(WW) + Q(WW)))
655 W(WW) = ((Q(WW) * .44) + (P(WW) * .232) + ((NT(WW)+Q(WW)) * .28)
660 X(WW) = (W(WW) * (1-T(WW))) + (T(WW) * 18)
665 Y(WW) = (H(WW)/13.6) + D
670 Z(WW) = (SQRT(((I(WW)+460)/X(WW))/Y(WW))) * J * K(WW) * 85.49
675 AA(WW) = Z(WW) * L * 60
680 BB(WW) = (((528 * D)/(I(WW) + 460))/29.92) * L * Z(WW) * 3600 * (1-T(WW))
685 CC(WW) = BB(WW) * V(WW)
690 AN = (((XX/2)*(XX/2))*3.14159)/144
695 DD(WW) = ((R(WW)/17.64) + (.002669 * F(WW)))/AN/Z(WW)/M/Y(WW)*(I(WW)+460)*1.
667
700 PRINT
705 PRINT "VMSTD = "R(WW)
710 PRINT
715 PRINT "VWSTD = "S(WW)
720 PRINT
725 PRINT "BWS = "T(WW)
730 PRINT
735 PRINT "GR/SCF DB = "U(WW)
740 PRINT
745 PRINT "LBS/SCF DB = "V(WW)
750 PRINT
755 PRINT "MOLECULAR WEIGHT, DRY = "W(WW)
760 PRINT
765 PRINT "MOLECULAR WEIGHT, WET = "X(WW)
770 PRINT
775 PRINT "STACK PRESSURE = "Y(WW)
780 PRINT
785 PRINT "VELOCITY = "Z(WW)
790 PRINT
795 PRINT "VOLUME, ACFM = "AA(WW)
800 PRINT

```

```

805 PRINT "HIT ANY KEY TO CONTINUE":INPUT AX
810 PRINT
815 PRINT"VOLUME, SCFH = "BB(WW)
820 PRINT
825 PRINT"EMISSIONS, LBS/HR = "CC(WW)
830 PRINT
835 PRINT"ISOKINETIC RATIO = "DD(WW)
840 PRINT
845 PRINT"DO YOU WISH TO CALCULATE ANY OF THE FOLLOWING? 1=YES 2=NO"
850 PRINT
855 PRINT"EXCESS AIR":INPUT AB
860 PRINT"GRAINS/SCF @ 12% CO2":INPUT AC
865 PRINT"LBS/10^6 BTU":INPUT AD
870 PRINT"LBS/PROCESS WEIGHT":INPUT AE
875 PRINT"LBS/1000 LBS GAS @ 50% EXCESS AIR":INPUT AF
880 IF AB = 2 THEN GOTO 900
885 AB(WW) = 100 * (P(WW)-Q(WW))/(((.264 * NT(WW))-(P(WW)-Q(WW)))
890 PRINT"EXCESS AIR = "AB(WW)
900 IF AC = 2 THEN GOTO 920
905 AC(WW) = 12/D(WW) * U(WW)
910 PRINT"GR/SCF @ 12% CO2 = "AC(WW)
920 IF AD = 2 THEN GOTO 940
940 IF AE = 2 THEN GOTO 960
960 IF AF = 2 THEN GOTO 980
980 PRINT"HARD COPY? 1=YES 2=NO":INPUT AG
985 IF AG = 2 THEN GOTO 35
990 PRINT"INPUT THE FOLLOWING"
995 PRINT"COMPANY NAME":INPUT A$
1000 PRINT"SOURCE TESTED":INPUT B$
1005 PRINT"TEST DATE":INPUT C$
1010 LPRINT A$
1015 LPRINT B$
1016 LPRINT C$
1020 LPRINT"Repetition #"WW
1025 LPRINT
1030 LPRINT
1035 LPRINT"SAMPLE VOLUME, STANDARD CUBIC FEET"
1040 LPRINT"(((H/13.6) / TM) * Y * VM * 17.64 = "R(WW)
1045 LPRINT
1050 LPRINT"VOLUME OF WATER VAPOR, STANDARD CUBIC FEET"
1055 LPRINT"VLC * 0.04707 = "S(WW)
1060 LPRINT
1065 LPRINT"FRACTIONAL MOISTURE CONTENT"
1067 LPRINT"VMSTD / (VMSTD + VWSTD) = "T(WW)
1070 LPRINT
1075 LPRINT"PARTICULATE CONCENTRATION, GR/SCF DB"
1080 LPRINT"(MN/VMSTD) * 0.01543 = "U(WW)
1085 LPRINT
1090 LPRINT"PARTICULATE CONCENTRATION, LBS/SCF DB"
1095 LPRINT"(MN/VMSTD) * 2.205^-06 = "V(WW)
1100 LPRINT
1105 LPRINT"MOLECULAR WEIGHT OF STACK GAS, DRY BASIS"
1110 LPRINT"(CO2 * .44) + (O2 * .32) + ((N2 + CO) * .28) = "W(WW)
1115 LPRINT
1120 LPRINT"MOLECULAR WEIGHT OF STACK GAS, WET BASIS"
1125 LPRINT"(MD * (1 - BWS)) + (18 * BWS) = "X(WW)
1130 LPRINT
1135 LPRINT"STACK PRESSURE, INCHES OF MERCURY"
1140 LPRINT"(SP / 13.6) + PBAR = "Y(WW)
1145 LPRINT
1150 LPRINT"STACK GAS VELOCITY, FPS"
1155 LPRINT"(SQR(((TS + 460) / MS) / PS)) * CP * DP * 85.49 = "Z(WW)
1160 LPRINT
1165 LPRINT"STACK GAS VOLUME, ACFM"
1170 LPRINT"V * AS * 60 = "AA(WW)
1175 LPRINT

```

```

1180 LPRINT"STACK GAS VOLUME, SCFH"
1185 LPRINT"(((528*PBAR)/(TS+460)/29.92)) *AS*V*(1-BWS) * 3600 = "BB(WW)
1190 LPRINT
1195 LPRINT"PARTICULATE EMISSIONS, LBS/HR"
1200 LPRINT"CS * QS = "CC(WW)
1205 LPRINT
1210 LPRINT"ISOKINETIC RATIO, %"
1215 LPRINT"((VMSTD/17.64)+(.002669*VLC))/AN/V/PS/T*(TS+460)*1.667 = "DD(WW)
1217 LPRINT
1220 IF AB =2 THEN GOTO 1230
1222 LPRINT
1225 LPRINT"EXCESS AIR = "AB(WW)
1230 IF AC = 2 THEN GOTO 1240
1234 LPRINT"GRAINS/SCF @ 12% CO2 = "AC(WW)
1236 LPRINT
1240 IF AD = 2 THEN GOTO 1250
1250 IF AE = 2 THEN GOTO 1260
1260 IF AF = 2 THEN GOTO 1270
1270 LPRINT CHR$(12)
1275 LPRINT A$
1280 LPRINT B$
1285 LPRINT C$
1290 LPRINT"Repetition #"WW
1295 LPRINT
1300 LPRINT
1305 LPRINT"PRESSURE DROP ACROSS ORIFICE, H = "A(WW)
1310 LPRINT"METER CO-EFFICIENT, Y = "B
1315 LPRINT"METER TEMPERATURE, TM = "C(WW)
1320 LPRINT"BARMETRIC PRESSURE, PBAR = "D
1325 LPRINT"GAS METER VOLUME, VM = "E(WW)
1330 LPRINT"LIQUID COLLECTED, VLC = "F(WW)
1335 LPRINT"PARTICULATE SAMPLE WEIGHT, MN = "G(WW)
1340 LPRINT"STATIC PRESSURE, SP = "H(WW)
1345 LPRINT"STACK TEMPERATURE, TS = "I(WW)
1350 LPRINT"PITOT CO-EFFICIENT, CP = "J
1355 LPRINT"SQUARE ROOT OF DELTA P, DP = "K(WW)
1360 LPRINT"AREA OF STACK, AS = "L
1365 LPRINT"TEST DURATION, T = "M
1370 LPRINT"AREA OF NOZZLE, AN = "AN
1375 LPRINT"CO2 % = "O(WW)
1380 LPRINT"O2 % = "P(WW)
1385 LPRINT "CO % = "Q(WW)
1390 LPRINT CHR$(12)
1400 GOTO 30

```



```

1 DIM AG(24): DIM AH(24)
10 REM PM10 Field Calculations
15 PRINT"PM 10 Feild Calculations"
20 PRINT
25 PRINT"Input the following"
30 PRINT
35 PRINT"Barometric Pressure, in hg. = ":INPUT A
40 PRINT
45 PRINT"STATIC PRESSURE, IN H2O = ":INPUT B
50 PRINT
55 PRINT"STACK TEMPERATURE, F = ":INPUT C
60 PRINT
65 PRINT"METER TEMPERATURE, F = ":INPUT D
70 PRINT
75 PRINT"ORIFACE DELTA H@ = ":INPUT E
80 PRINT
85 PRINT"CO2, % = ":INPUT F
90 PRINT
95 PRINT"O2, % = ":INPUT G
100 PRINT
105 PRINT"MOISTURE, % = ":INPUT H
110 PRINT
115 PRINT"AVERAGE DELTA P = ":INPUT I
117 J = H/100
118 REM VISCOSITY OF STACK GAS
120 K = ((152.418 + (.2552 * C)) + (3.2355E-05 * (C*C)) + (.53147 * G)) - (74.14
3 * J)
122 REM MOLECULAR WEIGHT, DRY
125 L = (F*.44) + (G*.32) + ((100 - (F+G)) * .28)
127 REM MOLECULAR WEIGHT, WET
130 M = (L * (1 - J)) + (18 * J)
135 REM STACK PRESSURE
140 N = A + (B/13.6)
145 REM CYCLONE FLOW RATE
150 O = (((C + 460) / M) / N) ^ .2949 * .002837 * K
152 PRINT"CYCLONE FLOW RATE = "O
155 REM NOZZLE SIZE
160 REM GAS METER FLOW RATE
165 P = O * (((D+460)/(C+460))*(1-J))
170 PRINT
175 PRINT"GAS METER FLOW RATE = "P
180 REM STACK GAS VELOCITY
185 Q = (SQR(((C+460)*I)/(M*N))) * 85.49 *.84
190 PRINT
195 PRINT"VELOCITY = "Q
200 REM NOZZLE SIZE
205 S = (P * (C + 460)) / (D + 460) / 60 / Q
210 T = (SQR((S * 144) / 3.14157)) * 2
215 PRINT
220 PRINT"NOZZLE SIZE = "T
225 REM DELTA H
230 U = (P*P) * A * E * .05952
235 PRINT
240 PRINT"DELTA H = "U
245 PRINT
250 PRINT"HARD COPY? 1 = YES, 2 = NO": INPUT V
260 IF V = 2 THEN GOTO 500
265 PRINT"INPUT THE FOLLOWING"
270 PRINT
275 PRINT"COMPANY":INPUT A$
280 PRINT
285 PRINT"SOURCE":INPUT B$

```

```

290 PRINT
295 PRINT"REPETITION": INPUT C$
300 PRINT
305 PRINT"TEST DATE":INPUT D$
310 LPRINT "PM10 CALCULATION SUMMARY"
315 LPRINT
320 LPRINT A$
325 LPRINT B$
330 LPRINT "REPETITION# "C$
335 LPRINT D$
340 LPRINT
345 LPRINT"CYCLONE FLOW = "O" CFM"
350 LPRINT
355 LPRINT"GAS METER FLOW = "P" CFM"
360 LPRINT
365 LPRINT"STACK GAS VELOCITY = "Q" FPS"
370 LPRINT
375 LPRINT"NOZZLE SIZE = "T" INCHES"
380 LPRINT
385 LPRINT"AVERAGE DELTA H = "V" INCHES H2O"
390 LPRINT
395 LPRINT"BAROMETRIC PRESSURE = "A" IN HG"
400 LPRINT
405 LPRINT"STATIC PRESSURE = "B" IN H2O"
410 LPRINT
415 LPRINT"STACK TEMPERATURE, F = "C
420 LPRINT
425 LPRINT"METER TEMPERATURE, F = "D
430 LPRINT
435 LPRINT"ORIFACE DELTA H@ = "E
440 LPRINT
445 LPRINT"CO2, % = "F
450 LPRINT
455 LPRINT"O2, % = "G
460 LPRINT
465 LPRINT"MOISTURE, % = "H
470 LPRINT
475 LPRINT"AVERAGE DELTA P = " I
480 LPRINT CHR$(12)
485 GOTO 10
500 PRINT"CALCULATE DWELL TIME? 1 = YES , 2 = NO":INPUT X
510 IF X = 2 THEN GOTO 800
515 PRINT
520 PRINT"INPUT THE FOLLOWING"
525 PRINT
530 PRINT"TOTAL RUN TIME": INPUT AA
535 PRINT
540 PRINT"TOTAL POINTS":INPUT AB
545 PRINT
550 FOR AF = 1 TO AB
554 PRINT
555 PRINT"DELTA P FOR POINT #"AF" = ":INPUT AG(AF)
556 PRINT
560 NEXT AF
562 AH(1) = ((AG(1) / I) ^ .5) * (AA/AB)
565 FOR Z = 2 TO AB
570 AH(Z) = (AH(1) / (AG(1) ^ .5)) * (AG(Z) ^ .5)
572 NEXT Z
575 FOR Z = 1 TO AB
580 PRINT"DURATION, POINT# "Z" = "AH(Z)
590 NEXT Z
600 PRINT
605 PRINT"HARD COPY? 1 = YES, 2 = NO":INPUT Y
610 IF Y = 2 THEN GOTO 10
615 PRINT"INPUT THE FOLLOWING"
620 PRINT

```

```

625 PRINT"PLANT":INPUT A$
630 PRINT"LOCATION":INPUT B$
635 PRINT"TEST DATE":INPUT C$
640 PRINT"REPETITION":INPUT D$
650 LPRINT "POINT TO POINT TIME DURATIONS"
655 LPRINT
660 LPRINT A$
665 LPRINT B$
670 LPRINT C$
675 LPRINT "REPETITION# "D$
680 LPRINT
685 FOR Z = 1 TO AB
690 LPRINT"POINT # "Z" DURATION "AH(Z)" MINUTES
700 NEXT Z
705 LPRINT CHR$(12)
800 REM CUTPOINT
805 PRINT
810 PRINT"INPUT THE FOLLOWING"
815 PRINT
820 PRINT"VOLUME OF WATER VAPOR":INPUT H
825 PRINT
830 PRINT"METER VOLUME":INPUT BF
835 PRINT
840 PRINT"METER Y":INPUT BG
845 PRINT
850 PRINT"DELTA H":INPUT BH
855 PRINT
860 PRINT"SAMPLE TIME":INPUT BZ
865 PRINT
870 REM CYCLONE FLOW
875 BJ = ((BH/13.6)+A)/(D+460))*BF*BG*17.64
880 BL = ((C+460)/(17.64*N))*((BJ+H)/BZ)
890 REM CUTPOINT
895 BM = .15625 * (((C+460)/(M*N))^.2091)*((K/BL)^(.7091))
900 PRINT
905 PRINT"CUTPOINT = "BM
910 REM NOZZLE VELOCITY
915 PRINT"INPUT NOZZLE DIAMETER":INPUT BN
920 BQ = (3.056 * BL)/(BN*BN)
925 REM MINIMUM NOZZLE VELOCITY
930 BP = BQ*(.2457+((.3072-((.2603*(BL^.5)*K)/(BQ^1.5)))^1.5))
935 REM MAXIMUM NOZZLE VELOCITY
940 BQ = BQ*(.4457+((.569-((.2603*(BL^.5)*K)/(BQ^1.5)))^1.5))
945 REM MINIMUM DELTA P
950 BR = 1.3686E-04 * (N*M*(BP*BP))/((C+460)*(.84*.84))
955 REM MAXIMUM DELTA P
960 PS = 1.3686E-04 * (N*M*(BQ*BQ))/((C+460)*(.84*.84))
965 PRINT
970 PRINT"NOZZLE VELOCITY = "BQ
975 PRINT
980 PRINT"MINIMUM NOZZLE VELOCITY = "BP
985 PRINT
990 PRINT"MAXIMUM NOZZLE VELOCITY = "BQ
995 PRINT
1000 PRINT"MINIMUM DELTA P = "BR
1005 PRINT
1010 PRINT"MAXIMUM DELTA P = "PS
1015 PRINT
1020 PRINT"HARD COPY? 1 = YES 2 = NO":INPUT XX
1025 IF XX = 2 THEN GOTO 800
1030 PRINT
1035 PRINT"COMPANY NAME":INPUT A$
1040 PRINT
1045 PRINT"SOURCE":INPUT B$
1050 PRINT
1055 PRINT"DATE":INPUT C$

```

```
1060 PRINT
1065 PRINT"REPETITION":INPUT D$
1068 LPRINT"PM10 CUTPOINT RESULTS"
1069 LPRINT
1070 LPRINT A$
1075 LPRINT B$
1080 LPRINT C$
1085 LPRINT"REPETITION "D$
1090 LPRINT
1100 LPRINT"CUTPOINT, D50 = "BM
1105 LPRINT
1110 LPRINT"CYCLONE FLOW, CU FT/MIN = "BL
1115 LPRINT
1120 LPRINT"NOZZLE VELOCITY, FT/SEC = "BO
1125 LPRINT
1130 LPRINT"MINIMUM NOZZLE VELOCITY, FT/SEC = "BP
1135 LPRINT
1140 LPRINT"MAXIMUM NOZZLE VELOCITY, FT/SEC = "BQ
1145 LPRINT
1150 LPRINT"MINIMUM DELTA P = "BR
1155 LPRINT
1160 LPRINT"MAXIMUM DELTA P = "PS
1165 LPRINT CHR$(12)
1170 GOTO 10
```

APPENDIX B

BLANK ANALYTICAL DATA FORM

PLANT: Kirby Forest Products

SAMPLE LOCATION: Dryers 1 thru 5

LIQUID LEVEL MARKED? ✓

BLANK VOLUME (Va): 100

DATE OF WEIGHING 3/9/92 8:17 AM GROSS WEIGHT 98.1220 g

DATE OF WEIGHING 3/9/92 3:11 PM GROSS WEIGHT 98.1219 g

AVERAGE GROSS WEIGHT 98.12195 g

TARE WEIGHT 98.1218 g

WEIGHT OF BLANK (Ma) 0.00015 g

$$Ca = \frac{Ma}{Va Pa} = \frac{0.00015}{100 \times 1} = 0.0015 \text{ mg/g}$$

Note: In no case should a blank residue greater than 0.01 mg/g or 0.001% of the blank weight be subtracted from the sample weight.

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, PW + Filter

Location: Dryer # 1 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 155

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:13 AM Gross Wt. 102.2730 g

Date of Weighing 3/9/92 3:09 PM Gross Wt. 102.2723 g

Average Gross Wt. 102.27265 g

Less Blank Residue (Wa) 0

Tare Wt. 102.2543 g

Weight of Particulate in Acetone Rinse 0.01835 g → 18.35 mg

8:36 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.61549 g

2:45 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.61541 g

Average Gross Wt. 0.61545 g

Filter Tare Wt. 0.44640 g

Weight of Particulate on Filter 0.16905 g → 169.05 mg

Weight of Particulate 187.40 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, PW + Filter

Location: Dryer # 1 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 175

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:13 AM Gross Wt. 98.7636g

Date of Weighing 3/9/92 3:10 PM Gross Wt. 98.7633g

Average Gross Wt. 98.76345g

Less Blank Residue (Wa) 0

Tare Wt. 98.7461g

Weight of Particulate in Acetone Rinse 0.01735g → 17.35mg

8:37 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.63757g

2:49 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.63750g

Average Gross Wt. 0.637535g

Filter Tare Wt. 0.45729g

Weight of Particulate on Filter 0.180245g → 180.245mg

Weight of Particulate 197.595

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, PW + Filter

Location: Dryer #1 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 180

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:14AM Gross Wt. 107.4253 g

Date of Weighing 3/9/92 3:10PM Gross Wt. 107.4251 g

Average Gross Wt. 107.4552 g

Less Blank Residue (Wa) 0

Tare Wt. 107.4083 g

Weight of Particulate in Acetone Rinse 0.0469 g → 46.9 mg

8:39AM Date of Weighing 3/10/92 Gross Filter Wt. 0.60112 g

2:50PM Date of Weighing 3/10/92 Gross Filter Wt. 0.60108 g

Average Gross Wt. 0.60110 g

Filter Tare Wt. 0.45452 g

Weight of Particulate on Filter 0.14658 g → 146.58 mg

Weight of Particulate 193.48 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, PW & Filter

Location: Dryer #2 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 175

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:10 AM Gross Wt. 101.5369 g

Date of Weighing 3/9/92 3:07 PM Gross Wt. 101.5364 g

Average Gross Wt. 101.53665 g

Less Blank Residue (Wa) 0

Tare Wt. 101.5187 g

Weight of Particulate in Acetone Rinse 0.01795 g → 17.95 mg

7:16 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.63312 g

3:11 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.63315 g

Average Gross Wt. 0.633135 g

Filter Tare Wt. 0.46665 g

Weight of Particulate on Filter 0.166485 g → 166.485 mg

Weight of Particulate 184.435 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, PW + Filter

Location: Dryer #2 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 135

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:11 AM Gross Wt. 102.4592 g

Date of Weighing 3/9/92 3:07 PM Gross Wt. 102.4580 g

Average Gross Wt. 102.4586 g

Less Blank Residue (Wa) 0

Tare Wt. 102.4476 g

Weight of Particulate in Acetone Rinse 0.0110 g → 11.0 mg

8:16 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.59628 g

3:12 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.59632 g

Average Gross Wt. 0.59635 g

Filter Tare Wt. 0.45531 g

Weight of Particulate on Filter 0.14104 g → 141.04 mg

Weight of Particulate 152.04 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, PW + Filter

Location: Dryer #2 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 165

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:11 AM Gross Wt. 97.3210 g

Date of Weighing 3/9/92 3:08 PM Gross Wt. 97.3206 g

Average Gross Wt. 97.3208 g

Less Blank Residue (Wa) 0

Tare Wt. 97.3083 g

Weight of Particulate in Acetone Rinse 0.0125 g → 12.5 mg

8:18 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.57448 g

3:14 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.57440 g

Average Gross Wt. 0.57444 g

Filter Tare Wt. 0.46389 g

Weight of Particulate on Filter 0.11055 g → 110.55 mg

Weight of Particulate 123.05 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, PW & Filter

Location: Dryer #3 Acetone Density (Pa): 0.7852

Date: 3/3/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 170

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:09 AM Gross Wt. 100.1691 g

Date of Weighing 3/9/92 3:05 PM Gross Wt. 100.1682 g

Average Gross Wt. 100.16865 g

Less Blank Residue (Wa) 0

Tare Wt. 100.1446 g

Weight of Particulate in Acetone Rinse 0.02405 g → 24.05 mg

8:19 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.58981 g

3:18 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.58977 g

Average Gross Wt. 0.58979 g

Filter Tare Wt. 0.44840 g

Weight of Particulate on Filter 0.14139 g → 141.39 mg

Weight of Particulate 165.44 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, PW + Filter

Location: Dryer #3 Acetone Density (Pa): 0.7852

Date: 3/3/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 150

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:09 AM Gross Wt. 99.8886 g

Date of Weighing 3/9/92 3:05 PM Gross Wt. 99.8878 g

Average Gross Wt. 99.8882 g

Less Blank Residue (Wa) 0

Tare Wt. 99.8709 g

Weight of Particulate in Acetone Rinse 0.0173 g → 17.3 mg

8:25 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.57661 g

3:19 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.57664 g

Average Gross Wt. 0.576625 g

Filter Tare Wt. 0.44373 g

Weight of Particulate on Filter 0.132895 g → 132.895 mg

Weight of Particulate 150.195 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, PW & Filter

Location: Dryer # 3 Acetone Density (Pa): 0.7852

Date: 3/3/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 210

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:10 AM Gross Wt. 104.6017 g

Date of Weighing 3/9/92 3:06 PM Gross Wt. 104.6011 g

Average Gross Wt. 104.6014 g

Less Blank Residue (Wa) 0

Tare Wt. 104.5697 g

Weight of Particulate in Acetone Rinse 0.0317 g → 31.7 mg

8:26 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.57568 g

3:21 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.57566 g

Average Gross Wt. 0.57567 g

Filter Tare Wt. 0.45638 g

Weight of Particulate on Filter 0.11929 g → 119.29 mg

Weight of Particulate 150.99 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, PW + Filter

Location: Dryer #4 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 175

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:06 AM Gross Wt. 99.0268 g

Date of Weighing 3/9/92 3:02 PM Gross Wt. 99.0252 g

Average Gross Wt. 99.0260 g

Less Blank Residue (Wa) 0

Tare Wt. 98.9953 g

Weight of Particulate in Acetone Rinse 0.0307 g → 30.7 mg

8:27 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.59546 g

3:22 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.59546 g

Average Gross Wt. 0.59546 g

Filter Tare Wt. 0.45856 g

Weight of Particulate on Filter 0.13690 g → 136.9 mg

Weight of Particulate 167.6 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, PW + Filter

Location: Dryer #4 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 210

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:08 AM Gross Wt. 103.7240 g

Date of Weighing 3/9/92 3:03 PM Gross Wt. 103.7226 g

Average Gross Wt. 103.7233 g

Less Blank Residue (Wa) 0

Tare Wt. 103.6824 g

Weight of Particulate in Acetone Rinse 0.0409 g 40.9 mg

8:35 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.58120 g

3:24 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.58111 g

Average Gross Wt. 0.581155 g

Filter Tare Wt. 0.45338 g

Weight of Particulate on Filter 0.127775 g 127.775 mg

Weight of Particulate 168.675 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, PW & Filter

Location: Dryer # 4 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 170

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:08 AM Gross Wt. 92.6116g

Date of Weighing 3/9/92 3:03 PM Gross Wt. 92.6115g

Average Gross Wt. 92.61155g

Less Blank Residue (Wa) 0

Tare Wt. 92.5746g

Weight of Particulate in Acetone Rinse 0.03695g = 36.95mg

3:36 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.58284g

3:25 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.58280g

Average Gross Wt. 0.58282g

Filter Tare Wt. 0.44803g

Weight of Particulate on Filter 0.13479g = 134.79mg

Weight of Particulate 171.74mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, PW + Filter

Location: Dryer #5 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 255

Residue in Rinse (Wa) = $Ca * Vaw * Pa$ 0

Date of Weighing 3/9/92 8:05 AM Gross Wt. 103.2529 g

Date of Weighing 3/9/92 3:00 PM Gross Wt. 103.2524 g

Average Gross Wt. 103.25265 g

Less Blank Residue (Wa) 0

Tare Wt. 103.2163 g

Weight of Particulate in Acetone Rinse 0.03635g → 36.35mg

8:38 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.54844 g

3:45 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.54838 g

Average Gross Wt. 0.54841 g

Filter Tare Wt. 0.44938 g

Weight of Particulate on Filter 0.09903g → 99.03mg

Weight of Particulate 135.38 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, PW + Filter

Location: Dryer #5 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 175

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:05 AM Gross Wt. 93.3152 g

Date of Weighing 3/9/92 3:01 PM Gross Wt. 93.3145 g

Average Gross Wt. 93.31485 g

Less Blank Residue (Wa) 0

Tare Wt. 93.2842 g

Weight of Particulate in Acetone Rinse 0.0365 g → 36.5 mg

3:39 AM Date of Weighing 3/10/92 Gross Filter Wt. 0.55370 g

3:47 PM Date of Weighing 3/10/92 Gross Filter Wt. 0.55366 g

Average Gross Wt. 0.55368 g

Filter Tare Wt. 0.45342 g

Weight of Particulate on Filter 0.10026 g → 100.26 mg

Weight of Particulate 136.76 mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, PW & Filter

Location: Dyer #5 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 170

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:06 AM Gross Wt. 106.8386g

Date of Weighing 3/9/92 3:01 PM Gross Wt. 106.8376g

Average Gross Wt. 106.8381g

Less Blank Residue (Wa) 0

Tare Wt. 106.7972g

Weight of Particulate in Acetone Rinse 0.0409g → 40.9mg

8:40AM Date of Weighing 3/10/92 Gross Filter Wt. 0.58081g

3:52PM Date of Weighing 3/10/92 Gross Filter Wt. 0.58077g

Average Gross Wt. 0.58079g

Filter Tare Wt. 0.47040g

Weight of Particulate on Filter 0.11039g → 110.39mg

Weight of Particulate 151.29mg

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, Cyclone & Imps

Location: Dryer #1 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 50

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:32 AM Gross Wt. 98.2294g

Date of Weighing 3/9/92 3:29 PM Gross Wt. 98.2296g

Average Gross Wt. 98.2295g

Less Blank Residue (Wa) 0

Tare Wt. 98.2231g

Cyclone → Weight of Particulate in Acetone Rinse 0.0064g → 6.4mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 105.7434g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 105.7430g

Average Gross Wt. 105.7432g

~~Filter~~ Tare Wt. 105.7288g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0144g → 14.4mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, Cyclone Wash & Imps

Location: Dryer #1 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 45

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:34 AM Gross Wt. 102.6363g

Date of Weighing 3/9/92 3:31 PM Gross Wt. 102.6356g

Average Gross Wt. 102.63595g

Less Blank Residue (Wa) 0

Tare Wt. 102.6301g

Cyclone → Weight of Particulate in Acetone Rinse 0.00585g → 5.85mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 99.2464

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 99.2460g

Average Gross Wt. 99.2462g

~~Filter~~ Tare Wt. 99.2398g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0064g → 6.4mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, Cyclone Wash & Imps

Location: Dryer #1 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 45

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:35 AM Gross Wt. 103.0872g

Date of Weighing 3/9/92 3:36 PM Gross Wt. 103.0867g

Average Gross Wt. 103.08695g

Less Blank Residue (Wa) 0

Tare Wt. 103.0809g

Weight of Particulate in Acetone Rinse 0.00605g → 6.05mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 94.2730g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 94.2728g

Average Gross Wt. 94.2729g

~~Filter~~ Tare Wt. 94.2628g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0101g → 10.1mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, Cyclone Wash & Imps

Location: Dryer # 2 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 55

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:30 AM Gross Wt. 100.6264 g

Date of Weighing 3/9/92 3:26 PM Gross Wt. 100.6259 g

Average Gross Wt. 100.62615 g

Less Blank Residue (Wa) 0

Tare Wt. 100.6185 g

Cyclone → Weight of Particulate in Acetone Rinse 0.00765 g → 7.65 mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 99.6019 g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 99.6016 g

Average Gross Wt. 99.60175 g

~~Filter~~ Tare Wt. 99.5959 g

Weight of Particulate on ^{Imps}~~Filter~~ 0.00585 g → 5.85 mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, Cyclone Wash & Imps

Location: Dryer #2 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 60

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:31 AM Gross Wt. 102.9302 g

Date of Weighing 3/9/92 3:28 PM Gross Wt. 102.9297 g

Average Gross Wt. 102.92995 g

Less Blank Residue (Wa) 0

Tare Wt. 102.9208 g

Cyclone → Weight of Particulate in Acetone Rinse 0.00915 g → 9.15 mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 104.5246 g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 104.5244 g

Average Gross Wt. 104.5245 g

~~Filter~~ Tare Wt. 104.5212 g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0033 g → 3.3 mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, Cyclone & Imps

Location: Dryer # 2 Acetone Density (Pa): 0.7852

Date: 3/5/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 50

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:31 AM Gross Wt. 103.8249g

Date of Weighing 3/9/92 3:29 PM Gross Wt. 103.8243g

Average Gross Wt. 103.8246g

Less Blank Residue (Wa) 0

Tare Wt. 103.8192g

Cyclone → Weight of Particulate in Acetone Rinse 0.0054g → 5.4mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 97.9489g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 97.9489g

Average Gross Wt. 97.9489g

~~Filter~~ Tare Wt. 97.9459g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0030g → 3.0mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, Cyclone + Imps

Location: Dryer #3 Acetone Density (Pa): 0.7852

Date: 3/3/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 110

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:25 AM Gross Wt. 97.2460g

Date of Weighing 3/9/92 3:24 PM Gross Wt. 97.2455g

Average Gross Wt. 97.24575g

Less Blank Residue (Wa) 0

Tare Wt. 97.2115g

Cyclone → Weight of Particulate in Acetone Rinse 0.03425g → 34.25mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 107.4255g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 107.4253g

Average Gross Wt. 107.4254g

~~Filter~~ Tare Wt. 107.4192

Weight of Particulate on ^{Imps}~~Filter~~ 0.0062g → 6.2mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, Cyclone Wash + Imps

Location: Dryer #3 Acetone Density (Pa): 0.7852

Date: 3/3/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 110

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:26 AM Gross Wt. 99.2051g

Date of Weighing 3/9/92 3:25 PM Gross Wt. 99.2050g

Average Gross Wt. 99.20505g

Less Blank Residue (Wa) 0

Tare Wt. 99.1829g

Cyclone → Weight of Particulate in Acetone Rinse 0.02215g → 22.15mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 105.4422g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 105.4418g

Average Gross Wt. 105.4420g

~~Filter~~ Tare Wt. 105.4375g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0045g → 4.5mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, Cyclone Wash + Imps

Location: Dryer #3 Acetone Density (Pa): 0.7852

Date: 3/3/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 90

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:27 AM Gross Wt. 104.8880 g

Date of Weighing 3/9/92 3:25 PM Gross Wt. 104.8875 g

Average Gross Wt. 104.88775 g

Less Blank Residue (Wa) 0

Tare Wt. 104.8694 g

Cyclone → Weight of Particulate in Acetone Rinse 0.01835 g → 18.35 mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 97.3268 g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 97.3265 g

Average Gross Wt. 97.32665 g

~~Filter~~ Tare Wt. 97.3222 g

Weight of Particulate on ^{Imps}~~Filter~~ 0.00445 g → 4.45 mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, Cyclone Wash + Imps

Location: Dryer # 4 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 50

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/2/92 8:23 AM Gross Wt. 104.5399 g

Date of Weighing 3/2/92 3:22 PM Gross Wt. 104.5392 g

Average Gross Wt. 104.53955 g

Less Blank Residue (Wa) 0

Tare Wt. 104.5211 g

Cyclone → Weight of Particulate in Acetone Rinse 0.01845g → 18.45mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 97.2032 g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 97.2032 g

Average Gross Wt. 97.2032 g

^{Imps}~~Filter~~ Tare Wt. 97.1956 g

Weight of Particulate on ^{IMPS}~~Filter~~ 0.0076g → 7.6mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, Cyclone Wash & Imps

Location: Dryer #4 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 75

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:23 AM Gross Wt. 114.6617g

Date of Weighing 3/9/92 3:23 PM Gross Wt. 114.6613g

Average Gross Wt. 114.6615g

Less Blank Residue (Wa) 0

Tare Wt. 114.6527g

Cyclone → Weight of Particulate in Acetone Rinse 0.0088g → 8.8mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 105.7766g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 105.7764g

Average Gross Wt. 105.7765g

~~Filter~~ Tare Wt. 105.7690g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0075g → 7.5mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, Cyclone Wash & Imps

Location: Dryer #4 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 85

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:25 AM Gross Wt. 104.4207g

Date of Weighing 3/9/92 3:24 PM Gross Wt. 104.4200g

Average Gross Wt. 104.42035g

Less Blank Residue (Wa) 0

Tare Wt. 104.4012g

Cyclone → Weight of Particulate in Acetone Rinse 0.01915g → 19.15mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 95.8006g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 95.8002g

Average Gross Wt. 95.8004g

~~Filter~~ Tare Wt. 95.7918g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0086g → 8.6mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 1, Cyclone Wash + Imps

Location: Dryer #5 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 115

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:20 AM Gross Wt. 103.2448g

Date of Weighing 3/9/92 3:19 PM Gross Wt. 103.2448g

Average Gross Wt. 103.2448g

Less Blank Residue (Wa) 0

Tare Wt. 103.2166g

Cyclone → Weight of Particulate in Acetone Rinse 0.0282g → 28.2mg

Date of Weighing 3/10/92 Gross ^{IMPS}~~Filter~~ Wt. 98.5563g

Date of Weighing 3/10/92 Gross ^{IMPS}~~Filter~~ Wt. 98.5561g

Average Gross Wt. 98.5562g

~~Filter~~ Tare Wt. 98.5506g

Weight of Particulate on ^{IMPS}~~Filter~~ 0.0056g → 5.6mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 2, Cyclone Wash + Imps

Location: Dryer #5 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 70

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:22 AM Gross Wt. 95.4669 g

Date of Weighing 3/9/92 3:20 PM Gross Wt. 95.4673 g

Average Gross Wt. 95.4671 g

Less Blank Residue (Wa) 0

Tare Wt. 95.4515 g

Cyclone → Weight of Particulate in Acetone Rinse 0.0156 g → 15.6 mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 106.5547 g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 106.5545 g

Average Gross Wt. 106.5546 g

~~Filter~~ Tare Wt. 106.5501 g

Weight of Particulate on ^{Imps}~~Filter~~ 0.0045 g → 4.5 mg

Weight of Particulate _____

PARTICULATE ANALYTICAL DATA FORM

Company: Kirby Run Number: 3, Cyclone Wash & Imps

Location: Dryer #5 Acetone Density (Pa): 0.7852

Date: 3/2/92

Liquid Level Marked? ✓

Acetone Blank Concentration (Ca) 0

Acetone Rinse Volume (Vaw) 70

Residue in Rinse (Wa) = Ca * Vaw * Pa 0

Date of Weighing 3/9/92 8:22 AM Gross Wt. 95.8325g

Date of Weighing 3/9/92 3:21 PM Gross Wt. 95.8318g

Average Gross Wt. 95.83215g

Less Blank Residue (Wa) 0

Tare Wt. 95.8073g

Cyclone → Weight of Particulate in Acetone Rinse 0.02485g → 24.85mg

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 98.9466g

Date of Weighing 3/10/92 Gross ^{Imps}~~Filter~~ Wt. 98.9465g

Average Gross Wt. 98.94655g

~~Filter~~ Tare Wt. 98.9431g

Weight of Particulate on ^{Imps}~~Filter~~ 0.00345g → 3.45mg

Weight of Particulate _____

APPENDIX C

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3/5/92
REPETITION: 1

LOCATION: Dryer Exhaust #1
OPERATOR: JS
STACK #: 1
SAMPLE BOX #: 3
METER BOX #: 5
AMBIENT TEMPERATURE: 70
BAROMETRIC PRESSURE: 30.03
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .0000964 sq. ft (.133")
STACK DIAMETER: 4 1/2"
METER H: 1.8
C FACTOR: .84
METER CO-EFFICIENT: .9689231

IMPINGERS

	Initial	Final
#1: 100 mb H ₂ O		260
#2: 100 mb H ₂ O		110
#3: -		3
#4: 200 gm S.Gel		211.4
#5:		184.4

COMMENTS:

CO₂ O₂
2% 18%

FILTER TARE: .44640

PRE-TEST LEAK CHECK

Meter: .009 Cu. ft. 15 in. HG
Pitots: ✓ 185 in. H₂O
175

POST-TEST LEAK CHECK

Meter: .005 Cu. ft. 5 in. HG
Pitots: ✓ 185 in. H₂O

	Ø	STATIC PRESS.	TS CF	ΔP	√ΔP	ΔH	VM FT. S	TM INLET	TM OUTLET	CHEN TEMP	IMP OUTLET TEMP	VACUUM (IN H ₂ O)
1	14.7		184	1.3		.48	423.14	97	92	262	64	3
2	5.0	+1.1	185	1.5		.48	424.93	98	92	263	64	3
3	5.0		185	1.5		.48	426.87	98	92	266	64	3
4	5.5		186	1.8		.48	428.82	98	93	261	64	3
5	5.5		186	1.8		.48	430.95	99	93	264	64	3
6	5.3		186	1.7		.48	433.09	100	94	263	64	3
7	5.5		187	1.8		.48	435.14	100	95	264	64	3
8	5.5		186	1.8		.48	437.28	100	95	265	64	3
9	5.5		186	1.8		.48	439.41	101	96	266	64	3
10	5.2		184	1.6		.48	441.55	101	95	263	64	3
11	5.0		185	1.5		.48	443.57	100	96	260	64	3
12	4.8		182	1.4		.48	445.51	100	95	261	64	3
13	5.0		185	1.5		.48	447.37	98	95	266	64	3
2	4.8		183	1.4		.48	449.31	100	95	260	64	3
3	5.0		183	1.5		.48	451.18	100	95	256	64	3
4	5.3		185	1.7		.48	453.12	101	95	255	64	3
5	5.5		183	1.8		.48	455.19	102	96	252	64	3
6	5.5		185	1.8		.48	457.31	102	97	255	64	3
7	5.5		185	1.8		.48	459.45	101	96	254	64	3
8	5.5		185	1.8		.48	461.59	101	95	252	64	3
9	5.5		184	1.8		.48	463.72	101	96	250	64	3
10	5.0		183	1.5		.48	465.85	100	95	253	64	3
11	4.3		181	1.1		.48	467.80	100	95	256	64	3
12	4.5		179	1.2		.48	469.46	100	95	254	64	3
							471.216					
AV	123.9	+1.1	183.5	1.593	1.262	.48	48.102		97.37			

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3/5/92
REPETITION: 2

LOCATION: Dryer Exhaust #1

OPERATOR: JS
STACK #: 1
SAMPLE BOX #: 6
METER BOX #: 5
AMBIENT TEMPERATURE: 75°
BAROMETRIC PRESSURE: 30.03
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .133
STACK DIAMETER: 4 1/2"
METER H: 1.8
C FACTOR: .84
METER CO-EFFICIENT: .9689231

IMPINGERS

	Initial	Final
#1: 100 mls H ₂ O		249
#2: 100 mls H ₂ O		114
#3: -		3
#4: 200 grms S.G.C.		215
#5:		181

COMMENTS:

CO₂ O₂
2% 18%

FILTER TARE: .44373
PRE-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 15 in. HG
Pitots: ✓
12.16

POST-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 5 in. HG
Pitots: ✓
in. H2O

	Ø	STATIC PRES.	TS OF	AP	ΔP	ΔH	Vm FT.3	Tm INLET	Tm OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN Hg)
1	5.0	4.95	180	1.5		.48	471.433	93	91	251	65	3
2	5.2		181	1.6		.48	473.37	95	90	250	65	3
3	5.2		180	1.6		.48	475.39	96	91	251	65	3
4	5.5		181	1.8		.48	477.41	98	93	253	65	3
5	5.3		181	1.7		.48	479.54	99	94	252	65	3
6	5.4		183	1.75		.48	481.66	99	94	254	65	3
7	5.5		184	1.8		.48	483.70	100	95	256	65	3
8	5.5		183	1.8		.48	485.83	102	96	252	65	3
9	5.5		184	1.8		.48	487.97	103	98	252	65	3
10	5.5		183	1.8		.48	490.10	104	99	253	65	3
11	4.7		183	1.35		.48	492.24	104	106	253	65	3
12	4.5		182	1.2		.48	494.06	102	98	254	65	3
13	5.0		183	1.5		.48	495.84	98	96	253	65	3
14	5.2		183	1.6		.48	497.75	99	96	256	65	3
15	5.5		183	1.8		.48	499.77	101	96	250	65	3
16	5.5		184	1.8		.48	501.90	100	96	253	65	3
17	5.5		184	1.8		.48	504.04	100	95	253	65	3
18	5.5		183	1.8		.48	506.18	99	95	255	65	3
19	5.5		184	1.8		.48	508.31	99	94	255	65	3
20	5.5		183	1.8		.48	510.45	99	93	253	65	3
21	5.5		184	1.8		.48	512.58	98	93	259	65	3
22	5.5		183	1.8		.48	514.72	97	93	253	65	3
23	5.0		182	1.5		.48	516.85	95	92	253	65	3
24	4.7		179	1.3		.48	518.79	95	92	255	65	3
25							520.622					
AV	126.7		182.5	1.661		.48	499.89		96.75			

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3/5/92
REPETITION: 3

LOCATION: Dryer Exhaust^{#1}
OPERATOR: JS
STACK #: 1
SAMPLE BOX #: 1
METER BOX #: 5
AMBIENT TEMPERATURE: 70°
BAROMETRIC PRESSURE: 30.03
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .133
STACK DIAMETER: 4 1/2"
METER H: 1.8
C FACTOR: .84
METER CO-EFFICIENT: .9689231

IMPINGERS

	<u>Initial</u>	<u>Final</u>
#1: 100 mls H ₂ O		266
#2: 100 mls H ₂ O		110
#3: -		0
#4: 200 grms S.Gel		215.3
#5: -		191.3

COMMENTS:

CO₂ O₂
2% 18%

FILTER TARE: .45453
PRE-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 15 in. HG
Pitots: ✓ 185 in. H₂O
2.46 175

POST-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 5 in. HG
Pitots: ✓ 5 in. H₂O

	Ø	STATIC PRES.	Ts °F	ΔP	√ΔP	ΔH	Vm FT. ³	Tm INLET	Tm OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN Hg)
A1	4.8	179	179	1.4		.48	520.757	89	86	251	65	2
2	5.2	182	182	1.6		.48	522.62	90	88	255	65	2
3	5.3	183	183	1.7		.48	524.63	94	91	250	65	2
4	5.5	184	184	1.8		.48	526.69	96	91	251	65	2
5	5.5	185	185	1.8		.48	528.83	97	92	265	65	2
6	5.5	187	187	1.8		.48	530.96	99	93	260	65	2
7	5.5	185	185	1.8		.48	533.10	97	92	261	65	2
8	5.5	183	183	1.8		.48	535.23	96	90	255	65	2
9	5.5	185	185	1.8		.48	537.37	96	90	255	65	2
10	5.2	181	181	1.6		.48	539.50	95	90	257	65	2
11	4.8	179	179	1.4		.49	541.52	94	90	256	65	2
12	4.5	179	179	1.2		.48	543.39	94	90	251	65	2
13	5.0	182	182	1.5		.48	545.138	92	89	250	65	2
2	5.3	181	181	1.7		.48	547.07	93	90	251	65	2
3	5.5	181	181	1.8		.48	549.13	93	90	251	65	2
4	5.5	182	182	1.8		.48	551.27	93	89	255	65	2
5	5.5	182	182	1.8		.48	553.40	93	89	251	65	2
6	5.5	182	182	1.8		.48	555.54	93	89	252	65	2
7	5.5	182	182	1.8		.49	557.67	93	89	250	65	2
8	5.5	182	182	1.8		.48	559.81	94	90	251	65	2
9	5.5	181	181	1.8		.48	561.94	93	87	255	65	2
10	5.3	181	181	1.7		.48	564.08	93	89	255	65	2
11	5.0	180	180	1.5		.48	566.14	94	90	257	65	2
12	4.8	179	179	1.4		.48	568.08	94	90	251	65	2
							569.946					
AV	126.7	965	181.9		1.2908	.48	49.189		91.98			

PARTICULATE FIELD DATA

PLANT: LP
DATE: 3-5-92
REPETITION: 1

LOCATION: Dryer #2
OPERATOR: MP, DB
STACK #: #2
SAMPLE BOX #: 7
METER BOX #: 6
AMBIENT TEMPERATURE: 75
BAROMETRIC PRESSURE: 30.03
ASSUMED MOISTURE: 15.7
PROBE LENGTH: 5
NOZZLE DIAMETER: .136, .137, .138 (.137)
STACK DIAMETER: 41.5
METER H: 1.8919
C FACTOR: .84
METER CO-EFFICIENT: .9786

IMPINGERS

	Initial	Final
#1: 100 H ₂ O		251
#2: 100 H ₂ O		107
#3:		3
#4: 200 SG		214
#5:		175

COMMENTS:

CO₂ O₂
2.0 18.5

FILTER TARE: .46665
PRE-TEST LEAK CHECK

Meter: 0.011 Cu. ft. 16 in. HG
Pitots: 1.4 in. H₂O
start 9:22

POST-TEST LEAK CHECK

Meter: 0.00 Cu. ft. 2 in. HG
Pitots: 1.3 in. H₂O
2.0

	$\frac{Q}{min/ft}$	STATIC PRES.	TS CF	ΔP	$\sqrt{\Delta P}$	ΔH	Vm FT.S	Tm INLET	Tm OUTLET	OVEN TEMP	IMP. OUTLET TEMP	VACUUM (IN Hg)
1	4.1		174	1.2		.56	228.283	71	72	254	64	1
2	4.2		177	1.2		.56	29.9	78	74	253	64	1
3	4.4		177	1.3		.56	31.6	81	74	259	64	1
4	4.7		178	1.5		.56	33.4	82	75	258	64	1
5	4.9	1.85	174	1.6		.56	35.3	84	77	258	64	1
6	4.9		179	1.6		.56	37.3	85	77	260	64	1
7	5.0		179	1.7		.56	39.3	87	78	263	64	1
8	5.4		179	1.9		.56	41.3	88	78	261	64	1
9	5.2		180	1.8		.56	43.5	88	79	262	64	1
10	4.7		179	1.5		.56	45.6	88	80	260	64	1
11	4.2		177	1.2		.56	47.6	86	79	255	64	1
12	4.1		175	1.1		.56	49.3	87	79	260	64	1
13	5.0	1.85	177	1.65		.56	250.976	81	79	265	64	1
14	5.2		178	1.8		.56	53.0	86	79	267	64	1
15	5.5		178	2.0		.56	55.1	88	80	261	64	1
16	5.5		180	2.0		.56	57.3	88	78	261	64	1
17	5.6		179	2.0		.56	59.6	89	80	260	64	1
18	5.5		180	2.0		.56	61.8	89	80	259	64	1
19	5.4		179	1.9		.56	64.1	89	81	261	64	1
20	5.1		179	1.65		.56	66.3	90	81	260	64	1
21	5.0		178	1.65		.56	68.4	90	82	266	64	1
22	4.7		178	1.45		.56	70.4	90	82	263	64	1
23	4.2		175	1.2		.56	72.3	91	82	262	64	1
24	4.1		174	1.2		.56	73.9	91	83	263	64	1
AV	116.5		177.8	1.5603	1.2491	.56	146.352		82.42			

PARTICULATE FIELD DATA

PLANT: LP
DATE: 3-5-92
RÉPÉTITION: 2

LOCATION: Dryer #2
OPERATOR: mp DB
STACK #: #2
SAMPLE BOX #: 6
METER BOX #: 6
AMBIENT TEMPERATURE: 80
BAROMETRIC PRESSURE: 30.03
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .137
STACK DIAMETER: 41.5"
METER H: 1.8919
C FACTOR: 1.84
METER CO-EFFICIENT: .9786

IMPINGERS

	Initial	Final
#1: 100 H ₂ O		259
#2: 100 H ₂ O		113
#3:		3
#4: 200 SG		215
#5:		185

COMMENTS:

CO₂ OL
2.0 19.0

FILTER TARE: 45531
PRE-TEST LEAK CHECK

Meter: 0.015 Cu. ft. 15 in. HG
Pitots: 1.6 in. H₂O
1.5

POST-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 5 in. HG
Pitots: 2.0 in. H₂O
1.5

	STATIC PRES.	TS °F	ΔP	√ΔP	ΔH	Vm FT. ³	Tm INLET	Tm OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN Hg)
1	5.1	178	1.7		.56	275.960	80	78	244	67	2.5
2	5.4	178	1.9		.56	18.0	85	79	246	67	2.5
3	5.5	178	2.0		.56	80.2	86	79	243	67	2.5
4	5.5	178	2.0		.56	82.4	88	80	256	67	2.5
5	5.7	178	2.0		.49	84.7	88	80	266	67	2.5
6	5.7	178	2.0		.49	86.8	88	80	258	67	2.5
7	5.4	178	1.9		.49	89.0	87	80	259	67	2.5
8	5.2	177	1.8		.49	91.1	90	82	261	67	2.5
9	5.0	177	1.65		.49	93.1	90	82	257	67	2.5
10	4.4	176	1.3		.49	95.0	91	83	258	67	2.5
11	4.1	173	1.1		.49	96.7	90	82	260	67	2.5
12	4.1	172	1.2		.49	98.2	91	83	261	67	2.5
13	4.6	175	1.4		.49	29.844	86	83	245	67	2.5
14	4.8	177	1.5		.49	301.6	91	84	240	67	2.5
15	5.1	179	1.75		.49	3.4	92	84	258	67	2.5
16	5.2	179	1.8		.49	5.4	93	85	259	67	2.5
17	5.4	179	1.9		.49	7.3	93	85	248	67	2.5
18	5.4	180	1.9		.49	9.4	92	85	250	67	2.5
19	5.4	179	1.9		.49	11.5	92	85	256	67	2.5
20	5.1	181	1.75		.49	13.5	92	84	261	67	2.5
21	5.1	179	1.7		.49	15.5	92	84	262	67	2.5
22	4.4	179	1.3		.49	17.4	90	83	245	67	2.5
23	4.1	169	1.2		.49	19.1	92	84	259	67	2.5
24	4.1	170	1.2		.49	20.7	90	83	254	67	2.5
AV	119.8	176.96	1.6463	1.2831	.502	46.326		85.95			

PARTICULATE FIELD DATA

PLANT: LP
DATE: 3-5-92
REPETITION: 3

LOCATION: Dryer #2
OPERATOR: MP DB
STACK #:
SAMPLE BOX #: 7
METER BOX #: 6
AMBIENT TEMPERATURE: 70
BAROMETRIC PRESSURE: 30.03
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5
NOZZLE DIAMETER: .137
STACK DIAMETER: 41.5"
METER H: 1.8919
C FACTOR: .84
METER CO-EFFICIENT: .9786

IMPINGERS

	Initial	Final
#1: 100 H ₂ O		242
#2: 100 H ₂ O		110
#3:		2
#4: 200 SO ₂		213.1
#5:		167.1

COMMENTS:

CO ₂	O ₂
2%	19%

FILTER TARE: .46287

PRE-TEST LEAK CHECK

Meter: 0.009 Cu. ft. 15 in. HG
Pitots: 1.6 in. H₂O
1.4

POST-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 2.5 in. HG
Pitots: in. H₂O

2.12	Ø	STATIC PRES.	Ts OF	ΔP	√ΔP	ΔH	Vm FT.3	Tm INLET	Tm OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN Hg)
1	4.7		176	1.45		.49	322.81	81	81	254	62	1
2	4.9		175	1.6		.49	24.6	84	79	251	62	1
3	5.0		177	1.65		.49	26.4	87	80	261	62	1
4	5.1		178	1.75		.49	28.4	86	79	255	62	1
5	5.4	4.87	178	1.9		.49	30.3	88	81	254	62	1
6	5.5		178	2.0		.49	32.4	88	80	257	62	1
7	5.9		178	1.9		.49	34.5	90	81	258	62	1
8	5.1		178	1.75		.49	36.5	89	81	258	62	1
9	5.1		176	1.75		.49	38.5	88	81	255	62	1
10	4.6		173	1.4		.49	40.4	89	81	258	62	1
11	4.1		170	1.1		.49	42.2	87	79	255	62	1
12	4.1		171	1.1		.49	43.8	88	79	265	62	1
1	5.1		175	1.75		.49	345.371	81	78	267	62	1
2	5.4		177	1.9		.49	47.3	86	78	265	62	1
3	5.5		176	2.0		.49	49.3	86	77	265	62	1
4	5.5		176	2.0		.49	51.5	83	77	262	62	1
5	5.5		177	2.0		.49	53.6	82	77	262	62	1
6	5.7	4.90	176	2.1		.49	55.7	83	76	264	62	1
7	5.4		177	1.9		.49	57.8	82	76	261	62	1
8	5.2		173	1.8		.49	59.9	84	77	262	62	1
9	5.2		173	1.8		.49	61.9	84	76	266	62	1
10	4.5		174	1.35		.49	63.9	84	76	260	62	1
11	4.1		163	1.1		.49	65.6	84	77	269	62	1
12	4.1		164	1.1		.49	67.2	85	76	259	62	1
							368.769					
AV	120.2	.885	174.5	1.654	1.2870	.49	45.958		82.02			

PLANT: Kirby
DATE: 3/3/92
REPETITION: 1

.253907
3.1827572

LOCATION: Dryer Exhaust #3
OPERATOR: JS, AB, LW
STACK #: 3
SAMPLE BOX #: 2
METER BOX #: 2
AMBIENT TEMPERATURE: 65°
BAROMETRIC PRESSURE: 30.3
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .136, .137, .138 (Ave. .137)
STACK DIAMETER: 4 1/2"
METER H: 1.764806
C FACTOR: .84
METER CO-EFFICIENT: 1.067884

IMPINGERS

	Initial	Final
#1: 100 mls H ₂ O		248
#2: 100 mls H ₂ O		112
#3: -		4
#4: 200 grms S. Gel		212.4
#5: -		176.4

COMMENTS:

	CO ₂	O ₂
A	1%	20%
B	1%	20%

FILTER TARE: .44840

PRE-TEST LEAK CHECK

Meter: 0.000 Cu. ft. 15 in. HG
Pitots: 2.1 in. H₂O
Start 9:10 3.0

POST-TEST LEAK CHECK

Meter: 0.000 Cu. ft. 4 in. HG
Pitots: 2.9 in. H₂O
3.8

	θ	STATIC PRES.	TS °F	AS	ΔP	ΔH	Vm FT./S	Tm INLET	Tm OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN H ₂ O)
1	4.9	14.89	168	1.4		.38	1448.82	77	75	258	68	1
2	5.4		173	1.7		.38	1450.53	82	77	267	68	1
3	5.5		176	1.8		.38	1452.42	86	79	269	68	1
4	5.7		176	1.9		.38	1454.35	91	82	263	63	1
5	5.5		178	1.8		.38	1456.34	93	84	268	63	1
6	5.7		179	1.9		.38	1458.27	96	86	265	63	1
7	5.4		178	1.7		.38	1460.26	97	88	266	63	1
8	5.2		177	1.6		.38	1462.15	98	90	265	63	1
9	4.9		176	1.4		.38	1463.97	100	91	262	64	1
10	4.3		174	1.1		.38	1465.69	102	91	266	64	1
11	4.1		173	.99		.38	1467.19	104	94	268	64	1
12	3.9		158	.88		.38	1468.63	102	94	260	64	1
13	4.5		168	1.2		.38	1469.95	102	96	258	64	1
2	5.1	11.15	173	1.5		.38	1471.57	102	96	264	64	1
3	5.1		175	1.5		.38	1473.35	103	97	263	64	1
4	5.4		173	1.7		.38	1475.14	104	97	264	65	1
5	5.4		174	1.7		.38	1477.02	104	98	253	65	1
6	5.7		174	1.9		.38	1478.91	104	99	251	65	1
7	5.5		175	1.8		.38	1480.91	101	99	256	65	1
8	5.7		175	1.9		.38	1482.83	100	98	258	65	1
9	5.1		176	1.5		.38	1484.83	101	98	256	65	1
10	5.1		175	1.5		.38	1486.61	103	98	257	62	1
11	4.2		174	1.0		.38	1488.40	103	98	251	58	1
12	3.8		173	1.0		.38	1489.87	106	98	255	58	1
SEP	MSIYAM						1491.20					
AV	12.1	11.02	173.8	1.495	1223	.38	1423.8			95.08		

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3-3-92
REPETITION: 2

LOCATION: Dyer Ex #3
OPERATOR: LW
STACK #: #3
SAMPLE BOX #: 6
METER BOX #: 2
AMBIENT TEMPERATURE: 68
BAROMETRIC PRESSURE: 30.3
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .137
STACK DIAMETER: 41.5"
METER H: 1.76481
C FACTOR: .84
METER CO-EFFICIENT: 1.06788

IMPINGERS

	Initial	Final
#1: 100 mls H ₂ O		260
#2: 100 mls H ₂ O		114
#3: —		2
#4: 200 gr SG		214.3
#5:		190.3

COMMENTS:

CO₂ O₂
1.5% 19.5%

FILTER TARE: .44373 gr
PRE-TEST LEAK CHECK

Meter: 0.003 Cu ft. 8 in. HG
Pitots: ✓ 2.4 in. H₂O
11.37 6.5

POST-TEST LEAK CHECK

Meter: 0.000 Cu. ft. 5 in. HG
Pitots: ✓ 2.9 in. H₂O
3.4

	Ø	STATIC PRES.	TS °F	ΔP	√ΔP	ΔH	Vm FT. ³	Tm INLET	Tm OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN H ₂ O)
A1	4.93		169	1.2		.389	141.324	93	90	255	67	1.0
2	5.43		172	1.6		.389	143.7	95	90	249	68	1.0
3	5.59		173	1.7		.389	144.9	99	91	251	67	1.0
4	5.74	1.87	174	1.8		.389	145.9	101	92	261	66	1.0
5	5.59		174	1.9		.389	148.9	102	93	260	66	1.0
6	5.74		176	1.9		.389	1500.9	104	94	261	67	1.0
7	5.43		176	1.7		.389	2.9	105	95	260	66	1.0
8	5.27		176	1.6		.389	4.8	104	96	259	66	1.0
9	4.93		177	1.4		.389	6.6	104	97	260	67	1.0
10	4.37		174	1.2		.389	8.4	105	97	261	66	1.0
11	4.15		162	1.0		.389	9.9	105	97	260	67	1.0
12	3.91		147	0.8		.389	11.3	104	98	258	66	1.0
B1	4.56	12.38	168	1.1		.389	112.701	102	98	253	66	1.0
2	5.10		175	1.3		.389	14.3	104	98	260	66	1.0
3	5.10		174	1.6		.389	16.1	105	98	257	66	1.0
4	5.43		176	1.9		.389	17.9	106	99	256	66	1.0
5	5.43		176	1.8		.389	19.8	106	99	258	67	1.0
6	5.27		176	1.8		.389	21.7	107	100	256	66	1.0
7	5.27		176	1.9		.389	23.7	109	100	255	66	1.0
8	5.27		176	1.8		.389	25.6	108	100	255	66	1.0
9	5.10		175	1.7		.389	27.6	110	100	251	67	1.0
10	5.10		175	1.6		.389	29.4	110	101	255	66	1.0
11	4.79		174	1.3		.389	31.2	108	100	248	67	1.0
12	4.03		173	1.0		.389	32.7	107	100	248	67	1.0
							534.089					
AV	122.19	.87	172.7	1.505	1.227	.389	42.765		100.1			

1:45 pm

3:40

100

47:48

12:39

6:27

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3-3-92
REPETITION: 3

LOCATION: Dryer Exhaust #3
OPERATOR: DB, LW, JS
STACK #3 Dryer
SAMPLE BOX #:
METER BOX #: 2
AMBIENT TEMPERATURE: 77
BAROMETRIC PRESSURE: 30.3
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .137
STACK DIAMETER: 41.5"
METER H: 1.76481
C FACTOR: .84
METER CO-EFFICIENT: 1.06788

IMPINGERS

	Initial	Final
#1: 100 mls H ₂ O		247
#2: 100 mls H ₂ O		104
#3: —		2
#4: 200 gr SG		216.2
#5:		169.2

COMMENTS:

CO₂ 1%
O₂ 19.0%

FILTER TARE: .45638 gr
PRE-TEST LEAK CHECK

Meter: 0.013 Cu. ft. 10 in. HG
Pitots: ✓ 3.4 in. H₂O
2:10 PM ✓ 3.1

POST-TEST LEAK CHECK

Meter: 0.013 Cu. ft. 6 in. HG
Pitots: ✓ 9.2 in. H₂O
4.7

	θ	STATIC PRES.	IS CF	ΔP	√ΔP	ΔH	Vm FT.3	Tm INLET	Tm OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN Hg)
A 1	4.56		176	1.2		.389	532.221	97	96	256	64	1.0
2	5.27		173	1.6		.389	33.8	97	93	261	69	1.0
3	5.43		174	1.9		.389	35.7	99	93	268	60	1.0
4	5.59		176	1.9		.389	37.6	100	93	270	57	1.0
5	5.74		177	1.9		.389	39.5	102	94	262	57	1.0
6	5.74 + .91		176	1.8		.389	41.5	104	95	258	55	1.0
7	5.43		178	1.9		.389	43.5	104	96	262	54	1.0
8	5.85		175	1.7		.389	45.4	105	96	262	55	1.0
9	4.93		174	1.5		.389	47.3	106	97	261	56	1.0
10	4.56		173	1.5		.389	49.0	107	98	266	56	1.0
11	4.19		168	1.2		.389	50.6	107	98	266	56	1.0
12	3.77		145	.82		.389	52.1	106	98	263	55	1.0
B 1	4.37 3:23		168	1.2		.389	553.381	102	98	264	56	1.0
2	4.84		173	1.4		.389	54.9	105	98	260	63	1.0
3	5.27		176	1.6		.389	56.6	106	98	260	60	1.0
4	5.74		176	1.7		.389	58.4	107	99	253	61	1.0
5	5.59		176	1.8		.389	60.5	109	100	256	64	1.0
6	5.59		176	1.9		.389	62.4	108	100	260	64	1.0
7	5.74		177	1.9		.389	64.4	108	100	263	65	1.0
8	5.59		178	1.8		.389	66.4	107	100	256	66	1.0
9	5.43		178	1.7		.389	68.3	106	100	255	68	1.0
10	5.27		170	1.5		.389	70.2	107	100	259	65	1.0
11	4.75		163	1.1		.389	72.1	107	100	257	63	1.0
12	3.97		169	1.0		.389	73.7	107	100	257	63	1.0
AV	122.02		172.7	1.545	1.243		42.816	101.1				

3:27

PARTICULATE FIELD DATA

PLANT: Kirby Forest Ind.
DATE: 3/2/92
REPETITION: 1

LOCATION: Dryer Exhaust #4
OPERATOR: JS, DB
STACK #: 4
SAMPLE BOX #: 1
METER BOX #: 6
AMBIENT TEMPERATURE: 65°
BAROMETRIC PRESSURE: 30.4
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .133, .132, .134 (Avg. .133) (00009648)
STACK DIAMETER: 4 1/2"
METER H: 1.891962
C FACTOR: .84
METER CO-EFFICIENT: .4786262

IMPINGERS

	Initial	Final
#1: 100mls H ₂ O		256
#2: 100mls H ₂ O		117
#3: —		3
#4: 200grms S.G.		210.4
#5: —		186.4

COMMENTS:

CO₂ O₂
2% 19.5%

FILTER TARE: .45856
PRE-TEST LEAK CHECK

Meter: 0.014 Cu. ft. 15 in. HG
Pitots: ☒ .85 in. H₂O

POST-TEST LEAK CHECK

Meter: 0.011 Cu. ft. 14 in. HG
Pitots: ☒ 1.2 in. H₂O

Start 10:54

End 11:59
Stop 12:08

	θ	STATIC PRES.	TS °F	ΔP	√ΔP	ΔH	Vm FT.	Tm INI	Tm ET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN Hg)
A1	4.85		161	1.4		.45	96.420	72	73	251	66	1
2	5.1	+1.2	169	1.6		.45	98.17	79	73	259	66	1
3	5.4		168	1.8		.45	100.02	83	75	261	66	1
4	5.5		170	1.9		.45	101.99	82	75	252	66	1
5	5.5		171	1.9		.45	103.99	85	77	255	67	1
6	5.8		172	2.1		.45	106.00	85	77	252	67	1
7	6.7		172	2.2		.45	108.11	86	78	252	67	1
8	6.1		172	2.2		.45	110.33	86	78	251	67	1
9	5.2		172	1.7		.45	112.56	86	79	253	67	1
10	5.8		170	2.1		.45	114.45	87	80	255	68	1
11	5.2		169	1.7		.45	116.56	87	81	263	68	1
12	4.0		158	1.1		.45	118.46	87	80	259	68	1
B1	4.9	11:59	166	1.5		.45	119.920	83	82	251	68	1
2	5.2		171	1.7		.45	121.70	86	80	250	68	1
3	5.2		171	1.7		.45	123.60	86	80	253	68	1
4	6.0		171	2.2		.45	125.49	86	80	256	68	1
5	6.0		172	2.2		.45	127.68	87	80	251	68	1
6	6.0		172	2.2		.45	129.86	88	80	254	68	1
7	5.7		173	2.0		.45	132.05	89	82	251	68	1
8	5.2		171	1.7		.45	134.12	89	82	255	68	1
9	5.4		173	1.8		.45	136.02	89	83	264	68	1
10	5.1		170	1.6		.45	137.99	89	82	256	68	1
11	4.0		169	1.1		.45	139.84	89	82	262	68	1
12	3.8		163	.95		.45	141.30	90	83	259	68	1
1311 PM							142.691					
AV		+1.2	169.4	1.744	1.3207	.45	146.271		82.46			

127 min.

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3/2/92
REPETITION: 2

LOCATION: Dryer Exhaust #4
OPERATOR: JS, DB
STACK #: 4
SAMPLE BOX #: 7
METER BOX #: 6
AMBIENT TEMPERATURE: 70°
BAROMETRIC PRESSURE: 30.4
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .133"
STACK DIAMETER: 4 1/2"
METER H: 1.89/962
C FACTOR: .84
METER CO-EFFICIENT: .9786262

IMPINGERS

	Initial	Final
#1: 100 ml H ₂ O		226
#2: 100 ml H ₂ O		106
#3: -		4
#4: 200 grms S.G. 6.0		212.5
#5: -		148.5

COMMENTS:

CO₂ O₂
10% 19%

FILTER TARE: .45338
PRE-TEST LEAK CHECK

Meter: 0.009 Cu. ft. 15 in. HG
Pitots: .85 in. H₂O
2:25

POST-TEST LEAK CHECK

Meter: 0.009 Cu. ft. 5 in. HG
Pitots: .85 in. H₂O

#	θ	STATIC PRESS	Ts OF	ΔP	VAP	ΔT	Vm FT.	Tm IN	Tm OUT	OVEN TEMP	IMP WILET TEMP	VACUUM IN HG
1	3.6	4	165	1.9		.45	142.868	77	77	250	68	1
2	4.4		168	1.4		.45	144.17	80	76	253	68	1
3	4.7		168	1.6		.45	145.78	82	76	259	68	1
4	4.7		170	1.6		.45	147.49	83	76	260	69	1
5	4.7		170	1.6		.45	149.20	85	77	264	69	1
6	4.8		170	1.7		.45	150.91	85	78	261	70	1
7	5.2		171	2.0		.45	152.66	86	79	265	70	1
8	5.2		171	2.0		.45	154.56	87	79	265	70	1
9	4.8	+1.3	171	1.7		.45	156.45	87	79	269	70	1
10	3.7		172	1.1		.45	158.20	87	79	266	70	1
11	4.7		167	1.6		.45	159.55	87	80	269	70	1
12	3.6		158	1.7		.45	161.26	88	81	265	70	1
13	3.6		169	.95		.45	162.578	83	81	250	70	1
2	4.4		170	1.4		.45	163.89	87	82	260	70	1
3	4.5		171	1.5		.45	165.49	89	82	251	70	1
4	5.0		171	1.8		.45	167.13	88	82	259	70	1
5	4.8		172	1.7		.45	168.95	88	82	267	70	1
6	4.8		172	1.7		.45	170.70	88	82	257	70	1
7	5.6		173	2.2		.45	172.45	89	82	259	70	1
8	5.4	+1.0	172	2.0		.45	174.49	89	82	259	70	1
9	4.8		171	1.7		.45	176.46	88	82	263	70	1
10	4.7		170	1.6		.45	178.21	87	82	256	71	1
11	4.4		168	1.4		.45	179.92	87	81	263	71	1
12	3.7		159	1.1		.45	181.52	87	80	259	71	1
							182.872					
AV		+1.15	169.1	1.545	1.243	.45	40.004		82.92			

109.8 min

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3/2/92
REPETITION: 3

LOCATION: Dryer Exhaust #4
OPERATOR: JS, DB
STACK #: 4
SAMPLE BOX #: 3
METER BOX #: 6
AMBIENT TEMPERATURE: 70°
BAROMETRIC PRESSURE: 30.4
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .133
STACK DIAMETER: 4 1/2"
METER H: 1.891962
C FACTOR: .84
METER CO-EFFICIENT: .9786262

IMPINGERS

	Initial	Final
#1: 100 mls H ₂ O		256
#2: 100 ml H ₂ O		111
#3: -		3
#4: 200 grms S. Gel		214.7
#5: -		184.7

COMMENTS:

CO₂ O₂
1.5% 19%

FILTER TARE: .44803

PRE-TEST LEAK CHECK

Meter: 0.089 Cu. ft. 15 in. HG
Pitots: 1.8 in. H₂O

Start 4:50 pm

POST-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 5 in. HG
Pitots: 2.2 in. H₂O

	Ø	STATIC PRES.	Ts °F	ΔP	√ΔP	ΔH	Vm ft. ³	Tm INLET	Tm OUTLET	OVEN TEMP.	IMP OUTLET TEMP.	VACUUM (IN Hg)
A1	4.5	71.1	161	1.5		.45	183.059	72	75	250	70	1
2	4.5		164	1.5		.45	184.69	80	76	255	70	1
3	4.7		167	1.6		.45	186.33	81	76	262	70	1
4	4.8		168	1.7		.45	188.05	82	76	258	70	1
5	5.0		169	1.8		.45	189.79	82	76	259	70	1
6	5.1		170	1.9		.45	191.62	82	77	260	70	1
7	5.6		170	2.3		.45	193.47	83	76	258	70	1
8	5.4		171	2.1		.45	195.51	84	76	265	70	1
9	5.4		171	2.1		.45	197.48	84	77	260	70	1
10	4.9		168	1.7		.45	199.45	84	77	262	70	1
11	4.7		168	1.6		.45	201.20	84	76	264	70	1
12	4.4		168	1.4		.45	202.91	84	77	262	70	1
13	4.7		163	1.6		.45	204.518	79	76	255	70	1
2	4.8		167	1.7		.45	206.23	82	75	253	70	1
3	5.1		167	1.9		.45	207.98	82	75	253	70	1
4	5.4		171	2.1		.45	209.83	83	75	256	70	1
5	5.4		164	2.1		.45	211.80	82	75	256	70	1
6	5.4		170	2.1		.45	213.77	82	75	253	70	1
7	5.4		172	2.1		.45	215.74	82	75	256	70	1
8	5.4		170	2.1		.45	217.70	81	75	255	70	1
9	5.0		169	1.8		.45	219.67	81	74	251	70	1
10	4.8		169	1.7		.45	221.49	81	75	256	70	1
11	4.7		166	1.6		.45	223.24	81	75	261	70	1
12	4.7		167	1.6		.45	224.95	81	75	259	70	1
							226.670					
AV			167.9	1.809	1.345	.45	43.611		78.63			

119.7 min

PARTICULATE FIELD DATA

Vel = 80.61

WMS 39.30

nd = 29.02

PLANT: Kirby
DATE: 3-2-92
REPETITION: 1

19.45

ms = 27.37

15.14% moisture

P₃ = 30.37

25-7.0134

msPs = 831.34

73 623.5

LOCATION: Dryer Ex #5

OPERATOR: LW, JB

STACK #: Dryer #5

SAMPLE BOX #: 6

METER BOX #: 2

AMBIENT TEMPERATURE: 62

BAROMETRIC PRESSURE: 30.3

ASSUMED MOISTURE: 15%

PROBE LENGTH: 8'

NOZZLE L. METER: .127, .132, .130 (.1297)

STACK DIAMETER: 41.5"

METER H: 1.76481

C FACTOR: .84

METER CO-EFFICIENT: 1.06788

IMPINGERS

	Initial	Final
#1: 100 mls H ₂ O		232
#2: 100 mls H ₂ O		107
#3: —		3
#4: 200 gr SG		212.7
#5:		154.7

COMMENTS:

CO₂
1.5%

O₂
19.5%

10:15 AM

FILTER TARE: 44938 gr

PRE-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 15 in. HG
Pitots: 2.5 in H₂O
9:45 AM 2.1 Run

POST-TEST LEAK CHECK

Meter: 0.010 Cu. ft. 6 in. HG
Pitots: 2.2 in H₂O
2.7

	Ø	STAT. PRES.	ΔP	ΔH	VM FT/S	TM INLET	TM OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN H ₂ O)
1	4.55	175	1.5	.31	136.28	66	65	263	65	1.0
2	4.82	161	1.7	.31	137.7	71	66	265	65	1.0
3	4.91	162	2.0	.31	139.2	75	68	264	63	1.0
4	5.09	164	2.0	.31	140.7	79	70	260	64	1.0
5	5.41	164	1.9	.31	142.3	82	72	257	64	1.0
6	5.49	165	2.0	.31	144.0	84	75	256	64	1.0
7	5.57	165	2.0	.31	145.7	86	76	253	64	1.0
8	5.49	165	2.0	.31	147.5	88	78	255	65	1.0
9	5.25	166	1.9	.31	149.2	87	79	259	66	1.0
10	4.64	163	1.3	.31	150.8	87	80	239	67	1.0
11	4.55	157	1.1	.31	152.3	88	81	268	67	1.0
12	3.44	142	0.71	.31	153.7	88	81	255	68	1.0
3	4.55	163	2.0	.31	154.954	83	82	265	68	1.0
2	4.73	165	2.1	.31	156.4	85	80	264	67	1.0
3	4.91	165	2.8	.31	157.9	87	81	266	66	1.0
4	5.25	165	2.8	.31	159.4	88	82	263	67	1.0
5	5.09	166	1.9	.31	161.0	88	83	262	67	1.0
6	5.17	167	1.7	.31	162.6	90	83	258	68	1.0
7	5.87	164	1.8	.31	164.2	90	84	258	65	1.0
8	5.80	167	2.0	.31	166.1	91	85	263	65	1.0
9	5.33	167	1.6	.31	167.9	90	85	264	66	1.0
10	4.73	165	1.4	.31	169.6	91	86	264	67	1.0
11	4.15	160	1.1	.31	171.0	91	86	265	67	1.0
12	4.05	159	1.1	.31	172.3	91	86	264	68	1.0
Stop	12:00				173.606					
AV		163.4	1.669	1.292	173.325		82.5			

119.34 min

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3-2-72
REPETITION: 2

LOCATION: Dryer Ex #5
OPERATOR: LW, JB
STACK #: Ex #5
SAMPLE BOX #: 3
METER BOX #: 2
AMBIENT TEMPERATURE: 70
BAROMETRIC PRESSURE: 30.3
ASSUMED MOISTURE: 15%
PROBE LENGTH: 8
NOZZLE DIAMETER: .129667"
STACK DIAMETER: 41.5
METER H: 1.76481
C FACTOR: .84
METER CO-EFFICIENT: 1.06788

IMPINGERS

	Initial	Final
#1: 100 mls H ₂ O		229
#2: 100 mls H ₂ O		105
#3: —		3
#4: 200 gr SG		211.2
#5:		148.2

COMMENTS:

CO₂ 1% O₂ 19% 2:50 pm

FILTER TARE: .45342 gr
PRE-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 8 in. FG
Pitots: ✓ 2.9 in. H₂O
1.31 pm ✓ 4.0

POST-TEST LEAK CHECK

Meter: 0.005 Cu. ft. 8 in. FG
Pitots: ✓ 3.1 in. H₂O
2.8

	Ø	STATIC PRESS.	IS CF	ΔP	√ΔP	ΔH	PI INLET	PI OUTLET	OVEN TEMP	IMP OUTLET TEMP	VACUUM (IN Hg)
B 1	4.72		165	1.4	.31	1373.918	84	84	253	66	1.0
2	5.03		166	1.5	.31	75.2	84	80	262	64	1.0
3	5.46		167	1.8	.31	76.8	87	81	268	64	1.0
4	5.46	+1.87	167	1.8	.31	78.5	90	83	267	64	1.0
5	5.32		167	2.0	.31	80.2	90	84	268	64	1.0
6	5.46		168	2.0	.31	81.8	91	85	266	66	1.0
7	5.59		168	2.0	.31	83.6	94	86	268	64	1.0
8	5.59		168	2.1	.31	85.3	94	87	267	64	1.0
9	5.31		167	2.0	.31	87.1	93	87	270	66	1.0
10	4.39		166	1.7	.31	88.7	91	87	271	66	1.0
11	3.62		159	1.0	.31	90.1	92	87	272	65	1.0
12	3.45		160	1.0	.31	91.2	91	86	270	65	1.0
A 1	5.46	2:50 5.34	158	1.8	.31	92.3	86	86	269	65	1.0
2	5.59		165	1.8	.31	94.0	89	85	249	66	1.0
3	5.17		164	2.0	.31	95.8	90	85	262	66	1.0
4	5.46		164	2.3	.31	97.4	91	85	275	66	1.0
5	5.32		166	2.1	.31	99.0	91	85	264	67	1.0
6	5.03		165	2.0	.31	100.7	91	85	263	68	1.0
7	5.32		167	1.9	.31	2.4	91	85	264	67	1.0
8	5.59	+1.0	167	1.8	.31	4.1	91	86	266	68	1.0
9	4.88		167	1.8	.31	5.9	93	87	261	68	1.0
10	4.56		165	1.0	.31	7.4	93	87	260	67	1.0
11	3.70		160	1.0	.31	18.9	93	88	261	68	1.0
12	3.45		153	0.82	.31	10.0	93	88	255	68	1.0
							1411.089				
AV	120.92	1.94	164.5	1.661	1.289	.31	37.378	87.96			

Stop - 3:35 pm

PARTICULATE FIELD DATA

PLANT: Kirby
DATE: 3-2-92
REPETITION: 3

LOCATION: Dryer Ex. #5
OPERATOR: CW, JB
STACK #: Dryer #5
SAMPLE BOX #: 6
METER BOX #: 2
AMBIENT TEMPERATURE: 69
BAROMETRIC PRESSURE: 30.3
ASSUMED MOISTURE: 15%
PROBE LENGTH: 5'
NOZZLE DIAMETER: .129667"
STACK DIAMETER: 41.5"
METER H: 1.76481
C FACTOR: .84
METER CO-EFFICIENT: 1.06788

IMPINGERS

	Initial	Final
#1: 100 m/s H ₂ O		224
#2: 100 m/s H ₂ O		104
#3: —		2
#4: 200 gr SG		213.2
#5:		143.2

COMMENTS:

CO₂ 1.5% O₂ 19% 5:30 pm

FILTER TARE: .47040 gr
PRE-TEST LEAK CHECK

Meter: 0.019 Cu. ft. 19 in. HG
Pitots: ✓ 3.2 in. H₂O
4:38 pm ✓ 3.4

POST-TEST LEAK CHECK

Meter: 0.011 Cu. ft. 9 in. HG
Pitots: ✓ in. H₂O

	θ	STATIC PRES.	Ts °F	ΔP	√ΔP	ΔH	Vm FT./S	Tm INLET	Tm OUTLET	OVEN TEMP.	IMP OUT. FT. TEMP.	VACUUM (IN H ₂ O)
A1	4.91		165	1.3		.31	411.263	76	76	234	63	1.0
A2	4.72		164	1.5		.31	412.8	79	75	245	64	1.0
3	5.18		164	1.8		.31	414.3	80	76	248	64	1.0
4	5.18	+78	165	1.7		.31	415.9	83	76	265	64	1.0
5	5.46		163	1.8		.31	417.5	85	76	268	65	1.0
6	5.46		165	2.0		.31	419.2	85	78	268	66	1.0
7	5.46		164	2.1		.31	420.9	86	79	267	66	1.0
8	5.60		165	2.0		.31	422.6	86	79	271	65	1.0
9	5.46		164	1.9		.31	424.4	87	80	266	64	1.0
10	5.03		162	1.6		.31	426.1	86	80	269	63	1.0
11	4.15		160	1.1		.31	427.7	87	80	265	63	1.0
12	3.70		155	1.1		.31	428.9	86	80	267	64	1.0
B1	5.18	5:39	163	2.0		.31	30.1	81	80	266	64	1.0
2	5.18	5:40	161	2.0		.31	31.7	85	80	262	65	1.0
3	5.46		163	2.0		.31	33.4	86	80	260	65	1.0
4	5.75		163	2.1		.31	35.1	86	80	261	65	1.0
5	5.59		164	2.1		.31	36.9	86	80	269	65	1.0
6	5.46	+92	165	2.0		.31	38.1	86	80	262	64	1.0
7	5.32		164	1.9		.31	40.3	86	80	261	64	1.0
8	5.18		164	1.8		.31	42.0	86	80	269	64	1.0
9	5.18		163	1.8		.31	43.6	86	89	260	64	1.0
10	4.15		161	1.1		.31	45.2	85	89	265	65	1.0
11	3.62		150	1.1		.31	46.5	86	79	262	65	1.0
12	3.47		148	0.60		.31	47.7	86	79	263	66	1.0
		6:40 pm					448.751					
AV	119.85	4.85	161.8	1.651	1.285	.31	37.488		81.73			

APPENDIX D

Thermometer Calibration

Company: Kirby

Calibrated by: S. Barrera

Date: 3/10/97

Barometric Pressure: 29.8

Meter Box #6

Thermometer	Boiling H ₂ O		Ice H ₂ O		%
	Reading	Ref. (Hg Thermo)	Reading	Ref. (Hg Thermo)	
Inlet Kieithley Temp. Meter	210°F		33°F		0.30%
Mercury Glass Therm.		212°F		33°F	0.0%
Outlet Kieithley Temp. Meter	210°F		33%		0.15%
Mercury/ Glass Therm.		211°F		32°F	-0.20%

Boiling

Ice

Boiling

Ice

$$\left(\text{Ref} + 460 \right) - \left(\text{Test Thermo Temp} + 460 \right) 100 = \% \\ \text{Ref} + 460$$

Thermometer Calibration

Company: Kirby

Calibrated by: J. Barrera

Date: 3/10/92

Barometric Pressure: 29.8

Meter Box # 5

Inlet

Outlet

		Boiling H ₂ O		Ice H ₂ O	
Thermometer	Reading	Ref. (Hg Thermo)	Reading	Ref. (Hg Thermo)	%
Kiethley Temp. Meter	209°F		32°F		0.15%
Mercury Glass Therm.		210°F		33°F	0.20%
Kiethley Temp. Meter	209°F		34°F		0.30%
Mercury Glass Therm.		211°F		33°F	-0.20%

Boiling

Ice

Boiling

Ice

$$\left(\text{Ref} + 460 \right) - \left(\text{Test Thermo Temp} + 460 \right) 100 = \% \\ \text{Ref} + 460$$

Thermometer Calibration

Company: Kirby

Calibrated by: J. Barrera

Date: 3/10/92

Barometric Pressure: 29.8

Meter Box # 2

		Boiling H ₂ O		Ice H ₂ O		
Thermometer		Reading	Ref. (Hg Thermo)	Reading	Ref. (Hg Thermo)	%
Inlet	Kiethley Temp. Meter	210		34°F		0.30%
	Mercury Glass Therm.		212°F		33°F	-0.20%
Outlet	Kiethley Temp. Meter	209		33°F		-0.20%
	Mercury Glass Therm.		212°F		32°F	0.45%

$$\frac{(\text{Ref} + 460) - (\text{Test Thermo Temp} + 460)}{\text{Ref} + 460} 100 = \%$$

Thermometer Calibration

Company: Kirby

Calibrated by: J. Barrera

Date: 3/10/92

Barometric Pressure: 29.8

Probe # 1 & 2 Thermocouple

Probe # 1
Thermo-
Couple

Thermometer	Boiling H ₂ O		Ice H ₂ O		%
	Reading	Ref. (Hg Thermo)	Reading	Ref. (Hg Thermo)	
Kiethley Temp. meter	210°F		32°F		0.14%
Mercury Glass Therm.		211°F	33°F		0.20%
Kiethley Temp. Meter	210°F		34°F		0.30%
Mercury Glass Temp.		212°F	33		0.20%

Boiling

Ice

Boiling

Ice

$$\frac{(\text{Ref} + 460) - (\text{Test Thermo Temp} + 460)}{\text{Ref} + 460} 100 = \%$$

SCALE CALIBRATIONS

METTLER AE 163 Digital Scale

Serviced and Calibrated by	
ASC/ALDINGER CO.	
DALLAS, TEXAS 214-827-1200	
Technician	
MARION D. MUEHL	
DATE	SERIAL NO.
12-30-91	E48169
Next Service Due:	
12-92	

OHAUS 147.5 Actual
 " 50.0 Actual
 " 20.0 Actual
 " 10.0 Actual
 " 5.0 Actual
 " 1.0 Actual

Scale wt. = 147.4998g
 Scale wt = 50.0002g
 Scale wt = 20.0000g
 Scale wt = 10.0001g
 Scale wt = 5.0001
 Scale wt = 1.0000g

Sargent Welch model TL 12000-DR

OHAUS 147.5 Actual
 " 295.0 Actual
 " 200.0 Actual

Scale wt = 147.5g
 Scale wt = 295.0g
 Scale wt = 200.1g

Thermometer Calibration

Company: Armstrong Environmental

Calibrated by: M.T.

Date: 2-22-92

Barometric Pressure: 29.8

All readings for Probe 2

Extech Instruments.
K Thermocouple Checker

Boiling H ₂ O			Ice H ₂ O		
Thermometer	Reading	Ref. (Hg Thermo)	Reading	Ref. (Hg Thermo)	%
Kiethley 873F	209°		36°		99.5%
Fluke 51	210°		38°		99%
Mercury Glass		207°		35°	98.5
K-Thermocouple Checker		212°		35°	

K-checker

Mercury

$$\left(\text{Ref} + 460 \right) - \left(\text{Test Thermo Temp} + 460 \right) 100 = \% \\ \text{Ref} + 460$$

Thermometer Calibration

Company: Armstrong Environmental

Calibrated by: M.T.

Date: 2-22-92

Barometric Pressure: 29.8

Probe 1

All reading F°

Extra Instruments
K-Thermocouple Checker

Boiling H ₂ O			Ice H ₂ O		
Thermometer °F	Reading	Ref. (Hg Thermo)	Reading	Ref. (Hg Thermo)	%
Kishly 873 F	209°		36°		98.5% 99%
Fluke 51	210°		38°		99% 99.5%
Mercury Glass		207°		35°	
Co. thermometer		215°		35°	

K-Thermo
Checker
Accuracy




$$\frac{(\text{Ref} + 460) - (\text{Test Thermo Temp} + 460)}{\text{Ref} + 460} \times 100 = \%$$

PITOT TUBE INSPECTION DATA SHEET


Company Name: Armstrong Env

Pre-sample Date 2-24-92

Post Sample Date 3/9/92



DEGREE INDICATING LEVEL POSITION FOR DETERMINING β, THEN CALCULATING γ



DEGREE INDICATING LEVEL POSITION FOR DETERMINING γ, THEN CALCULATING β

✓	level?	✓
NO	obstructions?	None
NO	damaged?	NO
3°	$-10^\circ < \alpha_1 < +10^\circ$	3°
7°	$-10^\circ < \alpha_2 < +10^\circ$	6°
3°	$-5^\circ < \beta_1 < +5^\circ$	3°
1°	$-5^\circ < \beta_2 < +5^\circ$	1°
1°	γ	1°
2°	θ	2°
0.75	A	.76
0.375	$1.05 D_t < P_a < 1.5 D_t$	.38
0.375	$1.05 D_t < P_b < 1.5 D_t$	.34
1/4"	$3/16" \leq D_t \leq 3/8"$	1/4"
0.013	$A \tan \gamma < 0.125"$	0.0133
0.026	$A \tan \theta < 0.03125"$	.0265
yes	$P_a = P_b \pm 0.063"$	yes

Comments: _____

Pitot tube/probe number 2 meets or exceeds all specifications criteria and/or applicable design features* and is hereby assigned a pitot tube calibration factor of 0.84.

Signature [Signature]

Date 2-24-92

*See 40 CFR 50, Vol. 32, No. 160, Method 3. Verify the minimum 2 inch setback of the thermocouple and the minimum 3/4 inch separation between the pitot tube and the nozzle as shown at the top of this page.

[Signature]
3/9/92

PITOT TUBE INSPECTION DATA SHEET


Company Name: Armstrong Env.

Pre-sample


Post Sample

Date 2-24-92

Date 3/9/92




THE IMPACT PRESSURE ORIFICE PLANE OF THE PITOT TUBE SHALL BE EVEN WITH OR ABOVE THE NOZZLE ENTRY PLANE.




DEGREE INDICATING LEVEL POSITION FOR DETERMINING α_1 THEN CALCULATING α_2

DEGREE INDICATING LEVEL POSITION FOR DETERMINING β_1



DEGREE INDICATING LEVEL POSITION FOR DETERMINING γ AND θ



DEGREE INDICATING LEVEL POSITION FOR DETERMINING α_1 AND α_2

Yes	level?	Yes
No	obstructions?	Minor
No	damaged?	Top
0°	$-10^\circ < \alpha_1 < +10^\circ$	-3°
0°	$-10^\circ < \alpha_2 < +10^\circ$	-6°
2°	$-5^\circ < \beta_1 < +5^\circ$	+4°
2°	$-5^\circ < \beta_2 < +5^\circ$	+3°
3°	Y	2°
1°	e	3°
0.625	A	0.562
.313	$1.05 D_t < P_a < 1.5 D_t$	0.28075
.313	$1.05 D_t < P_b < 1.5 D_t$	0.28125
1/4"	$3/16" \leq D_t \leq 3/8"$	✓
0.3275	$A \tan \gamma < 0.125"$	Yes
0.0191	$A \tan \theta < 0.03125"$	Yes
✓	$P_a = P_b \pm 0.063"$	Yes

Comments: Damaged on tip of pitot, circular section

Pitot tube/probe number 1 meets or exceeds all specifications criteria and/or applicable design features* and is hereby assigned a pitot tube calibration factor of 0.84.

Signature [Signature]

Date 2-24-92

*See 40 CFR 60, Vol. 32, No. 160, Method 2. Verify the minimum 2 inch setback of the thermocouple and the minimum 3/4 inch separation between the pitot tube and the nozzle as shown at the top of this page.

SUMMARY OF PRE METER BOX CALIBRATION

METER BOX NUMBER: 5
CALIBRATION DATE: 2/6/92
CALIBRATED BY: DAN BARRERA
BAROMETRIC PRESSURE: 29.6

```
*****
*                                     *
*   DELTA H = ORFICE PRESSURE       *
*   VW = VOLUME OF WET GAS METER    *
*   TW = AVERAGED TEMPERATURE OF WET METER *
*   VD = VOLUME OF DRY GAS METER    *
*   TD = AVERAGED TEMPERATURE OF DRY GAS METER *
*   TIME = DURATION OF EACH POINT RUN *
*                                     *
*****
```

POINT 1

VD = 5.236 TD = 59.5 TIME = 10.309 TEST METER Y = .998
METER BOX Y = .9657782
METER BOX H = 1.148643

POINT 2

VD = 5.309 TD = 64.25 TIME = 7.107 TEST METER Y = 1.003
METER BOX Y = .9638851
METER BOX H = 1.08405

POINT 3

VD = 10.706 TD = 69.5 TIME = 12.261 TEST METER Y = 1.003
METER BOX Y = .9629316
METER BOX H = 1.201441

POINT 4

VD = 10.711 TD = 72.75 TIME = 10.782 TEST METER Y = 1.002
METER BOX Y = .9662285
METER BOX H = 1.231206

POINT 5

VD = 10.579 TD = 76.25 TIME = 8.916001 TEST METER Y = .997
METER BOX Y = .9759559
METER BOX H = 1.258311

POINT 6

VD = 10.562 TD = 78.25 TIME = 7.914 TEST METER Y = .997
METER BOX Y = .9787592
METER BOX H = 1.316927

AVERAGE Y = .9689231
AVERAGE H = 1.206763

Meter Box Calibration

Dry Gas Meter #: 5
 Calibrated by: 03
 Date: 2-6-92
 Barometric Pressure: 29.6

Orifice ΔH	Test Meter Volume V_w	Dry Gas Meter Volume V_d	Temperature				Time e	γ	$\Delta H @$
			Test Meter. T_w	Dry Gas Meter					
				Inlet T_{di}	Outlet T_{do}	Ave T_d			
.5	5	5.236	52	57 65	57 59	59.5	10.309	.998	
1.0	5	5.309	52.5	62 70	62 63	64.25	7.107	1.003	
1.5	10	10.706	53.25	68 77	64 69	69.5	12.261	1.003	
2.0	10	10.711	53.25	73 78	69 71	72.75	10.782	1.002	
3.0	10	10.579	54	75 83	72 75	76.25	8.916	.997	
4.0	10	10.562	54	78 84	75 76	78.25	7.914	.997	

$$\gamma = \frac{V_w P_{bar} (T_d + 460)}{V_d (P_{bar} + \frac{\Delta H}{13.6}) (T_w + 460)}$$

$$\Delta H @ = \frac{0.0317 \Delta H}{P_{bar} (T_d + 460)} \left[\frac{(T_w + 460) \theta}{V_w} \right]^2$$

P_{bar} = Barometric Pressure

DRY GAS METER #: 5

DATE: 2-6-92

ΔH	VW	TW	VD	TDT	TDO	ΔTD	θ
.5(5FT ³)	705.00	52/51	334.069	57	57		
	700.00	53/52	328.833	65	59		10.309
	5	52	5.236		→	59.5	
1.0(5FT ³)	710.00	53/52	339.378	62	62		
	705.00	53/52	334.069	70	63		7.107
	5	52.5	5.309		→	64.25	
1.5(10 FT ³)	720.00	53/53	350.084	68	64		
	710.00	54/53	339.378	77	69		12.261
	10	53.25	10.706		→	69.5	
2.0(10FT ³)	730.00	54/53	360.795	73	69		
	720.00	54/54	350.084	78	71	72.75	10.782
	10	53.25	10.711		→		
3.0(10FT ³)	740.00	54/54	371.374	75	72		
	730.00	54/54	360.795	83	75		8.916
	10	54	10.579		→	76.25	
4.0(10FT ³)	750.00	54/54	381.936	78	75		
	740.00	54/54	371.374	84	76		7.914
	10	54	10.562		→	78.25	

SUMMARY OF POST METER BOX CALIBRATION

METER BOX NUMBER : 5
CALIBRATION DATE: 03/06/92
CALIBRATED BY: Dan barrera
BAROMETRIC PRESSURE (inch Hg): 29.6

*
* DELTA H = ORFICE PRESSURE *
* VW = VOLUME OF WET GAS METER *
* TW = AVERAGED TEEMPERATURE OF WET METER *
* VD = VOLUME OF DRY GAS METER *
* TD = AVERAGED TEMPERATURE OF DRY GAS METER *
* TIME = DURATION OF EACH POINT RUN *
*

POINT 1

DELTA H = 1 VW = 10 TW = 62.25
VD = 10.368 TD = 80.75 TIME = 15.33 TEST METER Y = 1.003
METER BOX Y = .9991864
METER BOX H = 1.26944

POINT 2

DELTA H = 1 VW = 10 TW = 62.25
VD = 10.558 TD = 86 TIME = 15.15 TEST METER Y = 1.003
METER BOX Y = .9907316
METER BOX H = 1.227883

POINT 3

DELTA H = 1 VW = 10 TW = 62.75
VD = 10.658 TD = 91.5 TIME = 15.09 TEST METER Y = 1.003
METER BOX Y = .9903739
METER BOX H = 1.208338

AVERAGE Y = .9934306
AVERAGE H = 1.235221

Post-Test
Meter Box Calibration

Dry Gas Meter #: 5

Calibrated by: DB

Date: 3-6-92

Barometric Pressure: 29.6

Orifice ΔH	Test Meter Volume V _w	Dry Gas Meter Volume V _d	Temperature			Time s	Y	ΔH@
			Test Meter T _w	Dry Gas Meter				
				Inlet T _{di}	Outlet T _{do}	Ave T _d		
1.0	10	10.368	62.25	80 87	78 78	80.75	15.33	1.003
1.0	10	10.558	62.24	83 95	79 87	86	15.15	1.003
1.0	10	10.658	62.75	91 98	86 91	91.5	15.09	1.003

$$Y = \frac{V_w P_{bar} (T_d + 460)}{V_d (P_{bar} + \frac{\Delta H}{13.6}) (T_w + 460)}$$

$$\Delta H@ = \frac{0.0317 \Delta H}{P_{bar} (T_d + 460)} \left[\frac{(T_w + 460) s}{V_w} \right]^2$$

P_{bar} = Barometric Pressure

ARMSTRONG ENVIRONMENTAL, INC.
 DRY GAS METER #: 5

DATE: 3-6-92

ΔH	VW	TW	VD	TDT	TDO	ΔTD	θ
1.0 (10FT ³)	167.0	62/62	580.380	80	78		
	157.0	63/62	570.012	87	78		
	10	62.25	10.368		→	80.75	15:326
1.0 (10FT ³)	177.0	63/62	590.938	83	79		
	167.0	63/62	580.380	95	87		
	10	62.5	10.558		→	86	15:149
1.0 (10FT ³)	187.0	63/62	601.596	91	86		
	177.0	63/63	590.938	98	91		
	10	62.75	10.658		→	91.5	15:091

SUMMARY OF PRE METER BOX CALIBRATION

METER BOX NUMBER: 6
CALIBRATION DATE: 2/12/92
CALIBRATED BY: dan barrera
BAROMETRIC PRESSURE: 28.83

*
* DELTA H = ORFICE PRESSURE *
* VW = VOLUME OF WET GAS METER *
* TW = AVERAGED TEMPERATURE OF WET METER *
* VD = VOLUME OF DRY GAS METER *
* TD = AVERAGED TEMPERATURE OF DRY GAS METER *
* TIME = DURATION OF EACH POINT RUN *

POINT 1

DELTA H = .5 VW = 5 TW = 59
VD = 5.293 TD = 70 TIME = 13.114 TEST METER Y = .998
METER BOX Y = .9615098
METER BOX H = 1.92209

POINT 2

DELTA H = 1 VW = 5 TW = 59.5
VD = 5.278 TD = 75 TIME = 9.279 TEST METER Y = 1.003
METER BOX Y = .9760309
METER BOX H = 1.910268

POINT 3

DELTA H = 1.5 VW = 10 TW = 59.75
VD = 10.573 TD = 79.5 TIME = 15.172 TEST METER Y = 1.003
METER BOX Y = .9809376
METER BOX H = 1.90103

POINT 4

DELTA H = 2 VW = 10 TW = 60
VD = 10.589 TD = 83.25 TIME = 13.219 TEST METER Y = 1.002
METER BOX Y = .9835569
METER BOX H = 1.912708

POINT 5

DELTA H = 3 VW = 10 TW = 60.25
VD = 10.541 TD = 86 TIME = 10.642 TEST METER Y = .997
METER BOX Y = .9851074
METER BOX H = 1.851884

POINT 6

DELTA H = 4 VW = 10 TW = 60.5
VD = 10.48 TD = 84.75 TIME = 9.206001 TEST METER Y = .996
METER BOX Y = .9846149
METER BOX H = 1.853791

AVERAGE Y = .9786262
AVERAGE H = 1.891962

Meter Box Calibration

Dry Gas Meter #: 6
 Calibrated by: DB
 Date: 2-12-92
 Barometric Pressure: 29.83

Orifice ΔH	Test Meter Volume V_w	Dry Gas Meter Volume V_d	Temperature				Time θ	γ	ΔH_0
			Test Meter. T_w	Dry Gas Meter					
				Inlet T_{di}	Outlet T_{do}	Ave T_d			
.5	5	5.293	59	67 77	67 69	70	13.114	.998	
1.0	5	5.278	59.5	72 84	71 84	75	9.279	1.003	
1.5	10	10.573	59.75	77 90	74 77	79.5	15.172	1.003	
2.0	10	10.589	60	82 93	78 80	83.25	13.219	1.002	
3.0	10	10.541	60.25	90 95	78 81	86	10.642	.997	
4.0	10	10.480	60.5	83 95	80 81	84.75	9.206	.996	

$$\gamma = \frac{V_w P_{bar} (T_d + 460)}{V_d (P_{bar} + \frac{\Delta H}{13.6}) (T_w + 460)}$$

$$\Delta H_0 = \frac{0.0317 \Delta H}{P_{bar} (T_d + 460)} \left[\frac{(T_w + 460) \theta}{V_w} \right]^2$$

P_{bar} = Barometric Pressure

ARMSTRONG ENVIRONMENTAL, INC.

DRY GAS METER #: 6

DATE: 2-12-92

ΔH	VW	TW	VD	TDT	TDO	ΔTD	θ
.5(5FT ³)	855.00	59/58	856.597	67	67		
	850.00	60/59	851.304	77	69		13.114
	5	59	5.293		→	70	
1.0(5FT ³)	860.00	60/59	861.875	72	71		
	855.00	60/59	856.597	84	73		9.279
	5	59.5	5.278		→	75	
1.5(10FT ³)	870.00	60/59	872.448	77	74		
	860.00	60/60	861.875	90	77		15.172
	10	59.75	10.573		→	79.5	
2.0(10FT ³)	880.00	60/60	883.037	82	78		
	870.00	60/60	872.448	93	80		13.219
	10	60	10.589		→	83.25	
3.0(10FT ³)	890.00	60/60	893.578	90	78		
	880.00	61/60	883.037	95	81		10.642
	10	60.25	10.541		→	86	
4.0(10FT ³)	900.00	61/60	904.058	83	80		
	890.00	61/60	893.578	95	81		9.206
	10	60.5	10.480		→	84.75	

SUMMARY OF POST METER BOX CALIBRATION

METER BOX NUMBER : 6
CALIBRATION DATE: 03/06/92
CALIBRATED BY: Dan
BAROMETRIC PRESSURE (inch Hg): 29.6

```
*****
*
*      DELTA H = ORFICE PRESSURE
*      VW = VOLUME OF WET GAS METER
*      TW = AVERAGED TEEMPERATURE OF WET METER
*      VD = VOLUME OF DRY GAS METER
*      TD = AVERAGED TEMPERATURE OF DRY GAS METER
*      TIME = DURATION OF EACH POINT RUN
*
*****
```

POINT 1
DELTA H = 1 VW = 10 TW = 59.75
VD = 10.612 TD = 71.75 TIME = 17.69 TEST METER Y = 1.003
METER BOX Y = .9645821
METER BOX H = 1.702569

POINT 2
DELTA H = 1 VW = 10 TW = 60.25
VD = 10.671 TD = 79 TIME = 17.75 TEST METER Y = 1.003
METER BOX Y = .9713931
METER BOX H = 1.694336

POINT 3
DELTA H = 1 VW = 10 TW = 60.5
VD = 10.729 TD = 83.75 TIME = 17.63 TEST METER Y = 1.003
METER BOX Y = .9741879
METER BOX H = 1.658495

AVERAGE Y = .9700543
AVERAGE H = 1.685134

Post-Test
Meter Box Calibration

Dry Gas Meter #: 6

Calibrated by: DB

Date: 3-6-92

Barometric Pressure: 29.6

Orifice ΔH	Test Meter Volume V_w	Dry Gas Meter Volume V_d	Temperature				Time θ	γ	$\Delta H @$
			Test Meter T_w	Dry Gas Meter					
				Inlet T_{di}	Outlet T_{do}	Ave T_d			
1.0	10	10.612	59.75	68 82	66 71	71.75	17.69	1.003	
1.0	10	10.671	60.25	76 89	74 77	79	17.75	1.003	
1.0	10	10.729	60.5	82 92	80 81	83.75	17.63	1.003	

$$\gamma = \frac{V_w P_{bar} (T_d + 460)}{V_d (P_{bar} + \frac{\Delta H}{13.6}) (T_w + 460)}$$

$$\Delta H @ = \frac{0.0317 \Delta H}{P_{bar} (T_d + 460)} \left[\frac{(T_w + 460) \theta}{V_w} \right]^2$$

P_{bar} = Barometric Pressure

DRY GAS METER #: 6

DATE: 3-6-92

ΔH	VW	TW	VD	TDT	TDO	ΔTD	θ
1.0 (10FT ³)	137.0	60/59	379.651	68	66		
	127.0	60/60	369.039	82	71		
	10	59.75	10.612		→	71.75	17.686
1.0 (10FT ³)	147.0	60/60	390.322	76	74		
	137.0	61/60	379.651	89	77		
	10	60.25	10.671		→	79	17.753
1.0 (10FT ³)	157.0	61/60	401.051	82	80		
	147.0	61/60	390.322	92	81		
	10	60.5	10.729		→	83.75	17.625

SUMMARY OF PRE METER BOX CALIBRATION

METER BOX NUMBER: 2
CALIBRATION DATE: 2-7-92
CALIBRATED BY: DAN BARRERA
BAROMETRIC PRESSURE: 29.85

*
* DELTA H = ORFICE PRESSURE *
* VW = VOLUME OF WET GAS METER *
* TW = AVERAGED TEMPERATURE OF WET METER *
* VD = VOLUME OF DRY GAS METER *
* TD = AVERAGED TEMPERATURE OF DRY GAS METER *
* TIME = DURATION OF EACH POINT RUN *

POINT 1

VD = 4.806 TD = 58.75 TIME = 12.804 TEST METER Y = .998
METER BOX Y = 1.053251
METER BOX H = 1.751035

POINT 2

VD = 4.778 TD = 61.25 TIME = 8.991999 TEST METER Y = 1.003
METER BOX Y = 1.069071
METER BOX H = 1.717248

POINT 3

VD = 9.608 TD = 66 TIME = 14.995 TEST METER Y = 1.003
METER BOX Y = 1.070609
METER BOX H = 1.778096

POINT 4

VD = 9.484 TD = 59.5 TIME = 12.982 TEST METER Y = 1.002
METER BOX Y = 1.068302
METER BOX H = 1.800982

POINT 5

VD = 9.448 TD = 64 TIME = 10.477 TEST METER Y = .997
METER BOX Y = 1.07206
METER BOX H = 1.749519

POINT 6

VD = 9.443 TD = 67 TIME = 9.2 TEST METER Y = .996
METER BOX Y = 1.074009
METER BOX H = 1.791957

AVERAGE Y = 1.067884
AVERAGE H = 1.764806

Meter Box Calibration

Dry Gas Meter #: 2

Calibrated by: AB

Date: 2-7-92

Barometric Pressure: 29.85

Orifice ΔH	Test Meter Volume V_w	Dry Gas Meter Volume V_d	Temperature				Time θ	γ	ΔH_B
			Test Meter. T_w	Dry Gas Meter					
				Inlet T_{di}	Outlet T_{do}	Ave T_d			
.5	5	4.801	50.75	55 66	55 59	58.75	12.804	0.998	
1.0	5	4.778	50.5	59 70	57 59	61.25	8.992	1.003	
1.5	10	9.608	51	62 76	60 66	66	14.995	1.003	
2.0	10	9.484	51.25	55 71	54 58	59.5	12.982	1.002	
3.0	10	9.448	52	61 74	58 63	64	10.477	0.997	
4.0	10	9.443	52.5	64 77	63 64	67	9.2	0.996	

$$\gamma = \frac{V_w P_{bar} (T_d + 460)}{V_d (P_{bar} + \frac{\Delta H}{13.6}) (T_w + 460)}$$

$$\Delta H_B = \frac{0.0317 \Delta H}{P_{bar} (T_d + 460)} \left[\frac{(T_w + 460) \theta}{V_w} \right]^2$$

P_{bar} = Barometric Pressure

ARMSTRONG ENVIRONMENTAL, INC.

DRY GAS METER #: 2

DATE: 2-7-92

ΔH	VW	TW	VD	TDT	TDO	ΔTD	θ
.5(5FT ³)	805.00	51/51	176.540	55	55		
	800.00	50/51	171.734	76	59		12.804
	5	50.75	4.806		→	58.75	
1.0(5FT ³)	810.00	50/50	181.318	59	57		
	805.00	51/51	176.540	70	59		8.992
	5	50.5	4.778		→	61.25	
1.5(10FT ³)	820.00	51/51	190.926	62	60		
	810.00	51/51	181.318	76	66		14.995
	10	51	9.608		→	66	
2.0(10FT ³)	830.00	51/51	200.410	55	54		
	820.00	52/52	190.926	71	58		12.982
	10	51.25	9.484		→	59.5	
3.0(10FT ³)	840.00	52/52	209.858	61	58		
	830.00	52/52	200.410	74	63		10.477
	10	52	9.448		→	64	
4.0(10FT ³)	850.00	52/52	219.301	64	63		
	840.00	53/52	209.858	77	64		9.2
	10	52.5	9.443		→	67	

SUMMARY OF PRE METER BOX CALIBRATION

METER BOX NUMBER: 2
CALIBRATION DATE: 3/7/92
CALIBRATED BY: BL
BAROMETRIC PRESSURE: 29.6

*
* DELTA H = ORFICE PRESSURE
* VW = VOLUME OF WET GAS METER
* TW = AVERAGED TEMPERATURE OF WET METER
* VD = VOLUME OF DRY GAS METER
* TD = AVERAGED TEMPERATURE OF DRY GAS METER
* TIME = DURATION OF EACH POINT RUN
*

POINT 1

DELTA H = .5 VW = 5 TW = 79
VD = 5.214 TD = 81 TIME = 12.17 TEST METER Y = .998
METER BOX Y = .9593983
METER BOX H = 1.703566

POINT 2

DELTA H = 1 VW = 5 TW = 79
VD = 5.116 TD = 82 TIME = 8.67 TEST METER Y = 1.003
METER BOX Y = .9832715
METER BOX H = 1.726013

POINT 3

DELTA H = 1.5 VW = 10 TW = 79
VD = 10.43 TD = 84 TIME = 14.17 TEST METER Y = 1.003
METER BOX Y = .9669666
METER BOX H = 1.722571

POINT 4

DELTA H = 2 VW = 10 TW = 79
VD = 10.395 TD = 86 TIME = 12.5 TEST METER Y = 1.002
METER BOX Y = .9716161
METER BOX H = 1.780748

POINT 5

DELTA H = 3 VW = 10 TW = 79
VD = 10.3 TD = 88 TIME = 10.01 TEST METER Y = .997
METER BOX Y = .9768439
METER BOX H = 1.706687

POINT 6

DELTA H = 4 VW = 10 TW = 79
VD = 10.283 TD = 88 TIME = 8.92 TEST METER Y = .996
METER BOX Y = .9750733
METER BOX H = 1.806984

AVERAGE Y = .972195
AVERAGE H = 1.741095

Meter Box Calibration

Dry Gas Meter #: 2

Calibrated by: BL

Date: 3/1/92

Barometric Pressure: 29.6

Orifice ΔH	Test Meter Volume V_w	Dry Gas Meter Volume V_d	Temperature				Time θ	γ	$\Delta H @$
			Test Meter. T_w	Dry Gas Meter					
				Inlet T_{di}	Outlet T_{do}	Ave T_d			
0.5	5.0	5.214	79	82	79	81	12.17	0.998	
1.0	5.0	5.116	79	85	80	82	8.67	1.003	
1.5	10.0	10.43	79	87	82	84	14.17	1.003	
2.0	10.0	10.395	79	89	82	86	12.50	1.002	
3.0	10.0	10.300	79	93	82	88	10.01	0.997	
4.0	10.0	10.283	79	94	82	88	8.92	0.996	

$$\gamma = \frac{V_w P_{bar} (T_d + 460)}{V_d (P_{bar} + \frac{\Delta H}{13.6}) (T_w + 460)}$$

$$\Delta H @ = \frac{0.0317 \Delta H}{P_{bar} (T_d + 460)} \left[\frac{(T_w + 460) \theta}{V_w} \right]^2$$

P_{bar} = Barometric Pressure

DRY GAS METER #: 2

DATE: 3/7/92

ΔH	VW	TW	VD	TDT	TDO	ΔTD	θ
.5(5FT ³)	244.0	80/78	631.695	79	78		
	249.0	80/78	636.909	84	80	1	12.17
	5.0	79	5.214	82	79	81	
1.0(5FT ³)	249.0	80/72	636.909	81	79		
	254.0	80/72	642.075	89	82		8.57
	5.0	79	5.166	85	80	82	
1.5(10FT ³)	254.0	80/72	642.075	82	80		
	264.0	80/72	652.505	92	83		14.77
	10.0	79	10.43	87	82	84	
2.0(10FT ³)	264.0	80/72	652.505	84	80		
	274.0	80/72	662.900	94	84		12.50
	10.0	79	10.395	89	82		
3.0(10FT ³)	274.0	80/72	662.900	84	81		
	284.0	80/72	673.200	102	84		10.01
	10.0	79	10.300	93	82	84	
4.0(10FT ³)	284.0	80/72	673.200	85	81		
	294.0	80/72	683.483	103	84		8.92
	10.0	79	10.283	94	82		

APPENDIX E

FAX NO. (214) 905-0634

CHAIN OF CUSTODY RECORD

Name of Unit and Address:			Number of Containers	Tag Numbers	Analyses Required			Remarks
Sample Number	Date Sampled	Time Sampled			Description of Samples	Particle Size	Wet/Dry	
1-S1	3/5	9:30	R1 Dryer 1 Filter	3/5/92				
2-S1	"	"	R1 Dryer 1 Pw					
3-S1	"	"	R1 Dryer 1 Cyclone					
4-S1	"	"	R1 Dryer 1 Impingers					
5-S1	"	"	R1 Dryer 1 SG					
6-S1	3/5	12:20	R2 Dryer 1 Filter					
7-S1	"	"	R2 Dryer 1 Pw					
8-S1	"	"	R2 Dryer 1 Cyclone					
9-S1	"	"	R2 Dryer 1 Imps					
10-S1	"	"	R2 Dryer 1 SG					
Relinquished by: (Signature)			Date		Time		Received by: (Signature)	
<i>[Signature]</i>			3/5/92					
Relinquished by: (Signature)			Date		Time		Received by: (Signature)	
Relinquished by: (Signature)			Date		Time		Received for Laboratory by: (Sig.)	

Distribution: Original Accompanies Shipment
 Copy to Client/Project Coordinator

DALLAS, TX 75247 CHAIN OF CUSTODY RECORD

Name of Unit and Address:			Number of Containers	Tag Numbers	Analyses Required			Remarks
Sample Number	Date Sampled	Time Sampled			Description of Samples	Technical Analysis	Sample Tag Verification	
Kirby Forest Products Silsbee, TX								
1-52	3/5	9:30	R1 Dryer 2 Filter 3/5/92		+			
2-52	"	"	R1 Dryer 2 PW		+			
3-52	"	"	R1 Dryer 2 Cyclone		+			
4-52	"	"	R1 Dryer 2 Imps		+			
5-52	"	"	R1 Dryer 2 SG			X		
6-52	"	12:20	R2 Dryer 2 Filter		+			
7-52	"	"	R2 Dryer 2 PW		+			
8-52	"	"	R2 Dryer 2 Cyclone		+			
9-52	"	"	R2 Dryer 2 Imps		+			
10-52	"	"	R2 Dryer 2 SG			X		
Relinquished by: (Signature)			Relinquished by: (Signature)		Date	Time	Received by: (Signature)	
<i>[Signature]</i>					3/5/92			
Relinquished by: (Signature)			Relinquished by: (Signature)		Date	Time	Received by: (Signature)	
Relinquished by: (Signature)			Received for Laboratory by: (Sig.)		Date	Time	Remarks	

DALLAS, TX 75247 CHAIN OF CUSTODY RECORD

Name of Unit and Address: Kirby Forest Products Silsbee, TX			Number of Containers		Tag Numbers		Analyses Required		Remarks	
Sample Number	Date Sampled	Time Sampled	Description of Samples							
11-51	3/5		R3 Filter Dryer #1							
12-51	"		R3 Pw Dryer #1							
13-51	"		R3 Cyclone Dryer #1							
14-51	"		R3 Impingers Dryer #1							
15-51	"		R3 SG Dryer #1							
11-52	"		R3 Filter Dryer #2							
12-52	"		R3 Pw Dryer #2							
13-52	"		R3 Cyclone Dryer #2							
14-52	"		R3 Impingers Dryer #2							
15-52	"		R3 SG Dryer #2							
Relinquished by: (Signature)			Date	Time	Received by: (Signature)		Date	Time	Received by: (Signature)	
			3/5/92							
Relinquished by: (Signature)			Date	Time	Received by: (Signature)		Date	Time	Received by: (Signature)	
Relinquished by: (Signature)			Date	Time	Received for Laboratory by: (Sig.)		Date	Time	Remarks	

ARMSTRONG ENVIRONMENTAL, INC.

4747 IRVING BLVD. #204

PHONE NO. (214) 631-0021

FAX NO. (214) 905-0634

DALLAS, TX 75247 CHAIN OF CUSTODY RECORD

Name of Unit and Address:

Kirby Forest Products
Silsbee, TX

Name of Unit and Address:			Number of Containers	Tag Numbers	Analyses Required			Remarks
Sample Number	Date Sampled	Time Sampled			Description of Samples	Particle Weight	Sample Tag Verification	
1-33	3/3/92	9:10 AM	R1 Dryer 3, Filter	1	1-33	X		
2-33	"	"	R1 Dryer 3, Probe Wash	1	2-33	X		
3-33	"	"	R1 Dryer 3, Cyclone Wash	1	3-33	X		
4-33	"	"	R1 Dryer 3, Imps 1&2	1	4-33	X		
5-33	"	"	R1 Dryer 3, Silica Gel	1	5-33	X		
6-33	"	11:37 AM	R2 Dryer 3, Filter	1	6-33	X		
7-33	"	"	R2 Dryer 3, Probe Wash	1	7-33	X		
8-33	"	"	R2 Dryer 3, Cyclone Wash	1	8-33	X		
9-33	"	"	R2 Dryer 3, Imps 1&2	1	9-33	X		
10-33	"	"	R2 Dryer 3, Silica Gel	1	10-33	X		
Relinquished by: (Signature)			Date	Time	Received by: (Signature)		Date	Time
Du. D. Baim			3/3/92					
Relinquished by: (Signature)			Date	Time	Received by: (Signature)		Date	Time
Relinquished by: (Signature)			Date	Time	Received for Laboratory by: (Sig.)		Date	Time

Distribution: Original Accompanies Shipment
Copy to Client/Project Coordinator

[illegible]

**Distribution: Original Accompanies Shipment
Copy to Client/Project Coordinator**

CHAIN OF CUSTODY RECORD

Name of Unit and Address:			Description of Samples	Number of Containers	Tag Numbers	Analyses Required			Remarks
Sample Number	Date Sampled	Time Sampled				Particle Weight	Sample Tag Verification	Remarks	
1-24	3/2/92	10:54 AM	R1 Dryer 4, Filter	1	1-24	X			
2-24	"	"	R1 Dryer 4, Probe Wash	1	2-24	X			
3-24	"	"	R1 Dryer 4, Cyclone Wash	1	3-24	X			
4-24	"	"	R1 Dryer 4, Imps 162	1	4-24	X			
5-24	"	"	R1 Dryer 4, Silica Gel	1	5-24	X			
6-24	"	2:25 PM	R2 Dryer 4, Filter	1	6-24	X			
7-24	"	"	R2 Dryer 4, Probe Wash	1	7-24	X			
8-24	"	"	R2 Dryer 4, Cyclone Wash	1	8-24	X			
9-24	"	"	R2 Dryer 4, Imps 162	1	9-24	X			
10-24	"	"	R2 Dryer 4, Silica Gel	1	10-24	X			
Relinquished by: (Signature)			Date	Time	Received by: (Signature)	Date	Time	Received by: (Signature)	
Relinquished by: (Signature)			Date	Time	Received by: (Signature)	Date	Time	Received by: (Signature)	
Relinquished by: (Signature)			Date	Time	Received for Laboratory by: (Sig)	Date	Time	Remarks	

Name of Unit and Address:

Kirby Forest Products
Silsbee, TX

Sample Number	Date Sampled	Time Sampled	Description of Samples	Number of Containers	Tag Numbers	Analyses Required			Remarks
						Particle Size	Weight	Sample Tag Verification	
1-25	3/2/02		R1 Dryer S, Filter	1		X			
2-25	"		R1 Dryer S, Probe Wash	1		X			
3-25	"		R1 Dryer S, Cyclone Wash	1		X			
4-25	"		R1 Dryer S, Imps 162	1		X			
5-25	"		R1 Dryer S, Silica Gel	1		X			
6-25	"		R2 Dryer S, Filter	1		X			
7-25	"		R2 Dryer S, Probe Wash	1		X			
8-25	"		R2 Dryer S, Cyclone Wash	1		X			
9-25	"		R2 Dryer S, Imps 162	1		X			
10-25	"		R2 Dryer S, Silica Gel	1		X			
Relinquished by: (Signature)					Relinquished by: (Signature)		Date	Time	Received by: (Signature)
<i>[Signature]</i>									
Relinquished by: (Signature)					Relinquished by: (Signature)		Date	Time	Received by: (Signature)
Relinquished by: (Signature)					Relinquished by: (Signature)		Date	Time	Received by: (Signature)

CHAIN OF CUSTODY RECORD

Name of Unit and Address:			Number of Containers	Tag Numbers	Analyses Required			Remarks
Sample Number	Date Sampled	Time Sampled			Description of Samples	Particle Weight	Sample Tag Verification	
Kirby Forest Products Silsboe, TX								
11-24	3/26/02		R3 Dryer 4, Filter	1	11-24	X		
12-24	"		R3 Dryer 4, Probe Wash	1	12-24	X		
13-24	"		R3 Dryer 4, Cyclone Wash	1	13-24	X		
14-24	"		R3 Dryer 4, Imps 162	1	14-24	X		
15-24	"		R3 Dryer 4, Silica Gel	1	15-24	X		
11-25	3/26/02		R3 Dryer 5, Filter	1	11-25	X		
12-25	"		R3 Dryer 5, Probe Wash	1	12-25	X		
13-25	"		R3 Dryer 5, Cyclone Wash	1	13-25	X		
14-25	"		R3 Dryer 5, Imps 162	1	14-25	X		
15-25	"		R3 Dryer 5, Silica Gel	1	15-25	X		
Relinquished by: (Signature)			Date	Time	Received by: (Signature)	Date	Time	Received by: (Signature)
<i>Joe D. Bann</i>								
Relinquished by: (Signature)			Date	Time	Received by: (Signature)	Date	Time	Received by: (Signature)
Relinquished by: (Signature)			Date	Time	Received for Laboratory by: (Sig)	Date	Time	Remarks

Enforcement Sensitive - Do NOT
Release for FOIA Request
(Entire Book)

At Nugent, MRI

(86) 753-7600
X 142 Voice Mail
box X 808



56-401	Ginger	Record
56-402	Black	2 Cols.
56-403	Red	3 Cols.
56-404	Blue	4 Cols.
56-406	Green	6 Cols.
56-408	Chestnut	8 Cols.
56-412	Maroon	12 Cols.
56-431	Black	S.E. Led.
56-441	Red	Cash

Made in U.S.A.

80 Pages
236-5139 11-21-80 at QD Bander
5124 R/L Jindly

NAC (303)

11-21-80
236-5139
QD Bander

51/5000 for (Kilby)

07 1022

Look at
inlet from sec. - 1000 ft. - 1000 ft.
old. 1000 ft. - 1000 ft. - 1000 ft.
Viny. etc.



Estimate, end of 1000 ft.



Phil Schmitt
(214) 341 6746
Firm (214) 340-0057

86-737-7600
547

2560 = 15%
1680

Good for
- det. test
METCO Env
Dadde
(214) 341-7729
pro Phil Schmitt
Cue P. 1000 ft. 1000 ft.

16.1
12
330
165
1980 72/4
14 1/2
192

304 Silsbee

Plant has
PV number
as follows

1000 ft. 1000 ft.
1000 ft. 1000 ft.

05 02 01
04 03

lbs = Tons FFX 2000/16.5
Dryer fir. = 1-0.22

07 1102

37.7 fine

25, not

5 upst
and time when
- was in a dig bin

make board

o dryer

+ temp of

-)

the time, same

see wide

vigan,

own

not

nd wet


to run as

ch Vaughn

5239

q -

47 1024



exhaust
air vent for pressurants
(on top of roof - temporary
exhaust stack)

baffles for evening out flow

(*)
(?)

Man were cleaning out Multichlor just
before tests. Danny Russell of EML said VOCs are
down after cleaning of Multichlor. When doing more
VOCs and particles get through
problems with Dryer #1 fan (just before
test - MEC came to inspect)

(*)

of MEC said water was in fan - couldn't run
they should drain it out
One of Dr. Boswell's friends died - he had to
set up funeral arrangements and his visit to
site was delayed.

Danny Russell of EML said Method 25A
sample line would be kept at 260°F
(while stack was at 160-180°F) in order
to prevent ^{VOCs} moisture from condensing out.

Danny
switched to
3 holes for
P.V.

Also said 25A would be done with only one
sample hole in probe which would be
located in a central position. They can't
do both VOC and PM (2 probes) at same time.

Laroni
said →

(except for pressurants, where we used 3 holes due to complex flow)

Declar (919) 541-~~5571~~ ~~5571~~ 5371

Seifert

to get variance on standard methods.

He must approve before test modification.

07 1025

Dallas said to talk to Ed McCauley
(919) 541-5546

Ed said most of VOC would be in
gaseous phase and would be
distributed OK. He said to have test
team check proposed sample point
against velocity profile and to
go ahead if it looked OK.

(*)?

Test at Sitstern

9-24/26/91

VOC

lbs/hr.
ppm

	1	2	3	4	5
lbs/hr.	21.5	22.7	25.4	29.7	27.1
ppm	316	344	380	388	359

Intally

7.8-8.6%

Ed Knight

CO

lbs/hr.
ppm

	1	2	3	4	5
lbs/hr.	4.18	2.4	4.96	1.68	1.04
ppm	31	18	37	10.8	6.8

1360T

dry
max design
per MEC

48 acfm

48000 acfm 48K 48K 48K 48K

Stack temp 194°F

197 186 177 179 175

Velocity heads

Constant deciphers from reports

operating conditions during test

dry temp averaged 708°F

No production monitored during tests.

07 1026

Incoming sheet

log

he is
d he
have test
pile point
and to

at 4:00 pm all stacks operating and test
equipment in calibration. Flow out of stacks

looks cyclonic
as it exits

Mike Hudson

of MEC

(7)?

probably too far
downstream to adequately
effect flow
in stack.

Said there is vortex at
very top of stack to create
this flow so that company
can tell flow is proper.

Test Run #1 start 4:15 pm

before
Drybins (1) $3/4 - 5/6$ full
(2) ~~full~~ $5/6$

Control Console
said both on
"mid" full

9.7 27.1

initially

88 359

7.8 - 9.2
8.6%

Moisture 5-6% (chart) Digital said 6.3

40% opacity

non
ed knight

Inlet temp 800 - 860°F

168 1.04

10.8 6.8

14-15 ma air demand → corresponds to about
45000 cfm air flow through dryer

Cycle time

into press

next load into press

6.5 min for the
23/32" board being
made.

48K 48K

press temp 417°F in → 425°F out

179 175

9.5 press loads/hr. according to press operator

($7/16$ " board would be about double this
press production.) (actually 16 p.l./hr. for $7/16$)

Density of board 41.6 lbs/ft³

7 1026

Increasing wet moisture of wafers on 9/24/92 was

07 1027

NOI
wafers 540.2%
542.6%
NO 549.4
wafers 47.0
13%

76

(*)

It's better to use dryer dump than weight of finished product, because

(Per Ed Knight) ~ 4 hrs time between dryer production and time ^{waters} dryer gets to press, (due to size of dry bins)

Board size vs % moisture - typical period:

65%	is	7/16"	(most of FP is this size)
20%		15/32"	
5%		23/32"	
10%		3/8" - 1/4"	

going to run either 7/16 or 15/32 for most of rest of weeks

Not dryer

Plant actually run at $> 105 \text{ mm}^2/\text{day}$ on 2/13 and 2/14/92, according to chart on wall in QA lab

Corresponds to about $383 \text{ mm}^2/\text{day}$ density of board

digital and strip chart don't agree

Start of Run #2 Days #1

$T \sim 750^\circ\text{F}$ per S.C.

moisture

Went up to 800°F and stayed fairly level

Operating 31% - 29% - 32%

Per Ed Knight

OUTlet ~ 200°F - 200 - 200

7500
11600

17820
13040
780

(*)

(*)

Can't trust strip charts or digital read out on moisture. They pull ^{grab} sample to check every hour

No. 1 dryer moisture 8.6 - 7.8% during test #1 - recorded in log books every hour. according to these pulled samples

Air demand run #2 dry 14-18 m.c.h

Moisture dry #1 run #2 6.8% 07 1028

T-O

(*)

weight of

action

(2 of dry bins)

ing to run
the 7/16 on
5/32 for
most of rest
of weeks

digital and
strip chart
don't agree

8 on Digital
5 on chart
not fairly
level

out on
every hour
using test

17 1028

To determine #/hr.

Dryer #1

16.4

16.8

15.6

48.8

16...

avg for

dryer #1

1

~ 16,000

lbs/hr

Five Dump Samplers to determine dryer
dry furnish rate

No. 1 ^{top} for Roswell - after 1st run -

dryer 840 lbs $\xrightarrow{3 \text{ min}}$ 16,800 lbs/hr

2/23
(P)

My observation of dump during at end of
2nd run

780 lbs = 15,600 lbs
3 min hr.

780
20
1,600

Swept up flakes that missed and put them
in trench, too.

Covered flakes with tarp to keep dry on way
to scales.

17820

13040

13820

780

observation by Al Bander

Run #2 VOC voided by Denny Russell

(*)

- said he forgot and removed cap from
line and pulled in ambient air - Al
Bander thought he moved probe to a different
position in stack - VOC was at
60 ppm (low).

T-O ~~Flows~~ not Venting Through stack - it's

(*)

going straight to atmosphere per
dryer operator (8 pm). Problem with dryer ->
for Roswell 07 1029

"This is the way we normally run" per console
operator in dryer room - we asked 2 of them on different
shifts and they replied the same way.

Run #3

Opacity 26% ~

Trillet = ~ 775°F → 850°F

Air demand 1515 ma

Opacity 30

Went with truck to get another empty wt of truck
tare weight was 13066 (compared to 13840
earlier)

Driver feed drive belt running at ~ 22
all during test runs 1 → 3

Board thickness check - 1 5/32 board
wt

$$\frac{51.165 \times 12 \frac{\text{in}}{\text{ft}}}{32.782 \times .444 \frac{\text{in}}{\text{lb}}} = 43.07 \frac{\text{lb}}{\text{ft}^2}$$

Slab production from display on side of QA Lab;

Shift	Run	Footage WTD	MTD	DownTime
SHIPT	Run-25192			
A	505536	505536	5,004,096	0
B	497472	497472	5,668,416	67 min
C	900288	900288	5,730,048	19
D	1,037,952	1,037,952	22,198,656	15
TOT	2,941,248	2,941,248	22,198,656	95

$$22,198,656 \text{ ft}^2 \times .03125 \text{ ft} \times 42 \frac{\text{lb}}{\text{ft}^2} \times \frac{\text{ton}}{2000 \text{ lb}} = 14568 \text{ tons}$$

in 23 days = 633 tons per day and 26.4 tons/hr. 07 1030

1/2 wks → 0

yes 0

How do you
AI Bunker
- its even
across the

2/25/92 →

Book

J. B. Bunker
Paw 107
Pinewood
Inn

all the time
before our
visit

1/2 wks

Thinner board (18/32") seems to
create more emissions off press than
thicker board 27/32"

kg wt of thick
13840

Press Fans (Hous) are either on or off - Only
light on front press console shows
whether they are on or off.

- 22

For tomorrow

(*) Dryer burners cleaned every wk
Now expect beds twice / wk

1/2 wks

Check cleaning frequency of multiclones
(are they doing it on dryer # or #3 today?)

yes

Katie's working? - Going through dryer #1 and 2?
(which is Danny testing?)

27 163
pg 3

How do you
AI Bender
- its even
across dia

What is AP across dryer #1 (and other stacks)?
(Record it)

QA Lab;

2/25/92

Lorrie said to tell Jim Bushwell:

DownTime

(1) Don't clean multiclones or other equipment
just before test

096 0

416 67 min

048 19

656 15

656 95

Book
J. Bushwell
Rm 107
Pinewood
Inn

all the time
before our
visit

(2) Return dryer #1 test when
Konus is being exhausted
through dryer

(3) J. Bushwell should call Lorrie if he has
any questions. (703) 308-8718

(4) how often do they have ^{MEC T-8} Thomas by pass
dryer?

ton = 14568
165 tons

1/2 wks

(5) how often do they clean multiclones?

1 hr. 07 1030

07 1031

(*) Danny Russell told Al that he didn't do isokinetic determination on the spot ~~just~~ to see if he was in the ballpark. He will still do isokinetic calculations in full during data reductions. He's trusting that 9/91 test conditions were about the same as what this test would be.

(*) Multimedia concern - when they clean out Multiclave they discharge resinous sludge to unpaved lot in side yard - near wood chip piles and fire dump log pile. VOCs in soil? probably should check.

(*) Dryer Console operator on 9/24 told Rich Ida that they "normally ^{T-O} by-pass dryer for the Komers" (2nd operator that has to do this) but that now they had been told to always put Komers through dryer.
- Incoming wet wafer moisture on Am 9/25/92

47% and 44% at 8:25 AM

Running 7/16" at 10 AM 9/25/92 - will probably switch to 15/32" later.

07 1032

(*) 6

We = Al Night al
and Rich loc
Ida (*)

Kom

44

st

(*)

also

c

c

4

c

1

1

c

5

(*)

30

the
ation on
is the
skinner
to
ing that
bout
or would

We = Al Noyt
and Rich
Ila

(*) Al Bauder said There is about as much
visible emissions coming out of peak of roof
as there is out of press vents. The emissions
out of roof peak, according to Al B, are
about as much as another roof vent. (We took a
look from 500 yds away and concluded the same)

(*) Korus Vent to atmosphere — even when
Korus vents to dryer, There is
Korus exhaust coming directly to atmosphere.
What is lost through dampers is we don't
know. Later — it's minor per Al Bauder except
when dampers to dryers are closed.

(*) Couldn't run H₂O test on 9/25 —
Lab that mixed DPHH mixed liters
not ml of reagent. Will hopefully
be ready for H₂O test on 9/26.

As of 10 AM Boswell had not been able to reach
Laxmi — Boswell said they would test on
dryer #2 with Korus venting through
dryers 1 and 2. They would also do
velocity / air flow on Korus outlet to
dryers to try to convince us that flow
was equal from Korus to both dryers.
Boswell said he would test dryer #1
again if he had to. Laxmi at 10:30 AM
said he would call Boswell right now.

(*) Operators are reading temperature chart
to 10⁵ million ~~to~~ divisions are in
30 ~~of~~ increments (Training needed?)
See later notes Some read digital, some read
strip charts.

07 1032

07 1033

Larini wants press vests to collect
all emissions from press. Said he
would tell Boswell that. (I did, since
Larini/Boswell could not reach each other by noon).

- (*) Dryer #3 was operating consistently at
50-60% opacity 9-10 AM when we
were looking at them.
Control room operator didn't know
why and didn't know why opacity
monitors were on console.
(lack of training?)

Dryer was operating at high opacity
levels even though gas was being
used as the fuel.

(What is state / SIP limit?) 20%

Testing starting on dryer #2. Opacity
looks high on dryers 2-5 at
1:30pm and looks lower on
dryer #1 stack.

[1:30pm] → test on #2 dryer just started for Ed Knight

Phone conversation Laxmi Karsni / Jim Boswell

(As report could only list and try to summarize below)

① Kirby will have dryer #1 restarted with hoses venting through dryers 1 and 2.

② Concerning emissions out of roof (instead of out of press vents). Boswell thinks they're insignificant and he has no feasible way of enclosing roof vents to prevent emissions.

Laxmi told Boswell to close off 30% of roof vent on either side of press.

Boswell said ok. He will do that.

Re:

③ Schedule of testing

— Hold off on all PM-10 until end of TSP, CO, VOC testing on all dryers.
Laxmi said ok.

④ Re ultimate end of schedule (3/31).

Intergall can't make it
Pace might be able to.

Alliance might be able to. (TRC subsidiary)
Laxmi said ok to use more test
cells, just use same test methods.

Laxmi to make Clayton test

Holiday Inn - Eufala is place
to stay. Plant is on White Oak
Station Rd (right turn coming from
Columbus GA).

7 1034

07 1035

Check on dryer dump to determine lbs/hr

13,880 full (3 min wt) at start of
13,060 tare wt 1st run of
day.

820 lbs

820 lbs * 20 3-min periods
3 min dump hr

820
20
16400

= 16,400 lbs/hr

WHAT DUMPER??

1st run of day moisture 7.5% at 2pm
3 party 46%

Shift A Chr
Shift B Kai

(*) Get Dryer Report for each dryer for
wk before and during tests to see if
They can test under different conditions
This did not occur after we discussed it with them.
Looks to us like dryer that is being
tested is being run at lower
inlet feed speed.

Forming,
(*) Press / Loading / drying takes place over
200 yds? A lot of VCs are in air in
150
this area that do not get pulled through
press vents by the Vent fans. They go out roof
Monitor 07 1036

3/hr

test of
run of
1/2

ids

9/25/92 #2 and #3
Rem #1-VOC

Ad B. vertical probe
off on side for last half of run
also it was pointed upwards R1 to
call Dallas Seifert / Ed McCarley
if those conditions are ok. - He checked, and
they said ok - don't worry.

Bond density 42-43 $\frac{16.5}{43}$ at 3 pm
probably corresponds to 1st run of day.

at 2 pm

(*)

$$32 \text{ ft}^2 \times \frac{19}{32} \times \frac{14}{12 \text{ ft}} \times 42 \frac{16.5}{43} =$$

Shift A Chris Hare - drop of console
Shift B Keith Ruggles - " "

Chris says he was
told yesterday to
run Rems through
drop until further
notice

for
of
conditions

Dryer #2 Rem #1 - inlet $\nabla \rightarrow$ 770-800

being

Rem #2 - about the same
Operating 32
Moisture 8% at 4 pm

over

end of run #2 dryer #2
Operating 26%
inlet ~ 800°F

air in
rough

inlet moisture 45% #1 defrizer
42.5% #2 defrizer

go out roof

outlet moisture 7%

17 1036

3801

07 1037

MECH
test

They closed louvers in roof monitors to some 50 ft on either side of press. I couldn't see any ^{significant} difference with emissions. Boswell / Nugent / Ido decided to go with this arrangement for press vent tests, but to realize we will have to estimate fugitive VOC (and other gaseous) discharges when we evaluate press vent emissions. Boswell may ask Danny Russell to try to sample ~~monitor~~ along the press monitor louvers to get a handle on this. Nugent / Ido / Boswell guess that fugitives may equal emissions from one of the press vents (crude quora). Radius of effectiveness of fans is not that great - can't seem to pull in many fugitives anyway. Would have to completely enclose ^{press area} and use the large fans to capture much of those fugitives.

Density - 42 41.7 43.7 ~~44.7~~
2-5pm 2/25/92

⑥ Al - call Rich - find out what permit ²⁰⁹⁰ application says for fugitive losses. ^{including} ^{under} ^{vent}

Check near end of run #3 - Dry #2
opacities 32, inlet temp = 800°F

07 1038

MEC reps were present during entire
test period.

Service reps of
Dryer Co.
MEC

tons to some
couldn't
Bismell/
arrangement
e we
- (and
e

Mike Hudson

Then Mike Weintraub

Advice to CP to minimize pollution

- Run steady - one ramp with not
much variation

- They say Sitsber has been running
pretty steady since startup.

- also, if you run steady
you notice changes and can
correct based on those changes
if you have

- Leakage (gradual) of air flow
through dryer - need higher
inlet temp to dry same moisture
cause seals load. - change twice
per year is standard
MEC gives them instructions and
checklist for maintenance.

generally, 0.5 miles hour

- Humboldt mortality - run all out

production - just getting up to speed
on sophistication of equipment in
OSD mills. - Lot of people come from
lumber background - not familiar with tight
environmental or process controls.

- he thinks They could show in real-time,
using a PID, how much VOC is
reduced by low temp drying

permit

2090
less 8. include
unloader
Vent

#2

17

7 1038

850

07 1039

- 5471

For ^{web} ~~Flows~~ - Find out: - frequency of cleanup of multiclone

Nothing
specific
according
to them.

- What MEC has told us to do,
anything specific which
may have led to lower
emissions?

has not started
→ 8:30am

seen
low
time

To do
wouldn't be
worth it
Test method
doubtful with
no smoke.

- Tell Danny if he's going to
do a roof monitor traverse,
it should include
a press maximum emission
cycle or two (with
roof monitor louvers
open).

acc
ho
de
dr

Ed
copying
we
handle

- get dryer report for 9/23/92
from Ed Knight
(see if belt drive
rates - input to dryers
- were same before tests)

⊗

To do
Business must read
as part of it

- See if I can get production
records (TSP, lbs/hr dryers,
inlet temp) for 9/24-9/26/91
from Ed Knight.

During witness
tests we
couldn't see
reasons for
change in
capacity.

Yps for Hecto
one points m
probe for vac

- make sure they're doing traverses
across process vents - not just
one point

07 1040

- talk to Laroni about
getting lbs/hr at beginning
and end of a test instead
of beginning and end of each
run.

map of multilayers

Run #1 Dryer #3

9/26/92 Wed.

2 up to 20,
- which
to lower

has not started ps of

→ 8:30am Press running 7/16" board
seems to be more change in bldg. (regulator
lowers closed and 7/16" has faster cycle
time) Running ~ 15 press loads/hr
according to press chart (press chart is 24
hour chart - 6 → 8 on chart = 1 hour
density 42-44 usually 43 for 15/32" board.

he's going to
near traverse,
lude
in emission
- (with
lowers

Dryer #3 ~ 800 → 820°F 9% moisture (800)
feed rate 27 opacity 27%

nt for 9/23/92
night
to drive
it to dryers
before tests)

⊗ Dryer operator didn't know of any point at
which an opacity reading should be reported
to supervisors (This is 3rd operator who had
similar comment) Operator: Calvin W, Freeman
Calvin G. (from log).

production
if dryers,
9/24-9/26/91

During witness
tests we
couldn't see
reasons for
change in
opacity.

Both Core Dryers (1 and 2) now higher in opacity
[38-40%] than the three face dryers (3, 4, and
5) [27-32%]. This is the reverse of what
we saw on 9/25 and 9/26 when we were
testing dryers 1 and 2. - in 3rd and 4th
3rd run operator did switch somewhat,
however.

long traverse
- Not just
7-1040
bout
beginning
- instead
of each

#1 ~ 9:15am
Dryer #3 test began - Stack velocity less at
center than between edge and center of
stack. At random to full E.M.T. sample
1/2 way between center and edge. (Dryer #2 was
done in center. (Factor changed to three holes
in probe)

07 1041

800-830°F

10:15 AM near end of 1st run on dryer #3

inlet T $\approx$ ~~270°F~~ (went down from 820°F - 840°F at about start of the run)

Operating 26% (but other driers went down in Temp) line speed $\approx$ 27 Moisture 9%

⊗

Dryer #3 shows more variability than the other driers according to Mike Weindorfer of MEC - might need electrical adjustment (by L-1 electrician)

11 AM - Still doing 16 press loads/hr. of 7/16" board.

$$\frac{16 \text{ press loads}}{\text{hr}} \times 12 \times 24 \times 8 \times \left(\frac{7/16}{12}\right) \text{ ft}^3 \times \frac{43 \text{ lbs}}{\text{ft}^3} \times \frac{1 \text{ ton}}{2000 \text{ lbs}} = 28.9 \frac{\text{tons}}{\text{hr}}$$

$$\begin{array}{r} 292.576 \\ \times 0.0646 \\ \hline \end{array}$$

Compared to dry production of 5 driers $\times 15,000 \frac{\text{lbs}}{\text{hr}} \times \frac{1 \text{ ton}}{2000 \text{ lbs}}$
 $= 38.5 \text{ tons/hr. } (0.15 \times 38.5 = 5.8)$
 without loss ~~44.3~~ tons/hr
 with 32.7

⊗

Why so big a difference? Even with 15% loss

$$\begin{array}{r} 38.5 \\ - 5.8 \\ \hline 32.7 \end{array}$$

press ~~32.7~~ tons/hr. with no loss
 5 driers 32.7 tons/hr.

Some driers must be operating well under (water) 15,000 lbs/hr. (probably, have high blow losses)

Dry bins both about mid-full for the run on dryer #3 (before and after)

Dry

$$\begin{array}{r} 2 \\ 14 \\ 14 \\ 14 \\ 14 \\ \hline 574 \\ 15.1 \end{array}$$

$$\begin{array}{r} 700 \\ 20 \\ \hline 14200 \end{array}$$

$$\begin{array}{r} 7400 \\ 4800 \\ \hline \end{array}$$

$$\begin{array}{r} 65600 \\ 600 \\ \hline \end{array}$$

fuel feed

ger #3

2/26

11:15 AM new truckload of wafers to be weighed for dryer production determination

Dryer #3 dumps

store 9%

2
14
14
14
14

13760	13800	13820	13820
13080	13100	13080	13080
<u>680</u>	<u>700</u>	<u>720</u>	<u>740</u>

Than the
of MEC
'electrician)

5174
15.1

avg $\frac{710 \text{ lbs}}{3 \text{ min}} \times 20 (3 \text{ min periods}) = 14,200$

of 7/16"

716
20
14200

740 → 14,800
680 → 13,600

Moisture 12%
(small sample
I took from fire
dump truck) -
moisture was 10% before
it went to truck.

11/12) PT

28.9 tons
hr

740
20
14800

Dryer #3 is face dryer - has higher
moisture level in wafers when
"dry" (~ 9%).

15,000 lbs x 200 lbs
hr. 200 lbs
38.5 = 5.8
loss 32.7 tons/hr

680
20
13600

11:40 Run #2 Dryer #3 started
inlet T = close to 900°F, had to put on "manual"
to pull it back down. Still at ~ 860°F when
I looked at 5 min data. opacity 28%
When temp was high, opacity had reached
about 39% but dropped to 27-28% after
manual was used.

with 1.5%

with no loss

well under
high (low losses)

for the

Press Vort #2 run #1 for ICH0 started
press load, per hr. = 16
TO heater temp 415°F
7/16" board density = 43 lb/ft³
line speed = 80


07 1042

07 1043

(*)

expect ② and ④ to be higher - they're in direct
line of emissions from press; ①, ③, and ⑤ should
be lower, with ⑤ lowest of all.

Press Vents
look at ~~plant~~ for actual
press Vent numbers per
plant



Press Control Room

Press Vent #2 run #3 - 16 press loads/hr
2:36 pm (not sure when it
started) line speed 80
7/16"
T-O heater 419°F

(*) 9
A
S

4:30 pm
Dryer #1
Run 12
Last 7
13
13

(*)

Start of test run #1 on Retest of Dryer #1

speed 22
dry bins low-low

operator cut back on speed
because wipers were
wetter (mistake)

Other dryers now
at higher speed
than #1, #1
had been higher
before.

had gone from 6.0 → 7.5
by 10 am; stayed at 7-7.5 up through
2 pm.

(*)

Room 1
Dr

73,600-

(*)

stack putting out little steam and mostly
particulate - plume didn't dissipate
Stacks 1 and 2, 3 look similar - not much
discharge compared to 3, 4, 5
Couldn't figure out why - even with
help of M&C reps.

(*)
ASP
Mike

Shannon

begin in direct
3, 5, and 4 should

using
lent

Also, not putting (3:30 pm) starting put old
scraps (branches, small logs) into
refrigerator.
This went through debarber, but not
through magazine - it's separated

4:30 pm inlet T ~ ~~770~~ 820°F (start)
Dryer #1 opacity ~~23~~ 26
Run 1 retest speed ~~22~~ 22

Last truck dumps: Dryer #1 retest
13740 4:44 pm 13760 4:01
13060 4:10 pm 13060 1:37 pm
680 700

How did
this off
test?

no loads/hr
read 80
heater 419°F

Dryer #1
dryers now
the speed
#1, #1
clean higher
before.

(*)

x26
13,600 lbs
hr.

x26
14,000 lbs
hr.

(*) incoming water
moisture content
only 39%

Run & dryer #1 retest (end)

Kirby only took one micron
-ing moisture all day.
So we know this fall on

up through

mostly

not much

(*)
ASK
Mike

Dryer #1 Stack now has (visual) opacity > Stack
#2 but air flow seems reduced and
water vapor is less than stacks 4 and 5.
Why? ID you get/lumps were alike for all dryers
(They can't be varied, anyway)

Thermal oil heater malfunctioning - high
skin temp. too high but haven't stopped
it yet. 5:30 pm change to dryer not
opening all the way. Could this have an
effect on Dryer 1 retest?

dryer NO. 1
Stochastic moisture content 40-49% Mon 2/24
Range for dryers 43-49 Tues. 2/25
dryer NO. 2 39-47 Wed 2/26
dryer NO. 1 39-52 Wed 2/26
dryer NO. 1 42-50 Thurs. 2/27

07 1044

220

07 1045

For Thurs

Simple subtraction from 100%
42-52%

shows limits calculated
→ check tons dry fuel - during test 42-52%
• check wood moisture - what's normal range?

• feed rate (speed)
• temp.
• which dryer's dryer doesn't work on T-0
in pm of 2/26? Did it affect test on dryer #1?

✓ Ed • last 2 wks of feed speed

(when was test)

get production TFP
feed 5 dryers inlet temp
brown fuel
dry feed rates (speeds)

avoided with J. Boswell

tests of 9-24/26/91

Testers }
for M-10 }

Shows me how fines/trim are being calculated

it was on 2/27

Last 2 dryer test (#3 and retest of #1)

were both run at 13,600 - 14,000 lbs/hr
getting lower. Keep production up.

For Fri

Remind J. Boswell we want to see results of
qualified dry #1 test on 2/24/92
(This was w/o ~~the~~ T-0 exhaust)

Ed ✓ get dimensions on press vents and
modifications made.

noted

Thursday 2/27

Surfactant #1 feeding
drops #1 and #3

47-52%

unlabeled?

8:15_{AM} at plant - Running 23/32"

- press line speed 50

T-O heater 420°F

~ 10-11 Press loads/hr.

Incoming moisture 44%
Wetness 26%

Dryer #1 800°F operating 26% line speed 2.3

Reg bins Mid - Mid

reads)

Testers
for PM-10

Armstrong Env. TDM Armstrong Pres. PM 10

(214) 905-0634

(214) 631-0021

ing calculated

of #1)

Observed person cleaning out dryer #4 burner
at 8:45 AM. This is the next burner to be

lbs/hr

fasted,

up.

Board Density (23/32") 41.6 lbs/ft³
(based on 3 measurements in AM)

etc of

t)

7 1046

0100 TO

07 1047

11/10/03

Trying to get ~~Konow~~ back on line after steam trap problem and subsequent use of gas as fuel

1130 21 809.2 26 809.6 26 800.0 21 820.84 22 820.40

12N 21 850 26 858 26 860 26 857 22 850 22 859

3:40 5pm 24 254 22 24 22 24 22 24 22 24 22 24 22 24

1103 dryer #1 wood fuel 314 071
 0947 -313 753
 1 hr 16 min = 1.26 hr.
 318
 x 6.2
 1972
 = 1.26 hr.

1565 16.5 hr.

Wood fuel usage

dryer → 1 2 3 4 5

1105 314082 568039 341974 858989 443139
 1205 fuel → 314 346 568 347 342314 859174 443490
 1637 1440 1910 2108 (gas) X 2176 165/hr.

Dryers 1 and 2 use less fuel when Konow is working (about 1000 lbs/hr. less) compared to dryers 3, 4, and 5

NOTE

2 tons 1 hr.
 1 1/4 hr.

fuel to dryer #1

Max design Capacity

1 morning

Other dryers distance increased fuel below set pt.

1 pitat

see if they

0-11

07 1048

Thurs. 2-27-98

Reins 2 and 3 on Restart of dryer #1 over at 12 noon.

12N noted more aged logs being put into debarker than before (1 truck load)

(*)

moved a truck load of new logs to storage pile from MCC reps

We will continue to get wet bin moisture to see how what changes moisture of wipers that go to dryer changes.

(*)

1:30 pm - another truck with older logs - logs loaded directly to debarker

Newer logs came in on next truck - They were not unloaded - turned around and went back toward plywood mill - and back again and were put on top of storage pile

07 1049

3rd truck came in - ~~newer~~ ^{older} logs - They ^(1/2) went to storage pile - ~~on top of pile~~ a separate older log section 1/2 went into debarker directly.

Next truck - newer logs - ^{all} went to storage pile

I talked to Ed Knight, Plant Mgr., he said they try to run older logs first all the time (no logs are older than 7 days in the whole yard)

(Logs in plywood mill are about 3 days old).

Sometimes they have to pick up newer wood off trucks because they have a line of trucks waiting.

Ed says this is their standard procedure.

2:10 pm - T-0 oil heater ~~205~~ 405 °F
10 press loads/hr.
23/32" bond.
density = 41.6 lbs/ft³

Drop No. 4 on wood fuel again to get ready for pm VOC CO test

pm test being run on dryer No. 3

T-0 ~~heater~~ running on gas - Switched over at lunch time (not testing 1 and 2 - no doesn't matter)

Time
1523 3
1205 3

Fuel usage →
in 3 hr. 18 min
= 3.3 hr

in 1 hr. →
T-0 running on

(X)

Time
1625
1523
1 hr. ²/₁₀

1.63

Fuel usage

4:40 p

07 1050

	Time	1	2	3	4	5
2) want to	1523	315406	569579	343441	860390	444679
older log	1205	314346	568347	342314	just at 86	443490
ch		1060	1232	1127	859174	
		x6.2	x6.2	x6.2	1216	1189
					x6.2	x6.2

age pile Fuel usage → 6572 7638 6987 7539 7372
in 3 hr. 18 min

said They time (no 2 yard) in 1 hr. → 1992 lbs/hr 2315 2117 2285 2224

old). wood off trucks This time

standard (X) PM 10 probe ~~not~~ temp not monitored well
- temps vary ^{with time} and are different from Eric's
Al Barker doesn't trust result.
1st run for PM-10 on stack #3

5' 408°F	Time					
	1625	315751	570026	343792	860756	445041
	1523	315406	569579	343444	860390	444679
P ₇ ³		345	4679	551	366	362
	1 hr. $\frac{2}{100}$		447			
ready for		x6.2	x6.2	x6.2	x6.2	x6.2
	1.03	÷ 1.03	÷ 1.03	÷ 1.03	÷ 1.03	÷ 1.03
		335				

3 fuel usage → 2077 $\frac{\text{lbs}}{\text{hr}}$ 2691 2113 2203 2179

rev at 4.40 pm Press 10 press loads/hr. 2732
and 2 line speed 50 T-0 heat 408°F
Density 41.8 lbs/P₇³ averaged over 10 hrs. 6 AM-4P

07 1050 07 1051

Stack #4 13880

-13000

880

x26

17600

165/hr.

5pm

2/27/92

Vince Loller (?)

(truck driver, bulldozer

operator), when asked, told me ^{he thought} that

they were ~~being~~ sending old wood to

debarbers first "because of the treating
that was going on". "Old wood had

less moisture or something like that".

Everyone else said it was their standard procedure; always

strip the old wood first - better for blades, less trig'd from dryers.

5:30 pm electricians (3) checking out burner on

#5 dryer - one that will be tested

tomorrow.

(*)

wt3.

5'3"

↓
Dry

temp
spec
moisture

Pne

07 1052

(*)

wt. of drums during 2/27
 14,400 $\frac{\text{lbs}}{\text{hr}}$ 12,800

15,200

might not be
 right maybe
 more than
 3 min
 17,600

5:34pm

? weathered
 turned out

Dryer → 1 2 3 4 5

tamp	832	841	836	824	824
speed	22	22	25	25	22
moisture	7.6	7.8	8.8	9.6	9.4

bulldoze
 e thought
 that
 ad to

Press now using making 15/32" board (Standard spec)
 Two heater 4190F
 line speed 80
 Press loads / hr. ~16

floating
 and hand

that
 volume; always
 Tregid from dryers,
 near 0%
 wetland

Rotation of dryers

8 ⁺ sec / revolution	- #2
9 sec / rev	- #3
9 sec / rev	- #4
8 ⁺	- #5
9 sec / rev	- #1

as operated

$\frac{9 \text{ sec}}{\text{rev}} \leftarrow$

$\frac{1 \text{ rev}}{9 \text{ sec}} \times \frac{60 \text{ sec}}{\text{min}} = 6.6 \text{ rpm}$

Mike W of MEC
 Verified this as correct
 doesn't change per Mike W.

$\frac{1 \text{ rev}}{8.5 \text{ sec}} \times \frac{60 \text{ sec}}{\text{min}} = 7.06 \text{ rpm}$

testing still in progress

6pm yard shack - new wood being put on storage
pile. Saw one stack of apparently green
wood going to debarkers. Did not see
any old wood on trucks. Truck drivers told
me all wood was coming from outside of L-P's
facilities at Silsbee - weren't using old wood
(They would probably save old wood for
"wet" periods when other lumber was not
available - my feeling. (except when
they can put some in to reduce
emissions during testing (also my
feeling)).

Stacks 4 and 5 look the same -
no water vapor.

1, 2, 3 all have about same water
vapor content. But, I looked at them later
and all lacked water vapor.

Summary of Thurs 2/27:

- Dryers over 820°F frequently
- dryer lbs/hr greater than 14,800 frequently
- facility using dry wood, ^{possibly} to try to cut emissions
- opacity almost always > 25%
(what is TX limit?) → 20%

07 1054

- need of conditions of 9/14-26/77 stack test
- want stack test on dryer 1 even w/o HSC T-0

storage

green

see

pieces told

idea of L-P's

old wood

good for

was not

except when

some

also my

me -

me with

at them later

ed frequently
missions

90

20%

07.1054

truck for

-0

- get incoming moisture overnight

- check dumps of 2/27 were they all
tared and all done correctly?

2/28/92 - Friday - 8:30 AM

Older logs being piled in separate
pile again. Also saw trucks being
loaded with older logs on plywood
mill property. Older logs being put
into debarker (#2)

8:40 Running 19/32" line speed 65
T-O heater 417°F Density 43 lbs
press loads 13/hr. #7

8:50 truck of new logs came in - They
were put on storage pile

Kirby ~~test~~ Internal "transfer track" - yellow, without
plates brought in older logs

I cautioned Ed Knight about biasing test results
by drying ^{older} wood. He said they always
try to use the older wood first. They're using
logs from plywood mill pile now because
they've had clear wood coming in from
forests lately. He said they've been doing
this all week. I said - no, not on Mon-
Wed. They were drying green wood
then. I said he should speak with
Boswell about their procedure. 07 1055

J. Boswell

Northern hardwoods have more moisture almost 100% they need higher T's to dry it.

10:15

4:14 pm

1/24/94	Drill 1	Drill 2	Drill 3	Drill 4	Drill 5
fuel speed	850	821	807	854	818
positive (out)	3	22	22	7.6	70
fuel count	319995	320376	320781	320781	321685
open	22	22	22	22	19
T	813	815	824	804	817
max	714	710	710	710	710
L.S.	12	22	22	22	22
F.C.	576400	576846	576338	576668	577508
open	19	22	19	22	18
T	832	840	807	819	815
max	1016	816	816	816	816
L.S.	23	24	24	24	24
F.C.	827987	349993	350194	350446	367676
open	28	24	24	24	22
T	844	847	870	811	828
M	1615	24	810	754	26
L.S.	23	24	24	24	24
F.C.	861444	867202	867730	867940	869118
open	28	22	24	24	21
T	858	801	816	813	909
M	4118	801	816	813	24
L.S.	25	25	25	25	24
F.C.	449193	44972	44972	44985	451729
open	29	29	29	29	37
T	855	855	855	855	855
M	4118	801	816	813	24
L.S.	25	25	25	25	24
F.C.	449193	44972	44972	44985	451729
open	29	29	29	29	37

NO
TRANSMISSION
2 2 2 2
1008

Missouri
(OUT)
Jude T
Yoder
Dm1

Ed K. said they never load green wood directly into debarker (unless trucks are lined up and the debarker is calling for wood - then the green wood would go directly ^{from truck to debarker} in order not to hold up the trucks.

Randy Norwood (409) 838-0397 → 898-3838

Jesse wrote letter to Randy Norwood at TNCB, 5/14/90

Deadwood - storm and beetle damaged wood
Most of deadwood
Moisture content of dead wood is 25%

Green wood 50-55 % moisture

Par Marion Everhart of TNCB, Beaumont
30% prior to 1972
20% after that

We have seen
only this low in
moisture
during
testing
but some
got to
36-39%

Nike Hudson, peer says this plant loses
15% to fines ^{alone} in Northern plant
about 8% The drier the wood, the more

fines. Don't want wood to get too
dry. Want to dry the older wood first if
you can.

Northern
hardwoods
have more
moisture
almost 100%
They need
higher Ts to
dry it.

wet bin
incoming
unfermented
dryer
Moisture content
42% #1
47 #2
48 #4

fuel usage #4 - 2471 lbs/hr. #3 2090 lbs/hr.
#1 - 1575 #5 2354
#2 - 2609 07 1057

8 850 8:45 am
7 821 10:15
8 807 10:35
7.6 856 10:45
22 826 12:20
22 818 2:40
22 849 4:47 pm

⊗ will wait to do next PM-10 on stack #1 until leaching day next week (Wed.)

Stacks 1 and 2 - T.O. heater running 20% gas

PM 10 Stack 2 - 1st run - might have lower emissions. 2nd run 3rd run

⊗ T.O. heater needs cleaning, may be on partial gas for several days

Truck dumps to get lbs/hr for dryer #4

~ 8 am - 10:30 am

empty 13080	138600	→ 780 x 20 =	15,600
	13820	→ 740 x 20 =	14,800
	13840	→ 760 x 20 =	15,200

2/28

empty 13660

76%
20%

⊗ These don't indicate older logs had less moisture

We took moisture sample at Wapizica when a load of older wood was going through.

Result: 51% Wapizica 46% Wapizica @ 11:00 AM

[41% at 10:00 AM Wapizica] → not sure if these were for old logs

⊗ Digital and strip charts for dryers do not agree:

Dryer	S.C.	Inlet T Digital	Digital Δ
5	800°F	819°F	+19°F
4	770	815	+45
3	800	857	+57
2	800	824	+24
1	800	841	+41

07 1058

#1 dryer

Incoming moisture 42%

4
4
4

2 stack #1 34
next week (Wed.)

20% gas
have lower

Difference between strip chart and digital moisture:

	Dryer	S.C.	Digital Moisture	Digital Δ
may be on	5	7.3%	9.3%	+ 2%
	4	6.3	7.4	+ 1.1
	3	7.3	8.7	+ 1.4
	2	NOT working	7.6	—
	1	4.0	5.9	+ 1.9

15,600

14,800

15,200

12:15 pm 4 trucks lined up waiting to load logs

truck (1) move logs onto storage pile

(2) Crane takes old logs from special pile to send to debarker while 4 trucks wait. New log truck backs into place.

Crane takes new logs to new log storage piles.

There's always a pile of old logs to put into debarker.

(3) > These trucks continued to wait 15-20 min

finally saw some new logs from #2 go into debarker as truck #3 pulled up. They were "new" but not real green like some on other trucks.

#1 Dryer 2 #3 #4 #5

Incoming moisture 43% 48% 47%

42% 44 44% 46

47 49.5

48

not that low, even with "older" logs

07 1058

07 1059

1st Run on #5 dryer for VOC, PM, CO complete
at approx. 11:50 AM 2/28/92

④ Al Barker noted stack at end of bldg.,
past NO.1 dryer stack, which is always
emitting lots of particulates - it looks like
a cyclone is being by-passed and
refrigerator emissions are going directly to atmosphere.
NO.1 stack has particulates all over it -
largely from this stack

Barker
No.1

⑤ Calvin says this
shows go through
cyclone for fuel bin
or cyclone to dump
it's emergency bypass
metal screen built in front
of stack.

class cyclone
recess in side
Wingwall
Cov. 2:05 pm
They boxed
this at
about 4 pm
for all 15.
put it through
dump rail fuel
cyclone

⑥ Al B. says cyclones
have been ~~not worked~~
week (M → today, Fri 2/18)

They've been bombarded with
particulates while stack sampling.

$\frac{5.2}{8} = .775$

Baswell says
it automatically
dumps when fuel
bin is high.

Press loads 15⁺/hr. 7 1/2"
T-O 420°F
density 42.1 lbs/ft³
line speed 82.5

2/28/92 Dump to determine lbs/hr on stack #5 ~3:52 pm
dump ran for 3 min 20 sec = 3.33 min

⑦ $\frac{3}{66} = \frac{1}{22}$
 $\frac{1 \text{ lb}}{3.3 \text{ min}} \times \frac{60 \text{ min}}{\text{hr}} = 1 \text{ lb} \times \frac{18.18}{\text{hr}} = 18.18$

$\frac{3.3}{66} = \frac{1}{20}$
 $820 \text{ lbs} \times 18.18 = 14908 \text{ lbs/hr}$
But Kirby will have $820 \times 20 = 16,400$

Co complete

Calvin's next dump on ~~the~~ stock was

3:00:25 on #5 dryer
at about 3:40pm - 3:45pm

16,000 $\frac{\text{lbs}}{\text{hr}}$

bldg.

4pm - Press loads 16/hr
82.5 line speed 7/16" board

his always
looks like

and
g to atmosphere
out -

Average fuel usage during 8:45am - 4:45pm

Burner
No. 1

321982
319995

1987 $\frac{\text{lbs}}{\text{hr}} \times 6.2 \frac{\text{lbs}}{\text{m}} \Rightarrow \frac{12,319 \text{ lbs}}{8 \text{ hr.}}$

= 1540 $\frac{\text{lbs}}{\text{hr.}}$

2 days cyclones
worked
~~through~~ all
today, Fri 2/18)

2

577861
575400

bombarded with
stock sampling

$\frac{6.2}{8} =$

2461 $\times 6.2 \div 8 = 1907 \text{ lbs/hr.}$

7/16"

3

352054
349387

2667 $\times 6.2 \div 8 = 2067 \text{ lbs/hr.}$

F

.1 lbs/ft³
82.5

4

869579
866664
2855

$\times 6.2 \div 8 = 2143 \text{ lbs/hr.}$

~3820pm

5

452155
449142

3013 $\times 6.2 \div 8 = 2335 \text{ lbs/hr.}$

min

07 1060
8.18
hr

lbs/hr

16,400

07 1061

2-24-92

Sat 2/29

8:30 AM

T-O heater 419°F

7/16"

Density 42.3-42.9

16 press loads/hr.

Line speed 82.5

Dura ①

16.

Capacity

22

Inlet T

8.

Fuel count

326

Moist in

Moist out

3 AM 7.

Line speed

2.

②

Capacity

20

Inlet T

84.

Fuel count

583

Moist in

Moist out

3 AM 7.

L.S.

2.

③

Capacity

3.

Inlet T

86.

Fuel count

357.

Moist in

Moist out

3 AM 7.

L.S.

2

④

Capacity

2

Inlet T

8

Fuel count

87

Moist in

Moist out

3 AM

L.S.

⑤

Capacity

Inlet T

Fuel count

Moist in

Moist out

L.S.

Noted big opening in Press Area roof

just ~~above~~ to right (estimated from press console in office) of

press vents - might have been used to raise equipment to roof (~20' x 1' opening) For umbilical cord.

This opening was closed later - see notes.

They ran 1/4 on night shift (for short time)

Density = 49 lbs/Pt3 - has to be this high to be able to cut it with saws.

Facility really looks hazy after they have run Thinner bonds for awhile (7/16" or less Thinner)

Crane ~~Frame~~ still loading older logs first into the Debar.

Forming line has no vents - only openings in roof - area is very hazy all the time. Only roof monitor lets haze slowly out.

pm 10 sampling team work slow up until Monday. No Tests on dryer stacks today. Only formaldehyde test on unloader vent today.

Unloader incoming moisture → #1 46%
9:30 AM → #2 44%Took at past unloader moisture records
wk of 2/10 and 2/17

07 1062

unloader vent gets much less of emissions when this opening is there. Press vents also get less.

See 12

22-4-42

[NO tests on drum stack this day (Sat)]

ty 42.3-42.9	Drum ①	10am	11am	2.45pm	4.07	5.28pm
mess loads / hr.	Opacity	22	22	21	22	21
Speed 82.5	Inlet T	830	831 (2145)	855 (2145)	832	853
7	Fuel count	326769	327042	328083	328444	328792
	Moist in					
fine) of	Moist out	8am 7.6		7.6	7.6 7.0	
in equipment	Like spread	23	23	23	22	22
ical cond.	②					
e notes.	Opacity	29	27	24	29	29
	Inlet T	848	859 (2145)	871 (2145)	862	851
nel	Fuel count	583 809	584 155	585 468	585 925	586 353
his high	Moist in					
	Moist out	8am 7.0		7.5	7.6	
	L.S.	24	24	23	22	22
ve run Thermo.	③					
a)	Opacity	32	38	35	34	32
	Inlet T	864	877 (2145)	900 (2145)	882	898
into the	Fuel count	357 905	358 247	359 573	360 045	360 516
	Moist in					
	Moist out	8am 7.5		10.2	9.0	
ly	L.S.	26	27	25	25	25
hazy	④					
hazy slowly	Opacity	27	24	21	36	19
	Inlet T	852	855 (2145)	846 (2145)	837	804
up until	Fuel count	875 822	876 186	877 546	878 038	878 513
today	Moist in					
today.	Moist out	8am 9.0		10.5	9.0	
6%	L.S.	25	25	24	23	26
14%	⑤					
	Opacity	31	29	38	42	38
eds	Inlet T	831	832 (2145)	813 (2145)	815	808
	Fuel count	458 764	459 120	460 464	460 923	461 393
	Moist in					
	Moist out	8am 9.3		9.5	8.9	07 1063
07 1062	L.S.	24	24	23	22	23

Compton

T-6 fuel usage: 9:58 am
was on gas at 10:50

245 349
245 686
x 6.2 lbs/hr.
2099 lbs/hr.

na

2

10 am - Kirby truck with 1/2 old logs 1/2 new
logs came in and crane took them directly
to debarker.

④ I noted ^{from my notes that} ~~Wanferizer~~ moisture was about
the same on Mon 2/24 and as on

2/26 Wed → Fri 2/28 when they seemed to
be using ^{more} older wood. Maybe wood
has to really be "dead" before

it has an effect on overall moisture or
emissions. We should ask Chuck if

he knows what moisture content
leads to lower emissions. Also ask
Dr. Boswell.

Chuck
didn't
know.

④ Calvin W said he trust strip chart reading
more than digital Calvin says he trusts
digital more. 1st Calvin said digital has
to be about 860°F on Aug. # 3 to be
about = 820°F (my observation says
digital is about 50°F higher). Which

Temp. is correct?

I told Danny about opening in roof and how
it would affect formaldehyde determinations, he

07 1064

820°F
1.5 = 25
26

2/29

Counter

245 349

248 686

x 6.2 lbs/hr.

2089 lbs/hr.

1/2 new

Three directly

as about

as on

seemed to

wood

before

nature on

checking

content

Also ask

chart reading

ays to transit

digital has

to be

ation says

Which

I have

as, he

17 1064

get down to put tarp over opening. Some open area remaining but it's miniscule - will not have impact on HCHC determinations

Switched to

20% gas usage on T-0:

12:24 PM

246 060

1463

10:24 AM

245 824

1463

$236 \times 6.2 = 1463$ lbs/hr wood

Reduction in wood burned of about 30% for 10% increase in gas fuel.

Pressure vent #1 (unloader vent)

(*)

started 1ST HCHC run w/o tarp on opening

After 15-30 min Al Bender plugged opening

1/2 of way. For wood 2 runs vent will be plugged all the way.

11:57 AM

T-0 421 °F

Pressure loads ~

7/16"

line speed 82.5

16+ lbs/hr.

Density 43.0 lbs/ft³

Get ready for dump to determine dryer lbs/hr.

on dump NO. 3 (running hot and at fairly high

line (input) line speed). Compare to our dump NO. 3 test runs

(no test run this day, just got lbs/hr for comparison

and to determine how furnish rate may vary day-to-day.

2/26

14,400

14,000

13,600

900°F 1.5-26

14,800

14,000

7/24

807°F 1.5-24

14,800

890°F

1.5-25

7/29

890°F 1.5-25/6

16,400

07 1065

(*)

Mike Hudson / Mike Wenzel of M&C said that digital read out for inlet Temp is probably closer to the accurate real Temp than is the strip chart (S.C. easily biased by handling, chugging)

(*)

Rich I / Al B. noted ~~red color~~ ^{red color} ~~not a stack~~ ^{not a stack} on ~~roof~~

3/1/92
all b. looking white and it was vent for belender, when resin is on roof particles coming out at good rate.

mixed. → CP-002 EPN 13

Should be tested for formaldehyde. I did not see any emissions coming out of this stack, however, maybe it was a start up problem?

2/29/92

(*)

PM-10 had break through on filters, tamperage labels on bottles (with liquid inside) that were not readable due to dripping water. Dryers #2 and #3 might be affected. Sloppy work in general we told Danny and J. Roswell.

VIDEX original 1000m bags and 3 and retested.

2000m Press check press loads/hr = 16t
7/16" 82.5 line speed T-0 = 420°F

2:50 pm
12:24 pm

T-0

246 549
246 066

2 hrs. 26 min
= 2.43 hrs

3520 wood
6590 gas
now

489
x 6.2 ÷ 2 hrs 26 min
= 489 x 6.2 ÷ 2.43 =

1248 lbs/hr

07 1066

fines -
all 5 →
dryer
screened
fines

(*)

Bu

$$12492 \cdot 36 \times c$$

$$c = \frac{27806}{3469 \text{ lbs/hr}} = 3.9 \text{ tons/hr} = 1.7 \text{ tons/hr}$$

Said that
bubbly close
in strip

capacity of T-0, calculating backward from
usage and % capacity number on
wood control and gas control meters.
It is the same as the dryer burners.
For ~~press~~ so 1.7 tons/hr. is about right.

not a stack
on ~~strip~~

rain is

I did not
see stacks
when?

2 filters,

legged
due to

2 and #3
work in general

2-2992

(*)
(*)

Press down for 17 min during 2:45-3:45pm
no press cycles. When up, still operating
at 16 press loads/hr on 7/16" board,
T-0 at 413°F

Pace Rosin feeder 6.5%

V_E 2650 lb/hr. O = 60%

Core Rosin feeder 2.00%

V_E 570 lb/hr. O = 12%

(*) want to look at fully loaded press at
some other mill to see what its
emissions are compared to Kirby. Then we
can estimate what ^{fugitive} losses might be.

(*)

Fines - from 6 min decamp (Mike W of REC coordinated)

all 5 → 11,200 lbs/hr

fines ÷ 5 dryers = 2240 lbs/hr per dryer

2 hrs 26 min

dryer
separated
fines

For 16,400 lbs/hr

89% moisture, 2240 lbs/hr fines

07 1067

2.43 C

Actual dry furnish rate: $\frac{16400}{1.06} - 2240 = 12945 \text{ lbs/hr}$

15/hr

07 1066

(*) But, how does state measure #/hr for permit
purposes? Should be based on water + fines + mols?

(*)

if average dryer rate is 16,400 lbs/hr

% of fines is $\frac{2246}{16400} \times 100\% = 14\%$

and higher for lower production dryer runs. Say on avg it's 15% loss

A fine, Doesn't count trim

and sanding losses. This is higher than Kinswell and Northern Div. have usually estimated in former applications. This would encourage higher dryer production rate to meet square feet goals.

All burners are the same - T-O and Dupes

36 mm BTU/hr might need to increase

T-O capacity in the future - it's making out. Backdraft from going through dryer 1 and 2 causes shell temp to get too high.

See 3/1/92

82.5 line speed, 7/16" board

T-O 419°F Press loads = 16/hr

density 43.4, 42.9

Did 1/4" again last night - density 49-48

Mike W and Dick of MBE said

low fire 3 mm BTU/hr dryer & T-O

% of on fuel meter is % of high fire rate
 $63.6\% = 63.6\% \text{ of } 90\% \text{ (} 63\% \text{ of } 832 \text{ BTU/hr)}$

9:25 AM Two heaters 251 132

wood control meter 63.6 % 07 1068

10 AM 16 press loads/hr 82.5 line speed 7/16" 420°F

density 42.8 42.9 43.1

Drop ①	91
spacity	2
in let T	81
(lbs/hr)	33
Fuel	
mois in	
mois out	
line speed	2
②	
OP	2
T	8
Fuel	59
M in	
M out	
L.S.	2
③	
OP	29
T	85
Fuel	366
M in	
M out	
L.S.	2
④	
OP	2
T	8
Fuel	884
M in	
M out	
L.S.	2
⑤	
OP	2
T	8
Fuel	41
M in	
M out	
L.S.	

or are they drying
 low moisture wood,
 then usually which creates more
 fines per Mike
 Hudson?

T-O and dryer
 design of 3 mm BTU/hr
 90% of high fire rate
 10% of low fire rate

		Sun. 3/1/92					
			9:20 AM	10:35	11:35	12:20	6:20
						OP. Chris For Gray 4:25	
10 165/hr	Drops ①	23	22	27	24	21	24
1 1490	inlet T	862	822	858	824	831	854
0.2	(lbs/hr)	333146	333514	333824	334046	335163	335713
fire dryer	Moist in						
5% loss	Moist out		6.8 ^{8 AM}	8.5	7.0	6.0	
- train	line speed	23	23	23	23	23	23
	②						
this is higher	OP	24	20	44	22	21	15
we usually estimate	T	840	841	862	831	824	788
marginage higher	Fuel	591501	591927	592270	592523	593795	594499
t goals.	M in						
and drops	M out		(8 AM) 8.2	7.8	8.0	7.0	
increase	L.S.	23	23	22	22	22	22
it's making	③						
rough drops	OP	29	35	32	32	22	22
t too high	T	856	876	904 → 915 at 11:43 (2172)	865	815	795
	Fuel	366094	366524	366875	367145	368438	369137
	M in				9:05-12:20		
and	M out		8 AM 8.4	10.0	10.5	9.0	
rolls = 16/hr	L.S.	24	26	26	25	24	24
	④			#3 switched to cone at 11:20 AM	switched back to flame		
- density 49-48	OP	22	30	28	22	19	24
	T	822	867	879	837	775	837
	Fuel	884386	884855	885225	885505	886830	887579
ET-0	M in						
	M out		8.5 ^{8 AM}	9.0	9.0	8.0	
high fire rate	L.S.	26	26	26	26	26	26
63% 832 (870) 10:37 251 472	⑤				11:35-12:20		
7 1068	OP	38	47	47	52	38	46
7 116 420°F	T	800 467268	838 467665	862 468038	921 (2447) 468334	838	857
	M in					469	468
	M out		8 AM 8.5	9.8	9.507	10698.5	470416
	L.S.	24	26	25	24	23	23

⊗ get EPN NOS for Press Vents

For mon } HCOH → dry stack 3

will probably } for 10 → release 4.5

sample } PM → Press Vents 4.5 1.3

ask Chuck about lower emission rate based on wood moisture

get Rich D to check estimate for HCOH

for EPN 13 CPO02

12:10 pm

- Get weather moisture over last week (dry report)

- Ask Boswell re CPO02 - EPN 13

- have Rich D look at onland pressure - what are

emissions for VOC / capacity / size / wood

etc. (to get loss estimate for site base)

4:15 -

- Retest PM10 dry stack 3 and 2

buffering moisture

39% 43% 361 Am

47 50 2/4 PM

41 51.4 2/4 Am

38 = 6
60

T-0 fuel usage 9:25 - 10:37 AM

1 hr. 12 min = 1.2 hr.

T-0

$$340 \times 6.2 \div 1.2 = 1757 \frac{\text{lbs}}{\text{hr.}}$$

and its on partial gas
switched to full gas ~ 10:30 AM
due to high shell temp.

10-11 am Stacks 1 → 3 Low water vapor
4-5 higher vapor content

07 1070

3



New shift dryer operator (Jamus, white on duty)
Chris, said operators read strip charts
not digital. I said no, some do and some
don't.

1.3
moisture

HCOH

12:10 pm

7/16"

16 press loads/hr.

line speed 82.5

T-O 419°F

all on all day or for in press; no breakdowns
will run 7/16" all day unless they dry drums
get slow.

4:15

T-O heater fuel usage 252 334

59% of 90% of wood fuel capacity (32
lb/hr)

Chris changed to 109% when I asked about
it at 4:15 pm

38 = 6
60

252 334

10:37 - 4:15

251 472

am pm

862

5 hr. 38 min
5.6 hrs.

T-O usage

$862 \times 6.2 \div 5.6 = 954 \frac{\text{lb}}{\text{hr}}$

T-O checks still having high

shell pump problems. Put on gas

but it hasn't brought it down

Went up to 109% since 59% didn't help on
wood

10:30 am

up

at Vapor
water
content

Sample taken at 5:00 pm
#1 51.9%
#2 52.9%

Looked like never logs or combination

of both and never to me on visual check

if delinker and crane loading logs.

17 1070

07 1071

Overtime Log: Silsbee, TX

Sun. 2/23	12N - 8pm	8 hrs. travel	
Mon. 2/24	—	—	
Tues 2/25	5:00 - 9:30	5.5 4.5	
Wed 2/26	5: - 7	2	
Thurs 2/27	5 6:30	1.5	Over
Fri 2/28	5 - 6	2.1	
Sat 2/29	8:30 - 6:30 (1 hr. break)	9	
Sun 3/1	8:30 - 7:00 (2 hr. break)	8.5	
Mon 3/2	5:00 - 8:00 8:00	3	
Tues 3/3	5:00 - 6:00	1.5	
Wed		0	
Thurs		0	

39 hours

07 1072

13. travel

34.5

2

1.5

3.1

9

8.5

3

15

0

0

39 hours

Chris said "normal" range is 40-53%
with most frequent moisture being
44%

al's recordings

Rich Ida's

Old samples taken during testing

humidity 39 11

median 44 111

median 44 111

45

46 11

47 111

48 1

49

50 11

51 11

52 1

53

Median is about where Chris (dryer op.)
said it was historically.

5:45 PM Press loads per hour = 16+

T=0 4180 F 7/16" 82.5

Press operated ~~with~~ missing maybe only one
cycle all day.

Density see Day 42.2 - 43.4 lbs/ft³

1072

07 1073

3-25-76

Blender Motors

Scale C: Face feeder

6.5% of wgt of resin

~ 2500 lbs wgt

~ 2500 lbs/hr resin use rate

Scale D: Core feeder

~ 626 lbs wgt

~ 626 lb/hr resin

2% of wgt of resin

(*)

Looking at forming line from beside
press crush room, haze going up
from former seems to drift away from
press (it's not being captured by
press vent fans) and toward
remaining openings in roof

Mon. 3/24/76

(*)

Termini agreed to not do PM-10 on Presidents
(too light a collection on 1st attempt). We do
want VOC and HAPs on EPN 13 CP002.

Hinesville
do

07 1074

(*)

Hinesville do dry stacks #2 and #3 over for PM10
but drop PM-10 on press vents.

(*)

Danny Russell & EML said he and Biswell agreed that a burst
fall PM from Press vents is PM-10.

Drier ① 9.46

opacity 22

inlet T 85

Fuel 3401

Moist OUT 8

line speed 22

②

opacity 26

inlet T 86

Fuel 5996

Moist. OUT 7

line speed 22

③

opacity 29

inlet T 84

Fuel 3742

Moist. OUT 9

line speed 24

④

opacity 24

inlet T 87

Fuel 8926

Moist. OUT 10

line speed 26

⑤

opacity 38

inlet T 83

Fuel 475

Moist OUT 9

line speed 22

T-0

Motor gas fuel no

Motor wood fuel 2590

T shell

% gas setting 0

% wood set. 70

		Mon 8/21/92										C = Core F = Face		
		Driers												
		9:40am	10:45	11:45	1:40	3:30	4:30	6:10	7:10	8:20	after testing			
		opacity	22	19	23	19	22	33	22	15	10			
		inlet T	852	842	845	795	780	875	791	724	747			
		Fuel	340196	340497	340785	341341	341850	342126	342565	342823	343087			
		Moist OUT	8		8	8.5	8.0	8.0	8.5					
		line speed	22 C	24 C	23 C	24 C	24 C	24 C	24 C	20 C	20 C			
		(2)												
se rate		opacity	26	22	23	22	22	20	15	19	16			
933		inlet T	866	837	833	851	864	845	790	809	804			
		Fuel	599619	599961	60270	600863	601475	601807	602313	602415	602972			
7.3		Moist. OUT	7		6	7.0	8.0	7.8	8.0					
		line speed	22 C	22 C	22 C	22 C	22 C	22 C	21 C	21 C	20 C			
		(3)												
in		opacity	29	32	35	30	34	30	15	16	12			
777		inlet T	844	836	826	790	818	822	660	729	670			
		Fuel	374277	374637	374958	375595	376208	376541	377062	377362	377709			
8.7		Moist. OUT	9		7.5	9.0	9.5	9.0	8.0					
brake		line speed	24 F	24 F	25 F	25 F	25 F	24 F	21 F	21 F	21 F			
going up		(4)												
away from		opacity	24	22	23	26	22	27	Flameout at 6:40pm (2-3 min down)			26	19	
		inlet T	871	871	824	850	843	844	683	850	814			
captured by		Fuel	892646	893045	893382	894065	894710	895077	895646	895992	896430			
		Moist. OUT	10.6		8	10.0	8.0	10.0	10.0	(2104 lbs/hr from 9:40-7:10)				
ward		line speed	26 F	26 F	25 F	25 F	25 F	25 F	25 F	25 F	26 F			
in roof		(5)												
95"		opacity	38	38	35	35	42	43	38	42	36			
		inlet T	833	835	833	822	860	852	828	812	816			
		Fuel	475726	476081	476416	477066	477681	478050	478666	478957	479372			
on Pressvents		Moist. OUT	9.0		8	10.0	10.0	10.5	8.5					
upt). Wrecks		line speed	22 F	22 F	22 F	22 F	22 F	22 F	22 F	22 F	22 F			
3 CP002.		(T-0)												
1074		Moist gas fuel	none	Some	lots	lots				07	1075			
on for PM10		Moist wood fuel	259087	259597	259728	259944	260328	260583	261443	262002	262514			
		T shell			195	185	188	196	203	203	200			
units.		% gas setting	0	25	95.3	6.2		0	0	0	82			
red that abrupt		% wood set.	70.9	-		0	36.1	91.4	87.4	100	10			

Mon 3/21/92

C = Core
F = Face

Driers

	Drier ①	9:40am	10:45	11:45	1:40	3:30	4:30	6:10	7:10	8:20
	opacity	22	24	23	19	22	33	22	15	after testing 10
	inlet T	852	842	845	795	780	875	791	724	747
	Fuel	340196	340497	340785	341341	341850	342126	342568	342823	343087
	Mois. OUT	8		8	8.5	8.0	8.0	8.5		
	line speed	22C	24C	23C	24C	24C	24C	28C	20C	20C
	②									
se rate	opacity	26	22	23	22	22	20	15	19	16
	inlet T	866	837	833	851	864	845	790	809	804
	Fuel	599619	599961	60270	600863	601475	601807	602313	602615	602972
	Mois. OUT	7		6	7.0	8.0	7.8	8.0		
	line speed	22C	22C	22C	22C	22C	22C	21C	21C	20C
	③									
in	opacity	29	32	35	30	34	30	15	16	12
	inlet T	844	836	820	790	818	822	660	729	670
	Fuel	374277	374637	374958	375895	376208	376541	377062	377362	377709
	Mois. OUT	9		7.5	9.0	9.5	9.0	8.0		
inside	line speed	24F	24F	25F	25F	25F	24F	21F	21F	21F
going up	④									
away from	opacity	24	22	23	26	22	27	Flameout at 6:40pm (2-3 min down)	26	19
	inlet T	871	871	824	850	843	844	683	850	814
turned by	Fuel	892646	893045	893382	894065	894710	895077	895446	895992	896430
	Mois. OUT	10.5		8	10.0	8.0	10.0	10.0	(2101 lbs/hr from 9:40-7:10)	
ward	line speed	26F	26F	25F	25F	25F	25F	25F	25F	26F
is roof	⑤									
	opacity	38	38	35	35	42	43	38	42	36
	inlet T	833	835	833	822	860	852	828	812	816
	Fuel	475726	476081	476416	477066	477681	478050	478666	478957	479372
on Pressurized	Mois. OUT	9.0		8	10.0	10.0	10.5	8.5		
pt). Winder	line speed	22F	22F	22F	22F	22F	22F	22F	22F	22F
CP002.	T-0									
1074	Motor gas fuel	none	Some	lots	lots				07	1075
→ 7A PM10	Motor wood fuel	259087	259597	259718	259944	260326	260583	261443	262002	262514
	T shell			195	185	188	196	203	203	200
ced that abrupt	% gas setting	0	25	95.3	6.2		0	0	0	82
	% wood set.	70.9	-		0	36.1	91.4	87.4	100	10

wood
Visual
(green aged)

Input Moisture
of Waters

Mon 3/2/92

Wagner #1
46

#2
46

Wet
~~bins~~

moisture

Time

Time

Boar
Thick

green

green

green

Dryer #3

#5

#5

#4

#3

#4

#3

#5

#4

#5

#4

#2

#4

#5

#3

#2

#2

#3

#3

#3

#3

#1

#1

#3

#3

—

47

43

47

45

50

42

50

48

49

57

49

48

43

47

49

43

51.4

45

48.6

46

47.4

47

45.2

0630

0930

1005

1050

1120

1135

1220

2:20

4:10

5:40

7:35

3:35

5:10

5:40

5:40

7:50pm

10:25

10:30

11:55

12:15

3:15

5:15

6:40pm

2:40

9:35am

10:40

12:20

1:15

(*) down at 1:1

I need down

portion in

2:20

4:10

5:40

7:35

5:50

6:55

cycle +

my memo

7:50pm

11:4

9:1

7:1

7:11

7:1

7:11

Raining → TUES 3/3/92

Mostly green

(newer) being

unloaded. Saw 1st

older wood at 10:55

but it was unloaded

to storage pile

07 1076

Press

Mon. 3/2/92, TUES 3/3/92

Moisture	Time	Time	Board Thickness	Line Speed	T-0 Temp	# Pressloads per hour	Density	Core Resin	Face Resin
								2.596	790
								2.596	2875 165/hr
								2.596	2793 16/hr
								2.596	2697 16/hr
								2.596	2623
								2.596	2916
								2.596	2923
								2.596	2578
								2.596	2427
								2.596	2255
								2.596	2332
								2.596	2575
								2.596	2291
								2.596	2578
								2.596	2659

3/2/92

Mon. 3/2/92, TUES 3/3/92

Core Resin

Face Resin

Density

Pressloads per hour

T-0 Temp

Line Speed

Board Thickness

Time

Time

Moisture

7 1076

07 1077

(*) down at 1:11 pm - down time 12 min (saw blade) but not include this portion in his averaging.
I need Danny Russell. He had seen it on chart and will not include this portion in his averaging.

switched to 3/8" board at 5:45 pm
cycle time for 3/8" board 189 sec. per console monitor
my measurement - one press entry (acc 12 boards) to the next: 3.5 min

3/3/92

TUES



#38

Empty

13080

09:50 AM 03/01/92

Full


13900

12:35 PM 03/01/92

820
20
16,400 lbs/hr

1:40 PM -

20-30% Opacity



opacity readings by Mike Kirby Forest Products Silsbee, TX 3/3/92

1:19 PM - 1:23 PM

40-60% Opacity

1:23 PM - 1:26 PM

20-30% Opacity

1:26 PM - 1:29 PM

40-60% Opacity

1:29 PM - 1:30 PM

20-30% Opacity

1:30 PM - 1:33 PM

30-40% Opacity

1:33 PM - 1:40 PM

40-60% Opacity 06:49 PM

Mon, 3/4/92 Sampling

Buc
ma

Source	Pollutant(s)	RUN	START	END	PROBLEMS	Time
dry# 3	HCOH	1	9:20	10:20		9:45 AM
		2	11:05	12:35		10:30 11
		3	13:35	14:35		11
dryer 4	pm-10	1	10:50	12:50		12:10
		2				1:15
dryer 5	pm-10	1	9:50	11:50		3:15
						4:00
dryer 5	pm-10	2	13:35	15:35		4:40 9

3/3/92 TUES

HCOH team didn't
let MEC personnel
know they had started
tests. Data not being
taken. MEC aborts
tests. Then team
changed stacks. MEC
upset - team needs
to communicate with
dry room (Dick -)

9:15 dan
10:30
10:55
12:10
12:40
1:45 Phil
2:30 Schmitt
6 pm Rod
6:20

Phil Schmitt

Capacity re

Time

1:19 - 1:2
1:23 - 1:2
1:26 - 1:
1:29 - 1:
1:30 - 1:
1:33 - 1:
1:38 - 1:3

07 1078

20BLEMS

background
patterns about

STACK OBSERVATION

Mon 3/2/92

Time

Plume
color
white

Water Vapor
Content
None

Flow

STACKS

9:45AM

white

None

high

1-5

~~Plume~~ 10:30

Same as

above

11

Same as

above

12:15

Same as

above

1:15

Same as

above

3:15

Same as

3:15

4:20

gray brown

None

2 lower
1345 high

1-5

2 looks
less intense

4:40

Rain

3/3/92

TUES

Team didn't

personnel
key had started
data not being

cc abouted

on team

stacks. MTC
team needs

communicate with

TM (Dick -)

9:15

dark gray

small

1-3 high
4-5 none

10:30

"

"

"

10:55

"

"

"

12:10

"

"

1-4 high
5 none

12:40

small

3 lower
others high

1-5 all operating now

Phil
Schneider

camp

2:45

White (but sun is
around)

small

lower

1-5 all running

2:30

Brown

small

lower

1-5 all up

6 pm

Red-Brown

small

3-high
4, 4, 5 less

6:20

3-high still

Phil Schneider Region 1 Stack Test witness did visual
opacity readings after his arrival; Looked at

Time

opacity

1:19-1:23 40-60%

1:23-1:26 20-30

1:26-1:29 40-60

1:29-1:30 20-30

1:30-1:33 30-40

1:33-1:40 40-60

1:40-? 20-30

7 1078

07 1079

Water lbs/hr.
Mon. 3/2/92

Time	Dryer	Tare	loaded wt.	lbs water + fines	Sample Time	lbs hr.	Time	T
1120	✓ 5	13020	13800	780	3 min.	1560	5:00	
	✓ 3			700		1400	5:30	
	✓ 4			880		1760	5:45	

3/3/92 TUES

10:45am ✓ 3
2pm ✓ 1

900 3 18,000
980 3 19,600

07 1080

0.01

finer determination

Mon. 3/2/92

		Fines determination					
		Mon. 3/2/92					
cr	Sample	lbs					
s	Time	hr.	Time	Tare	loaded wt.	Fines wt. (lbs) all 5 dryers	Fines (lbs/dryer)
1	3 1/2 in.	15600	5:00		1360	13600	2720
2		14000	5:30		1280	12800	2560
3		17600	5:45		1280	12800	2560

3/3/92

TUES

3	18,000
3	19,600

1030

07 1081

1/4" board
9:10 AM
TUES 3/31/92
DRYERS

C = Core
F = Face

7116 P.L. =
2304 x .037 =
= 36551

Dryer ①
10:35 12:20 2:35 PM 4:40 6:10
Opacity 22 19 19 19 15 13
inlet T 870 860 902 784 754 744 811 = AVL
Fuel 345477 345858 346379 346980 347481 347772
H.S. 19F 22F 24C 22C 22C 22C

7116 P.L. → 2304
8:30 AM R

②
Opacity 35 26 24 18 16 22
inlet T 864 856 855 805 823 834 840 = AVL
Fuel 607253 607697 608279 608994 609630 610039
line speed 22F 22F 22F 22C 22C 22C

15/32 * Trim B
2304 x .037
= 90 ft³
x 43 lbs/ft³
= 3870 lbs
E_c

③
Opacity 39 33 33 32 35 42
inlet T 843 894 865 812 796 889 850 = AVL
Fuel 382011 382460 383064 383868 384486 384987
L.S. 25F 26F 27F 24F 25C 26F

19/32 C
2304 x
.0465
x 42
= 4790
a₁
to
T₁
ca
h₁

④
Opacity 4 3** 31 19 14 12
inlet T 742 696 722 717 = AVL
Fuel 900580 900580 90042 901337 901999 902433
L.S. 0F 0F 24F** 23F 24F 25F

⑤
Opacity 49 21** 38 38 38 38
inlet T 769 824 751 770 783 779 = AVL
Fuel 483651 483661 483870 484037 485280 485742
L.S. 20F 0F 23F 22F 22F 23F

T=0
T shell 168 179 196 198 197 196

meta wood 264955 265465 266303 26707 267104 267367
% gas 0 0 36+ 99.9 100 106 07 1084
% wood 70.1 73.7 10.0 15 15 15

⑥ = See Phil Schmitt used opacity readings starting at 1:19 PM (pages back)

* Need mostly face on 1/4" board, just change one dryer over to
core periodically ** This shows that @ 3 and 4 need calibration
* 40% gas 10% wood setting (standard procedure to restart)

C = Core
F = Face

7/16 P.L. =

$$2304 \times .037 = 85 \text{ ft}^3 \times 43 \frac{\text{lbs}}{\text{ft}^3} = 3655 \text{ lbs}$$

$$44 \text{ PL} \rightarrow 2304 \times .0208 = 48 \text{ ft}^3 \times 46 \frac{\text{lbs}}{\text{ft}^3} = 2208 \text{ lbs}$$

8:30 AM Raining - very wet.

3/3/92

1 pre-load of 3/8"

$$2304 \text{ ft}^3 \times .03125 \text{ ft} = 72 \text{ ft}^3 \times 46 \frac{\text{lbs}}{\text{ft}^3} = 3312 \text{ lbs}$$

$$\text{I.P.L. of } \frac{23}{32} = 2304 \times .0599 = 1294 \text{ ft}^3 \times 42 = 5418 \text{ lbs}$$

15/32

$$2304 \times .039 = 90 \text{ ft}^3 \times 43 \frac{\text{lbs}}{\text{ft}^3} = 3870 \text{ lbs}$$

Jim Boswell, actually measured (method 25A) VOC at Clayton as a function of Wax and resin being added to dryer. Saw no difference when resin was not input, but saw a large difference when wax was not input. And people say it won't vaporize, but his measurement says it does.

Ed. Knight

no good correlation between Drive bottom (wet bin) spread and dryer throughput. Compression of wafers in bin can lead to more throughput. Depends on bin level also not just spread.

19/32

$$2304 \times .0465 = 107 \text{ ft}^3 \times 42 = 4790$$

at Silske they moisturize logs in Debarka to keep down fines.

Jim Boswell

says rain doesn't increase moisture. Seasonal differences (moisture in spring) and wood species make bigger difference.

High opacity on dryer #5 during our visit but zero of LEM is high by some 20-21%

Production Mon. 7/2/92:

Shift	ft ³	Downtime
A	523,584	35 min
B	522,046	10
C	0	
D	0	
total	1,050,624	45 min

density $\frac{43}{32} = 42$
density $\frac{46}{8} = 46$
1 pre-load =
 $12 \times 6 \times 4 \times 8 = 2304 \text{ ft}^3$
thickness $\frac{23}{32} = .0599$
 $\frac{3}{8} = .03125$

dryer throughput: $\frac{\text{dryer lbs}}{\text{hr}} = \frac{\text{TON FP} \times \frac{2000 \text{ lbs}}{\text{TON FP}}}{1.22} =$

07 1085

hr. 9:10-6:00 PM

07 1084

5 pages back

over to

need calibration

he didn't use these words
 J. Roswell said they consider Silsbee to
 be like their basic design wells now - others
 are too small to ~~be~~ ~~propose~~ have enough
 production

③ Plant uses 9%
 core → 2.5 MDE — 100% solids, gel is main
 Face 6.5% PF } → 50% solids, 50% water
 ↳ ~~knowing~~ is resin

④ Mike W. of Mike says they may increase ID
 for ^{ACFM} on lower stacks and go to higher
 Outlet Temp (2250F) in order to reduce
 condensation in stack and therefore reduce
 opacity.

Ryan op → Chris records strip chart inlet Temp.
 Calvin in reads digital valve

Da	
26	1
27 28	14
25	14
26	14
25	14
26	13
	14
24 25	14
24 25	12
8 (206	8 III
26	Dr
24	
24	
x 24	
24 25	
24 25	
85700	
22400	
5187600	
17520	
26	
5124	
25	Dr
23	
22	
23	
22	
23	
22	
26	
07 1086	23
	23

154,800
19600
91135200 23 15,600 2/24 9:50 pm
15022 101154800
101230
DRYER #2 (Average 14,571) (AVG. d.s. = 23)
22 13,600 2/25 10:45 Am 820 7.0
23 13,200 2/27 3:30 pm 808 8
24 16,400 2/25 4:55 pm 807 7
22 16,400 2/25 2:15 pm 827 7.5
24 14,000 2/25 7:10 pm 805 7.9
24 14,400 2/25 3:50 pm 822 8
24 14,000 2/25 6:30 pm 810 8.2
71163 71102,000
23 14 581

AVG. d.s. = 25
DRYER #5 (AVG. 15,600)

25 14,400 2/28 12 N 820 9
24 15,600 2/28 4:25 820 9
25 15,600 2/28 1 pm 825 11
25 16,400 2/28 3:10 pm 826 9
25 16,000 2/28 3:30 pm 822 9
25 15,600 3/2 11:15 Am 800 7.5

61149 6193,600
25 15,600

Average - Average
15,000 #1
14,600 #2
14,700 #3
16,300 #4
15,600 #5
5176,200
15,240 lbs/hr

Comparing fresh production would be

$$15240 \frac{\text{lbs}}{\text{hr}} = \frac{\text{Tons FP} \times \frac{2000 \text{ lbs}}{\text{Tons FP}}}{.78} = 071088$$

$$\text{Tons FP} = \frac{15240}{.78} = 19539.74$$

$$5.9 \frac{\text{Tons}}{\text{hr}} \times \frac{24 \text{ hrs}}{\text{day}} = 143.2 \frac{\text{Tons}}{\text{day}}$$

purchase clay on 6-2-05

3/4/0

meter	CE
inside Control Room	
60070	- 5th
02	
03	
01	
20	
2050	Nine
21500	Thas
20500	R
19500	Dryer
Throughput	
17,500	
17,500	
16,500	
15,500	
14,500	
13,500	
12,500	
20	

All papers shut off for maintenance
Phil Schindt

(7)

opacity on metal in box on Stock Certificate

7 810 8.2

2250

10

10

This meter may not read directly, but the one in the control room is supposed to.

Newer logs being loaded into storage pile

Δ ← This is a point on graph

Thes. 3/3 production went down 850,000,000 ft
per chest on QK Lab wall

This is a point on graph

822 9

Am 800 7.5

19500

Draper #10

Dryer #4 Δ

Disc #2

Throughput

18,500

17,500

16,500

15/506

14/5/20

3,500

2,500

20 21 22 23 24 25 26

Wet bottom speed

78 (153440)

$$5.9 \frac{\text{tons}}{\text{hr}} \times \frac{24 \text{ hrs}}{1 \text{ day}} =$$

1,025,280 ft² which is 222

$$\frac{1625 \text{ FP}}{100} =$$

11
furnace dryer on
5 x 205 056 =

337

~~07 1089~~

3/

Calculate dryer throughput using finished product (FP);

On 3/4/92 production (per press report):

Shift A (6 AM - 6 PM) 523,584 #12

4726023

= 15,200

117 press loads of 3/32" all during our test days

117 p.L. x 5418 lbs. = 633,906 lbs

P.L. of 3/32"

÷ 2000 = 316.95 317 tons FP

4.4

13,600

15,200

15,600

14,800

14,400

15,600

15,600

14,400

16,000

3 press loads of 3/8"

3 p.L. x 3240 lbs = 9,720 lbs

= 5 tons

35 d.t. min

35 min
downtime
total time

~ 11.5 hrs.

total tons FP during 12 hr. shift =

317

+ 5

322 tons FP

157,200

÷ 9

= 15,244

~ 15,250

Assume fines loss = 15% and trim

loss = 7% total loss from dryer before

gross = 22%

19 3/4"

64954

dryer lbs/hr =

$\frac{322 \text{ tons} \times 2000 \text{ lbs}}{11.5 \text{ hrs}} = 071090$

$\frac{68853 \text{ lbs}}{71,295 \text{ hr}} \rightarrow 14359 \text{ lbs/hr}$
for 5 dryers → 71,761 hr per dryer

dryer

end product (FP):

Using dump truck measurements on 3/2/92
we saw: (must subtract 15% from)

4726043
= 15,700

ring out

dryer #3 14,000 lbs/hr.
#4 17,600
#5 15,600

633,906 lbs

average 15,700 - 1570 = 14130
~~pretty close!~~

Try another day - on 2/28 we had 4
dryers measured by dumps:

tons FP

13,600
15,200
15,600
14,800
14,400
15,600
15,600
16,400
16,000

720 lbs

dryer #2 13,600 lbs/hr.
#5 14,400 - 16,400 (5 dumps)
#4 15,200, 15,600 (2)
#3 14,800

average 15,250 lbs/hr. - 1525 =
~~13,725 lbs/hr.~~

net =

137,200
= 9
= 15,244
~ 15,250

On 2/28 production was:

1 p.l. 15/32 = 3870 lbs
13 p.l. 7/16 = 13 x 3655 = 47,515 lbs
67 p.l. 19/32 = 67 x 4790 = 292,190
87 p.l. 7/16 = 87 x 3655 = 317,985

net from
dryer
before

19/32 =
64958

661,560 lbs
in 12 hrs = 59 min
~ 11 hrs
= 60142 lbs/hr

07 1090

11/2

dryer $\frac{155}{hr.} = \frac{60142}{1 - .22} = 77,105 \frac{lbs}{hr.} \div 5 \text{ dryers} = 15421 \frac{lbs}{hr.}$
hr. 07 1091

14359 lbs
5776/hr
per dryer

= 15421 lbs/hr. pretty close!
when we look at several dryers.

Summary of Important Silsbee Findings

- ~~Possible Non-compliance issues~~ ^{is needed} ^{is off} ^{W2}
- procedures
- ① Specify $>20\%$ (and calibration / zeroing) ^{is needed} ^{is off} ^{W2}
and training of operators on what to do if $>20\%$ ^{W2}
 - ② Inlet Temp $>820^{\circ}\text{F}$ (and calibration of ^{need} strip chart and digital) (and need training / procedures of what to do if it exceeds 820°F). Need better strip charts if they are really supposed to read them for inlet temp. ⁽⁶⁾ ^{W2}
 - ③ How will state enforce its dryer throughput limits? ^(include fines, moisture correction? Will throughput be based on dryer dumps or on press production?) ⁽⁷⁾ ^{W2}
 - ④ Process is not like a chemical plant ^{own statement} per LPSA since it's not, significantly can't control (limit) pollution through process controls - better to use actual control (instrumentation) to reduce pollution - ^(W2 PM) ⁽⁸⁾ ^{W2}
or ^{at least} to stack sample frequently ^{control a}
(once every 3-6 months for key pollutants - probably CO, VOC, PM, formaldehyde). Can that be frequent sampling? would be cheaper than controls ^{does} ^{W2}
 - ⑤ In order to really have good estimate on emissions from press, it would have to be analyzed (forming line, press, ^{and} unloader) ⁽⁹⁾ ⁽¹⁰⁾ ^{W2}

Findings needed (is off)

(zeroing)

do it > 20%

ation of

and need

to do if it

the strip charts

inlet temp.

its dryer

store

dump

real plant

comparably

section

- Ketter

DOE

(WSP - PM)

eventually

des

2C, PM,

the of present

I estimate

it

P (

unloader)

07 1032

We can compare Silsbee's emissions with an enclosed press first to see if we feel comfortable estimating fugitives that way.

(6) Draining & decamping multiclone clean out to ground may be a problem. Should sample effluent to see if it meets TCLP.

(7) T-0 heater had been vented directly to atmosphere, not through NO.1 and NO.2 dryers and their multiclones, before our arrival - No control for particulates when this is done.

(8) Doesn't seem to be a lot of environmental control awareness at plant. Seems like J. Boswell does all the env. work and that people at plant are most concerned with production. This reveals a lack of response to out-of-compliance conditions (opacity, high inlet temps) and out of calibration monitoring equipment (opacity, inlet T, strip charts - vs - digital)

(9) See in Stack tests of 2/27 - 2/28 had lower VOC emissions than other test days. On those days they were primarily using older logs.

(9) cyclone for dump of fuel fines (SP003) needs new bags or a new, larger cyclone as is needed. Lots of PM emitted when fuel bins are high. Probably due to faulty cyclone. (Happened frequently,)

07 1093

(CP0073)
EPN 13)

- ⑩ Stack from blending emits constant flow of moisture and particulate. May contain VOC and formaldehyde. Emissions as viewed from roof,

looked significant. Should be sampled but will need sampling platform, safety lines, parts, etc.

- ⑪ Compare steel tests on press vents with thickness of board being produced. Thinner boards seemed to have greater emissions.

- ⑫ Look through notes for other possible reasons for any unusual stack test results. Ask Rich Ida and Al Borden also.

- ⑬ ⑭ MFC intends to put larger ID fans on dryers and raise dryer outlet temp to reduce opacity in future. This may not require permit amendment, but should be evaluated.

- ⑮ ⑯ Two heaters may have to be replaced by larger one. Its shell temp gets high unless it's run on gas periodically each day. This ^{may} ~~will~~ probably require permit amendment.

How to understand permit emissions that must be met and how they relate to your job

