

Note: This is a reference cited in AP 42, *Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

**REPORT OF
AIR EMISSIONS TESTS
FOR
KIRBY FOREST INDUSTRIES
SILSBEE OSB PLANT**

**Silsbee, Texas
February 24, through March 6, 1992**

**Performed By:
Environmental Monitoring Laboratories
Ridgeland, Mississippi
(601-856-3092)**

ENVIRONMENTAL MONITORING LABORATORIES, INC.

P.O. Box 655 * 224-B Hwy 51 North
Ridgeland, Mississippi 39158

(601) 856-3092

April 24, 1992

Subject: Louisiana Pacific Corporation's Kirby Forest Industries
Silsbee, Texas OSB Plant

During the period February 24, 1992, through March 6, 1992, Environmental Monitoring Laboratories conducted air emissions tests for Kirby Forest Industries' OSB facility in Silsbee, Texas. Testing was performed to determine emissions of particulate (PM), PM₁₀, VOC, HCHO, and CO emissions from five OSB dryers and five press vents stacks in accordance with requirements of the Environmental Protection Agency.

A summary of stack test results in pounds per hour:

	PM	PM10	VOC	HCHO	CO
Dryer No. 1	15.9	17.9	41.8	0.16	14.9
Dryer No. 2	15.3	14.6	39.0	0.22	17.4
Dryer No. 3	13.2	14.6	45.4	0.39	3.80
Dryer No. 4	14.2	17.5	38.0	0.50	11.3
Dryer No. 5	15.9	15.7	39.4	0.35	4.10
Press Vent 1	1.01	----	9.92	0.53	1.82
Press Vent 2	0.79	----	14.4	0.40	1.91
Press Vent 3	0.45	----	9.58	0.73	1.86
Press Vent 4	1.21	----	9.23	0.54	1.77
Press Vent 5	0.70	----	8.29	0.39	1.62

The project was coordinated by Dr. James T. Boswell of Louisiana Pacific Corporation. Dr. Boswell was also responsible for acquiring and documenting plant operating records during test periods and descriptions and illustrations of processes and process flow. Daniel G. Russell of Environmental Monitoring Laboratories coordinated testing efforts and was responsible for the collection and analysis of all but PM₁₀ and formaldehyde samples. The PM, VOC, and CO sampling was performed by the field team of Daniel G. Russell, Rodney Moore, and Brad McKnight. Sample custody was limited to Mr. Russell. Formaldehyde sampling was done by Industrial and Environmental Analysts (P.O. Box 12846, RTP, North Carolina). The formaldehyde testing and reporting was coordinated by Mr. Jeffrey Burdette and conducted by a field team headed by Mr. John Sokash. PM10 sampling was performed by Armstrong Environmental, Inc. (4747 Irving Boulevard, #204, Dallas, Texas 75247). That testing was coordinated and reported by Mr. Tom Armstrong of Armstrong Environmental.

Plant and process operation was supervised by Mr. Ed Knight, plant manager. Mr. Mike Hudson and Mr. Mike Weindorfer of MEC Company were present to assist in coordinating dryer operation with testing. Environmental Protection Agency representatives Mr. Richard Ida, Mr. Al Bandur and Mr. Al Nugent (of MRI) were present to observe testing and plant operation.

Following is a report of the test.

REPORT OF AIR EMISSIONS TESTS
FOR KIRBY FOREST INDUSTRIES
SILSBEE OSB PLANT
SILSBEE, TEXAS
FEBRUARY 24, THROUGH MARCH 6, 1992

CONTENTS

1.0 Test Results	page 1
2.0 Source Description	11
3.0 Test Procedures	12
4.0 Data Reduction	13
5.0 Nomenclature	36
6.0 Calibration Procedures	37
7.0 Sample Train Configurations	38
8.0 Stack Configurations	41
9.0 Appendices	46

- A. Sampling and Analytical Data
- B. Calibration Data
- C. VOC/CO Recorder Trace
- D. 02-24-92 Test of No. 1 Dryer

REPORT CERTIFICATION

I certify that I have examined the information submitted herein, and based upon my inquiries of those directly responsible for obtaining the data or upon my direct acquisition of the data, I believe the submitted information is true, accurate and complete.

Signed



Daniel G. Russell

1.0 Test Results: The following tables present the measured flow parameters and test results for three separate emissions samples for each of 5 OSB dryer stacks and each of 5 press vents at Kirby Forest Industries in Silsbee, Texas during the period February 24, through March 6, 1992.

1.1 No. 1 Dryer:

1.1.1 PM, CO, VOC test: The results reported here are from the second of two tests done on Dryer No. 1. The first set of tests (done on 2-24-92) was rejected when it was discovered that the thermal oil heater exhaust was not directed to the dryer as has been intended. Data from the first test is provided in this report as Appendix D. Calculations from that test are found in Section 4.0.

Run. No.		1	2	3	avg.
Date		02-26-92	02-27-92	02-27-92	-----
Time start		1545	0904	1042	-----
Time end		1703	1009	1213	-----
PM EMISSIONS	#/hr.	15.9	13.8	15.6	15.1
PM EMISSIONS	gr/dscf	0.060	0.051	0.059	0.057
CPM EMISSIONS	#/hr.	0.92	0.69	0.91	0.84
CPM EMISSIONS	gr/dscf	0.003	0.003	0.003	0.003
PMT EMISSIONS	#/hr.	16.8	14.5	16.5	15.9
PMT EMISSIONS	gr/dscf	0.063	0.054	0.062	0.060
CO EMISSIONS	#/hr.	12.2	18.5	14.1	14.9
CO EMISSIONS	ppmv	90	135	105	110
VOC EMISSIONS	#/hr. as C	42.6	36.8	46.0	41.8
VOC EMISSIONS	ppmv as C	735	628	801	722
VOLUMETRIC FLOWRATE	acfm	45252	45623	44652	45176
VOLUMETRIC FLOWRATE	dscfm	30965	31344	30693	31001
VELOCITY	ft./sec.	78.4	79.0	77.4	78.3
STACK TEMPERATURE	degrees F	188	185	187	186
MOISTURE	%	15.9	16.0	15.7	15.9
SAMPLE RATE	%isokinetic	98	101	99	100

1.1.2 PM₁₀ sampling: (Performed and reported in detail by Armstrong Environmental)

Run. No.		1	2	3	avg.
Date		03-05-92	03-05-92	03-05-92	-----
Time start		0949	1216	1446	-----
Time end		1118	1426	1654	-----
PM10 EMISSIONS	#/hr.	17.4	18.4	17.8	17.9
>PM10 EMISSIONS	#/hr.	0.60	0.55	0.56	0.57
PM10 EMISSIONS	% of total	96.67	97.10	96.95	96.90

1.1.3 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		03-03-92	03-03-92	03-03-92	-----
Time start		1307	1550	1728	-----
Time end		1445	1700	1832	-----
HCHO EMISSIONS	#/hr.	0.26	0.14	0.10	0.16
HCHO EMISSIONS	ppm	2.03	0.95	0.64	1.21

1.2 No. 2 Dryer

1.2.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		02-25-92	02-25-92	02-25-92	-----
Time start		1342	1608	1825	-----
Time end		1444	1711	1935	-----
PM EMISSIONS	#/hr.	18.8	12.1	11.6	14.2
PM EMISSIONS	gr/dscf	0.071	0.046	0.044	0.054
CPM EMISSIONS	#/hr.	1.02	1.23	1.20	1.15
CPM EMISSIONS	gr/dscf	0.004	0.005	0.005	0.004
Pmt EMISSIONS	#/hr.	19.8	13.4	12.8	15.3
Pmt EMISSIONS	gr/dscf	0.075	0.051	0.049	0.058
CO EMISSIONS	#/hr.	14.7	22.8	14.6	17.4
CO EMISSIONS	ppmv	110	170	110	130
VOC EMISSIONS	#/hr. as C	44.3	37.4	35.4	39.0
VOC EMISSIONS	ppmv as C	774	650	621	682
VOLUMETRIC FLOWRATE	acfm	45623	45699	45085	45469
VOLUMETRIC FLOWRATE	dscfm	30586	30740	30472	30599
VELOCITY	ft./sec.	79.0	79.2	78.1	78.8
STACK TEMPERATURE	degrees F	189	184	186	186
MOISTURE	%	16.7	17.0	16.4	16.7
SAMPLE RATE	%isokinetic	104	100	104	103

1.2.2 PM₁₀ sampling: (Performed and reported in detail by Armstrong Environmental)

Run. No.		1	2	3	avg.
Date		03-05-92	03-05-92	03-05-92	-----
Time start		0922	1151	1412	-----
Time end		1124	1350	1615	-----
PM10 EMISSIONS	#/hr.	17.2	14.5	12.0	14.6
>PM10 EMISSIONS	#/hr.	0.71	0.87	0.53	0.70
PM10 EMISSIONS	% of total	96.04	94.34	95.77	95.38

1.2.3 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		03-02-92	03-02-92	03-03-92	-----
Time start		1621	1829	0916	-----
Time end		1740	1940	1022	-----
HCHO EMISSIONS	#/hr.	0.17	0.10	0.40	0.22
HCHO EMISSIONS	ppm	1.22	0.65	2.77	1.54

1.3 No. 3 Dryer

1.3.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		02-26-92	02-27-92	02-27-92	-----
Time start		0924	1105	1303	-----
Time end		1032	1229	1421	-----
PM EMISSIONS	#/hr.	12.2	12.1	12.6	12.3
PM EMISSIONS	gr/dscf	0.046	0.046	0.047	0.046
CPM EMISSIONS	#/hr.	0.92	1.05	0.68	0.88
CPM EMISSIONS	gr/dscf	0.003	0.004	0.003	0.003
Pmt EMISSIONS	#/hr.	13.1	13.2	13.3	13.2
Pmt EMISSIONS	gr/dscf	0.049	0.050	0.050	0.050
CO EMISSIONS	#/hr.	2.04	5.31	4.05	3.80
CO EMISSIONS	ppmv	15	40	30	28
VOC EMISSIONS	#/hr. as C	41.2	47.6	47.3	45.4
VOC EMISSIONS	ppmv as C	707	836	817	786
VOLUMETRIC FLOWRATE	acfm	45615	44580	44700	44965
VOLUMETRIC FLOWRATE	dscfm	31186	30454	30944	30861
VELOCITY	ft./sec.	79.0	77.2	77.4	77.9
STACK TEMPERATURE	degrees F	185	183	183	184
MOISTURE	%	16.4	16.7	15.6	16.2
SAMPLE RATE	%isokinetic	95	97	96	96

1.3.2 PM₁₀ sampling: (Performed and reported in detail by Armstrong Environmental)

Run. No.		1	2	3	avg.
Date		03-03-92	03-03-92	03-03-92	-----
Time start		0910	1137	1410	-----
Time end		1114	1345	1527	-----
PM10 EMISSIONS	#/hr.	15.4	13.9	14.4	14.6
>PM10 EMISSIONS	#/hr.	3.19	2.05	1.75	2.33
PM10 EMISSIONS	% of total	82.84	87.15	89.16	86.38

1.3.3 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		03-02-92	03-02-92	03-06-92	-----
Time start		0909	1118	1011	-----
Time end		1025	1235	1117	-----
HCHO EMISSIONS	#/hr.	0.53	0.40	0.25	0.39
HCHO EMISSIONS	ppm	3.74	2.80	1.74	2.76

1.4 No. 4 Dryer

1.4.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		02-27-92	02-27-92	02-28-92	-----
Time start		1516	1702	1048	-----
Time end		1618	1812	1048	-----
PM EMISSIONS	#/hr.	12.9	13.5	13.0	13.1
PM EMISSIONS	gr/dscf	0.047	0.050	0.048	0.048
CPM EMISSIONS	#/hr.	0.85	1.53	0.95	1.11
CPM EMISSIONS	gr/dscf	0.003	0.006	0.004	0.004
Pmt EMISSIONS	#/hr.	13.8	15.0	13.9	14.2
Pmt EMISSIONS	gr/dscf	0.050	0.056	0.052	0.053
CO EMISSIONS	#/hr.	23.5	5.46	4.81	11.3
CO EMISSIONS	ppmv	170	40	35	82
VOC EMISSIONS	#/hr. as C	38.5	36.8	38.5	38.0
VOC EMISSIONS	ppmv as C	649	630	655	645
VOLUMETRIC FLOWRATE	acfm	45761	44688	45181	45210
VOLUMETRIC FLOWRATE	dscfm	31733	31267	31473	31491
VELOCITY	ft./sec.	79.3	77.4	78.3	78.3
STACK TEMPERATURE	degrees F	179	176	176	177
MOISTURE	%	16.4	16.7	15.6	16.2
SAMPLE RATE	%isokinetic	95	97	96	96

1.4.2 PM₁₀ sampling: (Performed and reported in detail by Armstrong Environmental)

Run. No.		1	2	3	avg.
Date		03-02-92	03-02-92	03-02-92	-----
Time start		1054	1425	1650	-----
Time end		1311	1623	1853	-----
PM10 EMISSIONS	#/hr.	16.4	18.2	18.0	17.5
>PM10 EMISSIONS	#/hr.	1.81	0.95	2.00	1.59
PM10 EMISSIONS	% of total	90.06	95.04	90.00	91.70

1.4.3 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		03-05-92	03-05-92	03-06-92	-----
Time start		1420	1700	0822	-----
Time end		1522	1804	0927	-----
HCHO EMISSIONS	#/hr.	0.37	0.56	0.58	0.50
HCHO EMISSIONS	ppm	2.55	3.95	3.89	3.46

1.5 No. 5 Dryer

1.5.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		02-28-92	02-28-92	02-28-92	-----
Time start		1149	1426	1611	-----
Time end		1250	1528	1713	-----
PM EMISSIONS	#/hr.	17.1	13.5	14.5	15.0
PM EMISSIONS	gr/dscf	0.064	0.050	0.053	0.056
CPM EMISSIONS	#/hr.	0.97	0.76	0.93	0.89
CPM EMISSIONS	gr/dscf	0.004	0.003	0.003	0.003
Pmt EMISSIONS	#/hr.	18.1	14.3	15.4	15.9
Pmt EMISSIONS	gr/dscf	0.068	0.053	0.057	0.059
CO EMISSIONS	#/hr.	4.76	4.10	3.44	4.10
CO EMISSIONS	ppmv	35	30	25	30
VOC EMISSIONS	#/hr. as C	43.7	35.3	39.1	39.4
VOC EMISSIONS	ppmv as C	750	603	663	672
VOLUMETRIC FLOWRATE	acfm	44917	45285	45646	45283
VOLUMETRIC FLOWRATE	dscfm	31145	31293	31562	31334
VELOCITY	ft./sec.	77.8	78.5	79.1	78.4
STACK TEMPERATURE	degrees F	174	175	175	175
MOISTURE	%	16.8	16.9	16.8	16.8
SAMPLE RATE	%isokinetic	98	98	97	97

1.5.2 PM₁₀ sampling: (Performed and reported in detail by Armstrong Environmental)

Run. No.		1	2	3	avg.
Date		03-02-92	03-02-92	03-02-92	-----
Time start		0945	1331	1638	-----
Time end		1200	1535	1840	-----
PM10 EMISSIONS	#/hr.	15.0	15.3	16.7	15.7
>PM10 EMISSIONS	#/hr.	3.11	1.74	2.75	2.53
PM10 EMISSIONS	% of total	82.83	89.79	85.86	86.16

1.5.3 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		03-05-92	03-05-92	03-05-92	-----
Time start		0917	1111	1245	-----
Time end		1021	1216	1350	-----
HCHO EMISSIONS	#/hr.	0.34	0.36	0.34	0.35
HCHO EMISSIONS	ppm	2.37	2.48	2.32	2.39

1.6 No. 1 Press Vent

1.6.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		03-02-92	03-02-92	03-02-92	-----
Time start		1514	1631	1753	-----
Time end		1616	1733	1854	-----
PM EMISSIONS	#/hr.	0.75	0.96	0.51	0.74
PM EMISSIONS	gr/dscf	0.002	0.003	0.001	0.002
CPM EMISSIONS	#/hr.	0.39	0.10	0.33	0.27
CPM EMISSIONS	gr/dscf	0.003	0.003	0.002	0.003
PMT EMISSIONS	#/hr.	1.14	1.06	0.84	1.01
PMT EMISSIONS	gr/dscf	0.003	0.003	0.002	0.003
CO EMISSIONS	#/hr.	1.76	1.85	1.84	1.82
CO EMISSIONS	ppmv	10	10	10	10
VOC EMISSIONS	#/hr. as C	7.76	9.22	12.8	9.92
VOC EMISSIONS	ppmv as C	103	116	162	127
VOLUMETRIC FLOWRATE	acfm	43387	45680	45434	44834
VOLUMETRIC FLOWRATE	dscfm	40290	42422	42206	41639
VELOCITY	ft./sec.	36.8	38.8	38.6	38.1
STACK TEMPERATURE	degrees F	99	100	100	100
MOISTURE	%	2.12	1.97	1.93	2.00
SAMPLE RATE	%isokinetic	100	96	93	96

1.6.2 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		02-27-92	02-27-92	02-27-92	-----
Time start		0833	1040	1236	-----
Time end		0944	1145	1340	-----
HCHO EMISSIONS	#/hr.	0.50	0.50	0.59	0.53
HCHO EMISSIONS	ppm	2.11	2.02	2.41	2.18

1.7 No. 2 Press Vent
1.7.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		03-01-92	03-01-92	03-01-92	-----
Time start		1444	1614	1735	-----
Time end		1545	1715	1836	-----
PM EMISSIONS	#/hr.	0.38	0.68	0.72	0.59
PM EMISSIONS	gr/dscf	0.001	0.002	0.002	0.002
CPM EMISSIONS	#/hr.	0.14	0.25	0.21	0.20
CPM EMISSIONS	gr/dscf	0.0004	0.0006	0.0006	0.0005
Pmt EMISSIONS	#/hr.	0.52	0.92	0.94	0.79
Pmt EMISSIONS	gr/dscf	0.001	0.002	0.003	0.002
CO EMISSIONS	#/hr.	1.88	1.96	1.88	1.91
CO EMISSIONS	ppmv	10	10	10	10
VOC EMISSIONS	#/hr. as C	11.0	17.2	14.9	14.4
VOC EMISSIONS	ppmv as C	137	205	185	176
VOLUMETRIC FLOWRATE	acfm	46103	48441	46335	46966
VOLUMETRIC FLOWRATE	dscfm	43027	44928	43173	43709
VELOCITY	ft./sec.	39.1	41.1	39.4	39.9
STACK TEMPERATURE	degrees F	99	101	99	100
MOISTURE	%	1.61	1.80	1.80	1.74
SAMPLE RATE	%isokinetic	94	93	94	94

1.7.2 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		02-26-92	02-26-92	02-26-92	-----
Time start		1126	1357	1615	-----
Time end		1232	1501	1718	-----
HCHO EMISSIONS	#/hr.	0.37	0.41	0.42	0.40
HCHO EMISSIONS	ppm	1.42	1.59	1.62	1.55

1.8 No. 3 Press Vent

1.8.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		03-02-92	03-02-92	03-02-92	-----
Time start		0938	1104	1231	-----
Time end		1039	1205	1332	-----
PM EMISSIONS	#/hr.	0.45	0.55	0.35	0.45
PM EMISSIONS	gr/dscf	0.001	0.001	0.001	0.001
CPM EMISSIONS	#/hr.	0.10	0.20	0.41	0.24
CPM EMISSIONS	gr/dscf	0.0003	0.0005	0.0011	0.0006
PMT EMISSIONS	#/hr.	0.55	0.74	0.76	0.68
PMT EMISSIONS	gr/dscf	0.001	0.002	0.002	0.002
CO EMISSIONS	#/hr.	1.89	1.86	1.84	1.86
CO EMISSIONS	ppmv	10	10	10	10
VOC EMISSIONS	#/hr. as C	10.6	10.1	8.07	9.58
VOC EMISSIONS	ppmv as C	131	127	102	120
VOLUMETRIC FLOWRATE	acfm	46302	45933	44983	45739
VOLUMETRIC FLOWRATE	dscfm	43270	42740	42140	42716
VELOCITY	ft./sec.	39.3	39.0	38.2	38.8
STACK TEMPERATURE	degrees F	100	101	99	100
MOISTURE	%	1.45	1.62	1.32	1.46
SAMPLE RATE	%isokinetic	97	95	95	95

1.8.2 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		02-28-92	02-28-92	02-28-92	-----
Time start		1255	1440	1622	-----
Time end		1400	1546	1728	-----
HCHO EMISSIONS	#/hr.	0.68	0.74	0.76	0.73
HCHO EMISSIONS	ppm	2.83	2.99	3.07	2.96

1.9 No. 4 Press Vent
1.9.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		02-29-92	02-29-92	02-29-92	-----
Time start		1220	1456	1643	-----
Time end		1321	1609	1744	-----
PM EMISSIONS	#/hr.	1.02	0.94	0.59	0.85
PM EMISSIONS	gr/dscf	0.003	0.003	0.002	0.002
CPM EMISSIONS	#/hr.	0.19	0.57	0.58	0.44
CPM EMISSIONS	gr/dscf	0.004	0.004	0.003	0.004
Pmt EMISSIONS	#/hr.	1.21	1.51	1.17	1.30
Pmt EMISSIONS	gr/dscf	0.004	0.004	0.003	0.004
CO EMISSIONS	#/hr.	1.75	1.78	1.78	1.77
CO EMISSIONS	ppmv	10	10	10	10
VOC EMISSIONS	#/hr. as C	9.91	7.71	10.1	9.23
VOC EMISSIONS	ppmv as C	132	101	132	122
VOLUMETRIC FLOWRATE	acfm	42921	43810	43937	43556
VOLUMETRIC FLOWRATE	dscfm	40134	40879	40743	40585
VELOCITY	ft./sec.	36.4	37.2	37.3	37.0
STACK TEMPERATURE	degrees F	90	92	93	92
MOISTURE	%	2.54	2.49	2.84	2.62
SAMPLE RATE	%isokinetic	93	93	94	93

1.9.2 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		02-27-92	02-27-92	02-28-92	-----
Time start		1437	1717	0910	-----
Time end		1625	1822	1018	-----
HCHO EMISSIONS	#/hr.	0.53	0.54	0.54	0.54
HCHO EMISSIONS	ppm	2.13	2.14	2.08	2.12

1.10 No. 5 Press Vent
1.10.1 PM, CO, VOC test:

Run. No.		1	2	3	avg.
Date		03-01-92	03-01-92	03-01-92	-----
Time start		0953	1119	1321	-----
Time end		1054	1220	1422	-----
PM EMISSIONS	#/hr.	0.53	0.05	0.49	0.36
PM EMISSIONS	gr/dscf	0.001	0.0001	0.001	0.001
CPM EMISSIONS	#/hr.	0.14	0.35	0.54	0.34
CPM EMISSIONS	gr/dscf	0.0004	0.0009	0.0014	0.0009
PMT EMISSIONS	#/hr.	0.67	0.39	1.03	0.70
PMT EMISSIONS	gr/dscf	0.002	0.001	0.003	0.002
CO EMISSIONS	#/hr.	0.98	1.94	1.94	1.62
CO EMISSIONS	ppmv	5	10	10	8
VOC EMISSIONS	#/hr. as C	6.63	9.88	8.37	8.29
VOC EMISSIONS	ppmv as C	79	119	100	99
VOLUMETRIC FLOWRATE	acfm	47966	47253	47669	47629
VOLUMETRIC FLOWRATE	dscfm	44964	44427	44571	44654
VELOCITY	ft./sec.	40.7	40.1	40.5	40.4
STACK TEMPERATURE	degrees F	95	95	97	95
MOISTURE	%	1.93	1.60	1.69	1.74
SAMPLE RATE	%isokinetic	93	96	93	94

1.10.2 HCHO sampling: (Performed and reported in detail by Industrial and Environmental Analysts)

Run. No.		1	2	3	avg.
Date		02-29-92	02-29-92	02-29-92	-----
Time start		1018	1201	1336	-----
Time end		1122	1304	1440	-----
HCHO EMISSIONS	#/hr.	0.40	0.39	0.36	0.39
HCHO EMISSIONS	ppm	1.62	1.59	1.44	1.55

2.0 Source Description: Kirby Forest Industries' oriented strand board (OSB) facility in Silsbee, Texas produces oriented strand board from southern pine timber.

Five (5) identical MEC Company rotary dryers are used to dry wood flakes used in the board construction. Particulate emissions from each of the rotary dryers are controlled by a multi-cyclone. Each identical system exhausts to the atmosphere by way of a 42.0 inch diameter stack. Two sample ports are provided at a location which is approximately 28 feet (8.0 diameters) below the stack exit and 50 feet (14 diameters) above the blower inlet to the stack.

Five (5) roof vents exhaust to the atmosphere from the forming line and press area. By design, the axial fans moving air through the roof vents provide a turbulent air flow inappropriate for measurement by standard methods. In order to provide a suitably laminar air flow, a short stack extension and straightening vanes were installed. The dimensions of the stack extension do not meet minimum requirements of standard sampling procedures. The extensions are 60 inch diameter vertical stacks approximately 44 inches high added to the existing fan shroud. Straightening vanes were installed at a point approximately 18 inches above the axial fan blades. Two sample ports were installed at 90° in the extensions at a point approximately 30 inches below the stack exit and approximately 14 inches above the straightening vanes.

Sketches of the stacks illustrating dimensions and selection of sampling points are provided in Appendix A.

Detailed descriptions of the processes and operating rates, and operating conditions during the tests are supplied by Kirby Forest Industries under separate cover.

3.0 Test Procedures: Test procedures used are generally those described in the Code of Federal Regulations, Title 40, Part 60, Appendix A. Specifically those procedures used were Method 1 to determine the number of sample points (with the aforementioned exception), Method 3 to determine carbon dioxide and oxygen content of the stack gas, and Method 5 (incorporates Methods 2 and 4) to determine flow rates, moisture content, and particulate emissions. The sampling train used is identical to that described in Method 5 except that no cyclone was used. VOC emissions were measured using Method 25A (continuous monitoring with a flame ionization detector). The Ratfish™ FID is equipped with multiple scales. The 0 to 1000 ppm scale was used for measurement of stack concentrations of VOC as propane. Calibrations were made using certified propane in nitrogen mixtures in nominal concentrations of 31, 82 and 830 ppm. Charcoal filtered air was used for zero. To obtain results as methane (CH₄) (or as carbon), measured concentrations were increased by a factor of three. Carbon monoxide concentration was determined using the continuous sampling technique described in Method 10 using a Beckman model 864 NDIR analyzer. The discrimination ratios for CO₂ and moisture are very low and accordingly, the silica gel and ascarite traps were omitted. The exhaust of the NDIR was captured in a Tedlar™ bag for the Method 3 determination. In addition, the contents of the Tedlar bags was redirected to the NDIR at the conclusion of each run in order to obtain a trace of the composited sample. Schematics of the sample trains are included in section 7.0 of this report.

Particulate matter of less than 10 microns (PM₁₀) was determined using the EPA proposed method 201A/CSR: 55 FR 14246 (4/17/90) using an Andersen PM₁₀ cyclone. This testing was done by Armstrong Environmental and is reported under separate cover.

Formaldehyde emissions were measured using the BIF Method 0011. Formaldehyde testing was done by Industrial and Environmental Analysts and is reported under separate cover.

The particulate determination differed slightly from Method 5 in that the "back half" portion of the sample was captured (distilled water used in impingers) and analyzed for condensible particulate (CPM) using a methylene chloride extraction. Recovered samples were extracted four times with 15 milliliter portions of methylene chloride. The aqueous fraction was evaporated over low heat and the residue weight determined gravimetrically. The organic fraction was evaporated at room temperature and the residue weight determined gravimetrically.

Particulate filters were recovered by rinsing the front half of the filter holder into the probe wash and securing the filters in glass petri dishes. Filters were heated in an oven for 2 hours at 105° C, desiccated at least 24 hours and weighed to constant weight. Probe wash samples in acetone were evaporated to dryness over low heat in tarred beakers, desiccated for at least 24 hours and weighed to constant weight. Weighings are made at 6 hour or greater intervals (samples stored in desiccator). Final weights are considered valid and are recorded if there is no more than 0.5 milligrams difference from the previous weighing.

Equipment calibrations are described in Section 6.0. Calibration data is in Appendix C.

Calculations were made using a computer spreadsheet. Each new spreadsheet is generated from a master one which has constant values so that mathematical correctness can be confirmed with each use.

4.0 Data Reduction

RESECTED

Kirby Forest Industries - Silsbee OSB Facility
 No. 1 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 24, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	9.621128	9.621128	9.621128
2. Dn : in.	.196	.196	.196
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	29.61	29.61	29.61
7. Pg : in. H2O	-.46	-.46	-.46
8. Vm : cf (dry gas)	44.175	43.7	42.187
9. sqr(DP), avg: in.H2O ^{.5}	1.2043	1.2078	1.1889
10. DH : in. H2O	1.6875	1.6667	1.6083
11. ts : degrees F	190.92	187.17	185.50
12. tm : degrees F	98.50	105.63	102.42
13. Vlc : ml	187	188.5	194
14. CO2 : percent	.90	1.00	.97
15. O2 : percent	19.53	19.30	19.43
16. CO : ppm, dry (NDIR)	20	30	20
17.a M,PM : mg (front half)	266.7	187.4	200.5
17.b M,PM aqu: mg (aqu.fraction)	6.8	3	2.3
17.c M,PM org: mg (org.fraction)	8.4	9.5	6.9
18. C,VOC : ppmv as propane,wet	133	N/A	228

187.86

23.33333

N/A

Kirby Forest Industries - Silsbee OSB Facility
 No. 1 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 24, 1992

REJECT ⑥

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	29.73	29.73	29.73	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	29.58	29.58	29.58	N/A
3. An : sq ft ((Dn/24) ²)(3.1416)	2.095e-4	2.095e-4	2.095e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	40.67301	39.72643	38.56433	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	8.80209	8.872695	9.13158	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.1779095	.1825690	.1914542	.1839776
7. Md : mol.wt. dry basis .44 CO ₂ +.32 O ₂ +.28(CO+N ₂)	28.92533	28.932	28.932	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	26.98	26.94	26.84	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	78.11	78.17	76.99	77.76
10. Q : cfm Vs As(60 sec/min)	45088	45127	44444	44886
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	29722	29750	29056	29509
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	104.74	102.21	101.59	102.85
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	25.78 .66 .81 1.47 27.25	18.56 .30 .94 1.24 19.80	19.98 .23 .69 .92 20.90	21.44 .39 .81 1.21 22.65
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.1009805 .0025747 .0031805 .0057552 .1067356	.0726458 .0011630 .0036827 .0048456 .0774915	.0800662 .0009185 .0027554 .0036739 .0837401	.0845642 .0015520 .0032062 .0047582 .0893224
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	2.59	3.89	2.54	3.01
16. C,VOC: ppmv as C, dry basis ((C,VOC as C ₃ H ₈)(3))/(1-Bws)	487	N/A	846	N/A
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	27.05	N/A	45.96	36.50

← Q dscfm

- Filter + probe
- cond. inorganic
- cond organic
- total condensable
- 1.1.9 PM

Kirby Forest Industries - Silsbee OSB Facility
 No. 1 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 26 & 27, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	9.621128	9.621128	9.621128
2. Dn : in.	.196	.196	.196
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	29.91	29.92	29.92
7. Pg : in. H2O	-.45	-.46	-.46
8. Vm : cf (dry gas)	42.721	43.777	42.939
9. sqr(DP),avg: in.H2O^.5	1.2229	1.2354	1.2079
10. DH : in. H2O	1.7	1.7083	1.6625
11. ts : degrees F	187.67	184.92	186.67
12. tm : degrees F	98.83	87.42	99.38
13. Vlc : ml	160	168	158
14. CO2 : percent	1.00	.97	.83
15. O2 : percent	19.80	19.63	19.87
16. CO : ppm, dry (NDIR)	90	135	105
17.a M,PM : mg (front half)	153.9	138.7	152.7
17.b M,PM aqu: mg (aqu.fraction)	1.8	.8	.3
17.c M,PM org: mg (org.fraction)	7.1	6.1	8.6
18. C,VOC : ppmv as propane,wet	206	176	225

186.42

110

202

Kirby Forest Industries - Silsbee OSB Facility
 No. 1 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 26 & 27, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	30.04	30.05	30.04	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	29.88	29.89	29.89	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	2.095e-4	2.095e-4	2.095e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	39.70889	41.55323	39.88189	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	7.5312	7.90776	7.43706	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.1594239	.1598787	.1571687	.1588238
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.952	28.9404	28.92813	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	27.21	27.19	27.21	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	78.39	79.03	77.35	78.26
10. Q : cfm Vs As(60 sec/min)	45252	45623	44652	45176
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	30965	31344	30693	31001
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	98.15	101.47	99.45	99.69
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	15.87 .19 .73 .92 16.79	13.84 .08 .61 .69 14.53	15.55 .03 .88 .91 16.45	15.09 .10 .74 .84 15.92
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0596859 .0006981 .0027535 .0034516 .0631375	.0514035 .0002965 .0022607 .0025572 .0539607	.0589636 .0001158 .0033208 .0034366 .0624002	.0566843 .0003701 .0027784 .0031485 .0598328
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	12.16	18.46	14.06	14.89
16. C,VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	735	628	801	722
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	42.56	36.83	45.96	41.78

SILSBEES PM
COND. INORG.
COND. ORGANIC

Kirby Forest Industries - Silsbee OSB Facility
 No. 2 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 25, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	9.621128	9.621128	9.621128
2. Dn : in.	.196	.196	.196
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	29.62	29.62	29.64
7. Pg : in. H2O	-.52	-.52	-.52
8. Vm : cf (dry gas)	44.36	43.652	44.619
9. sqr(DP),avg: in.H2O ^{.5}	1.2235	1.2288	1.2124
10. DH : in. H2O	1.6917	1.7167	1.6708
11. ts : degrees F	188.75	184.42	186.08
12. tm : degrees F	88.54	96.88	93.58
13. Vlc : ml	177	175	173
14. CO2 : percent	.83	.80	.70
15. O2 : percent	19.87	19.77	20.03
16. CO : ppm, dry (NDIR)	110	170	110
17.a M,PM : mg (front half)	192.8	120.4	119.5
17.b M,PM aqu: mg (aqu.fraction)	2.2	.2	.6
17.c M,PM org: mg (org.fraction)	8.3	12	11.8
18. C,VOC : ppmv as propane,wet	215	180	173

186.42

130

189

Kirby Forest Industries - Silsbee OSB Facility
 No. 2 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 25, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	29.74	29.75	29.76	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	29.58	29.58	29.60	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	2.095e-4	2.095e-4	2.095e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	41.59937	40.32486	41.48704	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	8.33139	8.23725	8.14311	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.1668589	.1696230	.1640759	.1668526
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.92813	28.91893	28.91333	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	27.10	27.07	27.12	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	79.03	79.16	78.10	78.77
10. Q : cfm Vs As(60 sec/min)	45623	45699	45085	45469
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	30586	30740	30472	30599
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	104.10	100.40	104.20	102.90
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	18.75 .21 .81 1.02 19.77	12.14 .02 1.21 1.23 13.37	11.61 .06 1.15 1.20 12.82	14.17 .10 1.05 1.15 15.32
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0713742 .0008144 .0030726 .0038871 .0752612	.0459806 .0000764 .0045828 .0046592 .0506397	.0443584 .0002227 .0043802 .0046029 .0489613	.0539044 .0003712 .0040119 .0043830 .0582874
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	14.68	22.80	14.62	17.37
16. C'VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	774	650	621	682
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	44.27	37.38	35.37	39.01

Kirby Forest Industries - Silsbee OSB Facility
 No. 3 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 26, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	9.621128	9.621128	9.621128
2. Dn : in.	.196	.196	.196
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	29.92	29.92	29.91
7. Pg : in. H2O	-.48	-.48	-.48
8. Vm : cf (dry gas)	40.007	41.535	42.085
9. sqr(DP), avg: in.H2O ^{.5}	1.2333	1.2067	1.2123
10. DH : in. H2O	1.7292	1.6625	1.6125
11. ts : degrees F	185.17	183.08	183.00
12. tm : degrees F	75.00	100.46	101.50
13. Vlc : ml	161.5	164	152.5
14. CO2 : percent	.73	.80	.73
15. O2 : percent	19.67	19.73	19.64
16. CO : ppm, dry (NDIR)	15	40	30
17.a M,PM : mg (front half)	115.1	115.8	119.8
17.b M,PM aqu: mg (aqu.fraction)	2.8	.1	2.1
17.c M,PM org: mg (org.fraction)	5.9	9.9	4.4
18. C,VOC : ppmv as propane,wet	197	232	230

183.75

28

220

Kirby Forest Industries - Silsbee OSB Facility
 No. 3 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 26, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	30.05	30.04	30.03	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	29.88	29.88	29.87	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	2.095e-4	2.095e-4	2.095e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	38.85831	38.50351	38.92338	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	7.601805	7.71948	7.178175	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.1636200	.1670052	.1557035	.1621096
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.90413	28.91733	28.9028	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	27.12	27.09	27.21	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	79.02	77.23	77.43	77.89
10. Q : cfm Vs As(60 sec/min)	45615	44580	44700	44965
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	31186	30454	30944	30861
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	95.37	96.77	96.28	96.14
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	12.22 .30 .63 .92 13.14	12.12 .01 1.04 1.05 13.16	12.60 .22 .46 .68 13.28	12.31 .18 .71 .88 13.20
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0456155 .0011097 .0023382 .0034479 .0490634	.0463158 .0000400 .0039596 .0039996 .0503154	.0473988 .0008309 .0017409 .0025717 .0499705	.0464433 .0006602 .0026796 .0033398 .0497831
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	2.04	5.31	4.05	3.80
16. C,VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	707	836	817	786
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	41.20	47.57	47.28	45.35

Kirby Forest Industries - Silsbee OSB Facility
 No. 4 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 27 & 28, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	9.621128	9.621128	9.621128
2. Dn : in.	.196	.196	.196
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	29.92	29.94	29.96
7. Pg : in. H2O	-.53	-.57	-.46
8. Vm : cf (dry gas)	44.093	42.334	43.868
9. sqr(DP),avg: in.H2O^.5	1.2446	1.2197	1.2329
10. DH : in. H2O	1.7583	1.6917	1.725
11. ts : degrees F	179.42	175.83	175.75
12. tm : degrees F	100.00	106.67	99.00
13. Vlc : ml	164.5	153.5	167
14. CO2 : percent	.93	1.03	1.00
15. O2 : percent	19.87	19.37	19.80
16. CO : ppm, dry (NDIR)	170	40	35
17.a M,PM : mg (front half)	125.7	126.3	127.3
17.b M,PM aqu: mg (aqu.fraction)	.3	2.1	.9
17.c M,PM org: mg (org.fraction)	8	12.3	8.4
18. C,VOC : ppmv as propane,wet	182	177	183

177.00

82

181

Kirby Forest Industries - Silsbee OSB Facility
 No. 4 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 27 & 28, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	30.05	30.06	30.09	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	29.88	29.90	29.93	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	2.095e-4	2.095e-4	2.095e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	40.91798	38.84274	40.83297	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	7.743015	7.225245	7.86069	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.1591216	.1568387	.1614315	.1591306
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.94413	28.94013	28.952	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	27.20	27.22	27.18	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	79.27	77.41	78.27	78.32
10. Q : cfm Vs As(60 sec/min)	45761	44688	45181	45210
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	31733	31267	31473	31491
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	98.69	95.08	99.30	97.69
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	12.89 .03 .82 .85 13.75	13.45 .22 1.31 1.53 14.98	12.98 .09 .86 .95 13.93	13.11 .12 1.00 1.11 14.22
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0473088 .0001129 .0030109 .0031238 .0504326	.0500742 .0008326 .0048766 .0057092 .0557834	.0480107 .0003394 .0031680 .0035075 .0515182	.0484646 .0004283 .0036852 .0041135 .0525781
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	23.53	5.46	4.81	11.27
16. C'VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	649	630	655	645
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	38.52	36.82	38.52	37.95

Kirby Forest Industries - Silsbee OSB Facility
 No. 5 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 28, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	9.621128	9.621128	9.621128
2. Dn : in.	.196	.196	.196
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	29.96	29.96	29.96
7. Pg : in. H2O	-.57	-.57	-.57
8. Vm : cf (dry gas)	43.697	43.641	44.012
9. sqr(DP),avg: in.H2O ^{.5}	1.2258	1.2346	1.2439
10. DH : in. H2O	1.7125	1.7292	1.75
11. ts : degrees F	173.83	174.75	175.42
12. tm : degrees F	111.96	107.96	115.46
13. Vlc : ml	170	173	170.5
14. CO2 : percent	1.03	1.00	1.00
15. O2 : percent	19.60	19.80	19.50
16. CO : ppm, dry (NDIR)	35	30	25
17.a M,PM : mg (front half)	165.1	130.4	137.7
17.b M,PM aqu: mg (aqu.fraction)	2.1	.9	.6
17.c M,PM org: mg (org.fraction)	7.3	6.4	8.3
18. C,VOC : ppmv as propane,wet	208	167	184

174.67

30

186

Kirby Forest Industries - Silsbee OSB Facility
 No. 5 Dryer Stack
 Particulate/VOC/CO Emissions Test - February 28, 1992

Calculations:

	RUN 1	RUN 2	RUN 3	AVG.
1. Pm : in.Hg (DH/13.6)+Pbar	30.09	30.09	30.09	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	29.92	29.92	29.92	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	2.095e-4	2.095e-4	2.095e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	39.75096	39.98125	39.79765	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	8.0019	8.14311	8.025435	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.1675690	.1692097	.1678151	.1681979
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.94933	28.952	28.94	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	27.11	27.10	27.10	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	77.81	78.45	79.07	78.44
10. Q : cfm Vs As(60 sec/min)	44917	45285	45646	45283
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	31145	31293	31562	31334
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	97.69	97.79	96.51	97.33
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	17.11 .22 .76 .97 18.09	13.50 .09 .66 .76 14.26	14.45 .06 .87 .93 15.38	15.02 .12 .76 .89 15.91
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0639617 .0008136 .0028281 .0036417 .0676034	.0502275 .0003467 .0024652 .0028118 .0530394	.0532840 .0002322 .0032117 .0034439 .0567280	.0558244 .0004641 .0028350 .0032991 .0591236
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	4.76	4.10	3.44	4.10
16. C,VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	750	603	663	672
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	43.65	35.28	39.14	39.36

Kirby Forest Industries - Silsbee OSB Facility
 No. 1 Press Vent
 Particulate/VOC/CO Emissions Test - March 2, 1992

Collected test data		RUN 1	RUN 2	RUN 3	
1. As	: sq ft	19.63495	19.63495	19.63495	
2. Dn	: in.	.235	.235	.235	
3. Cp	: dimensionless	.84	.84	.84	
4. Theta	: minutes	60	60	60	
5. Y	: dimensionless	.98	.98	.98	
6. Pbar	: in. Hg	30.08	30.08	30.08	
7. Pg	: in. H2O	-.12	-.12	-.12	
8. Vm	: cf (dry gas)	40.097	41.522	39.989	
9. sqr(DP),avg:	in.H2O ^{-.5}	.636	.6693	.6657	
10. DH	: in. H2O	1.375	1.5117	1.525	
11. ts	: degrees F	99.33	100.17	100.25	99.92
12. tm	: degrees F	107.17	118.63	120.56	
13. Vlc	: ml	17	16	15	
14. CO2	: percent	.00	.00	.00	
15. O2	: percent	20.90	20.90	20.90	
16. CO	: ppm, dry (NDIR)	10	10	10	10
17.a M,PM	: mg (front half)	5.2	6.4	3.3	
17.b M,PM aqu:	mg (aqu.fraction)	1.7	.3	1.3	
17.c M,PM org:	mg (org.fraction)	1	.4	.8	
18. C,VOC	: ppmv as propane,wet	33.6	38	53	41.53333

Kirby Forest Industries - Silsbee OSB Facility
 No. 1 Press Vent
 Particulate/VOC/CO Emissions Test - March 2, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	30.18	30.19	30.19	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	30.07	30.07	30.07	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	3.012e-4	3.012e-4	3.012e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	36.90049	37.46756	35.96546	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	.80019	.75312	.70605	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.0212248	.0197045	.0192534	.0200609
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.836	28.836	28.836	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	28.61	28.62	28.63	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	36.83	38.77	38.57	38.06
10. Q : cfm Vs As(60 sec/min)	43387	45680	45434	44834
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	40290	42422	42206	41639
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	99.51	95.96	92.58	96.02
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	.75 .25 .14 .39 1.14	.96 .04 .06 .10 1.06	.51 .20 .12 .33 .84	.74 .16 .11 .27 1.01
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0021702 .0007095 .0004173 .0011268 .0032970	.0026305 .0001233 .0001644 .0002877 .0029183	.0014130 .0005566 .0003426 .0008992 .0023122	.0020712 .0004631 .0003081 .0007712 .0028425
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	1.76	1.85	1.84	1.82
16. C'VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	103	116	162	127
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	7.76	9.22	12.79	9.92

Kirby Forest Industries - Silsbee OSB Facility
 No. 2 Press Vent
 Particulate/VOC/CO Emissions Test - March 1, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	19.63495	19.63495	19.63495
2. Dn : in.	.235	.235	.235
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	30.05	30.05	30.05
7. Pg : in. H2O	-.12	-.12	-.12
8. Vm : cf (dry gas)	41.333	42.916	41.704
9. sqr(DP),avg: in.H2O^.5	.6764	.7089	.6798
10. DH : in. H2O	1.5413	1.66	1.5221
11. ts : degrees F	98.88	101.32	98.96
12. tm : degrees F	117.60	120.60	124.38
13. Vlc : ml	13	15	14.5
14. CO2 : percent	.00	.00	.00
15. O2 : percent	20.90	20.90	20.90
16. CO : ppm, dry (NDIR)	10	10	10
17.a M,PM : mg (front half)	2.5	4.4	4.7
17.b M,PM aqu: mg (aqu.fraction)	.9	1.1	1.1
17.c M,PM org: mg (org.fraction)	0	.5	.3
18. C,VOC : ppmv as propane,wet	45	67	61

99.72

10

58

Kirby Forest Industries - Silsbee OSB Facility
 No. 2 Press Vent
 Particulate/VOC/CO Emissions Test - March 1, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	30.16	30.17	30.16	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	30.04	30.04	30.04	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	3.012e-4	3.012e-4	3.012e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	37.32909	38.56964	37.22543	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	.61191	.70605	.682515	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.0161279	.0179768	.0180045	.0173697
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.836	28.836	28.836	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	28.66	28.64	28.64	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	39.13	41.12	39.35	39.87
10. Q : cfm Vs As(60 sec/min)	46103	48441	46355	46966
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	43027	44928	43173	43709
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	94.26	93.27	93.68	93.74
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	.38 .14 .00 .14 .52	.68 .17 .08 .25 .92	.72 .17 .05 .21 .94	.59 .16 .04 .20 .79
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0010314 .0003713 0 .0003713 .0014027	.0017568 .0004392 .0001996 .0006388 .0023957	.0019444 .0004551 .0001241 .0005792 .0025235	.0015775 .0004219 .0001079 .0005298 .0021073
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	1.88	1.96	1.88	1.91
16. C,VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	137	205	185	176
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	11.04	17.19	14.92	14.38

Kirby Forest Industries - Silsbee OSB Facility
 No. 3 Press Vent
 Particulate/VOC/CO Emissions Test - March 2, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	19.63495	19.63495	19.63495
2. Dn : in.	.235	.235	.235
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	30.08	30.08	30.08
7. Pg : in. H2O	-.13	-.13	-.13
8. Vm : cf (dry gas)	41.795	41.147	41.001
9. sqr(DP),avg: in.H2O ^{.5}	.6794	.6729	.6606
10. DH : in. H2O	1.5554	1.5321	1.4746
11. ts : degrees F	99.63	101.08	98.96
12. tm : degrees F	106.71	117.31	120.79
13. Vlc : ml	12	13	10.5
14. CO2 : percent	.00	.00	.00
15. O2 : percent	20.90	20.90	20.90
16. CO : ppm, dry (NDIR)	10	10	10
17.a M,PM : mg (front half)	3	3.6	2.3
17.b M,PM aqu: mg (aqu.fraction)	.6	.8	1.3
17.c M,PM org: mg (org.fraction)	.1	.5	1.4
18. C,VOC : ppmv as propane,wet	42.9	41.5	33.7

99.89

10

39.36667

Kirby Forest Industries - Silsbee OSB Facility
 No. 3 Press Vent
 Particulate/VOC/CO Emissions Test - March 2, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	30.19	30.19	30.19	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	30.07	30.07	30.07	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	3.012e-4	3.012e-4	3.012e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	38.51127	37.21592	36.85651	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	.56484	.61191	.494235	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.0144549	.0161762	.0132323	.0146211
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.836	28.836	28.836	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	28.68	28.66	28.69	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	39.30	38.99	38.18	38.82
10. Q : cfm Vs As(60 sec/min)	46302	45933	44983	45739
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	43270	42740	42140	42716
14. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	96.70	94.61	95.02	95.44
15. E,PM : pounds/hr (M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	.45 .09 .01 .10 .55	.55 .12 .08 .20 .74	.35 .20 .21 .41 .76	.45 .14 .10 .24 .68
16. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0011996 .0002399 .0000400 .0002799 .0014796	.0014897 .0003310 .0002069 .0005379 .0020276	.0009610 .0005432 .0005850 .0011282 .0020892	.0012168 .0003714 .0002773 .0006487 .0018655
17. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	1.89	1.86	1.84	1.86
18. C,VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	131	127	102	120
19. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	10.56	10.11	8.07	9.58

Kirby Forest Industries - Silsbee OSB Facility
 No. 4 Press Vent
 Particulate/VOC/CO Emissions Test - February 29, 1992

Collected test data

RUN 1

RUN 2

RUN 3

1. As : sq ft	19.63495	19.63495	19.63495
2. Dn : in.	.235	.235	.235
3. Cp : dimensionless	.84	.84	.84
4. Theta : minutes	60	60	60
5. Y : dimensionless	.98	.98	.98
6. Pbar : in. Hg	29.93	29.93	29.93
7. Pg : in. H2O	-.11	-.11	-.11
8. Vm : cf (dry gas)	37.238	38.648	39.437
9. sqr(DP),avg: in.H2O ^{.5}	.6322	.6445	.6451
10. DH : in. H2O	1.3088	1.3758	1.39
11. ts : degrees F	90.33	91.83	93.25
12. tm : degrees F	104.40	112.17	118.71
13. Vlc : ml	19	19	22
14. CO2 : percent	.00	.00	.00
15. O2 : percent	20.90	20.90	20.90
16. CO : ppm, dry (NDIR)	10	10	10
17.a M,PM : mg (front half)	6.6	6.1	3.9
17.b M,PM aqu: mg (aqu.fraction)	.8	2.6	2.4
17.c M,PM org: mg (org.fraction)	.4	1.1	1.4
18. C,VOC : ppmv as propane,wet	42.9	32.8	42.8

91.80

10

39.5

Kirby Forest Industries - Silsbee OSB Facility
 No. 4 Press Vent
 Particulate/VOC/CO Emissions Test - February 29, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	30.03	30.03	30.03	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	29.92	29.92	29.92	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	3.012e-4	3.012e-4	3.012e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	34.26089	35.08104	35.39391	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	.89433	.89433	1.03554	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.0254395	.0248595	.0284259	.0262416
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.836	28.836	28.836	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	28.56	28.57	28.53	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	36.43	37.19	37.30	36.97
10. Q : cfm Vs As(60 sec/min)	42921	43810	43937	43556
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	40134	40879	40743	40585
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	92.75	93.24	94.38	93.46
13. E,PM : pounds/hr ((M,PM/Vmstd)(Qstd)(60))/453590				
Front Half	1.02	.94	.59	.85
CPM, aqueous	.12	.40	.37	.30
CPM, organic	.06	.17	.21	.15
Total CPM	.19	.57	.58	.44
Total PM	1.21	1.51	1.17	1.30
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg)				
Front Half	.0029666	.0026778	.0016969	.0024471
CPM, aqueous	.0003596	.0011414	.0010442	.0008484
CPM, organic	.0001798	.0004829	.0006091	.0004239
Total CPM	.0005394	.0016242	.0016534	.0012723
Total PM	.0035060	.0043020	.0033503	.0037195
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	1.75	1.78	1.78	1.77
16. C,VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	132	101	132	122
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	9.91	7.71	10.07	9.23

Kirby Forest Industries - Silsbee OSB Facility
 No. 5 Press Vent
 Particulate/VOC/CO Emissions Test - March 1, 1992

Collected test data		RUN 1	RUN 2	RUN 3	
1. As	: sq ft	19.63495	19.63495	19.63495	
2. Dn	: in.	.235	.235	.235	
3. Cp	: dimensionless	.84	.84	.84	
4. Theta	: minutes	60	60	60	
5. Y	: dimensionless	.98	.98	.98	
6. Pbar	: in. Hg	30.04	30.04	30.04	
7. Pg	: in. H2O	-.08	-.08	-.08	
8. Vm	: cf (dry gas)	41.391	43.171	42.445	
9. sqr(DP),avg:	in.H2O ^{.5}	.706	.6958	.7002	
10. DH	: in. H2O	1.6638	1.6079	1.6179	
11. ts	: degrees F	94.50	94.71	97.25	95.49
12. tm	: degrees F	103.96	115.48	118.69	
13. Vlc	: ml	16	13.5	14	
14. CO2	: percent	.00	.00	.00	
15. O2	: percent	20.90	20.90	20.90	
16. CO	: ppm, dry (NDIR)	5	10	10	8.333333
17.a M,PM	: mg (front half)	3.4	.3	3.2	
17.b M,PM aqu:	mg (aqu.fraction)	.5	2.1	1.7	
17.c M,PM org:	mg (org.fraction)	.4	.2	1.8	
18. C,VOC	: ppmv as propane,wet	25.8	39	32.9	33

Kirby Forest Industries - Silsbee OSB Facility
 No. 5 Press Vent
 Particulate/VOC/CO Emissions Test - March 2, 1992

Calculations:

RUN 1

RUN 2

RUN 3

AVG.

1. Pm : in.Hg (DH/13.6)+Pbar	30.16	30.16	30.16	N/A
2. Ps : in. Hg (Pg/13.6)+Pbar	30.03	30.03	30.03	N/A
3. An : sq ft ((Dn/24)^2)(3.1416)	3.012e-4	3.012e-4	3.012e-4	N/A
4. Vmstd: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	38.28433	39.12606	38.25563	N/A
5. Vwstd: scf (.04707cf/ml)(Vlc)	.75312	.635445	.65898	N/A
6. Bws : dimensionless Vwstd/(Vwstd+Vmstd)	.0192922	.0159814	.0169340	.0174026
7. Md : mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	28.836	28.836	28.836	N/A
8. Ms : mol.wt. wet basis Md(1-Bws)+18 Bws	28.63	28.66	28.65	N/A
9. Vs : ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	40.72	40.11	40.46	40.43
10. Q : cfm Vs As(60 sec/min)	47966	47253	47669	47629
11. Qstd : dscfm Q(1-Bws)(Ps/Pstd)(Tstd/Ts)	44964	44427	44571	44654
12. I : percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm)]/ (60 Theta Vs Ps An)	92.51	95.68	93.25	93.81
13. E,PM : pounds/hr (M,PM/Vmstd)(Qstd)(60))/453590 Front Half CPM, aqueous CPM, organic Total CPM Total PM	.53 .08 .06 .14 .67	.05 .32 .03 .35 .39	.49 .26 .28 .54 1.03	.36 .22 .12 .34 .70
14. C,PM : grains/dscf (M,PM/Vmstd)(.0154 grains/mg) Front Half CPM, aqueous CPM, organic Total CPM Total PM	.0013677 .0002011 .0001609 .0003620 .0017297	.0001181 .0008266 .0000787 .0009053 .0010234	.0012882 .0006843 .0007246 .0014089 .0026971	.0009246 .0005707 .0003214 .0008921 .0018167
15. E,CO : pounds/hr (C,CO*7.27e-8)(Qstd)(60)	.98	1.94	1.94	1.62
16. C,VOC: ppmv as C, dry basis ((C,VOC as C3H8)(3))/(1-Bws)	79	119	100	99
17. E,VOC : pounds/hr as carbon (C,VOC)(3)(3.1161e-8)(Qstd)60	6.63	9.88	8.37	8.29

5.0 NOMENCLATURE

SYMBOL	UNITS	DESCRIPTION
An	ft ²	Nozzle area
As	ft ²	Stack area
Bws	dimensionless	Proportion of water vapor
CO ₂	percent	Carbon dioxide content by volume
CO	percent	Carbon monoxide content by volume
Cp	dimensionless	Pitot correction factor
C _{PM}	grains/dscf	Particulate concentration
C' _{PM}	gr/dscf@12% CO ₂	Particulate emissions corrected to 12% excess air
C _[X]	ppm	Concentration of [X]
Dn	inches	Nozzle diameter
delta H	in. H ₂ O	Pressure drop across meter orifice (also DH)
delta P	in. H ₂ O	Stack velocity pressure head (also DP)
E _{PM}	#/hr	Particulate emission rate
E _[X]	#/hr	Emission rate of X
I	per cent	Per cent isokinetic sampling
Kp	consistent	Pitot tube constant = 85.49
M _{PM}	milligrams	Particulate sample weight
Md	## mole	Dry molecular wt. of stack gas
Ms	## mole	Wet molecular wt. of stack gas
N ₂	percent	Nitrogen content by volume
O ₂	percent	Oxygen content by volume
Pbar	in. Hg	Barometric pressure
Pg	in. H ₂ O	Static pressure
Pm	in. Hg	Meter pressure = Pbar+(delta H/13.6)
Ps	in. Hg	Stack pressure = Pbar+(Pg/13.6)
Pstd	in. Hg	Standard pressure = 29.92
Q	ft ³ /min	Volumetric flow rate at stack conditions
Qstd	dscf/min	Volumetric flow rate at dry, std. conditions
Theta	minutes	Sampling time per run
tm	°F	Meter temperature (Tm denotes °R)
ts	°F	Stack temperature (Ts denotes °R)
Tstd	°R	Standard temperature = 528°
Vlc	ml	Volume of water collected
Vm	ft ³	Volume of dry gas sampled
Vmatd	dscf	Sample volume at standard conditions
Vwstd	scf	Sample volume of water vapor
Y	dimensionless	Meter correction factor
Xsair	percent	Excess air

6.0 CALIBRATIONS: Measurement devices used by Environmental Monitoring Laboratories and subject to changes in measurement precision are initially calibrated prior to use. Those instruments for which calibration factors are subject to change or for which calibration checks are required, are calibrated following each field use or as otherwise directed and noted. Calibration procedures for specific equipment are as follows.

Dry Gas Meter: Dry gas meters are periodically removed from the sampling consoles and cleaned and repaired (new gaskets etc. as required). Following the overhaul of a meter, the measuring precision is checked by the Bell Prover Method and adjusted when necessary to read to within 2% of 100% accuracy. This service is provided by Big Three Meter Company in Jackson, Mississippi. Overhaul service or any six month period is followed by a five point calibration described in APTD-0576 using either a wet test meter or calibrated dry gas meter (used exclusively for calibrations) as a standard reference. Following field use, a gas meter calibration is checked in one of two ways. [1] Three calibration checks at intermediate orifice settings are performed or [2] orifice meter coefficients are used.

If a meter coefficient obtained from pre-test and post-test checks differs by more than 5%, the coefficient (Y) giving the lower sample volume is used in the calculations.

Orifice: The orifice coefficient is initially determined and is rechecked following a major gas meter repair and calibration.

Nozzles: Nozzles are checked before each field use with a precision (.001 in.) dial caliper. Three measurements on different axes are made; an average of those three readings is used in calculations. If the tolerance among measurements exceeds 0.004 inches (highest to lowest reading) the nozzle is repaired and recalibrated or discarded.

Pitot Tubes: Pitot tubes meeting EPA geometry standards are assigned a coefficient of 0.84. Pitot tubes are visually inspected for damage before, during and after use. Those pitot tubes not meeting the geometry standards are assigned a coefficient from the manufacturer's calibration which it retains unless damaged. All pitot tubes used by Environmental Monitoring Laboratories are manufactured by NAPP, Inc.

Temperature Measuring Instruments: Most temperature measurements are made with a type K thermocouple and an Omega digital thermocouple thermometer which has an initial calibration traceable to NBS. Other measurements are made using bimetallic dial thermometers. The thermocouples and dial thermometers are checked following or during a test series against an ASTM mercury in glass thermometer.


Barometer: Aneroid field barometers are checked against and adjusted to readings from a mercury barometer or readings obtained from local weather authorities.

Differential Pressure Gauges: Velocity head (ΔP) and orifice pressure differential (ΔH) measurements are made using water manometers of the appropriate range unless otherwise noted in the test data. Manometers do not require calibration.


Flame Ionization Detector (FID): VOC measurements were made with a Ratfisch portable flame ionization detector set in a range of 0 to 1000 ppm propane. Following a sufficient warm up period the instrument was set to respond to and measure certified propane in nitrogen mixtures. Available concentrations were 31.1, 82.3, and 830 ppm certified propane. Prior to and following each sample run, the instrument's zero and span were checked and adjusted if necessary using supplies of air and calibration propane. Copies of the gas concentrations certifications are provided.

Non-dispersive Infrared Analyzer (NDIR): Carbon monoxide measurements are made with a Beckman 864 infrared instrument calibrated in ranges of 0 to 1000 ppm and 0 to 5000 ppm. Following a sufficient warm up period of at least 1 hour and prior to each sample run, the instrument's zero and calibration are checked and adjusted if necessary using a supply of 100% nitrogen and a collection of certified CO in nitrogen mixtures of nominally 50 ppm, 150 ppm, 300, and 700 ppm CO respectively. These calibrations and adjustments are repeated at the conclusion of each sampling period.

7.0 SAMPLE TRAIN CONFIGURATIONS



pm: CS Sample TRAIN




VOC Sample TRAIN

8.0 STACK CONFIGURATIONS:

STACK CONFIGURATION / SAMPLE AND VELOCITY POINTS

Plant Name La. Pacific (Kirby Forest Ltd.) Source OSB Dryers (1-5)
 Data For: _____ Date _____

Sketch of stack




PERCENT OF DIAMETER

Point No	Points on a Diameter							
	2	4	6	8	10	12	14	16
1	14.6	6.7	4.4	3.2	2.6	2.1	1.8	1.6
2	85.4	25.0	14.6	10.5	8.2	6.7	5.7	4.9
3	75.0	29.6	19.4	14.6	11.8	9.9	8.5	
4	93.3	70.4	32.3	22.6	17.7	14.6	12.5	
5	85.4	67.7	34.2	25.0	20.1	16.9		
6	95.6	80.6	65.8	35.6	26.9	22.0		
7		89.5	77.4	64.4	36.6	28.3		
8		96.8	85.4	75.0	63.4	37.5		
9			91.8	82.3	73.1	62.5		
10			97.4	88.2	79.9	71.7		
11				93.3	85.4	78.0		
12				97.9	90.1	83.1		
13					94.3	87.5		
14					98.2	91.5		
15						95.1		
16						98.4		

Stack diameter 42.0
 Distance from ports to disturbance:
 distance to upstream disturbance 50'
 distance to downstream disturbance 28'
 upstream diameters 14
 downstream diameters B
 Minimum No. points required 12
 No. points selected 6 x 2
 Nipple length 6" P.N 9" long

Point	inches from wall	velocity head
1	1.8	
2	6.1	
3	12.4	
4	29.6	
5	35.6	
6	40.2	
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
Pg =		Ts =
Pitot ID		Cp =




REMARKS

STACK CONFIGURATION / SAMPLE AND VELOCITY POINTS

Plant Name Kirby Forest Refinery Source Press Vents 1 through 5
 Data For: _____ Date Stack Extension

Sketch of stack



PERCENT OF DIAMETER

		Points on a Diameter							
		2	4	6	8	10	12	14	16
Point No									
1	..	14.6	6.7	4.4	3.2	2.6	2.1	1.8	1.6
2	..	85.4	25.0	14.6	10.5	8.2	6.7	5.7	4.9
3		75.0	29.6	19.4	14.6	11.8	9.9	8.5	
4		93.3	70.4	32.3	22.6	17.7	14.6	12.5	
5		85.4	67.7	34.2	25.0	20.1	16.9		
6		95.6	80.6	65.8	35.6	26.9	22.0		
7		89.5	77.4	64.4	36.6	28.3			
8		96.8	85.4	75.0	63.4	37.5			
9		91.8	82.3	73.1	62.5				
10		97.4	88.2	79.9	71.7				
11			93.3	85.4	78.0				
12			97.9	90.1	83.1				
13				94.3	87.5				
14				98.2	91.5				
15					95.1				
16					98.4				

Stack diameter 60

Distance from ports to disturbance:

distance to upstream disturbance _____

distance to downstream disturbance _____

upstream diameters _____


downstream diameters _____

Minimum No. points required _____

No. points selected 24 (12x2)


Nipple length 6" long 6" Flange

Point	inches from wall	velocity head
1	1.3	
2	4.0	
3	7.1	
4	10.6	
5	15.0	
6	21.4	
7	33.6	
8	45.0	
9	49.4	
10	52.9	
11	56.0	
12	58.7	
13		
14		
15		
16		
Pg =		Ts =
Pitot ID		Cp =



REMARKS

Press Vents



9.0 APPENDICES

- A. Sampling and Analytical Data
- B. Calibration Data
- C. VOC/CO Recorder Trace
- D. 02-24-92 Test for Dryer No. 1

9.0 APPENDICES

A. SAMPLING AND ANALYTICAL DATA

DRYER NO. 1

Plant Kimby Forest Industries
 Sampling Location No. 1 OSB Dryer
 Test For Am/CPM/VOL/CO
 Test Operators Russell/more

RUN No. 1
 Date 2-26-92
 Time start 1545 end 1703

Meter Box RAC591349
 Sample Box N.O. 1
 Probe/Pitot 5' inc.
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No.

No. Sample Pts. 6 x 2
 Minutes/Pt. 5.0
 NOMOGRAPH
 $\Delta H @$ 1.85
 Meter Temp.
 % H₂O
 C-Factor
 Stack Temp.
 Ref. ΔP 1.65

Gas Analysis int. or ext.
 CO₂ 1.0 1.0 1.0
 O₂ 20.8 20.8 20.8
 CO NDIR = 90 ppm
 Time
 Condensate:
 tare 200 fin 346
 Silica gel:
 tare 645 fin 659

Remarks:
Nozzle calib.
D.196
D.196
D.196

Amb. Temp. °F 61
 Bar. Press. "Hg 29.91
 Static Press. "H₂O -.45

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH , in. H ₂ O	Stack Temp. °F	Meter Temp., °F In Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	162.169	1.30	1.50	186	88 86	250	57	2	1.0
2	5	165.8	1.50	1.70	191	93 86	265	60	2	1.0
3	10	169.2	1.60	1.80	187	103 87	265	60	2	1.0
4	15	172.9	1.70	1.90	185	106 88	260	60	2	1.0
5	20	176.8	1.60	1.80	187	111 89	235	59	2	1.0
6	25	180.3	1.25	1.45	181	115 91	270	58	2	1.0
7										
1	30	183.522	1.30	1.50	182	110 93	235	64	2	1.0
2	35	186.9	1.50	1.70	190	109 93	250	55	2	1.0
3	40	189.8	1.60	1.80	188	113 92	265	54	2	1.0
4	45	194.7	1.75	1.95	192	110 95	230	55	2	1.0
5	50	198.4	1.60	1.80	191	113 96	225	60	2	1.0
6	55	202.0	1.30	1.50	192	117 98	240	64	2	1.0
end	60	205.168								
15										
16										
17										
18										
19										
20										
21										
22										
23										
24										
25										
26										
27										
28										
29										
30										
31										
32										
33										
34										
35										

* filter plugged @ 10' 34" into 2nd traverse
 mid test leak check [190.081] .030 → .030 = 0.000 cfm @ 17" Hg
 [190.359]
 resumed @ 1644
 leak check .048 → .056 = .008 cfm @ 7" Hg

42.721 1.2229 1.7000 187.67 98.83

Plant Kisby Forest Industries - SilasSampling Location No. 1 OSB DyeingTest For PM / CPM /Test Operators Russell / Moore / Mc KnightRUN No. 2Date 2-27-92Time start 0904 end 1009Meter Box RAC591349Sample Box N/AProbe/Pitot 5' inc.Pitot Cp .84Nozzle Dia. .196Filter No. No. Sample Pts. 6 x 2Minutes/Pt. 5.0

NOMOGRAPH

 $\Delta H @$ 1.9Meter Temp. 100% H₂O 16C-Factor .90Stack Temp. 185Ref. ΔP 1.6Gas Analysis int reactCO₂ 0.9 0.9 1.0O₂ 20.6 20.6 20.6CO NDIR = 140 ppmTime

Condensate:

tare 2.00 fin 3.49

Silica gel:

tare 681 fin 700Remarks:

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	205.495	1.30	1.50	175	70	67	225	53	2	1.0
2	5	209.5	1.50	1.70	179	75	67	235	45	2	1.0
3	10	212.7	1.60	1.85	180	83	68	235	50	2	1.0
4	15	216.3	1.80	2.00	188	92	70	250	50	2	1.0
5	20	220.3	1.70	1.90	185	99	73	265	51	2	1.0
6	25	224.3	1.20	1.40	180	104	75	265	53	2	1.0
7											
8	30	227.222	1.40	1.60	192	101	79	255	53	2	1.0
9	5	231.8	1.50	1.70	189	99	82	245	50	2	1.0
10	10	235.3	1.50	1.70	191	107	84	245	50	2	1.0
11	15	239.0	1.70	1.90	187	111	86	235	50	2	1.0
12	20	242.4	1.60	1.80	188	113	88	235	50	2	1.0
13	25	246.3	1.25	1.45	185	116	90	235	50	2	1.0
14	end 60	249.272									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

leak check: .053 → .059 = .006 ΔP 12 1/4"
 pitot + v = 3.9
 pitot - v = 8.2

43.777

1.2354

1.7083

184.92

87.42

Plant Kirby Export ProductsSampling Location No. 1 OSB DryerTest For PM/CPM/VOC/COTest Operators Russell/Moore/McKnightRUN No. 3Date 2-27-92Time start 1042 end 1212Meter Box RAC 591349Sample Box No. 1Probe/Pitot 5' incPitot Cp .84Nozzle Dia. .196Filter No. Amb. Temp. °F 60Bar. Press. "Hg 29.92Static Press. "H₂O -.46No. Sample Pts. 6x2Minutes/Pt. 5.0

NOMOGRAPH

ΔH@ 1.9Meter Temp. % H₂O C-Factor Stack Temp. Ref. ΔP 1.6Gas Analysis in/outCO₂ 0.8 0.9 0.8O₂ 20.7 20.7 20.7CO Time

Condensate:

tare 200 fin 341

Silica gel:

tare 596 fin 613Remarks:

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	249.604	1.30	1.50	189	91	88	225	60	2	1.0
2	5	254.0	1.50	1.70	194	96	88	240	54	2	1.0
3	10	256.9	1.65	1.85	186	104	88	235	55	2	1.0
4	15	260.2	1.65	1.85	187	110	90	235	62	2	1.0
5	20	264.3	1.45	1.65	182	115	91	230	62	2	1.0
6	25	268.3	1.30	1.50	182	118	93	240	62	2	1.0
7											
8	30	271.288	1.25	1.40	184	94	90	235	58	2	1.0
9	5	274.9	1.45	1.65	187	97	91	245	50	2	1.0
10	10	278.6	1.55	1.75	186	108	94	250	50	2	1.0
11	15	281.9	1.65	1.90	192	113	96	245	54	2	1.0
12	20	285.5	1.50	1.70	185	118	95	240	55	2	1.0
13	25	289.3	1.30	1.50	186	121	97	250	55	2	1.0
14	end 60	292.543									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

leak check: .0865 093 : .0074 @ 6" Hg
pitot +ve 4.4
pitot -ve 3.0

2.939 1.2079 1.6625 186.67 99.38

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby - Silchester OSB / Dryer No. 1
 DATE TAKEN: 3-26-92 SAMPLING TEAM: Russell / Moore / McKnight
 SAMPLES RECOVERED BY: DSR DATE RECOVERED: 3-26-92

SAMPLE ID/ANALYSES REQUIRED:

DIR1 (2) Filter - grav.
DIR2 (2) Filter - grav
DIR3 (2) Filter - grav
DIR1 (2) Acetone - grav
DIR2 (2) Acetone - grav

No. OF CONTAINERS:

6 (3 filter) (3 probe wash)
DIR3 (2) Acetone - grav

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Russell - Recovery, Transport, analysis David G. Rasmussen

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	419 420	422	421	
FILTER TARE, gms	.5664 .5680	.5654	.5660	
1st weighing	.6547 .6166	.6927	.7124	
2nd weighing	.6547 .6168	.6925	.7126	
3rd weighing				
FINAL WEIGHT, gms.	.6547 .6168	.6925	.7126	
NET GAIN, gms.	.0983 .0488	.1271	.1466	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER ID	DIR1 (2)	DIR2 (2)	DIR3 (2)	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	160	100	140	
TARE WT., gms.	(1) 114.8224	(2) 99.0858	(25) 97.0906	
1st weighing	114.8289	99.0973	97.0970	
2nd weighing	114.8293	99.0975	97.0968	
3rd weighing				
FINAL WEIGHT, gms.	114.8293	99.0975	97.0968	
NET GAIN, gms.	.0069	.0117	.0062	
LESS BLANK, gms.	-.0001	-.0001	-.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	153.9	138.7	152.7	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kirby F.I. - Silsbee OSB Run No. 1 (2nd)
 DATE TAKEN: 3-26-92 SAMPLING TEAM: Rennick - Moon - McKeith
 SAMPLES RECOVERED BY: DGR DATE RECOVERED: 3-26-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 6
DIR1(2) BAK
DIR2(2) BAK } methylene chloride / gravimetric
DIR3(2) BAK } extraction

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovered by DGR on 2-26-92
Transported by DGR on 3-3-92 } Paul G. Rensen
analyzed by DGR on 3-24-92 from 3-28-92

RUN NO.	1	2	3	
CONTAINER ID	DIR1(2)BAK	DIR2(2)BAK	DIR3(2)BAK	
VOLUME INTACT?	☒	☒	☒	
VOLUME, ml	400	400	400	

AQUEOUS FRACTION

3-28-92

TARE WT., gms.	104.7565	97.5712	104.1113	
1st weighing	104.7586	97.5718	104.1112	
2nd weighing	104.7583	97.5720	104.1116	
3rd weighing				
FINAL WEIGHT, gms.	104.7583	97.5720	104.1116	
NET GAIN, gms.	.0018	.0008	.0003	
LESS BLANK, gms.	—	—	—	

ORGANIC FRACTION

3-21-92

TARE WT., gms.	103.1949	104.7516	98.3965	
1st weighing	103.2024	104.7582	98.4050	
2nd weighing	103.2020	104.7577	98.4051	
3rd weighing				
FINAL WEIGHT, gms.	103.2020	104.7577	98.4051	
NET GAIN, gms.	.0071	.0061	.0086	
LESS BLANK, gms.	—	—	—	

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	1.8	0.8	0.3	
Organic fraction	7.1	6.1	8.6	

			Time: 1535/0850/			Time: 1703/1015/1215					
FID ANALYZER CALIBRATION DATA	Cylinder Value, ppm	Initial analyzer response			Final analyzer response			Difference ppm			
Zero gas	Air 0	0	0	0	5	0	0	5	0	0	
Low-level gas	31.1	32	33	34	31		31	1		0/	
Mid-level gas	83.2	83	85	85	88	83	85	5	2	0	
High-level gas	830	830	830	830	820	810	835	10	20	5	

[illegible]

DRYER NO. 2

Plant Kirby Forest Industries
 Sampling Location No. 2 OSB Dryer
 Test For PM/CPM/VOC/CO
 Test Operators Russell/Moore/McKnight

RUN No. 1
 Date 2-25-92
 Time start 1342 end 1444

Meter Box RACS91349
 Sample Box No. 1
 Probe/Pitot 5' inc
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No.

No. Sample Pts. 6x2
 Minutes/Pt. 5.0
 NOMOGRAPH
 $\Delta H @$ 1.85
 Meter Temp. 100
 % H₂O 17
 C-Factor .86
 Stack Temp. 200
 Ref. ΔP 1.65

Gas Analysis int. stat
 CO₂ 0.8 0.9 0.8
 O₂ 20.7 20.7 20.7
 CO NDIR 110 ppm
 Time
 Condensate:
 tare 200 fin 359
 Silica gel:
 tare 611 fin 629

Remarks:
① .196
② .196
③ .196

Amb. Temp. °F 63
 Bar. Press. "Hg 29.62
 Static Press. "H₂O -.52

Port	El.	DGM	Velocity	Orifice	Stack	Meter	Oven	Imp.	Vac
Point	Time	Reading	Head ΔP	ΔH	Temp.	Temp.	Temp.	Temp.	in.
	Min.	Ft.	in. H ₂ O	in. H ₂ O	°F	In	Out	°F	Hg
1	0	901.372	1.25	1.40	187	69	68	175	61
2	5	904.9	1.70	1.90	187	73	68	200	50
3	10	908.6	1.90	2.10	186	80	71	230	50
4	15	913.3	1.65	1.85	191	96	71	245	51
5	20	917.2	1.50	1.70	190	102	74	255	50
6	25	921.0	1.25	1.40	190	106	77	260	56
7									
8	30/0	924.306	1.20	1.35	190	104	80	260	56
9	5	927.6	1.50	1.70	190	104	83	250	53
10	10	931.2	1.60	1.80	190	107	85	225	53
11	15	934.5	1.70	1.90	190	111	86	235	50
12	20	938.9	1.50	1.70	187	115	88	225	50
13	25	942.8	1.30	1.50	187	116	91	225	50
14	end 60	945.734							
15									
16									
17									
18									
19									
20									
21									
22									
23									
24									
25									
26									
27									
28									
29									
30									
31									
32									
33									
34									
35									

Leak check: .018 → .028 = .0104 in. H₂O
 pitot - v_c 7.6
 pitot - v_a 4.5

44.360 1.2235 1.6917 188.75 88.54

RUN No. 2
Date 2-25-92
Time start 1608 end 1711

Condensate:
tare 200 fin 358
Silica gel:
tare 703 fin 720

Remarks:

[illegible]

RUN No. 3
Date 2-25-92
Time start 1825 end 1935

No. Sample Pts. 6x2
Minutes/Pt. _____

NOMOGRAPH
 $\Delta H @$ 1.95
Meter Temp. _____
% H₂O _____
C-Factor _____
Stack Temp. _____
Ref. ΔP 1.65

Condensate:
tare 200 fin 357
Silica gel:
tare 580 fin 596

missed 9 minutes on
Bag sample
Paused test @ 1903
to ch. filter vac.
went to 15" Hg

Environmental Monitoring Laboratories — Biloxiand, Mississippi — 601-856-3092

PARTICULATE CATCH ANALYSIS AND SAMPLE RECORD:

SAMPLES/PROJECT: Kinby - Silsbee OSB - Dye No. 2
 DATE TAKEN: 2-25-92 SAMPLING TEAM: Russell / Moore / McKnight
 SAMPLES RECOVERED BY: DER DATE RECOVERED: 2-25-92
 SAMPLE ID/ANALYSES REQUIRED: NO. OF CONTAINERS: 6
DIR1 Filter - gravimetric DIR3 Action - grav.
DIR2 Filter ..
DIR3 Filter ..
DIR1 Action ..
DIR2 Action ..

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery - DER 2.5
Transfer - DER 3-3
Analysis - DER 3-5 John G. Russell

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

RUN NO.	1	2	3	4
FILTER NO.	412	411	414	
FILTER TARE, gms	.5672	.5680	.5666	
1st weighing	.7392	.6805	.6823	
2nd weighing	.7390	.6808	.6822	
3rd weighing				
FINAL WEIGHT, gms.	.7390	.6808	.6822	
NET GAIN, gms.	.1718	.1128	.1156	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	BLANK
CONTAINER ID	DIR1	DIR2	DIR3	DIR4
VOLUME INTACT?	✓	✓	✓	✓
VOLUME, ml	200	180	180	200
TARE WT., gms.	(26) 98.6779	(29) 98.3968	(31) 95.7673	98.2505
1st weighing	98.6990	98.4040	95.7771	98.2508
2nd weighing	98.6990	98.4045	95.7713	98.2506
3rd weighing				
FINAL WEIGHT, gms.	98.6990	98.4045	95.7713	98.2506
NET GAIN, gms.	.0211	.0077	.0040	.0001
LESS BLANK, gms.	-.0001	-.0001	-.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	192.8	120.4	119.5	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kinky - Silsbee OSB Dryer No. 2 BACK HALF
 DATE TAKEN: 2-25-92 SAMPLING TEAM: Russell - Moore - McKnight
 SAMPLES RECOVERED BY: DGR DATE RECOVERED: 2-25-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 3

D2 R1 BAK
D2 R2 BAK } Methylene chloride extraction / gravimetric
D2 R3 BAK

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery 2 DGR 2-25-92
Transport DGR 3-3-92
Analysis DGR 3-28-92 } Dr. G. Russell

RUN NO.	1	2	3	BLANK
CONTAINER ID	D2R1BAK	D2R2BAK	D2R3BAK	
VOLUME INTACT?	✓	✓	✓	—
VOLUME, ml	400	400	400	400

AQUEOUS FRACTION

TARE WT., gms.	98.8505	98.3976	111.8064	114.3930
1st weighing	98.8525	98.3982	111.8072	114.3921
2nd weighing	98.8527	98.3978	111.8070	114.3928
3rd weighing				
FINAL WEIGHT, gms.	98.8527	98.3978	111.8070	114.3928
NET GAIN, gms.	.0022	.0002	.0006	0
LESS BLANK, gms.	— 0 —	— 0 —	— 0 —	

ORGANIC FRACTION

TARE WT., gms.	107.2571	112.5838	111.3444	109.7652
1st weighing	107.2654	112.5962	111.3566	107.7653
2nd weighing	107.2654	112.5958	111.3562	107.7652
3rd weighing				
FINAL WEIGHT, gms.	107.2654	112.5958	111.3562	109.7653
NET GAIN, gms.	.0083	.0120	.0118	0
LESS BLANK, gms.	— 0 —	— 0 —	— 0 —	— 0 —

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	2.2	0.2	0.6	
Organic fraction	8.3	12.0	11.8	

DRYER NO. 3

Plant Kirby Forest Laboratory
Source No. 2 Dryer
Test For VOC
Test Operators Russell

RUN NO. 1,2,3
Date 2-25-92
Time start 1342
Time end 1935

		Time: <u>1720</u>		Time: <u>1755</u>					
FID ANALYZER CALIBRATION DATA	Cylinder Value, ppm	Initial analyzer response		Final analyzer response			Difference ppm		
Zero gas	Air	0		0	0	0	0	0	0
Low-level gas	31.1	31		21	33	31	0	0	0
Mid-level gas	83.2	85		85	82	83	0	3	0
High-level gas	830	830		830	830	830	0	0	0

[illegible]

Plant Rinky Forest Industries - Silas OSB
 Sampling Location No. 3 OSB Dryer
 Test For PM/CPM/VOL/CO
 Test Operators Russell / Moore / McKnight

RUN No. 1
 Date 2-26-92
 Time start 0924 end 1032

Meter Box RACS91349
 Sample Box No. 3
 Probe/Pitot 5' inc.
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No.
 Amb. Temp. °F 49
 Bar. Press. "Hg 29.92
 Static Press. "H₂O -.48

No. Sample Pts. 6 x 2
 Minutes/Pt. 5
 NOMOGRAPH
 ΔH@ 1.9
 Meter Temp.
 % H₂O
 C-Factor
 Stack Temp.
 Ref. ΔP 1.65

Gas Analysis int. sect
 CO₂ 0.8 0.7 0.7
 O₂ 20.4 20.4 20.4
 CO
 Time
 Condensate:
 tare 200 fin 346
 Silica gel:
 tare 612 fin 627.5

Remarks:
0.197
0.196 Dn: .196
0.196

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO lpm
1	0	036.482	1.30	1.50	186	55	53	260	49	2	1.0
2	5	039.9	1.70	1.90	189	60	54	265	47	2	1.0
3	10	043.3	1.80	2.00	184	69	58	240	45	2	1.0
4	15	047.4	1.70	1.90	184	81	59	255	46	2	1.0
5	20	050.7	1.65	1.85	185	90	63	250	45	2	1.0
6	25	054.5	1.40	1.60	187	93	63	260	48	2	1.0
7							6				
1	30	057.932	1.45	1.65	183	85	69	245	47	2	1.0
2	35	061.4	1.55	1.75	186	87	70	220	45	2	1.0
3	40	064.4	1.65	1.85	182	92	72	200	45	2	1.0
4	45	068.6	1.65	1.85	186	98	75	225	45	2	1.0
5	50	071.8	1.50	1.70	184	100	77	250	55	2	1.0
6	55	073.7	1.00	1.20	186	100	78	250	55	2	1.0
and	60	076.489									
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											
leak check: .053 → .059 = .006 cfm @ 10" Hg pitot + 1c 4.6 pitot - 1c 3.7 40.007 1.2333 1.7292 185.17 7500											

Plant Kirby Forest IndustriesSampling Location No. 3 OSB DryerTest For PM/CPM/VOC/COTest Operators Russell / Moore / Mc KnightRUN No. 3Date 2-26-92Time start 1303 end 1721Meter Box RACS91349Sample Box No. 3Probe/Pitot S'inc.Pitot Cp .84Nozzle Dia. .196Filter No. No. Sample Pts. 6 x 2Minutes/Pt. 3

NOMOGRAPH

 $\Delta H @$ 1.8Meter Temp. % H₂O C-Factor Stack Temp. Ref. ΔP 1.65Gas Analysis int. reactCO₂ 0.7 0.8 0.7O₂ 20.7 20.4 20.3CO Time

Condensate:

tare 200 fin 338

Silica gel:

tare 704.5 fin 718.5Remarks:

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg
1	0	118.915	1.10	1.30	175	95	91	195	60	2 1.0
2	5	122.3	1.60	1.80	180	94	89	230	50	2 1.0
3	10	126.2	1.60	1.80	189	106	90	265	50	2 1.0
4	15	129.7	1.70	1.90	184	108	91	260	50	2 1.0
5	20	133.1	1.60	1.80	191	108	91	270	51	2 1.0
6	25	136.8	1.50	1.70	184	115	92	235	55	3 1.0
7	30	140.8	1.25	1.45	179	112	94	225	56	3 1.0
8	35	148.9	1.60	1.80	178	112	95	210	50	3 1.0
9	40	147.4	1.75	1.95	180	111	97	275	52	3 1.0
10	45	151.0	1.55	1.75	183	120	98	260	55	3 1.0
11	50	154.7	1.50	1.70	183	121	98	270	59	3 1.0
12	55	158.6	1.00	1.20	190	109	99	235	60	3 1.0
13	60	161.493								
14										
15										
16										
17										
18										
19										
20										
21										
22										
23										
24										
25										
26										
27										
28										
29										
30										
31										
32										
33										
34										
35										

mid tank leak check: $[155.863] \cdot 0.031 \rightarrow 0.033 = 0.0024 @ 20" Hg$
 $[156.352]$

leak check: $0.097 \rightarrow 1.03 = 0.006 @ 7" Hg$
 pitot - ve 3.6
 mid - ve 6.9

42.085

1.2123

1.6125

183.00

101.50

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby - Silsbee OSB - Draw No. 3
 DATE TAKEN: 2-26-92 SAMPLING TEAM: Russell - Mason - M. Knight
 SAMPLES RECOVERED BY: DGR DATE RECOVERED: 2-26-92
 SAMPLE ID/ANALYSES REQUIRED: D3R1 Filt D3R3A Filt
D3R2 Filt
D3R3 Filt } grossing tank
D3R1 Acton
D3R2 Acton

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery by DGR on 2-26-92
Transfer by DGR on 3-3-92 } Danilo R. Rios
Analysis by DGR on 3-3-92

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least
24 hours, weighed to constant weight.

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	389	415 416	417 418	
FILTER TARE, gms	.5607	.5675 .5679	.5663 .5663	
1st weighing	.6712	.6188 .6300	.6665 .5808	
2nd weighing	.6712	.6187 .6299	.6667 .5807	
3rd weighing				
FINAL WEIGHT, gms.	.6712	.6187 .6299	.6667 .5807	
NET GAIN, gms.	.1105	.0512 .0620	.1005 .0144	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat,
desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER ID	D3R1	D3R2	D3R3	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	175	180	200	
TARE WT., gms.	(32) 97.5706	(45) 107.2585	(44) 104.1099	
1st weighing	97.5756	107.2620	104.1152	
2nd weighing	97.5753	107.2609	104.1149	
3rd weighing		107.2612		
FINAL WEIGHT, gms.	97.5753	107.2612	104.1149	
NET GAIN, gms.	.0049	.0027	.0050	
LESS BLANK, gms.	-.0001	-.0001	-.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	115.1	115.8	119.8	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kirby - Silsbee DSB Dryer No. 3 Back Half
 DATE TAKEN: 2-26-92 SAMPLING TEAM: Russell Moore - McKing
 SAMPLES RECOVERED BY: DSR DATE RECOVERED: 2-26-92
 SAMPLE ID/ANALYSES REQUIRED: _____ NO. OF CONTAINERS: 3

D3R1 BAK }
 D3R2 BAK } Methanol Chloride Extract in / preservative
 D3R3 BAK }

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery to DSR on 2-26-92
Transfer to DSR on 2-03-92 } David E. P. [unclear]
Analyzing DSR on 3-21-92 + 3-28-92

RUN NO.	1	2	3	
CONTAINER ID	D3R1 BAK	D3R2 BAK	D3R3 BAK	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	400	400	400	

AQUEOUS FRACTION (3-21-92)

TARE WT., gms.	107.2579	113.9910	113.2267	
1st weighing	107.2606	113.9914	113.2293	
2nd weighing	107.2607	113.9911	113.2288	
3rd weighing				
FINAL WEIGHT, gms.	107.2607	113.9911	113.2288	
NET GAIN, gms.	.0028	.0001	.0021	
LESS BLANK, gms.	- 0 -	- 0 -	- 0 -	

ORGANIC FRACTION (3-28-92)

TARE WT., gms.	113.9854	113.2244	109.8900	
1st weighing	113.9916	113.2343	109.8945	
2nd weighing	113.9913	113.2243	109.8944	
3rd weighing				
FINAL WEIGHT, gms.	113.9913	113.2343	109.8944	
NET GAIN, gms.	.0059	.0099	.0044	
LESS BLANK, gms.	- 0 -	- 0 -	- 0 -	

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	2.8	0.1	2.1	
Organic fraction	5.9	9.9	4.4	

DRYER NO. 4

Plant Kirby Forest Industries
 Sampling Location NO. 4 DSB Dryer
 Test For PM/CPM/VOC/CO
 Test Operators Russell / none / McKnight

RUN No. 1
 Date 2-27-92
 Time start 1516 end 1628

Meter Box	<u>RAC591349</u>	No. Sample Pts.	<u>6 x 2</u>	Gas Analysis	<u>int react</u>	Remarks:
Sample Box	<u>No. 3</u>	Minutes/Pt.	<u>5.0</u>	CO ₂	<u>0.9 0.9 1.0</u>	
Probe/Pitot	<u>5' inc.</u>			O ₂	<u>20.8 20.8 20.8</u>	
Pitot Cp	<u>.84</u>	NOMOGRAPH		CO		
Nozzle Dia.	<u>.196</u>	ΔH@	<u>1.9</u>	Time		
Filter No.		Meter Temp.		Condensate:		
Amb. Temp. °F	<u>69</u>	% H ₂ O		tare <u>200</u> fin <u>350</u>		
Bar. Press. "Hg	<u>29.92</u>	C-Factor		Silica gel:		
Static Press. "H ₂ O	<u>-.46</u>	Stack Temp.		tare <u>707</u> fin <u>721.5</u>		
		Ref. ΔP	<u>1.6</u>			

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	292.701	1.40	1.60	182	84	81	270	64	2	1.0
2	5	296.4	1.65	1.85	181	88	82	250	60	3	1.0
3	10	300.3	1.80	2.00	184	99	84	255	60	3	1.0
4	15	304.1	1.75	1.95	181	107	86	240	61	3	1.0
5	20	307.8	1.40	1.60	176	113	87	235	61	3	1.0
6	25	311.6	1.20	1.40	170	114	90	240	60	3	1.0
7											
8	30	314.515	1.15	1.30	178	114	93	250	60	3	1.0
9	35	318.6	1.45	1.65	179	116	94	255	61	3	1.0
10	40	321.8	1.50	1.70	180	119	94	250	60	3	1.0
11	45	325.3	1.95	2.20	178	120	95	225	59	3	1.0
12	50	329.2	1.75	1.95	184	123	96	255	55	3	1.0
13	55	333.0	1.70	1.90	180	124	97	255	54	3	1.0
14	and 60	336.794									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

back check: .033 → .039 = .0066 @ 14" H₂O
 pitot + se 4.6
 pitot - se 1.9

44.093 1.2446 1.7583 179.72 100.00

Plant Kirby Forest Industries
 Sampling Location No. 4 OSB Dryer
 Test For PM / CPM / VOC / CO
 Test Operators Russell / Moore / Mc Knight

RUN No. 2
 Date 2-27-92
 Time start 1702 end 1812

Meter Box	<u>RAC59/349</u>	No. Sample Pts.	<u>6 x 2</u>	Gas Analysis	<u>int. root</u>	Remarks: <u>residual 1259</u>
Sample Box	<u>No. 1</u>	Minutes/Pt.	<u>5.0</u>	CO ₂	<u>1.1 1.0 1.0</u>	
Probe/Pitot	<u>5' inc.</u>			O ₂	<u>20.4 20.4 20.4</u>	
Pitot Cp	<u>.84</u>	NOMOGRAPH		CO		
Nozzle Dia.	<u>.196</u>	ΔH@	<u>1.9</u>	Time		
Filter No.		Meter Temp.		Condensate:		
Amb. Temp. °F	<u>74</u>	% H ₂ O		tare <u>220</u> fin <u>339</u>		
Bar. Press. "Hg	<u>29.94</u>	C-Factor		Silica gel:		
Static Press. "H ₂ O	<u>-.57</u>	Stack Temp.		tare <u>635.5</u> fin <u>649</u>		
		Ref. ΔP	<u>1.65</u>			

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	
1	0	337.182	1.30	1.50	178	96	92	240	66	2	1.0
2	5	340.6	1.70	1.90	179	99	93	225	60	2	1.0
3	10	344.5	1.70	1.90	180	109	96	225	65	2	1.0
4	15	348.1	1.65	1.85	179	115	98	230	64	2	1.0
5	20	352.3	1.20	1.40	171	119	97	220	62	2	1.0
6	25	355.8	1.10	1.25	170	123	100	225	62	2	1.0
7											
8	30	258.794	1.30	1.50	175	122	101	230	62	2	1.0
9	5	363.1	1.40	1.60	179	122	102	225	60	2	1.0
10	10	365.7	1.70	1.90	181	123	102	250	62	3	1.0
11	15	368.7	1.70	1.90	176	120	102	255	63	3	1.0
12	20	372.6	1.70	1.90	171	116	100	245	50	3	1.0
13	25	376.5	1.50	1.70	171	114	99	200	55	3	1.0
14	end 60	379.771									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

his vacuum @ 16' 05" into 2nd traverser - changed filter holder
 mid test leak check: [369.081] .035 → .036 = .001 cfm @ 20" Hg
 [369.336]
 leak check: .023 → .029 = .006 cfm @ 6" Hg
 pitot + ve 3.9
 pitot - ve 3.9

42.334 1.2197 1.6917 175.83 106.67

Plant Kinky Forest Industries
 Sampling Location No. 4 DSB Dunes
 Test For PAH/CPM/CO/VOC
 Test Operators R. M. / M. / McKnight

RUN No. 3
 Date 2-28-92
 Time start 0947 end 1049

Meter Box RAC 591347 No. Sample Pts. 6x2
 Sample Box N.O. 3 Minutes/Pt. 5.0
 Probe/Pitot 5' inc
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No. _____

NOMOGRAPH
 $\Delta H @$ 1.95
 Meter Temp. 100
 % H₂O 16
 C-Factor .89
 Stack Temp. 180
 Ref. ΔP 1.6

Gas Analysis int. ext.
 CO₂ 6.0 1.0 1.0
 O₂ 20.8 22.8 20.8
 CO _____
 Time _____

Condensate:
 tare 200 fin 351
 Silica gel:
 tare 629.5 fin 645.5

Remarks: _____

Amb. Temp. °F 60
 Bar. Press. "Hg 29.96
 Static Press. "H₂O -.53

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	380.046	1.30	1.50	173	73	72	195	68	2	1.0
2	5	387.3	1.65	1.85	172	80	74	225	60	2	1.0
3	10	387.0	1.65	1.85	175	92	75	260	65	2	1.0
4	15	391.1	1.70	1.90	180	103	80	260	65	2	1.0
5	20	394.7	1.60	1.80	176	110	84	260	65	2	1.0
6	25	398.3	1.30	1.50	170	116	86	240	65	2	1.0
7											
8	30	402.084	1.15	1.30	178	119	93	265	69	2	1.0
9	35	405.7	1.45	1.65	176	121	96	270	60	2	1.0
10	40	409.2	1.70	1.90	179	122	96	255	60	2	1.0
11	45	413.3	1.90	2.10	180	123	98	240	60	2	1.0
12	50	416.8	1.75	1.95	177	128	102	265	60	2	1.0
13	55	420.7	1.20	1.40	173	129	104	245	60	2	1.0
14	end 60	423.914									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

each ΔP : .053 $\rightarrow$.063 = .010 ΔP 7' H₂O

43.868 1.2329 1.725 175.75 99.00

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby - Silsbee DSB - Paper No. 4
 DATE TAKEN: 3-27-92 + 3-28-92 SAMPLING TEAM: Russell - Moore - McKnight
 SAMPLES RECOVERED BY: DSR DATE RECOVERED: 3-27-92 + 3-28-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 6
D4R1 Filter D4R3 Acetone
D4R2 Filter } gravimetric
D4R3 Filter
D4R1 Acetone
D4R2 Acetone

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery by DSR on 3-27+28-92
Transport by DSR on 3-3-92
Analysis by DSR on 3-3-92 } David A. Russell

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight.

FILTERS:

RUN NO.	1	2	3
FILTER NO.	424	423 425	426
FILTER TARE, gms	.5681	.5662 .5662	.5673
1st weighing	.6870	.5989 .6585	.6917
2nd weighing	.6873	.5987 .6582	.6913
3rd weighing			
FINAL WEIGHT, gms.	.6873	.5987 .6583	.6913
NET GAIN, gms.	.1192	.0325 .0921	.1240

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3
CONTAINER ID	D4R1	D4R2	D4R3
VOLUME INTACT?	✓	✓	✓
VOLUME, ml	210	175	180
TARE WT., gms.	(61) 113.9914	(62) 113.2255	(64) 111.8066
1st weighing	113.9976	113.2272	111.8103
2nd weighing	113.9980	113.2273	111.8100
3rd weighing			
FINAL WEIGHT, gms.	113.9980	113.2273	111.8100
NET GAIN, gms.	.0066	.0018	.0034
LESS BLANK, gms.	-.0001	-.0001	-.0001

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3
filter + probe	125.7	126.3	127.3

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kirby - Silsbee DSB No. 4 Dryer
 DATE TAKEN: 2-27-92 + 2-28-92 SAMPLING TEAM: Russell - Moore - McKnight
 SAMPLES RECOVERED BY: DGR DATE RECOVERED: 2-27-92 + 2-28-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 3
D4R1 BAK
D4R2 BAK } Methylene Chloride extraction / gravimetric
D4R3 BAK

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

recovery by DGR on 2-27 + 2-28-92
throughout by DGR on 3-3-92 } Final Release
analysis by DGR on 3-21-92 + 3-28-92

RUN NO.	1	2	3	
CONTAINER ID	D4R1 BAK	D4R2 BAK	D4R3 BAK	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	400	400	400	

AQUEOUS FRACTION 3-21-92

TARE WT., gms.	99.0897	112.5402	111.3468	
1st weighing	99.0902	112.5422	111.3473	
2nd weighing	99.0900	112.5423	111.3777	
3rd weighing				
FINAL WEIGHT, gms.	99.0900	112.5423	111.3777	
NET GAIN, gms.	.0003	.0021	.0009	
LESS BLANK, gms.	—	—	—	

ORGANIC FRACTION 3-28-92

TARE WT., gms.	97.5708	105.8211	111.8041	
1st weighing	97.5790	105.8334	111.8126	
2nd weighing	97.5788	105.8334	111.8125	
3rd weighing				
FINAL WEIGHT, gms.	97.5788	105.8334	111.8125	
NET GAIN, gms.	.0080	.0123	.0084	
LESS BLANK, gms.	—	—	—	

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	0.3	2.1	0.9	
Organic fraction	8.0	12.3	8.4	

DRYER NO. 5

Plant Kirby Forest Industries
 Sampling Location No. 5 O.S.B. Oregon
 Test For PM/CPM/CO/VOC
 Test Operators _____

RUN No. 1
 Date 2-28-92
 Time start 1149 end 1250

Meter Box RAC 591349
 Sample Box No. 1
 Probe/Pitot 5' inc.
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No. _____

No. Sample Pts. 6x2
 Minutes/Pt. 5.0
 NOMOGRAPH
 $\Delta H @$ 1.85
 Meter Temp. _____
 % H₂O _____
 C-Factor _____
 Stack Temp. _____
 Ref. ΔP 1.6

Gas Analysis int. duct
 CO₂ 1.1 1.0 1.0
 O₂ 20.7 20.6 20.6
 CO NDIR = 35 ppm
 Time _____
 Condensate:
 tare 200 fin 355
 Silica gel:
 tare 631 fin 646

Remarks: _____

Amb. Temp. °F 70
 Bar. Press. "Hg 29.96
 Static Press. "H₂O -.57

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	424.159	1.15	1.35	174	96	93	240	68	2	1.0
2	5	427.6	1.60	1.80	177	100	94	225	55	2	1.0
3	10	421.2	1.65	1.85	172	109	96	195	60	2	1.0
4	15	435.8	1.75	1.95	172	117	97	230	60	2	1.0
5	20	438.6	1.40	1.60	174	123	100	225	60	2	1.0
6	25	442.4	1.15	1.35	169	127	103	235	61	2	1.0
7											
8	30/0	445.427	1.30	1.50	174	128	106	255	65	2	1.0
9	5	449.1	1.70	1.90	175	129	107	265	65	2	1.0
10	10	452.8	1.80	2.00	176	130	107	260	65	2	1.0
11	15	456.6	1.90	2.10	173	131	107	265	65	2	1.0
12	20	461.0	1.40	1.60	174	134	109	260	64	2	1.0
13	25	464.8	1.35	1.55	171	134	110	270	65	2	1.0
14	30	467.856				132	112				
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

back check: .006 → .064 = .006 cpc 8' Hg
 pitot - 6.1
 static - 5.9

43.697 1.2258 1.7125 173.83 111.96

Plant Kinky Forest Industries - Silabo OSB
 Sampling Location No. 5 OSB Dryer
 Test For PM/CPM/Vol/CO
 Test Operators Russell / Moore / Mc Knight

RUN No. 3
 Date 2-28-92
 Time start 1311 end 1713

Meter Box RALC91349
 Sample Box No. 3
 Probe/Pitot Sine
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No.

No. Sample Pts. 6x2
 Minutes/Pt. 5.0
 NOMOGRAPH
 $\Delta H @$ 1.85
 Meter Temp.
 % H₂O
 C-Factor
 Stack Temp.
 Ref. ΔP 1.45

Gas Analysis int. wet
 CO₂ 1.0 1.0 1.0
 O₂ 20.5 20.5 20.5
 CO
 Time
 Condensate: 355
 tare 200 fin 255
 Silica gel:
 tare 673.5 fin 689

Remarks:

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH , in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO g/m
1	0	512.732	1.25	1.45	176	102	98	250	67	2	1.0
2	5	516.5	1.55	1.75	177	105	98	255	55	2	1.0
3	10	520.0	1.55	1.75	176	113	101	230	58	2	1.0
4	15	523.3	1.60	1.80	176	120	102	230	60	2	1.0
5	20	527.2	1.50	1.70	177	126	104	230	60	2	1.0
6	25	530.6	1.45	1.65	173	130	106	225	65	2	1.0
7											
8	30/0	539.184	1.50	1.70	174	132	109	235	66	2	1.0
9	5	538.3	1.75	1.95	176	133	111	270	60	2	1.0
10	10	541.8	1.75	1.95	175	134	111	250	60	2	1.0
11	15	545.3	1.60	1.80	174	134	111	270	62	2	1.0
12	20	549.6	1.60	1.80	173	135	111	245	65	2	1.0
13	25	553.5	1.50	1.70	178	135	110	255	65	2	1.0
14	60	556.744									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

Leak check: .096 → .104 = .012 g/m³ @ 10" Hg
 pitot + ve 6.3
 pitot - ve 8.8

44.012 1.2439 1.7500 175.42 115.46

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby - Silsbee DSR - Run No 5
 DATE TAKEN: 2-28-92 SAMPLING TEAM: Russell/Moore/McKnight
 SAMPLES RECOVERED BY: DGR DATE RECOVERED: 2-28-92
 SAMPLE ID/ANALYSES REQUIRED: _____ No. OF CONTAINERS: 6
DSR1 Filt DSR3 Acton
DSR2 Filt
DSR3 Filt } 6 replicate
DSR1 Acton
DSR2 Acton

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery on 2-28-92 by DGR
Transport on 3-3-92 by DGR } David G. Russell
Analysis on 3-3-92 by DGR

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	427	428	429	
FILTER TARE, gms	.5652	.5658	.5678	
1st weighing	.7266	.6929	.7007	
2nd weighing	.7266	.6930	.7007	
3rd weighing				
FINAL WEIGHT, gms.	.7266	.6930	.7007	
NET GAIN, gms.	.1614	.1272	.1329	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER ID	DSR1	DSR2	DSR2	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	150	210	200	
TARE WT., gms.	(65) 114.7874	(66) 109.8923	(67) 111.4705	
1st weighing	114.7909	109.8956	111.4751	
2nd weighing	114.7912	109.8956	111.4754	
3rd weighing				
FINAL WEIGHT, gms.	114.7912	109.8956	111.4754	
NET GAIN, gms.	.0038	.0033	.0049	
LESS BLANK, gms.	-.0001	-.0001	-.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	145.1	130.4	137.7	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kinky - Silsbee O5B Run No. 5
 DATE TAKEN: 2-28-92 SAMPLING TEAM: Runwell - Moore - McKnight
 SAMPLES RECOVERED BY: DGR DATE RECOVERED: 2-28-92
 SAMPLE ID/ANALYSES REQUIRED: _____ NO. OF CONTAINERS: 3

DSR1 BAK }
 DSR2 BAK } Methylene chloride extraction
 DSR3 BAK }

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Received by DGR on 2-28-92
Transferred by DGR on 3-3-92
Analyses by DGR on 3-24-92 & 3-28-92

RUN NO.	1	2	3	
CONTAINER ID	DSR1 BAK	DSR2 BAK	DSR3 BAK	
VOLUME INTACT?	<u>✓</u>	<u>✓</u>	<u>✓</u>	
VOLUME, ml	400	400	400	

AQUEOUS FRACTION 2-28-92

TARE WT., gms.	114.8281	98.6806	112.5868	
1st weighing	114.8304	98.6819	112.5877	
2nd weighing	114.8302	98.6815	112.5874	
3rd weighing				
FINAL WEIGHT, gms.	114.8302	98.6815	112.5874	
NET GAIN, gms.	.0021	.0009	.0006	
LESS BLANK, gms.	—	—	—	

ORGANIC FRACTION 2-28-92

TARE WT., gms.	97.0908	104.1100	112.5386	
1st weighing	97.0980	104.1169	112.5471	
2nd weighing	97.0981	104.1164	112.5469	
3rd weighing				
FINAL WEIGHT, gms.	97.0981	104.1164	112.5469	
NET GAIN, gms.	.0073	.0064	.0083	
LESS BLANK, gms.	—	—	—	

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	2.1	0.9	0.6	
Organic fraction	7.3	6.4	8.3	

PRESS VENT NO. 1

Plant Kirby Forest Industries
 Sampling Location Pine Knot No. 1
 Test For Pm/CPm/CO/VOC
 Test Operators Russell / Moore / McKnight

RUN No. 1
 Date 3-2-92
 Time start 1514 end 1616

Meter Box	<u>RACS91349</u>	No. Sample Pts.	<u>1202</u>	Gas Analysis	<u>int wnat</u>	Remarks:
Sample Box	<u>N03</u>	Minutes/Pt.	<u>2.5</u>	CO ₂	<u>0.0</u>	
Probe/Pitot	<u>5' inc.</u>			O ₂	<u>Air</u>	
Pitot Cp	<u>.84</u>	NOMOGRAPH		CO	<u>10 ppm NDIR</u>	
Nozzle Dia.	<u>.235</u>	ΔH@	<u>1.9</u>	Time		
Filter No.		Meter Temp.		Condensate:		<u>Avg Vol = 33.6</u>
Amb. Temp. °F	<u>74</u>	% H ₂ O		tare	<u>200</u> fin <u>203</u>	
Bar. Press. "Hg	<u>30.08</u>	C-Factor		Silica gel:		
Static Press. "H ₂ O	<u>-.12</u>	Stack Temp.		tare	<u>688</u> fin <u>702</u>	
		Ref. ΔP	<u>.59</u>			

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head Δ P, in. H ₂ O	Orifice Δ H in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	
1	000	053.869	0.62	1.95	98	96	96	150	70	2	
2	230	056.0	0.64	2.00	97	101	96	145	55	2	
3	500	057.7	0.45	1.35	110	102	96	135	55	2	
4	730	060.6	0.37	1.15	100	107	96	140	55	2	
5	1000	062.0	0.15	0.46	108	109	95	150	55	2	
6	1230	063.5	0.04	0.13	98	108	96	175	60	2	
7	1500	064.0	0.36	1.10	95	108	95	185	62	2	
8	1730	065.2	0.60	0.90	103	108	96	220	58	2	
9	2000	067.4	0.41	1.25	93	108	94	225	58	2	
10	2230	068.9	0.50	1.60	96	110	92	225	56	2	
11	2500	070.8	0.45	1.40	94	113	93	230	58	2	
12	2730	072.6	0.35	1.15	95	117	92	225	58	2	
13											
14	30/60	074.014	0.61	1.90	96	121	95	250	60	2	
15	230	075.9	0.58	1.85	100	122	97	260	60	2	
16	500	077.4	0.46	1.45	103	123	100	230	61	2	
17	730	079.6	0.42	1.30	100	124	102	190	58	2	
18	5	1000	081.8	0.17	0.54	95	124	102	160	60	2
19	6	1230	082.5	0.05	0.16	94	123	103	160	60	2
20	7	1500	083.4	0.62	1.95	99	124	105	150	60	2
21	8	1730	085.1	0.87	2.70	106	122	106	135	60	2
22	9	2000	086.9	0.90	2.80	101	125	104	130	62	2
23	10	2230	089.5	0.33	1.10	104	128	104	120	58	3
24	11	2500	091.3	0.28	0.86	99	127	105	125	58	3
25	12	2730	092.7	0.30	0.95	100	126	105	100	58	3
26	and 60	093.966									
27											
28											
29											
30											
31											
32											
33											
34											
35											

check: 063 → 080 = 0.017 x 7" H₂O
pitot + 4.7
pitot - 3.6

40.097 1.6360 1.3250 99.33 102.17

Test Operators Russell / Moore / McKnight

Time start 1631 end 1733

Static Press. "H₂O" 1.12

Ref. ΔP

Time

tare 640 fin 652

Remarks:

AVG VOL = 38

118.63

leak check:
ptot + $\frac{1}{2} \rho v^2$
ptot - $\frac{1}{2} \rho v^2$

Plant Kirby Forest Industries - Silabes DSB
 Sampling Location No. 1 Pneu Vent
 Test For Pm/CPM/CO/VOC
 Test Operators Russell / Moore / McKnight

RUN No. 3
 Date 3-2-92
 Time start 1753 end 1854

Meter Box RALS91349
 Sample Box No. 3
 Probe/Pitot 5' inc.
 Pitot Cp .87
 Nozzle Dia. .235
 Filter No.
 Amb. Temp. °F 68
 Bar. Press. "Hg 30.06
 Static Press. "H₂O -.12

No. Sample Pts. 120
 Minutes/Pt. 2.5
 NOMOGRAPH
 ΔH@ 1.85
 Meter Temp.
 % H₂O
 C-Factor
 Stack Temp.
 Ref. ΔP 1.59

Gas Analysis int out
 CO₂
 O₂
 CO MDR = 10ppm
 Time
 Condensate:
 tare 200 fin 203
 Silica gel:
 tare 612 fin 624

Remarks:
AVG VOC = 53.0

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg
1	0000	136.415	0.85	2.65	99	117	112	210	60	2
2	230	138.8	0.85	2.65	109	120	113	225	50	3
3	500	170.9	0.56	1.75	101	122	111	235	50	2
4	730	142.9	0.48	1.50	96	123	111	240	55	2
5	1000	144.4	0.26	0.80	99	127	110	240	55	2
6	1230	145.9	0.04	0.13	103	124	109	250	58	2
7	1500	146.5	0.37	1.15	109	125	109	245	60	2
8	1730	147.9	0.64	2.00	104	126	110	250	55	2
9	2000	149.6	0.54	1.70	96	128	110	250	55	2
10	2230	152.0	0.33	1.05	100	129	109	250	56	2
11	2500	153.4	0.61	1.90	94	131	110	255	55	2
12	2730	154.8	0.50	1.55	93	132	109	260	54	2
13										
14	3000	156.572	0.90	2.80	96	132	110	255	54	2
15	230	158.8	0.82	2.60	103	126	111	260	55	3
16	500	160.4	0.86	1.102.55	108	135	111	265	56	3
17	730	162.9	0.34	1.05	99	137	111	250	58	3
18	1000	164.3	0.16	0.50	101	136	111	230	55	3
19	1230	165.4	0.05	0.16	95	133	112	220	55	2
20	1500	166.1	0.54	1.75	97	136	111	230	58	2
21	1730	168.0	0.98	3.10	96	132	112	245	55	2
22	2000	170.2	0.76	2.30	100	136	112	255	55	2
23	2230	172.3	0.27	0.85	105	137	112	250	58	2
24	2500	173.7	0.25	0.78	106	135	113	250	58	2
25	2730	175.1	0.25	0.78	99	136	113	240	58	2
26	3000	176.404								
27										
28										
29										
30										
31										
32										
33										
34										
35										

Leak check: .093 → .099 = .006 per 10" Hg
 pitot + ✓ 4.6
 pitot - ✓ 5.6

39.989 .6657 1.5250 100.25 120.56

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby - Silabur OSB P Vent No. 1
 DATE TAKEN: 3-2-92 SAMPLING TEAM: Russell-More-McKnight
 SAMPLES RECOVERED BY: RSM DATE RECOVERED: 3-2-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 6
PVIR1 Filter
PVIR2 Filter PVIR3 Action
PVIR3 Filter } grain dust
PVIR1 Action
PVIR2 Action

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovered by RSM on 3-2-92 to DGR
Transferred to DGR
Analysis by DGR on 3-5-92 } Dr. NG Rame

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	443	444	445	
FILTER TARE, gms	.5679	.5676	.5671	
1st weighing	.5713	.5700	.5691	
2nd weighing	.5713	.5703	.5690	
3rd weighing				
FINAL WEIGHT, gms.	.5713	.5703	.5690	
NET GAIN, gms.	.0034	.0027	.0019	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER ID	PVIR1	PVIR2	PVIR3	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	150	125	120	
TARE WT., gms.	(68) 112.5385	(69) 112.5844	(70) 113.8317	
1st weighing	112.5404	112.5883	113.8336	
2nd weighing	112.5404	112.5882	113.8332	
3rd weighing				
FINAL WEIGHT, gms.	112.5404	112.5882	113.8332	
NET GAIN, gms.	.0019	.0038	.0015	
LESS BLANK, gms.	-1.0001	-1.0001	-1.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	5.2	6.4	3.3	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kirby - Silas OCB Pres Vat No. 1
 DATE TAKEN: 3-2-92 SAMPLING TEAM: Rumer/Mann/McKinley
 SAMPLES RECOVERED BY: RSM DATE RECOVERED: 3-2-92
 SAMPLE ID/ANALYSES REQUIRED: _____ NO. OF CONTAINERS: 3

PVIR1BAK
PVIR2BAK
PVIR3BAK } gas methylene chloride extraction / gravimetric

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery by RSM on 3-2-92 to DGR
Transfer to DGR on 3-2-92
Analysis by DGR on 3-21-92 & 3-28-92 } Paul = Rumer

RUN NO.	1	2	3	
CONTAINER ID	<u>PVIR 1 BAK</u>	<u>PVIR 2 BAK</u>	<u>PVIR 3 BAK</u>	
VOLUME INTACT?	<u>✓</u>	<u>✓</u>	<u>✓</u>	
VOLUME, ml	<u>300</u>	<u>300</u>	<u>300</u>	

AQUEOUS FRACTION 3-28-92

TARE WT., gms.	<u>103.1953</u>	<u>104.7572</u>	<u>108.4662</u>	
1st weighing	<u>103.1971</u>	<u>104.7580</u>	<u>108.4677</u>	
2nd weighing	<u>103.1970</u>	<u>104.7575</u>	<u>108.4677</u>	
3rd weighing			<u>108.4675</u>	
FINAL WEIGHT, gms.	<u>103.1970</u>	<u>104.7575</u>	<u>108.4675</u>	
NET GAIN, gms.	<u>.0017</u>	<u>.0003</u>	<u>.0013</u>	
LESS BLANK, gms.	<u>—</u>	<u>—</u>	<u>—</u>	

ORGANIC FRACTION 3-21-92

TARE WT., gms.	<u>114.8233</u>	<u>98.8499</u>	<u>111.4691</u>	
1st weighing	<u>114.8244</u>	<u>98.8503</u>	<u>111.4700</u>	
2nd weighing	<u>114.8243</u>	<u>98.8503</u>	<u>111.4699</u>	
3rd weighing				
FINAL WEIGHT, gms.	<u>114.8243</u>	<u>98.8503</u>	<u>111.4699</u>	
NET GAIN, gms.	<u>.0010</u>	<u>.0004</u>	<u>.0008</u>	
LESS BLANK, gms.	<u>—</u>	<u>—</u>	<u>—</u>	

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	<u>1.7</u>	<u>0.3</u>	<u>1.3</u>	
Organic fraction	<u>1.0</u>	<u>0.4</u>	<u>0.8</u>	

Plant <u>Kirby</u>	RUN NO. <u>1, 2, 3</u>
Source <u>No. 1 Pump Vent</u>	Date <u>3-2-92</u>
Test For <u>VOE</u>	Time start <u>1514/1631/1</u>
Test Operators <u>Russell</u>	Time end <u>1616/1733/185</u>

			Time: 1505/1620/1745			Time: 1620/1740/1900				
FID ANALYZER CALIBRATION DATA	Cylinder Value, ppm	Initial analyzer response			Final analyzer response			Difference ppm		
Zero gas	0	0	0	10	0	4	6	0	4	0
Low-level gas	31.1	31	31	31	31	31	31	0	0	0
Mid-level gas	83.2	83	82	83	80	83	82	0	1	1
High-level gas	830	830	830	835	840	835	830	10	5	5

	el. time min.	FID Reading ppm	FID Range ppm	Sample Pressure mBar	Fuel Pressure psi	Air Pressure psi	Oven Temp C	Line Temp	Chart Speed cm/hr
R1	1514	Strip Chart	0-1000	4.0	6.75	12.0	153	258	20
R2	1631	Strip Chart	0-1000	4.0	6.75	12.0	153	258	20
R3	1854	Strip Chart	0-1000	4.0	6.75	12.0	153	260	20

PRESS VENT NO. 2

Plant Kinby Forest Industries - Silica OSB
 Sampling Location No. 2 Press Vent
 Test For PM/CPM/CO/VOC
 Test Operators Russell / Moore / McKnight

RUN No. 1
 Date 3-1-92
 Time start 1444 end 1545

Meter Box	<u>RAC591349</u>	No. Sample Pts.	<u>12 x 2</u>	Gas Analysis	<u>int. test</u>	Remarks: <u>VOC = 4.6 ppm</u>
Sample Box	<u>No. 3</u>	Minutes/Pt.	<u>2.5</u>	CO ₂	<u>0.0 0.0 0.0</u>	
Probe/Pitot	<u>5" inc.</u>			O ₂	<u>Air</u>	
Pitot Cp	<u>.87</u>	NOMOGRAPH		CO		
Nozzle Dia.	<u>.235</u>	ΔH@	<u>1.85</u>	Time		
Filter No.		Meter Temp.		Condensate:		
Amb. Temp. °F		% H ₂ O		tare <u>200</u> fin <u>200</u>		
Bar. Press. "Hg	<u>30.05</u>	C-Factor		Silica gel:		
Static Press. "H ₂ O	<u>-.12</u>	Stack Temp.		tare <u>656</u> fin <u>669</u>		
		Ref. ΔP	<u>.6</u>			

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO gm
1	000	800.416	0.78	2.45	103	116	109	240	62	3	1.0
2	230	802.6	0.72	2.20	93	118	109	250	60	3	
3	500	804.3	0.70	2.20	96	119	109	245	56	2	1.0
4	730	807.0	0.31	0.95	94	122	110	255	60	2	
5	1000	808.6	0.22	0.66	99	125	113	260	60	2	1.0
6	1230	810.0	0.06	0.18	92	126	112	260	60	2	
7	1500	810.7	0.36	1.10	98	121	110	270	60	2	1.0
8	1730	812.1	0.70	2.20	106	119	108	255	61	2	
9	2000	814.3	0.76	2.40	101	122	109	240	61	3	1.0
10	2230	816.6	0.51	1.60	97	124	109	260	63	2	
11	2500	818.2	0.45	1.40	94	123	109	265	60	3	1.0
12	2730	819.9	0.40	1.20	93	124	110	270	60	3	
13											
14	3000	821.415	0.83	2.65	95	128	112	250	60	4	1.0
15	230	823.5	0.66	2.05	99	126	112	255	60	4	
16	500	825.7	0.43	1.35	98	128	113	270	60	4	1.0
17	730	827.5	0.36	1.10	103	132	115	255	62	3	
18	1000	829.0	0.13	0.40	96	129	113	225	60	3	1.0
19	1230	830.4	0.05	0.15	99	124	110	225	60	3	
20	1500	830.9	0.54	1.55	98	121	110	235	64	3	1.0
21	1730	832.1	0.86	2.65	109	125	116	255	60	3	
22	2000	834.6	0.87	2.70	106	128	112	270	60	3	1.0
23	2230	836.9	0.42	1.30	99	133	111	260	60	3	
24	2500	838.5	0.45	1.35	102	132	109	235	60	3	1.0
25	2730	840.3	0.35	1.20	100	132	110	230	60	3	
26	End 60	841.749									
27											
28											
29											
30											
31											
32											
33											
34											
35											

leak check: .057 → .060 = .003 gpm 7 1/4"

pitot - 3.9

pitot - 6.0

41.333 .6764 1.5413 98.88 11760

Plant Kirby Forest Industries
 Sampling Location No. 2 Press Vent
 Test For PM/CO/CO₂/VOC
 Test Operators Russell / Moore

RUN No. 2
 Date 2-1-92
 Time start 1614 end 1715

Meter Box RACS91349
 Sample Box No. 1
 Probe/Pitot 5' inc
 Pitot Cp .84
 Nozzle Dia. .235
 Filter No.
 Amb. Temp. °F 78
 Bar. Press. "Hg 30.05
 Static Press. "H₂O -1.2

No. Sample Pts. 12 x 2
 Minutes/Pt. 2.5
 NOMOGRAPH
 ΔH@ 1.85
 Meter Temp.
 % H₂O
 C-Factor
 Stack Temp.
 Ref. ΔP .6

Gas Analysis indirect
 CO₂ 0.0 0.0 0.0
 O₂ Air
 CO NOLR = 10ppm
 Time
 Condensate:
 tare 200 fin 203
 Silica gel:
 tare 674 fin 656

Remarks:
VOC = 67.0 ppm

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	000	842.125	0.70	2.20	105	105	105	140	66	2	1.0
2	030	844.1	0.84	2.60	106	110	107	255	50	2	1.0
3	050	846.4	0.57	1.75	98	113	107	140	50	2	1.0
4	0730	848.2	0.55	1.70	93	118	107	165	53	2	1.0
5	1000	850.1	0.30	0.91	101	122	110	190	55	2	1.0
6	1230	851.5	0.12	0.37	96	118	108	190	58	2	1.0
7	1500	852.6	0.31	0.92	93	117	107	200	58	2	1.0
8	1730	853.9	0.71	2.20	99	120	109	190	60	2	1.0
9	2000	856.5	0.66	2.05	95	128	110	165	58	2	1.0
10	2230	858.0	0.85	2.60	107	131	110	155	58	2	1.0
11	2500	860.2	0.72	2.20	113	135	112	190	58	2	1.0
12	2730	863.0	0.53	1.65	100	135	113	190	58	2	1.0
13											
14	30/00	864.139	0.93	2.85	114	135	113	180	60	3	1.0
15	230	866.7	0.75	2.30	117	137	114	185	64	3	1.0
16	500	868.4	0.40	1.20	98	138	114	180	58	2	1.0
17	730	870.5	0.44	1.35	96	138	115	170	60	3	1.0
18	5	872.2	0.15	0.46	100	138	115	180	60	2	1.0
19	6	873.2	0.06	0.18	101	134	116	190	62	2	1.0
20	7	874.0	0.57	1.80	99	132	117	175	64	2	1.0
21	8	875.9	0.95	2.95	100	132	118	225	66	2	1.0
22	9	878.1	0.73	2.25	92	137	118	225	68	2	1.0
23	10	880.5	0.39	1.20	NTC *	139	118	230	62	2	1.0
24	11	882.2	0.36	1.10	NTC *	139	118	235	62	2	1.0
25	12	883.9	0.35	1.05	109	139	119	240	62	2	1.0
26	End 60	885.041									
27											
28											
29											
30											
31											
32											
33											
34											
35											

back check: .047 → .057 → .010 up to 12' Hg
 pitot + VE 8.2
 pitot - VE 5.1

42.916 27089 1.6600 101.32 120.60

Plant Risk Forest Industries - Silas OSB
 Sampling Location No. 2 Press Vent
 Test For PM/CO/NO
 Test Operators Russell / Moore / McKnight

RUN No. 3
 Date 3-1-92
 Time start 1735 end 1836

Meter Box RAC 591249
 Sample Box No. 3
 Probe/Pitot 5' line
 Pitot Cp .84
 Nozzle Dia. .285
 Filter No.
 Amb. Temp. °F 68
 Bar. Press. "Hg 30.05
 Static Press. "H₂O -.12

No. Sample Pts. 12x2
 Minutes/Pt.
 NOMOGRAPH
 ΔH@ 1.9
 Meter Temp.
 % H₂O
 C-Factor
 Stack Temp.
 Ref. ΔP .60

Gas Analysis int. direct
 CO₂ 0.0 0.0 0.0
 O₂ Ar
 CO NDIR 10 ppm
 Time
 Condensate:
 tare 200 fin 201.6
 Silica gel:
 tare 655 fin 668.5

Remarks: 100 = 60.5

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	000	885.716	0.77	2.35	104	117	114	230	68	3	1.0
2	230	888.2	0.64	1.95	94	120	114	250	60	3	1.0
3	500	890.5	0.57	1.75	91	124	114	255	52	3	1.0
4	730	891.6	0.44	1.35	102	119	115	265	52	3	1.0
5	1000	893.9	0.22	0.67	111	121	114	270	52	3	1.0
6	1230	895.0	0.07	0.22	97	127	114	255	52	3	1.0
7	1500	896.4	0.35	1.05	96	125	114	225	52	3	1.0
8	1730	897.7	0.64	2.00	99	126	114	220	52	3	1.0
9	2000	899.5	0.66	2.05	106	128	115	240	52	3	1.0
10	2230	901.4	0.67	2.10	97	128	116	255	53	3	1.0
11	2500	903.3	0.52	1.60	95	134	117	270	54	3	1.0
12	2730	905.4	0.53	1.60	91	135	117	255	52	3	1.0
13											
14	30/00	906.928	0.87	2.70	96	135	116	255	55	4	1.0
15	2	909.5	0.64	1.95	105	136	119	230	55	4	1.0
16	3	911.4	0.49	1.50	100	138	120	245	55	3	1.0
17	4	913.1	0.40	1.25	94	138	118	260	55	3	1.0
18	5	914.9	0.15	0.46	95	138	121	275	55	2	1.0
19	6	915.9	0.06	0.18	96	139	123	260	56	2	1.0
20	7	916.8	0.51	1.55	99	134	125	235	55	2	1.0
21	8	918.0	0.71	2.20	104	134	120	215	55	2	1.0
22	9	920.1	0.85	2.60	100	136	121	220	55	2	1.0
23	10	922.2	0.43	1.30	91	139	121	230	52	2	1.0
24	11	924.1	0.37	1.15	111	140	120	245	52	2	1.0
25	12	925.0	0.33	1.00	101	141	120	200	52	2	1.0
26	end 60	927.420					125				
27											
28											
29											
30											
31											
32											
33											
34											
35											

check the ds: .062 → .066 = -.0044 = 10" / ft
 pitot + ve 3.3
 pitot - ve 7.1

41.204 0.6798 1.5221 98.96 124.38

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby - Silsbee OSB Pass Vot No. 2
 DATE TAKEN: 3-1-92 SAMPLING TEAM: Rosen/moon/mckinstry
 SAMPLES RECOVERED BY: RSM DATE RECOVERED: 3-1-92
 SAMPLE ID/ANALYSES REQUIRED: PV2R1 Filter PV2R3 Acetone No. OF CONTAINERS: 6
PV2R2 Filter
PV2R3 Filter } green stain
PV2R1 Acetone
PV2R2 Acetone

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery by RSM on 3-1-92 to OGR
transport of OGR on 3-3-92
analysis of OGR on 3-5-92 } John A. G. Rosen

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	437	438	439	
FILTER TARE, gms	.5656	.5671	.5667	
1st weighing	.5676	.5688	.5688	
2nd weighing	.5676	.5688	.5687	
3rd weighing				
FINAL WEIGHT, gms.	.5676	.5688	.5687	
NET GAIN, gms.	.0020	.0017	.0020	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER ID	PV2R1	PV2R2	PV2R3	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	300	300	300	
TARE WT., gms.	(71) 115.8220	(72) 111.3451	(76) 105.8232	
1st weighing	115.8226	111.3477	105.8261	
2nd weighing	115.8226	111.3479	105.8260	
3rd weighing				
FINAL WEIGHT, gms.	115.8226	111.3479	105.8260	
NET GAIN, gms.	.0006	.0028	.0028	
LESS BLANK, gms.	-.0001	-.0001	-.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	2.5	4.4	4.7	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kirby - Silaba OGB Para Int No 2
 DATE TAKEN: 3-1-92 SAMPLING TEAM: Russell / Moore / Melvin
 SAMPLES RECOVERED BY: RSM DATE RECOVERED: 3-1-92
 SAMPLE ID/ANALYSES REQUIRED: _____ NO. OF CONTAINERS: 3

PV2R1 BAK
PV2R2 BAK } methylene chloride extracts - gravimetric
PV2R3 BAK

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery by RSM on 3-1-92 to OGB
transport by OGB on 3-3-92 } Don't know
analysis by OGB on 3-31-92

RUN NO.	1	2	3	
CONTAINER ID	PV2R1	PV2R2	PV2R3	
VOLUME INTACT?	✓	—	—	
VOLUME, ml	250	250	250	

AQUEOUS FRACTION 3-31-92

TARE WT., gms.	98.6777	97.5706	107.2582	
1st weighing	98.6784	97.5718	107.2593	
2nd weighing	98.6786	97.5717	107.2593	
3rd weighing				
FINAL WEIGHT, gms.	98.6786	97.5717	107.2593	
NET GAIN, gms.	.0009	.0011	.0011	
LESS BLANK, gms.				

ORGANIC FRACTION 3-31-92

TARE WT., gms.	99.0878	98.3978	115.8217	
1st weighing	99.0879	98.3987	115.8223	
2nd weighing	99.0876	98.3983	115.8220	
3rd weighing				
FINAL WEIGHT, gms.	99.0876	98.3983	115.8220	
NET GAIN, gms.	< 0	.0005	.0003	
LESS BLANK, gms.	—			

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	9.0	1.1	1.1	
Organic fraction	0	0.5	0.3	

Plant <u>Kirby</u>	RUN NO. <u>1, 2, 3</u>
Source <u>No. 2 Press Vent</u>	Date <u>3-1-92</u>
Test For <u>VOC</u>	Time start <u>1444/164/1735</u>
Test Operators <u>Russell</u>	Time end <u>1545/1715/1836</u>

		Time: 1430/1550/1725			Time: 1550/1723/1840					
FID ANALYZER CALIBRATION DATA	Cylinder Value, ppm	Initial analyzer response			Final analyzer response			Difference ppm		
Zero gas	0	0	0	0	0	0	0	0	0	0
Low-level gas	31.1	31	32	30	32	30	34	1	2	4
Mid-level gas	83.2	83	83	83	83	86	83	0	3	0
High-level gas	830	830	830	830	830	850	820	0	20	10

[illegible]

PRESS VENT NO. 3

Plant Kirby Forest Industries - Silica DSBSampling Location No. 3 Press VentTest For PM/CPM/CO/VOCTest Operators Russell/Mason/McKnightRUN No. 1Date 3-2-92Time start 0938 end 1039Meter Box RACS91349Sample Box N=1Probe/Pitot 5" i/cPitot Cp .84Nozzle Dia. .235Filter No. No. Sample Pts. 12 x 2Minutes/Pt. 2.5

NOMOGRAPH

 $\Delta H @$ 1.85Meter Temp. % H₂O C-Factor Stack Temp. Ref. ΔP .59Gas Analysis int. rectCO₂ 0.0 0.0 0.0O₂ 21CO NDIR = 10 ppmTime

Condensate:

tare 200 fin 205

Silica gel:

tare 656 fin 663

Remarks:

VOC = 42.9

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg
1	0100	927.682	0.88	2.75	98	84 84	245	60	3
2	220	929.9	0.72	2.25	93	86 82	245	58	3
3	5100	931.9	0.40	1.25	96	91 82	245	62	2
4	710	933.8	0.32	0.96	96	96 84	240	60	2
5	1000	935.5	0.18	0.57	105	100 86	240	58	2
6	1230	936.5	0.06	0.18	98	102 87	245	58	2
7	1500	937.3	0.54	1.70	102	104 86	245	56	2
8	1730	938.9	0.74	2.40	106	110 88	245	56	2
9	2000	941.8	0.70	2.20	104	114 91	245	86	2
10	2230	943.3	0.67	2.15	104	117 92	245	58	2
11	2500	945.1	0.53	1.70	100	121 94	250	58	2
12	2730	947.1	0.47	1.45	95	124 96	250	58	2
13									
14	3000	948.951	0.70	2.20	104	123 98	250	58	2
15	230	951.3	0.64	2.00	102	126 100	225	55	2
16	500	953.5	0.57	1.80	102	128 100	225	55	2
17	730	955.2	0.42	1.30	96	129 103	240	55	2
18	5100	956.9	0.17	0.54	98	131 104	245	55	2
19	1230	958.5	0.06	0.18	111	130 105	225	52	2
20	1500	959.7	0.46	1.40	96	129 106	240	52	2
21	1730	961.1	0.62	1.95	101	129 107	245	60	2
22	2000	962.9	0.78	2.45	95	131 108	240	60	2
23	2230	964.9	0.44	1.40	94	131 108	280	62	2
24	2500	966.0	0.45	1.40	96	136 110	245	60	2
25	2730	968.0	0.37	1.15	99	136 113	240	60	2
26	and 60	969.477							
27									
28									
29									
30									
31									
32									
33									
34									
35									

back check: .059 → .063 = .004 diff 6" Hg
 pitot - ve 6.6
 pitot - ve 5.0

41.295 16794 1.5554 99.63 100.71

Plant Kirby Forest IndustriesSampling Location 16.3 Press VentTest For PM / CPM / CO / VOCTest Operators Russell / Moore / McKnightRUN No. 2Date 3-2-92Time start 1104 and 1205Meter Box RACS91349Sample Box 16.3Probe/Pitot 5' inc.Pitot Cp .84Nozzle Dia. .235Filter No. Amb. Temp. °F 74Bar. Press. "Hg 30.08Static Press. "H₂O -13No. Sample Pts. 1202Minutes/Pt. 2.5

NOMOGRAPH

ΔH@ 1.8Meter Temp. % H₂O C-Factor Stack Temp. Ref. ΔP .59Gas Analysis indirectCO₂ 0.0 0.0 oneO₂ AirCO NDIR = 10 ppmTime

Condensate:

tare 200 fin 205

Silica gel:

tare 678 fin 686

Remarks:

1/OC = 41.5

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg
1	000	970.542	0.76	2.40	111	113 105	250	70	4
2	230	972.8	0.76	2.40	101	116 105	255	66	4
3	500	975.2	0.46	1.45	96	120 105	255	60	4
4	730	976.9	0.46	1.45	100	123 106	255	66	4
5	1000	978.9	0.20	0.63	109	124 105	260	65	2
6	1230	980.0	0.05	0.16	100	124 105	265	62	2
7	1500	981.0	0.54	1.70	98	123 106	270	60	2
8	1730	982.6	0.65	2.00	96	125 105	245	58	2
9	2000	984.2	0.79	2.50	95	127 105	225	58	4
10	2230	986.8	0.70	2.20	99	131 106	230	58	4
11	2500	988.7	0.61	1.95	103	132 106	230	58	4
12	2730	990.6	0.45	1.45	102	134 106	235	58	2
13									
14	30/00	992.268	0.65	2.00	93	133 108	260	62	3
15	230	994.7	0.63	1.95	98	133 106	265	58	3
16	500	996.4	0.40	1.25	97	133 106	260	58	2
17	730	997.9	0.39	1.25	106	133 106	245	62	2
18	1000	999.5	0.18	0.56	103	132 107	225	62	2
19	1230	000.7	0.04	0.12	96	131 107	230	60	2
20	1500	001.4	0.42	1.30	111	128 107	195	62	2
21	1730	003.0	0.71	2.20	102	129 107	165	62	2
22	2000	005.0	0.72	2.30	104	131 108	160	60	2
23	2230	007.0	0.36	1.15	107	134 108	160	60	2
24	2500	008.6	0.39	1.20	99	134 109	180	60	2
25	2730	010.1	0.38	1.20	100	134 110	200	60	2
26	and 60	011.689							
27									
28									
29									
30									
31									
32									
33									
34									
35									

Leak check: .049 → .061 = .012 @ 6" H₂O
 pitot @ 8.0
 pitot @ 7.6

41.147

6729

1.5321

101.08

117.31

Plant Kirby Forest Industries
 Sampling Location No. 3 Pass Vent
 Test For pm/cpm/co/voc
 Test Operators Russell / Moore / McKnight

RUN No. 3
 Date 3-2-92
 Time start 1231 end 1332

Meter Box	<u>RACS91349</u>	No. Sample Pts.	<u>12x2</u>	Gas Analysis	<u>int. or ext.</u>	Remarks: <u>AVG VOC = 58.7</u>
Sample Box	<u>N/A</u>	Minutes/Pt.	<u>2.5</u>	CO ₂	<u>0.0</u>	
Probe/Pitot	<u>#5" inc.</u>			O ₂	<u>20.9</u>	
Pitot Cp	<u>.84</u>	NOMOGRAPH		CO	<u>NDIR = 10 ppm</u>	
Nozzle Dia.	<u>.235</u>	ΔH@	<u>1.85</u>	Time		
Filter No.		Meter Temp.	<u>100</u>	Condensate:		
		% H ₂ O	<u>< 10</u>	tare	<u>200</u> fin <u>202</u>	
Amb. Temp. °F	<u>74</u>	C-Factor	<u>1.0</u>	Silica gel:		
Bar. Press. "Hg	<u>30.08</u>	Stack Temp.	<u>100</u>	tare	<u>663</u> fin <u>671.5</u>	
Static Press. "H ₂ O	<u>-.13</u>	Ref. ΔP	<u>.59</u>			

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg
1	000	012.228	0.60	1.90	98	114	107	200	66	2
2	230	014.3	0.57	1.75	101	116	110	210	62	2
3	500	016.5	0.32	1.00	101	123	110	190	62	2
4	730	017.6	0.35	1.15	96	125	112	185	62	2
5	1000	019.3	0.23	0.73	95	123	113	220	64	2
6	1230	020.7	0.03	0.10	104	125	114	200	60	2
7	1500	021.2	0.49	1.55	100	123	111	175	62	2
8	1730	022.8	0.74	2.30	95	128	112	145	60	2
9	2000	024.9	0.67	2.10	96	128	109	160	58	2
10	2230	027.0	0.76	2.40	99	131	109	185	58	2
11	2500	029.2	0.58	1.80	104	133	108	200	58	2
12	2730	031.2	0.42	1.30	100	134	110	210	57	2
13										
14	3000	032.718	0.69	2.20	93	133	112	220	58	2
15	230	035.4	0.70	2.20	101	134	110	210	58	2
16	500	037.0	0.40	1.25	106	136	111	220	58	2
17	730	038.7	0.39	1.25	100	135	110	220	60	2
18	5	040.2	0.18	0.56	96	140	112	230	60	2
19	1000	041.5	0.05	0.15	96	133	111	230	65	2
20	1230	042.3	0.43	1.30	98	132	112	235	65	2
21	1500	043.9	0.75	2.30	103	135	114	225	62	2
22	1730	045.8	0.73	2.30	100	133	112	215	58	2
23	2000	047.9	0.40	1.25	101	136	113	220	58	2
24	2230	050.0	0.41	1.30	92	140	114	220	60	2
25	2500	051.7	0.40	1.25	100	138	114	220	62	2
26	2730	053.229								
27										
28										
29										
30										
31										
32										
33										
34										
35										

leak check: 020 → .027 = 2007 cfm @ 9" w/g
 pitot + ve 7.0
 pitot - ve 7.0

41.00' .6606 1.4746 98.96 120.79

PARTICULATE SAMPLE ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby - Silsbee DGB P. Valt 3
 DATE TAKEN: 3-2-92 SAMPLING TEAM: Russell - Moore - McKnight
 SAMPLES RECOVERED BY: DGR DATE RECOVERED: 3-2-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 6
PV3 R1 Filt
PV3 R2 Filt PV3 R3 Action
PV3 R3 Filt } gravimetric
PV3 R1 Action
PV3 R2 Action

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovery by RSM to DGR on 3-2-92
Transfer by DGR on 3-3-92
Analysis by DGR on 3-5-92 } 1 David G. Russell

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least
24 hours, weighed to constant weight

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	440	441	442	
FILTER TARE, gms	.5669	.5680	.5676	
1st weighing	.5669	.5683	.5677	
2nd weighing	.5667	.5684	.5676	
3rd weighing				
FINAL WEIGHT, gms.	.5669	.5684	.5676	
NET GAIN, gms.	0	.0004	0	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat,
desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER ID	PV3R1	PV3R2	PV3R3	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	120	120	150	
TARE WT., gms.	(1) 103.1987	(3) 104.6360	(9) 114.8241	
1st weighing	103.2019	104.6333	114.8269	
2nd weighing	103.2018	104.6333	114.8265	
3rd weighing				
FINAL WEIGHT, gms.	103.2018	104.6333	114.8265	
NET GAIN, gms.	.0031	.0033	.0029	
LESS BLANK, gms.	-.0001	-.0001	-.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	3.0	3.6	2.3	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kirby - Silabon OSB Run Int No. 3
 DATE TAKEN: 3-2-92 SAMPLING TEAM: Russell - Moore - Indigitt
 SAMPLES RECOVERED BY: RSM DATE RECOVERED: 3-2-92
 SAMPLE ID/ANALYSES REQUIRED: NO. OF CONTAINERS: 3
PV3R1 BAK
PV3R2 BAK } methylene chloride extraction / gravimetric
PV3R3 BAK

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovered by RSM on 3-2-92 to OGR
Transported by OGR on 3-3-92
Analysis by OGR on 3-31-92 } Dr. G. K. Brown

RUN NO.	1	2	3	
CONTAINER ID	PV3R1	PV3R2	PV3R3	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	300 300	250	250	

AQUEOUS FRACTION 3-2-92

TARE WT., gms.	60 112.2245	112.5383	112.5842	
1st weighing	113.2252	112.5395	112.5858	
2nd weighing	113.2251	112.5391	112.5855	
3rd weighing				
FINAL WEIGHT, gms.	113.2251	112.5391	112.5855	
NET GAIN, gms.	.0006	.0008	.0013	
LESS BLANK, gms.	—	—	—	

ORGANIC FRACTION 3-31-92

TARE WT., gms.	111.5467	111.8045	111.3441	
1st weighing	111.5471	111.8047	111.3453	
2nd weighing	111.5468	111.8050	111.3455	
3rd weighing				
FINAL WEIGHT, gms.	111.5468	111.8050	111.3455	
NET GAIN, gms.	.0001	.0005	.0014	
LESS BLANK, gms.	—	—	—	

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	0.6	0.8	1.3	
Organic fraction	0.1	0.5	1.4	

Plant Kirby
Source Vent No. 3
Test For VOC
Test Operators Russell

RUN NO. 1, 2, 3
Date 8-2-92
Time start 0958/1104/1231
Time end 1029/1205/1332

		Time: <u>0940/1055/210</u>			Time: <u>1055/1210/240</u>					
FID ANALYZER CALIBRATION DATA	Cylinder Value, ppm	Initial analyzer response			Final analyzer response			Difference ppm		
Zero gas	0	0	0	0	0	0	0	0	0	0
Low-level gas	31.1	31	31	31	32	32	32	7	1	1
Mid-level gas	83.2	83	83	83	83	88	85	0	5	2
High-level gas	830	830	830	830	835	850	830	5	20	0

[illegible]

PRESS VENT NO. 4

Plant Kinky Forest
 Sampling Location Press Vent No. 4
 Test For PM/CPM/CO/NO
 Test Operators Russell/Moore/McKnight

RUN No. 1
 Date 2-29-92
 Time start 1220 end 1321

Meter Box RAC591349
 Sample Box 10.3
 Probe/Pitot 5' inc.
 Pitot Cp .84
 Nozzle Dia. .235
 Filter No.
 Amb. Temp. °F 78
 Bar. Press. "Hg 29.93
 Static Press. "H₂O -.11

No. Sample Pts. 12 x 2
 Minutes/Pt. 2.5
 NOMOGRAPH
 ΔH@ 1.85
 Meter Temp. 100
 % H₂O <10
 C-Factor 1.0
 Stack Temp. 100
 Ref. ΔP .595

Gas Analysis int. vent
 CO₂ 0 0 0
 O₂ 20.9 20.9 20.9
 CO 11 10 10 ppm
 Time
 Condensate:
 tare 200 fin 202
 Silica gel:
 tare 642 fin 659

Remarks:
DN Calibration
D.236
D.235 } .235
D.234
VOC = 42.8

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp. °F In	Meter Temp. °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg
1	000	557.063	0.86	2.65	90	85	83	230	63	2
2	230	558.7	0.50	1.50	89	87	83	250	60	2
3	500	560.6	0.40	1.20	90 90	84	83	265	65	3
4	730	562.3	0.38	1.15	90	97	83	250	63	2
5	1000	563.9	0.11	0.32	90	100	85	250	63	2
6	1230	564.7	0.10	0.30	90	102	85	240	63	2
7	1500	565.5	0.54	1.65	88	106	86	230	63	3
8	1730	567.1	0.77	2.35	90	108	88	250	64	3
9	2000	569.3	0.53	1.65	90	113	89	220	60	3
10	2230	571.0	0.53	1.65	90	118	91	230	60	3
11	2500	572.6	0.48	1.45	90	120	92	240	61	3
12	2730	574.6	0.43	1.35	91	122	94	240	62	3
13										
14	3000	576.050	0.70	2.15	91	122	96	250	62	3
15	230	577.9	0.51	1.45	92	125	97	240	60	3
16	500	579.8	0.34	1.00	91	126	98	250	60	3
17	730	581.3	0.29	0.88	90	127	100	230	60	3
18	1000	582.6	0.08	0.24	93	126	93	210	60	2
19	1230	583.9	0.07	0.22	93	127	95	240	60	2
20	1500	584.6	0.19	0.60	90	127	94	230	60	2
21	1730	585.7	0.54	1.65	91	125	97	230	60	3
22	2000	587.3	0.57	1.75	90	128	99	230	60	3
23	2230	589.3	0.61	1.85	90	130	103	250	62	3
24	2500	591.0	0.50	1.50	90	122	107	240	66	3
25	2730	593.0	0.35	1.00	89	135	108	255	64	2
26	End	594.701								
27										
28										
29										
30										
31										
32										
33										
34										
35										

Leak check: .060 → .066 = .006 lps 7" h
 pitot + .3.3
 pitot - .8.9
 37.238 .6322 1.3088 90.33 104.40

Plant Kirby Forest

Sampling Location _____

Test For PM/CPM/CO/VOCTest Operators Russell / Moore / McKnightRUN No. 2Date 2-29-92Time start 1456 end 1609Meter Box RALS91349Sample Box Nb. 1Probe/Pitot 5' inc.Pitot Cp .84Nozzle Dia. 2.35

Filter No. _____

No. Sample Pts. 12 x 2Minutes/Pt. 2.5

NOMOGRAPH

 $\Delta H @$

Meter Temp.

% H₂O

C-Factor

Stack Temp.

Ref. ΔP Gas Analysis interactCO₂ 0.0 0.0 0.0O₂ 4.4

CO _____

Time _____

Condensate:

tare 200 fin 203

Silica gel:

tare 633 fin 649

Remarks: _____

* delta for probe dia
@ 1535
up @ 1543changed VOC probe
to 3 hole snake type
VOC = 32.8

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg
1	000	594.548	0.87	2.65	88	100	98	170	70	2
2	230	597.1	0.66	2.05	88	102	98	180	60	2
3	500	599.0	0.35	1.15	89	107	96	180	60	2
4	730	600.4	0.32	0.96	89	110	100	210	70	2
5	1000	602.0	0.11	0.34	90	112	101	220	65	2
6	1230	602.9	0.06	0.18	89	113	100	225	65	2
7	1500	603.8	0.56	1.70	89	114	101	240	55	2
8	1730	605.1	0.85	2.60	89	115	102	245	60	2
9	2000	607.3	0.64	1.90	89	121	104	250	60	2
10	2230	609.9	0.40	1.20	89	125	103	250	60	2
11	2500	611.1	0.45	1.35	88	128	106	250	60	2
12	2730	612.9	0.36	1.10	92	128	105	250	60	2
13										
14	20/00	614.164	0.60	1.80	93	127	108	240	63	2
15	230	616.0	0.74	2.30	94	128	107	250	60	2
16	3	618.0	0.47	1.45	92	121	109	230	60	2
17	4	621.6	0.18	0.55	96	121	109	230	60	2
18	5	622.5	0.06	0.18	95	120	109	200	60	2
19	6	623.9	0.25	0.75	94	119	109	190	65	2
20	7	624.8	0.59	1.75	96	120	109	150	62	2
21	8	626.6	0.53	1.65	96	122	109	165	60	2
22	9	628.7	0.25	0.76	95	125	110	155	59	2
23	10	628.6	0.52	1.60	97	123	110	150	59	2
24	11	629.9	0.58	1.75	94	128	112	150	59	2
25	12	631.8	0.42	1.30	93	128	112	190	60	2
26	End	633.196								

leak check: 1093 → 1097 = .004
 pitot + ve
 pitot - ve

38.648 .6445 1.3758 91.83 112.17

Plant Kirby Forest Industries
 Sampling Location No. 4 Press Vent
 Test For PM/CPM/KO/VOC
 Test Operators Russell/More/McKnight

RUN No. 3
 Date 2-29-93
 Time start 1643 and 1744

Meter Box	<u>RACS91349</u>	No. Sample Pts.	<u>12 x 2</u>	Gas Analysis	<u>int-rmt</u>	Remarks: <u>VOC=42.8</u>	
Sample Box	<u>N/A</u>	Minutes/Pt.	<u>2.5</u>	CO ₂	<u>0.0</u> <u>0.0</u> <u>0.0</u>		
Probe/Pitot	<u>Sine</u>	NOMOGRAPH			O ₂		<u>20.8</u> <u>Air</u> <u>-</u>
Pitot Cp	<u>87</u>	ΔH@			CO		<u>-</u> <u>-</u> <u>-</u>
Nozzle Dia.	<u>.235</u>	Meter Temp.			Time		<u>-</u> <u>-</u> <u>-</u>
Filter No.	<u>-</u>	% H ₂ O			Condensate:		
Amb. Temp. °F	<u>84</u>	C-Factor			tare	<u>200</u> fin <u>200</u>	
Bar. Press. "Hg	<u>29.93</u>	Stack Temp.			Silica gel:		
Static Press. "H ₂ O	<u>- .11</u>	Ref. ΔP			tare	<u>659.0</u> fin <u>681.0</u>	

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	
1	000	633.542	0.86	2.65	93	106	106	265	73	5	1.0
2	230	625.7	0.53	1.65	89	108	104	260	61	3	
3	500	637.8	0.35	1.10	92	110	104	250	60	2	1.0
4	730	639.4	0.28	0.86	94	117	104	230	65	2	
5	1000	641.0	0.15	0.46	95	118	108	230	65	2	1.0
6	1230	642.1	0.08	0.24	90	117	105	250	60	2	
7	1500	642.8	0.59	1.80	90	120	106	235	62	2	1.0
8	1730	644.9	0.88	2.70	89	122	107	245	60	4	
9	2000	646.6	0.60	1.80	94	127	107	265	60	3	1.0
10	2230	648.7	0.46	1.40	95	130	109	250	60	3	
11	2500	650.5	0.44	1.35	94	134	109	230	60	2	1.0
12	2730	652.5	0.21	0.95	94	132	110	235	62	2	
13											
14	30/20	653.566	0.73	2.20	95	132	111	240	62	3	1.0
15	330	655.5	0.67	2.10	96	132	111	250	60	3	
16	500	657.8	0.30	0.90	95	135	112	270	62	4	1.0
17	730	659.9	0.25	0.75	94	135	113	260	60	4	
18	1000	661.2	0.09	0.28	94	135	113	245	62	4	1.0
19	1230	662.3	0.07	0.22	95	133	115	215	62	2	
20	1500	662.7	0.36	1.10	90	131	114	235	62	2	1.0
21	1730	664.1	0.77	2.40	92	132	116	240	60	2	
22	2000	666.1	0.59	1.80	92	134	118	200	62	2	1.0
23	2230	667.9	0.57	1.75	95	136	116	225	62	2	
24	2500	669.7	0.50	1.55	94	137	116	245	64	2	1.0
25	2730	671.4	0.44	1.35	96	137	119	270	66	2	
26	end 60	672.979									
27											
28											
29											
30											
31											
32											
33											
34											
35											

Leak check: 944 → 1.0 SO 1.006 ftm @ 8 "Hg
 pitot - 6.6
 pitot - 127.0

29.437 .6451 1.3900 93.25 118.71

SAMPLES/PROJECT: Kirby - Silica 1583 Private No. 4
 DATE TAKEN: 2-29-92 SAMPLING TEAM: Russell-Moon-McKnight
 SAMPLES RECOVERED BY: RSM DATE RECOVERED: 2-29-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 6

PV4R1 Filter
 PV4R2 Filter PV4R2 Acetone
 PV4R3 Filter PV4R3 Acetone } gravitation
 PV4R1 Acetone

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovered 2-29-92 RSM to DGR
 Transported 3-3-92 by DGR
 Analysis 3-5-92 by DGR } David C. Rasmussen

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	432	431	433	
FILTER TARE, gms	.5665	.5653	.5679	
1st weighing	.5672	.5677	.5685	
2nd weighing	.5671	.5672	.5685	
3rd weighing				
FINAL WEIGHT, gms.	.5671	.5677	.5685	
NET GAIN, gms.	.0006	.0024	.0006	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER ID	PV4R1	PV4R2	PV4R3	
VOLUME INTACT?	✓	—	—	
VOLUME, ml	150	180	210	
TARE WT., gms.	(22) 99.0862	(26) 98.6772	(27) 98.8502	
1st weighing	99.0921	98.6813	98.8537	
2nd weighing	99.0923	98.6810	98.8536	
3rd weighing				
FINAL WEIGHT, gms.	99.0923	98.6810	98.8536	
NET GAIN, gms.	.0061	.0038	.0034	
LESS BLANK, gms.	— .0001	— .0001	— .0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	6.6	6.1	3.9	

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD.

PV 4

Back Half
Agnes

SAMPLES/PROJECT: _____
 DATE TAKEN: _____ SAMPLING TEAM: _____
 SAMPLES RECOVERED BY: _____ DATE RECOVERED: _____
 SAMPLE ID/ANALYSES REQUIRED: _____ NO. OF CONTAINERS: _____

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

RUN NO.				
FILTER NO.				
FILTER TARE, gms				
1st weighing				
2nd weighing				
3rd weighing				
FINAL WEIGHT, gms.				
NET GAIN, gms.				

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.				
CONTAINER ID				
VOLUME INTACT?				
VOLUME, ml				
TARE WT., gms.	(25) 97.0874	(27) 98.8474	(29) 98.3921	
1st weighing				
2nd weighing				
3rd weighing				
FINAL WEIGHT, gms.	97.0882	98.8500	98.3945	
NET GAIN, gms.	.0008	.0026	.0024	
LESS BLANK, gms.				

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.				
filter + probe	8	2.6	2.4	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kirk - Slaters OSB Prerep Vnt No. 4

DATE TAKEN: 2-29-92

SAMPLING TEAM: Russell - Moore - McKnight

SAMPLES RECOVERED BY: RSM

DATE RECOVERED: 2-29-92

SAMPLE ID/ANALYSES REQUIRED:

NO. OF CONTAINERS: 3

PV4R1 BAK }
PV4R2 BAK } Methyene chloride extraction / gravimetric
PV4R3 BAK }

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovered by RSM on 2-29-92 }
transported by DGR on 3-3-92 } D. J. G. Rasmussen
analyzed by DGR on 3-31-92 }

RUN NO.	1	2	3	
CONTAINER ID	PV4R1 BAK	PV4R2 BAK	PV4R3 BAK	
VOLUME INTACT?	☒	☒	☒	
VOLUME, ml	300 300	300	300	

AQUEOUS FRACTION

4-2-92

TARE WT., gms.	97.0874	98.8474	98.3921	
1st weighing	97.0889	98.8502	98.3957	
2nd weighing	97.0880	98.8500	98.3945	
3rd weighing	97.0882		98.3945	
FINAL WEIGHT, gms.	97.0882	98.8500	98.3945	
NET GAIN, gms.	.0008	.0026	.0024	
LESS BLANK, gms.	.0008	.0026	.0024	

ORGANIC FRACTION

3-31-92

TARE WT., gms.	114.7883	109.8912	112.8307	
1st weighing	114.7883	109.8919	113.8326	
2nd weighing	114.7887	109.8923	113.8321	
3rd weighing				
FINAL WEIGHT, gms.	114.7887	109.8923	113.8321	
NET GAIN, gms.	.0004	.0011	.0014	
LESS BLANK, gms.	—	—	—	

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	0.8	2.6	2.4	
Organic fraction	0.4	1.1	1.7	

PRESS VENT NO. 5

Plant Kirby Forest IndustriesSampling Location No. 5Test For PM/CPM/CO/VOCTest Operators Russell/Moore/McKnightRUN No. 1Date 3-1-92Time start 0953 and 1054Meter Box RAC 591249Sample Box No. 1Probe/Pitot SinePitot Cp .84Nozzle Dia. .235Filter No. Amb. Temp. °F 78Bar. Press. "Hg 30.04Static Press. "H₂O -.08No. Sample Pts. 12 x 2Minutes/Pt. 2.5

NOMOGRAPH

ΔH@ 1.85Meter Temp. % H₂O C-Factor Stack Temp. Ref. ΔP Gas Analysis int. actCO₂ 0.0 0.0 0.0O₂ AvCO NDIR = 5ppmTime

Condensate:

tare 200 fin 198

Silica gel:

tare 641 fin 659

Remarks:

VOC = 25.8

Port Point	El. Time, Min.	DGM Reading, Ft. ²	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	000	673.242	0.67	2.10	93	84	82	100	66	2	1.0
2	230	675.4	0.72	2.25	97	86	82	135	64	2	
3	500	677.3	0.47	1.45	97	90	82	145	65	2	1.0
4	730	679.0	0.43	1.30	91	90	83	170	64	2	
5	1000	680.6	0.20	0.60	97	98	84	200	65	2	1.0
6	1230	681.8	0.07	0.22	93	101	86	220	68	2	
7	1500	682.7	0.47	1.45	90	100	86	225	67	2	1.0
8	1730	684.0	0.84	2.50	93	102	88	205	59	2	
9	2000	685.8	0.63	2.10	98	106	85	210	55	2	1.0
10	2230	688.1	0.63	2.10	95	110	88	215	55	2	
11	2500	689.8	0.56	1.75	92	115	91	220	55	2	1.0
12	2730	691.6	0.40	1.20	96	117	91	225	55	2	
13											
14	3000	693.086	0.97	3.00	100	114	95	230	55	2	1.0
15	230	695.5	0.78	2.35	102	122	96	230	60	2	
16	500	697.7	0.54	1.65	94	126	99	235	59	2	1.0
17	730	699.5	0.35	1.05	93	127	99	235	55	2	
18	1000	701.0	0.21	0.63	90	127	101	240	58	2	1.0
19	1230	702.2	0.06	0.18	95	126	102	245	60	2	
20	1500	703.2	0.61	1.85	91	132	105	250	60	2	1.0
21	1730	704.9	0.96	2.00	94	127	105	245	59	2	
22	2000	707.6	0.97	3.00	99	131	105	245	59	2	1.0
23	2230	709.6	0.54	1.65	95	134	105	250	59	2	
24	2500	711.5	0.48	1.50	93	135	107	245	60	2	1.0
25	2730	713.2	0.34	1.05	90	135	108	245	60	2	
26	End 60	714.639									
27											
28											
29											
30											
31											
32											
33											
34											
35											

leak check: .036 → .049 = .013 cpe 8" H₂O

pilot + = 3.3
pilot - = 3.9

47.391 7060 1.6638 94.50 103.96

Plant Kirby Forest Industries
 Sampling Location No. 5 Power Plant
 Test For PM/CPM/VOL/CO
 Test Operators Russell/Moore/McKnight

RUN No. 2
 Date 3-1-92
 Time start 1119 end 1220

Meter Box RAC 591349
 Sample Box No. 3
 Probe/Pitot 5' inc.
 Pitot Cp .84
 Nozzle Dia. .235
 Filter No.
 Amb. Temp. °F 80
 Bar. Press. "Hg 30.04
 Static Press. "H₂O -.08

No. Sample Pts. 12 x 2
 Minutes/Pt. 2.5
 NOMOGRAPH
 $\Delta H @$ 1.9
 Meter Temp.
 % H₂O
 C-Factor
 Stack Temp.
 Ref. ΔP .6

Gas Analysis int. used
 CO₂ 0 0 0
 O₂ 20.8 9u 9u
 CO NDIR = 10ppm
 Time

Condensate:
 tare 200 fin 201
 Silica gel:
 tare 629.0 fin 636.5

Remarks:
39.0

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp. °F In	Meter Temp. °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	000	715.046	0.83	2.60	93	112	106	270	70	4	1.0
2	230	717.3	0.74	2.30	96	111	105	250	61	4	
3	500	719.7	0.82	0.96	92	117	106	225	60	2	1.0
4	730	721.1	0.31	0.94	101	117	107	230	60	2	
5	1000	722.8	0.17	0.50	100	114	105	260	63	2	1.0
6	1230	723.8	0.06	0.18	95	118	104	265	60	2	
7	1500	724.5	0.58	1.75	95	116	104	275	60	2	1.0
8	1730	726.1	0.56	1.70	93	117	104	260	60	3	
9	2000	728.2	0.80	2.40	100	119	104	235	53	3	1.0
10	2230	730.1	0.70	2.10	95	121	104	205	52	4	
11	2500	732.2	0.48	1.50	94	121	104	225	52	4	1.0
12	2730	734.2	0.49	1.50	91	126	105	235	55	2	
13											
14	3000	735.527	0.83	2.60	94	126	108	250	55	4	1.0
15	330	737.9	0.74	2.30	91	128	108	250	57	4	
16	500	740.0	0.43	1.35	97	132	109	270	55	4	1.0
17	730	742.0	0.32	0.96	90	132	111	235	59	4	
18	1000	743.3	0.14	0.43	95	134	112	230	55	2	1.0
19	1230	744.5	0.07	0.22	93	151	109	225	58	2	
20	1500	745.5	0.56	1.70	99	128	109	215	60	2	1.0
21	1730	747.3	0.82	2.50	95	126	111	230	60	2	
22	2000	749.3	0.98	3.00	99	130	110	250	60	2	1.0
23	2230	752.1	0.57	1.70	97	133	110	265	60	2	
24	2500	753.8	0.55	1.70	90	133	111	270	60	2	1.0
25	2730	755.7	0.55	1.70	90	134	111	260	60	2	
26	end 60	757.217									
27											
28											
29											
30											
31											
32											
33											
34											
35											

hook check @ 1099 → 108 = .009 d/e 8 " 1/2
 pitot - v 5.3
 pitot - v 6.9

43.71 .6958 1.6079 94.71 115.48

Plant Kirby Forest IndustriesSampling Location No. 5 Press VentTest For PM / LPM / CO / VOCTest Operators Russell / Moore / McKnightRUN No. 3Date 2-1-92Time start 1321 end 1422Meter Box RAC 591349Sample Box No. 1Probe/Pitot 5" inc.Pitot Cp .84Nozzle Dia. .235Filter No. Amb. Temp. °F 80Bar. Press. "Hg 30.04Static Press. "H₂O -.08No. Sample Pts. 12 x 2Minutes/Pt. 2.5

NOMOGRAPH

ΔH@ 1.85Meter Temp. % H₂O C-Factor Stack Temp. Ref. ΔP .6Gas Analysis int. reactCO₂ 0.0 0.0 2.0O₂ 20.8 - -CO 10 ppm - -Time

Condensate:

tare 200 fin 200

Silica gel:

tare 643.5 fin 657.5

Remarks:

VOC = 32.9

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac. in. Hg	CO Lpm
1	000	757.532	0.72	2.20	100	100	98	110	67	2	1.0
2	230	759.9	0.73	2.25	97	101	99	120	69	2	1.0
3	500	761.8	0.41	1.25	95	102	101	125	65	2	1.0
4	730	763.0	0.50	1.55	103	111	101	162	65	2	1.0
5	1000	765.7	0.26	0.80	100	113	101	180	65	2	1.0
6	1230	766.6	0.06	0.18	96	117	104	195	65	2	1.0
7	1500	767.3	0.46	1.40	95	120	104	220	65	2	1.0
8	1730	769.0	0.67	2.10	97	121	106	215	64	2	1.0
9	2000	771.1	0.77	2.40	92	125	105	230	59	2	1.0
10	2230	773.3	0.75	2.30	99	129	107	240	58	2	1.0
11	2500	775.2	0.66	2.05	95	132	109	245	58	2	1.0
12	2730	777.3	0.37	1.15	94	136	109	250	58	2	1.0
13								250	58	2	1.0
14	30/100	779.183	0.79	2.40	99	136	111	250	62	2	1.0
15	230	781.4	0.68	2.10	99	136	111	225	55	2	1.0
16	500	783.5	0.36	1.10	92	139	114	240	55	2	1.0
17	730	785.1	0.39	1.15	95	138	114	240	55	2	1.0
18	1000	786.6	0.20	0.60	103	136	116	230	55	2	1.0
19	1230	787.8	0.05	0.15	100	135	114	230	58	2	1.0
20	1500	788.7	0.50	1.50	95	139	116	235	60	2	1.0
21	1730	790.1	0.97	3.00	96	136	120	230	60	2	1.0
22	2000	792.5	0.78	2.40	106	138	117	225	62	2	1.0
23	2230	795.0	0.55	1.70	98	139	118	240	59	2	1.0
24	2500	796.5	0.52	1.60	94	141	117	250	60	2	1.0
25	2730	798.3	0.48	1.50	94	142	118	245	60	2	1.0
26	End 60	799.977									
27											
28											
29											
30											
31											
32											
33											
34											
35											

Leak check: 1092 → 1105 = .013 in @ 10" Hg
 pitot - ve 6.9
 pitot - ve 7.8
 42.445 .7062 1.6179 97.25 11869

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby-Silabee DSB Permit No. 5
 DATE TAKEN: 3-1-92 SAMPLING TEAM: Russell/Mun/Reknight
 SAMPLES RECOVERED BY: RSR DATE RECOVERED: 3-1-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 6
PVSR1 Filter
PVSR2 Filter PVSR3 Action } gravimetric
PVSR3 Filter
PVSR1 Action
PVSR2 Action

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovered by RSR on 3-1-92 to DGR
transported by DGR on 3-2-92
analysis by DGR on 3-5-92 } Phil G. R...

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	434	435	436	
FILTER TARE, gms	.5659	.5667	.5658	
1st weighing	.5666	.5664	.5655	
2nd weighing	.5666	.5663	.5655	
3rd weighing				
FINAL WEIGHT, gms.	.5666	.5663	.5656	
NET GAIN, gms.	.0007	-.0004	-.0002	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat, desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER ID	PVSR1	PVSR2	PVSR3	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	100	150	150	
TARE WT., gms.	(29) 98.3960	(31) 95.7680	(32) 97.5695	
1st weighing	98.3989	95.7684	97.5735	
2nd weighing	98.3988	95.7688	97.5730	
3rd weighing				
FINAL WEIGHT, gms.	98.3988	95.7688	97.5730	
NET GAIN, gms.	.0028	.0008	.0035	
LESS BLANK, gms.	-.0001	-.0001	-.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1	2	3	
filter + probe	3.4	0.3	3.2	

**PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:
FOR BACK HALF EXTRACTION ANALYSIS**

SAMPLES/PROJECT: Kirby - Silebe DSB Pres Vat No. 5
 DATE TAKEN: 3-1-92 SAMPLING TEAM: Russell/Mann/McKnight
 SAMPLES RECOVERED BY: RSM DATE RECOVERED: 3-1-92
 SAMPLE ID/ANALYSES REQUIRED: No. OF CONTAINERS: 3

~~PVSR1 BAK~~
 PVSR2 BAK } meth for chloride / gravimetric
 PVSR3 BAK }

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

Recovered by RSM on 3-1-92 to OGR
transported by OGR on 3-3-92 } James S. Rann
analysis by OGR on 3-31-92

RUN NO.		2	3	
CONTAINER ID	PVSR1 BAK	PVSR2 BAK	PVSR3 BAK	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	250	250	250	

AQUEOUS FRACTION 4-2-92

TARE WT., gms.	111.8028	114.7843	109.8903	
1st weighing	111.8026	114.7864	109.8921	
2nd weighing	111.8033	114.7864	109.8920	
3rd weighing				
FINAL WEIGHT, gms.	111.8033	114.7864	109.8920	
NET GAIN, gms.	.0005	.0021	.0017	
LESS BLANK, gms.	—	—	—	

ORGANIC FRACTION 3-31-92

TARE WT., gms.	97.0921	105.8234	104.6318	
1st weighing	95.0029	105.8241	104.6335	
2nd weighing	95.0925	105.8236	104.6336	
3rd weighing				
FINAL WEIGHT, gms.	95.0925	105.8236	104.6336	
NET GAIN, gms.	.0004	.0002	.0018	
LESS BLANK, gms.	—	—	—	

BACK HALF PARTICULATE SAMPLE WEIGHT, mg.

Aqueous fraction	0.5	2.1	1.7	
Organic fraction	0.4	0.2	1.8	

Plant <u>Kirby</u>	RUN NO. <u>1, 2, 3</u>
Source <u>No. 5 Press Vent</u>	Date <u>3-1-92</u>
Test For <u>VOc</u>	Time start <u>0953/1149/132</u>
Test Operators <u>Russen</u>	Time end <u>1054/1220/1423</u>

		Time: 08/01/00/12/10			Time: 11/00/12/10/1425					
FID ANALYZER CALIBRATION DATA	Cylinder Value, ppm	Initial analyzer response			Final analyzer response			Difference ppm		
Zero gas	0	0	0	0	0	0	0	0	0	0
Low-level gas	31.1	31	31	30	31	30	31	0	1	1
Mid-level gas	83.2	83	82	82	82	83	85	1	1	2
High-level gas	830	830	835	830	835	840	830	5	5	0

[illegible]

APPENDIX B: CALIBRATION DATA

DRY GAS METER CALIBRATION

Meter ID Rac 591349

Date 2/22/92

Calibration Method DGM/DGM

By DGR

Calibration Meter ID 651729

Pbar 29.56

Vac	DH	Time	Calibrating Meter			Field Meter						Y	Q	K	DH@
			Vi cf	Vf cf	Temp F	Vi cf	Vf cf	Temp in		Temp out					
								initial	final	initial	final				
1	4.00	9.17	437.136	447.068	68	718.602	728.779	72	95	71	74	.9729	1.2048	0.744	1.67
1	3.00	10.6	447.068	456.814	66	728.779	738.918	95	109	74	81	.9853	1.0177	0.72	1.77
1	2.00	12.8	456.814	466.268	65	738.918	748.929	108	113	82	88	.9864	0.8309	0.712	1.81
1	1.50	15.6	466.268	476.154	66	748.929	759.548	113	118	87	95	.9813	0.733	0.72	1.78
1	1.00	17.3	476.154	485.584	68	759.548	769.651	117	118	95	100	.9887	0.6315	0.753	1.63
Average												.9829			1.73

$$Y = [V_{cal} (P_{bar}) (T_{dgm})] / [(V_{dgm}) (P_m) (T_{cal})]$$

$$K = Q(\sqrt{(P_m \text{ Mm}) / ((T_m \text{ out}) (DH))})$$

$$Q = ((V_{mi} - V_{mf}) / \text{min.}) (T_{m, out} / T_{m, avg}) (Y)$$

$$DH@ = 0.921 / K^2$$

WHERE:

Y = Meter correction factor

Vcal = Volume of gas through calibrating meter, cubic feet

Vdgm = Volume of gas through field dry gas meter, cubic feet

Pbar = Barometric pressure, in. Hg

Pm = Meter pressure, (Pbar + DH/13.6)

Tdgm = Average dry gas meter temp., degrees F

Tcal = Temperature of gas at calibrating meter

THERMOMETER/THERMOCOUPLE CALIBRATION

Date: 2-27-92

By: DR

Reference Thermometer ASTM Hz / glass 20°-760°F

Last Service _____

Field Thermometer	Temp. Source	Reference Temperature	Field Therm. Temperature	% error, absolute
S' T'couple Omega 650	No. 4 Oxyacetylene	177 +80°F	180°F	< 1
Meter In Omega 650	VAN Ant.	79	80	< 1
Meter Out Omega 650	VAN Ant.	79	80	< 1
Impinger out Bimetal-dial	VAN Ant.	79	79	-
Sample Box Bimetal-dial	Box No. 3	266	265	< 1

PITOT TUBE GEOMETRY CALIBRATION

Pitot tube/probe identification: 5' inc.


Date Checked: 2-27-92 By: OGP

1. Pitot tubes having the following geometric characteristics are assigned a pitot tube coefficient of 0.84.

1. Face openings perpendicular to transverse axis: (α_1 and $\alpha_2 < 10^\circ$)

$\alpha_1 = \underline{0}$

$\alpha_2 = \underline{0}$



2. Face openings parallel to longitudinal axis: (β_1 and $\beta_2 < 5^\circ$; $P = 1.05 D_t$ to $1.50 D_t$; $P_A = P_B$)

$D_t = \underline{.375''}$

$\beta_1 = \underline{0}$

$P_A = \underline{.46''}$

$\beta_2 = \underline{0}$


$P_B = \underline{.46''}$



3. Both legs equal length and centerline coincident ($z < .125$ inch; $w < .031$ inch)

$z = \underline{0}$

$w = \underline{0}$



PITOT/PROBE CLEARANCE CHECK:

Nozzle ID: .196

Nozzle dia: .196

Date: 2-27-92

II. Pitot/probe/nozzle assemblies have the same C_p as the isolated Pitot tube when the following conditions exist.

1. $D_t > .188$ & $< .375$ inch

$D_t = \underline{.375''}$

2. $X_1 \geq .75$ inch

$X_1 = \underline{.95''}$

3. $X_2 \geq 0$ inch



$X_2 = \underline{.30''}$

4. $Y \geq 3.0$ inch

$Y = \underline{6.25''}$

5. $z \geq 2.0$ inch

$z = \underline{2.25''}$



PITOT TUBE GEOMETRY CALIBRATION

Pitot tube/probe identification: 5' inc


Date Checked: 2-24-92 By: DGA

Pitot tubes having the following geometric characteristics are assigned a pitot tube coefficient of 0.84.

1. Face openings perpendicular to transverse axis: (α_1 and $\alpha_2 < 10^\circ$)

$$\alpha_1 = \underline{0}$$

$$\alpha_2 = \underline{0}$$



2. Face openings parallel to longitudinal axis: (β_1 and $\beta_2 < 5^\circ$; $P = 1.05 D_t$ to $1.50 D_t$; $P_A = P_B$)

$$D_t = \underline{.375}$$

$$\beta_1 = \underline{0}$$

$$P_A = \underline{.46}$$

$$\beta_2 = \underline{0}$$


$$P_B = \underline{.46}$$



3. Both legs equal length and centerline coincident ($z < .125$ inch; $w < .031$ inch)

$$z = \underline{0}$$

$$w = \underline{0}$$



PITOT/PROBE CLEARANCE CHECK:

Nozzle ID: .235

Nozzle dia: .235"

Date: 2-24-92

II. Pitot/probe/nozzle assemblies have the same C_p as the isolated Pitot tube when the following conditions exist.

1. $D_t > .188$ & $< .375$ inch

$$D_t = \underline{.375''}$$

2. $X_1 \geq .75$ inch

$$X_1 = \underline{.88''}$$

3. $X_2 \geq 0$ inch



$$X_2 = \underline{.50''}$$

4. $Y \geq 3.0$ inch

$$Y = \underline{6.25''}$$

5. $z \geq 2.0$ inch

$$z = \underline{2.25''}$$



AIRCO Industrial Gases
Division of the BOC Group, Inc.
1075 Cinclare Drive
Port Allen, LA 70767

Telephone: 504-388-0900
FAX: 504-388-0959

Date Reported: 12/18/91

Customer Order No.: 2004

Shipper No.: 463452

Test No.: 1291-051

ANALYTICAL REPORT

To: ANDRIES
317 WEST RANKIN
JACKSON, MS 39207

Material Submitted: PROPANE IN NITROGEN

Information Requested: PROPANE CONCENTRATION

Method of Analysis: GAS CHROMATOGRAPHY

Result of Investigation: Cyl.No.: N-421999

<u>Component</u>	<u>Specification</u>	<u>Concentration</u>
PROPANE	30 PPM	31.1 PPM
NITROGEN	BAL.	BAL.

Principal Analyst: C. Simon

AIRCO Industrial Gases
Division of the BOC Group, Inc.
1075 Cinclare Drive
Port Allen, LA 70767

Telephone: 504-388-0900
FAX: 504-388-0959

Date Reported: 12/18/91

Customer Order No.: 2004

Shipper No.: 463452

Test No.: 1291-052

ANALYTICAL REPORT

To: ANDRIES
317 WEST RANKIN
JACKSON, MS 39207

Material Submitted: PROPANE IN NITROGEN

Information Requested: PROPANE CONCENTRATION

Method of Analysis: GAS CHROMATOGRAPHY

Result of Investigation: Cyl.No.: N-101038

<u>Component</u>	<u>Specification</u>	<u>Concentration</u>
PROPANE	80 PPM	83.2 PPM
NITROGEN	BAL.	BAL.

Principal Analyst: Simon

AIRCO Industrial Gases
Division of the BOC Group, Inc.
1075 Cinclare Drive
Port Allen, LA 70767

Telephone: 504-388-0900
FAX: 504-388-0959

Date Reported: 12/18/91

Customer Order No.: 2004

Shipper No.: 463452

Test No.: 1291-053

ANALYTICAL REPORT

To: ANDRIES
317 WEST RANKIN
JACKSON, MS 39207

Material Submitted: PROPANE IN NITROGEN

Information Requested: PROPANE CONCENTRATION

Method of Analysis: GAS CHROMATOGRAPHY

Result of Investigation: Cyl.No.: N-413828


<u>Component</u>	<u>Specification</u>	<u>Concentration</u>
PROPANE	800 PPM	830 PPM
NITROGEN	BAL.	BAL.

Principal Analyst: C. Lemorini

C. VOC AND CO TRACES

PART NO. LO/2

PRINTED IN U.S.A.



2 - 24 - 9 R

Blk. Forest Production Inc VOC Ltr

PART NO. LO/6011

radio spike

TEST RZ 1824
DRYER NO. 1
2-24-97

1877

INSEIS

1802
Composite
Trace of
Run 1

1747

8300 ppm Phosphorus

1732

700 ppm CO

830 ppm
Phosphorus
140 ppm
CO
50 ppm
CO

and 1717
Run 1
DRYER NO. 1

1702

Change into

1647

PART NO. LG/6011

PRINTED IN U.S.A.

Start 2010
Rm 3
DRYER No. 1
9-24-92

2002

Composite
CO Trace of Run 2

Cal 50 CO

Calib. 832 ppm
Cal. 700 ppm Co

830 1932
ppm
proper

LINE IS

END Run 2

Single Run No. 2

had luck through Calib. time

1907

1902

Ch. ports

1847

1832

radio spike

PART NO. 10/8011

PRINTED IN U.S.A.

no data 2009

END R3 DRYER NO.1
2-24-92

2410

235

235

220

230

235

no data

230

230

225

220

OK (go) - CR. PORTS -

no data (SEP)

LINE IS

209

220

230

235

235

no data 2046

stop @ 2022

no data

START 2010
R3
DRYER NO.1
9-24-92

2132

2117

2102

2047

2022

2017

2002

PART NO. LD/8011
IN U.S.A.

205
220
215
210
215
210
210

Radio Spike

Radio Spike

START R 140134Z
DRYER NO. 2
2-25-92

1401

1346

1331

700 ppm CO

31.1 ppm propane

83.2 ppm propane

INSELS

830 ppm propane

2-25-92

END ALK 2-24-92

31.1 ppm propane

87.2 ppm propane

830 ppm propane

112

cal 150 ppm CO
cal 50 ppm CO

cal 700 ppm CO

2147

Composite Trace
Op Run 3

calibrate 700 ppm


End R3 DRYER NO. 1
2-24-92

2110

2132


PART NO. LD/8011


PRINTED



PART NO. LO/5001

PRINTED IN U.S.A.





poured 1813

1910

pave test for plugged filter
(12.5 filter)

ch points

165

160

160

150

160

170

175

180

75

70

165

1855

1840

1825

STENT - RGR 1825
DRYER No. 2
2-25-92

LINSEIS

Chart stop 1746
1752
Repair FID Pump & Filter

1731


36.1000

Run 2

1746

PART NO. LO/801

PRINTED IN U.S.A.



2-26-92

N

PART NO. LO/801

PRINTED IN U.S.A.

Start 0924 Dry No. 3 Run 1
2-26-92

LINE 15

2-26-92

2-26-92

240

LINE 15

max @ 1204

1159

0 10 20 30 40 50 60 70 80 90
100 90 80 70 60 50 40 30 20 10

230

delay for ch. MS filter

220

ch path

220

230

225

230

225

225

225

225

235

235

1129

1114

Test Run @ 1105

DRYER No. 3

2-26-72

1059

0 10 20 30 40 50 60 70 80 90
100 90 80 70 60 50 40 30 20 10

PART NO. LD/8011

zero

80.2 ppm

1044

2000

830 ppm

PRINTED IN U.S.A.

LINE 15

Test Run @ 1031

DRYER No. 3

2-26-72


1032

1029

205

205

210




1519


2-26-92

1517

INSEIS



Change chart ppm
lead = 1450 ch chart ppm



D11.1 program

83.2 ppm cal program

1421

830 ppm
program
(adjusted
plot)

RAN 3
Com-post

230

230

230

230

230

230

230

230


230

230

Ind R. 3 @ 1421
ORVER No 3
2-26-92

RAN 3 @ 1414

1414



PART NO. LO/800

PRINTED IN U.S.A.

NO. LO/800


2nd c. 1703
DRYER No. 1
2-26-92


LINE 15

stop

chip

Retest of Dryer No. 1
Start Run 1
Dryer No. 1 on 2-26-92
2-26-92





PART NO. LO/8011

PRINTED IN U.S.A.

230
230
225
220
220
220

DRYER No. 1
Start R2
@ 1042
2-27-72

1050

1035

700 ppm

Zero

93.2 ppm peak

150 ppm

adjusted

1020 830

Composite
Trace of
Run 2

INSEIS

End R2
@ 1009
DRYER No. 1
2-26-72

1005

175
175
175
170
170
170
170
175
180
180

0950

0930


0920

Peak

3 at

180
180
180
180

down down to release



PART NO. LO/501
PRINTED IN U.S.A.

2240

2-28-92

end all 2-27-92

700

1432

150

3880

PPH

45

NZ

82.3

31.1

240

Run 2 complete

1816

end RUN 2 - 1814
DRYER No. 4
2-27-92

0	10	20	30	40	50	60	70	80	90	100
100	90	80	70	60	50	40	30	20	10	0

185

185

180

180

180

180

180

180

180

180

180

180

180

175

175

180

180

180

180

180

180

185

180

name 1759

power for played in 5 ft

1746


LINE 15

chip

1731

PART NO. LO/80H

PRINTED IN U.S.A.



205

205

205

205

205

205

205

200

200

200

205

205

205

210

210

215

215

220

220

220

210

end 1250
Run
DRYER No-5
2-28-72

1247

1237

— Caprot —

1217

1202

start Run
DRYER No-5
2-28-72

1177

1132

1117

LINEIS

PART NO. LO/8011

PRINTED IN U.S.A.

140
1155
150

Start LINEIS
Run 2
Days 5
2-28-92

1429
1426

Next
830
ppm

10 20 30 40 50 60 70 80 90 100
90 80 70 60 50 40 30 20 10 0

0 10 20 30 40 50 60 70 80 90 100
80 70 60 50 40 30 20 10 0

700

150
830
50

5-832
311

1302
Composite
Run No. 1

LINEIS


End 1250

12.47

PART NO. LD/801

PRINTED IN U.S.A.

PART NO. LD/801



PART NO. LD/801

PRINTED IN U.S.A.

and all 2-27-92

200

150

50

LINSEIS

830

480

83.2

21.2

Zero

Composite
Run 3 Zero

and Run 3 1713

1714

Days

2-28-92

185

180

175

180

185

185

185

180

180

180

180

180

180

185

185

190

190

190

185

190

190

190

185

185

1659


1644

1624

164

Capote

Strike 164



— 9nd R1 @ 1321
PRESS VENT No. 4
2-29-92

1320 Rem Composite Zero?

1305

— ch pake

1250


1235

LINE 15
Start 1220
Press Vent No. 4
2-29-92

1220

83.2

20
83.0



1506

Run 2 PW No 4
2-29-92

1450

1438

1420

1406

LINE

1350

adj 700

1500

1336

ADJ

Run 1

PART NO. LO/801

PRINTED IN U.S.A.

Start RD 1643
PR No. 4
2-29-92

700

1625

8950

1050

830

1620

End RD 1643
PR No. 4
2-29-92

35

35

35

35

35

30

35

35

1605

1550

back up

1535

from beam 535

ch post

LINE 1

1520

30

35

30

30

35

30

20

1505


PART NO. LO/801

PRINTED IN U.S.A.

LINEIS

END ALL 9-29-92


1805



1750 R-3

end R
794
PR 11.4
2-29-92

1735



1708

1650

LINEIS

Start R 1643

20
20
25
25
20
25
20

25.8

1000

LINE 15
Start RI 0953
Begin Press Unit No. 6
3-1-92

Zero

0945

0 10 20 30 40 50 60 70 80 90 100
100 90 80 70 60 50 40 30 20 10 0

0930

0915

0900

0 10 20 30 40 50 60 70 80 90 100
100 90 80 70 60 50 40 30 20 10 0

0848
3-1-92

0845

PART NO. LO/8011

PRINTED IN U.S.A.

45

45

40 20

35 80

40

40

35

40

35

35

35

40

35

40 parts

390

1130

LINSEIS

Start Run 2 1119
Run 2 No. 5
3-1-72

1115

ADJ.
100

10 20 30 40 50 60 70 80 90 100
31.6 ppm paper
Zero

End Run 1 1054
PVS 3-1-72

Zero

20

25

30

30

35

30

30

30

35

35

20

40 parts

10 20 30 40 50 60 70 80 90 100
20 80 70 60 50 40 30 20 10
20
20




1045

1030

1015

PART NO. LO/8011

PRINTED IN U.S.A.



PART NO. LO/8011

PRINTED IN U.S.A.

50
45
40
30

- d. photo -

11515

45
35
35
35

144.5

1500

0 10 20 30 40 50 60 70 80 90 100
100 90 80 70 60 50 40 30 20 10 0

Start Run
PV No. 3 @ 1444
3-1-92

1445

7007

1500

1440

25
830

50
112

Composite
Run 3 112

LINE 15

Run 3 @ 1422
PVS 3-2-92

35
30
30
25
35
35

11415

0 10 20 30 40 50 60 70 80 90 100
100 90 80 70 60 50 40 30 20 10 0

465

30
35
30
30
35
35
30
30


- d. photo -

1395

1330

PART NO. LO/8011


PRINTED IN U.S.A.



100 90 80 70 60 50 40 30 20 10 0

65-1-55

1830



70
65
65
70
40
60
65
40
60
60
65
60
50

ok part

1815

1800

60.5

0 10 20 30 40 50 60 70 80 90 100
100 90 80 70 60 50 40 30 20 10 0

50
60
65
65
55

1725

Printout No. 2
3-1-72
Start @ 1735

ADJ 700

1730

ADJ 830

LINEIS

31-1

Run 2 complete
Zero

1715

Printout No. 2
Run 2
3-1-72

0 10 20 30 40 50 60 70 80 90 100
100 90 80 70 60 50 40 30 20 10 0

70
70
70
60
65
70
75
70
65

1700

PART M

PRINTED IN U.S.A.

PART NO. LO/801

PRINTED IN U.S.A.

35
40

Start R10 0937
Press Vent No. 3
3-2-92

0935

0930

0 10 20 30 40 50 60 70 80 90 100
100 90 80 70 60 50 40 30 20 10 0

0900

3-2-92

0857



1900

LINE IS


End of 3-1-92

off zero

70%

1845 50
1830

83.2
30.1



70 30
70 70
70

End Run 3 @ 1836
PRESS VENT No. 60
53-1-552

Composite
Run 3

1830 10
1830

PART NO. LO/8011
PRINTED IN U.S.A.

1044

45
50
35
45
30
50

Start Rant 1104
P. Vent No. 3
3-2-92

1105

1115

1105

1050

150

50

830

Compass
1039

83.2

311

45

50

45

60

45

60

50

50

50

45

45

45

45

45

40

40

40

40

45

35

40

Start R1
P. Vent No. 3
3-2-92

1045

1035

1020

1020

1005

1020

1005

1005

0950

Start R1e 0937
P. Vent No. 3

0935


0935

PART NO. LO/8011

PART NO. LO/8011

PRINTED IN U.S.A.

LO/8011



PART NO. LO/5011

PRINTED IN U.S.A.





Chart on @ 1505 — START RUN 1 @ 1514
Phase Volt No. 1 3-2-92



LINEIS






Chart STOP @ 1348




End Run 3 @ 1333
PV 3 3-2-92

Run 3 Complete



Line down 1.11



Q ports

PART NO. LO/8011

PRINTED IN U.S.A.

35

40

35

30

30

25

30

20

30

40

Aug = 38 00^m

1700

1645

1630

1615

1600

1545

1530

1515

RUN 2 ~~ADJ~~ No 1
Start 1634
3-1-72

ADJ

700

150

ADJ 502
1030

Rail Comp


and INSELS
Run 1 @ 1616
P.V. No. 1 3-2-72

cl. part

R1 = 33.6

PART NO. L0/8011

PRINTED IN U.S.A.



60
65
60
55
55
45
40
30
30
35
55
60
60
55
55
55
83.2
60
35
45
50
45
45
35
40
30
40
35
40
35

- ch pat

AVG 6
63.0

1830

1815

1800

stat R3@ 1753
PP No. 1 3-2-42
LINE EIS

small board to press

1745 150 50

830

Comp. Rn 2 →
1730

end 1733
RUN 2
DRYER No. 1
3-2-42-72-50

1715

1700

- ch pat

1.5 = 38 ppm

INSEIS

END ALL 3-2-92

31.1 83-2

1400

830

Composite
Photo

Grid R3 @ 1854
Photo No. 1
3-2-92

1845

1830

- Chap

AVG
3.0

1815

1800

start R3 @ 1753
Photo No. 1 3-2-92

INSEIS

1745 150

50

APPENDIX D: 02-24-92 TEST DATA FOR DRYER NO. 1

Plant Kirby Forest Industries - Silaboo DSB Plant
 Sampling Location No. 1 DSB Dryer
 Test For PM / CPM / VOC / CO
 Test Operators Rumsey / Moore / McKnight

RUN No. 1
 Date 2-27-92
 Time start 0616 end 1717

Meter Box RACS91349
 Sample Box No. 1
 Probe/Pitot 5' inc
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No.

No. Sample Pts. 622
 Minutes/Pt. 5.0

NOMOGRAPH
 $\Delta H @$ 1.85
 Meter Temp. 100
 % H₂O 15
 C-Factor .70
 Stack Temp. 200
 Ref. ΔP 1.6

Gas Analysis int. orsat
 CO₂ 0.9 0.9 0.9
 O₂ 20.5 20.7 20.4
 CO NDIR: 20 ppm
 Time

Condensate:
 tare 200 fin 372
 Silica gel:
 tare 721.0 fin 736.0

Remarks:
1616
0.196
0.196 } $D_n = .196$
0.196

Amb. Temp. °F 63
 Bar. Press. "Hg 29.61
 Static Press. "H₂O -4.6

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	770.039	1.30	1.50	191	86	77	255	60	3	1.0
2	5	773.6	1.45	1.65	190	84	77	250	60	3	1.0
3	10	776.9	1.50	1.75	190	92	79	245	62	3	1.0
4	15	780.5	1.65	1.90	194	102	81	240	62	3	1.0
5	20	784.2	1.55	1.80	195	108	84	250	62	4	1.0
6	25	788.4	1.25	1.45	189	114	87	250	62	4	1.0
7											
8	30	791.747	1.30	1.50	189	114	90	240	62	3	1.0
9	5	795.6	1.40	1.65	190	117	93	205	60	3	1.0
10	10	799.0	1.50	1.75	194	120	95	210	50	3	1.0
11	15	803.1	1.70	2.00	193	123	97	215	50	3	1.0
12	20	806.2	1.60	1.85	190	125	99	220	58	3	1.0
13	25	810.5	1.25	1.45	186	126	100	220	56	3	1.0
14	End 60	814.214									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

Leak check: .000 → .007 = .007 cpe 8" H₂O
 pitot + ve 3.6" H₂O
 pitot - ve 3.5" H₂O

44.175 1.2043 1.6875 190.92 48.50

Plant Kirby Forest Industries
 Sampling Location No. 1 OSB Dryer
 Test For PM/KPM/CO/VOC
 Test Operators Russell / Moore / McKnight

RUN No. 2
 Date 2-24-92
 Time start 1824 and 1929

Meter Box RACS91345
 Sample Box No. 3
 Probe/Pitot 5' inc.
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No. _____
 Amb. Temp. °F 64
 Bar. Press. "Hg 29.60
 Static Press. "H₂O -.46

No. Sample Pts. 6x2
 Minutes/Pt. 5.0
 NOMOGRAPH
 ΔH@ 1.85
 Meter Temp. 100
 % H₂O 18
 C-Factor .86
 Stack Temp. 190
 Ref. ΔP 1.65

Gas Analysis int. out
 CO₂ 1.0 1.0 1.0
 O₂ 20.3 20.3 20.3
 CO NDIR = 30ppm
 Time _____

Condensate:
 tare 200 fin 375
 Silica gel:
 tare 633 fin 646.5

Remarks:

 1st dump 840 # 1500
 2nd _____
 VOC sample not good
 - leaked thru Calib.
 nose

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	814.617	1.25	1.40	190	91	90	270	61	2	1.0
2	5	819.4	1.40	1.65	185	95	91	260	60	2	1.0
3	10	821.6	1.50	1.75	185	103	91	250	52	3	1.0
4	15	825.0	1.60	1.80	187	109	92	250	55	3	1.0
5	20	828.6	1.45	1.65	186	115	95	275	60	3	1.0
6	25	832.6	1.30	1.50	184	119	98	275	62	3	1.0
7											
8	30/0	936.113	1.35	1.60	187	118	100	250	62	3	1.0
9	5	839.9	1.60	1.80	188	120	100	225	62	3	1.0
10	10	844.0	1.50	1.70	189	121	101	235	55	3	1.0
11	15	847.5	1.70	1.90	188	125	102	250	55	3	1.0
12	20	851.8	1.65	1.85	192	126	103	250	55	3	1.0
13	25	855.1	1.25	1.40	185	127	103	240	58	3	1.0
14	and 60	858.317									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

Leak check: .097 → .099 = .002 cpe 6.14
 pitot + ve 4.9
 pitot - ve 6.9

43.700

1.2078

1.667

187.17

10563

Plant Kirby Forest Industries - Silabee, Texas OSB Plant
 Sampling Location No. 1 OSB Dryer
 Test For PM/CPM/CO/VOC
 Test Operators Russell / Moore / McKnight

RUN No. 3
 Date 2-27-92
 Time start 2010 end 2135

Meter Box RAC69145
 Sample Box No. 1
 Probe/Pitot 5' inc
 Pitot Cp .84
 Nozzle Dia. .196
 Filter No.

No. Sample Pts. 6x2
 Minutes/Pt. 5.0

NOMOGRAPH
 $\Delta H @$ 1.85
 Meter Temp. 100
 $\% H_2O$ 18
 C-Factor .86
 Stack Temp. 190
 Ref. ΔP 1.65

Gas Analysis intox
 CO_2 1.0 1.0 0.9
 O_2 20.4 20.4 20.4
 CO NDIR = 20 ppm
 Time

Condensate:
 tare 200 fin 378
 Silica gel:
 tare 617 fin 633

Remarks:
paused @ 11:35 "into
1st half - crimped
VOC sample line

Amb. Temp. °F 60
 Bar. Press. "Hg 29.61
 Static Press. "H₂O -4.6

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg	CO ppm
1	0	858.658	1.25	1.40	189	95	93	220	55	2	1.0
2	5	862.0	1.40	1.60	190	98	94	240	50	2	1.0
3	10	865.7	1.40	1.60	189	106	94	250	50	2	1.0
4	15	869.3	1.60	1.80	185	92	92	225	53	2	1.0
5	20	872.2	1.40	1.60	186	101	91	230	55	2	1.0
6	25	876.1	1.20	1.35	186	111	92	230	56	2	1.0
7											
8	30/0	879.201	1.30	1.50	185	112	93	225	60	2	1.0
9	5	883.1	1.40	1.60	185	114	95	200	56	2	1.0
10	10	886.1	1.50	1.70	185	118	97	225	56	2	1.0
11	15	889.9	1.70	1.90	181	122	99	230	60	2	1.0
12	20	893.8	1.50	1.70	185	124	100	190	60	2	1.0
13	25	897.4	1.35	1.55	180	125	106	195	60	2	1.0
14	and 60	900.847									
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											

leak check: .036 → .039 = .003 cfm @ 10" H₂O
 pitot + ve 4.5
 pitot - ve 3.6

42.189 1.1889 1.6083 185.5 102.42

PARTICULATE CATCH ANALYSIS AND SAMPLE CUSTODY RECORD:

SAMPLES/PROJECT: Kirby - Silsbee DSB / Degr No. 1
DATE TAKEN: 2-24-92 SAMPLING TEAM: Russell / Moore / Mc Knight
SAMPLES RECOVERED BY: JDSR DATE RECOVERED: 2-24-92

No. OF CONTAINERS: 2

DIR1 Probe Wash - Gravimetric	DIR1 Filter - grav	DIR1 BAK - ext grav
DIR2 " " " "	DIR2 " " "	DIR2 BAK - " "
DIR3 " " " "	DIR3 " " "	DIR2 BAK " "
Active BLANK - Gravimetric		

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)

CUSTODY EXCHANGES: (declare purpose, date and time, personnel)
 Samples recovered, stored, transported to lab by David S. Russell
~~Custody exchanges to Andrew C. Russell on 3/22/20 for analysis~~
 Analysis performed by DGR - No custody exchange

Filter treatment: Filters oven dried 2 hours at 105° C, desiccated at least 24 hours, weighed to constant weight

FILTERS:

FILTERERS:				
RUN NO.	1	2	3	
FILTER NO.	409	408	410	
FILTER TARE, gms	.5662	.5673	.5663	
1st weighing	.7906	.7445	.7517	
2nd weighing	.7907	.7446	.7517	
3rd weighing				
FINAL WEIGHT, gms.	.7907	.7446	.7517	
NET GAIN, gms.	.2245	.1773	.1854	

Probe wash treatment: Transferred to a tared beaker, acetone evaporated over low heat,
desiccated at least 24 hours, weighed to constant weight.

PROBE WASH:

PROBE WASH:				
RUN NO.	1	2	3	
CONTAINER ID	DIR1	DIR2	DIR3	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	120	150	155	
TARE WT., gms.	(2) 104.7550	(4) 108.4637	(7) 111.5447	
1st weighing	107.7777	108.4742	111.5598	
2nd weighing	104.7773	108.4739	111.5599	
3rd weighing				
FINAL WEIGHT, gms.	104.7773	108.4739	111.5599	
NET GAIN, gms.	.0223	.0102	.0152	
LESS BLANK, gms.	-.0001	-.0001	-.0001	

PARTICULATE SAMPLE WEIGHT, mg.

RUN NO.	1			
filter + probe	266.7	187.4	200.5	

SILSBEE, TX

KIRBY
SILSBEE

Source category:

Reconstituted wood products

Plant name :

Louisiana-Pacific

Date:

Test date :

Location:

Process :

Ref. No.: 1

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
M25A TTX Reported as Carbom [fill @ M5 all 5 dryers]	Multiclone	filt. PM	1	15.87	6.90	1.15	2.30
		filt. PM	2	13.84	7.05	0.98	1.96
		filt. PM	3	15.55	7.05	1.10	2.21
		AVERAGE				1.08	2.16
		cond. inorg. PM	1	0.19	6.90	0.014	0.028
		cond. inorg. PM	2	0.08	7.05	0.006	0.011
		cond. inorg. PM	3	0.03	7.05	0.002	0.004
		AVERAGE				0.007	0.014
		cond. org. PM	1	0.73	6.90	0.053	0.106
		cond. org. PM	2	0.61	7.05	0.043	0.087
		cond. org. PM	3	0.88	7.05	0.062	0.125
		AVERAGE				0.053	0.106
		PM-10	1	18.02	7.90	1.14	2.28
		PM-10	2	18.99	7.90	1.20	2.40
		PM-10	3	18.39	7.90	1.16	2.33
		AVERAGE				1.17	2.34
		cond. PM	1	1.34	7.90	0.085	0.169
		cond. PM	2	0.60	7.90	0.038	0.076
		cond. PM	3	0.93	7.90	0.059	0.118
		AVERAGE				0.060	0.121
		CO	1	12	6.90	0.88	1.8
		CO	2	19	7.05	1.31	2.62
		CO	3	14	7.05	1.00	2.00
		AVERAGE				1.07	2.13
		CO2	1	2,125	6.90	154	308
		CO2	2	2,087	7.05	148	296
		CO2	3	1,749	7.05	124	248
		AVERAGE				142	284
		formaldehyde	1	0.2600	9.80	0.0133	0.0265
		formaldehyde	2	0.1400	9.80	0.007	0.0143
		formaldehyde	3	0.1000	9.80	0.005	0.0102
		AVERAGE				0.0085	0.0170
		total hydrocarbon	1	42.6	6.90	3.09	6.17
		total hydrocarbon	2	36.8	7.05	2.61	5.22
		total hydrocarbon	3	46.0	7.05	3.26	6.52
		AVERAGE				2.99	5.97
Dryer No. 2	Multiclone	filt. PM	1	18.75	7.50	1.25	2.50
		filt. PM	2	12.14	7.50	0.81	1.62

NEW
PM-10
CONDas
Carbom

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
	Carbon	filt. PM	3	11.61	7.50	0.77	1.55
		AVERAGE				0.94	1.89
		cond. inorg. PM	1	0.21	7.50	0.014	0.028
		cond. inorg. PM	2	0.02	7.50	0.001	0.003
		cond. inorg. PM	3	0.06	7.50	0.004	0.008
		AVERAGE				0.006	0.013
		cond. org. PM	1	0.81	7.50	0.054	0.108
		cond. org. PM	2	1.21	7.50	0.081	0.161
		cond. org. PM	3	1.15	7.50	0.077	0.153
		AVERAGE				0.070	0.141
		PM-10	1	17.87	7.35	1.22	2.43
		PM-10	2	15.38	7.35	1.05	2.09
		PM-10	3	12.50	7.35	0.85	1.70
		AVERAGE				1.04	2.07
		cond. PM	1	0.54	7.35	0.037	0.074
		cond. PM	2	0.32	7.35	0.021	0.043
		cond. PM	3	0.29	7.35	0.020	0.040
		AVERAGE				0.026	0.052
		CO	1	15	7.5	0.98	1.96
		CO	2	23	7.5	1.52	3.04
		CO	3	15	7.5	0.97	1.95
		AVERAGE				1.16	2.32
		CO2	1	1,743	7.5	116	232
		CO2	2	1,688	7.5	113	225
		CO2	3	1,464	7.5	98	195
		AVERAGE				109	218
		formaldehyde	1	0.1700	7.20	0.0118	0.0236
		formaldehyde	2	0.1000	7.20	0.007	0.0139
		formaldehyde	3	0.4000	7.35	0.027	0.0544
		AVERAGE				0.0153	0.0306
		total hydrocarbon	1	44.3	7.50	2.95	5.91
		total hydrocarbon	2	37.4	7.50	2.49	4.99
		total hydrocarbon	3	35.4	7.50	2.36	4.72
		AVERAGE				2.60	5.20
Dryer No. 3	Multiclone	filt. PM	1	12.22	7.10	0.86	1.72
		filt. PM	2	12.12	7.75	0.78	1.56
		filt. PM	3	12.60	7.75	0.81	1.63
		AVERAGE				0.82	1.64

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
		cond. inorg. PM	1	0.30	7.10	0.021	0.042
		cond. inorg. PM	2	0.01	7.75	0.001	0.001
		cond. inorg. PM	3	0.22	7.75	0.014	0.028
		AVERAGE				0.012	0.024
		cond. org. PM	1	0.63	7.10	0.044	0.089
		cond. org. PM	2	1.04	7.75	0.067	0.134
		cond. org. PM	3	0.46	7.75	0.030	0.059
		AVERAGE				0.047	0.094
		PM-10	1	18.60	9.00	1.03	2.07
		PM-10	2	15.94	9.00	0.89	1.77
		PM-10	3	16.16	9.00	0.90	1.80
		AVERAGE				0.94	1.88
		cond. PM	1	0.58	9.00	0.032	0.064
		cond. PM	2	0.42	9.00	0.023	0.046
		cond. PM	3	0.42	9.00	0.024	0.047
		AVERAGE				0.026	0.053
		CO	1	2	7.10	0.14	0.3
		CO	2	5	7.75	0.34	0.69
		CO	3	4	7.75	0.26	0.52
		AVERAGE				0.25	0.50
		CO2	1	1,563	7.10	110	220
		CO2	2	1,672	7.75	108	216
		CO2	3	1,551	7.75	100	200
		AVERAGE				106	212
		formaldehyde	1	0.5300	7.10	0.0373	0.0746
		formaldehyde	2	0.4000	7.10	0.028	0.0563
		formaldehyde	3	0.2500	7.75	0.016	0.0323
		AVERAGE				0.0272	0.0544
		total hydrocarbon	1	41.2	7.10	2.90	5.80
		total hydrocarbon	2	47.6	7.75	3.07	6.14
		total hydrocarbon	3	47.3	7.75	3.05	6.10
		AVERAGE				3.01	6.02
Dryer No. 4	Multiclone	filt. PM	1	12.89	9.05	0.71	1.42
		filt. PM	2	13.45	9.05	0.74	1.49
		filt. PM	3	12.98	7.60	0.85	1.71
		AVERAGE				0.77	1.54
		cond. inorg. PM	1	0.03	9.05	0.002	0.003
		cond. inorg. PM	2	0.22	9.05	0.012	0.024

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
		cond. inorg. PM	3	0.09	7.60	0.006	0.012
		AVERAGE				0.007	0.013
		cond. org. PM	1	0.82	9.05	0.045	0.091
		cond. org. PM	2	1.31	9.05	0.072	0.145
		cond. org. PM	3	0.86	7.60	0.057	0.113
		AVERAGE				0.058	0.116
		PM-10	1	18.20	7.90	1.15	2.30
		PM-10	2	19.18	7.90	1.21	2.43
		PM-10	3	19.97	7.90	1.26	2.53
		AVERAGE				1.21	2.42
		cond. PM	1	0.74	7.90	0.047	0.094
		cond. PM	2	0.81	7.90	0.051	0.103
		cond. PM	3	0.90	7.90	0.057	0.114
		AVERAGE				0.052	0.104
		CO	1	24	9.05	1.30	2.60
		CO	2	5	9.05	0.30	0.60
		CO	3	5	7.6	0.32	0.63
		AVERAGE				0.64	1.28
		CO2	1	2,026	9.05	112	224
		CO2	2	2,211	9.05	122	244
		CO2	3	2,160	7.6	142	284
		AVERAGE				125	251
		formaldehyde	1	0.3700	8.20	0.0226	0.0451
		formaldehyde	2	0.5600	8.20	0.034	0.0683
		formaldehyde	3	0.5800	8.20	0.035	0.0707
		AVERAGE				0.0307	0.0614
		total hydrocarbon	1	38.5	9.05	2.13	4.25
		total hydrocarbon	2	36.8	9.05	2.03	4.07
		total hydrocarbon	3	38.5	7.60	2.53	5.07
		AVERAGE				2.23	4.46
Dryer No. 5	Multiclone	filt. PM	1	17.11	7.80	1.10	2.19
		filt. PM	2	13.50	7.80	0.87	1.73
		filt. PM	3	14.45	7.80	0.93	1.85
		AVERAGE				0.96	1.93
		cond. inorg. PM	1	0.22	7.80	0.014	0.028
		cond. inorg. PM	2	0.09	7.80	0.006	0.012
		cond. inorg. PM	3	0.06	7.80	0.004	0.008
		AVERAGE				0.008	0.016

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
		cond. org. PM	1	0.76	7.80	0.049	0.097
		cond. org. PM	2	0.66	7.80	0.042	0.085
		cond. org. PM	3	0.87	7.80	0.056	0.112
		AVERAGE				0.049	0.098
		PM-10	1	18.06	7.50	1.20	2.41
		PM-10	2	17.02	7.50	1.13	2.27
		PM-10	3	19.47	7.50	1.30	2.60
		AVERAGE				1.21	2.42
		cond. PM	1	0.62	7.50	0.041	0.082
		cond. PM	2	0.50	7.50	0.033	0.067
		cond. PM	3	0.38	7.50	0.025	0.051
		AVERAGE				0.033	0.067
		CO	1	5	7.8	0.31	0.61
		CO	2	4	7.8	0.26	0.53
		CO	3	3	7.8	0.22	0.44
		AVERAGE				0.26	0.53
		CO2	1	2,202	7.8	141	282
		CO2	2	2,148	7.8	138	275
		CO2	3	2,166	7.8	139	278
		AVERAGE				139	278
		formaldehyde	1	0.3400	7.65	0.0222	0.0444
		formaldehyde	2	0.3600	7.65	0.024	0.0471
		formaldehyde	3	0.3400	7.65	0.022	0.0444
		AVERAGE				0.0227	0.0453
		total hydrocarbon	1	43.7	7.8	2.80	5.60
		total hydrocarbon	2	35.3	7.8	2.26	4.53
		total hydrocarbon	3	39.1	7.8	2.51	5.01
		AVERAGE				2.52	5.05

as
Carbon