

Note: This is a reference cited in AP 42, *Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

Interpoll Laboratories, Inc.
4500 Ball Road N.E.
Circle Pines, Minnesota 55014-1819

TEL: (612) 786-6020
FAX: (612) 786-7854

RESULTS OF THE MARCH 24 - 28, 1992
EPA-AIR EMISSION COMPLIANCE TESTS
AT THE LOUISIANA-PACIFIC PLANT
IN CORRIGAN, TEXAS

Submitted to:

LOUISIANA-PACIFIC CORPORATION
P.O. Box 3107
Conroe, Texas 77305

Attention:

Dr. Jim Boswell
Director of Environmental Control

Approved by:



Daniel J. Despen
Manager
Field Testing Support Group

Report Number 2-3532
May 18, 1992
SP/slp

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

OSB

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
		cond. inorg. PM	1	0.36	7.80	0.23	0.047
		cond. inorg. PM	2	0.47	9.60	0.24	0.049
		cond. inorg. PM	3	0.83	9.10	0.46	0.091
		AVERAGE				0.310	0.062
		cond. org. PM	1	0.63	7.80	0.41	0.081
		cond. org. PM	2	0.65	9.60	0.34	0.067
		cond. org. PM	3	0.81	9.10	0.45	0.090
		AVERAGE				0.397	0.079
		formaldehyde	1	0.1077	9.60	0.06	0.0112
		formaldehyde	2	0.1268	9.60	0.07	0.0132
		formaldehyde	3	0.1160	10.50	0.06	0.0110
		AVERAGE				0.0591	0.0118
		total hydrocarbon	1	0.1	8.70	0.06	0.01
		total hydrocarbon	2	0.1	10.00	0.06	0.01
		total hydrocarbon	3	0.1	7.00	0.08	0.02
		AVERAGE				0.07	0.01
Press vent Total	none	filt. PM	1	7.79	9.30	4.19	0.84
		filt. PM	2	9.11	8.40	5.42	1.08
		filt. PM	3	8.73	10.43	4.18	0.84
		AVERAGE				4.60	0.92
		cond. inorg. PM	1	0.65	9.30	0.35	0.070
		cond. inorg. PM	2	1.27	8.40	0.76	0.151
		cond. inorg. PM	3	1.23	10.43	0.59	0.118
		AVERAGE				0.566	0.113
		cond. org. PM	1	6.94	9.30	3.73	0.747
		cond. org. PM	2	6.85	8.40	4.08	0.816
		cond. org. PM	3	5.95	10.43	2.85	0.571
		AVERAGE				3.555	0.711
		formaldehyde	1	0.92	9.90	0.46	0.0929
		formaldehyde	2	0.78	8.40	0.46	0.0926
		formaldehyde	3	1.18	10.90	0.54	0.1082
		AVERAGE				0.4896	0.0979
		total hydrocarbon	1	30.61	9.60	15.94	3.19
		total hydrocarbon	2	28.49	8.53	16.69	3.34
		total hydrocarbon	3	20.79	9.73	10.68	2.14
		AVERAGE				14.44	2.89
Exh. vent 8	none	filt. PM	1	3.71	9.60	1.93	0.39
		filt. PM	2	4.42	9.60	2.30	0.46

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

OSB

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
		filt. PM	3	4.41	10.50	2.10	0.42
		AVERAGE				2.11	0.42
		cond. inorg. PM	1	0.48	9.60	0.25	0.050
		cond. inorg. PM	2	0.21	9.60	0.11	0.022
		cond. inorg. PM	3	0.33	10.50	0.16	0.031
		AVERAGE				0.171	0.034
		cond. org. PM	1	1.43	9.60	0.74	0.149
		cond. org. PM	2	1.30	9.60	0.68	0.136
		cond. org. PM	3	0.85	10.50	0.41	0.081
		AVERAGE				0.609	0.122
		formaldehyde	1	0.1085	7.80	0.07	0.0139
		formaldehyde	2	0.1012	9.60	0.05	0.0105
		formaldehyde	3	0.1383	9.10	0.08	0.0152
		AVERAGE				0.0661	0.0132

CORRIJAN

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.: 4

Process :

OSB

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
Dryer No. 1	Unknown	filt. PM	1	15.23	7.65	1.00	1.99
		filt. PM	2	16.84	7.20	1.17	2.34
		filt. PM	3	13.09	7.20	0.91	1.82
		AVERAGE				1.02	2.05
		cond. inorg. PM		0.90	7.65	0.059	0.117
		cond. inorg. PM	2	0.85	7.20	0.059	0.117
		cond. inorg. PM	3	0.77	7.20	0.053	0.107
		AVERAGE				0.057	0.114
		cond. org. PM	1	4.92	7.65	0.322	0.644
		cond. org. PM	2	4.12	7.20	0.286	0.572
		cond. org. PM	3	4.06	7.20	0.282	0.564
		AVERAGE				0.297	0.593
		PM-10	1	18.90	6.75	1.40	2.80
		PM-10	2	16.69	6.75	1.24	2.47
		PM-10	3	23.21	7.50	1.55	3.09
		AVERAGE				1.39	2.79
		cond. inorg. PM	1	0.76	6.75	0.056	0.113
		cond. inorg. PM	2	0.47	6.75	0.035	0.070
		cond. inorg. PM	3	1.54	7.50	0.103	0.206
		AVERAGE				0.065	0.129
		cond. org. PM	1	0.99	6.75	0.073	0.146
		cond. org. PM	2	1.12	6.75	0.083	0.166
		cond. org. PM	3	2.08	7.50	0.139	0.277
		AVERAGE				0.098	0.197
		Total cond. PM	1	1.75	6.75	0.129	0.259
		Total cond. PM	2	1.60	6.75	0.118	0.237
		Total cond. PM	3	3.62	7.50	0.242	0.483
		AVERAGE				0.163	0.326
		CO	1	51	6.75	3.78	7.6
		CO	2	33	7.50	2.20	4.4
		CO	3	25	6.75	1.85	3.70
		CO	4	35	6.75	2.59	5.19
		CO	5	30	6.75	2.22	4.44
		CO	6	24	6.75	1.78	3.56
		CO	7	17	7.65	1.11	2.22
		CO	8	16	7.20	1.11	2.22
		CO	9	14	7.20	0.97	1.94
		AVERAGE				1.96	3.91

THC
REPORTED AS
CARBONNEW
PM-10
CONDM201A/202
@ stock temp
(7.50)

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

OSB

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
AS Calson	53.1 13/hr	CO2	1	4,033	6.75	299	597
		CO2	2	3,607	7.50	240	481
		CO2	3	3,710	6.75	275	550
		CO2	4	5,688	6.75	421	843
		CO2	5	5,485	6.75	406	813
		CO2	6	6,085	6.75	451	902
		CO2	7	4,343	7.65	284	568
		CO2	8	4,908	7.20	341	682
		CO2	9	5,268	7.20	366	732
		AVERAGE				343	685
		formaldehyde	1	0.6314	6.75	0.0468	0.0935
		formaldehyde	2	0.2187	6.75	0.016	0.0324
		formaldehyde	3	0.0724	6.75	0.005	0.0107
		AVERAGE				0.0228	0.0456
		total hydrocarbon	1	49.4	6.75	3.66	7.32
		total hydrocarbon	2	47.6	6.75	3.53	7.05
		total hydrocarbon	3	62.2	6.75	4.61	9.21
		AVERAGE				3.93	7.86
Dryer No. 2A	Multiclone	filt. PM	1	9.83	6.45	0.76	1.52
		filt. PM	2	6.35	7.50	0.42	0.85
		AVERAGE				0.59	1.19
		cond. inorg. PM	1	1.97	6.45	0.153	0.305
		cond. inorg. PM	2	1.95	7.50	0.130	0.260
		AVERAGE				0.141	0.283
		cond. org. PM	1	6.24	6.45	0.484	0.967
		cond. org. PM	2	3.27	7.50	0.218	0.436
		AVERAGE				0.351	0.702
		PM-10	1	7.80	6.30	0.62	1.24
		PM-10	2	11.15	6.45	0.86	1.73
		PM-10	3	7.52	6.60	0.57	1.14
		AVERAGE				0.68	1.37
		cond. inorg. PM	1	0.86	6.30	0.068	0.136
		cond. inorg. PM	2	0.88	6.45	0.068	0.137
		cond. inorg. PM	3	0.58	6.60	0.044	0.089
		AVERAGE				0.060	0.121
		cond. org. PM	1	1.18	6.30	0.093	0.187
		cond. org. PM	2	1.41	6.45	0.110	0.219
		cond. org. PM	3	1.02	6.60	0.077	0.155

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

OSB

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor			
						kg/Mg	lb/ton		
						AVERAGE		0.093	0.187
		CO	1	21	6.30	1.68	3.4		
		CO	2	15	6.45	1.15	2.3		
		CO	3	15	6.60	1.15	2.30		
		CO	4	12	6.45	0.90	1.80		
		CO	5	14	7.50	0.95	1.89		
		AVERAGE		1.17	2.33				
		CO2	1	3,477	6.30	276	552		
		CO2	2	3,473	6.45	269	538		
		CO2	3	3,348	6.60	254	507		
		CO2	4	3,083	6.45	239	478		
		CO2	5	3,178	7.50	212	424		
		AVERAGE		250	500				
		total hydrocarbon	1	23.4	6.30	1.86	3.71		
		total hydrocarbon	2	26.9	6.60	2.04	4.08		
		total hydrocarbon	3	21.5	6.75	1.59	3.19		
		AVERAGE		1.83	3.66				
		Dryer No. 2B	Multiclone	filt. PM	1	7.63	6.30	0.61	1.21
				filt. PM	2	6.35	7.50	0.42	0.85
				AVERAGE		0.51	1.03		
				cond. inorg. PM	1	1.11	6.30	0.088	0.176
cond. inorg. PM	2			1.00	7.50	0.066	0.133		
AVERAGE				0.077	0.154				
cond. org. PM	1			2.31	6.30	0.184	0.367		
cond. org. PM	2			2.11	7.50	0.140	0.281		
AVERAGE				0.162	0.324				
CO	1			20	6.30	1.60	3.2		
CO	2			17	6.60	1.31	2.6		
CO	3			14	6.75	1.00	2.01		
CO	4			12	6.30	0.95	1.90		
CO	5			11	7.50	0.70	1.41		
AVERAGE				1.11	2.23				
CO2	1			3,218	6.30	255	511		
CO2	2			3,347	6.60	254	507		
CO2	3			3,342	6.75	248	495		
CO2	4			3,454	6.30	274	548		
CO2	5			3,443	7.50	230	459		
AVERAGE		252	504						

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

OSB

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
Dryer No. 2 total	Multiclone	formaldehyde	1	0.0783	6.30	0.0062	0.0124
		formaldehyde	2	0.2425	6.60	0.018	0.0367
		formaldehyde	3	0.1460	6.75	0.011	0.0216
		AVERAGE				0.0118	0.0236
		filt. PM	1	17.47	6.38	1.37	2.74
		filt. PM	2	12.70	7.50	0.85	1.69
		AVERAGE				1.11	2.22
		cond. inorg. PM	1	3.08	6.38	0.241	0.483
		cond. inorg. PM	2	2.94	7.50	0.196	0.393
		AVERAGE				0.219	0.438
		cond. org. PM	1	8.56	6.38	0.671	1.342
		cond. org. PM	2	5.38	7.50	0.359	0.717
		AVERAGE				0.515	1.030
		PM-10	1	15.61	6.30	1.239	2.477
		PM-10	2	22.31	6.45	1.729	3.459
		PM-10	3	15.05	6.60	1.140	2.280
		AVERAGE				1.369	2.739
		cond. inorg PM	1	1.72	6.30	0.136	0.273
		cond. inorg PM	2	1.76	6.45	0.137	0.273
		cond. inorg PM	3	1.17	6.60	0.089	0.177
		AVERAGE				0.121	0.241
		cond. org. PM	1	2.35	6.30	0.187	0.374
		cond. org. PM	2	2.83	6.45	0.219	0.439
		cond. org. PM	3	2.04	6.60	0.155	0.310
		AVERAGE				0.187	0.374
		Total cond. PM	1	4.07	6.30	0.323	0.646
		Total cond. PM	2	4.59	6.45	0.356	0.712
		Total cond. PM	3	3.21	6.60	0.243	0.487
		AVERAGE				0.308	0.615
		CO	1	41.29	6.30	3.28	6.6
		CO	2	32.09	6.53	2.46	4.9
		CO	3	28.74	6.68	2.15	4.31
		CO	4	23.61	6.38	1.85	3.70
		CO	5	24.78	7.50	1.65	3.30
		AVERAGE				2.28	4.56
		CO2	1	6,695	6.30	531	1,063
		CO2	2	6,820	6.53	523	1,045
		CO2	3	6,690	6.68	501	1,002

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

OSB

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
	as carbon	CO2	4	6,537	6.38	513	1,025
		CO2	5	6,621	7.50	441	883
		AVERAGE				502	1,004
		formaldehyde	1	0.1565	6.30	0.0124	0.0248
		formaldehyde	2	0.4850	6.60	0.037	0.0735
		formaldehyde	3	0.2919	6.75	0.022	0.0432
		AVERAGE				0.0236	0.0472
		THC	1	46.8000	6.30	3.7143	7.4286
		THC	2	53.8000	6.60	4.076	8.1515
		THC	3	43.0000	6.75	3.185	6.3704
		AVERAGE				3.6584	7.3168
Dryer No. 3	Multiclone	filt. PM	1	7.92	6.00	0.66	1.32
		filt. PM	2	8.18	6.00	0.68	1.36
		filt. PM	3	7.16	5.70	0.63	1.26
		AVERAGE				0.66	1.31
		cond. inorg. PM	1	0.71	6.00	0.059	0.118
		cond. inorg. PM	2	0.52	6.00	0.043	0.086
		cond. inorg. PM	3	1.20	5.70	0.105	0.210
		AVERAGE				0.069	0.138
		cond. org. PM	1	1.82	6.00	0.151	0.303
		cond. org. PM	2	1.81	6.00	0.151	0.302
		cond. org. PM	3	3.42	5.70	0.300	0.600
		AVERAGE				0.201	0.401
		PM-10	1	9.25	4.35	1.06	2.13
		PM-10	2	14.56	5.55	1.31	2.62
		PM-10	3	13.07	5.85	1.12	2.23
		AVERAGE				1.16	2.33
		cond. inorg. PM	1	0.72	4.35	0.082	0.164
		cond. inorg. PM	2	0.32	5.55	0.029	0.058
		cond. inorg. PM	3	1.09	5.85	0.093	0.187
		AVERAGE				0.068	0.137
		cond. org. PM	1	0.53	4.35	0.061	0.121
		cond. org. PM	2	0.95	5.55	0.085	0.170
		cond. org. PM	3	0.51	5.85	0.043	0.086
		AVERAGE				0.063	0.126
		Total cond. PM	1	1.24	4.35	0.143	0.286
		Total cond. PM	2	1.27	5.55	0.114	0.229
		Total cond. PM	3	1.60	5.85	0.137	0.273

Date:

Location:

Ref. No.:

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor			
						kg/Mg	lb/ton		
as Carbon		AVERAGE				0.131	0.263		
		CO	1	44	4.35	5.05	10.1		
		CO	2	29	5.55	2.58	5.2		
		CO	3	31	5.85	2.67	5.34		
		CO	4	43	4.35	4.90	9.80		
		CO	5	29	5.55	2.60	5.21		
		CO	6	34	6.15	2.73	5.45		
		CO	7	42	6.00	3.47	6.94		
		CO	8	38	6.00	3.21	6.42		
		CO	9	45	5.70	3.91	7.81		
		AVERAGE				3.46	6.92		
		CO2	1	4,311	4.35	495	991		
		CO2	2	3,775	5.55	340	680		
		CO2	3	3,846	5.85	329	657		
		CO2	4	4,328	4.35	498	995		
		CO2	5	3,632	5.55	327	654		
		CO2	6	3,447	6.15	280	560		
		CO2	7	3,278	6.00	273	546		
		CO2	8	4,107	6.00	342	685		
		CO2	9	3,222	5.70	283	565		
		AVERAGE				352	704		
		formaldehyde	1	0.3154	4.35	0.0362	0.0725		
		formaldehyde	2	0.1446	5.55	0.013	0.0261		
		formaldehyde	3	0.3370	6.15	0.027	0.0548		
		AVERAGE				0.0256	0.0511		
		total hydrocarbon	1	18.4	4.35	2.11	4.23		
		total hydrocarbon	2	26.8	5.55	2.41	4.83		
		total hydrocarbon	3	48.4	6.15	3.93	7.87		
		AVERAGE				2.82	5.64		
		lb/hr				MSF/hr	kg/MSM	lb/MSF	
		Press vent 4	none	filt. PM	1	2.42	9.60	1.26	0.25
				filt. PM	2	3.31	9.60	1.72	0.34
				filt. PM	3	3.56	10.50	1.70	0.34
AVERAGE				1.56	0.31				
cond. inorg. PM	1			0.23	9.60	0.12	0.024		
cond. inorg. PM	2			0.11	9.60	0.06	0.012		

Source category:

Reconstituted wood products

Date:

Plant name :

Louisiana-Pacific

Location:

Test date :

Ref. No.:

Process :

OSB

Basis for process rate :

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor	
						kg/Mg	lb/ton
		cond. inorg. PM	3	0.17	10.50	0.08	0.016
		AVERAGE				0.087	0.017
		cond. org. PM	1	3.13	9.60	1.63	0.326
		cond. org. PM	2	3.70	9.60	1.93	0.386
		cond. org. PM	3	2.23	10.50	1.06	0.212
		AVERAGE				1.540	0.308
		formaldehyde	1	0.3430	9.60	0.18	0.0357
		formaldehyde	2	0.3735	9.60	0.19	0.0389
		formaldehyde	3	0.5224	10.50	0.25	0.0498
		AVERAGE				0.2073	0.0415
		total hydrocarbon	1	14.7	9.60	7.66	1.53
		total hydrocarbon	2	19.9	9.60	10.36	2.07
		total hydrocarbon	3	9.1	10.50	4.32	0.86
		AVERAGE				7.45	1.49
Press vent 3	none	filt. PM	1	3.77	10.50	1.79	0.36
		filt. PM	2	3.84	6.00	3.20	0.64
		filt. PM	3	3.39	11.70	1.45	0.29
		AVERAGE				2.15	0.43
		cond. inorg. PM	1	0.06	10.50	0.03	0.005
		cond. inorg. PM	2	0.69	6.00	0.57	0.115
		cond. inorg. PM	3	0.23	11.70	0.10	0.020
		AVERAGE				0.233	0.047
		cond. org. PM	1	3.18	10.50	1.51	0.302
		cond. org. PM	2	2.50	6.00	2.08	0.417
		cond. org. PM	3	2.91	11.70	1.24	0.249
		AVERAGE				1.613	0.323
		formaldehyde	1	0.4692	10.50	0.22	0.0447
		formaldehyde	2	0.2778	6.00	0.23	0.0463
		formaldehyde	3	0.5409	11.70	0.23	0.0462
		AVERAGE				0.2287	0.0457
		total hydrocarbon	1	15.8	10.50	7.52	1.50
		total hydrocarbon	2	8.5	6.00	7.05	1.41
		total hydrocarbon	3	11.6	11.70	4.96	0.99
		AVERAGE				6.51	1.30
Press vent 2	none	filt. PM	1	1.60	7.80	1.03	0.21
		filt. PM	2	1.97	9.60	1.03	0.21
		filt. PM	3	1.78	9.10	0.98	0.20
		AVERAGE				1.01	0.20

TABLE OF CONTENTS

ABBREVIATIONS	iii
1 INTRODUCTION	1
2 SUMMARY AND DISCUSSION	5
3 RESULTS	26
3.1 Results of Orsat and Moisture Determinations	27
3.2 Results of Particulate Determinations	46
3.3 Results of PM-10 Determinations	55
3.4 Results of Carbon Monoxide Determinations	59
3.5 Results of Formaldehyde Determinations	70

APPENDICES:

- A - Results of Volumetric Flow Rate Determinations
- B - Location of Test Ports
- C - Field Data Sheets
- D - Interpoll Laboratories Analytical Results
- E - Total Hydrocarbons Stripchart
- F - THC Analyzer Specifications
- G - Measurement Systems Performance Specifications
- H - Calibration Gas Certification Sheets
- I - Process Rate Information
- J - Procedures
- K - Calculation Equations
- L - Sampling Train Calibration Data

ABBREVIATIONS

ACFM	actual cubic feet per minute
cc (ml)	cubic centimeter (milliliter)
DSCFM	standard cubic foot of dry gas per minute
DSML	dry standard milliliter
DEG-F (°F)	degrees Fahrenheit
DIA.	diameter
FP	finished product for plant
FT/SEC	feet per second
g	gram
GPM	gallons per minute
GR/ACF	grains per actual cubic foot
GR/DSCF	grains per dry standard cubic foot
g/dscm	grams per dry standard cubic meter
HP	horsepower
HRS	hours
IN.	inches
IN.HG.	inches of mercury
IN.WC.	inches of water
LB	pound
LB/DSCF	pounds per dry standard cubic foot
LB/HR	pounds per hour
LB/10 ⁶ BTU	pounds per million British Thermal Units heat input
LB/MMBTU	pounds per million British Thermal Units heat input
LTPD	long tons per day
MW	megawatt
mg/Nm ³	milligrams per dry standard cubic meter
ug/Nm ³	micrograms per dry standard cubic meter
microns (um)	micrometer
MIN.	minutes
ng	nanograms
ohm-cm	ohm-centimeter
PM	particulate matter
PPH	pounds per hour
PPM	parts per million
ppmC	parts per million carbon
ppm,d	parts per million, dry
ppm,w	parts per million, wet
opt	parts per trillion
PSI	pounds per square inch
SQ.FT.	square feet
TPD	tons per day
ug	micrograms
v/v	percent by volume
w/w	percent by weight
<	≤ (when following a number)

Standard conditions are defined as 68 °F (20 °C) and 29.92 IN. of mercury pressure.

1 INTRODUCTION

During the period March 24 - 28, 1992 Interpoll Laboratories personnel conducted EPA-mandated air emission compliance tests at the Louisiana-Pacific Corporation (LP) Plant located in Corrigan, Texas. On-site testing was performed by Mark Kaehler, Duke Brennan, Curt Mosser, and Bob Aschenbach. Coordination between testing activities and plant operation was provided by Dr. Jim Boswell and Marty of LP. The test was witnessed by Jeffrey Burdette of IEA, who was representing the Environmental Protection Agency. Al Bander of the Environmental Protection Agency (Denver) witnessed some of the tests.

The Louisiana-Pacific Corporation owns and operates a waferboard plant in Corrigan Texas. This plant operates an oil heater, three dryers and a fixed press. The exhaust gases from the thermal oil heater are vented through the No. 2 Dryer, this dryer has a split exhaust system (labeled 2A and 2B in this report). The No. 1 Dryer and the No. 3 Dryer each have their own stacks. The press gases are vented by three press vents and an exhaust fan vent. 05B

Particulate evaluations were performed in accordance with EPA Methods 2-5, CFR Title 40, Part 60, Appendix A (revised July 1, 1991). A preliminary determination of the gas linear velocity profile was made before the first particulate determination at each test site to allow selection of the appropriate nozzle diameter for isokinetic sample withdrawal. An Interpoll Labs sampling train which meets or exceeds specifications in the above-cited reference was used to isokinetically extract particulate samples by means of a heated glass-lined probe. Wet catch samples were collected in the back half of the Method 5 sampling train in accordance with EPA Method 202 to determine total condensible organic and inorganic compounds. Yaw angle determinations were performed in accordance with EPA Method 1, Section 2.4 using an S-Type pitot tube system which allows rotation of the pitot tube on its long axis for nulling and measurement of the yaw angle.

PM-10 determinations were performed in accordance with EPA Method 201A (Ibid, Part 51, Appendix M). An Interpoll Labs sampling train which meets or exceeds specifications in the above-cited reference was used to extract PM-10 samples by means of an Anderson PM-10 cyclone and a stainless steel probe. The cyclone used in this work meets or exceeds the specifications of Method 201A. Velocity pressure measurements were made during each run to determine the proper dwell times at each traverse point.

Formaldehyde samples were collected in accordance with EPA Draft Method 0011 (SW 846 3rd Ed.). The samples were collected isokinetically using a Method 5 sampling train with an aqueous acidic 2,4-dinitrophenylhydrazine absorbing solution and analyzed by high performance liquid chromatography.

Total gaseous hydrocarbon concentrations were determined instrumentally using a Ratfisch Model RS 55 heated flame ionization detector (HFID) calibrated against propane in air standards. The THC concentration was continuously monitored by extracting a slipstream of exhaust gas by means of a heated probe and filter holder. A heat-traced teflon line was used to transport the sample gas from the filter holder outlet to the analyzer inlet.

Carbon monoxide determinations were performed in accordance with EPA Method 10 (Ibid). Concentrations were determined using a non-dispersive infrared (NDIR) continuous emission monitor.

Testing on the No. 1 Dryer was conducted from two test ports oriented at 90 degrees on the stack. The test ports are located greater than 8 stack diameters downstream of the nearest flow disturbance and greater than 2 stack diameters upstream of the stack exit. A 12-point traverse was used to isokinetically collect the particulate and formaldehyde samples. Each traverse point was sampled five minutes to give a total sampling time of sixty minutes per run. The PM-10 run times varied

from 85.2 to 93.5 minutes. A yaw angle determination was performed prior to sampling. The average of the absolute value was found to be 1° which meets the EPA specifications of less than 20° .

Testing on the No. 2A and 2B Dryer was conducted from two test ports oriented at 90 degrees on the stack. The test ports are located 4.9 diameters downstream of the nearest flow disturbance and greater than five diameters upstream of the stack exit. A 24-point traverse was used at each test site to isokinetically collect the particulate and formaldehyde samples. Each traverse point was sampled 2.5 minutes to give a total sampling time of sixty minutes per run. The PM-10 run times varied from 84.4 to 93.6 minutes.

Testing on the No. 3 Dryer was conducted from two test ports oriented at 90 degrees on the stack. The test ports are located 6.1 diameters downstream of the nearest flow disturbance and greater than five diameters upstream of the stack exit. A 12-point traverse was used to isokinetically collect the particulate and formaldehyde samples. Each traverse point was sampled 5 minutes to give a total sampling time of sixty minutes per run. The PM-10 run times varied from 83.5 to 86.0 minutes. A yaw angle determination was performed prior to sampling. The average absolute value was found to be $< 1^\circ$ which meets the EPA specifications of less than 20° .

Testing on the No. 2, 3, and 4 Press Vents and the No. 8 Exhaust Fan was conducted from two test ports oriented at 90 degrees on the stack. The test ports are located < 0.5 diameters downstream of the nearest flow disturbance (approved by the EPA) and 0.5 diameters upstream of the stack exit. A 24-point traverse was used at each test site to isokinetically collect the particulate and formaldehyde samples. Each traverse point was sampled 2.5 minutes to give a total sampling time of sixty minutes per run.

The important results of the test are summarized in Section 2. Detailed results are presented in Section 3. Field data and all other supporting information are presented in the appendices.

2 SUMMARY AND DISCUSSION

The important results of the particulate and PM-10 emission compliance tests are summarized in Tables 1 - 11. An overview of the results is presented below:

Source	Emission Rates	
	Particulate (LB/HR)	PM-10 (LB/HR)
No. 1 Dryer	20.3	21.9
No. 2 Dryer	25.1 ¹	22.1 ²
No. 3 Dryer	10.9	13.7
No. 2 Press Vent	3.03	NA
No. 3 Press Vent	6.85	NA
No. 4 Press Vent	6.29	NA
No. 8 Exhaust Fan	5.71	NA

1 - Result is the average of two runs each on the 2A and the 2B Stacks.

2 - Result extrapolated from the 2A PM-10 measurements and 2B vol. flows.

Carbon monoxide determinations were performed on the Nos 1-3 Dryers. the results of those determinations are summarized in Tables 12 - 15, and an overview provided below:

Source	Concentration	Emission rate
	(ppm,w)	(LB/HR)
No. 1 Dryer	145	27
No. 2 Dryer	174	30
No. 3 Dryer	242	37

Tables 16 - 17 summarize the results of the formaldehyde determinations. The average concentration and emission rates are summarized below:

<u>Source</u>	<u>Concentration (ppm.w)</u>	<u>Emission rate (LB/HR)</u>
No. 1 Dryer	1.5	0.31
No. 2 Dryer	1.7	0.32
No. 3 Dryer	1.6	0.27
No. 2 Press Vent	0.47	0.12
No. 3 Press Vent	1.6	0.43
No. 4 Press Vent	1.6	0.41
No. 8 Exhaust Fan	0.54	0.12

The results of the THC tests are summarized in Tables 18 - 19. The following table provides an overview:

<u>Source</u>	<u>Concentration (ppmC,w)</u>	<u>Emission rate (LB/HR)</u>
No. 1 Dryer	656	53.1
No. 2 Dryer	625	47.8
No. 3 Dryer	466	31.2
No. 2 Press Vent	26	2.5
No. 3 Press Vent	124	12.0
No. 4 Press Vent	159	14.5

No difficulties were encountered in the field by Interpoll Labs or in the laboratory evaluations of the samples which were conducted by Interpoll Labs. On the basis of this fact and a complete review of the entire data and results, it is our opinion that the results reported herein are accurate and closely reflect the actual values which existed at the time the test was performed.

Table 1. Summary of the Results of the March 24, 1992 Particulate Emission Test on the No. 1 Dryer at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2	Run 3
Date of test	03-24-92	03-24-92	03-24-92
Time runs were done (HRS)	1610/1712	1735/1838	1900/2002
Volumetric flow actual (ACFM) standard (DSCFM)	51613 35149	52489 35751	52112 34885
Gas temperature (DEG-F)	190	190	190
Moisture content (%V/V)	15.72	15.75	17.19
Gas composition (%V/V.dry) carbon dioxide oxygen nitrogen	1.80 18.90 79.30	2.00 18.70 79.30	2.20 18.70 79.10
Isokinetic variation (%)	102.1	100.9	100.8
Particulate concentration actual (GR/ACF) standard (GR/DSCF)	.0476 .0699	.0485 .0712	.0401 .0599
Part. emission rate (LB/HR)	21.05	21.81	17.92

Note: Dry + Organic/Inorganic Wet Catch

Table 2. Summary of the Results of the March 25, 1992 Particulate Emission Test on the No. 2A Dryer at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2
Date of test	03-25-92	03-25-92
Time runs were done (HRS)	1615/1717	1825/1927
Volumetric flow actual (ACFM) standard (DSCFM)	23907 16040	24205 15964
Gas temperature (DEG-F)	201	200
Moisture content (%V/V)	15.27	16.78
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	2.80 18.00 79.20	2.90 17.80 79.30
Isokinetic variation (%)	98.7	101.1
Particulate concentration actual (GR/ACF) standard (GR/DSCF)	.0880 0.131	.0557 .0845
Part. emission rate (LB/HR)	18.04	11.57

Note: Dry + Organic/Inorganic Wet Catch

Table 3. Summary of the Results of the March 25, 1992 Particulate Emission Test on the No. 2B Dryer at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2
Date of test	03-25-92	03-25-92
Time runs were done (HRS)	1510/1612	1710/1848
Volumetric flow actual (ACFM) standard (DSCFM)	25149 16774	25167 16717
Gas temperature (DEG-F)	199	197
Moisture content (%V/V)	16.06	16.62
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	3.00 17.90 79.10	3.00 17.80 79.20
Isokinetic variation (%)	100.3	100.8
Particulate concentration actual (GR/ACF) standard (GR/DSCF)	.0513 .0769	.0438 .0659
Part. emission rate (LB/HR)	11.06	9.45

Note: Dry + Organic/Inorganic Wet Catch

Table 4. Summary of the Results of the March 26, 1992 Particulate Emission Test on the No. 3 Dryer at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2	Run 3
Date of test	03-26-92	03-26-92	03-26-92
Time runs were done (HRS)	1555/1657	1725/1827	1900/2002
Volumetric flow actual (ACFM) standard (DSCFM)	42034 29852	42737 29917	41460 29342
Gas temperature (DEG-F)	195	194	193
Moisture content (%V/V)	11.45	12.86	11.98
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	1.60 19.30 79.10	2.00 18.80 79.20	1.60 19.20 79.20
Isokinetic variation (%)	97.4	100.8	100.2
Particulate concentration actual (GR/ACF) standard (GR/DSCF)	.0290 .0408	.0287 .0410	.0331 .0468
Part. emission rate (LB/HR)	10.44	10.51	11.78

Note: Dry + Organic/Inorganic Wet Catch

Table 5. Summary of the Results of the March 27, 1992 Particulate Emission Test on the No. 4 Press Vent Stack at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2	Run 3
Date of test	03-27-92	03-27-92	03-27-92
Time runs were done (HRS)	915/1017	1100/1202	1242/1344
Volumetric flow actual (ACFM) standard (DSCFM)	50060 48160	51836 47970	52000 48590
Gas temperature (DEG-F)	85	95	98
Moisture content (%V/V)	0.54	2.56	0.94
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	0.03 20.90 79.07	0.03 20.90 79.07	0.03 20.90 79.07
Isokinetic variation (%)	98.6	101.6	100.0
Particulate concentration actual (GR/ACF) standard (GR/DSCF)	.0135 .0140	.0160 .0173	.0134 .0143
Part. emission rate (LB/HR)	5.78	7.13	5.96

Note: Dry + Organic/Inorganic Wet Catch

Table 6. Summary of the Results of the March 27, 1992 Particulate Emission Test on the No. 3 Press Vent Stack at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2	Run 3
Date of test	03-27-92	03-27-92	03-27-92
Time runs were done (HRS)	1430/1532	1610/1712	1755/1857
Volumetric flow actual (ACFM) standard (DSCFM)	54441 50592	57062 53055	53077 49555
Gas temperature (DEG-F)	99	97	95
Moisture content (%V/V)	1.40	1.61	1.62
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	0.03 20.90 79.07	0.03 20.90 79.07	0.03 20.90 79.07
Isokinetic variation (%)	99.9	100.0	100.1
Particulate concentration actual (GR/ACF) standard (GR/DSCF)	.0150 .0161	.0144 .0154	.0143 .0154
Part. emission rate (LB/HR)	7.00	7.02	6.53

Note: Dry + Organic/Inorganic Wet Catch

Table 7. Summary of the Results of the March 28, 1992 Particulate Emission Test on the No. 2 Press Vent at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2	Run 3
Date of test	03-28-92	03-28-92	03-28-92
Time runs were done (HRS)	1415/1517	1610/1719	1742/1845
Volumetric flow actual (ACFM)	53416	57016	53092
standard (DSCFM)	50446	53980	49976
Gas temperature (DEG-F)	89	89	88
Moisture content (%V/V)	1.37	1.18	1.87
Gas composition (%V/V, dry)			
carbon dioxide	0.03	0.03	0.03
oxygen	20.90	20.90	20.90
nitrogen	79.07	79.07	79.07
Isokinetic variation (%)	98.9	99.4	101.0
Particulate concentration			
actual (GR/ACF)	.00568	.00630	.00751
standard (GR/DSCF)	.00601	.00666	.00799
Part. emission rate (LB/HR)	2.60	3.08	3.42

Note: Dry + Organic/Inorganic Wet Catch

Table 8. Summary of the Results of the March 28, 1992 Particulate Emission Test on the No. 8 Exhaust Fan Stack at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2	Run 3
Date of test	03-28-92	03-28-92	03-28-92
Time runs were done (HRS)	830/ 932	1035/1137	1220/1322
Volumetric flow actual (ACFM)	39353	39640	38771
standard (DSCFM)	38060	38180	37382
Gas temperature (DEG-F)	74	76	76
Moisture content (%V/V)	1.78	1.92	1.69
Gas composition (%V/V, dry)			
carbon dioxide	0.03	0.03	0.03
oxygen	20.90	20.90	20.90
nitrogen	79.07	79.07	79.07
Isokinetic variation (%)	100.6	99.9	99.8
Particulate concentration			
actual (GR/ACF)	.0166	.0174	.0168
standard (GR/DSCF)	.0172	.0181	.0174
Part. emission rate (LB/HR)	5.62	5.93	5.59

Note: Dry + Organic/Inorganic Wet Catch

Table 9. Summary of the Results of the March 24, 1992 PM-10 Determinations on the No. 1 Dryer at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2	Run 3
Date of test	03-24-92	03-24-92	03-24-92
Time runs were done (HRS)	930/1117	1200/1335	1437/1607
		0.0	0.0
Volumetric flow actual (ACFM) standard (DSCFM)	53069 36719	53874 37538	53125 36033
Gas temperature (DEG-F)	186	187	189
Moisture content (%V/V)	14.94	14.21	16.22
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	1.60 19.10 79.30	1.40 19.40 79.20	1.50 19.25 79.25
Isokinetic variation (%)	95.5	98.0	104.0
PM-10 concentration..... actual.....(GR/ACF) dry standard.....(GR/DSCF)	.0454 .0656	.0396 .0568	.0589 .0869
PM-10 mass rate.....(LB/HR)	20.65	18.29	26.83

Note: Dry + Organic/Inorganic Wet Catch

Table 10. Summary of the Results of the March 25, 1992 PM-10 Determinations on the No. 2A Dryer at the Louisiana Pacific Plant Located in Corrigan, Texas.

ITEM	Run 1	Run 2	Run 3
Date of test	03-25-92	03-25-92	03-25-92
Time runs were done (HRS)	930/1101	1145/1316	1345/1523
Volumetric flow actual (ACFM) standard (DSCFM)	25634 16883	25609 16866	26300 17418
Gas temperature (DEG-F)	198	201	202
Moisture content (%V/V)	17.22	16.91	16.29
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	3.00 17.90 79.10	3.00 17.80 79.20	2.80 18.00 79.20
Isokinetic variation (%)	103.8	100.6	98.4
PM-10 concentration..... actual.....(GR/ACF) dry standard.....(GR/DSCF)	.0448 .0680	.0613 .0931	.0405 .0611
PM-10 mass rate.....(LB/HR)	9.84	13.45	9.13

Note: Dry + Organic/Inorganic Wet Catch

Table 11. Summary of the Results of the March 25, 1992 PM-10 Determinations on the No. 3 Dryer at the Louisiana Pacific Plant Located in Corrigan, Texas.

26
- see p. 58

ITEM	Run 1	Run 2	Run 3
Date of test	03-26-92	03-26-92	03-26-92
Time runs were done (HRS)	915/1043	1130/1259	1333/1517
Volumetric flow actual (ACFM) standard (DSCFM)	44992 31400	44726 30550	44992 31132
Gas temperature (DEG-F)	204	200	196
Moisture content (%V/V)	11.76	14.21	13.54
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	2.00 18.90 79.10	1.80 18.90 79.30	1.80 19.00 79.20
Isokinetic variation (%)	87.7	94.6	88.7
PM-10 concentration..... actual.....(GR/ACF) dry standard.....(GR/DSCF)	.0272 .0390	.0413 .0605	.0380 .0550
PM-10 mass rate.....(LB/HR)	10.49	15.83	14.67

Note: Dry + Organic/Inorganic Wet Catch

Table 12. Summary of the March 24, 1992 Carbon Monoxide Emission Compliance Test on the No. 1 Dryer at the Louisiana Pacific Plant in Corrigan, Texas.

Date	Time	Volumetric		Emission Rate
		Flow Rate	Concentration	
	(HRS)	(DSCFM)	(ppm,w)	(LB/HR)
03-24-92	0930-1117	36720	272	51
03-24-92	1200-1335	37540	172	33
03-24-92	1437-1607	36035	134	25
Avg		36765	193	36
03-24-92	0955-1100	37665	182	35
03-24-92	1200-1337	38050	155	30
03-24-92	1403-1506	36940	127	24
Avg		37552	155	30
03-24-92	1610-1712	35150	96	17
03-24-92	1735-1838	35750	88	16
03-24-92	1900-2002	34885	77	14
Avg		35262	87	16

Table 13. Summary of the March 25, 1992 Carbon Monoxide Emission Compliance Test on the No. 2A Dryer at the Louisiana Pacific Plant in Corrigan, Texas.

Date	Time	Volumetric		Emission Rate
		Flow Rate	Concentration	
	(HRS)	(DSCFM)	(ppm,w)	(LB/HR)
03-25-92	0930-1101	16885	238	21
03-25-92	1145-1316	16865	168	15
03-25-92	1345-1523	17420	167	15
Avg		17057	191	17
03-25-92	1615-1717	16040	141	12
03-25-92	1825-1927	15965	170	14
Avg		16003	156	13

Table 14. Summary of the March 25, 1992 Carbon Monoxide Emission Compliance Test on the No. 2B Dryer at the Louisiana Pacific Plant in Corrigan, Texas.

Date	Time	Volumetric		Emission Rate
		Flow Rate	Concentration	
	(HRS)	(DSCFM)	(ppm,w)	(LB/HR)
(No. 2B Dryer)				
03-25-92	0930-1034	16745	231	20
03-25-92	1115-1218	16815	198	17
03-25-92	1255-1401	16790	154	14
Avg		16783	194	17
03-25-92	1510-1612	16775	138	12
03-25-92	1710-1848	16720	121	11
Avg		16748	130	12

Table 15. Summary of the March 26, 1992 Carbon Monoxide Emission Compliance Test on the No. 3 Dryer at the Louisiana Pacific Plant in Corrigan, Texas.

Date	Time	Volumetric		Emission Rate
		Flow Rate	Concentration	
	(HRS)	(DSCFM)	(ppm,w)	(LB/HR)
03-26-92	0915-1043	31400	283	44
03-26-92	1130-1259	30550	184	29
03-26-92	1333-1517	31130	199	31
Avg		31027	222	35
03-26-92	0916-1030	31530	273	43
03-26-92	1130-1251	31125	184	29
03-26-92	1400-1506	31385	212	34
Avg		31347	223	35
03-26-92	1555-1657	29850	283	42
03-26-92	1725-1827	29920	257	38
03-26-92	1900-2002	29340	306	45
Avg		29703	282	42

Table 16. Summary of the March 24-27, 1992 Formaldehyde Emission Compliance Test at the Louisiana Pacific Plant in Corrigan, Texas.

Date	Time	Volumetric		Emission Rate
		Flow Rate	Concentration	
	(HRS)	(DSCFM)	(ppm,w)	(LB/HR)
(No. 1 Dryer)				
03-24-92	0955-1100	37665	3.09	0.631
03-24-92	1200-1327	38048	1.07	0.219
03-24-92	1403-1506	36936	0.36	0.072
Avg		37550	1.51	0.307
(No. 2B Dryer)				
03-25-92	0930-1034	16746	0.84	0.078
03-25-92	1115-1218	16813	2.60	0.243
03-25-92	1255-1401	16789	1.55	0.146
Avg		16783	1.66	0.156
(No. 3 Dryer)				
03-26-92	0916-1030	31528	1.89	0.315
03-26-92	1130-1251	31125	0.86	0.145
03-26-92	1400-1506	31385	1.99	0.337
Avg		31346	1.58	0.266
(No. 4 Press Vent)				
03-27-92	0915-1017	53375	1.36	0.343
03-27-92	1100-1202	53125	1.48	0.374
03-27-92	1240-1345	56125	1.97	0.522
Avg		54208	1.60	0.413

Table 17. Summary of the March 27-28, 1992 Formaldehyde Emission Compliance Test at the Louisiana Pacific Plant in Corrigan, Texas.

Date	Time	Volumetric		Emission Rate
		Flow Rate	Concentration	
	(HRS)	(DSCFM)	(ppm,w)	(LB/HR)
(No. 3 Press Vent)				
03-27-92	1430-1531	58593	1.66	0.463
03-27-92	1610-1711	59434	1.04	0.278
03-27-92	1755-1856	57919	1.97	0.541
Avg		58649	1.56	0.427
(No. 2 Press Vent)				
03-28-92	0830-0943	52402	0.43	0.108
03-28-92	1033-1136	51778	0.51	0.127
03-28-92	1220-1324	52472	0.46	0.116
Avg		52217	0.47	0.117
(No. 8 Exhaust Fan Vent)				
03-28-92	1416-1518	45156	0.49	0.109
03-28-92	1600-1702	43365	0.48	0.101
03-28-92	1742-1847	43426	0.66	0.138
Avg		43982	0.54	0.116

Table 18. Summary of the March 24-27, 1992 Total Hydrocarbon Determinations at the Louisiana Pacific Plant in Corrigan, Texas.

Date	Time	Volumetric		Emission Rate
		Flow Rate	Concentration	
	(HRS)	(DSCFM)	(ppmC.w)	(LB/HR)
(No. 1 Dryer)				
03-24-92	0955-1100	36720	612	49.4
03-24-92	1200-1327	37540	582	47.6
03-24-92	1403-1538	36035	774	62.2
Avg		36765	656	53.1
(No. 2A Dryer)				
03-25-92	0955-1100	16885	615	23.4
03-25-92	1115-1225	16865	708	26.9
03-25-92	1255-1401	17420	552	21.5
Avg		17057	625	23.9
(No. 3 Dryer)				
03-26-92	0916-1030	31400	276	18.4
03-26-92	1135-1251	30550	402	26.8
03-26-92	1400-1506	31130	720	48.4
Avg		31027	466	31.2
(No. 4 Press Vent)				
03-27-92	0915-1019	48160	162	14.7
03-27-92	1100-1202	47970	216	19.9
03-27-92	1240-1345	48590	99	9.07
Avg		48240	159	14.5

$\times 2 = 47.8$

Table 19. Summary of the March 27, 1992 Total Hydrocarbon Determinations at the Louisiana Pacific Plant in Corrigan, Texas.

Date	Time	Volumetric		Emission Rate
		Flow Rate	Concentration	
	(HRS)	(DSCFM)	(ppmC,w)	(LB/HR)
(No. 3 Press Vent)				
03-27-92	1430-1531	50590	165	15.8
03-27-92	1610-1711	53055	84	8.46
03-27-92	1755-1856	49555	123	11.6
Avg		51067	124	12.0
(No. 2 Press Vent)				
03-27-92	1033-1140	50445	30	2.86
03-27-92	1148-1251	53980	18	1.83
03-27-92	1303-1406	49975	30	2.83
Avg		51467	26	2.51

3 RESULTS

The results of all field and laboratory evaluations are presented in this section. Gas composition (orsat and moisture) are presented first followed by the computer printout of the particulate, PM-10, carbon monoxide and formaldehyde results. Preliminary measurements including test port locations are given in the appendices.

The results have been calculated on a personal computer using programs written in Extended BASIC specifically for source testing calculations. EPA-published equations have been used as the basis of the calculation techniques in these programs.

The emission rates have been calculated using the product of the concentration times flow method.

3.1 Results of Orsat and Moisture Determinations

Test No. 1
No. 1 Dryer Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-24-92	03-24-92	03-24-92

Dry basis (orsat)

carbon dioxide.....	1.60	1.40	1.50
oxygen.....	19.10	19.40	19.25
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.30	79.20	79.25

Wet basis (orsat)

carbon dioxide.....	1.36	1.20	1.26
oxygen.....	16.25	16.64	16.13
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	67.45	67.94	66.39
water vapor.....	14.94	14.21	16.22

Dry molecular weight.....	29.02	29.00	29.01
Wet molecular weight.....	27.37	27.44	27.22
Specific gravity.....	0.946	0.948	0.940
Water mass flow.....(LB/HR)	18096	17446	19571

FO	1.125	1.071	1.100
----	-------	-------	-------

Test No. 2
No. 1 Dryer

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-24-92	03-24-92	03-24-92

Dry basis (orsat)

carbon dioxide.....	2.20	2.10	2.40
oxygen.....	18.50	18.70	18.30
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.30	79.20	79.30

Wet basis (orsat)

carbon dioxide.....	1.89	1.82	2.04
oxygen.....	15.92	16.22	15.54
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	68.25	68.71	67.33
water vapor.....	13.93	13.25	15.10

Dry molecular weight.....	29.09	29.08	29.12
---------------------------	-------	-------	-------

Wet molecular weight.....	27.55	27.62	27.44
---------------------------	-------	-------	-------

Specific gravity.....	0.952	0.954	0.948
-----------------------	-------	-------	-------

Water mass flow.....(LB/HR)	0.00	0.00	0.00
-----------------------------	------	------	------

FO	1.091	1.048	1.083
----	-------	-------	-------

Test No. 4
No. 1 Dryer Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-24-92	03-24-92	03-24-92

Dry basis (orsat)

carbon dioxide.....	1.80	2.00	2.20
oxygen.....	18.90	18.70	18.70
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.30	79.30	79.10

Wet basis (orsat)

carbon dioxide.....	1.52	1.68	1.82
oxygen.....	15.93	15.75	15.49
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	66.83	66.81	65.50
water vapor.....	15.72	15.75	17.19

Dry molecular weight.....	29.04	29.07	29.10
Wet molecular weight.....	27.31	27.32	27.19
Specific gravity.....	0.943	0.944	0.939
Water mass flow.....(LB/HR)	18391	18751	20310

FO	1.111	1.100	1.000
----	-------	-------	-------

Test No. 5
No. 2A Dryer Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-25-92	03-25-92	03-25-92

Dry basis (orsat)

carbon dioxide.....	3.00	3.00	2.80
oxygen.....	17.90	17.80	18.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.10	79.20	79.20

Wet basis (orsat)

carbon dioxide.....	2.48	2.49	2.34
oxygen.....	14.82	14.79	15.07
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	65.48	65.80	66.30
water vapor.....	17.22	16.91	16.29

Dry molecular weight.....	29.20	29.19	29.17
Wet molecular weight.....	27.27	27.30	27.35
Specific gravity.....	0.942	0.943	0.945
Water mass flow.....(LB/HR)	9848	9631	9506

FO	1.000	1.033	1.036
----	-------	-------	-------

Test No. 6
No. 2B Dryer Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-25-92	03-25-92	03-25-92

Dry basis (orsat)

carbon dioxide.....	2.80	2.90	2.90
oxygen.....	17.80	17.80	17.70
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.40	79.30	79.40

Wet basis (orsat)

carbon dioxide.....	2.35	2.44	2.41
oxygen.....	14.93	14.97	14.70
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	66.58	66.68	65.95
water vapor.....	16.14	15.92	16.94

Dry molecular weight.....	29.16	29.18	29.17
---------------------------	-------	-------	-------

Wet molecular weight.....	27.36	27.40	27.28
---------------------------	-------	-------	-------

Specific gravity.....	0.945	0.946	0.942
-----------------------	-------	-------	-------

Water mass flow.....(LB/HR)	0.00	0.00	0.00
-----------------------------	------	------	------

FO	1.107	1.069	1.103
----	-------	-------	-------

Test No. 8
No. 2A Dryer Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	4	5
	Run 1	Run 2
Date of run	03-25-92	03-25-92

Dry basis (orsat)

carbon dioxide.....	2.80	2.90
oxygen.....	18.00	17.80
carbon monoxide.....	0.00	0.00
nitrogen.....	79.20	79.30

Wet basis (orsat)

carbon dioxide.....	2.37	2.41
oxygen.....	15.25	14.81
carbon monoxide.....	0.00	0.00
nitrogen.....	67.10	66.00
water vapor.....	15.27	16.78

Dry molecular weight.....	29.17	29.18
Wet molecular weight.....	27.46	27.30
Specific gravity.....	0.949	0.943
Water mass flow.....(LB/HR)	8110	9026

FO	1.036	1.069
----	-------	-------

Test No. 9
No. 2B Dryer Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	4	5
	Run 1	Run 2
Date of run	03-25-92	03-25-92

Dry basis (orsat)

carbon dioxide.....	3.00	3.00
oxygen.....	17.90	17.80
carbon monoxide.....	0.00	0.00
nitrogen.....	79.10	79.20

Wet basis (orsat)

carbon dioxide.....	2.52	2.50
oxygen.....	15.03	14.84
carbon monoxide.....	0.00	0.00
nitrogen.....	66.40	66.04
water vapor.....	16.06	16.62

Dry molecular weight.....	29.20	29.19
Wet molecular weight.....	27.40	27.33
Specific gravity.....	0.946	0.944
Water mass flow.....(LB/HR)	9001	9343

FO	1.000	1.033
----	-------	-------

Test No. 10
No. 3 Dryer Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 03-26-92	Run 2 03-26-92	Run 3 03-26-92
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	2.00	1.80	1.80
oxygen.....	18.90	18.90	19.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.10	79.30	79.20

Wet basis (orsat)

carbon dioxide.....	1.76	1.54	1.56
oxygen.....	16.68	16.21	16.43
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	69.79	68.03	68.48
water vapor.....	11.76	14.21	13.54

Dry molecular weight.....	29.08	29.04	29.05
---------------------------	-------	-------	-------

Wet molecular weight.....	27.77	27.47	27.55
---------------------------	-------	-------	-------

Specific gravity.....	0.959	0.949	0.952
-----------------------	-------	-------	-------

Water mass flow.....(LB/HR)	11743	14191	13674
-----------------------------	-------	-------	-------

FO	1.000	1.111	1.056
----	-------	-------	-------

Test No. 11
No. 3 Dryer Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	4 Run 1	5 Run 2	4 Run 3
Date of run	03-26-92	03-26-92	03-26-92
Dry basis (orsat)			
carbon dioxide.....	2.00	1.70	1.60
oxygen.....	18.90	19.10	19.20
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.10	79.20	79.20
Wet basis (orsat)			
carbon dioxide.....	1.76	1.47	1.39
oxygen.....	16.66	16.49	16.62
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	69.71	68.39	68.56
water vapor.....	11.87	13.65	13.43
Dry molecular weight.....	29.08	29.04	29.02
Wet molecular weight.....	27.76	27.53	27.54
Specific gravity.....	0.959	0.951	0.951
Water mass flow.....(LB/HR)	0.00	0.00	0.00
FO	1.000	1.059	1.062

Test No. 13
No. 3 Dryer

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	7	8	9
	Run 1	Run 2	Run 3
Date of run	03-26-92	03-26-92	03-26-92

Dry basis (orsat)

carbon dioxide.....	1.60	2.00	1.60
oxygen.....	19.30	18.80	19.20
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.10	79.20	79.20

Wet basis (orsat)

carbon dioxide.....	1.42	1.74	1.41
oxygen.....	17.09	16.38	16.90
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	70.04	69.02	69.71
water vapor.....	11.45	12.86	11.98

Dry molecular weight.....	29.03	29.07	29.02
Wet molecular weight.....	27.77	27.65	27.70
Specific gravity.....	0.959	0.955	0.957
Water mass flow.....(LB/HR)	10826	12381	11204

FO	1.000	1.050	1.062
----	-------	-------	-------

Test No. 14
No. 4 Press Vent Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(t/v)

Date of run	Run 1 03-27-92	Run 2 03-27-92	Run 3 03-27-92
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.79	20.36	20.70
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	78.65	77.05	78.33
water vapor.....	0.54	2.56	0.94

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.78	28.56	28.74
Specific gravity.....	0.994	0.987	0.993
Water mass flow.....(LB/HR)	728	3535	1293

FO	0.000	0.000	0.000
----	-------	-------	-------

Test No. 15
No. 4 Press Vent Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-27-92	03-27-92	03-27-92

Dry basis (orsat)

carbon dioxide.....	0.00	0.00	0.00
oxygen.....	0.00	0.00	0.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	100.00	100.00	100.00

Wet basis (orsat)

carbon dioxide.....	0.00	0.00	0.00
oxygen.....	0.00	0.00	0.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	98.67	98.97	99.32
water vapor.....	1.33	1.03	0.68

Dry molecular weight.....	28.00	28.00	28.00
Wet molecular weight.....	27.87	27.90	27.93
Specific gravity.....	0.963	0.964	0.965
Water mass flow.....(LB/HR)	0.00	0.00	0.00

FO	0.000	0.000	0.000
----	-------	-------	-------

Test No. 17
No. 3 Press Vent Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-27-92	03-27-92	03-27-92

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.61	20.56	20.56
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	77.96	77.79	77.79
water vapor.....	1.40	1.61	1.62

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.69	28.67	28.66
Specific gravity.....	0.991	0.990	0.990
Water mass flow.....(LB/HR)	2012	2442	2296

FO	0.000	0.000	0.000
----	-------	-------	-------

Test No. 18
No. 3 Press Vent Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-27-92	03-27-92	03-27-92

Dry basis (orsat)

carbon dioxide.....	0.00	0.00	0.00
oxygen.....	0.00	0.00	0.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	100.00	100.00	100.00

Wet basis (orsat)

carbon dioxide.....	0.00	0.00	0.00
oxygen.....	0.00	0.00	0.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	98.35	98.63	98.14
water vapor.....	1.65	1.37	1.86

Dry molecular weight.....	28.00	28.00	28.00
Wet molecular weight.....	27.83	27.86	27.81
Specific gravity.....	0.961	0.962	0.961
Water mass flow.....(LB/HR)	0.00	0.00	0.00

FO	0.000	0.000	0.000
----	-------	-------	-------

Test No. 20
No. 8 Exhaust Fan Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 03-28-92	Run 2 03-28-92	Run 3 03-28-92
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.53	20.50	20.55
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	77.66	77.55	77.74
water vapor.....	1.78	1.92	1.69

Dry molecular weight.....	28.84	28.84	28.84
---------------------------	-------	-------	-------

Wet molecular weight.....	28.65	28.63	28.66
---------------------------	-------	-------	-------

Specific gravity.....	0.990	0.989	0.990
-----------------------	-------	-------	-------

Water mass flow.....(LB/HR)	1932	2095	1798
-----------------------------	------	------	------

FO	0.000	0.000	0.000
----	-------	-------	-------

Test No. 21
No. 2 Press Vent Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 03-28-92	Run 2 03-28-92	Run 3 03-28-92
Dry basis (orsat)			
carbon dioxide.....	0.00	0.00	0.00
oxygen.....	0.00	0.00	0.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	100.00	100.00	100.00
Wet basis (orsat)			
carbon dioxide.....	0.00	0.00	0.00
oxygen.....	0.00	0.00	0.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	97.86	98.03	98.46
water vapor.....	2.14	1.97	1.54
Dry molecular weight.....	28.00	28.00	28.00
Wet molecular weight.....	27.79	27.80	27.85
Specific gravity.....	0.960	0.960	0.962
Water mass flow.....(LB/HR)	0.00	0.00	0.00
FO	0.000	0.000	0.000

Test No. 23
No. 2 Press Vent

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	03-28-92	03-28-92	03-28-92

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.61	20.65	20.51
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	77.99	78.14	77.59
water vapor.....	1.37	1.18	1.87

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.69	28.71	28.64
Specific gravity.....	0.991	0.992	0.989
Water mass flow.....(LB/HR)	1965	1804	2666

FO	0.000	0.000	0.000
----	-------	-------	-------

Test No. 24
No. 8 Exhaust Fan Vent Stack

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 03-28-92	Run 2 03-28-92	Run 3 03-28-92
Dry basis (orsat)			
carbon dioxide.....	0.00	0.00	0.00
oxygen.....	0.00	0.00	0.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	100.00	100.00	100.00
Wet basis (orsat)			
carbon dioxide.....	0.00	0.00	0.00
oxygen.....	0.00	0.00	0.00
carbon monoxide.....	0.00	0.00	0.00
nitrogen.....	97.75	98.53	98.99
water vapor.....	2.25	1.47	1.01
Dry molecular weight.....	28.00	28.00	28.00
Wet molecular weight.....	27.78	27.85	27.90
Specific gravity.....	0.959	0.962	0.964
Water mass flow.....(LB/HR)	0.00	0.00	0.00
FO	0.000	0.000	0.000

3.2 Results of Particulate Determinations

Test No. 4
No. 1 Dryer

Results of Particulate Loading Determinations-----Method 5

	Run 1 03-24-92	Run 2 03-24-92	Run 3 03-24-92
Date of run			
Time run start/end.....(HRS)	1610/1712	1735/1838	1900/2002
Static pressure.....(IN.WC)	-0.75	-0.75	-0.75
Cross sectional area (SQ.FT)	12.57	12.57	12.57
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	113.0	113.0	122.0
desiccant.....(GRAMS)	8.0	9.0	10.0
total.....(GRAMS)	121.0	122.0	132.0
Total particulate material..			
.....collected(grams)	0.1385	0.1419	0.1165
Gas meter coefficient.....	1.0010	1.0098	1.0010
Barometric pressure..(IN.HG)	29.83	29.83	29.83
Avg. orif.pres.drop..(IN.WC)	0.83	0.83	0.81
Avg. gas meter temp..(DEF-F)	81.9	84.7	81.7
Volume through gas meter....			
at meter conditions...(CF)	31.40	31.47	30.78
standard conditions.(DSCF)	30.59	30.76	29.99
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.181	.181	.181
Avg.stack gas temp ..(DEG-F)	190	190	190
Volumetric flow rate.....			
actual.....(ACFM)	51613	52489	52112
dry standard.....(DSCFM)	35149	35751	34885
Isokinetic variation.....(%)	102.1	100.9	100.8
Particulate concentration...			
actual.....(GR/ACF)	0.04757	0.04846	0.04011
dry standard.....(GR/DSCF)	0.06987	0.07117	0.05995
Particle mass rate...(LB/HR)	21.051	21.809	17.925

Test No. 8
No. 2A Dryer Stack

Results of Particulate Loading Determinations-----Method 5

	Run 1	Run 2
Date of run	03-25-92	03-25-92
Time run start/end.....(HRS)	1615/1717	1825/1927
Static pressure.....(IN.WC)	-1.50	-1.50
Cross sectional area (SQ.FT)	4.59	4.59
Pitot tube coefficient.....	.840	.840
Water in sample gas		
condenser.....(ML)	0.0	0.0
impingers.....(GRAMS)	134.0	147.0
desiccant.....(GRAMS)	9.0	16.0
total.....(GRAMS)	143.0	163.0
Total particulate material..		
.....collected (grams)	0.3180	0.2089
Gas meter coefficient.....	0.9991	0.9991
Barometric pressure..(IN.HG)	29.77	29.77
Avg. orif.pres.drop..(IN.WC)	1.39	1.43
Avg. gas meter temp..(DEF-F)	89.4	84.6
Volume through gas meter....		
at meter conditions...(CF)	39.03	39.44
standard conditions.(DSCF)	37.40	38.13
Total sampling time....(MIN)	60.00	60.00
Nozzle diameter.....(IN)	.182	.182
Avg.stack gas temp ..(DEG-F)	201	200
Volumetric flow rate.....		
actual.....(ACFM)	23907	24205
dry standard.....(DSCFM)	16040	15964
Isokinetic variation.....(%)	98.7	101.1
Particulate concentration...		
actual.....(GR/ACF)	0.08798	0.05573
dry standard.....(GR/DSCF)	0.13118	0.08454
Particle mass rate...(LB/HR)	18.04	11.57

Test No. 9
No. 2B Dryer Stack

Results of Particulate Loading Determinations-----Method 5

	Run 1	Run 2
Date of run	03-25-92	03-25-92
Time run start/end.....(HRS)	1510/1612	1710/1848
Static pressure.....(IN.WC)	-1.30	-1.30
Cross sectional area (SQ.FT)	4.59	4.59
Pitot tube coefficient.....	.840	.840
Water in sample gas		
condenser.....(ML)	0.0	0.0
impingers.....(GRAMS)	147.0	154.0
desiccant.....(GRAMS)	16.0	16.0
total.....(GRAMS)	163.0	170.0
Total particulate material..		
.....collected (grams)	0.2002	0.1719
Gas meter coefficient.....	1.0010	1.0010
Barometric pressure..(IN.HG)	29.77	29.77
Avg. orif.pres.drop..(IN.WC)	1.46	1.45
Avg. gas meter temp..(DEF-F)	87.2	83.2
Volume through gas meter....		
at meter conditions...(CF)	41.67	41.42
standard conditions.(DSCF)	40.17	40.23
Total sampling time....(MIN)	60.00	60.00
Nozzle diameter.....(IN)	.183	.183
Avg.stack gas temp ..(DEG-F)	199	197
Volumetric flow rate.....		
actual.....(ACFM)	25149	25167
dry standard.....(DSCFM)	16774	16717
Isokinetic variation.....(%)	100.3	100.8
Particulate concentration...		
actual.....(GR/ACF)	0.05127	0.04378
dry standard.....(GR/DSCF)	0.07689	0.06594
Particle mass rate...(LB/HR)	11.06	9.45

Test No. 13
No. 3 Dryer

Results of Particulate Loading Determinations-----Method 5

	Run 1	Run 2	Run 3
Date of run	03-26-92	03-26-92	03-26-92
Time run start/end.....(HRS)	1555/1657	1725/1827	1900/2002
Static pressure.....(IN.WC)	-0.70	-0.70	-0.70
Cross sectional area (SQ.FT)	9.39	9.39	9.39
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	82.0	99.0	81.0
desiccant.....(GRAMS)	11.0	11.0	18.0
total.....(GRAMS)	93.0	110.0	99.0
Total particulate material..			
.....collected(grams)	0.0897	0.0934	0.1041
Gas meter coefficient.....	0.9991	0.9991	0.9991
Barometric pressure..(IN.HG)	29.82	29.82	29.82
Avg. orif.pres.drop..(IN.WC)	1.18	1.26	1.20
Avg. gas meter temp..(DEF-F)	92.4	89.5	86.1
Volume through gas meter....			
at meter conditions...(CF)	35.55	36.64	35.53
standard conditions.(DSCF)	33.92	35.15	34.29
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.183	.183	.183
Avg.stack gas temp ..(DEG-F)	195	194	193
Volumetric flow rate.....			
actual.....(ACFM)	42034	42737	41460
dry standard.....(DSCFM)	29852	29917	29342
Isokinetic variation.....(%)	97.4	100.8	100.2
Particulate concentration...			
actual.....(GR/ACF)	0.02897	0.02869	0.03314
dry standard.....(GR/DSCF)	0.04081	0.04100	0.04684
Particle mass rate...(LB/HR)	10.442	10.513	11.781

Test No. 14
No. 4 Press Vent Stack

Results of Particulate Loading Determinations-----Method 5

	Run 1	Run 2	Run 3
Date of run	03-27-92	03-27-92	03-27-92
Time run start/end.....(HRS)	915/1017	1100/1202	1242/1344
Static pressure.....(IN.WC)	-0.12	-0.12	-0.12
Cross sectional area (SQ.FT)	20.63	20.63	20.63
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	0.0	2.0	1.0
desiccant.....(GRAMS)	5.0	23.0	8.0
total.....(GRAMS)	5.0	25.0	9.0
Total particulate material..			
.....collected(grams)	0.0397	0.0504	0.0415
Gas meter coefficient.....	0.9991	0.9991	0.9991
Barometric pressure..(IN.HG)	29.86	29.86	29.86
Avg. orif.pres.drop..(IN.WC)	1.93	2.08	2.02
Avg. gas meter temp..(DEF-F)	86.7	94.6	93.7
Volume through gas meter....			
at meter conditions...(CF)	45.21	47.04	46.82
standard conditions.(DSCF)	43.73	44.86	44.72
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.241	.241	.241
Avg.stack gas temp ..(DEG-F)	85	95	98
Volumetric flow rate.....			
actual.....(ACFM)	50060	51836	52000
dry standard.....(DSCFM)	48160	47970	48590
Isokinetic variation.....(%)	98.6	101.6	100.0
Particulate concentration...			
actual.....(GR/ACF)	0.01347	0.01604	0.01337
dry standard.....(GR/DSCF)	0.01401	0.01733	0.01432
Particle mass rate...(LB/HR)	5.783	7.127	5.963

Test No. 17
No. 3 Press Vent Stack

Results of Particulate Loading Determinations-----Method 5

	Run 1	Run 2	Run 3
Date of run	03-27-92	03-27-92	03-27-92
Time run start/end.....(HRS)	1430/1532	1610/1712	1755/1857
Static pressure.....(IN.WC)	-0.10	-0.10	-0.10
Cross sectional area (SQ.FT)	20.63	20.63	20.63
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	0.0	0.0	3.0
desiccant.....(GRAMS)	14.0	17.0	13.0
total.....(GRAMS)	14.0	17.0	16.0
Total particulate material..			
.....collected(grams)	0.0487	0.0489	0.0455
Gas meter coefficient.....	0.9991	0.9991	0.9991
Barometric pressure..(IN.HG)	29.86	29.86	29.86
Avg. orif.pres.drop..(IN.WC)	2.23	2.47	2.16
Avg. gas meter temp..(DEF-F)	98.4	98.6	96.0
Volume through gas meter....			
at meter conditions...(CF)	49.13	51.54	48.00
standard conditions.(DSCF)	46.56	48.85	45.67
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.241	.241	.241
Avg.stack gas temp ..(DEG-F)	99	97	95
Volumetric flow rate.....			
actual.....(ACFM)	54441	57062	53077
dry standard.....(DSCFM)	50592	53055	49555
Isokinetic variation.....(%)	99.9	100.0	100.1
Particulate concentration...			
actual.....(GR/ACF)	0.01499	0.01435	0.01435
dry standard.....(GR/DSCF)	0.01614	0.01544	0.01537
Particle mass rate...(LB/HR)	6.999	7.024	6.529

Test No. 20
No. 8 Exhaust Fan Stack

Results of Particulate Loading Determinations-----Method 5

	Run 1	Run 2	Run 3
Date of run	03-28-92	03-28-92	03-28-92
Time run start/end.....(HRS)	830/ 932	1035/1137	1220/1322
Static pressure.....(IN.WC)	-0.25	-0.25	-0.25
Cross sectional area (SQ.FT)	21.48	21.48	21.48
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	0.0	4.0	3.0
desiccant.....(GRAMS)	13.0	10.0	9.0
total.....(GRAMS)	13.0	14.0	12.0
Total particulate material..			
.....collected(grams)	0.0378	0.0396	0.0373
Gas meter coefficient.....	0.9991	0.9991	0.9991
Barometric pressure..(IN.HG)	29.82	29.82	29.82
Avg. orif.pres.drop..(IN.WC)	1.30	1.32	1.27
Avg. gas meter temp..(DEF-F)	78.7	80.0	75.9
Volume through gas meter....			
at meter conditions...(CF)	34.61	34.55	33.54
standard conditions.(DSCF)	33.88	33.74	32.99
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.241	.241	.241
Avg.stack gas temp ..(DEG-F)	74	76	76
Volumetric flow rate.....			
actual.....(ACFM)	39353	39640	38771
dry standard.....(DSCFM)	38060	38180	37382
Isokinetic variation.....(%)	100.6	99.9	99.8
Particulate concentration...			
actual.....(GR/ACF)	0.01664	0.01744	0.01681
dry standard.....(GR/DSCF)	0.01722	0.01811	0.01745
Particle mass rate...(LB/HR)	5.617	5.927	5.590

Test No. 23
No. 2 Press Vent

Results of Particulate Loading Determinations-----Method 5

	Run 1 03-28-92	Run 2 03-28-92	Run 3 03-28-92
Date of run			
Time run start/end.....(HRS)	1415/1517	1610/1719	1742/1845
Static pressure.....(IN.WC)	-0.12	-0.12	-0.12
Cross sectional area (SQ.FT)	21.48	21.48	21.48
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	1.0	2.0	2.0
desiccant.....(GRAMS)	12.0	10.0	16.0
total.....(GRAMS)	13.0	12.0	18.0
Total particulate material..			
.....collected(grams)	0.0172	0.0205	0.0231
Gas meter coefficient.....	1.0010	1.0010	1.0010
Barometric pressure..(IN.HG)	29.82	29.82	29.82
Avg. orif.pres.drop..(IN.WC)	1.86	2.11	1.83
Avg. gas meter temp..(DEF-F)	88.8	81.9	84.5
Volume through gas meter....			
at meter conditions...(CF)	45.79	48.61	45.95
standard conditions.(DSCF)	44.14	47.48	44.63
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.241	.241	.241
Avg.stack gas temp ..(DEG-F)	89	89	88
Volumetric flow rate.....			
actual.....(ACFM)	53416	57016	53092
dry standard.....(DSCFM)	50446	53980	49976
Isokinetic variation.....(%)	98.9	99.4	101.0
Particulate concentration...			
actual.....(GR/ACF)	0.00568	0.00630	0.00751
dry standard.....(GR/DSCF)	0.00601	0.00666	0.00799
Particle mass rate...(LB/HR)	2.600	3.082	3.421

3.3 Results of PM-10 Determinations

Test No. 1
No. 1 Dryer Stack

Results of PM-10 Determinations -----

	Run 1	Run 2	Run 3
Date of run	03-24-92	03-24-92	03-24-92
Time run start/end.....(HRS)	930/1117	1200/1335	1437/1607
Static pressure.....(IN.WC)	-0.75	-0.75	-0.75
Cross sectional area (SQ.FT)	12.57	12.57	12.57
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	102.0	111.0	119.0
desiccant.....(GRAMS)	10.0	7.0	9.0
total.....(GRAMS)	112.0	118.0	128.0
Total PM-10 material.....			
.....collected(grams)	0.1278	0.1237	0.1755
Gas meter coefficient.....	0.9991	0.9991	0.9991
Barometric pressure..(IN.HG)	29.83	29.83	29.83
Avg. orif.pres.drop..(IN.WC)	0.38	0.43	0.45
Avg. gas meter temp..(DEF-F)	66.4	74.7	78.5
Volume through gas meter....			
at meter conditions...(CF)	30.07	34.12	31.89
standard conditions.(DSCF)	30.06	33.58	31.17
Total sampling time....(MIN)	87.87	93.51	85.21
Nozzle diameter.....(IN)	.150	.150	.150
Avg.stack gas temp ..(DEG-F)	186	187	189
Volumetric flow rate.....			
actual.....(ACFM)	53069	53874	53125
dry standard.....(DSCFM)	36719	37538	36033
Isokinetic variation.....(%)	95.5	98.0	104.0
PM-10 cutpoint.....(um)	10.54	10.31	9.96
PM-10 concentration.....			
actual.....(GR/ACF)	0.04538	0.03959	0.05891
dry standard.....(GR/DSCF)	0.06561	0.05684	0.08688
PM-10 mass rate.....(LB/HR)	20.648	18.289	26.834

Test No. 5
No. 2A Dryer Stack

Results of PM-10 Determinations -----

	Run 1 03-25-92	Run 2 03-25-92	Run 3 03-25-92
Date of run			
Time run start/end.....(HRS)	930/1101	1145/1316	1345/1523
Static pressure.....(IN.WC)	-1.50	-1.50	-1.50
Cross sectional area (SQ.FT)	4.59	4.59	4.59
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	126.0	121.0	124.0
desiccant.....(GRAMS)	7.0	9.0	11.0
total.....(GRAMS)	133.0	130.0	135.0
Total PM-10 material.....			
.....collected(grams)	0.1329	0.1816	0.1296
Gas meter coefficient.....	0.9991	0.9991	0.9991
Barometric pressure..(IN.HG)	29.79	29.79	29.77
Avg. orif.pres.drop..(IN.WC)	0.44	0.41	0.42
Avg. gas meter temp..(DEF-F)	86.3	88.4	89.8
Volume through gas meter....			
at meter conditions...(CF)	31.34	31.42	34.25
standard conditions.(DSCF)	30.15	30.11	32.71
Total sampling time....(MIN)	84.37	87.03	93.56
Nozzle diameter.....(IN)	.131	.131	.131
Avg.stack gas temp ..(DEG-F)	198	201	202
Volumetric flow rate.....			
actual.....(ACFM)	25634	25609	26300
dry standard.....(DSCFM)	16883	16866	17418
Isokinetic variation.....(%)	103.8	100.6	98.4
PM-10 cutpoint.....(um)	9.98	10.29	10.28
PM-10 concentration.....			
actual.....(GR/ACF)	0.04477	0.06126	0.04047
dry standard.....(GR/DSCF)	0.06801	0.09306	0.06113
PM-10 mass rate.....(LB/HR)	9.841	13.453	9.126

Test No. 10
No. 3 Dryer Stack

Results of PM-10 Determinations -----

	Run 1 03-26-92	Run 2 03-26-92	Run 3 03-26-92
Date of run			
Time run start/end.....(HRS)	915/1043	1130/1259	1333/1517
Static pressure.....(IN.WC)	-0.70	-0.70	-0.70
Cross sectional area (SQ.FT)	9.39	9.39	9.39
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	78.0	103.0	94.0
desiccant.....(GRAMS)	9.0	11.0	6.0
total.....(GRAMS)	87.0	114.0	100.0
Total PM-10 material.....			
.....collected(grams)	0.0777	0.1272	0.1073
Gas meter coefficient.....	0.9991	0.9991	0.9991
Barometric pressure..(IN.HG)	29.82	29.82	29.82
Avg. orif.pres.drop..(IN.WC)	0.44	0.50	0.45
Avg. gas meter temp..(DEF-F)	82.4	95.0	92.1
Volume through gas meter....			
at meter conditions...(CF)	31.72	34.23	31.60
standard conditions.(DSCF)	30.77	32.46	30.11
Total sampling time....(MIN)	85.54	86.04	83.53
Nozzle diameter.....(IN)	.150	.150	.150
Avg.stack gas temp ..(DEG-F)	204	200	196
Volumetric flow rate.....			
actual.....(ACFM)	44992	44726	44992
dry standard.....(DSCFM)	31400	30550	31132
Isokinetic variation.....(%)	87.7	94.6	88.7
PM-10 cutpoint.....(um)	10.53	9.93	10.31
PM-10 concentration.....			
actual.....(GR/ACF)	0.02718	0.04129	0.03803
dry standard.....(GR/DSCF)	0.03897	0.06047	0.05498
PM-10 mass rate.....(LB/HR)	10.488	15.834	14.672

3.4 Results of Carbon Monoxide Determinations

Test No. 1
No. 1 Dryer Stack

Results of CO Determinations -----Method 10

	Run 1	Run 2	Run 3
Date of run	03-24-92	03-24-92	03-24-92
Time run start/end.....(HRS)	0930-1117	1200-1335	1437-1607
Total sampling time....(MIN)	87.9	93.5	85.2
Moisture content.....(%V/V)	14.94	14.21	16.22
O2 Concentration.....(%V/V)	19.10	19.40	19.25
Volumetric flow rate (DSCFM)	36720	37540	36035
CO concentration.....			
(GR/DSCF).....	0.1628	0.1018	0.0814
(MG/DSCM).....	372.80	233.00	186.40
(PPM-WET).....	272.19	171.58	134.05
(PPM-DRY).....	320.00	200.00	160.00
(PPM-DRY @ 7% O2).....	2357.	1750.	1280.
CO emission rate.....(LB/HR)	51.248	32.745	25.146

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 2
No. 1 Dryer Stack

Results of CO Determinations -----Method 10

	⁴ Run 1	⁵ Run 2	⁶ Run 3
Date of run	03-24-92	03-24-92	03-24-92
Time run start/end.....(HRS)	0955-1100	1200-1327	1403-1506
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	13.93	13.25	15.10
O2 Concentration.....(%V/V)	18.50	18.70	18.30
Volumetric flow rate (DSCFM)	37665	38050	36940
CO concentration.....			
(GR/DSCF).....	0.1079	0.0911	0.0763
(MG/DSCM).....	246.98	208.53	174.75
(PPM-WET).....	182.47	155.28	127.35
(PPM-DRY).....	212.00	179.00	150.00
(PPM-DRY @ 7% O2).....	1187.	1089.	777.78
CO emission rate.....(LB/HR)	34.825	29.705	24.166

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 4
No. 1 Dryer Stack

Results of CO Determinations -----Method 10

	7 Run 1	8 Run 2	9 Run 3
Date of run	03-24-92	03-24-92	03-24-92
Time run start/end.....(HRS)	1610-1712	1735-1838	1900-2002
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	15.72	15.75	17.19
O2 Concentration.....(%V/V)	18.90	18.70	18.70
Volumetric flow rate (DSCFM)	35150	35750	34885
CO concentration.....			
(GR/DSCF).....	0.0580	0.0534	0.0473
(MG/DSCM).....	132.81	122.33	108.34
(PPM-WET).....	96.08	88.46	77.01
(PPM-DRY).....	114.00	105.00	93.00
(PPM-DRY @ 7% O2).....	760.00	639.13	566.09
CO emission rate.....(LB/HR)	17.476	16.371	14.150

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 5
No. 2A Dryer Stack

Results of CO Determinations -----Method 10

	Run 1	Run 2	Run 3
Date of run	03-25-92	03-25-92	03-25-92
Time run start/end.....(HRS)	0930-1101	1145-1316	1345-1523
Total sampling time....(MIN)	84.4	87.0	93.6
Moisture content.....(%V/V)	17.22	16.91	16.29
O2 Concentration.....(%V/V)	17.90	17.80	18.00
Volumetric flow rate (DSCFM)	16885	16865	17420
CO concentration.....			
(GR/DSCF).....	0.1460	0.1028	0.1018
(MG/DSCM).....	334.35	235.33	233.00
(PPM-WET).....	237.58	167.84	167.42
(PPM-DRY).....	287.00	202.00	200.00
(PPM-DRY @ 7% O2).....	1296.	883.75	933.33
CO emission rate.....(LB/HR)	21.135	14.858	15.195

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 8
No. 2A Dryer Stack

Results of CO Determinations -----Method 10

	4 Run 1	5 Run 2
Date of run	03-25-92	03-25-92
Time run start/end.....(HRS)	1615-1717	1825-1927
Total sampling time....(MIN)	60.0	60.0
Moisture content.....(%V/V)	15.27	16.78
O2 Concentration.....(%V/V)	18.00	17.80
Volumetric flow rate (DSCFM)	16040	15965
CO concentration.....		
(GR/DSCF).....	0.0845	0.1038
(MG/DSCM).....	193.39	237.66
(PPM-WET).....	140.65	169.77
(PPM-DRY).....	166.00	204.00
(PPM-DRY @ 7% O2).....	774.67	892.50
CO emission rate.....(LB/HR)	11.613	14.204

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 6
No. 2B Dryer Stack

Results of CO Determinations -----Method 10

	Run 1	Run 2	Run 3
Date of run	03-25-92	03-25-92	03-25-92
Time run start/end.....(HRS)	0930-1034	1115-1218	1255-1401
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	16.14	15.92	16.94
O2 Concentration.....(%V/V)	17.80	17.80	17.70
Volumetric flow rate (DSCFM)	16745	16815	16790
CO concentration.....			
(GR/DSCF).....	0.1404	0.1196	0.0941
(MG/DSCM).....	321.54	273.78	215.53
(PPM-WET).....	231.45	197.59	153.66
(PPM-DRY).....	276.00	235.00	185.00
(PPM-DRY @ 7% O2).....	1207.	1028.	784.85
CO emission rate.....(LB/HR)	20.157	17.234	13.547

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 9
No. 2B Dryer Stack

Results of CO Determinations -----Method 10

	4 Run 1	5 Run 2
Date of run	03-25-92	03-25-92
Time run start/end.....(HRS)	1510-1612	1710-1848
Total sampling time....(MIN)	60.0	60.0
Moisture content.....(%V/V)	16.06	16.62
O2 Concentration.....(%V/V)	17.90	17.80
Volumetric flow rate (DSCFM)	16775	16720
CO concentration.....		
(GR/DSCF).....	0.0835	0.0738
(MG/DSCM).....	191.06	168.92
(PPM-WET).....	137.66	120.90
(PPM-DRY).....	164.00	145.00
(PPM-DRY @ 7% O2).....	740.65	634.37
CO emission rate.....(LB/HR)	11.999	10.574

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 10
No. 3 Dryer Stack

Results of CO Determinations -----Method 10

	Run 1	Run 2	Run 3
Date of run	03-26-92	03-26-92	03-26-92
Time run start/end.....(HRS)	0915-1043	1130-1259	1333-1517
Total sampling time....(MIN)	85.5	86.0	83.5
Moisture content.....(%V/V)	11.76	14.21	13.54
O2 Concentration.....(%V/V)	18.90	18.90	19.00
Volumetric flow rate (DSCFM)	31400	30550	31130
CO concentration.....			
(GR/DSCF).....	0.1633	0.1094	0.1170
(MG/DSCM).....	373.97	250.48	267.95
(PPM-WET).....	283.25	184.45	198.86
(PPM-DRY).....	321.00	215.00	230.00
(PPM-DRY @ 7% O2).....	2140.	1433.	1610.
CO emission rate.....(LB/HR)	43.960	28.646	31.227

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 11
No. 3 Dryer Stack

Results of CO Determinations -----Method 10

	⁴ Run 1	⁵ Run 2	⁶ Run 3
Date of run	03-26-92	03-26-92	03-26-92
Time run start/end.....(HRS)	0916-1030	1130-1251	1400-1506
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	11.87	13.65	13.43
O2 Concentration.....(%V/V)	18.90	19.10	19.20
Volumetric flow rate (DSCFM)	31530	31125	31385
CO concentration.....			
(GR/DSCF).....	0.1577	0.1084	0.1247
(MG/DSCM).....	361.15	248.15	285.43
(PPM-WET).....	273.20	183.93	212.10
(PPM-DRY).....	310.00	213.00	245.00
(PPM-DRY @ 7% O2).....	2066.	1569.	1905.
CO emission rate.....(LB/HR)	42.629	28.914	33.536

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 13
No. 3 Dryer

Results of CO Determinations -----Method 10

	7 Run 1	8 Run 2	7 Run 3
Date of run	03-26-92	03-26-92	03-26-92
Time run start/end.....(HRS)	1555-1657	1725-1827	1900-2002
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	11.45	12.86	11.98
O2 Concentration.....(%V/V)	19.30	18.80	19.20
Volumetric flow rate (DSCFM)	29850	29920	29340
CO concentration.....			
(GR/DSCF).....	0.1628	0.1501	0.1771
(MG/DSCM).....	372.80	343.68	405.42
(PPM-WET).....	283.36	257.06	306.31
(PPM-DRY).....	320.00	295.00	348.00
(PPM-DRY @ 7% O2).....	2635.	1877.	2706.
CO emission rate.....(LB/HR)	41.660	38.495	44.531

CO = Carbon monoxide

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

3.5 Results of Formaldehyde Determinations

Test No. 2
No. 1 Dryer

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1	Run 2	Run 3
Date of run	03-24-92	03-24-92	03-24-92
Time run start/end.....(HRS)	955/1100	1200/1327	1403/1506
Static pressure.....(IN.WC)	-0.75	-0.75	-0.75
Cross sectional area (SQ.FT)	12.57	12.57	12.57
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	104.0	100.0	120.0
desiccant.....(GRAMS)	10.0	12.0	10.0
total.....(GRAMS)	114.0	112.0	130.0
Formaldehyde in sample..(uG)	4200	1500	510
Gas meter coefficient.....	1.0010	1.0010	1.0010
Barometric pressure..(IN.HG)	29.83	29.83	29.83
Avg. orif.pres.drop..(IN.WC)	0.96	1.06	1.06
Avg. gas meter temp..(DEF-F)	67.8	76.7	82.5
Volume through gas meter....			
at meter conditions...(CF)	33.19	35.15	35.41
standard conditions.(DSCF)	33.20	34.59	34.47
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.188	.188	.188
Avg.stack gas temp ..(DEG-F)	184	187	188
Volumetric flow rate.....			
actual.....(ACFM)	53651	53997	53617
dry standard.....(DSCFM)	37665	38048	36936
Isokinetic variation.....(%)	95.8	98.8	101.5
CH2O concentration.....			
(GR/DSCF).....	0.0020	0.0007	0.0002
(MG/DSCM).....	4.48	1.54	0.52
(PPM-DRY).....	3.59	1.23	0.42
(PPM-WET).....	3.09	1.07	0.36
CH2O emission rate...(LB/HR)	0.63141	0.21873	0.07244

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 6
No. 2B Dryer Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1	Run 2	Run 3
Date of run	03-25-92	03-25-92	03-25-92
Time run start/end.....(HRS)	930/1034	1115/1218	1255/1401
Static pressure.....(IN.WC)	-1.30	-1.30	-1.30
Cross sectional area (SQ.FT)	4.59	4.59	4.59
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	161.0	153.0	166.0
desiccant.....(GRAMS)	13.0	17.0	19.0
total.....(GRAMS)	174.0	170.0	185.0
Formaldehyde in sample..(uG)	1500	4600	2800
Gas meter coefficient.....	1.0010	1.0010	1.0010
Barometric pressure..(IN.HG)	29.77	29.77	29.77
Avg. orif.pres.drop..(IN.WC)	1.63	1.62	1.68
Avg. gas meter temp..(DEF-F)	79.0	86.5	90.8
Volume through gas meter....			
at meter conditions...(CF)	43.52	43.84	44.62
standard conditions.(DSCF)	42.61	42.34	42.76
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.188	.188	.188
Avg.stack gas temp ..(DEG-F)	197	199	198
Volumetric flow rate.....			
actual.....(ACFM)	25069	25159	25387
dry standard.....(DSCFM)	16746	16813	16789
Isokinetic variation.....(%)	101.0	99.9	101.1
CH2O concentration.....			
(GR/DSCF).....	0.0005	0.0017	0.0010
(MG/DSCM).....	1.25	3.85	2.32
(PPM-DRY).....	1.00	3.09	1.86
(PPM-WET).....	0.84	2.60	1.55
CH2O emission rate...(LB/HR)	0.07826	0.24250	0.14595

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 11
No. 3 Dryer Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1 03-26-92	Run 2 03-26-92	Run 3 03-26-92
Date of run			
Time run start/end.....(HRS)	916/1030	1130/1251	1400/1506
Static pressure.....(IN.WC)	-0.68	-0.68	-0.68
Cross sectional area (SQ.FT)	9.39	9.39	9.39
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	92.0	118.0	112.0
desiccant.....(GRAMS)	14.0	16.0	14.0
total.....(GRAMS)	106.0	134.0	126.0
Formaldehyde in sample..(uG)	2800	1400	3100
Gas meter coefficient.....	1.0010	1.0010	1.0010
Barometric pressure..(IN.HG)	29.82	29.82	29.82
Avg. orif.pres.drop..(IN.WC)	1.25	1.41	1.39
Avg. gas meter temp..(DEF-F)	72.4	72.4	96.4
Volume through gas meter....			
at meter conditions...(CF)	37.42	40.28	40.33
standard conditions.(DSCF)	37.12	39.98	38.30
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.188	.188	.188
Avg.stack gas temp ..(DEG-F)	205	200	197
Volumetric flow rate.....			
actual.....(ACFM)	45251	45292	45331
dry standard.....(DSCFM)	31528	31125	31385
Isokinetic variation.....(%)	95.7	104.4	99.2
CH2O concentration.....			
(GR/DSCF).....	0.0012	0.0005	0.0013
(MG/DSCM).....	2.67	1.24	2.87
(PPM-DRY).....	2.14	0.99	2.30
(PPM-WET).....	1.89	0.86	1.99
CH2O emission rate...(LB/HR)	0.31537	0.14461	0.33702

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 15
No. 4 Press Vent Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1 03-27-92	Run 2 03-27-92	Run 3 03-27-92
Date of run			
Time run start/end.....(HRS)	915/1017	1100/1202	1240/1345
Static pressure.....(IN.WC)	-0.12	-0.12	-0.12
Cross sectional area (SQ.FT)	21.48	21.48	21.48
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	0.0	0.0	-1.0
desiccant.....(GRAMS)	13.0	10.0	8.0
total.....(GRAMS)	13.0	10.0	7.0
Formaldehyde in sample..(uG)	2200	2400	3400
Gas meter coefficient.....	1.0010	1.0010	1.0010
Barometric pressure..(IN.HG)	29.86	29.86	29.86
Avg. orif.pres.drop..(IN.WC)	1.90	1.93	2.15
Avg. gas meter temp..(DEF-F)	83.1	92.2	96.6
Volume through gas meter....			
at meter conditions...(CF)	46.62	47.26	50.98
standard conditions.(DSCF)	45.47	45.34	48.55
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.239	.239	.239
Avg.stack gas temp ..(DEG-F)	83	95	98
Volumetric flow rate.....			
actual.....(ACFM)	55773	56548	59815
dry standard.....(DSCFM)	53375	53125	56125
Isokinetic variation.....(%)	97.9	98.1	99.4
CH2O concentration.....			
(GR/DSCF).....	0.0007,	0.0008	0.0011
(MG/DSCM).....	1.72	1.88	2.49
(PPM-DRY).....	1.38	1.50	1.99
(PPM-WET).....	1.36	1.48	1.97
CH2O emission rate...(LB/HR)	0.34300	0.37354	0.52240

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 18
No. 3 Press Vent Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1	Run 2	Run 3
Date of run	03-27-92	03-27-92	03-27-92
		/6/8	
Time run start/end.....(HRS)	1430/1531	4410/1711	1755/1856
Static pressure.....(IN.WC)	-0.12	-0.12	-0.12
Cross sectional area (SQ.FT)	21.48	21.48	21.48
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	4.0	-2.0	7.0
desiccant.....(GRAMS)	14.0	17.0	13.0
total.....(GRAMS)	18.0	15.0	20.0
Formaldehyde in sample..(uG)	3000	1900	3500
Gas meter coefficient.....	1.0010	1.0010	1.0010
Barometric pressure..(IN.HG)	29.86	29.86	29.86
Avg. orif.pres.drop..(IN.WC)	2.40	2.48	2.34
Avg. gas meter temp..(DEF-F)	98.3	98.8	96.3
Volume through gas meter....			
at meter conditions...(CF)	53.16	53.80	52.28
standard conditions.(DSCF)	50.50	51.07	49.84
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.239	.239	.239
Avg.stack gas temp ..(DEG-F)	99	98	95
Volumetric flow rate.....			
actual.....(ACFM)	63273	63804	62209
dry standard.....(DSCFM)	58593	59434	57919
Isokinetic variation.....(%)	99.1	98.8	98.9
CH2O concentration.....			
(GR/DSCF).....	0.0009	0.0006	0.0011
(MG/DSCM).....	2.11	1.32	2.50
(PPM-DRY).....	1.69	1.06	2.00
(PPM-WET).....	1.66	1.04	1.97
CH2O emission rate...(LB/HR)	0.46290	0.27777	0.54087

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 21
No. 2 Press Vent Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1 03-28-92	Run 2 03-28-92	Run 3 03-28-92
Date of run	03-28-92	03-28-92	03-28-92
Time run start/end.....(HRS)	830/ 940	1033/1136	1220/1324
Static pressure.....(IN.WC)	-0.12	-0.12	-0.12
Cross sectional area (SQ.FT)	21.48	21.48	21.48
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	4.0	3.0	-2.0
desiccant.....(GRAMS)	17.0	16.0	17.0
total.....(GRAMS)	21.0	19.0	15.0
Formaldehyde in sample..(uG)	700	820	750
Gas meter coefficient.....	1.0010	1.0010	1.0010
Barometric pressure..(IN.HG)	29.83	29.93	29.83
Avg. orif.pres.drop..(IN.WC)	1.93	1.83	1.91
Avg. gas meter temp..(DEF-F)	83.9	85.7	81.2
Volume through gas meter....			
at meter conditions...(CF)	46.49	45.72	46.10
standard conditions.(DSCF)	45.24	44.48	45.08
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.239	.239	.239
Avg.stack gas temp ..(DEG-F)	80	80	82
Volumetric flow rate.....			
actual.....(ACFM)	54964	53982	54839
dry standard.....(DSCFM)	52402	51778	52472
Isokinetic variation.....(%)	99.2	98.7	98.8
CH2O concentration.....			
(GR/DSCF).....	0.0002	0.0003	0.0003
(MG/DSCM).....	0.55	0.65	0.59
(PPM-DRY).....	0.44	0.52	0.47
(PPM-WET).....	0.43	0.51	0.46
CH2O emission rate...(LB/HR)	0.10771	0.12677	0.11596

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 24
No. 8 Exhaust Fan Vent Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1	Run 2	Run 3
Date of run	03-28-92	03-28-92	03-28-92
Time run start/end.....(HRS)	1416/1518	1600/1702	1742/1847
Static pressure.....(IN.WC)	-0.25	-0.25	-0.25
Cross sectional area (SQ.FT)	21.48	21.48	21.48
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	3.0	2.0	-2.0
desiccant.....(GRAMS)	16.0	10.0	10.0
total.....(GRAMS)	19.0	12.0	8.0
Formaldehyde in sample..(uG)	690	650	880
Gas meter coefficient.....	0.9991	0.9991	0.9991
Barometric pressure..(IN.HG)	29.83	29.83	29.83
Avg. orif.pres.drop..(IN.WC)	1.67	1.59	1.55
Avg. gas meter temp..(DEF-F)	77.9	76.7	78.2
Volume through gas meter....			
at meter conditions...(CF)	39.68	38.60	37.82
standard conditions.(DSCF)	38.94	37.96	37.08
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.239	.239	.239
Avg.stack gas temp ..(DEG-F)	74	73	73
Volumetric flow rate.....			
actual.....(ACFM)	46875	44594	44409
dry standard.....(DSCFM)	45156	43365	43426
Isokinetic variation.....(%)	99.1	100.6	98.2
CH2O concentration.....			
(GR/DSCF).....	0.0003	0.0003	0.0004
(MG/DSCM).....	0.63	0.61	0.84
(PPM-DRY).....	0.50	0.49	0.67
(PPM-WET).....	0.49	0.48	0.66
CH2O emission rate...(LB/HR)	0.10850	0.10122	0.13828

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value is less than or equal to the reported value

Test No. 1
No. 1 Dryer Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-24-92
Time of Determination.....(HRS)	848
Barometric pressure.....(IN.HG)	29.83
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	12
Shape of duct.....	Round
Stack diameter.....(IN)	48
Duct area.....(SQ.FT)	12.57
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.75
Avg. gas temp.....(DEG-F)	185
Moisture content.....(% V/V)	14.94
Avg. linear velocity.....(FT/SEC)	73.0
Gas density.....(LB/ACF)	.05791
Molecular weight.....(LB/LBMOLE)	29.02
Mass flow of gas.....(LB/HR)	191217
Volumetric flow rate.....	
actual.....(ACFM)	55034
dry standard.....(DSCFM)	38133

Test No. 2
No. 1 Dryer

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-24-92
Time of Determination.....(HRS)	848
Barometric pressure.....(IN.HG)	29.83
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	12
Shape of duct.....	Round
Stack diameter.....(IN)	48
Duct area.....(SQ.FT)	12.57
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.75
Avg. gas temp.....(DEG-F)	185
Moisture content.....(% V/V)	13.93
Avg. linear velocity.....(FT/SEC)	72.8
Gas density.....(LB/ACF)	.05827
Molecular weight.....(LB/LBMOLE)	29.09
Mass flow of gas.....(LB/HR)	191821
Volumetric flow rate.....	
actual.....(ACFM)	54861
dry standard.....(DSCFM)	38464

Test No. 4
No. 1 Dryer Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-24-92
Time of Determination.....(HRS)	848
Barometric pressure.....(IN.HG)	29.83
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	12
Shape of duct.....	Round
Stack diameter.....(IN)	48
Duct area.....(SQ.FT)	12.57
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.75
Avg. gas temp.....(DEG-F)	192
Moisture content.....(% V/V)	15.72
Avg. linear velocity.....(FT/SEC)	73.5
Gas density.....(LB/ACF)	.05715
Molecular weight.....(LB/LBMOLE)	29.04
Mass flow of gas.....(LB/HR)	190032
Volumetric flow rate.....	
actual.....(ACFM)	55419
dry standard.....(DSCFM)	37641

Test No. 5
No. 2A Dryer Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-25-92
Time of Determination.....(HRS)	830
Barometric pressure.....(IN.HG)	29.77
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	12
Shape of duct.....	Round
Stack diameter.....(IN)	29
Duct area.....(SQ.FT)	4.59
Direction of flow.....	UP
Static pressure.....(IN.WC)	-1.5
Avg. gas temp.....(DEG-F)	191
Moisture content.....(% V/V)	17.22
Avg. linear velocity.....(FT/SEC)	94.4
Gas density.....(LB/ACF)	.05698
Molecular weight.....(LB/LBMOLE)	29.20
Mass flow of gas.....(LB/HR)	88835
Volumetric flow rate.....	
actual.....(ACFM)	25985
dry standard.....(DSCFM)	17309

Test No. 6
No. 2B Dryer Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-25-92
Time of Determination.....(HRS)	400
Barometric pressure.....(IN.HG)	29.77
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	29
Duct area.....(SQ.FT)	4.59
Direction of flow.....	UP
Static pressure.....(IN.WC)	-1.3
Avg. gas temp.....(DEG-F)	198
Moisture content.....(% V/V)	16.14
Avg. linear velocity.....(FT/SEC)	91.4
Gas density.....(LB/ACF)	.05654
Molecular weight.....(LB/LBMOLE)	29.16
Mass flow of gas.....(LB/HR)	85343
Volumetric flow rate.....	
actual.....(ACFM)	25156
dry standard.....(DSCFM)	16788

Test No. 9
No. 2B Dryer Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-25-92
Time of Determination.....(HRS)	1500
Barometric pressure.....(IN.HG)	29.77
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	29
Duct area.....(SQ.FT)	4.59
Direction of flow.....	UP
Static pressure.....(IN.WC)	-1.3
Avg. gas temp.....(DEG-F)	199
Moisture content.....(% V/V)	16.06
Avg. linear velocity.....(FT/SEC)	91.4
Gas density.....(LB/ACF)	.05654
Molecular weight.....(LB/LBMOLE)	29.20
Mass flow of gas.....(LB/HR)	85361
Volumetric flow rate.....	
actual.....(ACFM)	25163
dry standard.....(DSCFM)	16785

Test No. 10
No. 3 Dryer Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-26-92
Time of Determination.....(HRS)	830
Barometric pressure.....(IN.HG)	29.82
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	12
Shape of duct.....	Round
Stack diameter.....(IN)	41.5
Duct area.....(SQ.FT)	9.39
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.7
Avg. gas temp.....(DEG-F)	204
Moisture content.....(% V/V)	11.76
Avg. linear velocity.....(FT/SEC)	80.6
Gas density.....(LB/ACF)	.05706
Molecular weight.....(LB/LBMOLE)	29.08
Mass flow of gas.....(LB/HR)	155595
Volumetric flow rate.....	
actual.....(ACFM)	45447
dry standard.....(DSCFM)	31726

Test No. 11
No. 3 Dryer Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-26-92
Time of Determination.....(HRS)	730
Barometric pressure.....(IN.HG)	29.82
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	20
Shape of duct.....	Round
Stack diameter.....(IN)	41.5
Duct area.....(SQ.FT)	9.39
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.68
Avg. gas temp.....(DEG-F)	205
Moisture content.....(% V/V)	11.87
Avg. linear velocity.....(FT/SEC)	74.0
Gas density.....(LB/ACF)	.05695
Molecular weight.....(LB/LBMOLE)	29.08
Mass flow of gas.....(LB/HR)	142462
Volumetric flow rate.....	
actual.....(ACFM)	41689
dry standard.....(DSCFM)	29026

Test No. 14
No. 4 Press Vent Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-27-92
Time of Determination.....(HRS)	830
Barometric pressure.....(IN.HG)	29.86
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	61.5
Duct area.....(SQ.FT)	20.63
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.12
Avg. gas temp.....(DEG-F)	82
Moisture content.....(% V/V)	0.54
Avg. linear velocity.....(FT/SEC)	39.5
Gas density.....(LB/ACF)	.07265
Molecular weight.....(LB/LBMOLE)	28.84
Mass flow of gas.....(LB/HR)	213206
Volumetric flow rate.....	
actual.....(ACFM)	48914
dry standard.....(DSCFM)	47286

Test No. 15
No. 4 Press Vent Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-27-92
Time of Determination.....(HRS)	900
Barometric pressure.....(IN.HG)	29.86
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	62.75
Duct area.....(SQ.FT)	21.48
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.12
Avg. gas temp.....(DEG-F)	99
Moisture content.....(% V/V)	1.33
Avg. linear velocity.....(FT/SEC)	44.1
Gas density.....(LB/ACF)	.06820
Molecular weight.....(LB/LBMOLE)	28.00
Mass flow of gas.....(LB/HR)	232533
Volumetric flow rate.....	
actual.....(ACFM)	56829
dry standard.....(DSCFM)	52842

Test No. 18
No. 3 Press Vent Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-27-92
Time of Determination.....(HRS)	1420
Barometric pressure.....(IN.HG)	29.86
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	62.75
Duct area.....(SQ.FT)	21.48
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.12
Avg. gas temp.....(DEG-F)	100
Moisture content.....(% V/V)	1.65
Avg. linear velocity.....(FT/SEC)	48.8
Gas density.....(LB/ACF)	.06800
Molecular weight.....(LB/LBMOLE)	28.00
Mass flow of gas.....(LB/HR)	256484
Volumetric flow rate.....	
actual.....(ACFM)	62867
dry standard.....(DSCFM)	58161

Test No. 20
No. 8 Exhaust Fan Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-28-92
Time of Determination.....(HRS)	800
Barometric pressure.....(IN.HG)	29.82
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	62.75
Duct area.....(SQ.FT)	21.48
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.25
Avg. gas temp.....(DEG-F)	72
Moisture content.....(% V/V)	1.78
Avg. linear velocity.....(FT/SEC)	32.7
Gas density.....(LB/ACF)	.07354
Molecular weight.....(LB/LBMOLE)	28.84
Mass flow of gas.....(LB/HR)	185675
Volumetric flow rate.....	
actual.....(ACFM)	42078
dry standard.....(DSCFM)	40857

Test No. 21
No. 2 Press Vent Stack

Results of Volumetric Flow Rate Determination-----Method 2


Date of Determination.....	03-28-92
Time of Determination.....(HRS)	830
Barometric pressure.....(IN.HG)	29.86
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	62.75
Duct area.....(SQ.FT)	21.48
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.12
Avg. gas temp.....(DEG-F)	84
Moisture content.....(% V/V)	2.14
Avg. linear velocity.....(FT/SEC)	41.9
Gas density.....(LB/ACF)	.06987
Molecular weight.....(LB/LBMOLE)	28.00
Mass flow of gas.....(LB/HR)	226435
Volumetric flow rate.....	
actual.....(ACFM)	54011
dry standard.....(DSCFM)	51182

Test No. 24
No. 8 Exhaust Fan Vent Stack


Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	03-28-92
Time of Determination.....(HRS)	1400
Barometric pressure.....(IN.HG)	29.83
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	62.75
Duct area.....(SQ.FT)	21.48
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.25
Avg. gas temp.....(DEG-F)	73
Moisture content.....(% V/V)	2.25
Avg. linear velocity.....(FT/SEC)	36.7
Gas density.....(LB/ACF)	.07119
Molecular weight.....(LB/LBMOLE)	28.00
Mass flow of gas.....(LB/HR)	202228
Volumetric flow rate.....	
actual.....(ACFM)	47343
dry standard.....(DSCFM)	45678

NO. 1 DRYER
L-P. CORRIGAN, TX




NO. 2 DRIVER
L-P CORRIGAN, TX




NOT TO SCALE

NO. 3 DRYER
L-P CORRIGAN, TX



NOT TO SCALE

PORTABLE PRESS VENT EXTENSION



NOTE: EXTENSION WAS APPROVED BY EPA

NOT TO SCALE

Job LOUISIANA PACIFIC (CONCRETE T.)

Test 1 Run# 1-3 Date 3/24/92


Dry bulb 187 °F Wet bulb 141 °F

Barometric pressure 29.83 in Hg

Static pressure - .75 in WC

Operators D. BRENNAN + B. ASCHENBACH

Pitot No. 24-4 Cp .84



Schematic of Cross Section

PM-10

TRAVERSE & CYCLONIC FLOW

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	6 in.	Time start: 848 hrs	
A	1	.044	2.112	8.112	0° .92 185
	2	.146	7.008	13.008	0° 1.30
	3	.296	14.208	20.208	0° 1.45 185
	4	.704	33.792	39.792	5° 1.40
	5	.854	40.992	46.992	5° 1.50 185
	6	.956	45.888	51.888	0° 1.30
B	1				0° .74 185
	2				0° 1.13
	3				5° 1.35 185
	4				0° 1.60
	5				0° 1.65 185
	6				5° 1.50
				Avg 1°	
Port C is 4' above level of ports A+B					
Temp. meas. tool & S/N: PDT 3					
				Time end: 900 hrs	

R or nothing= reg. manometer; F- expanded; E = electronic S-392.1

201A
INTERPOLL LABORATORIES EPA METHOD ~~505~~ SAMPLE LOG SHEET

Job LOUISIANA PACIFIC Date 3/24/92 Test 1 Run 1
 Source NO. 1 DRYER No. of traverse points 12
 Method 201A Filter holder: STAINLESS Filter type: 2.5" G.E.
Pm-10 STEEL

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: { .005 cfm at 7 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
5709 ☒ probe + nozzle
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D.B.

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	596	494	102.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1414	1404	10.0
Total			112.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 11 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 11 in. Hg.
 Time start: (0930) (HRS) Time end: (1117) (HRS)
 Sampling rate: 300 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

INTERPOLL LABORATORIES EPA METHOD 8 FIELD DATA SHEET

Sub	LOUISIANA - PACIFIC CAROLINA, TEXAS
Source	NO. 1 DAYER
Date	3/27/92 1981 RUN

Operator _____
Meter Box No. 3 ^{HP} 1.84 TR NE
Gometer Code. 9991

Pilot No. 24-4 CP 84
 Ser. Pres. 24-83 in H₂ 120 lb x
 Nozzle No. 4440-2 Nozzle Dia .150 in.

[illegible]

201A
INTERPOLL LABORATORIES EPA METHOD ~~505~~ SAMPLE LOG SHEET

Job LOUISIANA - PACIFIC (CORRIGAN, TEXAS) Date 3/24/92 Test 1 Run 2
 Source NO. 1 DRYER STACK No. of traverse points 12
 Method 201A Filter holder: STAINLESS Filter type: 2.5" 6.F.
 (PM-10) STEEL

Sample Train Leak Check:

Pretest: { .015 cfm at 15 in. Hg. (vac) ☒
 Posttest: .005 cfm at 5 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) ☒ acetone PROBE + NOZZLE WASH
S711 ☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D.B.

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	610	499	111.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1314	1307	7.0
Total			118.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 11 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 15 in. Hg.
 Time start: (1200) (HRS) Time end: (1335) (HRS)
 Sampling rate: 300 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 6

CF-023

INTERPOLLAB LABORATORIES EPA METHOD 5 FIELD DATA SHEET

JOB LOUISIANA - Pacific (Cameron, Tx)
 SOURCE NO. 1 DAYEA STAGE
 DATE 3/20/72 1981 1 RUN 2
 OPERATORS D. BRENNAN & B. ASCHEWEGH
 WATER BOX NO. 3 HP 190 TN NC
 GUNNATER CODE. 9991
 PITOT NO. 24-1 DP -84
 BAR. PRESS. 24.83 IN HG H2O 15 X
 NOZZLE NO. NO. 2 NOZZLE DID 250 IN.

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA - PACIFIC Date 3/24/92 Test 1 Run 3
 Source NO. 1 DRYER STACK No. of traverse points 12
 Method 201A Filter holder: STAINLESS Filter type: 2.5" G.F.
(m-10) STEEL

Sample Train Leak Check:

Pretest: .002 cfm at 15 in. Hg. (vac) ☒
 Posttest: .005 cfm at 5 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
(5708) ☒ other(s) PERC + NOZZLE
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	617	498	119.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1423	1414	9.0
Total			128.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 11 Bag No. 3
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 15 in. Hg.
 Time start: 1437 (HRS) Time end: 1607 (HRS)
 Sampling rate: 300 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 6

CF-023


INTERPOL LABORATORIES EPA METHOD 8 FIELD DATA SHEET

JOB _____
 SOURCE #061 DAYTON SPEC2 _____
 DATE 3/27/92 _____
 LOUISIANA - PACIFIC _____
 OPERATORS D. BOENWANT & ASCHENBACH _____
 WATER BOX NO. 3 _____
 COMPUTER CONF. 3 _____
 PITOT NO. 24-4 _____
 BAR. PRESS. 29.83 _____
 NOZZLE NO. PM-10 (2) _____
 IN. H₂O 14 _____
 IN. D₁₀ 1.50 _____
 C₁ 84 _____

[illegible]

INTERPOLL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX
Source No. 1 Dryer / Stack
Test 2 Run 0 Date 3-24-92
Stack dimen. 48 IN.
Dry bulb °F Wet bulb °F
Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 29.83 in Hg
Static pressure -1.75 in WC
Operators M. Kaehlen & C. Mosser
Pitot No. 29U-6-S Dp 84



Formaldehyde

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	6 in.	Time start: 0848 hrs	
A - 1	.044	2.11	8.11	.92	
2	.146	2.01	13.01	1.30	
3	.246	14.21	20.21	1.45	
4	.704	33.79	39.79	1.40	
5	.854	40.99	46.99	1.50	↑
6	.956	45.89	51.89	1.30	185
B - 1				.74	↓
2				1.13	
3				1.35	
4				1.60	
5				1.65	
6				1.50	
Port C x 4' above level of ports A & B					
Temp. meas. tool & S/N: PDT-3 / TC				Time end: hrs	

R or nothing= reg. manometer; S = expanded; E = electronic S-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-24-92 Test 2 Run 1
 Source No. 1 Dryer / Stack No. of traverse points 12
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 20.02 cfm at 5 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

NA ☐ acetone
☒ other(s) Me Cl₂

No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: Mikeahler & C. Masser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>703</u>	<u>599</u>	<u>104</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1392</u>	<u>1382</u>	<u>10</u>
Total			<u>114</u>

Integrated Gas Sampling Data:

Bag Pump No. B10 Box No. 30 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 0955 (HRS) Time end: 1100 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kaehler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

Job Louisiana Pacific / Corcoran, TX
Source No. 1 Dyer / Stack
Date 3-24-92 1991 2 RUN

Dyeaturs m. Kachler & Messer
 Motor Box No. 4 HP 1.75 IN DC
 Computer cost. 1.0000

Pilot No. 29V-6 Sp .04
Bar. Press. 29.83 in Hg H2D 13 X
Mozzle No. Glass Nozzle Dia 1.92 in.

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 1 Dryer / Stack
 Method DO 11 Filter holder: NA

Date 3-24-92 Test 2 Run 2
 No. of traverse points 12
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 20.02 cfm at 5 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)

☐ acetone
☒ other(s) MeCl₂

No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: M. Kaehler + C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	698	598	100
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1327	1315	12
Total			112

Integrated Gas Sampling Data:

Bag Pump No. 1310 Box No. 30 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 1200 (HRS) Time end: 1327 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kaehler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Sub Louisiana Pacific / Corrigan, TX
 Source Alvin Dwyer / Staff
 Date 3-24-92 1961 2 Run 2

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-24-92 Test 2 Run 3
 Source No. 1 Dwyer / Stack No. of traverse points 12
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: < 0.02 cfm at 5 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

NA ☐ acetone
☒ other(s) Me Cl₂

No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: M. Kaehler + C. Mosser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	717	597	120
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1402	1392	10
Total			130

Integrated Gas Sampling Data:

Bag Pump No. B10 Box No. 30 Bag No. 3
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 1403 (HRS) Time end: 1506 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kaehler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023


Job Louisiana Pacific / Corcoran, TX
 Supervisor No. 1 Dwyer / Stacey
 Date 3-24-92 1061 2 Run 3

Distributors
 Water Box No. 4 HP 1.75 IN NC
 Cooperator Code: 10010

Pitot No. 290-6 Cp .8%
 Bar. Press. 29.83 in Hg H₂O 13.2 X
 Nozzle No. Class NDX10 D. 0 180 IN.

[illegible]

Job LOUISIANA PACIFIC
Source NO. 1 DRYER STACK
Test 4 Runs 1-3 Date 3/24/92
Stack dimen. 48" IN.
Dry bulb °F Wet bulb °F
Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 29.83 in Hg
Static pressure - .75 in WC
Operators M. KOELLER + D. BRENNON
Pitot No. 29-65 Cp .84



Particulars

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	6 in.	Time start: 0848 hrs	
A	1	.1044	2.11	8.11	.93
	2	.196	2.01	13.01	1.30
	3	.296	14.21	20.21	1.45
	4	.704	33.79	39.79	1.40
	5	.854	40.99	46.99	1.50
	6	.956	45.89	51.89	1.30
B	1				71
	2				1.13
	3				1.35
	4				1.60
	5				1.65
	6				1.50
Port C is 4' above level of ports A & B					
Temp. meas. tool & S/N: PDT-191TC					
				Time end:	hrs

R or nothing= reg. manometer; S= expanded; E = electronic

S-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA- PACIFIC Date 3/24/72 Test 4 Run 1
 Source NO. 1 DRYER STACK No. of traverse points 12
 Method 5 Filter holder: GLASS Filter type: Y⁶ G.F.

Sample Train Leak Check:

Pretest: ^{.005} (0.02 cfm at 17 in. Hg. (vac) 
 Posttest: .00 cfm at 6 in. Hg. (vac) 

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s):
4040  acetone PROBE + NOZZLE
 other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: M.K.

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	600	487	113.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1410	1402	8.0
Total			121.0

Integrated Gas Sampling Data:

Bag Pump No. 8-10 Box No. 2 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 16 in. Hg.
 Time start: 1610 (HRS) Time end: 1712 (HRS)
 Sampling rate: 300 cc/min Operator: M.K. + D.B.
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

Sub Louisiana Pacific / Corrigan, TX
 Source Mr. Dryer / Staff
 Date 3-24-97 1081 4 RUN 1

Operators M. Kachler & C. Mosser
 Water Box No. 4 HP 1175 IN TC
 Computer conf. 1.0010

Pilot No. 29V-6 Cp 34
Bar. Press. 24.83 inHg H₂O 13.5 x
Nozzle No. 6-3 Nozzle Dia. 1/8 in.

[illegible]

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA-PACIFIC Date 3/24/92 Test 4 Run 2
 Source NO. 1 DRYER-STACK No. of traverse points 12
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: .002 cfm at 8 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
4119 ☒ other(s) probe + nozzle
 No. of probe wash bottles: 1
 Sample recovered by: M.K.

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	603	490	113.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1323	1314	9.0
Total			122.0

Integrated Gas Sampling Data:

Bag Pump No. B-10 Box No. 2 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 16 in. Hg.
 Time start: 1735 (HRS) Time end: 1838 (HRS)
 Sampling rate: 400 cc/min Operator: D.B. + M.K.
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA - PACIFIC Date 3/24/92 Test 4 Run 3
 Source NG-1 DRYER STALK No. of traverse points 12
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: .000 cfm at 9 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
4120 ☒ acetone probe + nozzle
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: M.K.

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>612</u>	<u>490</u>	<u>122.0</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1420</u>	<u>1410</u>	<u>10.0</u>
Total			<u>132.0</u>

Integrated Gas Sampling Data:

Bag Pump No. B-10 Box No. 2 Bag No. 3
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 15 in. Hg.
 Time start: 1900 (HRS) Time end: 2002 (HRS)
 Sampling rate: 400 cc/min Operator: D.B. + M.K.
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

Job WISCONSIA-PACIFIC (CIRCLE W), TEXAS
 Equip NO. 1 DRYER STACK
 Date 5/24/42 1942 4 RUN 3

Operators M. KERNER & D. BERNDT
 Meter Box No. 4 HP 1-25 IN NE
 Computer cost. 1,000


Put in
Box. Please
Return

29-65
29-83
8-3 NO 12 19 61
CP 1004 120
8-4

[illegible]

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job LOUISIANA PACIFIC (CORPUS, TX.)
 Source NO. 2A DRYER STACK
 Test 5 Run# 1-3 Date 3/25/72
 Stack dimen. 29" IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.77 in Hg
 Static pressure -1.5 in WC
 Operators D. BRENNAN & B. ASCHENBACH
 Pitot No. 24-4 (PMP) Cp .84



PM-10

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
Port length: <u>6</u> in.				Time start: <u>830</u> hrs	
A	1	.044	1.276	7.276	1.70 183
	2	.146	4.234	10.234	2.20
	3	.292	8.584	14.584	2.15 184
	4	.704	20.416	26.416	2.60
	5	.854	24.766	30.766	2.50 184
	6	.956	27.724	33.724	2.35
B	1				1.70 195
	2				1.85
	3				2.15 199
	4				2.35
	5				2.20 198
	6				2.25 2.15
port C $\approx$ 2' below level of ports A+B					
Temp. meas. tool & S/N: <u>PDT-23</u>				Time end: <u>850</u> hrs	

R or nothing = reg. manometer; S = expanded; E = electronic S-392.1
 C-22

201A
INTERPOLL LABORATORIES EPA METHOD ~~301~~ SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORRIGAN, TX.) Date 3/25/92 Test 5 Run 1
 Source NO. 2A DRYER No. of traverse points 12
 Method 201A Filter holder: STAINLESS Filter type: 2.5" G.F.
STEEL

Sample Train Leak Check:

Pretest: (0.02 cfm at 10 in. Hg. (vac)
 Posttest: .002 cfm at 5 in. Hg. (vac)

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
5635 ☒ acetone probe
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	625	499	126.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1354	1347	7.0
Total			133.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 14 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 15 in. Hg.
 Time start: (0930) (HRS) Time end: (1101) (HRS)
 Sampling rate: 300 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131 132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147 148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163 164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000 1001 1002 1003 1004 1005 1006 1007 1008 1009 1010 1011 1012 1013 1014 1015 1016 1017 1018 1019 1020 1021 1022 1023 1024 1025 1026 1027 1028 1029 1030 1031 1032 1033 1034 1035 1036 1037 1038 1039 1040 1041 1042 1043 1044 10

434

43

20. 5725

USIA
-A-
147

2nd

194
238
P1

5170

$$\frac{12}{12} \frac{12}{12} \frac{12}{12}$$

117

12621

111
Tx

১০	১১	১২	১৩	১৪	১৫	১৬	১৭	১৮	১৯	২০	২১	২২	২৩	২৪	২৫	২৬	২৭	২৮	২৯	৩০	৩১	৩২	৩৩	৩৪	৩৫	৩৬	৩৭	৩৮	৩৯	৪০	৪১	৪২	৪৩	৪৪	৪৫	৪৬	৪৭	৪৮	৪৯	৫০	৫১	৫২	৫৩	৫৪	৫৫	৫৬	৫৭	৫৮	৫৯	৬০	৬১	৬২	৬৩	৬৪	৬৫	৬৬	৬৭	৬৮	৬৯	৭০	৭১	৭২	৭৩	৭৪	৭৫	৭৬	৭৭	৭৮	৭৯	৮০	৮১	৮২	৮৩	৮৪	৮৫	৮৬	৮৭	৮৮	৮৯	৯০	৯১	৯২	৯৩	৯৪	৯৫	৯৬	৯৭	৯৮	৯৯
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

100

403
411
X

11

2511

24/10/99

15. 1. 95

78
75

11

1
2
3

01-10-2017

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

10. 11. 1950

107

25 Nov

11-12-13-14-15-16-17-18-19-20-21-22-23-24-25-26-27-28-29-30-31-32-33-34-35-36-37-38-39-40-41-42-43-44-45-46-47-48-49-50-51-52-53-54-55-56-57-58-59-60-61-62-63-64-65-66-67-68-69-70-71-72-73-74-75-76-77-78-79-80-81-82-83-84-85-86-87-88-89-90-91-92-93-94-95-96-97-98-99-100-101-102-103-104-105-106-107-108-109-110-111-112-113-114-115-116-117-118-119-120-121-122-123-124-125-126-127-128-129-130-131-132-133-134-135-136-137-138-139-140-141-142-143-144-145-146-147-148-149-150-151-152-153-154-155-156-157-158-159-160-161-162-163-164-165-166-167-168-169-170-171-172-173-174-175-176-177-178-179-180-181-182-183-184-185-186-187-188-189-190-191-192-193-194-195-196-197-198-199-200-201-202-203-204-205-206-207-208-209-210-211-212-213-214-215-216-217-218-219-220-221-222-223-224-225-226-227-228-229-230-231-232-233-234-235-236-237-238-239-240-241-242-243-244-245-246-247-248-249-250-251-252-253-254-255-256-257-258-259-260-261-262-263-264-265-266-267-268-269-270-271-272-273-274-275-276-277-278-279-280-281-282-283-284-285-286-287-288-289-290-291-292-293-294-295-296-297-298-299-300-301-302-303-304-305-306-307-308-309-310-311-312-313-314-315-316-317-318-319-320-321-322-323-324-325-326-327-328-329-330-331-332-333-334-335-336-337-338-339-340-341-342-343-344-345-346-347-348-349-350-351-352-353-354-355-356-357-358-359-360-361-362-363-364-365-366-367-368-369-370-371-372-373-374-375-376-377-378-379-380-381-382-383-384-385-386-387-388-389-390-391-392-393-394-395-396-397-398-399-400-401-402-403-404-405-406-407-408-409-410-411-412-413-414-415-416-417-418-419-420-421-422-423-424-425-426-427-428-429-430-431-432-433-434-435-436-437-438-439-440-441-442-443-444-445-446-447-448-449-450-451-452-453-454-455-456-457-458-459-460-461-462-463-464-465-466-467-468-469-470-471-472-473-474-475-476-477-478-479-480-481-482-483-484-485-486-487-488-489-490-491-492-493-494-495-496-497-498-499-500-501-502-503-504-505-506-507-508-509-510-511-512-513-514-515-516-517-518-519-520-521-522-523-524-525-526-527-528-529-530-531-532-533-534-535-536-537-538-539-540-541-542-543-544-545-546-547-548-549-550-551-552-553-554-555-556-557-558-559-560-561-562-563-564-565-566-567-568-569-570-571-572-573-574-575-576-577-578-579-580-581-582-583-584-585-586-587-588-589-590-591-592-593-594-595-596-597-598-599-600-601-602-603-604-605-606-607-608-609-610-611-612-613-614-615-616-617-618-619-620-621-622-623-624-625-626-627-628-629-630-631-632-633-634-635-636-637-638-639-640-641-642-643-644-645-646-647-648-649-650-651-652-653-654-655-656-657-658-659-660-661-662-663-664-665-666-667-668-669-670-671-672-673-674-675-676-677-678-679-680-681-682-683-684-685-686-687-688-689-690-691-692-693-694-695-696-697-698-699-700-701-702-703-704-705-706-707-708-709-710-711-712-713-714-715-716-717-718-719-720-721-722-723-724-725-726-727-728-729-730-731-732-733-734-735-736-737-738-739-740-741-742-743-744-745-746-747-748-749-750-751-752-753-754-755-756-757-758-759-760-761-762-763-764-765-766-767-768-769-770-771-772-773-774-775-776-777-778-779-780-781-782-783-784-785-786-787-788-789-790-791-792-793-794-795-796-797-798-799-800-801-802-803-804-805-806-807-808-809-810-811-812-813-814-815-816-817-818-819-820-821-822-823-824-825-826-827-828-829-830-831-832-833-834-835-836-837-838-839-840-841-842-843-844-845-846-847-848-849-850-851-852-853-854-855-856-857-858-859-860-861-862-863-864-865-866-867-868-869-870-871-872-873-874-875-876-877-878-879-880-881-882-883-884-885-886-887-888-889-890-891-892-893-894-895-896-897-898-899-900-901-902-903-904-905-906-907-908-909-910-911-912-913-914-915-916-917-918-919-920-921-922-923-924-925-926-927-928-929-930-931-932-933-934-935-936-937-938-939-940-941-942-943-944-945-946-947-948-949-950-951-952-953-954-955-956-957-958-959-960-961-962-963-964-965-966-967-968-969-970-971-972-973-974-975-976-977-978-979-980-981-982-983-984-985-986-987-988-989-990-991-992-993-994-995-996-997-998-999-1000-1001-1002-1003-1004-1005-1006-1007-1008-1009-1010-1011-1012-1013-1014-1015-1016-1017-1018-1019-1020-1021-1022-1023-1024-1025-1026-1027-1028-1029-1030-1031-1032-1033-1034-1035-1036-1037-1038-1039-1040-1041-1042-1043-1044-10

Hg D₁

02H

$$\frac{15}{131}$$

11

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drift Meter (inH ₂ O)	Dis. Vol. (cf)	VAC. inHg	Temperature (°F)						Oxigen (xv/v)
							Stack	Probe	Dry	Wet	Gas In	Gas Out	
A-	6	85.30	2.45	.43	7.50	1.0	198	210	255	46	71	71	18.1
	5	91.05	2.60	.44	7.89	1.0	200	212	253	45	75	73	18.0
	4	96.93	2.60	.44	7.89	1.5	200	216	260	42	78	74	18.0
	3	99.37	1.80	.44	6.57	1.5	200	217	261	42	80	76	18.1
	2	101.87	1.90	.44	6.75	1.5	198	217	263	42	82	77	18.2
	1	104.273	1.75	.44	6.48	1.5	196	219	265	42	83	78	18.0
B-	6	106.68	1.75	.44	6.48	1.5	200	251	262	40	78	78	18.1
	5	109.18	1.90	.44	6.75	1.5	199	250	260	40	86	81	17.9
	4	111.81	2.05	.44	7.01	2.0	198	259	252	46	87	82	17.9
	3	114.55	2.25	.44	7.34	2.0	198	261	250	47	88	83	17.9
	2	117.18	2.10	.44	7.09	2.0	197	246	250	49	89	84	17.8
	1	119.642	1.80	.44	6.57	2.0	196	240	248	49	90	84	17.7
(1101)													
$\theta = 84.37^\circ$ $V_0 = 31.342$ $AV_0 = 86.3$													

201A
INTERPOLL LABORATORIES EPA METHOD ~~541~~7 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORRIGAN, TX) Date 3/25/92 Test 5 Run 2
 Source NO. 2A DRYER STACK No. of traverse points 12
 Method 201A Filter holder: STAINLESS Filter type: 2.5" 6.7
STEEL

Sample Train Leak Check:

Pretest: .00 cfm at 10 in. Hg. (vac)
 Posttest: .000 cfm at 6 in. Hg. (vac)

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone FRONT HALF
(5637)
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	616	495	121.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1402	1393	9.0
Total			130.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 14 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 15 in. Hg.
 Time start: 1145 (HRS) Time end: 1316 (HRS)
 Sampling rate: 300 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

JOB _____
 SOURCE# NO 2A
 DATE 3/23/92

LOUISIANA - PACIFIC (CARBON TX.)
 NO 2A
 3/23/92

RUN 2
 RUN 2

JAN 1968

D. BAERMAN + B. ASCHENBERG

Pittet Hb.
Bar. Press
No. 10 No.

24-4 CP 84 H2
29.77 10 H4
P440 (1) NO 11 16 D 12

137
167
187

[illegible]

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC Date 3/25/92 Test 5 Run 3
 Source NO. 2A DRYER STACK No. of traverse points 12
 Method 201A Filter holder: STAINLESS Filter type: 2.5" G.F.
STEEL

Sample Train Leak Check:

Pretest: .012 cfm at 15 in. Hg. (vac) 書
 Posttest: .002 cfm at 6 in. Hg. (vac) 書

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone FRONT HALF
(5647) ☒ acetone FRONT HALF
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	621	497	124.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1407	1396	11.0
Total			135.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 14 Bag No. 3
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 16 in. Hg.
 Time start: 1345 (HRS) Time end: 1523 (HRS)
 Sampling rate: 300 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

JOB LOUISIANA PACIFIC (CORRELATION, T₂)
 SOURCE NO. 2A DRYER STACK
 DATE 3/23/92 1992 3 RUN 3

Operators D. Baernwald & B. Aschwald Bldg.
Meter Box No. 3 ^{CH} 186 IN NE
Comester cost. 999

Pitot No.	24.4	Ep	84
Ser. Press.	29.7	in Hg	H ₂ O 14 x
Nozzle No.	44-8	Nozzle Dia	.37 in.

[illegible]

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX

Source No. 2B Dryer / Stack

Test 6 Run 0 Date 3-25-92

Stack dimen. 29 IN.

Dry bulb °F Wet bulb °F


Manometer: ☒ Reg. ☐ Exp. ☐ Elec.

Barometric pressure 29.77 in Hg

Static pressure -1.30 in WC

Operators M. Kachler & C. Mosser

Pitot No. 29V-6 Cp .84



Schematic of Cross Section

Formaldehyde

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>6</u> in.		Time start: <u>0900</u> hrs	
A-1	.021	0.61/1	6.61/7.00	1.61	
2	.067	1.94	7.94	1.90	
3	.118	3.42	9.42	1.95	
4	.177	5.13	11.13	2.21	
5	.250	7.25	13.25	2.33	
6	.356	10.32	16.32	2.58	198
7	.644	18.68	24.68	2.75	
8	.750	21.75	27.75	2.59	
9	.923	23.97	29.87	2.25	
10	.982	25.58	31.58	1.90	
11	.933	27.06	33.06	1.85	
12	.979	28.39/28.00	34.39/34.00	1.60	
B-1				1.17	
2				1.55	
3				2.10	
4				2.22	
5				2.27	198
6				2.42	
7				2.70	
8				2.25	
9				2.23	
10				1.90	
11				1.60	
12				.98	

Temp. meas. tool & S/N: PDT-3 / TC

Time end: hrs

R or nothing = reg. manometer; S = expanded; E = electronic

9-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Cuccigan, TX Date 3-15-92 Test 6 Run 1
 Source No. 2 B. Dryer / Stack No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 15 in. Hg. (vac) ☒

Particulate Catch Data:

No. of filters used: NA Recovery solvent(s):
☐ acetone
☒ other(s) MeCl₂
 No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: M. Kachler & C. Mosser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	759	598	161
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1340	1327	13
Total			174

Integrated Gas Sampling Data:

Bag Pump No. 1310 Box No. 2 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 0930 (HRS) Time end: 1034 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kachler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX Operator M. Kaehler & C. Mosser Pitot No. 290-6 Cp 84
 Source W. B. Dwyer / Stack Meter Box No. 1001 Bar. Press. 29.77 in Hg 25 x
 Date 3-25-82 Gas meter coeff. 1.0010 Nozzle No. 6355 Nozzle Dia. 1.98 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inHG)	Drifts Meter (inHG)	Des. Vol. (cf)	VAC. (inHg)	Temperatures (°F)						Oxygen (xv/v)
							Stack	Probe	Dry	Wet	Gas In	Gas/Dut	
B-12	2.5	927.60	1.65	1.32	9.23	4	191	243	256	46	68	68	18.0
11	5	930.85	1.60	1.27	0.93	4	195			46	70	68	17.9
10	7.5	932.61	2.05	1.63	2.64	5	198	249	252	48	72	69	17.8
9	10	934.67	2.45	1.94	4.62	6	199				75	70	17.6
8	12.5	936.63	2.63	2.10	6.68	7	198	255	254	48	77	71	17.7
7	15	938.72	2.82	2.26	8.82	8	198				79	72	17.7
6	17.5	940.75	2.50	2.01	0.84	7.5	198	253	254	48	80	73	17.7
5	20	942.68	2.13	1.71	2.71	7	198				81	73	17.6
4	22.5	944.35	1.80	1.45	4.43	6	198	245	258	46	82	74	17.8
3	25	946.03	1.58	1.27	6.05	6	198				83	75	17.8
2	27.5	947.32	.95	.77	7.31	4	197	248	255	46	83	75	17.8
1	30	948.47	.81	.65	8.47	3.5	197				84	76	17.8
A-12	32.5	950.14	1.61	1.30	0.11	7	198	249	258	47	80	75	17.5
11	35	951.86	1.95	1.57	1.90	7	197				85	77	17.5
10	37.5	953.64	1.92	1.56	3.69	7.5	198	253	255	47	86	78	17.7
9	40	955.57	2.26	1.84	5.64	10	198				87	78	17.7
8	42.5	957.59	2.48	2.02	7.68	11	198	250	259	48	88	79	17.8
7	45	959.75	2.77	2.26	9.84	12.5	198				88	79	17.7
6	47.5	961.88	2.62	2.13	1.93	12.5	198	247	255	48	88	80	17.6
5	50	963.89	2.33	1.90	3.42	12	198				88	80	17.5
4	52.5	965.83	2.21	1.80	5.85	10	198	249	258	48	88	81	17.5
3	55	967.71	1.95	1.59	7.67	7	197				88	81	17.3
2	57.5	969.47	1.90	1.55	9.46	6	197	252	260	48	89	81	17.4
1	60	971.02	1.61	1.32	1.11	5.5	197				90	82	17.4
(1034)													
Σ = 60		43.52	14.63								Avg. = 78.0		

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-25-92 Test 6 Run 2
 Source No. 2 B Dryer / Stack No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 2.002 cfm at 17 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

NA ☐ acetone
☒ other(s) MeCl₂

No. of ^{Emp} wash bottles: 1
 Sample recovered by: M. Kaehler & C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>750</u>	<u>597</u>	<u>153</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1357</u>	<u>1340</u>	<u>17</u>
Total			<u>170</u>

Integrated Gas Sampling Data:

Bag Pump No. 1310 Box No. 6 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 11:5 (HRS) Time end: 12:18 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kaehler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX Operator W. S. Gable Pict No. 29U-6 Cp BY
 Source Wabash Dryer Motor Box No. 1-25 IN NO 29.77 inHg 16.1 X
 Date 3-25-92 Run 2 Gasometer const. 1.0010 Nozzle No. 6033 Nozzle Dia. 9.5 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Orifice Meter (inWC)	Des. Vol. (cf)	VAD. (inHg)	Temperature (°F)						Oxygen (xv/v)
							Stack	Probe	Duct	Inlet	Gas/Duct		
A-12	(1115)	971.40	1.40	1.11	2.91	4.5	197	248	254	54	80	17.6	
11	5	972.82	1.25	1.39	4.59	7	198				82	17.2	
10	7.5	974.52	2.10	1.67	6.45	6	198	250	257	52	84	17.3	
9	10	976.41	2.29	1.82	8.38	7	199				86	17.4	
8	12.5	978.32	2.57	2.04	10.44	9	200	246	259	51	88	17.4	
7	15	980.37	2.70	2.16	12.55	9.5	199				89	17.4	
6	17.5	982.46	2.51	2.00	14.59	9	200	247	258	51	89	17.4	
5	20	984.55	2.28	1.82	16.54	8	199				90	17.4	
4	22.5	986.47	2.19	1.75	18.45	8	199	250	255	52	91	17.3	
3	25	988.42	1.90	1.53	20.23	8	197				91	17.3	
2	27.5	990.15	1.50	1.21	21.82	6	196	246	253	52	92	17.6	
1	30	991.80	1.20	.97	23.24	5	197				92	17.6	
B-12	31.5	993.27	1.33	1.07	24.74	5	199	245	256	50	89	17.7	
11	35	996.42	1.77	1.42	26.46	7	199				91	17.2	
10	37.5	998.37	2.18	1.75	28.37	9	199	248	260	50	92	17.1	
9	40	1000.37	2.45	1.96	30.39	12	200				92	17.1	
8	42.5	1002.47	2.70	2.16	32.52	14	200	249	258	49	92	17.2	
7	45	1004.52	2.81	2.25	34.68	15	200				91	17.4	
6	47.5	1006.55	2.40	1.92	36.69	14	200	242	255	49	90	17.2	
5	50	1008.46	2.18	1.75	38.59	12	200				89	17.2	
4	52.5	1010.37	2.00	1.60	40.42	13	200	245	257	49	89	17.1	
3	55	1012.10	1.83	1.46	42.16	12	200				89	17.0	
2	57.5	1013.77	1.48	1.19	43.74	9	199	247	260	50	91	17.1	
1	60	1015.24	1.20	.97	45.16	6	198				92	17.1	
	(1218)												
Σ =		44.84		4.62							avg. =	86.5	

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-25-92 Test 6 Run 3
 Source No. 2 B Dryer / Stack No. of traverse points LV
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 20.02 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s) ☐ acetone
☒ other(s) MeCl₂
 No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: McKaepler & C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>263</u>	<u>597</u>	<u>166</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1373</u>	<u>1354</u>	<u>19</u>
Total			<u>185</u>

Integrated Gas Sampling Data:

Bag Pump No. B10 Box No. 6 Bag No. 3
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 1255 (HRS) Time end: 1401 (HRS)
 Sampling rate: 400 cc/min Operator: McKaepler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023


INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Cossayan, TX Operator M. Kaeberle & C. Mosser Pilot No. 290-6 Cp BY
 Source Way 25 Dyer / Street Meter Box No. 4 HA 1.25 IN DC Bar. Press. 29.77 inHg H₂O 25.9 K
 Date 3-25-82 Test 6 Run 3 Coefficient 1.0010 Nozzle No. Glass Nozzle Dia. 1/8 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Orifice Meter (inH ₂ O)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)				Dye	Gas In	Gas Out	Oxygen (xv/v)
							Stack	Probe	Dye	Impq.				
B-12	(1255) 2.5	15.60	1.30	1.05	7.07	3	198	241	256	48		82	82	12.8
11	5	17.10	1.78	1.42	8.79	4	198					85	83	17.1
10	2.5	20.62	2.10	1.68	0.65	4	199	247	258	48		87	84	17.0
9	10	22.62	2.43	1.95	2.66	5	198					84	84	17.0
8	12.5	24.72	2.72	2.19	4.79	6	198	249	257	48		91	85	16.8
7	15	26.95	2.87	2.31	6.99	6.5	198					92	86	17.1
6	12.5	29.05	2.61	2.11	9.09	6	198	245	259	49		94	87	17.1
5	20	31.03	2.31	1.87	1.07	6	198					95	87	16.8
4	22.5	32.92	1.89	1.54	2.86	4.5	197	248	262	50		95	87	16.9
3	25	34.62	1.63	1.32	4.53	4	197					95	87	17.0
2	27.5	35.92	1.07	.87	5.88	3	197	246	260	50		95	87	16.9
1	30	37.30	1.03	.84	7.21	3	197					95	88	16.9
A-12	32.5	39.04	1.98	1.61	9.05	4.5	197	243	258	48		94	88	17.0
11	35	40.83	1.92	1.48	0.81	4.5	197					95	88	17.4
10	32.5	42.80	2.15	1.75	2.72	5	198	247	260	48		96	89	17.2
9	40	44.25	1.35	1.91	4.73	5.5	197					97	89	17.1
8	42.5	46.82	2.63	2.14	6.85	6	198	251	263	49		98	89	17.2
7	45	49.10	2.85	2.32	9.06	7	198					98	90	17.2
6	47.5	51.20	2.67	2.18	1.20	6	198	249	263	51		98	90	17.3
5	50	53.21	2.37	1.93	3.22	6	198					98	90	17.2
4	52.5	55.18	2.13	1.74	5.13	5.5	198	247	261	51		98	90	17.2
3	55	56.97	1.91	1.56	6.95	5	197					98	90	17.2
2	57.5	58.68	1.64	1.32	8.62	4	197	249	261	49		98	90	17.2
1	60	60.22	1.41	1.15	0.18	4	197					98	91	17.2
	(1401) 60													
		V _m = 44.62		ΔH 1.68									Avg. = 90.8	

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job LOUISIANA PACIFIC
 Source NO. 2A DRYER STACK
 Test 8 Runs 1-2 Date 3/25/92
 Stack dimen. 29" IN.
 Dry bulb _____ °F Wet bulb _____ °F
 Manometer: ☐ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.77 in Hg
 Static pressure -1.5 in WC
 Operators D. BRENNON & B. ASCHENBACH
 Pitot No. 24-4 Cp .84



Particulate

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	in.	Time start:	hrs
A	1				
	2				
	3				
	4				
	5				
	6				
	7				
	8				
	9				
	10				
	11				
	12				
B	1				
	2				
	3				
	4				
	5				
	6				
	7				
	8				
	9				
	10				
	11				
	12				
Temp. meas. tool & S/N:				Time end:	hrs

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC Date 3/25/92 Test 8 Run 1
 Source NO. 2A DRYER STEEL No. of traverse points
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: ^{.006} ~~0.02~~ cfm at 15 in. Hg. (vac) ☒
 Posttest: .005 cfm at 6 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone FRONT HALF
4123 ☒ other(s)
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	630	496	134.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1410	1401	9.0
Total			143.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 30 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 00 cc/min at 16 in. Hg.
 Time start: 1615 (HRS) Time end: 1717 (HRS)
 Sampling rate: 400 cc/min Operator: D.B.
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA PACIFIC (Continued)
 Source NO. 2A PLYING STAIR
 Date 3/25/92 1992 8 Run 1

Operator D. BOZEMAN
 Water Box No. 3
 Gas meter count. 941

Pitot No. 24-4 (6005)
 Sur. Press. 29.7 in Hg
 Nozzle No. 8-3 Nozzle Dia. 1/32 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Drifted Water (in H ₂ O)	Dep. Vol. (cf)	VAC. in Hg	Temperature (°F)					Oxygen (xv/v)
							Stack	Probe	Duct	Inlet	Gas/Out	
A-12	(1615) 2.5	188.100	1.95	1.48	9.79	4.0	200	269	254	48	84	18.3
"	5.0	189.81	2.10	1.58	1.53	4.5	200				87	18.3
"	7.5	191.54	2.20	1.66	3.31	5.0	201	240	255	47	88	18.1
"	10.0	193.34	2.35	1.77	5.16	5.0	201				89	18.2
"	12.5	195.17	2.35	1.77	7.01	5.0	201	267	255	47	90	18.1
"	15.0	198.81	2.30	1.74	8.84	5.0	201				91	18.2
"	17.5	200.57	2.00	1.51	6.55	5.0	201	261	256	44	91	18.0
"	20.0	202.28	1.95	1.47	2.24	4.5	203				91	18.3
"	22.5	203.89	1.85	1.40	3.88	4.0	203	260	265	44	92	18.4
"	25.0	205.48	1.70	1.29	5.46	4.0	202				92	18.4
"	27.5	206.96	1.45	1.10	6.92	3.5	201	258	265	43	92	18.3
"	30.0	208.109	.89	.68	8.07	2.0	198				92	18.2
B-12	32.5	209.62	1.55	1.18	9.58	4.0	200	257	267	43	92	18.3
"	35.0	211.24	1.75	1.33	1.19	4.0	202				93	17.9
"	37.5	212.90	1.90	1.44	2.86	4.5	202	260	270	43	93	18.0
"	40.0	214.65	2.10	1.60	4.62	5.0	201				93	18.1
"	42.5	216.41	2.15	1.63	6.40	5.0	201	249	260	45	94	18.2
"	45.0	218.17	2.15	1.64	8.18	5.0	201				94	18.0
"	47.5	219.92	2.10	1.60	9.94	5.0	200	251	262	45	94	18.0
"	50.0	221.63	1.95	1.48	1.64	5.0	201				94	18.0
"	52.5	223.24	1.70	1.29	3.22	4.0	202	253	270	48	93	17.9
"	55.0	224.73	1.45	1.10	4.69	3.5	201				94	17.9
"	57.5	225.99	1.10	.84	5.96	3.0	200	255	268	48	93	17.9
"	60.0	227.134	.93	.71	7.14	2.5	200				93	17.8
	(1717)											
	P = 60	V _s = 39.034		ΔH 1.39							Av _g = 89.4	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC Date 3/25/92 Test 8 Run 2
 Source NO. 2A DRYER STACK No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: .005 cfm at 15 in. Hg. (vac) ☒
 Posttest: .005 cfm at 7 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) ☒ acetone FRONT HALF
4124 ☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	244	497	147.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1423	1407	16.0
Total			163.0


Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 30 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: -00 cc/min at 16 in. Hg.
 Time start: 1825 (HRS) Time end: 1927 (HRS)
 Sampling rate: 400 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 2B Dryer / Stack
 Test 9 Run 0 Date 3-25-92
 Stack dimen. 29 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.77 in Hg
 Static pressure -1.30 in WC
 Operators M. Kaehler & C. Mosser
 Pitot No. 29V-4 Cp .84



Portulato 1202 Back-half

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>6</u> in.		Time start: <u>1500</u> hrs	
A-1	.021	0.61/1	6.61/17	1.60	
2	.067	1.94	7.94	1.85	
3	.118	3.42	9.42	1.93	
4	.177	5.13	11.13	2.25	
5	.250	7.25	13.25	2.41	
6	.356	10.32	16.32	2.55	
7	.644	18.68	24.68	2.73	
8	.750	21.75	27.75	2.78	
9	.823	23.87	29.87	2.27	↑
10	.882	25.58	31.58	1.87	199
11	.933	27.06	33.06	1.87	
12	.979	28.34/28.00	34.34/34.00	1.55	↓
B-1				1.20	
2				1.50	
3				2.00	
4				2.19	
5				2.23	
6				2.40	
7				2.71	
8				2.21	
9				2.20	
10				1.85	
11				1.77	
12				1.00	
Temp. meas. tool & S/N: <u>PDT-19/TC</u>				Time end: <u> </u> hrs	

R or nothing = reg. manometer; S = expanded; E = electronic S-392.1

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-25-92 Test 9 Run 1
 Source No. 2B Dryer / Stach No. of traverse points 24
 Method 5 Filter holder: 4" Glass Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 2.02 cfm at 11 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

4122 ☒ acetone
☒ other(s) Me Cl₂

No. of probe wash bottles: 1
 Sample recovered by: M. Kaehler & C. Mosser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>641</u>	<u>494</u>	<u>147</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1340</u>	<u>1324</u>	<u>16</u>
Total			<u>163</u>

Integrated Gas Sampling Data:

Bag Pump No. B10 Box No. 4 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 1510 (HRS) Time end: 1612 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kaehler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX
 Source W. 20 Drift / Stack
 Date 3-25-92

Operators M. Kaehler & C. Mosser
 Meter Box No. 4
 Counter Edit. 1.0010

Pilot No. 29U-4 CP BY
 Bar. Press. 29.77 inHg H₂O 16 in.
 Nozzle No. 3-3 Nozzle Dia. 0.83 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifts Meter (inWC)	Dep. Vol. (cf)	VAC. inHg	Temperatures (°F)					Oxygen (xv/v)	
							Stack	Probe	Oven	Inpg.	Gas In		Gas/Out
A-12	(1510) 2.5	60.25	1.70	1.22	2.84	5.5	197	245	258	42	80	81	18.0
11	5	62.05	1.90	1.35	4.51	6	200				82	81	18.0
10	7.5	64.51	2.13	1.52	6.28	6.5	199	247	261	42	85	82	17.7
9	10	66.50	2.20	1.58	8.08	7	199				87	83	17.5
8	12.5	69.93	2.43	1.74	9.99	8	199	243	261	43	88	83	17.5
7	15	71.87	2.58	1.85	19.5	8.5	199				88	83	17.5
6	12.5	73.81	2.44	1.79	3.07	8.5	200	246	260	42	89	83	17.7
5	10	75.72	2.40	1.72	5.77	8.5	200				89	84	17.7
4	12.5	77.60	2.29	1.65	7.62	8.5	200	250	257	42	90	84	17.6
3	25	79.44	2.18	1.57	9.43	8	199				91	84	17.6
2	17.5	81.22	2.00	1.44	1.16	7	199	247	255	44	91	85	17.6
1	30	82.63	1.38	1.00	2.60	5	199				91	85	17.7
B-12	32.5	83.98	1.17	.84	3.93	4	199	251	260	44	90	84	17.6
11	35	85.61	1.87	1.35	5.61	6	200				91	85	17.7
10	37.5	87.36	2.13	1.54	7.40	7	199	253	262	44	93	85	17.9
9	40	89.23	2.38	1.72	9.30	8	200				93	86	17.7
8	42.5	91.20	2.53	1.83	12.5	8.5	199	249	261	43	93	86	17.9
7	45	93.23	2.67	1.93	3.26	9	199				93	86	17.8
6	47.5	95.17	2.49	1.80	5.20	9	195	247	255	45	93	86	17.7
5	50	97.08	2.20	1.59	7.03	8	200				93	86	17.9
4	52.5	98.82	2.00	1.45	8.77	7.5	199	245	253	45	93	86	17.8
3	55	100.40	1.60	1.16	0.33	5.5	198				93	86	17.8
2	57.5	101.23	1.18	.85	1.67	4	198	244	250	47	93	87	17.7
1	60	102.92	.85	.62	2.81	3.5	197				93	86	17.6
	(1612)												
	0 = 60	V _s = 41.67	ΔH 1.46								Av _g = 87.2		

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-25-92 Test 9 Run 2
 Source No. 2 B Dryer / Stack No. of traverse points 4
 Method 5 Filter holder: AA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 11 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 4125 Recovery solvent(s)
☒ acetone
☒ other(s) Me Cl₂

No. of probe wash bottles: 1
 Sample recovered by: M. Kaehler & C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>650</u>	<u>496</u>	<u>154</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1356</u>	<u>1340</u>	<u>16</u>
Total			<u>170</u>

Integrated Gas Sampling Data:

Bag Pump No. 1310 Box No. 4 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0.00 cc/min at 15 in. Hg.
 Time start: 1210 (HRS) Time end: 1048 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kaehler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pac. Co. / Carriegen TX
 Source No. 213 Dyer / Spach
 Date 3-25-92 1981 9 Run 2

Operator M. Kachler, C. Mosser
 Meter Box No. 4
 Counter Count. 10010

Pilot No. 29V-6 Cp 84
 Bar. Press. 29.77 inHg H₂O 12.8
 Nozzle No. 3.3 Nozzle Dia. 18.3 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifts Meter (inWC)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)				Gas In	Gas Out	Oxygen (xv/v)
							Stack	Probe	Dye	Ingr.			
B-12	(1710)	103.20	1.43	1.03	4.66	5	198	245	251	45	80	80	17.8
11	5	104.68	1.68	1.20	6.23	5	199				81	80	17.6
10	7.5	106.22	2.03	1.45	7.96	6	199	247	248	45	83	81	17.6
9	10	107.89	2.32	1.66	9.01	7.5	199				85	81	17.9
8	12.5	109.72	2.50	1.79	1.73	8	199	246	253	44	86	82	18.0
7	15	111.65	2.60	1.86	3.69	8.5	200				87	82	18.0
6	17.5	113.62	2.42	1.74	5.59	8.5	199	249	258	44	88	83	18.0
5	20	115.58	2.19	1.58	7.40	8	198				89	83	17.8
4	22.5	117.42	1.87	1.35	9.07	6.5	198	252	261	44	89	83	17.6
3	25	119.15	1.60	1.15	0.62	5.5	198				90	83	17.7
2	27.5	120.88	1.15	.83	1.94	4	196	251	263	45	90	83	17.6
1	30	121.99	1.06	.76	3.20	4	197				90	83	17.8
A-12	32.5	123.20	1.67	1.20	4.79	5.5	198	248	260	46	89	83	18.0
11	35	124.84	1.85	1.33	6.45	6	198				80	79	17.7
10	37.5	126.42	2.12	1.51	8.22	7	197	242	258	43	81	79	17.7
9	40	128.20	2.23	1.59	0.03	7	196				83	80	17.6
8	42.5	130.00	2.52	1.80	1.95	8	198	246	255	45	84	80	17.6
7	45	131.88	2.63	1.89	3.92	9	196				85	80	17.6
6	47.5	133.85	2.47	1.77	5.84	9	196	249	258	45	85	80	17.7
5	50	135.77	2.38	1.71	2.71	8.5	197				85	80	18.1
4	52.5	137.73	2.25	1.62	9.54	8	196	252	261	46	85	80	18.3
3	55	139.57	2.07	1.49	1.30	7.5	195				86	80	18.0
2	57.5	141.36	1.87	1.35	2.96	6.5	195	249	257	46	86	80	17.9
1	60	142.99	1.72	1.24	4.57	6	195				86	80	17.8
	(1840)	144.62											
	θ = 60			ΔH 1.45									
		V = 41.42									Av. = 83.2		

11/10/92
 11/10/92
 11/10/92

Job LOUISIANA PACIFIC
Source NO. 3 DRYER STACK
Test 10 Runs 1-3 Date 3/22/92
Stack dimen. 41.5" IN.
Dry bulb _____ °F Wet bulb _____ °F
Manometer: ☐ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 29.82 in Hg
Static pressure - .70 in WC
Operators D. ROSENWALD + B. ASCHEN
Pitot No. 24-45 Cp .84



Schematic of
Cross Section

[illegible]

R or nothing= reg. manometer; S= expanded; E = electronic S-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC
 Source NO. 3 DRYER STACK
 Method 201A Filter holder: STAINLESS
STEEL

Date 3/26/92 Test 10 Run 1
 No. of traverse points 12
 Filter type: 2.5 µm

Sample Train Leak Check:

Pretest: (0.02 cfm at 18 in. Hg. (vac) ☒
 Posttest: -0.04 cfm at 6.0 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
(5648) ☒ other(s) none
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>573</u>	<u>495</u>	<u>78.0</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1350</u>	<u>1341</u>	<u>9.0</u>
Total			<u>87.0</u>

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 11 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 15 in. Hg.
 Time start: 0915 (HRS) Time end: 1043 (HRS)
 Sampling rate: 300 cc/min Operator: D.B.
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

1. Trans Pacific (Central, Tx.)

**Jatnabadi
Koshatnadi**

687
JN 11
S. ACE ADVISORY

NOTICE
SPECIAL
FEDERAL

29.57
29.57
29.57

912
5471

120

$$\begin{array}{r} 55 \\ \times 11 \\ \hline 55 \\ 550 \\ \hline 605 \end{array}$$
[illegible]

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORROSION TX.)
 Source NO. 3 DRYER STACK
 Method 201A Filter holder: STAINLESS
STEEL

Date 3/26/92 Test 10 Run 2
 No. of traverse points 12
 Filter type: 2.5 µm

Sample Train Leak Check:

Pretest: (1005) cfm at 12 in. Hg. (vac) ☒
 Posttest: cfm at in. Hg. (vac) ☐

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
(5722) ☒ other(s) PROSE
☐
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	598	495	103
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1338	1327	11.0
Total			114.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 11 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 100 cc/min at 17 in. Hg.
 Time start: 1130 (HRS) Time end: 1259 (HRS)
 Sampling rate: 300 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC
Source CORRIGAN, TX.
Method 201A Filter holder: STEINLUS
STEEL

Date 3/26/92 Test 10 Run 3
No. of traverse points 12
Filter type: 2.5' G.F.

Sample Train Leak Check:

Pretest: (⁻⁰⁰⁸ 0.02 cfm at 11 in. Hg. (vac) 11
Posttest: - ⁰⁰⁵ 0.05 cfm at 6 in. Hg. (vac) 12

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

1
3723

☒ acetone probz
☐ other (s)

No. of probe wash bottles: 1
Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	590	496	94.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1356	1350	6.0
Total			100.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 11 Bag No. 3

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: 000 cc/min at 1/4 in. Hg.

Time start: 1333 (HRS) Time end: 1517 (HRS)

Sampling rate: 300 cc/min Operator: D. BRENNAN

S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

JOB _____
 SOURCE NO. 3 DRYER
 DATE 3/26/42

LOUISIANA PACIFIC (CORP)

OPERATORS _____
 WATER BOX NO. 3
 COMPRESSOR COPIES 3


OPERATORS D. BRENNAN + B. ASKEWEN
 WATER BOX NO. 3
 COMPRESSOR COPIES 3

PITOT NO. 24.45
 BAR. PRESS. 29.82
 NOZZLE NO. PA-10 (2)

CP 84
 IN HG H2O
 NOZZLE DIA. 1.50 IN.

[illegible]

INTERPOLL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TXSource No. 3 Dryer / StackTest 11 Run 0 Date 3-26-92Stack dimen. 41.5 IN.Dry bulb °F Wet bulb °FManometer: ☒ Reg. ☐ Exp. ☐ Elec.Barometric pressure 29.82 in HgStatic pressure -0.68 in WCOperators M. Kachler & C. MosserPitot No. 24V-6 Cp .84

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>6</u> in.	Time start: <u>0730</u> hrs		
A-1	.026	1.08	2.08	.15	
2	.082	3.40	9.40	.60	
3	.146	6.06	12.06	1.00	
4	.226	9.38	15.38	1.23	
5	.342	14.19	20.19	1.15	
6	.658	27.31	33.31	1.40	
7	.774	32.12	38.12	2.00	
8	.854	35.44	41.44	2.18	
9	.918	38.10	44.10	2.20	
10	.974	40.42	46.42	2.00	205
B-1				.44	
2				.74	
3				.84	
4				.92	
5				1.40	
6				2.00	
7				2.30	
8				1.70	
9				1.58	
10				1.43	
Port C ≈ 2 ft below ports A + B					
Temp. meas. tool & S/N: <u>PDT-3 / TC</u>				Time end: <u> </u> hrs	

R or nothing = reg. manometer; S = expanded; E = electronic

9-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-26-92 Test 11 Run 1
 Source No. 3 Dryer / Stach No. of traverse points 20
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 20.02 cfm at 7 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) MeCl₂
 No. of ^{Imp}probe wash bottles: 1
 Sample recovered by: McKaepler & C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	690	598	92
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1489	1475	14
Total			106

Integrated Gas Sampling Data:

Bag Pump No. 1310 Box No. 4 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 0916 (HRS) Time end: 1030 (HRS)
 Sampling rate: 400 cc/min Operator: McKaepler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

Job	Lowmunda Pacific / Corvaya, TX	
Source	Mo. 3 Dayer / Steach	Run
Date	3-26-92	Run
Operator	M. Knepler & C. Mosser	
Water Box No.	4	IN NC
Comometer Count	1.0010	
Pitot No.	29V-6	CP
Bar. Press.	29.02	in Hg
Nozzle No.	0103	Nozzle Dia. 1.875 in.

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 3 Dryer / Stack
 Method DO11 Filter holder: NA

Date 3-26-92 Test 11 Run 2
 No. of traverse points 20
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: < 0.02 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) MeCl₂
 No. of ^{Imp}probe wash bottles: 1
 Sample recovered by: M. Kaehler & C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>205</u>	<u>507</u>	<u>118</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1505</u>	<u>1489</u>	<u>16</u>
Total			<u>134</u>

Integrated Gas Sampling Data:

Bag Pump No. B10 Box No. 4 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 1130 (HRS) Time end: 1251 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kaehler
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

Job Louisiana Pacific / Corrugated IX
 Source No. 3 Dryer / Stack
 Date 3-26-92 1001 Run 11

010017 11403 J4140802
JN N1 527 47 ON X08 J41408
Machef & Co. Moscow 310101400

Pitot No. 29V-5 Cp .34
Bar. Press. 29.82 in Hg H2O 11.9 x
Nozzle No. Class Nozzle Dia 1.83 in.

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pac. Inc / Corrigan, TX Date 3-26-92 Test 11 Run 3
 Source No. 3 Dryer / Stack No. of traverse points 20
 Method 0041 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 0 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) Me Cl
 No. of probe wash bottles: 1
 Sample recovered by: M. Kaehle + C. Mosser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>708</u>	<u>596</u>	<u>112</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1429</u>	<u>1415</u>	<u>14</u>
Total			<u>126</u>

Integrated Gas Sampling Data:

Bag Pump No. B10 Box No. 4 Bag No. 3
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 0 cc/min at 15 in. Hg.
 Time start: 1400 (HRS) Time end: 1506 (HRS)
 Sampling rate: 400 cc/min Operator: M. Kaehle
 S/N of O₂ Analyzer used to monitor train outlet: 3

CF-023

Sub Louisiana Pacific / Corrigan, TX

SOURCE	M.B. 3	Payer	/	Stacy	
DATES	3-26-92	1987	11	RUN	3

Operator's Name M. Laehle, & Co. Moser
 Meter Box No. 4
 Counter Code 01001

Pilot No. 29V-5 CP 198
Bar. Press. 29.82 inHg H2O 14 x
Muzzle No. 6755 Muzzle Dia. .38 IN.

[illegible]

Job LOUISIANA PACIFIC (CORRIGAN TX)

Test 13 Runs (1-3) Date 3/26/92

Stack dimen. 41.5" IN.

Dry bulb _____ °F Wet bulb _____ °F


Manometer: ☒ Reg. ☐ Exp. ☐ Elec.

Barometric pressure 29.82 in Hg

Static pressure -1.70 in WC

Operators A. BURENDAN + B. ASCHENBACH

Pitot No. 24-46 Cp .84



Portulante

Traverse Point No.		Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas ($^{\circ}$ F)
			Port length:	6 in.	Time start:	hrs
A	1	.026	1.079	7.079		
	2	.082	3.403	9.403		
	3	.146	6.059	12.059		
	4	.226	9.379	15.379		
	5	.342	14.193	20.193		
	6	.658	27.307	33.307		
	7	.774	32.121	38.121		
	8	.854	35.441	41.441		
	9	.918	38.097	44.097		
	10	.974	40.421	46.421		
B	1					
	2					
	3					
	4					
	5					
	6					
	7					
	8					
	9					
	10					
Temp. meas. tool & S/N: PDT-3 / TC					Time end:	hrs

R or nothing = reg. manometer; S = expanded; E = electronic

S-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job COCAINE PACIFIC (CORAL GABLES, FL) Date 3/26/92 Test 13 Run 1
 Source NO. 3 DRYER STALK No. of traverse points 20
 Method 5 Filter holder: GLASS Filter type: 1" 6.5"

Sample Train Leak Check:

Pretest: (0.005 cfm at 15 in. Hg. (vac) ☒
 Posttest: .002 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s):
(4127) acetone PRECED + NOZZLE
 other(s) BACK-HELF - D.I. H₂O + M₂Cl₂
 No. of probe wash bottles: 1
 Sample recovered by: M. K. DEHLER

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	581	499	82.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1349	1338	11.0
Total			93.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 6 Bag No. 1
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 16 in. Hg.
 Time start: 1555 (HRS) Time end: 1657 (HRS)
 Sampling rate: 400 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

LOUISIANA PACIFIC (CORP) TX.

Operators

ASHEWORTH

Pitt + Tuttle

CP 13

108

15

66. 3 RYER STICK

Computer Box No. 3 1.90

1.80

4110R
4110R
4110R

11 23
25.67

David Allen

三十一

[illegible]

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA-PACIFIC Date 3/26/92 Test 13 Run 2
 Source NO 3 DRYER No. of traverse points 20
 Method 5 Filter holder: 6035 Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: ^{.002} ~~0.02~~ cfm at 15 in. Hg. (vac)
 Posttest: .616 cfm at 11 in. Hg. (vac)

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
4128 ☒ acetone proB2 + No2202
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>595</u>	<u>496</u>	<u>99.0</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1360</u>	<u>1349</u>	<u>11.0</u>
Total			<u>110.0</u>

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 6 Bag No. 2
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 15 in. Hg.
 Time start: 1725 (HRS) Time end: 1827 (HRS)
 Sampling rate: 400 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

JOB _____
SOURCE NO. 3 DOWELL
DATE 3/26/49 1949 13 APR 2
LOUISIANA PACIFIC (CORP) INC., TX.

Outer Box
 Material
 Dimensions
 D. 1

22 NOV 68 C. MESSER
3 APR 7-92 IN DE
9991

Pitt No.
Sur. Press.
Naxile No.

2446
29.92
5.3
17211
101
Cp

$$\begin{array}{r} 511 \\ \times 20 \\ \hline 1022 \\ 0000 \\ \hline 10220 \end{array}$$

[illegible]

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORP) TX. Date 3/26/92 Test 13 Run 3
 Source NO. 3 DRYER No. of traverse points 20
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: .005 cfm at 15 in. Hg. (vac)
 Posttest: .005 cfm at 12 in. Hg. (vac)

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
4129 ☒ acetone PROBE + NOZZLE
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	576	495	81.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1520	1502	18.0
Total			99.0

Integrated Gas Sampling Data:

Bag Pump No. B-7 Box No. 6 Bag No. 3
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: .00 cc/min at 16 in. Hg.
 Time start: 1900 (HRS) Time end: 2002 (HRS)
 Sampling rate: 400 cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

Job _____
 Source _____
 Date _____
 3/24/72 13 Nov 3
 3 DAYTON STATION
 LOUISIANA PACIFIC COMMUNICATIONS, INC.
 Operators _____
 Water Box No. _____
 Computer Conf. _____
 3 991
 IN NC
 192
 D. B. SCHENCK
 Pitot No. _____
 Bar. Press. _____
 Nozzle No. _____
 29.32 14.4g 29.32 14.4g 29.32 14.4g
 8-3 8-3 8-3 8-3 8-3 8-3

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifts Water (inWC)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)						Oxygen (xv/v)
							Stack	Probe	Duct	Inpg.	Gas/In	Gas/Dut	
B-10	1900	454.100					194	236	240	49	82	81	19.0
	3	456.31	2.10	1.77	6.31	6.5	194				83	82	19.2
	6	458.58	2.35	1.97	8.63	7.0	194				85	82	19.5
	9	460.83	2.20	1.85	0.88	6.5	194	238	240	49	86	82	19.4
	12	462.93	1.85	1.56	2.45	6.0	194	212	245	47	86	83	19.4
	15	464.71	1.35	1.14	4.72	4.5	194				88	83	19.4
	18	466.20	.88	.74	6.16	3.0	194	240	259	45	88	83	19.4
	21	467.65	.90	.76	7.61	3.0	193				89	84	19.5
	24	469.07	.87	.74	9.04	3.0	193	243	255	45	89	84	19.4
	27	470.41	.78	.66	6.39	3.0	193	245	258	44	90	84	19.3
A-10	30	471.488	.52	.44	1.50	2.0	194				90	85	19.1
	33	473.88	2.35	1.99	3.85	7.5	194				90	85	19.3
	36	476.21	2.40	2.03	6.22	7.5	193	246	260	44	90	85	19.2
	39	478.50	2.15	1.83	8.47	7.0	193				90	85	19.3
	42	480.62	1.85	1.57	6.55	6.0	193				90	85	19.2
	45	482.35	1.35	1.15	2.34	4.5	193	244	262	44	90	85	19.3
	48	483.99	1.08	.92	3.94	3.5	193				90	85	19.2
	51	485.57	1.05	.89	5.51	3.5	194	249	265	44	91	85	19.4
	54	487.12	1.05	.89	7.09	3.5	193				91	86	19.2
	57	488.54	.84	.71	8.50	3.0	192	253	264	44	91	85	19.2
60	489.627	.52	.44	9.61	2.0	190				90	85	19.2	
(2002)													
Avg. = 82.1													
V _m = 55.507													
θ = 60													

INTERPOLL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job LOUISIANA PACIFIC CORP. IN TX.

Source NO. 4 PRESS VENT STACK

Test 14 Runs 1-3 Date 3/27/92

Stack dimen. 61.5 IN.

Dry bulb °F Wet bulb °F

Manometer: ☒ Reg. ☐ Exp. ☐ Elec.

Barometric pressure 29.86 in Hg

Static pressure -.12 in WC

Operators D. BRENNAN & B. ASCHENBACH

Pitot No. 21-6 Cp 84

Schematic of Cross Section

Particulate

(19)

Traverse Point No.		Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
			Port length:	6 in.	Time start: 0830 hrs	
B	1	.021	1.29	7.29	.40	81
	2	.067	4.12	10.12	.58	
	3	.118	10.38 7.26	16.88 13.26	.54	82
	4	.177	10.88	16.88	.61	
	5	.250	15.38	21.38	.43	82
	6	.356	21.89	27.89	.30	
	7	.644	39.61	45.61	.33	82
	8	.750	46.125	52.125	.50	
	9	.823	50.61	56.61	.72	85
	10	.882	54.24	60.24	.55	
	11	.933	57.38	63.38	.52	
	12	.979	60.21	66.21	.37	
A-	1					
	2					
	3					
	4					
	5					
	6					
	7					
	8					
	9					
	10					
	11					
	12					
Temp. meas. tool & S/N:					Time end: hrs	

R or nothing = reg. manometer; S = expanded; E = electronic S-392.1

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA - PACIFIC COASTAL TR. Date 3/17/92 Test 14 Run 1
 Source VENT 4 No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" GF

Sample Train Leak Check:

Pretest: 0.02 cfm at 15 in. Hg. (vac)
 Posttest: 0.11 cfm at 17 in. Hg. (vac)

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
4130 ☒ other(s) PREP2 + 2022LS

No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	495	495	0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1395	1390	5.0
Total			5.0

Integrated Gas Sampling Data:

AMBIENT A102
 Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 915 (HRS) Time end: 1017 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

CF-011

Job Louisiana Pacific (Concession Tr)
 Source NO. 7 PRESS VENT
 Date 3/27/92 Test 14 Run 1

Operator B. BERNARD & B. ASCHENBACH
 Meter Box No. 3 SH 1-90 IN NC
 Gas meter coeff. 99.1

Pilot No. 26-6 Cp 8.4
 Bar. Press. 29.80 inHg H2O 2 X
 Nozzle No. 5-4 Nozzle Dia. 3/16 IN

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifts Water (inWC)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)						Dargen (Kv/v)
							Stack	Probe	Dry	Imp.	Gas In	Gas Out	
B-120	(0915)	513.700					83	240	251	46	82	80	26.8
11	2.5	515.36	.38	1.41	5.34	6.0	83				83	81	26.9
10	5.0	517.41	.60	2.21	7.36	10.0	84	236	250	45	84	81	26.9
9	7.5	519.32	.51	1.88	9.27	8.5	67				85	81	26.9
8	10.0	521.41	.63	2.39	1.40	10.0	66	237	248	45	86	81	26.8
7	12.5	523.23	.43	1.64	3.17	7.5	67				86	82	26.9
6	15.0	524.61	.28	1.07	4.59	5.0	67	240	246	44	87	82	26.9
5	17.5	526.21	.34	1.30	6.17	5.5	65				89	83	26.9
4	20.0	528.24	.59	2.26	8.24	10.0	86	239	243	44	89	83	26.9
3	22.5	530.42	.69	2.54	6.45	12.5	86				90	85	26.9
2	25.0	532.29	.48	1.77	2.29	8.0	88	240	245	43	90	85	26.9
1	27.5	534.10	.45	1.66	4.07	7.5	90				91	86	26.9
A-12	30.0	535.548	.28	1.03	5.17	4.5	89	242	246	40	91	86	26.9
11	32.5	537.42	.53	1.95	7.41	9.0	89				91	86	26.9
10	35.0	539.86	.90	3.31	9.43	14.0	95	245	250	40	91	86	26.9
9	37.5	542.20	.80	2.91	2.29	13.5	95				91	86	26.9
8	40.0	544.85	1.0	3.67	4.94	15.0	90	244	251	40	91	86	26.9
7	42.5	546.59	.42	1.54	6.66	7.0	92				91	86	26.9
6	45.0	547.94	.24	.88	7.97	4.0	87	240	250	40	91	86	26.9
5	47.5	548.99	.15	.55	9.00	3.0	87				93	87	26.9
4	50.0	551.16	.69	2.55	1.21	12.0	87	243	248	40	93	87	26.9
3	52.5	553.50	.77	2.85	3.55	14.0	88				93	87	26.9
2	55.0	555.59	.59	2.15	5.59	12.0	98	243	248	40	93	87	26.9
1	57.5	557.35	.44	1.62	7.36	8.0	90				93	87	26.9
(1017)	60.0	558.413	.34	1.21	8.91	6.0	97				93	87	26.9
V ₀ = 45.213												Avg. = 86.7	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORRIGON, TX) Date 3/27/92 Test 14 Run 2
 Source NO. 7 PRESS VENT STACK No. of traverse points 24
 Method 5 Filter holder: GLOSS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: .01 cfm at 17 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone PRESS & NOZZLE
4132 ☒ other(s)
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	497	495	2.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1418	1395	23.0
Total			25.0

Integrated Gas Sampling Data:

AMBIENT AIR
 Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1100 (HRS) Time end: 1202 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA PACIFIC CAROLINA TX.
 Source NO. 1 PAPER REENT STACK
 Date 3/27/82 Test 14 Run 2

Operator D. BROWN + B. ASCHENBACH
 Meter Box No. 3 SHF 190 IN MC
 Gas meter corr. -.991

Pilot No. 21-6
 Bar. Press. 29.86
 Nozzle No. 0-1 H₂O 247 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Orifice Meter (inWC)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)						Oxygen (xv/v)
							Stack	Probe	Oven	Inpg.	Gas/in	Gas/Dut	
A-12	(1100)	559.31	.50	1.90	123	8.0	94	230	253	46	90	88	20.9
"	5.0	561.21	.96	3.54	3.83	14.0	104				92	89	20.9
10	7.5	563.76	.75	2.83	6.16	14.0	93	232	255	46	93	89	20.9
9	10.0	566.10	.96	3.63	8.80	14.0	92				93	89	20.9
8	12.5	570.51	.43	1.62	6.58	7.0	95	232	257	45	93	90	20.9
7	15.0	572.22	.35	1.32	2.17	6.5	96				93	90	20.9
6	17.5	573.26	.15	.56	3.22	2.5	98	235	259	45	94	90	20.9
5	20.0	575.28	.58	2.20	5.28	10.5	92				97	92	20.9
4	22.5	577.70	.85	3.19	9.77	14.0	99	231	255	45	97	92	20.9
3	25.0	579.90	.60	2.28	9.87	11.0	93				97	92	20.9
2	27.5	581.83	.54	2.05	1.87	9.5	94	230	254	45	97	92	20.9
1	30.0	583.496	.37	1.41	3.53	6.0	94				98	93	20.9
B-12	32.5	585.48	.53	2.02	5.51	8.5	93	233	255	45	96	92	20.9
11	35.0	587.93	.82	3.09	7.95	14.0	97				98	93	20.9
10	37.5	590.14	.68	2.58	6.19	13.0	96	232	254	45	99	93	20.9
9	40.0	592.43	.72	2.72	2.49	14.0	99				98	94	20.9
8	42.5	594.18	.37	1.41	4.15	7.0	96	231	252	43	98	94	20.9
7	45.0	595.80	.35	1.33	5.76	6.0	96				99	94	20.9
6	47.5	597.21	.26	.99	7.15	4.5	95	234	255	43	100	94	20.9
5	50.0	599.05	.45	1.73	8.99	7.0	91				100	95	20.9
4	52.5	601.20	.62	2.37	1.14	12.5	93	236	251	42	101	95	20.9
3	55.0	603.44	.73	2.81	3.48	14.0	89				101	95	20.9
2	57.5	605.30	.43	1.65	5.28	8.0	91	235	252	40	101	96	20.9
1	60.0	606.348	.16	.61	6.58	2.5	92				101	96	20.9
(1202)													
0 = 60		V ₁ = 47.038		M = 2.08								Av. g. = 94.6	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC Date 3/27/92 Test 14 Run 3
 Source NO. 4 PRESS VENT No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" 6.0

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ~~8~~
 Posttest: 101 cfm at 16 in. Hg. (vac) ~~8~~

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s)
(4/33) ☒ acetone PROCESSED WASTE
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: 0.3

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	496	495	1.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1431	1423	8.0
Total			9.0


Integrated Gas Sampling Data: AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1242 (HRS) Time end: 1345 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 4 Press Vent / Stack
 Test 15 Run 0 Date 3-27-91
 Stack dimen. 62.75 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.86 in Hg
 Static pressure -.12 in WC
 Operators M. Kachler & C. Mosser
 Pitot No. 290-6 Cp .84



Y. Maldonado

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: 6 in.	Time start: 0900 hrs		
A-1	.041	1.32	7.37	.36	
2	.067	4.20	10.20	.48	
3	.118	7.40	13.40	.60	
4	.177	11.11	17.11	.70	
5	.250	15.69	21.69	.82	
6	.356	22.34	28.34	.94	
7	.644	40.41	46.41	1.31	
8	.750	47.06	53.06	1.40	9
9	.823	51.64	57.64	1.00	99
10	.882	55.35	61.35	.81	
11	.933	58.55	64.55	.95	
12	.979	61.43	67.43	.72	
B-1				.30	
2				.48	
3				.57	
4				.77	
5				.65	
6				.42	
7				.28	
8				.50	
9				.71	
10				.54	
11				.61	
12				.78	
Temp. meas. tool & S/N: PDI-3 / TC				Time end:	hrs

R or nothing = reg. manometer; S = expanded; E = electronic

S-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 4 Press Vent / Stack
 Method 0011 Filter holder: NA

Date 3-27-92 Test 15 Run 1
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 20.02 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

NA

☐ acetone
☒ other(s) Me Cl₂

No. of ^{Imp} ~~probe~~ wash bottles: 1
 Sample recovered by: M. Kaehler & C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>596</u>	<u>596</u>	<u>-</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1372</u>	<u>1359</u>	<u>13</u>
Total			<u>13</u>

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX
 Source 20.4 Press Vent / Stack
 Date 3-27-92 15 Run 1

Operator M. Kaehler & C. Mosser
 Meter Box No. 4 HP 175 IR NC
 Computer conf. 1.0010

Pitot No. 29U-6 Cp .84
 Bar. Press. 29.86 inHg H₂O 3
 Nozzle No. Class Nozzle Dia. 2.39 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifting Water (inH ₂ O)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)						Oxygen (xv/v)
							Stack	Probe	Oven	Inlet	Gas/Dut		
-----	0915	283.00	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----
A-1	2.5	284.54	.35	1.12	4.50	3	83	240	249	45	72	72	20.9
2	5	286.28	.50	1.60	6.30	4	78				74	72	20.9
3	7.5	288.22	.58	1.88	8.26	5	73	242	253	45	77	74	20.9
4	10	290.38	.72	2.38	0.45	6	66				79	74	20.9
5	12.5	292.50	.65	2.15	2.54	5.5	67	245	255	44	81	75	20.9
6	15	293.87	.25	.83	3.84	2.5	67				82	76	20.9
7	17.5	295.27	.28	.93	5.23	3	65	240	256	44	83	76	20.9
8	20	296.94	.76	1.53	2.00	4	67				85	77	20.9
9	22.5	299.51	.99	3.24	9.57	8	76	242	254	44	87	78	20.9
10	25	301.82	.82	2.63	1.89	7	89				87	79	20.9
11	27.5	304.35	.98	3.17	4.44	8	83	244	253	45	88	79	20.9
12	30	306.60	.77	2.45	6.68	7	94				89	80	20.9
B-1	32.5	308.10	.32	1.03	8.15	3	87	240	256	46	87	80	20.9
2	35	309.90	.51	1.64	9.48	4	90				88	80	20.9
3	37.5	311.78	.55	1.75	1.89	4.1	94	238	255	46	90	81	20.9
4	40	314.02	.74	2.38	4.10	6	90				91	82	20.9
5	42.5	316.52	.62	2.46	6.57	2.5	91	241	258	46	92	82	20.9
6	45	318.15	.39	1.26	8.19	3.5	91				92	83	20.9
7	47.5	319.48	.26	.84	9.52	2.5	87	247	258	46	92	83	20.9
8	50	321.22	.47	1.53	1.30	4	87				92	83	20.9
9	52.5	323.38	.69	2.25	3.46	6	85	248	255	47	94	84	20.9
10	55	325.35	.53	1.69	5.34	4.5	98				94	85	20.9
11	57.5	327.35	.61	1.98	7.36	5	90	245	257	48	95	85	20.9
12	60	329.62	.78	2.50	9.64	6.5	97				95	86	20.9
(1017)													
V _m = 46.62				ΔH 1.90							Avg. = 83.1		
θ = 60													

INTERFOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-27-92 Test 15 Run 2
 Source No. 4 Press Vent / Stack No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) MeCl₂
 No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: McKaeher & C. Moser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>599</u>	<u>599</u>	<u>—</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1528</u>	<u>1518</u>	<u>10</u>
Total			<u>10</u>

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Koussiana facility / Corrugated TX Operator W. Kuchler & C. Moser Pitot No. 200-6 Cp 94
 Source Abby Press Vent / Stack Meter Box No. 4 Bar. Press. 29.86 inHg H₂O 7.3 K
 Date 3-27-92 Computer soft. 1.00.10 Nozzle No. 6 Glass Nozzle Dia. 232 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifts Water (inH ₂ O)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)						Oxygen (xv/v)
							Stack	Probe	Dyn	Impq.	Gas In	Gas Out	
B-1	2.5	330.00	.44	1.44	1.72	4	95	245	253	47	93	82	20.9
2	5	331.80	.49	1.57	3.52	4	104				85	82	20.9
3	7.5	335.55	.55	1.80	5.45	4.5	93	248	255	47	87	83	20.9
4	10	337.72	.72	2.36	7.65	6	94				90	84	20.9
5	12.5	339.07	.68	2.24	9.81	6	95	249	258	48	91	85	20.9
6	15	341.30	.33	1.08	1.31	3.5	98				93	86	20.9
7	17.5	342.98	.38	1.25	2.92	3.5	98	246	255	46	93	86	20.9
8	20	344.99	.57	1.88	4.91	5	95				94	87	20.9
9	22.5	347.42	.89	2.92	2.37	7	99	244	259	45	96	88	20.9
10	25	349.62	.68	2.27	9.55	6	93				97	88	20.9
11	27.5	351.93	.74	2.47	1.82	6	93	248	257	45	97	89	20.9
12	30	353.92	.59	1.97	3.85	5	94				98	89	20.9
A-1	32.5	355.42	.34	1.13	5.39	3	94	247	256	47	96	89	20.9
2	35	357.25	.53	1.76	7.32	4	94				98	90	20.9
3	37.5	359.27	.58	1.93	9.33	4.5	97	245	255	47	99	90	20.9
4	40	361.70	.84	2.78	1.74	7	98				100	91	20.9
5	42.5	363.00	.63	2.10	3.84	6	96	248	259	47	100	91	20.9
6	45	365.10	.21	.70	5.06	2.5	96				100	92	20.9
7	47.5	366.18	.15	.50	6.09	2.5	95	245	261	48	100	92	20.9
8	50	367.93	.42	1.42	7.82	3.5	91				99	91	20.9
9	52.5	370.23	.86	2.87	0.28	6.5	94	244	261	48	100	92	20.9
10	55	372.41	.70	2.37	2.51	6	89				101	92	20.9
11	57.5	375.10	.95	3.19	5.10	9	92	246	258	48	102	93	20.9
12	60	377.26	.69	2.33	7.31	7	92				102	93	20.9
(1202)													
θ = 60		V _h = 47.26	^H 6.93								Avq. = 92.2		

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 4 Press Vent / Stack
 Method 0011 Filter holder: NA

Date 3-27-92 Test 15 Run 3
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 20.02 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) Me Cl₂
 No. of ^{Imp}probe wash bottles: 1
 Sample recovered by: Michaeler & C. Mosser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>597</u>	<u>598</u>	<u>(1)</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1380</u>	<u>1372</u>	<u>8</u>
Total			<u>?</u>

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Cagayan, TX
 Source No. 4 Press Vent / Stack
 Date 3-27-74 15 Run 3


Operator M. Koehler & C. Mosser
 Meter Box No. 4 HF 275 IN UC
 Gas meter coeff. 1.0010

Pitot No. 29U-6 Cp .84
 Bar. Press. 29.86 inHg H₂O
 Nozzle No. Glass Nozzle Dia. .235 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Orifice Meter (inWC)	Dis. Vol. (cf)	VAC. inHg	Temperatures (°F)						Oxygen (xv/v)
							Stack	Probe	Duct	Impg.	Gas In	Gas/Dut	
A-1	(12.40)	377.60	.42	1.41	9.31	3	93	245	256	45	90	88	20.9
2	5	379.31	.55	1.83	1.26	4	95				90	88	20.9
3	7.5	383.55	.73	2.41	3.50	6	97	248	259	45	93	89	20.9
4	10	385.85	.85	2.80	5.92	7	100				95	90	20.9
5	12.5	387.90	.61	2.04	7.98	6	94	244	262	46	97	91	20.9
6	15	389.00	.15	.50	9.01	2	98				97	91	20.9
7	17.5	390.46	.30	1.01	0.17	3	93	247	260	46	97	91	20.9
8	20	392.30	.44	1.48	2.24	4	92				98	91	20.9
9	22.5	394.81	1.02	3.43	9.92	9	92	250	262	46	100	92	20.9
10	25	397.15	.74	2.47	7.20	7	98				101	93	20.9
11	27.5	399.73	.96	3.22	9.80	8	96	248	261	47	102	93	20.9
12	30	402.04	.74	2.48	2.09	6.5	98				102	93	20.9
B-1	32.5	403.94	.49	1.64	3.95	4	98	251	264	47	100	93	20.9
2	35	405.95	.56	1.87	5.93	4.5	100				101	94	20.9
3	37.5	408.27	.80	2.69	8.32	6.5	95	250	263	49	103	94	20.9
4	40	410.52	.73	2.44	0.59	6	101				103	95	20.9
5	42.5	412.77	.68	2.27	2.78	6	101	247	260	49	104	95	20.9
6	45	415.14	.81	2.73	5.18	7	96				104	95	20.9
7	47.5	416.75	.37	1.25	6.81	3.5	95	251	260	48	104	95	20.9
8	50	418.87	.59	2.00	8.87	5	95				104	96	20.9
9	52.5	421.20	.78	2.63	1.23	6.5	96	248	259	48	105	96	20.9
10	55	423.42	.70	2.32	3.45	6	107				105	96	20.9
11	57.5	425.68	.72	2.38	5.70	6	108	247	260	49	105	96	20.9
12	60	427.98	.72	2.39	7.95	6	105				105	97	20.9
	(1345)												
	θ = 60	V _s = 50.98		ΔH 2.15							Av _g = 96.6		

INTERPOLL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job LOUISIANA PACIFIC
 Source NO. 3 PRESS VENT STACK
 Test 17 Runs 1-3 Date 3/27/92
 Stack dimen. 61.5 IN.
 Dry bulb _____ °F Wet bulb _____ °F
 Manometer: ☐ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.86 in Hg
 Static pressure - .10 in WC
 Operators D. BRENNAN & B. ASCHENBACH
 Pitot No. 21-G Cp .84



Schematic of
Cross Section

Particulate

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>6</u> in.	Time start: _____ hrs		
<u>B</u>	<u>12</u>	<u>.021</u>	<u>1.29</u>	<u>7.29</u>	
	<u>11</u>	<u>.067</u>	<u>4.12</u>	<u>10.12</u>	
	<u>10</u>	<u>.118</u>	<u>7.26</u>	<u>13.26</u>	
	<u>9</u>	<u>.177</u>	<u>10.88</u>	<u>16.88</u>	
	<u>8</u>	<u>.250</u>	<u>15.38</u>	<u>21.38</u>	
	<u>7</u>	<u>.356</u>	<u>21.89</u>	<u>27.89</u>	
	<u>6</u>	<u>.644</u>	<u>39.61</u>	<u>45.61</u>	
	<u>5</u>	<u>.750</u>	<u>46.125</u>	<u>52.125</u>	
	<u>4</u>	<u>.823</u>	<u>50.61</u>	<u>56.61</u>	
	<u>3</u>	<u>.882</u>	<u>54.24</u>	<u>60.24</u>	
	<u>2</u>	<u>.933</u>	<u>57.38</u>	<u>63.38</u>	
	<u>1</u>	<u>.979</u>	<u>60.21</u>	<u>66.21</u>	
<u>A</u>	<u>12</u>				
	<u>11</u>				
	<u>10</u>				
	<u>9</u>				
	<u>8</u>				
	<u>7</u>				
	<u>6</u>				
	<u>5</u>				
	<u>4</u>				
	<u>3</u>				
	<u>2</u>				
	<u>1</u>				
Temp. meas. tool & S/N:				Time end: _____	hrs

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC Date 3/27/92 Test 17 Run 1
 Source NO 5 PRESS TERT STALK No. of traverse points 24
 Method 5 Filter holder: 6055 Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: .015 cfm at 15 in. Hg. (vac) ~~15~~
 Posttest: .015 cfm at 17 in. Hg. (vac) ~~15~~

Particulate Catch Data:

No.s of filters used: 4/34 Recovery solvent(s) acetone probe + nozzle
☒ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	496	496	0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1413	1429	14.0
Total			14.0

Integrated Gas Sampling Data:

AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1430 (HRS) Time end: 1532 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023

INTERPOL LABS LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA PACIFIC (CARLTON TX.) Operator D. BERNARD B. H. Pilot No. 21-6 Cp 8.1
 Source NO. 3 PRESS VENT STACK Meter Box No. 3 Bar. Press. 29.38 inHg H₂O 1 x
 Date 3/22/92 1992 17 Run 1 Gas meter coeff. 991 Nozzle No. 8-7 Nozzle Dia. .271 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifted Water (inH ₂ O)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)					Dye (x/v/v)
							Stack	Probe	Dye	Imp.	Gas In	Gas Out
A-12	1430	651.660	.51	1.90	6.59	6.5	102	248	251	43	91	93
11	2.5	656.61	.55	2.02	8.57	7.0	102				95	94
10	5.0	658.59	.60	2.22	8.64	8.0	100	250	253	41	97	94
9	7.5	660.66	.67	2.84	2.99	9.5	101				98	94
8	10.0	663.66	.77	1.76	4.84	6.5	96	249	258	41	98	95
7	12.5	664.89	.77	1.57	6.59	5.0	96				99	95
6	15.0	666.60	.72	.75	7.81	2.0	95	246	256	41	100	95
5	17.5	667.80	.62	2.29	9.92	7.5	100				101	96
4	20.0	669.88	1.06	3.96	2.69	14.5	97	247	255	40	101	96
3	22.5	672.41	.93	3.44	5.28	14.5	103				101	96
2	25.0	675.19	.93	3.44	7.87	14.5	103	244	254	40	100	96
1	27.5	677.81	.90	3.35	0.12	14.0	99				100	97
B-12	30.0	680.049	.59	2.21	2.50	7.5	96	245	254	40	100	97
11	32.5	682.43	.63	2.34	4.64	8.0	101				100	97
10	35.0	684.57	.56	2.09	6.66	7.5	99	245	251	40	101	97
9	37.5	686.68	.76	2.81	9.00	10.0	104				102	97
8	40.0	689.06	.42	1.58	6.76	5.5	97	246	250	40	102	98
7	42.5	690.83	.39	1.46	2.46	5.0	99				103	98
6	45.0	692.50	.35	1.32	4.07	4.0	96	245	252	41	103	98
5	47.5	694.11	.90	3.38	6.64	13.0	96				103	98
4	50.0	696.60	.82	3.07	9.09	10.5	98	245	253	41	104	98
3	52.5	699.14	.48	1.80	6.97	6.0	99				103	99
2	55.0	701.05	.27	1.01	2.39	3.5	98	246	253	40	103	99
1	57.5	702.43	.25	.94	3.75	3.0	98				104	99
1	60.0	703.789										
(1538)												
Σ	60	79.129		2.23							Avg. = 93.4	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC Date 3/27/92 Test 17 Run 2
 Source NO 3 PRESS VENT STACK No. of traverse points 24
 Method 5 Filter holder: ELLS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: .012 cfm at 15 in. Hg. (vac) ☒
 Posttest: .012 cfm at 17 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
4135 ☒ probe + notice
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	494	494	0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1377	1360	17.0
Total			17.0

Integrated Gas Sampling Data:

AMBIENT AIR
 Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1610 (HRS) Time end: 1712 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA PACIFIC (COASTAL TX.)

Operator D. BARNETT + B. ASCHENBACH

21-6 EP 84

Pilot No.

D. BARNETT

Meter Box No. 3

Computer Conf.

1981

Run 2

Date 3/22/82

Press Vent Stack

Nozzle Dia 1.5 in.

Bar. Press.

Nozzle No. 8-4

29.82 inHg

20.9

20.9

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifts Meter (inH ₂ O)	Dec. Vol. (cf)	VAD. inHg	Temperatures (°F)					Oxygen (xv/v)
							Stack	Probe	Dry	Wet	Gas/Dut	
B-12	(16.0)	704.200	.54	2.00	6.18	8.0	102	229	239	56	96	20.9
"	2.5	706.16	.71	2.65	8.44	11.0	97				96	
10	5.0	708.42	.46	1.70	0.27	7.5	102	230	242	55	96	20.9
9	7.5	710.32	.64	2.39	2.13	10.0	96				96	
8	10.0	712.47	.42	1.57	4.18	7.0	96	230	245	55	97	20.9
7	12.5	714.24	.35	1.32	5.79	5.5	95				97	
6	15.0	715.85	.40	1.50	7.50	6.5	97	231	246	53	97	20.9
5	17.5	717.55	1.0	3.73	0.20	13.5	98				97	
4	20.0	720.13	.96	3.57	2.84	13.5	100	230	249	53	97	20.9
3	22.5	722.79	.58	2.15	4.88	9.0	97				98	
2	25.0	724.81	.43	1.62	6.66	7.5	96	233	250	53	98	20.9
1	27.5	726.62	.31	1.16	8.17	5.0	98				98	
A-12	30.0	728.175	.67	2.51	0.39	11.0	98	232	251	51	98	20.9
"	32.5	729.42	.93	3.49	3.00	14.0	96				98	
11	35.0	732.94	.67	2.51	5.22	11.0	99	231	249	51	98	20.9
10	37.5	735.26	1.10	4.13	8.03	14.0	95				98	
9	40.0	737.98	.65	2.42	6.23	11.0	100	230	250	50	98	20.9
8	42.5	740.16	.30	1.13	1.72	5.0	94				98	
7	45.0	741.79	.22	.82	2.99	3.5	98	229	254	50	98	20.9
6	47.5	743.05	.90	3.39	5.56	14.0	93				98	
5	50.0	745.50	1.05	3.92	8.33	14.5	98	226	255	50	98	20.9
4	52.5	748.27	.92	3.46	0.92	14.0	95				98	
3	55.0	750.85	.91	3.39	3.50	14.0	100	228	258	48	98	20.9
2	57.5	753.44	.72	2.69	5.79	12.5	99				98	
1	60.0	755.742									98	
(1712)												
Σ	θ = 60	Σ = 51.542		Σ = 2.47							Av. = 98.6	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (COASTAL, TX.) Date 3/27/92 Test 17 Run 3
 Source AG 3 PRESS VENT STACK No. of traverse points 24
 Method 5 Filter holder: GUDSS Filter type: GUDSS

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) 
 Posttest: .002 cfm at 18 in. Hg. (vac) 

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone filter + nozzle
4136 ☒ other(s)
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	499	496	3.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1391	1377	13.0
Total			16.0

Integrated Gas Sampling Data: AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1755 (HRS) Time end: 1857 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: 9

CF-023


INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job COVINGTON PACIFIC (CONCRETE), TX.Source NO. 3 PRESS VENT STACKDate 3/22/82 1981 12 Run 3Operator D. GAZDAROWSKI + B. ASCHENBACHPilot No. 21-6 Ep 51Water Box No. 3 Bar. Press. 29.82 in HgGenerator Coeff. 1.90 in Hg H2O 1.5 x
Nozzle No. 8-7 Nozzle Dia 2.71 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Drifted Water (in H ₂ O)	Obs. Vol. (cf)	VAC. in Hg	Temperatures (°F)						Oxygen (kv/v)
							Stack	Probe	Dry	Wet	Gas In	Gas/Dust	
A-12	(17.55)	756.200	.75	2.82	8.55	12.0	95	246	260	58	94	93	26.9
	2.5	758.51	.60	2.23	0.62	10.5	96				94	93	
	5.0	760.67	.51	1.90	2.54	8.0	95	245	259	57	95	94	20.9
	7.5	762.60	.86	3.19	5.03	13.5	97				96	94	
	10.0	765.09	.58	2.17	7.08	10.5	95	245	254	57	96	94	20.9
	12.5	767.12	.55	2.04	9.07	8.5	99				96	94	
	15.0	769.10	.18	.67	0.22	2.5	93	246	257	52	96	94	20.9
	17.5	770.27	.50	1.88	2.13	7.5	92				98	94	
	20.0	772.15	1.08	4.00	4.92	13.0	98	248	259	52	99	95	20.9
	22.5	774.87	.92	3.45	7.51	14.0	93				99	95	
	25.0	779.46	.80	2.97	9.91	13.0	99	250	260	51	98	95	20.9
	27.5	779.87	.51	1.90	1.83	8.5	99				98	95	
	30.0	781.86	.42	1.58	3.59	7.5	93	249	262	51	97	95	20.9
	32.5	783.62	.72	2.64	5.86	11.0	105				98	95	
	35.0	785.89	.46	1.72	7.69	8.0	95	249	261	51	98	95	20.9
	37.5	787.73	.63	2.55	9.92	11.0	93				98	95	
	40.0	789.96	.41	1.54	1.65	7.5	95	253	260	50	98	95	20.9
	42.5	791.67	.20	.75	2.87	3.0	92				98	95	
	45.0	792.89	.48	1.80	4.74	8.5	95	252	261	50	99	95	20.9
	47.5	794.77	1.08	4.06	7.55	15.0	91				100	95	
	50.0	797.61	.68	2.55	9.78	11.0	95	250	263	48	99	95	20.9
	52.5	799.80	.33	1.24	1.34	6.0	92				99	95	
	55.0	801.31	.38	1.43	3.01	6.5	92	246	259	48	99	95	20.9
	57.5	802.95	.19	.71	4.20	3.0	93				100	95	
	60.0	804.198											
	(1857)												
	0 = 60	V ₀ = 47.998		ΔH 2.16							Avg. = 92.0		

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 3 Press Vent / Stack
 Test 18 Run 0 Date 3-27-92
 Stack dimen. 62.75 IN.
 Dry bulb _____ °F wet bulb _____ °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.86 in Hg
 Static pressure -1.2 in WC
 Operators M. Kaehler & C. Mosser
 Pitot No. 290-6 Cp .84



Formaldehyde

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>6</u> in.	Time start: <u>1420</u> hrs		
A-1	.021	1.32	7.32	.67	
2	.067	4.20	10.20	1.00	
3	.110	7.40	13.40	1.03	
4	.127	11.11	17.11	.63	
5	.250	15.65	21.69	.70	
6	.358	22.34	28.34	1.49	
7	.644	40.41	46.41	.71	
8	.750	47.06	53.06	1.00	
9	.823	57.64	57.64	.80	
10	.982	55.35	61.35	.95	
11	.933	58.55	64.55	.93	
12	.979	61.43	67.43	.90	100°
B-1				.25	
2				.36	
3				.40	
4				.90	
5				.94	
6				.55	
7				.42	
8				.65	
9				.90	
10				.60	
11				.58	
12				.55	
Temp. meas. tool & S/N: <u>PDT-3 / TC</u>				Time end: _____	hrs

R or nothing = reg. manometer; S = expanded; E = electronic

9-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 3 Press Vent / Stack
 Method DOH Filter holder: NA

Date 3-27-92 Test 18 Run 1
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac)
 Posttest: 0.02 cfm at 12 in. Hg. (vac)

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)

☐ acetone
☒ other(s) MeCl₂

No. of ^{Imp} wash bottles: 1
 Sample recovered by: M. Kaeble & C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	602	598	4
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1488	1474	14
Total			18

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

JOB Louisiana Pac. & C. Co.
SOUR No. 3 Press Vent Stack
DATE 3-27-92 PB Ann

Operator _____
Meter Box No. 4 473 IN NE
Gasometer cost. 100.00

Pilot No. 290-6 CP 84
 Bar. Press. 29.86 inHg H2O / X
 Nozzle No. 61522 Nozzle Dia. .235 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Drifts Meter (in H ₂ O)	Des. Vol. (cf)	VAC. in Hg	Temperature (°F)						Oxygen (xv/v)
							Stack	Probe	Duct	Inp.	Gas In	Gas Out	
B-1	(1430) 2.5	428.40	1.8	.94	9.80	3	98	245	250	44	90	90	20.9
2	5	429.86	.34	1.12	1.33	3	102				92	90	20.9
3	7.5	432.99	.37	1.23	2.44	3	98	248	252	44	94	91	20.9
4	10	435.39	.93	3.07	5.47	2.5	101	253	256	45	97	92	20.9
5	12.5	438.05	.95	3.17	8.04	8	96				99	93	20.9
6	15	439.99	.53	1.77	9.98	4	98				99	93	20.9
7	17.5	441.68	.39	1.31	1.64	3.5	95	250	255	47	100	94	20.9
8	20	443.86	.68	2.27	3.83	6	100				101	94	20.9
9	22.5	446.41	.97	3.25	6.44	8	97	247	253	47	102	95	20.9
10	25	448.40	.55	1.83	8.41	5	103				102	95	20.9
11	27.5	450.65	.70	2.33	2.63	6	103	246	250	46	103	95	20.9
12	30	452.69	.57	1.91	2.64	5	100				103	95	20.9
A-1	32.5	455.09	.82	2.75	5.05	2.5	99	245	248	46	102	95	20.9
2	35	457.27	.67	2.24	2.23	6	101				103	96	20.9
3	37.5	459.98	1.05	3.50	9.94	9	102	246	252	47	104	96	20.9
4	40	462.60	1.07	3.55	2.68	10	104				105	96	20.9
5	42.5	464.75	.60	2.03	4.76	6	97	248	255	47	104	96	20.9
6	45	467.08	.75	2.52	2.07	8	99				105	97	20.9
7	47.5	468.93	.47	1.57	8.90	5	98	247	254	48	105	97	20.9
8	50	471.25	.73	2.45	1.19	8	100				106	97	20.9
9	52.6	473.85	1.02	3.42	3.88	10	100	244	262	48	106	98	20.9
10	55	476.38	.85	2.86	6.34	9	100				106	98	20.9
11	57.6	478.99	.98	3.30	8.99	10	98	244	260	49	106	98	20.9
12	60	481.56	.92	3.10	1.55	10	98				106	98	20.9
(1531) 60													
		V ₀ = 53.16		2.40							Av. = 98.3		

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 3 Piers Vent / Stack
 Method 0011 Filter holder: NA

Date 3-27-92 Test 18 Run 2
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 12 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)

☐ acetone
☒ other(s) Me Cl₂

No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: Mikaeler & C. Mosser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>598</u>	<u>598</u>	<u>(2)</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1417</u>	<u>1400</u>	<u>17</u>
Total			<u>15</u>

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Corgovan TX
 Source NO. 3 Press Vent / Stack
 Date 3-27-92 1992 18 Apr 2

Operator M. Kaehler & C. Mosser
 Motor Box No. 4 HR 1-23 IN NC
 Generator Coeff. 1.0010

Pitot No. 24U-6 CP .84
 Bar. Press. 29.86 IN HG H2O
 Nozzle No. 6655 Nozzle Dia .235 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifts Water (inH ₂ O)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)						Oxygen (xv/v)
							Stack	Probe	Oven	Insp.	Gas In	Gas Out	
A-1	(1410) 2.5	482.10	.86	2.98	4.57	7	102	248	256	45	92	91	20.9
2	5	484.58	.96	3.18	7.14	8	97				94	92	20.9
3	7.5	489.63	.93	3.09	9.68	8	97	245	258	45	96	93	20.9
4	10	492.40	1.10	3.63	2.44	9	102				99	94	20.9
5	12.5	494.63	.65	2.17	4.58	5.5	100	247	261	45	100	94	20.9
6	15	495.83	.20	1.67	5.77	2	95				100	94	20.9
7	17.5	498.07	.70	2.35	8.00	6	97	250	258	46	101	95	20.9
8	20	500.18	.61	2.05	0.00	5	98				102	95	20.9
9	22.5	502.85	1.10	3.68	2.86	10	99	246	255	46	103	96	20.9
10	25	505.32	.81	2.73	5.26	7	97				104	96	20.9
11	27.5	508.02	1.12	3.77	8.08	10	96	245	253	47	104	96	20.9
12	30	510.62	.90	3.02	0.61	9.0	98				104	96	20.9
B-1	32.5	511.92	.22	.74	1.07	2.5	98	243	255	48	101	95	20.9
2	35	513.25	.28	.94	3.28	3	96				102	96	20.9
3	37.5	515.20	.53	1.78	5.23	4	99	247	260	48	103	96	20.9
4	40	517.73	.92	3.07	7.78	8	97				104	97	20.9
5	42.5	520.40	1.03	3.45	0.48	9	100	250	262	48	105	97	20.9
6	45	522.38	.55	1.87	2.48	5	94				105	97	20.9
7	47.5	524.30	.47	1.59	4.81	4	98	253	261	48	105	97	20.9
8	50	526.31	.54	1.81	6.28	4.5	101				105	97	20.9
9	52.5	528.92	1.00	3.36	8.95	9	98	250	258	49	105	97	20.9
10	55	531.16	.63	2.12	1.07	6	98				105	97	20.9
11	57.5	533.59	.87	2.95	3.57	7.5	95	247	256	50	106	98	20.9
12	60	535.90	.76	2.58	5.91	7	95				106	98	20.9
(1711)													
θ = 60		V _m = 53.80	2.48								Avg. = 98.8		

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pac. Inc / Corrigan, TX Date 3-22-92 Test 18 Run 3
 Source No. 3 Press Vent / Stack No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: < 0.02 cfm at 12 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) Me Cl₂
 No. of ^{Imp} wash bottles: 1
 Sample recovered by: M. Kachler + C. Messer

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	606	599	7
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1501	1488	13
Total			20

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023


INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Calcasieu TX Operators M. Faehler & C. Mosser Pitot No. 29U-6 CP BY
 Source Ab-3 Press Vent / Stack Meter Box No. 4 HP 1-75 IN NC Bar. Press. 29.86 IN Hg H₂O 2.4 IN.
 Date 3-27-92 Cor. Coeff. 1.0010 Nozzle No. 6322 Nozzle Dia. 2.55 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifted Water (inH ₂ O)	Des. Vol. (cf)	VAC. in Hg	Temperature (°F)						Oxygen (xv/v)
							Stack	Probe	Dyn	Impq.	Gas In	Gas Out	
-----	(1755)	536.20	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----
B-1	2.5	537.72	.30	1.01	7.66	3	93	245	253	46	89	89	20.9
2	5	539.27	.40	1.32	9.32	3.5	95				91	90	20.9
3	7.5	541.10	.43	1.42	10.4	4	95	249	258	46	93	90	20.9
4	10	543.62	.94	3.10	3.58	7.5	97				96	91	20.9
5	12.5	546.14	.98	3.25	6.19	8	95	246	257	45	98	92	20.9
6	15	547.82	.35	1.17	7.76	3	93				98	92	20.9
7	17.5	549.60	.46	1.54	9.56	4	93	244	260	45	98	92	20.9
8	20	551.63	.57	1.90	1.56	5	94				99	93	20.9
9	22.5	553.99	.84	2.79	3.98	7	98	248	263	45	100	93	20.9
10	25	556.15	.63	2.08	6.08	5.5	93				101	93	20.9
11	27.5	558.46	.73	2.49	8.37	6.5	99	252	261	46	101	94	20.9
12	30	560.70	.69	2.31	0.58	6	95				102	94	20.9
A-1	32.5	562.99	.83	2.77	2.99	7	97	249	258	46	100	94	20.9
2	35	565.70	.99	3.26	5.61	9	103				101	94	20.9
3	37.5	568.28	.98	3.77	8.23	8.5	95	245	255	46	102	94	20.9
4	40	570.97	1.08	3.60	0.98	10	97				102	95	20.9
5	42.5	573.26	.73	2.45	3.26	7	95	240	253	47	102	95	20.9
6	45	574.42	.18	.61	4.39	2	92				101	95	20.9
7	47.5	576.52	.54	1.81	6.35	5	95	238	256	47	102	95	20.9
8	50	578.46	.58	1.96	8.39	5	91				102	95	20.9
9	52.5	581.20	1.10	3.68	1.17	11	95	239	255	48	102	95	20.9
10	55	583.47	.70	2.35	3.40	7	95				101	95	20.9
11	57.5	586.05	.94	3.13	5.97	9	97	243	252	48	101	95	20.9
12	60	588.48	.89	2.98	8.47	8	95				101	95	20.9
(1856)													
θ = 60		V _s = 57.28	ΔH = 2.34								Avq. = 96.3		

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job LOUISIANA PACIFIC
 Source NO. 8 EXHAUST FAN STACK
 Test 20 Runs 1-3 Date 3/28/92
 Stack dimen. 62.75 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.82 in Hg
 Static pressure - .25 in WC
 Operators D. BRENNAN
 Pitot No. 21-C Cp .84



Particulate

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>6</u> in.	Time start: <u>8:00</u> hrs		
A	12				
	11				
	10				
	9				
	8				
	7				
	6				
	5				
	4				
	3				
	2				
	1				
A	12			.08	72
	11			.06	
	10			.35	73
	9			.79	
	8			.63	73
	7			.30	
	6			.55	70
	5			.60	
	4			.74	70
	3			.23	
	2			.12	71
	1			.13	
Temp. meas. tool & S/N:				Time end:	hrs

R or nothing = reg. manometer; S = expanded; E = electronic S-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORRIGAN, TX.) Date 3/28/92 Test 20 Run 1
 Source NG. 3 EXHAUST FAN STACK No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: ^{.005} ~~0.02~~ cfm at ¹⁵ ~~15~~ in. Hg. (vac) ☒
 Posttest: .005 cfm at 18 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) ☒ acetone probe & nozzle
4157 ☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	490	490	6.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1390	1385	13.0
Total			13.0

Integrated Gas Sampling Data: AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 0830 (HRS) Time end: 0932 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

Job counsel Pacific

2001 STAFF LISTING
 SOURCE NO. 3 EXHIBIT FAN SIDE 12
 DATE 3/28/95 1981 20 RU

Printer's Mark
Letter Box No.
Contractor's

Pitot No. 21-6 Cp 34
Bar. Press. 29.87 inHg Hg
Muzzle No. 34 Muzzle Dia

MILITARY NO. 91 HAZARD DIO 287 IN.

[illegible]

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORRIBAW TR.) Date 3/28/92 Test 20 Run 2
 Source NO. 3 EXHAUST FAN STACK No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: 0.01 cfm at 15 in. Hg. (vac) ~~0.02~~
 Posttest: 0.005 cfm at 12 in. Hg. (vac) ~~0.01~~

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone
4158 ☒ other(s) probe + nozzle
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	494	490	4.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1423	1413	10.0
Total			(14.0)

Integrated Gas Sampling Data: AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1035 (HRS) Time end: 1137 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA PACIFIC Operators D. BERGMAN & B. ACHENBACH Pitot No. 21-6 Cp .84
 Source NO. 3 SOUTHWEST FLOW STACK Meter Box No. 3 XHP 190 IN NC Bar. Press. 29.82 IN Hg H₂O 3.5X
 Date 3/28/92 Test 20 Run 2 Computer coeff. .999 Nozzle No. 52-1 Nozzle Dia 2.7 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in NC)	Drifts Meter (in NC)	Dep. Vol. (cf)	VAC. IN Hg	Temperature (°F)					Dye	Dye/Dye	Dye
							Stack	Probe	Dye	Temp.	Gas In	Gas Out		
A-12	(1035)	857.200												
	2.5	857.87	.06	.22	7.85	1.0	75	230	246	45	75	75	75	20.9
	5.0	858.44	.05	.18	8.44	1.0	75				78	77		
	7.5	859.61	.19	.70	9.60	2.0	76	232	245	45	80	77	77	20.9
	10.0	861.88	.77	2.86	1.92	8.5	76				81	78		
	12.5	863.92	.55	2.05	3.89	6.0	76	232	246	45	83	78		20.9
	15.0	865.46	.32	1.19	5.40	3.5	77				83	78		
	17.5	867.39	.55	2.05	4.37	6.0	77	230	245	44	83	79		20.9
	20.0	869.25	.47	1.75	9.19	5.0	77				83	79		
	22.5	870.80	.35	1.31	6.77	4.0	76	231	246	44	83	79		20.9
B-	25.0	871.69	.11	.41	1.66	2.0	74				83	79		
	27.5	872.31	.65	.18	2.26	1.0	74	230	243	43	82	78		20.9
	30.0	872.872	.65	.18	2.86	1.0	74				80	78		
	32.5	873.81	.12	.45	3.78	2.5	75	228	245	43	80	77		20.9
	35.0	874.45	.06	.22	4.43	1.0	75				81	78		
	37.5	875.42	.135	.50	5.41	2.5	76	229	248	43	82	78		20.9
	40.0	877.85	.84	3.13	7.84	16.0	76				84	78		
	42.5	880.18	.75	2.80	0.15	8.5	76	232	249	43	83	78		20.9
	45.0	882.39	.67	2.50	2.32	7.5	77				83	78		
	47.5	884.42	.61	2.27	4.39	7.0	77	231	246	43	83	79		20.9
	50.0	886.61	.71	2.65	6.63	8.0	76				84	79		
	52.5	888.90	.70	2.62	8.86	8.0	75	230	251	43	84	79		20.9
	55.0	890.04	.18	.67	9.00	2.0	75				84	79		
	57.5	890.85	.09	.34	6.80	2.0	74	230	248	43	83	79		20.9
	60.0	891.755	.12	.45	1.73	2.5	74				83	79		
	(1137)													
	0 = 60													
		V ₀ = 31.555		ΔH = 1.30									Avg. = 80.0	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORAL GABLE, FL.) Date 3/28/92 Test 20 Run 3
 Source NO. 8 #1 EXHAUST FAN SALON No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: .015 cfm at 17 in. Hg. (vac) ☒
 Posttest: .015 cfm at 18 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) acetone PROBE & NOZZLE
4159 ☒ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	495	492	3.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1407	1398	9.0
Total			12.0

Integrated Gas Sampling Data: AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1220 (HRS) Time end: 1322 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023


INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA Pacific Corporation, TX. Operator D. ROEDERMAN & B. ASCHENBACH Pitot No. 21-C DP 84
 Source NO. 8 PRESS VENT Meter Box No. 3 Bar. Press. 29.82 inHg H₂O 2.5X
 Date 3/28/72 Computer count. 9991 IN HC Nozzle No. 5-1 Nozzle Dia. 3/4 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifted Meter (inH ₂ O)	Des. Vol. (cf)	VAC. (inHg)	Temperatures (°F)				Gas In	Gas Out	Oxygen (XV/V)
							Stack	Probe	Oven	Impq.			
B-12	(1220)	892.40	.06	.22	3.05	1.0	76	240	255	51	75	74	20.9
11	5.0	893.06	.04	.14	3.58	1.0	76				75	74	
10	7.5	894.80	.22	.81	4.82	3.0	76	240	254	50	78	75	20.9
9	10.0	897.18	.82	3.03	7.20	11.5	77				79	75	
8	12.5	899.33	.68	2.52	9.37	10.0	77	240	255	50	79	75	20.9
7	15.0	901.47	.60	2.22	1.42	10.0	77				78	75	
6	17.5	903.44	.56	2.07	3.39	8.5	78	239	257	48	78	75	20.9
5	20.0	905.55	.66	2.44	5.53	9.0	78				78	75	
4	22.5	907.64	.64	2.37	7.64	9.0	77	237	255	48	78	75	20.9
3	25.0	908.79	.18	.67	8.76	3.0	76				78	75	
2	27.5	909.35	.05	.18	9.36	1.0	75	238	256	48	77	74	20.9
1	30.0	910.207	.10	.37	6.20	1.5	75				77	74	
A-12	32.5	910.73	.04	.14	6.73	1.0	74	240	255	47	76	74	20.9
A-17	35.0	911.25	.04	.14	1.25	1.0	76				76	74	
10	37.5	912.82	.36	1.33	2.84	5.0	76	240	254	46	76	74	20.9
9	40.0	914.94	.66	2.43	4.97	10.0	77				79	75	
8	42.5	917.04	.61	2.26	7.63	9.5	77	238	250	46	78	75	20.9
7	45.0	918.68	.36	1.33	8.62	6.0	77				77	74	
6	47.5	920.65	.60	2.21	6.66	9.0	77	237	246	45	77	74	20.9
5	50.0	922.41	.40	1.48	2.33	6.5	76				78	74	
4	52.5	923.98	.36	1.33	3.92	5.0	76	238	245	45	78	74	20.9
3	55.0	924.85	.12	.44	4.83	2.0	76				79	74	
2	57.5	925.40	.04	.14	5.36	1.0	75	235	242	45	78	74	20.9
1	60.0	925.936	.64	.14	5.90	1.0	75				78	74	
(1322)													
θ = 60		V = 33.536	ΔH = 1.27								Avg. = 75.9		

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 2 Press Vent / Stack
 Test 21 Run 0 Date 3.28.92
 Stack dimen. 62.75 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.86 in Hg
 Static pressure -.12 in WC
 Operators M. Kuehler & C. Mosser
 Pitot No. 29V-6 Cp .84



Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>6</u> in.	Time start: <u>09:30</u> hrs		
A-1	.021	1.32	7.32	.40	
2	.067	4.20	10.20	.55	
3	.118	7.40	13.40	.83	
4	.172	11.11	17.11	.93	
5	.250	15.69	21.69	.31	
6	.356	22.34	28.34	.23	
7	.644	40.41	46.41	.30	
8	.750	47.06	53.06	.67	↑
9	.823	51.64	57.64	.90	
10	.882	55.35	61.35	.71	84
11	.933	58.55	64.55	.90	
12	.979	61.43	67.43	.89	↓
B-1				.12	
2				.20	
3				.30	
4				.93	
5				.20	
6				.61	
7				.32	
8				.44	
9				.59	
10				.60	
11				.62	
12				.23	
Temp. meas. tool & S/N: <u>PDT-3 / TC</u>				Time end: <u> </u> hrs	

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific Flouring Co. TA Date 3-28-92 Test 21 Run 1
 Source Al. 2 Press Vent 1 Stack No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: 1A

Sample Train Leak Checks:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No. of filters used: NA Recovery solvent(s):
☐ acetone
☒ other(s) Me Cl₂
 No. of probe wash bottles: 1
 Sample recovered by: Mikheiler + C. Messer

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	604	600	4
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1422	1405	17
Total			21

Integrated Gas Sampling Data: NA (Ambient)

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Carriagan TX Operators M. Kaehler + C. M. Sasser Pitot No. 24V-6 Cp .84
 Source Ab. 2 Press Vent / Stack Meter Box No. 4 HP 1.25 IN MC Bar. Press. 27.83 IN Hg H2O X
 Date 3-28-82 1982 21 Run 1 Gasometer conf. 100% Nozzle No. Glass Nozzle Dia. 2.35 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Orifice Meter (in H ₂ O)	Des. Vol. (cf)	VAC. in Hg	Temperature (°F)						Oxygen (xv/v)
							Stack	Probe	Oven	Wtg.	Gas In	Gas Out	
B-12	2.5	596.80	.73	2.40	9.00	6	86	238	240	47	75	75	20.9
11	5	599.02	.62	2.04	1.03	5	85				77	75	20.9
10	7.5	601.10	.60	1.99	3.05	5	81	242	247	46	80	76	20.9
9	10	603.15	.59	1.95	5.05	5	85				81	77	20.9
8	12.5	605.11	.44	1.48	6.79	4	78	245	250	46	83	78	20.9
7	15	606.83	.32	1.08	8.28	3	78				84	78	20.9
6	17.5	608.37	.61	2.06	0.33	5	77	244	253	45	84	78	20.9
5	20	610.37	.70	2.36	2.54	6	77				86	79	20.9
4	22.5	612.54	.93	3.14	5.07	7.5	78	246	253	45	88	80	20.9
3	25	615.13	.30	1.01	6.52	3	80				88	81	20.9
2	27.5	616.70	.20	.68	7.71	2	80	245	256	45	88	81	20.9
1	30	617.82	.12	.41	8.63	2	76				87	80	20.9
A-12	32.5	618.75	.89	2.98	1.11	7.5	83	248	257	46	86	81	20.9
11	35	621.25	.90	3.02	3.60	7.5	83				89	82	20.9
10	37.5	623.72	.71	2.38	5.81	6	86	247	260	45	90	82	20.9
9	40	625.88	.90	3.04	8.32	7.5	82				92	83	20.9
8	42.5	628.41	.67	2.27	0.49	6	83	245	262	46	92	83	20.9
7	45	630.30	.30	1.03	1.95	3	75				91	83	20.9
6	47.5	631.99	.23	.78	3.23	2.5	81	249	261	46	90	83	20.9
5	50	633.35	.31	1.05	4.71	3	79				90	83	20.9
4	52.5	634.75	.93	3.19	7.28	8	79	252	258	47	92	84	20.9
3	55	637.22	.83	2.83	9.70	8	78				93	84	20.9
2	57.5	639.64	.55	1.88	1.68	5	78	251	258	47	93	85	20.9
1	60	641.73	.38	1.31	3.33	9.5	76				93	85	20.9
(0940)													
0 = 60		V = 46.49		CH 193							Av. = 83.9		

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-28-92 Test 21 Run 2
 Source No. 2 Press Vent / Steel No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 2 0.02 cfm at 12 in. Hg. (vac) ☒

Particulate Catch Data:

No. of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) Me Cl-
 No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: M. Kachler & C. Masser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Inpinger No. 1	603	600	3
Inpinger No. 2			
Inpinger No. 3			
Condenser			
Desiccant	1433	1417	16
Total			19

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operators: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific/Curran TX Operators McGee, G. & C. Moser Pitot No. 29V-6 CP 181
 Source Ab. 2 Press Vent / Stack Meter Box No. 4 Bar. Press. 29.93 inHg H₂O 2 X
 Date 3-28-92 Test 21 Run 2 Computer Code 1.00.00 Nozzle No. Class Nozzle Dia. 237 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifts Meter (inH ₂ O)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)					Oxygen (xv/v)
							Stack	Probe	Dye	Inpg.	Gas In	Gas Out
A-12	2.5	673.60	.55	1.81	5.53	5	85	245	253	47	79	28
11	5	645.55	.50	1.64	7.36	5	83				81	79
10	7.5	647.45	.48	1.58	9.16	4	82	248	258	47	83	79
9	10	651.64	.72	2.38	1.37	6.5	79				85	80
8	12.5	653.29	.49	1.62	3.20	4	81	247	260	47	86	80
7	15	658.20	.45	1.50	4.95	4	79				87	81
6	17.5	656.22	.20	.66	6.13	2	81	249	262	46	87	81
5	20	657.78	.37	1.24	7.73	3.5	80				87	81
4	22.5	660.42	1.06	3.51	0.41	9.5	81	252	264	46	89	82
3	25	662.93	.90	2.99	2.90	8	81				90	82
2	27.5	665.20	.75	2.51	5.17	7	79	252	260	46	91	83
1	30	667.51	.75	2.52	7.46	7	77				91	83
13-12	32.5	669.47	.56	1.88	9.44	5	78	249	258	47	84	83
11	35	671.50	.60	2.01	1.47	5	78				90	83
10	37.5	673.55	.58	1.94	3.48	5	79	250	255	48	91	84
9	40	675.53	.57	1.90	5.47	5	81				92	84
8	42.5	677.61	.64	2.15	7.58	5.5	79	247	256	48	92	84
7	45	679.25	.43	1.45	9.32	4	77				92	84
6	47.5	680.70	.15	.81	9.64	3	81	250	259	49	92	84
5	50	682.40	.41	1.37	2.33	4	80				92	84
4	52.5	684.49	.66	2.22	4.48	6	78	245	258	49	93	85
3	55	686.97	.90	3.03	6.98	8	77				94	85
2	57.5	688.37	.25	.84	8.31	3	79	247	260	50	93	85
1	60	689.32	.13	.44	9.27	2	76				91	85
(1136)												
0 = 60		V ₀ = 45.72		ΔH 1.03							Avg. = 85.7	

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corroguard Date 3-28-92 Test 21 Run 3
 Source W. 2 River / Stack No. of traverse points 24
 Method 0211 Filter holder: NA Filter type: NA

Sample Train Leak Checks:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: { 0.02 cfm at 12 in. Hg. (vac) ☒

Particulate Catch Data:

No. of filters used: NA Recovery solvent(s):
☐ acetone
☒ other(s) MeCl₂
 No. of probe wash bottles: 1
 Sample recovered by: M. LaMotte & C. Mosser

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Inpinger No. 1	597	595	(2)
Inpinger No. 2			
Inpinger No. 3			
Condenser			
Desiccant	1435	1422	17
Total			15

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Materials: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operators: _____
 S/N of O₂ Analyzer used to monitor train outlets: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Lowiana fac. h. / Georgetown, TX Operator Mr. Gehlert, C. Mosser Pitot No. 240-6 Cp 1.87
 Sample 20-2 10025 Meter 1500 / 5000 Water Box No. 29-83 Bar. Press. 29.83 inHg H₂O 2 x
 Date 8-28-92 Test 21 Run 3 Counter coeff. 7.0000 IN NC Nozzle No. 6452 Nozzle Dia. 232 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifted Water (inH ₂ O)	VAC. Vol. (cf)	VAC. inHg	Temperature (°F)						Oxygen (xv/v)	
							Stack	Probe	Oven	Ingh.	Gas In	Gas Out		
B-12	(1220)	689.80												
	2.5	691.97	.68	2.26	1.96	5.5	82	245	256	47	78	77		20.9
11	5	694.15	.70	2.29	4.12	6	82				80	78		20.9
10	7.5	696.37	.72	2.36	6.31	6	83	248	260	47	83	79		20.9
9	10	698.50	.63	2.07	8.37	6	83				84	80		20.9
8	12.5	699.81	.27	.89	9.72	3	85	246	260	46	85	80		20.9
7	15	701.62	.50	1.64	1.56	4	85				85	80		20.9
6	17.5	703.80	.75	2.44	3.83	7	78	249	263	45	88	81		20.9
5	20	706.14	.84	2.78	6.22	7.5	82				89	82		20.9
4	22.5	707.72	.29	.97	7.64	3	77	247	260	45	89	82		20.9
3	25	708.81	.17	.57	8.73	2	79				88	82		20.9
2	27.5	709.71	.12	.40	9.64	2	81	251	257	46	87	81		20.9
1	30	710.56	.10	.33	10.47	2	82				87	81		20.9
A-12	32.5	712.53	.55	1.82	2.41	5	83	248	255	45	86	81		20.9
11	35	714.75	.75	2.50	4.68	6.5	78				89	82		20.9
10	37.5	716.98	.73	2.42	6.92	6.5	82	245	256	46	90	83		20.9
9	40	719.60	1.00	3.32	9.53	9	82				91	83		20.9
8	42.5	721.64	.59	1.98	1.56	6	78	247	258	46	91	83		20.9
7	45	722.92	.72	.73	2.80	2	83				90	83		20.9
6	47.5	724.66	.45	1.50	4.56	4	83	245	257	46	90	83		20.9
5	50	727.28	1.03	3.42	7.21	8	82				91	83		20.9
4	52.5	729.68	.85	2.84	9.64	8	79	244	259	47	92	83		20.9
3	55	732.10	.77	2.55	1.94	7	86				92	84		20.9
2	57.5	734.22	.68	2.27	4.11	6	81	247	261	48	92	84		20.9
1	60	735.96	.46	1.54	5.90	4	80				91	84		20.9
	(1324)													
	0 = 60													
		V = 46.16		1.91										
											Avg. = 81.2			

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job LP / CORRIGAN TX.Source No. 2 PressureTest 23 Run 1-3 Date 3/28/92Stack dimen. 62.75 IN.Dry bulb °F Wet bulb °FManometer: ☒ Reg. ☐ Exp. ☐ Elec.Barometric pressure 29.82 in HgStatic pressure -1.12 in WCOperators D. BRENNAN + B. ASHERBACHPitot No. 21-6 Cp 84Schematic of
Cross Section

Particulate

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	in.	Time start: hrs	
A	1				
	2				
	3				
	4				
	5				
	6				
	7				
	8				
	9				
	10				
	11				
	12				
B	1				
	2				
	3				
	4				
	5				
	6				
	7				
	8				
	9				
	10				
	11				
	12				
Temp. meas. tool & S/N:				Time end: hrs	

R or nothing = reg. manometer; S = expanded; E = electronic 9-392.1

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC Date 3/28/92 Test 23 Run 1
 Source NO 2 PRESS VENT 9-TALL No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" GF

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.05 cfm at 12 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) ☒ acetone PREPARE + NOZZLE
4160 ☐ other(s) _____
 No. of probe wash bottles: _____
 Sample recovered by: _____

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	499	498	1.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1434	1423	12.0
Total			13.0

Integrated Gas Sampling Data: AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1415 (HRS) Time end: 1517 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA Pacific (CORLEON), TX Operators D. Beggs + B. Ascaraga HP Tit No. 21-6 CP 84
 Source NO. 2 PROCESS VENT STACK Meter Box No. 4 Bar. Press. 29.82 in Hg H2O 1.00X
 Date 3/28/82 1982 Run 1 Computer coeff. 1.00 1.25 IN NC Nozzle No. 8.4 Nozzle Dia 2.271 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inHG)	Drifts Meter (inHG)	Dee. Vol. (cf)	VAC. inHg	Temperatures (°F)						Dye (x/v/v)
							Stack	Probe	Oven	Ingr.	Gas In	Gas Out	
A-12	(1415)	736.222	.63	2.13	0.31	7.5	85	232	244	46	80	77	20.9
"	5.0	738.35	.80	2.68	0.61	8.0	88				81	77	
10	7.5	740.69	.52	1.76	2.51	5.0	84	235	245	45	86	80	20.9
9	10.0	742.57	.78	2.65	4.88	8.0	85				88	81	
8	12.5	744.84	.54	1.84	6.83	6.0	85	233	246	45	89	81	20.9
7	15.0	746.84	.35	1.19	8.40	4.0	86				89	82	
6	17.5	748.46	.20	.62	9.59	1.0	86	234	248	45	90	82	20.9
5	20.0	751.94	.79	2.69	1.95	8.0	87				90	82	
4	22.5	754.41	.88	2.98	4.43	9.5	89	234	247	42	91	83	20.9
3	25.0	756.61	.67	2.26	6.60	7.5	94				91	83	
2	27.5	758.46	.47	1.60	8.42	5.0	89	236	245	42	91	83	20.9
1	30.0	759.366	.12	.40	9.34	1.0	92				89	82	
B-12	32.5	761.39	.62	2.10	1.42	7.0	90	235	246	42	90	83	20.9
"	35.0	763.72	.78	2.65	3.76	8.0	88				91	84	
10	37.5	765.80	.55	1.86	5.73	6.0	93	233	248	40	91	83	20.9
9	40.0	767.81	.60	2.02	7.78	7.0	95				91	84	
8	42.5	769.50	.41	1.39	9.47	4.0	93	234	247	39	91	83	20.9
7	45.0	770.88	.27	.91	6.85	3.0	95				90	83	
6	47.5	773.10	.74	2.51	3.13	7.5	90	234	250	39	90	83	20.9
5	50.0	775.43	.79	2.68	5.48	8.0	90				92	84	
4	52.5	777.95	.88	2.94	7.95	9.5	98	232	251	37	92	84	20.9
3	55.0	779.56	.35	1.18	9.52	4.0	93				91	82	
2	57.5	781.04	.31	1.06	10.1	3.5	87	230	246	36	91	84	20.9
1	60.0	782.016	.13	.44	1.97	1.0	84				90	83	
(1517)													
Σ = 60		45.794	4.18								Av. = 88.8		

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORAL GULF, TX.) Date 3/28/92 Test 23 Run 2
 Source NO. 2 PRESS VENT STACK No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: .005 cfm at 17 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) ☒ acetone PROBE + NOZZLE
4175 ☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>500</u>	<u>498</u>	<u>2.0</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1413</u>	<u>1403</u>	<u>10.0</u>
Total			<u>12.0</u>

Integrated Gas Sampling Data:

AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1610 (HRS) Time end: 1719 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA PACIFIC Operator D. BRENNAN + B. A. SCHWARTZ Pitot No. 21-6 CP 5.1
 Source NO. 2 04253 12.00 STAKE Meter Box No. 4 Bar. Press. 29.82 inHg H₂O 1.8 x
 Date 3/28/42 1961 23 Non 2 Computer Cor. 4 1.20 Nozzle No. 2-4 Nozzle Dia. 2.21 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifted Meter (inWC)	Des. Vol. (cf)	VAD. inHg	Temperature (°F)					Oxygen (xv/v)
							Stack	Probe	Dry	Wet	Gas/Dut	
B-12	16.0	982.70	.57	1.93	4.69	7.0	85	239	261	58	75	26.9
11	5.0	784.70	.66	2.20	6.80	7.5	88				81	77
10	7.5	786.82	.68	2.28	8.96	8.0	90	242	263	56	82	78
9	10.0	791.34	.84	2.82	1.36	10.0	89				85	78
8	12.5	793.23	.47	1.60	3.17	6.0	85	243	260	55	85	79
7	15.0	794.42	.21	.71	4.39	2.0	87				85	79
6	17.5	795.87	.30	1.00	5.83	4.0	96	245	258	55	85	79
5	20.0	798.08	.77	2.57	8.12	10.5	95				86	79
4	22.5	800.54	.89	2.98	0.60	12.0	95	244	256	53	87	80
3	25.0	802.12	.34	1.15	2.14	5.0	89				87	80
2	27.5	803.43	.23	.78	3.42	3.5	88	245	254	51	87	80
1	30.0	804.67	.20	.68	4.60	3.0	88				86	80
A-12	32.5	806.94	.80	2.74	6.96	12.0	88	245	251	50	87	80
11	35.0	809.53	1.05	3.57	9.17	15.5	82				88	80
10	37.5	812.40	1.04	3.50	2.35	15.5	92	248	253	50	86	80
9	40.0	814.75	1.08	3.63	5.08	15.5	92				80	78
8	42.5	817.01	.58	1.96	7.08	8.0	86	250	252	50	81	78
7	45.0	818.87	.50	1.69	8.94	7.0	88				82	78
6	47.5	820.33	.26	.87	0.28	4.0	89	252	255	50	82	78
5	50.0	822.51	.72	2.43	2.51	10.0	87				85	79
4	52.5	825.16	1.00	3.37	5.14	14.0	89	251	259	48	88	80
3	55.0	827.55	.80	2.72	7.51	13.0	87				88	81
2	57.5	829.59	.58	1.97	9.52	8.5	89	246	261	48	88	81
1	60.0	831.34	.45	1.52	1.30	7.0	91				89	81
(17.92)												
Σ = 60		Σ = 48.614		Σ = 2.11							Avg. = 81.9	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job LOUISIANA PACIFIC (CORRIWON, TX.) Date 3/28/92 Test 23 Run 3
 Source NO. 2 PRESS VENT STACK No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" G.F.

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒ LEAK CHECK BELOW 4%
 Posttest: 0.04 cfm at 12 in. Hg. (vac) ☒ OF SAMPLING RATE

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s) _____
4176 ☐ acetone PHASE 2 NO. 2
☐ other(s) _____
 No. of probe wash bottles: 1
 Sample recovered by: D. BRENNAN

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	499	497	2.0
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1429	1413	16.0
Total			18.0

Integrated Gas Sampling Data: AMBIENT AIR

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: 1742 (HRS) Time end: 1845 (HRS)
 Sampling rate: _____ cc/min Operator: D. BRENNAN
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023


INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job LOUISIANA PACIFIC - COASTAL TR.Source NO 2 PRESS VENT STACKDate 4/3/2002 1001 23 Run 3Operator D. GreenwayMeter Box No. 4Computer Edit. 1.001Pitot No. 21-6Bar. Press. 29.32 inHgH₂O 7.5 xNozzle Dia 29 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifts Meter (inH ₂ O)	Obs. Vol. (cf)	VAC. inHg	Temperature (°F)						Oxygen (xv/v)	
							Stack	Probe	Dye	Imp.	Gas In	Gas Out		
A-12	1742	831.60												
	2.5	833.73	.68	2.30	3.77	9.0	90	210	255	46	73	77		20.9
11	5.0	835.88	.65	2.18	5.88	7.0	92				80	78		
10	7.5	837.81	.52	1.76	7.78	6.0	88	212	256	45	81	78		20.9
9	10.0	840.32	.93	3.13	0.30	12.0	89				84	79		
8	12.5	842.30	.54	1.83	2.24	7.0	89	245	255	45	85	79		20.9
7	15.0	843.83	.33	1.12	3.77	5.0	88				85	79		
6	17.5	845.16	.26	.89	5.12	3.5	86	214	259	43	86	80		20.9
5	20.0	847.50	.82	2.80	7.52	11.0	86				86	80		
4	22.5	850.63	.89	3.05	6.02	12.0	85	210	259	42	88	81		20.9
3	25.0	852.35	.77	2.64	2.36	10.0	85				88	81		
2	27.5	854.46	.61	2.08	4.43	9.0	88	242	260	40	88	81		20.9
1	30.0	855.475	.15	.51	5.16	1.0	90				88	81		
B-12	32.5	857.72	.70	2.39	4.68	10.5	89	245	262	39	89	82		20.9
11	35.0	860.67	.82	2.76	0.07	12.0	96				90	82		
10	37.5	862.12	.54	1.84	2.02	8.0	92	244	262	39	90	82		20.9
9	40.0	864.18	.61	2.09	4.11	8.0	87				90	83		
8	42.5	865.80	.38	1.31	5.76	6.0	85	244	259	38	90	83		20.9
7	45.0	867.12	.24	.83	7.07	4.0	86				90	83		
6	47.5	869.34	.68	2.33	9.27	9.0	89	240	256	38	90	83		20.9
5	50.0	871.35	.59	2.01	1.30	9.0	93				92	84		
4	52.5	873.85	.90	3.08	3.83	13.0	90	238	255	38	92	84		20.9
3	55.0	875.30	.29	1.00	5.27	4.0	88				91	84		
2	57.5	876.32	.14	.18	6.28	1.0	86	236	255	37	90	84		20.9
1	60.0	877.516	.11	.38	7.17	1.0	86				89	83		
	(158.75)													
V ₁ = 45.946														Avg. = 81.5
0 = 60														

INTERPOL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 3 Exhaust Fan Vent/Stack
 Test 24 Run 0 Date 3-28-92
 Stack dimen. 62.75 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.83 in Hg
 Static pressure - .25 in WC
 Operators M. Kuebler & C. MASON
 Pitot No. 29U-6 Cp .84



Formaldehyde

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: 6 in.	Time start: 1400hrs		
A-1	.021	1.32	7.32	.05	
2	.067	4.20	10.20	.10	
3	.118	7.40	13.40	.40	
4	.177	11.11	17.11	.46	
5	.250	15.69	21.69	.73	
6	.356	22.34	28.34	.48	
7	.644	40.41	46.41	.85	
8	.750	47.06	53.06	.94	
9	.823	51.64	57.64	.75	↑
10	.882	55.35	61.35	.43	
11	.933	58.55	64.55	.10	73
12	.979	61.43	67.43	.05	
B-1				.09	↓
2				.18	
3				.70	
4				.75	
5				.63	
6				.74	
7				.85	
8				.90	
9				.48	
10				.47	
11				.10	
12				.13	
Temp. meas. tool & S/N: <u>PDI-3/TC</u>		Time end: <u> </u> hrs			

R or nothing = reg. manometer; S = expanded; E = electronic S-392.1

INTERFOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pct. Ac / Cocolayan, TX Date 3-28-92 Test 24 Run 1
 Source No. 8 Exhaust Fan Vent / Stack No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 12 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) MeCl₂
 No. of ^{EWB} probe wash bottles: 1
 Sample recovered by: M. Kaehler & C. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	592	589	3
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1449	1433	16
Total			19

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX Operator McKaeble & C. Messer Pitot No. 210-6 Dp .89
 Source Ab. Exhaust Stack Meter Box No. 3 HP 1.90 IN WC Bar. Press. 29.83 IN Hg H2O 25 X
 Date 3-28-92 Correlation 100% Meter 1 No. 1 Nozzle No. 6455 Nozzle Dia. 235 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifts Meter (inWC)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)						Oxygen (xv/v)
							Stack	Probe	Duct	lagg.	Gas In	Gas/Dut	
A-12 (1416)													
	2.5	926.70	.10	.36	7.52	2	75	240	250	43	75	74	20.9
11	5	927.52	.08	.29	8.26	2	76				76	74	20.9
10	7.5	928.24	.44	1.60	9.99	4	73	242	253	43	78	74	20.9
9	10	929.93	.84	3.03	2.37	8	75				80	78	20.9
8	12.5	932.33	.82	2.95	4.72	8	75	245	250	44	80	77	20.9
7	15	934.70	.83	3.01	7.10	8	75				80	75	20.9
6	17.5	937.08	.42	1.52	8.79	4	76	247	252	44	80	75	20.9
5	20	938.72	.74	2.68	1.04	7	75				81	75	20.9
4	22.5	941.00	.43	1.56	2.76	4	75	245	255	44	81	76	20.9
3	25	942.70	.38	1.38	4.38	4	74				81	76	20.9
2	27.5	944.35	.12	.43	5.29	2	74	248	256	45	81	76	20.9
1	30	945.32	.06	.22	5.94	2	72				80	76	20.9
B-12 (1518)													
	32.5	945.98	.13	.47	6.87	2	72	245	259	46	80	75	20.9
11	35	947.98	.15	.54	7.90	2	73				81	76	20.9
10	37.5	948.72	.10	.36	8.94	2	73	248	257	46	80	76	20.9
9	40	950.58	.51	1.86	0.61	5	73				81	76	20.9
8	42.5	953.37	.95	3.44	3.16	9	75	246	259	47	82	76	20.9
7	45	955.45	.82	2.98	5.53	8	74				82	77	20.9
6	47.5	957.73	.75	2.73	7.80	8	74	243	262	47	82	77	20.9
5	50	959.95	.63	2.30	9.88	6.5	74				82	77	20.9
4	52.5	962.20	.72	2.63	2.11	6.5	72	246	260	48	82	77	20.9
3	55	964.40	.74	2.71	4.37	7	72				82	77	20.9
2	57.5	965.63	.10	.73	5.55	2	73	248	260	48	82	77	20.9
1	60	966.38	.09	.33	6.35	2	72				81	77	20.9
Σ = 39.68 Avg. = 77.9													
θ = 60													

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX Date 3-28-92 Test 24 Run 2
 Source No. 9 Exhaust Fan Vent / Stack No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 12 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s)
☐ acetone
☒ other(s) Me Cl₂
 No. of ~~probe~~ ^{Imp} wash bottles: 1
 Sample recovered by: M. Kiedler & L. Messer

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>602</u>	<u>600</u>	<u>2</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1349</u>	<u>1359</u>	<u>10</u>
Total			<u>12</u>

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Pacific Operator M. Koehler PC-Mozzor Pitot No. 2906 Cp 8V
 Source Boiler Exhaust Fan Vent / Stack Meter Box No. 03 HP 1.90 IN WC Bar. Press. 29.83 IN Hg H2O 2.2 X
 Date 3-20-92 Test 24 Run 2 Gasometer const. 9991 Nozzle No. 6032 Nozzle Dia. 2.52 IN

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Orifice Meter (inWC)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)						Oxygen (xv/v)	
							Stack	Probe	Duct	Ingr.	Gas In	Gas Out		
B-12														
13-12	2.5	966.70	.10	.36	7.52	2	72	240	253	44	72	72	20.9	
11	5	967.48	.07	.25	8.21	2	72				73	72	20.9	
10	7.5	968.19	.49	1.75	0.02	4	72	243	256	44	75	73	20.9	
9	10	970.00	.75	2.68	2.26	6.5	73				76	73	20.9	
8	12.5	972.21	.85	3.04	9.64	8	73	243	258	44	77	74	20.9	
7	15	974.60	.72	2.58	6.84	7	73				78	74	20.9	
6	17.5	976.77	.65	2.34	8.93	6	72	247	255	45	78	74	20.9	
5	20	978.84	.76	2.73	1.19	7	73				79	74	20.9	
4	22.5	981.12	.70	2.52	3.37	6.5	72	245	257	46	79	75	20.9	
3	25	983.30	.18	.65	4.47	2	73	248	256	46	79	74	20.9	
2	27.5	984.52	.11	.39	5.34	2	73				78	74	20.9	
1	30	985.37	.09	.32	6.13	2	72				79	75	20.9	
A-12														
11	32.5	986.11	.16	.57	7.17	2	74	246	259	45	78	74	20.9	
11	35	987.16	.10	.36	7.99	2	74				79	75	20.9	
10	37.5	989.02	.63	2.26	0.05	6	74	243	262	45	81	75	20.9	
9	40	990.02	.85	3.04	2.44	7.5	76				82	76	20.9	
8	42.5	992.42	.87	3.12	4.87	8	75	245	260	46	81	76	20.9	
7	45	994.79	.42	1.51	6.56	4	75				81	76	20.9	
6	47.5	996.58	.64	2.30	8.04	6	74	247	258	47	81	76	20.9	
5	50	998.60	.63	2.27	0.71	6	74				81	76	20.9	
4	52.5	1000.73	.51	1.84	2.58	5	73	249	260	47	82	76	20.9	
3	55	1002.64	.22	.79	3.81	2.5	73				81	76	20.9	
2	57.5	1003.90	.08	.29	4.55	2	71	246	257	48	80	76	20.9	
1	60	1004.63	.07	.25	5.24	2	71				80	76	20.9	
(1702)														
θ = 60		V _s = 38.60	ΔH = 1.57		Avg. = 76.7									20.9

INTERFOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job Louisiana Pacific / Corrigan, TX
 Source No. 9 Exhaust Fan Vent / Stair
 Method 0011 Filter holder: NA

Date 3-20-92 Test 24 Run 3
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 20.02 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

NA ☐ acetone
☒ other(s) MeCl₂

No. of ^{Imp} probe wash bottles: 1
 Sample recovered by: Michael Miller & L. Mosser

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>596</u>	<u>598</u>	<u>(2)</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1459</u>	<u>1449</u>	<u>10</u>
Total			<u>9</u>

Integrated Gas Sampling Data: NA / Ambient

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job Louisiana Route / Caravan, TX Operator Michael C. Masse Pitot No. 290-6 Cp 84
 Source Exhaust Fan Vent / Stack Motor Box No. 3 Bar. Press. 29.83 inHg H2O 2.5 X
 Date 3-28-82 Exhaust Fan Vent / Stack Computer Count 9991 Nozzle No. 6455 Nozzle Dia. 257 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Orifice Meter (inH ₂ O)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)				Gas/Dut	Oxygen (xv/v)
							Stack	Probe	Oven	Inpp.	Gas/In	
A-12	2.5	5.60	.13	.47	6.54	2	72	243	255	45	73	20.9
11	5	6.55	.09	.32	7.33	2	72				74	20.9
10	7.5	7.35	.10	.36	8.15	2	73	245	253	45	75	20.9
9	10	8.15	.85	3.07	0.55	8	73				78	20.9
8	12.5	12.95	.15	2.72	2.80	7	73	248	256	46	77	20.9
7	15	14.82	.53	1.92	4.71	5	74				79	20.9
6	17.5	16.96	.73	2.65	6.94	6	74	247	255	46	80	20.9
5	20	18.87	.50	1.82	8.79	5	73				80	20.9
4	22.5	20.51	.41	1.50	0.47	4	73	250	258	45	81	20.9
3	25	21.68	.20	.73	1.65	2.5	72				81	20.9
2	27.5	22.93	.07	.25	2.35	2	71	248	260	45	80	20.9
1	30	22.99	.05	.18	2.94	2	71				79	20.9
B-12	32.5	23.63	.10	.36	3.77	2	72	245	261	46	79	20.9
11	35	24.45	.05	.18	4.36	2	72				80	20.9
10	37.5	26.24	.53	1.94	6.27	5	72	244	261	47	82	20.9
9	40	28.72	.86	3.14	8.71	8	73				83	20.9
8	42.5	31.1	.84	3.06	1.11	8	74	242	257	47	83	20.9
7	45	33.30	.70	2.56	3.31	7	73				93	20.9
6	47.5	35.46	.65	2.38	5.43	6	73	245	255	46	93	20.9
5	50	37.70	.74	2.70	2.69	6.5	74				93	20.9
4	52.5	40.03	.80	2.92	0.04	7	74	247	258	46	83	20.9
3	55	41.53	.50	1.10	1.49	3	72				83	20.9
2	57.5	42.50	.12	.44	2.41	2	71	245	256	46	83	20.9
1	60	43.42	.13	.48	3.36	2	71				83	20.9
	(1847)											
	θ = 60	∑ = 37.82		ΔH = 4.55							Avg. = 78.2	

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / Oregon
Team Leader B. Brennan
Date Submitted 3-24-92
Test No. 1
Date of Analysis 3-24-92

Source No. 1 Dryer
Test Site studs
Date of Test 3-24-92
No. of Runs Completed 3
Technician Mark Hearn

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F _o
			Zero Pt.	After CO ₂	After O ₂			
1/1	☒ B ☐ F	1	0.00	1.60	20.70	1.60	19.10	1.125
		2	0.00	1.60	20.70	1.60	19.10	1.125
		Avg				1.60	19.10	
1/2	☒ B ☐ F	1	0.00	1.40	20.80	1.40	19.40	1.000
		2	0.00	1.40	20.80	1.40	19.40	1.000
		Avg				1.40	19.40	
1/3	☒ B ☐ F	1	0.00	1.50	20.75	1.50	19.25	1.100
		2	0.00	1.50	20.75	1.50	19.25	1.100
		Avg				1.50	19.25	
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F_o Within EPA M-3 Guidelines
for fuel type.

Where F_o = $\frac{20.9 - O_2}{CO_2}$

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

EPA Method 3 Guidelines

Fuel Type	F _o Range
Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
D-1 Wood/Wood Bark	1.000-1.130

Interpoll Laboratories
(612) 786-6020

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / College, TX
Team Leader M. Kuehler
Date Submitted 3-24-92
Test No. 2
Date of Analysis 3-24-92

Source No. 1 Dryer
Test Site Stash
Date of Test 3-24-92
No. of Runs Completed 3
Technician Mark Kuehler

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F _o
			Zero Pt.	After CO ₂	After O ₂			
2/1	☒ B ☐ F	1	0.00	2.20	20.70	2.20	18.50	1.091
		2	0.00	2.20	20.70	2.20	18.50	1.091
		Avg				2.20	18.50	
2/2	☒ B ☐ F	1	0.00	2.10	20.80	2.10	18.70	1.048
		2	0.00	2.10	20.80	2.10	18.70	1.048
		Avg				2.10	18.70	
2/3	☒ B ☐ F	1	0.00	2.40	20.70	2.40	18.30	1.083
		2	0.00	2.40	20.70	2.40	18.30	1.083
		Avg				2.40	18.30	
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F_o Within EPA M-3 Guidelines
for fuel type.

Where $F_o = \frac{20.9 - O_2}{CO_2}$

EPA Method 3 Guidelines

Fuel Type	F _o Range
Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
Wood/Wood Bark	1.000-1.130

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / Corrigan, TX
Team Leader Mike Roehler
Date Submitted 3-24-92
Test No. 4
Date of Analysis 3-24-92

Source No. 1 Diesel
Test Site Stack
Date of Test 3-24-92
No. of Runs Completed 3
Technician Mark Roehler

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F _o
			Zero Pt.	After CO ₂	After O ₂			
4/1	☒ B ☐ F	1	0.00	1.80	20.70	1.80	18.90	1.111
		2	0.00	1.80	20.70	1.80	18.90	1.111
		Avg				1.80	18.90	
4/2	☒ B ☐ F	1	0.00	2.00	20.70	2.00	18.70	1.100
		2	0.00	2.00	20.70	2.00	18.70	1.100
		Avg				2.00	18.70	
4/3	☒ B ☐ F	1	0.00	2.20	20.90	2.20	18.70	1.000
		2	0.00	2.20	20.90	2.20	18.70	1.000
		Avg				2.20	18.70	
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F_o Within EPA M-3 Guidelines
for fuel type.

Where $F_o = \frac{20.9 - O_2}{CO_2}$

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

EPA Method 3 Guidelines
Fuel Type F_o Range

Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
D-3 Wood/Wood Bark	1.000-1.130

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / Corrigan, TX
Team Leader P. Brennan
Date Submitted 3-25-92
Test No. 5
Date of Analysis 3-25-92

Source No. 2A Dryer
Test Site Stack
Date of Test 3-25-92
No. of Runs Completed 3
Technician Mark Buehle

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F ₀
			Zero Pt.	After CO ₂	After O ₂			
5/1	☒ B ☐ F	1	0.00	3.00	20.90	3.00	17.90	1.000
		2	0.00	3.00	20.90	3.00	17.90	1.000
		Avg				3.00	17.90	
5/2	☒ B ☐ F	1	0.00	3.00	20.80	3.00	17.80	1.033
		2	0.00	3.00	20.80	3.00	17.80	1.033
		Avg				3.00	17.80	
5/3	☒ B ☐ F	1	0.00	2.80	20.80	2.80	18.00	1.036
		2	0.00	2.80	20.80	2.80	18.00	1.036
		Avg				2.80	18.00	
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F₀ Within EPA M-3 Guidelines
for fuel type.

Where $F_0 = \frac{20.9 - O_2}{CO_2}$

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

D-4

EPA Method 3 Guidelines

Fuel Type	F ₀ Range
Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.936
Propane	1.434-1.586
Butane	1.405-1.553
Wood/Wood Bark	1.000-1.130

Interpoll Laboratories
(612) 786-6020

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / Corrigan, TX
Team Leader M. Kaehler
Date Submitted 3-25-92
Test No. 6
Date of Analysis 3-25-92

Source No. 2 B Dryer
Test Site Stack
Date of Test 3-25-92
No. of Runs Completed 3
Technician Mark Kaehler

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F _O
			Zero Pt.	After CO ₂	After O ₂			
6/1		1	0.00	2.80	20.60	2.80	17.80	1.107
		2	0.00	2.80	20.60	2.80	17.80	1.107
		Avg				2.80	17.80	
6/2		1	0.00	2.90	20.70	2.90	17.80	1.069
		2	0.00	2.90	20.70	2.90	17.80	1.069
		Avg				2.90	17.80	
6/3		1	0.00	2.90	20.60	2.90	17.70	1.103
		2	0.00	2.90	20.60	2.90	17.70	1.103
		Avg				2.90	17.70	
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						

- ☐ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F_O Within EPA M-3 Guidelines
for fuel type.

Where $F_O = \frac{20.9 - O_2}{CO_2}$

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

D-5

EPA Method 3 Guidelines	
Fuel Type	F _O Range
Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
Wood/Wood Bark	1.000-1.130

Interpoll Laboratories
(612) 786-6020

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / Corrigan, TX
Team Leader D. Beegham
Date Submitted 3-25-92
Test No. 8
Date of Analysis 3-25-92

Source No. 2A Dryer
Test Site Stack
Date of Test 3-25-92
No. of Runs Completed 2
Technician Mark Bachler

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F _o
			Zero Pt.	After CO ₂	After O ₂			
8/1		1	0.00	2.80	20.80	2.80	18.00	1.036
		2	0.00	2.80	20.60	2.80	18.00	1.036
		Avg				2.80	18.00	
8/2		1	0.00	2.90	20.70	2.90	17.80	1.069
		2	0.00	2.90	20.70	2.90	17.80	1.069
		Avg				2.90	17.80	
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						
		1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F_o Within EPA M-3 Guidelines
for fuel type.

Where $F_o = \frac{20.9 - O_2}{CO_2}$

EPA Method 3 Guidelines
Fuel Type F_o Range

Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
Wood/Wood Bark	1.000-1.130

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisian Pacific / Corrigan, TX
Team Leader M. Kaphler
Date Submitted 3-25-92
Test No. 9
Date of Analysis 3-25-92

Source No. 213 Dryer #
Test Site Stack
Date of Test 3-25-92
No. of Runs Completed 2
Technician Mark Bachler

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F _o
			Zero Pt.	After CO ₂	After O ₂			
9/1	☒ B ☐ F	1	0.00	3.00	20.90	3.00	17.90	1.000
		2	0.00	3.00	20.90	3.00	17.90	1.000
		Avg				3.00	17.90	
9/2	☒ B ☐ F	1	0.00	3.00	20.80	3.00	17.80	1.033
		2	0.00	3.00	20.80	3.00	17.80	1.033
		Avg				3.00	17.80	
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F_o Within EPA M-3 Guidelines
for fuel type.

Where $F_o = \frac{20.9 - O_2}{CO_2}$

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

EPA Method 3 Guidelines	
Fuel Type	F _o Range
Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
Wood/Wood Bark	1.000-1.130

Interpoll Laboratories
(612) 786-6020

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / Corrigan, TX
Team Leader D. Baerman
Date Submitted 3-26-92
Test No. 10
Date of Analysis 3-26-92

Source No. 3 Dryer
Test Site Stack
Date of Test 3-26-92
No. of Runs Completed 3
Technician Mark Baerman

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F _o
			Zero Pt.	After CO ₂	After O ₂			
10/1	☒ B ☐ F	1	6.00	2.00	20.90	2.00	18.90	1.000
		2	0.00	2.00	20.90	2.00	18.90	1.000
		Avg				2.00	18.90	
10/2	☒ B ☐ F	1	6.00	1.80	20.70	1.80	18.90	1.111
		2	0.00	1.80	20.70	1.80	18.90	1.111
		Avg				1.80	18.90	
10/3	☒ B ☐ F	1	6.00	1.80	20.80	1.80	19.00	1.056
		2	0.00	1.80	20.80	1.80	19.00	1.056
		Avg				1.80	19.00	
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F_o Within EPA M-3 Guidelines
for fuel type.

Where $F_o = \frac{20.9 - O_2}{CO_2}$

EPA Method 3 Guidelines
Fuel Type F_o Range

Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
Wood/Wood Bark	1.000-1.130

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / Corrigan, TX
Team Leader M. Kaehler
Date Submitted 3-26-92
Test No. 11
Date of Analysis 3-26-92

Source No. 3 Dryer
Test Site Stack
Date of Test 3-26-92
No. of Runs Completed 3
Technician Mark Kaehler

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F _O
			Zero Pt.	After CO ₂	After O ₂			
11/1	☒ B ☐ F	1	0.00	2.00	20.90	2.00	18.90	1.000
		2	0.00	2.00	20.90	2.00	18.90	1.000
		Avg				2.00	18.90	
11/2	☒ B ☐ F	1	0.00	1.70	20.80	1.70	19.10	1.059
		2	0.00	1.70	20.80	1.70	19.10	1.059
		Avg				1.70	19.10	
11/3	☒ B ☐ F	1	0.00	1.60	20.80	1.60	19.20	1.063
		2	0.00	1.60	20.80	1.60	19.20	1.063
		Avg				1.60	19.20	
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F_O Within EPA M-3 Guidelines
for fuel type.

Where $F_{O_2} = \frac{20.9 - O_2}{CO_2}$

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

EPA Method 3 Guidelines	
Fuel Type	F _O Range
Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
Wood/Wood Bark	1.000-1.130

Interpoll Laboratories
(612) 786-6020

EPA Method 3 Data Reporting Sheet
Orsat Analysis

Job Louisiana Pacific / Colligan, TX
Team Leader Mr. D. Brennan
Date Submitted 3-26-92
Test No. 13
Date of Analysis 3-26-92

Source No. 3 Diesel
Test Site Stack
Date of Test 3-26-92
No. of Runs Completed 3
Technician Mark Buchter

Test/ Run	Sample Log Number and Type	No. of An.	Buret Readings (ml)			Conc. CO ₂ %v/v Dry	Conc. O ₂ %v/v Dry	F ₀
			Zero Pt.	After CO ₂	After O ₂			
13/1	☒ B ☐ F	1	0.00	1.60	20.90	1.60	19.30	1.000
		2	0.00	1.60	20.90	1.60	19.30	1.000
		Avg				1.60	19.30	
13/2	☒ B ☐ F	1	0.00	2.00	20.80	2.00	18.80	1.050
		2	0.00	2.00	20.80	2.00	18.80	1.050
		Avg				2.00	18.80	
13/3	☒ B ☐ F	1	0.00	1.60	20.80	1.60	19.20	1.063
		2	0.00	1.60	20.80	1.60	19.20	1.063
		Avg				1.60	19.20	
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						
	☐ B ☐ F	1						
		2						
		Avg						

- ☒ Ambient Air QA Check
☒ Orsat Analyzer System Leak Check
☒ F₀ Within EPA M-3 Guidelines
for fuel type.

Where $F_0 = \frac{20.9 - O_2}{CO_2}$

EPA Method 3 Guidelines	
Fuel Type	F ₀ Range
Coal:	
Anthracite/Lignite	1.016-1.130
Bituminous	1.083-1.230
Oil:	
Distillate	1.260-1.413
Residual	1.210-1.370
Gas:	
Natural	1.600-1.836
Propane	1.434-1.586
Butane	1.405-1.553
Wood/Wood Bark	1.000-1.130

F=Flask (250 cc all glass)
B=Tedlar Bag (5-layer)

Interpoll Laboratories
(612) 796-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan TX Source #1 Dryer Stack
Team Leader DB Test Site Stack
Date Submitted 7-13-92 Date of Test 3-24-92
Test No. 4 No. of Runs Completed 3
Date of Analysis 4-20-92 Technician C. Helgeson


		Solvent Phase	Aqueous Phase
0	Test <u>4</u> Run <u>0</u> Field Blank Log Number <u>5792-26</u> Comments _____	Dish No. <u>84</u> Dish Tare Wt. <u>79.0145</u> g Dish+Sample Wt. <u>79.0149</u> g Sample Wt. <u>0.0004</u> g	Dish No. <u>400</u> Dish Tare Wt. <u>47.1015</u> g Dish+Sample Wt. <u>47.1019</u> g Sample Wt. <u>0.0004</u> g
1	Test <u>4</u> Run <u>1</u> Log Number <u>-29</u> Comments _____	Dish No. <u>85</u> Dish Tare Wt. <u>73.9513</u> g Dish+Sample Wt. <u>73.9841</u> g Sample Wt. <u>0.0328</u> g	Dish No. <u>403</u> Dish Tare Wt. <u>47.0975</u> g Dish+Sample Wt. <u>47.1038</u> g Sample Wt. <u>0.0063</u> g
2	Test <u>4</u> Run <u>2</u> Log Number <u>-33</u> Comments _____	Dish No. <u>87</u> Dish Tare Wt. <u>73.3550</u> g Dish+Sample Wt. <u>73.3822</u> g Sample Wt. <u>0.0272</u> g	Dish No. <u>410</u> Dish Tare Wt. <u>46.4714</u> g Dish+Sample Wt. <u>46.4773</u> g Sample Wt. <u>0.0059</u> g
3	Test <u>4</u> Run <u>3</u> Log Number <u>-37</u> Comments _____	Dish No. <u>89</u> Dish Tare Wt. <u>71.7509</u> g Dish+Sample Wt. <u>71.7777</u> g Sample Wt. <u>0.0268</u> g	Dish No. <u>504</u> Dish Tare Wt. <u>50.0224</u> g Dish+Sample Wt. <u>50.0278</u> g Sample Wt. <u>0.0054</u> g
4	Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phase:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5
Blank Solvent Wt. 0.0004 g
0.0324 0.0268 0.0264

Results Aqueous Phase:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5
0.0059 0.0055 0.0050



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan TX Source #1 Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-24-92
Test No. 4 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson
Transport Leakage ☒ None ml Solvent Acetone


0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue <u>3.33</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>4</u> Run <u>1</u> Vol. of Solvent <u>130</u> ml Log Number <u>5792-27</u> Comments _____	Dish No. <u>405</u> Dish Tare Wt. <u>48.4904</u> g Dish+Sample Wt. <u>48.5180</u> g Sample Wt. <u>0.0276</u> g
2	Test <u>4</u> Run <u>2</u> Vol. of Solvent <u>140</u> ml Log Number <u>-31</u> Comments _____	Dish No. <u>410</u> Dish Tare Wt. <u>46.4687</u> g Dish+Sample Wt. <u>46.4940</u> g Sample Wt. <u>0.0253</u> g
3	Test <u>4</u> Run <u>3</u> Vol. of Solvent <u>150</u> ml Log Number <u>-35</u> Comments _____	Dish No. <u>411</u> Dish Tare Wt. <u>46.6833</u> g Dish+Sample Wt. <u>46.6980</u> g Sample Wt. <u>0.0147</u> g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10⁶)] / Vol. of Sol. _____ ml
EPA-MS Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0272</u>	<u>0.0248</u>	<u>0.0142</u>		
--	---------------	---------------	---------------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job L.P. Corrigan, Tx Source #1 Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-24-92
Test No. 4 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson

0	Test <u>4</u> Run <u>0</u> Field Blank Log Number _____ Comments _____	Filter No. <u>4131</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9559</u> g Filter+Sample Wt. <u>.9562</u> g Sample Wt. <u>0.0003</u> g
1	Test <u>4</u> Run <u>1</u> Log Number <u>5792-28</u> Comments _____	Filter No. <u>4040</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9689</u> g Filter+Sample Wt. <u>1.0419</u> g Sample Wt. <u>0.0730</u> g
2	Test <u>4</u> Run <u>2</u> Log Number <u>-32</u> Comments _____	Filter No. <u>4119</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9256</u> g Filter+Sample Wt. <u>1.0104</u> g Sample Wt. <u>0.0848</u> g
3	Test <u>4</u> Run <u>3</u> Log Number <u>-36</u> Comments _____	Filter No. <u>4120</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9533</u> g Filter+Sample Wt. <u>1.0242</u> g Sample Wt. <u>0.0709</u> g
4	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g

Results:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0730	0.0848	0.0709		

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.1385	0.1419	0.1165		

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan Tx Source #24 Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-25-92
Test No. 8 No. of Runs Completed 2
Date of Analysis 4-27-92 Technician C. Helgeson

	Solvent Phase	Aqueous Phase
0	Test <u>Run 0</u> Field Blank Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>8</u> Run <u>1</u> Log Number <u>5792-56</u> Comments	Dish No. <u>406</u> Dish Tare Wt. <u>49.6168</u> g Dish+Sample Wt. <u>49.7272</u> g Sample Wt. <u>0.1104</u> g
2	Test <u>8</u> Run <u>2</u> Log Number <u>-59</u> Comments	Dish No. <u>408</u> Dish Tare Wt. <u>47.6250</u> g Dish+Sample Wt. <u>47.6845</u> g Sample Wt. <u>0.0595</u> g
3	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
4	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phases:
Field Blk. Run 1 Run 2 Run 3


Blank Solvent Wt. 0.0004 g
Run 4 Run 5

	<u>0.1100</u>	<u>0.0591</u>			
--	---------------	---------------	--	--	--

Results Aqueous Phases:
Field Blk. Run 1 Run 2 Run 3

Run 4 Run 5

	<u>0.0347</u>	<u>0.0352</u>			
--	---------------	---------------	--	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan Tx. Source # 2A Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-25-92
Test No. 8 No. of Runs Completed 2
Date of Analysis 4-14-92 Technician C. Helgeson
Transport Leakage ☒ None ☐ ml Solvent Acetone


0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue <u>3.33</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>8</u> Run <u>1</u> Vol. of Solvent <u>210</u> ml Log Number <u>5792-54</u> Comments _____	Dish No. <u>200</u> Dish Tare Wt. <u>44.9364</u> g Dish+Sample Wt. <u>45.0120</u> g Sample Wt. <u>0.0756</u> g
2	Test <u>8</u> Run <u>2</u> Vol. of Solvent <u>110</u> ml Log Number <u>-57</u> Comments _____	Dish No. <u>212</u> Dish Tare Wt. <u>50.3579</u> g Dish+Sample Wt. <u>50.3715</u> g Sample Wt. <u>0.0136</u> g
3	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10⁶)] / Vol. of Sol. _____ ml
EPA-M5 Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0749	0.0132	D-15		
--	--------	--------	------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job L.P. Corrigan, Tx Source # 2A Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-25-92
Test No. 8 No. of Runs Completed 2
Date of Analysis 4-14-92 Technician C. Helgeson

0	Test <u> </u> Run <u>0</u> Field Blank Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
1	Test <u>8</u> Run <u>1</u> Log Number <u>5792-55</u> Comments <u> </u>	Filter No. <u>4123</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9554</u> g Filter+Sample Wt. <u>1.0538</u> g Sample Wt. <u>0.0984</u> g
2	Test <u>8</u> Run <u>2</u> Log Number <u>-58</u> Comments <u> </u>	Filter No. <u>4124</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9366</u> g Filter+Sample Wt. <u>1.0380</u> g Sample Wt. <u>0.1014</u> g
3	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
4	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
5	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0984	0.1014			
--	--------	--------	--	--	--

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.3180	0.2089			
--	--------	--------	--	--	--

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan Tx Source 2B Dryer
Team Leader MK Test Site Stock
Date Submitted 4-13-92 Date of Test 4-3-92
Test No. 9 No. of Runs Completed 2
Date of Analysis 4-23-92 Technician C. Helgeson

	Solvent Phase	Aqueous Phase
0 Test <u>9</u> Run <u>0</u> Field Blank Log Number <u>5792-62</u> Comments _____	Dish No. <u>1A</u> Dish Tare Wt. <u>44.1957</u> g Dish+Sample Wt. <u>44.1961</u> g Sample Wt. <u>0.0004</u> g	Dish No. <u>69</u> Dish Tare Wt. <u>47.9871</u> g Dish+Sample Wt. <u>47.9875</u> g Sample Wt. <u>0.0004</u> g
1 Test <u>9</u> Run <u>1</u> Log Number <u>-65</u> Comments _____	Dish No. <u>5A</u> Dish Tare Wt. <u>44.5327</u> g Dish+Sample Wt. <u>44.5750</u> g Sample Wt. <u>0.0423</u> g	Dish No. <u>105</u> Dish Tare Wt. <u>47.8621</u> g Dish+Sample Wt. <u>47.8826</u> g Sample Wt. <u>0.0205</u> g
2 Test <u>9</u> Run <u>2</u> Log Number <u>-69</u> Comments _____	Dish No. <u>44</u> Dish Tare Wt. <u>47.6231</u> g Dish+Sample Wt. <u>47.6618</u> g Sample Wt. <u>0.0387</u> g	Dish No. <u>117</u> Dish Tare Wt. <u>47.3712</u> g Dish+Sample Wt. <u>47.3897</u> g Sample Wt. <u>0.0185</u> g
3 Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
4 Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5 Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phases:


Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0419</u>	<u>0.0383</u>			
--	---------------	---------------	--	--	--

Results Aqueous Phases:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0201</u>	<u>0.0181</u>	<u>0.17</u>		
--	---------------	---------------	-------------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan Tx Source 2B Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-25-92
Test No. 9 No. of Runs Completed 2
Date of Analysis 4-14-92 Technician C. Helgeson
Transport Leakage ☒ None ☐ _____ ml Solvent Acetone

0	Test <u>9</u> Run <u>0</u> Field Blank Log Number <u>5792-60</u> Vol. of Solvent <u>90</u> ml *Solvent Residue <u>3.33</u> ug/ml	Dish No. <u>503</u> Dish Tare Wt. <u>48.3109</u> g Dish+Sample Wt. <u>48.3112</u> g Sample Wt. <u>0.0003</u> g
1	Test <u>9</u> Run <u>1</u> Vol. of Solvent <u>190</u> ml Log Number <u>-63</u> Comments _____	Dish No. <u>505</u> Dish Tare Wt. <u>48.4510</u> g Dish+Sample Wt. <u>48.4684</u> g Sample Wt. <u>0.0174</u> g
2	Test <u>9</u> Run <u>2</u> Vol. of Solvent <u>170</u> ml Log Number <u>-67</u> Comments _____	Dish No. <u>514</u> Dish Tare Wt. <u>48.7126</u> g Dish+Sample Wt. <u>48.7260</u> g Sample Wt. <u>0.0134</u> g
3	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue 3.33 ug/ml = [(Sample Wt. 0.0003 g) (10⁶)] / Vol. of Sol. 90 ml
EPA-M5 Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0168</u>	<u>0.0128</u>	<u>D-18</u>		
--	---------------	---------------	-------------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job L.P. Corrigan Tx. Source #2B Dryer
 Team Leader MK Test Site Stack
 Date Submitted 4-13-92 Date of Test 3-25-92
 Test No. 9 No. of Runs Completed 2
 Date of Analysis 4-14-92 Technician C. Helgeson

0	Test <u>9</u> Run <u>0</u> Field Blank Log Number <u>5792-61</u> Comments _____	Filter No. <u>4126</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9445</u> g Filter+Sample Wt. <u>.9450</u> g Sample Wt. <u>.0005</u> g
1	Test <u>9</u> Run <u>1</u> Log Number <u>-64</u> Comments _____	Filter No. <u>4122</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9352</u> g Filter+Sample Wt. <u>1.0566</u> g Sample Wt. <u>0.1214</u> g
2	Test <u>9</u> Run <u>2</u> Log Number <u>-68</u> Comments _____	Filter No. <u>4125</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9543</u> g Filter+Sample Wt. <u>1.0570</u> g Sample Wt. <u>0.1027</u> g
3	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
4	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g

Results:


Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.1214	0.1027			
--	--------	--------	--	--	--

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.2002	0.1719			
--	--------	--------	--	--	--

LSC-02PR



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan Tx Source #3 Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-26-92
Test No. 13 No. of Runs Completed 3
Date of Analysis 4-23-92 Technician C. Helgeson

		Solvent Phase	Aqueous Phase
0	Test <u>Run 0</u> Field Blank Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>13</u> Run <u>1</u> Log Number <u>5792-88</u> Comments _____	Dish No. <u>57</u> Dish Tare Wt. <u>47.9137</u> g Dish+Sample Wt. <u>47.9297</u> g Sample Wt. <u>0.0160</u> g	Dish No. <u>513</u> Dish Tare Wt. <u>47.4124</u> g Dish+Sample Wt. <u>47.4189</u> g Sample Wt. <u>0.0065</u> g
2	Test <u>13</u> Run <u>2</u> Log Number <u>-91</u> Comments _____	Dish No. <u>59</u> Dish Tare Wt. <u>50.1521</u> g Dish+Sample Wt. <u>50.1686</u> g Sample Wt. <u>0.0165</u> g	Dish No. <u>516</u> Dish Tare Wt. <u>49.2700</u> g Dish+Sample Wt. <u>49.2750</u> g Sample Wt. <u>0.0050</u> g
3	Test <u>13</u> Run <u>3</u> Log Number <u>-94</u> Comments _____	Dish No. <u>61A</u> Dish Tare Wt. <u>51.4728</u> g Dish+Sample Wt. <u>51.5034</u> g Sample Wt. <u>0.0306</u> g	Dish No. <u>518</u> Dish Tare Wt. <u>48.1019</u> g Dish+Sample Wt. <u>48.1129</u> g Sample Wt. <u>0.0110</u> g
4	Test <u>Run</u> Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phases:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	<u>0.0156</u>	<u>0.0161</u>	<u>0.0302</u>		

Blank Solvent Wt. _____ g

Results Aqueous Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	<u>0.0061</u>	<u>0.0046</u>	<u>0.0106</u>		

D-20



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan, TX Source #3 Driver
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-26-92
Test No. 13 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helyer
Transport Leakage ☒ None ☐ _____ ml Solvent Acetone

0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue <u>3.33</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>13</u> Run <u>1</u> Vol. of Solvent <u>110</u> ml Log Number <u>5792-86</u> Comments _____	Dish No. <u>6</u> Dish Tare Wt. <u>48.2702</u> g Dish+Sample Wt. <u>48.2860</u> g Sample Wt. <u>0.0158</u> g
2	Test <u>13</u> Run <u>2</u> Vol. of Solvent <u>110</u> ml Log Number <u>-89</u> Comments _____	Dish No. <u>520</u> Dish Tare Wt. <u>48.5256</u> g Dish+Sample Wt. <u>48.5364</u> g Sample Wt. <u>0.0108</u> g
3	Test <u>13</u> Run <u>3</u> Vol. of Solvent <u>90</u> ml Log Number <u>-92</u> Comments _____	Dish No. <u>524</u> Dish Tare Wt. <u>48.0396</u> g Dish+Sample Wt. <u>48.0507</u> g Sample Wt. <u>0.0111</u> g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10⁶)] / Vol. of Sol. _____ ml

EPA-M5 Acetone Residue Blank Spec. { 7.3 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0154	0.0104	0.0108		
--	--------	--------	--------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job LoP. Corrigan, Tx. Source #3 Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-26-92
Test No. 13 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson

0	Test <u>Run 0</u> Field Blank Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____g Filter+Sample Wt. _____g Sample Wt. _____g
1	Test <u>13</u> Run <u>1</u> Log Number <u>5792-87</u> Comments _____	Filter No. <u>4127</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9331</u> g Filter+Sample Wt. <u>.9857</u> g Sample Wt. <u>0.0526</u> g
2	Test <u>13</u> Run <u>2</u> Log Number <u>-40</u> Comments _____	Filter No. <u>4128</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9306</u> g Filter+Sample Wt. <u>.9929</u> g Sample Wt. <u>0.0623</u> g
3	Test <u>13</u> Run <u>3</u> Log Number <u>-43</u> Comments _____	Filter No. <u>4129</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9539</u> g Filter+Sample Wt. <u>1.0064</u> g Sample Wt. <u>0.0525</u> g
4	Test <u>Run</u> Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____g Filter+Sample Wt. _____g Sample Wt. _____g
5	Test <u>Run</u> Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____g Filter+Sample Wt. _____g Sample Wt. _____g

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0526	0.0623	0.0525		
--	--------	--------	--------	--	--

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0897	0.0934	0.1041		
--	--------	--------	--------	--	--

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Carrigan DB Tx Source #4 Press vent
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 4-3-27-92
Test No. 14 No. of Runs Completed 3
Date of Analysis 4-23-92 Technician C. Helgeson

		Solvent Phase	Aqueous Phase
0	Test <u>Run 0</u> Field Blank Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>14</u> Run <u>1</u> Log Number <u>5792-92</u> Comments	Dish No. <u>2</u> Dish Tare Wt. <u>46.2246</u> g Dish+Sample Wt. <u>46.2465</u> g Sample Wt. <u>0.0219</u> g	Dish No. <u>3</u> Dish Tare Wt. <u>52.1224</u> g Dish+Sample Wt. <u>52.1244</u> g Sample Wt. <u>0.0020</u> g
2	Test <u>14</u> Run <u>2</u> Log Number <u>-100</u> Comments	Dish No. <u>17</u> Dish Tare Wt. <u>46.3755</u> g Dish+Sample Wt. <u>46.4021</u> g Sample Wt. <u>0.0266</u> g	Dish No. <u>29</u> Dish Tare Wt. <u>49.8009</u> g Dish+Sample Wt. <u>49.8021</u> g Sample Wt. <u>0.0012</u> g
3	Test <u>14</u> Run <u>3</u> Log Number <u>-103</u> Comments	Dish No. <u>111</u> Dish Tare Wt. <u>42.7805</u> g Dish+Sample Wt. <u>42.7964</u> g Sample Wt. <u>0.0159</u> g	Dish No. <u>34</u> Dish Tare Wt. <u>51.7552</u> g Dish+Sample Wt. <u>51.7568</u> g Sample Wt. <u>0.0016</u> g
4	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phase:


Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0215	0.0262	0.0155		

Results Aqueous Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0016	0.0008	0.0012		

D-23

LSC-03WYF



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan Tx Source # 4 Press Vent
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-27-92
Test No. 14 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Nelson
Transport Leakage ☒ None ☐ _____ ml Solvent Acetone


0	Test _____ Run <u>0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue <u>3.33</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>14</u> Run <u>1</u> Vol. of Solvent <u>110</u> ml Log Number <u>5792-95</u> Comments _____	Dish No. <u>3</u> Dish Tare Wt. <u>52.1200</u> g Dish+Sample Wt. <u>52.1304</u> g Sample Wt. <u>0.0104</u> g
2	Test <u>14</u> Run <u>2</u> Vol. of Solvent <u>100</u> ml Log Number <u>-98</u> Comments _____	Dish No. <u>24</u> Dish Tare Wt. <u>56.8221</u> g Dish+Sample Wt. <u>56.8330</u> g Sample Wt. <u>0.0109</u> g
3	Test <u>14</u> Run <u>3</u> Vol. of Solvent <u>90</u> ml Log Number <u>-101</u> Comments _____	Dish No. <u>25</u> Dish Tare Wt. <u>44.3430</u> g Dish+Sample Wt. <u>44.3575</u> g Sample Wt. <u>0.0145</u> g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10⁶)] / Vol. of Sol. _____ ml
EPA-M5 Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0100	0.0106D-24	0.0142		
--	--------	------------	--------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan TX Source #1 Dryer Stack
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-24-92
Test No. 4 No. of Runs Completed 3
Date of Analysis 4-20-92 Technician C. Helgeson

	Solvent Phase	Aqueous Phase
0 Test <u>4</u> Run <u>0</u> Field Blank Log Number <u>5792-26</u> Comments _____	Dish No. <u>84</u> Dish Tare Wt. <u>79.0145</u> g Dish+Sample Wt. <u>79.0149</u> g Sample Wt. <u>0.0004</u> g	Dish No. <u>400</u> Dish Tare Wt. <u>47.1015</u> g Dish+Sample Wt. <u>47.1019</u> g Sample Wt. <u>0.0004</u> g
1 Test <u>4</u> Run <u>1</u> Log Number <u>-29</u> Comments _____	Dish No. <u>85</u> Dish Tare Wt. <u>73.9513</u> g Dish+Sample Wt. <u>73.9541</u> g Sample Wt. <u>0.0328</u> g	Dish No. <u>403</u> Dish Tare Wt. <u>47.0975</u> g Dish+Sample Wt. <u>47.1038</u> g Sample Wt. <u>0.0063</u> g
2 Test <u>4</u> Run <u>2</u> Log Number <u>-33</u> Comments _____	Dish No. <u>87</u> Dish Tare Wt. <u>73.3550</u> g Dish+Sample Wt. <u>73.3822</u> g Sample Wt. <u>0.0272</u> g	Dish No. <u>410</u> Dish Tare Wt. <u>46.4714</u> g Dish+Sample Wt. <u>46.4773</u> g Sample Wt. <u>0.0059</u> g
3 Test <u>4</u> Run <u>3</u> Log Number <u>-37</u> Comments _____	Dish No. <u>89</u> Dish Tare Wt. <u>71.7509</u> g Dish+Sample Wt. <u>71.7777</u> g Sample Wt. <u>0.0268</u> g	Dish No. <u>504</u> Dish Tare Wt. <u>50.0224</u> g Dish+Sample Wt. <u>50.0278</u> g Sample Wt. <u>0.0054</u> g
4 Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5 Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phase:

Field Blk. Run 1 Run 2 Run 3

Blank Solvent Wt. 0.0004 g

Run 4 Run 5

	<u>0.0324</u>	<u>0.0268</u>	<u>0.0264</u>		
--	---------------	---------------	---------------	--	--

Results Aqueous Phases:

Field Blk. Run 1


Run 2

Run 3

Run 4

Run 5

	<u>0.0054</u>	<u>0.0055</u>	<u>0.0050</u>		
--	---------------	---------------	---------------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job L. P. Corrigan, Tx Source #4 Kent
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-27-92
Test No. 14 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson

0	Test <u>Run 0</u> Field Blank Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>14</u> Run <u>1</u> Log Number <u>5792-96</u> Comments _____	Filter No. <u>4130</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9588</u> g Filter+Sample Wt. <u>.9654</u> g Sample Wt. <u>0.0066</u> g
2	Test <u>14</u> Run <u>2</u> Log Number <u>-99</u> Comments _____	Filter No. <u>4132</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.7435</u> g Filter+Sample Wt. <u>.9563</u> g Sample Wt. <u>0.0128</u> g
3	Test <u>14</u> Run <u>3</u> Log Number <u>-102</u> Comments _____	Filter No. <u>4133</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9388</u> g Filter+Sample Wt. <u>.9494</u> g Sample Wt. <u>0.0106</u> g
4	Test <u>Run</u> Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g

Results:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0066	0.0128	0.0106		

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0397	0.0504	0.0415		

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job LP. Carrigan TX Source #3 Press Vent
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-27-92
Test No. 17 No. of Runs Completed 3
Date of Analysis 4-23-92 Technician C. Helsen

	Solvent Phase	Aqueous Phase
0	Test <u>Run 0</u> Field Blank Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>17 Run 1</u> Log Number <u>5792-111</u> Comments	Dish No. <u>404</u> Dish Tare Wt. <u>47.6390</u> g Dish+Sample Wt. <u>47.6615</u> g Sample Wt. <u>0.0225</u> g
2	Test <u>17 Run 2</u> Log Number <u>-114</u> Comments	Dish No. <u>503</u> Dish Tare Wt. <u>48.3108</u> g Dish+Sample Wt. <u>48.3286</u> g Sample Wt. <u>0.0178</u> g
3	Test <u>17 Run 3</u> Log Number <u>-117</u> Comments	Dish No. <u>509</u> Dish Tare Wt. <u>47.6202</u> g Dish+Sample Wt. <u>47.6409</u> g Sample Wt. <u>0.0207</u> g
4	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g


Results Solvent Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	<u>0.0221</u>	<u>0.0174</u>	<u>0.0203</u>		

Results Aqueous Phases:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
------------	-------	-------	-------	-------	-------

	<u>0.0004</u>	<u>0.0048</u>	<u>0.0016</u>		
--	---------------	---------------	---------------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan Tx Source #3 Press Vent
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-27-92
Test No. 17 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson
Transport Leakage ☒ None ☐ ml Solvent Acetone


0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue <u>3.33</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>17</u> Run <u>1</u> Vol. of Solvent <u>100</u> ml Log Number <u>5792-109</u> Comments _____	Dish No. <u>22</u> Dish Tare Wt. <u>51.3604</u> g Dish+Sample Wt. <u>51.3713</u> g Sample Wt. <u>0.0109</u> g
2	Test <u>17</u> Run <u>2</u> Vol. of Solvent <u>80</u> ml Log Number <u>-112</u> Comments _____	Dish No. <u>52</u> Dish Tare Wt. <u>49.8053</u> g Dish+Sample Wt. <u>49.8150</u> g Sample Wt. <u>0.0097</u> g
3	Test <u>17</u> Run <u>3</u> Vol. of Solvent <u>100</u> ml Log Number <u>-115</u> Comments _____	Dish No. <u>98</u> Dish Tare Wt. <u>47.2113</u> g Dish+Sample Wt. <u>47.2177</u> g Sample Wt. <u>0.0064</u> g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue ug/ml = [(Sample Wt. _____ g) (10⁶)] / Vol. of Sol. _____ ml
EPA-MS Acetone Residue Blank Spec. 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0106	0.0094	0.0061	D-27	
--	--------	--------	--------	------	--



EPA Method 5 Data Reporting Sheet
Filter Gravimetrics


Job LeP. Corrigan, Tx Source #3 Press Vent
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-27-92
Test No. 17 No. of Runs Completed 3
Date of Analysis 4-13-92 Technician C. Helgeson

0	Test <u> </u> Run <u>0</u> Field Blank Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
1	Test <u>17</u> Run <u>1</u> Log Number <u>5792-110</u> Comments <u> </u>	Filter No. <u>4134</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9706</u> g Filter+Sample Wt. <u>.9862</u> g Sample Wt. <u>0.0156</u> g
2	Test <u>17</u> Run <u>2</u> Log Number <u>-113</u> Comments <u> </u>	Filter No. <u>4135</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9640</u> g Filter+Sample Wt. <u>.9813</u> g Sample Wt. <u>0.0173</u> g
3	Test <u>17</u> Run <u>3</u> Log Number <u>-116</u> Comments <u> </u>	Filter No. <u>4136</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9312</u> g Filter+Sample Wt. <u>.9487</u> g Sample Wt. <u>0.0175</u> g
4	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
5	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g

Results:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0156	0.0173	0.0175		

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0487	0.0489	0.0455		



EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan Tx Source #8 Exhaust Vent
Team Leader DB Test Site Speck
Date Submitted 4-13-92 Date of Test 3-28-92
Test No. 20 No. of Runs Completed 3
Date of Analysis 4-23-92 Technician C. Helgeson

		Solvent Phase	Aqueous Phase
0	Test <u>Run 0</u> Field Blank Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>20</u> Run <u>1</u> Log Number <u>5792-123</u> Comments	Dish No. <u>2</u> Dish Tare Wt. <u>50.0287</u> g Dish+Sample Wt. <u>50.0387</u> g Sample Wt. <u>0.0100</u> g	Dish No. <u>22</u> Dish Tare Wt. <u>51.3597</u> g Dish+Sample Wt. <u>51.3633</u> g Sample Wt. <u>0.0036</u> g
2	Test <u>20</u> Run <u>2</u> Log Number <u>726</u> Comments	Dish No. <u>14</u> Dish Tare Wt. <u>49.7330</u> g Dish+Sample Wt. <u>49.7421</u> g Sample Wt. <u>0.0091</u> g	Dish No. <u>24</u> Dish Tare Wt. <u>56.8221</u> g Dish+Sample Wt. <u>56.8239</u> g Sample Wt. <u>0.0018</u> g
3	Test <u>20</u> Run <u>3</u> Log Number <u>-129</u> Comments	Dish No. <u>45</u> Dish Tare Wt. <u>50.8884</u> g Dish+Sample Wt. <u>50.8945</u> g Sample Wt. <u>0.0061</u> g	Dish No. <u>36</u> Dish Tare Wt. <u>43.5653</u> g Dish+Sample Wt. <u>43.5679</u> g Sample Wt. <u>0.0026</u> g
4	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phase:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0096</u>	<u>0.0087</u>	<u>0.0057</u>		
--	---------------	---------------	---------------	--	--

Results Aqueous Phase:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0032</u>	<u>0.0014</u>	<u>0.0022</u>		
--	---------------	---------------	---------------	--	--



EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan Tx Source #8 Exhaust Fan
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-28-92
Test No. 20 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson
Transport Leakage ☒ None ☐ _____ ml Solvent Acetone


0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent <u>0</u> ml *Solvent Residue <u>3.33</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>20 Run 1</u> Vol. of Solvent <u>100</u> ml Log Number <u>5792-121</u> Comments _____	Dish No. <u>2</u> Dish Tare Wt. <u>46.2264</u> g Dish+Sample Wt. <u>46.2490</u> g Sample Wt. <u>0.0226</u> g
2	Test <u>20 Run 2</u> Vol. of Solvent <u>110</u> ml Log Number <u>-124</u> Comments _____	Dish No. <u>7</u> Dish Tare Wt. <u>50.0320</u> g Dish+Sample Wt. <u>50.0615</u> g Sample Wt. <u>0.0295</u> g
3	Test <u>20 Run 3</u> Vol. of Solvent <u>80</u> ml Log Number <u>-127</u> Comments _____	Dish No. <u>29</u> Dish Tare Wt. <u>49.8009</u> g Dish+Sample Wt. <u>49.8273</u> g Sample Wt. <u>0.0264</u> g
4	Test <u>Run</u> Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10⁶)] / Vol. of Sol. _____ ml
EPA-M5 Acetone Residue Blank Spec. { 7.3 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0223	0.029 / 0-30	0.0261		
--	--------	--------------	--------	--	--



EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job L.P. Corrigan, TX Source #8 Exhaust Fan
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-28-92
Test No. 20 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson

0	Test <u> </u> Run <u>0</u> Field Blank Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
1	Test <u>20</u> Run <u>1</u> Log Number <u>5792-122</u> Comments <u> </u>	Filter No. <u>4157</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9358</u> g Filter+Sample Wt. <u>.9385</u> g Sample Wt. <u>0.0027</u> g
2	Test <u>20</u> Run <u>2</u> Log Number <u> 125</u> Comments <u> </u>	Filter No. <u>4158</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9511</u> g Filter+Sample Wt. <u>.9515</u> g Sample Wt. <u>0.0004</u> g
3	Test <u>20</u> Run <u>3</u> Log Number <u> -128</u> Comments <u> </u>	Filter No. <u>4159</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9524</u> g Filter+Sample Wt. <u>.9557</u> g Sample Wt. <u>0.0033</u> g
4	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
5	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g

Results:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0027	0.0004	0.0033		

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0378	0.0396	0.0373		

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan TX Source #2 Press Vent
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-28-92
Test No. 23 No. of Runs Completed 3
Date of Analysis 4-23-92 Technician C. Hulse

	Solvent Phase	Aqueous Phase
Test <u>Run 0</u> Field Blank Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
Test <u>23 Run 1</u> Log Number <u>5792-135</u> Comments	Dish No. <u>119</u> Dish Tare Wt. <u>47.7657</u> g Dish+Sample Wt. <u>47.7703</u> g Sample Wt. <u>0.0046</u> g	Dish No. <u>53</u> Dish Tare Wt. <u>44.3967</u> g Dish+Sample Wt. <u>44.3995</u> g Sample Wt. <u>0.0028</u> g
Test <u>23 Run 2</u> Log Number <u>-138</u> Comments	Dish No. <u>512</u> Dish Tare Wt. <u>49.3554</u> g Dish+Sample Wt. <u>49.3601</u> g Sample Wt. <u>0.0047</u> g	Dish No. <u>402</u> Dish Tare Wt. <u>47.5800</u> g Dish+Sample Wt. <u>47.5835</u> g Sample Wt. <u>0.0035</u> g
Test <u>23 Run 3</u> Log Number <u>-147</u> Comments	Dish No. <u>521</u> Dish Tare Wt. <u>50.5950</u> g Dish+Sample Wt. <u>50.6009</u> g Sample Wt. <u>0.0059</u> g	Dish No. <u>523</u> Dish Tare Wt. <u>49.8063</u> g Dish+Sample Wt. <u>49.8123</u> g Sample Wt. <u>0.0060</u> g
Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0042	0.0043	0.0055		

Results Aqueous Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0024	0.0031	0.0056		



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job LP. Corrigan Tr. Source #2 Press Vent
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-28-92
Test No. 23 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson
Transport Leakage ☒ None ☐ _____ ml Solvent Acetone

0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue <u>3.33</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>23</u> Run <u>1</u> Vol. of Solvent <u>70</u> ml Log Number <u>5792-133</u> Comments _____	Dish No. <u>31</u> Dish Tare Wt. <u>45.8034</u> g Dish+Sample Wt. <u>45.8107</u> g Sample Wt. <u>0.0073</u> g
2	Test <u>23</u> Run <u>2</u> Vol. of Solvent <u>100</u> ml Log Number <u>-136</u> Comments _____	Dish No. <u>36</u> Dish Tare Wt. <u>43.5634</u> g Dish+Sample Wt. <u>43.5785</u> g Sample Wt. <u>0.0051</u> g
3	Test <u>23</u> Run <u>3</u> Vol. of Solvent <u>80</u> ml Log Number <u>-147</u> Comments _____	Dish No. <u>112</u> Dish Tare Wt. <u>47.3842</u> g Dish+Sample Wt. <u>47.3884</u> g Sample Wt. <u>0.0042</u> g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g


Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10)] / Vol. of Sol. _____ ml

EPA-M5 Acetone Residue Blank Spec. (7.8 ug/ml)

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0071	0.0048	0.0039		
--	--------	--------	--------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job L.P. Corrigan, Tx Source #2 Press Vent
Team Leader DB Test Site Sfack
Date Submitted 4-13-92 Date of Test 3-28-92
Test No. 23 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson

0	Test <u>Run 0</u> Field Blank Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>23</u> Run <u>1</u> Log Number <u>5292-134</u> Comments _____	Filter No. <u>4160</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9378</u> g Filter+Sample Wt. <u>.9413</u> g Sample Wt. <u>0.0035</u> g
2	Test <u>23</u> Run <u>2</u> Log Number <u>-136</u> Comments _____	Filter No. <u>4175</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9566</u> g Filter+Sample Wt. <u>.9649</u> g Sample Wt. <u>0.0083</u> g
3	Test <u>23</u> Run <u>3</u> Log Number <u>-146</u> Comments _____	Filter No. <u>4176</u> Filter Type <u>4" GF</u> Filter Tare Wt. <u>.9361</u> g Filter+Sample Wt. <u>.9442</u> g Sample Wt. <u>0.0081</u> g
4	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g

Results:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0035	0.0083	0.0081		

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0172	0.0205	0.0231		

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan Tx Source #1 Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-24-92
Test No. 1 No. of Runs Completed 3
Date of Analysis 4-20-92 Technician C. Helgeson


	Solvent Phase	Aqueous Phase
0	Test <u>1</u> Run <u>0</u> Field Blank Log Number <u>5792-03</u> Comments _____ Dish No. <u>72</u> Dish Tare Wt. <u>64.1115</u> g Dish+Sample Wt. <u>64.1119</u> g Sample Wt. <u>0.0004</u> g	Dish No. <u>39</u> Dish Tare Wt. <u>49.4390</u> g Dish+Sample Wt. <u>49.4394</u> g Sample Wt. <u>0.0004</u> g
1	Test <u>1</u> Run <u>1</u> Log Number <u>-06</u> Comments _____ Dish No. <u>72 A</u> Dish Tare Wt. <u>80.0603</u> g Dish+Sample Wt. <u>80.0668</u> g Sample Wt. <u>0.0065</u> g	Dish No. <u>54</u> Dish Tare Wt. <u>51.8986</u> g Dish+Sample Wt. <u>51.9037</u> g Sample Wt. <u>0.0051</u> g
2	Test <u>1</u> Run <u>2</u> Log Number <u>-10</u> Comments _____ Dish No. <u>74</u> Dish Tare Wt. <u>77.3105</u> g Dish+Sample Wt. <u>77.3185</u> g Sample Wt. <u>0.0080</u> g	Dish No. <u>60</u> Dish Tare Wt. <u>49.6275</u> g Dish+Sample Wt. <u>49.6311</u> g Sample Wt. <u>0.0036</u> g
3	Test <u>1</u> Run <u>3</u> Log Number <u>-14</u> Comments _____ Dish No. <u>76</u> Dish Tare Wt. <u>70.2580</u> g Dish+Sample Wt. <u>70.2720</u> g Sample Wt. <u>0.0140</u> g	Dish No. <u>61</u> Dish Tare Wt. <u>44.5908</u> g Dish+Sample Wt. <u>44.6013</u> g Sample Wt. <u>0.0105</u> g
4	Test _____ Run _____ Log Number _____ Comments _____ Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____ Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	<u>0.0061</u>	<u>0.0076</u>	<u>0.0136</u>		

Results Aqueous Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	<u>0.0047</u>	<u>0.0032</u>	<u>0.0107</u>		



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan, TX Source #1 Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-24-92
Test No. 1 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson
Transport Leakage ☐ None ☐ ml Solvent Acetone

0

Test 1 Run 0 Dish No. 511
Field Blank Dish Tare Wt. 45.5432 g
Log Number 5792-01 Dish+Sample Wt. 45.5435 g
Vol. of Solvent 90 ml Sample Wt. 0.0003 g
*Solvent Residue 3.33 ug/ml

1

Test 1 Run 1 Dish No. 513
Vol. of Solvent 40 ml Dish Tare Wt. 47.4119 g
Log Number -04 Dish+Sample Wt. 47.4145 g
Comments Sample Wt. 0.0026 g

2

Test 1 Run 2 Dish No. 518
Vol. of Solvent 40 ml Dish Tare Wt. 48.1011 g
Log Number -08 Dish+Sample Wt. 48.1030 g
Comments Sample Wt. 0.0019 g

3

Test 1 Run 3 Dish No. 519
Vol. of Solvent 40 ml Dish Tare Wt. 49.0517 g
Log Number -12 Dish+Sample Wt. 49.0537 g
Comments Sample Wt. 0.0020 g

4

Test Run Dish No.
Vol. of Solvent ml Dish Tare Wt. g
Log Number Dish+Sample Wt. g
Comments Sample Wt. g

5


Test Run Dish No.
Vol. of Solvent ml Dish Tare Wt. g
Log Number Dish+Sample Wt. g
Comments Sample Wt. g

*Solvent Residue 3.33 ug/ml = [(Sample Wt. 0.0003 g) (10⁶)] / Vol. of Sol. ml
EPA-M5 Acetone Residue Blank Spec. { 7.3 ug/ml

Results:

Field Bk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0025	0.0018	0.0019		
--	--------	--------	--------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics
PM-10

Job L.P. Corrigan, Tx. Source #1 Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-23-92
Test No. 1 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson


0	Test <u>1</u> Run <u>0</u> Field Blank Log Number <u>5792-02</u> Comments _____	Filter No. <u>5710</u> Filter Type <u>2.5" GF</u> Filter Tare Wt. <u>.2691</u> g Filter+Sample Wt. <u>.2692</u> g Sample Wt. <u>0.0001</u> g
1	Test <u>1</u> Run <u>1</u> Log Number <u>-05</u> Comments _____	Filter No. <u>5709</u> Filter Type <u>2.5" GF</u> Filter Tare Wt. <u>.2691</u> g Filter+Sample Wt. <u>.3836</u> g Sample Wt. <u>0.1145</u> g
2	Test <u>1</u> Run <u>2</u> Log Number <u>-09</u> Comments _____	Filter No. <u>5711</u> Filter Type <u>2.5" GF</u> Filter Tare Wt. <u>.2673</u> g Filter+Sample Wt. <u>.3784</u> g Sample Wt. <u>0.1111</u> g
3	Test <u>1</u> Run <u>3</u> Log Number <u>-13</u> Comments _____	Filter No. <u>5708</u> Filter Type <u>2.5" GF</u> Filter Tare Wt. <u>.2663</u> g Filter+Sample Wt. <u>.4162</u> g Sample Wt. <u>0.1499</u> g
4	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g

Results:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.1145	0.1111	0.1499		

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.1278	0.1237	0.1755		

LSC-02PR



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan TX Source #2A Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 4-25-92
Test No. 5 No. of Runs Completed 3
Date of Analysis 4-23-92 Technician C. Helgeson


		Solvent Phase	Aqueous Phase
0	Test <u>Run 0</u> Field Blank Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>5</u> Run <u>1</u> Log Number <u>5792-41</u> Comments	Dish No. <u>88</u> Dish Tare Wt. <u>55.9104</u> g Dish+Sample Wt. <u>55.9267</u> g Sample Wt. <u>0.0163</u> g	Dish No. <u>520</u> Dish Tare Wt. <u>48.5267</u> g Dish+Sample Wt. <u>48.5387</u> g Sample Wt. <u>0.0120</u> g
2	Test <u>5</u> Run <u>2</u> Log Number <u>44</u> Comments	Dish No. <u>303</u> Dish Tare Wt. <u>49.5938</u> g Dish+Sample Wt. <u>49.5933</u> g Sample Wt. <u>0.0195</u> g	Dish No. <u>522</u> Dish Tare Wt. <u>47.0005</u> g Dish+Sample Wt. <u>47.0128</u> g Sample Wt. <u>0.0123</u> g
3	Test <u>5</u> Run <u>3</u> Log Number <u>47</u> Comments	Dish No. <u>304</u> Dish Tare Wt. <u>60.5548</u> g Dish+Sample Wt. <u>60.5647</u> g Sample Wt. <u>0.0149</u> g	Dish No. <u>524</u> Dish Tare Wt. <u>48.0411</u> g Dish+Sample Wt. <u>48.0498</u> g Sample Wt. <u>0.0087</u> g
4	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Log Number Comments	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phase:

Field Blk.	Run 1	Run 2	Run 3	Blank Solvent Wt. <u>0.0004</u> g	Run 4	Run 5
	<u>0.0159</u>	<u>0.0191</u>	<u>0.0145</u>			

Results Aqueous Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	<u>0.0116</u>	<u>0.0119</u>	<u>0.0083</u>		



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job L.P. Corrigan TX Source #2A Dwyer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-25-92
Test No. 3 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson
Transport Leakage ☒ None ☐ _____ ml Solvent Acetone

0	Test <u> </u> Run <u>0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue _____ ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>5</u> Run <u>1</u> Vol. of Solvent <u>40</u> ml Log Number <u>5792-39</u> Comments _____	Dish No. <u>504</u> Dish Tare Wt. <u>50.0204</u> g Dish+Sample Wt <u>50.0226</u> g Sample Wt. <u>0.0022</u> g
2	Test <u>5</u> Run <u>2</u> Vol. of Solvent <u>50</u> ml Log Number <u>-42</u> Comments _____	Dish No. <u>508</u> Dish Tare Wt. <u>46.5023</u> g Dish+Sample Wt. <u>46.5055</u> g Sample Wt. <u>0.0032</u> g
3	Test <u>5</u> Run <u>3</u> Vol. of Solvent <u>60</u> ml Log Number <u>-45</u> Comments _____	Dish No. <u>521</u> Dish Tare Wt. <u>50.5950</u> g Dish+Sample Wt <u>50.5981</u> g Sample Wt. <u>0.0031</u> g
4	Test <u> </u> Run <u> </u> Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u> </u> Run <u> </u> Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10⁶)] / Vol. of Sol. _____ ml
EPA-M5 Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0021	0.0030	D-39	0.0029		
--	--------	--------	------	--------	--	--



Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics
PM-10

Job LP. Corrigan, Tx Source #2A Dryer
Team Leader DB Test Site Stack
Date Submitted 4-13-92 Date of Test 3-25-92
Test No. 5 No. of Runs Completed 3
Date of Analysis 4-14-92 Technician C. Helgeson

0	Test <u> </u> Run <u>0</u> Field Blank Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
1	Test <u>5</u> Run <u>1</u> Log Number <u>5792-40</u> Comments <u> </u>	Filter No. <u>5635</u> Filter Type <u>2.5" GF</u> Filter Tare Wt. <u>.2500</u> g Filter+Sample Wt. <u>.3533</u> g Sample Wt. <u>0.1033</u> g
2	Test <u>5</u> Run <u>2</u> Log Number <u>-43</u> Comments <u> </u>	Filter No. <u>5637</u> Filter Type <u>2.5" GF</u> Filter Tare Wt. <u>.2535</u> g Filter+Sample Wt. <u>.4011</u> g Sample Wt. <u>0.1476</u> g
3	Test <u>5</u> Run <u>3</u> Log Number <u>-46</u> Comments <u> </u>	Filter No. <u>5647</u> Filter Type <u>2.5" GF</u> Filter Tare Wt. <u>.2516</u> g Filter+Sample Wt. <u>.3555</u> g Sample Wt. <u>0.1039</u> g
4	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g
5	Test <u> </u> Run <u> </u> Log Number <u> </u> Comments <u> </u>	Filter No. <u> </u> Filter Type <u> </u> Filter Tare Wt. <u> </u> g Filter+Sample Wt. <u> </u> g Sample Wt. <u> </u> g

Results:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.1033	0.1476	0.1039		

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.1329	0.1816	0.1296		

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Impinger Catch/Wisconsin Protocol

Job L.P. Corrigan TX Source #3 Dryer
Team Leader D.B. Test Site Stack
Date Submitted 4-13-92 Date of Test 4-26-92
Test No. 10 No. of Runs Completed 3
Date of Analysis 4-23-92 Technician C. Helgeson

		Solvent Phase	Aqueous Phase
0	Test <u>10</u> Run <u>0</u> Field Blank Log Number <u>5792-144</u> Comments _____	Dish No. <u>75</u> Dish Tare Wt. <u>80.5170</u> g Dish+Sample Wt. <u>80.5179</u> g Sample Wt. <u>0.0009</u> g	Dish No. <u>507</u> Dish Tare Wt. <u>47.8438</u> g Dish+Sample Wt. <u>47.8435</u> g Sample Wt. <u>0.0004</u> g
1	Test <u>10</u> Run <u>1</u> Log Number <u>-73</u> Comments _____	Dish No. <u>78</u> Dish Tare Wt. <u>85.5453</u> g Dish+Sample Wt. <u>85.5466</u> g Sample Wt. <u>0.0043</u> g	Dish No. <u>511</u> Dish Tare Wt. <u>45.5430</u> g Dish+Sample Wt. <u>45.5462</u> g Sample Wt. <u>0.0057</u> g
2	Test <u>10</u> Run <u>2</u> Log Number <u>-76</u> Comments _____	Dish No. <u>82</u> Dish Tare Wt. <u>60.7639</u> g Dish+Sample Wt. <u>60.7719</u> g Sample Wt. <u>0.0080</u> g	Dish No. <u>514</u> Dish Tare Wt. <u>48.7145</u> g Dish+Sample Wt. <u>48.7175</u> g Sample Wt. <u>0.0030</u> g
3	Test <u>10</u> Run <u>3</u> Log Number <u>-79</u> Comments _____	Dish No. <u>86</u> Dish Tare Wt. <u>73.5477</u> g Dish+Sample Wt. <u>73.5516</u> g Sample Wt. <u>0.0041</u> g	Dish No. <u>519</u> Dish Tare Wt. <u>49.0514</u> g Dish+Sample Wt. <u>49.0598</u> g Sample Wt. <u>0.0084</u> g
4	Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

Results Solvent Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	<u>0.0039</u>	<u>0.0076</u>	<u>0.0037</u>		

Blank Solvent Wt. 0.0004 g

Results Aqueous Phase:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	<u>0.0053</u>	<u>0.0026</u>	<u>0.0080</u>		

LSC-03WYR

LSC-011K

LSC-02PR

EPA Method 10 NDIR Analysis

Job Name Louisiana Pac. f.c. / Corrigan, TX
 Source No. 1 Dryer / Stack
 Date of Analysis 3-25-92
 Technician Mark Baehner

NDIR Analyzer: ☒ Fuji ACS Model 3300
☐ Mon. Lab Model 8310
☐ Dasibi Model 3003
 Range: 0 - 500 ppm
 Flow rate: 1000 cc/min

Pretest Calibration				Post-test Calibration			
Conc.	Reading	Vendor	Cyl. Number	Conc.	Reading	Vendor	Cyl. Number
Zero gas: <u>0</u> ppm	<u>0</u> ppm	<u>Scott</u>	<u>K000472</u>	Zero gas: <u>0</u> ppm	<u>0</u> ppm	<u>Scott</u>	<u>K000472</u>
Upscale gas: <u>150</u> ppm	<u>146</u> ppm	<u>Scott</u>	<u>AM008828</u>	Upscale gas: <u>150</u> ppm	<u>150</u> ppm	<u>Scott</u>	<u>AM008828</u>
Upscale gas: <u>237</u> ppm	<u>242</u> ppm	<u>Linde</u>	<u>HA 8854</u>	Upscale gas: <u>237</u> ppm	<u>245</u> ppm	<u>Linde</u>	<u>HA 8854</u>
Upscale gas: <u> </u> ppm	<u> </u> ppm	<u> </u>	<u> </u>	Upscale gas: <u> </u> ppm	<u> </u> ppm	<u> </u>	<u> </u>

Sample Description Test/Run	Sample Log Number	CO Conc. (ppm, Dry)		
		Dilution Factor	Reading	Actual ppm
2/1		1	212	213
2/2		1	179	179
2/3		1	150	150
4/1		1	114	114
4/2		1	105	105
4/3		1	93	93
6/1		1	276	276
6/2		1	235	235
6/3		1	185	185

Sample Description Test/Run	Sample Log Number	CO Conc. (ppm, Dry)		
		Dilution Factor	Reading	Actual ppm
5/1		1	207	207
5/2		1	202	202
5/3		1	200	200
9/1		1	164	164
9/2		1	145	145
8/1		1	166	166
8/2		1	204	204
1/1		1	320	320
1/2		1	200	200
1/3		1	160	160

Note 1: If sample dilution is required the sample is diluted with CO-free gas prior to analysis.

Note 2: The Fuji ACS model 3300 has a rejection ratio for CO to CO₂ greater than 100,000: 1 and the Mon. Labs Model 8310 and Dasibi Model 3003 have rejection ratios greater than 200,000: 1 and thus CO₂ removal prior to analysis is not required.

Note 3: The analyzer must be zeroed and spanned immediately before and after sample analysis. Additional checks may be performed between sample analyses if required.

Job Name Louisiana Pacific / Corrigan, TX
Source No. 3 Dryer / Stack
Date of Analysis 3-28-92
Technician Mark Bachler

Job Name Louisiana Pacific / Corvina, TX
Source No. 3 Dryer / Stack
Date of Analysis 3-28-92
Technician Mark Gachler

Post-test Calibration			
	Conc.	Reading	Vendor
Zero gas:	0 ppm	0	Scott
Upscale gas:	150 ppm	148	Scott
Upscale gas:	237 ppm	240	Linde
Upscale gas:	ppm	ppm	

[illegible]

Note 1: If sample dilution is required the sample is diluted with CO-free gas prior to analysis.

Note 2: The Fugio ACS model 3300 has a rejection ratio for CO to CO₂ greater than 100,000; 1 and the Mon. Labs Model 8310 and Dasibi Model 3003 have rejection ratios greater than 200,000; 1 and thus CO₂ removal prior to analysis is not required.

Note 3: The analyzer must be zeroed and spanned immediately before and after sample analysis. Additional checks may be performed between sample analyses if required.

INTERPOLL LABORATORIES, INC.
(612)786-6020

Louisiana Pacific/Corrigan, TX
Laboratory Log No. 5792

Results of Formaldehyde Analysis

Test: 2
Source: No. 1 Dryer Stack
Sample Type: Impinger Catch

Sample Log No.	Sample Description	Formaldehyde ^a
		Total ug
5792-16	Run 0, Field Blank	1.7
5792-17	Run 0, Field Spike	600
5792-18	Run 1	4200
5792-19	Run 2	1500
5792-20	Run 3	510

^aEPA Method 0011

INTERPOLL LABORATORIES, INC.
(612)786-6020

Louisiana Pacific/Corrigan, TX
Laboratory Log No. 5792

Results of Formaldehyde Analysis

Test: 6
Source: No. 1 Dryer Stack
Sample Type: Impinger Catch

Sample Log No.	Sample Description	Formaldehyde ^a
		Total ug
5792-48	Run 1	1500
5792-49	Run 2	4600
5792-50	Run 3	2800

^aEPA Method 0011

INTERPOLL LABORATORIES, INC.
(612)786-6020

Louisiana Pacific/Corrigan, TX
Laboratory Log No. 5792

Results of Formaldehyde Analysis

Test: 11
Source: No. 3 Dryer Stack
Sample Type: Impinger Catch

Sample Log No.	Sample Description	Formaldehyde ^a
		Total ug
5792-80	Run 1	2800
5792-81	Run 2	1400
5792-82	Run 3	3100

^aEPA Method 0011

INTERPOLL LABORATORIES, INC.
(612)786-6020

Louisiana Pacific/Corrigan, TX
Laboratory Log No. 5792

Results of Formaldehyde Analysis

Test: 15
Source: No. 4 Press Vent Stack
Sample Type: Impinger Catch

Sample Log No.	Sample Description	Formaldehyde ^a
		Total ug
5792-104	Run 0, Field Blank	5.2
5792-105	Run 0, Field Spike	600
5792-106	Run 1	2200
5792-107	Run 2	2400
5792-108	Run 3	3400

^aEPA Method 0011

INTERPOLL LABORATORIES, INC.
(612)786-6020

Louisiana Pacific/Corrigan, TX
Laboratory Log No. 5792

Results of Formaldehyde Analysis

Test: 18
Source: No. 3 Press Vent Stack
Sample Type: Impinger Catch

		Formaldehyde ^a
Sample Log No.	Sample Description	Total ug
5792-118	Run 1	3000
5792-119	Run 2	1900
5792-120	Run 3	3500

^aEPA Method 0011

INTERPOLL LABORATORIES, INC.
(612)786-6020

Louisiana Pacific/Corrigan, TX
Laboratory Log No. 5792

Results of Formaldehyde Analysis

Test: 21
Source: No. 2 Press Vent Stack
Sample Type: Impinger Catch

Sample Log No.	Sample Description	Formaldehyde ^a
		Total ug
5792-130	Run 1	700
5792-131	Run 2	820
5792-132	Run 3	750

^aEPA Method 0011

INTERPOLL LABORATORIES, INC.
(612)786-6020

Louisiana Pacific/Corrigan, TX
Laboratory Log No. 5792

Results of Formaldehyde Analysis

Test: 24
Source: No. 8 Exhaust Fan Vent Stack
Sample Type: Impinger Catch

Sample Log No.	Sample Description	Formaldehyde ^a
		Total ug
5792-139	Run 1	690
5792-140	Run 2	650
5792-141	Run 3	880

^aEPA Method 0011

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job LOUISIANA PACIFIC / CORVYAN, TX Source DRYER #1
Team Leader M.K. Test Site STACIL
Date Submitted _____ Date of Test 3/24/92
Test No. 1 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3 + BLANK	Probe Wash: ☒ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☒ Other <u>PM-10</u>	
3 + BLANK	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☒ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☒ Other <u>PM-10</u>	
3 + BLANK	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>PM-10</u>	
	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	
/	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
/	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
/	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
/	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pacific / Corrigan, TX Source No. 1 Dryer
 Team Leader M. Kaehler Test Site Stack
 Date Submitted _____ Date of Test 3-24-92
 Test No. 2 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
—	Probe Wash: ☐ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☐ Other _____	
—	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3+1+1	Impinger Catch: ☐ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☒ Other <u>2-4 DNPH</u>	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☒ Formaldehyde ☐ Metals ☐ Other _____	
3	Integrated Gas sample	☒ As per EPA M-3 ☒ As per EPA M-10 ☐ Other _____	
1	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
1	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
1	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
1	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pac. Co. / Corrigan, TX Source Ab. 1 Dryer
Team Leader M. Kachler Test Site Stueb
Date Submitted _____ Date of Test 3-24-92
Test No. 4 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3 +1	Probe Wash: ☒ Acetone ☐ D.I. Water	☒ As per EPA M-5 ☐ Other _____	
3 +1	Filter: ☒ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☒ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3 +1	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4MS Hg Only ☐ 4MS Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>Michigan Protocol</u>	<u>Method 202</u>
3	Integrated Gas sample	☒ As per EPA M-3 ☒ As per EPA M-10 ☐ Other _____	
-	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
-	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
-	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
-	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job LOUISIANA PACIFIC (CORAL GLEN, TX.) Source NO. 2A DRYER
Team Leader M. KOEHLER Test Site STALK
Date Submitted Date of Test 3/23/92
Test No. 5 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3	Probe Wash: ☒ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☒ Other <u>PM-10</u>	
3	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☒ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☒ Other <u>PM-10</u>	
3	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☐ Other <u> </u>	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>PM-10</u>	
/	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other <u> </u>	
/	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other <u> </u>	Date <u> </u> Time (HRS) <u> </u>
/	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
/	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other <u> </u>	
/	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other <u> </u>	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other <u> </u>	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pacific / Corrigan, TX Source No. 1 Dryer
Team Leader M. Raehler Test Site Stack
Date Submitted _____ Date of Test 3-24-92
Test No. 26 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
—	Probe Wash: ☐ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☐ Other _____	
—	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
2 3	Impinger Catch: ☐ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☒ Other <u>2-4 DAPH</u>	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☒ Formaldehyde ☐ Metals ☐ Other _____	
3	Integrated Gas sample	☒ As per EPA M-3 ☒ As per EPA M-10 ☐ Other _____	
—	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
—	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
—	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
—	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job LOUISIANA PACIFIC (CORRUGATED TX) Source NO. 2A DRYER STACK
Team Leader M. KESLER Test Site STACK
Date Submitted _____ Date of Test 3/25/92
Test No. 8 No. of Runs Completed 2

No. of Samples	Type of Sample	Analysis Required	Comments
2	Probe Wash: ☒ Acetone ☐ D.I. Water	☒ As per EPA M-5 ☐ Other _____	
2	Filter: ☒ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☒ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
2	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☐ Other _____	<u>BIASED IMPINGERS</u> <u>WITH D.I. H₂O</u> <u>+ METHALYN</u> <u>CHLORIDE AS PER</u> <u>TEST METHOD.</u>
0	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	
/	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
/	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
/	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
/	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☐ Wood ☒ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pacific / Corrigan, TX
Team Leader Michael
Date Submitted 3
Test No. 9

Source No. 2 B Dryer
Test Site Stach
Date of Test 3-25-92
No. of Runs Completed 2

No. of Samples	Type of Sample	Analysis Required	Comments
2+1	Probe Wash: ☒ Acetone ☐ D.I. Water	☒ As per EPA M-5 ☐ Other _____	
2+1	Filter: ☒ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☒ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
2+1	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>Michigan Protocol</u>	<u>202 Back half</u>
3	Integrated Gas sample	☒ As per EPA M-3 ☒ As per EPA M-10 ☐ Other _____	
—	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
—	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
—	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
—	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job LOUISIANA PACIFIC Source NO. 3 DRYER
Team Leader M. KAEHLER Test Site STACIL
Date Submitted - Date of Test 3/26/92
Test No. 10 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3	Probe Wash: ☒ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☒ Other <u>PM-10</u>	
3	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☒ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☒ Other <u>PM-10</u>	
3	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>PM-10</u>	
/	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	
/	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
/	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
/	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
/	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job LOUISIANA PACIFIC (CORRIGAN, TX.)
Team Leader M. KAEHLER
Date Submitted _____
Test No. 13

Source No. 3 DRYER
Test Site STACK
Date of Test 3/26/92
No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3	Probe Wash: ☒ Acetone ☐ D.I. Water	☒ As per EPA M-5 ☐ Other _____	
3	Filter: ☒ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☒ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4MS Hg Only ☐ 4MS Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>METHOD 202</u>	<u>RINSED IMPINGERS</u> <u>WITH D.I. H₂O</u> <u>+ M2 CL₂</u> <u>AND ADDED TO</u> <u>BACK-HOLE</u>
/	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	
/	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
/	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
/	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
/	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job LOUISIANA PACIFIC Source NO. 4 PRESS VENT
Team Leader A. KUEHLER Test Site STACIL
Date Submitted _____ Date of Test 3/27/92
Test No. 14 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3	Probe Wash: ☒ Acetone ☐ D.I. Water	☒ As per EPA M-5 ☐ Other _____	
3	Filter: ☒ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☒ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4MS Hg Only ☐ 4MS Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>METHOD 202</u>	<u>IMPINGERS RINSED</u> <u>WITH D.I. H₂O</u> <u>+ H₂O₂</u> <u>ADDED TO BACK</u> <u>HALF.</u>
/	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	<u>AMBIENT AIR</u>
/	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
/	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
/	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
/	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☐ Dryer
☒ Other PRESS VENT
- 2) Fuel: ☐ Coal ☐ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pacific / Corrigan, TX Source No. 4 Press Vent
Team Leader Mike Schler Test Site stack
Date Submitted _____ Date of Test 3-27-92
Test No. 15 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
—	Probe Wash: ☐ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☐ Other _____	
—	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3+1+1	Impinger Catch: ☐ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☒ Other <u>24 DAPV</u>	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☒ Formaldehyde ☐ Metals ☐ Other _____	
—	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	<u>Ambient</u>
—	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
—	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
—	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
—	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other Press
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other NA
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job LOUISIANA PACIFIC Source NO. 3 PRESS VENT
Team Leader M. KAENGER Test Site STACK
Date Submitted _____ Date of Test 3/27/92
Test No. 17 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3	Probe Wash: ☒ Acetone ☐ D.I. Water	☒ As per EPA M-5 ☐ Other _____	
3	Filter: ☒ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☒ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>METHOD 202</u>	<u>IMPINGERS RINSED WITH DI H₂O + MCL₂ AND DROD TO BULK-HOLE</u>
/	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	<u>AMBIENT AIR</u>
/	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
/	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
/	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
/	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☐ Dryer
☒ Other PRESS VENT
- 2) Fuel: ☐ Coal ☐ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pacific / Corrigan, TX Source No. 3 Dryer
Team Leader M. Kaehler Test Site stack
Date Submitted _____ Date of Test 3-26-92
Test No. 11 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
—	Probe Wash: ☐ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☐ Other _____	
—	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☐ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4MS Hg Only ☐ 4MS Metals ☐ 1.0 N NaOH ☒ Other <u>24 DAPH</u>	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☒ Formaldehyde ☐ Metals ☐ Other _____	
3	Integrated Gas sample	☒ As per EPA M-3 ☒ As per EPA M-10 ☐ Other _____	
—	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
—	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
—	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
—	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☒ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☒ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pacific / Kerrigan, TX Source No. 3 Press Vent
Team Leader M. Kuehler Test Site Stack
Date Submitted _____ Date of Test 3-27-92
Test No. 18 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
—	Probe Wash: ☐ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☐ Other _____	
—	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☐ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☒ Other <u>2-11 DUPH</u>	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☒ Formaldehyde ☐ Metals ☐ Other _____	
—	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	<u>Ambient</u>
—	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
—	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
—	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
✓	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☐ Dryer
☒ Other Press Vent
- 2) Fuel: ☐ Coal ☐ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other NA
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

No. 8

Job LOUISIANA PACIFIC Source Exhaust Fan
Team Leader D. Brennan Test Site Stack
Date Submitted _____ Date of Test 3-28-92
Test No. 20 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3	Probe Wash: ☐ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☐ Other _____	
3	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☐ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4MS Hg Only ☐ 4MS Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☐ Other _____	
	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	
	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☐ Dryer
☐ Other _____
- 2) Fuel: ☐ Coal ☐ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other _____
- 3) Is sample combustible? ☐ No ☐ Yes
- 4) Does sample need special handling? ☐ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pacific / Corcoran, TX Source No. 2 Press Vent
Team Leader M. Backler Test Site Stack
Date Submitted _____ Date of Test 3-20-92
Test No. 21 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
-	Probe Wash: ☐ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☐ Other _____	
-	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☐ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☒ Other <u>1-4 DNPH</u>	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☒ Formaldehyde ☐ Metals ☐ Other _____	
-	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	<u>Ambient</u>
-	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
-	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
-	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
-	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☐ Dryer
☒ Other Press Vent
- 2) Fuel: ☐ Coal ☐ Wood ☐ Gas ☐ Oil ☐ RDF ☒ Other NA
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job COUSIGNA PACIFIC / CORROSIVE TX Source NO. 2 PRESS VENT
Team Leader M. KASHLEN Test Site STOCK
Date Submitted _____ Date of Test 3/28/92
Test No. 23 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
3	Probe Wash: ☒ Acetone ☐ D.I. Water	☒ As per EPA M-5 ☐ Other _____	
3	Filter: ☒ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☒ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☒ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☐ Other _____	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☐ Formaldehyde ☐ Metals ☒ Other <u>HEAVY 202</u>	<u>IMPINGERS RINSED</u> <u>WITH D.I. H₂O</u> <u>& M&G/2 AND</u> <u>PODSD TO</u> <u>BACK HOLE</u>
/	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	
/	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
/	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
/	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
/	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	

Source Information

- 1) Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☐ Dryer
☒ Other PRESS VENT
- 2) Fuel: ☐ Coal ☐ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other N/A
- 3) Is sample combustible? ☒ No ☐ Yes
- 4) Does sample need special handling? ☒ No ☐ Yes If yes, explain _____

S-278RRRR

Interpoll Laboratories
(612) 786-6020

Chain of Custody
Sample Deposition Sheet

Job Louisiana Pacific / Corrigan, TX Source No. 8 Exhaust Fan Vent
Team Leader M. Kachler Test Site Stack
Date Submitted _____ Date of Test 3-20-92
Test No. 24 No. of Runs Completed 3

No. of Samples	Type of Sample	Analysis Required	Comments
—	Probe Wash: ☐ Acetone ☐ D.I. Water	☐ As per EPA M-5 ☐ Other _____	
—	Filter: ☐ 4" G.F. ☐ S.S. Thimble ☐ 2.5" G.F. ☐ 47 mm G.F.	☐ As per EPA M-5 ☐ As per EPA M-17 ☐ Other _____	
3	Impinger Catch: ☐ D.I. Water ☐ 3% H ₂ O ₂ ☐ 4M5 Hg Only ☐ 4M5 Metals ☐ 1.0 N NaOH ☒ Other <u>2-4 DAPH</u>	☐ MN Protocol ☐ WI Protocol ☐ EPA M-6 or 8 ☐ Acid Gases ☒ Formaldehyde ☐ Metals ☐ Other _____	
—	Integrated Gas sample	☐ As per EPA M-3 ☐ As per EPA M-10 ☐ Other _____	<u>Ambient</u>
—	Oxides of Nitrogen (NO _x)	☐ As per EPA M-7A ☐ Other _____	Date _____ Time (HRS) _____
—	☐ Fuel Sample ☐ Aggregate	☐ Attached fuel Form #S-0163RRR	
—	Particle Size	☐ X-Ray Sedigraph ☐ Bahco Method ☐ Other _____	
—	Audit Samples ☐ Sulfur Dioxide ☐ Oxides of Nit. ☐ Other _____	☐ As per EPA M-6 ☐ As per EPA M-7A ☐ Other _____	


Source Information

- Type of Source: ☐ Boiler ☐ Asphalt Plant ☐ Incinerator ☐ Dryer
☒ Other Conveyor Belt
- Fuel: ☐ Coal ☐ Wood ☐ Gas ☐ Oil ☐ RDF ☐ Other NA
- Is sample combustible? ☒ No ☐ Yes
- Does sample need special handling? ☒ No ☐ Yes If yes, explain _____



TEST 3
 RUN 1 →
 START
 No. 1 Dryer
 LP-
 Corrigan

Total
 Hydro-
 Carbons




TEST 3
RUN 2 →
START

TEST 3
RUN 1 →
END

LP-
Corrigan
(cont.)


THC



TEST 3
RUN 2

LP-
Corrigan
(cont.)


No. 1
Dryer
Stack



T3R3
START


TEST 3
RUN 2
END

LP-
Corrigan
(cont.)



LP-
Corrigan
(cont.)

T₃R₃
(cont.)



No. 2 A Dryer Stack

3-25-92

304 ppm 0-1000 scale system bias
1605 hrs


Oppn 0-1000 scale system bias 1600 hrs


T3 R3 →
END

No. 1
Dryer

15m60cm

LP -
Corrigan





TEST 7
 RUN 1
 START
 No. 2 A Dryer
 Stack


LP-
Corrigan
(cont.)



LP-
Corrigan

Test 7
Run 2
(cont.)


No. 2 A
Dryer
Stack



LP-
Corrigan
(cont.)

T₇ Run 3
START


T₇ R₂
END



T7R3
END


LP-
Corrigan
(cont.)

No. 2A
Dryer
Stack



No. 3 Dryer
Stack


TEST 12
LP-Corrigan
TOTAL
HYDRO-
CARBONS



→
TEST 12
RUN 1
END

LP-
Corrigan
T₁₂ R,
CONTINUED

THC



13m30cm

0 20 40 60 80 100

0 20 40 60 80 100

CHART NO. B9565AW IN

T12/R2 0-1000 scale 1135 Hz

304 ppm 0-1000 scale
system bias 1038

0 20 40 60 80 100
0 ppm 0-1000 scale system bias 1035

14m
END T12/R2 0-1000 scale 1030 Hz

(82521)

TEST 12
RUN 2 →
START

LP-
Corrigan
THC

1530 Hrs

0 ppm 0-1000 scale system blank 1524 Hrs

T₁₂ R₂ →
END

END TIR/RL 0-1000 scale 1251 Hrs

0 20 40 60 80 100

13 mEC cm

LP-
Corrigan
(cont.)

0 20 40 60 80 100

THC

0 20 40 60 80 100


CHART NO. B9565AW NH

13 m30 cm

62527


LP -
Corrigan
(cont.)
THC

TEST 12
RUN 3 →
START




TEST 12
RUN 3 →
END

LP-
Corrigan
THC




TEST 16
 RUN 1 →
 START
 NO. 4 Press
 Vent
 LP-
 Corrigan
 Total
 Hydro-
 Carbons




TEST 16
RUN 1 →
END

LP-Corrigan
(cont.)

THC




LP-
Corrigan
(cont.)
THC



TEST 16
RUN 2 →
START


LP-
Corrigan
(cont.)
TEST 16 →
RUN 3
START

TEST 16 →
RUN 2
END



TEST 16
 RUN 3
 END


LP-
 Corrigan



LP-
Corrigan
(cont.)


NO. 3 Press
Vent

TEST 19
RUN →
START



TEST 19
 RUN 2
 START
 LP-
 Corrigan

TEST 19
 RUN 1
 END




TEST 19
RUN 2
END

NO. 3 PRESS
Vent


LP-
Corrigan
(cont.)

THC



LP-
Corrigan
(cont.)

TEST 19
RUN 3
START →



TEST 22
RUN 1 →
START
NO. 2 Press
Vent Stack

LP-
Corrigan
(cont.)

TEST 19
RUN 3 →
END

changed Range 0-100 ppm

No. 2 Press Vent
stack

Corrigan, TX

3-27-92

T 22 / R 1 0-1000 scale 0830 Hrs

304 ppm 0-1000 scale
system bias 0815

30 ppm 0-1000 scale system bias 0812

0 ppm 0-1000 scale system bias 0810

3-28-92

10 ppm 304 ppm 0-1000 scale
system bias 1912 Hrs

30 ppm 0-1000 scale system bias 1910 Hrs

0 ppm 0-1000 scale system bias 1905 Hrs


END T 19 / R 3 0-1000 scale 1856 Hrs


CHART NO. B9565AW.NN

TEST 22
RUN 1
(cont.)

LP-
Corrigan
(cont.)

THC





TEST 22
RUN 2
START →

No. 2 Press
Vent Stack


TEST 22
RUN 1
END

TEST 22 →
 RUN 3
 START

TEST 22 →
 RUN 2
 END

LP-
 Corrigan
 (cont.)


THC



TGS# 22
Run 3
(cont.)

LP-
Corrigan


No. 2
Press vent
Stack



LP-
Corrigan

TEST 22
RUN 4 →
START


TEST 22
RUN 3
END




TEST 22
RUN 4
END

LP-
Corrigan

No. 2
Press vent
Stack







TOTAL HYDROCARBON ANALYZER (FLAME IONIZATION)
Model RS 55

TECHNICAL DATA

MAINS : 115V/60H

RECORDER OUTPUT : 0 - 5 V / 4-20mA

MODEL: ☒ Manual switching
 ☐ Solenoid valves

HOUSING: ☐ Case, ☐ 19"- Rack

MEASURING RANGES:	1 = 0 - 10	C ₁ -
	2 = 0 - 100	C ₁
	3 = 0 - 1,000	C ₁
	4 = 0 - 10,000	C ₁

SPECIAL OPTIONS:

Flame out alarm
1 Alarm
Sample line
.....

ANALYZER CONDITIONS:

Temperature : 160 °C

Zero Point : 3,90


Gain : 7,70

Pressure Setting: Sample/Spangas/Zerogas: 200 mbar

Fuel: Hydrogen : 0,35 bar

Combustion Air : 0,80 bar

Span Gases : 300 ppm C₁
 24.000 ppm C₁




- 1 Druckregler / pressure regulator
- 2 Manometer / Gauge
- 3 Filter / Filter
- 4 Mischventil / Mixture valve
- 5 3 Wege Ventil / 3 way valve
- 6 Kapillare / capillary
- 7 Magnetventil / solenoid valve
- 8 Pumpe / pump
- 9 Rückdruckregler / back pressure regulator

Zündventil / Ignition valve

P-A angezogen / Energized

R-A Stromlos / at rest



FLAMMEN IONISATIONS DETECTOR
Flame Ionization Detector


Fließplan / Flow diagram

RS 55

Handumschaltung / Manual switching

13.04.88

CALIBRATION DIAGRAMM



26A



INTERPOLL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX

Source No. 1 Dyer / Stuch

Test 23 Run 0 Date 3-24-92

Stack dimen. 48 IN.

Dry bulb _____ °F Wet bulb _____ °F


Manometer: ☐ Reg. ☐ Exp. ☐ Elec.

Barometric pressure 29.83 in Hg

Static pressure -1.75 in WC

Operators M. Hackler + C. Mosser

Pitot No. Inst Cp NA



Schematic of Cross Section

[illegible]

R or nothing= reg. manometer; S= expanded; E = electronic

S-392.1

Calibration Error Check & Drift Determination

Job Louisiana Pacific / Corrigan, TXTest #3 Run 1,2,3 Date 3-28-92Operator Michael & C. Mosser

THC Calibration (Low Range):

Time (HRS) 0845

*** A	Cylinder Value (ppm)	Analyzer Response (ppm)	Difference (ppm)	Span Value (ppm)	Percent of Span
Zero gas	0	0	0	100	0
Low level	30	30	0	100	0
Mid level	304	307	3	1000	.003
High level	3038	3042	4	10000	.0004

THC Calibration (High Range):

Time (HRS) _____

***	Cylinder Value (ppm)	Analyzer Response (ppm)	Difference (ppm)	Span Value (ppm)	Percent of Span
Zero gas	0				
Span					

O₂ Calibration:

Time (HRS) _____

***	Cylinder Value (%)	Analyzer Response (%)	Difference (%)	Span Value (%)	Percent of Span
Zero gas	0				
Mid level					
High level					

CO₂ Calibration:

Time (HRS) _____

***	Cylinder Value (%)	Analyzer Response (%)	Difference (%)	Span Value (%)	Percent of Span
Zero gas	0				
Mid level					
High level					

Must be within 2% of the span for each calibration gas

S-420-14

INTERPOLL LABORATORIES
(612) 786-6020

System Bias Check

Job Louisiana Pacific / Corrigan, TX Source No. 1 Dryer /
Test 22 Run 1,2,3 Date 3-24-92 Site Stach
Operator M. Kachler & C. Mosser

Run	Time (HRS)	***	Cylinder Value (ppm)	Analyzer Resp (ppm)		Diff. CE-SB (ppm)	Span Val (PPM)	% of span
				Cal Err	Sys Bias			
1	0910	Zero gas	0	0	1	1	100	1
		Upscale	30	30	29	1	100	1
2	1125	Zero gas	0	0	1	1	1000	.1
		Upscale	304	307	297	10	1000	1
3	1333	Zero gas	0	0	3	3	1000	.3
		Upscale	304	307	300	7	1000	.7
4	1600	Zero gas	0	0	1	1	1000	.1
		Upscale	304	307	299	8	1000	.8
5		Zero gas	0					
		Upscale						
6		Zero gas	0					
		Upscale						
7		Zero gas	0					
		Upscale						
8		Zero gas	0					
		Upscale						
9		Zero gas	0					
		Upscale						
10		Zero gas	0					
		Upscale						
11		Zero gas	0					
		Upscale						
12		Zero gas	0					
		Upscale						

Must be within 5% of the span for the zero or upscale cal. gas.

S420-11R

INTERPOLL LABORATORIES

EPA Method 6C/7E Response Time

Job Louisiana Pac. Inc. / Corns, TX
 Source No. 1 Dryer / Stack
 Date of test 3-24-92

Technician Mark Baskin
 System flow rate 2 PSI

Moisture removal: Via Model MK-1
 Condenser

	Response Time (secs)		
Analyzer type:	SO ₂ /NO _x	THC gas	CO ₂
Analyzer S/N:		3	
Analyzer Range:		0-1000	
High level span gas conc. (ppm or %)		304	
Upscale 1		20	
Upscale 2			
Upscale 3			
Average:			
Downscale 1			
Downscale 2			
Downscale 3			
Average:			

System Response Time: 20 seconds

1. Introduce gases at the 3-way valve on the probe. Use zero and stack gas for the upscale tests and high-level span gas and stack gas for the downscale tests. Alternatively, use zero and high-level gases for a more stringent test. Record the time in seconds from the moment of introduction until a stable response is achieved.
2. The response time test need only be conducted prior to the initial field use of the measurement system.
3. Attach a copy of the flow system schematic to this test.

INTERPOLL LABORATORIES EPA METHOD 2 FIELD DATA SHEET

Job Louisiana Pacific / Corrigan, TX

Source No. 2A Dyer / Staal

Test 2 Run 0 Date 3-25-92

Stack dimen. 29 IN.

Dry bulb _____ °F Wet bulb _____ °F


Manometer: ☐ Reg. ☐ Exp. ☐ Elec.

Barometric pressure 29.77 in Hg

Static pressure -1.5 in WC

Operators M. Kähler + B. Aschenbach

Pitot No. Inst Cp NA

[illegible]

R or nothing= reg. manometer; S= expanded; E = electronic S-392.1

INTERPOLL LABORATORIES
(612) 786-6020

System Bias Check


Job Louisiana Pacific / Corrigan, TX Source No. 2 A Dryer
Test 7 Run 1,2,3 Date 3-25-92 Site Stuck
Operator M. Kachler

Run	Time (HRS)	***	Cylinder Value (ppm)	Analyzer Resp (ppm)		Diff. CE-SB (ppm)	Span Val (PPM)	% of span
				Cal Err	Sys Bias			
1	0930	Zero gas	0	0	0	0	1000	
		Upscale	304	307	303	4	1000	
2	0955 1100	Zero gas	0	0	1	1	1000	
		Upscale	304	307	308	1	1000	
3	1225	Zero gas	0	0	2	2	1000	
		Upscale	304	307	312	5	1000	
4	1405	Zero gas	0	0	3	3	1000	
		Upscale	304	307	314	7	1000	
5		Zero gas	0					
		Upscale						
6		Zero gas	0					
		Upscale						
7		Zero gas	0					
		Upscale						
8		Zero gas	0					
		Upscale						
9		Zero gas	0					
		Upscale						
10		Zero gas	0					
		Upscale						
11		Zero gas	0					
		Upscale						
12		Zero gas	0					
		Upscale						

Must be within 5% of the span for the zero or upscale cal. gas.

S420-11R

Job Louisiana Pacific / Corrigan, TX
Source No. 3 Dryer / Stack
Test 12 Run 0 Date 3-26-92
Stack dimen. 41.5 IN.
Dry bulb °F Wet bulb °F
Manometer: ☐ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 29.92 in Hg
Static pressure -0.68 in WC
Operators M. Kaehler & C. Mosser
Pitot No. Inst Cp NA

[illegible]

R or nothing= reg. manometer; S= expanded; E = electronic

S-392.1

INTERPOLL LABORATORIES
(612) 786-6020

System Bias Check


Job Louisiana Pacific / Corrigan, TX Source No. 3 Dryer
Test 12 Run 1,2,3 Date 3-26-92 Site Stark
Operator Mike Kehler

Run	Time (HRS)	***	Cylinder Value (ppm)	Analyzer Resp (ppm)		Diff. CE-SB (ppm)	Span Val (PPM)	% of span
				Cal Err	Sys Bias			
1	0845	Zero gas	0	0	0	0	1000	
		Upscale	304	307	303	4	1000	
2	1035	Zero gas	0	0	3	3	1000	
		Upscale	304	307	300	7	1000	
3	1322	Zero gas	0	0	3	3	1000	
		Upscale	304	307	304	3	1000	
4	1530	Zero gas	0	0	2	2	1000	
		Upscale	304	307	313	6	1000	
5		Zero gas	0					
		Upscale						
6		Zero gas	0					
		Upscale						
7		Zero gas	0					
		Upscale						
8		Zero gas	0					
		Upscale						
9		Zero gas	0					
		Upscale						
10		Zero gas	0					
		Upscale						
11		Zero gas	0					
		Upscale						
12		Zero gas	0					
		Upscale						

Must be within 5% of the span for the zero or upscale cal. gas.

S420-11R

Job Louisiana Pacific/Korrigan, TX
Source No. 34 Press Vents / Stacks
Test 164P Run 0 Date 3-27-92
Stack dimen. 62.75 IN.
Dry bulb _____ °F Wet bulb _____ °F
Manometer: ☐ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 29.56 in Hg
Static pressure -.12 in WC
Operators M. Kachler & C. Mosser
Pitot No. Inst Cp NA

[illegible]

R or nothing= reg. manometer; S= expanded; E = electronic S-392.1

INTERPOLL LABORATORIES
(612) 786-6020

System Bias Check


Job Louisiana Pacific / Corrigan, TX Source Ab. 34 Press Vents
Test 1649 Run 1,2,3 Date 3-27-92 Site Stacks
Operator Michael

Run	Time (HRS)	***	Cylinder Value (ppm)	Analyzer Resp (ppm)		Diff. CE-SB (ppm)	Span Val (PPM)	% of span
				Cal Err	Sys Bias			
1	0910	Zero gas	0	0	0	0	1000	
		Upscale	304	307	307	0	1000	
2	1021	Zero gas	0	0	2	2	1000	
		Upscale	304	307	308	1	1000	
3		Zero gas	30	30	32	2	1000	
		Upscale						
4	1207	Zero gas	0	0	2	2	1000	
		Upscale	304	307	311	4	1000	
5		Zero gas	30	30	32	2	1000	
		Upscale						
6	1348	Zero gas	0	0	3	3	1000	
		Upscale	304	307	312	5	1000	
7		Zero gas	30	30	33	3	1000	
		Upscale						
8	1535	Zero gas	0	0	3	3	1000	
		Upscale	304	307	307	0	1000	
9		Zero gas	30	30	32	2	1000	
		Upscale						
10	1714	Zero gas	0	0	3	3	1000	
		Upscale	304	307	302	5	1000	
11		Zero gas	30	30	31	1	1000	
		Upscale						
12	1900	Zero gas	0	0	1	1	1000	
		Upscale	304	307	297	10	1000	
			30	30	30	0	1000	

Must be within 5% of the span for the zero or upscale cal. gas.

S420-11R

Job Louisiana Pacific / Corrigan, TX
Source Ab. 2 Press Vent / Stack
Test 22 Run 0 Date 3-27-92
Stack dimen. 62-75 IN.
Dry bulb °F Wet bulb °F
Manometer: ☐ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 29.96 in Hg
Static pressure -1.12 in WC
Operators M. Fackler + C. Messer
Pitot No. Inst Cp VA

[illegible]

INTERPOLL LABORATORIES
(612) 786-6020

System Bias Check

Job Louisiana Pacific / Corrigan, TX Source No. 2 Press Vent
Test 22 Run 1, 2, 3, 4 Date 3-27-92 Site Stack
Operator M. LaChelle

Run	Time (HRS)	***	Cylinder Value (ppm)	Analyzer Resp (ppm)		Diff. CE-SB (ppm)	Span Val (PPM)	% of span
				Cal Err	Sys Bias			
1	0810	Zero gas	0	0	0	0	1000	
		Upscale						
2		Zero gas	30	30	30	0	1000	
		Upscale						
3	0943	Zero gas	0	0	0	0	1000	
		Upscale	30	28	28	2	100	
4	1143	Zero gas	0	0	1	0	100	
		Upscale	30	30	30	0	100	
5	1256	Zero gas	0	0	0	0	100	
		Upscale	30	32	2	0	100	
6	1407	Zero gas	0	0	0	0	100	
		Upscale	30	30	31	1	100	
7		Zero gas	0					
		Upscale						
8		Zero gas	0					
		Upscale						
9		Zero gas	0					
		Upscale						
10		Zero gas	0					
		Upscale						
11		Zero gas	0					
		Upscale						
12		Zero gas	0					
		Upscale						

Must be within 5% of the span for the zero or upscale cal. gas.

S420-11R

Scott Specialty Gases

a division of
Scott Environmental Technology, Inc.

1290 COMBERMERE STREET, TROY, MICHIGAN 48064 (313) 589-2950

Customer :

GENEX
2455 CLEVELAND AVENUE N.
ROBEVILLE, MN. 55113

1111 CERTIFICATE OF ANALYSIS - EPA PROTOCOL BASES 1111
PERFORMED ACCORDING TO SECTION 3.0.4
Certified Per Traceability
Protocol # 1

Certified Accuracy 1 % NBS Traceable

File # PO-2217

Cylinder Pressure 1500 psig

1 OF 1 COMPONENT(S)

INSTRUMENTATION

REFERENCE STD

ANALYZED CYLINDER

COMPONENT
PROpane

CERTIFIED
CONC.

SRM #
(CRM #)

CYLINDER
NUMBER

CONC.

INSTR/MODEL/SERIAL #

LAST CALIBRA-
TION DATE

ANALYTICAL PRINCIPLE

FLAME IONIZATION DETECTOR

2-18-92

BECKMAN
400

FF-26980
ALN-008846

47.80 PPM
31.20 PPM

16678
8M19

30.07 PPM

BALANCE GAS : AIR

ANALYSIS

DATE : 2-18-92

ZERO	TEST	REFERENCE	RESULTS
GAS	GAS	GAS	PPM
(mV)	(mV)	CONC.	PPM
0.00	30.20	47.80 PPM	47.80
0.00	30.20	47.80	47.80
0.00	30.20	47.80	47.80

CALCULATED
RESULTS
30.07

AVERAGE : 30.07 PPM

CALIBRATION CURVE 3 rd DEGREE

SRM #	CONC.	SPLIT	DVM	FITTED PERCENT
(CRM #)	PPM	PT (%)	(mV)	VALUE ERROR
16678	47.80	100	47.80	47.80 0.00
	31.20	65	31.40	31.26 0.20
	22.61	47	22.60	22.53 -0.33
	8.17	17	8.20	8.23 0.70
	0.00	0	0.00	0.00 0.00
		0		0.0000 0.00
		0		0.00 0.00
8M19	8.17	LOW	8.20	8.23 0.70
16849	47.80	HIGH	47.80	47.80 0.00

8M19 - GAS MANUFACTURER'S INTERNAL STANDARD
This Company for Gas which fail to comply with this analysis shall be replaced at the expense of the Company without extra cost.

Scott Specialty Gases



Scott Specialty Gases

a division of
Scott Environmental Technology, Inc.

1290 COMBERMERE STREET, TROY, MICHIGAN 48064 (313) 589-2950

Customer :

GENEX
2455 CLEVELAND AVENUE N.
ROBEVILLE, MN. 55113

*** CERTIFICATE OF ANALYSIS - EPA PROTOCOL BASED ***
PERFORMED ACCORDING TO SECTION 3.0.4
Certified Per Traceability
Procedure # 01
Protocol # 1

Certified Accuracy 1X NBS TRACEABLE

REFERENCE STD

COMPONENT	CERTIFIED CONC.	SRM # (CRM #)	CYLINDER NUMBER	CONC.
PROPANE	304.3 PPM	1669B	CLM-000702	466.0 PPM
		1668B	CLM-000694	95.00 PPM

BALANCE GAS : AIR

INSTRUMENTATION

INSTR/MODEL/SERIAL #
LAST CALIBRATION DATE
1-23-92
BECKMAN 400
1002059

ANALYTICAL PRINCIPLE

FLAME IONIZATION DETECTOR

ANALYSIS

DATE : 2-6-92

ZERO	TEST GAS	REFERENCE GAS	RESULTS
(mV)	(mV)	CONC.	PPM
0.00	65.70	466.0 PPM	100.00
0.00	65.70	100.00	100.00
0.00	65.70	100.00	100.00

CALCULATED RESULTS
304.3
304.3
304.3

AVERAGE : 304.3 PPM

CALIBRATION CURVE				2 nd DEGREE	
SRM # (CRM #)	CONC. PPM	SPLIT PT (%)	DVM (mV) VALUE	FITTED PERCENT	ERROR
1669B	466.0	100	100.00	466.0	0.00
	315.8	68	68.10	315.6	-0.08
	199.9	43	43.30	199.7	-0.10
1668B	95.00	20	20.80	95.45	0.47
	0.0000	0	0.00	0.0000	0.00
		0		0.0000	0.00
		0		0.00	0.00
1668B	95.00	LOW	20.80	95.45	0.47
1669B	466.0	HIGH	100.00	466.0	0.00

APPROVED BY :

which fails to comply with this analysis shall be replacement thereof by the Company without extra cost.

1 6819 - GAS MANUFACTURER'S INTERNAL STANDARD

Shapiro

Scott Specialty Gases

a division of
Scott Environmental Technology, Inc.

1290 COMBERMERE STREET, TROY, MICHIGAN 48064 (313) 589-2950

Customer :

BENEX

2455 CLEVELAND AVENUE N.
ROSEVILLE, MN. 55113

1111 CERTIFICATE OF ANALYSIS - EPA PROTOCOL GASES 1111

PERFORMED ACCORDING TO SECTION 2.0.7.

Certified Per Traceability Procedure # 62

Protocol # 2

File # PD-2184

Certified Accuracy 2% ANALYTICAL UNCERTAINTY

Shipped From : Scott Michigan

Our Project # : 333359

Your P.O. # : 6033WH

Expiration Date : 8-6-93

Cylinder Number : BLM-001645

Cylinder Pressure : 1665 psig

1 OF 1 COMPONENTS

INSTRUMENTATION

REFERENCE STD

SRM #	CYLINDER NUMBER	CONC.
1669B	CLM-000702	466.0 PPM
1668B	CLM-000694	95.00 PPM

INSTR/MODEL/SERIAL #

BECKMAN
400
1002059

LAST CALIBRATION DATE

1-23-92

ANALYTICAL PRINCIPLE

FLAME IONIZATION DETECTOR

ANALYZED CYLINDER

COMPONENT	CERTIFIED CONC.
PROPANE	3038 PPM

BALANCE GAS : AIR

ANALYSIS

DATE : 2-6-92

ZERO GAS (mV)	TEST GAS (mV)	REFERENCE		RESULTS PPM
		CONC.	GAS	
0.00	65.60	466.0 PPM	100.00	466.0
0.00	65.60	100.00	100.00	466.0
0.00	65.60	100.00	100.00	466.0

CALCULATED RESULTS
303.8
303.8
303.8
AVERAGE : 303.8 PPM

SAMPLE GAS SPLIT & 10% OF FULL CONC.
303.8 PPM DIVIDED BY 10% = 3038 PPM.

CALIBRATION CURVE		2 nd DEGREE	
SRM #	CONC. (PPM)	SPLIT DVM PT (X)	FITTED PERCENT VALUE ERROR
1669B	466.0	100 100.00	466.0 0.00
	315.8	68 68.10	315.6 -0.08
	199.9	43 43.30	199.7 -0.10
1668B	95.00	20 20.80	95.45 0.47
	0.0000	0 0.00	0.0000 0.00
	0	0	0.0000 0.00
	0	0	0.00 0.00
1668B	95.00	LOW 20.80	95.45 0.47
1669B	466.0	HIGH 100.00	466.0 0.00

Approved By : 1

Shapiro

1 8819 - GAS MANUFACTURER'S INTERPRETATION STANDARD of this Company for use with this analysis shall be replacement thereof by the Company without extra cost.



Particulate Loadings and Emission Rates

The particulate emission rates were determined per EPA Methods 1-5, CFR title 40, Part 60, Appendix A (revised July 1, 1987). In this procedure, a preliminary velocity profile of the gases in the flue is obtained by means of a temperature and velocity traverse. On the basis of these values, sampling nozzles of appropriate diameter are selected to allow isokinetic sampling, a necessary prerequisite for obtaining a representative sample.

The sampling train consists of a heated glass-lined sampling probe equipped with a Type S pitot and a thermocouple. The probe is attached to a sampling module which houses the all-glass in line filter holder in a temperature controlled oven. In addition, the sampling module also houses the impinger case and a Drierite drying column. The sampling module is connected by means of an umbilical cord to the control module which houses the dry test gasmeter, the calibrated orifice, a leakless pump, two inclined manometers, and all controls required for operating the sampling train.

Particulate samples were collected as follows: The sample gas was drawn in through the sampling probe isokinetically and passed through a 4-inch diameter Gelman Type A/E glass fiber filter. The particulates were removed at this point and collected on the filter. The gases then passed through an ice-cooled impinger train and a desiccant-packed drying column which quantitatively absorb all moisture from the sample gas stream after which the sample gas passes through the pump and the dry test gasmeter which integrates the sample gas flow throughout the course of the test. A calibrated orifice attached to the outlet of the gasmeter provides instantaneous flow rate data.

A representative particulate sample was acquired by sampling for equal periods of time at the centroid of a number of equal area regions in the duct. The sampling rate is adjusted at each site such that an isokinetic sampling condition prevails. Nomographs are used to aid in the rapid determination of the sampling rate.

After sampling is complete, the filter is removed and placed in a clean container. The nozzle and inlet side of the filter holder are quantitatively washed with acetone and the washings are stored in a second container. A brush is often used in the cleaning step to help dislodge deposits. The samples are returned to the laboratory where they are logged in and analyzed. The volume of the acetone rinse ("probe wash") is noted and then the rinse is quantitatively transferred to a tared 120 cc porcelain evaporating dish and the acetone evaporated off at 97-105 °F. This temperature is used to prevent condensation of atmospheric moisture due to the cooling effect induced by the evaporation of acetone. The acetone-free sample is then transferred to an oven and dried at 105 °C for 30 minutes, cooled in a desiccator over Drierite, and then weighed to the nearest .01 mg. The filter sample is quantitatively transferred to a 6-inch watch glass and dried in an oven at 105 °C for two hours. The filter and watch glass are then cooled in a desiccator and the filter weighed to the nearest .01 mg. All weighings are performed in a balance room where the relative humidity is hydrostatted to less than 50% relative humidity. Microscopic examination of the samples is performed if any unusual characteristics are observed. The weight of the acetone rinse is corrected for the acetone blank. The Drierite column is weighed on-site and the water collected by Drierite is added to the condensate so that the total amount of absorbed water may be ascertained.

Integrated gas samples for Orsat analysis were collected at a constant flow rate throughout each particulate run. The gas samples were analyzed using an all-glass Orsat analyzer. Standard commercially prepared solutions were used in the Orsat analyzer (sat. KOH for carbon dioxide and reduced methylene blue for oxygen). In addition to the above, the oxygen content of the flue gas was measured at each traverse during the particulate determinations using a Teledyne Model 320P-4 Portable Oxygen Analyzer to sample the effluent from the Method 5 train.

Interpoll Laboratories
(612)786-6020

Condensible Organic Compounds Analysis
(State of Wisconsin - EPA Method 5)
Method II-8672-WI

Equipment: Separatory funnel - 500 cc with Teflon stopcock
 Powder funnel - 75 mm ID with a glass wood plug
 Evaporating dish(es) - 200 cc or 250 cc beaker

Reagents: Methylene chloride

 Sodium sulfate - (ACS) granular anhydrous (purified by
 heating for four hours in a shallow tray)

SAMPLING:

An all-glass impinger assembly is used in the back half of the EPA Method 5 sampling train when an organic wet catch is to be collected. The impinger assembly consists of a modified impinger, a Greenburg Smith impinger followed by another modified impinger. The third impinger should have a temperature measuring device at the outlet upstream of a final impinger or desiccant column to monitor the temperature of the outlet gas stream. Prior to the start of the test, each of the first two impingers should be charged with 100 g of Class I water. The Method 5 train should be operated as provided for in EPA Method 5. Ice should be added to the impinger bath to keep the temperature of the gas at the outlet at or less than 68 °F. After the post test leak check, the impinger train is removed and impinger contents poured into a tared all-glass sample bottle and closed with a Teflon-lined cap. The sample bottle is then weighed and the total condensate calculated by subtraction of the bottle tare weight and the

weight of initial water added to the impingers (200 g). A label is affixed and the sample is returned to the laboratory for analysis. The sample should be stored at 4 °C if the analysis is not conducted within 48 hours.

ANALYSIS:

1. Sample bottles are removed from storage and the contents quantitatively transferred to a clean 500 cc separatory funnel equipped with a Teflon stopcock.
2. Rinse the sample container with distilled water and add to separatory funnel.
3. Then rinse the sample container with acetone and pour through sodium sulfate into a tare beaker marked A.
4. The sample is then extracted consecutively with three 50 cc aliquots of methylene chloride. The extraction is performed according to normal laboratory practice observing the customary safety precaution of releasing excess pressure after each shaking.
5. After each of the three extractions are completed, the organic solvent should be dried by passing it through a funnel containing anhydrous sodium sulfate and collecting it and two 50 cc rinses in the tared beaker marked A (the same one used to catch the acetone container rinse).
6. Evaporate to dryness in a hood at 70 °F or less. Do not evaporate so quickly as to allow evaporative cooling to lower the temperature of the container below the dew point otherwise water will be condensed in the container.


7. Desiccate for two hours in a sealed desiccator and final weigh. Report all results in grams. All weighings should be made to nearest 0.1 mg (four places).
8. The remaining liquid in the separatory funnel is then transferred to a tared beaker marked B and is evaporated to dryness at $220^{\circ}\text{F} \pm 10^{\circ}\text{F}$. The analyst may take an aliquot of the sample, transferring it to a tared beaker and evaporate to dryness at $220^{\circ}\text{F} \pm 10^{\circ}\text{F}$. If an aliquot is used, the weight of the sample and aliquot will have to be taken to correct for the total sample weight.
9. After the drying step, the sample is cooled in a desiccator and weighted to a constant weight to the nearest 0.1 mg.

Calculation (if aliquot is taken):

$$\text{grams} = \frac{(\text{grams recovered from aliquot}) \times (\text{total volume (ml) or grams of sample})}{(\text{aliquot volume (ml) or grams used})}$$

If volume is used, it must be used for both the aliquot and sample. The same goes for using weight.

10. A field blank should be analyzed in an identical manner. If a field blank is not submitted, take an aliquot of Class I water equal in volume to the samples and analyze in a similar manner.
11. The results for container A are to be marked in the organic section of Interpoll Form #LSC-036.
12. The results for container B are to be marked in the inorganic section of Interpoll Form #LSC-036.



Particulate sampling train.

METHOD 201A - DETERMINATION OF PM_{10} EMISSIONS
(Constant Sampling Rate Procedure)

(55 FR 14246)

1. Applicability and Principle

1.1 Applicability. This method applies to the in-stack measurement of particulate matter (PM) emissions equal to or less than an aerodynamic diameter of nominally 10 μm (PM_{10}) from stationary sources. The EPA recognizes that condensible emissions not collected by an in-stack method are also PM_{10} , and that emissions that contribute to ambient PM_{10} levels are the sum of condensible emissions and emissions measured by an in-stack PM_{10} method, such as this method or Method 201. Therefore, for establishing source contributions to ambient levels of PM_{10} , such as for emission inventory purposes, EPA suggests that source PM_{10} measurement include both in-stack PM_{10} and condensible emissions. Condensible emissions may be measured by an impinger analysis in combination with this method.

1.2 Principle. A gas sample is extracted at a constant flow rate through an in-stack sizing device, which separates PM greater than PM_{10} . Variations from isokinetic sampling conditions are maintained within well-defined limits. The particulate mass is determined gravimetrically after removal of uncombined water.

2. Apparatus

NOTE: Methods cited in this method are part of 40 CFR Part 60, Appendix A.

2.1 Sampling Train. A schematic of the Method 201A sampling train is shown in Figure 1. With the exception of the PM_{10} sizing device and in-stack filter, this train is the same as an EPA Method 17 train.

2.1.1 Nozzle. Stainless steel (316 or equivalent) with a sharp tapered leading edge. Eleven nozzles that meet the design specifications in Figure 2

are recommended. A large number of nozzles with small nozzle increments increase the likelihood that a single nozzle can be used for the entire traverse. If the nozzles do not meet the design specifications in Figure 2, then the nozzles must meet the criteria in Section 5.2.

2.1.2 PM_{10} Sizer. Stainless steel (316 or equivalent), capable of determining the PM_{10} fraction. The sizing device shall be either a cyclone that meets the specifications in Section 5.2 or a cascade impactor that has been calibrated using the procedure in Section 5.4.

2.1.3 Filter Holder. 63-mm, stainless steel. An Andersen filter, part number SE274, has been found to be acceptable for the in-stack filter.

NOTE: Mention of trade names or specific products does not constitute endorsement by the Environmental Protection Agency.

2.1.4 Pitot Tube. Same as in Method 5, Section 2.1.3. The pitot lines shall be made of heat resistant tubing and attached to the probe with stainless steel fittings.

2.1.5 Probe Liner. Optional, same as in Method 5, Section 2.1.2.

2.1.6 Differential Pressure Gauge, Condenser, Metering System, Barometer, and Gas Density Determination Equipment. Same as in Method 5, Sections 2.1.4, and 2.1.7 through 2.1.10, respectively.

2.2 Sample Recovery.

2.2.1 Nozzle, Sizing Device, Probe, and Filter Holder Brushes. Nylon bristle brushes with stainless steel wire shafts and handles, properly sized and shaped for cleaning the nozzle, sizing device, probe or probe liner, and filter holders.

2.2.2 Wash Bottles, Glass Sample Storage Containers, Petri Dishes, Graduated Cylinder and Balance, Plastic Storage Containers, Funnel and Rubber

Policeman, and Funnel. Same as in Method 5, Sections 2.2.2 through 2.2.8, respectively.

2.3 Analysis. Same as in Method 5, Section 2.3.

3. Reagents

The reagents for sampling, sample recovery, and analysis are the same as that specified in Method 5, Sections 3.1, 3.2, and 3.3, respectively.

4. Procedure

4.1 Sampling. The complexity of this method is such that, in order to obtain reliable results, testers should be trained and experienced with the test procedures.

4.1.1 Pretest Preparation. Same as in Method 5, Section 4.1.1.

4.1.2 Preliminary Determinations. Same as in Method 5, Section 4.1.2, except use the directions on nozzle size selection and sampling time in this method. Use of any nozzle ^{less than} greater than 0.16 in. in diameter require a sampling port diameter of 6 inches. Also, the required maximum number of traverse points at any location shall be 12. ? See pg. 22

4.1.2.1 The sizing device must be in-stack or maintained at stack temperature during sampling. The blockage effect of the CSR sampling assembly will be minimal if the cross-sectional area of the sampling assembly is 3 percent or less of the cross-sectional area of the duct. ^{ie $D_s \geq 17.5$ inches} If the cross-sectional area of the assembly is greater than 3 percent of the cross-sectional area of the duct, then either determine the pitot coefficient at sampling conditions or use a standard pitot with a known coefficient in a configuration with the CSR sampling assembly such that flow disturbances are minimized.

* When $D_s \leq 17.5$ inches, blockage exceeds 3%

4.1.2.2 The setup calculations can be performed by using the following procedures.

4.1.2.2.1 In order to maintain a cut size of $10\ \mu\text{m}$ in the sizing device, the flow rate through the sizing device must be maintained at a constant, discrete value during the run. If the sizing device is a cyclone that meets the design specifications in Figure 3, use the equations in Figure 4 to calculate three orifice ^{pressure drops} heads (ΔH): one at the average stack temperature, and the other two at temperatures $\pm 28^\circ\text{C}$ ($\pm 50^\circ\text{F}$) of the average stack temperature. Use the ΔH calculated at the average stack temperature as the ^{orifice} pressure head for the sample flow rate as long as the stack temperature during the run is within 28°C (50°F) of the average stack temperature. If the stack temperature varies by more than 28°C (50°F), then use the appropriate ΔH .

4.1.2.2.3 To select a nozzle, use the equations in Figure 5 to calculate $\Delta p_{\min}$ and $\Delta p_{\max}$ for each nozzle at all three temperatures. If the sizing device is a cyclone that does not meet the design specifications in Figure 3, the example worksheets can be used.

4.1.2.2.4 Correct the Method 2 pitot readings to Method 201A pitot readings by multiplying the Method 2 pitot readings by the square of a ratio of the Method 201A pitot coefficient to the Method 2 pitot coefficient.

Select the nozzle for which $\Delta p_{\min}$ and $\Delta p_{\max}$ bracket all of the corrected Method 2 pitot readings. If more than one nozzle meets this requirement,

select the nozzle giving the greatest symmetry. Note that if the expected pitot reading for one or more points is near a limit for a chosen nozzle, it may be outside the limits at the time of the run.

4.1.2.2.5 Vary the dwell time, or sampling time, at each traverse point proportionately with the point velocity. Use the equations in Figure 6 to calculate the dwell time at the first point and at each subsequent point. It is recommended that the number of minutes sampled at each point be rounded to the nearest 15 seconds.

4.1.3 Preparation of Collection Train. Same as in Method 5, Section 4.1.3, except omit directions about a glass cyclone.

4.1.4 Leak-Check Procedure. The sizing device is removed before the post-test leak-check to prevent any disturbance of the collected sample prior to analysis.

4.1.4.1 Pretest Leak-Check. A pretest leak-check of the entire sampling train, including the sizing device, is required. Use the leak-check procedure in Method 5, Section 4.1.4.1 to conduct a pretest leak-check.

4.1.4.2 Leak-Checks During Sample Run. Same as in Method 5, Section 4.1.4.1.

4.1.4.3 Post-Test Leak-Check. A leak-check is required at the conclusion of each sampling run. Remove the cyclone before the leak-check to prevent the vacuum created by the cooling of the probe from disturbing the collected sample and use the procedure in Method 5, Section 4.1.4.3 to conduct a post-test leak-check.

4.1.5 Method 201A Train Operation. Same as in Method 5, Section 4.1.5, except use the procedures in this section for isokinetic sampling and flow rate adjustment. Maintain the flow rate calculated in Section 4.1.2.2.1

throughout the run provided the stack temperature is within 28°C (50°F) of the temperature used to calculate ΔH . If stack temperatures vary by more than 28°C (50°F), use the appropriate ΔH value calculated in Section 4.1.2.2.1. Calculate the dwell time at each traverse point as in Figure 6.

4.2 Sample Recovery. If a cascade impactor is used, use the manufacturer's recommended procedures for sample recovery. If a cyclone is used, use the same sample recovery as that in Method 5, Section 4.2, except an increased number of sample recovery containers is required.

4.2.1 Container Number 1 (In-Stack Filter). The recovery shall be the same as that for Container Number 1 in Method 5, Section 4.2.

4.2.3 Container Number 2 (Cyclone or Large PM Catch). This step is optional. The anisokinetic error for the cyclone PM is theoretically larger than the error for the PM_{10} catch. Therefore, adding all the fractions to get a total PM catch is not as accurate as Method 5 or Method 201. Disassemble the cyclone and remove the nozzle to recover the large PM catch. Quantitatively recover the PM from the interior surfaces of the nozzle and cyclone, excluding the "turn around" cup and the interior surfaces of the exit tube. The recovery shall be the same as that for Container Number 2 in Method 5, Section 4.2.

4.2.4 Container Number 3 (PM_{10}). Quantitatively recover the PM from all of the surfaces from the cyclone exit to the front half of the in-stack filter holder, including the "turn around" cup inside the cyclone and the interior surfaces of the exit tube. The recovery shall be the same as that for Container Number 2 in Method 5, Section 4.2.

4.2.6 Container Number 4 (Silica Gel). The recovery shall be the same as that for Container Number 3 in Method 5, Section 4.2.

4.2.7 Impinger Water. Same as in Method 5, Section 4.2, under "Impinger Water."

4.3 Analysis. Same as in Method 5, Section 4.3, except handle Method 201A Container Number 1 like Container Number 1, Method 201A Container Numbers 2 and 3 like Container Number 2, and Method 201A Container Number 4 like Container Number 3. Use Figure 7 to record the weights of PM collected. Use Figure 5-3 in Method 5, Section 4.3, to record the volume of water collected.

4.4 Quality Control Procedures. Same as in Method 5, Section 4.4.

4.5 PM_{10} Emission Calculation and Acceptability of Results. Use the procedures in Section 6 to calculate PM_{10} emissions and the criteria in Section 6.3.5 to determine the acceptability of the results.

5. Calibration

Maintain an accurate laboratory log of all calibrations.

5.1 Probe Nozzle, Pitot Tube, Metering System, Probe Heater Calibration, Temperature Gauges, Leak-check of Metering System, and Barometer. Same as in Method 5, Section 5.1 through 5.7, respectively.

6. Calculations

Calculations are as specified in Method 5, Sections 6.3 through 6.7, and 6.9 through 6.11, with the addition of the following:

6.1 Nomenclature.

B_{ws} = Moisture fraction of stack, by volume, dimensionless.

C_1 = Viscosity constant, 51.12 micropoise for °K (51.05 micropoise for °R).

C_2 = Viscosity constant, 0.372 micropoise/°K (0.207 micropoise/°R).

C_3 = Viscosity constant, 1.05×10^{-6} micropoise/°K²
(3.24×10^{-5} micropoise/°R²).

C_4 = Viscosity constant, 53.147 micropoise/fraction O₂.

C_5 = Viscosity constant, 74.143 micropoise/fraction H₂O.

D_{50} = Diameter of particles having a 50 percent probability of penetration, μm .

f_o = Stack gas fraction O₂, by volume, dry basis.

K_1 = 0.3858 °K/mm Hg (17.64 °R/in. Hg).

M_w = Wet molecular weight of the stack gas, g/g-mole (lb/lb-mole).

M_d = Dry molecular weight of stack gas, g/g-mole (lb/lb-mole).

P_{bar} = Barometric pressure at sampling site, mm Hg (in. Hg).

P_s = Absolute stack pressure, mm Hg (in. Hg).

Q_s = Total cyclone flow rate at wet cyclone conditions, m³/min
(ft³/min).

$Q_{s(\text{std})}$ = Total cyclone flow rate at ^{dry} standard conditions, dscm/min
(dscf/min). DSCFM

T_m = Average absolute temperature of dry meter, °K (°R).

T_s = Average absolute stack gas temperature, °K (°R).

YES!

YES!

$V_{m(std)}$ = Volume of gas measured by the dry gas meter, corrected to standard conditions, dscm (dscf).

$V_{w(std)}$ = Volume of water vapor in gas sample (standard conditions), scm (scf).

θ = Total sampling time, min.

μ_s = Viscosity of stack gas, micropoise.

6.2 Analysis of Cascade Impactor Data. Use the manufacturer's recommended procedures to analyze data from cascade impactors.

6.3 Analysis of Cyclone Data. Use the following procedures to analyze data from a single stage cyclone.

6.3.1 PM_{10} Weight. Determine the PM catch in the PM_{10} range from the sum of the weights obtained from Container Numbers 1 and 3 less the acetone blank.

6.3.2 Total PM Weight (optional). Determine the PM catch for greater than PM_{10} from the weight obtained from Container Number 2 less the acetone blank, and add it to the PM_{10} weight.

6.3.3 PM_{10} Fraction. Determine the PM_{10} fraction of the total particulate weight by dividing the PM_{10} particulate weight by the total particulate weight.

6.3.4 Aerodynamic Cut Size. Calculate the stack gas viscosity as follows:

$$\mu_s = C_1 + C_2 T_s + C_3 T_s^2 + C_4 f_{O_2} - C_5 B_{ws}$$

No! Use equation on page 24

6.3.4.1 The PM_{10} flow rate, at actual cyclone conditions, is calculated as follows:

$$Q_s = \frac{T_s}{K_1 P_s} \left[Q_{s(std)} + \frac{V_{w(std)}}{\theta} \right]$$

$$\begin{aligned} V_{w(std)} &= .04707 (V_f - V_i) \\ T_s &= \bar{T}_s + 466 \\ \text{but } Q_{s(std)} &= \frac{V_{m(std)}}{\theta} \\ K_1 &= 17.64 \\ \text{Substituting gives:} \\ Q_s &= \frac{5.669 \times 10^{-2} (\bar{T}_s + 466)}{\theta P_s} [V_{m(std)} - .04707(V_f - V_i)] \end{aligned}$$

6.3.4.2 Calculate the molecular weight on a wet basis of the stack gas as follows:

$$M_w = M_d (1 - B_{ws}) + 18.0 (B_{ws})$$

6.3.4.3 Calculate the actual D_{50} of the cyclone for the given conditions as follows:

$$D_{50} = \beta_1 \left[\frac{T_s}{M_w P_s} \right]^{0.2091} \left[\frac{\mu_s}{Q_s} \right]^{0.7091}$$

actual cutpoint
achieved during
run

where $\beta_1 = 0.027754$ for metric units (0.15625 for English units).

6.3.5 Acceptable Results. The results are acceptable if two conditions are met. The first is that $9.0 \mu m \leq D_{50} \leq 11.0 \mu m$. The second is that no sampling points are outside Δp_{min} and Δp_{max} , or that 80 percent $\leq I \leq 120$ percent and no more than one sampling point is outside Δp_{min} and Δp_{max} . If D_{50} is less than $9.0 \mu m$, reject the results and repeat the test.

7. Bibliography

1. Same as Bibliography in Method 5.
2. McCain, J.D., J.W. Ragland, and A.D. Williamson. Recommended Methodology for the Determination of Particle Size Distributions in Ducted Sources, Final Report. Prepared for the California Air Resources Board by Southern Research Institute. May 1986.
3. Farthing, W.E., S.S. Dawes, A.D. Williamson, J.D. McCain, R.S. Martin, and J.W. Ragland. Development of Sampling Methods for Source PM_{10} Emissions. Southern Research Institute for the Environmental Protection Agency. April 1989. NTIS PB 89 190375, EPA/600/3-88-056.
4. Application Guide for Source PM_{10} Measurement with Constant Sampling Rate, EPA/600/3-88-057.






Figure 1. CSR Sampling Train



Nozzle Diameter (inches)	Cone Angle, θ (degrees)	Outside taper, ϕ (degrees)	Straight inlet length, l (inches)	Total Length L (inches)
0.136	4	5	<0.05	2.653±0.05
0.150	4	5	<0.05	2.553±0.05
0.164	5	5	<0.05	1.970±0.05
0.180	6	5	<0.05	1.572±0.05
0.197	6	5	<0.05	1.491±0.05
0.215	6	5	<0.05	1.45 ±0.05
0.233	6	5	<0.05	1.45 ±0.05
0.264	5	5	<0.05	1.45 ±0.05
0.300	4	5	<0.05	1.48 ±0.05
0.342	4	5	<0.05	1.45 ±0.05
0.390	3	5	<0.05	1.45 ±0.05

Figure 2. Nozzle design specifications.

Cyclone Interior Dimensions



	Dimensions (+0.02 cm, +0.01 in.)												
	Din	D	De	B	H	h	Z	S	Hcup	Dcup	De'	Do	E
cm	1.27	4.47	1.50	1.88	6.95	2.24	4.71	1.57	2.25	4.45	1.02	1.24	0.25
in.	0.50	1.76	0.59	0.74	2.74	0.88	1.85	0.62	0.89	1.75	0.40	0.49	0.10

Figure 3. Cyclone design specifications.

Barometric pressure, P_{bar} , in. Hg = _____
 Stack static pressure, P_s , in. H₂O = _____
 Average stack temperature, t_s , °F = _____
 Meter temperature, t_m , °F = _____
 Orifice ΔH_o , in. H₂O = _____

Gas analysis:

$\%CO_2$ = _____
 $\%O_2$ = _____
 $\%N_2 + \%CO$ = _____
 Fraction moisture content, B_{ws} = _____

Molecular weight of stack gas, dry basis:

$$M_d = 0.44(\%CO_2) + 0.32(\%O_2) + 0.28(\%N_2 + \%CO) = \text{_____ lb/lb mole}$$

Molecular weight of stack gas, wet basis:

$$M_w = M_d(1 - B_{ws}) + 18(B_{ws}) = \text{_____ lb/lb mole}$$

Absolute stack pressure:

$$P_s = P_{\text{bar}} + \frac{P_g}{13.6} = \text{_____ in. Hg}$$

Viscosity of stack gas:

$$\mu_s = 152.418 + 0.2552 t_s + 3.2355 \times 10^{-5} t_s^2 + 0.53147 (\%O_2) - 74.143 B_{ws} = \text{_____ micropoise}$$

Cyclone flow rate:

$$Q_s = 0.002837 \mu_s \left(\frac{t_s + 460}{M_w P_s} \right)^{0.2949} = \text{_____ ft}^3/\text{min}$$

Figure 4. Example worksheet 1 (Page 1 of 2), cyclone flow rate and ΔH .

Orifice pressure head (ΔH) needed for cyclone flow rate: note

$$\Delta H = \left[\frac{Q_s (1 - B_{ws}) P_s}{t_s + 460} \right]^2 \frac{(t_m + 460) M_d (1.083) \Delta H_a}{P_{bar}} = \text{_____ in. H}_2\text{O}$$

Calculate ΔH for three temperatures:

$t_s, ^\circ\text{F}$			
$\Delta H, \text{in. H}_2\text{O}$			

Figure 4. Example worksheet 1 (Page 2 of 2), cyclone flow rate and ΔH .

Stack viscosity, μ_s , micropoise = _____
 Absolute stack pressure, P_s , in. Hg = _____
 Average stack temperature, t_s , °F = _____
 Meter temperature, t_m , °F = _____
 Method 201A pitot coefficient, C_p = _____
 Cyclone flow rate, ft^3/min , Q_p = _____
 Method 2 pitot coefficient, C_p = _____
 Molecular weight of stack gas, wet basis, M_w = _____
 Nozzle diameter, D_n , in. = _____

Nozzle velocity

$$v_n = \frac{3.056 Q_s}{D_n^2} = \text{_____ ft/sec}$$

Maximum and minimum velocities:

Calculate R_{min} .

$$R_{min} = 0.2457 + \left[0.3072 - \frac{0.2603 (\sqrt{Q_s}) \mu_s}{v_n^{1.5}} \right] = \text{_____}$$

If R_{min} is less than 0.5, or if an imaginary number occurs when calculating R_{min} , use Equation 1 to calculate v_{min} . Otherwise, use Equation 2.

Eq. 1 $v_{min} = v_n (0.5) = \text{_____ ft/sec}$

Eq. 2 $v_{min} = v_n R_{min} = \text{_____ ft/sec}$

Calculate R_{max} .

$$R_{max} = 0.4457 + \left[0.5690 + \frac{0.2603 (\sqrt{Q_s}) \mu_s}{v_n^{1.5}} \right] = \text{_____}$$

Figure 5. Example worksheet 2 (page 1 of 2), nozzle selection.

If $R_{\max}$ is greater than 1.5, use Equation 3 to calculate $v_{\max}$. Otherwise, use Equation 4.

$$\text{Eq. 3} \quad v_{\max} = v_n (1.5) = \underline{\hspace{2cm}} \text{ ft/sec}$$

$$\text{Eq. 4} \quad v_{\max} = v_n R_{\max} = \underline{\hspace{2cm}} \text{ ft/sec}$$

Maximum and minimum velocity head values:

$$\Delta p_{\min} = 1.3686 \times 10^{-4} \frac{P_s M_w (v_{\min})^2}{(t_s + 460) C_p^2} = \underline{\hspace{2cm}} \text{ in. H}_2\text{O}$$

$$\Delta p_{\max} = 1.3686 \times 10^{-4} \frac{P_s M_w (v_{\max})^2}{(t_s + 460) C_p^2} = \underline{\hspace{2cm}} \text{ in. H}_2\text{O}$$

Nozzle Number				
D_n , in.				
v_n , ft/sec				
$v_{\min}$, ft/sec				
$v_{\max}$, ft/sec				
$\Delta p_{\min}$, in. H ₂ O				
$\Delta p_{\max}$, in. H ₂ O				

Velocity traverse data:

incorrect

$$\Delta p(\text{Method 201A}) = \Delta p(\text{Method 2}) \left(\frac{C_p}{C_p} \right)^2 = \Delta p^{M2} \left(\frac{C_p^{M2}}{C_p^{201A}} \right)^2$$

4-11-91 PL

Figure 5. Example worksheet 2 (page 2 of 2), nozzle selection.

Total run time, minutes = _____

Number of traverse points = _____

$$t_1 = \left[\frac{\Delta p'_1}{\Delta p'_{avg}} \left(\frac{\text{Total run time}}{\text{Number of points}} \right) \right]$$

where:

t_1 = dwell time at first traverse point, minutes.

$\Delta p'_1$ = the velocity head at the first traverse point (from a previous traverse), in. H_2O .

$\Delta p'_{avg}$ = the square of the average square root of the Δp 's (from a previous velocity traverse), in. H_2O .

At subsequent traverse points, measure the velocity Δp and calculate the dwell time by using the following equation:

$$t_n = \frac{t_1}{\sqrt{\Delta p_1}} \sqrt{\Delta p_n}, \text{ where } n = 2, 3, \dots \text{total number of sampling points}$$

where:

t_n = dwell time at traverse point n , minutes.

Δp_n = measured velocity head at point n , in. H_2O .

Δp_1 = measured velocity head at point 1, in. H_2O .

Figure 6. Example worksheet 3 (page 1 of 2), dwell time.

Port No _____ Port No _____ Port No _____ Port No _____

Point Number	Δp	t	Δp	t	Δp	t	Δp	t
1								
2								
3								
4								
5								
6								

Figure 6. Example worksheet 3 (page 2 of 2), dwell time.

Plant _____
 Date _____
 Run no. _____
 Filter no. _____
 Amount of liquid lost during transport _____
 Acetone blank volume, ml _____
 Acetone wash volume, ml (4) _____ (5) _____
 Acetone blank conc., mg/mg (Equation 5-4, Method 5) _____
 Acetone wash blank, mg (Equation 5-5, Method 5) _____

Container number	Weight of PM ₁₀ (mg)		
	Final weight	Tare weight	Weight gain
1			
3			
Total.....			
Less acetone blank....			
Weight of PM ₁₀			

Figure 7. Method 201A analysis sheet.

TABLE 1. PERFORMANCE SPECIFICATIONS FOR SOURCE PM₁₀ CYCLONES
AND NOZZLE COMBINATIONS

Parameter	Units	Specification
1. Collection efficiency	Percent	Such that collection efficiency falls within envelope specified by Section 5.2.6 and Figure 8.
2. Cyclone cut size (D ₅₀)	μm	10 ± 1 μm aerodynamic diameter

TABLE 2. PARTICLE SIZES AND NOMINAL GAS VELOCITIES FOR EFFICIENCY

Particle size (μm) ^a	Target gas velocities (m/sec)		
	7 ± 1.0	15 ± 1.5	25 ± 2.5
5 ± 0.5			
7 ± 0.5			
10 ± 0.5			
14 ± 1.0			
20 ± 1.0			

(a) Mass median aerodynamic diameter.




Figure 8. Efficiency envelope for the PM₁₀ cyclone.




Figure 9. Efficiency envelope for first calibration stage.

(CO) content using a Luft-type nondispersive infrared analyzer (NDIR) or equivalent.

1.2 Applicability. This method is applicable for the determination of carbon monoxide emissions from stationary sources only when specified by the test procedures for determining compliance with new source performance standards. The test procedure will indicate whether a continuous or an integrated sample is to be used.

2. Range and Sensitivity

2.1 Range. 0 to 1,000 ppm.

2.2 Sensitivity. Minimum detectable concentration is 20 ppm for a 0 to 1,000 ppm span.

3. Interferences

Any substance having a strong absorption of infrared energy will interfere to some extent. For example, discrimination ratios for water (H₂O) and carbon dioxide (CO₂) are 3.5 percent H₂O per 7 ppm CO and 10 percent CO₂ per 10 ppm CO, respectively, for devices measuring in the 1,500 to 3,000 ppm range. For devices measuring in the 0 to 100 ppm range, interference ratios can be as high as 3.5 percent H₂O per 25 ppm CO and 10 percent CO₂ per 50 ppm CO. The use of silica gel and ascarite traps will alleviate the major interference problems. The measured gas volume must be corrected if these traps are used.

4. Precision and Accuracy

4.1 Precision. The precision of most NDIR analyzers is approximately ± 2 percent of span.

4.2 Accuracy. The accuracy of most NDIR analyzers is approximately ± 5 percent of span after calibration.

5. Apparatus

5.1 Continuous Sample (Figure 10-1).

5.1.1 Probe. Stainless steel or sheathed Pyrex¹ glass, equipped with a filter to remove particulate matter.

5.1.2 Air-Cooled Condenser or Equivalent. To remove any excess moisture.

5.2 Integrated Sample (Figure 10-2).

5.2.1 Probe. Stainless steel or sheathed Pyrex glass, equipped with a filter to remove particulate matter.

5.2.2 Air-Cooled Condenser or Equivalent. To remove any excess moisture.

5.2.3 Valve. Needle valve, or equivalent, to adjust flow rate.

5.2.4 Pump. Leak-free diaphragm type, or equivalent, to transport gas.

5.2.5 Rate Meter. Rotameter, or equivalent, to measure a flow range from 0 to 1.0 liter per min (0.035 cfm).

METHOD 10—DETERMINATION OF CARBON MONOXIDE EMISSIONS FROM STATIONARY SOURCES

1. Principle and Applicability

1.1 Principle. An integrated or continuous gas sample is extracted from a sampling point and analyzed for carbon monoxide

¹ Mention of trade names or specific products does not constitute endorsement by the Environmental Protection Agency.

5.2.6 Flexible Bag. Tedlar, or equivalent, with a capacity of 60 to 90 liters (2 to 3 ft³). Leak-test the bag in the laboratory before using by evacuating bag with a pump followed by a dry gas meter. When evacuation is complete, there should be no flow through the meter.

5.2.7 Pitot Tube. Type S, or equivalent, attached to the probe so that the sampling rate can be regulated proportional to the stack gas velocity when velocity is varying with the time or a sample traverse is conducted.

5.3 Analysis (Figure 10-3).

5.3.1 Carbon Monoxide Analyzer. Nondispersive infrared spectrometer, or equivalent. This instrument should be demonstrated, preferably by the manufacturer, to meet or exceed manufacturer's specifications and those described in this method.

5.3.2 Drying Tube. To contain approximately 200 g of silica gel.

5.3.3 Calibration Gas. Refer to section 6.1.

5.3.4 Filter. As recommended by NDIR manufacturer.




Figure 10-1. Continuous sampling train.




Figure 10-2. Integrated gas-sampling train.

5.3.5 CO₂ Removal Tube. To contain approximately 500 g of ascarite.

5.3.6 Ice Water Bath. For ascarite and silica gel tubes.

5.3.7 Valve. Needle valve, or equivalent, to adjust flow rate

5.3.8 Rate Meter. Rotameter or equivalent to measure gas flow rate of 0 to 1.0 liter per min (0.035 cfm) through NDIR.

5.3.9 Recorder (optional). To provide permanent record of NDIR readings.

6. Reagents

6.1 Calibration Gases. Known concentration of CO in nitrogen (N₂) for instrument span, prepurified grade of N₂ for zero, and two additional concentrations corresponding approximately to 60 percent and 30 percent span. The span concentration shall not exceed 1.5 times the applicable source performance standard. The calibration gases shall be certified by the manufacturer to be within ± 2 percent of the specified concentration.




Figure 10-3. Analytical equipment.

6.2 Silica Gel. Indicating type, 6 to 16 mesh, dried at 175° C (347° F) for 2 hours.

6.3 Ascarite. Commercially available.

7. Procedure

7.1 Sampling.

7.1.1 Continuous Sampling. Set up the equipment as shown in Figure 10-1 making sure all connections are leak free. Place the probe in the stack at a sampling point and purge the sampling line. Connect the analyzer and begin drawing sample into the analyzer. Allow 5 minutes for the system to stabilize, then record the analyzer reading as required by the test procedure. (See section 7.2 and 8). CO₂ content of the gas may be determined by using the Method 3 integrated sample procedure, or by weighing the ascarite CO₂ removal tube and computing CO₂ concentration from the gas volume sampled and the weight gain of the tube.

7.1.2 Integrated Sampling. Evacuate the flexible bag. Set up the equipment as shown in Figure 10-2 with the bag disconnected. Place the probe in the stack and purge the sampling line. Connect the bag, making sure that all connections are leak free. Sample at a rate proportional to the stack velocity. CO₂ content of the gas may be determined by using the Method 3 integrated sample procedures, or by weighing the ascarite CO₂ removal tube and computing CO₂ concentration.

tion from the gas volume sampled and the weight gain of the tube.

7.2 CO Analysis. Assemble the apparatus as shown in Figure 10-3, calibrate the instrument, and perform other required operations as described in section 8. Purge analyzer with N₂ prior to introduction of each sample. Direct the sample stream through the instrument for the test period, recording the readings. Check the zero and span again after the test to assure that any drift or malfunction is detected. Record the sample data on Table 10-1.

8. Calibration

Assemble the apparatus according to Figure 10-3. Generally an instrument requires a warm-up period before stability is obtained. Follow the manufacturer's instructions for specific procedure. Allow a minimum time of 1 hour for warm-up. During this time check the sample conditioning apparatus, i.e., filter, condenser, drying tube, and CO₂ removal tube, to ensure that each component is in good operating condition. Zero and calibrate the instrument according to the manufacturer's procedures using, respectively, nitrogen and the calibration gases.

TABLE 10-1—FIELD DATA

Comments	
Location _____	
Test _____	
Date _____	
Operator _____	
Clock time _____	Rotameter setting, liters per minute (cubic feet per minute)

9. Calculation

Concentration of carbon monoxide. Calculate the concentration of carbon monoxide in the stack using Equation 10-1.

$$C_{CO \text{ stack}} = C_{CO \text{ NDIR}}(1 - F_{O_2})$$

Eq. 10-1

Where:

$C_{CO \text{ stack}}$ = Concentration of CO in stack, ppm by volume (dry basis).

$C_{CO \text{ NDIR}}$ = Concentration of CO measured by NDIR analyzer, ppm by volume (dry basis).

F_{O_2} = Volume fraction of CO₂ in sample, i.e., percent CO₂ from Orsat analysis divided by 100.

10.1 Interference Trap. The sample conditioning system described in Method 10A, sections 2.1.2 and 4.2, may be used as an alternative to the silica gel and ascarite traps.

11. Bibliography

- 11.1 McElroy, Frank, The Intertech NDIR-CO Analyzer, Presented at 11th Methods Conference on Air Pollution, University of California, Berkeley, CA. April 1, 1970.
- 11.2 Jacobs, M. B., et al., Continuous Determination of Carbon Monoxide and Hydrocarbons in Air by a Modified Infrared Analyzer, J. Air Pollution Control Association, 9(2): 110-114. August 1959.
- 11.3 MSA LIRA Infrared Gas and Liquid Analyzer Instruction Book, Mine Safety Appliances Co., Technical Products Division, Pittsburgh, PA.
- 11.4 Models 215A, 315A, and 415A Infrared Analyzers, Beckman Instruments, Inc., Beckman Instructions 1635-B, Fullerton, CA. October 1967.
- 11.5 Continuous CO Monitoring System, Model A5611, Intertech Corp., Princeton, NJ.
- 11.6 UNOR Infrared Gas Analyzers, Bendix Corp., Ronceverte, WV

APPENDIX

A. PERFORMANCE SPECIFICATIONS FOR NDIR CARBON MONOXIDE ANALYZERS

Range (minimum) _____	0-1000 ppm.
Output (minimum) _____	0-10mV.
Minimum detectable sensitivity.	20 ppm.
Rise time, 90 percent (maximum).	30 seconds.
Fall time, 90 percent (maximum).	30 seconds.
Zero drift (maximum) _____	10% in 8 hours.
Span drift (maximum) _____	10% in 8 hours.
Precision (minimum) _____	±2% of full scale.
Noise (maximum) _____	±1% of full scale.
Linearity (maximum deviation) _____	2% of full scale.
Interference rejection ratio _____	CO ₂ —1000 to 1, H ₂ O—500 to 1.

B. Definitions of Performance Specifications

Range—The minimum and maximum measurement limits.

Output—Electrical signal which is proportional to the measurement; intended for connection to readout or data processing devices. Usually expressed as millivolts or milliamperes full scale at a given impedance.

Full scale—The maximum measuring limit for a given range.

Minimum detectable sensitivity—The smallest amount of input concentration that can be detected as the concentration approaches zero.

Accuracy—The degree of agreement between a measured value and the true value; usually expressed as $\pm$ percent of full scale.

Time to 90 percent response—The time interval from a step change in the input concentration at the instrument inlet to a reading of 90 percent of the ultimate recorded concentration.

Rise Time (90 percent)—The interval between initial response time and time to 90 percent response after a step increase in the inlet concentration.

Fall Time (90 percent)—The interval between initial response time and time to 90 percent response after a step decrease in the inlet concentration.

Zero Drift—The change in instrument output over a stated time period, usually 24 hours, of unadjusted continuous operation when the input concentration is zero; usually expressed as percent full scale.

Span Drift—The change in instrument output over a stated time period, usually 24 hours, of unadjusted continuous operation when the input concentration is a stated upscale value; usually expressed as percent full scale.

Precision—The degree of agreement between repeated measurements of the same concentration, expressed as the average deviation of the single results from the mean.

Noise—Spontaneous deviations from a mean output not caused by input concentration changes.

Linearity—The maximum deviation between an actual instrument reading and the reading predicted by a straight line drawn between upper and lower calibration points.

METHOD 10A—DETERMINATION OF CARBON MONOXIDE EMISSIONS IN CERTIFYING CONTINUOUS EMISSION MONITORING SYSTEMS AT PETROLEUM REFINERIES

1. Applicability and Principle

1.1 Applicability. This method applies to the measurement of carbon monoxide (CO) at petroleum refineries. This method serves as the reference method in the relative accuracy test for nondispersive infrared (NDIR) CO continuous emission monitoring systems (CEMS's) that are required to be installed in petroleum refineries on fluid cata-

lytic cracking unit catalyst regenerators [40 CFR Part 60.105(a)(2)].

1.2 Principle. An integrated gas sample is extracted from the stack, passed through an alkaline permanganate solution to remove sulfur and nitrogen oxides, and collected in a Tedlar bag. The CO concentration in the sample is measured spectrophotometrically using the reaction of CO with p-sulfamino-benzoic acid.

1.3. Range and Sensitivity.

1.3.1 Range. Approximately 3 to 1800 ppm CO. Samples having concentrations below 400 ppm are analyzed at 425 nm, and samples having concentrations above 400 ppm are analyzed at 600 nm.

1.3.2 Sensitivity. The detection limit is 3 ppm based on three times the standard deviation of the mean reagent blank values.

1.4 Interferences. Sulfur oxides, nitric oxide, and other acid gases interfere with the colorimetric reaction. They are removed by passing the sampled gas through an alkaline potassium permanganate scrubbing solution. Carbon dioxide (CO₂) does not interfere, but, because it is removed by the scrubbing solution, its concentration must be measured independently and an appropriate volume correction made to the sampled gas.

1.5 Precision, Accuracy, and Stability.

1.5.1 Precision. The estimated intralaboratory standard deviation of the method is 3 percent of the mean for gas samples analyzed in duplicate in the concentration range of 39 to 412 ppm. The interlaboratory precision has not been established.

1.5.2 Accuracy. The method contains no significant biases when compared to an NDIR analyzer calibrated with National Bureau of Standards (NBS) standards.

1.5.3 Stability. The individual components of the colorimetric reagent are stable for at least 1 month. The colorimetric reagent must be used within 2 days after preparation to avoid excessive blank correction. The samples in the Tedlar² bag should be stable for at least 1 month if the bags are leak-free.

2. Apparatus

2.1 Sampling. The sampling train is shown in Figure 10A-1, and component parts are discussed below:

² Mention of trade names or commercial products in this publication does not consti-

tute the endorsement or recommendation for use by the Environmental Protection Agency.

EPA
METHOD 0011

RECEIVED

SAMPLING FOR FORMALDEHYDE EMISSIONS FROM STATIONARY SOURCES JUL 16 1990

1.0 SCOPE AND APPLICATION

INTERPOL LABORATORIES

1.1 This method is applicable to the determination of Destruction and Removal Efficiency (DRE) of formaldehyde, CAS Registry number 50-00-0, and possibly other aldehydes and ketones from stationary sources as specified in the regulations. The methodology has been applied specifically to formaldehyde; however, many laboratories have extended the application to other aldehydes and ketones. Compounds derivatized with 2,4-dinitrophenylhydrazine can be detected as low as 6.4×10^{-8} lbs/cu ft (1.8 ppbv) in stack gas over a 1 h sampling period, sampling approximately 45 cu ft.

2.0 SUMMARY OF METHOD

2.1 Gaseous and particulate pollutants are withdrawn isokinetically from an emission source and are collected in aqueous acidic 2,4-dinitrophenylhydrazine. Formaldehyde present in the emissions reacts with the 2,4-dinitrophenylhydrazine to form the formaldehyde dinitrophenylhydrazone derivative. The dinitrophenylhydrazone derivative is extracted, solvent-exchanged, concentrated, and then analyzed by high performance liquid chromatography.

3.0 INTERFERENCES

3.1 A decomposition product of 2,4-dinitrophenylhydrazine, 2,4-dinitroaniline, can be an analytical interferent if concentrations are high. 2,4-dinitroaniline can coelute with the 2,4-dinitrophenylhydrazone of formaldehyde under high performance liquid chromatography conditions which may be used for the analysis. High concentrations of highly oxygenated compounds, especially acetone, that have the same retention time or nearly the same retention time as the dinitrophenylhydrazone of formaldehyde and that also absorb at 360 nm will interfere with the analysis.

Formaldehyde, acetone, and 2,4-dinitroaniline contamination of the aqueous acidic 2,4-dinitrophenylhydrazine (DNPH) reagent is frequently encountered. The reagent must be prepared within five days of use in the field and must be stored in an uncontaminated environment both before and after sampling in order to minimize blank problems. Some level of acetone contamination is unavoidable, because acetone is ubiquitous in laboratory and field operations. However, the acetone contamination must be minimized.

4.0 APPARATUS AND MATERIALS

4.1 A schematic of the sampling train is shown in Figure 1. This sampling train configuration is adapted from EPA Method 5 procedures. The sampling train consists of the following components: Probe Nozzle, Pitot Tube, Differential Pressure Gauge, Metering System, Barometer, and Gas Density Determination Equipment.

4.1.1 Probe Nozzle: Quartz or glass with sharp, tapered (30° angle) leading edge. The taper shall be on the outside to preserve a constant inner diameter. The nozzle shall be buttonhook or elbow design. A range of nozzle sizes suitable

INTERPOL LABORATORIES
4500 BALL ROAD N.E.
CIRCLE PINES, MN 55014-1819
(612) 786-8020

for isokinetic sampling should be available in increments of 0.16 cm (1/16 in), e.g., 0.32 to 1.27 cm (1/8 to 1/2 in), or larger if higher volume sampling trains are used. Each nozzle shall be calibrated according to the procedures outlined in Section 8.1.

4.1.2 Probe Liner: Borosilicate glass or quartz shall be used for the probe liner. The tester should not allow the temperature in the probe to exceed $120 \pm 14^{\circ}\text{C}$ ($248 \pm 25^{\circ}\text{F}$).

4.1.3 Pitot Tube: The Pitot tube shall be Type S, as described in Section 2.1 of EPA Method 2, or any other appropriate device. The pitot tube shall be attached to the probe to allow constant monitoring of the stack gas velocity. The impact (high pressure) opening plane of the pitot tube shall be even with or above the nozzle entry plane (see EPA Method 2, Figure 2-6b) during sampling. The Type S pitot tube assembly shall have a known coefficient, determined as outlined in Section 4 of EPA Method 2.

4.1.4 Differential Pressure Gauge: The differential pressure gauge shall be an inclined manometer or equivalent device as described in Section 2.2 of EPA Method 2. One manometer shall be used for velocity-head readings and the other for orifice differential pressure readings.

4.1.5 Impingers: The sampling train requires a minimum of four impingers, connected as shown in Figure 1, with ground glass (or equivalent) vacuum-tight fittings. For the first, third, and fourth impingers, use the Greenburg-Smith design, modified by replacing the tip with a 1.3-cm inside diameter (1/2 in) glass tube extending to 1.3 cm (1/2 in) from the bottom of the flask. For the second impinger, use a Greenburg-Smith impinger with the standard tip. Place a thermometer capable of measuring temperature to within 1°C (2°F) at the outlet of the fourth impinger for monitoring purposes.

4.1.6 Metering System: The necessary components are a vacuum gauge, leak-free pump, thermometers capable of measuring temperature within 3°C (5.4°F), dry-gas meter capable of measuring volume to within 1%, and related equipment as shown in Figure 1. At a minimum, the pump should be capable of 4 cfm free flow, and the dry gas meter should have a recording capacity of 0-999.9 cu ft with a resolution of 0.005 cu ft. Other metering systems may be used which are capable of maintaining sampling rates within 10% of isokinetic collection and of determining sample volumes to within 2%. The metering system may be used in conjunction with a pitot tube to enable checks of isokinetic sampling rates.

4.1.7 Barometer: The barometer may be mercury, aneroid, or other barometer capable of measuring atmospheric pressure to within 2.5 mm Hg (0.1 in Hg). In many cases, the barometric reading may be obtained from a nearby National Weather Service Station, in which case the station value (which is the absolute barometric pressure) is requested and an adjustment for elevation differences between the weather station and sampling point is applied at a rate of minus 2.5 mm Hg (0.1 in Hg) per 30 m (100 ft) elevation increase (vice versa for elevation decrease).

4.1.8 Gas Density Determination Equipment: Temperature sensor and pressure gauge (as described in Sections 2.3 and 2.4 of EPA Method 2), and gas analyzer, if necessary (as described in EPA Method 3). The temperature sensor ideally should be permanently attached to the pitot tube or sampling probe in a fixed

configuration such that the tip of the sensor extends beyond the leading edge of the probe sheath and does not touch any metal. Alternatively, the sensor may be attached just prior to use in the field. Note, however, that if the temperature sensor is attached in the field, the sensor must be placed in an interference-free arrangement with respect to the Type S pitot tube openings (see EPA Method 2, Figure 2-7). As a second alternative, if a difference of no more than 1% in the average velocity measurement is to be introduced, the temperature gauge need not be attached to the probe or pitot tube.

4.2 Sample Recovery

4.2.1 Probe Liner: Probe nozzle and brushes; Teflon® bristle brushes with stainless steel wire handles are required. The probe brush shall have extensions of stainless steel, Teflon®, or inert material at least as long as the probe. The brushes shall be properly sized and shaped to brush out the probe liner, the probe nozzle, and the impingers.

4.2.2 Wash Bottles: Three wash bottles are required. Teflon® or glass wash bottles are recommended; polyethylene wash bottles should not be used because organic contaminants may be extracted by exposure to organic solvents used for sample recovery.

4.2.3 Graduated Cylinder and/or Balance: A graduated cylinder or balance is required to measure condensed water to the nearest 1 mL or 1 g. Graduated cylinders shall have divisions not >2 mL. Laboratory balances capable of weighing to ±0.5 g are required.

4.2.4 Amber Glass Storage Containers: One-liter wide-mouth amber flint glass bottles with Teflon®-lined caps are required to store impinger water samples. The bottles must be sealed with Teflon® tape.

4.2.5 Rubber Policeman and Funnel: A rubber policeman and funnel are required to aid in the transfer of materials into and out of containers in the field.

5.0 REAGENTS

Reagent grade chemicals or better grades shall be used in all tests. Unless otherwise indicated, all reagents shall conform to the specifications of the Committee on Analytical Reagents of the American Chemical Society, where such specifications are available.

5.1 Water: HPLC-grade water is used in preparation of DNPH reagent and in all other applications in the sampling train.

5.2 Silica Gel: Silica gel shall be indicating type, 6-16 mesh. If the silica gel has been used previously, dry at 175°C (350°F) for 2 h before using. New silica gel may be used as received. Alternatively, other types of desiccants (equivalent or better) may be used.

5.3 Crushed Ice: Quantities ranging from 10-50 lb may be necessary during a sampling run, depending upon ambient temperature. Samples which have been taken must be stored and shipped cold; sufficient ice for this purpose must be allowed.

5.4 2,4-Dinitrophenylhydrazine Reagent: The 2,4-dinitrophenylhydrazine reagent must be prepared in the laboratory within five days of sampling use in the field. Preparation of DNPH can also be done in the field, with consideration of appropriate procedures required for safe handling of solvent in the field. When a container of prepared DNPH reagent is opened in the field, the contents of the opened container should be used within 48 hours. All laboratory glassware must be washed with detergent and water and rinsed with water, methanol, and methylene chloride prior to use.

NOTE: The glassware must not be rinsed with acetone or unacceptable levels of acetone contamination will be introduced. If field preparation of DNPH is performed, caution must be exercised in avoiding acetone contamination.

Reagent bottles for storage of cleaned DNPH derivatizing solution must be rinsed with acetonitrile and dried before use. Baked glassware is not essential for preparation of DNPH reagent.

NOTE: DNPH crystals or DNPH solution should be handled with plastic gloves at all times, with prompt and extensive use of running water in case of skin exposure.

5.4.1 Preparation of Aqueous Acidic DNPH: The following materials and reagents are required for preparation of the reagent.

5.4.1.1 Bottles/Caps: amber 1- or 4 L bottles with Teflon®-lined caps are required for storing cleaned DNPH solution. Additional 4-L bottles are required to collect waste organic solvents.

5.4.1.2 Large Glass Container: at least one large glass container (8 to 16 L) is required for mixing the aqueous acidic DNPH solution.

5.4.1.3 Stir Plate/Large Stir Bars/Stir Bar Retriever: a magnetic stir plate and large stir bar are required for the mixing of the aqueous acidic DNPH solution. A stir bar retriever is needed for removing the stir bar from the large container holding the DNPH solution.

5.4.1.4 Buchner Filter/Filter Flask/Filter Paper: a large filter flask (2-4 L) with a buchner filter, appropriate rubber stopper, filter paper, and connecting tubing are required for filtering the aqueous acidic DNPH solution prior to cleaning.

5.4.1.5 Separatory Funnels: at least one large separatory funnel (2 L) is required for cleaning the DNPH prior to use.

5.4.1.6 Beakers: beakers (150 mL, 250 mL, and 400 mL) are useful for holding/measuring organic liquids when cleaning the aqueous acidic DNPH solution and for weighing DNPH crystals.

5.4.1.7 Funnels: at least one large funnel is needed for pouring the aqueous acidic DNPH into the separatory funnel.

5.4.1.8 Graduated Cylinders: at least one large graduated cylinder (1 to 2 L) is required for measuring HPLC-grade water and acid when preparing the DNPH solution.

5.4.1.9 Top-Loading Balance: a one-place top loading balance is needed for weighing out the DNPH crystals used to prepare the aqueous acidic DNPH solution.

5.4.1.10 Spatulas: spatulas are needed for weighing out DNPH when preparing the aqueous DNPH solution.

5.4.1.11 HPLC-Grade Water: water (HPLC-grade) is required to mix the aqueous DNPH solution.

5.4.1.12 Hydrochloric Acid: reagent grade hydrochloric acid (approximately 12N) is required for acidifying the aqueous DNPH solution.

5.4.1.13 2,4-Dinitrophenylhydrazine: a supply of moist solid 2,4-dinitrophenylhydrazine (DNPH) is required for preparation of aqueous acidic DNPH solution. The quantity of water may vary from 10 to 30%. Reagent grade or equivalent is required.

5.4.1.14 Methylene Chloride: methylene chloride (suitable for residue and pesticide analysis, GC/MS, HPLC, GC, Spectrophotometry or equivalent) is required for cleaning the aqueous acidic DNPH solution, rinsing glassware, and recovery of sample trains.

5.4.1.15 Cyclohexane: cyclohexane (HPLC grade) is required for cleaning the aqueous acidic DNPH solution.

NOTE: Do not use spectroanalyzed grades of cyclohexane if this sampling methodology is extended to aldehydes and ketones with four or more carbon atoms.

5.4.1.16 Methanol: methanol (HPLC grade or equivalent) is required for rinsing glassware.

5.4.1.17 Acetonitrile: acetonitrile (HPLC grade or equivalent) is required for rinsing glassware.

5.4.1.18 Formaldehyde: Analytical grade or equivalent formaldehyde is required for preparation of standards. If other aldehydes or ketones are used, analytical grade or equivalent is required.

5.4.2 Preparation of Aqueous Acidic DNPH Derivatizing Reagent: Each batch of DNPH reagent should be prepared and purified within five days of sampling, according to the procedure described below.

5.4.2.1 Place an 8-L container under a fume hood on a magnetic stirrer. Add a large stir bar and fill the container half full of HPLC-grade water. Save the empty bottle from HPLC-grade water. Start the stirring bar and adjust the stir rate to be as fast as possible. Using a graduated cylinder, measure 1.4 mL of concentrated hydrochloric acid. Slowly pour the acid into the stirring water. Fumes may be generated and the water may become warm. Weigh the DNPH crystals on a one-place balance (see Table 1 for approximate amounts) and add to the stirring acid solution. Fill the 8 L container to the 8 L mark with HPLC water and stir overnight. If all of the DNPH crystals have dissolved overnight, add additional DNPH and stir for two more hours. Continue the process of adding DNPH with additional stirring until a saturated solution has been formed. Filter the DNPH solution using vacuum filtration. Gravity filtration may be used, but a

much longer time is required. Store the filtered solution in an amber bottle at room temperature.

TABLE 1. APPROXIMATE AMOUNT OF CRYSTALLINE DNPH USED
TO PREPARE A SATURATED SOLUTION

Amount of Moisture in DNPH	Weight Required per 8 L of Solution
10 weight percent	31 g
15 weight percent	33 g
30 weight percent	40 g

Within five days of proposed use, place about 1.6 L of the DNPH reagent in a 2 L separatory funnel. Add approximately 200 mL of methylene chloride and stopper the funnel. Wrap the stopper of the funnel with paper towels to absorb any leakage. Invert and vent the funnel. Then shake vigorously for 3 minutes. Initially, the funnel should be vented frequently (every 10 - 15 sec). After the layers have separated, discard the lower (organic) layer.

Extract the DNPH a second time with methylene chloride and finally with cyclohexane. When the cyclohexane layer has separated from the DNPH reagent, the cyclohexane layer will be the top layer in the separatory funnel. Drain the lower layer (the cleaned extracted DNPH reagent solution) into an amber bottle that has been rinsed with acetonitrile and allowed to dry.

5.4.3 Quality Control: Take two aliquots of the extracted DNPH reagent. The size of the aliquots is dependent upon the exact sampling procedure used, but 100 mL is reasonably representative. To ensure that the background in the reagent is acceptable for field use, analyze one aliquot of the reagent according to the procedure of EPA Draft Method 8315. Save the other aliquot of aqueous acidic DNPH for use as a method blank when the analysis is performed.

5.4.4 Shipment to the Field: Tightly cap the bottle containing extracted DNPH reagent using a Teflon®-lined cap. Seal the bottle with Teflon® tape. After the bottle is labeled, the bottle may be placed in a friction-top can (paint can or equivalent) containing a 1 -2 inch layer of granulated charcoal and stored at ambient temperature until use.

If the DNPH reagent has passed the Quality Control criteria, the reagent may be packaged to meet necessary shipping requirements and sent to the sampling area. If the Quality Control criteria are not met, the reagent solution may be re-extracted or the solution may be re-prepared and the extraction sequence repeated.

If the DNPH reagent is not used in the field within five days of extraction, an aliquot may be taken and analyzed as described Draft Method 8315. If the reagent meets the Quality Control requirements, the reagent may be used. If the reagent does not meet Quality Control requirements, the reagent must be discarded and new reagent must be prepared and tested.

5.4.5 Calculation of Acceptable Levels of Impurities in DNPH Reagent: The acceptable impurity level (AIL, µg/mL) is calculated from the expected analyte level in the sampled gas (EAL, ppbv), the volume of air that will be sampled at standard conditions (SVOL, L), the formula weight of the analyte (FW, g/mol), and the volume of DNPH reagent that will be used in the impingers (RVOL, mL):

$$AIL = 0.1 \times [EAL \times SVOL \times FW/22.4 \times (FW + 180)/FW] / (RVOL \times 1000).$$

where 0.1 is the acceptable contaminant level, 22.4 is a factor relating ppbv to g/L, 180 is a factor relating the underivatized analyte to the derivatized analyte, and 1000 is a unit conversion factor.

5.4.6 Disposal of Excess DNPH Reagent: Excess DNPH reagent may be returned to the laboratory and recycled or treated as aqueous waste for disposal purposes. 2,4-Dinitrophenylhydrazine is a flammable solid when dry so water should not be evaporated from the solution of the reagent.

5.5 Field Spike Standard Preparation: To prepare a formaldehyde field spiking standard at 4.01 mg/mL, use a 500µL syringe to transfer 0.5 mL of 37% by weight of formaldehyde (401 mg/mL) to a 50 mL volumetric flask containing approximately 40 mL of methanol. Dilute to 50 mL with methanol.

6.0 SAMPLE COLLECTION, PRESERVATION, AND HANDLING

6.1 Because of the complexity of this method, field personnel should be trained in and experienced with the test procedures in order to obtain reliable results.

6.2 Laboratory Preparation:

6.2.1 All the components shall be maintained and calibrated according to the procedure described in APTD-0576, unless otherwise specified.

6.2.2 Weigh several 200- to 300-g portions of silica gel in airtight containers to the nearest 0.5 g. Record on each container the total weight of the silica gel plus containers. As an alternative to preweighing the silica gel, it may instead be weighed directly in the impinger or sampling holder just prior to train assembly.

6.3 Preliminary Field Determinations:

6.3.1 Select the sampling site and the minimum number of sampling points according to EPA Method 1 or other relevant criteria. Determine the stack pressure, temperature, and range of velocity heads using EPA Method 2. A leak-check of the pitot lines according to EPA Method 2, Section 3.1, must be performed. Determine the stack gas moisture content using EPA Approximation Method 4 or its alternatives to establish estimates of isokinetic sampling-rate settings. Determine the stack gas dry molecular weight, as described in EPA Method 2, Section 3.6. If integrated EPA Method 3 sampling is used for molecular weight determination, the integrated bag sample shall be taken simultaneously with, and for the same total length of time as, the sample run.

6.3.2 Select a nozzle size based on the range of velocity heads so that it is not necessary to change the nozzle size in order to maintain isokinetic sampling rates below 28 L/min (1.0 cfm). During the run, do not change the nozzle.

Ensure that the proper differential pressure gauge is chosen for the range of velocity heads encountered (see Section 2.2 of EPA Method 2).

6.3.3 Select a suitable probe liner and probe length so that all traverse points can be sampled. For large stacks, to reduce the length of the probe, consider sampling from opposite sides of the stack.

6.3.4 A minimum of 45 ft³ of sample volume is required for the determination of the Destruction and Removal Efficiency (DRE) of formaldehyde from incineration systems (45ft³ is equivalent to one hour of sampling at 0.75 dscf). Additional sample volume shall be collected as necessitated by the capacity of the DNPH reagent and analytical detection limit constraints. To determine the minimum sample volume required, refer to sample calculations in Section 10.

6.3.5 Determine the total length of sampling time needed to obtain the identified minimum volume by comparing the anticipated average sampling rate with the volume requirement. Allocate the same time to all traverse points defined by EPA Method 1. To avoid timekeeping errors, the length of time sampled at each traverse point should be an integer or an integer plus 0.5 min.

6.3.6 In some circumstances (e.g., batch cycles) it may be necessary to sample for shorter times at the traverse points and to obtain smaller gas-volume samples. In these cases, careful documentation must be maintained in order to allow accurate calculation of concentrations.

6.4 Preparation of Collection Train:

6.4.1 During preparation and assembly of the sampling train, keep all openings where contamination can occur covered with Teflon® film or aluminum foil until just prior to assembly or until sampling is about to begin.

6.4.2 Place 100 mL of cleaned DNPH solution in each of the first two impingers, and leave the third impinger empty. If additional capacity is required for high expected concentrations of formaldehyde in the stack gas, 200 mL of DNPH per impinger may be used or additional impingers may be used for sampling. Transfer approximately 200 to 300 g of pre-weighed silica gel from its container to the fourth impinger. Care should be taken to ensure that the silica gel is not entrained and carried out from the impinger during sampling. Place the silica gel container in a clean place for later use in the sample recovery. Alternatively, the weight of the silica gel plus impinger may be determined to the nearest 0.5 g and recorded.

6.4.3 With a glass or quartz liner, install the selected nozzle using a Viton-A O-ring when stack temperatures are <260°C (500°F) and a woven glass-fiber gasket when temperatures are higher. See APTD-0576 (Rom, 1972) for details. Other connecting systems utilizing either 316 stainless steel or Teflon® ferrules may be used. Mark the probe with heat-resistant tape or by some other method to denote the proper distance into the stack or duct for each sampling point.

6.4.4 Assemble the train as shown in Figure 1. During assembly, do not use any silicone grease on ground-glass joints upstream of the impingers. Use Teflon® tape, if required. A very light coating of silicone grease may be used on ground-glass joints downstream of the impingers, but the silicone grease should be limited to the outer portion (see APTD-0576) of the ground-glass joints to

minimize silicone grease contamination. If necessary, Teflon® tape may be used to seal leaks. Connect all temperature sensors to an appropriate potentiometer/display unit. Check all temperature sensors at ambient temperature.

6.4.5 Place crushed ice all around the impingers. . .

6.4.6 Turn on and set the probe heating system at the desired operating temperature. Allow time for the temperature to stabilize.

6.5 Leak-Check Procedures:

6.5.1 Pre-test Leak Check:

6.5.1.1 After the sampling train has been assembled, turn on and set the probe heating system at the desired operating temperature. Allow time for the temperature to stabilize. If a Viton-A O-ring or other leak-free connection is used in assembling the probe nozzle to the probe liner, leak-check the train at the sampling site by plugging the nozzle and pulling a 381-mm Hg (15 in Hg) vacuum.

NOTE: A lower vacuum may be used, provided that the lower vacuum is not exceeded during the test.

6.5.1.2 If an asbestos string is used, do not connect the probe to the train during the leak check. Instead, leak-check the train by first attaching a carbon-filled leak check impinger to the inlet and then plugging the inlet and pulling a 381-mm Hg (15 in Hg) vacuum. (A lower vacuum may be used if this lower vacuum is not exceeded during the test.) Then connect the probe to the train and leak-check at about 25 mm Hg (1 in Hg) vacuum. Alternatively, leak-check the probe with the rest of the sampling train in one step at 381 mm Hg (15 in Hg) vacuum. Leakage rates in excess of 4% of the average sampling rate or $>0.00057 \text{ m}^3/\text{min}$ (0.02 cfm), whichever is less, are acceptable.

6.5.1.3 The following leak check instructions for the sampling train described in APTD-0576 and APTD-0581 may be helpful. Start the pump with the fine-adjust valve fully open and coarse-adjust valve completely closed. Partially open the coarse-adjust valve and slowly close the fine-adjust valve until the desired vacuum is reached. Do not reverse direction of the fine-adjust valve, as liquid will back up into the train. If the desired vacuum is exceeded, either perform the leak check at this higher vacuum or end the leak check, as shown below, and start over.

6.5.1.4 When the leak check is completed, first slowly remove the plug from the inlet to the probe. When the vacuum drops to 127 mm (5 in) Hg or less, immediately close the coarse-adjust valve. Switch off the pumping system and reopen the fine-adjust valve. Do not reopen the fine-adjust valve until the coarse-adjust valve has been closed to prevent the liquid in the impingers from being forced backward into the sampling line and silica gel from being entrained backward into the third impinger.

6.5.2 Leak Checks During Sampling Runs:

6.5.2.1 If, during the sampling run, a component change (i.e., impinger) becomes

necessary, a leak check shall be conducted immediately after the interruption of sampling and before the change is made. The leak check shall be done according to the procedure described in Section 6.5.1, except that it shall be done at a vacuum greater than or equal to the maximum value recorded up to that point in the test. If the leakage rate is found to be no greater than 0.00057 m³/min (0.02 cfm) or 4% of the average sampling rate (whichever is less), the results are acceptable. If a higher leakage rate is obtained, the tester must void the sampling run.

NOTE: Any correction of the sample volume by calculation reduces the integrity of the pollutant concentration data generated and must be avoided.

6.5.2.2 Immediately after a component change and before sampling is re-initiated, a leak check similar to a pre-test leak check must also be conducted.

6.5.3 Post-test Leak Check:

6.5.3.1 A leak check is mandatory at the conclusion of each sampling run. The leak check shall be done with the same procedures as the pre-test leak check, except that the post-test leak check shall be conducted at a vacuum greater than or equal to the maximum value reached during the sampling run. If the leakage rate is found to be no greater than 0.00057 m³/min (0.02 cfm) or 4% of the average sampling rate (whichever is less), the results are acceptable. If, however, a higher leakage rate is obtained, the tester shall record the leakage rate and void the sampling run.

6.6 Sampling Train Operation:

6.6.1 During the sampling run, maintain an isokinetic sampling rate to within 10% of true isokinetic, below 28 L/min (1.0 cfm). Maintain a temperature around the probe of 120° ± 14°C (248° ± 25°F).

6.6.2 For each run, record the data on a data sheet such as the one shown in Figure 2. Be sure to record the initial dry-gas meter reading. Record the dry-gas meter readings at the beginning and end of each sampling time increment, when changes in flow rates are made, before and after each leak check, and when sampling is halted. Take other readings required by Figure 2 at least once at each sample point during each time increment and additional readings when significant adjustments (20% variation in velocity head readings) necessitate additional adjustments in flow rate. Level and zero the manometer. Because the manometer level and zero may drift due to vibrations and temperature changes, make periodic checks during the traverse.

6.6.3 Clean the stack access ports prior to the test run to eliminate the chance of sampling deposited material. To begin sampling, remove the nozzle cap, verify that the filter and probe heating systems are at the specified temperature, and verify that the pitot tube and probe are properly positioned. Position the nozzle at the first traverse point, with the tip pointing directly into the gas stream. Immediately start the pump and adjust the flow to isokinetic conditions. Nomographs, which aid in the rapid adjustment of the isokinetic sampling rate without excessive computations, are available. These nomographs are designed for use when the Type S pitot tube coefficient is 0.84 ± 0.02 and the stack gas equivalent density (dry molecular weight) is equal to 29 ± 4. APTD-0576 details the procedure for using the nomographs. If the stack gas molecular weight and

the pitot tube coefficient are outside the above ranges, do not use the nomographs unless appropriate steps are taken to compensate for the deviations.

6.6.4 When the stack is under significant negative pressure (equivalent to the height of the impinger stem), take care to close the coarse-adjust valve before inserting the probe into the stack in order to prevent liquid from backing up through the train. If necessary, the pump may be turned on with the coarse-adjust valve closed.

6.6.5 When the probe is in position, block off the openings around the probe and stack access port to prevent unrepresentative dilution of the gas stream.

6.6.6 Traverse the stack cross section, as required by EPA Method 1, being careful not to bump the probe nozzle into the stack walls when sampling near the walls or when removing or inserting the probe through the access port, in order to minimize the chance of extracting deposited material.

6.6.7 During the test run, make periodic adjustments to keep the temperature around the probe at the proper levels. Add more ice and, if necessary, salt, to maintain a temperature of $<20^{\circ}\text{C}$ (68°F) at the silica gel outlet. Also, periodically check the level and zero of the manometer.

6.6.8 A single train shall be used for the entire sampling run, except in cases where simultaneous sampling is required in two or more separate ducts or at two or more different locations within the same duct, or in cases where equipment failure necessitates a change of trains. An additional train or additional trains may also be used for sampling when the capacity of a single train is exceeded.

6.6.9 When two or more trains are used, separate analyses of components from each train shall be performed. If multiple trains have been used because the capacity of a single train would be exceeded, first impingers from each train may be combined, and second impingers from each train may be combined.

6.6.10 At the end of the sampling run, turn off the coarse-adjust valve, remove the probe and nozzle from the stack, turn off the pump, record the final dry gas meter reading, and conduct a post-test leak check. Also, leak check the pitot lines as described in EPA Method 2. The lines must pass this leak check in order to validate the velocity-head data.

6.6.11 Calculate percent isokineticity (see Method 2) to determine whether the run was valid or another test should be made.

7.0 SAMPLE RECOVERY

7.1 Preparation:

7.1.1 Proper cleanup procedure begins as soon as the probe is removed from the stack at the end of the sampling period. Allow the probe to cool. When the probe can be handled safely, wipe off all external particulate matter near the tip of the probe nozzle and place a cap over the tip to prevent losing or gaining particulate matter. Do not cap the probe tip tightly while the sampling train is cooling because a vacuum will be created, drawing liquid from the impingers back through the sampling train.

7.1.2 Before moving the sampling train to the cleanup site, remove the probe from the sampling train and cap the open outlet, being careful not to lose any condensate that might be present. Remove the umbilical cord from the last impinger and cap the impinger. If a flexible line is used, let any condensed water or liquid drain into the impingers. Cap off any open impinger inlets and outlets. Ground glass stoppers, Teflon® caps, or caps of other inert materials may be used to seal all openings.

7.1.3 Transfer the probe and impinger assembly to an area that is clean and protected from wind so that the chances of contaminating or losing the sample are minimized.

7.1.4 Inspect the train before and during disassembly, and note any abnormal conditions.

7.1.5 Save a portion of all washing solutions (methylene chloride, water) used for cleanup as a blank. Transfer 200 mL of each solution directly from the wash bottle being used and place each in a separate, pre-labeled sample container.

7.2 Sample Containers:

7.2.1 Container 1: Probe and Impinger Catches. Using a graduated cylinder, measure to the nearest mL, and record the volume of the solution in the first three impingers. Alternatively, the solution may be weighed to the nearest 0.5 g. Include any condensate in the probe in this determination. Transfer the impinger solution from the graduated cylinder into the amber flint glass bottle. Taking care that dust on the outside of the probe or other exterior surfaces does not get into the sample, clean all surfaces to which the sample is exposed (including the probe nozzle, probe fitting, probe liner, first impinger, and impinger connector) with methylene chloride. Use less than 500 mL for the entire wash (250 mL would be better, if possible). Add the washings to the sample container.

7.2.1.1 Carefully remove the probe nozzle and rinse the inside surface with methylene chloride from a wash bottle. Brush with a Teflon® bristle brush, and rinse until the rinse shows no visible particles or yellow color, after which make a final rinse of the inside surface. Brush and rinse the inside parts of the Swagelok® fitting with methylene chloride in a similar way.

7.2.1.2 Rinse the probe liner with methylene chloride. While squirting the methylene chloride into the upper end of the probe, tilt and rotate the probe so that all inside surfaces will be wetted with methylene chloride. Let the methylene chloride drain from the lower end into the sample container. The tester may use a funnel (glass or polyethylene) to aid in transferring the liquid washes to the container. Follow the rinse with a Teflon® brush. Hold the probe in an inclined position, and squirt methylene chloride into the upper end as the probe brush is being pushed with a twisting action through the probe. Hold the sample container underneath the lower end of the probe, and catch any methylene chloride, water, and particulate matter that is brushed from the probe. Run the brush through the probe three times or more. With stainless steel or other metal probes, run the brush through in the above prescribed manner at least six times since there may be small crevices in which particulate matter can be entrapped. Rinse the brush with methylene chloride or water, and quantitatively collect these washings in the sample container. After the brushings, make a final rinse

of the probe as described above.

NOTE: Two people should clean the probe in order to minimize sample losses. Between sampling runs, brushes must be kept clean and free from contamination.

7.2.1.3 Rinse the inside surface of each of the first three impingers (and connecting tubing) three separate times. Use a small portion of methylene chloride for each rinse, and brush each surface to which sample is exposed with a Teflon® bristle brush to ensure recovery of fine particulate matter. Water will be required for the recovery of the impingers in addition to the specified quantity of methylene chloride. There will be at least two phases in the impingers. This two-phase mixture does not pour well, and a significant amount of the impinger catch will be left on the walls. The use of water as a rinse makes the recovery quantitative. Make a final rinse of each surface and of the brush, using both methylene chloride and water.

7.2.1.4 After all methylene chloride and water washings and particulate matter have been collected in the sample container, tighten the lid so that solvent, water, and DNPH reagent will not leak out when the container is shipped to the laboratory. Mark the height of the fluid level to determine whether leakage occurs during transport. Seal the container with Teflon® tape. Label the container clearly to identify its contents.

7.2.1.5 If the first two impingers are to be analyzed separately to check for breakthrough, separate the contents and rinses of the two impingers into individual containers. Care must be taken to avoid physical carryover from the first impinger to the second. The formaldehyde hydrazone is a solid which floats and froths on top of the impinger solution. Any physical carryover of collected moisture into the second impinger will invalidate a breakthrough assessment.

7.2.2 Container 2: Sample Blank. Prepare a blank by using an amber flint glass container and adding a volume of DNPH reagent and methylene chloride equal to the total volume in Container 1. Process the blank in the same manner as Container 1.

7.2.3 Container 3: Silica Gel. Note the color of the indicating silica gel to determine whether it has been completely spent and make a notation of its condition. The impinger containing the silica gel may be used as a sample transport container with both ends sealed with tightly fitting caps or plugs. Ground-glass stoppers or Teflon® caps may be used. The silica gel impinger should then be labeled, covered with aluminum foil, and packaged on ice for transport to the laboratory. If the silica gel is removed from the impinger, the tester may use a funnel to pour the silica gel and a rubber policeman to remove the silica gel from the impinger. It is not necessary to remove the small amount of dust particles that may adhere to the impinger wall and are difficult to remove. Since the gain in weight is to be used for moisture calculations, do not use water or other liquids to transfer the silica gel. If a balance is available in the field, the spent silica gel (or silica gel plus impinger) may be weighed to the nearest 0.5 g.

7.2.4 Sample containers should be placed in a cooler, cooled by although not in contact with ice. Sample containers must be placed vertically and, since they are glass, protected from breakage during shipment. Samples should be cooled during shipment so they will be received cold at the laboratory.

8.0 CALIBRATION

8.1 Probe Nozzle: Probe nozzles shall be calibrated before their initial use in the field. Using a micrometer, measure the inside diameter of the nozzle to the nearest 0.025 mm (0.001 in). Make measurements at three separate places across the diameter and obtain the average of the measurements. The difference between the high and low numbers shall not exceed 0.1 mm (0.004 in). When the nozzles become nicked or corroded, they shall be replaced and calibrated before use. Each nozzle must be permanently and uniquely identified.

8.2 Pitot tube: The Type S pitot tube assembly shall be calibrated according to the procedure outlined in Section 4 of EPA Method 2, or assigned a nominal coefficient of 0.84 if it is not visibly nicked or corroded and if it meets design and intercomponent spacing specifications.

8.3 Metering system:

8.3.1 Before its initial use in the field, the metering system shall be calibrated according to the procedure outlined in APTD-0576. Instead of physically adjusting the dry-gas meter dial readings to correspond to the wet-test meter readings, calibration factors may be used to correct the gas meter dial readings mathematically to the proper values. Before calibrating the metering system, it is suggested that a leak check be conducted. For metering systems having diaphragm pumps, the normal leak check procedure will not detect leakages within the pump. For these cases, the following leak check procedure will apply: make a ten-minute calibration run at 0.00057 m³/min (0.02 cfm). At the end of the run, take the difference of the measured wet-test and dry-gas meter volumes and divide the difference by 10 to get the leak rate. The leak rate should not exceed 0.00057 m³/min (0.02 cfm).

8.3.2 After each field use, check the calibration of the metering system by performing three calibration runs at a single intermediate orifice setting (based on the previous field test). Set the vacuum at the maximum value reached during the test series. To adjust the vacuum, insert a valve between the wet-test meter and the inlet of the metering system. Calculate the average value of the calibration factor. If the calibration has changed by more than 5%, recalibrate the meter over the full range of orifice settings, as outlined in APTD-0576.

8.3.3 Leak check of metering system: The portion of the sampling train from the pump to the orifice meter (see Figure 1) should be leak-checked prior to initial use and after each shipment. Leakage after the pump will result in less volume being recorded than is actually sampled. Use the following procedure: Close the main valve on the meter box. Insert a one-hole rubber stopper with rubber tubing attached into the orifice exhaust pipe. Disconnect and vent the low side of the orifice manometer. Close off the low side orifice tap. Pressurize the system to 13 - 18 cm (5 - 7 in) water column by blowing into the rubber tubing. Pinch off the tubing and observe the manometer for 1 min. A loss of pressure on the manometer indicates a leak in the meter box. Leaks must be corrected.

NOTE: If the dry-gas-meter coefficient values obtained before and after a test series differ by >5%, either the test series must be voided or calculations for test series must be performed using whichever meter coefficient value (i.e., before or after) gives the lower value of total sample volume.

8.4 Probe heater: The probe heating system must be calibrated before its initial use in the field according to the procedure outlined in APTD-0576. Probes constructed according to APTD-0581 need not be calibrated if the calibration curves in APTD-0576 are used.

8.5 Temperature gauges: Each thermocouple must be permanently and uniquely marked on the casting. All mercury-in-glass reference thermometers must conform to ASTM E-1 63C or 63F specifications. Thermocouples should be calibrated in the laboratory with and without the use of extension leads. If extension leads are used in the field, the thermocouple readings at ambient air temperatures, with and without the extension lead, must be noted and recorded. Correction is necessary if the use of an extension lead produces a change $>1.5\%$.

8.5.1 Impinger and dry-gas meter thermocouples: For the thermocouples used to measure the temperature of the gas leaving the impinger train, three-point calibration at ice water, room air, and boiling water temperatures is necessary. Accept the thermocouples only if the readings at all three temperatures agree to $\pm 2^{\circ}\text{C}$ (3.6°F) with those of the absolute value of the reference thermometer.

8.5.2 Probe and stack thermocouple: For the thermocouples used to indicate the probe and stack temperatures, a three-point calibration at ice water, boiling water, and hot oil bath temperatures must be performed. Use of a point at room air temperature is recommended. The thermometer and thermocouple must agree to within 1.5% at each of the calibration points. A calibration curve (equation) may be constructed (calculated) and the data extrapolated to cover the entire temperature range suggested by the manufacturer.

8.6 Barometer: Adjust the barometer initially and before each test series to agree to within ± 2.5 mm Hg (0.1 in Hg) of the mercury barometer or the corrected barometric pressure value reported by a nearby National Weather Service Station (same altitude above sea level).

8.7 Triple-beam balance: Calibrate the triple-beam balance before each test series, using Class S standard weights. The weights must be within $\pm 0.5\%$ of the standards, or the balance must be adjusted to meet these limits.

9.0 CALCULATIONS

Carry out calculations, retaining at least one extra decimal figure beyond that of the acquired data. Round off figures after final calculation.

9.1 Calculation of Total Formaldehyde:

To determine the total formaldehyde in mg, use the following equation:

$$\text{Total mg formaldehyde} = C_d \times V \times DF \times \\ \left(\frac{[\text{g/mole aldehyde}]}{[\text{g/mole DNPH derivative}]} \right) \times \\ 10^{-3} \text{ mg/\mu g}$$

where:

C_d = measured concentration of DNPH-formaldehyde derivative, $\mu\text{g/mL}$

V = organic extract volume, mL

DF = dilution factor

9.2 Formaldehyde concentration in stack gas:

Determine the formaldehyde concentration in the stack gas using the following equation:

$$C_f = K [\text{total formaldehyde, mg}] / V_{m(\text{std})}$$

where:

$K = 35.31 \text{ ft}^3/\text{m}^3$ if $V_{m(\text{std})}$ is expressed in English units

$= 1.00 \text{ m}^3/\text{m}^3$ if $V_{m(\text{std})}$ is expressed in metric units

$V_{m(\text{std})}$ = volume of gas sample as measured by dry gas meter, corrected to standard conditions, dscm (dscf)

9.3 Average Dry Gas Meter Temperature and Average Orifice Pressure Drop are obtained from the data sheet.

9.4 Dry Gas Volume: Calculate $V_{m(\text{std})}$ and adjust for leakage, if necessary, using the equation in Section 6.3 of EPA Method 5.

9.5 Volume of Water Vapor and Moisture Content: Calculate the volume of water vapor and moisture content from equations 5-2 and 5-3 of EPA Method 5.

10.0 DETERMINATION OF VOLUME TO BE SAMPLED

To determine the minimum sample volume to be collected, use the following sequence of equations.

10.1 From prior analysis of the waste feed, the concentration of formaldehyde (FORM) introduced into the combustion system can be calculated. The degree of destruction and removal efficiency that is required is used to determine the maximum amount of FORM allowed to be present in the effluent. This amount may be expressed as:

Max FORM₁ Mass -

$$[(WF) (FORM_1 \text{ conc}) (100 - \%DRE)] / 100$$

where:

WF - mass flow rate of waste feed per h, g/h (lb/h)

FORM₁ - concentration of FORM (wt %) introduced into the combustion process

DRE - percent Destruction and Removal Efficiency required

Max FORM - mass flow rate (g/h [lb/h]) of FORM emitted from the combustion source

10.2 The average discharge concentration of the FORM in the effluent gas is determined by comparing the Max FORM with the volumetric flow rate being exhausted from the source. Volumetric flow rate data are available as a result of preliminary EPA Method 1 - 4 determinations:

$$\text{Max FORM}_1 \text{ conc} = [\text{Max FORM}_1 \text{ Mass}] / DV_{\text{eff(Std)}}$$

where:

DV_{eff(Std)} - volumetric flow rate of exhaust gas, dscm (dscf)

FORM₁ conc - anticipated concentration of the FORM in the exhaust gas stream, g/dscm (lb/dscf)

10.3 In making this calculation, it is recommended that a safety margin of at least ten be included.

$$[LDL_{\text{FORM}} \times 10] / [FORM_1 \text{ conc}] = V_{\text{abc}}$$

where:

LDL_{FORM} - detectable amount of FORM in entire sampling train

V_{abc} - minimum dry standard volume to be collected at dry-gas meter

10.4 The following analytical detection limits and DNPH Reagent Capacity (based on a total volume of 200 mL in two impingers) must also be considered in determining a volume to be sampled.

Table 2. Instrument Detection Limits and Reagent Capacity for Formaldehyde Analysis¹

Analyte	Detection Limit, ppbv ²	Reagent Capacity, ppmv
formaldehyde	1.8	66
acetaldehyde	1.7	70
acrolein	1.5	75
acetone/propionaldehyde	1.5	75
butyraldehyde	1.5	79
methyl ethyl ketone	1.5	79
valeraldehyde	1.5	84
isovaleraldehyde	1.4	84
hexaldehyde	1.3	88
benzaldehyde	1.4	84
o-/m-/p-tolualdehyde	1.3	89
dimethylbenzaldehyde	1.2	93

¹ Oxygenated compounds in addition to formaldehyde are included for comparison with formaldehyde; extension of the methodology to other compounds is possible.

² Detection limits are determined in solvent. These values therefore represent the optimum capability of the methodology.

11.0 QUALITY CONTROL

11.1 Sampling: See EPA Manual 600/4-77-027b for Method 5 quality control.

11.2 Analysis: The quality assurance program required for this method includes the analysis of field and method blanks, procedure validations, and analysis of field spikes. The assessment of combustion data and positive identification and quantitation of formaldehyde are dependent on the integrity of the samples received and the precision and accuracy of the analytical methodology. Quality Assurance procedures for this method are designed to monitor the performance of the analytical methodology and to provide the required information to take corrective action if problems are observed in laboratory operations or in field sampling activities.

11.2.1 Field Blanks: Field blanks must be submitted with the samples collected at each sampling site. The field blanks include the sample bottles containing aliquots of sample recovery solvents, methylene chloride and water, and unused DNPH reagent. At a minimum, one complete sampling train will be assembled in the field staging area, taken to the sampling area, and leak-checked at the beginning and end of the testing (or for the same total number of times as the actual sampling train). The probe of the blank train must be heated during the sample test. The train will be recovered as if it were an actual test sample. No gaseous sample will be passed through the Blank sampling train.

11.2.2 Method Blanks: A method blank must be prepared for each set of analytical operations, to evaluate contamination and artifacts that can be derived from glassware, reagents, and sample handling in the laboratory.

11.2.3 Field Spike: A field spike is performed by introducing 200 µL of the Field Spike Standard into an impinger containing 200 mL of DNPH solution. Standard impinger recovery procedures are followed and the field spike sample is returned to the laboratory for analysis. The field spike is used as a check on field handling and recovery procedures. An aliquot of the field spike standard is retained in the laboratory for derivatization and comparative analysis.

12.0 METHOD PERFORMANCE

12.1 Method performance evaluation: The following expected method performance parameters for precision, accuracy, and detection limits are provided in Table 3.


Table 3. Expected Method Performance for Formaldehyde

Parameter	Precision	¹ Accuracy ²	Detection Limit ³
Matrix: Dual trains	±15% RPD	±20%	1.5×10^{-7} lb/ft ³ (1.8 ppbv)

¹ Relative percent difference limit for dual trains.

² Limit for field spike recoveries.

³ The lower reporting limit having less than 1% probability of false positive detection.



Formaldehyde Sampling Train

Stialto Pressure, mm Hg (In. Hg) _____

Filter No. _____

[illegible]

Figure 2. Field Data Sheet

METHOD 25A—DETERMINATION OF TOTAL GASEOUS ORGANIC CONCENTRATION USING A FLAME IONIZATION ANALYZER**1. Applicability and Principle**

1.1 **Applicability.** This method applies to the measurement of total gaseous organic concentration of vapors consisting primarily of alkanes, alkenes, and/or arenes (aromatic hydrocarbons). The concentration is expressed in terms of propane (or other appropriate organic calibration gas) or in terms of carbon.

1.2 **Principle.** A gas sample is extracted from the source through a heated sample line, if necessary, and glass fiber filter to a flame ionization analyzer (FIA). Results are reported as volume concentration equivalents of the calibration gas or as carbon equivalents.

2. Definitions

2.1 **Measurement System.** The total equipment required for the determination of the gas concentration. The system consists of the following major subsystems:

2.1.1 **Sample Interface.** That portion of the system that is used for one or more of the following: sample acquisition, sample transportation, sample conditioning, or protection of the analyzer from the effects of the stack effluent.

2.1.2 **Organic Analyzer.** That portion of the system that senses organic concentration and generates an output proportional to the gas concentration.

2.2 **Span Value.** The upper limit of a gas concentration measurement range that is

specified for affected source categories in the applicable part of the regulations. The span value is established in the applicable regulation and is usually 1.5 to 2.5 times the applicable emission limit. If no span value is provided, use a span value equivalent to 1.5 to 2.5 times the expected concentration. For convenience, the span value should correspond to 100 percent of the recorder scale.

2.3 **Calibration Gas.** A known concentration of a gas in an appropriate diluent gas.

2.4 **Zero Drift.** The difference in the measurement system response to a zero level calibration gas before and after a stated period of operation during which no unscheduled maintenance, repair, or adjustment took place.

2.5 **Calibration Drift.** The difference in the measurement system response to a mid-level calibration gas before and after a stated period of operation during which no unscheduled maintenance, repair or adjustment took place.

2.6 **Response Time.** The time interval from a step change in pollutant concentration at the inlet to the emission measurement system to the time at which 95 percent of the corresponding final value is reached as displayed on the recorder.

2.7 **Calibration Error.** The difference between the gas concentration indicated by the measurement system and the known concentration of the calibration gas.

3. Apparatus

A schematic of an acceptable measurement system is shown in Figure 25A-1. The essential components of the measurement system are described below:




Figure 25A-1. Organic Concentration Measurement System.

3.1 Organic Concentration Analyzer. A flame ionization analyzer (FIA) capable of meeting or exceeding the specifications in this method.

3.2 Sample Probe. Stainless steel, or equivalent, three-hole rake type. Sample holes shall be 4 mm in diameter or smaller and located at 16.7, 50, and 83.3 percent of the equivalent stack diameter. Alternatively, a single opening probe may be used so that a gas sample is collected from the centrally located 10 percent area of the stack cross-section.

3.3 Sample Line. Stainless steel or Teflon[®] tubing to transport the sample gas to the analyzer. The sample line should be heated, if necessary, to prevent condensation in the line.

3.4 Calibration Valve Assembly. A three-way valve assembly to direct the zero and calibration gases to the analyzers is recommended. Other methods, such as quick-connect lines, to route calibration gas to the analyzers are applicable.

3.5 Particulate Filter. An in-stack or an out-of-stack glass fiber filter is recommended if exhaust gas particulate loading is significant. An out-of-stack filter should be heated to prevent any condensation.

3.6 Recorder. A strip-chart recorder, analog computer, or digital recorder for recording measurement data. The minimum data recording requirement is one measurement value per minute. Note: This method is often applied in highly explosive areas. Caution and care should be exercised in choice of equipment and installation.

4. Calibration and Other Gases

Gases used for calibrations, fuel, and combustion air (if required) are contained in compressed gas cylinders. Preparation of calibration gases shall be done according to the procedure in Protocol No. 1, listed in Reference 9.2. Additionally, the manufacturer of the cylinder should provide a recommended shelf life for each calibration gas cylinder over which the concentration does not change more than ± 2 percent from the certified value. For calibration gas values not generally available (i.e., organics between 1 and 10 percent by volume), alternative methods for preparing calibration gas mixtures, such as dilution systems, may be used with prior approval of the Administrator.

Calibration gases usually consist of propane in air or nitrogen and are determined in terms of the span value. Organic compounds other than propane can be used following the above guidelines and making the appropriate corrections for response factor.

* Mention of trade names or specific products does not constitute endorsement by the Environmental Protection Agency.

4.1 Fuel. A 40 percent H₂/60 percent He or 40 percent H₂/60 percent N₂ gas mixture is recommended to avoid an oxygen synergism effect that reportedly occurs when oxygen concentration varies significantly from a mean value.

4.2 Zero Gas. High purity air with less than 0.1 parts per million by volume (ppmv) of organic material (propane or carbon equivalent) or less than 0.1 percent of the span value, whichever is greater.

4.3 Low-level Calibration Gas. An organic calibration gas with a concentration equivalent to 25 to 35 percent of the applicable span value.

4.4 Mid-level Calibration Gas. An organic calibration gas with a concentration equivalent to 45 to 55 percent of the applicable span value.

4.5 High-level Calibration Gas. An organic calibration gas with a concentration equivalent to 80 to 90 percent of the applicable span value.

5. Measurement System Performance Specifications

5.1 Zero Drift. Less than ± 3 percent of the span value.

5.2 Calibration Drift. Less than ± 3 percent of span value.

5.3 Calibration Error. Less than ± 5 percent of the calibration gas value.

6. Pretest Preparations

6.1 Selection of Sampling Site. The location of the sampling site is generally specified by the applicable regulation or purpose of the test; i.e., exhaust stack, inlet line, etc. The sample port shall be located at least 1.5 meters or 2 equivalent diameters upstream of the gas discharge to the atmosphere.

6.2 Location of Sample Probe. Install the sample probe so that the probe is centrally located in the stack, pipe, or duct and is sealed tightly at the stack port connection.

6.3 Measurement System Preparation. Prior to the emission test, assemble the measurement system following the manufacturer's written instructions in preparing the sample interface and the organic analyzer. Make the system operable.

FIA equipment can be calibrated for almost any range of total organics concentrations. For high concentrations of organics (>1.0 percent by volume as propane) modifications to most commonly available analyzers are necessary. One accepted method of equipment modification is to decrease the size of the sample to the analyzer through the use of a smaller diameter sample capillary. Direct and continuous measurement of organic concentration is a necessary consideration when determining any modification design.

6.4 Calibration Error Test. Immediately prior to the test series, (within 2 hours of the start of the test) introduce zero gas and

high-level calibration gas at the calibration valve assembly. Adjust the analyzer output to the appropriate levels, if necessary. Calculate the predicted response for the low-level and mid-level gases based on a linear response line between the zero and high-level responses. Then introduce low-level and mid-level calibration gases successively to the measurement system. Record the analyzer responses for low-level and mid-level calibration gases and determine the differences between the measurement system responses and the predicted responses. These differences must be less than 5 percent of the respective calibration gas value. If not, the measurement system is not acceptable and must be replaced or repaired prior to testing. No adjustments to the measurement system shall be conducted after the calibration and before the drift check (Section 7.3). If adjustments are necessary before the completion of the test series, perform the drift checks prior to the required adjustments and repeat the calibration following the adjustments. If multiple electronic ranges are to be used, each additional range must be checked with a mid-level calibration gas to verify the multiplication factor.

6.5 Response Time Test. Introduce zero gas into the measurement system at the calibration valve assembly. When the system output has stabilized, switch quickly to the high-level calibration gas. Record the time from the concentration change to the measurement system response equivalent to 95 percent of the step change. Repeat the test three times and average the results.

7. Emission Measurement Test Procedure

7.1 Organic Measurement. Begin sampling at the start of the test period, recording time and any required process information as appropriate. In particular, note on the recording chart periods of process interruption or cyclic operation.

7.2 Drift Determination. Immediately following the completion of the test period and hourly during the test period, reintroduce the zero and mid-level calibration gases, one at a time, to the measurement system at the calibration valve assembly. (Make no adjustments to the measurement system until after both the zero and calibration drift checks are made.) Record the analyzer response. If the drift values exceed the specified limits, invalidate the test results preceding the check and repeat the test following corrections to the measurement system. Alternatively, recalibrate the test measurement system as in Section 6.4 and report the results using both sets of calibration data (i.e., data determined prior to the test period and data determined following the test period).

8. Organic Concentration Calculations

Determine the average organic concentration in terms of ppmv as propane or other

calibration gas. The average shall be determined by the integration of the output recording over the period specified in the applicable regulation.

If results are required in terms of ppmv as carbon, adjust measured concentrations using Equation 25A-1.

$$C_c = K C_{mcs}$$

Eq. 25A-1

Where:

C_c = Organic concentration as carbon, ppmv.

C_{mcs} = Organic concentration as measured, ppmv.

K = Carbon equivalent correction factor.

$K=2$ for ethane.

$K=3$ for propane.

$K=4$ for butane.

K = Appropriate response factor for other organic calibration gases.

9. Bibliography

9.1 Measurement of Volatile Organic Compounds—Guideline Series. U.S. Environmental Protection Agency. Research Triangle Park, NC. Publication No. EPA-450/2-78-041. June 1978. p. 46-54.

9.2 Traceability Protocol for Establishing True Concentrations of Gases Used for Calibration and Audits of Continuous Source Emission Monitors (Protocol No. 1). U.S. Environmental Protection Agency, Environmental Monitoring and Support Laboratory. Research Triangle Park, NC. June 1978.

9.3 Gasoline Vapor Emission Laboratory Evaluation—Part 2. U.S. Environmental Protection Agency, Office of Air Quality Planning and Standards. Research Triangle Park, NC. EMB Report No. 75-GAS-6. August 1975.

CALCULATION EQUATIONS

METHOD 2

$$\bar{V}_s = 85.48 C_p (\sqrt{\Delta p})_{avg} \sqrt{\frac{T_{s(avg)}}{P_s M_s}}$$

$$Q_{s,d} = 60(1 - B_{ws}) \bar{V}_s A \left(\frac{528}{T_{s(avg)}} \right) \left(\frac{P_s}{29.92} \right)$$

$$Q_a = 60 \bar{V}_s A$$

$$\dot{m}_g = \frac{4.995 Q_{s,d} G_d}{1 - B_{ws}}$$

$$RH^* = 100 (vp_{twb} 0.0003641 P_s (T_{db} - T_{wb})) / vp_{tdb}$$

$$B_{ws}^* = RH(vp_{tdb}) / P_s$$

$$= \frac{4.585 \times 10^{-2} P_s M_s}{T_s (avg)}$$

*Alternate equations for calculating moisture content from wet bulb and dry bulb data.

SYMBOLS

A	=	Cross sectional area of stack, SQ. FT.
A _n	=	Cross sectional area of nozzle, SQ. FT.
B _{ws}	=	Water vapor in gas stream, proportion by volume
C _p	=	Pitot tube coefficient, dimensionless
C _a	=	Concentration of particulate matter in stack gas, wet basis, GR/ACF
C _s	=	Concentration of particulate matter in stack gas, dry basis, corrected to standard conditions, GR/DSCF
EA	=	Excess air, percent by volume
Y	=	Dry test meter correction factor, dimensionless
G _d	=	Specific gravity (relative to air), dimensionless
I	=	Isokinetic variation, percent by volume
M _d	=	Molecular weight of stack gas, dry basis, g/g - mole.
$\dot{m}_g$	=	Mass flow of wet flue gas, LB/HR
$\dot{m}_p$	=	Particulate mass flow, LB/HR
M _s	=	Molecular weight of stack gas, wet basis, g/g, mole.
M _p	=	Total amount of particulate matter collected, g
P _{bar}	=	Atmospheric pressure, IN. HG. (uncompensated)
P _g	=	Stack static gas pressure, IN. WC.

P_s = Absolute pressure of stack gas, IN.HG.
 P_{std} = Standard absolute pressure, 29.92 IN. HG.
 A_a = Actual volumetric stack gas flow rate, ACFM
 $Q_{s,d}$ = Dry volumetric stack gas flow rate corrected to standard conditions, DSCFM
 RH = Relative humidity, %
 T_{db} = Dry bulb temperature of stack gas, °F
 T_{wb} = Wet bulb temperature of stack gas, °F
 $T_m(avg)$ = Absolute average dry gas meter temperature, °R
 $T_s(avg)$ = Absolute average stack temperature, °F
 T_{std} = Standard absolute temperature, 528 °F (68 °F)
 θ = Total sampling time, min.
 V_{lc} = Total volume of liquid collected in impingers and silica gel, ml
 V_m = Volume of gas sample as measured by dry gas meter, CF
 $V_m(std)$ = Volume of gas sample measured by the dry gas meter corrected to standard conditions, DSCF
 $V_w(std)$ = Volume of water vapor in the gas sample corrected to standard conditions, SCF
 $\bar{V}_s$ = Average actual stack gas velocity, FT/SEC
 v_{ptdb} = Vapor pressure at T_{db} , IN. HG.

$v_{p_{twb}}$ = Vapor pressure at T_{wb} , IN. HG

$\overline{\Delta H}$ = Average pressure differential across the orifice meter, IN. WC.

ΔP = Velocity pressure of stack gas, IN. WC.

γ = Dry test meter correction coefficient, dimensionless

ρ = Actual gas density, LB/ACF

CALCULATION EQUATIONS

METHOD 3

$$\%EA = \frac{100(\%O_2 - .5\% CO)}{0.264\% N_2 - \%O_2 + 0.5\% CO}$$

$$M_d = 0.44(\%CO_2) + 0.32 (\%O_2) + 0.28 (\%N_2 + \%CO)$$

$$M_s = M_d (I - B_{ws}) + 0.18 B_{ws}$$

$$B_{ws} = \frac{V_{w(std)}}{V_{w(std)} + V_{m(std)}}$$

CALCULATION EQUATIONS

METHOD 5

$$V_{m(std)} = 17.65 V_m \gamma \left(\frac{P_{bar} + \overline{\Delta H}/13.6}{I_{m(avg)}} \right)$$

$$V_{w(std)} = 0.0472 V_{Is}$$

$$B_{ws} = \frac{V_{w(std)}}{V_{w(std)} + V_{m(std)}}$$

$$I = 0.0944 \left(\frac{T_{s(avg)} V_{m(std)}}{P_s V_s A_n \theta (I - B_{ws})} \right)$$

$$C_s = \frac{15.43 M_p}{V_{m(std)}}$$

$$C_a = \frac{272.3 M_p P_s}{T_{s(avg)} (V_{w(std)} + V_{m(std)})}$$

$$(\dot{m}_p)_1 = 8.5714 \times 10^{-3} C_s Q_{s,d}$$

$$(\dot{m}_p)_2 = \frac{1.3228 \times 10^{-1} M_p A}{O A_n}$$

$$\dot{m}_p = \frac{(\dot{m}_p)_1 + (\dot{m}_p)_2}{2}$$

SYMBOLS

A	= Cross sectional area of stack, SQ. FT.
A_n	= Cross sectional area of nozzle, SQ. FT.
B_{ws}	= Water vapor in gas stream, proportion by volume
C_p	= Pitot tube coefficient, dimensionless
C_a	= Concentration of particulate matter in stack gas, wet basis, GR/ACF
C_s	= Concentration of particulate matter in stack gas, dry basis, corrected to standard conditions, GR/DSCF
EA	= Excess air, percent by volume
γ	= Dry test meter correction factor, dimensionless
G_d	= Specific gravity (relative to air), dimensionless
I	= Isokinetic variation, percent by volume
M_d	= Molecular weight of stack gas, dry basis, g/g - mole.
$\dot{m}_g$	= Mass flow of wet flue gas, LB/HR
$\dot{m}_p$	= Particulate mass flow, LB/HR
M_s	= Molecular weight of stack gas, wet basis, g/g, mole.
M_p	= Total amount of particulate matter collected, g
P_{bar}	= Atmospheric pressure, IN. HG. (uncompensated)
P_g	= Stack static gas pressure, IN. WC.

P_s = Absolute pressure of stack gas, IN.HG.
 P_{std} = Standard absolute pressure, 29.92 IN. HG.
 A_a = Actual volumetric stack gas flow rate, ACFM
 $Q_{s,d}$ = Dry volumetric stack gas flow rate corrected to standard conditions, DSCFM
 RH = Relative humidity, %
 T_{db} = Dry bulb temperature of stack gas, °F
 T_{wb} = Wet bulb temperature of stack gas, °F
 $T_m(avg)$ = Absolute average dry gas meter temperature, °R
 $T_s(avg)$ = Absolute average stack temperature, °F
 T_{std} = Standard absolute temperature, 528 °F (68 °F)
 θ = Total sampling time, min.
 V_{lc} = Total volume of liquid collected in impingers and silica gel, ml
 V_m = Volume of gas sample as measured by dry gas meter, CF
 $V_m(std)$ = Volume of gas sample measured by the dry gas meter corrected to standard conditions, DSCF
 $V_w(std)$ = Volume of water vapor in the gas sample corrected to standard conditions, SCF
 $\bar{V}_s$ = Average actual stack gas velocity, FT/SEC
 v_{ptdb} = Vapor pressure at T_{db} , IN. HG.

v_{ptwb} = Vapor pressure at T_{wb} , IN. HG

$\overline{\Delta H}$ = Average pressure differential across the orifice meter, IN. WC.

ΔP = Velocity pressure of stack gas, IN. WC.

γ = Dry test meter correction coefficient, dimensionless

ρ = Actual gas density, LB/ACF

Interpoll Laboratories
PM-10 Equations

Preliminary Run Calculations:

$$M_d = 0.44 B_{CO_2} + 0.32 B_{O_2} + 0.28 (B_{N_2} + B_{CO})$$

$$M_s = M_d \left(1 - \frac{MC}{100} \right) + 0.18 (MC)$$

$$P_s = P_b + \frac{P_g}{13.6}$$

$$\mu = 152.418 + 0.2552 t_s + 3.2355 \times 10^{-5} t_s^2 \\ + 0.53147 (B_{O_2}) - 0.74143 MC$$

$$Q_s = 2.837 \times 10^{-3} \mu \left[\frac{(t_s + 460)}{(M_s P_s)} \right]^{0.2949}$$

$$\Delta H = \frac{1.083 (t_s + 460) M_d \Delta H_g}{P_b} \left[\frac{Q_s \left(1 - \frac{MC}{100} \right) P_s}{t_s + 460} \right]^2$$

$$\Delta_P^{M201A} = \Delta_P^{M2} \left(\frac{C_P^{M2}}{C_P^{M201A}} \right)^2$$

Dwell Times:

$$\text{Firstpoint} \quad \Delta t_1 = \left[\frac{\sqrt{\Delta P_1}}{(\sqrt{\Delta P})_{AVG}} \right]$$

$$\text{OtherPoints} \quad \Delta t_n = \left(\frac{\Delta t_1}{\sqrt{\Delta P_1}} \right) \sqrt{\Delta P_n} \quad \text{where } n = 2, 3, \dots, 12$$

9-5-91/PL

Post Test Calculations:

$$V_{m(std)} = 17.64 \gamma V_m \left(\frac{P_b + \frac{\Delta H}{13.6}}{(\bar{t}_m + 460)} \right)$$

$$Q_s = \frac{5.669 \times 10^{-2} (\bar{t}_s + 460)}{\Theta P_s} [V_{m(std)} + 0.04707 (V_f - V_i)]$$

$$\mu = 152.418 + 0.2552 \bar{t}_s + 3.2355 \times 10^{-5} \bar{t}_s^2 + 0.53147 B_{O_2} - 0.74143 MC$$

$$M_s = M_d \left(1 - \frac{MC}{100} \right) + 0.18 MC$$

$$D_{50} = 0.15625 \left(\frac{\bar{t}_s + 460}{M_s P_s} \right)^{0.2091} \left(\frac{\mu}{Q_s} \right)^{0.7091}$$

where

- M_d - dry molecular weight of exhaust gas
- B_{CO_2} - percent volume of CO_2 in exhaust gas on a dry basis
- B_{O_2} - percent by volume of O_2 in exhaust gas on a dry basis
- B_{N_2} - percent by volume of N_2 in exhaust gas on a dry basis
- B_{CO} - percent by volume of CO in exhaust gas on a dry basis
- MC - percent by volume of water vapor in exhaust gas
- M_s - actual molecular weight of exhaust gas
- P_s - absolute pressure of exhaust gas, IN.HG
- P_g - static pressure of exhaust gas, IN.WC
- P_b - absolute barometric pressure, IN.HG
- $\bar{t}_s$ - average exhaust gas temperature from preliminary determination or point gas temperature, $^{\circ}F$
- Q_s - cyclone flow rate at actual (or stack) conditions, ACFM

$Q_{s(std)}$ = cyclone flow rate at dry standard conditions, DSCFM
 ΔH = pressure drop across calibrated orifice, IN.WC
 ΔH_c = orifice coefficient or pressure drop across calibrated orifice @ 0.75 DSCFM, IN.WC
 t_d = temperature of dry test meter, °F
 ΔP^{H201A} = velocity pressure of gas stream as measured with S-type pitot attached to cyclone, IN.WC
 ΔP^{H2} = velocity pressure of gas stream as measured with S-type pitot tube as per EPA Method 2 (preliminary traverse), IN.WC
 C_p^{H201A} = pitot tube coefficient of S-type pitot tube attached to cyclone, dimensionless
 C_p^{H2} = pitot tube coefficient of S-type pitot tube used in preliminary traverse, dimensionless
 Δt_n = dwell time at traverse point n, where n = 2, 3, ..., 12, minutes
 Δt_1 = dwell time at the first sampling point, minutes
 $\bar{t}_g$ = average stack gas temperature during test run, °F
 θ = total run time, minutes
 $V_{s(std)}$ = total dry volume of gas sampled, DSCF
 V_f = final volume of water in sampling train condenser system, ml
 V_i = initial volume of water in sampling train condenser system, ml
 $\bar{t}_d$ = average temperature of dry test meter during run, °F
 γ = dry test meter coefficient, dimensionless
 $\overline{\Delta H}$ = average pressure drop across the calibrated orifice in the sampling train during the run, IN.WC
 V_d = volume of dry gas sampled as measured by the dry test meter at meter conditions, CF
 D_{50} = actual or achieved 50% cutpoint for a given run of the device or cyclone used to remove or skim off those particles with aerodynamic equivalent diameters greater than or equal to 10 microns, microns

CALCULATION EQUATIONS

METHOD 10

$$\text{CO-PPM-DRY} = \text{CO}_{\text{CO}_2\text{-free,dry,avg}} (1 - \text{CO}_{2,d}/100)$$

$$\text{CO-PPM-WET} = \text{CO-PPM-DRY} (1 - \text{MC}/100)$$

$$\text{GR/DSCF} = 5.0885 \times 10^{-4} (\text{CO-PPM-DRY})$$

$$\text{mg/dscm} = 1.165 (\text{CO-PPM-DRY})$$

$$\dot{m} = 8.5714 \times 10^{-3} (\text{GR/DSCF})(Q_{s,d})$$

$$E = \frac{2.9857 \times 10^{-3} F_d (\text{GR/DSCF})}{20.9 - O_{2,d}}$$

Where

$\text{CO}_{\text{CO}_2\text{-free,dry,avg}}$ = average of two determinations of carbon monoxide on a dry, CO_2 -free integrated flue gas sample reported in ppm by volume

$\text{CO}_{2,d}$ = carbon dioxide concentration of flue gas on a dry percent by volume basis

$O_{2,d}$ = oxygen concentration of flue gas on a dry percent by volume basis

MC	= moisture content of flue gas on a percent by volume basis
CO-PPM-DRY	= carbon monoxide concentration in ppm by volume on a dry basis
CO-PPM-WET	= carbon monoxide concentration in ppm by volume on a wet or actual basis
GR/DSCF	= concentration of carbon monoxide in flue gas on a grains per dry standard cubic foot basis (68 °F, 29.92 IN.HG.)
mg/dscm	= concentration of carbon monoxide in flue gas on a milligrams per dry standard cubic meter basis (60 °F, 29.92 IN.HG.)
m	= emission or mass rate of carbon monoxide on a LB/HR basis
Q _{s,d}	= volumetric flow rate of flue gas in dry standard cubic feet per minute
E	= emission factor of carbon monoxide in pounds of carbon monoxide emitted per million BTU heat input (LB/MMBTU)
F _d	= F-Factor of respective fuel in dry standard cubic feet of exhaust gas at 0% oxygen per million BTU of heat input (DSCF/MMBTU)

CALCULATION EQUATIONS

Chromotropic Acid Method for Formaldehyde

$$m_t = \frac{m_a \times V_{\text{soln}}}{V_{\text{aliq}}}$$

where m_t = mass of formaldehyde in total sample in ug
 m_a = mass of formaldehyde in aliquot in ug
 V_{soln} = volume of total sample in cc (500 cc normally)
 V_{aliq} = volume of aliquot taken for analysis in cc

$$\text{PPM} \cdot \text{DRY} = \frac{.0283 m_t}{V_{\text{std}}}$$

$$\text{PPM} \cdot \text{WET} = \text{PPM DRY} (1 - \text{MC}/100)$$

$$\text{GR/DSCF} = 5.45 \times 10^{-4} (\text{PPM} \cdot \text{DRY})$$

$$\text{mg/dscm} = 1.249 (\text{PPM} \cdot \text{DRY})$$

$$\dot{m} = 8.5714 \times 10^{-3} (\text{GR/DSCF}) (Q_{s,d})$$

where $\text{PPM} \cdot \text{DRY}$ = concentration of formaldehyde in parts per million by volume on a dry basis
 $\text{PPM} \cdot \text{WET}$ = concentration of formaldehyde in parts per million by volume on an actual or wet basis
 MC = moisture content of gas on a percent by volume basis
 GR/DSCF = concentration of formaldehyde in gas on a grains per dry standard cubic foot basis (68°F, 29.92 IN.HG.)
 m = emission or mass rate of formaldehyde in pounds per hour (LB/HR)

Method 25A

Total Gaseous Organics Calculation Equations

$$\text{GR C/SCF} = 2.180 \times 10^{-4} (\text{ppm,w})$$

$$\text{GR C/DSCF} = 2.180 \times 10^{-4} (\text{ppm,w}) / (1 - \text{MC}/100)$$

$$\text{LB C/HR} = 8.5714 \times 10^{-3} (\text{GR/DSCF}) (\text{DSCFM})$$

where:

GR C/SCF = grains of total gaseous organics as carbon per actual (wet) standard cubic foot

GR C/DSCF = grains of total gaseous organics as carbon per dry standard cubic foot

LB C/HR = pounds of total gaseous organics as carbon emitted per hour

Note 1: The Ratfisch Model RS55 Heated FID Analyzer as normally operated with a heated filter, heated sample line and heated detector oven gives ppm,w.

Note 2: ppm,C = ppm as carbon = ppm methane



EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job LOUISIANA PACIFIC
Operator D. BRENNAN

Date 3/23/92
Module No. 3

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.85 in. Hg. $\uparrow =$.9991 ΔH_0 1.90 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	'984.00'		
2.5	985.85	68	63
5.0	987.68	70	64
7.5	989.53	71	65
10	991.363	73	66
	$V_m = 7.363$	Avg (t_m) = <u>67.5</u> °F	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\uparrow V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{(.9991)(7.363)} \left[\frac{(67.5 + 460)}{(29.85)} \right]^{0.5}$$

$$Y_{en} = \underline{1.0206}$$

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432R

EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job LOUISIANA PACIFIC (CORRIGAN, TX.)

Date 3/26/92

Operator D. BRENNAN

Module No. 3

Instructions: Operate the control module at a flow rate equal to ΔH_e for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.82 in. Hg. $\tau =$.9991 ΔH_e 1.90 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(275.50)		
2.5	277.36	64	57
5.0	279.23	65	58
7.5	281.08	67	59
10	282.928	68	60
	$V_m = 7.428$	Avg (t_m) = 62.25 °F	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{(7.428)(.9991)} \left[\frac{(62.25) + 460}{(29.82)} \right]^{0.5}$$

$$Y_{en} = \underline{1.0071}$$

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job LOUISIANA PACIFIC (CONRIGAN TX.)

Date 3/27/92

Operator D. BRENNAN

Module No. 3

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.86 in. Hg. $\uparrow =$.9991 ΔH_0 1.90 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(506.00)		
2.5	507.88	80	72
5.0	509.75	81	73
7.5	511.63	81	73
10	513.485	82	74
	$V_m = 7.485$	Avg (t_m) = °F	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\uparrow V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{(.9991)(7.485)} \left[\frac{\frac{537.0}{(77.0) + 460}}{(29.86)} \right]^{0.5}$$

$$Y_{en} = \underline{1.013}$$

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432R

EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job LOUISIANA PACIFIC CORRIDOR, TX.

Date 3/28/92

Operator D. BRENNAN

Module No. 3

Instructions: Operate the control module at a flow rate equal to ΔH for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.83 in. Hg. $\tau =$.9991 ΔH 1.90 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(814.00)		
2.5	815.90	82	75
5.0	817.79	82	75
7.5	819.68	83	75
10	821.561	83	76
	$V_m = 7.561$	Avg (t_m) = °F	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{(.9991)(7.561)} \left[\frac{538.875}{(78.875) + 460} \right]^{0.5}$$

$$Y_{en} = \underline{1.0049}$$

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job LP / Corrigan, TX

Date 3-23-92

Operator M. Kuehler

Module No. 4

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.85 in. Hg. $\tau = \underline{1.0010}$ ΔH_0 1.75 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
0.0	(709.80)	52	55
2.5	711.64	57	55
5.0	713.48	58	56
7.5	715.42	61	57
10	717.18	63	58
12.5	$V_m = 7.38$	Avg (t_m) = 58.13 °F	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{(1.0010)(7.38)} \left[\frac{(58.13) + 460}{(29.85)} \right]^{0.5}$$

$$Y_{en} = \underline{1.007}$$

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job Louisiana Pacific / Corrigan, TX

Date 3-25-92

Operator M. Kaehler

Module No. 4

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.77 in. Hg. $\tau =$ 1.0010 ΔH_0 1.75 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
1.0	(920.00)	61.63	
2.5	921.83	63	62
5.0	923.68	65	63
7.5	925.57	67	64
10	927.45	68	65
11.0	$V_m = 2.45$	Avg (t _m) = 64.63 °F	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{(1.0010)(2.45)} \left[\frac{(64.63) + 460}{(29.77)} \right]^{0.5}$$

$$Y_{en} = \underline{1.005}$$

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job Louisiana Pacific / Corrigan, TX

Date 3-26-92

Operator Mike Kuebler

Module No. 4

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.92 in. Hg. $\uparrow =$ 1.0010 ΔH_0 1.75 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
<u>1.0</u>	<u>(146.10)</u>	<u>55</u>	<u>55</u>
<u>2.5</u>	<u>147.97</u>	<u>55</u>	<u>55</u>
<u>5.0</u>	<u>149.85</u>	<u>57</u>	<u>55</u>
<u>7.5</u>	<u>151.69</u>	<u>59</u>	<u>56</u>
<u>10</u>	<u>153.56</u>	<u>60</u>	<u>57</u>
<u>1.0</u>	$V_m = 7.46$	$Avg(t_m) = 56.75^\circ F$	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\uparrow V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{(1.0010)(7.46)} \left[\frac{(56.75) + 460}{(29.92)} \right]^{0.5}$$

$$Y_{en} = \underline{0.996}$$

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job Louisiana Pacific / Corrigan, TX

Date 3-27-92

Operator M. Kaehler

Module No. 4

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.86 in. Hg. $\tau =$ 1.0010 ΔH_0 1.75 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
<u>2.5</u>	<u>275.20</u>	<u>71</u>	<u>70</u>
<u>5.0</u>	<u>277.11</u>	<u>72</u>	<u>71</u>
<u>7.5</u>	<u>279.02</u>	<u>74</u>	<u>71</u>
<u>10</u>	<u>280.90</u>	<u>76</u>	<u>72</u>
	$V_m = 7.63$	Avg (t_m) = <u>72.13</u> °F	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{(1.0010)(7.63)} \left[\frac{(72.13) + 460}{(29.86)} \right]^{0.5}$$

$$Y_{en} = \underline{.987}$$

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job Louisiana Pacific / Corrigan, TX

Date 3-28-92

Operator m. Kaehler

Module No. 4

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.83 in. Hg. $\tau = \underline{1.0010}$ ΔH_0 1.75 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(638.80)		
2.5	580.71	75	75
5.0	592.62	76	76
7.5	594.53	78	77
10	596.47	80	77
	$V_m =$	$\text{Avg}(t_m) =$ °F	

Calculate Y_{en} as follows:

$$Y_{en} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{en} = \frac{1.786}{() ()} \left[\frac{() + 460}{()} \right]^{0.5}$$

$Y_{en} =$ _____

If Y_{en} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

Interpoll Laboratories, Inc.
(612) 786-6020

Meter Box Calibration and Usage Status

Date of Report: April 17, 1992

Meter Box No. : 3 (Rockwell Dry Test Meter Serial No. 712852)

Date of Last Calibration: March 18, 1992

Calibration Technician: D. Brennan

Wet Test Meter No.: American Meter AL-20

Date of Use	Report No.	Initial Meter Reading	Final Meter Reading	Volume/Job (cu. ft.)	Total Volume* (cu. ft.)
March 24, 1992	2-3532	984.00	2043.42	1059.42	1059.42

* Total volume through meter since last calibration.

Interpoll Laboratories, Inc.
(612) 786-6020

Meter Box Calibration and Usage Status

Date of Report: April 17, 1992

Meter Box No. : 4 (Rockwell Dry Test Meter Serial No. 964553)

Date of Last Calibration: March 17, 1992

Calibration Technician: D. Brennan

Wet Test Meter No.: American Meter AL-20

Date of Use	Report No.	Initial Meter Reading	Final Meter Reading	Volume/Job (cu. ft.)	Total Volume* (cu. ft.)
March 24, 1992	2-3532	709.80	1877.54	1167.74	1167.74

* Total volume through meter since last calibration.

3/18/92

8. 29.21

Control Module No.

Serial No. DTM 717 852

EPA METHOD 5

Wat Test Water No. AL-20

Technician D. GREENMAN

11/11

Positive leak check performed by D. BENNAN
Water was in tolerance

Water was not in tolerance ☒: readjusted linkage

Water was not in tolerance ☒; changed dry test meters

Approved by K. Daniel Dege Date 3/18/92

* Based on AL-20 wet test meter calibration in Nov. 1991 against Bell Prover (NBS Traceable) - Carl Poe Co.

S0102RR 11/91

Bar. Press. 29.21 in. Hg

INTERPOLL LABORATORIES, INC.
METER CALIBRATION SHEET

EPA METHOD 5

Control Module No. _____

Serial No. DTM 964 553

Wet Test Meter No.

Technician D. BERNARD

[illegible]

Positive leak check performed by D. BRENNAN
Water was in tolerance

Motor was not in tolerance ☐; readjusted linkage

Heter was not in tolerance ☒: changed dry test waters

Approved by Daniff R. Dye Date 3/17/92

* Based on AL-20 wet test meter calibration in Nov. 1991 against Bell Prover (NBS Traceable) - Carl Poe Co.

S0102RR 11/91

DIFFERENTIAL PRESSURE AND PROOF CALIBRATION CURVES

WET TEST METER

PULSATON RANGE

DIFFERENTIAL INCHES H2O

.30

.20

.10

0

Calibrated with a 10 ft. American Bell Prover, Serial No. 3157. Traceable to the Bureau of Standards. Reference No. 5249068, PI-TAPE.

AL-20 American Wet Test Meter
Serial No. p-717

Stainless Steel w/Removable Back
Calibrated w/Saturated Air
Water Temp. 74° F.

Air Temp. 74° F.

Inlet Pressure 2" H2O Constant

Calibration Rate: 60 CFH Per/Hr.

Capacity Rate: 120 CFH Per/Hr.

Restricted Outlet for Rate Deviation

PROOF

101

%

100

99

CORRECT VOLUME = INDEX READING x PROOF ÷ 100

120

100

80

60

40

20

DAVID BANKS

FLOW RATE - CUBIC FEET OF AIR PER HOUR

12 292

November, 1991

20 Squares to the Inch

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 03-27-92
Technician: M. Kaehler

Nozzle : Glass

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.239
2	.239
3	.239
Average:	.239

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 03-24-92

Nozzle : Glass

Technician: M. Kaehler

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.188
2	.188
3	.187
Average:	.188

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 03-25-92
Technician: M. Kaehler

Nozzle Number 3-3

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.184
2	.183
3	.182
Average:	.183

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 03-24-92

Nozzle Number 8-3

Technician: M. Kaehler

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.181
2	.180
3	.181
Average:	.181

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 03-27-92
Technician: D. Brennan

Nozzle Number 8-4

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.241
2	.241
3	.240
Average:	.241

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 03-25-92

Nozzle PM1-1

Technician: D. Brennan

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.131
2	.131
3	.131
Average:	.131

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 03-24-92

Nozzle : PM1-2

Technician: D. Brennan

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.150
2	.150
3	.150
Average:	.150

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 03-26-92

Nozzle PM1-2

Technician: D. Brennan

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.130
2	.131
3	.130
Average:	.130

Interpoll Laboratories, Inc.

**Temperature Measurement Device
Calibration Sheet**

Unit under test:

Vendor Atkins
 Model Model # 39658-K Serial Number PDT #3
 Range — 1999 °F Thermocouple Type K
 Date of Calibration 3/9/91 Technician D. van Hoever

Method of Calibration:

- ☐ Comparison against ASTM mercury in glass thermometer using a thermostatted and insulated aluminum block designed to provide uniform temperature. The temperature is adjusted by adjusting the voltage on the block heater cartridge.
- ☒ Omega Model CL-300 Type K Thermocouple Simulator which provides 22 precise temperature equivalent millivolt signals. The CL-300 is cold junction compensated. Calibration accuracy is $\pm 0.1\%$ of span (2100 °F) ± 1 degree (for negative temperatures add ± 2 degrees. The CL-300 simulates exactly the millivoltage of a Type K thermocouple at the indicated temperature.

Desired Temp (°F) Nominal	Temperature of Standard or Simulated Temp (°F)	Response of Unit Under Test (°F)	Deviation	
			Δt (°F)	(%)
0	0	-4	4	.87
100	100	43.5	6.5	1.16
200	200	195.8	4.2	.64
300	300	294	6	.79
400	400	390	10	1.16
500	500	489	11	1.14
600	600	591	9	.85
700	700	690	10	.86
800	800	794	6	.48
900	900	895	5	.37
1000	1000	999	1	.07
1100	1100	1100	—	—
1200	1200	1205	5	.30
1300	1300	1304	4	.23
1400	1400	1407	7	.38
1500	1500	1502	2	.10
1600	1600	1602	2	.10
1700	1700	1693	5	.33
1800	1800	1791	9	.40
1900	1900	1881	19	.80
2000	2000	1974	26	1.06
2100				
		Averages:		.57

OF = off scale response by unit under test (°F)
 % dev = $100 \Delta t / (460 + t)$



Unit in tolerance
 Unit was not in tolerance; recalibrated - See new calibration sheet.

Interpoll Laboratories, Inc.

Temperature Measurement Device
Calibration Sheet

Unit under test:

Vendor Beckman Industrial
Model HD 110 T Serial Number PDT-19
Range 0-2000 °F Thermocouple Type K
Date of Calibration 3-20-94 Technician Mark Bachler

Method of Calibration:

- ☐ Comparison against ASTM mercury in glass thermometer using a thermostatted and insulated aluminum block designed to provide uniform temperature. The temperature is adjusted by adjusting the voltage on the block heater cartridge.
- ☒ Omega Model CL-300 Type K Thermocouple Simulator which provides 22 precise temperature equivalent millivolt signals. The CL-300 is cold junction compensated. Calibration accuracy is $\pm 0.1\%$ of span (2100°F) ± 1 degree (for negative temperatures add ± 2 degrees. The CL-300 simulates exactly the millivoltage of a Type K thermocouple at the indicated temperature.

Desired Temp (°F) Nominal	Temperature of Standard or Simulated Temp (°F)	Response of Unit Under Test (°F)	Deviation	
			Δt (°F)	(%)
0	0	-001	1	.22
100	100	96	4	.71
200	200	198	2	.30
300	300	297	3	.39
400	400	394	6	.70
500	500	494	6	.63
600	600	596	6	.57
700	700	697	3	.26
800	800	802	2	.16
900	900	904	4	.29
1000	1000	1009	9	.62
1100	1100	1113	13	.83
1200	1200	1219	19	1.14
1300	1300	1319	19	1.08
1400	1400	1424	24	1.29
1500	1500	1522	22	1.12
1600	1600	1623	23	1.12
1700	1700	1718	18	.83
1800	1800	1816	16	.71
1900	1900	1909	9	.39
2000				
2100				
Averages:			10.45	0.67

OF = off scale response by unit under test (°F)
% dev = $100 \Delta t / (460 + t)$

- ☒ Unit in tolerance
☐ Unit was not in tolerance; recalibrated - See new calibration sheet.

S-433

Interpoll Laboratories, Inc.

Temperature Measurement Device
Calibration Sheet

Unit under test:

Vendor Beckman Industrial
Model HD110 T Serial Number #23
Range 0 - 1999 °F Thermocouple Type K
Date of Calibration 1/24/92 Technician Duane Van Hoever

Method of Calibration:

- ☐ Comparison against ASTM mercury in glass thermometer using a thermostatted and insulated aluminum block designed to provide uniform temperature. The temperature is adjusted by adjusting the voltage on the block heater cartridge.
- ☒ Omega Model CL-300 Type K Thermocouple Simulator which provides 22 precise temperature equivalent millivolt signals. The CL-300 is cold junction compensated. Calibration accuracy is ± 0.15 of span (2100 °F) ± 1 degree (for negative temperatures add ± 2 degrees. The CL-300 simulates exactly the millivoltage of a Type K thermocouple at the indicated temperature.

Desired Temp (°F) Nominal	Temperature of Standard or Simulated Temp (°F)	Response of Unit Under Test (°F)	Deviation	
			Δt (°F)	(%)
0	0	0	0	0
100	100	97	3	.53
200	200	200	0	0
300	300	299	1	.13
400	400	396	4	.46
500	500	495	5	.52
600	600	598	2	.18
700	700	699	1	.08
800	800	803	3	.24
900	900	906	6	.44
1000	1000	1011	11	.75
1100	1100	1114	14	.89
1200	1200	1220	20	1.2
1300	1300	1321	21	1.19
1400	1400	1426	26	1.39
1500	1500	1523	23	1.17
1600	1600	1625	25	1.21
1700	1700	1720	20	.92
1800	1800	1818	18	.90
1900	1900	1911	11	.46
2000	—	—	—	—
2100	—	—	—	—
		Averages:		.62

OF = off scale response by unit under test (°F)
% dev = $100 \Delta t / (450 + t)$

- ☒ Unit in tolerance
☐ Unit was not in tolerance; recalibrated - See new calibration sheet.

S-Type Pitot Tube Inspection SheetPitot No. 24-4Pitot tube dimensions:

1. External tubing diameter (D_t) .316 IN.
2. Base to Side A opening plane (P_A) .460 IN.
3. Base to Side B opening plane (P_B) .462 IN.

Alignment:

4. $\alpha_1 < 10^\circ$ 0
5. $\alpha_2 < 10^\circ$ 0
6. $B_1 < 5^\circ$ 0
7. $B_2 < 5^\circ$ 1
8. $Z < .125"$.02
9. $W < .0625"$.01

Distance from Pitot to Probe Components:

10. Pitot to 0.500 IN. nozzle .760 IN.
11. Pitot to probe sheath 3.00 IN.
12. Pitot to thermocouple (parallel to probe) 3.00 IN.
13. Pitot to thermocouple (perpendicular to probe) .761 IN.

☒ Meets all EPA design criteria thus $C_p = 0.84$

☐ Does not meet EPA design criteria - thus calibrate in wind tunnel
 $C_p =$ _____

Date of Inspection:

3-2-92

Inspected by:

E. Trawbridge

S-Type Pitot Tube Inspection SheetPitot No. 6-29Pitot tube dimensions:

1. External tubing diameter (D_t) .316 IN.
2. Base to Side A opening plane (P_A) .462 IN.
3. Base to Side B opening plane (P_B) .462 IN.

Alignment:

4. $\alpha_1 < 10^\circ$ 0
5. $\alpha_2 < 10^\circ$ 0
6. $B_1 < 5^\circ$ 1
7. $B_2 < 5^\circ$ 1
8. $Z < .125"$.02
9. $W < .0625"$.02

Distance from Pitot to Probe Components:

10. Pitot to 0.500 IN. nozzle .762 IN.
11. Pitot to probe sheath 3.00 IN.
12. Pitot to thermocouple (parallel to probe) 3.00 IN.
13. Pitot to thermocouple (perpendicular to probe) .763 IN.

Meets all EPA design criteria thus $C_p = 0.84$ Does not meet EPA design criteria - thus calibrate in wind tunnel
 $C_p =$ _____

Date of Inspection:

Inspected by:

2-29-92G. T. White

CFR Title 40 Part 60 Appendix A Method 2

S-Type Pitot Tube Inspection SheetPitot No. 4-29Pitot tube dimensions:

1. External tubing diameter (D_t) .316 IN.
2. Base to Side A opening plane (P_A) .463 IN.
3. Base to Side B opening plane (P_B) .462 IN.

Alignment:

4. $\alpha_1 < 10^\circ$ 0
5. $\alpha_2 < 10^\circ$ 0
6. $B_1 < 5^\circ$ 2
7. $B_2 < 5^\circ$ 1
8. $Z < .125"$.02
9. $W < .0625"$.01

Distance from Pitot to Probe Components:

10. Pitot to 0.500 IN. nozzle .760 IN.
11. Pitot to probe sheath 3.00 IN.
12. Pitot to thermocouple (parallel to probe) 3.00 IN.
13. Pitot to thermocouple (perpendicular to probe) .760 IN.

Meets all EPA design criteria thus $C_p = 0.84$ Does not meet EPA design criteria - thus calibrate in wind tunnel
 $C_p =$ _____

Date of Inspection:

2-29-92

Inspected by:

E. Trawbridge

INTERPOLL LABORATORIES

(612)786-6020

Stack Sampling Department - QA
Aneroid Barometer Calibration Sheet

Date 11/14/91
Technician DUKE BRENDAN
Mercury Column Barometer No. LAP
Aneroid Barometer No. 90222001 (Duke's)

Actual Mercury Barometer Read	Ambient Temp.	Temperature Correction Factor	Adjusted Mercury Barometer Read	Initial Aneroid Barometer Read	Difference (P _{ba} -P _{bm})
29.47	69°	-108	29.361	29.37	-.009

Has this barometer shown any consistent problems with calibration? Yes/No If
yes, explain. _____

Has problem been alleviated? Yes/No. How? _____

*Note

Aneroid barometers will be calibrated periodically against a mercury column barometer. The aneroid barometer to be calibrated should be placed in close proximity to the mercury barometer and left to equilibrate for 20-30 minutes before calibrating. Aneroid barometer will be calibrated to the adjusted mercury barometer readings.

S-312

INTERPOLL LABORATORIES
(612)786-6020
Stack Sampling Department - QA
Aneroid Barometer Calibration Sheet

Date 3-20-92
Technician Mark Kaehler
Mercury Column Barometer No. Lab 1
Aneroid Barometer No. 560815

Actual Mercury Barometer Read	Ambient Temp.	Temperature Correction Factor	Adjusted Mercury Barometer Read	Initial Aneroid Barometer Read	Difference (P _{ba} -P _{bm})
29.260	76	.126	29.134	29.150	.016

Has this barometer shown any consistent problems with calibration? Yes/No. If yes, explain. _____

Has problem been alleviated? Yes/No. How? _____

***Note**

Aneroid barometers will be calibrated periodically against a mercury column barometer. The aneroid barometer to be calibrated should be placed in close proximity to the mercury barometer and left to equilibrate for 20-30 minutes before calibrating. Aneroid barometer will be calibrated to the adjusted mercury barometer readings.

S-312

mead

Comer

Lupin. Hall - White's Capetani

CORE = 11698

FACE = 14057

SQUARE
DEAL

one of highest months

$$\text{dryer } \frac{\text{lbs}}{\text{hr.}} = \frac{\text{lbs(FP)}/\text{hr.}}{1-.15}$$

$$\frac{14 \times 10^6 \text{ ft}^3/\text{mo.} \times .03125 \text{ ft}^3 \times \frac{42 \text{ lbs}}{\text{ft}^3}}{744 \text{ hrs}/\text{mo.}} = 0.85$$

$$= 29,055 \frac{\text{lbs}}{\text{hr.}} \text{ (3 drums)}$$

$$= 9,685 \frac{\text{lbs}}{\text{hr.}} \text{ (1 drum)}$$

CLASS PROGRAM

28

NAME _____ ADDRESS @ 155 maff/yr. :

SCHOOL _____ CLASS = $\frac{155 \times 10^6 \times .03125 \times 42}{9760 \times .85} = 27,321$ (3 drums)

		PERIOD 1	PERIOD 2	PERIOD 3	PERIOD 4	PERIOD 5	PERIOD 6	PERIOD 7	PERIOD 8
	TIME								
	FROM TO...								
MONDAY	SUBJECT								
	ROOM								
	INSTRUCTOR	La Bunta Inn (409) 634-3351							
TUESDAY	SUBJECT								
	ROOM								
	INSTRUCTOR	Corigan Plant (409) 398-2581							
WEDNESDAY	SUBJECT								
	ROOM								
	INSTRUCTOR	fax → (409) 398-5202							
THURSDAY	SUBJECT								
	ROOM								
	INSTRUCTOR								
FRIDAY	SUBJECT								
	ROOM								
	INSTRUCTOR								
SATURDAY	SUBJECT								
	ROOM								
	INSTRUCTOR								

$$= 9100 \frac{\text{lbs}}{\text{hr}}$$

per dryer
@ 1500
fins/min
loss

fax ←

FOR
AP-42
REF (4)
1005

3/24/9

142

inlet T
lbs/hr

CORE
TACB chucks
face 14/145

Wood
Fuel use
inlet
Wood moisture
OUTLET
moisture

STACK Flow
STACK Temp

hessloads/hr
TFP
lbs/hr.

ft³/day

density

Cycle Time

board Thicken

Resin in FP

Resin used

Wax use

04 1240

3/24/92

Corrigan, TX
Whole Book - Do NOT Release for FOIA Request
Enforcement Sensitive

HISTORICAL BENCHMARKS

	FACE #1 DRYER	FACE #2 T-DRYER	FACE #3 CORE	
inlet T	1050°F	1300	1000	(1990-91 data)
lbs/hr	-	-	12,000	#3 permit limit
(3 dryers)	9,700	9,700	9,700	avg. during high production of 7/91 (14 mft ²)
(1 dryer)	9,100	9,100	9,100	@ 155 mft ² /yr. (15% loss to trim/finch)
	10,300	10,300	10,300	@ 155 mft ² /yr. } with 25% loss to trim/finch
	14,057	11,698	14,057	
WOOD FUEL USE	13,500	13,500	13,500	protocol max, with opacity < 2.0% Based on TACB checklist and 820 hrs. op.
	2.77 tph	3.44 tph	2.77 tph	
inlet wood moisture	46-56%			
OUTLET moisture	dryers 1,3	6-10%		
	dryer 2	4-7%		
STACK FLOW	{ DP 0.64-1.1, 6.14 ft/sec, (1) 62.5 ft/sec. DP 0.49-1.70			
STACK TEMP	{ 205°F (4) 193°F (2) 206°F DP 0.7-2.1			
	PRESS			
press loads/hr.	16.74	(12/90)	12.9	(1/91)
TFP tons/hr.	17.23	(12/90)	13.41	(2/91)
ft ² /day	450,000	(7-15-91)	450,000	(7-8-91)
density	42 lbs/ft ³ ± 2 lbs/ft ³			450 K 18,750 ft ² /hr 400 K 16,700 ft ² /hr
Cycle Time	4-5 min			
board Thickness	1/4, 3/8, 7/16, 15/32			
Resin in FP	1.5% - 2.5% (1)			04 1241
Resin used	2,559,707	lbs/yr. (1988)	1.2%	18.9 lbs/1000 ft ² 7010 lbs/day
Wax used	1,374,704	lbs/yr. (1988)	0.6%	10.1 lbs/1000 ft ² 3800 lbs/day

ft x 42 lbs
x 42 lbs
ft³

(3 dryers)

(1 dryer)

= 27,321
(3 dryers)

9100 lbs
hr

27 dryers

15%
loss

loss

To do

- ^{daily} get production records - last 2 yrs.

daily during test

- get stack test field data sheets daily

→ when was 3rd dryer added? → 1987?
→ when was it permitted?

④ - explain lbs/hr. → tons/yr. calculations
Prosser has will respond

→ 70% resin
loss

J.B. said
2.5%
or less

In life calc. with 114 Submittals
Figures we have look like 15%
This must be on production records

- ✓ photos

- ✓ measure cycle times

→ how ^{and exp} resin use measured? (witness it)

✓ Process flow chart

✓ Telephone

✓ Tour - ^{identify} other sources
Blender
forming line
aspiration system

✓ Estimate fugitive loss (ok to test?)

04 1242

Re Marty Nisumala :

2164 m/fk

Nominal

cycle time $54 \frac{1}{4}$

155 ± 20

% of production


- 3/8

98% 7/16

270

217 sec + 10 sec = 227 sec.

200 sec. } mass plot run



dareen
15/32

I saw it
at 4:45 pm

on 3/25/92
dan

These times
do not
include all
loading/
unloading
and do not
consider variation
which may occur
due to line speed

ns
initially
be 15%
reps

1991 40

04 1243

Names	Pos.	SKT
Mike Weindorfer	MEC	
Frank Oldwies project designer	MEC	
Jimi Boswell	LP	
Marty Neiswander	LP	
John Kernan	LP - PM	
Mark Kachon	Interpell	
Hyde Tidwell	Mgr of sils bee, Corrigan, Cleveland plywood	

Using small dia logs (plantation logs) can't get equipment in forests where large logs are - too wet. Smaller dia logs - can only debark one at a time in each debarker, so volume of wood available is much less than normal.

Running 2 minute dumps to get wafer production
multiply x 30 to get per minute.

04 1244

16.7 lbs
P13

wood fuel density - analyzed 3/24/91
↓ for burner use

fuel
#1
DRYER

inlet T
fuel or
OUTlet T

Moist. in

Moist. OUT

opacity

Wet bot.
speed
fuel rate
DRYER 2

inlet T
OUTlet T
fuel rate
M in

M OUT

opacity

Wet bot
speed (fuel)

DRYER 3

inlet T
OUTlet T
M in

M OUT

opacity
Wet bot.
speed

DRYERS

3/24													3/25			both #1 and #2 delivered to 500 CF from 2:55 PM - 6:00 PM	
fuel	10:55 AM	2 PM	4 PM	5:15	6 PM	7 PM	9 AM	10:45	12	1:50 PM	4:30	6:05					
#1 wood	green	green	green	green	green	green	green	green	green	green	green	green					
DRYER	44 mm or less	oversize															
inlet T	725	725	850	775	800	800	725	800	775	780	700	725					
fuel counter	265933	267302	268567	269218	269678	270240	270700	271117	271570	271946	272304	272654					
OUTlet T	218	215	220	219	221	220	218	212	208	210	209	206					
Moist. in	44.2	46.2	49.54	48.8	51.2	50.6											
Moist. OUT	52.3	50.8		50.4		55											
opacity	7.2-10	7.0-8.4	8-10	7.8-8.0	8.6	9.0-9.2		8.9-9.0	5.2-6.0	28-10	10						
probe of sample																	
in way of CEM								16	19	15	18	12					
Wet bot. speed (feed rate)	287	290	284	277	277	275	240	265	235	265	250	271					
DRYER 2 wood	green																
inlet T	800	825	875	850	850	850	900	860	875	850	850	840					
OUTlet T	230	226	225	234	225	240	247	230	229	228	229	224					
fuel counter	510241																
M in	71.4% high	71.4% high	71.4% high	71.4% high	71.4% high	71.4% high	71.4% high	71.4% high	71.4% high	71.4% high	71.4% high	71.4% high					
M OUT	115 V.	96.5%															
opacity	no CEM on #2 stacks																
Wet bot speed (feed rate)	250	255	260	260	255	255	285	285	280	270	270	270					
DRYER 3 wood																	
inlet T	down to keep from running out of wood																
OUTlet T																	
M in																	
M OUT	Swing dryer can either be face or core																
opacity	10																
Wet bot. speed																	

04 1245

Dry #1 Dump to determine dryer production

11:57 AM

13720 truck full - 2 min dump
13280 truck empty

$$\begin{array}{r} 440 \text{ lbs} \\ \times 30 \\ \hline 13,200 \text{ lbs/hr.} \end{array}$$

4 PM

13780
- 13280

500
x 30

15,000 lbs/hr

Board

cycle tr.

press lbs/

density

T (pr
Resin

Wax

line speed

Board

cycle time

press lbs/

density

T_{fuel}
T_{to} T_{in}

Resin

Wax

line sp

MATERIAL
COMING OUT
OF DRYER

No conveyor along the way, This is a dump
direct from cyclone → same for all dryers
at this plant. Dryer operator cut back

on feed rate compared to 1st 2 dumps
to maintain temperature. Fines also included in
dump, according to process flow chart.

Filene gas damper "open" - to atmosphere

"closed" - goes through #2 dryer

Fuel meter not working for T-O heater (or
for #2, #3 dryers)

use "cores" (no bark) as backup when
belarker on pluck deck run down

Champion getting large dia logs -
Insulated LUP using ^{more} larger logs also as of

2 pm 3/24/92.

04 1246

PRESS

3/24 3/25

2:30pm 4:45 pm 6pm 7pm 9pm 10:30 12N 1:50 PM 4:30

Board 15/32"

cycle time
 Press lds/hr.
 density
 T (press)
 Resin
 Wax
 line speed

5:02
 11
 425
 66.8

was able to speed up
 because dry bins
 were full

Board 7/16"

cycle time
 Press lds/hr.
 density
 T
 Resin
 Wax
 line speed

7:36 7:35
 8+ 8+
 43.3
 414 52.59 51.09 62.6 58.5 57.5 49.7 419 64.5
 174.15
 45.2 45.4 65 45.9 0

nominal
 5

press
 down

This meter doesn't work
 when MEC is counting
 revolutions of auger feed.

8151 46

04 1247

Board $\frac{3}{8}$ "

— cycle time
— press lds/hr.
— density
— T
— Resin
— Wax
— line speed

Board $\frac{1}{4}$ "

— cycle time
— press lds/hr.
— density
— T
— Resin
— Wax
— line speed

TD Fast
Boswell
to estimate
to fast

Par

Core

04 1248

0.

TO test

Boswell
to estimate

to test

~~other room~~

Conveyer from belander

Cooling wheel

$\frac{1}{4}$ "

press vent sampling

re-est. dry avg. Temp. if necessary

Confirm that press vent (now one in middle of building
identified with shut off fan - This one is outside

partial hood of press vent) which is not functioning
will not be turned on during test - is it
permitted?) Shut down due to fire - will not
restart according to Marty N.

Willie
estimated

NEOH, PM

Shut one vent
down and
test the other

test ~~the~~ pollutants

test ~~on~~ estimate - all pollutants

do I run on $\frac{1}{4}$ "
do others on $\frac{1}{16}$ "

Per Stone (at room)

190 vox used on 90 of FP

≤ 290 resin used

Resin room -

Total resin
used as of
2:30pm

~~349 lbs
8 hrs.~~

~~119 lbs
hr.~~

4:30pm - 2:30pm (8 hrs)

1.490 resin on 90 of what comes
across scale

(must be actual 90. Then test
board quality to make sure quality
is ok). Calibrate Meter

Core

Set point

~~14,000 lbs/hr.~~

8-12 hrs down for maintenance every
other wed.

0451 TO

04 1249

Thes run
at 96 fpm
but not for
long. He's seen
it run at 50 well.

65 fpm

7pm
for Joel
(Pneumometer)

7/14

5-6 min

He's ^{fast} line speed

70 fpm

7/16"

425°F - 430°F

operator has seen
Lynn - 4pm
3/24/92

Cycle time ~ 5 min.

ran this last winter
when they had log supply of larger

See logs.

(*)

4/12/88 - } Dryer #3
#1

7/1/88 - #3

12/1/88 - #3

Steve (QA) to
get these
dryer, war,
for reports

and board the times
reports and density

for 1-91 through 3-92
(Steve only keeps for one year,
JBoswell will see if he has copies
of them)

3/25/92

(*)

Thermal oil heat exhausting ~~through~~
to atmosphere, not through #2 dryer.
Valve ^{has not been} ~~not~~ working. They will fix for
tomorrow's run on #2.

Joel said thinner logs started coming
in just around Oct 191 and have
continued ever since

fine

04 1250

430°F

Shift density of bond from press sheets

2# 3/23/92 7/16 42.2 lbs/ft² - 44.6

1# 3/23/92 1/4 49.5 - 55.0

2 - 3/22/92 7/16 41.9 - 45.0

larger

1 - 3/22/92 7/16 41.7 - 44.8

? - 3/21/92 7/16 41.4 - 45.3

8

1 - 3/9/92 1/4 49.6 - 52.4

(*) Corriger permit application 8/9/89
Baswell to figure out why voc ~~44~~ neg 2x lbs/hr.

Reason for not wanting to trim 1/4" - changeover
time - more time down.

stamps
city

gh 3-92
one year
has copies
now

3/23/92

Untrimmed board size 52" x 296"

untrimmed
15392 in²
10768"

can adjust length but not width

(*) trimmed to 48" width

length trim ~ 2" on each end

[recalc. of trim loss

trim loss % = $\frac{9.7}{107} = 9\%$

loss
 $\frac{4 \times 9}{2} =$
 $\frac{36}{2} = 18$
 $4" \times 52" =$
 $208 \times 4 = 832$

for

very

el.

T-O heater now venting through #2 dryer

- have valve tied in position with rope

fire loss ~ 12% per past J. Baswell permit applications

total loss = 9 + 12 = 21%

0

04 1251

04 1251

Fajmi said ok to test stacks 2A and 2B

2 runs on each stack for ^{PM10, PM, HCOH} ~~the~~ pollutants
(both branches go through own set of multiclones
and $\therefore$ will not necessarily have same PM and
PM10) ~~but~~ ^{but} CO, VOC can be done
on one side only if LP wants.

Blue haze outside bldg. in back of press line

Also - sludge pit - metal - grey sludge
coming out - took photo - roof over it
in back of press building

NO residences nearby - all open LP land
where plume impacts - but haze and odor
evident - I was standing in plume as
it impacted

Emissions from Champion International
plant (plywood) next door - 500 yds away -
seemed much greater - got photos of
boiler stack on 3/24/92 which showed
50 - 75% opacity ^{on and off} over several hours

Trough out back also with aerator - foam on
 surface. - drains to creek which goes
 under RR bridge and then toward
 Champion property. - got photo. Metal like (?)
 looks like it ^{traces} present migration to RR bridge

Re: Press fugitives (VOC) - Curtain around
 press only comes down 10' from ceiling. VOCs
 escape around curtain. Guess at how
 → much → maybe add 5-10% more for leakage
 around press and unloader.

Use Latex semi gloss paint to paint
 edges of board (red). Exhausts out side of
 bldg. lots of particulate on nearby ductwork -
 got photo. This is not a constant emission source.
 NOT sure what schedule is.

Fugitives (HCOH particulate?) near blender
 hard to estimate but it's noticeable in odor and
 sight. he also noted this in an inspection report.

Steve (QA) said metal container for wastewater
 was for sanitary waste only. They have permit

04 1253

and sample. Aeration pond is for run-off from log storage. They also have permit and sample it. His supervisor is in G.W.

Treatment operator Training school today.
Have had at least one dumping problem
(unspecified pollutant₃).

They lose lots of papers in forming line (don't
use suction to mat as at Clayton) and some
from passing operation.

Dump - 1:39 pm

#2 Inq. Test

13 722

13280

486

30

14, 400

$$\begin{array}{r} 3 \overline{) 25} \end{array}$$

(*) Real moist wafers going to dryer - Nugent/Branden felt them. Much more moist than those at Silsbee (really damp)

Damp 6343 gm

#2 dryer

13760

13220

$$540 \times 30 = 16,200$$

465

ww

04 1254

$$\frac{.3}{25}$$

$3/24 \rightarrow 7/16$ "production" 319, 872 #2

$\frac{3}{8}$ " production would have been $\left(\frac{7/16}{3/8}\right) \times 319,872 = 373,183$

used $3/8"$ basis.

7/10
as

0524

DRYER
TRASH POT ??

Average dryer dumps, dryer #1 3/24/92: (all 7/16" board)

10:52 am 460 lbs $\times 30 = 13,800$ lbs/hr

11:52 440 = 13,200

12:53 pm 460 = 13,800

1:50 400 = 12,000

2:52 500 = 15,000

3:56 500 = 15,000

4:47 520 = 15,600

5:46 500 = 15,000

6:54 pm 460 = 13,800

7:48 500 = 15,000

average 14,220 lbs/hr.

On This day They ran 319,872 ft² on ^{7/16"} basis,
according to Resin/box use / production sheets.

used ^{3/8"} basis
to dryer $\frac{\text{lbs}}{\text{hr.}} = \frac{319,873 \text{ ft}^2 \times 0.03125 \text{ ft} \times 43 \frac{\text{lbs}}{\text{ft}^3}}{24 \text{ hrs.} (1 - 0.25 \text{ loss to fines/trim})}$

"7/16" density throughout day was ~ ^{43.2} ~~43~~ lbs/ft³ during our test
Assume 3/8" density is the same day (roughly 9:30 am - 8:00 pm)

dryer $\frac{\text{lbs}}{\text{hr.}} = 27,859 \frac{\text{lbs}}{\text{hr.}}$ (2 dryers)

1 dryer $\rightarrow 13,930 \frac{\text{lbs}}{\text{hr.}}$ Based on process calculation

04 1255

319,872 = 319,872

(7/16" / 3/8")

3/24 $\rightarrow$ 7/16" production 319,872 ft²

3/8" production used here

exit,

7.

out
some

3 inches

54

I checked with Mike Weinberger of MEC - he said he would expect 10-12 % loss to fines at Corrigan (better than Silsbee due to type of waferizer) but yes, it could be as high as 16% (my guess based on my estimate of 25% loss to fines and fines - and we thought fines is ~ 9%). My 16% makes dryer production based on press look much more like dry production based on dumps.

Jeff Bursell noted Hett reagent holding time had expired by the first day of testing (5 days) - OK to use it if it passes a QC test. Intergall will have it tested and report to Jeff.

Lynn R

1 ~~set~~

set records for p.l. per hour (but several yrs ago)

7/14"

161 p.l. / Shift

73-74 ppm line speed

11/4"

177 p.l. / Shift

80 ppm

did that for 4 days with
no down time

JB

Marty-W

Marty

Steve

3/26/92

04 1256

85

For Interpell

- 1) Get field notes last 2 days
- 2) Get BADC check sheets from MN Lab for Hcott reagent

Comments for Laramie on 3/26:

- 1) HCOH reagent holding time
- 2) Production OK, compression OK
- 3) Need more than copy of requisition to keep working beyond 3/31 - need WA signed by ESD Contracting Officer.

Questions for J. Boswell / Marty / Steve

- JB 1) Moisture at Silsbee vs moisture at Corrigan
- Marty-JB 2) production sq ft on daily sheets
- Marty - 3) resin % - looks low - how calculated - how can I
- Steve (QA) 4) check? wood use figure 1-91 -> pivot (annual not daily)

Questions for MEC:

- 1) Does wafer size affect max throughput through dryer? How, why?
- 2) Moisture - Silsbee vs Corrigan again
- 3) Wood fuel use rate - factors used lbs/rev, etc. (Mike W. didn't have yet)

~~all 3 dryers running on 3/26/92 as day~~

3/26/92

10:30 AM - talked to dryer operators - #3 runs

normally at 290-300 feed rate and 850°F

1st run showed they were running too slow. I told

them to increase feed rate and they did. 94 12:57

Had been low during 1st test. ~~1st~~ Run 2 will

④

be on higher feed rate (temp. will increase as feed rate increases) Set at 295 at 10:35

high temp
concentrations
may be low
for →

{ 2nd run of HCOH
1st run of PM-10
1st run of VOC } on 3/26/92

(Later) → No — Plant mgr. said occasionally ^(John) ~~it~~ ^{#3 dryer} does go higher but during max production months (summer 1991) They looked at records and it was more like 700°F as average.

I looked at the months (Feb 92) and they showed ~~that~~ ^(#3) it averaged more like 800-850°F

John Kiernan said They get in opacity, trouble ~~about~~ above 750°F and that's why overall average for #3 would have been more like 700°F. John said he would run dryer #3 at 750°F which, he feels, is on high side

of average. They have operated #1 and #2 dryers on high side of average also — so this is consistent (if their temp average are accurate).

#1 DRYER
wood
inlet T
outlet T
Moisture OUT
opacity
feed rate
fuel counter
% of high fire rate
#2 DRYER
wood
inlet T
outlet T
Moisture OUT
opacity
feed rate
% of high fire rate
T-0 % high fire rate
T-0 Temp
#3 DRYER
wood
inlet T
outlet T
opacity
Moisture OUT
feed rate
% of high fire rate
opacity (L)
Moisture

04 1258

		DRYERS					
#1 DRYER		3/4 hr 10 min	11:40	3:20	3:45	5:15	
wood		green	slightly drier green	(slightly less green some notes)			
inlet T		675	700	650	675	625	625
outlet T		215	222	216	224	216	218
moisture out		9.6	5.6	6.6	9.4		9.0
opacity		14	24	26	15	09	08
feed rate		250	260	220	220	220	220
fuel counter		258524	289448	290682	291306	292171	292915
% of high fire rate		28.7%	79	68.2	57.7	48.6	
		Met an Varis	a lot	55-100%	70-	might be bad Thermocouple; they're working on it	
#2 DRYER							
wood		green	slightly less green		See above		
inlet T		775	750	875	800	775	775
outlet T		230	236	232	240	237	240
moisture out		5.4	5.0	5.4	7.2		5.2
opacity		X	X	X	X	X	X
feed rate		260	260	260	260	260	260
% of high fire rate		60.7	48.1	98.7	62.5	78.6	47.0
T-O % high fire rate		72.2	73.5	61.4	76.2	74.2	67.2
T-O Temp		491	489	489	488	490	489
#3 DRYER							
wood		green	slightly less green		See above		
inlet T		650	575	750	750	700	650
outlet T		237	227	224	224	221	224
opacity		couldn't operate due to use of test plant for sampling					
moisture out		5.8	5.2	5.6	8.6	6-6.2	8.0
feed rate		262	305	290	290	315	305
% high fire rate		79.9	98%	98.5	94.5	74.6	79.2
opacity (visual by A.S.)			420				
moisture in		51.5	45.6	45.6	42.2	38.6	47.0
HIST		20	51.5	46.8	-55	41.8	44.2

04 1259

04 1259

Interpoll
using one gas at
304 ppm for method 25A VOC
we would like

Method requires two more:
alternative ① 500 ppm propane in air
550 ppm " "

~~600 ppm propane in air cylinders~~

alternative:

② 1 audit gas cylinder around 200 ppm
I told Larami to call Interpoll

dry #3 / 12:15 pm - had to cut back on feed rate and
temp. - wafers getting too dry.

(it's less than 5% moisture - glue won't adhere

properly, burning edges of wafers - hasn't
occurred yet, but could. I told Marty N /

John K to cut back but keep it as high

as possible. Al Barden checked opacity

it was 30-40% - confirmed fears of

Marty N and John K. - we told

them again ^{it was OK} to lower feed rate (and temp).

Al Barden / Al Nugent / Jeff Burdette tried

to figure out why VOCs increased during 2:00-2:30

- we couldn't. Tilet, type of wood stayed same
and moisture, went down slightly.

(290)

Al B. calculated that, at speed belt was moving,

a wafer would take 108 min to go from entry

of wet bin to the exit Mike Warden 1260

but see later
notes - 165/hr.
was the
reason

Board Thru

cycle time

press losses

density

Press Tem

line spe

PRESS

3/24/64
10AM

4PM

2:05

8-

Board Thickness

7/16

7/16

7/16

cycle time

5:19

5:20

press loads/hr

10

11+

11+

density

See

press reports

Press Temp

424

425

424

line speed

55.4

65.1

65.1

04 1261

of MEC said it takes ~ 8 min for a wafer to go through the dryer. Mike estimates it takes ~ 2 hrs. ~~min~~ to go from dryer exit to the forming

Dump Test #3 dryer 3/26/92 3:25 pm
3:36 pm 13 660 lbs
2 min run - 13 240 lbs
 $420 \text{ lbs} \times 30 = 12,600 \frac{\text{lbs}}{\text{hr}}$

VC
150-100 Rem 1
150-100 Rem 2
240-290 Rem 3
-200

	Line speed,	Dump lbs/hr	T
0916 - 1030	260	9000 - 8400	650-700
1135 - 1251	305-290 (1/2)	10,800 - 11,400	700
1400 - 1506	290	12,000 - 12,600	700

VC's seem to correlate best to $\frac{\text{lbs}}{\text{hr}}$

through dryer.

For 3/27 -
 ① - Call Maria to coordinate Sat - where, where? I don't have the key.
 ② - Call Hosta re WA
 ③ - Call Rich D - get H&M usually

⑥ ?
 Cheryl Doctor
 app.

$\frac{\text{lbs}}{\text{hr}}$ and Temp and any other key issues

③ get protocol for Jeff
 ✓ ④ Call Julie
 ✓ ⑤ Tell Yoko

04 1262

dump, dryer #3

6:30pm

3/26/92

13640 lbs

13240 lbs

$$400 \times 30 = 12,000 \text{ lbs/hr.}$$

Inlet Temp of dryer #3 dipped from 3:30 → 4:30pm

750°F → 550°F, Then climbed again

550 → 750°F 4:30 → 6:30pm

(Might have been caused by incoming moisture drop - see ^{MEC} dryer reports which they should send us in stock test report)

4m T
1400 650-700
1400 700
13600 700

where?
rucking.

why

log

04 1263

#2
 Check of production vs dump truck loads to
 calculate dryer lbs/hr. on 3/25/92:

Press

press loads	85	$7/16$	$85 \times 1568 \text{ ft}^2 = 133,280 \text{ ft}^2$
	31	$15/32$	$31 \times 1680 = 52,080$
	106	$7/16$	$106 \times 1568 = 166,208 \text{ ft}^2$
	4	$15/32$	$4 \times 1680 = 6,720$
			29,780
			428,848 \text{ ft}^2
			358,288

$$\left. \begin{aligned} \frac{7/16}{3/8} &= \\ \frac{1/4 \times 1/3}{2} &= \\ \frac{1}{4} &= \\ 1.167 & \end{aligned} \right\}$$

for $3/8$ " basis

$$\begin{aligned} &133,280 \\ &+ 166,208 \\ &299,488 \text{ ft}^2 \times \frac{7/16}{3/8} = 349,602 \end{aligned}$$

$$\begin{aligned} &52,080 \\ &6,720 \\ &\frac{58,800}{58,800} \times \frac{15/32}{3/8} = 73,500 \\ &+ 423,002 \text{ ft}^2 \end{aligned}$$

$$423,002 \times .03125 \text{ ft}^2 \times 43 \frac{\text{lbs}}{\text{ft}^3} = 568,409 \frac{\text{lbs}}{24 \text{ hrs}}$$

$$\text{dryer} \left(\frac{\text{lbs}}{\text{hr}} \right) = \frac{568,409 \text{ lbs}}{1-.25} = 757,878 \frac{\text{lbs}}{24 \text{ hrs}}$$

$$\left. \begin{aligned} \frac{15/32}{3/8} &= \\ \frac{15/32 \times 8}{3} &= \\ \frac{40}{32} &= \\ 1.25 & \end{aligned} \right\}$$

On 3/25/92, all 3 dryers operated but #3 only
 operated for ~ 3 hrs (shift 1) + 6 hrs. = 9 hrs
 total dryers operating = 2.375 dryers

0001 10

04 1264

$$\frac{757,878 \text{ lbs}}{2.375 \text{ days}} = \frac{319,107 \text{ lbs}}{24 \text{ hrs}} \text{ per day}$$

$$= 13,296 \frac{\text{lbs}}{\text{hr.}}$$

Using dump truck Wts:

3
440
440
400
400
480
420
460
540
420
440

$$4440 \times 30 = 133,200 \frac{\text{lbs}}{\text{hr.}}$$

$$\div 10 = 13,320 \frac{\text{lbs}}{\text{hr.}}$$

Good Agreement

04 1265

2. dup

1 for Monday 3/30 - ① get units on log/production
for Donna at Corrigan (tons, pounds
1000 tons, ?)

② Tell Linda C what Arturo and
Garry Phillips need on MZ training

③ Hand in expense report / pick up checks

④ Check Tina to see if Time Sheet arrived

⑤ Call Jeff Burdette re Schedule
funding, New Wave's operating
parameters, old stock tests etc.

⑥ file overtime report

20 $\frac{\text{lbs}}{\text{hr.}}$

04 1266

Summary of Corrigan:

- ① Previously unidentified point sources:
 - blander conveyor line - tested
 - paint booth exhaust - ^{not tested} batch operation ^{water based paint}
- ② Production records appear to be kept on as produced thickness basis instead of 3/8" basis (underestimates production)
- ③ Cycle times we have been given in 114 do not reflect variability possible from adjusting line speed.
- ④ Mass loads during our tests may be less than 114 data because facility (and neighboring plants) had mostly small dia logs which slows their production (debarker only takes one log at a time) drop production could go much higher for same reason
- ⑤ Champion International plywood mill next door had opacity problem on fossil fired boiler through my dates on-site. Also significant emissions ^{04 1267} from other sources - appears worse than Lf.

⑥ Question unanswered - What's variability and range of their resin use? 114 gives higher amount than we saw during our tests and during other records we looked at.

⑦ What's average temp (inlet) on dryers. They ran tests at what they said was high side of average rates. They would not run any higher (reasons - don't run that high due to opacity regulations and due to potential to burn ureters. - ~~operators~~ we should calculate mean, std deviation, range based on last year or so of operation to check their statements.

⑧ They (like Silsbee) also have operated T-O heater ~~continuously~~ while venting directly to atmosphere. They said

Electronic Valve was broken. Had to use
rope during our tests to close ~~it~~ valve
and to ^{exhaust} T-O Through Dye #2.
Had been venting to atmosphere for some time,
but we couldn't determine how long.

(9) Line Speed vs cycle time during our
tests : $\begin{cases} 65 \text{ fpm} = 5 \text{ min } 20 \text{ sec. cycle} \\ 45 \text{ fpm} = 7 \text{ min } 35 \text{ sec. cycle} \end{cases}$
They said they have run at 70-80 but was several yrs ago

(10) possible wastewater permit problems -
but probably not major. Looks like
stormwater runoff from pine is only
effluent unless someone dumps something.
They treat with aeration and put into creek.
They say they have permit. Someone
(State, EPA) should check status.

(11) Question about moisture of incoming vapors -
They were ^{real to the touch} wet here but had same
measured moisture content as the ones at
Silsbee which did not feel wet. Why?

J. Boswell

Actual

3/8" ft²

Corrigen

143,668,000 ft² (3/8" basis)

$$\frac{7/8}{3/8} \times 143,668,000 = 167,660,550$$

42 lbs/ft³

43 ~~lb~~ lbs/ft³

wood used

3.5% resin

2.5% resin + wax

= 128 ft³
1 cord

finer 10% loss


finer + trim 25% loss

2.568 lb VOC / 1000 lb wafers
(or 5.136 lb / ton wafers)

9 lbs / ton wafers



242.73 ton VOC



even accepting the
dead wood argument
~~but using EPA's 10% loss~~
~~which is not correct~~

~~167,660,550~~ ~~72,093,800~~ 225,299,840 lb FP

ms,

168
50
84
68,000

I

$$225,299,840 \text{ lbs} \times .975 = 219,667,340$$

(resin/wax) ^

and

$$231,076,710 \times .87 \times \frac{9}{2000} +$$

1 809 332 900
135 180 000
1 944 512 900

$$231,076,710 \times .13 \times \frac{4.5}{2000}$$

$$= 1,809,332,900 + 135,180,000$$
$$= 1,944,512,900 \text{ lbs}$$
$$= 972256$$

231,076,710 lb (with resin/wax correction)

$$231,076,710 / .75 = 308,102,660 \text{ lb (with trim/finer correction)}$$

70

521 10

04 1271

Wet
wood
portion

$$\frac{154,000 \text{ tons wafers}}{308,102 \text{ lbs} \times .87 \times 5.136 \text{ lb VOC}} \times \frac{2000 \text{ lbs/ton}}{\text{ton wafers}}$$

$$= 344 \text{ tons VOC}$$

Dry
wood
portion

$$\frac{154,000 \text{ tons wafers}}{2060 \text{ lb/ton}} \times .13 \times 2.568 \frac{\text{lb VOC}}{\text{ton wafers}}$$

$$= 26 \text{ tons VOC}$$

total dryer VOC emissions 370 tpy

or, ~~123~~ 123 tpy per dryer

So plant is probably became major in 1986-7 when 3rd dryer was added.

Should have had PSD review for any mods since then (MDE application?, application to increase production to 155MM ft²/yr. ?)

Also - was the switch to OSB from particleboard a major modification acc. by it, must evaluate this as well.

A high-contrast, black and white image of a lined notepad. The word "NOTES" is printed vertically on the left side. The notepad has horizontal ruling lines. Faint, illegible text is visible in the background, possibly from the reverse side or a reflection. The image is heavily textured with noise and grain.


FOR
AP-412
REF (4)
KRB

NOTES

CHEQUE LEAF 97-018652
CITY OF LOS ANGELES
\$500
\$500

1951

04 0553



Don't Talk.

013600 LB 09:45 AM 03/24/92

013100 LB 09:51 AM 03/24/92

2 min Jump 0500
15000 10.0

Driver
No. 1

NOTES

Don't Talk

013500 LB 10:52 AM 03/24/92

013120 LB 10:57 AM 03/24/92

760

NOTES

Don't Talk

013720 LB 11:58 AM 03/24/92

013720 LB 11:58 AM 03/24/92

740

3000

NOTES

013580 LB 12:53 PM 03/24/92

013420 LB 12:57 PM 03/24/92

NOTES

013760 LB 01:50 PM 03/24/92

013350 LB 01:54 PM 03/24/92

NOTES

013800 LB 02:52 PM 03/24/92

013300 LB 02:55 PM 03/24/92

580

Driver
No. 1

04 0554

TES

11-27-80 LE 13-50 PM 03-24-92

11-28-80 LE 04-00 PM 03-24-92

500

15,000

14.00

TES

11-28-80 LE 04-40 PM 03-24-92

11-29-80 LE 12-50 PM 03-24-92

Dinner
No 1

16:51 130

NOTES

11-29-80 LE 13-40 PM 03-24-92

11-30-80 LE 06-00 PM 03-24-92

500

15,000

17.56

04 0555

LOUISIANA-PACIFIC CORPORATION
SOUTHERN DIVISION
WAVERWOOD

$$\frac{7}{16} = .4375 \text{ in}$$

$$= .03646 \text{ ft}$$

Daily Resin and Wax Usage

Date: 3-24-92
Beginning Inventory
Incoming Resin
Total

<u>74 270</u>	lbs.
<u>. 36 000</u>	lbs.
<u>110 270</u>	lbs.

Resin Room:

Bags in Resin Room:

3133 FACE Totalizer

2589 CORE Totalizer

$\frac{111}{93} = 204$ press loads $\times 14$ openings $\times$ press load
This is actually on $\frac{7}{16}$ " basis
Since they were running $\frac{7}{16}$ " all day

Ending Total

24 Hour Usage

Footage for Day $93 + 111$

LBS/24 Hrs
M Feet $\frac{3}{8}$ Basis

Shift 1 6am-6pm
Shift 2 6pm-6am

$$319,872 \text{ ft}^2 \times \frac{7}{16} = 373,183 \left(\frac{3}{8}\right) \text{ ft}^2$$

<u>104 548</u>	lbs.
<u>5 722</u>	lbs.
<u>319 872</u>	ft ² $\frac{3}{8}$ " Basis
<u>17.9</u>	lbs/msf

Wax Room:

(Usage: (Gallons) $\times$ 6.57 = Lbs.)

Beginning Inventory

Incoming Wax

Total

Storage Tank Level

13'9" 7920 Gal 52034 lbs.

<u>55 819</u>	lbs.
<u>-</u>	lbs.
<u>55 819</u>	lbs.

Ending Total

24 Hour Usage

LBS/24 Hrs
M Feet $\frac{3}{8}$ Basis

<u>52 034</u>	lbs.
<u>3 785</u>	lbs.
<u>11.8</u>	lbs/msf

FP $\rightarrow 319,872 \text{ ft}^2 \times .03646 \text{ ft} \times 42.3 \frac{\text{lb}}{\text{ft}^3} = 493,325 \text{ lbs}$

RESIN $\rightarrow \frac{5722 \text{ lbs}}{493,325 \text{ lbs}} \times 100\% = 1.16\%$

WAX $\rightarrow \frac{3785 \text{ lbs}}{493,325 \text{ lbs}} = 0.8\%$

04 0556

DRYER REPORT

DATE: 24 MAR 72

SHIFT: 1

CREW: 1

FOREMAN: J. Wilson

OPERATOR: J. Perkins

#I DRYER

#II DRYER

#III DRYER

TIME	OUT-LET	INLET	CENCO	SPEED	OPAC MON	OUT-LET	INLET	CENCO	SPEED	OUT-LET	INLET	CENCO	SPEED	OPAC MON	KONUS
6:30	START UP					START UP				START UP					
7:00	215	650	7.8	2.72	12/12	230	720	8.8	2.60	245	800	7.8	2.90	0/05	489
7:30	220	550	9.0	2.80	15/15	235	775	7.8	2.70	245	250	7.0	3.20	0/08	489
8:00	220	600	8.0	2.60	0/08	230	725	6.0	2.70	Down					490
8:30	216	700	7.8	2.80	2/08	220	675	5.8	2.70	Down					481
9:00	215	650	8.4	2.90		START UP				Down					489
9:30	215	710	7.2	2.90		230	750	7.0	2.50	Down					486
10:00	215	800	10.0	2.85		230	750	6.0	2.50	Down					490
10:30	215	725	9.0	2.85		230	750	7.0	2.50	Down					489
11:00	220	400	8.8	2.87		236	800	6.0	2.50	Down					489
11:30	220	700	7.8	2.87		225	810	5.8	2.50	Down					489
12:00	220	700	7.6	2.87		225	800	5.8	2.50	Down					488
12:30	220	675	7.0	2.90		230	800	5.0	2.50	Down					489
1:00	220	750	8.4	2.90		230	675	5.6	2.50	Down					489
1:30	215	700	10.0	2.90		230	800	6.4	2.70	Down					489
2:00	215	725	9.0	2.90		230	815	6.8	2.55	Down					489
2:30	215	800	10.0	2.88		230	825	8.0	2.55	Down					489
3:00	220	400	9.4	2.80		230	850	7.6	2.56	Down					489
3:30	220	400	8.0	2.80		230	825	6.0	2.60	Down					489
4:00	220	850	9.4	2.81		235	825	6.0	2.60	Down					489
4:30	220	850	8.0	2.77		235	850	6.2	2.60	Down					489
5:00	220	775	7.8	2.77		235	850	6.0	2.60	Down					489
5:30	220	950	8.6	2.77	0/08	235	875	6.0	2.60	Down					4790
Avg	734					Avg	790			Avg	525				48

04 0557

DRYER REPORT

DATE: 24 March 1992

SHIFT: 1

CREW: 2

FOREMAN: Andy L

OPERATOR: Karen C

#I DRYER

#II DRYER

#III DRYER

TIME	OUT-LET	INLET	CENCO	SPEED	OPAC MON	OUT-LET	INLET	CENCO	SPEED	OUT-LET	INLET	CENCO	SPEED	OPAC MON	KONUS
6:30	220	825	9.0	275	51/51	235	825	8.4	255	DOWN					490
7:00	220	800	9.2	275	49/51	235	840	5.2	255	DOWN					489
7:30	220	891	9.4	275	48/51	235	825	7.2	255	245	650	5.0	260	09/08	489
8:00	220	975	8.4	275	52/52	235	850	7.4	255			5.0	265	09/06	484
8:30	225	900	9.0	275	13/12	235	950	7.0	260			7.0	270	07/07	484
9:00	230	875	8.2	275	15/16	240	850	5.8	260			6.2	270	06/07	491
9:30	230	830	7.6	280	15/16	245	950	5.6	270			6.8	280	07/05	488
10:00	230	830	7.0	265	12/12	250	840	4.0	255			6.0	265	04/05	488
10:30	230	800	8.4	255	08/12	250	800	4.8	255			5.8	260	05/05	488
11:00	270	790	12.2	240	07/06	250	900	3.6	255			6.2	260	09/05	491
11:30	240	725	6.8	240	05/11	250	800	5.0	255	DOWN					489
12:00	240	750	7.2	240	07/08	245	775	5.0	255	DOWN					489
12:30	240	725	6.6	240	09/11	245	810	6.2	255	DOWN					48
1:00	235	750	7.8	250	10/13	240	800	5.4	255	DOWN					489
1:30	235	790	7.0	250	15/13	240	850	5.6	255	255	625	7.0	265	05/05	48
2:00	230	750	7.4	250	19/14	240	850	5.0	255	255	700	8.2	265	06/05	48
2:30	230	725	7.2	250	14/14	240	850	5.8	255	255	700	6.0	265	07/08	490
3:00	230	710	5.6	250	09/12	240	750	5.4	255	255	800	4.8	270	08/07	48
3:30	230	710	8.0	250	11/12	240	775	5.2	255	255	650	5.6	290	06/09	492
4:00	DOWN														487
4:30	Start up														488
5:00	230	725	5.8	230	09/08	240	750	3.4	255	255	600	4.2	250	04/05	487
5:30	230	725	6.6	255	09/10	240	775	5.8	255	255	700	5.8	275	04/05	48

AL 791

AL 815

AL 851



Louisiana-Pacific

ORIENTED STRUCTURAL BOARD

HAVE C6
DATE/SHIFT 3-24-92 - 1
NOMINAL THICKNESS 7/16
TYPE A5

NUMBER OF LOADS 93
STORAGE TANK LEVEL _____
FACE RESIN TOTALIZER _____
CORE RESIN TOTALIZER _____

PRESSLOAD	4	10	21	27	31	37	43	50	64	70	74	81	88						
BOARD	1	1	1	1	1	1	1	1	1	1	1	1	1						
TIME	6:47	7:29	8:43	9:30	10:00	10:47	11:32	12:06	1:14	2:59	3:30	4:23	5:26						
LINE SPD.	60	60	45	45	45	45	45	45	45	45	45	45	45						
SL	145	144	144	145	147	147	149	149	149	151	152	150	151						
CL																			
T.T.P.	159	160	145	104	133	82	114	146	92	95	109	141							
O.T.	220	220	310	330	330	330	330	330	330	325	320	—	320						
O.T.	65	65	—	—	—	—	—	65	65	65	70	—	70						
O.P.	25	25	—	—	—	—	—	25	25	25	20	—	22						
POS. #2	450	450	—	—	—	—	—	450	450	450	450	—	—						
TEMP.	427	427	427	420	421	420	417	415	415	415	415	—	—						
WEIGHT																			
THICKNESS																			
DENSITY	43.2	44.1	42.0	41.9	44.5	42.7	44.3	42.8	41.9	42.0	45.0	43.6	42.5						
M.C. (F/C)																			
M.O.E.																			
M.O.R.																			
I.B.					78														

04 0559

LOUISIANA-PACIFIC CORPORATION
SOUTHERN DIVISION
WAVERWOOD

Daily Resin and Wax Usage

Date: 3-25-92

Beginning Inventory

Incoming Resin

Total

<u>104 548</u>	lbs.
<u>36 000</u>	lbs.
<u>- 140 548</u>	lbs.

Resin Room:

 Bags in Resin Room:

3535 Face Totalizer

2866 Core Totalizer

Ending Total

24 Hour Usage

Footage for Day $85 + 31(\frac{1}{2}) + 106 + 4(\frac{1}{2})$

LBS/24 Hrs

M Feet $\frac{3}{8}$ Basis

<u>134 147</u>	lbs.
<u>6 401</u>	lbs.
<u>355 152</u>	ft ² $\frac{3}{8}$ " Basis
<u>18.0</u>	lbs/msf

Wax Room:

(Usage: (Gallons) X 6.57 = Lbs.)

Beginning Inventory

Incoming Wax

Total

<u>52 034</u>	lbs.
<u>-</u>	lbs.
<u>52 034</u>	lbs.

Storage Tank Level

12'9" 7344 Gal 48 250 lbs.

Ending Total

24 Hour Usage

LBS/24 Hrs

M Feet $\frac{3}{8}$ Basis

<u>48 250</u>	lbs.
<u>3 784</u>	lbs.
<u>10.7</u>	lbs/msf



Louisiana-Pacific


ORIENTED STRUCTURAL BOARD

NAME CB
DATE/SHIFT 3-25-92 - 1
NOMINAL THICKNESS 7/16
TYPE RS

NUMBER OF LOADS 18
STORAGE TANK LEVEL 13
FACE RESIN TOTALIZER
CORE RESIN TOTALIZER

15/32

PRESSLOAD	4	14	23	30	40	49	59	67	73	8	10	26							
BOARD	1	1	1	1	1	1	1	1	1	1	1	1							
TIME	6:35	7:28	8:23	9:00	10:02	11:01	12:05	1:05	1:47	2:17	3:59	5:26							
LINE SPD.	68	65	65	65	50	55	45	45	50	65	65	68							
SL	147	148	150	149	149	148	147	149	151	156	157	158							
CL																			
I.T.P.	140	151	186	140	131	146	115	110	95	150	135	141							
O.I.	210	200	200	—	280	265	310	310	295	220	225	215							
D.T.	55	55	55	—	55	—	—	—	—	40	35	35							
D.P.	29	29	29	—	29	—	—	—	—	35	35	35							
POS. #2	450	450	450	—	450	—	—	—	—	465	465	465							
TEMP.	439	429	429	423	423	419	—	—	—	422	422	425							
WEIGHT																			
THICKNESS																			
DENSITY	42.0	44.3	44.7	43.2	45.3	44.6	41.9	41.5	41.7	42.3	43.2	44.5							
M.C. (F/C)																			
M.O.E.																			
M.O.R.																			
I.B.																			



DRYER REPORT

DATE: 25 MAR 92

SHIFT: 1

CREW: 1

FOREMAN: J. Wilson

OPERATOR: J. Perkins

#I DRYER

#II DRYER

#III DRYER

TIME	OUT-LET	INLET	CENCO	SPEED	OPAC MON	OUT-LET	INLET	CENCO	SPEED	OUT-LET	INLET	CENCO	SPEED	OPAC MON	KONUS
6:30	Down				X	235	825	6.0	2.75	Down				X	489
7:00	START	UP			X	230	800	4.4	2.75	START	UP			X	485
7:30	230	650	7.0	2.40	08/09	230	825	5.0	2.90	Down				X	490
8:00	225	700	7.4	2.40	08/09	230	825	5.8	2.90	Down				X	489
8:30	225	700	7.8	2.40	07/09	230	875	6.6	2.85	START	UP			X	489
9:00	220	700	8.6	2.40	06/06	230	850	6.0	2.85	Down				X	489
9:30	220	725	7.8	2.50	07/07	230	900	6.4	2.85	Down				X	489
10:00	220	700	9.0	2.70	11/11	230	850	6.0	2.85	Down				X	489
10:30	215	750	8.8	2.80	15/15	230	875	6.8	2.85	Down				X	489
11:00	215	800	7.8	2.65	13/12	230	825	6.0	2.80	Down				X	489
11:30	215	775	6.4	2.60	22/17	230	850	5.2	2.80	Down				X	490
12:00	216	750	8.8	2.35	19/24	230	875	5.4	2.80	Down				X	489
12:30	210	750	8.6	2.35	16/17	230	875	5.6	2.80	Down				X	490
1:00	210	775	10.0	2.40	13/12	230	900	5.0	2.88	Down				X	488
1:30	210	800	7.8	2.50	12/12	230	900	6.4	2.70	Down				X	489
2:00	210	775	8.0	2.65	17/16	230	810	6.4	2.70	Down				X	489
2:30	210	700	8.0	2.65	15/14	230	850	6.0	2.70	Down				X	489
3:00	210	775	7.8	2.45	16/17	230	850	5.6	2.70	Down				X	489
3:30	210	775	7.8	2.50	19/21	230	850	6.0	2.70	START	UP			X	487
4:00	210	725	70.0	2.50	15/16	230	850	6.0	2.70	250	800	5.0	3.10	16/14	489
4:30	210	775	9.0	2.30	20/20	230	825	5.6	2.70	250	650	5.6	3.10	08/06	489
5:00	210	700	8.0	2.30	19/20	230	850	6.4	2.70	245	650	6.2	3.10	08/06	489
5:30	210	675	8.8	2.30	14/18	230	875	6.8	2.70	245	800	6.8	3.10	08/08	489
	742					855				725				04 0562H	

DRYER REPORT

DATE: 25 March 92

SHIFT: 2

CREW: 2

FOREMAN: Pring L

OPERATOR: John Snyder

#I DRYER

#II DRYER


#III DRYER

TIME	OUT-LET	INLET	CENCO	SPEED	OPAC MON	OUT-LET	INLET	CENCO	SPEED	OUT-LET	INLET	CENCO	SPEED	OPAC MON	KONL
6:30	210	660	9.6	230	12	230	850	8.2	270	245	575	7.8	250	04/05	489
7:00	210	675	13.4	270	12	230	850	7.4	265	245	625	9.6	250	05/04	488
7:30	210	650	11.0	230	11	230	850	7.4	260	245	500	7.6	250	04/04	489
8:00	210	700	12.0	235	11	230	850	6.8	260	245	600	5.6	250	05/05	489
8:30	215	550	9.4	240	05/06	235	850	6.3	260	245	650	5.6	260	06/06	489
9:00	210	725	7.0	240	08/11	235	800	5.6	260	245	550	5.2	260	08/05	488
9:30	220	660	4.0	240	09/10	235	775	5.2	260	245	650	5.2	260	09/07	489
10:00	220	660	9.0	240	12/12	235	750	5.0	260	245	600	5.2	260	06/07	489
10:30	220	625	7.4	240	07/10	235	725	5.0	260	240	600		260	07/07	489
11:00	225	625	6.8	240	09/11	235	725	4.8	260	DOWN					489
11:30	220	600	7.2	240	08/10	230	750	5.6	260	DOWN					489
12:00	220	625	7.0	240	09/12	230	750	8.2	270	DOWN					488
12:30	Start up					236	725	5.0	270	DOWN					488
1:00	205	600	7.6	240	14/11	230	725	5.6	270	DOWN					489
1:30	225	650	7.2	250	13/18	230	700	5.2	270	DOWN					488
2:00	220	675	7.4	250	12/13	230	740	6.0	270	DOWN					489
2:30	220	675	7.4	250	13/13	230	750	6.8	270	DOWN					489
3:00	220	675	7.6	250	14/14	230	750	5.2	270	DOWN					489
3:30	220	700	8.0	250	11/13	230	750	5.6	270	DOWN					488
4:00	220	675	8.2	250	12/12	230	750	6.2	270	DOWN					489
4:30	220	675	7.6	260	13/15	230	750	5.8	270	START UP					489
5:00	220	675	7.4	260	14/15	230	750	7.2	270	240	750	10.0	260	09/07	489
5:30	220	660	7.6	260	09/14	230	750	6.0	270	240	700	7.0	240	06/07	489

627

773

625



ORIENTED STRUCTURAL BOARD

TYPE

CORE RESIN TOTALIZER

2589

PRESSLOAD	3	10	21	27	41	50	66	99	85	97	103
BOARD	1	2	3	4	5	6	7	8	9	10	1
TIME	6'19"	7'12"	8'34"	8'13"	10'32"	11'27"	12'46"	152	2'39"	4'36"	5'08"
LINE SPD.	45	-	55	60	65	-	-	-	-	-	-
SL											
CL	150	-	-	-	-	148	147	-	-	-	-
T.T.P.	132	125	123	124	165	154	121	130	116	158	157
O.T.	320	-	250	230	205	-	-	-	-	-	-
D.T.	70	-	-	-	50	-	-	-	-	-	-
D.P.	22	-	27	-	29	-	-	-	-	-	-
POS. #2	450	-	-	-	-	-	-	-	-	-	-
TEMP.	74.3	-	-	-	-	-	-	-	-	-	-
WEIGHT	744	740	756	725	773	765	737	724	723	745	730
THICKNESS											
DENSITY	438	433	445	419	455	450	433	421	425	438	429
M.C. (F/C)											
M.O.E.											
M.O.R.											
I.B.					66						

04 0564




Louisiana-Pacific

ORIENTED STRUCTURAL BOARD

NAME CB NUMBER OF LOADS 93
DATE/SHIFT 5-24-92 - 1 STORAGE TANK LEVEL
NOMINAL THICKNESS 7/16 FACE RESIN TOTALIZER
TYPE RS CORE RESIN TOTALIZER

PRESSLOAD	4	10	21	27	31	37	43	50	64	70	74	81	88						
BOARD	1	1	1	1	1	1	1	1	1	1	1	1	1						
TIME	6:47	7:29	8:43	9:30	10:00	10:47	11:32	12:26	2:14	2:59	3:30	4:23	5:26						
LINE SPD.	60	60	45	45	45	45	45	45	45	45	45	45	45						
SL	145	144	144	145	147	147	149	149	149	151	152	150	151						
CL																			
T.T.P.	159	160	145	104	133	82	114	146	92	95	109	141							
O.T.	220	220	310	330	330	330	330	330	330	325	320	-	320						
D.T.	65	65	-	-	-	-	-	65	65	65	70	-	70						
D.P.	25	25	-	-	-	-	-	25	25	25	20	-	22						
POS. #2	450	450	-	-	-	-	-	450	450	450	450	-	-						
TEMP.	427	427	427	420	421	420	417	415	415	415	415	-	-						
WEIGHT																			
THICKNESS																			
DENSITY	432	441	420	419	445	427	443	428	419	420	450	436	425						
M.C. (F/C)																			
M.O.E.																			
M.O.R.																			
I.B.																			

04 0565



ORIENTED STRUCTURAL BOARD

PLATE

DATE/SHIFT 3-24-92-2

NOMINAL THICKNESS

Type

NUMBER OF LOADS

STORAGE TANK LEVEL 13.9"

FACE RESIN TOTALIZER 3133

CORE RESIN TOTALIZER 2589

PRESSLOAD	3	10	21	27	41	50	66	79	87	99	103
BOARD	1	2	3	4	5	6	7	8	9	10	1
TIME	6'19	7'12	8'34	9'13	10'32	11'20	12'40	1'52	2'39	4'36	5'08
LINE SPD.	45	-	55	60	65	-	-	-	-	-	-
SL											
CL	150	-	-	-	-	148	147	-	-	-	-
T.T.P.	132	135	133	124	165	154	121	130	116	158	157
O.T.	320	-	350	232	205	-	-	-	-	-	-
D.T.	70	-	-	-	50	-	-	-	-	-	-
D.P.	22	-	27	-	29	-	-	-	-	-	-
POS. #2	450	-	-	-	-	-	-	-	-	-	-
TEMP.	420	-	-	-	-	-	-	-	-	-	-
WEIGHT	744	740	756	725	777	765	737	724	723	745	730
THICKNESS											
DENSITY	438	435	445	429	455	452	433	421	425	437	429
M.C. (F/C)											
M.O.E.											
M.O.R.											
I.B.					66						

04.0366

Driver #2
Test Dumper

NOTES

13560

013560 LB 11:48 AM 03/25/92

13120

013120 LB 11:52 AM 03/25/92

440

NOTES

13560

013560 LB 10:45 AM 03/25/92

13120

013120 LB 10:47 AM 03/25/92

440

Driver
No 2

NOTES

013120

LB 09:20 AM 03/25/92

013520

LB 09:49 AM 03/25/92

440

~~013120 LB 11:48 AM 03/25/92~~

440

04 0567

Driver #2
Test Dumps

NOTES

013780 LB 02:42 PM 03/25/92

013380 LB 02:46 PM 03/25/92

466

NOTES

013720 LB 01:39 PM 03/25/92

013240 LB 01:43 PM 03/25/92

480

Driver
No. 2

NOTES

013740 LB 12:42 PM 03/25/92

013320 LB 12:44 PM 03/25/92

420

04 0568

NOTES

13920
013820 LB 05:44 PM 03/25/92

13960
013360 LB 05:46 PM 03/25/92

460

13960
013700 LB 06:43 PM 03/25/92

13220
013220 LB 06:45 PM 03/25/92

540

013800 LB 04:43 PM 03/25/92

013380 LB 04:56 PM 03/25/92

420

NOTES

Dryer
#2 Test
Dumps

Dryer
No. 2

013800 LB 03:43 PM 03/25/92

013360 LB 03:45 PM 03/25/92

440

NOTES

04 0569

04 0615

13080m

13440m

19800

1136

26/03/20 10:01 AM

26/03/20 10:01 AM

Left -
Three copies
for you

2.44
1.2

8,400 15/4

1036

027

26/03/20 10:01 AM

13400m

26/03/20 10:01 AM

13680m

NOTES

300

26/03/20 10:01 AM

13320m

26/03/20 10:01 AM

13020m

NOTES

9,400 15/4
5,000 15/4

03/26/92

Dryer #3

04 0616

420

03/26/92 12:20 PM 03/26/92

13240

03/26/92 12:20 PM 03/26/92

13440

NOTES

380

03/26/92 12:20 PM 03/26/92

13000

03/26/92 12:20 PM 03/26/92

13440

NOTES

380

03/26/92 12:20 PM 03/26/92

03/26/92 12:20 PM 03/26/92

NOTES

Driver
No 3

13:35

12:39

Driver #3

04 0617

17:33

400

01:30:30 LB 05:23 PM 03/26/92

130800

01:30:30 LB 05:23 PM 03/26/92

134900

NOTES

380

01:30:30 LB 04:23 PM 03/26/92

130400

01:30:30 LB 04:23 PM 03/26/92

134400

NOTES

400

01:30:30 LB 04:23 PM 03/26/92

134400

01:30:30 LB 04:23 PM 03/26/92

138000

NOTES

Page # 3

Down
M. 3

14:37

14:37

04 0618

NOTES

13060 m

13420 m

19:32

2003

2003

NOTES

13060 m

13420 m

18:42

2003

2003

Page # 3

PRESS OPERATING DATA

Time	Band Thickness	Cycle Time	Press Loads/Hour	Density	Press Temp	Line Speed
9:55	7/16	5:20	11.5	43.1	424	65
11:00	7/16	5:21	11.5	43.0	425	65
12:00	7/16	5:20	10.0	42.0	423	65
12:50	7/16	5:20	12.0	43.8	424	65
1:34	7/16	5:19	11.0	41.2	421	65
1:57	7/16	5:20	11.0	43.2	423	65
1:55	7/16	4:57	12.0	41.3	401	70
17:00	7/16	5:19	11.0	423	423	65.5

3/27

25

the press runs didn't have as much red (particulate) cake on the impinger glassware (cokes & stem)

Lunch w/ Al Bender
Press stopped for 10 minutes - Back questioned at 1340
Conversation w/ Cathy () of Inkeroll
She informed us that she had baked product 1 gas cylinders of propane in air from CAFE in the 550pm and 850pm range. She said they would feed to the

04 0704

3/27/92

Time

Pounds of

Wax

Start 9:15
End 10:15
Total 1:00

10:15	11:15	12:15	1:15	2:15	3:15	4:15	5:15	6:15	6:55
155.2	137	152.7	160.8	128.6	176.8	112.5	144.7	122.6	
12 1/2"	14 3/8"	17 1/2"	19 1/2"	21 1/2"	24 1/4"	26	28 1/4"	31 1/2"	

Pounds of

Resin

Start 9:15
End 10:15
Total 1:00

168.2	61.7	294.3	194.4	127.3	166.6	133.8	123.1	192.5	175.6
140.5	129.2	135.2	142.5	104.7	148.8	113.3	104.1	177.5	120.7

of Presses

Press Temp

of Sheets Produced
KOD

Tons of Finished

Product

423	424	424	424	424	424	403	400	428	428
154	140	154	168	112	168	154	168	140	126
11.6	10.3	11.8	12.1	8.5	12.7	8.2	9.0	11.0	9.5

04 0705

of that
ed
each
remg
and
due
eng
K
than

1011
1015
1030
1030-1100
1100
1118

Press still having some problems - No testing
was started yet
Press OK back on line
Test run #2 of the day started
Make-out list of production records needed
from facility before leaving site today
Observe/record process after an pass -
VOC concentration observed to be about
30 ppm at maximum - might in a 4m test
for VOC on the #2 vent
Informed by dryer operator that he switched
the No.2 dryer back to wood from Natural gas

Press	Good thickness %	Cycle Time	Press loads/ hour	Density	Press Temp	Line Speed
0815	7/16	5:18	11	45.9	425	65.5
0945	7/16	5:19	11	41.2	424	65.1
1100	7/16	5:18	11	43.7	425	65.5
1155	7/16	5:19	11	42.2	425	65.3
1319	7/16	5:18	10	43.2	425	65.0
1450	7/16	5:17	10	43.7	424	65.5
1550	7/16	5:18	10	41.2	424	65.5
1640	7/16	5:17	12	43.3	424	65.5
1737	7/16	5:17				65.5

Press OPERATING DATA

3/28
29

3/25/92

Time

ends of

max

9 1/2"

ends of

2500

of Pressloads

Press Temp

Sheets #
Boards
Produced

in of finished
product

8:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
9:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
10:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
11:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
12:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
1:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
2:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
3:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
4:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
5:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
6:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
7:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3
8:30	144.7	112.5	160.6	144.7	112.5	144.7	176.8	160.6	5:30	425	112	154	11.8	8.1	11.1	10.5	12.7	7.4	9.1	40.3	11.7	10.8	3.3

04 0763

DRIVER REPORT

DATE: 3-28-92

SHIFT: 2

CREW: 3

FOREMAN: Glen

OPERATOR: Charles

#1 DRIVER

#11 DRIVER

#111 DRIVER

TIME	OUT-TEMP	INLET	CENCO	SPEED	OPAC	MON	OUT-TEMP	INLET	CENCO	SPEED	OPAC	MON	KONUS
------	----------	-------	-------	-------	------	-----	----------	-------	-------	-------	------	-----	-------

6:30	215	650	8.2	260	12	230	800	7.0	270	230	550	7.4	285	60	489
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

7:00	215	660	7.6	260	11	230	750	5.0	270	230	506	7.6	303	01	489
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

7:30	220	650	7.6	260	11	230	750	6.2	270	230	600	6.4	305	03	489
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

8:00	220	650	7.0	260	12	230	750	5.6	270	230	700	5.8	305	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

8:30	215	650	5.8	260	20	235	825	5.4	270	235	600	5.4	305	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

9:00	220	625	6.4	240	16	230	800	5.8	270	235	700	6.0	205	09	489
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

9:30	210	675	8.0	250	16	230	1000	7.6	270	235	650	6.0	205	09	489
------	-----	-----	-----	-----	----	-----	------	-----	-----	-----	-----	-----	-----	----	-----

10:00	215	700	5.8	250	16	240	700	8.6	210	235	500	9.0	310	01	489
-------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

10:30	215	650	9.2	250	15	240	600	8.8	200	235	650	6.8	310	03	488
-------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

11:30	215	700	8.2	260	14	240	750	6.4	215	235	750	6.0	310	07	490
-------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

12:00	215	700	8.2	260	14	240	750	6.4	215	235	750	6.0	310	07	490
-------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

12:30	220	850	8.5	260	14	230	850	4.4	235	235	650	7.4	310	07	490
-------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

1:00	220	800	7.0	260	14	235	800	11.8	245	235	200	8.4	310	04	489
------	-----	-----	-----	-----	----	-----	-----	------	-----	-----	-----	-----	-----	----	-----

1:30	220	750	6.4	260	17	235	800	11.8	245	235	200	8.4	310	04	489
------	-----	-----	-----	-----	----	-----	-----	------	-----	-----	-----	-----	-----	----	-----

2:00	220	700	5.6	260	14	240	900	6.4	245	235	200	8.4	310	04	489
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

2:30	220	750	1.2	260	20	240	900	6.4	245	235	200	8.4	310	04	489
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

3:00	220	700	6.4	260	17	235	800	11.8	245	235	200	8.4	310	04	489
------	-----	-----	-----	-----	----	-----	-----	------	-----	-----	-----	-----	-----	----	-----

3:30	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

4:00	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

4:30	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

5:00	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

5:30	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

6:00	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

6:30	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

7:00	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

7:30	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

8:00	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

8:30	225	800	7.4	230	23	240	850	5.0	210	235	650	7.4	310	07	490
------	-----	-----	-----	-----	----	-----	-----	-----	-----	-----	-----	-----	-----	----	-----

04 0761



Louisiana-Pacific

ORIENTED STRUCTURAL BOARD

NAME 110 NUMBER OF LOADS _____
DATE/SHIFT 3-28-52 STORAGE TANK LEVEL _____
NOMINAL THICKNESS 1/4 FACE RESIN TOTALIZER _____
TYPE A15 CORE RESIN TOTALIZER _____

PRESSLOAD	2	13	23	31	44	59	65	74	83	90	100	105	112						
BOARD	1	3	5	6	8	9	10	2	3	5	7	9	10						
TIME	605	703	800	905	1007	1134	1214	1301	150	152	350	423	502						
LINE SPD.	65	65	65	65	65	65	65	65	65	65	65	65	65						
SL																			
CL	154	157	152	152	150	152	154	154	152	154	152	152	152						
T.T.P.	139	123	129	144	121	98	94	133	96	84	101	104	122						
O.T.	210	205	205	215	215	215	196	210	195	190	200	200	200						
D.T.	45	55	55	45	45	45	68	50	67	45	55	45	55						
D.P.	30	30	30	27	30	30	25	30	96	24	27	27	27						
POS. #2	450	400	450	450	450	400	440	450	450	450	450	450	450						
TEMP.	420	420	424	425	425	425	424	424	424	423	423	423	424						
WEIGHT	767	705	424	492	701	701	443	718	735	735	701	714	736						
THICKNESS																			
DENSITY	451	437	426	430	412	410	434	422	432	437	412	420	433						
M.C. (F/C)																			
M.O.E.																			
M.O.R.																			
I.B.																			

