

Note: This is a reference cited in AP 42, *Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

**REPORT OF
AIR EMISSIONS TESTS
FOR
LOUISIANA PACIFIC CORPORATION
NEW WAVERLY OSB FACILITY**

**New Waverly, Texas
May 31, and June 1, 1995**

**Louisiana Pacific Corporation
Post Office Box 368
New Waverly, Texas 77358**

**ph: 409/295-5471
Contact: Paul Pickett**

**Prepared for
Louisiana Pacific Corporation
Post Office Box 3107
Conroe, Texas 77305**

**ph: 409/760-5921
Contact: Dr. James T. Boswell**

***Performed By:
Environmental Monitoring Laboratories
Ridgeland, Mississippi
< 601/856-3092 >***

ENVIRONMENTAL MONITORING LABORATORIES, INC.

P.O. Box 655 • 624 Ridgewood Road
Ridgeland, Mississippi 39158

phone: 601/856-3092
fax : 601/853-2151

July 18, 1995

Subject: Louisiana Pacific Corporation
New Waverly, Texas

On May 31, and June 1, 1995, Environmental Monitoring Laboratories performed air emissions testing for Louisiana Pacific Corporation's oriented strand board (OSB) facility in New Waverly, Texas. L.P. operates a rotary OSB dryer which exhausts to a regenerative thermal oxidizer (RTO) for emissions control. Testing was performed to determine emissions of particulate matter (PM), volatile organic compounds (VOC), formaldehyde (HCOH) nitrogen oxides (NOx), and carbon monoxide (CO) from the RTO. Testing was also simultaneously performed at the RTO inlet to determine removal efficiency.

Test Results:

DRYERS RTO	PM		VOC as C		HCOH		CO		NOx	
	#/hr.	gr/dscf	#/hr.	ppm	#/hr.	ppm	#/hr.	ppm	#/hr.	ppm
RTO OUTLET	2.04	0.007	0.45	7.4	0.072	0.47	36.24	238	8.07	33
RTO INLET	25.77	0.104	90.30	1728	1.025	7.89	34.63	275	6.76	33
REMOVAL EFFICIENCY	92.08		99.50		92.98		N/A		N/A	

The testing project was coordinated by Dr. James T. Boswell of Louisiana Pacific Corporation. Danny Russell of Environmental Monitoring laboratories coordinated sample collection and analysis and report preparation. All formaldehyde samples were shipped to Oxford Laboratories in Wilmington, North Carolina, for analysis. Otherwise sample custody was limited to Mr. Russell.

Following is a report of the test.

REPORT OF AIR EMISSIONS AND INLET LOADING TESTS FOR
LOUISIANA PACIFIC CORPORATION
NEW WAVERLY OSB FACILITY
NEW WAVERLY, TEXAS
MAY 31, AND JUNE 1, 1995

CONTENTS

1.0	TEST RESULTS	page 1
2.0	SOURCE DESCRIPTION	5
3.0	TEST PROCEDURES	5
4.0	DATA REDUCTION	6
5.0	NOMENCLATURE	15
6.0	CALIBRATION	16
7.0	APPENDICES:	17
	A. Field and Laboratory Data	
	B. Calibrations	
	C. Instrument Recorder Traces/Data Log	
	D. HCHO Analysis Report (Oxford Laboratories)	

REPORT CERTIFICATION

I certify that I have examined the information submitted herein,
and based upon my inquires of those responsible for obtaining the
data or upon my direct acquisition of data, I believe the submitted
information is true, accurate and complete.

Signed



Daniel G. Russell

1.0 TEST RESULTS: The following tables present the measured flow parameters and test results for air emissions and inlet loading samples taken on May 31, and June 1, 1995, for the RTO at Louisiana Pacific Corporation 's OSB facility in New Waverly, Texas.

1.1 Dryers RTO

1.1.1 PC/CO/NO_x Emissions Test

Run No.		1	2	3	AVG.
Date		5/31/95	5/31/95	5/31/95	—
Time Start		0933	1210	1349	—
Time End		1048	1312	1450	—
PARTICULATE EMISSIONS	#/hr	2.12	2.25	1.76	2.04
PARTICULATE EMISSIONS	gr/dscf	0.007	0.008	0.006	0.007
CO EMISSIONS	#/hr	51.89	29.63	27.20	36.24
CO EMISSIONS	ppm	330	200	184	238
NO _x EMISSIONS	#/hr	7.88	8.80	7.52	8.07
NO _x EMISSIONS	ppm	31	36	31	33
VOLUMETRIC FLOWRATE	acfm	64662	65115	65057	64945
VOLUMETRIC FLOWRATE	dscfm	36047	33959	33887	34631
VELOCITY	ft./sec.	70.3	70.8	70.8	70.7
STACK TEMPERATURE	°F	344	363	349	352
MOISTURE	%	13.8	17.5	19.0	16.8
SAMPLE RATE	% isokinetic	98	104	107	103

Dryer RTO

1.1.2 VOC, HCHO Emissions Test

Run No.		4	5	6	AVG.
Date		5/31/95	6/1/95	6/1/95	---
Time Start		1649	0855	1031	---
Time End		2114	1004	1133	---
FORMALDEHYDE EMISSIONS	#/hr	0.068	0.080	0.069	0.072
FORMALDEHYDE EMISSIONS	ppm	0.45	0.52	0.44	0.47
VOC EMISSIONS	#/hr as C	0.56	0.36	0.43	0.45
VOC EMISSIONS	ppm as C	9.2	6.0	6.9	7.4
VOLUMETRIC FLOWRATE	acfm	63213	64509	64092	63938
VOLUMETRIC FLOWRATE	dscfm	32500	32628	33029	32719
VELOCITY	ft./sec.	68.8	70.2	69.7	69.6
STACK TEMPERATURE	°F	364	365	369	366
MOISTURE	%	18.5	19.7	17.8	18.7
SAMPLE RATE	% isokinetic	103	108	100	104

1.2 RTO Inlet

1.2.1 PM/CO/NOx Loading Test

Run No.		1	2	3	AVG.
Date		5/31/95	5/31/95	5/31/95	---
Time Start		0932	1208	1347	---
Time End		1047	1310	1449	---
PARTICULATE LOADING	#/hr	22.34	25.87	29.09	25.77
PARTICULATE LOADING	gr/dscf	0.087	0.106	0.119	0.104
CO LOADING	#/hr	33.54	32.04	38.31	34.63
CO LOADING	ppm	258	259	309	275
NOx LOADING	#/hr	6.38	7.51	6.37	6.76
NOx LOADING	ppm	30	37	31	33
VOLUMETRIC FLOWRATE	acfm	44701	44510	44694	44635
VOLUMETRIC FLOWRATE	dscfm	29799	28362	28420	28860
VELOCITY	ft./sec.	79.3	79.0	79.3	79.2
STACK TEMPERATURE	°F	182	180	177	180
MOISTURE	%	15.8	19.8	20.3	18.6
SAMPLE RATE	% isokinetic	99	107	109	105

RTO Inlet

1.2.2 VOC and HCHO Loading Test

Run No.		4	5	6	AVG.
Date		5/31/95	6/1/95	6/1/95	---
Time Start		0836	1012	1147	---
Time End		0938	1114	1248	---
FORMALDEHYDE LOADING	#/hr	0.748	1.535	0.792	1.025
FORMALDEHYDE LOADING	ppm	5.84	11.90	5.92	7.89
VOC LOADING	#/hr as C	~ 59.34	104.86	106.68	90.30
VOC LOADING	ppm as C	~ 1157.4	2033.4	1993.1	1728.0
VOLUMETRIC FLOWRATE	acfm	43386	45469	44955	44603
VOLUMETRIC FLOWRATE	dscfm	~ 27423	27583	28630	27879
VELOCITY	ft./sec.	77.0	80.7	79.8	79.1
STACK TEMPERATURE	°F	186	194	184	188
MOISTURE	%	19.6	22.0	19.3	20.3
SAMPLE RATE	% isokinetic	101	108	106	105

2.0 SOURCE DESCRIPTION: Louisiana Pacific Corporation operates an Oriented Strand Board (OSB) plant in New Waverly, Texas. Process description here is limited to a brief description of the emissions sources and their sampling locations. Detailed descriptions of the processes, the pollution control equipment, and records of operating rates and conditions during testing may be supplied by Louisiana Pacific Corporation.

A rotary dryer is used for drying wood flakes. The dryer exhausts to a primary cyclone, then to bank of high efficiency cyclones. Exhaust from the multicyclone is directed to a manifold and then to the RTO. Inlet sampling was done upstream of the multicyclone in a vertical turned down 41.5 inch diameter duct. Two sample ports at 90° are installed at a location that is 36 inches upstream of a vertical to horizontal elbow and 138 inches downstream of a horizontal to vertical elbow. The RTO exhausts to the atmosphere by way of a vertical 53.0 inch diameter stack. Two sample ports are provided at a location that is 562 inches (2.5 diameters) downstream of the inlet duct and 562 inches (10.6 diameters) below the stack exit. Sketches of the stacks and sampling locations are provided in Appendix A.

3.0 TEST PROCEDURES: Test procedures used are those described in 40 CFR, Part 60, Appendix A and in Part 266, Appendix IX.

Particulate sampling was done as described in Method 5. An exception was the inclusion of the condenser section particulate. Reported particulate is based on three fractions: the front half, the back half organic (methylene chloride extraction), and the back half aqueous. The contribution of each fraction can be reviewed in Section 4.0.

Carbon monoxide concentrations were continuously monitored as described in Method 10. Two TECO Model 48H gas correlation filter NDIRs in various ranges were used to monitor CO at the inlet and outlet. Instrument calibration and bias checks were performed prior to and following each series of tests, and a mid range system bias check was made following each run by directing calibration to the gas sampling probe.

Nitrogen oxides were continuously monitored as described in Method 7E. Two TECO Model 10S analyzers were used. Instrument calibration was performed prior to and following each series of tests, and a mid range system bias check was made prior to and following each run by directing calibration to the gas sampling probe.

VOC concentrations were measured using Method 25A (continuous monitoring with a flame ionization detector). Two TECO Model 51 heated FIDs were used. The 0 to 100 ppm scale and the 0 to 1000 ppm scale were used for calibrations using zero air, and appropriate low, mid and high range concentrations of EPA protocol propane in nitrogen. Since calibrations are made with propane (C_3H_8), results as methane (CH_4) (or as carbon) are determined by increasing the measured concentration by a factor of three. A continuous trace of VOC as propane was recorded and manually integrated for each 60 minute test period. Instrument calibration was performed initially, and following each 60 minute test period. Any necessary adjustments were made after recording the response of the mid range calibration gas, which was introduced at the inlet to the VOC sampling probe. The gas samples were directed to the heated FID analyzers by way of heated teflon sample lines maintained at a minimum temperature of 250°F.

Instrument calibrations were made with Protocol 1 cylinder gas, an EnviroNics Model 2020 gas diluter and EPA Conditional Method 7. (Carbon monoxide cylinder gas was certified rather than Protocol 1). All calibrations were made by introducing calibration gas at the probe inlet.

Formaldehyde was measured using the procedure described in CFR 40, Part 266, Appendix IX, Method 0011. Reagent preparation and sample analysis was performed by Oxford Laboratories of Wilmington, North Carolina.

Inlet sampling was done simultaneously with outlet sampling in order to determine removal efficiency or additional pollutant contribution. This was accomplished by operating two sampling trains simultaneously.

4.0 DATA REDUCTION

Louisiana Pacific Corporation - New Waverly, Texas
 OSB RTO
 PM/NOx/CO Emissions Test - May 31 through June 1, 1995

Collected Test Data:

	RUN 1	RUN 2	RUN 3
Date :	5/31/95	5/31/95	5/31/95
Time start :	0933	1210	1349
Time end :	1048	1312	1450
1. As : sq ft	15.3207	15.3207	15.3207
2. Dn : in.	0.250	0.250	0.250
3. Cp : dimensionless	0.84	0.84	0.84
4. Theta : minutes	60.00	60.00	60.00
5. Y : dimensionless	1.00	1.00	1.00
6. Pbar : in. Hg	29.55	29.55	29.55
7. Pg : in. H2O	-0.98	-0.98	-0.98
8. Vm : cf (dry gas)	49.637	50.279	51.917
9. $\text{sqr}(\text{DP})_{\text{avg}}$: in.H2O ^{.5}	0.9850	0.9733	0.9787
10. DH : in. H2O	2.1563	2.1708	2.2625
11. ts : degrees F	344.08	362.67	349.33
12. tm : degrees F	92.92	97.35	103.92
13. Vlc : ml	160.5	213.5	240
14. CO2 : percent	2.50	2.50	3.00
15. O2 : percent	18.00	18.00	18.00
16. CO : percent	0.03	0.02	0.02
17. CO : ppm	330.0	200.0	184.0
18. M,PM : milligrams			
front half	15.5	16	15.5
back half organic	1.9	3.4	2.3
back half aqueous	3.5	4.3	1.2
19. NOx : ppm	30.6	36.3	31.1

352.03

238.0

33

Louisiana Pacific Corporation - New Waverly, Texas
 OSB RTO
 PM/NOx/CO Emissions Test - May 31 through June 1, 1995

Calculations:		RUN 1	RUN 2	RUN 3	AVG.
1. Pm	: in.Hg (DH/13.6)+Pbar	29.7086	29.7096	29.7164	
2. Ps	: in. Hg (Pg/13.6)+Pbar	29.4779	29.4779	29.4779	
3. An	: sq ft ((Dn/24)*2)(3.1416)	3.41E-04	3.41E-04	3.41E-04	
4. Vmstd	: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	47.065	47.296	48.279	
5. Vwstd	: scf (.04707cf/ml)(Vlc)	7.555	10.049	11.297	
6. Bws	: dimensionless Vwstd/(Vwstd+Vmstd)	0.1383	0.1752	0.1896	0.1677
7. Md	: mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	29.12	29.12	29.2	
8. Ms	: mol.wt. wet basis Md(1-Bws)+18 Bws	27.58	27.17	27.08	
9. Vs	: ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	70.34	70.84	70.77	70.65
10. Q	: cfm Vs As(60 sec/min)	64662	65115	65057	64945
11. Qstw	: scfm Q(Ps/Pstd)(Tstd/Ts)	41833	41174	41816	41608
12. Qstd	: dscfm Qstw(1-Bws)	36047	33959	33887	34631
13. I	: percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm))/(60 theta Vs Ps An)	97.81	104.34	106.73	102.96

Particulate Emissions

14. E,PM	: pounds/hr (M,PM/Vmstd)(Qstd)(60)/(453590)				
front half		1.570	1.520	1.439	1.510
back half organic		0.192	0.323	0.214	0.243
back half aqueous		0.355	0.408	0.111	0.291
Total		2.117	2.251	1.764	2.044
15. C,PM	: grains/dscf (M,PM/Vmstd)(.0154 grains/mg)				
front half		0.0051	0.0052	0.0049	0.0051
back half organic		0.0006	0.0011	0.0007	0.0008
back half aqueous		0.0011	0.0014	0.0004	0.0010
Total		0.0068	0.0077	0.0061	0.0069

CO Emissions

16. E,CO	: pounds/hr (C,CO)(7.27e-8)(Qstd)(60)	51.89	29.63	27.20	36.24
----------	--	-------	-------	-------	-------

NOx Emissions

17. E,NOx	: pounds/hr C,NOx(1.19e-7)(Qstd)(60)	7.88	8.80	7.52	8.07
-----------	---	------	------	------	------

Louisiana Pacific Corporation - New Waverly, Texas
 OSB RTO
 VOC/HCHO Emissions Test - May 31 through June 1, 1995

Collected Test Data:

RUN 4

RUN 5

RUN 6

Date :	5/31/95	6/1/95	6/1/95
Time start :	1649	0855	1031
Time end :	2114	1004	1133
1. As : sq ft	15.3207	15.3207	15.3207
2. Dn : in.	0.260	0.260	0.260
3. Cp : dimensionless	0.84	0.84	0.84
4. Theta : minutes	60.00	60.00	60.00
5. Y : dimensionless	1.00	1.00	1.00
6. Pbar : in. Hg	29.55	29.52	29.52
7. Pg : in. H2O	-0.98	-0.98	-0.98
8. Vm : cf (dry gas)	50.956	53.295	50.962
9. $\text{sqr}(\text{DP})_{\text{avg}}$: in.H2O ^{.5}	0.9412	0.9600	0.9555
10. DH : in. H2O	2.3979	2.5146	2.4813
11. ts : degrees F	364.13	365.21	368.63
12. tm : degrees F	92.67	90.96	99.65
13. Vlc : ml	234	264	220
14. CO2 : percent	2.00	3.50	3.50
15. O2 : percent	18.50	17.50	17.50
16. CO : percent	0	0	0
17. M,HCOH : micrograms	769	938	750
18. C,VOC : ppm as CH ₄	2.5	1.6	1.9

365.99

Louisiana Pacific Corporation - New Waverly, Texas
 OSB RTO
 VOC/HCHO Emissions Test - May 31 through June 1, 1995

Calculations:		RUN 4	RUN 5	RUN 6	AVG.
1. Pm	: in.Hg (DH/13.6)+Pbar	29.7263	29.7049	29.7024	
2. Ps	: in. Hg (Pg/13.6)+Pbar	29.4779	29.4479	29.4479	
3. An	: sq ft ((Da/24)^2)(3.1416)	3.69E-04	3.69E-04	3.69E-04	
4. Vmstd	: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	48.366	50.707	47.730	
5. Vwstd	: scf (.04707cf/ml)(Vlc)	11.014	12.426	10.355	
6. Bws	: dimensionless Vwstd/(Vwstd+Vmstd)	0.1855	0.1968	0.1783	0.1869
7. Md	: mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	29.06	29.26	29.26	
8. Ms	: mol.wt. wet basis Md(1-Bws)+18 Bws	27.01	27.04	27.25	
9. Vs	: ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	68.77	70.18	69.72	69.55
10. Q	: cfm Vs As(60 sec/min)	63213	64509	64092	63938
11. Qstw	: scfm Q(Ps/Pstd)(Tstd/Ts)	39901	40624	40195	40240
12. Qstd	: dscfm Qstw(1-Bws)	32500	32628	33029	32719
13. I	: percent [(100 Ts)/(0.02669 Vlc+(Vm Pm/Tm))]/(60 theta Vs Ps An)	103.08	107.64	100.09	103.60

Formaldehyde Emissions

14. E,HCOH	: pounds/hr (M,HCOH/Vmstd)(Qstd)(60)/(453590000)	0.068	0.080	0.069	0.072
15. C,HCOH	: ppm (M,HCOH/Vmstd)(.0283)	0.45	0.52	0.44	0.47

VOC Emissions

16. C,VOC	: ppm as Carbon, dry ((C,VOC)*3)/(1-Bws)	9.21	5.98	6.94	7.37
17. E,VOC	: pounds/hr (C,VOC)(3.116e-8)(Qstd)(60)	0.56	0.36	0.43	0.45

Louisiana Pacific Corporation - New Waverly, Texas
 OSB RTO Inlet
 PM/NO_x/CO Emissions Test - May 31 through June 1, 1995

Collected Test Data:

	RUN 1	RUN 2	RUN 3	
Date :	5/31/95	5/31/95	5/31/95	
Time start :	0932	1208	1347	
Time end :	1047	1310	1449	
1. As : sq ft	9.3934	9.3934	9.3934	
2. Dn : in.	0.210	0.185	0.185	
3. Cp : dimensionless	0.84	0.84	0.84	
4. Theta : minutes	60.00	60.00	60.00	
5. Y : dimensionless	1.00	1.00	1.00	
6. Pbar : in. Hg	29.55	29.55	29.55	
7. Pg : in. H ₂ O	-10	-10	-10	
8. Vm : cf (dry gas)	48.09	38.985	40.203	
9. sqrt(DP),avg : in.H ₂ O ^{0.5}	1.2237	1.2083	1.2180	
10. DH : in. H ₂ O	2.1729	1.3125	1.3917	
11. ts : degrees F	182.29	179.75	177.42	179.82
12. tm : degrees F	93.69	101.17	111.71	
13. Vlc : ml	181.5	191	199	
14. CO ₂ : percent	2.50	1.50	3.00	
15. O ₂ : percent	18.00	18.50	17.50	
16. CO : percent	0.03	0.03	0.03	
17. CO : ppm	258.0	259.0	309.0	275.3
18. M _{PM} : milligrams				
front half	251.2	246.7	279.1	
back half organic	6.2	2.4	4.8	
back half aqueous	0.7	1.5	0.8	
19. NO _x : ppm	30.0	37.1	31.4	33

Louisiana Pacific Corporation - New Waverly, Texas
 OSB RTO Inlet
 PM/NOx/CO Emissions Test - May 31 through June 1, 1995

Calculations:

		RUN 1	RUN 2	RUN 3	AVG.
1. Pm	: in.Hg (DH/13.6)+Pbar	29.7098	29.6465	29.6523	
2. Ps	: in. Hg (Pg/13.6)+Pbar	28.8147	28.8147	28.8147	
3. An	: sq ft ((Dn/24)^2)(3.1416)	2.41E-04	1.87E-04	1.87E-04	
4. Vmstd	: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	45.537	36.345	36.797	
5. Vwstd	: scf (.04707cf/ml)(Vlc)	8.543	8.990	9.367	
6. Bws	: dimensionless Vwstd/(Vwstd+Vmstd)	0.1580	0.1983	0.2029	0.1864
7. Md	: mol.wt. dry basis .44 CO2+.32 O2+.28(CO+N2)	29.12	28.98	29.18	
8. Ms	: mol.wt. wet basis Md(1-Bws)+18 Bws	27.36	26.80	26.91	
9. Vs	: ft/sec Kp Cp (sqrDP)sqr(Ts/(Ps Ms))	79.31	78.97	79.30	79.20
10. Q	: cfm Vs As(60 sec/min)	44701	44510	44694	44635
11. Qstw	: scfm Q(Ps/Pstd)(Tstd/Ts)	35389	35378	35654	35474
12. Qstd	: dscfm Qstw(1-Bws)	29799	28362	28420	28860
13. I	: percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm))/(60 theta Vs Ps An)	99.47	107.49	108.60	105.19

Particulate Emissions

14. E,PM	: pounds/hr (M,PM/Vmstd)(Qstd)(60)/(453590)				
front half		21.744	25.465	28.514	25.241
back half		0.537	0.248	0.490	0.425
back half		0.061	0.155	0.082	0.099
Total		22.342	25.868	29.086	25.765
15. C,PM	: grains/dscf (M,PM/Vmstd)(.0154 grains/mg)				
front half		0.0850	0.1045	0.1168	0.1021
back half		0.0021	0.0010	0.0020	0.0017
back half		0.0002	0.0006	0.0003	0.0004
Total		0.0873	0.1062	0.1192	0.1042

CO Emissions

16. E,CO	: pounds/hr (C,CO)(7.27e-8)(Qstd)(60)	33.54	32.04	38.31	34.63
----------	--	-------	-------	-------	-------

NOx Emissions

17. E,NOx	: pounds/hr C,NOx(1.19e-7)(Qstd)(60)	6.38	7.51	6.37	6.76
-----------	---	------	------	------	------

Louisiana Pacific Corporation - New Waverly, Texas
 OSB RTO Inlet
 VOC/HCHO Emissions Test - May 31 through June 1, 1995

Collected Test Data:

RUN 4

RUN 5

RUN 6

Date :	5/31/95	6/1/95	6/1/95
Time start :	0836	1012	1147
Time end :	0938	1114	1248
1. As : sq ft	9.3934	9.3934	9.3934
2. Dn : in.	0.205	0.205	0.205
3. Cp : dimensionless	0.84	0.84	0.84
4. Theta : minutes	60.00	60.00	60.00
5. Y : dimensionless	1.00	1.00	1.00
6. Pbar : in. Hg	29.55	29.55	29.55
7. Pg : in. H2O	-10	-10	-10
8. Vm : cf (dry gas)	42.906	45.933	48.207
9. $\text{sqr}(\text{DP})_{\text{avg}}$: $\text{in. H}_2\text{O}^{.5}$	1.1753	1.2178	1.2193
10. DH : in. H2O	1.8271	1.9521	1.9750
11. ts : degrees F	186.42	194.21	184.17
12. tm : degrees F	93.42	93.19	111.25
13. Vlc : ml	211	260	225
14. CO2 : percent	3.00	2.50	2.00
15. O2 : percent	17.00	18.00	19.00
16. CO : percent	0	0	0
17. M,HCOH : micrograms	8380	18300	9250
18. C,VOC : ppm as CH ₄	310.0	529.0	536.0

188.27

Louisiana Pacific Corporation - New Waverly, Texas
 OSB RTO Inlet
 VOC/HCHO Emissions Test - May 31 through June 1, 1995

Calculations:		RUN 4	RUN 5	RUN 6	AVG.
1. Pm	: in.Hg (DH/13.6)+Pbar	29.6843	29.6935	29.6952	
2. Ps	: in. Hg (Pg/13.6)+Pbar	28.8147	28.8147	28.8147	
3. An	: sq ft ((Dn/24) ²)(3.1416)	2.29E-04	2.29E-04	2.29E-04	
4. Vmstd	: dscf Vm Y(Pm/Pstd)(Tstd/Tm)	40.613	43.510	44.222	
5. Vwstd	: scf (.04707cf/ml)(Vlc)	9.932	12.238	10.591	
6. Bws	: dimensionless Vwstd/(Vwstd+Vmstd)	0.1965	0.2195	0.1932	0.2031
7. Md	: mol.wt. dry basis .44 CO ₂ + .32 O ₂ + .28(CO+N ₂)	29.16	29.12	29.08	
8. Ms	: mol.wt. wet basis Md(1-Bws)+18 Bws	26.97	26.68	26.94	
9. Vs	: ft/sec Kp Cp (sq rDP)sqr(Ts/(Ps Ms))	76.98	80.67	79.76	79.14
10. Q	: cfm Vs As(60 sec/min)	43386	45469	44955	44603
11. Qstw	: scfm Q(Ps/Pstd)(Tstd/Ts)	34129	35341	35487	34986
12. Qstd	: dscfm Qstw(1-Bws)	27423	27583	28630	27879
13. I	: percent [(100 Ts)(.002669 Vlc+(Vm Pm/Tm))/(60 theta Vs Ps An)	101.17	107.76	105.51	104.81

Formaldehyde Emissions

14. E,HCOH	: pounds/hr (M,HCOH/Vmstd)(Qstd)(60)/(453590000)	0.748	1.535	0.792	1.025
15. C,HCOH	: ppm (M,HCOH/Vmstd)(.0283)	5.84	11.90	5.92	7.89

VOC Emissions

16. C,VOC	: ppm as Carbon, dry ((C,VOC)*3)/(1-Bws)	1157.43	2033.39	1993.10	1727.97
17. E,VOC	: pounds/hr (C,VOC)(3.116e-8)(Qstd)(60)	59.34	104.86	106.68	90.30

5.0 NOMENCLATURE

SYMBOL	UNITS	DESCRIPTION
A_n	ft^2	Nozzle cross sectional area
A_s	ft^2	Stack cross sectional area
B_{ws}	dimensionless	Wet gas fraction
CO_2	percent	Carbon dioxide content by volume
CO	percent	Carbon monoxide content by volume
C_p	dimensionless	Pitot correction factor
C_x	as labeled	Concentration of pollutant X
DGF	dimensionless	Dry gas fraction
D_n	inches	Nozzle diameter
ΔH (delta H)	in. H_2O	Pressure drop across meter orifice
ΔP (delta P)	in. H_2O	Stack gas velocity pressure
E_x	$\#/\text{hr}$	Emission rate of pollutant X
E_X	$\#/\text{MM Btu}$	Emission rate of pollutant X
F	dscf	Volume of flue gas per MM Btu
I	percent	Nozzle velocity/stack gas velocity
K_p	consistent	Pitot tube constant
M_x	milligrams	Sample weight of pollutant X
M_d	$\#/\#$ mole	Dry molecular weight of stack gas
M_s	$\#/\#$ mole	Wet molecular weight of stack gas
N_2	percent	Nitrogen content by volume, dry basis
O_2	percent	Oxygen content by volume, dry basis
P_{bar}	in. Hg	Barometric pressure
P_g	in. Hg	Stack static pressure
P_m	in. Hg	Total pressure at meter ($P_{bar} + (\Delta H/13.6)$)
P_s	in. Hg	Total stack pressure ($P_{bar} + (P_g/13.6)$)
P_{std}	in. Hg	Standard barometric pressure = 29.92
Q	acfm	Volumetric flow rate at stack conditions
Q_{std}	dscfm	Volumetric flow rate at standard conditions, dry basis
Q_{stdw}	scfm	Volumetric flow rate at standard conditions, wet basis
θ (theta)	minutes	Sample duration
t_m	$^{\circ}\text{F}$	Meter temperature (T_m denotes $^{\circ}\text{R}$)
t_s	$^{\circ}\text{F}$	Stack temperature (T_s denotes $^{\circ}\text{R}$)
T_{std}	$^{\circ}\text{R}$	Standard temperature = 528 $^{\circ}\text{R}$
V_{lc}	ml	volume of water collected
V_m	ft^3	Volume of dry gas sampled through meter
V_{mstd}	dscf	Sample volume at standard conditions
V_{wstd}	scf	Sample volume of water vapor
Y	dimensionless	Meter coefficient
X_{sair}	percent	Excess air

6.0 CALIBRATIONS:

Measurement devices used by Environmental Monitoring Laboratories and subject to changes in measurement precision are initially calibrated prior to use. Those instruments for which calibration factors are subject to change or for which calibration checks are required, are calibrated following each field use or as otherwise directed and noted. Calibration procedures for specific equipment are as follows.

Dry Gas Meter:

Dry gas meters are periodically removed from the sampling consoles and cleaned and repaired (new gaskets etc. as required). Following the overhaul of a meter, the measuring precision is checked by the Bell Prover Method and adjusted when necessary to read to within 2% of 100% accuracy. This service is provided by Big Three Meter Company in Jackson, Mississippi. Overhaul service or any six month period is followed by a five point calibration described in APTD-0576 using either a wet test meter or calibrated dry gas meter (used exclusively for calibrations) as a standard reference. Following field use, a gas meter calibration is checked in one of two ways. [1] Three calibration checks at intermediate orifice settings are performed or [2] orifice meter coefficients are used.

If a meter coefficient obtained from pre-test and post-test checks differs by more than 5%, the coefficient (Y) giving the lower sample volume is used in the calculations.

Orifice:

The orifice coefficient is initially determined and is rechecked following a major gas meter repair and calibration.

Nozzles:

Nozzles are checked before each field use with a precision (.001 in.) dial caliper. Three measurements on different axes are made; an average of those three readings is used in calculations. If the tolerance among measurements exceeds 0.004 inches (highest to lowest reading) the nozzle is repaired and recalibrated or discarded.

Pitot Tubes:

Pitot tubes meeting EPA geometry standards are assigned a coefficient of 0.84. Pitot tubes are visually inspected for damage before, during and after use. Those pitot tubes not meeting the geometry standards are assigned a coefficient from the manufacturer's calibration which it retains unless damaged. All pitot tubes used by Environmental Monitoring Laboratories are manufactured by NAPP, Inc.

Temperature Measuring Instruments:

Most temperature measurements are made with a type K thermocouple and an Omega digital thermocouple thermometer which has an initial calibration traceable to NBS. Other measurements are made using bimetallic dial thermometers. The thermocouples and dial thermometers are checked following or during a test series against an ASTM mercury in glass thermometer.

Barometer:

Aneroid field barometers are checked against and adjusted to readings from a mercury barometer or readings obtained from local weather authorities.

Differential Pressure Gauges:

Velocity head (ΔP) and orifice pressure differential (ΔH) measurements are made using water manometers of the appropriate range unless otherwise noted in the test data. Manometers do not require calibration.

7.0 APPENDICES

A. Field and Laboratory Data

B. Calibrations

C. Instrument Recorder Traces/Data Log

D. HCOH Analysis Report (Oxford Laboratories)

7.0 APPENDICES

APPENDIX A.


SAMPLING AND ANALYTICAL DATA

RTO OUTLET

STACK CONFIGURATION AND SAMPLE POINT LAYOUT FOR CIRCULAR STACKS

PLANT: LOUISIANA PACIFIC NEW WAVEPORT, TX. Date: 3-36-95
 SOURCE: RTO OUTLET
 TEST FOR: PM SET-UP
 TEST OPERATORS: BRAID MCKNIGHT

SKETCH OF STACK



PERCENT OF DIAMETER


point no.	points on a diameter							
	2	4	6	8	10	12	14	16
1	14.6	6.7	4.4	3.2	2.6	2.1	1.8	1.6
2	85.4	25.0	14.6	10.5	8.2	6.7	5.7	4.9
3		75.0	29.6	19.4	14.6	11.8	9.9	8.5
4		93.3	70.4	32.3	22.6	17.7	14.6	12.5
5			85.4	67.7	34.2	25.0	20.1	16.9
6			95.6	80.6	65.8	35.6	26.9	22.0
7				89.5	77.4	64.4	36.6	28.3
8				96.8	85.4	75.0	63.4	37.5
9					91.8	82.3	73.1	62.5
10					97.4	88.2	79.9	71.7
11						93.3	85.4	78.0
12						97.9	90.1	83.1
13							94.3	87.5
14							98.2	91.5
15								95.1
16								98.4

STACK DIAMETER:

Distance from ports to disturbance:
 A. to upstream disturbance 136"
 B. to downstream disturbance 562"
 Upstream diameters: 2.5"
 Downstream diameters: 10.6"
 Minimum No. sample points required: 24
 No. sample points selected: 12 X 2
 Port Length: 7.75"
 Port Type: 4" nipple
 Port Access: CAT WALK / MONORAILS

Point No.	inches from wall	velocity head
1	1.1	1.20 < 5
2	3.6	1.30
3	6.3	1.30
4	9.4	1.20
5	13.3	1.20
6	18.9	.90
7	34.1	.82
8	39.8	.78
9	43.6	.78
10	46.7	.70
11	49.4	.62
12	51.9	.60

MINIMUM NO. OF POINTS ON A DIAMETER



Pitot ID: _____ Pitot Cp: _____ Stack Temp: _____

Remarks:

Plant <u>LOUISIANA PACIFIC</u> <u>NEW HAVEN TR.</u>		RUN No. <u>1</u> Date <u>5-31-95</u> Time start <u>0933</u> end <u>1048</u>
Sampling Location <u>DRIVERS RTO EXHAUST</u>		
Test For <u>PM / CO / NOx</u>		
Test Operators <u>B. MCKNIGHT / L. CARRUTH</u>		

Meter Box <u>RADSON</u> Sample Box <u>NO. 3</u> Probe/Pitot <u>64 s.s.</u> Pitot Cp <u>.84</u> Nozzle Dia. <u>.250</u> Filter No. _____	No. Sample Pts. <u>12 x 2</u> Minutes/Pt. <u>2.5</u> NOMOGRAPH Δ H @ _____ Meter Temp. <u>100</u> % H ₂ O <u>21</u> C-Factor <u>.75</u> Stack Temp. <u>400</u> <u>325</u> Ref. Δ P <u>.94</u> <u>.86</u>	Gas Analysis <u>Exhaust</u> CO ₂ <u>2.5</u> O ₂ <u>18.0</u> CO <u>330 ppm TEL 048</u> Time <u>NOx = 30.6 ppm</u> Condensate: tare <u>200</u> fin <u>343</u> Silica gel: tare <u>685.5</u> fin <u>703</u>	Remarks: <u>Dr</u> <u>0.250</u> <u>0.250</u> } <u>.250</u> <u>0.250</u> }
--	---	--	---

Amb. Temp. °F <u>75</u>
Bar. Press. "Hg <u>29.95</u>
Static Press. "H ₂ O <u>-.98</u>

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head Δ P, in. H ₂ O	Orifice Δ H, in. H ₂ O	Stack Temp. °F	Meter Temp., °F in out	Oven Temp. °F	Imp. Temp. °F	Vac. in. Hg
1	00:00	892.851	1.40	2.80	320	77	76	248	66.2
2	2:30	894.6	1.40	2.80	320	83	76	249	66.2
3	5:00	897.0	1.40	3.00	341	90	77	251	66.2
4	7:30	899.7	1.10	2.40	363	95	78	252	65.2
5	10:00	901.7	1.10	2.40	389	97	80	255	60.2
6	12:30	904.1	0.98	2.10	332	100	81	192	60.2
7	15:00	906.4	0.81	1.75	271	101	83	175	60.2
8	17:30	908.1	0.80	1.70	369	102	84	145	60.2
9	20:00	909.9	0.76	1.55	366	103	85	135	60.2
10	22:30	911.7	0.76	1.55	332	103	86	128	60.2
11	25:00	913.8	0.56	1.20	325	91	88	100	60.2
12	27:30	915.2	0.50	1.15	325	93	88	100	60.2
1	30:00	916.958	0.58	1.25	326	92	90	254	62.2
2	2:30	918.5	0.64	1.35	373	94	88	253	62.2
3	5:00	920.1	0.60	1.30	376	96	88	257	62.2
4	7:30	921.8	0.65	1.40	327	99	88	254	62.2
5	10:00	923.6	0.64	1.35	344	101	89	254	62.2
6	12:30	925.2	0.80	1.70	376	103	90	253	62.2
7	15:00	927.2	1.20	2.60	328	106	91	247	62.2
8	17:30	929.3	1.40	3.00	323	109	92	252	62.2
9	20:00	931.9	1.70	3.60	352	111	93	248	62.2
10	22:30	934.8	1.50	3.20	330	112	94	260	62.2
11	25:00	937.2	1.40	3.00	325	112	95	258	62.2
12	27:30	939.8	1.40	3.00	325	113	97	244	62.2
END	60:00	942.488							
LOW check: 073 → 075 = .002 atm @ 7 Hg + pitot 3.6 - pitot 3.5									
49.637 9850 2.1563 344.08 9292									

Plant L.P. New Waverly, Tx
 Sampling Location Peters RTO Exhaust
 Test For PM/CO/NO_x
 Test Operators B.M. KNIGHT / L. CARLUTH

RUN No. 2
 Date 5-31-95
 Time start 1210 end 1312

Meter Box Anderson
 Sample Box No. 4
 Probe/Pitot 64.5.5
 Pitot Cp .84
 Nozzle Dia. .250
 Filter No.

No. Sample Pts. 24/1222
 Minutes/Pt. 2.5
 NOMOGRAPH
 $\Delta H @$ 1.75
 Meter Temp. 100
 % H₂O 21 / 15
 C-Factor .75 / .84
 Stack Temp. 400 / 385
 Ref. ΔP .94 / .82

Gas Analysis Fyrite
 CO₂ 2.5
 O₂ 18.0
 CO 200 ppm
 Time 1120 = 36.3

Condensate:
 tare 200 fin 405
 Silica gel: 100 708.5
 tare 685.5 fin 703

Remarks:

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH , in. H ₂ O	Stack Temp. °F	Meter Temp. °F In Out	Oven Temp. °F	Imp. Temp. °F	Vac. in Hg
1	0 00	942.791	1.30	2.80	380	81 79	253	61	2
2	2 30	944.7	1.20	2.40	385	84 79	250	61	2
3	5 00	946.9	1.40	3.00	391	87 80	249	61	2
4	7 30	949.4	1.20	2.40	337	92 81	252	61	2
N 5	10 00	951.6	1.20	2.40	353	95 82	249	60	2
6	12 30	953.9	1.00	2.25	368	98 83	256	60	2
7	15 00	956.1	0.80	1.80	392	100 85	251	60	2
8	17 30	958.2	0.75	1.70	357	100 87	256	60	2
9	20 00	960.1	0.73	1.65	345	101 88	257	62	2
10	22 30	961.9	0.68	1.55	357	102 90	258	62	2
11	25 00	963.8	0.55	1.25	357	103 92	251	62	2
12	27 30	965.3	0.54	1.25	357	104 93	252	62	2
13									
14	30 00	967.142	0.53	1.20	372	98 95	251	60	2
15	2 30	968.6	0.60	1.35	389	101 97	247	60	2
16	5 00	970.4	0.60	1.35	338	103 97	242	62	2
17	7 30	972.2	0.66	1.50	394	103 98	253	63	2
18	10 00	973.9	0.67	1.55	359	105 99	252	60	2
19	12 30	975.7	0.70	1.60	367	106 100	255	60	2
20	15 00	977.5	1.10	2.50	338	108 101	256	60	2
21	17 30	979.7	1.50	3.40	353	112 102	248	60	2
22	20 00	982.4	1.50	3.40	370	115 103	249	60	2
23	22 30	985.7	1.40	3.20	345	116 104	246	60	2
24	25 00	987.6	1.50	3.40	350	117 105	261	60	2
25	27 30	990.3	1.40	3.20	350	117 105	249	60	2
26	end	993.070							

Leak check: 0.38 → 0.41 = 0.03 cfm @ 6" H₂O

+ pitot ✓
 - pitot ✓

50.279 9733 21708 36262 92.35

PARTICULATE CATCH ANALYSIS

SAMPLES: L.P. - New Waverly RTO
 DATE TAKEN: 5-31-95 DATE ANALYZED: 6-10-94
 DELIVERED BY: Dea RECEIVED BY: Dea
 ANALYZED BY: Dea

(Attach chain of custody if additional exchanges occur)

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	2788	2743	2744	
FILTER TARE, gms.	.5700	.5705	.5659	
	.5777	.5802	.5766	
	.5777	.5800	.5766	
FINAL WEIGHT, gms.	.5777	.5800	.5766	
NET GAIN, gms.	.0077	.0095	.0107	

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER I.D.	L.P. New RI	L.P. New RI	L.P. New RI	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	190	140	150	
	(3)	(62)	(69)	()
TARE WEIGHT, gms.	104.6247	113.1132	112.5838	
	104.6328	113.1197	112.5888	
	104.6325	113.1197	112.5886	
FINAL WEIGHT, gms.	104.6325	113.1197	112.5886	
NET GAIN, gms.	.0078	.0065	.0048	
LESS BLANK, gms.				

PARTICULATE SAMPLE WEIGHT:

RUN NO.	1	2	3	
filter + probe, mg.	15.5	16.0	15.5	

BACK HALF PARTICULATE CATCH ANALYSIS

Methylene Chloride Extraction

SAMPLES: L.P. - New Wavely RTO exhaust
 DATE TAKEN: 5-31-95 DATE ANALYZED: 6-10-95
 DELIVERED BY: DER RECEIVED BY: DER
 ANALYZED BY: DER

(Attach chain of custody if additional exchanges occur)

RUN NO.	1	2	3	
CONTAINER ID.	LPNEW R1 BAK	LPNEW R2 BAK	LPNEW R3 BAK	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	351	440	445	

Organic Fraction

	(4)	(45)	(85)	()
TARE WEIGHT, gms.	108.4536	107.2474	109.1504	
	108.4552	107.2510	109.1523	
	108.4555	107.2508	109.1527	
FINAL WEIGHT, gms.	108.4555	107.2508	109.1527	
less blank, gms.				
NET GAIN, milligrams	1.9	3.4	2.3	

Aqueous Fraction

	(56)	(65)	(71)	()
TARE WEIGHT, gms.	105.8149	114.7804	115.8206	
	105.8184	114.7850	115.8222	
	105.8184	114.7847	115.8218	
FINAL WEIGHT, gms.	105.8184	114.7847	115.8218	
less blank, gms.				
NET GAIN, milligrams	3.5	4.3	1.2	

Plant LOUISIANA PACIFIC NEW ORLEANS TX
 Sampling Location RTD DRYER EXHAUST
 Test For HCHO/VOC
 Test Operators B. MCKINNEY L. CARPENT

RUN No. 4
 Date 5-31-95
 Time start 1649 end 2114

Meter Box KNORSEN No. Sample Pts. 12X2
 Sample Box N. 4 Minutes/Pt. 2.5
 Probe/Pitot 6 ft. 6 in.
 Pitot Cp .84 NOMOGRAPH
 Nozzle Dia. .260 in. ΔH@ 1.75
 Filter No. Meter Temp. 100
 % H₂O 15
 C-Factor .84
 Stack Temp. 375
 Ref. ΔP 0.70
 Amb. Temp. °F 85
 Bar. Press. "Hg 29.55
 Static Press. "H₂O -.98

Gas Analysis Expts
 CO₂ 2.0
 O₂ 18.5
 CO
 Time
 Condensate:
 tare REMARKS
 Silica gel:
 tare fin

Remarks:
impingers: Tare Final

1) DNPH	589	736
2) DNPH	576	634
3) MT	494	503
4) S.Gel	684	704

DRYERS WENT DOWN @
1720

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp. °F in	Meter Temp. °F Out	Oven Temp. °F	Imp. Temp. °F	Vac. in. Hg
1	000	045.556	1.30	3.40	404	87	85	N/A	65	2
2	230	047.3	1.20	3.40	338	87	85		63	2
3	500	050.0	1.20	3.20	396	93	85		63	2
4	770	053.1	1.10	2.95	345	99	86		60	2
5	1000	054.8	1.10	2.95	355	101	87		60	2
6	1230	057.2	1.00	2.60	357	103	88		60	2
7	1520	059.7	0.85	2.20	358	105	90		60	2
8	1730	061.7	0.73	1.90	395	105	92		59	2
9	2000	063.8	0.68	1.80	397	106	93		59	2
10	2230	045.8	0.70	1.85	335	108	95		59	2
11	2500	067.7	0.65	1.70	315	107	96		59	2
12	2730	069.7	0.65	1.70	310	107	96		59	2
13										
14	3000	071.710	0.50	1.30	366	78	76		55	2
15	230	073.1	0.54	1.40	356	82	77		58	2
16	500	074.5	0.56	1.50	367	86	77		58	2
17	730	076.2	0.58	1.55	411	91	78		58	2
18	1000	078.1	0.60	1.60	408	94	77		58	2
19	1230	079.7	0.64	1.65	364	97	81		57	2
20	1500	081.3	0.82	2.40	355	102	83		58	2
21	1730	083.3	1.10	2.90	402	105	85		58	2
22	2000	085.9	1.05	2.80	335	106	87		58	2
23	2230	088.4	1.30	3.40	385	108	89		60	2
24	2500	091.1	1.50	4.00	359	110	91		60	2
25	2730	093.6	1.30	3.40	376	111	91		60	2
26	END 3000	096.512								
27										
28										
29										
30										
31										
32										
33										
34										
35										

LEAK CHECK: 0.076 → 0.086 = 0.010 ΔP due to leak

4 probes - photo

50.956
 40.956
 9412
 2.3579
 364.13
 92.67

Plant L.P. - New Industry, TX
 Sampling Location Process RTO Exhaust
 Test For HCHO/VOC
 Test Operators Russell / Kenneth G. McKnight

RUN No. 5
 Date 6-21-95
 Time start 0855 end 1007

Meter Box Anderson
 Sample Box ALO.3
 Probe/Pitot 6' 2 ft. flange
 Pitot Cp .81
 Nozzle Dia. 260 Qtz
 Filter No. _____

No. Sample Pts. 12x2
 Minutes/Pt. 2-5

NOMOGRAPH

$\Delta H @$ _____
 $\Delta H @$ 1.75
 Meter Temp. _____
 % H₂O _____
 C-Factor _____
 Stack Temp. _____
 Ref. ΔP 70

Gas Analysis F_{gas}
 CO₂ 3.5
 O₂ 17.5
 CO _____
 Time _____

Condensate:
 tare Ren fin _____
 Silica gel:
 tare _____ fin _____

Remarks:
 Impinger Tare Final
 1) 1NPH 595 767
 2) 2NPH 526 654
 3) MT 494 507
 4) S. Gel 682 712
 0.260 Qtz
 0.260
 0.260

Port Point	El. Time, Min.	DGM Reading, Ft.	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F in. Out	Oven Temp. °F	Imp. Temp. °F	Vac. in. Hg
1	006	097.557	1.40	3.70	340	74	74	N/A	62.2
2	270	099.9	1.35	3.60	409	78	73		61.2
3	500	102.9	1.35	3.60	348	84	74		62.2
4	730	105.4	1.20	3.20	404	90	75		61.2
5	1000	108.2	1.05	2.80	351	93	77		60.2
6	1230	110.4	1.05	2.80	359	95	78		60.2
7	1500	112.6	0.78	2.10	355	97	79		62.2
8	1730	115.0	0.75	2.00	349	97	82		62.2
9	2000	116.8	0.67	1.75	391	98	83		62.2
10	2230	118.7	0.73	1.90	390	98	85		62.2
11	2500	120.8	0.57	1.50	375	99	87		62.2
12	2730	122.4	0.63	1.65	375	98	88		62.2
13									
14	340	124.283	0.50	1.30	369	89	90		62.2
15	230	126.2	0.56	1.50	409	91	91		62.2
16	500	127.6	0.59	1.55	404	92	91		62.2
17	730	129.4	0.60	1.60	347	93	91		62.2
18	1000	131.3	0.64	1.70	380	95	91		62.2
19	1230	133.0	0.65	1.75	385	97	92		62.2
20	1500	134.9	1.25	3.25	379	100	92		62.2
21	1730	137.2	1.10	2.90	345	104	93		62.2
22	2000	138.7	1.30	3.40	335	106	94		62.2
23	2230	142.5	1.30	3.40	325	109	95		63.2
24	2500	144.7	1.40	3.70	320	110	96		63.2
25	2730	147.8	1.40	3.70	321	111	97		63.2
26	0900	150.852							

LEAK CHECK: 025 → 029 = .004 GPM @ 11 TB

+ pitot v/d
 - pitot v/d

53.295 19600 2.5146 365.21 90.96

Plant Louisiana Pacific - New Haven O&BSampling Location Bayou DEE RIOTest For HCHO / VOCTest Operators Russell B. McKnight / ChantRUN No. 6Date 6-1-95Time start 1031 end 1133

Meter Box Andrews
 Sample Box 10.4
 Probe/Pitot 6" teflon
 Pitot Cp 89
 Nozzle Dia. .260 QTZ
 Filter No. N/A

No. Sample Pts. 12x2
 Minutes/Pt. 2.5

NOMOGRAPH

 $\Delta H @$ 1.75

Meter Temp. _____

% H₂O _____

C-Factor _____

Stack Temp. _____

Ref. ΔP 0.70Gas Analysis typicalCO₂ 3.5O₂ 17.5

CO _____

Time _____

Condensate:

tare 200 fin _____

Silica gel:

tare _____ fin _____

Remarks:

impinger: tan final
 1) DNPH 597 747
 2) DNPH 576 620
 3) MT 494 502
 4) S.Gol 681 699

Amb. Temp. °F 74Bar. Press. "Hg 29.52Static Press. "H₂O -98

Port Point	El. Time, Min.	DGM Reading, Ft. ²	Velocity Head ΔP , in. H ₂ O	Orifice ΔH , in. H ₂ O	Stack Temp. °F	Meter Temp., °F in Out	Oven Temp. °F	Imp. Temp. °F	Vac. in. Hg
1	000	151.368	1.35	2.50	387	87 87	N/A	65	2
2	230		1.30	3.40	352	87 90		65	2
3	500	153.5	1.30	3.40	344	91 90		65	2
4	730	156.5	1.10	2.90	382	96 89		65	2
5	1000	158.9	1.00	2.60	365	98 91		65	2
6	1230	161.2	1.00	2.60	408	101 90		65	2
7	1500	163.0	0.80	2.10	391	102 91		65	2
8	1730	165.8	0.74	2.00	374	103 92		65	2
9	2000	167.7	0.74	2.00	380	103 93		65	2
10	2230	169.8	0.66	1.70	375	104 94		65	2
11	2500	171.8	0.66	1.70	360	104 95		65	2
12	2730	173.6	0.66	1.70	345	104 96		65	2
2	3060	175.717	0.50	1.30	390	101 97		65	2
2	230	177.2	0.55	1.45	394	102 98		65	2
3	500	179.0	0.60	1.60	348	102 99		65	2
4	730	140.9	0.63	1.70	345	103 99		65	2
5	1000	182.6	0.63	1.70	366	104 100		65	2
6	1230	184.3	0.65	1.70	364	105 100		65	2
7	1500	186.2	0.99	2.60	378	106 101		65	2
8	1730	188.5	1.10	2.90	367	110 102		65	2
9	2000	190.9	1.50	4.00	350	112 103		65	2
10	2230	193.8	1.50	4.00	367	115 104		65	2
11	2500	196.6	1.20	3.20	360	117 104		65	2
12	2730	199.2	1.40	3.80	355	116 105		65	2
END	4400	202.330							

Leak check: .002 → .004 = .002 cfm @ 6" Hg
 pitot + V₀
 pitot - V₀

50962 .9555 2.4813 368.63 99.65

RTO INLET

STACK CONFIGURATION AND SAMPLE POINT LAYOUT FOR CIRCULAR STACKS

PLANT:

SOURCE:


TEST FOR:

TEST OPERATORS:

Louisiana Pacific - New Waverly
PROBERT INLET
Pm Setup
Russell

Date:

SKETCH OF STACK



PERCENT OF DIAMETER

point no.	points on a diameter							
	2	4	6	8	10	12	14	16
1	14.6	6.7	4.4	3.2	2.6	2.1	1.8	1.6
2	85.4	25.0	14.6	10.5	8.2	6.7	5.7	4.9
3		75.0	29.6	19.4	14.6	11.8	9.9	8.5
4		93.3	70.4	32.3	22.6	17.7	14.6	12.5
5			85.4	67.7	34.2	25.0	20.1	16.9
6			95.6	80.6	65.8	35.6	26.9	22.0
7				89.5	77.4	64.4	36.6	28.3
8				96.8	85.4	75.0	63.4	37.5
9					91.8	82.3	73.1	62.5
10					97.4	88.2	79.9	71.7
11						93.3	85.4	78.0
12						97.9	90.1	83.1
13							94.3	87.5
14							98.2	91.5
15								95.1
16								98.4

STACK DIAMETER:

Distance from ports to disturbance:

A. to upstream disturbance

B. to downstream disturbance

Upstream diameters:

Downstream diameters:

Minimum No. sample points required:

No. sample points selected:

Port Length:

Port Type:

Port Access:

41.5

138.5

36

3.3

.86

24

12 x 2


5"

3" Nipple

MANUALS / MANU LIFT

Point No.	inches from wall	velocity head
1	.9	1.7
2	2.8	1.7
3	4.9	1.5
4	2.3	1.4
5	10.4	1.3
6	14.8	1.3
7	26.7	
8	31.1	1.4
9	34.2	
10	36.6	1.8
11	38.7	
12	40.6	

MINIMUM NO. OF POINTS ON A DIAMETER



Pitot ID :

Pitot Cp:

Stack Temp:

180

Remarks:

Plant LOUISIANA PACIFIC NEW WABERIN, TX.Sampling Location RTO INLETTest For PM / CO / NOxTest Operators B. MCKNIGHT / G. MCKNIGHTRUN No. 1Date 5-31-95Time start 0932 end 1047

Meter Box RAC
 Sample Box NO. 2
 Probe/Pitot 544-55
 Pitot Cp .89
 Nozzle Dia. .210
 Filter No. 21

No. Sample Pts. 24 (12x2)
 Minutes/Pt. 2.5

NOMOGRAPH

$\Delta H @$ 1.90
 Meter Temp. 100
 % H₂O 21
 C-Factor .81
 Stack Temp. 180
 Ref. ΔP 1.3

Gas Analysis

CO₂ 2.5
 O₂ 18.0
 CO 258 ppm
 Time NOx = 27.8 ppm

Condensate:

tare 200 fin 359
 Silica gel:
 tare 692.5 fin 715

Remarks:

PLUGGED FILTER
stopped @ 911.462
START @ 911.664
LEAK CHECK .001 change 5 1/2

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP , in. H ₂ O	Orifice ΔH , in. H ₂ O	Stack Temp, °F	Meter Temp., °F In Out	Oven Temp, °F	Imp. Temp, °F	Vac. in. Hg
1	0000	892.544	1.60	2.30	204	75 76	252	60	2
2	230	894.5	1.70	2.40	203	81 76	250	60	2
3	500	896.6	1.50	2.15	196	80 77	251	60	2
4	730	898.7	1.40	2.00	190	86 79	252	60	2
5	1000	900.5	1.30	1.85	181	87 79	250	60	2
6	1230	902.4	1.10	1.55	176	90 80	254	60	2
7	1500	904.1	1.30	1.85	180	94 78	252	60	2
8	1730	906.0	1.60	2.30	177	97 82	250	60	3
9	2000	908.2	1.70	2.40	175	100 80	250	59	2
10	2230	909.9	1.90	2.60	175	100 81	250	59	2
11	2500	912.1	1.30	1.85	175	100 81	252	59	2
12	2730	913.9	1.80	2.60	174	100 86	250	58	2
1	3000	916.248	2.10	3.05	181	100 88	240	59	2
2	3230	918.7	2.20	3.20	180	102 86	250	59	2
3	500	920.9	2.10	3.05	180	105 89	251	59	2
4	730	923.9	1.80	2.60	182	111 86	251	59	2
5	1000	925.6	1.60	2.30	184	113 91	216	59	2
6	1230	928.7	1.70	2.40	181	117 91	253	59	2
7	1500	930.0	1.30	1.85	185	117 92	255	59	2
8	1730	931.9	1.30	1.85	190	117 92	251	59	2
9	2000	933.7	1.00	1.40	201	119 92	253	58	2
10	2230	935.5	1.00	1.40	170	123 93	251	58	2
11	2500	937.1	1.10	1.60	200	123 93	252	58	2
12	2730	938.7	1.10	1.60	198	119 93	249	58	2
End	6000	940.634							

LEAK CHECK: 030 → 033 = .003 change 7 1/2

+ pilot 6.0
 - pilot 1.0

48.090

1.2237

2.1729

182.29

93.69

Plant L.P. New wave, TX.Sampling Location RTD TOWERTest For PM/CO/NOxTest Operators B. McKnight / G. McKnightRUN No. 2Date 5-31-95Time start 1208 end 1310

Meter Box RAC
 Sample Box No. 1
 Probe/Pitot 5 ft ss
 Pitot Cp .84
 Nozzle Dia. .185
 Filter No. _____

No. Sample Pts. 12x2
 Minutes/Pt. 2.5

NOMOGRAPH

$\Delta H @$ 1.20
 Meter Temp. 100
 % H₂O 21 15
 C-Factor .81 0.9
 Stack Temp. 180 180
 Ref. ΔP 235 1.95

Gas Analysis

CO₂ 1.5
 O₂ 18.5
 CO 259 ppm
 Time 20.5 28.3

Remarks: _____

Amb. Temp. °F 75
 Bar. Press. "Hg 29.55
 Static Press. "H₂O -10.00

Condensate:

tare 200 fin 381
 Silica gel:
 tare 690 fin 700

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP , in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F In	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac. in. Hg
1	2:00	940.889	1.80	1.40	197	85	85	248	60	2
2	2:30	942.9	2.20	1.75	194	86	85	249	60	2
3	5:00	944.6	2.60	1.60	190	89	87	252	60	2
4	7:30	946.4	1.80	1.40	186	90	86	249	60	2
5	10:00	948.1	1.60	1.30	184	94	86	249	60	2
6	12:30	949.8	1.60	1.30	180	97	87	249	60	2
7	15:00	951.4	1.30	1.00	177	100	88	249	60	2
8	17:30	953.0	1.20	1.15	174	104	89	252	60	2
9	20:00	954.4	1.20	1.15	172	105	89	253	60	2
10	22:30	955.9	0.97	0.90	168	109	91	253	60	2
11	25:00	957.3	1.10	1.05	170	110	91	249	60	2
12	27:30	958.8	1.10	1.05	169	111	92	249	60	2
13										
14	30:00	960.338	1.80	1.70	174	111	93	253	60	2
15	2:30	961.9	1.60	1.50	177	113	95	248	60	2
16	5:00	963.7	1.50	1.40	177	114	96	251	60	2
17	7:30	965.5	1.30	1.25	180	118	97	248	60	2
18	10:00	967.2	1.30	1.25	178	117	97	250	60	2
19	12:30	968.8	1.30	1.25	180	120	99	252	60	2
20	15:00	970.2	1.50	1.40	180	121	99	251	60	2
21	17:30	972.0	1.40	1.30	180	123	100	253	60	2
22	20:00	973.5	1.40	1.30	181	124	100	251	60	2
23	22:30	975.1	1.50	1.40	179	125	101	246	60	2
24	25:00	976.6	1.50	1.40	183	126	103	250	60	2
25	27:30	978.4	1.40	1.30	184	127	101	257	60	2
26	end 6:00	979.974								

Leak check: .060 → .062 = .002 at 26 "Hg

+ pitot / 2
 - pitot / 2

38.985

1.2083

1.3125

179.75

101.17

Plant L.P. New Waverly, Tex.
 Sampling Location RTO Inlet
 Test For PM/CO/NOx
 Test Operators B. McKnight / G. McKnight

RUN No. 3
 Date 5-31-95
 Time start 1347 end 1449

Meter Box	<u>RAC</u>	No. Sample Pts.	<u>24(12x2)</u>	Gas Analysis	Remarks:		
Sample Box	<u>NO. 3</u>	Minutes/Pt.	<u>2.5</u>	CO ₂		<u>3.0</u>	
Probe/Pitot	<u>5 ft S.S.</u>	NOMOGRAPH				O ₂	<u>12.5</u>
Pitot Cp	<u>.84</u>	ΔH@	<u>190</u>	CO		<u>3.09</u>	
Nozzle Dia.	<u>210 .185</u>	Meter Temp.	<u>100</u>	Time		<u>NO2 = 33.0</u>	
Filter No.		% H ₂ O	<u>15</u>	Condensate:			
Amb. Temp. °F	<u>78°</u>	C-Factor	<u>0.9</u>	tare	<u>200</u> fin <u>384</u>		
Bar. Press. "Hg	<u>29.55</u>	Stack Temp.	<u>180</u>	Silica gel:			
Static Press. "H ₂ O	<u>-10</u>	Ref. ΔP	<u>1.95</u>	tare	<u>615</u> fin <u>630</u>		

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp. °F In Out	Oven Temp. °F	Imp. Temp. °F	Vac. in. Hg
1	0 00	980.650	1.20	1.15	173	100 98	256	869	2
2	2 30	982.1	1.40	1.30	174	104 98	251	69	2
3	5 00	983.7	1.70	1.60	174	107 96	250	69	2
4	7 30	985.3	1.50	1.40	172	106 98	247	69	2
5	10 00	987.6	1.30	1.20	175	110 101	259	69	2
6	12 30	989.0	1.30	1.20	171	112 96	248	67	2
7	15 00	990.2	1.40	1.30	170	113 100	253	69	2
8	17 30	991.8	1.50	1.40	171	119 105	248	69	2
9	20 00	993.5	1.40	1.30	172	118 107	249	69	2
10	22 30	995.1	1.80	1.70	173	121 100	253	69	2
11	25 00	997.2	1.50	1.40	172	120 100	256	69	2
12	27 30	998.5	1.80	1.70	175	121 105	256	69	2
13									
14	30 00	000.460	1.30	1.20	177	122 102	256	69	2
15	2 30	002.1	1.40	1.55	180	122 105	250	69	2
16	5 00	003.8	1.70	1.40	180	125 108	257	69	2
17	7 30	005.5	1.50	1.40	185	125 107	250	69	2
18	10 00	007.3	1.40	1.30	185	127 105	255	68	2
19	12 30	008.9	1.30	1.20	185	125 105	250	88	2
20	15 00	010.6	1.50	1.40	182	126 107	256	68	2
21	17 30	012.2	1.50	1.40	184	130 108	256	68	2
22	20 00	013.8	1.50	1.40	184	130 107	256	68	2
23	22 30	015.5	1.40	1.50	182	133 108	257	68	2
24	25 00	017.2	1.50	1.40	182	131 108	253	68	2
25	27 30	018.9	1.50	1.40	180	131 109	253	48	2
26	RAC 6000	020.853							

Leak check: .031 → .035 = .004 cfm 28 "H₂O

+ pilot / 2 4.1
 - pilot / 2 4.2

40203 1.2180 1.3917 17.42 111.71

PARTICULATE CATCH ANALYSIS

SAMPLES:

L.P. - New Haven RTD Bldg

DATE TAKEN:

5-31-95

DATE ANALYZED:

6-9-95

DELIVERED BY:

DEAR

RECEIVED BY:

DEAR

ANALYZED BY:

DEAR

(Attach chain of custody if additional exchanges occur)

FILTERS:

RUN NO.	1	2	3	
FILTER NO.	2742	2741	2787	2745
FILTER TARE, gms.	.5754	.5704	.5699	.5676
	.6856	.6176	.7400	.7657
	.6857	.6176	.7399	.6756
FINAL WEIGHT, gms.	.6857	.6176	.7399	.7656
NET GAIN, gms.	.1103	.0472	.1700	.1980

PROBE WASH:

RUN NO.	1	2	3	
CONTAINER I.D.	L.P.N. N. R1	L.P.N.N R2	L.P.N.N R3	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	220	230	200	
TARE WEIGHT, gms.	(E) 99.1369	(89) 106.4091	(91) 102.7991	()
	99.2303	106.4866	102.8808	
	99.2306	106.4854	102.8804	
		106.4858		
FINAL WEIGHT, gms	99.2306	106.4858	102.8804	
NET GAIN, gms.	.0937	.0767	.0811	
LESS BLANK, gms.				

PARTICULATE SAMPLE WEIGHT:

RUN NO.	1	2	3	
filter + probe, mg.	251.2	246.7	279.1	

BACK HALF PARTICULATE CATCH ANALYSIS

Methylene Chloride Extraction

SAMPLES:

L.P. New Waverly RTO Inlet

DATE TAKEN:

5-31-95

DATE ANALYZED:

6-9-95

DELIVERED BY:

DER

RECEIVED BY:

DER

ANALYZED BY:

DER

(Attach chain of custody if additional exchanges occur)

RUN NO.	1	2	3	
CONTAINER I.D.	LPNN R1 BAK	LPNN R2 BAK	LPNN R3 BAK	
VOLUME INTACT?	✓	✓	✓	
VOLUME, ml	360	400	400	

Organic Fraction

	(61)	(62)	(68)	()
TARE WEIGHT, gms.	113.9845	113.1125	112.5352	
	113.9907	113.1152	112.5404	
	113.9907	113.1149	112.5400	
FINAL WEIGHT, gms.	113.9907	113.1149	112.5400	
less blank, gms.				
NET GAIN, milligrams	6.2	2.4	4.8	

Aqueous Fraction

	(7)	(10)	(11)	()
TARE WEIGHT, gms.	107.3574	98.0019	101.6861	
	107.3586	98.0033	101.6867	
	107.3581	98.0034	101.6869	
FINAL WEIGHT, gms.	107.3581	98.0034	101.6869	
less blank, gms.				
NET GAIN, milligrams	0.7	1.5	0.8	

Plant L.P. New Waverly, TX
 Sampling Location RTO INLET
 Test For HCOH VOC
 Test Operators R. McKnight / G. McKnight

RUN No. 1
 Date 5-31-95
 Time start 1650 end 2113

Meter Box RAC
 Sample Box NO. 1
 Probe/Pitot 4.44 tef
 Pitot Cp .89
 Nozzle Dia. 2059t2
 Filter No. _____
 Amb. Temp. °F 85
 Bar. Press. "Hg 29.55
 Static Press. "H₂O -10
 No. Sample Pts. 24/12/12
 Minutes/Pt. 2.5
 NOMOGRAPH
 ΔH@ 1.90
 Meter Temp. 100
 % H₂O 15
 C-Factor .90
 Stack Temp. 175
 Ref. ΔP 1.4

Gas Analysis
 CO₂ 3.0
 O₂ 17.0
 CO _____
 Time _____
 Condensate: REMARKS
 tare 200 fin _____
 Silica gel: _____
 tare _____ fin _____

Remarks:

Impingers	tare	fin
1) DNPH	593	751
2) DNPH	577	611
3) MT	462	465
4) S-BEL	668	685

 ① .205
 ② .205 } 10 = 2.05
 ③ .205

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F in Out	Oven Temp. °F	Imp. Temp. °F	Vac. in. Hg
1	0000	021.148	0.80	1.05	183	89 90	200	60	2
2	0230	022.8	1.50	2.00	187	90 90	200	60	2
3	0500	024.7	1.50	2.00	189	92 90	200	60	2
4	0730	026.5	1.60	2.10	180	97 92	200	60	2
5	1000	028.8	1.30	1.70	193	100 94	200	60	2
6	1230	030.2	1.20	1.60	195	103 90	200	60	2
7	1500	032.1	1.40	1.85	198	106 90	200	60	2
8	1730	033.7	1.50	1.95	199	109 91	200	60	2
9	2000	035.7	1.50	1.95	204	113 97	200	60	2
10	2230	037.7	1.60	2.10	190	115 93	200	59	2
11	2500	039.7	1.60	2.05	201	117 93	200	58	2
12	2730	041.6	1.90	2.50	190	115 93	200	58	2
13									
1	3000	043.890	1.50	1.95	209	80 77	200	58	2
2	3230	045.7	1.70	2.20	201	81 78	200	58	2
3	3500	047.5	1.60	2.10	194	82 78	200	58	2
4	3730	049.3	1.30	1.70	184	82 78	200	58	2
5	4000	051.7	1.30	1.70	179	81 84	200	58	2
6	4230	053.0	1.10	1.45	170	83 80	200	58	2
7	4500	054.6	1.20	1.60	173	90 80	200	58	5
8	4730	056.3	1.30	1.70	173	103 94	200	58	5
9	5000	058.0	1.50	2.00	175	107 85	200	58	5
10	5230	059.6	1.30	1.70	175	111 85	200	58	5
11	5500	061.1	1.10	1.45	168	109 89	200	58	5
12	5730	062.5	1.10	1.45	158	112 88	200	58	5
end	6000	064.054							
27									
28									
29									
30									
31									
32									
33									
34									
35									

LEAK CHECK 055 → 7.057 = .002 cm³/6 1/8

total 6.8
- 0.400 7.2

42.906 1.1753 1.8271 186.42 93.42

Plant L.P. New Waverly, Tx.

Sampling Location RTO 2nd

Test For HCHO / UOX

Test Operators B. Knight / G. Knight Russell / Carruth

RUN No. 5

Date 6-01-95

Time start 0854 end 0000

Meter Box RAC
Sample Box No. 2
Probe/Pitot 4' tip
Pitot Cp .87
Nozzle Dia. .205
Filter No.

No. Sample Pts. 24 (12/2)
Minutes/Pt. 2.5

NOMOGRAPH

$\Delta H @$ 1.90
Meter Temp. 100
% H₂O 15
C-Factor .90
Stack Temp. 175
Ref. ΔP 1.9

Gas Analysis F₂

CO₂ 2.5
O₂ 18
CO
Time

Condensate:

tare 200 fin
Silica gel:
tare fin

Remarks:

Impurities	TARE	FIN
DMPH	575	702
DNP	604	714
MT	483	489
S. GEL	704	721

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP , in. H ₂ O	Orifice ΔH , in. H ₂ O	Stack Temp., °F	Meter Temp., °F In Out	Oven Temp., °F	Imp. Temp., °F	Vac. in. Hg
1	000	067.981	1.60	2.25	182	74 73	141	66	2
2	230	070.3	1.50	2.00	186	76 74		60	2
3	565	072.3	1.45	1.90	186	80 74		60	2
4	730	074.0	1.40	1.85	186	82 73		60	2
5	1000	076.3	1.30	1.70	187	87 75		62	2
6	1230	077.8	1.05	1.40	188	87 75		62	2
7	1500	079.3	1.50	2.00	189	91 75		62	2
8	1730	081.1	1.45	1.90	188	95 77		62	2
9	2000	082.9	1.50	2.00	185	99 79		62	2
10	2230	084.5	1.70	2.20	185	100 77		62	2
11	2500	086.4	1.70	2.20	185	104 77		62	2
12	2730	088.3	1.70	2.20	190	107 84		62	2
13	3000	090.461	1.50	2.00	204	102 88		62	2
14	3300	092.5	1.60	2.10	208	106 87		64	2
15	3600	094.5	1.60	2.10	209	109 87		64	2
16	3900	096.5	1.50	2.00	206	110 89		64	2
17	4230	098.3	1.25	1.65	201	113 90		64	2
18	4500	100.1	1.20	1.60	203	116 91		64	2
19	4830	101.8	1.70	2.20	202	118 89		64	2
20	5100	104.0	1.50	2.00	201	119 92		64	2
21	5430	105.8	1.40	2.25	203	123 93		64	2
22	5700	108.0	1.40	1.85	200	122 95		65	2
23	6030	109.9	1.50	2.00	197	124 96		65	2
24	6300	111.7	1.50	2.00	200	125 97		65	2
25	6600	113.914							

LEAK CHECK: 095 → 097 = .002 in @ 6 1/8"

+ pitot 6.8
- pitot 6.5

45.933 1.2178 1.9521 194.21 93.19

Plant Louisiana Pacific - New Waverly OSB
 Sampling Location Drum RTO Inlet
 Test For VOC/HK/HO
 Test Operators B. McKnight / G. McKnight

RUN No. 86
 Date 8-01-95
 Time start 1030 end 1132

Meter Box RAC
 Sample Box No. 1
 Probe/Pitot 5 ft. S.S.
 Pitot Cp .84
 Nozzle Dia. .185
 Filter No. _____
 Amb. Temp. °F 70
 Bar. Press. "Hg 29.55
 Static Press. "H₂O -10

No. Sample Pts. 24/12x2
 Minutes/Pt. 2.5
 NOMOGRAPH
 ΔH@ 1.90
 Meter Temp. 100
 % H₂O 15
 C-Factor 90
 Stack Temp. 175
 Ref. ΔP 1.4

Gas Analysis
 CO₂ _____
 O₂ _____
 CO _____
 Time _____
 Condensate:
 tare 900 fin _____
 Silica gel:
 tare _____ fin _____

Remarks:
 Impingers: tare Final
 1) DNPH 600 679
 2) DNPH 576 676
 3) MT 462 492
 4) S. Gel 694 710
 ID 185
 0 185
 0 185

Port Point	El. Time, Min.	DGM Reading, Ft. ³	Velocity Head ΔP, in. H ₂ O	Orifice ΔH in. H ₂ O	Stack Temp. °F	Meter Temp., °F in	Meter Temp., °F Out	Oven Temp. °F	Imp. Temp. °F	Vac in. Hg
1	6:00	114.181	1.80	2.40	188	100	96	N/A	60	2
2	2:30	115.6	1.60	2.10	188	102	97		60	2
3	5:00	117.7	1.50	2.00	186	105	96		60	2
4	7:30	119.7	1.30	1.90	187	108	96		60	2
5	10:00	121.5	1.30	1.70	188	110	97		60	2
6	12:30	123.2	1.30	1.70	191	113	96		60	2
7	15:00	124.8	1.60	2.10	191	114	97		60	2
8	17:30	127.3	1.50	2.00	191	119	98		60	2
9	20:00	129.2	1.50	2.00	190	121	99		60	2
10	22:30	131.5	1.60	2.10	189	124	100		60	2
11	25:00	133.6	1.50	2.00	186	126	100		60	2
12	27:30	136.0	1.50	2.00	184	128	101		60	2
13										
14	30:00	138.166	1.70	2.10	181	125	102		60	2
15	2:30	140.0	2.00	2.60	182	126	102		60	2
16	5:00	142.3	2.00	2.60	181	127	103		60	2
17	7:30	144.5	1.90	2.55	179	128	104		60	2
18	10:00	146.8	1.90	2.55	179	129	104		60	2
19	12:30	149.0	1.50	2.00	179	131	105		60	2
20	15:00	151.1	1.40	1.80	180	132	105		60	2
21	17:30	153.4	1.00	1.30	181	132	106		60	2
22	20:00	155.0	1.00	1.30	180	132	106		60	2
23	22:30	156.9	1.20	1.60	180	133	107		60	2
24	25:00	158.7	1.20	1.60	180	135	108		60	2
25	27:30	160.5	1.20	1.60	179	131	108		60	2
26	60:00	162.388								

Leak check: 093 → 095 = .005 cfm @ 6" H₂O

Pitot + ✓
 Pitot - ✓

48.207 1.2193 1.9750 184.17 111.25

APPENDIX B.

CALIBRATION DATA

DRY GAS METER CALIBRATION

Meter ID RAC
 Calibration Method DGM/DGM By DGR
 Calibration Meter ID 651729 Pbar 30.05
 Date 2/18/95

Run In. Hg	DH In. H ₂ O	Time min	Calibrating Meter			Field Meter						Y	Q	K	DH@
			V _i ft	V _f ft	Temp °F	V _i ft	V _f ft	Temp. in		Temp. out					
								init	final	init	final				
1	5.00	12.50	772.047	787.047	59	612.402	627.716	59	98	58	69	0.990	1.2	0.694	1.911
1	4.00	19.25	787.047	807.415	59	627.716	648.935	96	111	68	77	1.004	1.08	0.691	1.929
1	3.00	13.45	807.415	819.741	62	648.935	661.985	109	114	77	82	0.998	0.94	0.692	1.921
1	2.00	18.00	819.741	832.838	62	661.985	675.978	110	108	81	84	0.992	0.75	0.676	2.015
1	1.00	21.00	832.838	844.241	62	675.978	688.173	106	111	84	87	0.995	0.57	0.716	1.795
Averages:												1.00			1.91

$$Y = [V_{cal}(P_{bar})(T_{dgm})]/[(V_{dgm})(P_m)(T_{cal})]$$

$$K = Q(\sqrt{(P_m M_m)/((T_m \text{ out})(DH))})$$

$$Q = ((V_{mi} - V_{mf})/\text{min.})(T_{m, out}/T_{m, avg})(Y)$$

$$DH@ = 0.921/K^2$$

Where:

Y = Meter correction factor, dimensionless

V_{cal} = Volume of gas through calibrating meter, cubic feet

V_{dgm} = Volume of gas through field dry gas meter, cubic feet

P_{bar} = Barometric pressure, in. Hg

P_m = Meter pressure, (P_{bar} = DH/13.6)

T_{dgm} = Average dry gas meter temp, degrees R

T_{cal} = Temperature of gas at calibrating meter, degrees R

DRY GAS METER CALIBRATION

Meter ID RAC
Calibration Method DGM/DGM **By** GNM
Calibration Meter ID 651729 **Pbar** 29.76
Date 7/13/95

Vac. in. Hg	DH in. H ₂ O	Time min	Calibrating Meter			Field Meter						Y	Q	K	DH@
			V _i ft ³	V _f ft ³	Temp °F	V _i ft ³	V _f ft ³	Temp. in		Temp. out					
								init	final	init	final				
1	5.00	8.50	432.392	442.521	76	569.427	579.951	91	103	91	92	0.983	1.21	0.682	1.982
1	4.00	9.50	442.521	452.659	83	579.951	590.419	103	120	92	97	0.994	1.08	0.676	2.013
1	3.00	11.00	452.659	462.725	86	590.419	600.891	117	128	97	104	0.999	0.93	0.671	2.049
1	2.00	13.50	462.725	472.804	88	600.891	611.460	126	135	104	111	1.003	0.77	0.673	2.036
1	1.00	18.25	472.804	482.837	89	611.460	622.042	132	135	109	117	1.005	0.57	0.703	1.862
Averages:												1.00			1.99

$$Y = [V_{cal}(P_{bar})(T_{dgm})]/[(V_{dgm})(P_m)(T_{cal})]$$

$$K = Q(\sqrt{(P_m \text{ Mm})}/((T_m \text{ out})(DH)))$$

$$Q = ((V_{mi} - V_{mf})/\text{min.})(T_{M,out}/T_{m,avg})(Y)$$

$$DH@ = 0.921/K^2$$

Where:

Y = Meter correction factor, dimensionless

V_{cal} = Volume of gas through calibrating meter, cubic feet

V_{dgm} = Volume of gas through field dry gas meter, cubic feet

P_{bar} = Barometric pressure, in. Hg

P_m = Meter pressure, (P_{bar} = DH/13.6)

T_{dgm} = Average dry gas meter temp, degrees R

T_{cal} = Temperature of gas at calibrating meter, degrees R

953.4 Propane



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(810) 589-2950 FAX: (810) 589-2134

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer
ENVIRONMENTAL MON
242 INGLESIDE DRIVE
MADISON, MS 39110

Assay Laboratory
Scott Specialty Gases, Inc
1290 Combermere
Troy, MI 48083

Purchase Order : DRV0116
Scott Project # : 576120

ANALYTICAL INFORMATION

This certification was performed according to EPA Traceability Protocol For Assay and Certification of Gaseous Calibration Standards, Procedure G1, September, 1993.

Cylinder Number : ALM049194
Cylinder Pressure + : 1900 psig

Certificate Date : 2/1/95
Previous Certificate Date : None

Expiration Date : 2/1/98

ANALYZED CYLINDER

Components
Propane

Certified Concentration
953.4 ppm

Analytical Uncertainty*
±1% NIST Directly Traceable

Balance Gas: Nitrogen

Do not use when cylinder pressure is below 150 psig.

Analytical accuracy is inclusive of usual known error sources which at least include precision of the measurement processes.

REFERENCE STANDARD

Type
NTRM 1668

Expiration Date
6/7/96

Cylinder Number
ALM-032015

Concentration
95.5 ppm Propane in Air.

INSTRUMENTATION

Instrument/Model/Serial #
Frog Beckman/400/1002059

Last Date Calibrated
1/19/95

Analytical Principle
Flame Ionization Detection

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components
Propane

First Triad Analysis

Date: 2/1/95 Response Units: mv
Z1=0.00 R1=14.40 T1=143.00
R2=14.40 Z2=0.00 T2=143.00
Z3=0.00 T3=143.00 R3=14.40
Avg. Conc. of Cust. Cyl. 953.4 ppm

Second Triad Analysis

Calibration Curve

Concentration = $A + Bx + Cx^2 + Dx^3 + Ex^4$
r=1.00000 NTRM 1668
Constants: A=0.237940000
B=6.669000000 C=0.000000000
D=0.000000000 E=0.000000000

Special Notes

Analyst

475.3 Propane

Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(810) 589-2950 FAX: (810) 589-2134

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer: ENVIRONMENTAL MON
242 INGLESIDE DRIVE
MADISON, MS 39110

Assay Laboratory
Scott Specialty Gases, Inc
1290 Combermere
Troy, MI 48083

Purchase Order : DRV0116
Scott Project # : 576120

ANALYTICAL INFORMATION

This certification was performed according to EPA Traceability Protocol For Assay and Certification of Gaseous Calibration Standards, Procedure G1, September, 1993.

Cylinder Number : ALM016861
Cylinder Pressure + : 1900 psig

Certificate Date : 1/27/95
Previous Certificate Date : None

Expiration Date : 1/27/98

ANALYZED CYLINDER

Components
Propane

Certified Concentration
475.3 ppm

Analytical Uncertainty*
±1% NIST Directly Traceable

Balance Gas: Air

Do not use when cylinder pressure is below 150 psig.

Analytical accuracy is inclusive of usual known error sources which at least include precision of the measurement processes.

REFERENCE STANDARD

Type
NTRM 1668

Expiration Date
6/7/96

Cylinder Number
ALM-032015

Concentration
95.5 ppm Propane in Air.

INSTRUMENTATION

Instrument/Model/Serial #
Beckman/400/1002059

Last Date Calibrated
1/19/95

Analytical Principle
Flame Ionization Detection

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components
Propane

First Triad Analysis

Date: 1/27/95 Response Units: mv
Z1=0.00 R1=14.40 T1=71.30
R2=14.40 Z2=0.00 T2=71.30
Z3=0.00 T3=71.30 R3=14.40
Avg. Conc. of Cust. Cyl. 475.3 ppm

Second Triad Analysis

Calibration Curve

Concentration = $A + Bx + Cx^2 + Dx^3 + Ex^4$
r = 1.00000 NTRM 1668
Constants: A = -0.237940000
B = 6.669000000 C = 0.000000000
D = 0.000000000 E = 0.000000000

Special Notes


Analyst



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(810) 589-2950 FAX: (810) 589-2134

90.46 Propane

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer

ENVIRONMENTAL MON
242 INGLESIDE DRIVE
MADISON, MS 39110

Assay Laboratory

Scott Specialty Gases, Inc
1290 Combermere
Troy, MI 48083

Purchase Order : DRV0116

Scott Project # : 576120

ANALYTICAL INFORMATION

This certification was performed according to EPA Traceability Protocol For Assay and Certification of Gaseous Calibration Standards; Procedure G1; September, 1993.

Cylinder Number : ALM016008

Certificate Date : 1/27/95

Expiration Date : 1/27/98

Cylinder Pressure + : 1900 psig

Previous Certificate Date : None

ANALYZED CYLINDER

Components

Propane

Certified Concentration

90.46 ppm

Analytical Uncertainty*

±1% NIST Directly Traceable

Balance Gas: Air

*Do not use when cylinder pressure is below 150 psig.

Analytical accuracy is inclusive of usual known error sources which at least include precision of the measurement processes.

REFERENCE STANDARD

Type

NTRM 1668

Expiration Date

6/7/96

Cylinder Number

ALM-032015

Concentration

95.5 ppm Propane in Air

INSTRUMENTATION

Instrument/Model/Serial

Propane : Beckman/400/1002059

Last Date Calibrated

1/19/95

Analytical Principle

Flame Ionization Detector

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components

Propane

First Triad Analysis

Date: 1/27/95 Response Units: mv
Z1=0.00 R1=95.50 T1=90.50
R2=95.50 Z2=0.00 T2=90.40
Z3=0.00 T3=90.50 R3=95.50
Avg. Conc. of Cust. Cyl. 90.46 ppm

Second Triad Analysis

Calibration Curve

Concentration = $A + Bx + Cx^2 + Dx^3 + Ex^4$
 $r = 1.00000$ NTRM 1668
Constants: $A = -0.086524000$
 $B = 1.000900000$ $C = 0.000000000$
 $D = 0.000000000$ $E = 0.000000000$

Special Notes

Analyst

2410 NOx



Scott Specialty Gases, Inc.

500 WEAVER PARK ROAD, LONGMONT, CO 80501 (303) 442-4700, (303) 651-3094 FAX (303) 772-7673

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer
ENVIRONMENTAL MONITORING
242 INGLESIDE DRIVE
MADISON, MS 39110

Assay Laboratory
Scott Specialty Gases, Inc.
500 Weaver Park Road
Longmont, CO 80501

Purchase Order DRV0826
Scott Project # 0815606
CGA Fitting 660
QC Number 11039435
File Number 15606-01

ANALYTICAL INFORMATION

This analysis was performed according to EPA-Traceability Protocol to Assay and certification of Gaseous Calibration Standards; Procedure G1; September, 1993.

Cylinder Number ALM-043125 Certification Date 08/30/94 Expiration Date 08/30/96
Cylinder Pressure 2000 psig Previous Certification Dates None

ANALYZED CYLINDER

Components (Nitric Oxides)	Certified Concentration 2400 ppm 2410 ppm Balance
-------------------------------	--

Analytical Uncertainty*
+1% NIST Directly Traceable
Reference Value Only

*Analytical uncertainty is inclusive of usual known error sources which at least include precision of the measurement processes.

REFERENCE STANDARD

Type NTRM 2631 GMS	Expiration Date 06/18/95 NONE	Cylinder Number ALM-022283 AAL-19328	Concentration 2814.0ppm NO / N2 2170.0ppm NO / N2
--------------------------	-------------------------------------	--	---

INSTRUMENTATION

Instrument/Model/Serial # Monitor Labs 8840-857	Last Date Calibrated 08/22/94	Analytical Principle Chemiluminescence
--	----------------------------------	---

ANALYZER READINGS

(Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components
(Nitric Oxides)

First Triad Analysis

Date: 12/22/93 Response Units: mv
Z1 = 0.0000 R1 = 0.4316 T1 = 0.4785
R2 = 0.4316 Z2 = 0.0000 T2 = 0.4785
Z3 = 0.0000 T3 = 0.4785 R3 = 0.4316
Avg. Conc. of Cust. Cyl. = 2401.1 ppm

Second Triad Analysis

Date: 08/30/94 Response Units: mv
Z1 = 0.0000 R1 = 0.4316 T2 = 0.4786
R2 = 0.4316 Z2 = 0.0000 T2 = 0.4786
Z3 = 0.0000 T3 = 0.4786 R3 = 0.4316
Avg. Conc. of Cust. Cyl. = 2401.6 ppm

Calibration Curve

Concentration = A+Bx+Cx+Dx+Ex
r = 0.999997 NTRM 2631
Constants: A = -11.764180
B = 5151.8800 C = -232.7234
D = 0 E = 0

Special Notes

Do not use when cylinder pressure is below 150 psig.

Diana L. Beehler
Analyst: Diana L. Beehler



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(810) 589-2950 FAX: (810) 589-2134

102.0NOx

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer
ENVIRONMENTAL MONITORING
242 INGLESIDE DRIVE
MADISON, MS 39110

Assay Laboratory
Scott Specialty Gases, Inc
1290 Combermere
Troy, MI 48083

Purchase Order : DRV0826
Scott Project # : 570523

ANALYTICAL INFORMATION

This certification was performed according to EPA Traceability Protocol For Assay and Certification of Gaseous Calibration Standards; Procedure G1; September, 1993.

Cylinder Number : ALM036349
Cylinder Pressure + : 1900 psig

Certificate Date : 8/30/94
Previous Certificate Date : None

Expiration Date : 8/30/96

ANALYZED CYLINDER

Components
Nitric Oxide
Total Oxides of Nitrogen

Certified Concentration
99.90 ppm
102.0 ppm

Analytical Uncertainty*
±1% NIST Directly Traceable
Reference Value Only

Balance Gas: Nitrogen

*Do not use when cylinder pressure is below 150 psig.

*Analytical accuracy is inclusive of usual known error sources which at least include precision of the measurement processes.

REFERENCE STANDARD

Type
NTRM 1684

Expiration Date
4/1/96

Cylinder Number
ALM-024582

Concentration
95.2 ppm Nitric Oxide in Nitrogen

INSTRUMENTATION

Instrument/Model/Serial #
NO Horiba/OPE-235/483814

Last Date Calibrated
8/24/94

Analytical Principle
Chemiluminescence

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components
Nitric Oxide

First Triad Analysis

Date: 3/28/94 Response Units: mv
Z1=0.00 R1=95.20 T1=99.80
R2=95.20 Z2=0.00 T2=99.80
Z3=0.00 T3=99.80 R3=95.20
Avg. Conc. of Cust. Cyl: 99.80 ppm

Second Triad Analysis

Date: 8/30/94 Response Units: mv
Z1=0.00 R1=95.20 T1=100.00
R2=95.20 Z2=0.00 T2=100.00
Z3=0.00 T3=100.00 R3=95.20
Avg. Conc. of Cust. Cyl: 100.0 ppm

Calibration Curve

Concentration = $A \cdot Bx + Cx^2 + Dx^3 + Ex^4$
r=0.99999 NTRM 1684
Constants: A=0.000000000
B=1.000000000 C=0.000000000
D=0.000000000 E=0.000000000

Special Notes

Don E. [Signature]
Analyst



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48063

(313) 589-2950 FAX: (313) 589-2134

12.90 NOx

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer
ENVIROMENTAL MONITORING
242 INGLESIDE DRIVE
MADISON MS 39110

Assay Laboratory
Scott Specialty Gases, Inc.
1290 Combermere
Troy, MI 48083

Purchase Order 0630DR
Scott Project # 553186

ANALYTICAL INFORMATION

Certified to exceed the minimum specifications of EPA Protocol 1 Procedure # G1, Section Number 3.0.4

Cylinder Number ALM022478
Cylinder Pressure 1900 psig

Certification Date 7-19-93
Previous Certification Dates None

General Exp. Date 7-19-95
Acid Rain Exp. Date 7-19-95

ANALYZED CYLINDER

Components
Nitric Oxide

Certified Concentration
12.90 ppm

Analytical Uncertainty*
±1% NIST Directly Traceable

Total Oxides of Nitrogen
Balance Gas: Nitrogen

12.90 ppm

Reference Value Only

*Analytical uncertainty is inclusive of usual known error sources which at least includes reference standard error & precision of the measurement processes.

REFERENCE STANDARD

Type SRM 2629A
Expiration Date 1-4-95

Cylinder Number
FF-28502

Concentration
19.40 ppm NO in N₂

INSTRUMENTATION

Instrument/Model/Serial #
NO: Horiba/OPE-235/560543082

Last Date Calibrated
5-18-93

Analytical Principle
Chemiluminescence

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components

First Triad Analysis

Second Triad Analysis

Calibration Curve

Nitric Oxide

Date: 7-11-93 Response Units: mv
Z1=0.00 R1=19.40 T1=12.90
R2=19.40 Z2=0.00 T2=12.90
Z3=0.00 T3=12.90 R3=19.40
Avg. Conc. of Cust. Cyl. 12.90 ppm

Date: 7-19-93 Response Units: mv
Z1=0.00 R1=19.40 T1=12.90
R2=19.40 Z2=0.00 T2=12.90
Z3=0.00 T3=12.90 R3=19.40
Avg. Conc. of Cust. Cyl. 12.90 ppm

Concentration=A+Bx+Cx²+Dx³+Ex⁴
r=0.99999 SRM 2629A
Constants: A=0.01381712
B=0.9992878 C=0
D=0 E=0

Concentration=A+Bx+Cx²+Dx³+Ex⁴

Concentration=A+Bx+Cx²+Dx³+Ex⁴

Special Notes

If this product is used for Acid Rain Rule Compliance, the Acid Rain Expiration Date noted above applies per 40 CFR Part 75, Appendix H. Otherwise, the General Expiration Date applies.

F. P. Doran
Analyst Frank P. Doran



Scott Specialty Gases, Inc.

PAGE 1

Shipped
From:3714 LAPAS DRIVE
HOUSTON
Phone: 713-644-4820

TX 77023

Fax: 713-644-0244

CERTIFICATE OF ANALYSIS

ENVIRONMENTAL MONITORING
DANNY RUSSELL
P O BOX 655PROJECT #: 04-43368-001
PO#: DRV0517
ITEM #: 04024315 2AL
DATE: 5/26/95

RIDGELAND

MS 39158

CYLINDER #: ALM055984

ANALYTICAL ACCURACY: +/- 1%
PRODUCT EXPIRATION: 5/24/96

BLEND TYPE : ACUBLEND MASTER GAS

COMPONENTCARBON MONOXIDE
OXYGEN
NITROGENREQUESTED GASCONC MOLES

452. PPM

11. %

BALANCE

ANALYSIS(MOLES)


453. PPM

11.01 %

BALANCE

2000 PSI

V53

THIS PRODUCT IS TRACEABLE TO
DOCUMENTATION BY BOTH THE
NUMBERS IDENTIFIED ON THISALL PRODUCTION & ANALYTICAL
PROJECT & CYLINDER SERIAL
CERTIFICATE OF ANALYSIS.ANALYST: PLUMSTEADVILLE, PENNSYLVANIA / TROY, MICHIGAN / HOUSTON, TEXAS / DURHAM, NORTH CAROLINA
SOUTH PLAINFIELD, NEW JERSEY / FREMONT, CALIFORNIA / WAKEFIELD, MASSACHUSETTS / LONGMONT, COLORADO
BATON ROUGE, LOUISIANA



Scott Specialty Gases, Inc.

Shipped From: 3714 LAPAS DRIVE
HOUSTON TX 77023
Phone: 713-644-4820 Fax: 713-644-0244

CERTIFICATE OF ANALYSIS

ENVIRONMENTAL MONITORING
DAN RUSSELL
P O BOX 655

PROJECT #: 04-29381-003
PO#: DRV-0107
ITEM #: 04021453 2AL
DATE: 1/11/94

RIDGELAND MS 39158

CYLINDER #: ALM007930 ANALYTICAL ACCURACY: +/- 1%
FILL PRESSURE: 2000 PSI PRODUCT EXPIRATION: 1/11/95
BLEND TYPE : ACUBLEND MASTER GAS

COMPONENT


CARBON MONOXIDE
NITROGEN


REQUESTED GAS

CONC MOLES
4,500. PPM
BAL

ANALYSIS

(MOLES)
4,540. PPM
BAL

ANALYST: 

APPROVED BY: 

PLUMSTEADVILLE, PENNSYLVANIA / TROY, MICHIGAN / HOUSTON, TEXAS / DURHAM, NORTH CAROLINA
SOUTH PLAINFIELD, NEW JERSEY / FREMONT, CALIFORNIA / WAKEFIELD, MASSACHUSETTS / LONGMONT, COLORADO
BATON ROUGE, LOUISIANA



Scott Specialty Gases, Inc.

Shipped
From:

3714 LAPAS DRIVE
HOUSTON
Phone: 713-644-4820

TX 77023

Fax: 713-644-0244

C E R T I F I C A T E O F A N A L Y S I S

ENVIRONMENTAL MONITORING
DANNY RUSSELL
P O BOX 655

PROJECT #: 04-39907-002
PO#: DRV0116
ITEM #: 04024520 2AL
DATE: 1/27/95

RIDGELAND

MS 39158

CYLINDER #: AAL19761

ANALYTICAL ACCURACY: +/-1%
PRODUCT EXPIRATION: 1/27/96

BLEND TYPE : ACUBLEND MASTER GAS

COMPONENT

CARBON DIOXIDE
CARBON MONOXIDE
OXYGEN
NITROGEN

REQUESTED GAS CONC MOLES

12. %
955. PPM
3. %
BALANCE

ANALYSIS (MOLES)

12.08 %
953. PPM
3.03 %
BALANCE

2000 PSI

THIS PRODUCT IS TRACEABLE TO
DOCUMENTATION BY BOTH THE
NUMBERS IDENTIFIED ON THIS

ALL PRODUCTION & ANALYTICAL
PROJECT & CYLINDER SERIAL
CERTIFICATE OF ANALYSIS.


ANALYST:

PLUMSTEADVILLE, PENNSYLVANIA / TROY, MICHIGAN / HOUSTON, TEXAS / DURHAM, NORTH CAROLINA
SOUTH PLAINFIELD, NEW JERSEY / FREMONT, CALIFORNIA / WAKEFIELD, MASSACHUSETTS / LONGMONT, COLORADO
BATON ROUGE, LOUISIANA

APPENDIX C.

INSTRUMENT RECORDER TRACES/DATA LOG

OUTLET NO_x AND CO TRACE



5/31/95

L.R. - New WARELY RTO 0100

L to R = 0 - 1000 ppm C.D

R to L = 0 - 100 ppm NO

Chart = 2.0 cm/hr

START R.I.
@ 0100 @ 0933

- Composite of inlet sample

← Composite to outlet


END @ 1045
R.I.

PART NO. 107601

PRINTED IN U.S.A.

PART NO. LO/501


PRINTED IN U.S.A.



PART NO. LD/608


PRINTED IN U.S.A.

PART NO. LD/608




PART NO. 10/9011

PRINTED IN U.S.A.




INLET NO_x AND CO TRACE



PRINTED IN U.S.A.

SUFFALO, NEW YORK

GRAPHIC CONTROLS CORPORATION



STAFF R2
1206

30 000

END R1
© 10/5

BUFFALO, NEW YORK
DRAWING CONTROLS CORPORATION
CHART NO. 106 2045 13

N. USA

1250cm

1260cm

1270cm

1280cm





CHART NO. 105 3043-13

PRINTED IN U.S.A.

BUFFALO, NEW YORK




INLET AND OUTLET VOC TRACE

PART NO. LO/800

PRINTED IN U.S.A.

PART NO. LO/800


PRINTED IN U.S.A.



PART NO. LO/801

PRINTED IN U.S.A.

IT NO. LO/801



PART NO. LO/BDH

PRINTED IN U.S.A.

LINEIS

LS-PM C₁Ap

6/1/85


END DAY

START Run B @ 0854

on 6/1/85

PART NO. LO/001

PRINTED IN U.S.A.



START R6
@ 1030

520pm
435pm


END R5
1.6 mm

112 115

START R6 @ 0854

on 6/1/95

PRINTED IN U.S.A.



APPENDIX D.

HCHO ANALYSIS REPORT (OXFORD LABS)



Analytical and Consulting Chemists

1316 South Fifth Street
Wilmington, N.C. 28401
(910) 763-9793
Fax (910) 343-9688

DATE RECEIVED 06-06-95
DATE REPORTED 06-12-95
95W7216

PAGE 1 OF 2

ENVIRONMENTAL MONITORING
242 INGLE SIDE DR.
MADISON, MS 39110

P.O. # DR0604

ATTENTION: DANNY RUSSELL

SAMPLE DESCRIPTION: 10 FORMALDEHYDE

1. LPNR1 (R4)
2. LPNR2 (R5)
3. LPNR3 (R6)
4. LPNNR1 (R4)
5. LPNNR2 (R5)
6. LPNNR3 (R6)

RESULTS

	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
Formaldehyde, as HCHO, Total ug	769	938	750	8380	18300	9250



Analytical and Consulting Chemists

1316 South Fifth Street
Wilmington, N.C. 28401
(910) 763-9793
Fax (910) 343-9688

DATE RECEIVED 06-06-95
DATE REPORTED 06-12-95
95W7216

PAGE 2 OF 2

ENVIRONMENTAL MONITORING
242 INGLE SIDE DR.
MADISON, MS 39110

P.O. # DR0604


ATTENTION: DANNY RUSSELL

SAMPLE DESCRIPTION: 10 FORMALDEHYDE

- 7. LPC R1
- 8. LPC R2
- 9. LPC R3
- 10. BLANK

RESULTS

	<u>7</u>	<u>8</u>	<u>9</u>	<u>10</u>
Formaldehyde, as HCHO, Total ug	2480	2870	1490	37.9


ANN MCMILLAN, ANALYST

CHAIN OF CUSTODY AND REQUEST FOR ANALYSIS

PAGE 1 OF 1

ENVIRONMENTAL MONITORING LABORATORIES
POST OFFICE BOX 655
RIDGELAND, MISSISSIPPI 39158

Laboratory:

Oxford Labs

PHONE: 601/856-3092
FAX: 601/853-2151

Attention: Danny Russell

Please return copy of chain of custody with analytical report

Attention:

EML PO No. DR 0604

Project: Louisiana Pacific New Urethane, Texas
and Louisiana Pacific Corrigan, Texas

Rush ☐

Routine ☒

Fax Results ☒

ANALYSES REQUESTED

HCOH - Method 0011

No. of Containers	SAMPLE ID	Sample matrix	REMARKS	UNITS
1	LPN R1	Aqueous DNPH	✓	
1	LPN R2	"	✓	
1	LPN R3	"	✓	
1	LPN NR1	"	✓	
1	LPN NR2	"	✓	
1	LPN NR3	"	✓	
1	LPC R1	"	✓	
1	LPC R2	"	✓	
1	LPC R3	"	✓	
1	Blank	"	✓	

Relinquished by: (print name; initial)

Daniel G. Russell

Date/time

6/5/95

Received by: (print name; initial)

Date/time

Received by: (print name; initial)

Date/time

Received by: (print name; initial)

Date/time

Relinquished by: (print name; initial)

Date/time

Received for lab by:

Date/time

COURIER

Date Shipped

Federal Express

Mary Coxsteln

6/6/95 10:00

NEW WAVERLY TEXAS OSB STACK TEST OPERATIONAL SUMMARY

05/31/95

DRYER R-T-O

PM CO, NOx

DRYER 1

Dry Furnish
Moisture (%)

6.6 - 10.0

8.3

Inlet Temp.
(°F)

715 - 1087

901

Outlet Temp.
(°F)

165 - 280

223

Production
(lbs/hr)

15,480

7.7 0074

CONTINUOUS PRESS*

Press
Temp. (°F)

428

Thickness
(in)

0.438**

Density
(nominal, lbs/cu ft)

41

PRODUCTION (Finished 3/8 in basis)

8,236 ft²/hr ***
10,552 lbs/hr

*No press stack samples were collected per accepted sampling protocol - currently no control on press emissions.

**Nominal Thickness = 7/16 inch

***Annualized Production of 72,147,360 ft² 3/8 basis (8760 hrs)

NEW WAVERLY TEXAS OSB STACK TEST OPERATIONAL SUMMARY

06/01/95

DRYER R-T-O

DRYER 1

Dry Furnish Moisture (%)	4.2 - 8.5	6.4
Inlet Temp. (°F)	737 - 1026	892
Outlet Temp. (°F)	164 - 205	195
Production (lbs/hr)	18,300	9.2 0074

CONTINUOUS PRESS*

Press Temp. (°F)	428
Thickness (in)	0.438**
Density (nominal, lbs/cu ft)	41

PRODUCTION (Finished 3/8 in basis) 9,045 ft²/hr ***
11,589 lbs/hr

*No press stack samples were collected per accepted sampling protocol - currently no control on press emissions.

**Nominal Thickness = 7/16 inch

***Annualized Production of 79,234,200 ft² 3/8 basis (8760 hrs)