

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

#45

Interpoll Laboratories, Inc.
4500 Ball Road N.E.
Circle Pines, Minnesota 55014-1819

4-716

TEL: (612) 786-6020
FAX: (612) 786-7854



**RESULTS OF THE JUNE 1993
AIR EMISSION TESTS AT TWO
LOUISIANA PACIFIC
WAFERBOARD PLANTS**

Submitted to:

ICI POLYURETHANES GROUP
286 Mantua Grove Road
West Deptford, New Jersey 08066-1732

Attention:

Bill Karoly

Prepared Under the Supervision of:

A handwritten signature in dark ink, appearing to read "Daniel J. Despen".

Daniel J. Despen
Manager
Stationary Source Testing Department

Report Number 3-9202
September 2, 1993
DD/djd

TABLE OF CONTENTS

	ABBREVIATIONS	iii
1	INTRODUCTION	1
2	MDI SAMPLING AND ANALYTICAL RESULTS	4
3	SUMMARY AND DISCUSSION	7

APPENDICES:

- A - Results - Sagola
- B - Results - Two Harbors
- C - Field Data Sheets
- D - Interpoll Laboratories Analytical Results
- E - Process Information
- F - Sampling Train Calibration Data

1 INTRODUCTION

During June 1993 Interpoll Laboratories personnel conducted a series of air emission measurements on the Press and Unloader Vents at the Louisiana Pacific Corporation (LP) Waferboard Plants located in Sagola, Michigan and Two Harbors, Minnesota. These tests were performed on behalf of ICI Polyurethanes (ICI) to characterize various emissions from the board press vents when using a 4,4-methylene bis(phenylisocyanate) (MDI) based resin. Emission tests were performed for MDI, particulates, phenol, formaldehyde, and total hydrocarbons. On-site testing was performed by D. Van Hoeve, G. Hove, J. Bergstrom and S. Ertle. Coordination between testing activities and plant operation was provided by Mark Baker and Bill Karoly of ICI.

The primary objective of these tests was to characterize MDI emissions from board press vents and to compare the efficiency of the four MDI methodologies under real world conditions. Four different sampling trains and/or analytical methods for MDI were used in this work:

1. Nitro reagent-impregnated filters following an Interpoll Labs modification of NIOSH Method 347 (Interpoll Labs Method II-8791) with analysis by normal-phase HPLC.
2. Nitro reagent-impregnated filters following Interpoll Labs modification of of NIOSH Method 347 with analysis after solvent exchange by reverse-phase HPLC.
3. 1,2-MP-impregnated filters followed by two impingers containing 1,2-MP in dry toluene with analysis after solvent exchange by reverse-phase HPLC.
4. 1,2-MP in dry toluene in first two impingers followed by a 1,2-MP-impregnated filter with analysis after solvent exchange by reverse-phase HPLC.

The trains were modified (as described above) Method 5 sampling trains. Samples were collected isokinetically with the filters and probes at ambient temperature. The impingers were immersed in a water/salt bath which gave an unstirred temperature of 32-34°F. A special activated charcoal assembly was used after the third impinger (trap) to adsorb

volatilized toluene. Each sample was collected over a sixty minute period using a standard EPA Method 1 particulate traverse procedure.

The press vents tested are the exhaust from general ventilators positioned over the board press and/or unloader areas. The Press and Unloader vents at Sagola are combined and exhaust through a common stack which is 72 inches in diameter. The Press and Unloader vents at the Two Harbors facility each have their own 55-inch square stacks.

Particulate evaluations were performed in accordance with EPA Methods 2-5, CFR Title 40, Part 60, Appendix A (revised July 1, 1992). A preliminary determination of the gas linear velocity profile was made before the first particulate determination to allow selection of the appropriate nozzle diameter for isokinetic sample withdrawal. An Interpoll Labs sampling train which meets or exceeds specifications in the above-cited reference was used to isokinetically extract particulate samples by means of a heated glass-lined probe.

Phenol samples were collected in the back half of the Method 5 sampling train using a neutral-buffered absorbing reagent. The samples were extracted with methylene chloride and analyzed by direct injection GC/MS with no preconcentration. The GC/MS analysis was performed as per EPA Method 8270 (SW 846).

Formaldehyde samples were collected in accordance with EPA Method 0011 (SW 846 3rd Ed.) as requested by ICI. The samples were collected isokinetically using a Method 5 sampling train with an aqueous acidic 2,4-dinitrophenylhydrazine absorbing solution and analyzed by reverse-phase HPLC.

Total gaseous hydrocarbon concentrations were determined instrumentally in accordance with EPA Method 25A using a Ratfisch Model RS55 heated flame ionization detector (HFID) calibrated against propane in air standards. The THC concentration was continuously monitored by extracting a slipstream of exhaust gas by means of a heated probe and filter holder. A heat-traced teflon line was used to transport the sample gas from the filter holder outlet to the analyzer inlet.

Testing on the Press and Unloader Vent at the Sagola plant was conducted from two test ports oriented at 90 degrees on the combined stack. A 24-point traverse was used to

isokinetically collect representative particulate, phenol, formaldehyde and MDI samples. Each traverse point was sampled 2.5 minutes for a total sampling time of 60 minutes per run.

Testing on the Press and Unloader Vents at Two Harbors was conducted from horizontal rows of four test ports on each stack. 24-point traverses were used to isokinetically collect representative particulate, phenol, formaldehyde and MDI samples. Each point was sampled for 2.5 minutes for a total of 60 minutes per run.

The important results of the test are summarized in Section 2. Detailed results are presented in Section 3. Other supporting information is presented in the appendices.

2 MDI SAMPLING AND ANALYTICAL RESULTS

The results of all of the MDI samplings and analyses together with blanks, audits and field spikes are presented in tabular form. As will be noted, the Interpoll Laboratories Method II-8791 which is based on the use of quartz filters impregnated with N-p-nitrobenzyl-N-propylamine (Nitro Reagent) for collection with analysis by normal phase HPLC gave the highest results and probably the most accurate estimates of MDI. Four Nitro Reagent filters were spiked with MDI at the 100 or 250 ug level (using a technique which ensures that the MDI is uniformly distributed over the entire filter surface) and recovered with the other Nitro Reagent MDI field samples. The results of these recoveries fall within the acceptable range for trace organics (76, 78, 115 and 117%).

In cases where other organics are present in the gas stream, a higher resolution chromatographic separation is preferable. In this study, the Nitro Reagent samples were split, solvent exchanged and also analyzed by reverse phase HPLC which is inherently more efficient in resolving organic compounds in this boiling point range. The results of the reverse phase HPLC are in excellent agreement, in this case, with the results of the normal phase determinations. All but two of the reverse-phase results are less than the normal phase results but too few data are in hand to suggest a statistically significant difference in the two methods. From a theoretical standpoint, the reverse phase analytical method should be the more definitive of the two separations and therefore capable of producing the most accurate and precise data.

The results of the MDI samplings and analyses using N-1,2-methoxyphenyl piperazine (1,2-MP) as a collecting and derivatizing agent are quite inconsistent. Recoveries of filter spikes and impinger spikes are similarly inconsistent suggesting a recovery problem and/or an interference problem. Recovery from filters is extremely poor. Recovery of impinger spikes is better but equally inconsistent. It may be difficult to recover the 1,2-MP urea derivative with toluene, especially since toluene does not wet those surfaces wetted with water. Similar experience in dioxin recoveries from water-wetted XAD-2 resin showed that methanol or acetone rinses and/or extractions were required to dry the resin prior to extraction with toluene. The acetone or methanol was then volatilized; the aqueous residue extracted with methylene chloride; the methylene chloride evaporated and the residue combined with the toluene extract. A similar approach can be imagined for the 1,2-MP urea

adduct which may grossly improve its recovery. Solubility of the urea adduct may also play a role but the occasional presence of several very high masses of MDI (192, 235, 294, and 340 ug) seems to suggest otherwise.

In conclusion it can be safely stated that the Nitro Reagent based sampling and analytical methods outperformed the 1,2-MP based sampling and analytical methods and that additional laboratory work needs to be performed before the 1,2-MP approach can be further field evaluated. It is recommended that a sufficiently large quantity of 1,2-MP urea adduct be synthesized, purified and its physical properties accurately characterized so that an appropriate recovery procedure can be chosen.

RESULTS OF HPLC ANALYSES OF 4,4'-METHYLENEBIS(PHENYL ISOCYANATE)

MDI (ug)

PLANT/SOURCE	TEST/RUN	TRAIN N				LOG #	SPIKE	DETECT	LIMIT
		LOG #	AMOUNT	DETECT	NORMAL				
				LIMIT	PHASE		AMOUNT	AMOUNT	PHASE
SAG/P&U	6/S	9202-67	100	6.5	86	97	9202-25	100	
SAG/P&U	6/S	9202-68	250	13	295	324	9202-26	250	
SAG/P&U	6/S						9202-27	500	
SAG/P&U	6/S						9202-28	1000	
SAG/P&U	6/O-1	9202-69		13	BDL	BDL	9202-49		
SAG/P&U	6/O-2						9202-53		
SAG/P&U	6/1	9202-70		20	207	226	9202-55		
SAG/P&U	6/2	9202-71		13	220	250	9202-59		
SAG/P&U	6/3	9202-72		13	287	288	9202-63		
2HB/P	7/S	9289-40	100	6.5	76	78	9289-136	100	
2HB/P	7/S	9289-41	250	13	288	279	9289-137	250	
2HB/P	7/S						9289-57	500	
2HB/P	7/S						9289-58	1000	
2HB/P	7/O-1	9289-42		13	BDL	BDL	9289-47		
2HB/P	7/O-2	9289-43		13	BDL	BDL	9289-51		
2HB/P	7/1	9289-44		13	1580	1510	9289-61		
2HB/P	7/2	9289-45		13	1350	1250	9289-65		
2HB/P	7/3	9289-46		20	1560	1530	9289-69		
2HB/U	10/S	9289-97	100	6.5	78	89	9289-112	100	
2HB/U	10/S	9289-98	250	13	292	310	9289-113	250	
	10/S						9289-83	500	
	10/S						9289-84	1000	
2HB/U	10/O-1	9289-99		13	BDL	BDL	9289-104		
2HB/U	10/O-2	9289-100		13	BDL	BDL	9289-108		
2HB/U	10/1	9289-101		13	1080	1040	9289-116		
2HB/U	10/2	9289-102		20	802	790	9289-120		
2HB/U	10/3	9289-103		13	1170	1090	9289-124		
ICI Audit -Sagola			ICI # 7051-198A				9202-29	295	
ICI Audit -Sagola			ICI # 7051-198B				9202-30	177	
CI Audit - 2 Harb			ICI # 7051-205B				9289-59	177	
CI Audit - 2 Harb			ICI # 7051-205A				9289-60	295	

NOTES:

I = Spike

P&U = Press & Unloader Vent Stack

P = Press Vent Stack

U = Unloader Vent Stack

SAG = Louisiana Pacific Plant in Sagola, Michigan

2HB = Louisiana Pacific Plant in Two Harbors, Minnesota

TRAIN N = Nitro Reagent Modified NIOSH Method P&CAM 347

RAIN F = 1,2-MP Reagent ; Filter first

L = 1,2-MP Reagent ; Filter Last

[illegible][illegible]

[illegible][illegible]

3 SUMMARY AND DISCUSSION

No difficulties in performing the particulate, phenol, formaldehyde and total hydrocarbons determinations were encountered in the field by Interpoll Labs or in the laboratory evaluation of the samples. On the basis of this fact and a complete review of the data and results, it is our opinion that the results for the determinations reported below are accurate and closely reflect the actual values which existed at the time the test was performed.

In the case of the MDI determinations, the results of the MDI determinations performed using Interpoll Labs Method II-8791 were viewed as the accurate of the four sampling and analytical methods performed and only these values have been converted and reported as exhaust gas concentrations.

The particulate results for the Sagola facility are summarized in Table 1, for the Two Harbors facility in Tables 2 and 3. The average particulate emission rate for the combined Press and Unloader Vent at the Sagola Plant was 6.87 LB/HR. The Press Vent and Unloader Vent at the Two Harbors Plant averaged 2.53 LB/HR and 3.21 LB/HR of particulate.

The results of the phenol determinations are summarized in Table 4, and 5 for the Sagola and Two Harbors facilities respectively. The phenol emission rate averaged 0.001 LB/HR for the combined Press and Unloader Vent at Sagola and 0.0002 LB/HR for the Press Vent, and 0.0001 LB/HR for the Unloader Vent at Two Harbors.

Formaldehyde results are summarized in Tables 6 and 7. Note that the formaldehyde emission rate averaged 0.29 LB/HR for the combined Press and Unloader Vent at Sagola and 0.54 LB/HR at the Press Vent and 0.47 LB/HR for the Unloader Vent at the Two Harbors facility.

The THC results are summarized in Tables 8 and 9. The average THC emission rates for the three sources tested are: 4.19, 0.74 and 0.69 LB/HR for the combined Press and Unloader Vent at Sagola, the Press Vent and the Unloader Vent at Two Harbors respectively.

The MDI concentrations and emission rates for the Two Harbors and Sagola facilities are summarized in Tables 8 and 9 respectively. Note that only the Interpoll Labs Method II-8791 results have been reported here. The average MDI emission rate from the Press and Unloader Vent at the Sagola Plant was 0.070 LB/HR. The average MDI emission rates for the Press vent and Unloader Vent at the Two Harbors Plant were 0.19 and 0.13 LB/HR respectively.

Table 1. Summary of the Results of the June 25, 1993 Particulate Emission Compliance Test on the Press & Unloader Vent Stack at the Louisiana Pacific Plant Located in Sagola, Michigan.

ITEM	Run 1	Run 2	Run 3
Date of test	06-25-93	06-25-93	06-25-93
Time runs were done (HRS)	944/1048	1158/1205	1336/1440
Process rate			
Volumetric flow actual (ACFM) standard (DSCFM)	135792 116269	141731 121332	146850 126152
Gas temperature (DEG-F)	99	99	102
Moisture content (%V/V)	2.52	2.46	1.69
Gas composition (%V/V, dry) carbon dioxide oxygen nitrogen	0.03 20.90 79.07	0.03 20.90 79.07	0.03 20.90 79.07
Isokinetic variation (%)	101.2	101.4	100.7
Particulate concentration actual (GR/ACF) standard (GR/DSCF)	.00637 .00744	.00524 .00612	.00543 .00632
Part. emission rate (LB/HR)	7.42	6.36	6.84

Note: Dry Catch Only

Table 2. Summary of the Results of the June 29, 1993 Particulate Emission Compliance Test on the Press Vent Stack at the Louisiana Pacific Plant in Two Harbors, Minnesota.

ITEM	Run 1	Run 2	Run 3
Date of test	06-29-93	06-29-93	06-29-93
Time runs were done (HRS)	1322/1423	1448/1549	1617/1629
Process rate			
Volumetric flow actual (ACFM)	39395	39828	40501
standard (DSCFM)	35735	35735	36784
Gas temperature (DEG-F)	98	98	96
Moisture content (%V/V)	1.48	1.92	1.73
Gas composition (%V/V, dry)			
carbon dioxide	0.03	0.03	0.03
oxygen	20.90	20.90	20.90
nitrogen	79.07	79.07	79.07
Isokinetic variation (%)	99.9	99.1	100.1
Particulate concentration			
actual (GR/ACF)	.00641	.00803	.00770
standard (GR/DSCF)	.00706	.00896	.00849
Part. emission rate (LB/HR)	2.16	2.74	2.68

Note: Dry Catch Only

Table 3. Summary of the Results of the June 29, 1993 Particulate Emission Compliance Test on the Unloading Vent Stack at the Louisiana Pacific Plant in Two Harbors, Minnesota.

ITEM	Run 1	Run 2	Run 3
Date of test	06-29-93	06-29-93	06-29-93
Time runs were done (HRS)	822/ 922	957/1059	1134/1237
Process rate			
Volumetric flow actual (ACFM)	46664	44356	42856
standard (DSCFM)	43354	41027	39544
Gas temperature (DEG-F)	86	88	90
Moisture content (%V/V)	1.40	1.53	1.38
Gas composition (%V/V, dry)			
carbon dioxide	0.03	0.03	0.03
oxygen	20.90	20.90	20.90
nitrogen	79.07	79.07	79.07
Isokinetic variation (%)	99.2	100.0	99.9
Particulate concentration			
actual (GR/ACF)	.0101	.00822	.00663
standard (GR/DSCF)	.0109	.00889	.00719
Part. emission rate (LB/HR)	4.06	3.13	2.44

Note: Dry Catch Only

Table 4. Summary of the June 25, 1993 Phenol Determinations on the Press & Unloader Vent at the Louisiana Pacific Waferboard Plant in Sagola, Michigan.

Time (HRS)	Volumetric Flow Rate (DSCFM)	Concentration (ppb,d)	Emission Rate (LB/HR)
0944-1048	116300	0.58	0.00098
1158-1205	121300	0.59	0.00104
1336-1440	126200	0.57	0.00105
Avg.		0.58	0.00102

Table 5. Summary of the June 29, 1993 **Phenol** Determinations on the Press and Unloader Vents at the Louisiana Pacific Waferboard Plant in Two Harbors, Minnesota.

Time (HRS)	Volumetric Flow Rate (DSCFM)	Concentration (ppb.d)	Emission Rate (LB/HR)
Press Vent			
1322-1423	35730	0.44	0.00023
1448-1549	35730	0.49	0.00026
1617-1629	36780	0.43	0.00023
Avg.		0.45	0.00024
Unloader Vent			
0822-0922	43350	0.21	0.00013
0957-1059	41030	0.22	0.00013
1134-1237	39540	0.26	0.00015
Avg.		0.23	0.00014

Table 6. Summary of the June 25, 1993 **Formaldehyde** Determinations on the Press & Unloader Vent at the Louisiana Pacific Waferboard Plant in Sagola, Michigan.

Time (HRS)	Volumetric Flow Rate (DSCFM)	Concentration (ppm,d)	Emission Rate (LB/HR)
0944-1048	122300	0.54	0.31
1158-1258	120100	0.52	0.29
1336-1433	124100	0.45	0.26
Avg.		0.50	0.29

Table 7. Summary of the June 29, 1993 **Formaldehyde** Determinations on the Press and Unloader Vents at the Louisiana Pacific Waferboard Plant in Two Harbors, Minnesota.

Time (HRS)	Volumetric Flow Rate (DSCFM)	Concentration (ppm,d)	Emission Rate (LB/HR)
Press Vent			
0822-0922	39560	3.20	0.59
0957-1058	40890	2.65	0.51
1137-1239	41060	2.72	0.52
Avg.		2.86	0.54
Unloader Vent			
1321-1421	41340	2.19	0.42
1446-1547	43300	2.61	0.53
1617-1720	38400	2.62	0.47
Avg.		2.47	0.47

Table 8. Summary of the Results of the June 25, 1993 **Total Hydrocarbon** Determinations on the Press & Unloader Vent at the Louisiana Pacific Waferboard Plant Located in Sagola, Michigan.

Time (HRS)	Volumetric Flow Rate (DSCFM)	Concentration (ppmC.w)	Emission Rate (LB C/HR)
1241-1341	122000	19.2	4.46
1345-1445	122000	17.5	4.07
1450-1540	122000	17.4	4.04
Avg.		18.0	4.19

Table 9.

Summary of the Results of the June 29, 1993 **Total Hydrocarbon** Determinations on the Press and Unloader Vents at the Louisiana Pacific Waferboard Plant Located in Two Harbors, Minnesota.

Time (HRS)	Volumetric Flow Rate (DSCFM)	Concentration (ppmC,w)	Emission Rate (LB C/HR)
Press Vent			
0822-0922	39600	9.9	0.73
0957-1057	40900	10.8	0.83
1137-1237	41100	8.7	0.67
Avg.		9.8	0.74
Unloader Vent			
1321-1421	41300	9.3	0.73
1445-1545	43300	7.5	0.61
1618-1718	38400	10.2	0.74
Avg.		9.0	0.69

Table 10.

Summary of the Results of the June 25, 1993 MDI Determinations on the Press & Unloader Vent at the Louisiana Pacific Waferboard Plant Located in Sagola, Michigan. (Nitro-reagent, normal phase)

Time (HRS)	Volumetric Flow Rate (DSCFM)	Concentration (ppb.d)	Emission Rate (LB/HR)
0836-0952	122000	12.6	0.0604
1121-1241	124000	13.5	0.0647
1353-1509	124000	17.5	0.0842
Avg.		14.5	0.0698

Table 11. Summary of the Results of the June 29 and July 1, 1993 MDI Determinations on the Press and Unloader Vents at the Louisiana Pacific Waferboard Plant Located in Two Harbors, Minnesota. (Nitro-reagent, normal phase)


Time (HRS)	Volumetric Flow Rate (DSCFM)	Concentration (ppb,d)	Emission Rate (LB/HR)
Press Vent (June 29)			
0825-0942	37900	136	0.201
1118-1238	38200	116	0.173
1410-1513	39500	137	0.211
Avg.		130	0.195
Unloader Vent (July 1)			
0754-0856	40100	87.4	0.137
1003-1105	36900	69.5	0.100
1214-1353	36900	101.4	0.146
Avg.		86.1	0.128

APPENDIX A
RESULTS - SAGOLA

TABLE OF CONTENTS

Volumetric Flow Rate	1
Orsat and Moisture	2
Particulate	7
Formaldehyde	8
Phenol	9
MDI	10

Job LOUISIANA PACIFIC/SEALAP, MI
Source PROSS + UNLOADER BENT-STACK
Test 4 Run 1 Date 2-26-92
Stack dimen. 71 1/4 IN.
Dry bulb _____ °F Wet bulb _____ °F
Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 28.34 in Hg
Static pressure -1.00 in WC
Operators E. TROWBRIDGE - C. MOSSER
Pitot No. 22V-6 Co 840



PM-10

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	5 in.	Time start: 0835 hrs	
A 1	.044	3.14	8.14	1.70	84
2	.146	10.40	15.40	2.40	84
3	.296	21.09	26.09	2.10	82
4	.704	50.16	55.16	2.20	80
5	.854	60.85	65.85	2.30	80
6	.956	68.12	73.12	2.60	80
B 1				1.30	84
2				1.70	84
3				1.80	85
4				2.20	86
5				2.10	86
6				2.00	86
Temp. meas. tool & S/N: VDT-12				Time end: 0845 hrs	

R or nothing= reg. manometer; G= expanded; E = electronic

S-392.1

Test No. 1
Press & unloader vent stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	06-25-93
Time of Determination.....(HRS)	840
Barometric pressure.....(IN.HG)	28.44
Pitot tube coefficient.....	.84
Number of sampling ports.....	2
Total number of points.....	24
Shape of duct.....	Round
Stack diameter.....(IN)	71.25
Duct area.....(SQ.FT)	27.69
Direction of flow.....	UP
Static pressure.....(IN.WC)	-8.5
Avg. gas temp.....(DEG-F)	96
Moisture content.....(% V/V)	2.52
Avg. linear velocity.....(FT/SEC)	81.9
Gas density.....(LB/ACF)	.06549
Molecular weight.....(LB/LBMOLE)	28.84
Mass flow of gas.....(LB/HR)	534760
Volumetric flow rate.....	
actual.....(ACFM)	136083
dry standard.....(DSCFM)	117112

Test No. 1
Press & unloader vent stack
Particulate and Phenol Tests

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-25-93	Run 2 06-25-93	Run 3 06-25-93
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.37	20.38	20.55
nitrogen.....	77.08	77.12	77.73
water vapor.....	2.52	2.46	1.69
 Dry molecular weight.....	 28.84	 28.84	 28.84
Wet molecular weight.....	28.57	28.57	28.66
Specific gravity.....	0.987	0.987	0.990
Water mass flow.....(LB/HR)	8426	8598	6097

Test No. 2
Press & Unloader vent Stack
Formaldehyde Test

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-25-93	Run 2 06-25-93	Run 3 06-25-93
Dry basis (orsat)			
carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07
Wet basis (orsat)			
carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.50	20.49	20.52
nitrogen.....	77.56	77.52	77.64
water vapor.....	1.91	1.97	1.81
Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.63	28.63	28.64
Specific gravity.....	0.989	0.989	0.989

Test No. 4
Press & unloader vent stack
MDI Train F

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	06-26-93	06-26-93	06-26-93

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.10	20.42	20.42
nitrogen.....	76.06	77.24	77.25
water vapor.....	3.81	2.31	2.30

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.43	28.59	28.59
Specific gravity.....	0.982	0.988	0.988

Test No. 5
Press & unloader vent stack
MDI Train L

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-26-93	Run 2 06-26-93	Run 3 06-26-93
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.03	20.36	20.37
nitrogen.....	75.77	77.03	77.07
water vapor.....	4.18	2.58	2.53
Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.39	28.56	28.57
Specific gravity.....	0.981	0.987	0.987

Test No. 6
Press & unloader vent stack

MDI Train N

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-25-93	Run 2 06-25-93	Run 3 06-25-93
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.41	20.39	20.40
nitrogen.....	77.23	77.16	77.16
water vapor.....	2.32	2.42	2.41
 Dry molecular weight.....	 28.84	 28.84	 28.84
Wet molecular weight.....	28.59	28.58	28.58
Specific gravity.....	0.988	0.987	0.987

Test No. 1
Press & unloader vent stack

Results of Particulate Loading Determinations-----Method 5

	Run 1	Run 2	Run 3
Date of run	06-25-93	06-25-93	06-25-93
Time run start/end.....(HRS)	944/1048	1158/1205	1336/1440
Static pressure.....(IN.WC)	-8.50	-8.50	-8.50
Cross sectional area (SQ.FT)	27.69	27.69	27.69
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	11.5	13.1	6.8
desiccant.....(GRAMS)	16.0	15.0	13.0
total.....(GRAMS)	27.5	28.1	19.8
Total particulate material..			
.....collected(grams)	0.0242	0.0208	0.0222
Gas meter coefficient.....	0.9970	0.9970	0.9970
Barometric pressure..(IN.HG)	28.44	28.44	28.44
Avg. orif.pres.drop..(IN.WC)	2.36	2.61	2.78
Avg. gas meter temp..(DEF-F)	85.9	92.7	93.1
Volume through gas meter....			
at meter conditions...(CF)	54.44	57.56	59.49
standard conditions.(DSCF)	50.18	52.44	54.18
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.190	.190	.190
Avg.stack gas temp ..(DEG-F)	99	99	102
Volumetric flow rate.....			
actual.....(ACFM)	135792	141731	146850
dry standard.....(DSCFM)	116269	121332	126152
Isokinetic variation.....(%)	101.2	101.4	100.7
Particulate concentration...			
actual.....(GR/ACF)	0.00637	0.00524	0.00543
dry standard.....(GR/DSCF)	0.00744	0.00612	0.00632
Particle mass rate...(LB/HR)	7.415	6.365	6.836

Test No. 2
 Press & Unloader Vent Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1	Run 2	Run 3
Date of run	06-25-93	06-25-93	06-25-93
Time run start/end.....(HRS)	0944-1048	1158-1258	1336-1433
Barometric pressure...(IN.HG)	28.44	28.44	28.44
Meter temperature....(DEG-F)	99.00	96.00	101.00
Meter correction coefficient	0.9983	0.9983	0.9983
Volume through gas meter....			
at meter conditions...(CF)	54.180	53.310	55.600
standard conditions (DSCF)	48.561	48.039	49.656
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	1.91	1.97	1.81
Volumetric flow rate (DSCFM)	122301	120102	124055
Formaldehyde in sample..(uG)	927	879	791
CH2O concentration.....			
(GR/DSCF).....	0.0003	0.0003	0.0002
(MG/DSCM).....	0.67	0.65	0.56
(PPM-DRY).....	0.54	0.52	0.45
(PPM-WET).....	0.53	0.51	0.44
CH2O emission rate...(LB/HR)	0.30877	0.29065	0.26136

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
 is less than or equal to the reported value

Test No. 1
Press & Unloader Vent Stack

Results of Phenol Determinations -----

	Run 1	Run 2	Run 3
Date of run	06-25-93	06-25-93	06-25-93
Time run start/end.....(HRS)	0944-1048	1158-1205	1336-1440
Barometric pressure...(IN.HG)	28.44	28.44	28.44
Meter temperature....(DEG-F)	85.90	92.70	93.10
Meter correction coefficient	0.9970	0.9970	0.9970
Volume through gas meter.... at meter conditions...(CF)	54.440	57.560	59.490
standard conditions (DSCF)	50.204	52.462	54.206
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	2.52	2.46	1.69
Volumetric flow rate (DSCFM)	116269	121332	126152
Phenol in sample.....(uG)	3.20	3.40	3.40
Phenol concentration..... (GR/10 ³ DSCF).....	0.0010	0.0010	0.0010
(uG/DSCM).....	2.25	2.29	2.22
(PPB-DRY).....	0.58	0.59	0.57
(PPB-WET).....	0.56	0.57	0.56
Phenol emis. rate(10 ⁻³ LB/HR)	0.980	1.040	1.046

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Analysis performed according to NIOSH Method 3502

ICI - LOUISIANA PACIFIC - SAGOLA PRESS & UNLOADER VENT STACK

June 26, 1993

TRAIN F

Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	MDI Conc (ppb)	MDI E-Rate (LB/HR)
4/1	31.73	122175	3.20	3.56	0.34	0.00163
4/2	32.20	124143	12.4	13.60	1.31	0.006324
4/3	32.00	124353	9.20	10.15	0.98	0.004729

TRAIN L

Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	MDI Conc (ppb)	MDI E-Rate (LB/HR)
5/1	29.24	118694	9.90	11.96	1.15	0.005316
5/2	29.01	119565	80.30	97.75	9.39	0.043778
5/3	30.08	123396	43.90	51.54	4.95	0.023821

*
0.054
0.065
0.051

TRAIN N

*corrected for recoveries

NORMAL PHASE

Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	MDI Conc (ppb)	MDI E-Rate (LB/HR)
6/1	55.66	123168	207.00	131	12.6	0.0604
6/2	55.51	123303	220.00	140	13.5	0.0647
6/3	55.60	123467	287.00	182	17.5	0.0842

Avg 0.0697

REVERSE PHASE

Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	MDI Conc (ppb)	MDI E-Rate (LB/HR)
6/1	55.66	123168	226.00	143	13.8	0.0662
6/2	55.51	123303	250.00	159	15.3	0.0735
6/3	55.60	123467	288.00	183	17.6	0.0846

Avg 0.0747

NOTES:

TRAIN N = Nitro Reagent Modified NIOSH Method P&CAM 347

TRAIN F = 1,2-MP Reagent ; Filter First

TRAIN L = 1,2-MP Reagent ; Filter Last

Test No. 4
Press & unloader vent stack

MDI SAMPLING DATA.....TRAIN F

	Run 1 06-26-93	Run 2 06-26-93	Run 3 06-26-93
Date of run			
Time run start/end.....(HRS)	836/ 952	1121/1241	1353/1509
Static pressure.....(IN.WC)	-0.85	-0.85	-0.85
Cross sectional area (SQ.FT)	27.69	27.69	27.69
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	-45.0	-34.0	-30.0
desiccant.....(GRAMS)	70.0	49.0	45.0
total.....(GRAMS)	25.0	15.0	15.0
Gas meter coefficient.....	0.9983	0.9983	0.9983
Barometric pressure..(IN.HG)	28.36	28.36	28.36
Avg. orif.pres.drop..(IN.WC)	0.64	0.65	0.65
Avg. gas meter temp..(DEF-F)	73.8	79.7	73.6
Volume through gas meter....			
at meter conditions...(CF)	31.73	32.20	32.00
standard conditions.(DSCF)	29.74	29.85	30.00
Total sampling time....(MIN)	72.00	72.00	72.00
Nozzle diameter.....(IN)	.130	.130	.130
Avg.stack gas temp ..(DEG-F)	92	97	88
Volumetric flow rate.....			
actual.....(ACFM)	140406	141752	139702
dry standard.....(DSCFM)	122175	124143	124353
Isokinetic variation.....(%)	101.6	100.4	100.7

Interpoll Labs Report No. 3-9202
ICI Polyurethanes Group - Louisiana Pacific
Sagola, Michigan

Test No. 5
Press & unloader vent stack

MDI SAMPLING DATA.....TRAIN L

	Run 1	Run 2	Run 3
Date of run	06-26-93	06-26-93	06-26-93
Time run start/end.....(HRS)	830/ 955	1121/1240	1353/1510
Static pressure.....(IN.WC)	-0.85	-0.85	-0.85
Cross sectional area (SQ.FT)	27.69	27.69	27.69
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	0.0	-72.0	0.0
desiccant.....(GRAMS)	25.0	87.0	15.0
total.....(GRAMS)	25.0	15.0	15.0
Total particulate material..			
.....collected(grams)	0.0000	0.0000	0.0000
Gas meter coefficient.....	0.9970	0.9970	0.9970
Barometric pressure..(IN.HG)	28.36	28.36	28.00
Avg. orif.pres.drop..(IN.WC)	0.47	0.46	0.49
Avg. gas meter temp..(DEF-F)	80.3	83.5	83.8
Volume through gas meter....			
at meter conditions...(CF)	29.24	29.01	30.08
standard conditions.(DSCF)	27.03	26.65	27.27
Total sampling time....(MIN)	72.00	72.00	72.00
Nozzle diameter.....(IN)	.125	.125	.125
Avg.stack gas temp ..(DEG-F)	94	97	89
Volumetric flow rate.....			
actual.....(ACFM)	137495	136944	141058
dry standard.....(DSCFM)	118694	119565	123396
Isokinetic variation.....(%)	102.8	100.7	99.8

Test No. 6
Press & unloader vent stack

MDI SAMPLING DATA.....TRAIN N


	Run 1 06-25-93	Run 2 06-25-93	Run 3 06-25-93
Date of run			
Time run start/end.....(HRS)	836/ 946	1121/1236	1353/1506
Static pressure.....(IN.WC)	-8.50	-8.50	-8.50
Cross sectional area (SQ.FT)	27.69	27.69	27.69
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	0.0	0.0	0.0
desiccant.....(GRAMS)	26.0	27.0	27.0
total.....(GRAMS)	26.0	27.0	27.0
Gas meter coefficient.....	0.9996	0.9996	0.9996
Barometric pressure..(IN.HG)	28.36	28.36	28.36
Avg. orif.pres.drop..(IN.WC)	2.52	2.52	2.53
Avg. gas meter temp..(DEF-F)	83.6	84.4	83.1
Volume through gas meter....			
at meter conditions...(CF)	55.66	55.51	55.60
standard conditions.(DSCF)	51.54	51.32	51.53
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.187	.187	.187
Avg.stack gas temp ..(DEG-F)	94	97	90
Volumetric flow rate.....			
actual.....(ACFM)	142709	143814	142236
dry standard.....(DSCFM)	123168	123303	123467
Isokinetic variation.....(%)	101.3	100.8	101.0

APPENDIX B

RESULTS - TWO HARBORS

TABLE OF CONTENTS

Volumetric Flow Rate	1
Orsat and Moisture	3
Particulate	13
Formaldehyde	15
Phenol	17
MDI	19



Test No. 4
Press Vent Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	06-29-93
Time of Determination.....(HRS)	1310
Barometric pressure.....(IN.HG)	29.19
Pitot tube coefficient.....	.84
Number of sampling ports.....	4
Total number of points.....	24
Shape of duct.....	Rectangular
Duct width.....(IN)	55
Duct length.....(IN)	55
Duct area.....(SQ.FT)	21.01
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.78
Avg. gas temp.....(DEG-F)	0
Moisture content.....(% V/V)	1.48
Avg. linear velocity.....(FT/SEC)	46.5
Gas density.....(LB/ACF)	.08324
Molecular weight.....(LB/LBMOLE)	28.84
Mass flow of gas.....(LB/HR)	292580
Volumetric flow rate.....	
actual.....(ACFM)	58583
dry standard.....(DSCFM)	64501

Test No. 2
Unloader Vent Stack

Results of Volumetric Flow Rate Determination-----Method 2

Date of Determination.....	06-29-93
Time of Determination.....(HRS)	745
Barometric pressure.....(IN.HG)	29.19
Pitot tube coefficient.....	.84
Number of sampling ports.....	4
Total number of points.....	24
Shape of duct.....	Rectangular
Duct width.....(IN)	55
Duct length.....(IN)	55
Duct area.....(SQ.FT)	21.01
Direction of flow.....	UP
Static pressure.....(IN.WC)	-.62
Avg. gas temp.....(DEG-F)	85
Moisture content.....(% V/V)	1.40
Avg. linear velocity.....(FT/SEC)	34.0
Gas density.....(LB/ACF)	.07031
Molecular weight.....(LB/LBMOLE)	28.84
Mass flow of gas.....(LB/HR)	180700
Volumetric flow rate.....	
actual.....(ACFM)	42836
dry standard.....(DSCFM)	39858

Test No. 1
Press Vent Stack

Formaldehyde Test

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	06-29-93	06-29-93	06-29-93

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.85	20.63	20.78
nitrogen.....	78.88	78.05	78.61
water vapor.....	0.24	1.29	0.59
Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.81	28.70	28.78
Specific gravity.....	0.995	0.991	0.994

Test No. 4
Press Vent Stack
Particulate and Phenol Tests

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-29-93	Run 2 06-29-93	Run 3 06-29-93
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.59	20.50	20.54
nitrogen.....	77.90	77.55	77.70
water vapor.....	1.48	1.92	1.73

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.68	28.63	28.65
Specific gravity.....	0.991	0.989	0.990
Water mass flow.....(LB/HR)	1510	1961	1820

Test No. 7
Press Vent Stack
MDI Train N

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-30-93	Run 2 06-30-93	Run 3 06-30-93
Dry basis (orsat)			
carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07
Wet basis (orsat)			
carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.61	20.59	20.55
nitrogen.....	77.99	77.88	77.76
water vapor.....	1.37	1.50	1.66
Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.69	28.68	28.66
Specific gravity.....	0.991	0.991	0.990

Test No. 8
Press Vent Stack
MDI Train L

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-30-93	Run 2 06-30-93	Run 3 06-30-93
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.58	20.59	20.56
nitrogen.....	77.85	77.90	77.80
water vapor.....	1.54	1.48	1.61

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.67	28.68	28.67
Specific gravity.....	0.990	0.991	0.990

Test No. 9
Press Vent Stack
MDI Train F

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-30-93	Run 2 06-30-93	Run 3 06-30-93
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.58	20.60	20.59
nitrogen.....	77.86	77.94	77.88
water vapor.....	1.52	1.43	1.51
Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.68	28.69	28.68
Specific gravity.....	0.991	0.991	0.991

Test No. 2
Unloader Vent Stack
Particulate and Phenol Tests

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	06-29-93	06-29-93	06-29-93

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.61	20.58	20.61
nitrogen.....	77.96	77.86	77.98
water vapor.....	1.40	1.53	1.38

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.69	28.67	28.69
Specific gravity.....	0.991	0.990	0.991
Water mass flow.....(LB/HR)	1727	1794	1551

Test No. 5
Unloader Vent Stack
Formaldehyde Test

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

Date of run	Run 1 06-29-93	Run 2 06-29-93	Run 3 06-29-93
-------------	-------------------	-------------------	-------------------

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.66	20.60	20.54
nitrogen.....	78.16	77.92	77.71
water vapor.....	1.15	1.46	1.72

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.72	28.68	28.65
Specific gravity.....	0.992	0.991	0.990

Test No. 10
Unloader Vent Stack
MDI Train N

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	07-01-93	07-01-93	07-01-93

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.65	20.61	20.63
nitrogen.....	78.13	77.96	78.06
water vapor.....	1.19	1.40	1.28

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.71	28.69	28.70
Specific gravity.....	0.992	0.991	0.991

Test No. 11
 Unloader Vent Stack
 MDI Train L

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	07-01-93	07-01-93	07-01-93

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.58	20.58	20.63
nitrogen.....	77.86	77.85	78.04
water vapor.....	1.53	1.54	1.30

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.68	28.67	28.70
Specific gravity.....	0.991	0.990	0.991

Test No. 12
 Unloader Vent Stack
 MDI Train F

Results of Orsat & Moisture Analyses-----Methods 3 & 4(%v/v)

	Run 1	Run 2	Run 3
Date of run	07-01-93	07-01-93	07-01-93

Dry basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.90	20.90	20.90
nitrogen.....	79.07	79.07	79.07

Wet basis (orsat)

carbon dioxide.....	0.03	0.03	0.03
oxygen.....	20.57	20.59	20.60
nitrogen.....	77.83	77.90	77.93
water vapor.....	1.57	1.48	1.44

Dry molecular weight.....	28.84	28.84	28.84
Wet molecular weight.....	28.67	28.68	28.68
Specific gravity.....	0.990	0.991	0.991

Test No. 4
Press Vent Stack

Results of Particulate Loading Determinations-----Method 5

	Run 1 06-29-93	Run 2 06-29-93	Run 3 06-29-93
Date of run			
Time run start/end.....(HRS)	1322/1423	1448/1549	1617/1629
Static pressure.....(IN.WC)	-0.78	-0.78	-0.78
Cross sectional area (SQ.FT)	21.01	21.01	21.01
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	3.1	5.3	5.4
desiccant.....(GRAMS)	8.0	9.0	8.0
total.....(GRAMS)	11.1	14.3	13.4
Total particulate material..			
.....collected(grams)	0.0159	0.0200	0.0197
Gas meter coefficient.....	0.9970	0.9970	0.9970
Barometric pressure..(IN.HG)	29.19	29.00	29.19
Avg. orif.pres.drop..(IN.WC)	1.45	1.45	1.57
Avg. gas meter temp..(DEF-F)	97.2	97.2	90.6
Volume through gas meter....			
at meter conditions...(CF)	37.56	37.51	38.27
standard conditions.(DSCF)	34.73	34.46	35.82
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.250	.250	.250
Avg.stack gas temp ..(DEG-F)	98	98	96
Volumetric flow rate.....			
actual.....(ACFM)	39395	39828	40501
dry standard.....(DSCFM)	35735	35735	36784
Isokinetic variation.....(%)	99.9	99.1	100.1
Particulate concentration...			
actual.....(GR/ACF)	0.00641	0.00803	0.00770
dry standard.....(GR/DSCF)	0.00706	0.00896	0.00849
Particle mass rate...(LB/HR)	2.164	2.743	2.675

Test No. 2
Unloader Vent Stack

Results of Particulate Loading Determinations-----Method 5

	Run 1 06-29-93	Run 2 06-29-93	Run 3 06-29-93
Date of run			
Time run start/end.....(HRS)	822/ 922	957/1059	1134/1237
Static pressure.....(IN.WC)	-0.62	-0.62	-0.62
Cross sectional area (SQ.FT)	21.01	21.01	21.01
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	2.6	3.2	2.4
desiccant.....(GRAMS)	10.0	10.0	9.0
total.....(GRAMS)	12.6	13.2	11.4
Total particulate material..			
.....collected(grams)	0.0296	0.0230	0.0179
Gas meter coefficient.....	0.9970	0.9970	0.9970
Barometric pressure..(IN.HG)	29.19	29.19	29.19
Avg. orif.pres.drop..(IN.WC)	1.79	1.64	1.61
Avg. gas meter temp..(DEF-F)	97.0	97.9	98.9
Volume through gas meter....			
at meter conditions...(CF)	45.19	43.21	41.68
standard conditions.(DSCF)	41.84	39.93	38.44
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.250	.250	.250
Avg.stack gas temp ..(DEG-F)	86	88	90
Volumetric flow rate.....			
actual.....(ACFM)	46664	44356	42856
dry standard.....(DSCFM)	43354	41027	39544
Isokinetic variation.....(%)	99.2	100.0	99.9
Particulate concentration...			
actual.....(GR/ACF)	0.01014	0.00822	0.00663
dry standard.....(GR/DSCF)	0.01092	0.00889	0.00719
Particle mass rate...(LB/HR)	4.056	3.126	2.435

Test No. 1
Press Vent Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1	Run 2	Run 3
Date of run	06-29-93	06-29-93	06-29-93
Time run start/end.....(HRS)	0822-0922	0957-1058	1137-1239
Barometric pressure...(IN.HG)	29.19	29.19	29.19
Meter temperature....(DEG-F)	95.00	95.00	99.00
Meter correction coefficient	0.9983	0.9983	0.9983
Volume through gas meter....			
at meter conditions...(CF)	41.910	43.160	43.140
standard conditions (DSCF)	38.832	39.990	39.686
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	0.24	1.29	0.59
Volumetric flow rate (DSCFM)	39560	40888	41059
Formaldehyde in sample..(uG)	4390	3740	3820
CH2O concentration.....			
(GR/DSCF).....	0.0017	0.0014	0.0015
(MG/DSCM).....	4.00	3.31	3.40
(PPM-DRY).....	3.20	2.65	2.72
(PPM-WET).....	3.19	2.61	2.71
CH2O emission rate...(LB/HR)	0.59149	0.50575	0.52270

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 5
Unloader Vent Stack

Results of Formaldehyde Tests ----- EPA Method 0011

	Run 1	Run 2	Run 3
Date of run	06-29-93	06-29-93	06-29-93
Time run start/end.....(HRS)	1321-1421	1446-1547	1617-1720
Barometric pressure..(IN.HG)	29.19	29.19	29.19
Meter temperature....(DEG-F)	90.00	88.00	88.00
Meter correction coefficient	0.9983	0.9983	0.9983
Volume through gas meter....			
at meter conditions...(CF)	43.920	45.010	40.700
standard conditions (DSCF)	41.064	42.237	38.180
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	1.15	1.46	1.72
Volumetric flow rate (DSCFM)	41342	43301	38404
Formaldehyde in sample..(uG)	3180	3900	3540
CH2O concentration.....			
(GR/DSCF).....	0.0012	0.0014	0.0014
(MG/DSCM).....	2.74	3.26	3.28
(PPM-DRY).....	2.19	2.61	2.62
(PPM-WET).....	2.17	2.58	2.58
CH2O emission rate...(LB/HR)	0.42342	0.52879	0.47094

CH2O = Formaldehyde

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Test No. 4
Press Vent Stack

Results of Phenol Determinations -----

	Run 1	Run 2	Run 3
Date of run	06-29-93	06-29-93	06-29-93
Time run start/end.....(HRS)	1322-1423	1448-1549	1617-1629
Barometric pressure...(IN.HG)	29.19	29.19	29.19
Meter temperature....(DEG-F)	97.20	97.20	90.60
Meter correction coefficient	0.9970	0.9970	0.9970
Volume through gas meter.... at meter conditions...(CF)	37.560	37.510	38.270
standard conditions (DSCF)	34.745	34.699	35.837
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	1.48	1.92	1.73
Volumetric flow rate (DSCFM)	35735	35735	36784
Phenol in sample.....(uG)	1.70	1.90	1.70
Phenol concentration..... (GR/10 ³ DSCF).....	0.0008	0.0008	0.0007
(uG/DSCM).....	1.73	1.94	1.68
(PPB-DRY).....	0.44	0.49	0.43
(PPB-WET).....	0.44	0.48	0.42
Phenol emis. rate(10 ⁻³ LB/HR)	0.231	0.259	0.231

A trailing '<' symbol indicates that the true value
is less than or equal to the reported value

Analysis performed according to NIOSH Method 3502

Test No. 2
Unloading Vent Stack

Results of Phenol Determinations -----

	Run 1	Run 2	Run 3
Date of run	06-29-93	06-29-93	06-29-93
Time run start/end.....(HRS)	0822-0922	0957-1059	1134-1237
Barometric pressure..(IN.HG)	29.19	29.19	29.19
Meter temperature....(DEG-F)	97.00	97.90	98.90
Meter correction coefficient	0.9970	0.9970	0.9970
Volume through gas meter....			
at meter conditions...(CF)	45.195	43.210	41.680
standard conditions (DSCF)	41.859	39.941	38.455
Total sampling time....(MIN)	60.0	60.0	60.0
Moisture content.....(%V/V)	1.40	1.53	1.38
Volumetric flow rate (DSCFM)	43354	41027	39544
Phenol in sample.....(uG)	0.96	0.98	1.10
Phenol concentration.....			
(GR/10 ³ DSCF).....	0.0004	0.0004	0.0004
(uG/DSCM).....	0.81	0.87	1.01
(PPB-DRY).....	0.21	0.22	0.26
(PPB-WET).....	0.20	0.22	0.25
Phenol emis. rate(10 ⁻³ LB/HR)	0.131	0.133	0.150

A trailing '<' symbol indicates that the true value is less than or equal to the reported value

Analysis performed according to NIOSH Method 3502

Test No. 7
Press Vent Stack

MDI SAMPLING DATATRAIN N

	Run 1	Run 2	Run 3
Date of run	06-30-93	06-30-93	06-30-93
Time run start/end.....(HRS)	825/ 942	1118/1238	1410/1513
Static pressure.....(IN.WC)	-0.78	-0.78	-0.78
Cross sectional area (SQ.FT)	21.01	21.01	21.01
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	0.0	0.0	0.0
desiccant.....(GRAMS)	11.0	12.0	13.0
total.....(GRAMS)	11.0	12.0	13.0
Gas meter coefficient.....	0.9996	0.9996	0.9996
Barometric pressure..(IN.HG)	29.15	29.15	29.15
Avg. orif.pres.drop..(IN.WC)	1.69	1.66	1.68
Avg. gas meter temp..(DEF-F)	85.5	90.2	89.0
Volume through gas meter....			
at meter conditions...(CF)	39.41	39.50	38.70
standard conditions.(DSCF)	37.29	37.06	36.39
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.251	.251	.251
Avg.stack gas temp ..(DEG-F)	86	87	89
Volumetric flow rate.....			
actual.....(ACFM)	40890	41370	42978
dry standard.....(DSCFM)	37933	38221	39549
Isokinetic variation.....(%)	100.2	98.8	93.8

ICI - LOUISIANA PACIFIC - TWO HARBORS
PRESS VENT STACK
JUNE 30, 1993

TRAIN F

Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	MDI Conc (ppb)	MDI E-Rate (LB/HR)
9/1	25.99	37758	147.16	199.95	19.2	0.02828
9/2	27.94	40541	371.00	468.92	45.1	0.071207
9/3	26.64	38143	65.90	87.36	8.4	0.012481

TRAIN L

Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	* Conc (ug/Nm3)	MDI Conc (ppb)	MDI E-Rate (LB/HR)
8/1	26.27	38899	459.50	730 617.69	59.4	0.09
8/2	26.98	40441	382.90	570 501.18	48.2	0.075918
8/3	25.48	37311	399.60	160 553.83	53.2	0.0774

0.14

0.12

0.03

0.097 Ave

*corrected for recoveries

TRAIN N

NORMAL PHASE				MDI Conc (ppb)	MDI E-Rate (LB/HR)
Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	
7/1	39.41	37933	1580.00	1415.79	136 0.201163
7/2	39.50	38221	1350.00	1206.93	116 0.17279
7/3	38.70	39549	1560.00	1423.51	137 0.210877

REVERSE PHASE				MDI Conc (ppb)	MDI E-Rate (LB/HR)
Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	
7/1	39.41	37933	1510.00	1353.06	130 0.192251
7/2	39.50	38221	1250.00	1117.53	107 0.159991
7/3	38.70	39549	1530.00	1396.13	134 0.206822

NOTES:

TRAIN N= Nitro Reagent Modified NIOSH Method P&CAM 347

TRAIN F= 1,2-MP Reagent ; Filter First

TRAIN L = 1,2-MP Reagent ; Filter Last

Test No. 8
Press Vent Stack

MDI SAMPLING DATA.....TRAIN L

	Run 1	Run 2	Run 3
Date of run	06-30-93	06-30-93	06-30-93
Time run start/end.....(HRS)	825/ 957	1118/1248	1410/1528
Static pressure.....(IN.WC)	-0.78	-0.78	-0.78
Cross sectional area (SQ.FT)	21.01	21.01	21.01
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	-29.0	-28.0	-32.0
desiccant.....(GRAMS)	37.0	36.0	40.0
total.....(GRAMS)	8.0	8.0	8.0
Gas meter coefficient.....	0.9978	0.9970	0.9970
Barometric pressure..(IN.HG)	29.15	29.15	29.15
Avg. orif.pres.drop..(IN.WC)	0.48	0.49	0.44
Avg. gas meter temp..(DEF-F)	100.1	92.3	105.8
Volume through gas meter....			
at meter conditions...(CF)	26.27	26.98	25.48
standard conditions.(DSCF)	24.09	25.08	23.11
Total sampling time....(MIN)	72.00	72.00	72.00
Nozzle diameter.....(IN)	.182	.182	.182
Avg.stack gas temp ..(DEG-F)	85	87	90
Volumetric flow rate.....			
actual.....(ACFM)	41905	43763	40636
dry standard.....(DSCFM)	38899	40441	37311
Isokinetic variation.....(%)	100.1	100.2	100.1

Test No. 9
Press Vent Stack

MDI SAMPLING DATA.....TRAIN F

	Run 1 06-30-93	Run 2 06-30-93	Run 3 06-30-93
Date of run			
Time run start/end.....(HRS)	825/ 957	1118/1248	1410/1512
Static pressure.....(IN.WC)	-0.78	-0.78	-0.78
Cross sectional area (SQ.FT)	21.01	21.01	21.01
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	-28.0	-26.0	-29.0
desiccant.....(GRAMS)	36.0	34.0	37.0
total.....(GRAMS)	8.0	8.0	8.0
Gas meter coefficient.....	0.9987	0.9983	0.9983
Barometric pressure..(IN.HG)	29.15	29.15	29.15
Avg. orif.pres.drop..(IN.WC)	0.54	0.61	0.54
Avg. gas meter temp..(DEF-F)	88.6	90.8	95.0
Volume through gas meter....			
at meter conditions...(CF)	25.99	27.94	26.64
standard conditions.(DSCF)	24.36	26.07	24.67
Total sampling time....(MIN)	72.00	72.00	72.00
Nozzle diameter.....(IN)	.185	.185	.185
Avg.stack gas temp ..(DEG-F)	86	88	90
Volumetric flow rate.....			
actual.....(ACFM)	40762	43876	41462
dry standard.....(DSCFM)	37758	40541	38143
Isokinetic variation.....(%)	100.9	100.6	101.1

ICI - LOUISIANA PACIFIC - TWO HARBORS
UNLOADER VENT STACK
JULY 1, 1993

TRAIN F

Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	MDI Conc (ppb)	MDI E-Rate (LB/HR)
12/1	25.37	36952		#VALUE!	#VALUE!	#VALUE!
12/2	27.00	38588		#VALUE!	#VALUE!	#VALUE!
12/3	27.75	39944		#VALUE!	#VALUE!	#VALUE!

TRAIN L

Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	MDI Conc (ppb)	MDI E-Rate (LB/HR)
11/1	26.36	39495	296.30	430 396.95	38.1	0.058723
11/2	26.18	39109	201.80	370 272.21	26.2	0.039876
11/3	27.29	40533	300.80	460 389.24	37.4	0.059097

0.085
0.073
0.090
0.083 Ave

TRAIN N

NORMAL PHASE				MDI Conc (ppb)	MDI E-Rate (LB/HR)
Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	
10/1	41.95	40113	1080.00	909.16	87.4 0.136602
10/2	39.15	36872	802.00	723.42	69.5 0.099912
10/3	39.14	36899	1170.00	1055.63	101.4 0.145901

REVERSE PHASE				MDI Conc (ppb)	MDI E-Rate (LB/HR)
Test/Run	Vstd (CF)	Flow (DSCFM)	MDI (ug)	Conc (ug/Nm3)	
10/1	41.95	40113	1040.00	875.48	84.1 0.131543
10/2	39.15	36872	790.00	712.59	68.5 0.098417
10/3	39.14	36899	1090.00	983.45	94.5 0.135925

NOTES:

TRAIN N = Nitro Reagent Modified NIOSH Method P&CAM 347
TRAIN F = 1,2-MP Reagent ; Filter First
TRAIN L = 1,2-MP Reagent ; Filter Last

Test No. 10
Unloader Vent Stack

MDI SAMPLING DATA.....TRAIN N

	Run 1	Run 2	Run 3
Date of run	07-01-93	07-01-93	07-01-93
Time run start/end.....(HRS)	754/ 856	1003/1105	1214/1353
Static pressure.....(IN.WC)	-0.62	-0.62	-0.62
Cross sectional area (SQ.FT)	21.01	21.01	21.01
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	0.0	0.0	0.0
desiccant.....(GRAMS)	10.0	11.0	10.0
total.....(GRAMS)	10.0	11.0	10.0
Gas meter coefficient.....	0.9996	0.9996	0.9996
Barometric pressure..(IN.HG)	29.10	29.10	29.10
Avg. orif.pres.drop..(IN.WC)	1.65	1.51	1.54
Avg. gas meter temp..(DEF-F)	89.9	92.0	93.8
Volume through gas meter....			
at meter conditions...(CF)	41.95	39.15	39.14
standard conditions.(DSCF)	39.31	36.53	36.41
Total sampling time....(MIN)	60.00	60.00	60.00
Nozzle diameter.....(IN)	.251	.251	.251
Avg.stack gas temp ..(DEG-F)	87	88	88
Volumetric flow rate.....			
actual.....(ACFM)	43275	39947	39918
dry standard.....(DSCFM)	40113	36872	36899
Isokinetic variation.....(%)	99.9	101.0	100.6

Interpoll Labs Report No. 3-9289
ICI - Louisiana Pacific - Two Harbors
Two Harbors, Minnesota

Test No. 11
Unloader Vent Stack

MDI SAMPLING DATA.....TRAIN L

	Run 1	Run 2	Run 3
Date of run	07-01-93	07-01-93	07-01-93
Time run start/end.....(HRS)	754/ 908	1003/1104	1214/1424
Static pressure.....(IN.WC)	-0.62	-0.62	-0.62
Cross sectional area (SQ.FT)	21.01	21.01	21.01
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	-32.0	-25.0	-25.0
desiccant.....(GRAMS)	40.0	33.0	32.0
total.....(GRAMS)	8.0	8.0	7.0
Gas meter coefficient.....	0.9970	0.9970	0.9970
Barometric pressure..(IN.HG)	29.10	29.10	29.10
Avg. orif.pres.drop..(IN.WC)	0.42	0.42	0.45
Avg. gas meter temp..(DEF-F)	95.6	95.6	98.7
Volume through gas meter....			
at meter conditions...(CF)	26.36	26.18	27.29
standard conditions.(DSCF)	24.31	24.14	25.03
Total sampling time....(MIN)	72.00	72.00	72.00
Nozzle diameter.....(IN)	.182	.182	.182
Avg.stack gas temp ..(DEG-F)	87	88	88
Volumetric flow rate.....			
actual.....(ACFM)	42770	42485	43919
dry standard.....(DSCFM)	39495	39109	40533
Isokinetic variation.....(%)	99.4	99.7	99.8

Interpoll Labs Report No. 3-9289
ICI - Louisiana Pacific - Two Harbors
Two Harbors, Minnesota


Test No. 12
Unloader Vent Stack

MDI SAMPLING DATA.....TRAIN F

	Run 1	Run 2	Run 3
Date of run	07-01-93	07-01-93	07-01-93
Time run start/end.....(HRS)	754/ 908	1003/1120	1215/1423
Static pressure.....(IN.WC)	-0.80	-0.80	-0.80
Cross sectional area (SQ.FT)	21.01	21.01	21.01
Pitot tube coefficient.....	.840	.840	.840
Water in sample gas			
condenser.....(ML)	0.0	0.0	0.0
impingers.....(GRAMS)	-38.0	-17.0	-35.0
desiccant.....(GRAMS)	46.0	25.0	43.0
total.....(GRAMS)	8.0	8.0	8.0
Gas meter coefficient.....	0.9983	0.9983	0.9983
Barometric pressure..(IN.HG)	29.10	29.10	29.10
Avg. orif.pres.drop..(IN.WC)	0.50	0.51	0.54
Avg. gas meter temp..(DEF-F)	89.3	90.4	92.6
Volume through gas meter....			
at meter conditions...(CF)	25.37	27.00	27.75
standard conditions.(DSCF)	23.70	25.17	25.77
Total sampling time....(MIN)	72.00	72.00	72.00
Nozzle diameter.....(IN)	.185	.185	.185
Avg.stack gas temp ..(DEG-F)	87	89	88
Volumetric flow rate.....			
actual.....(ACFM)	40034	41940	43320
dry standard.....(DSCFM)	36952	38588	39944
Isokinetic variation.....(%)	100.3	102.0	100.9


APPENDIX C

FIELD DATA SHEETS



INTERPOL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ICI SAGOLA
 Source PRESS & UNLOADER VENT
 Test 1 Run 0 Date 6-25-93 ^{STACK}
 Stack dimen. 71.25 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 28.44 in Hg
 Static pressure -.85 in WC
 Operators CH &
 Pitot No. 27-UG C_p .84



Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>5</u> in.		Time start: <u>0840</u> hrs	
D-1	.021	1.5	6.5	1.1	96
2	.067	4.77	9.77	1.5	
3	.118	8.48	13.48	1.7	
4	.177	12.61	17.61	1.7	
5	.250	17.81	22.81	1.4	
6	.356	25.36	30.36	1.5 1.9	
7	.644	45.88	50.88	1.9	
8	.750	52.44	57.44	1.7	
9	.823	58.64	63.64	1.8	
10	.882	62.84	67.84	1.7	
11	.933	66.47	71.47	1.7	
12	.979	69.75	74.75	1.7	
C-1				1.5 1.1	96
2				2.5	
3				2.5	
4				2.3	
5				2.3	
6				2.0	
7				1.9	
8				2.3	
9				2.5	
10				2.5	
11				2.2	
12				1.7	
Temp. meas. device & S/N: <u>24</u>				Time end: <u>0950</u> hrs	

R or nothing = reg. manometer; S= expanded; E=electronic

S-3921

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI SABOLA Date 6-25-93 Test 1 Run 1
 Source PRESS AND UNLOADER VENT No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: GLASS FIBER

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 15 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

5427 ☒ acetone
☐ other(s) _____
NO OF FILTER WASH BOTTLES 1
 No. of probe wash bottles: _____
 Sample recovered by: CH

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>272</u>	<u>267.5</u>	<u>4.5</u>
Impinger No. 2	<u>272</u>	<u>265</u>	<u>7</u>
Impinger No. 3			
Condenser			
Desiccant	<u>1357</u>	<u>1341</u>	<u>16</u>
Total			<u>22.5</u>

Integrated Gas Sampling Data:

Bag Pump No. N/A Box No. N/A Bag No. N/A
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: NA - AMBIENT

CF-023

INTERPOL LABORATORIES DATA SHEET

 Job
 Source
 Date

 IS SAGOLA
 PRESS AND UNLADDER
 6-25-93

 Operator
 Meter Box No.
 Computer Code

 CH 2 SE
 174 TN MC
 9970

 Pitot No. 3706
 Bar. Press. 38.94
 Nozzle No. 27-5

 Cp
 inHg
 Nozzle Dia. 1.00 in.

Traverse Point No.	Supplying Pipe (in)	Supply Volume (cf)	Velocity Head (inWC)	Orifice Meter (inWC)	Dis. Vol. (cf)	VAC. inHg	Temperature (°F)				Dye/Dot	Dye/Dot (X/V/V)
							Static	Probe	Dye/Dot	Temp.		
C 12	2.5	898.40	1.7	2.14	0.54	7	96	242	39	74	73	20.9
11	5	900.54	1.7	2.13	2.68	8	96	242	39	76	74	20.9
10	7.5	902.68	1.9	2.38	4.95	9	95	243	39	78	74	20.9
9	10	904.95	2.1	2.63	7.33	10	97	244	40	80	75	20.9
8	12.5	907.33	2.2	2.78	9.78	11	101	245	42	82	76	20.9
7	15	912.13	2.0	2.54	2.13	11	96	245	43	84	77	20.9
6	17.5	914.64	2.3	2.92	4.64	12	96	246	44	85	78	20.9
5	20	917.15	2.3	2.88	7.15	12	96	248	45	86	79	20.9
4	22.5	919.75	2.4	3.03	9.72	13	105	248	44	87	86	20.9
3	25	922.15	2.1	2.68	2.15	13	102	249	40	88	85	20.9
2	27.5	924.78	2.5	3.16	4.78	13	100	249	41	89	82	20.9
1	30	927.42	2.5	3.16	7.42	14	103	249	41	90	82	20.9
D 12	52.5	929.46	1.5	1.90	9.46	8	103	245	41	88	84	20.9
11	35	931.51	1.5	1.90	1.51	8	103	246	42	89	84	20.9
10	37.5	933.68	1.65	2.14	3.68	7	93	248	43	91	84	20.9
9	40	935.85	1.65	2.12	5.85	7	93	247	41	93	85	20.9
8	42.5	938.06	1.70	2.20	8.06	7	96	247	42	95	86	20.9
7	45	940.31	1.60	2.08	0.21	8	95	246	42	96	87	20.9
6	47.5	942.42	1.70	2.21	2.42	10	95	247	41	97	88	20.9
5	50	944.44	1.4	1.82	4.44	9	95	247	42	97	88	20.9
4	52.5	946.58	1.6	2.05	6.58	10	104	247	43	97	89	20.9
3	55	948.78	1.7	2.18	8.78	10	104	245	44	97	89	20.9
2	57.5	950.92	1.6	2.05	0.92	9	104	246	44	97	89	20.9
1	60	952.84	1.3	1.66	2.84	9	104	245	44	97	89	20.9
(1048)		954.44		2.36								
Avg. = 85.9												

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI SAGOLA STACK Date 6-25-93 Test 1 Run 2
 Source PRESS AND UNLOADER VENT No. of traverse points 27
 Method 5 Filter holder: GLASS Filter type: GLASS FIBER

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: .00 cfm at 15 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

5425 ☒ acetone _____
☐ other(s) _____
NO OF FILTER WASH BOTTLES 1
 No. of probe wash bottles: 1
 Sample recovered by: GA

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1 <u>A</u>	<u>275</u>	<u>267</u>	<u>8</u>
Impinger No. 2 <u>B</u>	<u>272</u>	<u>266.9</u>	<u>5.1</u>
Impinger No. 3			
Condenser			
Desiccant	<u>1452</u>	<u>1437</u>	<u>15</u>
Total			<u>26.1</u>

Integrated Gas Sampling Data:

Bag Pump No. N/A Box No. N/A Bag No. N/A
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

Jul. 1901

Дыктант

6 Nov 55

5. 50155

Pituitary. 2.

४४

3

REF-UNIT

PAUPER VENT SLACK
1961 1 AUG 2

— १५०३ —
४७३ १९६१
४७३ १९६१

3 6-74 9970

BU. 11. 10. 11.

110

1951.

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICTI SACOLA STACK Date 6-25-93 Test 1 Run 3
 Source PRESS AND UNLOADER VENT No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: GLASS FIBER

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: .00 cfm at in. Hg. (vac) ☐

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

5428 ☒ acetone
☐ other(s)
NO OF FILTER WASH BOTTLES 1
 No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1 } Impinger No. 2 } Impinger No. 3 }	271	267.2	3.8
Condenser			
Desiccant	1387	1374	13
Total			19.8

Integrated Gas Sampling Data:

Bag Pump No. N/A Box No. N/A Bag No. N/A
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: cc/min at in. Hg.
 Time start: (HRS) Time end: (HRS)
 Sampling rate: cc/min Operator:
 S/N of O₂ Analyzer used to monitor train outlet:


CF-023

Job 101 SACOLA STAC Operators CHOUK - S. F. R. L. Pilot No. 274-6 Dp 84
Source PRESS AND UNLOADED Receiver Box No. 74 IN NC Bur. Proc. 2842 INH 120 R
Date 25-92 Recorder Cost. 9970 Nozzle No. 27-3 Nozzle Dia. 190 IN.

[illegible]

INTERPOL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job L.P. Sagala
 Source Press + U-loading Vent Stack
 Test 2 Run Date 6/25/93
 Stack dimen. 71.25 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 28.44 in Hg
 Static pressure -1.85 in WC
 Operators D. VAN HANER & J. Bergstrom
 Pitot No. V23-6 C, 84



CH₂O

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: in.		Time start: hrs	
A 1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
B 1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
Temp. meas. device & S/N: <u>PDT #18</u>				Time end: hrs	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / Sagola Date 6/25/93 Test 2 Run 1
 Source PRESS & UNLOADING VENT STACK No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: { 0 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☒ other(s) MECL₂ & DI H₂O

No. of probe wash bottles: 7

Sample recovered by: DUST

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2	<u>209</u>	<u>200</u>	<u>9</u>
Impinger No. 3			
Condenser			
Desiccant	<u>1320</u>	<u>1308</u>	<u>12</u>
Total			<u>21</u>

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

1001 1CJ SAGOLA

ICI SAGOLA

अ. १८

2011-12-15

Putt No. _____
Bar. Price _____

236.44

21-511-1

05

Traverse Point No.	Sampling Time (min)	Sample Volume (cc)	Velocity Head (in WC)	Driftless Meter (in WC)	Obs. Vol. (cc)	VAC. in Hg	Temperature (°F)					Oxygen (xv/v)
							Stack	Probe	Duct	Inlet	Exhaust	
1	30	286.75	1.60	2.11	6.80	4	104	43	77	73	73	
2	37.5	284.84	1.70	2.25	4.80	4	102	43	79	73	73	
3	35	282.73	1.80	2.38	2.73	4.5	102		78	73	73	
4	22.5	280.49	1.80	2.37	0.61	4.5	102		78	72	72	
5	30	278.42	1.80	2.36	8.48	4.5	105		77	71	71	
6	17.5	276.36	1.80	2.39	6.37	4.5	96		76	71	71	
7	15	274.20	1.80	2.39	4.24	4.5	96		75	70	70	
8	12.5	272.20	1.40	1.85	2.12	4	97		73	70	70	
9	10	270.26	1.85	2.44	0.25	4.5	97		72	69	69	
10	7.5	268.18	1.90	2.49	8.11	4.5	97		71	69	69	
11	5	266.97	1.95	2.57	5.95	4.5	96		67	66	66	
12	25	266.83	1.50	1.99	3.76	4	96		68	68	68	
Avg. = 76.3												

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job TLI / Sugala Date 6/25/93 Test 2 Run 2
 Source PRESS & UNLOADING VENT STACK No. of traverse points 24
 Method COU Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 11 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) MCCl₂ & DI H₂O

No. of probe wash bottles: 1
 Sample recovered by: DUH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2	208	200	8
Impinger No. 3			
Condenser			
Desiccant	1457	1444	13
Total			21

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICJ / Sagola MI Operator SEFF BERGSTRON Pilot No. 230-6 CP 84
 Source Press and water vent stack Meter Box No. 7 Bar. Press. 28.90 inHg H₂O 3
 Date 6/25/83 Recorder 2 H₂O 2 Nozzle Dia 1/2 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Orifice Meter (inWC)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)				Gas/Dut	Oxygen (xv/v)
							Stack	Probe	Duct	Ingr.	Gas/in	
G-1	1158	316.24	2.6	3.43	18.79	9.5	103	ND	Heat	41	78	76
2	2.5	318.70	2.4	3.20	21.25	9	98			41	79	76
3	5	321.16	2.2	2.93	23.62	9	99			41	81	77
4	7.5	323.66	1.5	2.01	25.58	6	100			42	83	78
5	10	325.60	1.5	2.03	27.55	6	94			42	85	79
6	12.5	327.62	2.0	3.71	29.83	7.5	94			43	87	80
7	15	329.79	2.4	3.24	32.33	9	98			43	88	80
8	17.5	332.28	2.6	3.51	34.93	9.5	98			43	89	81
9	20	334.85	1.8	2.44	37.10	2.5	99			44	89	81
10	22.5	337.18	1.2	1.62	38.87	6	100			44	89	81
11	25	338.90	2.8	3.75	41.56	10	103			44	90	82
12	30	344.18	2.5	3.35	44.11	10	104			44	90	82
D-1	32.5	346.24	1.7	2.29	46.21	6.5	103			42	86	81
2	35	348.39	1.8	2.41	48.37	7	103			42	87	82
3	37.5	350.56	1.9	2.55	50.89	7	103			43	88	82
4	40	352.79	1.9	2.55	52.81	7	103			44	88	82
5	42.5	354.71	1.5	2.03	54.79	6	99			45	89	83
6	45	356.73	1.5	2.05	56.79	6	94			45	90	83
7	47.5	358.95	1.8	2.45	58.97	7	98			45	90	83
8	50	361.15	1.9	2.58	61.20	7.5	98			46	90	84
9	52.5	363.30	1.7	2.34	63.32	7.5	98			46	90	84
10	55	365.40	1.6	2.16	53.37	7	104			47	90	84
11	57.5	367.50	1.7	2.28	7.47	7	107			48	91	84
12	60	369.55	1.6	2.15	69.51	7	107			48	92	85
Σ = 53.31											Av. = 84.3	
Σ = 60												

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / Sagola Date 6/25/93 Test 2 Run 3
 Source Press + Unloading Vent Stacks No. of traverse points 24
 Method 0011 Filter Holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: { 0 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) MECL₂ + DI H₂O

No. of probe wash bottles: 1
 Sample recovered by: D/H

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1		200	
Impinger No. 2	208		8
Impinger No. 3			
Condenser			
Desiccant	1332	1320	12
Total			

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICI / SAGOLA Operator DUH + S.E Pitot No. 123-6 CP 84
 Supp. RESS / UNLOADING VENT STACK Motor Box No. 7 XHP 1.97 IN HC 1.97 Bar. Press. 28.44 IN HG 2 IN.
 Date 6/25/93 Computer conf. 7 983 Nozzle No. 7-3 Nozzle Dia. 1.22 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in HC)	Drifted Meter (in HC)	Des. Vol. (cf)	VAC. in HG	Temperature (°F)				Gas In	Gas Out	Oxygen (xy/v)
							Stack	Probe	Duct	Inpy.			
1	1336	369.90	1.80	2.44	2.06	5	98			44	80	80	AMBIENT
2	2.5	372.30	1.80	2.42	4.22	5	98				84	82	AIR
3	5	374.23	1.80	2.42	6.35	5	99			45	87	82	
4	7.5	376.40	1.75	2.36	8.39	5	99				90	83	
5	10	378.46	1.60	2.16	0.38	5	99			43	91	83	
6	12.5	380.40	1.50	2.04	2.41	5	99				90	83	
7	15	382.40	1.55	2.11	4.64	5	99			45	92	84	
8	17.5	384.60	1.90	2.58	6.82	5	99				95	85	
9	20	386.72	1.80	2.45	9.05	5	109			46	94	85	
10	22.5	389.01	1.90	2.54	1.25	5	106			45	95	86	
11	25	391.20	1.85	2.49	3.37	4.5	105				96	86	
12	27.5	393.35	1.7	2.30	5.36	4.5	106			45	92	86	
1	30	395.33	1.5	2.03	7.98	7	104				95	87	
1	32.5	397.96	2.6	3.52	0.60	7	98			46	93	86	
2	35	400.56	2.6	3.54	3.23	7	97				95	87	
3	37.5	403.25	2.6	3.55	5.81	7	97			45	95	87	
4	40	405.70	2.5	3.43	8.20	6	100				97	88	
5	42.5	408.16	2.15	2.93	0.20	6	98			46	98	85	
6	45	410.71	1.50	2.06	5.21	6	102				98	89	
7	47.5	412.60	2.20	3.0	7.84	6	102			46	99	89	
8	50	415.26	2.5	3.41	0.47	6	102				99	89	
9	52.5	417.80	2.6	3.53	3.11	6	102				99	89	
10	55	420.40	2.6	3.54	5.61		102				99	89	
11	57.5	423.04	2.6	3.55			102				99	89	
12	60	425.50	2.35	3.21			102				99	89	
(1433)													
Average	10 = 60	55.60		2.80							Avg. = 89.5		

Start Test 3 Run at 1241

ICI / Sagola

ambient air Press + Unloading Vent Stack


6/25/93

30 ppm wds

0 10 20 30 40 50 60 70 80 90 100

CHART NO. LIC-0100-0011

100 90 80 70 60 50 40 30 20 10 0



RUN 2 5.8 PPM C_3H_8
17.5 PPM C

1341

RUN 1 6.4 PPM C_3H_8
(19.2 PPM C)

Start Test 3 Run 1 at 1241

ICI / Sagola


ambient air Press + Unloading Vent-Stack

6/25/93


30 ppm bias

C-17


CHART NO. 1




RUN 3 5.8 PPM C₂H₄
17.4 PPM C



zero gas
start T₃R₃ at 1450
scale 0-100 ppm
30 ppm gas




RUN 2



INTERPOL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ICI / Sagola
 Source Press & Chubading Vents Stack
 Test 4 Run Date 6/26/93
 Stack dimen. 71.25 IN.
 Dry bulb 100°F Wet bulb 76 °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 28.36 in Hg
 Static pressure - .85 in WC
 Operators: D. VAN HOPPER & J. Ertle
 Pitot No. V23-6 C_p .87



Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	in.	Time start:	hrs
A 1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
B 1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
Temp. meas. device & S/N: <u>PDT #18</u>				Time end:	hrs

R or nothing = reg. manometer; S = expanded; E = electronic

S-3921

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / Sago/9 Date 6/26/83 Test 4 Run 1
 Source PRESS + UNLOADING VENT No. of traverse points 24
 Method FF Filter holder: 91255 Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 15 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
☒ other(s) 1-2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: DUAL

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	80	122	-42
Impinger No. 2	81	84	-3
Impinger No. 3			
Condenser			
Desiccant			
Total			

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

Job _____ ICI / Sagola
 Source _____ PRESS & UNLOADING VEN
 Date 6/24/93 1991 2

0000	IC-I / Sag. 0.14
0001	PRESS & UNLOADING VENT STACK
0002	000003 1951 24 NOV 1

Department of
Water & Power
Construction

863
11x 6
3.5 x 4

1.27-28.7 JN NJ JN NC

Pitt Pitt
Bur. Pitt
Mozz Pitt

$$\begin{array}{r} \sqrt{23-6} \\ 16.28-36 \\ \hline 5-2 \end{array}$$

CP - 8
in Hg D: 10

$$\begin{array}{r} 21 \\ 130 \overline{) 2114} \\ \underline{260} \\ 514 \\ \underline{460} \\ 540 \\ \underline{520} \\ 20 \end{array}$$

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Orifice Meter (in H ₂ O)	Dis. Vol. (cf)	VAC. in Hg	Temperature (°F)						Oxygen (Xv/v)
							Stack	Probe	Duct	Inlet	CasIn	Out/Dut	
C 1	0836	427.00	2.4	.75	8.42	5	86	NO	HEAT	40	64	64	AMBIENT
2	4	428.54	2.6	.81	9.90	5	85				67	65	AIR
3	9	429.95	2.6	.81	1.39	5	86			39	69	66	
4	12	431.40	2.5	.78	2.84	5	89			40	71	66	
5	15	432.90	2.15	.67	4.20	5	89				72	67	
6	18	435.60	2.10	.66	5.54	5	89				74	68	
7	21	436.90	2.2	.69	6.91	5	89			39	74	69	
8	24	438.40	2.3	.72	8.32	5	90				76	69	
9	27	439.80	2.6	.82	9.82	5	90			38	77	70	
10	30	441.36	2.6	.82	1.32	5	91				77	70	
11	33	442.70	2.1	.65	2.66	5	101			38	78	71	
12	36	444.30	2.4	.74	4.09	5	101				79	71	
D 1	39	445.23	1.2	.37	5.10	4	101			40	74	70	
2	42	446.40	1.6	.49	6.26	4	100				77	72	
3	45	447.56	1.9	.59	7.55	4	98			40	79	72	
4	48	448.70	1.7	.53	8.76	4	95				80	73	
5	51	449.88	1.6	.50	9.94	4	95			40	80	73	
6	54	451.20	1.8	.56	1.19	4	95				81	74	
7	57	452.46	1.8	.56	2.44	4	95			43	82	74	
8	60	453.64	1.70	.53	3.66	4	95				82	74	
9	63	454.90	1.70	.54	4.89	4	87			40	83	75	
10	66	456.10	1.7	.54	6.12	4	87				83	75	
11	69	457.46	1.85	.59	7.41	4	87				83	75	
12	72	458.73	1.8	.57	8.67	4	87				84	75	
												Avg. = 73.8	
				AH = .64									
				VM = 31.7 ft/s									
				(0952)									
				P = 73									

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI Sagola Date 6/26/83 Test 4 Run 2
 Source PRESS & UNLOADING VENT No. of traverse points 24
 Method FF Filter holder: glass Filter type: glass

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ~~0~~
 Posttest: { 0 cfm at 6 in. Hg. (vac) ~~0~~

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☒ other(s) 1-2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: PORT

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	93	126	-33
Impinger No. 2	84	85	-1
Impinger No. 3			
Condenser			
Desiccant			
Total			-34

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES A METHOD 5 FIELD DATA SHEET

Job TLI Sagola Operator Duck & S.E. Pilot No. V23-6 Cp 1.5
 Source Press & Unloading Motor Box No. 7 Bar. Pres. 25.30 inHg H₂O 2 X
 Date 6/26/83 Computer Code: 9483 Nozzle No. 3-2 Nozzle Dia. .30 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cc)	Velocity Head (inWC)	Orifice Meter (inWC)	Dis. Vol. (cc)	VAC. inHg	Temperature (°F)				Oxygen (xv/v)	
							Stack	Probe	Duct	Gas In Gas Out		
D 1	121	459.20	1.90	.59	0.47	45	101		40	72	72	AMBIENT
2	3	460.55	1.85	.57	1.72	45	100			74	72	AIR
3	6	461.20	2.0	.62	3.02	5	100			77	74	
4	9	463.09	1.8	.56	4.27	5	100		40	77	74	
5	12	464.50	1.8	.56	5.51	5	100			77	75	
6	15	465.60	1.7	.53	6.72	5	97			81	76	
7	18	466.77	1.6	.5	7.91	5	97		40	82	76	
8	21	467.96	1.6	.5	9.09	5	97			82	76	
9	24	469.12	1.9	.6	10.38	5	94			83	77	
10	27	470.38	1.7	.54	1.61	5	91		41	84	77	
11	30	471.80	1.70	.54	2.84	5	91			83	78	
12	33	472.89	1.80	.57	4.11	5	91		41	85	78	
C 1	36	474.15	1.6	.50	5.29	5	98			80	78	
2	39	475.30	2.6	.82	6.81	5	93		44	82	78	
3	42	476.75	2.6	.82	8.32	5	92			83	78	
4	45	478.26	2.5	.79	9.81	5	92		43	84	78	
5	48	479.80	2.5	.79	1.30	5	93			85	79	
6	51	481.28	2.4	.76	2.76	5	93			85	79	
7	54	482.79	2.4	.76	4.22	5	94		44	86	79	
8	57	484.30	1.95	.61	5.53	5	99			86	79	
9	60	485.53	2.10	.66	6.89	5	102		45	86	80	
10	63	486.93	2.4	.75	8.34	5	103			87	80	
11	66	488.36	2.6	.81	9.85	5	105			87	80	
12	69	489.86	2.6	.81	1.30					87	80	
12	72	491.40	2.6	.81						87	80	
1241												
V = 29.20		H = 65		Avg. = 79.7								

INTERFOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI Sagola
 Source PRESS & UNLOADING VENT
 Method MDL-FF Filter holder: 9/RES

Date 6/26/83 Test 4 Run 3
 No. of traverse points 24
 Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) 1-2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: DUP

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>100</u>	<u>130</u>	<u>-30</u>
Impinger No. 2	<u>86</u>	<u>86</u>	<u>—</u>
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>-30</u>

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____


CF-023

INTERPOLL LABORATORIES A METHOD 5 FIELD DATA SHEET

Job ICI Sagola Operators DUA & S.F. Pitot No. U23-6 Cp 1.8
 Source Process + unloading vent stack Motor Box No. 7 IN NC 28.30 IN Hg 2 X
 Date 6/26/93 Gasometer Count 7 9983 Nozzle No. 3-2 Nozzle Dia 130 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Orifice Meter (in H ₂ O)	Des. Vol. (cf)	VAC. in Hg	Temperature (°F)				Dwyer (xv/v)	
							Stack	Probe	Oven	Imp.	Gas/in	Gas/Dut
1	1353	491.82	1.4	.44	2.93	6	89			45	74	74
2	3	493.86	2.6	.82	4.44	6	86			43	75	74
3	6	494.46	2.6	.83	5.95	6	86				75	74
4	9	495.93	2.6	.80	7.43	8	85			42	75	74
5	12	497.46	1.8	.58	8.70	8	83				75	74
6	15	498.83	2.1	.67	10.06	8	82			43	75	74
7	18	500.03	2.2	.70	11.25	8	82			40	75	74
8	21	501.66	2.4	.77	12.91	8	82				75	74
9	24	502.90	2.7	.86	14.45	8	82			40	75	74
10	27	504.46	2.6	.82	15.95	8	91				75	74
11	30	505.96	2.5	.79	17.43	8	91			41	75	74
12	33	507.43	2.6	.82	18.93	8	91				75	74
1	36	508.94	1.6	.50	20.11	8	95				75	73
2	39	510.16	1.9	.60	21.39	8	90			40	75	73
3	42	511.35	1.8	.56	22.64	8	93				75	73
4	45	512.66	1.8	.56	23.89	8	93			41	74	72
5	48	513.90	1.6	.50	25.06	8	90				74	72
6	51	515.10	1.50	.47	26.20	6	90			41	74	72
7	54	516.63	1.90	.60	27.49	8	89				73	72
8	57	517.86	1.80	.57	28.74	8	88			41	73	71
9	60	518.86	1.8	.57	29.99	8	88				73	71
10	63	519.96	1.8	.57	31.24	8	88			40	73	71
11	66	521.30	1.8	.56	32.48	8	90				74	71
12	69	522.49	1.75	.55	33.71		90			40	74	72
12	72	523.82										
(1509)												
V = 33.00												
W = 63												
Avg. = 73.6												

Job ICI SAGOLA
Source PRESS AND UNLOADER VENT
Test 5 Run 0 Date 6-26 STACK
Stack dimen. 71-25 IN.
Dry bulb _____ °F Wet bulb _____ °F
Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 28.36 in Hg
Static pressure -.85 in WC
Operators GH & SE
Pitot No. 27 ✓ 6 Cp .84



MDI - FILTER LAST

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI SAGOLA STACK Date 6-26-93 Test 5 Run 1
 Source PRESS AND UNLOADER VENT No. of traverse points 24
 Method MOI Filter holder: GLASS Filter type: G.F.

FILTER LAST

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 10.2 cfm at 8 in. Hg. (vac) ☐
LESS THAN

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

NA ☐ acetone
☒ other(s) 1,2-DIPICIN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>25</u>

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICL SAGOLA, MICH Operators GH & SF Pilot No. 2706 DP 84
 Service STRESS AND HYDRAULIC VENT Motor Box No. 3 Bar. Press. 28.36 IN HG 20.9
 Date 6-26-93 Computer Edit. 9970 IN UC 174 Nozzle Dia. 1.25 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Orifice Meter (in H ₂ O)	Des. Vol. (cf)	VAC. in Hg	Temperatures (°F)					Oxygen (xv/v)
							Stack	Probe	Duct	Gas In	Gas Out	
D-12	0830	73.760	1.7	.40	4.88	4	88	NO	NO	72	72	20.9
11	3	74.88	1.5	.36	5.94	3	85			73	69	20.9
10	6	75.94	1.7	.40	7.06	4	86			75	71	20.9
9	9	77.06	1.7	.40	8.19	4	86			78	71	20.9
8	12	78.19	1.7	.40	9.31	4	90			78	72	20.9
7	15	79.31	1.7	.40	10.44	4	89			80	73	20.9
6	18	80.44	1.7	.40	11.58	4	89			81	74	20.9
5	21	81.58	1.7	.40	12.71	5	89			83	75	20.9
4	24	82.71	2.2	.53	13.84	5	90			82	75	20.9
3	27	83.84	3.0	.68	14.97	4	90			83	75	20.9
2	30	84.97	1.5	.36	16.10	4	101			85	77	20.9
A	33	86.10	1.7	.40	17.23	4	100			86	77	20.9
13	36	87.23	1.65	.39	18.36	4	100			85	78	20.9
11	39	88.36	1.7	.40	19.49	4	100			87	79	20.9
10	42	89.49	2.5	.59	20.62	5	100			88	79	20.9
9	45	90.62	2.8	.66	21.75	5	99			88	79	20.9
8	48	91.75	2.85	.62	22.88	5	99			89	80	20.9
7	51	92.88	2.5	.59	24.01	5	99			89	80	20.9
6	54	94.01	1.7	.40	25.14	5	99			89	80	20.9
5	57	95.14	1.7	.40	26.27	5	98			89	81	20.9
4	60	96.27	1.9	.45	27.40	5	99			89	81	20.9
3	63	97.40	2.2	.52	28.53	5	100			89	80	20.9
3	66	98.53	2.2	.54	29.66	5	86			89	81	20.9
3	69	99.66	2.4	.58	30.79	5	89			89	82	20.9
1	72	100.79	2.4	.58	31.92	5	90			90	81	20.9
	0955											
Σ = 72							Avg. = 80.3					

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI SAGOLA Date 6-26-83 Test 5 Run 2
 Source PRESS AND UNLOADER No. of traverse points 24
 Method MD1 Filter holder: GLASS Filter type: 2.5 GF
FL

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.02 cfm at 12 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

NA ☐ acetone ☒ other(s) 1, 2 MP IN TOLUENE

No. of probe wash bottles: 1

Sample recovered by: CH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1		<u>131</u>	<u>-69</u>
Impinger No. 2	<u>81</u>	<u>84</u>	<u>-3</u>
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>15</u>

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICI SAGOSA MICH Operator CH A S. F. F. F. Pilot No. 2716 Cp. 84
 Sample PRESS AND UNLOADER VENT Water Box No. 63 Bar. Press. 28.36 inHg H₂O 2 X
 Date 6-26-93 Calculator 5 Run 2 Nozzle No. 27-2 Nozzle Dia. 125 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inHg)	Orifice Water (inHg)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)				Oxygen (xv/v)		
							Stack	Probe	Oven	Leq.		Gas/In	Gas/Out
		103.53			4.81	9	101	NONE		39	76	76	20.9
A 12	3	104.81	3.2	.52	6.05	10	100			39	77	76	20.9
11	6	106.05	3.1	.49	7.38	10	100			39	78	76	20.9
10	9	107.38	2.4	.56	8.74	10	100			40	78	76	20.9
9	12	108.74	2.5	.59	9.96	10	100			40	82	78	20.9
8	15	109.96	2.0	.47	1.25	10	97			40	82	78	20.9
7	18	111.25	3.2	.52	2.38	10	101			40	84	78	20.9
6	21	112.38	1.7	.40	3.54	10	97			39	86	80	20.9
5	24	113.54	1.8	.43	4.75	10	94			41	86	80	20.9
4	27	114.72	1.9	.45	6.04	10	95			40	86	80	20.9
3	30	116.04	2.2	.53	7.34	10	91			39	80	80	20.9
2	33	117.34	2.2	.53	8.64	10	93			39	86	81	20.9
1	36	118.64	2.2	.53	9.71	8	98			40	82	79	20.9
D 12	39	119.71	1.5	.36	0.85	7	93			39	88	83	20.9
11	42	120.85	1.7	.40	2.03	7	92			40	89	83	20.9
10	45	122.03	1.8	.43	3.21	10	96			40	90	88	20.9
9	48	123.21	1.8	.46	4.43	10	93			41	90	84	20.9
8	51	124.43	1.9	.48	5.68	10	93			39	91	84	20.9
7	54	125.68	2.0	.39	6.79	10	92			39	90	84	20.9
6	57	126.79	1.6	.38	7.90	10	99			39	91	84	20.9
5	60	127.90	1.6	.38	9.02	10	97			40	91	85	20.9
4	63	129.02	1.8	.43	0.19	10	102			40	91	84	20.9
3	66	130.19	1.8	.43	1.36	10	103			40	91	85	20.9
2	69	131.36	1.8	.40	2.50	10	105			40	91	85	20.9
1	72	132.64	1.7										
		(1240)											
		V = 29.01	ΔH = 44	Avg. = 83.5									
		O = 72											

INTERFOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI SAGOLA STACK Date 6 Test 5 Run 3
 Source PRESS AND UNLOADER VENT No. of traverse points 24
 Method MOL Filter holder: GLASS Filter type: 25 GF
FL

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 1.02 cfm at 12 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: NA Recovery solvent(s) ☐ acetone ☒ other(s) 1, 2-MP IN TOLUENE
 No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

189
274 →
313
Final 284
189
272
Final 272

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant			
Total			

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job 101 SAGACA Pitot No. 2706 CP 84
 Source WESS AND UNLOADER VENT Meter Box No. 3 Bar. Press. 1.74 IN HG H₂O 3 X
 Date 6-26-93 Computer Serial 9970 Nozzle No. 27-2 Nozzle Dia. 2.25 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Orifice Meter (inH ₂ O)	Des. Vol. (cf)	VAC. (inHg)	Temperature (°F)					Oxygen (xv/v)	
							Stack	Probe	Duct	Imp.	Gas In		Gas/Duct
UNRECORDED (1353)													
D-13	3	133.03	1.7	.71	4.17	5	89	N0	N0	39	80	80	20.9
11	6	134.17	1.7	.74	5.31	5	90			40	82	80	20.9
10	9	135.31	1.7	.71	6.46	5	86			41	83	81	20.9
9	" 12	136.46	1.9	.76	7.67	5	85			40	84	81	20.9
8	" 15	137.67	1.9	.74	8.88	6	87			41	84	81	20.9
7	" 18	138.88	2.0	.79	0.13	6	81			39	85	81	20.9
6	" 21	140.13	2.0	.79	1.39	6	82			39	85	81	20.9
5	" 24	141.39	1.8	.74	2.57	6	83			39	86	81	20.9
4	" 27	142.57	2.1	.50	3.84	5	95			40	87	81	20.9
3	" 30	143.84	1.8	.73	5.02	5	91			41	87	81	20.9
2	" 33	145.02	1.8	.73	6.20	5	91			41	87	81	20.9
1	" 36	146.20	1.9	.76	7.41	5	91			40	87	81	20.9
A 12	" 39	147.41	2.5	.60	8.80	7	91			39	86	81	20.9
11	" 42	148.80	2.5	.60	1.19	7	90			42	87	81	20.9
10	" 45	150.19	2.6	.63	1.60	8	93			41	88	81	20.9
9	" 48	151.60	3.6	.63	3.01	8	93			39	88	81	20.9
8	" 51	153.01	2.2	.53	4.32	6	92			39	88	81	20.9
7	" 54	154.32	1.7	.41	5.46	6	96			39	88	81	20.9
6	" 57	155.46	1.9	.46	6.67	5	89			39	89	81	20.9
5	" 60	156.67	1.8	.43	7.86	5	90			40	89	81	20.9
4	" 63	157.86	1.9	.46	9.07	5	90			39	89	81	20.9
3	" 66	159.07	2.4	.58	0.44	6	89			40	89	82	20.9
2	" 69	160.44	2.4	.58	1.80	7	90			41	90	82	20.9
1	" 72	161.80	2.2	.53	3.11	6	90			41	90	82	20.9
UNRECORDED (1510)													
0 = 72													
V = 30.08													
Avg. = 83													

on

Job ICI SAGO A
Source press d unloading vent stack
Test 6 Run 0 Date 6-26-93
Stack dimen. 71.25 IN.
Dry bulb °F Wet bulb °F
Manometer: ☐ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 28.36 in Hg
Static pressure -85 in WC
Operators GH, JB
Pitot No. 236 Cp .84

Elevation
View

Drawing of Test Site

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / Sagola
 Source Press + unloading vent stack
 Method Nitro Filter holder: ERC

Date 6/26/93 Test 6 Run 1
 No. of traverse points _____
 Filter type: Glass fiber

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ~~X~~
 Posttest: { 0 cfm at 15 in. Hg. (vac) ~~X~~

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) meth. chloride

No. of probe wash bottles: _____

Sample recovered by: DUH/JS

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1362	1336	26
Total			26

Integrated Gas Sampling Data:

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES A METHOD 5 FIELD DATA SHEET

Job IC I / Sagola Operator SEFF BERSIG Pitot No. V-23-6 Dp 204
 Source Press + unloading vent stacks Meter Box No. 6 No. 1.72 IN MC Bar. Press. 28.36 IN HG No. 2
 Date 6-26-43 Gas meter const. 9946 Nozzle No. 2-2 Nozzle Dia. 1.82 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Drifted Meter (in H ₂ O)	Des. Vol. (cf)	VAC. in Hg	Temperature (°F)				Gas in Col/Dut	Oxygen (xv/v)
							Stack	Probe	Dyn	Impq.		
A-1	0836	499.85	2.5	3.02	02.8	9	86	120	Heat	40	83	20.9
2	5	502.30	2.3	2.85	04.83	9	86			41	83	
3	7.5	504.75	2.35	2.91	07.32	9	86			41	83	
4	10	507.28	2.2	2.71	09.73	9	90			41	84	
5	12.5	509.68	2.0	2.47	12.04	9	89			42	85	
6	15	514.30	1.9	2.35	14.28	8	89			42	86	
7	17.5	516.70	2.3	2.85	16.76	9	88			42	86	
8	20	519.00	2.0	2.47	19.06	9	90			43	87	
9	22.5	521.19	1.75	2.17	21.23	8	90			43	89	
10	25	523.39	1.90	2.36	23.48	8	91			43	88	
11	27.5	526.01	2.5	3.09	26.06	10.5	91			44	87	
12	30	528.73	2.7	3.37	28.71	12	101			44	85	
B-1	32.5	530.80	1.75	2.12	30.85	7	101			45	83	
2	35	532.89	1.70	2.05	32.95	7	101			42	86	
3	37.5	535.06	1.75	2.13	35.09	7	100			42	85	
4	40	537.27	1.85	2.25	37.29	7	98			41	84	
5	42.5	539.43	1.8	2.18	39.45	7	98			42	82	
6	45	541.40	1.5	1.81	41.62	6.5	98			42	81	
7	47.5	543.59	1.9	2.29	43.83	6.5	98			43	82	
8	50	545.95	2.15	2.60	46.08	9.5	98			43	84	
9	52.5	548.31	2.2	2.68	48.33	9.5	95			44	86	
10	55	550.67	2.15	2.62	50.58	9.5	96			45	86	
11	57.5	553.05	2.1	2.56	52.83	9.5	96			45	86	
12	60	555.51	2.15	2.67	55.08	10	86			45	87	
	0946											
W = 5566											Av. = 83.6	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / sagola Date 6/26/83 Test 6 Run 2
 Source Press + unloading vent stack No. of traverse points 24
 Method VITRO Filter holder: ERC Filter type: Glass Fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 15 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s)
☐ acetone
☒ other(s) Meth. Chloride
 No. of probe wash bottles: 1
 Sample recovered by: DVH / SA

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	—	—	
Impinger No. 2	—	—	
Impinger No. 3	—	—	
Condenser	—	—	
Desiccant	1460	1433	27
Total			27

Integrated Gas Sampling Data:

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES METHOD 5 FIELD DATA SHEET

Job ICF / Sagoka Operators JEFF BERGERON Pitot No. V-23-6 Cp 64
 Source Press + unloading vent stack Motor Box No. 6 Bar. Press. 23.36 inHg 2 x
 Date 6-26-92 Computer Cont. 9996 Nozzle No. 2-3 Nozzle Dia. 1/8" - 1/4"

Traverse Point No.	Sampling Time (min)	Supply Volume (cf)	Velocity Head (inWC)	Orifice Meter (inWC)	Obs. Vol. (cf)	VAC. inHg	Temperature (°F)				Oxygen (Xv/v)		
							Stack	Probe	Dry	Wet			
B-1	112.1	555.80	1.5	1.81	2.77	4	101	120	Heat	39	85	85	20.9
2	2.5	552.74	1.4	1.69	9.68	4	104			40	87	86	
3	5	559.65	1.75	2.13	18.3	4	100			41	87	85	
4	10	564.00	1.85	2.25	40.3	4	100			41	86	84	
5	12.5	566.15	1.80	2.17	6.19	4	103			41	85	83	
6	15	568.40	1.85	2.25	8.39	4	97			42	85	82	
7	17.5	570.04	1.5	1.22	0.02	3	101			42	85	82	
8	20	572.15	1.8	2.18	2.18	4	101			43	86	82	
9	22.5	574.50	2.25	2.72	4.59	5	101			43	85	81	
10	25	576.98	2.2	2.69	6.99	5	94			43	86	82	
11	27.5	579.35	2.15	2.65	9.38	5	91			44	86	82	
12	30	581.63	1.90	2.34	16.2	4.5	92			44	89	84	
A-1	32.5	584.15	2.45	2.99	4.16	5.5	98			41	83	82	
2	35	586.65	2.50	3.05	6.71	5.5	94			42	84	81	
3	37.5	589.12	2.2	2.70	9.11	5.5	92			42	85	81	
4	40	591.46	2.0	2.44	1.40	5	96			43	86	83	
5	42.5	593.55	1.8	2.21	3.58	4.5	93			43	85	80	
6	45	595.70	1.75	2.14	5.72	4.5	93			43	86	81	
7	47.5	598.12	2.20	2.70	8.13	5	93			44	89	82	
8	50	600.77	2.55	3.13	0.72	6	94			45	87	81	
9	52.5	603.35	2.70	3.27	3.37	6	99			45	87	82	
10	55	606.52	2.45	3.59	6.14	6.5	97			46	88	82	
11	57.5	608.80	2.75	3.35	8.82	6.5	97			46	89	83	
12	60	611.31	2.3	2.81	1.28	5.5	98			46	90	84	
Avg. = 84.4													

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / Sagola Date 6/26/93 Test 6 Run 3
 Source Press + Unloading Vent Stack No. of traverse points 24
 Method Nitro Filter holder: ERC Filter type: Glass Fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 15 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: 1 Recovery solvent(s)
☐ acetone
☒ other(s) meth. chloride
 No. of probe wash bottles: 1
 Sample recovered by: DVH / JB

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	—	—	
Impinger No. 2	—	—	
Impinger No. 3	—	—	
Condenser	—	—	
Desiccant	1389	1362	27
Total			27

Integrated Gas Sampling Data:

Bag Pump No. _____ Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: 1 cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023



INTERPOL LABORATORIES PA METHOD 5 FIELD DATA SHEET

Job 2 CI / Sagoka Operator EFF BERGROM Pilot No. U-23-6 CP 04
 Source Press. + Umbilical Vent Stack Meter Box No. 177 IN NC 2836 IN HG 209
 Date 6/20/83 Computer Code 9996 Nozzle No. 2-3 Nozzle Dia. 182 IN.

Traverse Point No.	Sampling Time (min)	Supply Volume (cf)	Velocity Head (inWC)	Orifice Meter (inWC)	Dis. Vol. (cf)	VAC. inHg	Temperature (°F)					Oxygen (Xv/vv)
							Stack	Probe	Duct	Imp.	Gas/In	
A-1	1353	611.60	2.65	3.25	4.24	8	89	120	Heat	40	79	20.9
2	2.5	614.17	2.6	3.16	6.82	8	89			40	79	
3	5	616.79	2.6	2.69	9.22	7.5	86			41	80	
4	7.5	619.17	2.20	2.57	1.56	7	85			41	80	
5	10	621.63	2.10	2.53	3.79	7	85			41	81	
6	12.5	623.84	1.90	2.15	5.93	7	86			42	82	
7	15	625.99	1.75	2.90	8.41	7	82			42	84	
8	17.5	628.47	2.35	3.46	1.13	7	82			42	85	
9	20	631.10	2.80	3.53	3.87	9	82			43	85	
10	22.5	633.81	2.85	3.14	6.46	9	95			43	85	
11	25	636.45	2.60	2.66	8.85	8	95			44	85	
12	27.5	638.79	2.20	2.06	0.95	6.5	95			44	80	
B-1	30	640.99	1.70	2.20	3.34	7	95			44	85	
2	32.5	643.30	1.75	2.11	5.68	6.5	95			41	87	
3	35	645.61	1.80	2.18	7.62	6	95			42	80	
4	37.5	647.60	1.80	2.20	9.80	6	90			43	81	
5	40	649.84	1.85	2.26	2.00	6	91			43	90	
6	42.5	652.19	1.50	1.83	3.99	6	93			43	90	
7	45	653.94	2.0	2.45	6.29	7	93			44	91	
8	47.5	656.20	2.10	2.56	8.64	7	94			44	91	
9	50	658.60	2.20	2.69	1.05	7.5	94			45	92	
10	52.5	661.03	1.65	2.01	3.13	6.5	96			45	92	
11	55	663.10	1.55	1.91	5.17	6	90			46	93	
12	57.5	665.15	1.50	1.86	7.18	6	89			46	85	
12	60	667.21	1.50	1.86		6						
	(1506)											
		V = 55.6		ΔH = 2.5							Av. = 82.1	

INTERPOL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ICI / TWO HARBORS
 Source PRESS VENT STACK
 Test 1 Run Date 6/29/93
 Stack dimen. 55 x 55 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.19 in Hg
 Static pressure -78 in WC
 Operators D. VanHoever + J. Bergstrom
 Pitot No. V23-5 Cp 84

Cross-section View 	Elevation View 
Drawing of Test Site <u> </u>	

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	in.	Time start:	hrs
A 1					
2					
3					
4					
5					
6					
B 1					
2					
3					
4					
5					
6					
C 1					
2					
3					
4					
5					
6					
D 1					
2					
3					
4					
5					
6					
Temp. meas. device & S/N: <u>PDT #18</u>				Time end:	hrs

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI Two Harbors
 Source PRESS VENT STACK
 Method 0011 Filter holder: NA

Date 6/29/93 Test 1 Run 1
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 7 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) MECC₂ + DI H₂O

No. of probe wash bottles: 1
 Sample recovered by: DH

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2	<u>195</u>	<u>200</u>	<u>-5</u>
Impinger No. 3			
Condenser			
Desiccant	<u>1304</u>	<u>1297</u>	<u>7</u>
Total			<u>2</u>

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICS / TWO HARBORSSource Press Vent StackOperator DEMO G.H.Meter Box No. 7 SHF 1.97 IN RCComputer Config. 7 9983Pilot No. V23-5 CP 8-1Bar. Press. 29.9 IN Hg H2O 2 RNozzle No. 6-4 Nozzle Dia. 251 IN.Date 6/29/83 Test 7 Run 1

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Orifice Meter (in H ₂ O)	Vac. in Hg	Temperature (°F)				Gas In	Gas Out	Oxygen (xv/v)
						Stack	Probe	Duct	Atm.			
A 6"	0822	532.70	.23	1.0	4.06	93			43	81	80	Ambient
5	2.5	534.09	.26	1.14	5.53	94				82	80	AIR
4	2.5	535.50	.26	1.14	6.99	97				83	81	
3	10	536.96	.10	.44	7.96	97				85	82	
2	12.5	537.97	.03	.13	8.40	97				87	84	
1	15	538.96	.01	.04	8.70	95				88	85	
B 6"	17.5	540.94	.65	2.88	1.03	95				96	89	
5	20	543.57	.88	3.95	3.77	93				98	90	
4	22.5	546.00	.60	2.69	6.04	96				100	91	
3	25	548.40	.69	3.09	8.47	98				100	91	
2	27.5	550.58	.51	2.3	0.58	95				102	92	
1	30	551.76	.16	.73	1.77	88				102	93	
C 6"	32.5	554.40	.74	3.39	4.32	88				103	94	
5	35	557.16	.90	4.08	7.12	93				104	94	
4	37.5	559.85	.84	3.80	9.83	95				105	95	
3	40	562.36	.66	2.99	2.23	97				106	96	
2	42.5	564.71	.16	8.73	4.53	95				106	96	
1	45	565.23	.05	.22	5.20	95				103	96	
D 6"	47.5	567.26	.44	2.0	7.17	95				104	96	
5	50	569.52	.54	2.47	9.36	92				105	97	
4	52.5	571.20	.30	1.37	0.99	95				103	96	
3	55	572.96	.47	2.04	2.98	98				105	97	
2	57.5	573.68	.08	.36	3.82	93				106	97	
1	60	574.61	.08	.36	4.67	93				103	97	
(0922)												
V = 41.91												
V = 6.0												
V = 4.89												
Avg. = 94.7												

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / TWO HARBORS
 Source PRESS VENT STACK
 Method 0011 Filter holder: NA

Date 6/29/93 Test 1 Run 2
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☐
 Posttest: 0 cfm at 8 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) MCCl₂ & DEH₂O

No. of probe wash bottles: 1
 Sample recovered by: DOH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2	<u>202</u>	<u>200</u>	<u>2</u>
Impinger No. 3			
Condenser			
Desiccant	<u>1409</u>	<u>1400</u>	<u>9</u>
Total			<u>11</u>

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICR / Two Harbors
 Source Press Vent Stack
 Date 6/29/83

Operator Dud & J.B.
 Motor Box No. 7
 Generator Conf. 983

Pilot No. 123-5 Cp 84
 Bar. Press. 29.17 inHg H₂O 1 in.
 Hozzle No. 6-4 Hozzle Dia. 2.5 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Orifice Water (inH ₂ O)	Dis. Vol. (cf)	VAC. inHg	Temperature (°F)				Stack	Probe	Duct	Tapp.	Gas In	Gas Out	Oxygen (xv/v)
							Stack	Probe	Duct	Tapp.	Gas In	Gas Out					
D	0957	574.90															
	2.5	577.14	.55	2.55	7.11	45	88				93	93		47	93	93	AMBIEN
	5	579.57	1.67	3.07	9.53	6	93				94	95		50	95	95	AIR
	2.5	581.36	1.34	1.56	1.26	3	96				101	95					
	10	583.45	5.6	2.58	3.49	45	96				102	96		57	96	96	
	12.5	584.77	.17	.78	4.73	35	95				99	96		46	96	96	
C	15	584.93	0	.00	4.73	0	96				102	97					
	17.5	587.57	.77	3.53	7.33	6	96				103	97					
	20	590.40	.96	4.43	0.25	65	93				102	97					
	22.5	592.96	.80	3.70	2.92	6	94				103	97					
	25	592.60	.76	3.49	5.52	6	97				102	97					
	27.5	597.96	.56	2.59	7.75	4	95				103	97					
B	30	598.66	.05	.23	8.42	0	97				102	97					
	32.5	601.40	.79	3.63	1.07	6	97				103	97					
	35	603.96	.91	4.21	3.92	65	93				104	97					
	37.5	606.40	.57	2.63	6.17	45	96				105	98					
	40	608.70	.68	3.14	8.64	45	97				106	98					
	42.5	610.76	.49	2.28	0.74	4	98				107	99					
A	45	611.85	.16	.74	1.95	2.5	96				107	98					
	47.5	613.40	.23	1.07	3.39	3	96				103	97					
	50	614.73	.23	1.07	4.84	3	94				104	98					
	52.5	616.40	.21	.97	6.21	3	97				104	98					
	55	617.60	.18	.83	7.48	3	100				105	98					
	57.5	618.06	.02	.09	7.91		95				104	98					
	60	618.06	.00	0.0	7.91		97				104	98					
Avg. = 99.5																	
V _s = 43, 16																	
(1058)																	
0 = 60																	

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ILI / TWO HARBORS Date 6/29/93 Test 1 Run 3
 Source PRESS VENT STALK No. of traverse points 24
 Method 0011 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☐
 Posttest: { 0 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) MELL, & DI H₂O

No. of probe wash bottles: _____
 Sample recovered by: _____

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2	<u>199</u>	<u>200</u>	<u>-1</u>
Impinger No. 3			
Condenser			
Desiccant	<u>1310</u>	<u>1304</u>	<u>6</u>
Total			<u>5</u>

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABRATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICI / Two Harbors Date 6/29/93 Operator DCH + J.B. Pitot No. V23-S DP 8-1
 Supply Press Vent STACK Meter Box No. 7 Bar. Press. 29.19 inHg H2O 1.5 in.
 Date 6/29/93 Computer Code 9983 Nozzle No. 6-1 Nozzle Dia 25.4 in.

Traverse Point No.	Sampling Time (min)	Supply Volume (cf)	Velocity Head (inHg)	Drifts Meter (inHg)	Dps. Vol. (cf)	VAC. inHg	Temperature (°F)				Gas/Dust	Oxygen (xv/v)
							Stack	Probe	Duct	Insp.	Gas/in	
A 6	137	619.00									91	AMBIENT
5	25	620.64	30	1.37	0.63	3	99				95	92 AIR
4	5	622.11	23	1.04	2.03	3	97				96	92
4	7.5	623.61	28	1.26	3.59	3	101				97	92
3	10	625.40	24	4.03	5.40	3	101				98	92
2	12.5	625.81	102	0.9	5.45	—	100				94	91
1	15	625.81	0	0	5.45	—	97				98	93
B 6	17.5	628.12	82	3.68	8.10	3	97				102	91
5	20	630.93	90	4.04	0.89	6	94				103	95
4	22.5	633.23	64	2.91	3.26	3	98				104	95
3	25	635.56	65	2.96	5.65	5	97				104	95
2	27.5	637.80	54	2.42	7.81	5	98				103	95
1	30	638.73	113	5.9	8.88	2	101				104	96
C 6	32.5	641.43	75	3.39	1.44	6	101				105	96
5	35	644.16	92	4.20	4.28	6.5	96				105	96
4	37.5	647.06	90	4.0	7.01	6.5	98				105	96
3	40	649.42	72	3.26	9.60	6	102				105	96
2	42.5	651.82	56	2.57	1.83	5.6	96				104	96
1	45	652.70	108	3.6	2.68	1	98				103	95
D 6	47.5	654.49	35	1.60	4.44	3	98				103	96
5	50	656.55	51	2.33	6.56	4	97				105	96
4	52.5	658.60	32	1.46	8.24	3	99				105	96
3	55	660.94	52	2.36	0.38	4	101				104	97
2	57.5	661.81	119	8.6	1.68	2	102				101	96
1	60	662.14	102	0.9	2.10	—	102					
C 139												
SUMMARY		V = 43.14	ΔH = 2.0								Avg. = 97.5	

RUN 1 3.3 PPM C_3H_8
9.9 PPM C

0852

0 10 20 30 40 50 60 70 80 90 100

radio interference

0822

Start Test 3 Run 31 at 0822

Range 0-100 ppm

Speed 10 cm/hr

ICI / TWO HARBORS

Press Vent Stack 6/29

30 ppm system bias

zero gas system bias

3000 ppm gas

zero gas

100 90 80 70 60 50 40 30 20 10 0

300 ppm gas

zero gas

30 ppm

zero gas

CALIBRATION
(PROPANE STDs)




CHART NO. LIC-0100-0011

system bias 31.1 ppm gas

zero gas 11.00

1057

radio

RUN 2 3.6 PPM C₃H₈
10.8 PPM C

radio

0957

Start Run 2 Test 3 at
0957

zero gas

31 ppm bias

lost ignition - air pressure low

0922

RUN 1

0852

ICI Two Harbors
Start Test 6 Run 1 at 1321

Unloading Vent Stack

6/29/93

Scale 0-100

speed 10 cm/hr

100 90 80 70 60 50 40 30 20 10 0

1237

RUN 3 2.9 PPM C_3H_8

8.7 PPM C

1137

Start Test 3 Run 3 at 1137

6/29/93

0 10 20 30 40 50 60 70 80 90 100

Two Harbors


Press Vent Stack

system via 3.11 ppm gas

C-49

INTERPOL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ICI PRESS VENT
 Source PRESS VENT
 Test 1 Run 0 Date 6-29-93
 Stack dimen. 55 x 55 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.19 in Hg
 Static pressure -.78 in WC
 Operators GH & SE
 Pitot No. 23-V6C .84



Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>4</u> in.		Time start: <u>1310</u> hrs	
A	1	<u>4.58</u>	<u>8.58</u>	<u>.00</u>	
	2	<u>13.25</u>	<u>17.25</u>	<u>.00</u>	
	3	<u>22.92</u>	<u>26.92</u>	<u>.05</u>	
	4		<u>36.08</u>	<u>.11</u>	
	5	<u>41.25</u>	<u>44.25</u>	<u>.27</u>	
	6	<u>50.41</u>	<u>54.41</u>	<u>.10</u>	
B	1			<u>.40</u>	
	2			<u>.44</u>	
	3			<u>.55</u>	
	4			<u>.52</u>	
	5			<u>.82</u>	
	6			<u>.83</u>	
C	1			<u>.75</u>	
	2			<u>.64</u>	
	3			<u>.75</u>	
	4			<u>.91</u>	
	5			<u>.80</u>	
	6			<u>.65</u>	
D	1			<u>.00</u>	
	2			<u>.00</u>	
	3			<u>.14</u>	
	4			<u>.28</u>	
	5			<u>.36</u>	
	6			<u>.25</u>	
Temp. meas. device & S/N: <u>24</u>				Time end: <u>1320</u> hrs	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI TWO HARBORS Date 6-29-93 Test 4 Run 1
 Source PRESS VENT No. of traverse points _____
 Method 5 Filter holder: GLASS Filter type: GF
PLUS PHENOLS 4"

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 100 cfm at 15 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: 5375 Recovery solvent(s) acetone
☒ acetone
☐ other(s) _____
NO OF FILTER WASH BOTTLES - 1
 No. of probe wash bottles: 1
 Sample recovered by: GA

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1 } Impinger No. 2 }	272	268.9	3.1
Impinger No. 3	261.0	261.0	0
Condenser			
Desiccant	1403	1395	8
Total			11.1

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job 151 TWO HARBORS MN Pitot No. 23-11-6 CP -84
 Source PRESS VENT Meter Box No. 3 HP 7.24 IN MC Bar. Press. 29.14 IN Hg 1201.5
 Date 6-29-83 Recorder Conf. 9970 Nozzle No. 274 Nozzle Dia. 350 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (ft)	Drifted Water (ft)	Dwg. Vol. (cf)	VAC. IN Hg	Temperature (°F)					Dwg. Vol. (cf)
							Stack	Probe	Dry	Wet	Gas In	Gas Out
A	1322	302.70	.09	.36	359	1	895				94	94
	25	303.59	.15	.59	473	2	95				95	93
	5	304.73	.10	.39	565	2	100				96	93
	75	305.65	.10	.39	658	2	100				97	94
	10	306.58	.00	.00	658	0	98				96	94
B	125	306.58	.00	.00	658	0	96				94	90
	15	306.58	.00	.00	658	0	93				99	95
	175	309.19	.80	3.15	719	10	97				100	95
	20	311.63	.69	2.73	163	12	98				99	95
	225	313.85	.57	2.25	385	12	97				100	95
C	25	315.82	.45	1.78	582	7	97				100	95
	35	317.43	.30	1.18	743	5	98				100	95
	30	319.00	.28	1.11	900	4	100				102	96
	325	321.61	.80	3.14	161	12	98				101	94
	35	324.25	.80	3.16	425	12	92				99	95
D	375	327.02	.89	3.55	703	13	99				99	95
	40	329.57	.75	2.95	957	13	101				99	95
	425	332.15	.78	3.06	215	13	100				100	95
	45	333.47	.20	.79	347	3	100				100	95
	475	334.94	.25	.98	494	4	100				102	96
	50	336.55	.130	1.18	652	5	101				102	96
	525	337.94	.22	.87	794	5	101				103	100
	55	339.32	.22	.87	932	5	101				103	100
	575	340.26	.10	.39	026	3	100				103	100
	60	340.26	.00	.00	026	0						
(1423)												
Total		3756		145								
Avg.		37.56		145								
0 = 60												
Avg. = 97.5												

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI TWO HARBORS Date 6-29-93 Test 4 Run 2
 Source PRESS VENT No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: GLASS FIBER
PLUS PHENOLS 41'

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: + 10.2 cfm at 14 in. Hg. (vac) ☐
LESS THAN

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

5374 ☐ acetone
☐ other(s) _____
 NO. OF FILTER WASH BOTTLES: 1
 No. of probe wash bottles: 1
 Sample recovered by: CH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	274	268.7	5.3
Impinger No. 2			
Impinger No. 3			
Condenser	267	267	0
Desiccant	1460	1451	9
Total			14.3

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. _____ Bag No. _____
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORDIORIES EPA METHOD 5 FIELD DATA SHEET

Job 151 TWO HARBORS
 Source PRESS VENT
 Date 6-29-93

Operator C. MOSE
 Meter Box No. 3
 Gas meter serial 2970

Pitot No. 23 V 8
 Bar. Press. 29.7
 Nozzle No. 27

CP 8
 H₂O 1.5
 Dia. 25.0

Traverse Point No.	Sampling Time (min)	Supply Volume (cf)	Velocity Head (inH ₂ O)	Orifice Meter (inH ₂ O)	Dep. Vol. (cf)	VAC. inH ₂	Temperature (°F)				Gas/Dist	Oxygen (xv/v)
							Stack	Probe	Duct	Inlet		
A	6 (1448)	340.60	.09	.35	148	2	99				96	96
	5	341.48	.15	.59	262	2	96				97	95
	4	342.62	.10	.34	355	2	100				98	95
	3	343.55	.12	.47	457	2	99				99	95
	2	344.57	.10	.00	457	0	99				99	95
	1	344.57	.00	.00	457	0	94				99	95
B	6	349.11	.75	2.96	711	12	98				100	95
	5	349.87	.88	3.47	987	13	97				101	95
	4	352.57	.85	3.34	757	10	97				101	96
	3	355.03	.70	2.75	503	9	101				100	95
	2	357.42	.67	2.64	743	7	98				100	96
	1	358.58	.15	.59	858	2	99				101	97
C	6	361.28	.85	3.35	138	10	99				101	95
	5	363.98	.84	3.31	398	9	98				102	95
	4	366.35	.65	2.57	635	8	99				101	96
	3	368.70	.64	2.52	870	8	100				101	96
	2	370.78	.50	1.98	078	8	99				101	96
	1	372.10	.20	.79	310	3	97				101	95
D	6	373.92	.38	1.51	393	5	97				102	95
	5	375.49	.28	1.11	549	4	98				101	97
	4	376.97	.35	.99	697	4	98				101	99
	3	378.11	.15	.59	811	4	100				102	96
	2	378.11	.00	.00	811	0	98				102	96
	1	378.11	.00	.00	811	0	98				102	96
	(1549)											
Total		V = 37.51		ΔH = 1.45							Avg. = 97.5	
		0 = 60										

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job IC/ TWO HARBORS Date 6-29-93 Test 4 Run 3
 Source PRESS VENT STACK No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: GF
PLUS PHENOLS

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☐
 Posttest: { _____ cfm at _____ in. Hg. (vac) ☐

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

5378 ☒ acetone _____
☐ other(s) _____
 NO. OF FILTER WASH BOTTLES - 1
 No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	271	265.6	5.4
Impinger No. 2			
Impinger No. 3			0
Condenser			
Desiccant	1411	1403	8
Total			13.4

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

1C1
 UNLOADING VENT STACK
 6-29-93
 1991
 4
 HUN -3

Operators CH + SE
 Meter Box No. 3
 Computer Code: 9970

Pitot No. 23V-6 Cv 84
 Bar. Press. 29.17 in Hg H2O 15 x
 Nozzle No. 27-4 Nozzle Dia .350 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inHg)	Orifice Water (inHg)	Dis. Vol. (cf)	VAC. inHg	Temperature (°F)					Oxygen (xv/v)	
							Stack	Probe	Duct	Inpg.	Gas/In		Gas/Duct
A-4	1617	378.70	.09	.36	9.59	2	83			39	93	92	AMBI
5	35	379.59	.128	.110	1.14	5	95			40	96	92	
4	75	381.14	.10	.39	2.08	2	96			40	97.5	93	
3	10	382.08	.06	.23	2.80	1	95			40	96	93	
3	12.5	382.80	.00	.00	2.80	0	94			39	94	92	
1	15	382.80	.00	.00	2.80	0	95			42	93	92	
B-6	175	385.40	.80	.314	5.40	13	95			41	98	93	
5	20	388.11	.85	.336	8.11	13	94			40	97	92	
4	22.5	390.22	.52	.205	0.22	13	96			40	96	92	
3	25	392.05	.52	.205	2.33	8	96			39	95	92	
2	27.5	394.29	.45	1.76	4.29	7	100			40	95	92	
1	30	396.12	.39	1.54	6.12	6	96			40	96	92	
C-6	32.5	398.51	.67	2.63	8.51	11	99			39	98	92	
5	35	401.24	.87	3.41	12.4	13	98			41	98	92	
4	37.5	404.01	.90	3.56	4.01		94			39	97	93	
3	40	406.54	.75	3.95	6.54	12	98			39	97	92	
2	42.5	408.90	.65	3.55	8.90	10	100			39	97	93	
1	45	411.41	.74	2.90	1.41	11	99			41	97	93	
D-6	47.5	412.88	.25	.98	2.88	5	99			41	97	93	
5	50	414.61	.35	1.37	4.61	5	100			40	99	94	
4	52.5	415.83	.25	.82	5.83	4	94			41	100	94	
3	55	416.97	.15	.59	6.97	2	98			40	99	94	
2	57.5	416.97	.00	.00	6.97	0	94			39	99	93	
1	60	416.97	.00	.00	6.97	0	94			39	99	93	
Σ = 382.27												AVG. = 90.6	
(1629)													

INTERPOLL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ILI / TWO HARBORS
 Source Press Vent + Stack
 Test 7 Run Date 6/30/93
 Stack dimen. 55 x 55 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.15 in Hg
 Static pressure -7.78 in WC
 Operators D. Van Hoever & J. Bergstrom
 Pitot No. V23-5 C_p .84

Cross-section View	Elevation View

Drawing
of Test Site

MDI NITRO

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	in.	Time start:	hrs
A 1					
2					
3					
4					
5					
6					
B 1					
2					
3					
4					
5					
6					
C 1					
2					
3					
4					
5					
6					
D 1					
2					
3					
4					
5					
6					

Temp. meas. device & S/N: PDT #18 Time end: hrs

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ILI / TWO HARBORS Date 6/30/93 Test 7 Run 1
 Source PRESS VENT STACK No. of traverse points 24
 Method MOE-N Filter holder: SS-ERC Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) MECL₂

No. of probe wash bottles: 1
 Sample recovered by: Dust

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1307</u>	<u>1296</u>	<u>11</u>
Total			<u>11</u>

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES METHOD 5 FIELD DATA SHEET

Job ICI Two Harbors Operator DUNN J.B. Pitot No. MD-6 Cp 84
 Source PROCESS WENT SPECK Meter Box No. 6 Bar. Press. 29.5 inHg H2O 1 X
 Date 6/22/83 Computer conf. 4996 Nozzle No. 6-4 Nozzle Dia 3/4 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifted Water (inH ₂ O)	Dis. Vol. (cf)	VAC. inHg	Temperatures (°F)					Oxygen (XV/V)	
							Stack	Probe	Duct	lagg.	Gas/In		Gas/Dut
C 6	0825	676.10	.83	3.42	8.77	6.5	83	NA	NA	84	84	Ambient	
5	2.5	678.76	.90	3.69	1.54	6	85			84	83	AIR	
4	5	681.53	.69	2.59	3.86	6	85			85	83		
3	7.5	683.60	.72	8.94	6.34	6	89			85	84		
2	10	686.30	.25	1.03	7.81	2.5	86			86	85		
1	12.5	687.71	0	0	7.81	—	86			86	85		
① 6	15	687.71	.75	3.08	0.35	5	86			86	84		
5	17.5	690.40	.29	1.19	1.94	2.5	86			86	84		
4	20	691.96	.30	1.20	3.56	2.5	82			86	84		
3	22.5	693.42	.45	1.83	5.52	3	92			87	84		
2	25	695.43	.08	.33	6.35	1	88			86	84		
1	27.5	696.58	0	0	6.35	—	88			86	84		
6	30	696.36	.18	.74	7.60	1	88			86	84		
5	32.5	697.85	.14	.57	8.70	1	88			86	84		
4	35	698.90	.18	.74	9.05	1	88			86	84		
3	37.5	699.90	.15	.61	1.08	1	91			86	84		
2	40	701.02	.00	0	1.08	—	82			86	84		
1	42.5	701.91	0	0	1.08	—	87			85	85		
6	45	702.21	.83	3.40	3.75	6	87			87	85		
5	47.5	703.80	.81	3.34	6.39		84			87	85		
4	50	706.40	.64	2.85	8.84		89			89	86		
3	52.5	708.86	.40	1.93	0.80		83			89	86		
2	55	710.94	.70	2.90	3.27	5	83			90	87		
1	57.5	713.29	.50	2.33	5.48	4	83			91	87		
	60	715.51											
	0942												
V = 39.41													
Q = 60													
H = 6.69													
Avg. = 85.5													

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / TWO HARBORS
 Source PRESS VENT STACK
 Method MDI-SS Filter holder: ERC-SS

Date 6/30/93 Test 7 Run 2
 No. of traverse points 24
 Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 13 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☒ other(s) MECL₂

No. of probe wash bottles: 1
 Sample recovered by: DUP

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1433	1421	12
Total			12

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOLL LABORATORIES METHOD 5 FIELD DATA SHEET

Job ICI / Two Harbors Operators DON & J.B. Pitot No. 023-5 CP 84
 Source Press Vent Stack Meter Box No. 6 Bar. Press. 29.15 inHg H₂O 1.5 x
 Date 6/30/97 1997 7 Run 3 Gasometer coeff. 0.996 Nozzle No. 6-4 Nozzle Dia. 0.57 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifts Water (inWC)	Des. Vol. (cf)	VAC. inHg	Temperatures (°F)				Oxygen (xv/v)
							Stack	Probe	Dry	Wet	
C	118	715.70									
	2.5	718.41	74	3.21	8.29	6	87	NA	NA		AmB, EA
	5	720.45	50	2.04	0.36	4	85				AIR
	4	722.70	65	2.65	2.72	5	88				
	3	724.91	34	1.39	4.43	4	88				
D	12.5	726.91	46	1.80	6.38	5	85				
	1	726.91	01	0.41	6.67	-	85				
	17.5	729.01	79	3.22	9.27	1	85				
	5	730.73	25	1.01	0.73	35	88				
	4	732.28	84	1.40	2.46	4	86				
A	3	734.50	51	2.08	4.55	5	86				
	2	735.41	08	0.32	5.38	2	87				
	1	735.40	0	0	5.38	-	87				
	33.5	737.60	48	1.96	2.41	4	87				
	35	738.58	16	0.65	8.58	2	87				
B	4	740.03	24	0.98	0.02	2	86				
	3	740.96	10	0.41	0.95	-	88				
	2	741.08	0	0	0.95	-	87				
	1	741.09	0	0	0.95	-	87				
	47.5	743.81	87	3.50	3.75	6	92				
	5	746.54	93	3.76	6.45	6	90				
	4	748.1	70	2.85	8.90		89				
	3	751.23	70	2.85	1.35		89				
	2	753.30	47	1.92	3.36		88				
	1	755.20	45	1.84	5.34		88				
1238											
θ = 60		V = 34.50	ΔH = 1.00								
										Avg. = 90.2	

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / TWO HARBORS
 Source PRESS VENT STACK
 Method MDI-NITR filter holder: ERL-SS

Date 6/30/93 Test 7 Run 3
 No. of traverse points 24
 Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ~~X~~
 Posttest: 0 cfm at 14 in. Hg. (vac) ~~X~~

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) MECL₂

No. of probe wash bottles: 1
 Sample recovered by: DUH

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1320</u>	<u>1307</u>	<u>13</u>
Total			<u>13</u>

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES METHOD 5 FIELD DATA SHEET


Job TL1 / Two Harbors
 Source Pass that Street
 Date 6/20/84

Operator 4-J.B.
 Meter Box No. 6
 Computer Code 9996

Pilot No. 023-6 CP 84
 Bar. Press. 29.15 inHg H2O 1.5 X
 Nozzle No. 244

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inHg)	Orifice Meter (inHg)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)				Gas In	Gas Out	Oxygen (xv/v)
							Stack	Probe	Dyn	Leq.			
C	410	755.10											
	3.5	757.91	81	3.34	7.75	6	84	NA	NA	NA	86	86	Ambient
	5	760.65	91	3.69	0.52	6	89				89	87	Air
	7.5	763.30	101	3.98	3.15	6	92				89	87	
	10	765.43	6	2.45	5.42	5	89				90	88	
B	12.5	767.60	55	2.25	7.60	5	87				90	87	
	15	768.09	102	0.8	8.02	-	87				89	87	
	17.5	770.59	75	3.07	0.56	6	87				89	87	
	20	772.40	130	1.47	2.32	2.5	89				89	88	
	22.5	773.83	125	1.02	3.79	2.5	89				89	88	
A	25	775.89	50	2.04	5.87	5	88				89	88	
	27.5	776.68	15	2.0	6.53	1	83				89	88	
	30	776.60	0	0	6.53	-	89				90	88	
	32.5	778.30	28	1.14	8.08	3	89				90	88	
	35	779.60	26	1.06	9.58	3	89				90	88	
B	37.5	780.60	110	1.41	0.52	0	83				90	88	
	40	782.00	51	2.08	2.62	6	90				90	88	
	42.5	782.00	0	0	2.62	-	90				90	88	
	45	782.00	0	0	2.62	-	90				90	88	
	47.5	784.17	70	3.09	5.17	6	90				91	89	
B	50	786.40	83	3.34	7.83	6	94				91	89	
	52.5	788.82	53	2.19	9.98	5	84				97	90	
	55	791.06	50	2.07	2.08		84				97	90	
	57.5	793.75	140	1.63	3.94		90				92	90	
	60	793.85	09	1.37	4.83	1	90				93	90	
(1513)													
Total		38.70		1.68							Avg. = 89		

Job IC1
Source PRESS VENT STACK
Test 8-Run @ Date 6-30-93
Stack dimen. 55X55 IN.
Dry bulb °F Wet bulb °F
Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 29.15 in Hg
Static pressure - .78 in WC
Operators CHOYE & SE
Pitot No. 23 V-6 Cp .84

[illegible]

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

FL

Job ICI
 Source PRESS VENT
 Method MDI Filter holder: GLASS
FL

Date 6-30-93 Test 8 Run 1
 No. of traverse points 24
 Filter type: CF

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: { .02 cfm at 10 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) 1,2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: CH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>100</u>	<u>129</u>	<u>-29</u>
Impinger No. 2	<u>81</u>	<u>86</u>	<u>-5</u>
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>-34</u>

8

Integrated Gas Sampling Data: AMBIENT

Bag Pump No. NA Box No. NA Bag No. NA

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

PRESS VENT INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job 181 - TWO HARBORS
 Source PRESS VENT
 Date 6-30-93

Operator
 Meter Box No.
 Gasometer conf.

C. HOUK
 3
 9976

Pilot No. 2346 DP 84
 Bur. Press. 29.15 IN Hg
 Nozzle No. 27-3 Nozzle Dia. .82 IN.

Traverse Point No.	Sampling Time (min)	Supply Volume (cf)	Velocity Head (IN Hg)	Drifted Meter (IN Hg)	Det. Vol. (cf)	VAC. IN Hg	Temperature (°F)				Gas In	Gas Out	Oxygen (xv/v)
							Stack	Probe	Duct	Insp.			
A	6	417.51	.18	.20	830	1	83			39	96	95	AMBIENT
	5	418.30	.22	.25	918	2	85			40	97	96	
	4	419.84	.12	.13	984	1	85			41	97	97	
	3	420.27	.05	.05	0.27	1	85			39	97	97	
	2	420.27	.00	.00	0.27	0	86			42	98	97	
	1	420.27	.00	.00	0.27	0	86			42	98	97	
B	6	421.91	.75	.85	191	7	87			40	101	97	
	5	422.56	.75	.86	356	7	83			41	102	98	
	4	424.98	.55	.63	498	5	82			43	102	99	
	3	426.40	.55	.62	640	5	88			39	102	98	
	2	427.61	.40	.45	761	3	86			39	103	98	
	1	428.04	.05	.05	8.04	0	81			40	103	98	
C	6	429.52	.60	.69	952	5	83			42	103	98	
	5	431.28	.85	.97	128	5	83			44	104	98	
	4	433.05	.86	.98	305	7	87			39	108	101	
	3	434.49	.56	.64	449	6	87			40	105	99	
	2	436.02	.64	.73	602	5	84			41	105	100	
	1	436.60	.09	.10	6.60	1	83			42	106	99	
D	6	438.08	.60	.68	808	5	83			44	104	99	
	5	439.74	.75	.75	974	5	83			46	105	99	
	4	441.10	.50	.57	110	5	83			43	106	100	
	3	442.65	.65	.75	265	5	83			44	105	100	
	2	443.78	.35	.40	378	4	88			39	105	102	
	1	443.78	.00	.00	378	0	85			40	102	99	
	(09.57)												
	0 = 72												
		V. = 26.27		ΔH = 48								Avg. = 100.1	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job IC1 Date 6-30-93 Test 8 Run 2
 Source PRESS VENT No. of traverse points 24
 Method MD 1 Filter holder: GLASS Filter type: GF

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 102 cfm at 12 in. Hg. (vac) ☐
LESS THAN

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☐ other(s) 1, 2 MP IN TOLUENE
NO OF FILTER WASH BOTTLES
 No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>104</u>	<u>129</u>	<u>-25</u>
Impinger No. 2	<u>81</u>	<u>84</u>	<u>-3</u>
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>-28</u>

8

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job IC1 - PRESS VENT Date 6-30-93 Operator 0 HOUSE - S. EARLE Pilot No. 33 V-6 CP 84
 Source TWO HARBORS Water Box No. 3 Bar. Press. 29.15 inHg H₂O 15 x
 Date 6-30-93 1991 8 Run 2 Computer Edit. 977 IN NC Nozzle No. 27-3 Nozzle Dia. 1/2 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Orifice Meter (inH ₂ O)	Dis. Vol. (cf)	VAC. inHg	Temperature (°F)				Gas/in	Gas/Det	Oxygen (xx/vv)
							Stack	Probe	Dyn	Imp			
B (1118)													
6	3	444.135									100	100	AMBIENT
		445.78	.75	.85	5.78	7	87				100	100	
5	6	447.32	.65	.75	7.32	8	85				101	100	
4	9	448.66	.49	.56	8.66	4	85				103	100	
3	13	450.20	.65	.74	0.20	6	87				104	100	
2	15	451.28	.32	.36	1.28	7	91				104	101	
1	18	451.85	.09	.10	1.85	5	87				104	100	
C													
6	21	453.54	.78	.89	3.54	7	88				103	100	
5	24	455.31	.86	.98	5.31	10	88				106	101	
4	27	457.02	.80	.91	7.02	10	87				106	101	
3	30	458.62	.70	.80	8.62	9	87				106	102	
2	33	460.21	.68	.78	0.21	8	86				105	101	
1	36	460.95	.15	.17	0.95	1	91				105	101	
D													
6	39	462.32	.51	.58	2.32	5	87				105	101	
5	42	463.80	.60	.68	3.80	6	88				107	102	
4	45	464.84	.29	.33	4.84	6	87				107	102	
3	48	466.26	.55	.63	6.26	6	88				107	102	
2	51	467.68	.65	.68	7.68	6	87				107	102	
1	54	469.17	.60	.68	9.17	6	89				107	102	
A													
6	57	469.71	.08	.09	9.71	1	87				105	101	
5	60	470.32	.10	.11	0.32	1	88				105	102	
4	63	470.93	.10	.11	0.93	0	88				102	101	
3	66	471.12	.07	.01	1.12	0	88				102	101	
2	69	471	.00	.00	1.12		87				102	102	
1	72	471.12	.00	.00	1.12		87				102	102	
(1248)													
Avg. = 92.3												Oxygen	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI TWO HARBORS Date 6-30-93 Test 8 Run 3
 Source PRESS VENT No. of traverse points 24
 Method MDI Filter holder: CLASS Filter type: GF

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 02 cfm at 15 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) 1,2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	98	126	-28
Impinger No. 2	81	85	-4
Impinger No. 3			
Condenser			
Desiccant			
Total			-32

Integrated Gas Sampling Data: - AMBIENT

Bag Pump No. NA Box No. NA Bag No. NA

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job IC1 - TWO HARBORS Operator G. MOORE Pitot No. 23 V6 CP 84
 Sample CRESS VENT Meter Box No. 3 HP 174 IN NC Bar. Press. 29.15 IN HG H2O 15.8
 Date 6-30-93 Calculator 3 Nozzle No. 27-3 Nozzle Dia. 1.82 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Orifice Meter (in H ₂ O)	Des. Vol. (cf)	VAC. in Hg	Temperature (°F)				Gas In	Gas Out	Oxygen (xv/v)
							Stack	Probe	Duct	Inpy.			
B - 6 (1410)													
6	3	471.490	.1	.11	2.08	1	84				101	101	AMBIENT
5	6	472.08	.15	.17	2.82	1	89				104	102	
4	9	473.29	.06	.06	3.29	1	92				104	102	
3	12	473.29	.00	.00	3.29	0	91				103	102	
2	15	473.29	.00	.00	3.29	0	91				102	102	
1	18	473.29	.00	.00	3.29	0	90				102	102	
C 6	21	474.84	.66	.75	4.84	7	91				107	103	
5	24	476.39	.65	.74	6.39	7	88				108	104	
4	27	477.81	.55	.78	7.81	7	90				109	104	
3	30	479.29	.60	.68	9.29	8	93				109	104	
2	33	480.49	.39	.44	0.49	7	93				109	104	
1	36	481.34	.15	.17	1.34	1	89				110	102	
D 6	39	482.73	.60	.69	2.73	6	89				109	105	
5	42	484.48	.80	.92	4.48	8	90				110	104	
4	45	486.29	.88	1.01	6.26	10	89				110	104	
3	48	487.71	.64	.73	7.71	6	94				110	104	
2	51	489.15	.50	.57	9.15	5	89				110	105	
1	54	490.04	.20	.23	0.02	3	88				110	105	
A 6	57	491.51	.60	.69	1.51	5	89				110	105	
5	60	493.80	.48	.55	2.85	5	88				110	105	
4	63	493.62	.30	.34	3.90	4	91				110	105	
3	66	494.83	.25	.28	4.87	3	90				110	105	
2	69	496.22	.50	.57	6.22	5	93				110	105	
1	72	496.97	.15	.17	6.97	1	93				110	105	
(1528)													
V = 25.48													
H = .44													
0 = 72													
Avg. = 105													

INTERPOL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ICI / TWO HARBORS
 Source PRESS VENT STACK
 Test 9 Run Date 6/30/93
 Stack dimen. 55 x 55 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.15 in Hg
 Static pressure - .78 in WC
 Operators D. Van Hoever & J. Bergstrom
 Pitot No. V23-5 Cp .84

Cross-section View	Elevation View
Drawing of Test Site	

MDI - FILTER FIRST

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	in.	Time start:	hrs
A 1					
2					
3					
4					
5					
6					
B 1					
2					
3					
4					
5					
6					
C 1					
2					
3					
4					
5					
6					
D 1					
2					
3					
4					
5					
6					
Temp. meas. device & S/N: <u>PDT #18</u>				Time end:	hrs

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / TWO HARBORS Date 6/30/93 Test 9 Run 1
 Source PRESS VENT STACK No. of traverse points 24
 Method MDI Filter holder: Filter First Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) MECL₂ + DI H₂O

No. of probe wash bottles: 1
 Sample recovered by: DVA

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>101</u>	<u>129</u>	<u>-28</u>
Impinger No. 2			
Impinger No. 3	<u>81</u>	<u>86</u>	<u>-5</u>
Condenser			
Desiccant			
Total			<u>-33</u>

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES A METHOD 5 FIELD DATA SHEET

Job ICI Two Harbors
 Sample press vent stack
 Date 6/30/93 1993 Run 1

Operator DWH + J.B. + J.E.
 Water Box No. 7
 Gas analyzer serial 99833

Pilot No. V23-5
 Bar. Press. 29.75 inHg
 Nozzle No. 7-3 Nozzle Dia. 1.5 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifted Water (inH ₂ O)	Obs. Vol. (cf)	VAC. inHg	Temperature (°F)				Oxygen (Xv/v)
							Stack	Probe	Dry	Wet	
B	0825	793.63									
	3	794.50	.63	.85	5.14	5	83			81	81
	6	796.73	.73	.98	6.77	5	85			83	82
	9	798.20	.45	.60	8.06	4	85			86	83
	12	799.72	.60	.81	9.54	2	88			87	83
	15	800.53	.26	.35	0.53	1	86			89	84
C	18	801.16	.11	.15	1.17	—	84			89	83
	21	802.96	.78	1.06	2.87	5	84			91	83
	24	804.89	.90	1.23	4.71	5	83			93	86
	27	806.50	.90	1.22	6.84	5	82			93	86
	30	808.05	.65	.90	8.10	5	88			95	87
	33	809.61	.62	.84	9.63	5	88			95	87
D	36	810.40	.08	.10	0.17	—	91			95	88
	39	811.93	.68	.92	1.77	5	91			97	88
	42	813.40	.68	.93	3.38	5	83			95	88
	45	814.65	.34	.46	4.51	2	87			96	89
	48	816.03	.50	.68	5.89	2	87			95	88
	51	816.79	.13	.17	6.60	1	84			94	88
A	54	816.79	0	0	0.60	1	84			91	88
	57	817.23	.10	.13	7.21	1	84			92	88
	60	818.19	.18	.24	8.04	1	83			92	88
	63	818.90	.20	.27	8.91	1	83			92	88
	66	819.62	.08	.11	9.46	1	83			92	88
	69	819.62	0	0	9.46	—	88			90	88
1	72	819.62	0	0	9.46	—	88			89	88
0957											
0 = 72		V = 25.90	ΔH = .34							Avg. = 88.6	

INTERFOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / TWO HARBORS
 Source PRESS VENT STACK
 Method MDI Filter holder: glass

Date 6/30/93 Test 9 Run 2
 No. of traverse points 24
 Filter type: glass fiber

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: { 0 cfm at 14 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) 1-2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: DWH

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>103</u>	<u>126</u>	<u>-23</u>
Impinger No. 2	<u>81</u>	<u>84</u>	<u>-3</u>
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>-26</u>

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / TWO HARBORS
 Source PRESS VENT STACK
 Method MDI-FF Filter holder: glass

Date 6/30/93 Test 9 Run 3
 No. of traverse points 24
 Filter type: glass fiber

Sample Train Leak Check:

Pretest: 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 15 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) 1-2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: DUP

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>101</u>	<u>128</u>	<u>- 27</u>
Impinger No. 2	<u>82</u>	<u>84</u>	<u>- 2</u>
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>- 29</u>

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES 2A METHOD 5 FIELD DATA SHEET

Job ICI / Togo Harbors
 Source Press Vent Stack
 Date 10/30/95

Operator DOW & J.B.
 Meter Box No. 7
 Gas meter coeff. 1.00

Pilot No. 023-5
 Bur. Press. 29.15
 Nozzle No. 7-3 Mobile Dia 1.5 IN.

Pilot No. 023-5
 Bur. Press. 29.15
 Nozzle No. 7-3 Mobile Dia 1.5 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifted Meter (inH ₂ O)	Des. Vol. (cf)	VAC. inH ₂ O	Temperature (°F)				Stack	Probe	Duct	Leaky	Gas In	Gas Out	Oxygen (xv/v)
A 6	1410	849.435	.51	.69	0.82	10								89	89	Ambient	
5	3	850.87	.63	.85	2.35	11								95	91	Air	
4	6	852.32	.49	.66	3.70	10								96	91		
3	9	853.73	.66	.84	5.27	11								97	92		
2	12	855.30	.51	.69	6.66	10								97	92		
1	15	856.83	.37	.50	7.84	9								97	92		
B 6	18	857.96	.73	.94	9.19	11								99	93		
5	21	859.50	.86	1.17	1.30	12								99	93		
4	24	861.32	.69	.94	2.91	12								98	93		
3	27	862.99	.58	.78	4.39	12								98	93		
2	30	864.55	.60	.81	5.90	12								98	93		
1	33	865.93	.13	.17	6.60	2								98	93		
C 6	36	866.69	.55	.71	8.04	8								97	93		
5	39	868.60	.59	.80	9.53	8								98	93		
4	42	869.93	.37	.50	0.72	5								99	93		
3	45	870.93	.51	.69	2.10	5								99	94		
2	48	872.09	.38	.51	3.30	5								100	94		
1	51	873.90	.36	.35	4.19	2								100	94		
D 6	54	874.38	.11	.15	4.94	1								98	94		
5	57	874.99	.06	.08	5.42	1								99	94		
4	60	875.69	.06	.08	5.90	-								97	94		
3	63	876.07	0	0	5.90	-								96	94		
2	66	876.07	0	0	5.90	-								95	94		
1	69	876.07	0	0	5.90	-								95	94		
Σ = 72															Avg. = 95.0		Ambient

INTERPOLL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job 1C1 TWO HARBORS MN

Source UNLOADING VENT

Test 2 Run 0 Date 6-29-93

Stack dimen. 55 x 55 IN.

Dry bulb °F Wet bulb °F

Manometer: ☒ Reg. ☐ Exp. ☐ Elec.


Barometric pressure 29.19 in Hg

Static pressure - .62 in WC

Operators CH - SE

Pitot No. 234-6 C_p .84

PH Thermal



Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: <u>4</u> in.	Time start: <u>0745</u> hrs		
A	1	<u>4.58</u>	<u>9.57</u>	<u>.08</u>	
	2	<u>13.25</u>	<u>17.25</u>	<u>.17</u>	
	3	<u>22.92</u>	<u>26.92</u>	<u>.15</u>	
	4	<u>32.08</u>	<u>36.08</u>	<u>.16</u>	
	5	<u>41.25</u>	<u>44.25</u>	<u>.00</u>	
	6	<u>50.41</u>	<u>54.41</u>	<u>.05</u>	
B	1			<u>.15</u>	
	2			<u>.70</u>	
	3			<u>.60</u>	
	4			<u>.66</u>	
	5			<u>.65</u>	
	6			<u>.61</u>	
C	1			<u>.10</u>	
	2			<u>.68</u>	
	3			<u>.65</u>	
	4			<u>.64</u>	
	5			<u>.61</u>	
	6			<u>.55</u>	
D	1			<u>.10</u>	
	2			<u>.31</u>	
	3			<u>.63</u>	
	4			<u>.40</u>	
	5			<u>.41</u>	
	6			<u>.57</u>	
Temp. meas. device & S/N: <u>NO 24</u>				Time end: <u>0755</u> hrs	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job UN Date 6-29 Test 2 Run 1
 Source UNLOADER VENT STACK No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: GLASS FIBER
PLUS PHENOLS

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: (0.02 cfm at 15 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

5373 ☒ acetone
☐ other(s) _____
 NO OF FILTER WASH BOTTLES 1
 No. of probe wash bottles: 1
 Sample recovered by: PH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1A	277.0	274.4	2.6
Impinger No. 2B	266.7	266.7	0
Impinger No. 3B			
Condenser			
Desiccant	1442	1432	10
Total			12.6

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

Job 101 TWO HARBORS
 Source UNLOADER USNT
 Date 1-29-63 1961 3 HUN 1
 Operators 6 MOVE 2 S FERTLE
 Water Box No. 3 111 177 IN MC
 Compressor Code 9970
 Pitot No. 23-V 6 Cp .87
 Bar. Press. 29.19 IN Hg 2
 Nozzle No. 27-4 Nozzle Dia. 2.50 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Drift Factor (in H ₂ O)	Obs. Vol. (cf)	VAC. (in Hg)	Temperature (°F)				Gas In	Gas Out	Oxygen (xv/v)
							Stack	Probe	Dry	Wet			
A	0822	171.875											
6	2.5	173.94	.56	3.14	394	6				93	93		
5	5	176.10	.54	3.14	610	6				96			
4	7.5	177.36	.18	.72	736	4				97	93		
3	10	178.93	.28	1.12	892	5				97	93		
2	12.5	180.86	.43	1.72	0.86	5				98	92		
1	15	180.86	.00	.00	.86	0				97	92		
B	17.5	183.13	.60	2.38	3.13	6				98	92		
5	20	185.51	.65	2.59	5.51	8				99	92		
4	22.5	187.88	.65	2.59	7.88	8				100	92		
3	25	190.15	.59	2.39	0.15	7				100	93		
2	27.5	192.53	.65	2.59	2.53	8				100	94		
1	30	193.92	.22	.88	392	5				99	94		
C	32.5	196.13	.56	2.24	6.13	5				100	93		
5	35	198.52	.65	2.61	8.52	8				101	93		
4	37.5	200.19	.59	2.36	.19	7				101	98		
3	40	203.12	.62	2.49	3.12	8				102	94		
2	42.5	205.51	.65	2.61	5.51	9				103	94		
1	45	206.67	.15	.60	6.67	9				102	94		
D	47.5	208.70	.47	1.88	8.70	5				102	95		
5	50	210.22	.26	1.05	0.22	4				102	95		
4	52.5	212.17	.43	1.73	2.17	4				102	95		
3	55	214.54	.64	2.57	4.54	8				102	96		
2	57.5	216.31	.35	1.42	6.31	5				104	99		
1	60	217.04	.06	.24	7.04	2				104	97		
	0922												
		45.195		1.79							97.0		

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job 101 TWO HARBORS Date Test 2 Run 3
 Source UNLOADER VENT No. of traverse points 24
 Method 5 Filter holder: GLASS Filter type: 4" GLASS FIBER
PLUS PHENOLS

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0.2 cfm at 15 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

5459 ☒ acetone
☐ other(s)
 NO OF FILTER WASH BOTTLES 1
 No. of probe wash bottles: 1
 Sample recovered by: GA

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	271.0	267.8	3.2
Impinger No. 2			
Impinger No. 3	264.6	264.6	0
Condenser			
Desiccant	1395	1385	10
Total			13.2

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: cc/min at in. Hg.
 Time start: (HRS) Time end: (HRS)
 Sampling rate: cc/min Operator:
 S/N of O₂ Analyzer used to monitor train outlet:

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job 101 TWO HARBORS Operator CHOUK Pilot No. 2346 CP. 84
 Survey UNLOADING Water Box No. 3 Bar. Press. 29.19 IN HG. H₂O 1.5
 Date 6-29-83 Gun 2 Gun No. 9970 Nozzle No. 274 Nozzle Dia. 250 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (IN HG)	Orifice Water (IN HG)	Dis. Vol. (cf)	VAC. (IN HG)	Temperature (°F)				Dye	Dye (XV/V)
							Black	Probe	Oven	Inp.	Cas/in	Cas/Dut
0-6	0957	217.330										
5	2.5	218.48	.15	.60	8.48	3	88				94	94
4	5	220.78	.61	2.44	0.78	7	88				97	94
3	7.5	232.11	.20	9.11	2.11	3	84				98	94
3	10	223.26	.15	.60	3.26	3	87				98	94
3	13.5	224.41	.15	.60	4.41	3	85				100	95
1	15	225.71	.19	.76	5.71	3	88				101	95
C-6	17.5	227.83	.51	2.05	7.83	9	88				102	94
5	20	230.25	.66	2.66	0.25	9	88				103	94
4	22.5	232.68	.67	2.71	2.68	9	87				102	94
3	25	234.97	.59	2.38	4.97	9	88				102	94
2	27.5	237.18	.55	2.23	2.18	8	86				102	94
1	30	239.45	.58	2.34	9.45	8	87				102	94
B-6	32.5	241.77	.61	2.46	1.77	9	87				102	94
5	35	244.12	.62	2.51	4.12	9	86				102	94
4	37.5	246.49	.64	2.58	6.49	6	88				102	94
3	40	248.82	.61	2.46	8.82	8	88				102	94
2	42.5	251.22	.65	2.62	12.22	8	87				102	94
1	45	253.40	.54	2.18	3.40	8	87				102	95
A-6	47.5	254.50	.15	.60	4.50	3	87				101	95
5	50	255.41	.08	.32	5.41	2	88				100	95
4	52.5	256.00	.04	.16	6.00	1	90				98	94
3	55	257.48	.25	.99	7.48	5	93				100	95
2	57.5	259.24	.35	1.41	9.24	5	87				101	95
1	60	260.54	.19	.76	0.54	3	88				101	95
(1059)												
		V = 43.21	W = 1.64								Av. = 97.9	100.000

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI TWO HARBORS Date 6-29-93 Test 2 Run 3
 Source UNLOADER VENT No. of traverse points 24
 Method S Filter holder: GLASS Filter type: GLASS FIBER
4"

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: .02 cfm at _____ in. Hg. (vac) ☐
LESS THAN

Particulate Catch Data:

No.s of filters used: 5374 Recovery solvent(s) _____
☒ acetone _____
☐ other(s) _____
NO OF FILTER WASH BOTTLES - 1
 No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1 <u>A</u>	<u>270</u>	<u>267.6</u>	<u>2.4</u>
Impinger No. 2			
Impinger No. 3 <u>B</u>	<u>263.1</u>	<u>263.1</u>	<u>0</u>
Condenser			
Desiccant	<u>1451</u>	<u>1442</u>	<u>9</u>
Total			<u>11.4</u>

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA
 Bag Material: 5-layer Aluminized Tedlar Size: 44 L
 Pretest leak check: _____ cc/min at _____ in. Hg.
 Time start: _____ (HRS) Time end: _____ (HRS)
 Sampling rate: _____ cc/min Operator: _____
 S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job IC-1 TWO HARBORS Operator CH Pilot No. 2316 Ep 84
 Source UNRAIDER 14 NT Meter Box No. 3 Bar. Press. 29.19 inHg H₂O 1.5 x
 Date 6-29-93 Recorder 2 Run 3 Nozzle No. 27-4 Nozzle Dia. 250 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Orifice Meter (inH ₂ O)	Obs. Vol. (cf)	VAC. inHg	Temperature (°F)					Oxygen (xv/v)
							Stack	Probe	Duct	Inlet	Outlet	
A-6	1134	260.80	.08	.32	1.63	2	95			94	94	MA571
5	2.5	261.63	.15	.60	2.78	2	88			98	95	
4	7.5	262.78	.15	.60	3.93	2	93			100	95	
3	10	263.93	.15	.60	5.08	2	93			101	96	
3	12.5	265.08	.05	.20	5.08	2	94			101	96	
1	15	265.74	.10	.20	5.74	2	91			101	96	
B-6	17.5	268.04	.60	2.40	8.04	9	91			102	95	
5	20	270.45	.66	2.65	0.45	9	90			103	100	
4	22.5	272.87	.66	2.68	2.87	9	87			102	95	
3	25	275.17	.60	2.40	5.17	9	91			102	95	
2	27.5	277.63	.69	2.78	7.63	10	88			102	95	
1	30	278.78	.15	.60	8.78	2	89			103	95	
C-6	32.5	280.98	.15	2.20	0.98	7	93			103	95	
5	35	283.29	.60	2.42	3.29	7	87			104	97	
4	37.5	285.69	.65	2.63	5.69	8	88			104	96	
3	40	288.09	.65	2.62	8.09	10	89			104	97	
2	42.5	290.53	.67	2.72	0.53	10	86			103	97	
1	45	291.48	.10	.40	1.48	1	90			101	96	
D-6	47.5	293.72	.57	2.29	3.72	6	90			103	98	
5	50	295.66	.42	1.71	5.66	5	86			103	97	
4	52.5	297.52	.39	1.58	7.52	5	88			103	97	
3	55	299.90	.64	2.58	9.90	7	89			103	97	
2	57.5	301.54	.30	1.22	1.54	5	87			102	96	
1	60	302.48	.10	.40	2.48	2	90			102	96	
(1237)												
Σ		41.68		4.61						99	989	

INTERPOL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ILI / TWO HARBORS
 Source Unloading Vent Stack
 Test 5 Run Date 6/29/93
 Stack dimen. 55 x 55 IN.

Dry bulb °F Wet bulb °F

Manometer: ☐ Reg. ☐ Exp. ☐ Elec.



Barometric pressure 29.19 in Hg

Static pressure -.78 in WC

Operators D. VAN HORNER & J. Bergstrom

Pitot No. V23-5 Cp .84

CH₂O

Cross-section View 	Elevation View 
--	---

Drawing of Test Site ← N

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	in.	Time start:	hrs
A 1					
2					
3					
4					
5					
6					
B 1					
2					
3					
4					
5					
6					
C 1					
2					
3					
4					
5					
6					
D 1					
2					
3					
4					
5					
6					
Temp. meas. device & S/N: <u>PDT # 18</u>				Time end:	hrs

R or nothing = (reg.) manometer; S = expanded; E = electronic

S-3921

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ILI / TWO HARBORS
 Source UNLOADING VENT
 Method 0011 Filter holder: NA

Date 6/29/93 Test 5 Run 1
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: { 0 cfm at 65 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☒ other(s) MCCl₂ + DI H₂O

No. of probe wash bottles: 1
 Sample recovered by: DEH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>199</u>	<u>200</u>	<u>1</u>
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1420</u>	<u>1409</u>	<u>11</u>
Total			<u>10</u>

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERCOLL LABORATORIES A METHOD 5 FIELD DATA SHEET

Job ICI / Two Harbors Date 6/29/95 Operator DAK & J.B. Pitot No. 123-5 DP 87
 Source UNLOADING VENT STACK Motor Box No. 1 IN NC 197 Bar. Press. 29.19 IN HG 720
 Date 6/29/95 Computer Code 1061 Nozzle No. 6-24 Nozzle Dia 25 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (L)	Velocity Head (INCH)	Drifted Meter (INCH)	Obs. Vol. (L)	VAC. IN HG	Temperature (°F)				Oxygen (XV/V)
							Stack	Probe	Duct	Inlet	
A	13.1	662.90	0.32	1.49	4.59	4	90			92	93
	2.5	664.60	16	74	5.79	3	90			98	92
	5	665.80	40	185	7.68	5	91			100	94
	7.5	667.60	54	250	9.87	4	91			101	94
	10	669.70	06	28	0.61	4	89			101	94
B	12.5	670.55	0	0	0.61	—	89			98	93
	15	670.55	60	2.78	2.92	5	89			101	94
	17.5	672.91	63	292	5.29	5	90			102	94
	20	675.20	70	325	7.79	5.5	90			103	95
	22.5	677.77	68	316	0.16	5.5	90			104	95
C	25	680.35	72	336	2.81	5.5	88			105	96
	27.5	682.86	117	79	4.05	2	91			104	96
	30	684.20	56	261	6.30	5	91			103	96
	32.5	686.53	68	318	8.78	6	87			104	96
	35	688.90	152	244	0.95	6	88			105	96
D	37.5	690.96	68	317	3.43	6	90			105	97
	40	693.60	161	284	5.77	6	91			106	98
	42.5	695.90	10	47	6.73	2	90			106	98
	45	696.83	51	239	8.89	5	90			104	98
	47.5	698.90	30	140	0.54	3	90			106	98
E	50	700.46	42	198	2.51	4	87			105	98
	52.5	702.36	55	258	4.74	4.5	89			106	100
	55	704.64	30	141	6.40	4	88			106	98
	57.5	706.35	02	09	6.83	—	89			106	98
	60	706.82									
Total		43.92		1.99						Av. = 99.5	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI Two Harbors
 Source Unloading Vent Stack
 Method 0011 Filter holder: NA

Date 6/29/93 Test 5 Run 2
 No. of traverse points 24
 Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 2 cfm at 8 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☒ other(s) MeCCl₂ & D₂O

No. of probe wash bottles: 1
 Sample recovered by: Dust

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	204	<u>200</u>	4
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1319	1310	9
Total			13

Integrated Gas Sampling Data:

Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOLL LABORATORIES 'A' METHOD 5 FIELD DATA SHEET

Job ICE Twp Harbors Date 6/29/83 Operator Don & J.B. Pitot No. U23-5 DP 1051
 Source Wabamung Tent Stack Meter Box No. 7 SHF 97 IN HC Bar. Press. 29.17 IN HG H₂O 1 X
 Date 6/29/83 Meter conf. 8483 Nozzle Dia. 257 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in HC)	Orificed Meter (in HC)	Dis. Vol. (cf)	VAC. (in Hg)	Temperature (°F)					Dwygno (xv/v)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
							Stack	Probe	Dyn	Insp.	Chaslin		Col/Dul																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
A	1446	707.20																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI Tyo Harbors Date 6/29/93 Test 5 Run 3
 Source Unloading Vent Stack No. of traverse points 2
 Method AO11 Filter holder: NA Filter type: NA

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 6 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☒ other(s) MeCl₂ x DI H₂O

No. of probe wash bottles: 1
 Sample recovered by: Dust

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	369	5200	6
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1428	1420	8
Total			14

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

Job _____
Source 2 UNLACHING VENT STAIRS
Date 10/13/1961 5 H

OPERATORS
MAILER BOX NO. 7 JUL 1971 IN NC
COMPTON CORP. 985

Pilot No. 623-5 CP 104
Bar. Press. 29.9 H₂O 1.5
Nozzle No. 6-2 Nozzle Dia. 25/16 IN.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifted Meter (inWC)	VAC. inHg	Temperatures (°F)						Dwyer (xv/v)
						Stack	Probe	Dryn	Ingg.	Gas In	Gas Out	
A 6	167	752.51	.25	1.19	4.03					91	91	AMBIEN
A 8	2.5	754.10	.18	.82	5.28					95	92	AIR
A 4	7.5	755.40	.29	1.33	6.88					96	92	
A 3	10	756.99	.51	2.32	8.99					97	93	
A 2	12.5	758.90	.07	.32	9.78					98	93	
A 1	15	759.96	0	0	9.79					99	93	
B 6	17.5	759.96	.48	2.21	1.85					96	92	
B 5	20	761.96	.56	2.58	4.07					100	93	
B 4	22.5	764.06	.70	3.23	6.56					100	94	
B 3	25	766.57	.47	2.15	8.59					102	94	
B 2	27.5	768.66	.13	1.39	6.24					102	94	
B 1	30	770.36	.16	.74	1.44					102	94	
C 6	32.5	771.46	.5	2.32	3.55					102	94	
C 5	35	773.60	.27	1.25	5.11					103	94	
C 4	37.5	775.31	.37	1.72	6.93					102	94	
C 3	40	776.96	.63	2.90	9.29					103	95	
C 2	42.5	779.40	.13	.60	0.37					102	94	
C 1	45	780.48	0	0	0.37					102	94	
D 6	47.5	780.48	.56	2.59	2.61					102	95	
D 5	50	782.61	.72	3.33	5.14					102	95	
D 4	52.5	785.16	.58	2.70	7.42					102	95	
D 3	55	787.35	.67	3.11	9.87					104	96	
D 2	57.5	789.83	.65	3.04	2.29					104	96	
D 1	60	792.34	.09	.42	3.20					104	96	
	(1720)	793.21										
	0 = 100	794.21										
		795.21										
		796.21										
		797.21										
		798.21										
		799.21										
		800.21										
		801.21										
		802.21										
		803.21										
		804.21										
		805.21										
		806.21										
		807.21										
		808.21										
		809.21										
		810.21										

1515

RUN 2 2.5 PPM C_3H_8
7.5 PPM C

1445

Start Take at 1445
Unloading Vent Stack
6/29/93

zero gas

3.1 ppm gas

1421

RUN 1 3.1 PPM C_3H_8
9.3 PPM C

radio interference

ICL / Two Harbors
Start Test to Run 1 at 1321
Unloading Vent Stack
6/29/93

Scale 0-100

speed 10 cm/hr C-92

1321

CHART NO. LIC 0100-0011




CHART NO. LIC-0103-0011

INTERPOLL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ICI / TWO HARBORS
 Source UNLOADING VENT STACK
 Test 10 Run Date 7/1/93
 Stack dimen. 55 x 55 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.10 in Hg
 Static pressure in WC
 Operators D. VAN HOOVER & J. BERGSTROM
 Pitot No. 1123-5 C_p .84

Cross-section View	Elevation View
Drawing of Test Site	

MDI - NITRO

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length:	in.	Time start:	hrs
A 1					
2					
3					
4					
5					
6					
B 1					
2					
3					
4					
5					
6					
C 1					
2					
3					
4					
5					
6					
D 1					
2					
3					
4					
5					
6					
Temp. meas. device & S/N:				Time end:	hrs

INTERFOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ILI / TWO HARBOR
Source UNLOADING VENT STACK
Method MDI - NIT₂ Filter holder: ERG

Date 7/1/23 Test 10 Run 1
No. of traverse points 24
Filter type: glass fiber

Sample Train Leak Check:

Pretest: 0.02 cfm at 15 in. Hg. (vac) ☒
Posttest: 0 cfm at 14 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☒ other (s) MEL

No. of probe wash bottles: 1
Sample recovered by: Duff

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1414	1406	10
Total			10

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: cc/min at in. Hg.

Time start: (HRS) Time end: (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

Nitro

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job TCI Two Harbor

Source Unloading Vent

Date 4/7/93 Test 10 Run 1

Operator DVH & J.B.

Water Box No. 6

Compressor Conf. 77

Pilot No. U23-5

Bar. Press. 29.10

Nozzle No. 251

Dp 5.2

InHg H2O 1

Nozzle Dia. 251

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Orifice Water (inH ₂ O)	Dis. Vol. (cf)	VAC. inHg	Temperature (°F)					Stack	Probe	Dye	Imp.	Gas In	Gas Out	Oxygen (xv/v)	
C 6	0754	794.10																	
	2.5	796.36	.61	2.47	6.36	4	88	NA	NA		88	88				88	AMBIENT		
	5	798.57	.60	2.47	8.65	4	88				88	88				88	AIR		
	7.5	800.54	.49	2.02	0.21	4	89				88	87				88			
	10	802.78	.58	2.38	2.95	4	89				89	88				88			
	12.5	805.00	.54	2.24	5.12	4	85				89	87				87			
D 6	15	806.05	.09	.37	10.01	1	85				89	88				88			
	17.5	807.97	.43	1.79	7.96	1	84				90	89				89			
	20	809.40	.21	.87	9.30	1	87				90	89				89			
	22.5	811.46	.51	2.11	1.43	4	87				89	89				89			
	25	813.54	.48	1.98	3.48	4	89				89	90				90			
	27.5	814.97	.20	.82	4.81	2	89				90	89				89			
A 6	30	815.86	.12	.50	5.84	2	86				90	90				90			
	32.5	817.80	.48	1.99	7.89	4	86				91	90				90			
	35	819.40	.27	1.12	9.44	4	85				91	90				90			
	37.5	821.06	.30	1.26	10.7	4	82				91	91				91			
	40	822.68	.33	1.37	2.78	4	87				92	91				91			
	42.5	823.48	.02	.08	3.20	1	87				92	91				91			
B 6	45	823.58	0	00	3.20	1	90				91	91				91			
	47.5	825.60	.63	2.60	5.55	5	90				92	91				91			
	50	827.99	.65	2.68	7.93	5	90				92	91				91			
	52.5	830.30	.60	2.49	0.23	5	86				92	91				91			
	55	832.66	.64	2.74	2.64	5	87				92	91				91			
	57.5	835.00	.64	2.66	5.02	5	87				92	91				91			
1	60	836.05	.12	.50	6.05		85				92	91				91			
		(0850)																Avg. = 89.9	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job TLI / TWO HARBOR
 Source UNLOADING VENT STACK
 Method MPE-N₂TRO Filter holder: ERC

Date 2/1/92 Test 10 Run 2
 No. of traverse points 24
 Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 11 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) MELLI

No. of probe wash bottles: 1
 Sample recovered by: DUH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	<u>1372</u>	<u>1361</u>	<u>11</u>
Total			<u>11</u>

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICI / Two Harbor Date 7/1/93 Source UNLOADING DEP Stack 10 Run 1

Operator DUH & J.B. Rep 1.77 IN MC 9992

Pilot No. V23-5 Cp 84 Bar. Press. 29.10 inHg H₂O / X
 Nozzle No. 257 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Orifice Meter (inH ₂ O)	Des. Vol. (cf)	VAC. (inHg)	Temperature (°F)				Gas In	Gas Out	Oxygen (XV/V)
							Stack	Probe	Dyn	Imp			
C 6	1003	836.20											
	2.5	838.46	.58	2.41	8.45	5	85				91	91	AMBIENT
5	5	840.69	.61	2.53	0.77	5	86				91	91	AIR
4	7.5	842.76	.45	1.87	2.77	5	86				92	91	
3	10	844.99	.52	2.33	4.99	5	86				93	92	
2	12.5	847.22	.54	2.23	7.23	5	91				93	92	
1	15	848.21	.12	.49	8.20	3	90				93	92	
D 6	17.5	850.30	.48	1.99	0.26	5	90				93	92	
5	20	851.75	.25	1.04	1.75	4	86				93	92	
4	22.5	853.27	.25	1.04	3.24	4	87				93	92	
3	25	855.21	.46	1.91	5.26	4	88				93	92	
2	27.5	856.74	.24	1.00	6.72	4	89				94	92	
1	30	856.74	0	0	6.72	—	86				94	93	
6	32.5	858.02	.20	.83	8.06	3	86				93	93	
5	35	859.52	.24	1.0	9.52	4	88				93	92	
4	37.5	861.11	.27	1.12	1.07	4	85				93	92	
3	40	862.95	.38	1.58	2.90	4	89				93	92	
2	42.5	863.19	0	.00	2.90	—	87				92	91	
1	45	863.19	0	.00	2.90	—	86				91	91	
B 6	47.5	865.04	.52	2.16	5.05	5	86				91	91	
5	50	867.40	.63	2.61	7.40	5	88				92	91	
4	52.5	869.76	.67	2.77	9.82	5	88				92	91	
3	55	872.16	.60	2.48	2.12	5	89				92	91	
2	57.5	874.45	.62	2.56	4.45	5	89				92	91	
1	60	875.35	.60	.24	5.18		91				92	91	
	1105												
Total		V = 39.15	H = 1.57									Avg. = 92	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / TWO HARBORS Date 2/1/93 Test D Run 3
 Source UNLOADING VENT STACK No. of traverse points 24
 Method MOE - Nitro Filter holder: ERC Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 13 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) MELLS

No. of probe wash bottles: 1
 Sample recovered by: DUB

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1			
Impinger No. 2			
Impinger No. 3			
Condenser			
Desiccant	1426	1416	10
Total			10

Integrated Gas Sampling Data: Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

NITRO


INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICI Two Hazards Operator DUNN, J.B. Pilot No. 123-5 Cp 84
 Source Unloading Tent Stack Meter Box No. 6 Bar. Press. 29.0 inHg H₂O 1 X
 Date 8/1/83 Computer Code 10 Run 3 Nozzle No. 251 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inHg)	Drifts Meter (inHg)	Des. Vol. (cf)	VAD. inHg	Temperature (°F)				Gas In	Gas Out	Oxygen (xv/v)
							Stack	Probe	Duct	Inlet			
C-6	12.4	825.71	66	2.75	8.13	4	88				93	93	AMBIENT
5	2.5	878.16	64	2.66	0.51	4	88				95	91	AIR
4	7.5	880.40	47	1.96	2.35	4	89				96	94	
3	10	882.56	60	2.50	4.86	4	89				96	94	
2	12.5	884.82	61	2.55	7.20	4	87				96	95	
1	15	887.17	65	2.21	7.87	1	83				95	94	
D-6	17.5	887.90	135	1.46	9.69	3	88				96	94	
5	20	889.66	135	1.63	0.81	2	83				96	94	
4	22.5	890.93	131	1.29	2.47	3	88				96	95	
3	25	892.54	136	2.34	4.71	5	88				96	95	
2	27.5	894.80	127	1.12	6.26	3	91				97	95	
1	30	896.36	0	0.00	6.36	—	92				96	95	
A-6	32.5	897.93	133	1.38	7.98	3	89				96	94	
5	35	898.98	110	1.42	8.93	1	87				96	94	
4	37.5	900.71	135	1.47	0.71	3	86				96	96	
3	40	903.20	129	1.21	2.32	3	87				91	91	
2	42.5	903.54	120	0	2.32	—	91				91	91	
1	45	903.54	0	0	2.32	—	86				91	91	
B-6	47.5	905.78	162	2.57	4.65	5	88				93	91	
5	50	908.30	166	2.13	7.05	5	89				93	91	
4	52.5	909.40	150	2.08	9.16	5	87				93	91	
3	55	912.73	164	2.67	1.54	—	84				93	92	
2	57.5	915.05	159	2.45	3.82	—	87				93	92	
1	60	916.09	112	1.49	4.85	—	86				94	93	
Total		1353		15.7									
V = 29.14													
Q = 6.0													
Avg. = 93.5													

Method 5
 Standard
 90.5
 (-1.5)

Job IC1 TWO HARBORS
Source UNLOADING VENT STACK
Test 11 Run 0 Date 7-1-93
Stack dimen. 55x55 IN.
Dry bulb °F Wet bulb °F
Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
Barometric pressure 29.10 in Hg
Static pressure -0.62 in WC
Operators QH - SE
Pitot No. 230-6 Cp .84



Drawing of Test Site

MDI TRAIN L

[illegible]

INTERPOL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

FL

Job ICI - TWO HARBORS
 Source UNLOADING VENT
 Method MD1 Filter holder: GLASS
 FL

Date 7-1-93 Test 11 Run 1
 No. of traverse points _____
 Filter type: _____

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 1.02 cfm at 10 in. Hg. (vac) ☐
LESS THAN

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) 1, 2 HP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	100	128	-28
Impinger No. 2	81	85	-4
Impinger No. 3			
Condenser			
Desiccant			
Total			-32

Integrated Gas Sampling Data:

AMBIENT

Bag Pump No. NA Box No. NA Bag No. NA

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOLLE LABORATORIES A METHOD 5 FIELD DATA SHEET

Job IC1 TWO HARBOR S
 Source WYLADEK VENT
 Date 7-1-93

Operator 6/10 SFE
 Meter Box No. 3
 Gas meter serial 9970

Pilot No. 231 CP 84
 Bar. Press. 29.10 inHg
 Nozzle No. 231 inHg

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inWC)	Drifted Meter (inWC)	Obs. Vol. (cf)	VAC. inHg	Temperature (°F)					Oxygen (xy/v)		
							Stack	Probe	Dyn	Leq.	Gas/In		Gas/Out	
B	(0754)	497.35											MBE	
	6	498.68	.50	.56	867	6	88				39	89		89
	5	499.96	.48	.53	996	6	87				40	89		89
	4	501.39	.61	.68	142	6	87				41	90		89
	3	502.76	.62	.69	290	8	89				42	91		90
	2	504.27	.55	.61	428	8	90				42	92		90
C	1	505.03	.15	.16	501	1	84				40	93	90	
	6	506.21	.42	.47	623	5	85				41	95	90	
	5	507.60	.60	.67	769	5	89				39	94	90	
	4	508.98	.48	.54	899	5	88				39	95	91	
	3	510.48	.60	.67	045	7	84				40	95	91	
	2	511.73	.45	.50	171	6	87				40	95	91	
D	1	513.05	.48	.54	302	6	85				39	98	91	
	6	514.19	.38	.43	419	5	85				39	96	93	
	5	515.15	.25	.28	512	4	85				41	97	93	
	4	516.39	.40	.45	633	4	87				42	97	93	
	3	517.67	.50	.56	767	4	86				40	97	95	
	2	518.62	.28	.31	867	3	87				40	98	92	
A	1	519.21	.08	.09	921	1	85				40	98	92	
	6	520.25	.30	.34	024	4	85				40	98	92	
	5	521.09	.20	.22	109	3	85				39	97	92	
	4	521.96	.20	.22	193	3	88				40	98	93	
	3	523.05	.36	.39	305	1	88				41	97	93	
	2	523.71	.12	.13	571	1	87				42	98	93	
	72	523.71	.00	.00	571	1	87				40	95	92	
	0908													
		V _s = 36.36		ΔH = 42									Avg. = 95.6	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI TWO HARBORS
 Source UNLOADING VENT STACK
 Method NO1 Filter holder: GLASS

Date 7-1-93 Test 11 Run 2
 No. of traverse points 2
 Filter type: GF

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: { 102 cfm at 10 in. Hg. (vac) ☒
LESS THAN

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

☐ acetone
☒ other(s) 1,2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: GH

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>106</u>	<u>127</u>	<u>-21</u>
Impinger No. 2	<u>82</u>	<u>85</u>	<u>-3</u>
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>-25</u>

Integrated Gas Sampling Data:

- AMBIENT

Bag Pump No. NA Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES A METHOD 5 FIELD DATA SHEET

Job IC1 TWO HARBORS Pitot No. 23 Date 12-6 DP 87
 Source UNLOADERS VENT STACK Operator CHASE Bar. Press. 29.10 inHg 120
 Date 7-1-93 Meter Box No. 3970 Nozzle No. 27-3 Nozzle Dia. 1/2 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Hood (ft/min)	Orifice Meter (ft/min)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)					Oxygen (xv/v)
							Stack	Probe	Dry	Wet	Gas In	
A	6	524.280	.20	.22	5.12	1	85			41	95	95
	5	525.10	.22	.25	6.01	2	86			42	95	95
	4	526.00	.15	.16	6.74	1	88			43	95	94
	3	526.74	.39	.43	7.92	4	91			40	96	95
	2	527.92	.05	.05	8.34	1	90			41	97	95
B	1	528.36	.00	.00	8.34	0	86			40	96	84
	6	528.34	.45	.51	9.61	5	86			40	96	93
	5	529.61	.40	.54	0.92	5	86			41	98	94
	4	530.95	.61	.69	2.40	5	88			39	99	94
	3	532.40	.63	.71	3.90	6	91			39	99	94
C	3	533.93	.55	.62	5.30	7	90			40	99	94
	2	535.30	.35	.20	6.25	7	88			39	98	93
	1	536.25	.50	.56	7.57	5	88			40	98	94
	6	537.59	.60	.68	9.05	6	87			40	98	94
	5	539.05	.50	.56	0.39	6	86			39	98	93
D	4	540.39	.60	.67	1.85	6	89			39	98	93
	3	541.85	.60	.67	3.32	6	88			40	99	95
	2	543.32	.05	.05	3.74	1	88			34	96	93
	1	543.77	.50	.56	5.07	5	88			40	97	93
	6	545.07	.38	.42	6.24	5	89			40	99	94
	5	546.25	.35	.39	7.36	5	91			43	99	94
	4	547.37	.50	.56	8.69	5	89			41	99	94
	3	548.68	.38	.42	9.86	5	91			41	98	93
	2	549.86	.10	.11	0.44	3	91			41	99	93
	1	550.76										
		Σ = 26.18		Σ = 42						Avg. 95.4		

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job 1C1 TWO HARBORS
 Source UNLOADER VENT STACK
 Method MPI Filter holder: GLASS

Date 7-1-93 Test 11 Run 3
 No. of traverse points 34
 Filter type: 6F

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: .00 cfm at 10 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: Recovery solvent(s)

☐ acetone
☒ other(s) 1.2 M³ IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: GA

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	<u>106</u> <u>10</u>	<u>128</u>	<u>- 22</u>
Impinger No. 2	<u>82</u>	<u>85</u>	<u>- 3</u>
Impinger No. 3			
Condenser			
Desiccant			
			<u>- 25</u>
Total			

Integrated Gas Sampling Data:

Bag Pump No. NA Box No. NA Bag No. NA

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES A METHOD 5 FIELD DATA SHEET

 Job IC1 TWO HARBORS
 Source UNLOADERS
 Date 7-1-83


 Operators GH JSE
 Meter Box No. 3
 Gas meter serial 9470

 Pilot No. 2316
 Bar. Press. 29.10 in Hg
 Nozzle No. 12 in.

Traverse Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (in H ₂ O)	Drifts Water (in H ₂ O)	Dep. Vol. (cf)	VAC. in Hg	Temperatures (°F)					Oxygen (xv/v)	
							Stack	Probe	Duct	Inlet	Gas/Out		
AMBIENT													
B	3	552.72	.57	.64	2.72	5	88			40	98	97	
	6	554.15	.57	.64	4.15	5	89			41	98	97	
	9	555.64	.61	.69	5.63	6	90			40	99	96	
	12	557.10	.60	.68	7.10	6	87			40	100	97	
	15	558.63	.64	.73	8.63	7	93			39	101	99	
	18	560.03	.58	.65	0.08	6	90			39	101	97	
C	21	561.47	.54	.61	1.47	5	90			40	101	97	
	24	562.89	.60	.68	2.89	5	88			39	101	96	
	27	564.22	.50	.56	4.28	5	91			40	101	96	
	30	565.68	.54	.61	5.68	5	92			42	101	97	
	33	567.08	.55	.62	7.09	6	89			43	101	96	
	36	567.68	.09	.10	7.66	6	87			40	102	97	
D	39	568.89	.40	.48	8.87	5	85			41	102	97	
	42	569.92	.30	.34	9.91	5	87			40	97	99	
	45	571.09	.38	.43	1.08	5	89			39	100	97	
	48	572.42	.50	.56	2.42	5	88			40	101	97	
	51	573.60	.38	.43	3.60	3	89			42	101	97	
	54	574.20	.10	.11	4.20	1	87			40	101	97	
A	57	575.31	.34	.38	5.31	1	87			40	100	98	
	60	576.09	.17	.19	6.09	1	91			41	100	98	
	63	577.08	.27	.30	7.08	2	86			41	100	97	
	66	578.16	.32	.36	8.16	4	88			39	101	98	
	69	578.59	.05	.05	8.59	1	90			39	103	99	
	72	578.59	.00	.00	8.59	0	90			39	100	99	
(1424)													
Σ = 72		27.29											
Avg. = 98.7													

INTERPOL LABORATORIES - EPA METHOD 2 FIELD DATA SHEET

Job ICF / TWO HARBORS
 Source UNLOADING VENT STACK
 Test 12 Run Date 7/1/93
 Stack dimen. 55 x 55 IN.
 Dry bulb °F Wet bulb °F
 Manometer: ☒ Reg. ☐ Exp. ☐ Elec.
 Barometric pressure 29.15 in Hg
 Static pressure -.80 in WC
 Operators D. Van Hoever & J. Bergstrom
 Pitot No. 123-5 Cp .84



MDI TRAIN F

Traverse Point No.	Fraction of Diameter	Distance from Stack Wall (in)	Distance from End of Port (in)	Velocity Pressure (in WC)	Temperature of gas (°F)
		Port length: in.		Time start: hrs	
A 1					
2					
3					
4					
5					
6					
B 1					
2					
3					
4					
5					
6					
C 1					
2					
3					
4					
5					
6					
D 1					
2					
3					
4					
5					
6					
Temp. meas. device & S/N: <u>PDT #18</u>				Time end: hrs	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI / TWO HARBORS
 Source UNLOADING VENT STACK
 Method MDL-EF Filter holder: 91655

Date 7/1/93 Test 12 Run 1
 No. of traverse points 24
 Filter type: glass fiber

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 15 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) 1-2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: DIST

Condensate Data:

Item	Weight (g)		
	Final	Tare	Difference
Impinger No. 1	95	126	- 31
Impinger No. 2	78	85	- 7
Impinger No. 3			
Condenser			
Desiccant			
Total			-38

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job IC1 TWO HARBORS
 Source UNDAQUADER
 Date 7-1-93

Operator SE
 Meter Box No. 17
 Gas analyzer config. IN NC

Pilot No. 23106 CP 84
 Bar. Press. 29.10 inHg H₂O LS
 Nozzle No. 1

Transfer Point No.	Sampling Time (min)	Sample Volume (cf)	Velocity Head (inH ₂ O)	Drifts Meter (inH ₂ O)	Des. Vol. (cf)	VAD. inHg	Temperature (°F)				Oxygen (xv/v)	
							Stack	Probe	Dry	Wet	Gas/in	Cal/Dpt
A	0754	876.60									82	82
	3	877.53	.23	.20	7.51	4	88			46	82	82
	6	878.40	.15	.20	8.25	4	87				83	83
	9	879.23	.27	.36	9.25	4	87			46	84	83
	12	880.30	.46	.61	0.55	7	89			47	85	83
B	15	880.5	0	.00	0.55	-	85				87	84
	18	880.50	0	.00	0.55	-	84			46	85	84
	21	882.00	.60	.81	2.03	9	87			46	88	85
	24	883.44	.61	.82	3.54	9	89			45	90	86
	27	885.03	.62	.84	5.06	9	88			44	92	86
C	30	886.63	.65	.88	6.62	8	89				92	87
	33	888.10	.59	.80	8.10	8	87			44	93	88
	36	888.96	.19	.76	8.95	5	85				94	88
	39	890.65	.15	.76	0.48	8	82			43	94	88
	42	891.99	.64	.88	1.96	8	85			42	94	88
D	45	893.46	.53	.72	3.37	8	87				95	88
	48	894.80	.53	.72	4.70	8	87			41	95	89
	51	896.20	.60	.82	6.30	8	85				95	90
	54	897.10	.13	.17	7.01	4	85			43	96	90
	57	898.42	.41	.50	8.26	5	85				94	90
E	60	899.46	.30	.41	9.33	4	85			42	95	90
	63	900.27	.22	.30	0.24	4	85				96	90
	66	901.48	.45	.61	1.55	6	88			41	97	90
	69	901.97	.05	.66	1.99		88				96	91
	72	901.97	0	.00	1.99		88				97	91
C9908												
72		25.37		.50							AVG. = 89.7	

INTERPOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI TWO HARBORS
 Source _____
 Method MD1 Filter holder: _____

Date 7-1-93 Test 12 Run 2
 No. of traverse points 34
 Filter type: _____

Sample Train Leak Check:

Pretest: { 0.02 cfm at 15 in. Hg. (vac) ☐
 Posttest: _____ cfm at _____ in. Hg. (vac) ☐

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone _____
 _____ ☐ other(s) _____

No. of probe wash bottles: _____
 Sample recovered by: _____

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	116	129	-13
Impinger No. 2	77	81	-4
Impinger No. 3			
Condenser			
Desiccant			
Total			-17

Integrated Gas Sampling Data:

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

CF-023

INTERFOLL LABORATORIES EPA METHOD 5/17 SAMPLE LOG SHEET

Job ICI TWO HARBORS Date 7/1/93 Test 12 Run 3
 Source UNLOADING KENT STACK No. of traverse points _____
 Method MDI Filter holder: 9655 Filter type: _____

Sample Train Leak Check:

Pretest: (0.02 cfm at 15 in. Hg. (vac) ☒
 Posttest: 0 cfm at 15 in. Hg. (vac) ☒

Particulate Catch Data:

No.s of filters used: _____ Recovery solvent(s) _____

_____ ☐ acetone
 _____ ☒ other(s) 1-2 MP IN TOLUENE

No. of probe wash bottles: 1
 Sample recovered by: Duff

Condensate Data:

Item	Weight(g)		
	Final	Tare	Difference
Impinger No. 1	<u>107</u>	<u>139</u>	<u>-32</u>
Impinger No. 2	<u>83</u>	<u>86</u>	<u>-3</u>
Impinger No. 3			
Condenser			
Desiccant			
Total			<u>-35</u>

Integrated Gas Sampling Data: - Ambient Air

Bag Pump No. _____ Box No. _____ Bag No. _____

Bag Material: 5-layer Aluminized Tedlar Size: 44 L

Pretest leak check: _____ cc/min at _____ in. Hg.

Time start: _____ (HRS) Time end: _____ (HRS)

Sampling rate: _____ cc/min Operator: _____

S/N of O₂ Analyzer used to monitor train outlet: _____

INTERPOL LABORATORIES EPA METHOD 5 FIELD DATA SHEET

Job ICI / Two Harbor Operator DW4 & J.B Pitot No. 123-5 DP 184
 Source unloading vent stack Meter Box No. 1 Bar. Press. 24.10 inHg H₂O x
 Date 11/23 Cassette diff. 1.97 TN NC 1.97 Nozzle Dia. 1.25 in.

Traverse Point No.	Sampling Time (min)	Supply Volume (cf)	Velocity Head (inH ₂ O)	Drifts Meter (inH ₂ O)	Des. Vol. (cf)	VAC. inHg	Temperature (°F)					Oxygen (xv/v)
							Stack	Probe	Duct	Insp.	Gas In	
A 6	12.15	929.69	.23	.31	0.62	6	88			41	91	AMBIEN
5	3	930.75	.17	.21	1.36	6	88			43	92	Air
4	6	931.60	.23	.31	2.29	5	90			44	92	
3	9	932.25	.29	.53	3.51	10	87			44	93	
2	12	933.56	.47	.65	4.86	10	83			44	93	
1	15	934.82	0	0.00	4.86	—	90			44	93	
B 6	18	934.82	.50	.69	6.25	12	83			44	93	
5	21	936.26	.63	.86	7.80	15	88			44	93	
4	24	937.83	.59	.80	9.30	15	91			43	94	
3	27	939.19	.62	.84	8.84	15	92			42	94	
2	30	946.83	.63	.86	2.39	15	89			42	94	
1	33	947.25	.22	.30	3.31	5	87			42	94	
C 6	36	943.41	.51	.70	4.72	13	87			42	91	
5	39	944.85	.62	.85	6.26	15	87			42	92	
4	42	946.37	.45	.61	7.56	13	87			41	92	
3	45	947.57	.56	.76	9.02	13	88			42	92	
2	48	949.06	.58	.79	0.51	13	89			42	92	
1	51	950.61	.07	.09	1.02	5	87			42	93	
D 6	54	951.11	.47	.64	2.37	10	87			42	92	
5	57	952.46	.37	.50	3.55	6	87			42	92	
4	60	953.60	.43	.59	4.84	10	86			42	92	
3	63	954.93	.56	.76	6.30		88			42	93	
2	66	956.19	.27	.37	7.31		88			42	93	
1	69	959.30	.0	0	7.31		88			42	93	
V = 27.75							Avg. = 92.6					

APPENDIX D

INTERPOLL LABORATORIES ANALYTICAL DATA

TABLE OF CONTENTS

Particulate	1
Formaldehyde	10
Phenol	15

Note: MDI results presented in Section 2

THC results (strip charts) presented in Appendix C

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash
(Filter wash)

Job IC1 Two Harbors Mn. Source Press Vent
Team Leader G.H. Test Site Stack
Date Submitted 7-6-93 Date of Test 6-29-93
Test No. 7 No. of Runs Completed 3
Date of Analysis 7-13-93 Technician C. Helgeson
Transport Leakage ☒ None ☐ _____ ml Solvent Acetone

0	Test <u>Run 0</u>	Dish No. _____
	Field Blank	Dish Tare Wt. _____ g
	Log Number _____	Dish+Sample Wt. _____ g
	Vol. of Solvent _____ ml	Sample Wt. _____ g
	*Solvent Residue <u>3.0</u> ug/ml	
1	Test <u>4</u> Run <u>1</u>	Dish No. <u>601</u>
	Vol. of Solvent <u>20</u> ml	Dish Tare Wt. <u>47.6657</u> g
	Log Number <u>9289-23</u>	Dish+Sample Wt. <u>47.6662</u> g
	Comments _____	Sample Wt. <u>0.0005</u> g
2	Test <u>4</u> Run <u>2</u>	Dish No. <u>602</u>
	Vol. of Solvent <u>35</u> ml	Dish Tare Wt. <u>47.2210</u> g
	Log Number <u>-26</u>	Dish+Sample Wt. <u>47.2217</u> g
	Comments _____	Sample Wt. <u>0.0007</u> g
3	Test <u>4</u> Run <u>3</u>	Dish No. <u>604</u>
	Vol. of Solvent <u>30</u> ml	Dish Tare Wt. <u>50.1445</u> g
	Log Number <u>-29</u>	Dish+Sample Wt. <u>50.1451</u> g
	Comments _____	Sample Wt. <u>0.0006</u> g
4	Test _____ Run _____	Dish No. _____
	Vol. of Solvent _____ ml	Dish Tare Wt. _____ g
	Log Number _____	Dish+Sample Wt. _____ g
	Comments _____	Sample Wt. _____ g
5	Test _____ Run _____	Dish No. _____
	Vol. of Solvent _____ ml	Dish Tare Wt. _____ g
	Log Number _____	Dish+Sample Wt. _____ g
	Comments _____	Sample Wt. _____ g

*Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10⁶) / Vol. of Sol. _____ ml]
EPA-M5 Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk.	Run 1	Run 2	Run 3	Run 4	Run 5
	0.0004	0.0006	0.0005	0-1	

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job IC1 Two Harbors mn Source Press Vent
Team Leader GH Test Site Stack
Date Submitted 7-6-93 Date of Test 6-29-92
Test No. 4 No. of Runs Completed 3
Date of Analysis 7-13-93 Technician C. Helgeson
Transport Leakage ☒ None ☐ ml Solvent Acetone

0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue <u>3.0</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>4</u> Run <u>1</u> Vol. of Solvent <u>100</u> ml Log Number <u>9289-22</u> Comments _____	Dish No. <u>606</u> Dish Tare Wt. <u>48.5721</u> g Dish+Sample Wt. <u>48.5782</u> g Sample Wt. <u>0.0061</u> g
2	Test <u>4</u> Run <u>2</u> Vol. of Solvent <u>125</u> ml Log Number <u>-25</u> Comments _____	Dish No. <u>607</u> Dish Tare Wt. <u>47.3962</u> g Dish+Sample Wt. <u>47.4056</u> g Sample Wt. <u>0.0096</u> g
3	Test <u>4</u> Run <u>3</u> Vol. of Solvent <u>90</u> ml Log Number <u>-28</u> Comments _____	Dish No. <u>611</u> Dish Tare Wt. <u>50.0090</u> g Dish+Sample Wt. <u>50.0157</u> g Sample Wt. <u>0.0067</u> g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue ___ ug/ml = [(Sample Wt. ___ g) (10⁶)] / Vol. of Sol. ___ ml
EPA-M5 Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0058</u>	<u>0.0042</u>	<u>0.0064</u>	<u>0.002</u>		LSC-01YR
--	---------------	---------------	---------------	--------------	--	----------

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job ICI Two Harbors Mn. Source UnLoader Vent
Team Leader GH Test Site Stack
Date Submitted 7-6-93 Date of Test 6-29-93
Test No. 7 No. of Runs Completed 3
Date of Analysis 7-13-93 Technician C. Helgeson

0	Test <u>4</u> Run <u>0</u> Field Blank Log Number <u>9289-152</u> Comments _____	Filter No. <u>5377</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9466</u> g Filter+Sample Wt. <u>.9470</u> g Sample Wt. <u>0.0004</u> g
1	Test <u>4</u> Run <u>1</u> Log Number <u>-24</u> Comments _____	Filter No. <u>5375</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9497</u> g Filter+Sample Wt. <u>.9514</u> g Sample Wt. <u>0.0017</u> g
2	Test <u>4</u> Run <u>2</u> Log Number <u>-27</u> Comments _____	Filter No. <u>5376</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9378</u> g Filter+Sample Wt. <u>.9480</u> g Sample Wt. <u>0.0102</u> g
3	Test <u>4</u> Run <u>3</u> Log Number <u>-30</u> Comments _____	Filter No. <u>5378</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9310</u> g Filter+Sample Wt. <u>.9438</u> g Sample Wt. <u>0.0128</u> g
4	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0097	0.0102	0.0128		
--	--------	--------	--------	--	--

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

--	--	--	--	--	--

LSC-02PR

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash
(Filter Wash)

Job IC1 Two Harbors Mn. Source Unloader Vent
Team Leader GH Test Site Stack
Date Submitted 7-6-93 Date of Test 6-29-93
Test No. 2 No. of Runs Completed 3
Date of Analysis 7-13-93 Technician C. Helgeson
Transport Leakage ☒ None ☐ ml Solvent Acetone

0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent _____ ml *Solvent Residue <u>3.0</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>2</u> Run <u>1</u> Vol. of Solvent <u>30</u> ml Log Number <u>9289-10</u> Comments _____	Dish No. <u>612</u> Dish Tare Wt. <u>49.6249</u> g Dish+Sample Wt. <u>49.6258</u> g Sample Wt. <u>0.0009</u> g
2	Test <u>2</u> Run <u>2</u> Vol. of Solvent <u>20</u> ml Log Number <u>-13</u> Comments _____	Dish No. <u>614</u> Dish Tare Wt. <u>44.4103</u> g Dish+Sample Wt. <u>44.4109</u> g Sample Wt. <u>0.0006</u> g
3	Test <u>2</u> Run <u>3</u> Vol. of Solvent <u>30</u> ml Log Number <u>-16</u> Comments _____	Dish No. <u>615</u> Dish Tare Wt. <u>48.1014</u> g Dish+Sample Wt. <u>48.1059</u> g Sample Wt. <u>0.0045</u> g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue _____ ug/ml = [(Sample Wt. _____ g) (10⁶)] / Vol. of Sol. _____ ml
EPA-M5 Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0008	0.0005	0.0044 D-4		
--	--------	--------	------------	--	--

LSC-01YR

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job IC1 Two Harbors Mn. Source Unloader vent
Team Leader G H Test Site Stack
Date Submitted 7-6-93 Date of Test 6-29-93
Test No. 2 No. of Runs Completed 3
Date of Analysis 7-13-93 Technician C. Helgeson
Transport Leakage ☒ None ☐ _____ ml Solvent Acetone

0	Test <u>2</u> Run <u>0</u>	Dish No. <u>605</u>	
	Field Blank	Dish Tare Wt. <u>49.6843</u>	g
	Log Number <u>9284-07</u>	Dish+Sample Wt. <u>49.6846</u>	g
	Vol. of Solvent <u>100</u> ml	Sample Wt. <u>0.0003</u>	g
	*Solvent Residue <u>3.0</u> ug/ml		
1	Test <u>2</u> Run <u>1</u>	Dish No. <u>304</u>	
	Vol. of Solvent <u>100</u> ml	Dish Tare Wt. <u>60.5531</u>	g
	Log Number <u>-09</u>	Dish+Sample Wt. <u>60.5744</u>	g
	Comments _____	Sample Wt. <u>0.0213</u>	g
2	Test <u>2</u> Run <u>2</u>	Dish No. <u>305</u>	
	Vol. of Solvent <u>100</u> ml	Dish Tare Wt. <u>56.0206</u>	g
	Log Number <u>-12</u>	Dish+Sample Wt. <u>56.0356</u>	g
	Comments _____	Sample Wt. <u>0.0150</u>	g
3	Test <u>2</u> Run <u>3</u>	Dish No. <u>518</u>	
	Vol. of Solvent <u>120</u> ml	Dish Tare Wt. <u>48.1020</u>	g
	Log Number <u>-15</u>	Dish+Sample Wt. <u>48.1098</u>	g
	Comments _____	Sample Wt. <u>0.0078</u>	g
4	Test _____ Run _____	Dish No. _____	
	Vol. of Solvent _____ ml	Dish Tare Wt. _____	g
	Log Number _____	Dish+Sample Wt. _____	g
	Comments _____	Sample Wt. _____	g
5	Test _____ Run _____	Dish No. _____	
	Vol. of Solvent _____ ml	Dish Tare Wt. _____	g
	Log Number _____	Dish+Sample Wt. _____	g
	Comments _____	Sample Wt. _____	g

*Solvent Residue 3.0 ug/ml = [(Sample Wt. 0.0003 g) (10⁶)] / Vol. of Sol. 100 ml
EPA-M5 Acetone Residue Blank Spec. 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0210</u>	<u>0.0147</u>	<u>0.0074</u> D-5		
--	---------------	---------------	-------------------	--	--

LSC-01YR

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job ICI Two Harbors Mn. Source Unloader Vent
Team Leader GL Test Site Stack
Date Submitted 7-6-93 Date of Test 6-29-93
Test No. 2 No. of Runs Completed 3
Date of Analysis 7-14-93 Technician C. Helgeson

0	Test <u>Run 0</u> Field Blank Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>2</u> Run <u>1</u> Log Number <u>9289-11</u> Comments _____	Filter No. <u>5373</u> Filter Type <u>4"GF</u> Filter Tare Wt. <u>.9404</u> g Filter+Sample Wt. <u>.9482</u> g Sample Wt. <u>0.0078</u> g
2	Test <u>2</u> Run <u>2</u> Log Number <u>-14</u> Comments _____	Filter No. <u>5429</u> Filter Type <u>4"GF</u> Filter Tare Wt. <u>.9236</u> g Filter+Sample Wt. <u>.9314</u> g Sample Wt. <u>0.0078</u> g
3	Test <u>2</u> Run <u>3</u> Log Number <u>-17</u> Comments _____	Filter No. <u>5374</u> Filter Type <u>4"GF</u> Filter Tare Wt. <u>.9478</u> g Filter+Sample Wt. <u>.9539</u> g Sample Wt. <u>0.0061</u> g
4	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0078	0.0078	0.0061		
--	--------	--------	--------	--	--

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

--	--	--	--	--	--

LSC-02PR

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash
(Filter wash)

Job IC1 Sagola Mich Source Press unloader vent
Team Leader GH Test Site stack
Date Submitted 6-29-93 Date of Test 6-25-93
Test No. 1 No. of Runs Completed 3
Date of Analysis 7-13-93 Technician C. Helgeson
Transport Leakage ☒ None ☐ ml Solvent Acetone

0	Test <u>Run 0</u> Field Blank Log Number _____ Vol. of Solvent <u>ml</u> *Solvent Residue <u>3.0</u> ug/ml	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
1	Test <u>1</u> Run <u>1</u> Vol. of Solvent <u>25</u> ml Log Number <u>9202-18</u> Comments _____	Dish No. <u>519</u> Dish Tare Wt. <u>49.0521</u> g Dish+Sample Wt. <u>49.0534</u> g Sample Wt. <u>0.0013</u> g
2	Test <u>1</u> Run <u>2</u> Vol. of Solvent <u>20</u> ml Log Number <u>-19</u> Comments _____	Dish No. <u>521</u> Dish Tare Wt. <u>50.5453</u> g Dish+Sample Wt. <u>50.5970</u> g Sample Wt. <u>0.0017</u> g
3	Test <u>1</u> Run <u>3</u> Vol. of Solvent <u>30</u> ml Log Number <u>-20</u> Comments _____	Dish No. <u>520</u> Dish Tare Wt. <u>48.5267</u> g Dish+Sample Wt. <u>48.5286</u> g Sample Wt. <u>0.0019</u> g
4	Test <u>Run</u> Vol. of Solvent <u>ml</u> Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test <u>Run</u> Vol. of Solvent <u>ml</u> Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue ug/ml = [(Sample Wt. g) (10⁶)] / Vol. of Sol. ml

EPA-M5 Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0012</u>	<u>0.0016</u>	<u>0.0018</u>	<u>D-7</u>	
--	---------------	---------------	---------------	------------	--

SC 0140

Interpoll Laboratories
(612) 786-6020

EPA Method 5 Data Reporting Sheet
Probe/Cyclone Wash

Job IC1 Sogola MT Source Press Unloading Vent
Team Leader GH Test Site Stack
Date Submitted 6-29-93 Date of Test 6-25-93
Test No. 1 No. of Runs Completed 3
Date of Analysis 7-14-93 Technician C. Helgeson
Transport Leakage ☒ None ☐ ml Solvent Acetone

0	Test <u>1</u> Run <u>0</u> Field Blank Log Number _____ Vol. of Solvent <u>100</u> ml *Solvent Residue <u>3.0</u> ug/ml	Dish No. <u>1</u> Dish Tare Wt. <u>51.9667</u> g Dish+Sample Wt. <u>51.9870</u> g Sample Wt. <u>0.0003</u> g
1	Test <u>1</u> Run <u>1</u> Vol. of Solvent <u>85</u> ml Log Number _____ Comments _____	Dish No. <u>6</u> Dish Tare Wt. <u>44.5276</u> g Dish+Sample Wt. <u>44.5460</u> g Sample Wt. <u>0.0184</u> g
2	Test <u>1</u> Run <u>2</u> Vol. of Solvent <u>85</u> ml Log Number _____ Comments _____	Dish No. <u>18</u> Dish Tare Wt. <u>49.9831</u> g Dish+Sample Wt. <u>49.9972</u> g Sample Wt. <u>0.0141</u> g
3	Test <u>1</u> Run <u>3</u> Vol. of Solvent <u>90</u> ml Log Number _____ Comments _____	Dish No. <u>27</u> Dish Tare Wt. <u>52.4403</u> g Dish+Sample Wt. <u>52.4554</u> g Sample Wt. <u>0.0151</u> g
4	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Vol. of Solvent _____ ml Log Number _____ Comments _____	Dish No. _____ Dish Tare Wt. _____ g Dish+Sample Wt. _____ g Sample Wt. _____ g

*Solvent Residue 3.0 ug/ml = [(Sample Wt. 0.0003g) (100)] / Vol. of Sol. 100 ml
EPA-MS Acetone Residue Blank Spec. { 7.8 ug/ml

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	<u>0.0181</u>	<u>0.0138</u>	<u>0.0148</u>	<u>D-8</u>	
--	---------------	---------------	---------------	------------	--

LSC-01YR

EPA Method 5 Data Reporting Sheet
Filter Gravimetrics

Job ICI Segole MI Source Press unloader vent
Team Leader OH Test Site stack
Date Submitted 6-29-93 Date of Test 6-25-93
Test No. 1 No. of Runs Completed 3
Date of Analysis 7-14-93 Technician C. Helgeson

0	Test <u>1</u> Run <u>0</u> Field Blank Log Number <u>9202-02</u> Comments _____	Filter No. <u>5372</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9387</u> g Filter+Sample Wt. <u>.9390</u> g Sample Wt. <u>0.0003</u> g
1	Test <u>1</u> Run <u>1</u> Log Number <u>-05</u> Comments _____	Filter No. <u>5427</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9178</u> g Filter+Sample Wt. <u>.9227</u> g Sample Wt. <u>0.0049</u> g
2	Test <u>1</u> Run <u>2</u> Log Number <u>-09</u> Comments _____	Filter No. <u>5425</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9203</u> g Filter+Sample Wt. <u>.9257</u> g Sample Wt. <u>0.0054</u> g
3	Test <u>1</u> Run <u>3</u> Log Number <u>-09</u> Comments _____	Filter No. <u>5428</u> Filter Type <u>4"6F</u> Filter Tare Wt. <u>.9160</u> g Filter+Sample Wt. <u>.9216</u> g Sample Wt. <u>0.0056</u> g
4	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g
5	Test _____ Run _____ Log Number _____ Comments _____	Filter No. _____ Filter Type _____ Filter Tare Wt. _____ g Filter+Sample Wt. _____ g Sample Wt. _____ g

Results:

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

	0.0049	0.0054	0.0056		
--	--------	--------	--------	--	--

Field Blk. Run 1 Run 2 Run 3 Run 4 Run 5

--	--	--	--	--	--

7/14/93

Interpoll Laboratories
(612)786-6020

Due Date: _____

Data Reporting Sheet

CLIENT: Internal / Dept. 020

JOB: ICI Polyurethanes / LP-Sagola

CLIENT NO: _____

P.O. NO: _____

PROJECT MGR: _____

PHONE: _____

DATE: _____

CONTACT: _____

Press & Unloader Vent Stack

LABORATORY REPORT #: 9202

SAMPLES COLLECTED: 6-25-93

SAMPLES RECEIVED: 6-24-93

SAMPLE ID: _____

Invoicing Signature Report
Routing

SAMPLE TYPE: _____

LOG NO: _____

PL ☐ ☐ ☐
Lab Mgr ☐ ☐ ☐
Ino Mgr ☐ ☐ ☐
Org Mgr ☐ ☐ ☐

T ₂ R ₀	T ₂ R ₁	T ₂ R ₂	T ₂ R ₃
Field Blank			
Impinger Catch			
9202-14	-15	-16	-17

PARAMETER	UNITS	DETECT LIMIT	ANALYSIS DATE & INITIALS	METHOD				
Formaldehyde	mg	0.050	8/24/93 <i>mm</i>	0011	x 11.4	<i>mm</i> x 927	x	x
↓	↓	2.5*	↓	↓		927	979	
↓	↓	5.0†	↓	↓				771

Footnotes: * 50X dilution † 100X dilution

In-House Comments: See Gregg before starting analysis
D-10 There are 2 Bottles each for 9202-15, 16 & 17
Talked to Gregg 7/14/93 *mm* LCI-01R Normal 001.

Due Date: _____

Interpoll Laboratories
(612) 786-6120

Data Reporting Sheet

CLIENT: Internal / Dept. 020

JOB: ICI Polyurethanes / LP-Two Harbors

CLIENT NO: _____

P.O. NO: _____

PROJECT MGR: _____

PHONE: _____

DATE: _____

CONTACT: _____

Press Vent Stuck

LABORATORY REPORT #: 9289

LABORATORY REPORT: 77
SAMPLES COLLECTED: 6-28-93

SAMPLES RECEIVED: 7-6-43

Invoicing		Signature	Report Routing

SAMPLE ID:

PL			
Lab Mgr			
Ino Mgr			
Org Mgr			

SAMPLE TYPE:

LOG NO:

Test 1	Test 1		
Trip Blank	Field Spike		
9289-01	-02		

[illegible]

after Blackpe subtraction:

Footnotes: * Spike Level $\Rightarrow 75.0 \mu\text{g}$ % Rec $\Rightarrow 100\%$

In-House Comments: see Gregg before starting analysis

D-11

Talked to Gregg
7/17/91 mjt Normal 0011 LC1-01R

Talked to Grew
LC1-01R
1/17/37 Normal

CLIENT: Internal / Dept. 020

JOB: ICI Polyurethanes / LP-Two Harbo
CLIENT NO: _____
P.O. NO: _____
PROJECT MGR: _____

PHONE: _____

DATE: _____

CONTACT: _____

unloading Vent Stack

LABORATORY REPORT #: 9289
 SAMPLES COLLECTED: 6-29-93
 SAMPLES RECEIVED: 7-6-93

SAMPLE ID:

Invoicing		Signature	Report Routing

SAMPLE TYPE:

LOG NO:

Test 5	Test 5		
Trip Blank	Field Spoke		
9284-35	-36		

PL	0	0	0
Lab Mgr	0	0	0
Ino Mgr	0	0	0
Org Mgr	0	0	0

[illegible]

Footnotes: * Spike level $\Rightarrow 75,0 \mu\text{m}$ % Rec $\Rightarrow 712$

In-House Comments: see Gregg before starting analysis

Talked to Gregg
7/14/93 only
Normal 0011

Interpoll Laboratories
(612) 786-6020

Data Reporting Sheet

CLIENT: Internal / Dept. 020

JOB: ICI Blyuothanes/LP-Two Harbor

CLIENT NO: _____

P.O. NO: _____

PROJECT MGR:

PHONE: _____

DATE: _____

CONTACT: _____

unloading Vent Stack

LABORATORY REPORT #: 9289

SAMPLES COLLECTED: 6-29-93

SAMPLES RECEIVED: 7-6-93

Invoicing	Signature	Report Routine
-----------	-----------	-------------------

SAMPLE ID:

PL			
Lab Mgr			
Ino Mgr			
Org Mgr			

SAMPLE TYPE:

LOG NO:

$T_5 R_1$	$T_5 R_2$	$T_5 R_3$	
Impinger Catch	→		
9284-37	-38	-39	

[illegible]

Footnotes:

to 50% dilution

In-House Comments:

D-14

see Gregg before starting analysis
There are 2 bottles each for 9209-57, 38+34

Talked to Gregg
2/19/93 mlt LC1-61R
normal 0011

INTERPOLL LABORATORY

PHENOL RESULTS

MASS OF ANALYTE (ug)

LP - SAGOLA

PRESS & UNLOADER COMMON VENT

	Spike	Field Blank	Run 1	Run 2	Run 3	Spike
2-fluorophenol	59.8	46.7	27.4	31.4	28.4	59.8
phenol-d6	5.33	3.32	3.3	3.54	3.36	5.33
2,4,6-tribromophenol	19.6	15.9	17.4	16.0	16.8	19.6
phenol	NA	<0.84	3.2	3.4	3.4	NA

NA = not applicable

% RECOVERY OF SURROG

2-fluorophenol	78	46	53	47
phenol-d6	62	62	66	63
2,4,6-tribromophenol	81	89	82	86

TORIES

FOR ICI

) IN SAMPLE

LP - TWO HARBORS

RESS VENT STACK

UNLOADER STACK

Run 1	Run 2	Run 3	Spike	Field Blank	Run 1	Run 2	Run 3
29.4	35.3	30.7	49.8	34.8	28.8	27.5	28.7
3.68	3.7	3.4	5.33	3.12	3.4	3.08	3.22
15.4	15.9	15.9	19.6	16.9	16.9	15.6	16.3
1.7	1.9	1.7	NA	<0.84	0.96	0.98	1.1
	2.6						

GATES

49	59	51		70	58	55	58
69	69	64		59	64	58	60
79	81	81		86	86	80	83

APPENDIX E

PROCESS INFORMATION

PRODUCTION DATA (FROM REG. REPORTS)

SAGOLA 6-25-93

DAILY TONS F.P. = 586.86 24.7 TONS/HR

RUNTIME = 23.75 HOURS

RESIN USED : MDI = 12487 LBS

528 LB/HR

1.06 %

LIQUID PHENOLIC - 100% SOLIDS

19994 LBS

842 LB/HR

1.70 %

TWO HARBORS 6-29

PRODUCTION 532,038 LBS

266 TONS 11.66 TONS/HR

RUNTIME = 22.82 HR

RESIN = 3.4% MDI (MONTHLY AVERAGE)

793 LBS/HR

PRESS VENT PROCESS DATA

11:58 AM - 12:29 PM - traverse #1

Date: 6/25/93
Run #: 2Time: 12:32 PM
Traverse #: 2PT $\approx 396^{\circ}\text{F}$ Surface Resin Type: _____ % Application: _____
Core Resin Type: _____ % Application: _____Wax Content & Type Surface: 0.68 Core: 0.5

Lbs Furnish Across Weigh Belt per hr

Surface: / / / / /Core: / / / / /Ave 29,628Ave 29,628Surface to Core Former Ratio: 50 Surface 50 CoreBoard Thickness Produced: 7/16Line Speed 89 Press Cycle (sec/1/16) 202 sec.

Line Moisture Content

Surface: _____

Ave 7.61 %

Core: _____

Ave 5.3 %Start run time: 12:32 PMStop: 1:02 PM $\therefore 30 \text{ min}$ Press load # start: 77Stop: 86Number of Press Loads During Run: 10Footage During Run: 51,073 FT² (as 3/8") both traverses

Delays During Run: _____

Total # press beds for run #2 (both traverses) = 19+

Total time _{net} = 31+30 = 61 min

Materials used during run #2 - lbs.

PE = 908 #s as 100% solid

MDI = 585 #s

Wax

ave = ~~245~~ 155 > 365 #s
surface = ~~155~~ 210

PRESS VENT PROCESS DATA

Date: 6/26/93
Run #: 1

Time: 9:16 AM
Traverse #: 2

Surface Resin Type: LS-96B * Application: 2.95
Core Resin Type: Pulvinex 1840 * Application: 1.9

Pressure 317°F

Wax Content & Type Surface: EW 58LV Core: EW 58LV
0.68% 0.5%

Lbs Furnish Across Weigh Belt per hr

Surface: _____ Ave 29,753
Core: _____ Ave 29,753

Surface to Core Former Ratio: 50 Surface 50 Core

Board Thickness Produced: 7/16 (nominal) [6.72/16]
Line Speed 89 Press Cycle (sec/1/16) 19.30

Line Moisture Content

Surface: _____ Ave 8.0
Core: _____ Ave 5.5

Start run time: _____ Stop: _____

Press load # start: _____ Stop: _____

Number of Press Loads During Run: _____

Footage During Run: _____

Delays During Run: _____

Nitro train

Loads = 19
Footage = 51,073 FT (as 3/4)
Time = 6.1 min
PF #5 = 1211 906
HDE #5 = 671 524

1,2 MP Trains

Loads = 22
Footage = 59,138 FT²
Time = 72 min
PF = 1115 1069
HDE = 720 681
HDE = 440 429

28,385?

PRESS VENT PROCESS DATA

Date: 6/26/93
Run #: 2

Time: 11:20 AM - 11:56 AM $\Rightarrow$ 36 min
12:05 PM - 12:41 PM $\Rightarrow$ 36 min
Traverse #: 2

Surface Resin Type: LS-96B $\Rightarrow$ 2.95
Core Resin Type: Pulvinex 1840 $\Rightarrow$ 1.9
Press temp $\sim$ 397°F

Wax Content & Type Surface: EW 58LV Core: EW 58LV
0.68% 0.5%

Lbs Furnish Across Weigh Belt per hr

Surface: 30,392
Core: 33,392

Surface to Core Former Ratio: 50 Surface 50 Core

Board Thickness Produced: 7/16 nominal (6.72/16)
Line Speed 89 Press Cycle (sec/1/16) 19 (30)
202 sec/press load

Line Moisture Content

Surface: 8.5
Core: 6.0

Start run time: Stop:

Press load # start: Stop:

Number of Press Loads During Run:

Footage During Run:

Delays During Run:

With train
Press loads = 18
Footage = 48,385 FT² (6 3/8)
Time = 61 min
PF #s = 906
MDI #s = 585
H₂O #s = 363

1,2 MP train
Press loads = 22
Footage = 59,137 FT² (6 3/8)
Time = 72 min
PF #s = 1069
MDI #s = 691
H₂O #s = 429

APPENDIX F

SAMPLING TRAIN CALIBRATION DATA

INTERPOLL LABORATORIES
EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job L.P. SAGOLA

Date 6-25-93

Operator G. HOVE

Module No. 3

Instructions: Operate the control module at a flow rate equal to $\dot{V}_{He}$ for 10 minutes before attaching the umbilical. Record the following data:

Bar press 28.44 in. Hg. $\tau =$.9970 $\dot{V}_{He}$ 1.74 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	1890.40		
2.5	892.34	66	65
5.0	894.28	68	66
7.5	896.20	70	67
10	898.12	73	68
	$V_m = 7.72$	$Avg(t_m) = 67.87^\circ F$	

Calculate Y_{cn} as follows:

$$Y_{cn} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{cn} = \frac{1.786}{(.9970)(7.72)} \left[\frac{(67.87 + 460)}{(28.44)} \right]^{0.5}$$

$$Y_{cn} = \underline{.996}$$

If Y_{cn} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432

INTERPOLL LABORATORIES
EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job LP / Sagola ME
 Operator D.V.H.

Date 6/25/93
 Module No. 7

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 28.44 in. Hg. $\tau =$.9983 ΔH_0 1.97 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(254.25)		
2.5	256.08	67	66
5.0	257.99	67	67
7.5	259.91	68	67
10	261.83	68	67
	$V_m = 7.58$	$Avg(t_m) = 67.125^\circ F$	

Calculate Y_{cn} as follows:

$$Y_{cn} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{cn} = \frac{1.786}{(.9983)(1.97)} \left[\frac{(67.125) + 460}{(28.44)} \right]^{0.5}$$

$$Y_{cn} = \underline{1.01}$$

If Y_{cn} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432

INTERPOLL LABORATORIES
EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job IC1 SAGOLA MICH

Date 6-25-93

Operator Q/H

Module No. 3

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press _____ in. Hg. $\tau =$ _____ ΔH_0 _____ in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(890.40)		
2.5	892.34	66	65
5.0	894.28	68	66
7.5	896.20	70	67
10	898.12	73	68
	$V_m = 7.72$	Avg(t_m) = 67.87 °F	

Calculate Y_{on} as follows:

$$Y_{on} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{on} = \frac{1.786}{(.9970)(7.72)} \left[\frac{(67.87 + 460)}{(28.44)} \right]^{0.5}$$

$$Y_{on} = \underline{.996}$$

If Y_{on} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432

Interpoll Laboratories, Inc.
(612) 786-6020

Meter Box Calibration and Usage Status

Date of Report: June 28, 1993

Meter Box No. : 3 (Rockwell Dry Test Meter Serial No. 35302)

Date of Last Calibration: June 4, 1993

Calibration Technician: B. Aschenbach

Wet Test Meter No.: American Meter AL-20

Date of Use	Report No.	Initial Meter		Final Meter		Volume/Job (cu. ft.)	Total Volume* (cu. ft.)
		Reading		Reading			
June 21, 1993	3-9191	743.90		890.02		146.12	146.12
June 25, 1993	3-9202	890.40		1163.11		272.71	418.83

* Total volume through meter since last calibration.

Interpoll Laboratories, Inc.
(612) 786-6020

Meter Box Calibration and Usage Status

Date of Report: June 28, 1993

Meter Box No. : 6 (Rockwell Dry Test Meter Serial No. 712852)

Date of Last Calibration: June 22, 1993
Calibration Technician: D. Van Hoever
Wet Test Meter No.: American Meter AL-20

Date of Use	Report No.	Initial Meter Reading	Final Meter Reading	Volume/Job (cu. ft.)	Total Volume* (cu. ft.)
June 26, 1939	3-9202	499.85	667.21	167.36	167.36

* Total volume through meter since last calibration.

Interpoll Laboratories, Inc.
(612) 786-6020

Meter Box Calibration and Usage Status

Date of Report: June 28, 1993

Meter Box No. : 7 (Rockwell Dry Test Meter Serial No. 965550)

Date of Last Calibration: June 23, 1993

Calibration Technician: E. Trowbridge

Wet Test Meter No.: American Meter AL-20

Date of Use	Report No.	Initial Meter		Final Meter		Volume/Job (cu. ft.)	Total Volume* (cu. ft.)
		Reading		Reading			
June 23, 1993	3-9197	218.30		225.20		6.90	6.90
June 25, 1993	3-9202	254.25		523.82		269.57	276.47

* Total volume through meter since last calibration.

Date 6-4-93
Bar. Press. 29.10 in. Hg

INTERNATIONAL LABORATORIES, INC.
METER CALIBRATION SHEET

9 DOLBY YD3 EPA METHOD 5

Control Module No. 5

Serial No. DTH 35302

Wet Test Water No. AL-20

Technician B. ASCHENBACH

[illegible]

Positive leak check performed by BA
 Meter was in tolerance ☒
 Meter was not in tolerance ☐; readjusted linkage
 Meter was not in tolerance ☐; changed dry test meters

Approved by Daniel K. esp Date 6/4/93

* Based on AL-20 wet test meter calibration in Nov., 1991, against Bell Prover (NBS Traceable) - Carl Poe Co.

S0102RR 11/91

6/22/93

28.98

INTERPOLL LABORATORIES, INC.
METER CALIBRATION SHEET

EPA METHOD 5

Control Module No.

Serial No, DTN

Wet Test Meter No. AL-20

Technician *D. Van Hoever*

[illegible]

Positive leak check performed by DAH
 Water was in tolerance ☒
 Water was not in tolerance ☐; readjusted linkage
 Water was not in tolerance ☐; changed dry test meters

Approved by Daniel R. Ryan Date 6/28/93

* Based on AL-20 wet test meter calibration in Nov. 1991 against Bell Prover (NBS Traceable) - Carl Poe Co.

S0102RR 11/91

Control Module No.

Serial No. DTH 05550

Bar. Press. 28.95 in. Hg

Wet Test Heter No. AL-20

Technician E. Taverne

INTERPOLL LABORATORIES, INC.
METER CALIBRATION SHEET

5 EPA METHOD 5

A vertical ruler with markings from 0 to 12 inches. The markings are in inches, with major ticks every inch and minor ticks every half-inch. The ruler is oriented vertically, with the 0 mark at the top and the 12 mark at the bottom.

Positive leak check performed by _____

Water was in tolerance

Meter was not in tolerance ☒; readjusted linkage

Heter was not in tolerance ☒; changed dry test meters

Approved by Danish Dey Date 6/25/23

* Based on AL-20 wet test meter calibration in Nov. 1991 against Bell Prover (NBS Traceable) - Carl Poe Co.

S0102RR 11/91

DIFFERENTIAL PRESSURE AND PROOF CALIBRATION CURVES

WET TEST METER

PULSATION RANGE

DIFFERENTIAL - INCHES H₂O

0.30

0.20

0.10

0

Calibrated with a 10 Ft. American Bell
Prover, Serial No. 3157. Traceable to
the Bureau of Standards. Reference No.
5249068, PI-TAPE.

AL-20 American Wet Test Meter

Serial No. p-717

Stainless Steel w/Removable Back

Calibrated w/Saturated Air

Water Temp. 74° F.

Air Temp. 74° F.

Inlet Pressure 2" H₂O Constant

Calibration Rate: 60 CFH Per/Hr.

Capacity Rate: 120 CFH Per/Hr.

Restricted Outlet for Rate Deviation

PROOF

101

100

99

CORRECT VOLUME * INDEX READING * PROOF * 100

20

40

60

80

100

120

DAVID BANKS

FLOW RATE - CUBIC FEET OF AIR PER HOUR

November, 1991

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 6-25-93
Technician: Gary Hove

Nozzle Number 27-3

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.188
2	.194
3	.190
Average:	.190

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 6-25-93

Nozzle Number 1-6

Technician: Duane Van Hoever

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.185
2	.187
3	.189
Average:	.187

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 6-26-93

Nozzle Number 3-2

Technician: Duane Van Hoever

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.130
2	.130
3	.131
Average:	.130

Interpoll Laboratories, Inc.

(612) 786-6020

Nozzle Calibration

Data Sheet

Date of Calibration: 6-26-93

Nozzle Number 3-3

Technician: Gary Hove

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.125
2	.123
3	.125
Average:	.125

Interpoll Laboratories, Inc.

Temperature Measurement Device
Calibration Sheet

Unit under test:

Vendor Beckman Industrial
Model HD 110 T Serial Number POT #18
Range -1999 °F Thermocouple Type K
Date of Calibration 4/7/93 Technician D. VAN HOOVER

Method of Calibration:

- ☐ Comparison against ASTM mercury in glass thermometer using a thermostatted and insulated aluminum block designed to provide uniform temperature. The temperature is adjusted by adjusting the voltage on the block heater cartridge.
- ☒ Omega Model CL-300 Type K Thermocouple Simulator which provides 22 precise temperature equivalent millivolt signals. The CL-300 is cold junction compensated. Calibration accuracy is $\pm 0.1\%$ of span (2100°F) ± 1 degree (for negative temperatures add ± 2 degrees. The CL-300 simulates exactly the millivoltage of a Type K thermocouple at the indicated temperature.

Desired Temp (°F) Nominal	Temperature of Standard or Simulated Temp (°F)	Response of Unit Under Test (°F)	Deviation	
			Δt (°F)	(%)
0		0	0	0
100		96	4	.71
200		199	1	.15
300		298	2	.26
400		395	5	.58
500		495	5	.52
600		597	3	.28
700		698	2	.25
800		803	3	.24
900		906	6	.38
1000		1011	11	.75
1100		1114	14	.89
1200		1220	20	1.20
1300		1321	21	1.19
1400		1426	26	1.39
1500		1524	24	1.22
1600		1625	25	1.21
1700		1721	21	.97
1800		1819	19	.84
1900		1912	12	.51
2000				
2100				
		Averages:		.68

OF = off scale response by unit under test (°F)
% dev = $100 \Delta t / (460 + t)$

- ☒ Unit in tolerance
☐ Unit was not in tolerance; recalibrated - See new calibration sheet.

Interpoll Laboratories, Inc.

Temperature Measurement Device
Calibration Sheet

Unit under test:

Vendor OMEGA
Model OMEGA SIMULATOR Serial Number 29
Range 0 - 2100 °F Thermocouple Type OMEGA
Date of Calibration 1-4-93 Technician QA

Method of Calibration:

- ☐ Comparison against ASTM mercury in glass thermometer using a thermostatted and insulated aluminum block designed to provide uniform temperature. The temperature is adjusted by adjusting the voltage on the block heater cartridge.
- ☐ Omega Model CL-300 Type K Thermocouple Simulator which provides 22 precise temperature equivalent millivolt signals. The CL-300 is cold junction compensated. Calibration accuracy is $\pm 0.1\%$ of span (2100 °F) ± 1 degree (for negative temperatures add ± 2 degrees. The CL-300 simulates exactly the millivoltage of a Type K thermocouple at the indicated temperature.

Desired Temp (°F) Nominal	Temperature of Standard or Simulated Temp (°F)	Response of Unit Under Test (°F)	Deviation	
			Δt (°F)	(%)
0				
100	100	98.1	1.9	1.33
200	200	200.3	.3	.145
300	300	298.3	1.7	.23
400	400	398.0	2.0	.23
500	500	499.3	.7	.07
600	600	599.3	.7	.066
700	700	699.3	.7	.060
800	800	801.1	1.1	.087
900	900	899.3	.7	.05
1000	1000	1000.1	.1	.007
1100	1100	1099.5	.5	.032
1200	1200	1201.5	1.5	.090
1300	1300	1299.2	.8	.045
1400	1400	1402.2	2.2	.118
1500	1500	1498.8	1.2	.06
1600	1600	1601.3	1.3	.063
1700	1700	1698.8	1.2	.056
1800	1800	1800	0	0
1900	1900	1898.2	1.2	.051
2000	2000	1999.0	.4	.016
2100	2100	2098.0	2.0	.078
		Averages:		

OF = off scale response by unit under test (°F)
% dev = $100 \Delta t / (460 + t)$

- ☒ Unit in tolerance
☐ Unit was not in tolerance; recalibrated - See new calibration sheet.

S-433

S-Type Pitot Tube Inspection SheetPitot No. 23-6Pitot tube dimensions:

1. External tubing diameter (D_t) .316 IN.
2. Base to Side A opening plane (P_A) .460 IN.
3. Base to Side B opening plane (P_B) .461 IN.

Alignment:

4. $\alpha_1 < 10^\circ$ 1
5. $\alpha_2 < 10^\circ$ 1
6. $B_1 < 50$ 1
7. $B_2 < 50$ 2
8. $Z < .125"$.02
9. $W < .0625"$.02

Distance from Pitot to Probe Components:

10. Pitot to 0.500 IN. nozzle .750 IN.
11. Pitot to probe sheath 3.00 IN.
12. Pitot to thermocouple (parallel to probe) 3.00 IN.
13. Pitot to thermocouple (perpendicular to probe) .760 IN.

☒ Meets all EPA design criteria thus $C_p = 0.84$ ☐ Does not meet EPA design criteria - thus calibrate in wind tunnel
 $C_p =$ _____

Date of Inspection:

Inspected by:

4-7-93[Signature]

CFR Title 40 Part 60 Appendix A Method 2

S-Type Pitot Tube Inspection Sheet

Pitot Tube No. 27-6

Pitot tube dimensions:

1. External tubing diameter (D) .316 IN.
2. Base to Side A opening plane (P_A) .460 IN.
3. Base to Side B opening plane (P_B) .462 IN.

Alignment:

4. α_1 < 10° 0
5. α_2 < 10° 0
6. B₁ < 5° 0
7. B₂ < 5° 0
8. Z < .125" 0
9. W < .0625" .02

Distance from Pitot to Probe Components:

10. Pitot to 0.500 IN. nozzle .750 IN.
11. Pitot to probe sheath 3.0 IN.
12. Pitot to thermocouple (parallel to probe) 3.0 IN.
13. Pitot to thermocouple (perpendicular to probe) .760 IN.

- ☒ Meets all EPA design criteria thus C_p = 0.84
☐ Does not meet EPA design criteria - thus calibrate in wind tunnel.
C_p = _____

Date of Inspection:

4-8-93

Inspected by:

G. J. [Signature]

INTERPOLL LABORATORIES

(612)786-6020

Stack Sampling Department - QA
Aneroid Barometer Calibration Sheet

Date 1-4-93
Technician B. HOUF
Mercury Column Barometer No. _____
Aneroid Barometer No. 636235

Actual Mercury Barometer Read	Ambient Temp.	Temperature Correction Factor	Adjusted Mercury Barometer Read	Initial Aneroid Barometer Read	Difference (P _{ba} -P _{bm})
29.27	73	-.114	29.155	29.30	.185

Has this barometer shown any consistent problems with calibration? Yes/No. If yes, explain. NO

Has problem been alleviated? Yes/No. How? _____

I ADJUSTED THE
ANEROID TO
MATCH THE Hg

***Note**

Aneroid barometers will be calibrated periodically against a mercury column barometer. The aneroid barometer to be calibrated should be placed in close proximity to the mercury barometer and left to equilibrate for 20-30 minutes before calibrating. Aneroid barometer will be calibrated to the adjusted mercury barometer readings.

S-312

INTERPOLL LABORATORIES

(612)786-6020

Stack Sampling Department - QA
Aneroid Barometer Calibration Sheet

Date 4/7/93
Technician D. VAN HOEVER
Mercury Column Barometer No. _____
Aneroid Barometer No. 861216

Actual Mercury Barometer Read	Ambient Temp.	Temperature Correction Factor	Adjusted Mercury Barometer Read	Initial Aneroid Barometer Read	Difference (Pba-Pbm)
29.11	72	.110	29.00	28.94	.06

Has this barometer shown any consistent problems with calibration? Yes/No. If
yes, explain. NO

Has problem been alleviated? Yes/No. How? _____

***Note**

Aneroid barometers will be calibrated periodically against a mercury column barometer. The aneroid barometer to be calibrated should be placed in close proximity to the mercury barometer and left to equilibrate for 20-30 minutes before calibrating. Aneroid barometer will be calibrated to the adjusted mercury barometer readings.

S-312

INTERPOLL LABORATORIES
EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job ICF-LP-TWO HARBOURS
 Operator GH

Date 6-25-93
 Module No. 7

Instructions: Operate the control module at a flow rate equal to $\dot{V}_{He}$ for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.05 in. Hg. $\tau =$.9983 $\dot{V}_{He}$ 1.97 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	524.60		
2.5	526.55	90	88
5.0	528.50	92	87
7.5	530.40	94	88
10	532.29	95	89
	$V_m = 7.69$	$Avg(t_m) = 90.375^\circ F$	

Calculate Y_{cn} as follows:

$$Y_{cn} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{cn} = \frac{1.786}{(.9983)(7.69)} \left[\frac{(90.375 + 460)}{(29.05)} \right]^{0.5}$$

$$Y_{cn} = \underline{1.012}$$

If Y_{cn} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432

INTERPOLL LABORATORIES
EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job ICI TWO HARBORS
 Operator G HOVE

Date 6-29-93
 Module No. 3

Instructions: Operate the control module at a flow rate equal to ΔH_e for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.05 in. Hg. $\tau =$.9970 ΔH_e 1.74 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(163.8)		
2.5	165.88	87	84
5.0	167.72	88	84
7.5	169.70	88	85
10	171.51	92	86
	$V_m = 7.61$	$Avg(t_m) = 86.75^\circ F$	

Calculate Y_{cn} as follows:

$$Y_{cn} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{cn} = \frac{1.786}{(.9970)(7.61)} \left[\frac{(86.75) + 460}{(29.05)} \right]^{0.5}$$

$$Y_{cn} = \underline{1.021}$$

If Y_{cn} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432

INTERPOLL LABORATORIES
EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job AC1
 Operator DVH

Date 6-30-93
 Module No. 6

Instructions: Operate the control module at a flow rate equal to ΔH_0 for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.15 in. Hg. $\tau =$.9996 ΔH_0 1.77 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(668.10)		
2.5	670.26	83	82
5.0	672.03	85	82
7.5	674.05	85	83
10	675.84	86	83
	$V_m = 7.74$	Avg(t_m) = 83.6 °F	

Calculate Y_{cn} as follows:

$$Y_{cn} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{cn} = \frac{1.786}{(.9996)(7.74)} \left[\frac{(83.6) + 460}{(29.15)} \right]^{0.5}$$

$$Y_{cn} = \underline{.9968}$$

If Y_{cn} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432

INTERPOLL LABORATORIES
EPA Method 5 Gas Metering System
Quality Control Check Data Sheet

Job ICI TWO HARBORS

Date 6-29-93

Operator C HOVE

Module No. 3

Instructions: Operate the control module at a flow rate equal to $\dot{V}_{He}$ for 10 minutes before attaching the umbilical. Record the following data:

Bar press 29.05 in. Hg. $\tau =$ 9970 $\dot{V}_{He}$ 1.74 in. W.C.

Time (min)	Volume (CF)	Meter Temp. (°F)	
		Inlet	Outlet
	(163.90)		
2.5	165.88	87	84
5.0	167.72	88	84
7.5	169.70	88	85
10	171.51	92	86
	$V_m = 7.61$	Avg(t_m) = <u>86.75</u> °F	

Calculate Y_{cn} as follows:

$$Y_{cn} = \frac{1.786}{\tau V_m} \left[\frac{(t_m + 460)}{P_b} \right]^{0.5}$$

$$Y_{cn} = \frac{1.786}{(9970)(7.61)} \left[\frac{(86.75) + 460}{29.05} \right]^{0.5}$$

$$Y_{cn} = \underline{1.021}$$

If Y_{cn} is not within the range of 0.97 to 1.03, "the volume metering system should be investigated before beginning."

CFR Title 40, Part 60, Appendix A, Method 5, Section 4.4.1

S-432

Interpoll Laboratories, Inc.
(612) 786-6020

Meter Box Calibration and Usage Status

Date of Report: July 8, 1993

Meter Box No. : 3 (Rockwell Dry Test Meter Serial No. 35302)

Date of Last Calibration: June 4, 1993

Calibration Technician: B. Aschenbach

Wet Test Meter No.: American Meter AL-20

Date of Use	Report No.	Initial Meter Reading	Final Meter Reading	Volume/Job (cu. ft.)	Total Volume* (cu. ft.)
June 21, 1993	3-9191	743.90	890.02	146.12	146.12
June 25, 1993	3-9202	890.40	1163.11	272.71	418.83
June 29, 1993	3-9289	1163.90	1578.59	414.69	833.52

* Total volume through meter since last calibration.

Interpoll Laboratories, Inc.
(612) 786-6020

Meter Box Calibration and Usage Status

Date of Report: July 8, 1993

Meter Box No. : 6 (Rockwell Dry Test Meter Serial No. 712852)

Date of Last Calibration: June 22, 1993

Calibration Technician: D. Van Hoever

Wet Test Meter No.: American Meter AL-20

Date of Use	Report No.	Initial Meter Reading	Final Meter Reading	Volume/Job (cu. ft.)	Total Volume* (cu. ft.)
June 26, 1939	3-9202	499.85	667.21	167.36	167.36
June 30, 1993	3-9289	668.10	916.09	247.99	415.35

* Total volume through meter since last calibration.

Interpoll Laboratories, Inc.
(612) 786-6020

Meter Box Calibration and Usage Status

Date of Report: July 8, 1993

Meter Box No. : 7 (Rockwell Dry Test Meter Serial No. 965550)

Date of Last Calibration: June 23, 1993

Calibration Technician: E. Trowbridge

Wet Test Meter No.: American Meter AL-20

Date of Use	Report No.	Initial Meter		Final Meter		Volume/Job (cu. ft.)	Total Volume* (cu. ft.)
		Reading		Reading			
June 23, 1993	3-9197	218.30		225.20		6.90	6.90
June 25, 1993	3-9202	254.25		523.82		269.57	276.47
June 25, 1993	3-9289	524.60		957.44		432.84	709.31

* Total volume through meter since last calibration.

Date 6-4-93
Bar. Press. 29.10 in. Hg

INTERPOLL LABORATORIES, INC.
METER CALIBRATION SHEET

9 DOKLEH V43

Control Module No. 3

Serial No. DTM 35302

Wet Test Water No. AL-20

Technician B. ASCHENBACH

[illegible]

Positive leak check performed by BA
 Meter was in tolerance ☒
 Meter was not in tolerance ☐; readjusted linkage
 Meter was not in tolerance ☐; changed dry test meters

Approved by Daniel K. Esp. Date 6/4/93

* Based on AL-20 wet test meter calibration in Nov. 1991, against Bell Prover (NBS Traceable) - Carl Poe Co.

16/11 11/91

6/22/93

2808

EPA METHOD 5

2

712852

AL-20

Niether

Positive leak check performed by DAH
 Meter was in tolerance ☒
 Meter was not in tolerance ☐: readjusted linkage
 Meter was not in tolerance ☐: changed dry test meters

Approved by Daniel R. Ryan Date 6/28/93

* Based on AL-20 wet test meter calibration in Nov. 1991 against Bell Prover (NBS Traceable) - Carl Poe Co

S0102RR 11/91

Bar. Press. 28.95 in. Hg

INTERPOL LABORATORIES, INC.
METER CALIBRATION SHEET
EPA METHOD 5

Control Module No.

Serial No. DTH

Wet Test Meter No. AL-20

Technician

ΔH (In. WC)		Gas Volume Test Meter (ft ³)	Cal. Index ♦ (%)	Diff. Met. Test Meter ΔP _w (In. WC)	Gas Volume Dry test meter (ft ³)		Gas temperatures			Time θ (min/sec)	Meter Coeff.	Orifice Const.	C _f
nominal	actual				V _{df}	V _{dfr}	Met Test t _w (°F)	Dry Test					
							t _{dg} (°F)	t _{d0} (°F)			Y	ΔH ₀	
0.5	1.5	2	99.85	0.01	237.000	239.035	72	80	76	5/05	.9911	1.87	
1.2	1.2	3	99.91	0.025	233.000	236.050	72	82	76	5/05	.9925	1.98	
2.0	2.0	3	99.93	0.055	239.500	242.550	72	86	79	3/58	.9971	2.00	
3.3	3.3	5	100.00	0.09	243.000	248.060	72	91	81	5/09	1.0054	1.98	
4.7	4.7	5	100.02	0.12	249.000	254.070	72	95	83	7/22	1.0055	2.02	

Positive leak check performed by 221
 Water was in tolerance ☒
 Meter was not in tolerance ☐; readjust linkage
 Meter was not in tolerance ☐; changed dry test meters

Approved by Daniff Dep Date 6/25/93


* Based on AL-20 wet test meter calibration in Nov. 1991 against Bell Prover (NBS Traceable) - Carl Poe Co

SN102RR 11/91

WET TEST METER

PULSATION RANGE

DIFFERENTIAL - INCHES H2O



Calibrated with a 10 Ft. American Bell Prover, Serial No. 3157. Traceable to the Bureau of Standards. Reference No. 5249068, PI-TAPE.

AL-20 American Wet Test Meter

Serial No. P-717

Stainless Steel w/Removable Back

Calibrated w/Saturated Air

Water Temp. 74° F.

Air Temp. 74° F.

Inlet Pressure 2" H2O Constant


Calibration Rate: 60 CFH Per/Hr.

Capacity Rate: 120 CFH Per/Hr.

Restricted Outlet for Rate Deviation

PROOF

PROOF %



CORRECT VOLUME = INDEX READING x PROOF + 100

FLOW RATE - CUBIC FEET OF AIR PER HOUR

DAVID BANKS

November, 1999

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 6-29-93

Nozzle Number 6-4

Technician: Duane Van Hoever

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.251
2	.249
3	.252
Average:	.251

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 6-29-93
Technician: Gary Hove

Nozzle Number 23-4

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.251
2	.250
3	.249
Average:	.250

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 6-30-93

Nozzle Number 27-3

Technician: Gary Hove

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.183
2	.182
3	.182
Average:	.182

Interpoll Laboratories, Inc.
(612) 786-6020

Nozzle Calibration
Data Sheet

Date of Calibration: 7-3-93

Nozzle Number 7-3

Technician: Duane Van Hoever

The nozzle is rotated in 60 degree increments and the diameter at each point is measured to the nearest 0.001 inch. The observed readings and average are shown below.

Position	Diameter (inches)
1	.186
2	.185
3	.185
Average:	.185

Interpoll Laboratories, Inc.

Temperature Measurement Device
Calibration Sheet

Unit under test:

Vendor Beckman Industrial
Model HD 110 T Serial Number PDT #18
Range -1999 °F Thermocouple Type K
Date of Calibration 4/7/93 Technician D. VAN HOEVER

Method of Calibration:

- ☐ Comparison against ASTM mercury in glass thermometer using a thermostatted and insulated aluminum block designed to provide uniform temperature. The temperature is adjusted by adjusting the voltage on the block heater cartridge.
- ☒ Omega Model CL-300 Type K Thermocouple Simulator which provides 22 precise temperature equivalent millivolt signals. The CL-300 is cold junction compensated. Calibration accuracy is $\pm 0.1\%$ of span (2100 °F) ± 1 degree (for negative temperatures add ± 2 degrees. The CL-300 simulates exactly the millivoltage of a Type K thermocouple at the indicated temperature.

Desired Temp (°F) Nominal	Temperature of Standard or Simulated Temp (°F)	Response of Unit Under Test (°F)	Deviation	
			Δt (°F)	(%)
0		0	0	0
100		96	4	.71
200		199	1	.15
300		298	2	.26
400		395	5	.58
500		495	5	.52
600		597	3	.28
700		698	2	.25
800		803	3	.24
900		906	6	.38
1000		1011	11	.75
1100		1114	14	.89
1200		1220	20	1.20
1300		1321	21	1.19
1400		1426	26	1.39
1500		1524	24	1.22
1600		1625	25	1.21
1700		1721	21	.97
1800		1819	19	.84
1900		1912	12	.51
2000				
2100				
		Averages:		.68

OF = off scale response by unit under test (°F)
% dev = $100 \Delta t / (460 + t)$

- ☒ Unit in tolerance
☐ Unit was not in tolerance; recalibrated - See new calibration sheet.

S-Type Pitot Tube Inspection SheetPitot No. 23-5Pitot tube dimensions:

1. External tubing diameter (D_t) .316 IN.
2. Base to Side A opening plane (P_A) .455 IN.
3. Base to Side B opening plane (P_B) .460 IN.

Alignment:

4. $\alpha_1 < 10^\circ$ 1
5. $\alpha_2 < 10^\circ$ 1
6. $B_1 < 50$ 2
7. $B_2 < 50$ 2
8. $Z < .125"$.04
9. $W < .0625"$.02

Distance from Pitot to Probe Components:

10. Pitot to 0.500 IN. nozzle .760 IN.
11. Pitot to probe sheath 3.00 IN.
12. Pitot to thermocouple (parallel to probe) 3.00 IN.
13. Pitot to thermocouple (perpendicular to probe) .750 IN.

☒ Meets all EPA design criteria thus $C_p = 0.84$
☐ Does not meet EPA design criteria - thus calibrate in wind tunnel
 $C_p =$ _____

Date of Inspection:

4-7-93

Inspected by:

[Signature]

CFR Title 40 Part 60 Appendix A Method 2

S-Type Pitot Tube Inspection SheetPitot No. 23-6Pitot tube dimensions:

1. External tubing diameter (D_t) .316 IN.
2. Base to Side A opening plane (P_A) .460 IN.
3. Base to Side B opening plane (P_B) .461 IN.

Alignment:

4. $\alpha_1 < 10^\circ$ 1
5. $\alpha_2 < 10^\circ$ 1
6. $B_1 < 5^\circ$ 1
7. $B_2 < 5^\circ$ 2
8. $Z < .125"$.02
9. $W < .0625"$.02

Distance from Pitot to Probe Components:

10. Pitot to 0.500 IN. nozzle .950 IN.
11. Pitot to probe sheath 3.00 IN.
12. Pitot to thermocouple (parallel to probe) 3.00 IN.
13. Pitot to thermocouple (perpendicular to probe) .760 IN.

Meets all EPA design criteria thus $C_p = 0.84$ Does not meet EPA design criteria - thus calibrate in wind tunnel
 $C_p =$ _____

Date of Inspection:

4-7-93

Inspected by:

[Signature]

CFR Title 40 Part 60 Appendix A Method 2

INTERPOLL LABORATORIES

(612)786-6020

Stack Sampling Department - QA
Aneroid Barometer Calibration Sheet

Date 4/7/93
Technician D. VAN HOEVER
Mercury Column Barometer No. _____
Aneroid Barometer No. 861216

Actual Mercury Barometer Read	Ambient Temp.	Temperature Correction Factor	Adjusted Mercury Barometer Read	Initial Aneroid Barometer Read	Difference (P _{ba} -P _{bm})
29.11	72	.110	29.00	28.94	.06

Has this barometer shown any consistent problems with calibration? Yes/No. If
yes, explain. NO

Has problem been alleviated? Yes/No. How? _____

*Note

Aneroid barometers will be calibrated periodically against a mercury column barometer. The aneroid barometer to be calibrated should be placed in close proximity to the mercury barometer and left to equilibrate for 20-30 minutes before calibrating. Aneroid barometer will be calibrated to the adjusted mercury barometer readings.

S-312

10/10/10

10/10/10

10/10/10

10/10/10