

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

Commonwealth of Pennsylvania
Environmental Resources
September 6, 1990

Subject: Stack Test Review

To: Data File
Latrobe Construction Company
Legionier Township, Westmoreland County

From: Timothy R. Brooks *TRB*
Air Quality Program Specialist
Division of Technical Services and Monitoring
Bureau of Air Quality Control

Through: Chief, Source Testing and Monitoring Section *Wm*

The Latrobe Construction Company operates their No. 3 Barber-Green Batch Asphalt Plant at the above location. The plant is rated at 300 tons per hour and emissions are controlled by a Griffin Environmental BE-101X Fabric Filter.

Hemion Associates, Inc. conducted three particulate tests in the baghouse outlet. The tests were conducted in accordance with Chapter 139 of the Commonwealth of Pennsylvania, Department of Environmental Resources' Rules and Regulations and are acceptable to the Department.

The following information was extracted from the test report:

Test Date	04/25/90	04/25/90	04/26/90
Run No.	1	2	3
Volumetric Flow Rate (dscfm)	26,000	26,400	25,000
Average Production Rate (T/hr) ⁺	264	264	264
Particulate Concentration (g/dscf)	0.004	0.003	0.005
Allowable Concentration (g/dscf) [*]	0.04	0.04	0.04
Particulate Emission Rate (lbs/hr)	0.94	0.71	1.01

- + Combination of ID#2 Binder and ID #2 Top
- * NSPS Allowable

cc: File No. 65-303-012
Keith Gratzmiller, Greensburg District Office
EPA/RSLL
Doug Leshner
Reading File

TRB:taw

HEMEON ASSOCIATES INC.

Air Pollution Consulting Engineers
125 Thirty-Ninth Street
Pittsburgh, PA 15201

(412) 683-2100

FAX (412) 683-4188

PARTICULATE EMISSION TESTING
LATROBE CONSTRUCTION COMPANY
ASPHALT PLANT
LIGONIER, PA

Report to:
Mr. Merle Rahl
Latrobe Construction Co.
P.O. Box 150
Latrobe, PA 15650

Report by:
Mr. Christopher J. Michael
Project Manager
Hemeon Associates, Inc.
125 Thirty-ninth Street
Pittsburgh, PA 15201

May 3, 1990

My file

9/14

TABLE OF CONTENTS

- 1.0 Introduction
- 2.0 Summary of Results
- 3.0 Test Program & Process Description

APPENDICES

- A. Formulas and Calculations
- B. Test Methodology
- C. Field Data Sheets
- D. Laboratory Data
- E. Process Data

1.0 INTRODUCTION

On April 25, and 26, 1990, particulate emission testing was conducted on the asphalt plant baghouse at Latrobe Construction Company's plant in Ligonier, PA. The test program was authorized by Mr. Merle Rahl Latrobe Construction Company. Testing was performed by Mr. John C. Parry and Mr. Russell Lantz of Hameon Associates, Inc. Process Coordination was provided by Latrobe Construction Company's personnel. Testing was observed by the P.A. D.E.R. Bureau of Air Pollution Control.

PURPOSE

The purpose of this test program was to determine whether particulate matter emissions from the baghouse exit were in compliance with the Environmental Protection Agency and Department of Environmental Resources emission regulations during normal operation.

2.0 SUMMARY OF RESULTS

TABLE NO. 1 below presents the particulate emission results from testing the baghouse outlet at Latrobe Construction Company's plant in Ligonier, PA.

TABLE NO. 1

Particulate Emission Results

Date 1989	Sample Location	Test No.	Particulate Emissions			
			a gr/dscf	measured lb/hr b	allowable lb/hr b	
4/25	Baghouse Outlet	1	0.004	0.936	16.776	
4/25	Baghouse Outlet	2	0.003	0.712	16.776	
4/26	Baghouse Outlet	3	0.005	1.013	16.776	

a - grains per dry standard cubic foot

b - pounds per hour

According to regulations of the P.A.D.E.R., the allowable emission rate is based on . Based on the test results, the baghouse is in compliance with DER regulations for particulate emissions.

TABLE NO. 2 is a summary of the flue gas parameters and particulate results.

TABLE NO. 3 is a summary of allowable emission rate calculations.

Table No. 2
SUMMARY OF FLUE GAS PARAMETERS

LATCOFLO

TEST NO.	1	2	3
TEST DATA			
Test Date	4/25/90	4/25/90	4/26/90
Static Pres., in. WC	-.21	-.21	-.26
Pitot Readings, rms	.734	.759	.673
Gas Temp., deg. F	191	192	191
Flowmeter Ave., "WC	2.45	2.75	2.34
Gasmeter Av. Temp., deg. F	87	95	99
Sampling Time, min.	72	72	72
Sample Vol., acf	59.962	61.497	59.64
Barom. Pres., in. Hg	28.91	28.87	28.76
Condensate, ml	86	96	72
Desica. Gain, g	14.7	12.5	14.8
GAS COMPOSITION			
CO ₂ , mole fraction	.015	.015	.015
O ₂ , mole fraction	.19	.19	.19
N ₂ , mole fraction	.795	.795	.795
AREAS			
Stack Area, sq. ft.	10.875	10.875	10.875
Nozzle Diameter, in.	.25	.25	.25
Nozz. Area, sq. ft.	.0003409	.0003409	.0003409
CALCULATED RESULTS			
Gas, Dry mol. wt.	29.01	29	29
Gas Dens., lb/cu ft	.075	.075	.075
Sample vol., dry scf	56.2	56.7	54.4
Gas samp., dry lbs	4.22	4.25	4.08
Water in Samp., lbs	.222	.239	.191
Water Cont. lbs/lb	.053	.056	.047
Water, volume %	7.8	8.3	7
Water, weight %	5	5.3	4.5
Gas Mol. Wt., Actual	28.15	28.09	28.23
Gas Dens. in stack	.0572	.057	.0571
Stack Gas, acfm	35900	36600	34400
Stack Gas, lbs/hr	123200	125200	117900
St. Gas, lbs/hr dry	117000	118600	112600
St. Gas, scfm, dry	26000	26360	25020
Percent Isokinetic	95.8	95.3	94.3

3.0 TEST PROGRAM & PROCESS DESCRIPTION

Test Program & Process Description

The plant is a bituminous Barber Green batch plant. The exhaust gases from the dryer are passed through a model JA 960 DA continuous duty jet-airo pulse jet baghouse dust collector, consisting of the following: 960 bags 4 inch diameter by 99 inches long, made of 16 oz. polyester felt with galvanized cages. Cloth area 8,768 square feet. The rated capacity of the plant is 100 ton per hour. The actual operating rate is not expected to exceed 264 T.P.H. The operating rate during stack test was 264 T.P.H. The two types of aggregate mixes were dried during the emission test. Mix 1 with #57 stone 37.2%, #8 stone 29.3%, shot stone 4.6%, with sand 24.3%. Mix 2 with #8 stone 31.8%, shot stone 15.3%, sand 46.5%, oil 6.5%. Cold feed settings: sand 50%, #8 1B 40%, #57 2B 70% and during tests the magnehelic pressure was 3.0 in. H₂O.


Sampling was conducted at the baghouse outlet as shown in Figure No. 1. A total of 24 sample points were used to traverse the rectangular exit duct. There were three sample ports located equidistant on one side. Eight points were sampled in each port for 3 minutes a point for a total test time of 24 minutes for all tests.

Sampling Procedure

After selecting the sampling site and the minimum number of traverse points, the stack pressure, temperature, moisture and range of velocity head were measured according to the procedures described in the "Federal Register."

Approximately 200 grams of silica gel were weighed in a sealed impinger prior to each test. Glass fiber filters (4 inch diameter) were desiccated for at least 24 hours and weighed to the nearest 0.1 mg on an analytical balance. One-hundred ml of distilled water was placed in each of the first two impingers; the third impinger was initially empty; and the impinger containing the silica gel was placed next in series. The sampling train was leak-checked at the sampling site prior to each test run by plugging the inlet to the nozzle and pulling a 15 inch Hg vacuum, and at the conclusion of the test by plugging the inlet to the nozzle and pulling a vacuum equal to the highest vacuum reached during the test run.

A more detailed description of sampling and analytical procedure is given in Appendix B.



3 Sample Ports

8 Points Per Port

24 Total Points

Point Number	Point Location
1	4-1/8"
2	12-1/4"
3	20-3/8"
4	28-1/2"
5	36-3/4"
6	44-7/8"
7	53"
8	61-1/8"

Figure No. 1
Asphalt Plant No. 3 Stack
Latrobe Construction Co.
Ligonier, PA

Hemench Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

A. Formulas and Calculations

Hemcon Associates, Inc.

NOMENCLATURE

A_s "	Cross-sectional area of stack, (ft ²).
A_n "	Cross-sectional area of nozzle, (ft ²).
c_p "	Concentration of particulate matter in stack gas, dry basis corrected to standard conditions, (g/dscf).
C_p "	Pitot tube coefficient.
D_g "	Flue gas density (lbs. per scf).
D_{gs} "	Flue gas density at stack conditions (lbs/ft ³).
E_r "	Emission rate (lbs/hr).
GVW "	Gas sample volume weight (lbs).
H_{fg} "	Humidity of flue gas (lbs of H ₂ O/lb. dry gas).
I "	Percent of isokinetic sampling (%).
m_m "	Total amount of particulate matter collected, g.
P_{bar} "	Barometric pressure at the sampling site, (in. Hg).
P_a "	Absolute stack gas pressure, (in. Hg).
P_{std} "	Standard absolute pressure, (29.92 in. Hg).
P_s "	Static pressure of stack.
SE "	Stack volumetric flow (ACFM).
Swf "	Stack weight flow at stack conditions (lbs./hr).
$Swfd$ "	Stack weight flow dry basis (lbs./hr).
T_m "	Absolute average dry gas meter temperature (°R).
T_g "	Absolute average stack gas temperature (°R).
T_{std} "	Standard absolute temperature, (528°R).

V_m " Volume of gas sample as measured by dry gas meter, (dcf).

$V_m(\text{std})$ Volume of gas sample measured by the dry gas meter, corrected to standard conditions, (dcf).

W_{fg} " Water in flue gas sample (lbs. of H_2O).

W_p " Weight of particulate (10^{-3} lbs.).

W_p/g " Pounds of particulate per 1000 lbs. of gas (lbs. particulate/1000 lbs. gas).

Y " Dry gas meter calibration factor.

ΔH " Average pressure differential across the orifice meter (in. H_2O).

θ " Total sampling time, min.

Hemcon Associates, Inc.

Example Calculations for Particulate Emissions

1. Volume of dry gas sampled corrected to standard conditions. Note: V_m must be corrected for leakage if any leakage rates exceed L_a .

$$V_{mstd} = 17.65 \times V_m \times Y \left[\frac{P}{\text{bar}} + \frac{\Delta H}{13.6} \right] \frac{1}{T_m}$$

2. Weight of water in flue gas sample (lbs.).

$$Wfg = \frac{(\text{ml condensate} + \text{grams desic. gain})}{453.6}$$

3. Water vapor concentration (%).

$$Wvc = \frac{(21.5 \times Wfg \times 100)}{(21.5 \times Wfg + Vmstd)}$$

4. Dry molecular weight of stack gas.

$$M_d = 0.44 (\% \text{ CO}_2) + 0.32 (\% \text{ O}_2) + 0.28 (\% \text{ N}_2 + \% \text{ CO})$$

5. Stack gas density (lbs./dscf).

$$Dg = \left(\frac{M_d}{29} \right) \times .0753$$

6. Stack gas density at stack conditions (lbs./ft.³).

$$Dgs = .0753 \times \left(\frac{M_d}{29} \right) \times \frac{P_s}{29.92 \text{ in.Hg}} + \frac{13.6}{T_s} \times \left(\frac{528}{T_s} \right)$$

7. Molecular weight of stack gas.

$$M_s = M_d (1 - Wvc) + 18 Wvc$$

8. Stack velocity at stack conditions, fps.

$$V_s = 85.49 C_p \sqrt{\Delta P} \text{ avg. } \sqrt{\frac{T_s}{P_s M_s}}$$

9. Actual volumetric flow rate (ACFM).

$$Sf = \frac{1096.7 \times Cp \times \sqrt{\Delta P(RMS)} \times As}{\sqrt{Dgs}}$$

10. Stack weight flow at stack conditions (lbs./hr.).

$$Swf = Sf \times Dgs \times 60$$

11. Gas sample weight (lbs.).

$$Gsw = Vmstd \times Dg$$

12. Humidity of flue gas (lbs. of H₂O/lbs. dry gas).

$$Hfg = \left(\frac{Wfg}{Gsw} \right)$$

13. Stack weight flow on dry basis (lbs./hr.).

$$Swfd = \left(\frac{Swf}{1 + Hfg} \right)$$

14. Stack volumetric flow at standard conditions (SCFM).

$$Sfs = \left(\frac{Swfd}{60 \times Dg} \right)$$

15. Isokinetic sampling rate (%).

$$I = \left(\frac{Vmstd \times As \times 100}{Sfs \times An \times 0} \right)$$

16. Weight of particulate (10⁻³ lbs.).

$$Wp = (M_m \text{ wt. grams}) \times 2.2046$$

17. Pounds of particulate per 1000 lbs. of gas (lbs. part./1000 lbs. gas).

$$(Wp/g) = \left(\frac{Wp}{GVw} \right)$$

18. Concentration of particulate in stack, dry basis corrected to standard conditions (g/dscf).

$$C_d = \left(\frac{7}{V_m \text{ std}} \right) \times W_p$$

19. Particulate emission rate (lbs./hr.)

$$E_r = S_{wfd} \times (W_p/g) \times 10^{-3}$$

Homon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

TABLE NO. 3

CALCULATION OF ALLOWABLE EMISSION RATE

Allowable Emission Formula

$A = 0.76E^{0.42}$, where:
A = Allowable emissions in pounds per hour
E = Emission index = $F \times W$ tons per hour
F = Process factor in pounds per unit, and
W = Production or charging rate in units per hour

Allowable Emission Rate, $A = .76 (W \times F)^{0.42}$

Test No.1 & No.2

Date: April 26, 1990
Average ~~Production~~ Rate: 264 tons/hr.

Allowable Emission Rate, $A = .76 (W \times F)^{0.42}$
 $A = .76 (264 \times 6)^{0.42}$
 $A = 16.776 \text{ lbs/hr}$

Test No.3

Date: April 27, 1990
Average Production Rate: 264 tons/hr.

Allowable Emission Rate, $A = .76 (W \times F)^{0.42}$
 $A = .76 (264 \times 6)^{0.42}$
 $A = 16.776 \text{ lbs/hr}$

Not Feed? - should be dry aggregate feed

STACK GAS FLOW AND PARTICULATE EMISSIONS

Test No.	1	2	3
Date	4/25/90	4/25/90	4/26/90
Overall sampling period	7:22 AM 8:54 AM	9:57 AM 11:21 AM	9:59 AM 11:45 AM
Net sampling time, min.	72	72	72

STACK GAS

Temperature, deg. F	191	192	191
Flow rate:			
Actual lbs/hr	123200	125200	117900
Dry basis lbs/hr	117000	118600	112600
Acfm	35900	36600	34400
Scfm, dry	26000	26360	25020

PARTICULATE MATTER

Concentration			
Dry Basis:			
Lbs dust per 1000 lb gas	.008	.006	.009
Grains per scf	.004	.003	.005
DUST EMISSION RATE, lbs/hr	.936	.712	1.013

Hemdon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

B. Test Methodology

Hemcon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

DETERMINATION OF PARTICULATE EMISSIONS EPA METHOD 5

The following method was used in this test program. Sampling procedures follow those described in Method 5 of the Federal Register and Department of Environmental Resources.

SAMPLING APPARATUS

The particulate sampling train used in these tests at the exit stack met certain design specifications established by the Federal EPA and was assembled by Hemcon personnel. It consisted of:

Nozzle - Stainless steel (316) with sharp, tapered leading edge and accurately measured round opening.

Probe - Glass lined with a heating system capable of maintaining a minimum gas temperature of 250°F at the exit end during sampling.

Pitot Tube - Type S pitot tube that met all geometry standards was used to monitor stack gas velocity.

Filter Holder - Pyrex glass with heating system capable of maintaining a filter temperature of approximately 250°F.

Draft Gauge - An inclined manometer made by Dwyer with a readability of 0.01 inches H₂O in the 0-1 inch range was used.

Impingers - Four impingers connected in series with glass ball joints. The first, third and fourth impingers were of the Greensburg-Smith design, modified by replacing the tip with a 1/2 inch I.D. glass tube extending to 1/2 inch from the bottom of the flask.

Measuring System - Vacuum gauge, leak-free pump, thermometers capable of measuring temperature to within 5°F, calibrated dry gas meter, and related equipment, to maintain an isokinetic sampling rate and to determine sample volume. The dry gas meter is made by Rockwell and the fiber vane pump is made by Gast.

Barometer - Aneroid type to measure atmospheric pressures to ±0.1 inch Hg.

*Federal Register, CFR 40, Part 60, July 1, 1967

**D.E.R. Source Testing Manual, January 1983

Hemcon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

SAMPLING PROCEDURE - PARTICULATE


After selecting the sampling site and the minimum number of traverse points, the stack pressure, temperature, moisture and range of velocity head were measured according to the procedures described in the ~~Federal Register~~.

Approximately 200 grams of silica gel were weighed in a sealed impinger prior to each test. ~~Glass Fiber Filters~~ (4 inch diameter) were desiccated for at least 24 hours dried at 105°C for two hours and weighed to the nearest 0.1 mg on an analytical balance. One-hundred ml of distilled water was placed in each of the first two impingers; the third impinger was initially empty; and the impinger containing the silica gel was placed next in series. The train was set up with the probe as shown in Figure A-1. The sampling train was leak-checked at the sampling site prior to each test run by plugging the inlet to the nozzle and pulling a 15 inch Hg vacuum, and at the conclusion of the test by plugging the inlet to the nozzle and pulling a vacuum equal to the highest vacuum reached during the test run.

The pitot tube and lines were leak-checked at the test site prior to and following the initial velocity traverse. The check is made by blowing into the impact opening of the pitot tube until 3 or more inches of water are recorded on the manometer and then capping the impact opening and holding it for 15 seconds to assure it was leak free. The static pressure side of the pitot tube was leak-checked using the same procedure, except suction was used to obtain the 3 inch H₂O manometer reading. Crushed ice was placed around the impingers to keep the temperature of the gases leaving the last impinger at 68°F or less.

During sampling, stack gas and sampling train data were recorded at each sampling point and when significant changes in stack flow conditions occurred. Isokinetic sampling rates were set throughout the sampling period with the aid of isokinetic sampling equations. All sampling data was recorded on the Particulate Field Data Sheet.

~~Federal Register~~ CFR 40, Part 60, July 1, 1986
~~Glass Fiber Filters~~ Type 934 AH



Particulate sampling train

Hemcon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

SAMPLE RECOVERY PROCEDURE

The sampling train was moved carefully from the test site to the cleanup area. Samples of the acetone and distilled water used in the sample recovery were taken for use as blanks. The volume of water from the first three impingers were measured. Sample fractions were recovered as follows:

Container No. 1 - The filter was removed from its holder and placed in a petri dish and sealed.

Container No. 2 - Loose particulate and water washings from all sample-exposed surface prior to the filter were placed in a sample container, sealed and labeled. Particulate was removed from the probe with the aid of a brush and water rinsing. The liquid level was marked after the container was sealed.

Container No. 3 - Loose particulate and acetone washings from all sample-exposed surface prior to the filter were placed in a glass jar, labeled and sealed. Particulate was removed from the probe with the aid of a brush and acetone rinsing. The liquid level was marked after the container was sealed.

Container No. 4 - A minimum of 200 ml of acetone was taken for the blank analysis. The blank was obtained and treated in a similar manner as the acetone washing.

Container No. 5 - Distilled water in the impinger section of the sampling train was placed in a sample container. The impingers and connecting glassware were rinsed with distilled H₂O and this rinse added to the container for shipment to the laboratory.

Container No. 6 - Acetone washings from all sample-exposed surfaces in the impingers were placed in a sample container, labeled and sealed. The liquid level was marked after the container was sealed.

Container No. 7 - A minimum of 200 ml of distilled water was taken for the blank analysis. The blank was obtained and treated in a similar manner as the water rinse.

The silica gel from the fourth impinger was weighed and the gain recorded on the Sample Recovery Data Sheet with other pertinent data.

Hemcon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA ;

ANALYTICAL PROCEDURES

The following procedures were used and follow the methods prescribed by the Department of Environmental Resources.

Container No. 1 - The filter and any loose particulate matter from this sample container were placed into a tared glass weighing dish, dried at 105°C, desiccated for 24 hours to a constant weight and weighed to the nearest 0.1 mg.

Container No. 2 - The distilled water washings were transferred to a tared beaker and evaporated to dryness at 105°C temperature and pressure, desiccated for 24 hours to a constant weight and weighed to the nearest 0.1 mg.

Container No. 3 - The acetone washings was transferred to a tared beaker and evaporated to dryness at ambient temperature and pressure, desiccated for 24 hours to a constant weight and weighed to the nearest 0.1 mg.

Container No. 4 - The acetone blank was transferred to a tared beaker and evaporated to dryness at ambient temperature and pressure. The blank was then desiccated 24 hours to a constant weight and weighed to the nearest 0.1 mg.

Container No. 5 - The contents of this container were filtered through tared (0.6u - 0.22u) filters to remove insoluble particulate. The filters and filtrates were put in tared beakers, evaporated to dryness at 105°C, desiccated to constant weight and weighed on an analytical balance to nearest 0.1 mg.

Container No. 6 - The contents of this container were evaporated to dryness at ambient temperature and pressure, desiccated to constant weight and weighed on an analytical balance to the nearest 0.1 mg.

Container No. 7 - The distilled water blank was transferred to a tared beaker and evaporated to dryness at 105°C. The blank was then desiccated to a constant weight and weighed on an analytical balance to the nearest 0.1 mg.

The term "constant weight" means a difference of no more than 0.5 mg or 1% of total weight less tare weight, whichever is greater between two consecutive readings, with no less than 6 hours of desiccation between weighings.

Hemdon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

C. Field Data Sheets

HEMEON ASSOCIATES, INC.
Particulate Field Data Sheet

Plant Long Beach Refinery City Long Beach, Calif. Operator John J. Smith
 Location Refinery Foot no. 1007
 Stack diam. 14.25 in. Desiccant no. 0015 Filter no. 10523
 Pitoc coeff. 0.7 Pitoc number 3 Motorbox number 1007 Motorbox Nom. 1007 Diam. 1.5 I.D. 0.25

Trav. point no.	Velocity head (in. H ₂ O)	Gas temp. logroom P	Orifice ΔH		Clock time	Sample time min	Vacuum "Hg	Meter reading cu. ft.	Motor temperature degrees F		Temperature Probe Filter box	
			Uncorr. In. (H ₂ O)	Corr. for moist. In. (H ₂ O)					In	Out		
Init	xx		xx	Factor (0.75)	7:22	0	xx	590	xx	xx	23	252
1	55	157		1.7	7:25	3	100	575	71	69	23	252
2	44	182		0.7	7:28	6	100	565	71	69	240	252
3	44	185		0.7	7:31	9	100	555	62	69	241	254
4	40.5	190		3.2	7:34	12	101	545	63	69	247	251
5	40	188		3.4	7:37	15	102	535	63	69	240	239
6	40.5	185		3.2	7:40	18	101	525	100	70	244	243
7	40	183		0.5	7:43	21	100	515	85	70	245	251
8	40	192		0.4	7:46	24	100	507	8	72	243	252
9	43	188		1.3	7:49	27	100	499	81	71	244	241
10	39	192		1.1	7:52	30	100	491	90	71	244	240
11	44	189		0.7	7:55	33	100	483	90	72	245	242
12	48	189		1.4	7:58	36	100	475	98	74	241	245
Summary	0.734	191		2.45		72	1007	545	87			

Ambient temp. 51 °F

Bar. Press. 29.9 in. Hg

Stat. Press. 2.2 in. Hg

IMPINGER WATER
Final 484 ml

Init. 100 ml

Cond. 24 ml

DESICCANT
Final 420.9 gms

Init. 406.2 gms

Gain 14.7 gms

Time
CO₂
O₂
CO

ORGANALYZER

CO ₂	1.5	1.5	1.5
O ₂	1.5	1.5	1.5
CO			

Final leak rate 0.000 cfm at 10.5 in. Hg

0.000 cfm at 10.5 in. Hg

HEMEON ASSOCIATES, INC.
Particulate Field Data Sheet

Plant W. H. H. Co. City W. H. H. Operator W. H. H.
Location W. H. H. Test No. W. H. H. Date W. H. H.
Stack diam. W. H. H. Desiccant no. W. H. H. Filter no. W. H. H.
Pitot coeff. W. H. H. Pitot no. W. H. H. Meterbox W. H. H. Nozz. W. H. H.
number W. H. H. (Cal. (Y) W. H. H. Diam. W. H. H. I.D. W. H. H.

Trav. point no.	Velocity Head (Δ P) (in. H ₂ O)	Gas temp. °F	Orifice Δ H		Clock time	Sample time, min	Vacuum, in. Hg	Meter reading cu. ft.	Meter Temperature Degrees F		Temperatures °F		
			Uncorr. in. (H ₂ O)	Corr. for moist. Factor (1.25) in. (H ₂ O)					In	Out	Probe	Filter box	Impinger
1	1.15	120		3.5	8:15	38		2.18	104	25	259	259	259
2	1.15	124		3.8	8:22	42		2.21	104	24	257	259	259
3	1.25	122		4.0	8:24	45		2.24	104	28	254	257	259
4	1.45	123		4.5	8:30	48		2.27	104	28	252	257	259
5	1.45	127		1.3	8:31	51	11.0	2.29	104	28	259	258	259
6	1.45	128		1.4	8:34	54	11.0	2.31	104	21	254	259	259
7	1.25	115		1.2	8:37	57	11.0	2.30	104	22	250	257	259
8	1.25	122		1.7	8:40	60	11.0	2.31	109	23	254	259	259
9	1.15	123		0.5	8:43	63	11.1	2.39	104	24	257	259	259
10	1.25	124		0.8	8:49	66	11.3	2.41	114	25	255	259	259
11	1.50	124		4.2	8:51	69	13.1	2.44	117	28	252	257	259
12	1.45	124		5.2	8:54	72	12.5	2.50	118	27	251	257	259

HEMEON ASSOCIATES, INC.
Particulate Field Data Sheet

Plant Rockwell City Albuquerque Operator W. J. [Signature]
Location Rockwell Plant Test no. 222 Date 11/15/68
Stack diam. 24" I.D. Desiccant no. 222 Filter no. 222
Pitot Meterbox Meterbox No. No. No.
coeff. 0.84 number 12 number 259 Cal(Y) 1.002 Diam 14" I.D. 14.25"

Trav. point no.	Velocity Head (in.) H ₂ O	Temp. degrees F	Orifice ΔH		Clock time	Sample time	Vacuum in. Hg	Meter reading cu. ft.	Meter temperature degrees F		Temperature		
			Uncorr. in. (H ₂ O)	Corr. for moist. in. (H ₂ O)					In	Out	Probe	Filter box	Leakage
Init	xx		xx	Factor (.84)			xx	2.50	xx	xx			
1-1	1.5	124		1.1	10:00	3	11.0	2.52	87	77	149	153	148
2	1.4	121		0.7	10:03	4	11.0	2.53	90	79	150	151	149
3	1.4	120		0.7	10:06	9	11.0	2.55	98	78	154	159	149
4	1.5	122		0.7	10:09	12	11.2	2.56	102	80	155	159	149
5	1.20	122		1.3	10:12	15	11.3	2.61	109	81	158	153	149
6	1.5	128		3.8	10:15	18	11.8	2.57	108	82	157	151	149
7	1.7	124		1.5	10:18	21	12.0	2.73	108	83	153	149	149
8	3.3	124		1.0	10:21	24	11.0	2.91	105	84	149	151	149
13-1	3.2	128		1.1	10:23	27	11.2	2.71	91	83	140	155	149
2	1.4	123		1.3	10:28	30	11.0	2.33	91	83	141	150	149
3	1.4	121		1.3	10:39	33	11.0	2.25	100	84	140	149	149
4	1.9	129		0.8	10:41	36	11.0	2.26	108	84	139	151	149
Summary	0.759	192		2.75		72	10.27	2.49	87	95			

Ambient temp. 11 °F IMPINGER WATER Final 291 ml DESICCANT Final 412.3 gms
Bar. Press. 29.2 in. HG Init. 200 ml Init. 404.8 gms
Stat. Press. 24.1 in. WC Cond. 81 ml Gain 12.5 gms

ORSAT ANALYSES			
Time			
CO ₂	<u>1.5</u>	<u>4.5</u>	<u>4.5</u>
O ₂	<u>12.0</u>	<u>12.0</u>	<u>12.0</u>
CO			

Final leak rate 0.000 cfm at 14.5 in. Hg

W. J. [Signature]

HEMEON ASSOCIATES, INC.
Particulate Field Data Sheet

Plant Los Angeles City Los Angeles Operator John
Location California Test No. 100 Date 10/23
Stack dimen. 12" x 12" Desiccant no. 2-229 Filter no. 100
Pitot coeff. 0.95 Pitot no. 100 Meterbox Nozz. Nozz.
number 100 (Cal. (V) 1.00 Diam. 1/4" I.D. 1/4"

Trav. point no.	Velocity Head (ΔP) (in. H ₂ O)	Gas temp. °F	Orifice ΔH		Clock time	Sample time, min	Vacuum, " Hg	Meter reading, cu. ft.	Meter Temperature Degrees F		Temperature °F		
			Uncorr.	Corr. for moist. in (H ₂ O) Factor					In	Out	Probe	Filter box	Impinger
Init.	xxx	xxx	xxx	(.80)			xxx	xxx	xxx	xxx			
1	1.25	192		4.1	10:40	38	2.2	280	112	84	241	252	249
2	1.45	192		4.1	10:40	40	2.2	280	112	84	241	252	249
3	1.35	193		4.1	10:40	45	2.0	285	114	84	243	251	249
4	1.40	192		4.1	10:40	48	2.0	285	114	84	243	251	249
5	1.30	192		1.0	10:40	51	2.0	290	103	84	242	247	248
6	1.51	199		1.4	11:01	54	2.0	291	103	84	244	252	248
7	1.31	199		1.4	11:01	57	2.0	293	105	84	245	253	249
8	1.40	191		3.5	11:09	60	2.1	298	108	87	255	257	249
9	1.30	192		4.2	11:14	63	2.8	285	112	87	252	259	249
10	1.30	192		4.3	11:15	66	2.8	285	114	88	253	260	249
11	1.50	199		5.0	11:19	69	3.4	287	118	89	255	259	249
12	1.40	192		5.3	11:20	72	3.8	281	118	90	254	257	249

Particulate Field Data Sheet

Plant Waco Co. Co. City Waco, Tex. Operator W. J. ...
 Location ... Test no. ... Date ...
 Stack dimen. ... Desiccant no. ... Filter no. ...
 Pitot ... Pitot ... Meterbox ... Meterbox ... Nozz. ... Nozz. ...
 coeff. ... number ... number ... Cal(Y) 1002 Diam. 1 1/2" I.D. ...

Trav. point no.	Velocity Head $\left\{ \frac{\Delta P}{\rho g} \right\}$ in. H ₂ O	San temp. degrees F	Orifice ΔH		Clock time	Sample time mins	Vacuum "Hg	Meter reading cu. ft.	Meter temperature degrees F		Temperature		
			Uncorr. in. (H ₂ O)	Corr. for moist. in. (H ₂ O)					In	Out	Probe	Filter box	Leakage
Init	xx		xx	Factor			xx		xx	xx			
1	1.15	184		5.0	10:00	3	24	25	28	22	230	230	169
2	1.25	186		4.4	10:05	8	22	22	28	20	231	231	169
3	1.25	189		3.8	10:09	9	22	22	29	20	230	230	169
4	1.40	188		2.5	10:11	12	20	20	29	21	234	233	169
5	1.44	185		0.7	10:14	15	20	25	28	23	234	230	169
6	1.56	189		1.7	10:17	19	20	25	29	24	243	247	169
7	1.25	187		2.5	10:20	21	20	25	28	25	244	250	169
8	1.25	190		3.4	10:23	24	22	24	28	26	244	250	169
9	1.57	185		1.8	10:27	27	20	24	28	26	245	251	169
10	1.45	187		2.1	10:30	30	20	24	28	27	243	251	169
11	1.49	187		0.9	10:33	33	20	24	28	26	241	252	169
12	1.44	184		0.7	10:39	38	20	22	29	28	240	253	169
Summary	0.673	191		2.34		72	100%	25	29	99			

Ambient temp. 22 °F

Bar. Proc. 22210

Scat. Prod ~~24000~~ 10,000

IMPLINGER WATER
Final 22 ml

Table ~~continued~~ on 2

Cond. 22.5 ml.

DESICCANT

Final 418.9 gmo

Ref. 104.1 1000

Cost: \$4.80 each

ORSAT ANALYSES

Time

 CO_2

0.4

cd

Final leak rate 2.00E-6 cfm at 2.0 in. Hg

Geopelia striata

HEMEON ASSOCIATES, INC. Particulate Field Data Sheet

Plant Rocky Mountain City Denver Operator Keith Gatzmiller
 Location Rocky Mountain Test No. 222
 Stack dimen. 12" x 12" x 12" Desiccant no. 222 Filter no. 222
 Pitot coeff. 0.9 Pitot no. 52 Meter box number 52 Meter box no. 222 Nozz. 1.0

Trav. point no.	Velocity Head (ΔP) (in. H ₂ O)	Gas temp. °F	Orifice ΔH		Clock time	Sample time, min	Vacuum, " Hg	Meter reading cu. ft.	Meter Temperature Degrees F		Temperature °F		
			Uncorr. in. (H ₂ O)	Corr. for moist. in. (H ₂ O) Factor					In	Out	Probe	Filter box	Lin in pin for
Init.	xx	xx	xx	(.9)			xx		xx	xx			
1.5	1.22	119		0.9	10:50	38	11.2	1.22	10.1	9.1	21.2	25.3	1.0
2	1.37	123		1.0	10:52	39	11.0	1.37	10.1	9.1	21.2	25.3	1.0
3	1.54	124		1.2	11:00	45	11.0	1.54	10.3	9.3	21.2	25.3	1.0
4	1.25	121		0.9	11:02	48	11.3	1.25	11.7	9.4	21.2	25.3	1.0
5	1.02	118		0.9	11:04	51	11.0	1.02	10.9	9.4	21.2	25.3	1.0
6	1.17	120		1.0	11:15	54	11.0	1.17	11.0	9.4	21.2	25.3	1.0
7	1.10	118		1.5	11:18	57	11.0	1.10	11.1	9.4	21.2	25.3	1.0
8	1.27	125		1.1	11:20	60	11.0	1.27	11.0	9.5	21.2	25.3	1.0
9	1.57	124		1.8	11:31	63	11.0	1.57	10.0	9.3	21.2	25.3	1.0
10	1.10	121		0.5	11:39	66	11.1	1.10	10.7	9.4	21.2	25.3	1.0
11	1.84	122		1.4	11:40	69	11.0	1.84	11.0	9.3	21.2	25.3	1.0
12	1.91	124		1.9	11:45	72	11.0	1.91	10.1	9.4	21.2	25.3	1.0

Keith Gatzmiller

DRY GAS METER CALIBRATION DATA FORM

Test numbers

Date 15 Mar 90 Meter box number 9AC 2518 Plant

Barometric pressure, $P_b = 29.27$ in. Hg Dry gas meter number 2d1009 Pretest Y 1.009

Orifice manometer setting, (ΔH), in. H_2O	Gas volume		Temperature			Time (θ), min	Vacuum setting, in. Hg	Y_i	Y_i	
	Wet test meter (V_w), ft^3	Dry gas meter (V_d), ft^3	Wet test meter (t_w), $^{\circ}F$	Inlet (t_{d_i}), $^{\circ}F$	Dry gas meter Outlet (t_{d_o}), $^{\circ}F$				$V_w P_b (t_d + 460)$	$V_d P_b + \frac{\Delta H}{13.6} t_w + 460$
0.0	10.000	10.555	74	125	96	110.5	2.4	1.009		
0.5	10.028	10.414	74	124	98	112	2.4	1.007		
1.0	10.044	10.449	74	127	100	113.5	2.4	1.006		
$Y = 1.007$										

* If there is only one thermometer on the dry gas meter, record the temperature under t_d .

V_w = Gas volume passing through the wet test meter, ft^3 .

V_d = Gas volume passing through the dry gas meter, ft^3 .

t_w = Temperature of the gas in the wet test meter, $^{\circ}F$.

t_{d_i} = Temperature of the inlet gas of the dry gas meter, $^{\circ}F$.

t_{d_o} = Temperature of the outlet gas of the dry gas meter, $^{\circ}F$.

t_d = Average temperature of the gas in the dry gas meter, obtained by the average of t_{d_i} and t_{d_o} , $^{\circ}F$.

ΔH = Pressure differential across orifice, in H_2O .

Y_i = Ratio of accuracy of wet test meter to dry gas meter for each run.

Y = Average ratio of accuracy of wet test meter to dry gas meter for all three runs;
tolerance = pretest $Y \pm 0.05Y$

P_b = Barometric pressure, in. Hg.

θ = Time of calibration run, min.

Hemson Associates, Inc.
125 Thirty-Ninth Street
Pittsburgh, PA 15201

PTTOT TUBE CALIBRATION DATA

Calibration pitot tube: type 522 size (OD) .225 ID number 44224

Type S pitot tube ID number 521 C_p (std) = 1.00

Calibration: date 12/6/22 performed by 60267

A - Side "Calibration"

Δp_{red} cm H ₂ O (in. H ₂ O)	Δp_B cm H ₂ O (in. H ₂ O)	a $C_p(s)$	b DEV.
0.10	0.146	0.822	0.001
0.20	0.295	0.842	0
0.30	0.457	0.822	0.001
Average		0.832	0.002

A - Side Calibration

Δp_{std} cm H_2O (in. H_2O)	Δp_{D} cm H_2O (in. H_2O)	$C_p(s)$	DEV.
0.10	0.143	0.834	0.014
0.22	0.295	0.840	0
0.40	0.55	0.840	0
Average		0.839	0.001

$$C_p(s) = C_p(\sigma_d) \sqrt{\frac{\Delta p_{std}}{\Delta p_s}} = 2.84$$

$$b_{DEV} = C_p(s) - C_p \quad (\text{must be } \leq 0.01)$$

$$\chi^2_p(A) - \chi^2_p(B) = \underline{0.0002} \quad (\text{must be } \leq 0.01)$$

Korrosion Consultants, Inc.
125 Thirty-Ninth Street
Pittsburgh, PA 15201

Hemdon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

D. Laboratory Data.

SAMPLE WEIGHTS AND DUST CONCENTRATION

Test No.	1	2	3
Test Date	4/25/90	4/25/90	4/26/90
Filter No.	120503	120504	120506
*Impinger Solut'n Sol.,mg	.39	.4	7.09
Impinger Solut'n, Insol.,mg	1.82	2.62	2.38
Probe Rinse, Acetone, mg	7	4.4	8.5
Probe Rinse, Water, mg	3.1	1.5	2.7
Filter Tare, mg	651.5	660.1	681.6
Filter + Sample, mg	655.7	663.7	685.4
Filterable sample, mg	4.2	3.6	3.8
Total Sample, mg	16.12	12.12	17.38
Sample Gas Volume scf	56.2	56.7	54.4
Sample Gas Weight, lbs	4.22	4.25	4.08
PM Conc., #/1000 #gas	.009	.007	.01
PM Conc., gr/dry scf	.004	.003	.005

* DATA NOT USED IN CALCULATIONS

TABLE I
TOTAL SOLIDS ANALYSIS
HEMEON ASSOCIATES, INC.
125 THIRTY-NINTH STREET
PITTSBURGH, PA 15201
PURCHASE ORDER # 3390 LATROBE CONSTRUCTION
SAMPLES RECEIVED: APRIL 27, 1990

HEMEON SAMPLE NUMBER	AQS LABORATORY NUMBER	SAMPLE TYPE	SAMPLE VOLUME MILLILITER	TOTAL SOLIDS MILLIGRAMS
7286	53924	ACETONE	77	7.0
7287	53925	ACETONE	57	4.4
7288	53926	ACETONE	80	8.5
7298	53927	ACETONE	98	2.0
7289	53928	WATER	96	3.1
7290	53929	WATER	89	1.5
7291	53930	WATER	94	2.7
7299	53931	WATER	103	1.0

THE SAMPLES WERE WEIGHED ON A BALANCE CALIBRATED WITH WEIGHTS
TRACEABLE TO THE NATIONAL BUREAU OF STANDARDS.
THE DATA HAS NOT BEEN CORRECTED FOR THE BLANK.

John C. Frohlinger
MR QUALITY SERVICES, INC.

JOB 2344

TABLE II
ANALYSIS OF SAMPLES FOR SOLUBLE-INSOLUBLE SOLIDS
HEMEON ASSOCIATES, INC.
125 THIRTY-NINTH STREET
PITTSBURGH, PA 15201
PURCHASE ORDER # 3390 LATROBE CONSTRUCTION
SAMPLES RECEIVED: APRIL 27, 1990

HEMEON SAMPLE NUMBER	AQS LABORATORY NUMBER	SAMPLE VOLUME MILLILITERS	INSOLUBLE SOLIDS MILLIGRAMS	SOLUBLE SOLIDS MILLIGRAMS
7292	53932	330	1.82	0.39
7293	53933	340	2.62	0.40
7294	53934	335	2.38	7.09

THE FILTERS WERE WEIGHED ON A MICRO BALANCE CALIBRATED WITH WEIGHTS
TRACEABLE TO THE NATIONAL BUREAU OF STANDARDS.
THE DATA HAS NOT BEEN CORRECTED FOR A BLANK.

John C. Frohlinger
AQS QUALITY SERVICES, INC.

JOB 2344

Homecon Associates, Inc. report of 5/3/90
to Latrobe Construction Co., Inc., Latrobe, PA

E. Process Data

May, 3 1990

To: John C. Perry

Kemcon Associates Inc.

125 39th St.

Pittsburgh, Pa. 15201

The plant is a bituminous Barber Green batch plant.

~~The exhaust gases from the dryer are passed through a model JA 960 BA~~

continuous duty jet-air pulse jet baghouse dust collector, consisting of the following: 960 bags 4 inch diameter x 99 inches long, made of 16oz polyester felt with galvanized cages.

Cloth area 8768 square feet.

The rated capacity of the plant is 300 ton per hour. The actual operating rate is not expected to exceed 264 T.P.H. The operating rate during stack test was 264 T.P.H.

The two types of aggregate mixes were dried during the emission test. ID#2 Binder with #57 stone 37.2%, #8 stone 29.3 %, shot stone 4.6%, with sand 24.3 %.

ID#2 Top with #8 stone 31.8 %, shot stone 15.3%, sand 46.5 %, oil 6.5 %.

Cold feed settings : sand 50 %, #8 13 40 %, #57 25 70%.

During tests the magnahelic pressure was 3 % to 3.5 %.