

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP42 Section: 11.1

Reference Number: 66

Title: Air Emission Test Report, Results Of Emission Compliance Test Performed On A Asphalt Plant Baghouse System, Northern Asphalt Construction, Inc., Minneapolis, Minnesota, August 17, 1993,

Twin City Testing Corporation, St. Paul, MN,

September 16, 1993.

Report Number: 4232-93-2677

Report Issued: September 16, 1993

AIR EMISSION TEST REPORT
RESULTS OF EMISSION COMPLIANCE TEST
PERFORMED ON A ASPHALT PLANT
BAGHOUSE SYSTEM
NORTHERN ASPHALT CONSTRUCTION, INC.
MINNEAPOLIS, MINNESOTA
AUGUST 17, 1993


Submitted to:

NORTHERN ASPHALT CONSTRUCTION, INC.
11064 Raddison Road, NE
Minneapolis, MN 55449


Submitted by:

TWIN CITY TESTING CORPORATION
Air Quality Services Department
737 Pelham Blvd.
St. Paul, Minnesota 55114

Prepared by:


James Tryba, Manager
Source and Ambient Testing
Air Quality Services

Approved by:


Ahto Niemioja
Director
Air Quality Services



twin city testing
corporation

662 CROMWELL AVENUE
ST. PAUL, MN 55114
PHONE 612/645-3601

September 16, 1993

Mr. Jeffrey Dusenka
Northern Asphalt Construction, Inc.
11064 Raddison Road, NE
Minneapolis, MN 55449

Re: Source Emission Compliance Test Report

Dear Mr. Dusenka:

Enclosed are two copies of Twin City Testing Corporation's report #4232-93-2677 concerning the particulate and opacity emission compliance test performed on the baghouse system at your asphalt plant located in Minneapolis, Minnesota. Please review and forward a copy of this report to the Minnesota Pollution Control Agency at your earliest convenience.

Thank you for allowing TCT the opportunity of working with you on this project. If you have any questions regarding this report please call me at (612) 659-7566.

Sincerely,

Ahto Niemioja
Ahto Niemioja
Director, Air Quality Services

TABLE OF CONTENTS

	<u>Page</u>
Introduction	1
Test Results	1
Process Data	3
Test Procedures	3
 Appendix A: Calculations	
Appendix B: Field Data Forms	
Appendix C: Laboratory Reports	
Appendix D: Calibration Data	
Appendix E: Minnesota Exhibit C and Process Data	
Appendix F: MPCA Test Plan	

INTRODUCTION

Twin City Testing Corporation (TCT) was contracted by Northern Asphalt Construction, Inc. to perform a source emission compliance test on the baghouse system at their asphalt plant located in Minneapolis, Minnesota. The exhaust gases from the baghouse were tested for particulate and opacity emissions on August 17, 1993. This report presents the results of the test program along with all substantiating documentation.

Northern Asphalt Construction, Inc. was represented throughout the test period by Mr. Jeffrey Dusenka. The TCT sampling team consisted of Messrs. Jim Tryba, Dave Christian, and Brad Lavold. The opacity testing was performed by Mr. Dave Christian, who is a certified visible emissions evaluator.

TEST RESULTS

The results of the particulate emission test are summarized in Table 1. The data indicates an average grain loading of 0.0130 grains per dry standard cubic foot of exhaust gas. A 60 minute visible emissions test was performed concurrent with each test run. The highest average opacity achieved during each of the three test runs was 0.0%.

There were no sampling problems encountered during the test.

Table 1
Summary of Emission Test Results
Northern Asphalt Construction, Inc., Minneapolis, Minnesota
Asphalt Plant Baghouse
August 17, 1993

<u>SAMPLING TRAIN DATA</u>		<u>Run 1-1</u>	<u>Run 1-2</u>	<u>Run 1-3</u>	<u>Average</u>
Sampling time, minutes		70	70 ✓	70 ✓	
Sampling nozzle diameter, inches	Dn	0.188	0.188 ✓	0.188	
Sampling nozzle area, sq.ft.	An	0.000193	0.000193	0.000193	
Isokinetic variation, %	I	100.9	101.8	99.0	100.6
Sample gas volume, acf	Vm	49.810	53.237 ✓	53.154 ✓	52.067
Sample gas volume, dscf	Vmstd	50.268	52.828	51.476	51.524
Avg. meter temperature, deg R	Tm	531	541 ✓	555	542
Avg. orifice pressure drop, in. H ₂ O	dH	2.08	2.27	2.21	2.19
Total particulate collected, mg	Mn	51.19	38.43	40.41	43.34
<u>VELOCITY TRAVERSE DATA</u>					
Stack Area, sq.ft.	A	6.0156	6.0156 ✓	6.0156	
Abs. stack gas pressure, in. Hg.	Ps	29.88	29.92	29.96	
Barometric pressure, in. Hg.	Pbar	30.00	30.04 ✓	30.08 ✓	
Avg. stack temperature, deg R	Ts	698	686 ✓	681 ✓	688
Avg. sq.rt. velocity head (Cp=.84)		1.51645	1.58243	1.56539 ✓	1.55476
Avg. stack gas velocity, ft./sec.	Vs	97.302	100.592	99.079	98.991
<u>STACK GAS MOISTURE CONTENT</u>					
Total water collected, ml	Vic	215.0	241.2 ✓	224.1 ✓	226.8
Moisture in stack gas, %	Bws	16.73	17.62	16.94	17.10
<u>STACK GAS FLOW RATE</u>					
Stack gas flow rate, dscf/hr.	Qsd	1,325,529	1,381,263	1,383,637	1,363,476
Stack gas flow rate, acfm		35,120	36,307	35,761	35,729
Stack gas flow rate, dscfm		22,092	23,021	23,061	22,725
<u>PARTICULATE EMISSION RATE</u>					
Particle grain loading, gr/dscf	Cs	0.0157	0.0112	0.0121 ✓	0.0130
Particle mass rate, lb./hr.	E	2.97	2.21	2.39	2.52
<u>ORSAT DATA</u>					
Percent CO ₂ by volume	CO ₂	3.13	3.23	3.10 ✓	3.15
Percent O ₂ by volume	O ₂	16.30	16.23	16.37	16.30
Percent CO by volume	CO	0.00	0.00	0.00	0.00
Percent N ₂ by volume	N ₂	80.57	80.54	80.53	80.55

PROCESS DATA

Northern Asphalt Construction, Inc. operates a Barber-Greene asphalt plant utilizing a Barber-Greene Model CF-11 baghouse for controlling particulate emissions. The process data is included in Appendix E. The maximum hourly plant hot mix asphalt output rate was 127 tons per hour. The maximum fuel usage was 247 gallons per hour. The average aggregate moisture content as sampled from the aggregate stockpile was 1.72%.

TEST PROCEDURES

The EPA Methods referenced below are described in Appendix A of the Code of Federal Regulations, Title 40, Part 60 (40 CFR 60).

The number of sampling points and their location within the source stack/duct was determined per EPA Method 1 which is entitled "Sample and velocity traverses for stationary sources". In this method the number of sampling points is based on the length of straight, undisturbed flow both before and after the sampling port location. The following data is specific to the source tested:

Stack cross-sectional dimensions, inches:	31.5" x 27.5"
Distance from flow disturbances to test ports;	
Upstream from disturbance, inches:	31.0"
Downstream from disturbance, inches:	89.5"
Minimum required number of sampling points:	25
Number of sampling points used:	28
Sampling point distribution;	
Number of sampling ports:	4
Number of sampling points per port:	7
Particulate test sampling time;	
Time at each sampling point, minutes:	2.5
Test run total sampling time, minutes:	70.0

Effluent flow measurements were made per EPA Method 2 which is entitled "Determination of stack gas velocity and volumetric flow rate (Type S pitot tube)". A check for cyclonic gas flow indicated that the exhaust gas flow was parallel to the stack walls. Gas velocity pressure (head) and temperature data were obtained during each EPA Method 5 particulate test run by traversing each of the sampling points defined by EPA Method 1. This data along with gas density (EPA Method 3) and moisture content (EPA Method 4) data was used to calculate the gas velocity at each sampling point. The source volumetric flow rate was calculated by multiplying the average gas velocity by the stack/duct cross-sectional area at the point of measurement. Velocity pressure (head) measurements were made using a Type S pitot tube constructed to the design specifications detailed in EPA Method 2. Such pitot tubes have a base line coefficient of 0.84.

The density of the effluent was determined per EPA Method 3 which is entitled "Gas analysis for the determination of dry molecular weight". A multi-point, integrated gas sample was collected simultaneously with each EPA Method 5 particulate test run. The gas sample was analyzed for carbon dioxide and oxygen concentrations with a standard Orsat analyzer using commercially prepared solutions. For calculations of gas density the balance of the gas was assumed to be nitrogen and carbon monoxide.

The effluent moisture content was determined per EPA Method 4 which is entitled "Determination of moisture content in stack gases". Data for making a gas moisture content determination was collected simultaneously with each EPA Method 5 particulate test run. The gas moisture content was calculated from the mass and/or volume of liquid collected in the Method 5 sampling train cold box impingers and the volume of gas sampled.

The effluent particulate concentration was determined per EPA Method 5 which is entitled "Determination of particulate emissions from stationary sources". For each test run, particulate matter was with drawn from the gas stream at each of the EPA Method 1 defined sampling points and collected on a glass fiber filter which was maintained at $248 \pm 25^{\circ}\text{F}$. Water vapor, organic vapors and other matter in vapor form which passed through the filter was collected in an ice-cooled impinger trap who's exit temperature was maintained at less than 68°F . Sampling was performed using a Grasby-Nutech Model 2010 Method 5 stack sampling system which employed a three foot inconel lined probe and a 0.188 inch nominal diameter nozzle. Particulate emissions included analyses of both the front and back (condensible organics) catches as required by Minnesota Rule 7005.0500.

Source visible emissions were determined by plume opacity observations made by a certified opacity reader per EPA Method 9 which is entitled "Visual determination of the opacity of emissions from stationary sources".

APPENDIX A
CALCULATIONS

* DRY GAS VOLUME *

$$Vm(std) = Vm [T(std) / Tm] [(Pbar + (dH/13.6)) / P(std)]$$
$$= 17.64 \times [degR / in.Hg.] \times Y \times Vm [(Pbar + (dH/13.6))/Tm]$$

Where:

$Vm(std)$ = Dry Gas Volume through meter at standard conditions

Vm = Dry Gas Volume measured by meter

$Pbar$ = Barometric pressure at orifice meter

$Pstd$ = Standard absolute pressure

Tm = Absolute temperature at meter degR.

$Tstd$ = Standard absolute temperature (528 degR).

dH = Average pressure drop across orifice meter

Y = Dry gas meter calibration factor.

13.6 = Inches water per inches Hg.

Run 1-1

$$Vm(std) = 17.64 \times 1.0075 \times 49.810 [(30.00 + (2.08 / 13.6)) / 531] = \underline{50.268 \text{ dscf}}$$

Run 1-2

$$Vm(std) = 17.64 \times 1.0075 \times 53.237 [(30.04 + (2.27 / 13.6)) / 541] = \underline{52.828 \text{ dscf}}$$

Run 1-3

$$Vm(std) = 17.64 \times 1.0075 \times 53.154 [(30.08 + (2.21 / 13.6)) / 555] = \underline{51.476 \text{ dscf}}$$

• TOTAL CONTAMINANTS by WEIGHT: GRAIN LOADING •

$$C's = [0.0154 \text{ gr/mg}] [Mn/Vm(\text{std})]$$

Where:

C's = Concentration of particulate matter in stack gas
corrected to standard conditions

Mn = Total amount of particulate matter collected

Vm(std) = Dry gas volume through meter at standard conditions

Run 1-1

$$C's = 0.0154 \times [0.05119 \times 1000] / 50.268 = \underline{0.0157 \text{ gr/dscf}}$$

Run 1-2

$$C's = 0.0154 \times [0.03843 \times 1000] / 52.828 = \underline{0.0112 \text{ gr/dscf}}$$

Run 1-3

$$C's = 0.0154 \times [0.04041 \times 1000] / 51.476 = \underline{0.0121 \text{ gr/dscf}}$$



• DRY MOLECULAR WEIGHT •

$$Md = 0.44 (\% \text{ CO}_2) + 0.32 (\% \text{ O}_2) + 0.28 (\% \text{ CO} + \% \text{ N}_2)$$

Where:

Md = Dry molecular weight

% CO₂ = Percent carbon dioxide by volume (dry basis).

% O₂ = Percent oxygen by volume (dry basis).

% N₂ = Percent nitrogen by volume (dry basis).

% CO = Percent carbon monoxide by volume (dry basis).

0.264 = Ratio of O₂ to N₂ in air

0.28 = Molecular weight of N₂ or CO

0.32 = Molecular weight of O₂ divided by 100.

0.44 = Molecular weight of CO₂ divided by 100.

Run 1-1

$$Md = 0.44 (3.13) + 0.32 (16.30) + 0.28 (80.57) = \underline{29.153 \text{ lb/lb-mole}}$$

Run 1-2

$$Md = 0.44 (3.23) + 0.32 (16.23) + 0.28 (80.54) = \underline{29.166 \text{ lb/lb-mole}}$$

Run 1-3

$$Md = 0.44 (3.10) + 0.32 (16.37) + 0.28 (80.53) = \underline{29.151 \text{ lb/lb-mole}}$$



* WATER VAPOR CONDENSED *

$$V_{wc}(std) = (V_f - V_i) [P_w R T(std) / M_w P(std)] = 0.04707 (V_f - V_i)$$

$$V_{wsg}(std) = (W_f - W_i) [R T(std) / M_w P(std)] = 0.04715 (W_f - W_i)$$

Where:

0.04707 = Conversion factor

0.04715 = Conversion factor

$V_{wc}(std)$ = Volume of water vapor condensed (standard conditions)

$V_{wsg}(std)$ = Volume of water vapor collected in silica gel (standard conditions)

$V_f - V_i$ = Final volume of impinger contents less initial volume

$W_f - W_i$ = Final weight of silica gel less initial weight

P_w = Density of water

R = Ideal gas constant

M_w = Molecular weight of water vapor

$T(std)$ = Absolute temperature at standard conditions

$P(std)$ = Absolute pressure at standard conditions

Run 1-1

$$V_{wc}(std) = 0.04707 \times 207 \text{ ml} = \underline{9.7 \text{ cu.ft.}}$$

$$V_{wsg}(std) = 0.04715 \times 8.0 \text{ gr} = \underline{0.4 \text{ cu.ft.}}$$

Run 1-2

$$V_{wc}(std) = 0.04707 \times 228 \text{ ml} = \underline{10. \text{ cu.ft.}}$$

$$V_{wsg}(std) = 0.04715 \times 13.2 \text{ gr} = \underline{0.6 \text{ cu.ft.}}$$

Run 1-3

$$V_{wc}(std) = 0.04707 \times 211 \text{ ml} = \underline{9.9 \text{ cu.ft.}}$$

$$V_{wsg}(std) = 0.04715 \times 13.1 \text{ gr} = \underline{0.6 \text{ cu.ft.}}$$

* MOISTURE CONTENT OF STACK GASES *

$$Bws = [Vwc(std) + Vwsg(std)] / [Vwc(std) + Vwsg(std) + Vm(std)] \times 100$$

Where:

Bws = Proportion of water vapor

Vm = Dry gas volume measured by dry gas meter

Vwc(std) = Volume of water vapor condensed corrected to standard conditions

Vwsg(std) = Volume of water vapor collected in silica gel corrected to standard conditions

Run 1-1

$$Bws = (9.7 + 0.4) / (9.7 + 0.4 + 50.268) \times 100 = \underline{16.73 \%}$$

Run 1-2

$$Bws = (10.7 + 0.6) / (10.7 + 0.6 + 52.828) \times 100 = \underline{17.62 \%}$$

Run 1-3

$$Bws = (9.9 + 0.6) / (9.9 + 0.6 + 51.476) \times 100 = \underline{16.94 \%}$$

• **MOLECULAR WEIGHT of STACK GASES ***

$$M_s = M_d (1 - B_{ws}) + 18 (B_{ws})$$

Where:

M_s = Molecular weight of stack gas

M_d = Molecular weight of stack gas

B_{ws} = Proportion of water vapor

Run 1-1

$$M_s = 29.28 (1 - 0.1673) + 18 (0.1673) = \underline{29.26 \text{ lb/lb-mole}}$$

Run 1-2

$$M_s = 29.28 (1 - 0.1762) + 18 (0.1762) = \underline{29.26 \text{ lb/lb-mole}}$$

Run 1-3

$$M_s = 29.28 (1 - 0.1694) + 18 (0.1694) = \underline{29.26 \text{ lb/lb-mole}}$$

* STACK GAS VELOCITY *

$$V_s = K_p C_p [\text{sq. rt. } dP] \times \text{avg. } [\text{sq. rt. } (T_s(\text{avg.})/P_s M_s)]$$

Where :

V_s = Average velocity of gas stream in stack

K_p = 85.49 ft/sec [(g/g-mole) - (mm Hg) / (degK) (mm H₂O)]^{1/2}

C_p = Pitot tube coefficient

dP = Velocity head of stack gas

P_{bar} = Barometric pressure at measurement site

P_g = Stack static pressure

P_s = Absolute stack gas pressure

P_{std} = Standard absolute pressure

t_s = stack temperature

T_s = Absolute stack temperature

M_s = Molecular weight of stack gas

Run 1-1

$$V_s = 85.49 \times 0.84 \times 1.51645 \times \text{Sq. Rt. } [698 / (29.88 \times 29.26)] = \underline{97.302 \text{ ft/sec.}}$$

Run 1-2

$$V_s = 85.49 \times 0.84 \times 1.58243 \times \text{Sq. Rt. } [686 / (29.92 \times 29.26)] = \underline{100.592 \text{ ft/sec.}}$$

Run 1-3

$$V_s = 85.49 \times 0.84 \times 1.56539 \times \text{Sq. Rt. } [681 / (29.96 \times 29.26)] = \underline{99.079 \text{ ft/sec.}}$$

* STACK GAS FLOW RATE *

$$Q_{std} = 3600 (1 - Bws) V_s A (T_{std} / T_s) (P_s / P_{std})$$

Where :

Q_{std} = Dry volumetric stack gas flow rate corrected to std.conditions.

A = Cross sectional area of stack

3600 = Conversion factor

t_s = Stack temperature

T_s = Absolute stack temperature

T_{std} = Standard absolute temperature

P_{bar} = Barometric pressure at measurement site

P_g = Stack static pressure

P_s = Absolute stack gas pressure

P_{std} = Standard absolute pressure

Run 1-1

$$Q (std) = 3600 (1 - 0.1673) (97.302) (6.015) (528 / 698) (29.88 / 29.92)$$

$$Q (std) = \underline{1,325,529 \text{ dscf/hr}}$$

Run 1-2

$$Q (std) = 3600 (1 - 0.1762) (100.59) (6.015) (528 / 686) (29.92 / 29.92)$$

$$Q (std) = \underline{1,381,263 \text{ dscf/hr}}$$

Run 1-3

$$Q (std) = 3600 (1 - 0.1694) (99.079) (6.015) (528 / 681) (29.96 / 29.92)$$

$$Q (std) = \underline{1,383,637 \text{ dscf/hr}}$$

* EMISSIONS RATE FROM STACK *

$$E = [C_s \ Q_{std}] / 7000 \text{ gr./lb.} = \text{lb. / hr.}$$

Where :

E = Emissions rate

C_s = Concentration of particulate matter corrected to std.conditions.

Q_{std} = Dry volumetric stack gas flow rate corrected to std.conditions.

Run 1-1

$$E = [0.0157 \times 1,325,529] / 7000 = \underline{2.97 \text{ lb./hr.}}$$

Run 1-2

$$E = [0.0112 \times 1,381,263] / 7000 = \underline{2.21 \text{ lb./hr.}}$$

Run 1-3

$$E = [0.0121 \times 1,383,637] / 7000 = \underline{2.39 \text{ lb./hr.}}$$

• ISOKINETIC VARIATION •

$$I = 100 T_s [0.002669 V_{ic} + (V_m / T_m) (P_{bar} + dH / 13.6)] / 60 e V_s P_s A_n$$

Where :

- I = Percent isokinetic sampling.
- 100 = Conversion to percent.
- T_s = Absolute average stack gas temperature
- 0.002669 = Conversion factor
- V_{ic} = Total volume of liquid collected in impingers and silica gel
- T_m = Absolute average dry gas meter temperature
- P_{bar} = Barometric pressure at sampling site
- dH = Average pressure differential across the orifice meter
- 13.6 = Specific gravity of mercury.
- 60 = Conversion seconds to minutes.
- e = Total sampling time
- V_s = Stack gas velocity
- P_s = Absolute stack gas pressure
- A_n = Cross sectional area of nozzle

Run 1-1

$$I = 100 \times 698 \times \frac{[(0.002669 \times 215.0) + (49.810 / 531) (30.00 + (2.08 / 13.6))]}{60 \times 70 \times 97.302 \times 29.88 \times 0.0001928} = \underline{100.9 \%}$$

Run 1-2

$$I = 100 \times 686 \times \frac{[(0.002669 \times 241.2) + (53.237 / 541) (30.04 + (2.27 / 13.6))]}{60 \times 70 \times 100.592 \times 29.92 \times 0.0001928} = \underline{101.8 \%}$$

Run 1-3

$$I = 100 \times 681 \times \frac{[(0.002669 \times 224.1) + (53.154 / 555) (30.08 + (2.21 / 13.6))]}{60 \times 70 \times 99.079 \times 29.96 \times 0.0001928} = \underline{99.0 \%}$$

1.125 sec?

APPENDIX B
FIELD DATA FORMS

Field Data :

Plant # & Location = NORTHERN ASPHALT COMPANY, Blaine, MN
Date of Test = August 18, 1993
Process Tested = Asphalt Plant Baghouse
Number of Sampling Points = 28
Pitot Tube Coefficient = 0.84 ✓
Stack Area, sq.ft. = 6.0156 ✓
Y Factor = 1.0075 ✓

	<u>Run 1-1</u>	<u>Run 1-2</u>	<u>Run 1-3</u>
Dry Gas Meter Volume, cfd.	= 49.810	53.237	53.154
Barometric Pressure, in.Hg.	= 30.00	30.04	30.08
Stack Pressure, in.Hg.	= 29.88	29.92	29.96
Total Water Collected, ml.	= 215.0	241.2	224.1
% Carbon Dioxide	= 3.13	3.23	3.10
% Oxygen	= 16.30	16.23	16.37
% Carbon Monoxide	= 0.00	0.00	0.00
% Nitrogen	= 80.57	80.54	80.53
Total Particulate, gr.(see Lab Data)	= 0.05119	0.03843	0.04041
Total Sampling Time, min.	= 70	70	70
Nozzle Diameter, inches	= 0.188	0.188	0.188
Nozzle Area, sq.ft.	= 0.0001928	0.0001928	0.0001928

Laboratory Data:

Front Catch :	<u>Run 1-1</u>	<u>Run 1-2</u>	<u>Run 1-3</u>
Front Wash =	0.01726	0.01503	0.01753
Filter Catch =	0.01307	0.01328	0.01540
Front Half Total =	0.03033	0.02831	0.03293

Back Catch :			
** Impinger Catch =	0.01397	0.00798	0.00511
Impinger Wash =	0.00689	0.00214	0.00237
Back Half Total =	0.02086	0.01012	0.00748

TOTAL PARTICULATE =	0.05119	0.03843	0.04041
---------------------	---------	---------	---------

** Chloroform/Ethyl Ether Extraction

Run 1-1

Ts = 698 dH = 2.08
Tm = 531 SR dP = 1.51645

Impinger Water = 207 ml
Silica Gel = 8.0 gr

Run 1-1 Point #	Stack Temp.	Velocity Pressure	Orifice Pressure	Meter Temperature		Sq.Root Velocity Pressure
				Inlet	Outlet	
A1	220	2.3	2.0	64	65	1.51658
2	230	3.1	2.8	63	64	1.76068
3	242	3.2	2.9	64	64	1.78885
4	246	2.2	2.0	65	64	1.48324
5	247	2.6	2.3	67	64	1.61245
6	248	2.7	2.4	68	65	1.64317
7	248	2.6	2.3	69	65	1.61245
B1	208	2.0	1.8	70	66	1.41421
2	245	2.9	2.6	71	66	1.70294
3	250	3.0	2.7	72	67	1.73205
4	251	2.1	1.9	73	67	1.44914
5	250	2.4	2.2	73	67	1.54919
6	249	2.7	2.4	74	68	1.64317
7	245	2.2	2.0	75	68	1.48324
C1	235	2.2	2.0	73	69	1.48324
2	239	2.6	2.3	75	70	1.61245
3	242	2.6	2.3	76	70	1.61245
4	242	2.2	2.0	77	70	1.48324
5	240	2.2	2.0	78	71	1.48324
6	238	2.2	2.0	78	71	1.48324
7	236	2.1	1.9	79	72	1.44914
D1	219	1.5	1.3	79	73	1.22474
2	229	2.2	2.0	79	73	1.48324
3	231	2.3	2.0	80	73	1.51658
4	236	2.2	2.0	81	74	1.48324
5	237	1.5	1.3	81	74	1.22474
6	237	1.6	1.4	82	75	1.26491
7	237	1.6	1.4	82	75	1.26491

Run 1-2

Ts = 686 dH = 2.27
Tm = 541 SR dP = 1.58243

Impinger Water = 228 ml
Silica Gel = 13.2 gr

Run 1-2 Point #	Stack Temp.	Velocity Pressure	Orifice Pressure	Meter Temperature		Sq.Root Velocity Pressure
				Inlet	Outlet	
A1	200	2.7	2.4	73	72	1.64317
2	210	3.5	3.2	73	72	1.87083
3	208	3.6	3.3	74	72	1.89737
4	215	2.7	2.4	75	72	1.64317
5	218	2.9	2.6	77	73	1.70294
6	219	3.1	2.8	78	73	1.76068
7	223	3.0	2.7	79	74	1.73205
B1	226	2.5	2.3	80	75	1.58114
2	222	3.3	2.9	81	75	1.81659
3	225	3.1	2.8	82	75	1.76068
4	231	2.6	2.3	83	76	1.61245
5	232	2.7	2.4	84	76	1.64317
6	230	2.8	2.4	85	77	1.67332
7	231	2.5	2.3	86	78	1.58114
C1	216	2.2	2.0	86	79	1.48324
2	225	2.8	2.4	87	79	1.67332
3	230	2.8	2.4	87	79	1.67332
4	233	2.5	2.3	88	80	1.58114
5	234	2.2	2.0	89	81	1.48324
6	233	2.2	2.0	89	81	1.48324
7	234	2.2	2.0	90	82	1.48324
D1	233	2.1	1.9	90	83	1.44914
2	231	2.4	2.2	91	83	1.54919
3	231	2.2	2.0	91	84	1.48324
4	235	2.0	1.8	91	84	1.41421
5	235	1.5	1.3	92	85	1.22474
6	235	1.4	1.1	92	85	1.18322
7	232	1.5	1.3	92	86	1.22474

Run 1-3

Ts = 681 dH = 2.21
Tm = 555 SR dP = 1.56539

Impinger Water = 211 ml
Silica Gel = 13.1 gr

Run 1-3 Point #	Stack Temp.	Velocity Pressure	Orifice Pressure	Meter Temperature		Sq.Root Velocity Pressure
				Inlet	Outlet	
A1	205	2.3	2.0	89	87	1.51658
2	208	3.3	2.9	89	87	1.81659
3	217	3.1	2.8	89	87	1.76068
4	220	2.4	2.2	90	88	1.54919
5	222	2.4	2.2	92	88	1.54919
6	223	2.6	2.3	93	88	1.61245
7	223	2.8	2.4	94	88	1.67332
B1	225	2.7	2.4	94	89	1.64317
2	220	3.1	2.8	96	90	1.76068
3	223	3.0	2.7	97	90	1.73205
4	225	2.3	2.0	98	90	1.51658
5	225	2.6	2.3	98	91	1.61245
6	223	2.7	2.4	99	91	1.64317
7	223	2.5	2.3	99	92	1.58114
C1	226	2.8	2.4	97	92	1.67332
2	221	2.9	2.6	100	93	1.70294
3	222	2.9	2.6	100	93	1.70294
4	226	2.2	2.0	101	93	1.48324
5	227	2.2	2.0	101	94	1.48324
6	225	2.4	2.2	101	94	1.54919
7	225	2.4	2.2	101	94	1.54919
D1	210	2.0	1.8	102	96	1.41421
2	215	2.5	2.3	101	95	1.58114
3	222	2.3	2.0	103	96	1.51658
4	224	2.0	1.8	102	96	1.41421
5	224	1.5	1.3	102	96	1.22474
6	223	1.6	1.4	102	97	1.26491
7	223	1.7	1.5	102	97	1.30384

2732

2572

5301.00

≈ 94.71

SOURCE EMISSION TEST FIELD DATA SHEET

TEST: 1 RUN: 1

PAGE: 1 of 2

TEST IDENTIFICATION		EQUIPMENT IDENTIFICATION		NOMOGRAPH SETTINGS	
TCT Project Number: 4232-93-2677		Control Unit Number: 1		shd 2.0416	
Date: 8/17/93		Gas Meter Coefficient: 10075		Tm 70	
Company: NORTHERN ASPHALT		Sample Box Number: 1		MC 16%	
Source: BAGHOUSE		Probe No: 3 Length: 3'		Ps/Pm .996	
Source Dimensions: 31 1/2" x 27 1/2"		Pitot No: 3 Coefficient: 0.84		C 2.0	
Test Team: JT/BL/DC		Nozzle No: 6 Diameter: .188		Ts 220	
Test Procedures: EPA 1-S + 9		Filter No: 102		R -	
Ambient Temp., °F: 65°		Barometric Pressure, in.Hg: 30.00		Static Pressure, in.WC: -1.6	

EPA METHOD 5 TRAVERSE DATA

CLOCK TIME hours	TRAVERSE POINT NUMBER	SAMPLE TIME minute	SAMPLE VOLUME cu.ft.	VELOCITY HEAD in.WC	ORIFICE		PUMP VAC. inHG	TEMPERATURE, °F							
					PH, in.WC REQ.	ACT.		STACK GAS	PROBE LINER	FILTER OVEN	IMPINGER EXIT	AUXILIARY	GAS METER		
														IN	OUT
6:31	A1	0	780.000	2.3	2.0	2.0	3.5	220	256	253	50	-		64	65
	2	2.5	781.8	3.1	2.8	2.8	5.0	230	255	251	45	-		63	64
	3	5	783.8	3.2	2.9	2.9	5.5	242	256	251	46	-		64	64
	4	7.5	785.8	2.2	2.0	2.0	4.0	246	257	251	49	-		65	64
	5	10	787.7	2.6	2.3	2.3	4.5	247	257	251	52	-		67	64
	6	12.5	789.7	2.7	2.4	2.4	5.0	248	258	252	53	-		68	65
	7	15	791.4	2.6	2.3	2.3	5.0	248	258	253	56	-		69	65
	END A	17.5	793.1	X	X	X	X	X	X	X	X	X	X	X	X
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
	B1	0	793.1	2.0	1.8	1.8	4.0	248	254	255	56	-		70	66
	2	2.5	794.8	2.9	2.6	2.6	5.0	245	257	253	55	-		71	66
	3	5	796.6	3.0	2.7	2.7	5.0	250	257	253	55	-		72	67
	4	7.5	798.6	2.1	1.9	1.9	4.0	251	258	252	56	-		73	67
	5	10	800.4	2.4	2.2	2.2	4.5	250	259	252	56	-		73	67
	6	12.5	802.3	2.7	2.4	2.4	5.0	249	258	252	57	-		74	68
	7	15	804.1	2.2	2.0	2.0	4.0	245	259	253	56	-		75	68
	END B	17.5	806.0	X	X	X	X	X	X	X	X	X	X	X	X
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
	C1	0	806.0	2.2	2.0	2.0	3.5	235	257	256	59	-		73	69
	2	2.5	807.8	2.6	2.3	2.3	5.0	239	257	255	57	-		75	70
	3	5	809.7	2.6	2.3	2.3	5.0	242	258	253	56	-		76	70
	4	7.5	811.6	2.2	2.0	2.0	4.0	242	258	254	56	-		77	70
	5	10	813.3	2.2	2.0	2.0	4.0	240	258	254	57	-		78	71
	6	12.5	815.1	2.2	2.0	2.0	4.0	238	258	254	58	-		78	71
	7	15	816.9	2.1	1.9	1.9		236	259	253	59	-		79	72
	END C	17.5	818.6	X	X	X	X	X	X	X	X	X	X	X	X

EPA METHOD 4: MOISTURE DETERMINATION

IMPINGER	1	2	3	4	5
Final	313	89	5	692.9	
Initial	100	100	0	684.9	
Net	213	-11	5	8.0	

Total Moisture Collected: 215.0

Impinger Catch Description: CLEAR

EPA METHOD 5 LEAK CHECK

Time	Rate, dcfm	Vac, in.Hg
6:15	0.000	15
7:52	0.000	6.5

Total Volume of Gas Sampled, DCF: 49.810

Total Sampling Time, Min: 70

Filter Catch Description:

VERY LIGHT TAN

EPA METHOD 3: GAS COMPOSITION BY ORSAT ANALYSIS

Sample Identification	Replicate 1		Replicate 2		Replicate 3		Replicate 4		Compound Average Percent Volume
	Buret Reading	Percent Volume	Buret Reading	Percent Volume	Buret Reading	Percent Volume	Buret Reading	Percent Volume	
Initial Reading									
Carbon Dioxide	3.0	3.0	3.2	3.2	3.2	3.2			3.13
Oxygen	19.4	16.4	19.4	16.2	19.5	16.3			16.30
Carbon Monoxide	0	0	0	0	0	0			0

Form SST5, Revised 12/28/92

Signature of Sampling Team Leader:

Aggregate Moisture - 1.81%

TWIN CITY TESTING CORPORATION

PAGE: 2 of 2

TEST IDENTIFICATION		EQUIPMENT IDENTIFICATION		NOMOGRAPH SETTINGS
TCT Project Number: 4232-93-2677		Control Unit Number: 1		ahd 2.0416
Date: 8/17/93		Gas Meter Coefficient: 1.0075		Im 70
Company: NORTHERN ASPHALT		Sample Box Number: 1		MC 16 3/4
Source: BAEHOWE		Probe No: 3' Length: 3'		Ps/Pm .996
Source Dimensions: 3 1/2" x 27 1/2"		Pitot No: 3 Coefficient: 0.84		C 2.0
Test Team: JT / BL / OC		Nozzle No: 6 Diameter: .188"		Ts 220
Test Procedures: CPA 15 + 9		Filter No: 102		R -
Ambient Temp., °F: 65.5		Barometric Pressure, in.Hg: 30.00		Static Pressure, in.WC: - 1.6

EPA METHOD 5 TRAVERSE DATA

[illegible]

EPA METHOD 4: MOISTURE DETERMINATION

IMPINGER	1	2	3	4	5
Final	313	89	5	692.9	X
Initial	100	100	0	68.9	
Net	213	-11	5	8.0	

Total Moisture Collected: 215.6

Impinger Catch Description: C L C 74 C

EPA METHOD 5 LEAK CHECK

Time	Rate, dcfm	Vac, in. Hg
6:45	0.000	15
7:51	0.000	6.5
	.	

Total Volume
of Gas
Sampled, DCF: 45.810

Total Sampling Time, Min: 70

Filter Catch Description:

Very Love You

EPA METHOD 3: GAS COMPOSITION BY ORSAT ANALYSIS

[illegible]

Form SS15, Revised 12/28/92

Signature
of Sampling
Team Leader:

Agg. 100% Moisture - 1.81%



twin city testing
Corporation

SOURCE EMISSION TEST FIELD DATA SHEET

TEST: 1 RUN: 2

PAGE: 1 of 2

TEST IDENTIFICATION		EQUIPMENT IDENTIFICATION		NOMOGRAPH SETTINGS	
TCT Project Number: 4232-93-2677		Control Unit Number: 1		ohm 2.0416	
Date: 8/17/93		Gas Meter Coefficient: 1.0075		Tm 70	
Company: NORTHERN ASPHALT		Sample Box Number: 2		MC 16%	
Source: BAGHOUSE		Probe No: 3 Length: 3'		Ps/Pm .946	
Source Dimensions: 3' 1/2" x 27 1/2"		Pitot No: 3 Coefficient: 0.84		C 2.0	
Test Team: JT/BL/DC		Nozzle No: 6 Diameter: .188		Ts 220	
Test Procedures: EPA 1-5 + 9		Filter No: 103		R -	
Ambient Temp., °F: 70		Barometric Pressure, in.Hg: 30.0-1		Static Pressure, in.WC: -1.7	

EPA METHOD 5 TRAVERSE DATA

CLOCK TIME hours	TRAVERSE POINT NUMBER	SAMPLE TIME minute	SAMPLE VOLUME cu.ft.	VELOCITY HEAD in.WC	ORIFICE		PUMP VAC. inHG	TEMPERATURE, °F							
					in.WC REQ.	in.WC ACT.		STACK GAS	PROBE LINER	FILTER OVEN	IMPINGER EXIT	AUXILIARY	GAS METER		
														IN	OUT
9:15	A1	0	830.80	2.7	2.4	2.4	4.0	200	256	251	58	-		73	72
	2	2.5	32.7	3.5	3.2	3.2	4.5	210	254	250	57	-		73	72
	3	5	35.0	3.6	3.3	3.3	5.0	208	256	251	53	-		74	72
	4	7.5	37.3	2.7	2.7	2.4	4.0	215	256	251	55	-		75	72
	5	10	39.3	2.9	2.6	2.6	4.5	218	257	253	57	-		77	73
	6	12.5	41.3	3.1	2.8	2.8	5.0	219	258	253	58	-		78	73
	7	15	43.4	3.0	2.7	2.7	5.0	223	259	253	58	-		77	74
	END A	17.5	45.5	X	X	X	X	X	X	X	X	X	X	X	X
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
	B1	0	45.5	2.5	2.3	2.3	4.0	226	260	254	57	-		80	75
	2	2.5	47.5	3.3	2.9	2.9	5.0	226	259	254	60	-		81	75
	3	5	49.5	3.1	2.8	2.8	5.0	225	259	254	60	-		82	75
	4	7.5	51.7	2.6	2.3	2.3	4.0	231	259	254	60	-		83	76
	5	10	53.7	2.7	2.4	2.4	4.0	232	260	255	60	-		84	76
	6	12.5	55.7	2.8	2.7	2.4	4.0	230	260	255	61	-		85	77
	7	15	57.7	2.5	2.3	2.3	4.0	231	259	255	59	-		86	78
	END B	17.5	59.7	X	X	X	X	X	X	X	X	X	X	X	X
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
	C1	0	59.7	2.2	2.0	2.0	3.5	216	260	256	61	-		86	79
	2	2.5	61.4	2.8	2.7	2.4	4.0	225	259	256	58	-		87	79
	3	5	63.3	2.8	2.7	2.4	4.0	230	260	256	57	-		87	79
	4	7.5	65.3	2.5	2.3	2.3	4.0	233	260	255	57	-		88	80
	5	10	67.3	2.2	2.0	2.0	4.0	234	260	255	57	-		89	81
	6	12.5	69.1	2.2	2.0	2.0	4.0	233	260	255	57	-		89	81
	7	15	70.9	2.2	2.0	2.0	4.0	234	261	254	57	-		90	82
	END C	17.5	72.7	X	X	X	X	X	X	X	X	X	X	X	X

EPA METHOD 4: MOISTURE DETERMINATION

IMPINGER	1	2	3	4	5
Final	297	130	1	704.4	X
Initial	100	100	0	691.1	X
Net	197	30	1	13.2	X

Total Moisture Collected: 241.2

Impinger Catch Description: C L LAR

EPA METHOD 5 LEAK CHECK

Time	Rate, dcfm	Vac, in.Hg
8:11	0.000	15
10:24	0.000	9

Total Volume of Gas Sampled, DCF: 53.63

Total Sampling Time, Min: 70

Filter Catch Description:

VERY LIGHT TAN

EPA METHOD 3: GAS COMPOSITION BY ORSAT ANALYSIS

Sample Identification	Replicate 1		Replicate 2		Replicate 3		Replicate 4		Compound Average Percent Volume
	Buret Reading	Percent Volume	Buret Reading	Percent Volume	Buret Reading	Percent Volume	Buret Reading	Percent Volume	
Initial Reading									
Carbon Dioxide	3.2	3.2	3.3	3.3	3.2	3.2	X	X	3.23
Oxygen	19.5	16.5	19.4	16.1	19.5	16.3	X	X	16.63
Carbon Monoxide	0	0	0	0	0	0	X	X	0

Form SST5, Revised 12/28/92

Signature of Sampling Team Leader:

AGGREGATE PRODUCTION - 1.54%


twin city testing
 corporation

PAGE: 2 of 2

TEST IDENTIFICATION		EQUIPMENT IDENTIFICATION		NOMOGRAPH SETTINGS	
TCT Project Number: 4232-43-2677		Control Unit Number: 1		shd 2.0416	
Date: 4/17/93		Gas Meter Coefficient: 1.0075		Tm 70	
Company: NORTHON ASPHALT		Sample Box Number: 2		MC 16%	
Source: BACHOUSE		Probe No: 3 Length: 3'		Ps/Pm .996	
Source Dimensions: 3 1/2" x 27 1/2"		Pitot No: 3 Coefficient: 0.841		C 2.0	
Test Team: JT/BK/AC		Nozzle No: 6 Diameter: .188		Ts 220	
Test Procedures: EPA 1-5 ; 9		Filter No: 103		R -	
Ambient Temp., °F: 70°		Barometric Pressure, in.Hg: 30.041		Static Pressure, in.WC: -1.7	

[illegible]

IMPINGER	1	2	3	4	5
Final	297	130	1	704.4	
Initial	100	100	0	691.2	
Net	197	30	1	13.2	
Total Moisture Collected:			241.2		
Impinger Catch Description:			CLC30		

Time	Rate, dcfm	Vac, in. Hg
8:11	0.000	15
10:29	0.000	6

Total Volume of Gas Sampled, DCF:	53.237
Total Sampling Time, Min:	70
Filter Catch Description	VERY LIGHT TAN

[illegible]

Form SST5, Revised 12/28/92

Signature
of Sampling
Team Leader:

Aggregate Positive - 1.54%

SOURCE EMISSION TEST FIELD DATA SHEET

TEST: 1 RUN: 3

PAGE: 1 of 2

TEST IDENTIFICATION		EQUIPMENT IDENTIFICATION		NOMOGRAPH SETTINGS	
TCT Project Number: 4232-93-2677		Control Unit Number: 1		ohm 2.04/16	
Date: 8/17/93		Gas Meter Coefficient: 1.0075		Tm 80°	
Company: NORTHERN ASPHALT		Sample Box Number: 3		MC 16.9%	
Source: BATHHOUSE		Probe No: 3 Length: 3'		Ps/Pm -9.96	
Source Dimensions: 3 1/2" x 27 1/2"		Pitot No: 3 Coefficient: 0.84		C 2.0	
Test Team: JT/BL/DC		Nozzle No: 6 Diameter: .188		Ts 220	
Test Procedures: EPA 1-5 + 9		Filter No: 104		R -	
Ambient Temp., °F: 74°		Barometric Pressure, in.Hg: 30.08		Static Pressure, in.WC: -1.7	

EPA METHOD 5 TRAVERSE DATA

CLOCK TIME hours	TRAVERSE POINT NUMBER	SAMPLE TIME minute	SAMPLE VOLUME cu.ft.	VELOCITY HEAD in.WC	ORIFICE in.WC		PUMP VAC. inHG	TEMPERATURE, °F							
					REQ.	ACT.		STACK GAS	PROBE LINER	FILTER OVEN	IMPINGER EXIT	AUXILIARY	GAS METER		
														IN	OUT
11:03	A1	0	887.500	2.3	2.0	2.0	3.5	205	259	255	64	-		89	87
	2	2.5	86.3	2.3	2.9	2.9	5.0	208	259	255	58	-		89	87
	3	5	88.3	3.1	2.8	2.8	5.0	217	259	254	54	-		89	87
	4	7.5	90.5	2.4	2.6	2.6	4.0	220	260	256	54	-		90	88
	5	10	92.4	2.4	2.6	2.6	4.0	222	260	255	56	-		92	88
	6	12.5	94.4	2.6	2.3	2.3	4.0	223	260	256	57	-		93	88
	7	15	96.3	2.8	2.8	2.4	4.0	223	261	256	58	-		94	88
	END A	17.5	98.3	X	X	X	X	X	X	X	X	X	X	X	X
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
	B1	0	98.3	2.7	2.4	2.4	4.0	225	261	256	60	-		94	89
	2	2.5	900.3	3.1	2.8	2.8	5.0	220	260	255	58	-		96	90
	3	5	2.4	3.0	2.7	2.7	5.0	223	261	255	58	-		97	90
	4	7.5	4.6	2.3	2.0	2.0	4.0	225	260	256	59	-		98	90
	5	10	6.4	2.6	2.3	2.3	4.0	225	260	256	59	-		98	91
	6	12.5	8.4	2.7	2.4	2.4	4.0	223	255	256	59	-		99	91
	7	15	10.3	2.5	2.3	2.3	4.0	223	259	256	58	-		99	92
	END B	17.5	12.3	X	X	X	X	X	X	X	X	X	X	X	X
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
	C1	0	12.3	2.8	2.4	2.4	4.0	226	258	257	60	-		98	92
	2	2.5	14.3	2.9	2.6	2.6	4.5	221	260	256	60	-		100	93
	3	5	16.3	2.9	2.6	2.6	4.5	222	261	256	60	-		100	93
	4	7.5	18.4	2.2	2.0	2.0	4.0	226	260	256	60	-		101	93
	5	10	20.2	2.2	2.0	2.0	4.0	227	260	255	60	-		101	94
	6	12.5	22.1	2.4	2.2	2.2	4.0	225	260	256	60	-		101	94
	7	15	24.0	2.4	2.2	2.2	4.0	225	260	255	60	-		101	94
	END C	17.5	25.8	X	X	X	X	X	X	X	X	X	X	X	X

EPA METHOD 4: MOISTURE DETERMINATION

IMPINGER	1	2	3	4	5
Final	274	136	1	705.0	X
Initial	100	100	0	691.9	X
Net	174	36	1	13.1	X

Total Moisture Collected: 224.1

Impinger Catch Description: CLETA

EPA METHOD 5 LEAK CHECK

Time	Rate, dcfm	Vac, in.Hg
10:47	0.000	15
11:18	0.000	6

Total Volume of Gas Sampled, DCF: 55.154

Total Sampling Time, Min: 70

Filter Catch Description:

Very LIGHT TAN

EPA METHOD 3: GAS COMPOSITION BY ORSAT ANALYSIS

Sample Identification	Replicate 1		Replicate 2		Replicate 3		Replicate 4		Compound Average Percent Volume
	Buret Reading	Percent Volume	Buret Reading	Percent Volume	Buret Reading	Percent Volume	Buret Reading	Percent Volume	
Initial Reading									
Carbon Dioxide	5.6	3.2	3.1	3.1	3.0	3.0	X	X	3.10
Oxygen	19.4	16.2	19.5	16.4	19.5	16.5	X	X	16.37
Carbon Monoxide	0	0	0	0	0	0	X	X	0

Form SS75, Revised 12/28/92

Signature of Sampling Team Leader:

AGRICULTURAL MOISTURE - 1.24%

TWIN CITY TESTING CORPORATION

SOURCE EMISSION TEST FIELD DATA SHEET

TEST: 1 RUN: 3

PAGE: 2 of 2

TEST IDENTIFICATION		EQUIPMENT IDENTIFICATION		NOMOGRAPH SETTINGS	
TCT Project Number:	4232-93-2677	Control Unit Number:	1	ohd	2.0416
Date:	5/12/93	Gas Meter Coefficient:	1.0075	Im	80%
Company:	NORTHSTAR ASPHALT	Sample Box Number:	3	MC	16.46
Source:	BAGHOUSE	Probe No:	3	Length:	3'
Source Dimensions:	3' 1/4" x 27' 1/2"	Pitot No:	3	Coefficient:	0.84
Test Team:	JT/BK/OL	Nozzle No:	6	Diameter:	1.88
Test Procedures:	EPA 1-5 & 9	Filter No:	104		
Ambient Temp., °F:	74	Barometric Pressure, in.Hg:	30.08	Static Pressure, in.WC:	-1.7

EPA METHOD 5 TRAVERSE DATA

CLOCK TIME hours	TRAVERSE POINT NUMBER	SAMPLE TIME minute	SAMPLE VOLUME cu.ft.	VELOCITY HEAD in.WC	ORIFICE		PUMP VAC. in.Hg	TEMPERATURE, °F						GAS METER	
					REQ.	ACT.		STACK GAS	PROBE LINER	FILTER OVEN	IMPINGER EXIT	AUXILIARY		IN	OUT
	1	0	25.8	2.0	1.8	1.8	3.5	210	260	255	60	-		102	96
	2	2.5	27.5	2.5	2.3	2.3	4.0	215	258	256	61	-		101	95
	3	5	29.4	2.3	2.0	2.0	4.0	222	260	255	60	-		103	96
	4	7.5	31.2	2.0	1.8	1.8	3.5	224	259	255	60	-		102	96
	5	10	33.0	1.5	1.3	1.3	3.0	224	259	255	61	-		102	96
	6	12.5	34.5	1.6	1.4	1.4	3.0	223	260	256	62	-		102	97
	7	15	36.0	1.7	1.5	1.5	3.0	223	260	256	62	-		102	97
12:16	END	17.5	937.654												

EPA METHOD 4: MOISTURE DETERMINATION

IMPINGER	1	2	3	4	5
Final	274	136	1	705.0	
Initial	100	100	0	691.9	
Net	174	36	1	13.1	

Total Moisture Collected: 224.1

Impinger Catch Description: OCEAN

EPA METHOD 5 LEAK CHECK

Time	Rate, dcfm	Vac, in.Hg
10:41	0.000	15
12:18	0.000	6

Total Volume of Gas Sampled, DCF: 53.154

Total Sampling Time, Min: 70

Filter Catch Description: Very Light Tan

EPA METHOD 3: GAS COMPOSITION BY ORSAT ANALYSIS

Sample Identification	Replicate 1		Replicate 2		Replicate 3		Replicate 4		Compound Average Percent Volume
	Buret Reading	Percent Volume	Buret Reading	Percent Volume	Buret Reading	Percent Volume	Buret Reading	Percent Volume	
Initial Reading									
Carbon Dioxide	3.2	3.2	3.1	3.1	3.0	3.0			3.10
Oxygen	19.4	16.2	19.5	16.4	19.5	16.5			16.37
Carbon Monoxide	0	0	0	0	0	0			0

Form SST5, Revised 12/28/92


Signature of Sampling Team Leader:

Aggregate Moisture - 1.74%


twin city testing
 corporation

Visible Emission Observation Form

SOURCE NAME				OBSERVATION DATE				START TIME				STOP TIME			
NORTHERN ASPHALT				8-17-93				6:32				7:32			
ADDRESS				SEC				SEC							
11064 Avenue Rd. N.E.				MIN				MIN							
				0 15 30 45				0 15 30 45							
CITY				1				31							
Blaine				0 0 0 0				0 0 0 0							
STATE				2				32							
MN				0 0 0 0				0 0 0 0							
ZIP				3				33							
55434				0 0 0 0				0 0 0 0							
PHONE				4				34							
284-1805				0 0 0 0				0 0 0 0							
SOURCE ID NUMBER				5				35							
1059-93-6-1				0 0 0 0				0 0 0 0							
PROCESS EQUIPMENT				6				36							
ASPHALT PLANT				0 0 0 0				0 0 0 0							
OPERATING MODE				7				37							
130 T/H				0 0 0 0				0 0 0 0							
CONTROL EQUIPMENT				8				38							
BAG HOUSE				0 0 0 0				0 0 0 0							
OPERATING MODE				9				39							
100 %				0 0 0 0				0 0 0 0							
DESCRIBE EMISSION POINT				10				40							
START EXHAUST STACK STOP EXHAUST STACK				0 0 0 0				0 0 0 0							
HEIGHT ABOVE GROUND LEVEL				11				41							
START 40' STOP 40'				0 0 0 0				0 0 0 0							
HEIGHT RELATIVE TO OBSERVER				12				42							
START 37' STOP 37'				0 0 0 0				0 0 0 0							
DISTANCE FROM OBSERVER				13				43							
START 120' STOP				0 0 0 0				0 0 0 0							
DIRECTION FROM OBSERVER				14				44							
START WEST STOP				0 0 0 0				0 0 0 0							
DESCRIBE EMISSIONS				15				45							
START WHITE STOP WHITE				0 0 0 0				0 0 0 0							
EMISSION COLOR				16				46							
START WHITE STOP WHITE				0 0 0 0				0 0 0 0							
PLUME TYPE: CONTINUOUS ☒				17				47							
FUGITIVE ☐ INTERMITTENT ☐				0 0 0 0				0 0 0 0							
WATER DROPLETS PRESENT:				18				48							
NO ☐ YES ☒				0 0 0 0				0 0 0 0							
IF WATER DROPLET PLUME:				19				49							
ATTACHED ☒ DETACHED ☐				0 0 0 0				0 0 0 0							
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED				20				50							
START END OF TRAIL STOP SAME				0 0 0 0				0 0 0 0							
DESCRIBE BACKGROUND				21				51							
START BLUE SKY STOP BLUE SKY				0 0 0 0				0 0 0 0							
BACKGROUND COLOR				22				52							
START BLUE STOP				0 0 0 0				0 0 0 0							
SKY CONDITIONS				23				53							
START CLEAR STOP				0 0 0 0				0 0 0 0							
WIND SPEED				24				54							
START 0-5 STOP				0 0 0 0				0 0 0 0							
WIND DIRECTION				25				55							
START NE STOP				0 0 0 0				0 0 0 0							
AMBIENT TEMP.				26				56							
START 62 STOP 69				0 0 0 0				0 0 0 0							
WET BULB TEMP.				27				57							
30°				0 0 0 0				0 0 0 0							
RH, percent				28				58							
82				0 0 0 0				0 0 0 0							
29				0 0 0 0				0 0 0 0							
30				0 0 0 0				0 0 0 0							
31				0 0 0 0				0 0 0 0							
32				0 0 0 0				0 0 0 0							
33				0 0 0 0				0 0 0 0							
34				0 0 0 0				0 0 0 0							
35				0 0 0 0				0 0 0 0							
36				0 0 0 0				0 0 0 0							
37				0 0 0 0				0 0 0 0							
38				0 0 0 0				0 0 0 0							
39				0 0 0 0				0 0 0 0							
40				0 0 0 0				0 0 0 0							
41				0 0 0 0				0 0 0 0							
42				0 0 0 0				0 0 0 0							
43				0 0 0 0				0 0 0 0							
44				0 0 0 0				0 0 0 0							
45				0 0 0 0				0 0 0 0							
46				0 0 0 0				0 0 0 0							
47				0 0 0 0				0 0 0 0							
48				0 0 0 0				0 0 0 0							
49				0 0 0 0				0 0 0 0							
50				0 0 0 0				0 0 0 0							
51				0 0 0 0				0 0 0 0							
52				0 0 0 0				0 0 0 0							
53				0 0 0 0				0 0 0 0							
54				0 0 0 0				0 0 0 0							
55				0 0 0 0				0 0 0 0							
56				0 0 0 0				0 0 0 0							
57				0 0 0 0				0 0 0 0							
58				0 0 0 0				0 0 0 0							
59				0 0 0 0				0 0 0 0							
60				0 0 0 0				0 0 0 0							
AVERAGE OPACITY FOR HIGHEST PERIOD				0				NUMBER OF READINGS ABOVE 20% WERE				0			
RANGE OF OPACITY READINGS				0% MINIMUM				0% MAXIMUM							
OBSERVER'S NAME (PRINT)				DAVID R. CHRISTIAN											
OBSERVER'S SIGNATURE				David R. Christian				DATE				8-17-93			
ORGANIZATION				TWIN CITY TESTING											
I HAVE RECEIVED A COPY OF THESE OPACITY OBSERVATIONS				CERTIFIED BY				DATE							
SIGNATURE				ETA				8-1-93							
TITLE				DATE				VERIFIED BY				DATE			



Visible Emission Observation Form

SOURCE NAME NORTHEAN ASPHALT			OBSERVATION DATE 8-17-93		START TIME 9:20		STOP TIME 10:20																																																																																																																																																																																																																																																																																																																	
ADDRESS 11064 Agassiz Ave. NE			SEC MIN	0	15	30	45	SEC MIN	0	15	30	45																																																																																																																																																																																																																																																																																																												
CITY BLAINE			STATE MN		ZIP 55434																																																																																																																																																																																																																																																																																																																			
PHONE 787-1805			SOURCE ID NUMBER 1059-43-6-1																																																																																																																																																																																																																																																																																																																					
PROCESS EQUIPMENT ASPHALT PLANT			OPERATING MODE 125 TPI																																																																																																																																																																																																																																																																																																																					
CONTROL EQUIPMENT BAG HOUSE			OPERATING MODE 100%																																																																																																																																																																																																																																																																																																																					
DESCRIBE EMISSION POINT START EXHAUST STACK STOP SAME																																																																																																																																																																																																																																																																																																																								
HEIGHT ABOVE GROUND LEVEL START 41' STOP 41'			HEIGHT RELATIVE TO OBSERVER START 34' STOP 34'																																																																																																																																																																																																																																																																																																																					
DISTANCE FROM OBSERVER START 120' STOP 120'			DIRECTION FROM OBSERVER START WEST STOP SAME																																																																																																																																																																																																																																																																																																																					
DESCRIBE EMISSIONS START CLEAR STOP SAME																																																																																																																																																																																																																																																																																																																								
EMISSION COLOR START CLEAR STOP CLEAR			PLUME TYPE: CONTINUOUS ☒ FUGITIVE ☐ INTERMITTENT ☐																																																																																																																																																																																																																																																																																																																					
WATER DROPLETS PRESENT: NO ☒ YES ☐			IF WATER DROPLET PLUME: ATTACHED ☐ DETACHED ☐																																																																																																																																																																																																																																																																																																																					
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED START 3' ABOVE STACK STOP SAME																																																																																																																																																																																																																																																																																																																								
DESCRIBE BACKGROUND START SKY STOP SKY																																																																																																																																																																																																																																																																																																																								
BACKGROUND COLOR START BLUE STOP BLUE			SKY CONDITIONS START CLEAR STOP CLEAR																																																																																																																																																																																																																																																																																																																					
WIND SPEED START 5-10 STOP 5-10			WIND DIRECTION START S.E. STOP S.E.																																																																																																																																																																																																																																																																																																																					
AMBIENT TEMP. START 74 STOP 79			WET BULB TEMP. 68		RH. percent 73																																																																																																																																																																																																																																																																																																																			
Source Layout Sketch			<table border="1"> <tr><td>1</td><td>0</td><td>0</td><td>0</td><td>0</td><td>31</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>2</td><td>0</td><td>0</td><td>0</td><td>0</td><td>32</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>3</td><td>0</td><td>0</td><td>0</td><td>0</td><td>33</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>4</td><td>0</td><td>0</td><td>0</td><td>0</td><td>34</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>5</td><td>0</td><td>0</td><td>0</td><td>0</td><td>35</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>6</td><td>0</td><td>0</td><td>0</td><td>0</td><td>36</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>7</td><td>0</td><td>0</td><td>0</td><td>0</td><td>37</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>8</td><td>0</td><td>0</td><td>0</td><td>0</td><td>38</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>9</td><td>0</td><td>0</td><td>0</td><td>0</td><td>39</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>10</td><td>0</td><td>0</td><td>0</td><td>0</td><td>40</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>11</td><td>0</td><td>0</td><td>0</td><td>0</td><td>41</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>12</td><td>0</td><td>0</td><td>0</td><td>0</td><td>42</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>13</td><td>0</td><td>0</td><td>0</td><td>0</td><td>43</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>14</td><td>0</td><td>0</td><td>0</td><td>0</td><td>44</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>15</td><td>0</td><td>0</td><td>0</td><td>0</td><td>45</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>16</td><td>0</td><td>0</td><td>0</td><td>0</td><td>46</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>17</td><td>0</td><td>0</td><td>0</td><td>0</td><td>47</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>18</td><td>0</td><td>0</td><td>0</td><td>0</td><td>48</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>19</td><td>0</td><td>0</td><td>0</td><td>0</td><td>49</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>20</td><td>0</td><td>0</td><td>0</td><td>0</td><td>50</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>21</td><td>0</td><td>0</td><td>0</td><td>0</td><td>51</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>22</td><td>0</td><td>0</td><td>0</td><td>0</td><td>52</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>23</td><td>0</td><td>0</td><td>0</td><td>0</td><td>53</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>24</td><td>0</td><td>0</td><td>0</td><td>0</td><td>54</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>25</td><td>0</td><td>0</td><td>0</td><td>0</td><td>55</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>26</td><td>0</td><td>0</td><td>0</td><td>0</td><td>56</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>27</td><td>0</td><td>0</td><td>0</td><td>0</td><td>57</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>28</td><td>0</td><td>0</td><td>0</td><td>0</td><td>58</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>29</td><td>0</td><td>0</td><td>0</td><td>0</td><td>59</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> <tr><td>30</td><td>0</td><td>0</td><td>0</td><td>0</td><td>60</td><td>0</td><td>0</td><td>0</td><td>0</td></tr> </table>										1	0	0	0	0	31	0	0	0	0	2	0	0	0	0	32	0	0	0	0	3	0	0	0	0	33	0	0	0	0	4	0	0	0	0	34	0	0	0	0	5	0	0	0	0	35	0	0	0	0	6	0	0	0	0	36	0	0	0	0	7	0	0	0	0	37	0	0	0	0	8	0	0	0	0	38	0	0	0	0	9	0	0	0	0	39	0	0	0	0	10	0	0	0	0	40	0	0	0	0	11	0	0	0	0	41	0	0	0	0	12	0	0	0	0	42	0	0	0	0	13	0	0	0	0	43	0	0	0	0	14	0	0	0	0	44	0	0	0	0	15	0	0	0	0	45	0	0	0	0	16	0	0	0	0	46	0	0	0	0	17	0	0	0	0	47	0	0	0	0	18	0	0	0	0	48	0	0	0	0	19	0	0	0	0	49	0	0	0	0	20	0	0	0	0	50	0	0	0	0	21	0	0	0	0	51	0	0	0	0	22	0	0	0	0	52	0	0	0	0	23	0	0	0	0	53	0	0	0	0	24	0	0	0	0	54	0	0	0	0	25	0	0	0	0	55	0	0	0	0	26	0	0	0	0	56	0	0	0	0	27	0	0	0	0	57	0	0	0	0	28	0	0	0	0	58	0	0	0	0	29	0	0	0	0	59	0	0	0	0	30	0	0	0	0	60	0	0	0	0
1	0	0	0	0	31	0	0	0	0																																																																																																																																																																																																																																																																																																															
2	0	0	0	0	32	0	0	0	0																																																																																																																																																																																																																																																																																																															
3	0	0	0	0	33	0	0	0	0																																																																																																																																																																																																																																																																																																															
4	0	0	0	0	34	0	0	0	0																																																																																																																																																																																																																																																																																																															
5	0	0	0	0	35	0	0	0	0																																																																																																																																																																																																																																																																																																															
6	0	0	0	0	36	0	0	0	0																																																																																																																																																																																																																																																																																																															
7	0	0	0	0	37	0	0	0	0																																																																																																																																																																																																																																																																																																															
8	0	0	0	0	38	0	0	0	0																																																																																																																																																																																																																																																																																																															
9	0	0	0	0	39	0	0	0	0																																																																																																																																																																																																																																																																																																															
10	0	0	0	0	40	0	0	0	0																																																																																																																																																																																																																																																																																																															
11	0	0	0	0	41	0	0	0	0																																																																																																																																																																																																																																																																																																															
12	0	0	0	0	42	0	0	0	0																																																																																																																																																																																																																																																																																																															
13	0	0	0	0	43	0	0	0	0																																																																																																																																																																																																																																																																																																															
14	0	0	0	0	44	0	0	0	0																																																																																																																																																																																																																																																																																																															
15	0	0	0	0	45	0	0	0	0																																																																																																																																																																																																																																																																																																															
16	0	0	0	0	46	0	0	0	0																																																																																																																																																																																																																																																																																																															
17	0	0	0	0	47	0	0	0	0																																																																																																																																																																																																																																																																																																															
18	0	0	0	0	48	0	0	0	0																																																																																																																																																																																																																																																																																																															
19	0	0	0	0	49	0	0	0	0																																																																																																																																																																																																																																																																																																															
20	0	0	0	0	50	0	0	0	0																																																																																																																																																																																																																																																																																																															
21	0	0	0	0	51	0	0	0	0																																																																																																																																																																																																																																																																																																															
22	0	0	0	0	52	0	0	0	0																																																																																																																																																																																																																																																																																																															
23	0	0	0	0	53	0	0	0	0																																																																																																																																																																																																																																																																																																															
24	0	0	0	0	54	0	0	0	0																																																																																																																																																																																																																																																																																																															
25	0	0	0	0	55	0	0	0	0																																																																																																																																																																																																																																																																																																															
26	0	0	0	0	56	0	0	0	0																																																																																																																																																																																																																																																																																																															
27	0	0	0	0	57	0	0	0	0																																																																																																																																																																																																																																																																																																															
28	0	0	0	0	58	0	0	0	0																																																																																																																																																																																																																																																																																																															
29	0	0	0	0	59	0	0	0	0																																																																																																																																																																																																																																																																																																															
30	0	0	0	0	60	0	0	0	0																																																																																																																																																																																																																																																																																																															
COMMENTS			AVERAGE OPACITY FOR HIGHEST PERIOD 0%		NUMBER OF READINGS ABOVE 20% WERE 0																																																																																																																																																																																																																																																																																																																			
			RANGE OF OPACITY READINGS 0% MINIMUM		0% MAXIMUM																																																																																																																																																																																																																																																																																																																			
			OBSERVER'S NAME (PRINT) DAVID L. CHRISTIAN																																																																																																																																																																																																																																																																																																																					
			OBSERVER'S SIGNATURE <i>David L. Christian</i>		DATE 8-17-93																																																																																																																																																																																																																																																																																																																			
			ORGANIZATION TWIN CITY TESTING																																																																																																																																																																																																																																																																																																																					
I HAVE RECEIVED A COPY OF THESE OPACITY OBSERVATIONS			CERTIFIED BY E.T.A.		DATE 8-1-93																																																																																																																																																																																																																																																																																																																			
SIGNATURE			VERIFIED BY		DATE																																																																																																																																																																																																																																																																																																																			
TITLE			DATE		DATE																																																																																																																																																																																																																																																																																																																			

Visible Emission Observation Form

SOURCE NAME			OBSERVATION DATE				START TIME				STOP TIME			
NORTHERN ASPHALT			8-17-93				11:07				12:04			
ADDRESS			SEC				SEC							
11064 Ardenwood M.D.			MIN				MIN							
			0 15 30 45				0 15 30 45							
CITY			STATE				ZIP							
B.L.G.W.			M.D.				55434							
PHONE			SOURCE ID NUMBER											
781-185			1059-93-0-1											
PROCESS EQUIPMENT			OPERATING MODE											
ASPHALT PLANT			125 T/H											
CONTROL EQUIPMENT			OPERATING MODE											
BAG HOUSE			100											
DESCRIBE EMISSION POINT														
START EXHAUST STACK STOP SAME														
HEIGHT ABOVE GROUND LEVEL			HEIGHT RELATIVE TO OBSERVER											
START 40' STOP 40'			START 34' STOP 34'											
DISTANCE FROM OBSERVER			DIRECTION FROM OBSERVER											
START 120' STOP 120'			START 120' WEST STOP SAME											
DESCRIBE EMISSIONS														
START CLEAR STOP CLEAR														
EMISSION COLOR			PLUME TYPE: CONTINUOUS ☒											
START CLEAR STOP CLEAR			FUGITIVE ☐ INTERMITTENT ☐											
WATER DROPLETS PRESENT:			IF WATER DROPLET PLUME:											
NO ☒ YES ☐			ATTACHED ☐ DETACHED ☐											
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED														
START 3' ABOVE STACK STOP SAME														
DESCRIBE BACKGROUND														
START SKY STOP SKY														
BACKGROUND COLOR			SKY CONDITIONS											
START BLUE STOP BLUE			START CLEAR STOP CLEAR											
WIND SPEED			WIND DIRECTION											
START 5-10 STOP 5-10			START S.E. STOP S.E.											
AMBIENT TEMP.			WET BULB TEMP.				RH. percent							
START 79 STOP 83			74				78							
Source Layout Sketch			Draw North Arrow											
COMMENTS			AVERAGE OPACITY FOR HIGHEST PERIOD				NUMBER OF READINGS ABOVE							
			0				20 % WERE				0			
			RANGE OF OPACITY READINGS											
			0% MINIMUM				0% MAXIMUM							
			OBSERVER'S NAME (PRINT)											
			DAVID L. CHRISTIAN											
			OBSERVER'S SIGNATURE				DATE							
			David L. Christian				8-17-93							
			ORGANIZATION											
			TWIN CITY TESTING											
I HAVE RECEIVED A COPY OF THESE OPACITY OBSERVATIONS			CERTIFIED BY				DATE							
SIGNATURE			E.T.A.				4-1-93							
TITLE			DATE				VERIFIED BY				DATE			

APPENDIX C
LABORATORY REPORTS

LABORATORY REPORT: EPA METHOD 5 PARTICULATE ANALYSIS

Project Number: 4232-93-2677	TEST	RUN
Client: Northern Asphalt	1	1

FILTER CATCH				
Sample Number: 324583		Filter Number: 102		
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-25-93	4:30	MJC	0.36351
Weight #1	8-25-93	8:50	MJC	0.36383
Filter Tare Weight			0.35074	
Net Sample Weight			0.01307	

WEIGHING PROCEDURE
Weighings shall be to the nearest 0.1 mg. Weighings shall be to "constant weight" which means a difference of no more than 0.5 mg between two consecutive weighings, with no less than six hours of desiccation time between weighings.

IMPINGER CATCH VOLUME
Measured Sample Volume, ml: 510
Estimated Volume Lost, ml:

FRONT WASH				
Sample Number: 324586		Measured Sample Volume, ml 113		Estimated Volume Lost, ml
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-25-93	4:40	MJC	2.63653
Weight #1	8-25-93	9:00	MJC	2.63662
Dish Tare	8-18-93	3:35	MJC	2.61900
Weight of collected matter			0.01753	
Water Blank based on 56.5 ml			ND	
Acetone Blank based on 56.5 ml			0.00027	
Net Sample Weight			0.01726	

IMPINGER CATCH ORGANIC EXTRACTION				
Sample Number: 324588				
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-25-93	4:45	MJC	2.64732
Weight #1	8-25-93	9:05	MJC	2.64720
Dish Tare	8-18-93	3:35	MJC	2.63280
Weight of collected matter			0.01456	
Less Solvent Blanks				
Ethyl Ether based on 75 ml			0.00050	
Chloroform based on 75 ml			0.00023	
			based on ml	
Net Sample Weight			0.01397	

IMPINGER ACETONE RINSE				
Sample Number: 324587		Measured Sample Volume, ml 110		Estimated Volume Lost, ml
Date	Time	By	grams	
Weight #3				
Weight #2	8-25-93	4:45	MJC	2.63432
Weight #1	8-25-93	9:05	MJC	2.63436
Dish Tare	8-18-93	3:35	MJC	2.62690
Weight of collected matter			0.00742	
Acetone Blank based on 110 ml			0.00053	
Net Sample Weight			0.00689	

IMPINGER CATCH MASS RESIDUE				
Sample Number:				
Date	Time	By	grams	
Weight #5				
Weight #4				
Weight #3				
Weight #2				
Weight #1				
Dish Tare				
Weight of collected matter				
Water Blank based on ml				
Net Sample Weight				

Form: SST-LAB52C

LABORATORY REPORT: EPA METHOD 5 PARTICULATE ANALYSIS

Project Number: 4232-93-2677	TEST	RUN
Client: Northern Asphalt	1	2

FILTER CATCH				
Sample Number: 324584		Filter Number: 103		
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-25-93	4:30	MKC	0.36342
Weight #1	8-25-93	8:50	MKC	0.36351
Filter Tare Weight				0.35014
Net Sample Weight				0.01328

WEIGHING PROCEDURE
Weighings shall be to the nearest 0.1 mg. Weighings shall be to "constant weight" which means a difference of no more than 0.5 mg between two consecutive weighings, with no less than six hours of desiccation time between weighings.

IMPINGER CATCH VOLUME
Measured Sample Volume, ml: 504
Estimated Volume Lost, ml:

FRONT WASH				
Sample Number: 324589		Measured Sample Volume, ml 93		Estimated Volume Lost, ml
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-25-93	4:30	MKC	2.61552
Weight #1	8-25-93	8:55	MKC	2.61545
Dish Tare	8-18-93	3:40	MKC	2.60027
Weight of collected matter				0.01525
Water Blank based on 46.5 ml				ND
Acetone Blank based on 46.5 ml				0.00022
Net Sample Weight				0.01503

IMPINGER CATCH ORGANIC EXTRACTION				
Sample Number: 324591				
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-25-93	4:45	MKC	2.61582
Weight #1	8-25-93	9:10	MKC	2.64690
Dish Tare	8-18-93	3:40	MKC	2.63825
Weight of collected matter				0.00825
Less Solvent Blanks				
Ethyl Ether	based on 75 ml		0.00006	
Chloroform	based on 75 ml		0.00023	
				based on ml
Net Sample Weight				0.00798

IMPINGER ACETONE RINSE				
Sample Number: 324590		Measured Sample Volume, ml 91		Estimated Volume Lost, ml
Date	Time	By	grams	
Weight #3				
Weight #2	8-25-93	4:50	MKC	2.63560
Weight #1	8-25-93	9:10	MKC	2.63569
Dish Tare	8-18-93	3:40	MKC	2.63302
Weight of collected matter				0.00258
Acetone Blank based on 91 ml				0.00044
Net Sample Weight				0.00214

IMPINGER CATCH MASS RESIDUE				
Sample Number:				
Date	Time	By	grams	
Weight #5				
Weight #4				
Weight #3				
Weight #2				
Weight #1				
Dish Tare				
Weight of collected matter				
Water Blank based on ml				
Net Sample Weight				

Form: SST-LAB52C

LABORATORY REPORT: EPA METHOD 5 PARTICULATE ANALYSIS

Project Number: 4232- 93-2677	TEST 1	RUN 3
Client: Northern Asphalt		

FILTER CATCH				
Sample Number: 324585		Filter Number: 104		
	Date	Time	By	grams
Weight #4				
Weight #3	8-25-93	4:30	MKC	0.36515
Weight #2	8-25-93	8:50	MKC	0.36510
Weight #1	8-25-93	8:50	MKC	0.36510
Filter Tare Weight				0.34975
Net Sample Weight				0.01540

WEIGHING PROCEDURE
Weighings shall be to the nearest 0.1 mg. Weighings shall be to "constant weight" which means a difference of no more than 0.5 mg between two consecutive weighings, with no less than six hours of desiccation time between weighings.

IMPINGER CATCH VOLUME
Measured Sample Volume, ml: 515
Estimated Volume Lost, ml:

FRONT WASH				
Sample Number: 324592		Measured Sample Volume, ml 98		Estimated Volume Lost, ml
	Date	Time	By	grams
Weight #4				
Weight #3				
Weight #2	8-25-93	4:35	MKC	2.64496
Weight #1	8-25-93	8:55	MKC	2.64472
Dish Tare	8-18-93	3:45	MKC	2.62719
Weight of collected matter				0.01777
Water Blank based on 49 ml				ND
Acetone Blank based on 49 ml				0.00024
Net Sample Weight				0.01753

IMPINGER CATCH ORGANIC EXTRACTION				
Sample Number: 324594				
	Date	Time	By	grams
Weight #4				
Weight #3				
Weight #2	8-25-93	4:50	MKC	2.61657
Weight #1	8-25-93	9:10	MKC	2.61650
Dish Tare	8-18-93	3:45	MKC	2.61087
Weight of collected matter				0.00570
Less Solvent Blanks				
Ethyl Ether	based on 75 ml			0.00036
Chloroform	based on 75 ml			0.00023
	based on ml			
Net Sample Weight				0.00511

IMPINGER ACETONE RINSE				
Sample Number: 324593		Measured Sample Volume, ml 91		Estimated Volume Lost, ml
	Date	Time	By	grams
Weight #3				
Weight #2	8-25-93	4:35	MKC	2.65087
Weight #1	8-25-93	8:55	MKC	2.65075
Dish Tare	8-18-93	3:45	MKC	2.64806
Weight of collected matter				0.00281
Acetone Blank based on 91 ml				0.00044
Net Sample Weight				0.00237

IMPINGER CATCH MASS RESIDUE				
Sample Number:				
	Date	Time	By	grams
Weight #5				
Weight #4				
Weight #3				
Weight #2				
Weight #1				
Dish Tare				
Weight of collected matter				
Water Blank based on ml				
Net Sample Weight				

Form: SST-LAB52C

LABORATORY REPORT: EPA METHOD 5 PARTICULATE TEST SOLVENT BLANKS

Project Number: 4232-93-2677	TEST 1
Client: Northern Asphalt	

DISTILLED, DEIONIZED WATER				
Sample Number:	Measured Sample Volume, ml		Estimated Volume Lost, ml	
324595	200			
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-27-93	7:50	MXL	3.48816
Weight #1	8-26-93	4:25	MXL	3.48658
Dish Tare	8-18-93	3:25	MLC	3.49109
Weight of residual matter				ND
Mass Concentration:				ND mg/ml

ACETONE				
Sample Number:	Measured Sample Volume, ml		Estimated Volume Lost, ml	
324596	186			
Date	Time	By	grams	
Weight #4				
Weight #3	8-27-93	2:20	MXL	3.5623
Weight #2	8-27-93	7:50	MXL	3.7947
Weight #1	8-26-93	4:25	MXL	3.80078
Dish Tare	8-18-93	3:25	MLC	3.79928
Weight of residual matter				0.00095
Mass Concentration:				4.85 mg/ml

CHLOROFORM				
Sample Number:	Measured Sample Volume, ml		Estimated Volume Lost, ml	
324597	75			
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-25-93	4:40	MXL	2.63071
Weight #1	8-25-93	9:00	MXL	2.63058
Dish Tare	8-18-93	3:30	MLC	2.63048
Weight of residual matter				0.00023
Mass Concentration:				3.07 mg/ml

ETHYL ETHER				
Sample Number:	Measured Sample Volume, ml		Estimated Volume Lost, ml	
324598	75			
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2	8-25-93	4:40	MXL	2.61164
Weight #1	8-25-93	9:00	MXL	2.61163
Dish Tare	8-18-93	3:30	MLC	2.61128
Weight of residual matter				0.00036
Mass Concentration:				4.8 mg/ml

Sample Number:	Measured Sample Volume, ml		Estimated Volume Lost, ml	
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2				
Weight #1				
Dish Tare				
Weight of residual matter				
Mass Concentration:				mg/ml

Sample Number:	Measured Sample Volume, ml		Estimated Volume Lost, ml	
Date	Time	By	grams	
Weight #4				
Weight #3				
Weight #2				
Weight #1				
Dish Tare				
Weight of residual matter				
Mass Concentration:				mg/ml

Form: SST-LAB53C

Job Name: EIH-N-ASPH.1
 Description: 4232-93-2677 TOTAL PARTIC.
 Invoice: 4410_03-2216
 Printed: 18-AUG-1993 15:07

Date Created: 18-AUG-1993
 Login by: MICROSCOPY
 Project Alert: None
 Job Due Date: 1-SEP-1993

Rot & Bill to: Northern Asphalt
 Customer Inv/PO: 4232-93-2677

Sample Number	Customer Sample Description	ISI ICI	Date Smpld / Rec'd	IPI Inl	Sample Matrix	A N A L Y S E S	S T O R A G E
324563	11-1 FILTER 102	IVI	/18-AUG	131	FILTER	PARTICULAT	EIH
324584	11-2 FILTER 103	IVI	/18-AUG	131	FILTER	PARTICULAT	EIH
324585	11-3 FILTER 104	IVI	/18-AUG	131	FILTER	PARTICULAT	EIH
324566	11-1 PROBE WASH	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324587	11-1 ACETONE RINSE	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324588	11-1 IMPINGER CATCH	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324589	11-2 PROBE WASH	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324590	11-2 ACETONE RINSE	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324591	11-2 IMPINGER CATCH	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324592	11-3 PROBE WASH	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324593	11-3 ACETONE RINSE	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324594	11-3 IMPINGER CATCH	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324595	WATER BLANK	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324596	ACETONE BLANK	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324597	CHLOROFORM BLANK	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH
324598	ETHER BLANK	IVI	/18-AUG	131	LIQUID	PARTICULAT	EIH

Paula Crowley has 16 tests assigned to 16 samples.

Status Codes: V = available W = awaiting prep P = in progress C = completed A = authorized
 H = hold S = suspended X = cancelled U = unavailable

Remarks:

RESULTS TO JIM TRYBA

Sample remarks:



739 VANDALIA ST.
ST. PAUL, MN 55114
(612) 642-1150
FAX (612) 642-1239

September 3, 1993

Mr. Jeff Dusenka
Northern Asphalt
11064 Radison Road
Minneapolis, MN 55434

SUBJECT: Bag House
LEGEND No. 93-1459

1.0 INTRODUCTION

LEGEND TECHNICAL SERVICES, INC. (LEGEND) received three oil samples from a representative of Northern Asphalt on August 19, 1993. Our laboratory was requested to analyze the samples for the presence of polychlorinated biphenyls, total organic halogens, flashpoint, lead, BTU, percent sulfur, and percent ash.

2.0 DISCUSSION

The sample analysis indicated the presence of some of the analytes requested.

3.0 SAMPLE IDENTIFICATION

Laboratory No.

Client ID

SN93-14413

Bag House 1-1

SN93-14414

Bag House 1-2

SN93-14415

Bag House 1-3

4.0 METHODOLOGY

Lead

The samples were prepared and analyzed using EPA SW-846, Method 7420.

Flashpoint

The samples were analyzed by the Pensky Martens Method SW-846, method 1010.

Percent Ash

The samples were prepared and analyzed with methods based on ASTM D482-87.

SEP-23-1993 13:26 FROM Legend Technical Services TO

7841831 P.03

BTU/Sulfur

The samples were prepared and analyzed with methods based on ASTM D-2382-88.

Polychlorinated Biphenyls

The samples were prepared and analyzed with methods based on SW-846 8080.

Total Halogens

The samples were combusted in an oxygen bomb and the rinsate was analyzed using a chloride ion electrode.

5.0 CASE NARRATIVE

The associated method blanks were free of target analytes at detectable levels, and the associated batch quality assurance/quality control criteria were met with satisfaction.

6.0 REMARKS

The samples will be retained by our laboratory for 30 days from the date of this report and then discarded unless other instructions are received by the client.

Submitted by,

LEGEND TECHNICAL SERVICES, INC.

Chris Bremer (CB)
Chris Bremer
Laboratory Manager

Jeffery Zeake
Jeffery Zeake
Chemist

CB/TZ/11

Attachment

SEP-03-1993 13:26 FROM Legend Technical Services TO

7841831 P.04

LEGEND TECHNICAL SERVICES, INC.**TABLE #1****LEGEND No. 93-1459
NORTHERN ASPHALT
ANALYTICAL RESULTS**

Parameter	Bag House 1-1	Bag House 1-2	Bag House 1-3	MDL	Date Analyzed
BTU/lb	19,000	19,000	19,000	—	8/27/93 Btu/lb
Percent Sulfur	0.62	0.54	0.47	—	8/27/93 ✓
Percent Ash	0.43	0.42	0.42	—	8/24/93 ✓
Total Organic Halogens, mg/kg	280	260	420	50	8/31/93 ✓
Flashpoint	135° F	140° F	125° F	—	8/31/93 ✓
Lead, mg/kg	80 <i>ppm</i>	92	85	2.5	8/29/93 ✓

MDL - Method detection limit.

mg/kg is equal to parts per million.

< = Less than number shown.

LEGEND TECHNICAL SERVICES, INC.
TABLE #2
LEGEND No. 93-1459
NORTHERN ASPHALT
POLYCHLORINATED BIPHENYLS

Aroclor	Bag House 1-1 (mg/kg)	Bag House 1-2 (mg/kg)	Bag House 1-3 (mg/kg)	Method Blank (mg/kg)	MDL (mg/kg)
1016	<5.0	<5.0	<5.0	<5.0	5.0
1221	<5.0	<5.0	<5.0	<5.0	5.0
1232	<5.0	<5.0	<5.0	<5.0	5.0
1242	<1.0	<1.0	<1.0	<1.0	1.0
1248	<1.0	<1.0	<1.0	<1.0	1.0
1254	<1.0	<1.0	<1.0	<1.0	1.0
1260	<1.0	<1.0	<1.0	<1.0	1.0

Recovery Data

Percent Recovery

Spike #1

102%

Date Extracted: 9/01/93

Date Analyzed: 9/01/93

MDL = Method detection limit

mg/kg is equal to parts per million

LEGEND TECHNICAL SERVICES, INC.

739 Vandavia Street
St. Paul, MN 55114
(612)642-1150

CHAIN OF CUSTODY RECORD

TOTAL P. 86

#500 P06

TEL NO: 612 784 1831

SEP-07-'93 TUE 08:11 ID: NORTHERN ASPHALT

SEP-03-1993 13:27 FROM Legend Technical Services TO

7841831 P. 86

Client Name:		Verbal Results To:		Analysis / Parameters	
Report To:		Copy of Report To:		Sulfur Content	
Sample:		Sample Returned To:		Ash Content	
Project No.:		Laboratory Project No. 93-1459		Lead Content	
				PCB	
				Halogens, Organic	
				Gross Heating Value	
				Flashpoint	

Item #	Field ID #	Sample Description	Collection		Sample Matrix		Lab ID #	Analysis / Parameters								
			Date	Time	Air	Soil		Oil	Sulfur Content	Ash Content	Lead Content	PCB	Halogens, Organic	Gross Heating Value	Flashpoint	
1		Baghouse 1-1					oil	14413	X	X	X	X	X	X	X	X
2		Baghouse 1-2					oil	14414	X	X	X	X	X	X	X	X
3		Baghouse 1-3					oil	14415	X	X	X	X	X	X	X	X
4																
5																
6																
7																
8																
9																
10																
11																

Accepted By: <i>[Signature]</i>		Date: 8/10/93		Time: 8:10		Comments: See MPCA guidelines.	
Transfer No.	Item Number	Rechecked By	Accepted By	Date	Time	Comments	
1							
2							
3							
4							

11-10-93

APPENDIX D
CALIBRATION DATA



twin city testing
corporation

GAS METER AND ORIFICE CALIBRATION

Pretest calibration of TCT control unit #1 generated a gas meter coefficient of 1.0075. Post test calibration yielded a coefficient of 1.0083. Both sets of calibration data are included on the following pages. All calculations for tests performed using unit #1 were made using the lower (1.0075) calibration factor which produces worst case emission data.

PITOT TUBE CALIBRATION DATA

Pitot tube #3 is a Type S pitot tube which meets the design specifications described in EPA Method 2 and the base line coefficient of 0.84 was used.



ORIFICE and DRY GAS METER CALIBRATION FORM

Date: Jun 30, 1993		Meter # 1		Barometric Pressure, Pb: 29.98			
Orifice manometer setting dH, in. H ₂ O	Gas Wet test meter Vw, ft ³	Volume Dry gas meter Vd, ft ³	Wet test meter tw, dF	Temperature Dry gas meter			Time e, min.
				Inlet tdi, dF	Outlet tdo, dF	Average td, dF	
0.5	5.000	5.035	69	75	73	74.0	13.35
1.0	5.000	5.030	69	78	74	76.0	9.40
2.0	10.000	9.944	69	76	71	73.5	13.55
4.0	10.000	9.925	69	79	72	75.5	9.60
6.0	10.000	9.899	69	80	73	76.5	7.95
8.0	10.000	9.874	69	82	74	78.0	6.90

Y	dH _e
$\frac{Vw Pb (td + 460)}{Vd [Pb + (dH/13.6)] (tw + 460)}$	$\frac{0.0317 dH}{Pb (to + 460)} \left[\frac{(tw + 460) e}{Vw} \right]^2$
Yi 1 = 1.0012	dH _e i 1 = 1.9788
Yi 2 = 1.0047	dH _e i 2 = 1.9585
Yi 3 = 1.0092	dH _e i 3 = 2.0462
Yi 4 = 1.0100	dH _e i 4 = 2.0504
Yi 5 = 1.0097	dH _e i 5 = 2.1052
Yi 6 = 1.0102	dH _e i 6 = 2.1105
Y = 1.0075	dH _e = 2.0416

Definitions:

- Vw = Gas volume passing through the wet test meter, ft³.
 Vd = Gas volume passing through the dry gas meter, ft³.
 tw = Temperature of the gas in the wet test meter, dF.
 tdi = Temperature of the inlet gas of the dry gas meter, dF.
 tdo = Temperature of the outlet gas of the dry gas meter, dF.
 td = Average temperature of the gas in the dry gas meter, dF.
 dH = Pressure differential across orifice, in. H₂O.
 Yi = Ratio of accuracy of wet test meter to dry gas meter for each run.
 Y = Average of Yi. Tolerance = +/- 0.02
 Pb = Barometric pressure, in Hg.
 e = Time of calibration run, min.
 dH_ei = Orifice pressure differential for each run.
 dH_e = Average orifice pressure differential. Tolerance = +/- 0.20


 Calibrator - James Tryba

Jun 30, 1993

Date

ORIFICE and DRY GAS METER POST TEST FORM

Client: NORTHERN ASPHALT COMPANY, Blaine, MN
 Date: Aug 18, 1993 Meter # 1 Barometric Pressure, Pb: 29.90
 Max. Vacuum Achieved (in.Hg.): 6.0 Intermediate Orifice Setting: 2.19
 dH_e Factor Used: 2.0416 Y Factor Used: 1.0075


Orifice manometer setting dH, in.H2O	Gas Wet test meter Vw, ft3	Volume Dry gas meter Vd, ft3	Wet test meter tw, dF	Temperature Dry gas meter			Time e, min.
				Inlet tdi, dF	Outlet tdo, dF	Average td, dF	
2.19	10.000	9.998	76	87	79	83.0	12.95
2.19	10.000	10.015	76.5	88	81	84.5	13.00
2.19	10.000	10.023	76.5	89	82	85.5	12.95

Y	dH _e
$\frac{Vw \text{ Pb } (td + 460)}{Vd [Pb + (dH/13.6)] (tw + 460)}$	$\frac{0.0317 \text{ dH}}{Pb (to + 460)} \left[\frac{(tw + 460) e}{Vw} \right]^2$
Yi 1 = 1.0078	dH _e i 1 = 2.0755
Yi 2 = 1.0080	dH _e i 2 = 2.0877
Yi 3 = 1.0090	dH _e i 3 = 2.0678
Y = 1.0083	dH _e = 2.0770
Difference = 0.08 % *	Difference = 1.73 % *

* Tolerance must be within +/- 5% of calibrated factors.

Definitions:

Vw = Gas volume passing through the wet test meter, ft3.
 Vd = Gas volume passing through the dry gas meter, ft3.
 tw = Temperature of the gas in the wet test meter, dF.
 tdi = Temperature of the inlet gas of the dry gas meter, dF.
 tdo = Temperature of the outlet gas of the dry gas meter, dF.
 td = Average temperature of the gas in the dry gas meter, dF.
 dH = Pressure differential across orifice, in. H2O.
 Yi = Ratio of accuracy of wet test meter to dry gas meter for each run.
 Y = Average of Yi.
 Pb = Barometric pressure, in Hg.
 e = Time of calibration run, min.
 dH_ei = Orifice pressure differential for each run.
 dH_e = Average orifice pressure differential.


 Calibrator - James Tryba

Aug 18, 1993

Date

VISIBLE EMISSIONS EVALUATOR

This is to certify that

David Christian

met the specifications of Federal Reference Method 9 and qualified as a visible emissions evaluator. Maximum deviation on white and black smoke did not exceed 7.5% opacity and no single error exceeding 15% opacity was incurred during the certification test conducted by Eastern Technical Associates of Raleigh, North Carolina. This certificate is valid for six months from date of issue.

Thomas Lane
President

Will S. [Signature]
Vice President

David B. Savage, Jr.
Program Manager

238374
Certificate Number

Minneapolis
Location

April 1, 1993
Date of Issue

APPENDIX E
MINNESOTA EXHIBIT C
PROCESS DATA

Asphalt Plant Operating Conditions During Stack Testing

Rev/VH/93

Test Date(s) AUG. 17 - 1993

Plant Mfr. & Model Barber Greene

Type (circle one): Drum Mix Conventional
Other (list): Continuous drum mix

Pollution Control Equipment: Baghouse Venturi Scrubber wet scrubber cyclone multistage

List model: Barber Greene CF-11 If wet scrubbing: % scrubber water recycled

Air flow through control equipment: 37000 acfm at 250° F Normal pressure drop across control equipment: inches water

Date & procedures of last maintenance/cleaning of control equipment: replaced bags throughout season as nec Was control equipment operating normally during testing?

Fuel:

Itemize all fuels and materials added to the combustion process during the test period. List fuel type used during testing (if oil, specify grade) Waste oil If other units of measure are used, specify and calculate appropriate heat input.

Test No. <u> </u>	Fuel Input (Gal/hr)	BTU/GAL (as received)	Heat Input (BTU/HR)	% Moisture (as received in aggregate) Virgin	recycle	combined
Run 1	247 G	138,500	34,209,500	5%	—	—
Run 2	247 G	138,500	34,209,500	5%	—	—
Run 3	—	—	—	—	—	—

Is the above fuel substantially the highest sulfur containing fuel normally burned? yes

Production specific fuel usage: (circle one) measured or calculated: cubic foot/ ton hot mix

No. of Burners: 1 Burner(s) rating: 86 MMBTU/HR = 100% setting 1.4 gallon hot mix

Operation:

time 15 min. intervals	burner setting %	aggregate tons per hour	recycle tons per hour	asphalt tons per hour	Drum Mix temp. F	dust collector pressure drop inches water	scrubber water flow rate gpm	Other (list)
5:30	25	131		140	310	2		
6:15	25	139		147	310	2		
7:00	25	132		138	300	2		
7:15	25	130		136	300	2		
7:30	24	122		127	300	2 1/2		
7:45	24	130		136	300	2		
9:20	25	124		134	315	2		
9:35	24	133		140	300	2		
9:50	25	129		139	300	2		
10:05	24	128		137	300	2 1/2		
10:20	24	127		135	290	2		
10:35	24	129		138	300	2		

Plant Operator's Certification: I certify that the information submitted herein is accurate and correct and that no information requested was withheld from the Division Manager.

By: Jeff Jusselyn Phone: () 784-1805

Position: General Manager

Note: All information required must be completed and submitted as part of the performance test. Failure to submit the required information will result in an incomplete performance test report.

Asphalt Plant Operating Conditions During Stack Testing

Rev/11/83

Test Date(s) AUG. 17 - 1993

Plant Mfr. & Model Barber Greene

Type (circle one): Drum Mix Conventional
Other (list): Continuous drum mix

Pollution Control Equipment: Baghouse Venturi Scrubber wet scrubber cyclone multiclone
(circle one)
List model: Barber Greene CF-11 If wet scrubbing: _____ % scrubber water recycled
Normal pressure drop across control equipment: _____ inches water
Air flow through control equipment: 3700 acfm at 250° F Was control equipment operating normally during testing? _____
Date & procedures of last maintenance/cleaning of control equipment: replaced bags throughout season as nec.

Fuel:

Itemize all fuels and materials added to the combustion process during the test period. List fuel type used during testing (if oil, specify grade) Waste oil. If other units of measure are used, specify and calculate appropriate heat input.

Test No. _____	Fuel Input (Gal/hr)	BTU/GAL (as received)	Heat Input (BTU/HR)	%Moisture (as received in aggregate)		
				Virgin	recycle	combined
Run 1	—	—	—	—	—	—
Run 2	—	—	—	—	—	—
Run 3	<u>2356</u>	<u>138,500</u>	<u>325,475,000</u>	<u>5%</u>	—	—

Is the above fuel substantially the highest sulfur containing fuel normally burned? yes

Production specific fuel usage: (circle one) measured or calculated: 1.9 cubic foot/ton hot mix

No. of Burners: 1 Burner(s) rating: 86 MMBTU/HR = 100% rating


Operation:

time 15 min. intervals	burner setting %	aggregate tons per hour	recycle tons per hour	asphalt tons per hour	Drum Mix temp. F	dust collector pressure drop inches water	scrubber water flow rate gpm	Other (list)
<u>11:00</u>	<u>2 1/2</u>	<u>122</u>		<u>129</u>	<u>310</u>	<u>2 1/2</u>		
<u>11:15</u>	<u>2 1/2</u>	<u>124</u>		<u>130</u>	<u>310</u>	<u>2</u>		
<u>11:30</u>	<u>2 1/2</u>	<u>125</u>		<u>132</u>	<u>300</u>	<u>2</u>		
<u>11:45</u>	<u>2</u>	<u>123</u>		<u>130</u>	<u>310</u>	<u>2 1/2</u>		
<u>12:00</u>	<u>2</u>	<u>122</u>		<u>130</u>	<u>310</u>	<u>2 1/2</u>		
<u>12:15</u>	<u>2</u>	<u>124</u>		<u>130</u>	<u>300</u>	<u>2 1/2</u>		

Plant Operator's Certification: I certify that the information submitted herein is accurate and correct and that no information requested was withheld from the Division Manager.


By: Jeff Shumaker, Phone: () 7841805
Position: General Manager

Note: All information required must be completed and submitted as part of the performance test. Failure to submit the required information will result in an incomplete performance test report.



PROJECT:	DATE: FEBRUARY 8, 1993
PROCESS FLOW DIAGRAM	PROJECT NO: 4232 93-2247
HOT ASPHALT PRODUCTION	DRAWN BY: S. GOEPFERT
NORTHERN ASPHALT CONSTRUCTION	REVIEWED BY: S. ADAMS
BLAINE, MINNESOTA	SCALE: NONE
	MACDRAW PRO DWG:

NORTHERN ASPHALT CONSTRUCTION



APPENDIX F
MPCA TEST PLAN

TWIN CITY TESTING AIR QUALITY SERVICES TEST PLAN

CLIENT INFORMATION

Company- Northern Asphalt Construction, Inc.
Address- 11064 Raddison Road NE, Minneapolis, MN 55434
Contact- Jeff Dusenka
Phone: (612) 784-1805
FAX: (612) 784-1831

PRETEST MEETING

Location - MPCA building, St. Paul, MN
Date - August 4, 1993
Time - 2:00 p.m.

TEST PARAMETERS

Location- Client's facility at address above.

Source(s)- Asphalt Plant Baghouse.

Procedures/Methods-

- EPA Methods 1 thru 5 including back half analysis for particulate matter.
- EPA Method 9 for opacity.
- Aggregate moisture content.

Test Date - August ¹⁷12, 1993

Time of Test - Approximately 6:00 a.m.

Comments: - AUGUST 17 TEST DATE
- 1500 TAN 135TPH
- 4 PORTS
- 3 HOURS OF OPACITY READINGS
- YOUNGA WILL WITNESS
- USED CIL
- VIRGIN AGGREGATES ONLY, NO RECYCLE

Minnesota Pollution Control Agency
Division of Air Quality
Stack Testing Protocol
April 29, 1993

The following is a summary of the testing requirements for the portable asphalt plant owned by Northern Asphalt Construction, Inc. :

I. Test Methods

- A. EPA Method 1 for the location of sampling ports and points. Location of the sampling ports must be approved before the test.**

Check for cyclonic flow must be done whenever there is a cyclonic type of device directly upstream of the sampling location. Correction of cyclonic flow by straightening vanes must also be verified by checking the cyclonic flow before the test.

If the location does not meet the minimum requirements in Method 1, the testing firm must conduct the flow pattern evaluation and testing according to the alternative procedures in part 2.5 of EPA Method 1 (Three-dimensional directional probe).

- B. EPA Method 2 for velocity and volumetric flow rate. Three determinations: one measurement concurrently with each test run for pollutant.**
- C. EPA Method 3 for gas analysis. Three determinations: one measurement on an integrated sample taken concurrently with each test run for pollutant.**
- D. EPA Method 4 for the determination of moisture in the flue gases. Three determinations: one measurement concurrently with each test for pollutant.**
- E. EPA Method 5 as amended in Exhibit C and Minn. Rules 7005.0500 for the determination of particulate matter emissions including condensibles. The sampling time for each run must be at least 60 minutes, and the sampling rate must be at least 0.9 dscm/hr (0.53 dscf/min). Three one-hour determinations are required. The results should be reported as dry catch only and dry catch plus wet catch.**
- F. EPA Method 9 for the determination of visible emissions as amended in Minn. Rules part 7005.1860. Three hours of opacity readings are required for initial compliance of NSPS sources.**

AQD File No.: 1095

Note: The protocol, testplan, and any information required in Exhibit C shall be submitted as part of the performance test report.

TEST PLAN
FOR
ASPHALT PLANTS
April 29, 1993

I. GENERAL INFORMATION

Permittee: Northern Asphalt Construction, Inc.

Permittee's contact person and telephone number: Jeffrey Dusenka 784-1805

Permittee's mailing address: 11064 Raddison Road Northeast, Blaine, Mn. 55449

DAQ File No.: 1059

MPCA permitting engineer: Jerry Liefert

Applicable regulations for each source tested (be specific): Federal NSPS 40
CFR Part 60, Subp. I and Mn. Rules 7005.2020 A & B for PM and opacity.

Reason for testing: initial compliance with permit

Is this test for initial compliance demonstration: Yes

Drawings showing location of sampling ports included: To be submitted

Location of the plant at the time of the test: Unknown

Date when test plan was discussed and agreed upon with the permittee, or
Pre-test meeting needed: Pre-test meeting to be scheduled by Permittee.

II. NOTIFICATION REQUIREMENTS:

The permittee must contact the Agency at least two weeks before the scheduled test to have a pre-test meeting and obtain all necessary approvals.

It is very important to allow at least two weeks before the test to review the testing requirements in order to avoid last minute cancellations due to inadequate testing conditions.

Among the potential problems that may need to be solved before the test are:

1. Unsuitable location of sampling ports. The stack may need to be extended and/or straightening vanes be installed.
2. Permittee must schedule the test at a time when the plant can be operated at 100% of rated capacity, and at maximum recycle rate if applicable. If the plant is tested at less than 100% of capacity, the Permittee will be required to limit production to the tested rate.
3. Permittee must be ready to burn specified fuel.

4. Permittee may have to install pressure drop taps and gauges.
5. Permittee may have to install sampling taps on the line feeding fuel to the burner.

III. TEST PLAN

The following is the test plan developed for the Barber Greene drum mix plant.

- A. Emission point(s) to be tested: Exhaust stack for fabric filter
- B. Parameters to be tested at each emission point: PM and opacity for Emission Point 1.
- C. Fuel sampling and analysis. (Fuel oils and used oil)

This is part of the compliance demonstration requirements. Please note that the test report will not be accepted without complete submittal of fuel analysis results of samples taken at the time of the test.

1. Sampling. One tap sample per particulate test run must be taken. The sample must be taken as close as possible to the burner, (somewhere in feeding line) to be representative of the fuel burned at the time of the test. The sample may be taken in a pint-size clean container, and according to the procedures in Exhibit D. Mix the three samples taken into a composite.

2. Analysis. The composite must be analyzed as specified in Exhibit D.

D. Moisture content in the virgin aggregate

1. Take two samples the virgin aggregate per test run of particulates. Sample must be taken as close as possible to the feeding conveyor and during the corresponding run. Mix the two samples of virgin aggregate, this will give one composite sample per test run.
2. Perform one analysis of moisture content in each composite sample as per ASTM or other recognized methodologies. A total of three analysis shall be performed, one per test run for particulates.

E. Operating Conditions during the Test

1. Operation must be at 100% of design capacity at the existing aggregate moisture content - no deliberate reduction of feed rate or fan speed during testing, except for nominal damper adjustment for proper combustion. - The test report must include copies of the manufacturer's specifications that define the design capacity of the plant as a function of the moisture content of the aggregate. If circumstances cause operation of the plant to be less than 100% during the test, the Permittee will be required to limit production to the tested rate.
2. Must burn 100% of the highest emitting fuel to be listed in and allowed by the permit: Used oil (waste oil, crank oil).
3. If normal operation of the plant will be with recycling of collected PM from the baghouse into the dryer, the test must be conducted under the same conditions.

F. Operating Data to Be Recorded during the Test

Operating data must be recorded during the test in its entirety i.e., particulates and visible emission observations. Operating data must be recorded every fifteen minutes. Please use the attached data sheet or equivalent.

Note: No test report will be accepted without a complete data sheet included.

1. During testing the following measurements must be made:

- a) Pressure drop across the baghouse.
- b) Virgin aggregate input (ton per hour) as well as asphalt input (ton per hour). Provide the manufacturer's rating of the asphalt plant at different moisture contents in the aggregate.
- c) Moisture content of the aggregate.

2. Please provide the following data:

- a) Average fuel consumption rate (calculated or measured) and type
- b) Cleaning cycles of the baghouse
- c) Operating data sheet enclosed

G. Testing schedules and testing firm: Test shall be conducted by the date specified in the final letter for the August 4, 1992 performance test.

H. Permitting engineer to witness the test: No