

Note: This is a reference cited in *AP 42, Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP42 Section:	11.3
Reference:	12
Title:	Source Emission Test At Belden Brick, Inc., Sugarcreek, OH, No. 1 Kiln, Plant 3, CSA Company, Alliance, OH, March 3, 1992.

CSA COMPANY

(Custom Stack Analysis)

ENGINEERING REPORT

SOURCE EMISSION TEST
AT
BELDEN BRICK, INC.
SUGARCREEK, OHIO
NO. 1 KILN, PLANT 3
MARCH 3, 1992

TECHNICAL SERVICES FOR POLLUTION CONTROL
SOURCE TESTING - LAB SERVICE - BOILER CONSULTING

BELDEN BRICK, INC., SUGARCREEK, OH, NO. 1 KILN, PLANT 3, MARCH 3, 1992

CONTENTS

BRIEF OF TESTS	1
RESULTS	1
TEST METHODS	1
PARTICULATE TEST APPARATUS	1
PARTICULATE TEST PROCEDURES	2
SULFUR DIOXIDE TEST PROCEDURES	4
NOx APPARATUS AND PROCEDURES	4
NOx LAB ANALYSIS	5
MISCELLANEOUS	6
COMPILED DATA	7
LOCATION OF SAMPLE PORTS AND POINTS	8
SCHEMATIC OF METHOD 5 APPARATUS	9
SCHEMATIC OF INTEGRATED SAMPLER	10
APPENDIX I	
COMPUTER NOMENCLATURE	11
CALCULATION FORMULA	12
PROCESS WEIGHT SHEET	13
NOx DATA SHEET	14
TEST 1 RAW DATA AND CALCULATIONS	15-20
TEST 2 " " " "	21-25
TEST 3 " " " "	26-30
APPENDIX II	
INTENT TO TEST NOTIFICATION	31-43

CSA CO., PO BOX 3750, ALLIANCE, OH 44601 PH (216)525-5119
FAX (216)525-7908

Permit
limits
PM 4.20 #/hr
SO₂ 6.60
NOx 6.00

SOURCE EMISSION TESTS

AT

BELDEN BRICK INC.

SUGARCREEK, OHIO

NO.1 KILN, PLANT 3

MARCH 3, 1992

Brief of Tests

Particulate emission tests were performed on the stack of the brick kiln as per EPA Federal Register methods 1 through 5, 6 and 7 as set forth in the Appendix to Part 60, "Standards of Performance for stationary sources", Subchapter C, Chapter 1, Title 40, Volume 42, No. 160, July 1, 1988 as amended from the original Federal Register, Volume 36, No. 247, December 23, 1971.

The tunnel kiln is a continuous operation where the green product is loaded on cars that travel through the various heat zones and discharge as a finished product at the other end. The kiln is heated with natural gas with the products of combustion and the emissions from the curing process discharging to a stack via induced draft fan.

Results

- A) The particulate emission rate was 2.50 pounds per hour.
- B) The sulfur dioxide emission rate was ^{2.71}~~2.29~~ pounds per hour.
- C) The nitrogen oxides emission rate was 2.29 pounds per hour.
- D) The process weight rate was 15,660 pounds per hour.

Test Methods

A twelve point traverse was selected for the ⁴⁴~~thirty five~~ inch square brick stack as per method 1. Each point was sampled for five minutes for a total test time of 60 minutes (See figure 1). The CO₂ and O₂ analysis were conducted by an orsat flue gas analyzer from an integrated sample taken at the test ports to provide data for method 3.

Method 5 was used to determine the particulate quantity, moisture determination by method 4 and gas velocity by method 2 using a Research Appliance Corp. "Stacksamplr".

The sulfur dioxide tests were performed by method 6.

The nitrogen oxides were determined by EPA method 7.

Particulate Test Apparatus

A schematic of the apparatus is shown in figure 2.

The dust laden gases were passed through a pyrex lined probe and heated glass cyclone separator bypass followed by a four inch filter holder containing Gelman Type A-E fiberglass filter media. The gases leaving the filter were cooled in a series of three impingers packed in ice. The first and third impinger were the modified Greenburg-Smith type and the second one was a standard Greenburg-Smith. The First and second impingers were filled with 100 ml of distilled water with the third one used as a dry trap. After leaving the dry trap, the gases passed through a "Drierite" column containing about 500 grams of calcium sulfate (CaSO_4) desiccant to remove the remaining water vapor. The dry gas passed through the hose portion of the umbilical cord to a Research Appliance Corp. model 2343 "Stacksamplr" module. In the module the gas was moved through the system by a leakless air pump to a Rockwell 175-S dry test meter. The dry test meter exhausted to a calibrated orifice to measure the flow rate of the gases passing through the sampling apparatus. A type "S" pitot tube was attached to the sheath of the heated probe to measure the velocity head of the flue gases near the tip of the probe nozzle. The orifice pressure taps and the pitot tube were connected to a Dwyer dual 10 inch combination inclined well type manometer. One half of the manometer measured the orifice differential (ΔH) and the other half measured the flue gas velocity head (ΔP).

The temperature of the flue gas was measured by a type "K" thermocouple connected to a PyroMation digital temperature indicator.

The CO_2 and O_2 were measured with a Burrell "Industro" Model B orsat from an integrated sample taken by withdrawing a constant flow rate of gas from the stack and injecting it into a Tedlar bag. This was done by drawing the gas through an in-stack filter via neoprene tubing to a condenser and condensate collector ahead of a leakless diaphragm vacuum-pressure pump. The pump discharged to the rotometer and the Tedlar bag. The apparatus is equipped with valves to by-pass the rotometer and bag when clearing the sample line as shown in figure 3.

Particulate Test Procedures

The probe, filter and glassware was assembled and leak tested in our lab before transporting to the job site. Three sets of equipment

were used. At the job site a preliminary pitot traverse was performed to select the proper nozzle size. The nozzles were measured with an inside vernier caliper and micrometer calibrated with a one inch micrometer standard.

The first and second impingers were filled with 100 ml of distilled water and the "Drierite" columns were connected just prior to elevating the probe into position.

After leak testing the apparatus at 10 inches of mercury the probe was inserted at the first sample point to start the test.

The isokinetic sampling rates were determined using a portable desk top computer programmed to calculate the proper ΔH setting at the flue gas temperature, pressure, density and the assumed moisture along with the temperature, ΔP and an assumed ΔH of the test module. The sampling rate (ΔH) can be determined in less than 5 seconds using this technique.

The apparatus was leak tested after the test was completed at a vacuum exceeding that encountered during the test.

The moisture content was determined from the amount of condensate collected in the impingers and the difference of the tare and gross weight of the "Drierite" desiccant column. The desiccant column was weighed on an Ohaus 5 Kg industrial lab balance to the nearest half gram.

The filter media was dried in a desicator at room temperature to dryness before tare and gross weighing on a Stanton CL4D analytical balance.

The probe liner, nozzle, cyclone bypass and front half of the filter holder were washed with acetone and brush after testing and evaporated to dryness at room temperature in 500 ml beakers. The beakers were dried and tare weighed prior to sample evaporation and gross weighed after allowing the samples to desiccate to dryness. These weights were accomplished with the Stanton Balance.

The integrated gas sampler was started at the beginning of the method 5 test with about two cubic foot of gas collected in the tedlar bag at the end of the test. The sampling rate was maintained constant during the test by maintaining a constant reading on the rotometer.

The orsat analysis was performed on the gases contained in the

bag shortly after the test was completed.

Sulfur dioxide test apparatus and procedures.

A schematic of the test apparatus is shown in figure 4. The gases were drawn through a heated pyrex probe with a fiberglass wad attached to the sampling end of the probe. The probe was connected to the impinger train where it first passed through a midget bubbler containing 15 ml of 80% isopropyl alcohol. A wad of glass wool was packed in the top of the bubbler to collect any acid mist carryover. The gases then passed through two midget impingers, each containing 15 ml of 3% hydrogen peroxide solution followed by an empty midget impinger to collect the carryover from the preceding impingers. The midget bubbler and impingers were contained in an ice bath to condense acid and water vapor. After leaving the dry trap the gases passed through a "Drierite" column containing about 500 grams of "Drierite" via rubber hose to remove the remaining water vapor. The dry gas was transmitted to the module through a "polyflow" tubing. In the module the gas was moved through the system by a leakless air pump connected to the rotometer to measure the gas flow rate and a Rockwell type "S" dry test meter to measure the gas volume. The dry test meter was equipped with a thermometer located in the top half of the gas meter to measure the temperature of the meter. The gas from the meter was discharged to the atmosphere.

Class "A" burettes and pipets were used for the titrations in the lab analysis of the contents of the impingers.

The run was started shortly after the method 5 test was started and ran for twenty minutes. Two runs comprised one test.

The calculations are shown in Appendix I.

NOx Apparatus & Procedure

The NOx sampling apparatus is shown in figure 4. Prior to testing the absorbing solution was made by adding 2-8 ml of concentrated H_2SO_4 to 1 liter of deionized, distilled water. After mixing, 6 ml of 3 per cent H_2O_2 was added. This solution was made just prior to testing and was stored in a dark glass bottle away from sunlight. 25 ml of this solution was used for each test. Four tests were performed during of the three method 5 tests. The raw data and calculations are shown in Appendix II.

Before taking a sample the system was leak checked by evacuating the flask to the maximum vacuum and closing the valve to the pump with the three way stopcock left in the evacuate position and the one way stopcock open. The system was considered leak-free if the vacuum remained the same for a period of one minute. The reading indicated on the manometer was recorded along with the temperature of the flask.

The contents in the flask were shaken for at least five minutes after collecting the sample. The samples were contained in the flask for at least sixteen hours before transferring to plastic bottles. The flasks were rinsed twice with about five ml portions of distilled water that was added to the plastic bottle. The pH of the contents of the plastic bottle was adjusted to about ten with one normal sodium hydroxide. The bottles were marked and sealed for transport. The barometric pressures were obtained from the local airport and corrected for elevation.

NOx Lab Analysis

1) Spectrophotometer Calibration

The spectrophotometer was turned on and allowed to warm up for about one hour prior to calibrating with a didymium calibrating standard along with the procedures of standard practice for the Perkin-Elmer model 44 linear absorbance spectrophotometer.

A KNO_3 standard solution was made by dissolving 2.198 grams of KNO_3 in one liter of distilled deionized water in a 1,000 ml volumetric flask. Ten ml of this solution was diluted to 100 ml in a 100 ml volumetric flask to use as a working standard where one ml is equal to 100 μg NO_2 .

The spectrophotometer calibration factor was made by adding 0, 1, 2, 3 & 4 ml of the standard working solution to a series of five porcelain evaporating dishes along with 25 ml of the absorbing solution and 10 ml of distilled water. The pH of this solution was adjusted to about 10 by adding NaOH (1N) before evaporating to dryness on a steam bath. After drying and cooling 2 ml of phenoldisulfonic acid was added to the residue. One ml of distilled water and four drops of concentrated sulfuric acid was added and titrated thoroughly with a polyethylene policeman. This solution was stirred while being heated for about 3 minutes on the steam

bath. After cooling, 20 ml of distilled water was added and mixed well. Concentrated NH_4OH was added dropwise with constant stirring until the pH was 10 by pH paper. This solution was added to 100 ml volumetric flasks and diluted to the mark with distilled water. The contents were mixed thoroughly before transferring a portion to the 25 x 105 mm round spectrophotometer cuvettes. The absorbance of each of the solutions was measured and recorded at 410 nm wavelength using the 0 ml sample as the blank. The blank sample showed the same absorbance as the distilled water. The absorbance for each standard is shown on the data sheet in Appendix II.

2) Sample Analysis

All samples were returned with none of the liquid lost in transit. The contents of the plastic bottles were transferred to 50 ml volumetric flasks and rinsed twice with 5 ml portions of distilled water, then diluted to the mark with distilled water and mixed thoroughly. A 25 ml aliquot was piped into the 250 ml porcelain evaporating dish and evaporated to dryness on the steam bath. Since there were no solids in the solution the remaining procedures were performed the same as the calibration standards.


The volume of the 2 liter sample flask was determined by filling the flask to the one way stopcock bore and emptying it into a graduated cylinder for measurement. This was done with water at room temperature.

Miscellaneous

All raw data and calculations are shown in Appendix I.

The Intent to test notification is included in Appendix II.

Submitted by



Ernest L. Kolm

Test	1	2	3	Average
Date	3/3/92	3/3/92	3/3/92	
Time	9:57/11:00	11:12/12:15	12:33/13:25	

PARTICULATE QUANTITY

Grains/f3 Dry STP	0.0198	0.0153	0.0190	0.0180
Pounds/Hr.	2.8331	2.1060	2.5511	2.4967

GASEOUS EMISSIONS

SO2 Pounds/Hr	2.79	2.87	2.48	2.71
SO2 Parts/Million	17.0	18.0	16.0	17.0
NOx Pounds/Hr	2.47	2.42	1.97	2.29

STACK GAS CONDITIONS


Temperature -dg. F	402.0	429.0	397.0	409.3
Static Pressure-in H2O	0.00	0.00	0.00	0.00
CO2 - %	3.2	3.1	3.0	3.1
O2 - %	16.4	16.5	16.9	16.6
H2O - %	5.5	5.4	5.7	5.6
Velocity - FPS	36.62	36.40	34.34	35.79
Stack Area - sqr. ft.	13.40	13.40	13.40	13.40
Gas Flow - ACFM	29445	29266	27610	28774
Gas Flow (DSTP) CFH	998281	962687	939679	966882

SAMPLE TRAIN CONDITIONS

Pitot Delta P in H2O	0.2510	0.2400	0.2220
Orifice Delta P in H2O	1.51	1.61	1.44
Temp. Meter - dg. F	78	95	98
Gas Volume - CF Dry STP	39.24	39.61	38.66
Barometer - in Hg	29.10	29.10	29.10
Probe Tip Dia. - in.	.313	.313	.313
Isokinetic Var. - %	99.0	103.6	103.6

BELDEN BRICK, INC.
SUGARCREEK, OHIO
NO.1 KILN, PLANT 3
COMPILED DATA

Table 1





$$\text{AREA} = 13.4 \text{ f}^2$$

$$\text{EQUIVALENT DIA.} = 44"$$

$$\text{EQUIV. DIA. UPSTREAM} = 7.1$$


$$\text{EQUIV. DIA. DOWNSTREAM} = 2+$$





C.S.A. Co.
 MODIFICATION OF R.A.C. SAMPLE TEST
 USING DRIERITE COLUMN IN PLACE OF
 IMPINGER DESICCANT

Figure 2



INTEGRATED SAMPLER

APPENDIX I

CSA CO.
COMPUTER NOMENCLATURE FOR CFR Method 5

SYMBOL	DESCRIPTION	UNITS
V_m	METER VOLUME	CUBIC FEET
P_{bar}	BAROMETER	INCHES MERCURY
ΔH	ORIFICE DIFFERENTIAL	INCHES WATER
P_m	ABSOLUTE PRESSURE OF METER	INCHES MERCURY
t_m	TEMPERATURE OF METER	$^{\circ}F$
T_m	TEMPERATURE OF METER	$^{\circ}R$
t_s	TEMPERATURE OF STACK	$^{\circ}F$
T_s	TEMPERATURE OF STACK	$^{\circ}R$
P_g	STACK STATIC PRESSURE	INCHES WATER
P_{ga}	ABSOLUTE STACK PRESURE	INCHES MERCURY
C	PITOT COEFFICIENT	DIMENSIONLESS
ΔP	PITOT DIFFERENTIAL	INCHES WATER
CO_2	CARBON DIOXIDE	PERCENT
O_2	OXYGEN	PERCENT
N_2	NITROGEN	PERCENT
CO	CARBON MONOXIDE	PERCENT
M_d	MOLECULAR WEIGHT DRY	LB/LB-MOLE
V_{lc}	VOLUME OF CONDENSATE	MILLILITERS
A_s	AREA OF STACK	SQUARE FEET
D_n	DIAMETER OF NOZZLE	INCHES
A_n	AREA OF NOZZLE	SUARE FEET
M_s	MOLECULAR WEIGHT OF GAS WET	LB/LB-MOLE
M_n	TOTAL PARTICULATE CATCH	MILLIGRAMS
θ	TIME	MINUTES

CSA CO.
PARTICULATE CALCULATIONS FOR CFR METHOD 5

Dry Molecular Weight lb/lb-mole

$$M_d = 0.44 (\%CO_2) + 0.32 (\%O_2) + 0.28 (\%N_2 + \%CO)$$

Dry Gas Volume (standard conditions), ft³

$$V_{mstd} = 17.64 V_m Y (P_{bar} + \Delta H/13.6) / T_m$$

Volume of Water (standard conditions), ft³

$$V_{wstd} = 0.04707 V_{lc}$$

Moisture Content (proportion by volume)

$$B_{wo} = V_{wstd} / (V_{mstd} + V_{wstd})$$

Molecular Weight of Stack Gas (wet basis), lb/lb-mole

$$M_s = M_d (1 - B_{wo}) + 18 B_{wo}$$

Stack Gas Velocity ft/sec

$$V_s = 85.49 C_p \sqrt{\Delta P_{avg}} \sqrt{T_s (avg)} / P_s M_s$$

Stack Gas Volumetric Flow Rate (dry standard conditions), ft³/hr

$$Q_s = 3600 (1 - B_{wo}) V_s A_s (528 / T_{savg}) (P_{sa} / 29.92)$$

Concentration (particulate in gas), lb/f³_{std dry}

$$C_s = 2.205 \times 10^{-6} M_n / V_{mstd}$$

Load (particulate in stack gas), lb/hour

$$L = Q_s C_s$$

Concentration (particulate in gas), grains/f³_{std dry}

$$C''_s = 0.0154 M_n V_{mstd}$$

Isokinetic Variation, %

$$I = 100 T_s [0.002669 V_{lc} + (V_m Y / T_m) (P_{bar} + \Delta H/13.6)] / 600 V_s P_s A_n$$

PUSH @ 930
12 30
3 30

3 CAR SCHEDULE
15660 #/HR

NEOPORD IN -

KINGSPRO OUT -

CSA CO. NO_x DATA SHEET

TEST	DATE	TIME	BAROMETER		FLASK VACUUM		FLASK TEMP		FLASK VOLUME
			INITIAL	FINAL	INITIAL	FINAL	INITIAL	FINAL	
1A	8/3/62	9:50	29.10	29.06	27.0	.3	58	70	2040
1B	"	10:10	29.1	29.06	27.0	.5	68	70	2090
2	"	12:15	29.1	29.06	27.0	.1	73	70	1953
3	"	13:25	29.1	29.06	27.0	.3	72	70	1951

SPECTROPHOTOMER CALIBRATION

ABSORBANCE OF ABSORBANT SOLUTION = 0

A1=ABSORBANCE OF 100 g STD = .110

A2= " " 200 g " = .210

A3= " " 300 g " = .305

A4= " " 400 g " = .395

SAMPLE DILLUTION FACTOR = 1

A=SAMPLE ABSORBANCE

TEST	A
1A	.035
1B	.037
2	.035
3	.029

Q
998,281
998,281
962,687
939,679

Q FLOW - M-S
GAS FLOW CPM - DISA

SEE COMPUTER CALCULATION SHEET FOR RESULTS

FOR BELDEN BRICK BY ECGT
LOCATION NO1 KILN PLANT 3

CSA CO. DATA SHEET (METHOD 5)

TEST NO.		PLANT BELDEN BAICK SUGAR CREEK						DATE 3/3/92			
LOCATION No 1 KILN STACK PLANT 3								BY ECR GT			
BAROMETER (P _B) 29.10		AMBIENT TEMP		ASSUMED MOISTURE				"Y"/1003			
MODULE NO. 2031		PROBE NO. 1-5		FILTER NO. 3		HEATER NO. 3		NOZZLE DIA.			
TEST POINT	METER VOLUME (V _m)	METER TEMP (T _m) IN OUT		COND TEMP °F	FILTER HEATER TEMP °F	STACK TEMP °F (T _s)	STACK PRESS. (Ps)	VACUUM "Hg	ORIFICE "H ₂ O (ΔH) (Pm)	VEL HEAD (ΔP)	TIME
1	724.8	60	60	42	252	394	0	3-	.70	.13	9:57
1	727.2	64	60	42	248	393		3-	.70	.13	10:02
2	730.2	76	62	42	250	394		3-	1.1	.20	07
2	732.8	75	63	42	250	396		3-	1.1	.20	12
4	735.8	78	65	42	250	398		3-	1.2	.20	17
1	735.8	78	66	42	252	397		4-	1.6	.27	10:18
1	739.7	85	70	42	250	399		4-	1.6	.27	22
2	743.0	89	74	43	256	402		4	1.7	.28	28
2	746.5	91	76	46	258	405		4	1.7	.28	32
4	750.4	94	78	47	250	408		4	1.8	.29	38
1	750.4	92	78	48	248	409		4	1.7	.27	10:40
1	754.1	94	82	48	250	409		4	1.7	.27	45
2	757.7	95	83	48	252	412		4	1.9	.30	50
3	761.4	98	85	48	252	412		4	2.0	.31	55
4	765.8	99	87	48	250	414		4	2.1	.32	11:00
(V _m)	41.0	84.1	72.6								
AVERAGE		78	****	*****	402	0	MAX 5	1.51	.251	60 MINUTES	
INTEGRATED GAS SAMPLE V ₁₀		AVG		N ₂ = 80.4	CONDENSATE COLLECTED						
CO ₂	3.3	3.2	3.4	3.2	DRIERITE	FINAL 961.8	INITIAL 957.1	TOTAL 4.7			
O ₂	16.5	16.4	16.4	16.4	IMPINGER	243.9	200.0	43.9			
CO					GRAND TOTAL 48'6						
FILTER WT	PROBE WASH WT		IMPINGER WASH WT		LEAK RATE @ 10" Hg = <.02						
GROSS .6847	186.0298		NA		STACK AREA (As) 13.4 ft ²						
TARE .6637	186.0003				AVG SQ RT ΔP .5007						
NET .0210	.0295										
TOTAL PARTICULAT WT (Mn)		50.5 Mg									

E.P.A. METHOD 5

DATA INPUT

Pb,In Hg	Barometer -----	29.10
VM,ft3	Meter Volume -----	41.0
ΔH,In H2O	Orifice Differential-----	1.51
PG,In H2O	Stack Static Pressure -----	0
Tm,F	Meter Temperture -----	78
Ts,F	Stack Temperture -----	402
CP	Pitot Coefficient -----	.84
ΔP,In H2O	Average Square Root Of Delta P -----	.5007
% CO2	Carbon Dioxide -----	3.2
% O2	Oxygen -----	16.4
% N	Nitrogen -----	80.4
VCL,Ml	Volume Of Condensate -----	48.6
AS,ft2	Stack Area -----	13.4
MN,Mg	Total Particulate Catch Weight -----	50.5
Q,Min	Test Time -----	60
DN,In	Diameter Of Nozzle -----	.313

RESULTS

Pma,In Hg	Absolute Meter Pressure -----	29.21
PSA,In Hg	Absolute Stack Pressure -----	29.10
MD	Molecular Weight Dry Gas -----	29.17
MS	Molecular Weight @ Stack Conditions -----	28.55
VMSTP,ft3	VM Standard Temp.& Press. Dry -----	39.24
VWSTP,ft3	VM Standard Temp.& Press. Wet -----	2.29
BWD,%	Moisture -----	5.51
I,%	Isokeimetic Variation -----	99.00
VS,ft/Sec	Stack Velocity -----	36.62
QA,ASCFM	Stack Gas Flow (Actual) -----	29445
QS,ft3/HR	Stack Gas Flow (Dry STP) -----	998281
L,#/Hr	Emission Rate -----	2.83
CS,#/SCF	Particulate Emission -----	2.837957E-06
C/S,Grn/SCF	Particulate Emission -----	0.0198

BELDEN BRICK INC
 SUGARCREEK OH
 KILN 1 PLANT 3
 3/3/92
 TEST 1

CSA CO.

EPA METHOD 6 (SULFUR DIOXIDE) DATA AND CALCULATION SHEET

TEST NO 1-1 PLANT BELDEN BAICK DATE 3/7/92
LOCATION NO 1 KILN PLANT 3 BY ARK GT

Vm	Tm	ROTOMETER	TIME
123.370	50	3	9:55
3.620	59	3	10:00
1.835	59	3	10:05
4.068	62	3	10:10
4.267	64	3	10:15
3.370		—	20 MIN
Vm .897	avg 60		

Pb 29.10

$$Vm_{std} = K_1 Y(Vm)(Pb)/(Tm)$$

$$Vm_{std} = 17.64 (1.001) (.897) (29.10) / (460 + 60) = .886$$

	1st TITRATION	2nd TITRATION	3rd TITRATION	AVERAGE	Vb TITRATION
Vt	17.9	17.9	—	2.8	.1

$$C_{SO_2} = K_2(Vt - Vb)(N)(Va)/(Vm_{std})(V_{soln})$$

$$= 0.00007061(17.9 - .1)(.0099)(20)/(.886)(100)$$

$$= 2.78 \times 10^{-6} \text{ lb/f}^3\text{DSTP}$$

$$SO_2 \text{ PPM} = (C_{SO_2})(6.037 \times 10^6) = 16.8$$

$$SO_2 \text{ LB/HR} = (C_{SO_2})(448,281 \text{ f}^3/\text{Hr DSTP}^*) = 2.77$$

$$SO_2 \text{ LB/MMBTU} = SO_2 \text{ LB/HR} / \text{MMBTU/HR} =$$

*FROM METHOD 5 CALCULATION "Q"

C_{SO_2} = Concentration of sulfur dioxide - lb/dry standard cubic foot
N = Normality of barium perchlorate titrant
Pb = Barometric pressure - inches Hg
Tm = Temperature of meter - °F
Va = Volume of sample aliquot - ml
Vm = Volume of gas at meter temperature and pressure - f³
Vm_{std} = Vm corrected to standard temperature and pressure - f³
Vsoln = Total volume of sample solution - ml
Vb = Volume of titrant used for blank - ml
Y = dry gas meter calibration factor - dimensionless
K₁ = 17.64
K₂ = 7.061 X 10⁻⁶

CSA CO.

EPA METHOD 6 (SULFUR DIOXIDE) DATA AND CALCULATION SHEET

TEST NO 1-2 PLANT BELOW BRICK DATE 3/7/82
 LOCATION N01 KILN PLANT 3 BY SGR GT

Vm	Tm	ROTOMETER	TIME
124.267	66	3	10130
4.485	68	3	35
4.797	71	3	40
4.989	74	3	45
5.150	76	3	50
4.267			
Vm .913	avg 71		

Pb 29.10

$$Vm_{std} = K_1 Y(Vm)(Pb)/(Tm)$$

$$Vm_{std} = 17.64 (1.001) (.913) (29.10) / (460 + 71) = .8835$$

	1st TITRATION	2nd TITRATION	3rd TITRATION	AVERAGE	Vb TITRATION
Vt	18.0	18.0		18.0	.1

$$C_{SO_2} = K_2 (Vt - Vb)(N)(Va) / (Vm_{std})(V_{soln})$$

$$= 0.00007061 (18.0 - .1) (.0098) (20) / (.8835) (100)$$

$$= 2.864 \times 10^{-6} \text{ lb/f}^3 \text{ DSTP}$$

$$SO_2 \text{ PPM} = (C_{SO_2})(6.037 \times 10^6) = 16.93$$

$$SO_2 \text{ LB/HR} = (C_{SO_2})(998,261 \text{ f}^3/\text{Hr DSTP}^*) = 2.80$$

$$SO_2 \text{ LB/MMBTU} = SO_2 \text{ LB/HR} / \text{MMBTU/HR} =$$

*FROM METHOD 5 CALCULATION "Q"

$$\frac{2.77 + 2.80}{2} = 2.79 \text{ #/H}^2 \text{ AVG}$$

$$\frac{16.8 + 16.93}{2} = 16.86 \text{ PPM AVG}$$

C_{SO_2} = Concentration of sulfur dioxide - lb/dry standard cubic foot
 N = Normality of barium perchlorate titrant
 Pb = Barometric pressure - inches Hg
 Tm = Temperature of meter - °F
 Va = Volume of sample aliquot - ml
 Vm = Volume of gas at meter temperature and pressure - f³
 Vm_{std} = Vm corrected to standard temperature and pressure - f³
 V_{soln} = Total volume of sample solution - ml
 Vb = Volume of titrant used for blank - ml
 Y = dry gas meter calibration factor - dimensionless
 K_1 = 17.64
 K_2 = 7.061×10^{-6}

EPA METHOD 7
(NOx)

Barometer, Initial = 29.10	Inches Hg (Pbi)
Flask Vacuum Initial = 27.00	Inches Hg (Pfi)
Flask Temp. Initial = 58.0	Degrees F (Tfi)
Barometer, Final = 29.06	Inches Hg (Pbf)
Flask Vacuum Final = 0.30	Inches Hg (Pbf)
Flask Temp. Final = 70.00	Degrees F (Tff)
Flask Volume = 2040	Ml. (Vf)

$P_i = P_{bi} - P_{fi} = 2.10$ Inches Hg Absolute
 $T_i = 460 + T_{fi} = 518$ Temp. Absolute Degrees R
 $P_f = P_{bf} - P_{ff} = 28.76$ Inches Hg Absolute
 $T_f = 460 + T_{ff} = 530$ Temp. Absolute Degrees R

$V_{sc} = 17.64 (V_f - 25\text{ml.}) ((P_f / T_f) - (P_i / T_i)) = \text{ml. STP} = 1784.7$

Spectrophotometer Calibration Factor = Kc

A 1 = Absorbance of 100 ug Standard = .11
 A 2 = Absorbance of 200 ug Standard = .21
 A 3 = Absorbance of 300 ug Standard = .305
 A 4 = Absorbance of 400 ug Standard = .395

$K_c = 100((A_1 + 2A_2 + 3A_3 + 4A_4) / (A_1^2 + A_2^2 + A_3^2 + A_4^2)) = 991.0$

A = Absorbance Of Sample = 0.035 , F= Dilution Factor = 1.000

M = Total ug NO₂ Per Sample = 2 x Kc x A x F = 69.369

C = Sample Concentration = $6.243 \times 10^{-5} \times M / V_{sc} = 2.4265 \times 10^{-6}$

QS From Method 5 Or Gas Volume Calculation = 998281

C x QS = 2.422 LB/HR

BELDEN BRICK INC
 SUGARCREEK OH
 KILN 1 PLANT 3
 3/3/92
 TEST 1A

EPA METHOD 7
(NOx)

Barometer, Initial = 29.10	Inches Hg (Pbi)
Flask Vacuum Initial = 27.00	Inches Hg (Pfi)
Flask Temp. Initial = 68.0	Degrees F (Tfi)
Barometer, Final = 29.06	Inches Hg (Pbf)
Flask Vacuum Final = 0.50	Inches Hg (Pbf)
Flask Temp. Final = 70.00	Degrees F (Tff)
Flask Volume = 2090	ml. (Vf)

$P_i = P_{bi} - P_{fi} = 2.10$ Inches Hg Absolute
 $T_i = 460 + T_{fi} = 528$ Temp. Absolute Degrees R
 $P_f = P_{bf} - P_{ff} = 28.56$ Inches Hg Absolute
 $T_f = 460 + T_{ff} = 530$ Temp. Absolute Degrees R

$V_{sc} = 17.64 (V_f - 25\text{ml.}) ((P_f / T_f) - (P_i / T_i)) = \text{ml. STP} = 1818.0$

Spectrophotometer Calibration Factor = Kc

A 1 = Absorbance of 100 ug Standard = .11
 A 2 = Absorbance of 200 ug Standard = .21
 A 3 = Absorbance of 300 ug Standard = .305
 A 4 = Absorbance of 400 ug Standard = .395

$K_c = 100((A_1 + 2A_2 + 3A_3 + 4A_4) / (A_1^2 + A_2^2 + A_3^2 + A_4^2)) = 991.0$

A = Absorbance Of Sample = 0.037 , F = Dilution Factor = 1.000
 M = Total ug NO₂ Per Sample = $2 \times K_c \times A \times F = 73.333$

$C = \text{Sample Concentration} = 6.243 \times 10^{-5} \times M / V_{sc} = 2.5182 \times 10^{-6}$

QS From Method 5 Or Gas Volume Calculation = 998281

$C \times QS = 2.514 \text{ LB/HR}$

$$\frac{2.422 + 2.514}{2} = 2.47 \text{ LB/HR Avg Test 1}$$

BELDEN BRICK INC
 SUGARCREEK OH
 KILN 1 PLANT 3
 3/3/92
 TEST 1B

CSA CO. DATA SHEET (METHOD 5)

TEST NO. 2 PLANT BELDEN BRICK								DATE 3/2/92		
LOCATION No 1 KILN PLANT 3						BY RAG GT				
BAROMETER(P _B) 29.10 AMBIENT TEMP				ASSUMED MOISTURE "Y" 1.00%						
MODULE NO. 203 PROBE NO. 2-4 FILTER NO. 5 HEATER NO. 4 NOZZLE DIA.										
TEST POINT	METER VOLUME (Vm)	METER TEMP(Tm) IN OUT	COND TEMP °F	FILTER HEATER TEMP°F	STACK TEMP °F(TS)	STACK PRESS. (Ps)	VACUUM "Hg	ORIFICE "H ₂ O ΔH)(Pm)	VEL HEAD ΔP)	TIME
1	765.9	90 86	46	244	417	0	4	1.8	.24	11:12
1	769.5	96 88	46	246	418		4	1.8	.24	17
2	773.8	100 90	50	248	422		4+	2.0	.30	22
7	777.4	100 90	52	248	424		4-	2.1	.31	27
4	777.4	100 90	54	250	424		4-	2.1	.31	32
1	777.4	98 90	54	250	425		4-	1.8	.27	33
1	783.1	101 91	56	252	425		4-	1.8	.27	38
2	789.4	102 92	58	252	427		4-	1.7	.25	43
7	792.4	102 92	58	250	429		4-	1.7	.25	48
4	796.1	102 92	58	250	431		4-	1.7	.25	53
1	796.1	97 92	54	250	432		3	1.0	.15	53
1	799.0	100 92	54	250	436		3	1.0	.15	12:02
2	802.1	98 92	52	250	440		3+	1.2	.18	05
3	805.3	100 92	50	250	441		3+	1.2	.18	10
4	808.6	100 92	50	250	443		3+	1.2	.18	15
(Vn)	42.7	99.1 90.7								
AVERAGE		95	****	*****	429	0	MAX 5	1.61	.240	60 MINUTES
INTEGRATED GAS SAMPLE				AVG N ₂ =80.4	CONDENSATE COLLECTED					
CO ₂	3.1	3.1		3.1	DRIERITE	FINAL 967.2	INITIAL 962.3	TOTAL 4.9		
O ₂	16.5	16.5		16.5	IMPINGER	243.6	200.0	43.6		
CO										
FILTER WT		PROBE WASH WT		IMPINGER WASH WT		GRAND TOTAL 48.5				
GROSS .6399	181.6350				LEAK RATE @10 "Hg= <.02					
TARE .6657	181.6199				STACK AREA (As) 13.4 ft²					
NET .0242	.0151				AVG SQ RT Δ P .4900					
TOTAL PARTICULAT WT (Mn)				39.3 Mg						

E.P.A. METHOD 5

DATA INPUT

Pb,In Hg	Barometer -----	29.10
VM,ft3	Meter Volume -----	42.7
ΔH,In H2O	Orifice Differential -----	1.61
PG,In H2O	Stack Static Pressure -----	0
Tm,F	Meter Temperture -----	95
Ts,F	Stack Temperture -----	429
CP	Pitot Coefficient -----	.84
√ΔP,In H2O	Average Square Root Of Delta P -----	.4900
% CO2	Carbon Dioxide -----	3.1
% O2	Oxygen -----	16.5
% N	Nitrogen -----	80.4
VCL,M1	Volume Of Condensate -----	48.5
AS,ft2	Stack Area -----	13.4
MN,Mg	Total Particulate Catch Weight -----	39.3
0,Min	Test Time -----	60
DN,In	Diameter Of Nozzle -----	.313

RESULTS

Pma,In Hg	Absolute Meter Pressure -----	29.22
PSA,In Hg	Absolute Stack Pressure -----	29.10
MD	Molecular Weight Dry Gas -----	29.16
MS	Molecular Weight @ Stack Conditions -----	28.55
VMSTP,ft3	VM Standard Temp.& Press. Dry -----	39.61
VWSTP,ft3	VM Standard Temp.& Press. Wet -----	2.28
BWD, %	Moisture -----	5.45
I, %	Isokeimetic Variation -----	103.64
VS,ft/Sec	Stack Velocity -----	36.40
QA,ASCFM	Stack Gas Flow (Actual) -----	29266
QS,ft3/HR	Stack Gas Flow (Dry STP) -----	962687
L, #/Hr	Emission Rate -----	2.11
CS, #/SCF	Particulate Emission -----	2.187629E-06
C'S,Grn/SCF	Particulate Emission -----	0.0153

BELDEN BRICK INC
 SUGARCREEK OH
 KILN 1 PLANT 3
 3/3/92
 TEST 2

CSA CO.

EPA METHOD 6 (SULFUR DIOXIDE) DATA AND CALCULATION SHEET

TEST NO 2-1 PLANT BELDEN BARK DATE 3/3/92
LOCATION No 1 Kiln PLANT 3 BY ERG

Vm	Tm	ROTOMETER	TIME
125.5180	75	3	11:15
5.5381	76	3	20
5.679	79	3	25
5.820	80	3	30
5.969	83	3	35
5.180			
Vm .809	avg 79		

Pb 21.10

$$Vm_{std} = K_1 Y(Vm)(Pb)/(Tm)$$

$$Vm_{std} = 17.64 (1.001) (.771) (29.10) / (460 + 79) = .7828$$

	1st TITRATION	2nd TITRATION	3rd TITRATION	AVERAGE	Vb TITRATION
Vt	17.6	17.7		17.65	.1

$$C_{SO_2} = K_2 (Vt - Vb)(N)(Va)/(Vm_{std})(Vsoln)$$

$$= 0.00007061 (17.65 - .1) (.0098) (20) / (.7828) (100)$$

$$= 3.1038 \times 10^{-6} \text{ lb/f}^3 \text{ DSTP}$$

$$SO_2 \text{ PPM} = (C_{SO_2})(6.037 \times 10^{-6}) = 18.7$$

$$SO_2 \text{ LB/HR} = (C_{SO_2})(962,687 \text{ f}^3/\text{Hr DSTP}^*) = 2.99$$

$$SO_2 \text{ LB/MMBTU} = SO_2 \text{ LB/HR} / \text{MMBTU/HR} =$$

*FROM METHOD 5 CALCULATION "Q"

C_{SO_2} = Concentration of sulfur dioxide - lb/dry standard cubic foot
N = Normality of barium perchlorate titrant
Pb = Barometric pressure - inches Hg
Tm = Temperature of meter - °F
Va = Volume of sample aliquot - ml
Vm = Volume of gas at meter temperature and pressure - f³
Vm_{std} = Vm corrected to standard temperature and pressure - f³
Vsoln = Total volume of sample solution - ml
Vb = Volume of titrant used for blank - ml
Y = dry gas meter calibration factor - dimensionless
K₁ = 17.64
K₂ = 7.061 × 10⁻⁶

CSA CO.

EPA METHOD 6 (SULFUR DIOXIDE) DATA AND CALCULATION SHEET

TEST NO 2-2 PLANT BELDEN BRICK DATE 3/3/92
 LOCATION NO 1 Kiln PLANT 3 BY AK OT

Vm	Tm	ROTOMETER	TIME
125.989	82	3	11:45
6.124	82	3	50
6.280	84	3	55
6.481	85	3	12:00
6.681	86	3	05
Vm .692	avg 84		

Pb 29.10

$$Vm_{std} = K_1 Y(Vm)(Pb)/(Tm)$$

$$Vm_{std} = 17.64 (1.001) (.692) (29.10) / (460 + 84) = .6536$$

	1st TITRATION	2nd TITRATION	3rd TITRATION	AVERAGE	Vb TITRATION
Vt	13.6	13.6		13.6	.1

$$C_{SO_2} = K_2(Vt - Vb)(N)(Va)/(Vm_{std})(Vsoln)$$

$$= 0.00007061(13.6 - .1)(.0098)(20)/(.6536)(100)$$

$$= 2.8585 \times 10^{-6} \text{ lb/f}^3\text{DSTP}$$

$$SO_2 \text{ PPM} = (C_{SO_2})(6.037 \times 10^6) = 17.26$$

$$SO_2 \text{ LB/HR} = (C_{SO_2})(462,687 \text{ f}^3/\text{Hr DSTP}^*) = 2.75$$

$$SO_2 \text{ LB/MMBTU} = SO_2 \text{ LB/HR} /$$

$$\text{MMBTU/HR} = \frac{2.99 + 2.75}{2} = 2.87 \text{ LB/HR AVERAGE}$$

$$\frac{18.7 + 17.3}{2} = 18 \text{ PPM AVERAGE}$$

*FROM METHOD 5 CALCULATION "Q"

C_{SO_2} = Concentration of sulfur dioxide - lb/dry standard cubic foot
 N = Normality of barium perchlorate titrant
 Pb = Barometric pressure - inches Hg
 Tm = Temperature of meter - °F
 Va = Volume of sample aliquot - ml
 Vm = Volume of gas at meter temperature and pressure - f³
 Vm_{std} = Vm corrected to standard temperature and pressure - f³
 Vsoln = Total volume of sample solution - ml
 Vb = Volume of titrant used for blank - ml
 Y = dry gas meter calibration factor - dimensionless
 K₁ = 17.64
 K₂ = 7.061 X 10⁻⁶

EPA METHOD 7
(NOx)

Barometer. Initial = 29.10	Inches Hg (Pbi)
Flask Vacuum Initial = 27.00	Inches Hg (Pfi)
Flask Temp. Initial = 73.0	Degrees F (Tfi)
Barometer. Final = 29.06	Inches Hg (Pbf)
Flask Vacuum Final = 0.10	Inches Hg (Pbf)
Flask Temp. Final = 70.00	Degrees F (Tff)
Flask Volume = 1953	Ml. (Vf)

$P_i \equiv P_{bi} - P_{fi} = 2.10$ Inches Hg Absolute
 $T_i = 460 + T_{fi} = 533$ Temp. Absolute Degrees R
 $P_f = P_{bf} - P_{ff} = 28.96$ Inches Hg Absolute
 $T_f = 460 + T_{ff} = 530$ Temp. Absolute Degrees R

$V_{sc} = 17.64 (V_f - 25\text{ml.}) ((P_f / T_f) - (P_i / T_i)) \equiv \text{ml. STP} = 1724.4$

Spectrophotometer Calibration Factor = Kc

A 1 = Absorbance of 100 ug Standard = .11
 A 2 = Absorbance of 200 ug Standard = .21
 A 3 = Absorbance of 300 ug Standard = .305
 A 4 = Absorbance of 400 ug Standard = .395

$K_c = 100((A_1 + 2A_2 + 3A_3 + 4A_4) / (A_1^2 + A_2^2 + A_3^2 + A_4^2)) = 991.0$

A = Absorbance Of Sample = 0.035 , F= Dilution Factor = 1.000
 M = Total ug NO₂ Per Sample = 2 x Kc x A x F = 69.369

$C = \text{Sample Concentration} = 6.243 \times 10^{-5} \times M / V_{sc} = 2.5115 \times 10^{-6}$

QS From Method 5 Or Gas Volume Calculation = 962687

$C \times QS = 2.418 \text{ LB/HR}$

BELDEN BRICK INC
 SUGARCREEK OH
 KILN 1 PLANT 3
 3/3/92
 TEST 2

CSA CO. DATA SHEET (METHOD 5)

TEST NO. 3 PLANT BELDEN BRICK									DATE 3/3/92		
LOCATION No. 1 KILN						PLANT 3		BY RAK CT			
BAROMETER (P _B) 29.10				AMBIENT TEMP		ASSUMED MOISTURE		"Y" 1.003			
MODULE NO. 2031		PROBE NO. 3-4		FILTER NO. 4		HEATER NO. 6		NOZZLE DIA.			
TEST POINT	METER VOLUME (Vm)	METER TEMP (Tm) IN OUT		COND TEMP °F	FILTER HEATER TEMP °F	STACK TEMP °F (Ts)	STACK PRESS. (Ps)	VACUUM "Hg"	ORIFICE "H ₂ O" (ΔH) (Pm)	VEL HEAD (ΔP)	TIME
1	808.8	95	92	50	248	416	0	3	1.0	.15	12:23
1	812.0	98	92	50	248	446		3	1.0	.15	28
2	815.5	101	93	50	250	408		4	1.6	.25	33
3	818.2	100	94	48	250	391		3-	1.62	.10	38
4	821.4	100	93	48	250	390		3+	1.3	.19	43
1	821.4	98	93	48	250	387		4-	1.6	.25	46
1	824.9	100	93	50	252	388		4-	1.6	.23	49
2	828.9	103	93	50	250	388		4-	1.5	.23	54
7	832.5	104	94	50	250	388		4-	1.5	.24	59
4	836.8	104	94	50	250	388		4-	1.5	.24	13:04
1	836.8	102	94	50	248	389		4-	1.5	.24	05
1	839.6	104	94	50	250	391		4-	1.5	.24	10
2	843.4	104	95	52	250	393		5-	1.8	.27	15
3	850.1	104	95	56	248	394		5-	1.8	.27	20
4	850.7	104	95	56	250	396		5-	1.6	.27	25
(Vm)	41.9	101.4	93.6								
AVERAGE		98	***	*****	397	0	MAX 6	1.44	.222	60 MINUTES	
INTEGRATED GAS SAMPLE				AVG	N ₂ = 80.1	CONDENSATE COLLECTED					
CO ₂	3.0	3.0		3.0	DRIERITE	FINAL	INITIAL	TOTAL			
O ₂	16.9	16.9		16.9	IMPINGER	970.7	963.9	6.8			
CO						242.8	200.0	42.8			
FILTER WT	PROBE WASH WT			IMPINGER WASH WT			GRAND TOTAL 49.6				
GROSS .6850	188.5725			NA NA			LEAK RATE @ 11 "Hg = <.02				
TARE .6645	188.5454						STACK AREA (As) 13.4 f ²				
NET .205	.0271						AVG SQ RT ΔP .4706				
TOTAL PARTICULAT WT (Mn) 47.6 Mg											

E.P.A. METHOD 5

DATA INPUT

Pb, In Hg	Barometer -----	29.10
VM, ft ³	Meter Volume	41.9
ΔH, In H ₂ O	Orifice Differential -----	1.44
PG, In H ₂ O	Stack Static Pressure	0
Tm, F	Meter Temperature -----	98
Ts, F	Stack Temperature	397
CP	Pitot Coefficient -----	.84
√ΔP, In H ₂ O	Average Square Root Of Delta P	.4706
% CO ₂	Carbon Dioxide -----	3.0
% O ₂	Oxygen	16.9
% N	Nitrogen -----	80.1
VCL, Ml	Volume Of Condensate	49.6
AS, ft ²	Stack Area -----	13.4
MN, Mg	Total Particulate Catch Weight	47.6
Ø, Min	Test Time -----	60
DN, In	Diameter Of Nozzle	.313

RESULTS

Pma, In Hg	Absolute Meter Pressure -----	29.21
PSA, In Hg	Absolute Stack Pressure	29.10
MD	Molecular Weight Dry Gas -----	29.16
MS	Molecular Weight @ Stack Conditions	28.52
VMSTP, ft ³	VM Standard Temp. & Press. Dry -----	38.66
VWSTP, ft ³	VM Standard Temp. & Press. Wet	2.33
BWD, %	Moisture -----	5.69
I, %	Isokeimetic Variation	103.63
VS, ft/Sec	Stack Velocity -----	34.34
QA, ASCFM	Stack Gas Flow (Actual)	27610
QS, ft ³ /HR	Stack Gas Flow (Dry STP) -----	939679
L, #/Hr	Emission Rate	2.55
CS, #/SCF	Particulate Emission -----	2.714833E-06
C'S, Grn/SCF	Particulate Emission	0.0190

BELDEN BRICK INC
 SUGARCREEK OH
 KILN 1 PLANT 3
 3/3/92
 TEST 3

CSA CO.

EPA METHOD 6 (SULFUR DIOXIDE) DATA AND CALCULATION SHEET

TEST NO 3-1 PLANT BELDEN BRICK DATE 3/3/92
 LOCATION NO 1 KILN PLANT 3 BY AK GT

Vm	Tm	ROTOMETER	TIME
126.681	82	3	12:30
126.958	82	3	33
127.235	84	3	40
127.547	86	3	45
127.659	87	3	50
6.681			
Vm .978	avg 84		

Pb 29.10

$$Vm_{std} = K_1 Y(Vm)(Pb)/(Tm)$$

$$Vm_{std} = 17.64 (1.001) (.978) (29.10) / (460 + 84) = .9238$$

	1st TITRATION	2nd TITRATION	3rd TITRATION	AVERAGE	V _b TITRATION
Vt	16.9	16.8		16.85	.1

$$C_{SO_2} = K_2 (Vt - Vb)(N)(Va)/(Vm_{std})(Vsoln)$$

$$= 0.00007061 (16.85 - .1) (.0099) (20) / (.9238) (100)$$

$$= 2.5093 \times 10^{-6} \text{ lb/f}^3 \text{ DSTP}$$

$$SO_2 \text{ PPM} = (C_{SO_2})(6.037 \times 10^6) = 15.15$$

$$SO_2 \text{ LB/HR} = (C_{SO_2})(939,679 \text{ f}^3/\text{Hr DSTP}^*) = 2.36$$

$$SO_2 \text{ LB/MMBTU} = SO_2 \text{ LB/HR} / \text{MMBTU/HR} =$$

*FROM METHOD 5 CALCULATION "Q"

C_{SO_2} = Concentration of sulfur dioxide - lb/dry standard cubic foot
 N = Normality of barium perchlorate titrant
 Pb = Barometric pressure - inches Hg
 Tm = Temperature of meter - °F
 Va = Volume of sample aliquot - ml
 Vm = Volume of gas at meter temperature and pressure - f³
 Vm_{std} = Vm corrected to standard temperature and pressure - f³
 Vsoln = Total volume of sample solution - ml
 Vb = Volume of titrant used for blank - ml
 Y = dry gas meter calibration factor - dimensionless
 K₁ = 17.64
 K₂ = 7.061 X 10⁻⁶

CSA CO.

EPA METHOD 6 (SULFUR DIOXIDE) DATA AND CALCULATION SHEET

TEST NO 3-2 PLANT BELDON BRICK DATE 3/3/91
 LOCATION NO 1 KILN PLANT 3 BY LEE GT

Vm	Tm	ROTOMETER	TIME
127.659	84	3	13:02
7.890	86	3	07
8.120	88	3	12
8.326	89	3	17
128.531	90	3	22
17.64			
Vm 1872	avg 87		

Pb 29.10

$$Vm_{std} = K_1 Y(Vm)(Pb)/(Tm)$$

$$Vm_{std} = 17.64 (1.001) (.872) (29.10) / (460 + 87) = .8191$$

	1st TITRATION	2nd TITRATION	3rd TITRATION	AVERAGE	Vb TITRATION
Vt	16.4	16.4		16.4	.1

$$C_{SO_2} = K_2 (Vt - Vb)(N)(Va)/(Vm_{std})(Vsoln)$$

$$= 0.00007061 (16.4 - .1) (.0098) (20) / (.8191) (100)$$

$$= 2.7541 \times 10^{-6} \text{ lb/f}^3 \text{ DSTP}$$

$$SO_2 \text{ PPM} = (C_{SO_2})(6.037 \times 10^6) = 16.62$$

$$SO_2 \text{ LB/HR} = (C_{SO_2})(939,679 \text{ f}^3/\text{Hr DSTP}^*) = 2.59$$

$$SO_2 \text{ LB/MMBTU} = SO_2 \text{ LB/HR} / \text{MMBTU/HR} =$$

$$\frac{2.36 + 2.59}{2} = 2.44 \text{ LB/HR AVERAGE}$$

*FROM METHOD 5 CALCULATION "Q"

$$\frac{15.13 + 16.62}{2} = 15.9 \text{ PPM AVERAGE}$$

C_{SO_2} = Concentration of sulfur dioxide - lb/dry standard cubic foot
 N = Normality of barium perchlorate titrant
 Pb = Barometric pressure - inches Hg
 Tm = Temperature of meter - °F
 Va = Volume of sample aliquot - ml
 Vm = Volume of gas at meter temperature and pressure - f³
 Vm_{std} = Vm corrected to standard temperature and pressure - f³
 Vsoln = Total volume of sample solution - ml
 Vb = Volume of titrant used for blank - ml
 Y = dry gas meter calibration factor - dimensionless
 K₁ = 17.64
 K₂ = 7.061 × 10⁻⁶

EPA METHOD 7
(NOx)

Barometer, Initial = 29.10	Inches Hg (Pbi)
Flask Vacuum Initial = 27.00	Inches Hg (Pfi)
Flask Temp. Initial = 72.0	Degrees F (Tfi)
Barometer, Final = 29.06	Inches Hg (Pbf)
Flask Vacuum Final = 0.30	Inches Hg (Pbf)
Flask Temp. Final = 70.00	Degrees F (Tff)
Flask Volume = 1951	Ml. (Vf)

$P_i = P_{bi} - P_{fi} = 2.10$ Inches Hg Absolute
 $T_i = 460 + T_{fi} = 532$ Temp. Absolute Degrees R
 $P_f = P_{bf} - P_{ff} = 28.76$ Inches Hg Absolute
 $T_f = 460 + T_{ff} = 530$ Temp. Absolute Degrees R

$V_{sc} = 17.64 (V_f - 25\text{ml.}) ((P_f / T_f) - (P_i / T_i)) = \text{ml. STP} = 1709.5$

Spectrophotometer Calibration Factor = Kc

A₁ = Absorbance of 100 ug Standard = .11
 A₂ = Absorbance of 200 ug Standard = .21
 A₃ = Absorbance of 300 ug Standard = .305
 A₄ = Absorbance of 400 ug Standard = .395

$K_c = 100((A_1 + 2A_2 + 3A_3 + 4A_4) / (A_1^2 + A_2^2 + A_3^2 + A_4^2)) = 991.0$

A = Absorbance Of Sample = 0.029 , F = Dilution Factor = 1.000
 M = Total ug NO₂ Per Sample = 2 x Kc x A x F = 57.477

$C = \text{Sample Concentration} = 6.243 \times 10^{-5} \times M / V_{sc} = 2.0990 \times 10^{-6}$

QS From Method 5 Or Gas Volume Calculation = 939679

$C \times QS = 1.972 \text{ LB/HR}$

BELDEN BRICK INC
 SUGARCREEK OH
 KILN 1 PLANT 3
 3/3/92
 TEST 3

APPENDIX II

INTENT TO TEST NOTIFICATION

Proposed test Date MARCH 3, 1992
Pre-Test Meeting Desired? Yes 1 No 0

NAME Béldér, Bence

Contact Person John Jensen

B. Testing Firm Information

CSA CO. (CUSTOM STACK ANALYSIS)

Ernie Kolm

Address Delaware 3 Submarine ON

Telephone Number (214) 852-2424

Address 24385 CENTER ROAD, ALLIANCE, OH 44601

Telephone Number (216) 525-5119

C. Source Sampling Information: Identify all sources and pollutants to be sampled.

[illegible]

Any modifications to USEPA Reference Method(s)? Yes ☒ No ☐ : If yes explain

Supplier(s)	Inlet	Outlet	Simultaneous
	17	17	

Fuel Sampling:	Coal - Proximate	Ultimate	Other (specify)
	✓	✓	

Emission Rate to be calculated using: F-Factor

Are concurrent Method 9 readings to be performed?	Yes	No
	☒	☐

D. Sample Train Calibration: All affected measuring and metering equipment should be calibrated within 60 days of the scheduled testing.

CSA COMPANY

CUSTOM STACK ANALYSIS

24661 CENTER ROAD

P.O. BOX 3730

ROUTE 5

ALLIANCE, OHIO 44501


GENERAL

Source emission tests will be performed at BELDEN BRICK
PLANT #3 on JULY 21, 198 with testing to
commence at about 900 O'clock 4 AM PM as per INTENT
TO TEST NOTIFICATION.

The sample train is a Research Appliance Corp model 2043 using
a Pyrex lined probe heated to 250 °F. The filter media is
A/E FIBROGLASS enclosed in pyrex holders heated to 250 °F. The
contents of the impingers will be used for (a) 4 moisture
determination only, (b) moisture determination and particulate
weight. The gas drying agent after the impingers is calcium sulfate
contained in a "Drierite" desiccant column. The probe and glassware
will be washed using ACE TONE & BAUSH. If impinger contents
are used as part of the particulate weight, they will be dried by
 at °C. The test and analytical procedures
used are as per latest FEDERAL EPA REGULATIONS AS WRITTEN IN THE
FEDERAL REGISTER.

An equivalent emissions opacity test is requested

DESCRIPTION OF PLANT OPERATIONCONTINUOUS BRICK KILNSTACK AND VENT DESCRIPTIONSEE SKETCHES





$$\text{AREA} = 13.4 \text{ f}^2$$

$$\text{EQUIVALENT DIA.} = 44"$$


$$\text{EQUIV. DIA. UPSTREAM} = 7.1$$

$$\text{EQUIV. DIA. DOWNSTREAM} = 2+$$







C.S.A. Co.
 MODIFICATION OF R.A.C. SAMPLE TR
 USING DRIERITE COLUMN IN PLACE O
 IMPINGER DESICANT



INTEGRATED SAMPLER








METHOD 7 NO_x SAMPLE APPARATUS




- 1) HEATED PYREX LINED PROBE. END PACKED WITH QUARTZ WOOL
- 2) MIDGET BUBBLER. TOP PAKED WITH GLASS WOOL
- 3) MIDGET IMPINGERS. EACH FILLED WITH 15 ml OF H_2O_2 (3%)
- 4) MIDGET IMPINGER. DRY TRAP
- 5) ICE BATH
- 6) DRIERITE COLUMN. FILLED WITH CALCIUM SULFATE DESICANT
- 7) UMBILICAL CORD
- 8) ROTAMETER
- 9) VACUUM GAGE
- 10) VALVE FOR COARSE FLOW ADJUSTMENT
- 11) VALVE FOR FINE FLOW ADJUSTMENT
- 12) OILER
- 13) OIL FILTER
- 14) VACUUM PUMP
- 15) DRY GAS TEST METER
- 16) THERMOMETER

E.P.A. METHOD 6 SO_2 SAMPLING TRAIN




NOTE: Flow rate held constant at 0.75; 50% change in flow rate has little effect on probe temperature.

Figure 16
Probe Temperatures



Bottom View Showing Pitot-Nozzle Separation



Side View Showing Pitot Static-Impact Dimensions and Distance of Impact Pressure Opening from Nozzle Entry Plane

X & Z 1/16" Tolerance

D_N - Inches (Nominal)	X	Y	Z	D_t
3/16	1	1 7/16	5/16	3/8
1/4	15/16	1 7/16	5/16	3/8
5/16	7/8	1 7/16	5/16	3/8
3/8	3/4	1 7/16	5/16	3/8
1/2	5/8	1 7/16	1/2	3/8

PITOT TUBE INTERFERENCE DIMENSIONS

CSA CO
EPA METHOD 6 (SULFUR DIOXIDE)
DATA AND CALCULATION SHEET

TEST NO. _____ PLANT _____ DATE _____
LOCATION _____ BY _____

V _m	T _{mi}	T _{mo}	ROTOMETER	TIME
V _m	T _m			

Pbar _____

$$Vmstd = K_1 Y \frac{V_m P_b}{T_m}$$

$$Vmstd = 17.64 () \frac{() ()}{(460. +)} =$$

	1 st TITRATION	2 nd TITRATION	3 rd TITRATION	AVERAGE	V _b TITRATION
V _t					

$$C_{SO_2} = K_2 \frac{(V_t - V_b)(N) \left(\frac{V_{soln}}{V_a} \right)}{Vmstd}$$

$$= .00007061 (-) () () = \text{Lb/f}^3\text{DSTP}$$

$$SO_2 \text{ (PPM)} = (C_{SO_2})(6.037)(10^6) =$$

$$\text{Lb } SO_2/\text{Hr} = (\text{f}^3/\text{HrDSTP}) (\text{Lb/f}^3\text{DSTP}) =$$

$$\text{Lb/MBTU} = \text{Lb/Hr} - \text{MBTU} =$$

- C_{SO_2} = Concentration of sulfur dioxide - lb/dry standard cubic foot
 N = Normality of barium perchlorate titrant
 P_{bar} = Barometric pressure - inches Hg
 T_{mi} = Temperature at meter inlet - °F
 T_{mo} = Temperature at meter outlet - °F
 T_m = Average meter temperature - °F
 V_a = Volume of sample aliquot titrated - ml
 V_m = Dry gas volume as measured at meter - dcf
 $V_m(std)$ = V_m corrected to standard conditions - dscf
 V_{soln} = Total volume of sample solution - ml
 V_t = Average volume of titrant used for sample aliquot - ml
 V_b = Volume of titrant used for blank - ml
 Y = Dry gas meter calibration factor
 K_1 = 17.64 K_2 = 7.061×10^{-5}

CSA CO. NO_x DATA SHEET

TEST	DATE	TIME	BAROMETER		FLASK VACUUM		FLASK TEMP		FLASK VOLUME
			INITIAL	FINAL	INITIAL	FINAL	INITIAL	FINAL	

SPECTROPHOTOMER CALIBRATION

ABSORBANCE OF ABSORBANT SOLUTION = 0

A1=ABSORBANCE OF 100 g STD = _____

A2= " " 200 g " = _____

A3= " " 300 g " = _____

A4= " " 400 g " = _____

SAMPLE DILLUTION FACTOR = _____

A=SAMPLE ABSORBANCE

TEST	A

SEE COMPUTER CALCULATION SHEET FOR RESULTS

FOR _____ BY _____
LOCATION _____

C.S.A. Co.
STACKSAMPLR CALIBRATION SHEET

Customer _____ Order No. _____
 Date 12/3/91 Serial No. 2031 RAC Order No. _____
 Pump OK Pump Oil CHG Clean Quick Disconnects YES
 Manometers CHG FLUID Dry Test Meter OK Thermometers CALIBRATED
 Lights OOK Electrical Check OK Variac OK
 Vacuum Gauge REPAVED Leak Check @ 27" Hg Vacuum NO LEAKES
 Remarks PRESSURE CHECK AT 9 IN. H2O-NO LEAKS

Barometer (Pb) 29.09

K	N	DH	CFw	CFd	Tw	ITd	OTd	TD	t	H	Y
0158	0368	0.5	5	5.05	70	75	72	74	12.84	1.891	0.996
0317	0737	1.0	5	5.03	70	77	73	75	9.06	1.886	1.001
0634	1470	2.0	10	10.04	70	79	74	76	12.85	1.893	1.002
1268	2490	4.0	10	10.11	70	85	81	83	9.12	1.882	1.005
1902	4310	6.0	10	10.09	70	89	81	85	7.48	1.899	1.004
2536	5880	8.0	10	10.09	70	91	82	86	6.47	1.891	1.001

Tolerances H=1.6-1.84-2.1 , Y=0.99-1.00-1.01 AVG 1.890 1.002

$$H = (K / (Pb(OTd + 460))) * (((Tw + 460)t) / CFw)^2$$

$$Y = (CFw Pb (Td \text{ avg.} + 460)) / (CFd (Pb + N) (Tw + 460))$$

DH= Orifice pressure drop - in. H₂O

CFw= Volume wet test meter - f³

CFd= Volume dry test meter - f³

Tw= Temp. wet test meter

ITd= Inlet temperature dry test meter

OTd= Outlet temperature dry test meter

Td avg.= Average temperature dry test meter

t= Time - minutes

Pb=Barometer press.

DIAL THERMOMETER CALIBRATION

Precision Lab Thermometer

Meter Thermometers

Impinger Outlet Thermometer (1)

(2)

ICE WATER

32

ITd 32 OTd 32

32

32

BOILING WATER

211

ITd 210 OTd 210

211

211

STACK DIGITAL TEMPERATURE INDICATORS

NBS TRACABLE FROM FACTORY. 2 UNITS CALIBRATED AGAINST EACH OTHER(PyroMation)

ALL THERMOCOUPLES ARE CALIBRATED BY OVEN FROM 100 TO 500°F AGAINST A CMS

LAB THERMOMETER (No. 227-934). ANY THERMOCOUPLE THAT IS MORE THAN ±2°F

FROM STANDARD IS DISCARDED.

C.S.A. Co.
STACKSAMPLR CALIBRATION SHEET

Customer _____ Order No. _____
Date 2/29/92 Serial No. 2031 RAC Order No. _____

Pump OK Pump Oil CHG Clean Quick Disconnects YES
Manometers OK Dry Test Meter OK Thermometers OK
Lights OK Electrical Check OK Variac OK
Vacuum Gauge OK Leak Check @ 27" Hg Vacuum NO LEAKS
Remarks _____

Barometer (Pb) 28.96

K	N	DH	CFw	CFd	Tw	ITd	OTd	TD	t	H	Y
.0158	.0368	0.5	5	5.06	72	76	73	74	12.82	1.905	0.991
.0317	.0737	1.0	5	5.03	72	79	76	78	9.05	1.894	1.003
.0634	.1470	2.0	10	10.05	72	81	76	78	12.83	1.903	1.001
.1268	.2490	4.0	10	10.10	72	87	82	84	9.10	1.893	1.004
.1902	.4310	6.0	10	10.08	72	90	83	86	7.45	1.900	1.003
.2536	.5880	8.0	10	10.07	72	92	84	88	6.45	1.895	1.003

Tolerances H=1.6-1.84-2.1 , Y=0.99-1.00-1.01

$$H=(K/(Pb(OTd+460)))*(((Tw+460)t)/CFw)^2$$

$$Y=(CFw Pb (Td \text{ avg.} +460))/(CFd (Pb+N) (Tw+460))$$

DH= Orifice pressure drop - in. H₂O

CFw= Volume wet test meter - f³

CFd= Volume dry test meter - f³

Tw= Temp. wet test meter

ITd= Inlet temperature dry test meter

OTd= Outlet temperature dry test meter

Td avg.= Average temperature dry test meter

t= Time - minutes

Pb=Barometer press.

DIAL THERMOMETER CALIBRATION

Precision Lab Thermometer

Meter Thermometers

Impinger Outlet Thermometer (1)
(2)

ICE WATER

32

ITd 33 OTd 33

31

33

BOILING WATER

211

ITd 210 OTd 211

210

212

STACK DIGITAL TEMPERATURE INDICATORS

NBS TRACABLE FROM FACTORY. 2 UNITS CALIBRATED AGAINST EACH OTHER(PyroMation)
ALL THERMOCOUPLES ARE CALIBRATED BY OVEN FROM 100 TO 500°F AGAINST A CMS
LAB THERMOMETER (No. 227-934). ANY THERMOCOUPLE THAT IS MORE THAN ±2°F
FROM STANDARD IS DISCARDED.