


Note: This is a reference cited in AP 42, *Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP42 Section:	11.3
Reference:	14
Title:	Mass Emission Tests Conducted On The Tunnel Kiln #21 In Glasgow, VA, For General Shale Products Corporation, Guardian Systems, Inc., Leeds, AL, October 16, 1990.

GUARDIAN SYSTEMS INC.

**P.O. Box 300
Leeds, Alabama 35094
205/699-6647**



Test Report

MASS EMISSION TESTS

CONDUCTED ON THE

TUNNEL KILN #21

IN

GLASGOW, VIRGINIA


FOR

GENERAL SHALE PRODUCTS CORPORATION

ON

OCTOBER 16, 1990

APPROVED BY




Tom Lotz
Director, Field Services

TABLE OF CONTENTS

Chapter		Page
I	Introduction and Process Description	1
II	Discussion of Test Results	2
	Tables	
	1 Summarized Test Results	3
	Graph	
	1 Mass Emissions	4
	Computer Input Parameters	5
	Complete Results	6
III	Sampling and Analytical Procedures	8
	Figures	
	1 Stack Breeching Diagram	
	and Sample Point Location	11
	2 Particulate Sampling Train	12
IV	Field Data	
	Nomenclature	13
	Equations	17
	Hand Calculations	20
	Data Sheets	21
	Particulate Analysis	24
V	Plant Operational Data	31
V	Calibrations	32

Introduction




I. INTRODUCTION AND TEST DESCRIPTION

On October 16, 1990, Guardian Systems, Inc., performed a series of particulate emissions test on the General Shale Products Brick Plant Tunnel Kiln No. 21 located in Glasgow, Virginia. These test were conducted in accordance to the rules and regulations expressed in the Code of Federal Regulations, Title 40, Section 60, Reference Method 1-5 as amended.

Individual bricks are formed and stacked onto kiln cars measuring approximately 5'9" x 9'2". Cars are inserted on a regular basis into a long, continuous-fired tunnel kiln. As one car is discharged another is inserted. This provides a constant moving mass inside the kiln. Cars are pushed through the 500 foot long kiln at a slow, methodical pace requiring almost 2 days for the complete travel. By means of a 100% coal firing process (See Coal analysis), heat is increased through the kiln until the total firing is complete. As the car continues through the kiln from the main firing zone the temperatures are reduced to provide necessary cooling.

Mr. Dave McNees and Mr. Mike Whitehead represented General Shale Products Corporation, and is responsible for all production data. Mr. Jeff Helbert, the Plant Manager, was responsible for the operation of the plant. Mr. Raymond Goetz, State Air Pollution Control Board, Commonwealth of Virginia observed the tests, while Ms. Robina Jordan read visual emissions. Mr. Tom Lotz and Mr. Emmanuel Isong of Guardian Systems, Incorporated, performed these test.

Test Results



II. SUMMARY OF TEST RESULTS

Table 1 is a summary of the test results on October 17-18, 1990 for the Tunnel Kiln #21.

$$E = 4.10 p^{0.67}$$

Where E = Allowable emission rate, lbs/hour

P = process weight, tons/hour

The allowable emission rate, based on a process weight of 8.41 tons per hour, is 17.08 pounds per hour. The permit limit is 16.66 pounds per hour. The average actual emission rate is 4.36 pounds per hour which is 26 percent of the allowable emission rate, and 26 percent of the permit limit.

Run Number	1	2	3	Composite
Process Weight, Tons/hr	8.41	8.41	8.41	8.41
Particulate Emissions, #/hr	5.63	4.94	3.14	4.36
Allowables, #/hr	17.08	17.08	17.08	17.08
Permit Limit, #/hr	16.66	16.66	16.66	16.66

G U A R D I A N * S Y S T E M S * I N C O R P O R A T E D

P.O. BOX 190
LEEDS, AL 35094
205-699-6647


Summarized Air Test Results for General Shale Products Corporation

Run Number	1	2	3	Composite
Date	10/16/90	10/16/90	10/16/90	10/16/90
Location	TK 21	TK 21	TK 21	TK 21
Time	1128-1231	1325-1428	1512-1614	1128-1614
Stack Gas Temperature, F	451	457	452	453
Moisture Content, % v/v	10.77	10.84	10.43	10.64
Oxygen Content, % v/v	11.50	14.00	15.25	13.58
Carbon Dioxide Content, % v/v	8.50	7.00	5.00	6.83
Carbon Monoxide Content, % v/v	0.00	0.00	0.00	0.00
Excess Air, %	119.54	204.20	262.75	182.90
Stack Gas Velocity Feet per Second	18.23	17.03	16.43	16.95
Volumetric Flow Actual Cubic Feet per Minute	5,546	5,180	4,997	5,156
Volumetric Flow Dry Std Cubic Feet per Minute	2,829	2,623	2,556	2,627
Concentration Grains per Dry Std Cubic Ft	0.232	0.220	0.143	0.194
Concentration Grains per Actual Cubic Foot	0.118	0.111	0.073	0.099
Particulate Mass Rate, #/hr	5.63	4.94	3.14	4.36
Allowable Emission Rate, #/hr	17.08	17.08	17.08	17.08
Permit Limit, #/hr	16.66	16.66	16.66	16.66
% Isokinetic	104.41	98.03	98.80	102.29

Table 1

GENERAL SHALE PRODUCTS TK21

On October 16, 1990



Graph 1

G U A R D I A N * S Y S T E M S * I N C O R P O R A T E D
P.O. BOX 190
LEEDS, AL 35094
205-699-6647

Computer Input Parameters for General Shale Products Corporation

Run Number	1	2	3 Composite	
Date	10/16/90	10/16/90	10/16/90	10/16/90
Location	TK 21	TK 21	TK 21	TK 21
Time	1128-1231	1325-1428	1512-1614	1128-1614
Barometric Pressure, in Hg	29.51	29.51	29.51	29.51
Static Pressure, in H2O	0.050	0.040	0.060	0.050
Run Time, minutes	62.50	62.50	62.50	187.50
Meter Volume, CF	27.808	44.064	42.969	114.841
Meter Correction factor, MCF	1.0498	1.0498	1.0498	
Meter Volume (Corrected)	29.193	46.258	45.109	120.560
Stack Temperature, F	451	457	452	453
Meter Temperature, F	71	91	87	83
Meter Pressure, in H2O	0.65	1.79	1.67	1.37
Sqr Velocity Pressure	0.239	0.222	0.214	0.225
Mass of Particulate, mg	432.3	626.3	401.5	1460.0
Ml of Water Collected	73.5	113.4	106.7	293.6
% Oxygen	11.50	14.00	15.25	13.58
% Carbon Dioxide	8.50	7.00	5.00	6.83
% Carbon Monoxide	0.00	0.00	0.00	0.00
Stack Area, Sq ft	5.070	5.070	5.070	5.070
Pitot Correction Factor	0.858	0.858	0.858	0.844
Nozzle Diameter, in	0.380	0.504	0.504	0.463
Feed Rate, Tons/hr	8.41	8.41	8.41	8.41

G U A R D I A N * S Y S T E M S * I N C O R P O R A T E D

P.O. BOX 190
LEEDS, AL 35094
205-699-6647

Computed Air Test Results for General Shale Products Corporation


Run Number	1	2	3 Composite	
Date	10/16/90	10/16/90	10/16/90	10/16/90
Location	TK 21	TK 21	TK 21	TK 21
Time	1128-1231	1325-1428	1512-1614	1128-1614
1. Stack Pressure				
Inches Hg	29.51	29.51	29.51	29.51
Millimeters Hg	749.65	749.63	749.67	749.65
2. Meter Pressure				
Inches Hg	29.56	29.64	29.63	29.61
Millimeters Hg	750.77	752.90	752.67	752.11
3. Meter Volume				
Dry Std Cubic Feet	28.677	43.915	43.124	116.018
Dry Std Cubic Meters	0.812	1.244	1.221	3.286
4. Water Volume				
Std Cubic Feet	3.460	5.338	5.022	13.820
Std Cubic Meters	0.098	0.151	0.142	0.391
5. Moisture Content, %	10.77	10.84	10.43	10.64
6. Molecular Weight Dry	29.82	29.68	29.41	29.64
7. Molecular Weight Wet	28.55	28.41	28.22	28.40
8. Stack Velocity				
Feet per Second	18.23	17.03	16.43	16.95
Meters per Second	5.56	5.19	5.01	5.17
9. Volumetric Flow				
Actual Cubic Ft per minute	5,546	5,180	4,997	5,156
Actual Cubic M per second	2.62	2.45	2.36	2.43
10. Volumetric Flow				
Dry Std Cubic Ft per minute	2,829	2,623	2,556	2,627
Dry Std Cubic M per second	1.34	1.24	1.21	1.24
11. Concentration				
Grains per Dry Std Cubic Ft	0.2321	0.2196	0.1434	0.1938
Grams per Dry Std Cubic M	0.5312	0.5026	0.3281	0.4435
12. Excess Air, %	119.54	204.20	262.75	182.90

GUARDIAN * SYSTEMS * INCORPORATED
P.O. BOX 190
LEEDS, AL 35094
205-699-6647

Computed Air Test Results for General Shale Products Corporation

Run Number	1	2	3	Composite
Date	10/16/90	10/16/90	10/16/90	10/16/90
Location	TK 21	TK 21	TK 21	TK 21
Time	1128-1231	1325-1428	1512-1614	1128-1614
15. Particulate Mass Rate Pounds per Hour, #/hr	5.63	4.94	3.14	4.36
16. Volume at Nozzle				
Actual Cubic Feet	56.214	86.725	84.310	227.700
Actual Cubic Meters	1.592	2.456	2.388	6.448
17. Concentration				
Grains per Actual Cubic Ft	0.1184	0.1112	0.0733	0.0987
Grams per Actual Cubic M	0.2710	0.2545	0.1678	0.2260
18. Isokinetic, %	104.41	98.03	98.80	102.29

Sampling & Analytical Procedures



III. SAMPLING AND ANALYTICAL PROCEDURES

General

All sampling and analytical procedures for the determination of the particulate emissions from these sources were conducted in strict adherence with the Code of Federal Regulations, Title 40, Part 60, Appendix A, Methods 1-5 as amended. The sampling equipment used in these tests was manufactured by Research Appliance Corporation and was properly calibrated before these tests (See Calibrations). The particulate mass was determined gravimetrically after removal of uncombined water.

METHOD 1

This method was used to determine the number of sampling points and the required sampling matrix. The dimension of the sample location (see Figure 1) indicated that 25 points would be required to sample this source. We sampled 25 points (5 x 5 matrix) for two and a half minutes at each point.

METHOD 2

Velocity measurements were taken using a properly calibrated S type pitot tube and a micro-manometer (0-0.25 inch scale) having 0.001 inch H₂O divisions on the 0 to 0.25 inch inclined scale was used due to the sufficient number of the low velocity pressures as specified in Method 2.

METHOD 3

Gas composition for CO₂, O₂, and N₂ by difference was performed by using the grab sample technique and analyzed with a Fyrite Gas Analyzer (0-20% scale with 0.5% divisions). Two analysis for CO₂ and O₂ were determined during each test.

METHOD 4

Moisture content of the stack gases was determined in conjunction with Method 5 for each test by measuring the amount of water collected in the condenser and the increase in weight of the silica gel. These weights were combined to give the total amount of water collected.

METHOD 5

Sampling Techniques

From previous data about stack temperature, pressure, range of velocity heads, moisture content and stack gas dry molecular weight; a Radio Shack PC-4 computer and a TI55 was used to calculate the sampling rate for isokinetic sampling. The particulate determinations were made by utilizing the sample train in Figure 2. The meter box was leak checked from the pump to the orifice and initial and final leak checks of the sampling system and pitot lines were performed as outlined in Method 5 and were recorded on the data sheets. The nozzle (stainless steel 316 with an angle of taper of 30 degrees and of button hook design) was calibrated before and after each test using a micrometer and was also recorded on the data sheets.

The sampling probe was placed at each sampling point and the gases were drawn through a stainless steel nozzle attached to a heated glass lined probe. The probe was maintained at the proper setting to obtain an exit temperature of $248 \pm 25^{\circ} \text{F}$ (See **Calibrations**). The gases then pass through a glass fiber filter (Gelman, Class A) of 0.3 micron retention to remove particulate matter. The filter was maintained at a temperature of $248 \pm 25^{\circ} \text{F}$. These temperatures were recorded at each point on the data sheets.

The gases then pass through a condenser placed in an ice bath to maintain a maximum exit temperature of 68°F . This temperature was also recorded on the data sheets. The gases then pass through a pre-weighed drying column filled with indicating silica gel to remove any remaining moisture. The clean and cool gases then entered the meter box where the gas flow and temperature were measured and recorded.

Upon completion of the sampling and the final leak checks, the gel column and the probe nozzle-filter holder assembly was transferred to the cleanup area making sure no particulate is lost. Particulate catches were placed in sealed petri dishes. Each acetone rinse from the nozzle, probe, and filter holder was combined and placed in a sealed container. For the group of tests an acetone blank of approximately 200 milliliters was placed in a sealed container. These containers were clearly marked and transported to our laboratory for analysis.



Analysis

The filters (Gelman, Class A, without organic binder, minimum 99.9% retention for particles of 0.3 microns as determined by DOP tests) were prepared for the field test by first heating for 2 hours 220 degrees F then desiccating at 68 ± 10^0 F at ambient pressure for 24 hours and weighing at intervals of at least six (6) hours to a constant weight to the nearest 0.1 milligrams (less than 0.5 milligrams change from previous reading). Upon return to the laboratory, the filters were subjected to the same procedures as outlined above. The weights were recorded in a bound laboratory book and transferred to the sheets in this report. During each weighing the filter was not exposed to laboratory atmosphere for more than two (2) minutes and a relative humidity of less than fifty percent (50%).

The acetone (reagent grade, 0.001% residue, in glass bottles) blank for the group of tests and the acetone rinses for each test were evaporated to dryness in tared glass beakers. They were then desiccated for twenty-four (24) hours and weighed to a constant weight as described above.


Stack Breeching Diagram
and
Sample Point Location

Point Number	Distance from wall (in.)
1	3.0
2	8.9
3	14.8
4	20.7
5	26.6



NOT TO SCALE


Figure 1



PARTICULATE SAMPLING TRAIN.. METHOD 5

Figure 2

Field Data



NOMENCLATURE

ACF -	Actual Cubic Feet
ACFM -	Actual Cubic Feet per minute
ACM -	Actual Cubic Meters
ACMS -	Actual Cubic Meters per second
An -	Cross sectional area of nozzle, (ft ²)
As -	Area of Stack, (ft ²)
Bws -	Water vapor in the gas stream, proportion by volume (dimensionless)
C _a -	Acetone blank residue concentration, mg/g
c _a -	Particulate Concentration, ACF
CFM -	Cubic feet per minute
C _p -	Pitot tube coefficient, (dimensionless)
c _s -	Particulate Concentration, grains/DSCF
Cso ₂ -	Concentration of sulfur dioxide (dry basis) corrected at standard conditions, lb/DSCF
C ₁₂ -	Particulate concentration (c _s adjusted to 12% excess air), grains/DSCF
C ₅₀ -	Particulate concentration (c _s adjusted to 50% excess air), grains/DSCF
DSCF -	Dry Standard Cubic Feet
DSCFM -	Dry Standard Cubic Feet per minute
DSCM -	Dry Standard Cubic Meters
DSCMS -	Dry Standard Cubic Meters per second
EA -	Excess Air, %
I -	Isokinetic Sampling, %
Km -	Orifice Correction Factor, (dimensionless)
Kp -	Pitot tube constant, $85.49 \frac{(\text{lb/lb-mole})(\text{in.Hg})^{1/2}}{(^{\circ}\text{R})(\text{in. H}_2\text{O})}$

NOMENCLATURE - continued

- La - Maximum acceptable leakage rate for either a pretest leak check or for a leak check following a component change; equal to 0.02 CFM or 4 percent of the average sampling rate, whichever is less.
- Li - Individual leakage rate observed during the leak check conducted prior to the "ith" component change (i = 1,2,3,...n), CFM.
- Lp - Leakage rate observed during the post test leak check, ft³/min. (cfm).
- Ma - Mass of residue of acetone after evaporation, mg.
- Md - Molecular weight of stack gas; dry basis, lb/lb-mole.
- Mn - Total amount of particulate matter collected, mg.
- Ms - Molecular weight of stack gas; wet basis, lb/lb-mole.
- Mw - Molecular weight of water, 18.0g/g-mole(18.01lb/lb-mole)
- ΔP - Velocity head of stack gas, in. H₂O
- Pa - Density of acetone, mg/ml
- Pbar - Barometric pressure at the sampling site, in. Hg
- Pg - Stack static pressure, in. H₂O
- Pm - Meter pressure, in. Hg
- PMR - Particulate Mass Rate, lbs per hour
- Ps - Absolute stack pressure, in. Hg
- Pstd - Standard absolute pressure, 29.92 in. Hg
- Pw - Density of water, 0.9982 g/ml (0.002201 lb/ml)
- Qa - Volumetric flow rate, ACFM
- Qs - Volumetric flow rate, DSCFM
- R - Ideal gas constant, 0.06236 mm Hg - m³/⁰K-g-mole (21.85 in. Hg-ft³/⁰R-lb-mole)
- SCF - Standard Cubic Foot
- ta - Ambient Temperature, ⁰F

NOMENCLATURE - continued

t_m - Average Temperature of meter, $^{\circ}\text{F}$

t_s - Average Temperature of stack, $^{\circ}\text{F}$

t_{std} - Standard Temperature, 68°F

NOTE: Capital "T" denotes degrees Rankin

V_a - Volume of acetone blank, ml

V_{aw} - Volume of acetone used in wash, ml

V_{lc} - Total volume of liquid collected in condenser and silica gel, ml

V_m - Volume of gas sample, as measured by the dry gas meter, AF

V_{mc} - Volume of gas sample, corrected for leak, ACF

$V_m(\text{std})$ - Volume of gas sample measured by the dry gas meter, corrected to standard conditions, DSCF

V_n - Volume collected at stack conditions through nozzle, ACF

V_s - Average stack gas velocity, ft/sec.

$V_w(\text{std})$ - Volume of water in the gas sample, corrected to standard conditions, SCF

W_a - Weight of residue in acetone wash, mg

Y - Dry gas meter calibration factor, (dimensionless)

ΔH - Average pressure differential across the calibrated orifice, in. H_2O

ΔH_a - Value of H measured for a specific orifice when operated under the following conditions: 0.75 cfm of dry air (M.W. = 29) at 68°F , 29.92 in. Hg.

$\sqrt{\Delta P}$ - Average of the square roots of the velocity pressure, in. H_2O

θ - Total Sampling time, min.

NOMENCLATURE - continued

- θ_1 - Sampling time interval from the beginning of a run until the first component change, min.
 - θ_i - Sampling time interval between two successive component changes, beginning with the interval between the first and second changes, min.
 - θ_p - Sampling time interval from the final (n^{th}) component change until the end of the sampling run, min.
- $\%CO_2$, $\%O_2$, $\%N_2$, $\%CO$ - Number percent (%) by volume (dry basis) of each compound in the stack gas.

EQUATIONS

1.

$$P_s = P_{b_{a,r}} + \frac{P_g}{13.6}$$

2.

$$P_m = P_{b_{a,r}} + \frac{\Delta \bar{H}}{13.6}$$

3.

$$V_m(std) = V_m Y \left(\frac{T_{std}}{T_m} \right) \left(\frac{P_m}{P_{std}} \right)$$

4.

$$V_w(std) = 0.04707 V_{L_c}$$

5.

$$B_{w,s} = \frac{V_w(std)}{V_m(std) + V_w(std)}$$

6.

$$M_d = 0.440 (\%CO_2) + 0.320 (\%O_2) + 0.280 (\%N_2 + \%CO)$$

7.

$$M_s = M_d (1 - B_{w,s}) + 18 (B_{w,s})$$

8.

$$v_s = K_p C_p (\sqrt{\Delta p}) \text{ avg. } \sqrt{\frac{T_s}{M_s P_s}}$$

EQUATIONS - Continued

9.

$$Q_a = (v_s) (A_s) (60)$$

10.

$$Q_s = Q_a (1 - B_{ws}) \left(\frac{528}{T_s} \right) \left(\frac{P_s}{29.92} \right)$$

11.

$$C_s = [0.0154 (Mn/Vmstd)]$$

12.

$$EA = \left[\frac{\%O_2 - 0.5\%CO}{0.264\%N_2 - (\%O_2 - 0.5\%CO)} \right] 100$$

13.

$$C_{5_0} = C_s / 1 - \left[\frac{(1.5) (\%O_2) - 0.133 (\%N_2) - 0.75 (\%CO)}{21} \right]$$

14.

$$C_{1_2} = C_s \frac{12}{\%CO_2}$$

15.

$$PMR = (C_s) (Q_s) \left(\frac{60}{7000} \right)$$

EQUATIONS - Continued

16.

$$V_n = \frac{T_g}{P_g} \left[(0.002669) (V_{1c}) + \frac{V_m}{T_m} (P_m) \right]$$

17.

$$C_a = (0.0154) (M_n) / V_n$$

18.

$$I = \frac{100 V_n}{60 V_s \theta A n}$$

19.

$$V_{m_c} = V_m - (L_p - L_a) \theta$$

20.

$$W_a = Ca V_a w P_a$$

EQUATIONS

Run # 1

$$1. P_g = P_{bar} + (P_g/13.6) = (27.51) + (.05)/13.6 = 27.51 \checkmark$$

$$2. P_m = P_{bar} + (\Delta H/13.6) = (27.51) + (.05)/13.6 = 27.51 \checkmark$$

$$3. V_{m(std)} = V_m Y (T_{std}/T_m) (P_m/P_{std}) \\ = (97.808) (1.0498) (528/531) (27.51/29.92) = 28.679 \checkmark$$

$$4. V_{w(std)} = 0.04707 V_{lc} = 0.04707 (73.5) = 3.460 \checkmark$$

$$5. B_{ws} = V_{w(std)} / (V_{m(std)} + V_{w(std)}) = (3.460) / (3.460 + 28.679) = .1077 \checkmark$$

$$6. M_d = 0.44 \%CO_2 + 0.32 \%O_2 + 0.28 (\%N_2 + \%CO) = \\ .44 (8.5) + .32 (11.5) + .28 (80) = 29.82 \checkmark$$

$$7. M_s = M_d (1 - B_{ws}) + 18 (B_{ws}) = (29.82) (1 - .1077) + 18 (.1077) = 28.55 \checkmark$$

$$8. v_s = K_p C_p (\sqrt{\Delta P}) / \sqrt{(T_s / (M_s P_s))} \\ = 85.49 (1.85) / \sqrt{(29.55 / (28.55))} = 18.23 \checkmark$$

$$9. Q_a = v_s A_s (60) = (18.23) (5.070) (60) = 5546 \checkmark$$

$$10. Q_s = Q_a (1 - B_{ws}) (528/T_s) (P_s/29.92) \\ = (5546) (1 - .1077) (528/911) (27.51/29.92) = 2829 \checkmark$$

$$11. c_s = 0.0154 (M_n/V_{m(std)}) = 0.0154 (437.3 / 28.679) = .2321 \checkmark$$

$$15. PMR = c_s Q_s (60/7000) = (.2321) (2829) (60/7000) = 5.63 \checkmark$$

$$16. \dot{V}_n = T_g/P_s \times \{ (0.002669) V_{lc} + V_m P_m/T_m \} \\ = (910/27.51) \{ (0.002669) (73.5) + (27.808) (27.51)/(531) \} \\ = 56.163 \checkmark$$

$$18. I = V_n (100) / ((60) \theta v_s A_n) = 100 (56.163) / (60 (62.5) (18.23) (.000787)) \\ = 104.38 \checkmark$$

$$(\frac{350}{24})^2 \checkmark$$

FIELD DATA SHEET

GUARDIAN SYSTEMS INC.

BOX 300
LEEDS, ALABAMA 35094PLANT BilshubRUN # 1LOCATION 7E 21DATE 10-16-90BARO. PRES. 29.51TIME 1128-1238 LOCAL TIME

	TIME		METER		STACK TEMP OF	METER TEMP. OF			IMP TEMP OF	BOX TEMP OF	METER PRESSURE H ₂ O	VELOCITY PRESSURE H ₂ O	VACUUM PRESSURE H _g	STATIC PRESSURE H ₂ O	
	MIN	DUR	VOL	FT ³		IN	OUT	AVG						BEFORE	AFTER
Port A			350.097	(1)	(1)	(3)		(4)	(5)					PROBE TIP SIZE	
1	2.5	2.5	351.1	450	60	60	60	32	253	.71	.065	—		.380	.280
2		5.0	352.6	452	63	61	62	34	254	1.04	.095	1.5		.380	.350
3		7.5	353.7	451	63	61	62	34	252	0.85	.078	1.0		.380	.380
4		10.0	354.7	449	63	61	62	34	252	.36	.033	—			
5		12.5	355.5	450	65	61	63	34	253	.33	.030	—			
Port B			356.7	451	64	61	64	34	253	.77	.070	1.0			
1		12.5	357.6	451	65	62	65	34	252	.38	.035	—			
2		20.0	358.5	454	70	64	67	34	251	.41	.037	—			
3		22.5	359.7	454	71	65	68	34	251	.62	.056	1.0			
4		25.0	360.9	454	72	65	68	39	250	.61	.055	1.0			
Port C			361.8	451	73	64	70	33	250	.77	.070	2.0			
1		20.0	362.8	449	73	66	70	33	247	.44	.040	—			
2		32.5	363.6	451	74	64	70	34	248	.39	.035	—			
3		35.0	364.8	451	73	67	70	34	251	.69	.062	2.0			
4		37.5	366.0	450	75	67	71	34	252	.67	.060	2.0			
Port D			366.9	450	76	68	72	34	249	.44	.035	1.0			
1		42.5	368.1	451	77	68	72	34	249	.78	.070	3.0			
2		45.0	369.3	452	80	70	75	34	249	.73	.065	3.0			
3		47.5	370.4	451	80	70	75	33	246	.69	.062	3.0			
4		50.0	371.5	450	81	71	76	33	247	.58	.052	2.0			
Port E			372.9	442	82	72	77	35	248	.84	.075	3.2			
1		55.0	374.0	445	83	73	78	35	248	.76	.067	3.0			
2		57.5	375.4	447	84	74	79	33	248	.85	.075	3.5			
3		60.0	376.1	447	84	74	79	33	248	.91	.080	4.0			
4		62.5	377.05	449	85	75	80	35	249	.68	.060	3.5			
5		65.0	378.12	451						.45	.239	4.0			
				457ms				71ms							

WATER

#1 70
ml.
gram 3.5
Total 73.5

OPERATOR

4072
Isak

Sample Box No. 2001
Meter Box No. 200
Meter ΔH@ 1.74
Pitot, CP .850
Temp. Device 24
Probe No. 421
Probe Liner 6055
Probe Htr. Set 35
Ambient Temp. 45
% O₂ 11.0 / 12.
% CO₂ 9.0 / 8.0

NOTES

Orifice ✓
Pitot ✓
Meter 1025
K=19.880
MICRO meteration
177.980
177.970
1010 0.54
R.00 5.04

FIELD DATA SHEET

PLANT

Cand State

RUN #

2

LOCATION

TK#21

DATE

10-16-90

BARO. PRES.

29.51

TIME

1325-1428

GUARDIAN SYSTEMS INC.

BOX 300

LEEDS, ALABAMA 35094

DATE	TIME		METER VOL FT 3	STACK TEMP OF	METER TEMP. OF			IMP TEMP OF	BOX TEMP OF	METER PRESSURE H ₂ O	VELOCITY PRESSURE H ₂ O	VACUUM PRESSURE H _g	STATIC PRESSURE "H ₂ O	
	MIN	DUR			IN	OUT	AVG							
			379.125	(1)	(2)	(3)		(4)	(5)				T.04	
													PROBE TIP SIZE	
													BEFORE	AFTER
1	2.5	25	380.9	452	85	82	84	33	228	2.28	.065	1.0	.504	.504
2		5.0	383.2	449	85	83	84	33	228	2.46	.070	2.5	.504	.504
3		7.5	385.3	455	87	83	85	35	242	2.81	.080	3.0	.504	.504
4		10.0	387.5	455	90	83	86	35	247	2.64	.075	3.0		
5		12.5	389.3	452	92	84	88	36	252	1.95	.055	2.5	WATER	
													#7	
													ml.	105
													gram	8.4
													Total	113.4
													OPERATOR	
													1072/	1504
													Sample Box No. 1	
													Meter Box No. 200	
													Meter ΔH@ 1.74	
													Pitot, CP .158	
													Temp. Device 2.17	
													Probe No. 4-1	
													Probe Liner 6405	
													Probe Htr. Set 75	
													Ambient Temp. 69	
													% O ₂ 16 / 12	
													% CO ₂ 5 / 9	
													NOTES	
													.05" x .17	
													Orifice	
													Pitot ✓	
													Meter 225"	
													K = 58.95	
													423.250	
													423.250	
													.006 29" H ₂ O	
													1 in	
													R = .03	
													5" .10	

FIELD DATA SHEET

GUARDIAN SYSTEMS INC.

BOX 300
LEEDS, ALABAMA 35094PLANT Gulf ShaleRUN 3LOCATION TK#21DATE 10-16-90BARO. PRES. 29.51TIME 1512-1614

	TIME		METER VOL FT 3	STACK TEMP OF	METER TEMP. OF			IMP TEMP OF	BOX TEMP OF	METER PRESSURE H ₂ O	VELOCITY PRESSURE H ₂ O	VACUUM PRESSURE Hg	STATIC PRESSURE "H ₂ O	
	MIN	OUR			IN	OUT	AVG						BEFORE	AFTER
<u>Port A</u>			425.72	(1)	(2)	(3)		(4)	(5)					<u>1.06</u>
1	2.5	2.5	425.0	449	79	79	79	33	238	1.29	.037	-	.504	.504
2	5.0		426.7	449	78	80	79	33	262	1.75	.055	-	.504	.504
3	7.5		428.5	451	80	80	80	34	263	1.71	.049	-	.504	.504
4	10.0		429.7	450	82	80	81	34	263	0.70	.020	-		
5	12.5		430.8	441	84	80	82	33	265	0.60	.017	-		
<u>Port B</u>														
1	15.0		433.4	451	84	80	82	33	265	2.88	.082	3.2		
2	17.5		434.9	452	86	80	83	36	264	1.75	.050	2.0		
3	20.0		436.0	455	89	81	85	35	264	1.72	.049	2.0		
4	22.5		438.8	455	90	82	86	35	261	1.90	.054	2.1		
5	25.0		440.0	463	91	82	86	35	259	1.75	.051	2.0		
<u>Port C</u>														
1	27.5		442.2	456	92	83	88	35	261	2.04	.058	2.3		
2	30.0		443.3	455	92	83	88	34	258	.67	.019	-		
3	32.5		444.6	455	92	84	88	34	260	.85	.024	-		
4	35.0		446.3	456	92	84	88	34	258	1.45	.041	1.5		
5	37.5		448.5	455	92	84	88	36	255	1.73	.049	2.0		
<u>Port D</u>														
1	40.0		449.7	455	92	84	88	36	260	1.66	.047	2.0		
2	42.5		451.6	452	93	86	90	39	259	1.63	.046	2.0		
3	45.0		453.4	450	92	85	88	37	257	1.60	.045	2.0		
4	47.5		455.0	447	92	85	88	37	262	1.53	.043	2.0		
5	50.0		456.4	449	92	86	89	37	262	1.49	.042	2.0		
<u>Port E</u>														
1	52.5		458.6	456	93	86	90	36	259	1.84	.052	2.2		
2	55.0		460.2	439	94	87	90	38	255	2.02	.056	2.5		
3	57.5		462.4	443	95	87	91	38	255	2.35	.065	3.2		
4	60.0		464.5	445	96	88	92	39	258	2.59	.072	3.5		
5	62.5		466.541	444	97	89	93	40	257	2.20	.061	3.0		
25	162.5		42.969	451			86			1.67	.214	3.5		
				452			87							

PROBE TIP SIZE
BEFORE AFTER

WATER

 ml. 95
 gram 11.7
 Total 106.7

OPERATOR

W72/1500
 Sample Box No. 1
 Meter Box No. 200
 Meter ΔH₀ 1.74
 Pitot, CP 1858
 Temp. Device W72
 Probe No. 41-1
 Probe Liner 6085
 Probe Htr. Set 65
 Ambient Temp. 67
 % O₂ 14.5/10
 % CO₂ 6/4

NOTES

 Orifice ✓
 Pitot ✓
 Meter 025
466.588
466.588
.008044
in
R-150
S-21

GUARDIAN * SYSTEMS * INCORPORATED
P.O. BOX 190
LEEDS, AL 35094
205-699-6647

Blank Analytical Data

Plant: General Shale Products Corporation
Sample location: TK 21
Relative humidity: 35%
Type of blank: Acetone
Liquid level at mark and container sealed: Yes
Density of blank: 0.7899 g/ml
Blank Volume 250 ml
Date & time of wt.: 10/25/90 0900 Gross wt. 106198.3 mg
Date & time of wt.: 11/1/90 0800 Gross wt. 106198.7 mg
Average Gross wt. 106198.5 mg
Tare wt. 106197.6 mg
Weight of blank 0.90 mg
Concentration of Blank 0.0046 mg/g 0.0005% of weight

Note: In no case shall a blank residue greater than (0.01mg/g)
of 0.001% of the weight of blank used be subtracted from the sample
weight.

Remarks: _____

Signature of analyst: _____

Signature of reviewer: _____

METHOD 5

PARTICULATE SAMPLE RECOVERY AND INTEGRITY SHEET

Plant: Good Shove Sample date: 10/16/90
Sample location: TK 21 Run no.: 1
Sample recovery person: LS TZ Recovery date: 10/16/90
Filter(s) no.: E-2

MOISTURE

Impingers Silica gel #12
Final volume (wt) 70 ml (gm) Final wt. 1003.0 g
Initial volume (wt) 0 ml (gm) Initial wt. 999.5 g
Net volume (wt) 70 ml (gm) Net wt. 3.5 g
Total moisture 73.5 g
Color of silica gel mixed
Description of impinger water Clear

RECOVERED SAMPLE

Filter container no. R #1 sealed ✓
Description of particulate on filter ~~PART~~ DARK BROWN

Acetone rinse container no. R #1 Liquid level marked ✓
Acetone blank container no. BLANK Liquid level marked ✓
Samples stored and locked ✓
Remarks: _____

Date of laboratory custody NA
Laboratory personnel taking custody LS TZ
Remarks: _____

GUARDIAN * SYSTEMS * INCORPORATED

P.O. BOX 190
LEEDS, AL 35094
205-699-6647

Method 5 Analytical Particulate Data

Plant: General Shale Produc Run Number: 1

Sample location: TK 21

Relative humidity: 35%

Density of Acetone: 0.7899 g/ml

Liquid level at mark and container sealed: Yes

Filter marked and container sealed: Yes

Acetone rinse container number: 1
Acetone rinse volume 175 ml
Acetone blank residue concentration: 0.0046 mg/g
Acetone blank weight 0.6 mg

ACETONE RINSE WEIGHT

Date & time of wt.:	10/25/90	0900 Gross wt.	100649.1 mg
Date & time of wt.:	11/1/90	0800 Gross wt.	100649.4 mg
		Average Gross wt.	100649.3 mg
		Tare wt.	100508.4 mg
		Less weight of acetone blank	0.6 mg
		Weight of particulate in acetone rinse	140.2 mg

PARTICULATE WEIGHT

Filter(s) container number:	1		
Date & time of wt.:	10/25/90	0900 Gross wt.	460.9 mg
Date & time of wt.:	10/25/90	0800 Gross wt.	460.6 mg
		Average Gross wt.	460.8 mg
		Tare wt.	168.7 mg
		Weight of particulate on filter (s)	292.1 mg
		Weight of particulate in acetone rinse	140.2 mg
		TOTAL WEIGHT OF PARTICULATE	432.3 mg

Note: In no case shall a blank residue greater than (0.01mg/g) of 0.001% of the weight of blank used be subtracted from the sample weight.

Remarks: _____

Signature of analyst: _____

Signature of reviewer: _____

METHOD 5

PARTICULATE SAMPLE RECOVERY AND INTEGRITY SHEET

Plant: General Steel Sample date: 10/16/90
Sample location: TE-21 Run no.: 2
Sample recovery person: L272 Recovery date: 10/16/90
Filter(s) no.: E-5

MOISTURE

Impingers Silica gel #7
Final volume (wt) 105 ml (gm) Final wt. 975.0 g
Initial volume (wt) 0 ml (gm) Initial wt. 967.2 g
Net volume (wt) 105 ml (gm) Net wt. 8.4 g
Total moisture 113.4 g
Color of silica gel milky
Description of impinger water not clean

RECOVERED SAMPLE

Filter container no. R #2 sealed ☒
Description of particulate on filter DARK BROWN

Acetone rinse container no. R #2 Liquid level marked add ☒
Acetone blank container no. _____ Liquid level marked _____
Samples stored and locked ☒

Remarks: _____

Date of laboratory custody _____

Laboratory personnel taking custody ☒

Remarks: _____

GUARDIAN * SYSTEMS * INCORPORATED
P.O. BOX 190
LEEDS, AL 35094
205-699-6647

Method 5 Analytical Particulate Data

Plant: General Shale Produc Run Number: 2

Sample location: TK 21

Relative humidity: 35%

Density of Acetone: 0.7899 g/ml

Liquid level at mark and container sealed: Yes
Filter marked and container sealed: Yes

Acetone rinse container number: 2
Acetone rinse volume 175 ml
Acetone blank residue concentration: 0.0046 mg/g
Acetone blank weight 0.6 mg

ACETONE RINSE WEIGHT

Date & time of wt.:	10/25/90	0900 Gross wt.	102690.9 mg
Date & time of wt.:	11/1/90	0800 Gross wt.	102690.8 mg
		Average Gross wt.	102690.9 mg
		Tare wt.	102534.8 mg
		Less weight of acetone blank	0.6 mg
Weight of particulate in acetone rinse			155.4 mg

PARTICULATE WEIGHT

Filter(s) container number:	2		
Date & time of wt.:	10/25/90	0900 Gross wt.	640.6 mg
Date & time of wt.:	10/25/90	1600 Gross wt.	640.2 mg
		Average Gross wt.	640.4 mg
		Tare wt.	169.5 mg
Weight of particulate on filter (s)			470.9 mg
Weight of particulate in acetone rinse			155.4 mg
TOTAL WEIGHT OF PARTICULATE			626.3 mg

Note: In no case shall a blank residue greater than (0.01mg/g) of 0.001% of the weight of blank used be subtracted from the sample weight.

Remarks: _____

Signature of analyst: _____

Signature of reviewer: _____

METHOD 5

PARTICULATE SAMPLE RECOVERY AND INTEGRITY SHEET

Plant: General SML Sample date: 10/16/80
 Sample location: TL21 Run no.: 3
 Sample recovery person: CTZ Recovery date: 10/16/80
 Filter(s) no.: E-3

MOISTURE

Impingers Silica gel #12
 Final volume (wt) 95 ml (gm) Final wt. 981.7 g
 Initial volume (wt) 0 ml (gm) Initial wt. 970.0 g
 Net volume (wt) 95 ml (gm) Net wt. 11.7 g
 Total moisture 106.7 g
 Color of silica gel milky
 Description of impinger water Clear

RECOVERED SAMPLE

Filter container no. Run #3 sealed ✓
 Description of particulate on filter DARK BROWN

Acetone rinse container no. Run #3 Liquid level marked ✓
 Acetone blank container no. _____ Liquid level marked _____
 Samples stored and locked ✓
 Remarks: _____

Date of laboratory custody ✓
 Laboratory personnel taking custody CTZ
 Remarks: _____

GUARDIAN * SYSTEMS * INCORPORATED
P.O. BOX 190
LEEDS, AL 35094
205-699-6647

Method 5 Analytical Particulate Data

Plant: General Shale Produc Run Number: 3

Sample location: TK 21

Relative humidity: 35%

Density of Acetone: 0.7899 g/ml

Liquid level at mark and container sealed: Yes

Filter marked and container sealed: Yes

Acetone rinse container number: 3
Acetone rinse volume 125 ml
Acetone blank residue concentration: 0.0046 mg/g
Acetone blank weight 0.4 mg

ACETONE RINSE WEIGHT

Date & time of wt.: 10/25/90 0900 Gross wt. 96662.5 mg
Date & time of wt.: 11/1/90 0800 Gross wt. 96662.1 mg
Average Gross wt. 96662.3 mg
Tare wt. 96573.6 mg
Less weight of acetone blank 0.4 mg
Weight of particulate in acetone rinse 88.3 mg

PARTICULATE WEIGHT

Filter(s) container number: 3
Date & time of wt.: 10/25/90 0900 Gross wt. 485.1 mg
Date & time of wt.: 10/25/90 1600 Gross wt. 485.3 mg
Average Gross wt. 485.2 mg
Tare wt. 172.0 mg
Weight of particulate on filter (s) 313.2 mg
Weight of particulate in acetone rinse 88.3 mg
TOTAL WEIGHT OF PARTICULATE 401.5 mg


Note: In no case shall a blank residue greater than (0.01mg/g) of 0.001% of the weight of blank used be subtracted from the sample weight.

Remarks: _____

Signature of analyst: _____

Signature of reviewer: _____

Plant Operation Data



PROCESS INFORMATION

PLANT: Glasgow, VA - 21

DATE: October 16, 1990

Brick Rate:

Car Schedule	=	<u>48</u>	Minutes	=	<u>1.25</u>	Cars/Hour
Car Count	=	<u>2,380</u>	S/S Brick/Car			
Hourly Rate	=	<u>2,975</u>	S/S Brick/Hour			
Brick Weight	=	<u>5.40</u>	Lbs.			
Brick Rate	=	<u>16,065</u>	Lbs./Hour			

Fuel Rate:

Total	=	<u>30.9</u>	Therms/M Brick			
Coal	=	<u>8.94</u>	Tons/Day			
		<u>745</u>	Lbs./Hour	=	<u>92</u>	% of Btu's
Natural Gas	=	<u>22</u>	MCF/Day			
		<u>916</u>	Cu. Ft./Hour	=	<u>8</u>	% of Btu's

Total Process Weight:

	<u>16,065</u>	Lbs. Brick/Hour
+	<u>745</u>	Lbs. Coal/Hour
	<u>16,810</u>	Total Lbs./Hour
	<u>8.41</u>	Tons/Hour

Coal Analysis:


<u>See Attached</u>	Btu/Lb.	<u> </u>
<u> </u>	Sulfur	<u> </u>
<u> </u>	Ash	<u> </u>

Allowable Emissions:

New Source Process Weight Formula: 17.1 Lbs./Hour

(Permit: 16.66 Lbs./Hour)

Calibrations



VI. CALIBRATIONS

Meter Box

The meter box shall be initially calibrated every 6 months at the fixed settings of 0.5, 1.0, 1.5, 2.0, 2.5, 3.0, 3.5, 4.0, 4.5, and 5.0 inches of H₂O. Upon return to the laboratory from this test the meter box was recalibrated using the average meter pressure for the test series. The recalibration point shall be the closest point to the initial calibration (for an average meter pressure of 1.37 a 1.50 inches H₂O was used as the recalibration point). These recalibrations produced a single point MCF and a ΔH which shall be compared to the original calibration to see if they are within the 5% allowed at the highest vacuum seen. These recalibration sheets are located behind the original calibration sheets.

Pitot Tubes

The S type pitot tubes are calibrated against a standard pitot tube ($C_p=0.99$) in a wind tunnel with a capacity to generate a test section velocity of approximately 3000 feet/minute every 6 months. Additionally the pitot tube is measured as to its specifications and alignment. Upon return, the intercomponent spacings and the face opening alignment of the pitot tube assembly were rechecked and if no changes are noticed; it shall be assumed that the coefficient of the assembly had not changed.

Temperature Measurements

All temperature devices (impinger, meter box, hot box and stack) are calibrated every 6 months against an ASTM mercury-in-glass reference thermometer or a reference thermocouple and potentiometer calibrated by fixed points, e.g., ice bath and boiling water (corrected to barometric pressure). Upon return the stack temperature device was recalibrated within 10% of the average absolute stack temperature. If the device being tested agrees within 1.5% of the reference device, the temperature data taken in the field shall be considered valid.

VI. CALIBRATIONS CONTINUED

Barometric Pressure

An aneroid barometer capable of measuring atmospheric pressure to within 0.1 inches Hg was used. If this device is defective the following alternate method shall be used. The barometric reading may be obtained from a nearby national weather service station, in which case the station value (which is the absolute barometric pressure) shall be requested and an adjustment for elevation differences between the weather station and sampling point shall be applied at a rate of minus 0.1 inches Hg per 100 feet elevation increase or vice versa for elevation decrease.

Specific Test Equipment and Measurements

The equipment used during these tests was as follows:

Probe	4-1
Meter Box:	#200
Stack Temperature:	Omega II
Sample Box	#1
Condenser	#1

The average stack temperature was 453 °F. The Omega II was recalibrated at 450 °F and agreed within 1.5% of the initial calibration value. The intercomponent spacing and the face opening alignment of the Pitot Tube assembly was rechecked and no changes were noticed; therefore, it was assumed that the coefficient of the assembly had not changed.

Type A Glass Fiber Filters

FEATURES

- High tensile strength. ■ Excellent handling characteristics. ■ Good wetting properties. ■ Minimum of 99.9% retention for particles of $.3 \mu\text{m}$ as determined by DOP tests. ■ Binder free.

This is the original glass fiber filter pioneered by Gelman Instrument Company over 15 years ago. It continues to be widely used for high volume sampling. Since zinc is one of the raw materials incorporated in the glass fibers, Type A Filters have a variable zinc content. Another component of the filter, sulfuric acid, is used as a dispersion medium, making the sheets unsuitable for measurement of sulfates.

Type A Glass Fiber Filters are less likely to develop static charge or tear than other glass fiber media types. They are used extensively in applications where zinc and iron content is not important, or where sulfate content is not being determined.

Size	37 mm	47 mm	102 mm	8"x10"
Product No.	61715	61694	61696	61701
Filters/Pkg.	500	100	100	100

TYPE A GLASS FIBER FILTER SPECIFICATION REPORT

The following physical/chemical properties represent typical, average values obtained in accordance with accepted test methods. They are subject to normal manufacturing variations and are supplied as a technical service. The analysis has been made in accordance with EPA procedures (micrograms/8" x 10" sheet).

ELEMENTS:

Antimony	.30	Manganese	.200
Arsenic	.30	Mercury	.100
Beryllium	.1	Molybdenum	.10
Bismuth	.10	Nickel	.10
Cadmium	.5	Selenium	.5000
Chromium	.10	Tin	.10
Cobalt	.10	Titanium	.170
Copper	.2	Vanadium	.10
Iron	.2300	Zinc	.5000
Lead	.20		to 25,000

OTHER PHYSICALS:

BSO	.522	Flow Resistance (Max.)	
*pH	8.5	@ 320 cm/min.	.80 mm
DOP @ 320/cm/min		Flow Rate (air)	
(ASTM Method 2986)	.99.9%	lpm/cm ² @ 70 cm Hg	.50
Tensile Strength		Max. Use Temp.	.400°C
(Fed. Spec. UUP31B)	.750 gr	Static Properties	Low
Weight,		Ability to	
8"x10" sheet	4.0±.3 gr.	Fold	Excellent

WATER EXTRACTABLE IONS:

Sulfate	.100	Chloride	.1500
Nitrate	.50	Fluoride	.15
Ammonia	.20		

*pH—Gelman Procedure:

- 500 ml distilled water.
- Add 15 drops saturated KCl solution.
- Shred one 8"x10" sheet and soak in prepared water for one hour.
- Run pH at ambient temperature.

Type A/E Glass Fiber Filters

FEATURES

- Low trace metals. ■ Medium Handling characteristics. ■ Available in all sizes. ■ Minimum of 99.9% retention for particles of $.3 \mu\text{m}$ as determined by DOP tests. ■ Binder free.

Type A/E Glass Fiber Filters are composed of low acid soluble glass fiber. They contain low levels of both zinc and iron. The filters do react with atmospheric sulfur dioxide; and therefore, when high levels of sulfur are expected, corrections for this reaction should be accounted for.

Type A/E Glass Fiber Filters are binder free and ideal for gravimetric analysis of air pollutants. This pure, organic free filter is the basis for procedures widely used in determining municipal and industrial air polluting substances.

Size	25 mm	37 mm	47 mm	102 mm	8"x10"
Product No.	61630	61652	61631	61633	61638
Filters/Pkg.	500	500	100	100	100

TYPE A/E GLASS FIBER FILTER SPECIFICATION REPORT

The following physical/chemical properties represent typical, average values obtained in accordance with accepted test methods. They are subject to normal manufacturing variations and are supplied as a technical service. The analysis has been made in accordance with EPA procedures (micrograms/8" x 10" sheet).

ELEMENTS:

Antimony	.20	Manganese	.2
Arsenic	.20	Mercury	.80
Beryllium	.1	Molybdenum	.10
Bismuth	.10	Nickel	.100
Cadmium	.2	Selenium	.200
Chromium	.10	Tin	.10
Cobalt	.10	Titanium	.10
Copper	.2	Vanadium	.10
Iron	100-1800	Zinc	.90
Lead	.10		

OTHER PHYSICALS:






BSO	.522	Flow Resistance (Max.)	
*pH	9.0	@ 320 cm/min.	.80 mm
DOP @ 320/cm/min		Flow Rate (air)	
ASTM Methods 2986)	.99.9%	lpm/cm ² @ 70 cm Hg	.60
Tensile Strength		Max. Use Temp.	.400°C
(Fed. Spec. UUP31B)	.600 gr.	Static Properties	Medium
Weight		Ability to	
8"x10" sheet	4.0±.3 gr.	Fold	Good

WATER EXTRACTABLE IONS:

Sulfate	.600	Chloride	.1500
Nitrate	.115	Fluoride	.87
Ammonia	.13		

*pH—Gelman Procedure:

- 500 ml distilled water.
- Add 15 drops saturated KCl solution.
- Shred one 8"x10" sheet and soak in prepared water for one hour.
- Run pH at ambient temperature.




NOTE: Flow rate held constant at 0.75; 50% change in flow rate has little effect on probe temperature.

GUARDIAN SYSTEMS INC
Initial Meter Calibration Box 200
on 8/15/90

Run Number	1	2	3	4	5
Barometric Pres, in Hg	29.56	29.56	29.56	29.56	29.56
Orifice pres drop, in H2O	0.5	1.0	1.5	2.0	2.5
Pres Wet Test Meter, in H2O	-0.30	-0.50	-0.70	-0.90	-1.00
Gas Volume Wet Init, CF	0.000	6.792	15.543	25.925	37.737
Gas Volume Wet Final, CF	6.792	15.543	25.925	37.737	50.764
Gas Volume Dry Init, CF	144.933	151.457	159.965	170.154	181.843
Gas Volume Dry Final, CF	151.457	159.965	170.154	181.843	194.802
Temp Wet Init, C	24.4	24.2	24.1	24.0	23.7
Temp Wet Final, C	24.2	24.1	24.0	23.7	23.6
Dry Gas Temp Init In, F	81	87	96	100	102
Dry Gas Temp Final In, F	87	96	100	102	103
Dry Gas Temp Init Out, F	80	83	89	93	94
Dry Gas Temp Final Out, F	83	89	93	94	95
Run Time, sec	970	900	900	900	900
Meter Calibration Factor, Y	1.0526	1.0501	1.0498	1.0451	1.0412
Average Y	1.0478				
Qm	0.4238	0.5927	0.7086	0.8090	0.8931
Km	0.7546	0.7435	0.7230	0.7136	0.7045
Average Km	0.7278				
Delta H@	1.62	1.67	1.76	1.81	1.86
Average H@	1.74				

SIGNATURE _____




GUARDIAN SYSTEMS INC
Recalibration of Meter Box 200
on 10/23/90

Run Number	1	2	3	Average
Barometric Pres, in Hg	29.67	29.67	29.67	29.67
Orifice pres drop, in H2O	1.5	1.5	1.5	1.50
Pres Wet Test Meter, in H2O	-0.70	-0.70	-0.70	-0.70
Gas Volume Wet Init, CF	0.000	9.960	19.943	29.903
Gas Volume Wet Final, CF	9.960	19.943	29.931	59.834
Gas Volume Dry Init, CF	751.219	761.431	771.743	2284.393
Gas Volume Dry Final, CF	761.431	771.743	782.166	2315.340
Temp Wet Init, C	17.5	17.5	17.5	17.5
Temp Wet Final, C	17.5	17.5	17.5	17.5
Dry Gas Temp Init In, F	105	109	110	108
Dry Gas Temp Final In, F	109	110	115	111
Dry Gas Temp Init Out, F	95	96	98	96
Dry Gas Temp Final Out, F	96	98	100	98
Run Time, sec	900	900	900	2700
Meter Calibration Factor, Y	1.0400	1.0359	1.0300	1.0353
Qm	0.7008	0.7043	0.7072	0.7041
Km	0.7134	0.7160	0.7177	0.7157
Delta H@	1.81	1.80	1.79	1.80

Previous Y	1.0498	% Difference	1.38%
Previous H@	1.76	% Difference	-2.16%

Project Good State Stack TK 21

SIGNATURE 

GUARDIAN SYSTEMS INC
Temperature Calibration for Omega II
on 5/18/90

Actual Temperature, F	Reading Temperature, F	Correction in Reading, F
-50	-52	2
0	-1	1
50	46	4
100	97	3
150	149	1
200	200	0
250	250	0
300	301	-1
350	348	2
400	400	0
450	448	2
500	500	0
550	549	1
600	598	2
650	648	2
700	698	2
750	748	2
800	798	2
850	848	2
900	899	1
950	949	1
1000	1000	0

SIGNATURE

Tom E. Grawler

GUARDIAN SYSTEMS INC
Temperature Calibration for Impingers
on 5/18/90

Device	Actual Temperature, F	Reading Temperature, F	Correction in Reading, F
Impinger 1	40	40	0
	50	50	0
	90	90	0
Impinger 2	40	40	0
	50	50	0
	90	90	0
Impinger 3	40	40	0
	50	50	0
	90	90	0
Impinger 4	40	40	0
	50	50	0
	90	90	0
Impinger 5	40	40	0
	50	50	0
	90	90	0
Impinger 6	40	40	0
	50	50	0
	90	90	0
Impinger 7	40	40	0
	50	50	0
	90	90	0
Impinger 8	40	40	0
	50	50	0
	90	90	0

SIGNATURE

Tom E. Graw

GUARDIAN SYSTEMS INC
Temperature Calibration for Hot Boxes
on 5/18/90

Device	Actual Temperature, F	Reading Temperature, F	Correction in Reading, F
Hot Box 1	225	225	0
	250	250	0
	275	275	0
Hot Box 2	225	225	0
	250	250	0
	275	275	0
Hot Box 3	225	225	0
	250	250	0
	275	275	0
Hot Box 4	225	225	0
	250	250	0
	275	275	0
Hot Box 5	225	225	0
	250	250	0
	275	275	0
Hot Box 6	225	225	0
	250	250	0
	275	275	0
Hot Box 7	225	225	0
	250	250	0
	275	275	0
Hot Box 8	225	225	0
	250	250	0
	275	275	0

SIGNATURE Tom E. Gual

GUARDIAN SYSTEMS INC
Pitot Calibration Form

Date: 5/15/90

Probe #: 4-1

Calibrated By: Morris/Gravlee

Average Velocity, f/m

2,901

Side A

Run #	Pstd	Ptype s	Cp(s)	Deviation
1	0.53	0.71	0.855	0.000
2	0.53	0.71	0.855	0.000
3	0.53	0.71	0.855	0.000

Avg Cp = 0.855 Avg = 0.000

Is average deviation less than or equal to 0.01? YES

Side B

Run #	Pstd	Ptype s	Cp(s)	Deviation
1	0.53	0.70	0.861	0.000
2	0.53	0.70	0.861	0.000
3	0.53	0.70	0.861	0.000

Avg Cp = 0.861 Avg = 0.000

Is average deviation less than or equal to 0.01? YES

Is average PCF equal to or less than 0.01 YES

Average PCF = 0.858

SIGNATURE

Tom E. Gravlee