

Note: This is a reference cited in AP 42, *Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP42 Section:	11.3
Reference:	36
Title:	Source Emissions Testing, Marseilles Brick, Marseilles, Illinois, Fugro Midwest, Inc., St. Ann, MO, October 13, 1994.



FUGRO MIDWEST, INC.

**SOURCE EMISSIONS TESTING
MARSEILLES BRICK
MARSEILLES, ILLINOIS**

MARSEILLES BRICK VENTURE, LTD.



5/20/97

Brian

The August 29, 1994
and August 30, 1994 Emission
Tests were performed
with the kiln on a
15 car/day production
rate

FAX TRANSMISSION

MARSEILLES BRICK

1401 BROADWAY ST.
MARSEILLES, IL 61341
(815)795-6922
FAX: (815)795-6869

To: *Brian Shrager*
First Midwest Research
Fax #: *(919) 677-0065*

Date: *5/1/97*

Pages: , including this cover sheet.

From: *Jock Laird*

Subject: *Stack Emission Tests*

COMMENTS:

Dear Brian

*The following is copied from our Stack
Test Report on Tests done 5/10/94 &
5/11/94. I do not have that information
on the August test where I can get to
it as readily. I will get it for you
and fax to you some time next week.*
Thanks

Jock Laird

MARSEILLES BRICK

VENTURE LIMITED PARTNERSHIP

*****FAX COVER SHEET*****

DATE: 5/25/94TO: Robt Felle
Eugene McClellandFROM: Jack LairdTOTAL # OF PAGES, INCLUDING COVER: 3MESSAGE: Dear Bob

Following is a Brief description of
our Drying & Firing process. The
test were set up for a 80% shale 20%
Fireclay mix. If you have any questions
about this information please give me a
call.

Regards
Jack

Description of Drying & Firing Procedure

Marseilles Brick has two independent Dryer tunnels approximately 200 ft. in length that hold 14 kiln cars each. Waste heat from the cooling section of the kiln is supplied to each dryer by a fan through a duct/plenum system. The heat to each dryer is boosted to 325°F by two natural gas burners, 442M BTU/hr and 432M BTU/hr respectively, located in the air supply duct. Moist warm air is exhausted to the atmosphere by a fan at the entrance end of each dryer tunnel. Dryer #1 and Dryer #2 are independent of each other except for the common waste heat supply from the kiln.

The tunnel kiln used by Marseilles Brick to fire its brick is a 498 ft. metal jacketed natural gas fired kiln designed by Ceric. The kiln holds a total of 36 kiln cars with 20 in the pre-heat and furnace section and 16 in the cooling section. The pre-heat section is divided into 6 zones with a total of 32 gas fired side burners. The furnace section is divided into 7 zones with 19 natural gas fired top burners in each zone for a total of 133 top fired burners. The cooling section has a rapid cool zone (2 car lengths long) where the brick are cooled from 1930°F to approximately 1300°F by injecting ambient air directly on the brick. The balance of the cooling section is used to cool the brick to approximately 100°F before exiting the kiln.

Waste heat is removed from the cooling section close to the exit to supply heated air to the dryers. The kiln exhaust fan is located near the entrance end of the pre-heat and exhausts the products of combustion to the atmosphere through a 40' high brick chimney.

MATERIAL BEING TESTED

80% Shale, 20% Fireclay

Size: Modular

Weight: Wet - 4.6 lbs., Dry - 4.1 lbs., Fired - 3.8 lbs.

Units per car: 10,080

Production rate 12 cars per day

Date: May 10, Time 12:00 p.m.

Position of cars in kiln

16 cars 80% Shale, 20% Fireclay in pre-heat & furnace section

20 cars 10% Shale, 90% Fireclay 4 in furnace & 16 in cooling

Position of cars in Dryers

Dryer #1

14 cars 80% Shale, 20% Fireclay

Dryer #2

14 cars 80% Shale, 20% Fireclay

06/24/04 15:47

002

Date: May 11, Time 7:00 a.m.

Position of cars in kiln

23 cars 80% Shale, 20% Fireclay in pre-heat, furnace & cooling
13 cars 10% Shale, 90% Fireclay in cooling section

Position of cars in Dryers

Dryer #1

14 cars 80% Shale, 20% Fireclay

Dryer #2

14 cars 80% Shale, 20% Fireclay

Date: May 11, Time 12:00 p.m.

Position of cars in kiln

25 cars 80% Shale, 20% Fireclay in pre-heat, furnace & cooling
11 cars 10% Shale, 90% Fireclay in cooling section

Position of cars in Dryers

Dryer #1

14 cars 80% Shale, 20% Fireclay

Dryer #2

14 cars 80% Shale, 20% Fireclay

Total fuel consumption during Test #1 (Dryer #1 exhaust)

May 10 - 14,200 cubic feet per hour

Total fuel consumption during Test #2 (Dryer #2 exhaust)

May 11 - 13,100 cubic feet per hour

Total fuel consumption during Test #3 (kiln exhaust)

May 11 - 13,100 cubic feet per hour

FUGRO MIDWEST, INC.



**SOURCE EMISSIONS TESTING
MARSEILLES BRICK
MARSEILLES, ILLINOIS**

MARSEILLES BRICK VENTURE, LTD.





FUGRO MIDWEST, INC.

October 13, 1994
Report 0894-8885-2

9921 St. Charles Rock Road
St. Ann (St. Louis), Missouri 63074
Tel: (314) 428-8880
Fax: (314) 428-8719

Mr. Charles Laird
Marseilles Brick Venture, Ltd.
P.O. Box 306
1401 Broadway
Marseilles, Illinois 61341

**Source Emissions Testing
Marseilles Brick
Marseilles, Illinois**

Dear Mr. Laird:

Fugro Midwest, Inc. (Fugro) is pleased to provide you with this report on the results of the air emissions tests conducted at the Marseilles Brick facility located in Marseilles, Illinois. Testing was conducted on August 29, 1994 on the outlet of the kiln, and on August 30, 1994 on the outlet of the number one and number two dryer stacks.

This report describes the testing methodologies and summarizes the results of the emissions testing.

Fugro appreciates this opportunity to provide service to Marseilles Brick, and we look forward to working with you on future projects. Please call us if you have any questions concerning this report.

Sincerely,

FUGRO MIDWEST, INC.

Robert F. Folle
Air Quality Scientist

Christopher N. Dawdy
Vice President
Manager, Air Quality Group

RFF:CND:nm

CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	1
2.0 SUMMARY OF TEST RESULTS	2
3.0 PURPOSE OF TESTING	2
4.0 ACTIVITIES DURING THE TESTING	2
5.0 TEST METHODS AND PROCEDURES	2
5.1 Field Procedures and Equipment (EPA Method 5 and 6)	5
5.1.1 Sampling Equipment and Procedures	5
5.1.2 Sample Recovery	8
5.1.3 Analytical Procedures	8
5.2 Oxygen (O ₂) and Carbon Dioxide (CO ₂) Sampling	8
5.2.1 Sampling Equipment and Procedures for Carbon Dioxide (CO ₂) and Oxygen (O ₂) Sampling - EPA Method 3A	11
5.2.2 Sampling Procedures	11
5.2.3 Analytical Procedures	11
5.3 Sampling and calibration procedures continuous monitoring of gaseous pollutants	12
5.4 Oxides of Nitrogen (NO _x) Sampling - EPA Method 7E	12
5.5 Sampling Equipment and Procedures for Carbon Monoxide (CO) Sampling - EPA Method 10.	13
5.6 Sampling Equipment and Procedures for Total Hydrocarbon (THC) Determination EPA Method 25A	13
6.0 EMISSION RESULTS	15

TABLES

Table

Emissions Summary	2-1
Emissions Summary	2-2
Oxygen (O ₂) and Carbon Dioxide (CO ₂) Analyzer Specifications	5-1
Particulate Matter Emission Summary – Kiln Stack	6-1
Sulfur Dioxide Emission Summary – Kiln Stack	6-2
Sulfur Trioxide Emission Summary – Kiln Stack	6-3
Particulate Matter Emission Summary – Dryer Stack #1	6-4
Sulfur Dioxide Emission Summary – Dryer Stack #1	6-5
Sulfur Trioxide Emission Summary – Dryer Stack #1	6-6
Particulate Matter Emission Summary – Dryer Stack #2	6-7
Sulfur Dioxide Emission Summary – Dryer Stack #2	6-8
Sulfur Trioxide Emission Summary – Dryer Stack #2	6-9
Total Hydrocarbons - Kiln Outlet	6-10
NO _x Emissions - Kiln Outlet	6-11
CO Emissions - Kiln Outlet	6-12
Total Hydrocarbons - North Dryer No. 1	6-13
CO Emissions - North Dryer No. 1	6-14
CO Emissions - South Dryer No. 2	6-15

FIGURES

Figure

Particulate SO ₂ /SO ₃ Sampling Train	5-1
Oxygen (O ₂) and Carbon Dioxide (CO ₂) Monitoring System	5-2
Continuous Emission Monitoring System	5-3

APPENDICES

- APPENDIX A: RESUMES OF TEST CREW
- APPENDIX B: LABORATORY ANALYSIS
- APPENDIX C: FIELD DATA SHEETS
- APPENDIX D: CALIBRATION DATA
- APPENDIX E: STRIP CHART RECORDINGS
- APPENDIX F: EXAMPLE CALCULATIONS
- APPENDIX G: CALIBRATION GAS CERTIFICATION

1.0 INTRODUCTION

Fugro Midwest, Inc. (Fugro) was contracted by Marseilles Brick Venture, Ltd. to conduct source emissions testing at their facility located in Marseilles, Illinois. Marseilles Brick has two independent dryer tunnels approximately 200 ft. in length that hold 14 kiln cars each. Waste heat from the cooling section of the kiln is supplied to each dryer by a fan through a duct/plenum system. The heat to each dryer is boosted to 325°F by two natural gas burners, 442M BTU/hr. and 432M BTU/hr. respectively, located in the air supply duct. Moist warm air is exhausted to the atmosphere by a fan at the entrance end of each dryer tunnel. Dryer #1 and dryer #2 are independent of each other except for the common waste heat supply from the kiln.

The tunnel kiln used by Marseilles Brick to fire its brick is a 498 ft. metal jacketed natural gas fired kiln designed by Ceric. The kiln holds a total of 36 kiln cars with 20 in the pre-heat and furnace section and 16 in the cooling section. The pre-heat section is divided into 6 zones with a total of 32 gas fired side burners. The furnace section is divided into 7 zones with 19 natural gas fired top burners in each zone for a total of 133 top fired burners. The cooling section has a rapid cool zone (2 car lengths long) where the brick is cooled from 1930°F to approximately 1300°F by injecting ambient air directly on the brick. The balance of the cooling section is used to cool the brick to approximately 100°F before exiting the kiln.

Waste heat is removed from the cooling section close to the exit to supply heated air to the dryers. The kiln exhaust fan is located near the entrance end of the pre-heat and exhausts the products of combustion to the atmosphere through a 40 ft high brick chimney.

Source emissions testing was conducted to determine mass emission rates of particulate, sulfur trioxide, sulfur dioxide, carbon monoxide, nitrogen oxide, and volatile organics. Three 1-hour test runs were conducted on each of the two dryer units and the kiln while firing bricks with a 17% shale/83% fireclay composition.

The emissions testing was conducted following the procedures outlined in 40 CFR Part 60, Appendix A, using USEPA Methods 1, 2, 3, 4, 5, and 6 to determine sampling point locations, volumetric flow rates, molecular weight, moisture concentrations, total particulate matter, and sulfur dioxide/sulfur trioxide, respectively. Additionally, USEPA Method 7E was used to determine nitrogen oxide (NO_x) emissions, USEPA Method 10 was used to determine carbon monoxide emissions, and USEPA Method 25A was used to determine total volatile organic emissions.

This report presents the results of the emissions testing. Copies of the field data sheets, laboratory analysis, equipment calibration records, calibration gas certifications, and example calculations are included in the appendices of this report.

2.0 SUMMARY OF TEST RESULTS

Fugro conducted source emissions testing at the Marseilles Brick facility located in Marseilles, Illinois, on August 29 and August 30, 1994 to quantify emission rates from three sources. An air emissions summary is presented in Table 2-1 for total particulate matter, NO_x , CO, and total hydrocarbon (THC) emissions. Table 2-2 presents the SO_2 and SO_3 results. The emissions were determined by averaging the results of three 1-hour test runs conducted on the exhaust of each unit. The testing was conducted during the use of a 17% shale/83% fire clay mixture and the north (#1) and south (#2) dryer, and the kiln stacks were tested.

Complete test results for total particulate matter, SO_2 , and SO_3 are presented in Tables 6-1 through 6-9. Example calculations for Test Run No. 1 for total particulate matter are presented in Appendix F.

The continuous emissions monitoring results for total hydrocarbons (THC), NO_x , and carbon monoxide (CO) are presented in Section 6.0, Tables 6-10 through 6-15.

3.0 PURPOSE OF TESTING

Fugro conducted air emissions testing at the facility located in Marseilles, Illinois for the purpose of determining mass emission rates of particulate matter, sulfur trioxide, sulfur dioxide, carbon monoxide, nitrogen oxide and volatile organics. These emissions rates will be used to evaluate the potential emissions associated with the brick manufacturing operation. The testing was conducted as required by 35 Ill. Adm. Code 201.282(a) in association with Permit #89010009.

4.0 ACTIVITIES DURING THE TESTING

Messrs. Robert Folle, Todd Staley, and Dan Cusac of Fugro conducted the emissions testing. Mr. Charles Laird of Marseilles Brick scheduled the testing and coordinated the testing effort. Mr. Mark Martin and John Krolak of the Illinois EPA were present and observed the testing. Resumes of the test crew are presented in Appendix A.

5.0 TEST METHODS AND PROCEDURES

Fugro utilized USEPA Test Methods 1, 2, 3, 4, 5, and 6 as outlined in 40 CFR Part 60, Appendix A, to determine traverse point locations, stack gas velocity, volumetric flow rates, molecular weight, moisture, total particulate matter emissions and sulfur emissions, respectively. Additionally, Methods 7E, 10, and 25A were used to determine nitrogen oxide, carbon monoxide, and total hydrocarbon emissions.

Table 2-1
Emissions Summary
Marseilles Brick Venture Ltd.
Marseilles, Illinois

Source	Run	Parameter				
			Particulate	NO _x	CO	THC
Dryer #1	1	gr/dscf	0.0039	-	-	-
		lb/hr	0.645	0	0.46	0.21
		ppm	-	0	5.5	1.55
	2	gr/dscf	.0010	-	-	-
		lb/hr	0.1641	0	1.20	0
		ppm	-	0	14.6	0
	3	gr/dscf	.0026	-	-	-
		lb/hr	0.4483	0	0.46	0
		ppm	-	0	5.4	0
	Avg.	gr/dscf	.0025	-	-	-
		lb/hr	0.4190	0	0.71	0.52
		ppm	-	0	8.5	0.068
Dryer #2	1	gr/dscf	.0017	-	-	-
		lb/hr	0.2663	0	0.396	0
		ppm	-	0	4.7	0
	2	gr/dscf	.0017	-	-	-
		lb/hr	0.2640	0	0.246	0
		ppm	-	0	3.0	0
	3	gr/dscf	.0012	-	-	-
		lb/hr	0.1890	0	0.430	0
		ppm	-	0	5.0	0
	Avg.	gr/dscf	0.0016	-	-	-
		lb/hr	.2397	0	0.357	0
		ppm	-	0	4.23	0
Kiln	1	gr/dscf	.1427	-	-	-
		lb/hr	21.58	2.02	9.78	0.92
		ppm	-	16.38	130.10	7.8
	2	gr/dscf	0.0759	-	-	-
		lb/hr	11.36	1.92	9.41	0.72
		ppm	-	15.63	125.98	6.1
	3	gr/dscf	.0907	-	-	-
		lb/hr	14.33	0.93	10.64	0.76
		ppm	-	7.250	136.82	6.2
	Avg.	gr/dscf	0.1031	-	-	-
		lb/hr	15.75	1.62	9.94	0.798
		ppm	-	13.1	130.97	6.7

Table 2-2 Emissions Summary Marseilles Brick Venture Ltd. Marseilles, Illinois				
Source	Run	Parameter		
			SO ₂	SO ₃
Dryer #1	1	mg	ND	0.18
		lb/hr	ND	0.0094
	2	mg	ND	0.25
		lb/hr	ND	0.0124
	3	mg	ND	10.67
		lb/hr	ND	0.556
	Avg.	mg	ND	3.70
		lb/hr	ND	0.193
Dryer #2	1	mg	ND	6.25
		lb/hr	ND	0.314
	2	mg	ND	3.31
		lb/hr	ND	0.165
	3	mg	1.60	2.33
		lb/hr	0.0796	0.116
	Avg.	mg	0.53	3.96
		lb/hr	0.0265	0.198
Kiln	1	mg	3,347	34.33
		lb/hr	119.89	1.26
	2	mg	3,411	44.14
		lb/hr	119.54	1.58
	3	mg	3,555	79.69
		lb/hr	127.36	2.95
	Avg.	mg	3,437.67	52.72
		lb/hr	122.26	1.93

ND = Non-detected


5.1 Field Procedures and Equipment (EPA Method 5 and 6)

5.1.1 Sampling Equipment and Procedures

The sampling equipment consists of the following:

1. Pitot Assembly
 - a. Nozzle — Glass with a sharp, tapered leading edge.
 - b. Probe — Stainless steel sheath with a 5/8-in. OD glass liner wrapped with nichrome wire; rheostat controlled and capable of maintaining a temperature of 248 degrees F $\pm$ 25 degrees F.
 - c. Pitot — Type "S" constructed and attached to probe according to specifications outlined in the "code of Federal Regulations, Chapter I, Title 40 Part 60, Appendix A, Method 2."
 - d. Fyrite probe — Stainless steel 1/4-in. tubing attached to pitot tube in an interference-free arrangement.
 - e. Thermocouple — Type "K" attached to the pitot tube such that the tip has no contact with the metal and does not interfere with the pitot tube face openings.
2. Filter Holder — Borosilicate glass with a glass fritted filter support and silicone rubber sealing gasket.
3. Filter Heating Assembly — Controlled heating element in aluminum module attached to end of probe; capable of maintaining 248 degrees F $\pm$ 25 degrees F.
4. Impingers — Four glass impingers connected in series with glass ball joint fittings and placed in an ice bath. The first, third, and fourth impingers were of the modified Greenburg-Smith design. The second impinger was of the Greenburg-Smith design with a standard tip. Final gas exit temperature was measured to within $\pm$ 5 degrees F with a thermometer immersed in the gas stream.
5. Control Box — Module containing the vacuum gauge, leak-free pump, thermometer capable of measuring temperature to within $\pm$ 5 degrees F, dry gas meter with a minimum of 2% accuracy, valves and related equipment as required to maintain an isokinetic sampling rate and to determine sample volume.
6. Nomograph — To determine isokinetic sampling rate.

A schematic of the particulate sampling train is shown in Figure 5-1.



SOURCE: ENVIRONMENT REPORTER

Figure 5-1
PARTICULATE SAMPLING TRAIN
EPA METHOD 5





Prior to leaving the laboratory, glass fiber filters were numbered for identification purposes, heated for 2 hours at 220 degrees F, desiccated for 2 hours, and preweighed to the nearest 0.1 mg.

Upon arrival at the sampling site, the control box was leak-checked from the pump to the orifice at 5 to 7 in. of water.

The sampling train was prepared in the following manner: 100 ml of 80% isopropanol in the first impinger, 100 ml of 3% hydrogen peroxide was added to each of the next two impingers. The fourth impinger was left empty and the fifth impinger contained 250 grams of silica gel.

After assembling the train with the pitot tube, as shown on the schematic, the system was leak-checked by plugging the inlet to the probe nozzle and pulling a 15-in. mercury vacuum. A leakage rate not to exceed 0.02 cfm is considered acceptable. The pitot tube system was also leak-checked at 2 to 3 in. of water, and any leaks found were corrected.

The probe nozzle size and moisture content were derived from a preliminary velocity and temperature traverse measurement. Sampling points within the duct were selected in accordance with EPA Method 1 (40 CFR 60, Appendix A). The sampling probe was attached and the heater was adjusted to provide a gas temperature of approximately 248 degrees F, +/- 25 degrees F.

The filter heating system was turned on, and ice was placed around the impingers. After a suitable warmup period, the nozzle was placed at the first traverse point with the flow adjusted to isokinetic conditions. Using calculated sampling points and sampling times, the probe was repositioned to the next traverse point, and isokinetic sampling was re-established. This was accomplished for each point along the traverse until the run was completed. Readings were taken at each traverse point and at the calculated time interval. At the conclusion of each run, the pump was turned off and the final readings were recorded. A final leak check of the sampling system was performed, as previously described at the highest vacuum encountered during the test run. A leak check of the pitot system was also repeated.

5.1.2 Sample Recovery

The volume of liquid in the first four impingers was measured and recorded on the field data sheet. The probe nozzle, and all sample-exposed surfaces were washed with reagent-grade acetone and put into a clean sample bottle marked "prefilter." A brush was used to loosen any adhering particulate matter, and subsequent washings were put into the "prefilter" container. The filter was carefully removed from the fritted teflon support and placed in its original container. Any filter material that adhered to the filter support surfaces was carefully removed and added to the filter container. The silica gel was removed from the fifth impinger and transferred to its original container. A sample of the acetone used in washing the probe was saved as a blank for laboratory analysis. The liquid from the first four impingers was collected and labeled for shipment to the laboratory.

5.1.3 Analytical Procedures

The filter and any loose particulate matter were transferred from the filter container to a clean, tared glass weighing dish. The filter was placed in a desiccator for 24 hours and weighed to a constant weight. The original weight of the filter was deducted, and the weight gain recorded to the nearest 0.1 mg.

The "prefilter" wash and blank acetone solutions were transferred to individual clean, tared beakers, then evaporated to dryness and desiccated to a constant weight. The weight gain of the "prefilter" was adjusted for the blank and recorded to the nearest 0.1 gram.

The impinger catch was shipped to Triangle Laboratory of North Carolina, for sulfur titrations. The analytical data sheets for particulate and SO_2/SO_3 analyses are presented in Appendix B.

5.2 Oxygen (O_2) and Carbon Dioxide (CO_2) Sampling

As required by EPA Method 3 (40 CFR 60, Appendix A), Oxygen and carbon dioxide samples were collected and analyzed. The collected sample was analyzed using a Horiba CMA-331A continuous gas analyzer. Oxygen and carbon dioxide concentrations were determined in percent of stack gas and stack gas molecular weight was then calculated.


Table 5-1 presents the equipment specifications of the continuous emissions monitors and Figure 5-2 presents a schematic of the analyzer system.

TABLE 5-1

CONTINUOUS EMISSIONS MONITORING
(CEM) SYSTEM
OXYGEN (O₂) AND CARBON DIOXIDE (CO₂)

CEM SYSTEM SPECIFICATIONS

PARAMETER:	O ₂	CO ₂
ANALYZER	HORIBA	HORIBA
MODEL	CMA-331A	CMA-331A
TYPE	PARAMAGNETIC	NDIR
RANGE	0-25 %	0-20 %
REPEATABILITY	+/- .5% Full scale (FS)	+/- .5% Full scale (FS)
DRIFT (ZERO)	+/- 1% FS/per week	+/- 1% FS/per week
DRIFT (SPAN)	+/- 2% FS per week	+/- 2% FS per week
RESPONSE TIME	90% FS < 1 MINUTE	90% FS < 1 MINUTE
ACCURACY	+/- 1% FS	+/- 1% FS
INPUT POWER	110-115 V.A.C./60 HZ.	110-115 V.A.C./60 HZ.



SOURCE: ENVIRONMENT REPORTER

Figure 5-2

OXYGEN (O₂) AND CARBON DIOXIDE (CO₂) MONITORING SYSTEM



5.2.1 Sampling Equipment and Procedures for Carbon Dioxide (CO₂) and Oxygen (O₂) Sampling - EPA Method 3A

The gas sample was continuously drawn from the stack with a Thomas Industries Model 107 diaphragm pump. The Gas flowed from the stack through Teflon tubing to a glass condenser where the majority of the water vapor was removed. From the condenser, the gas flow rate was reduced by a valve before entering the pump. The gas was then pumped through the analyzer at a constant flow rate and pressure (Figure 5-2). The analyzer was calibrated with known concentrations of certified N₂ for zero span and certified concentrations of gas for upscale span calibrations. The analyzer was calibrated before and after each test run. Photocopies of the actual concentration readings recorded on the data logger/chart recorder are presented in Appendix E. Protocol-1 calibration gas certificates are presented in Appendix G.

Tables 6-1 through 6-9 present the O₂ and CO₂ results.

5.2.2 Sampling Procedures

The sampling procedure consists of the following leak check and sampling techniques. Prior to sampling, the vase was leak-checked to 2 to 4 in. of water. The inlet to the condenser was plugged, and a vacuum of 10 in. of Hg was created. The outlet of the pump was then plugged and the pump was turned off. The vacuum was observed for 30 seconds to determine any leakage. The vacuum must hold steady for at least 30 seconds for the leak test to be acceptable. The sample line was then purged with stack gas and the bag was connected. Sampling was conducted at an appropriate constant rate at the same traverse points and for the same length of time as the other testing parameters were tested. At the conclusion of the run, the pump was turned off and the bag sealed.

5.2.3 Analytical Procedures

The percentage of effluent gas which was O₂ and CO₂ were measured directly. Nitrogen and CO content were determined by subtracting the sum of CO₂ and O₂ percent from 100 percent.

The dry molecular weight was calculated using the following equation:

$$M_d = 0.440 \times \%CO_2 + 0.320 \times \%O_2 + 0.280 \times (\%N_2 + \%CO)$$

The molecular weight results for each test run are included in Tables 6-1 through 6-9.

5.3 Sampling and calibration procedures continuous monitoring of gaseous pollutants

An initial analyzer calibration error test was performed for zero and upscale span calibrations on the analyzer to determine the difference between the gas concentrations exhibited by the gas analyzer and the known concentrations of the calibration gas, when the calibration gas is introduced directly to the analyzer's input ($\pm 2\%$ of span for each concentration is acceptable).

A sampling system bias test was performed on the analyzer system. Zero and calibration gases were introduced to the outlet of the sampling probe, and the difference between the bias readings and the initial analyzer calibration error readings (known gas concentrations introduced directly into the analyzer's input) were recorded (bias). Bias system limits for each concentration is $\pm 5\%$ of span. Sampling was performed simultaneously. Sampling was started at the first measurement point, as determined by Method 1, after twice the system response time (time it takes for calibration gas to travel up to the probe and back down to the analyzers input) had elapsed. System response time was 2 minutes and 36 seconds. Zero and calibration drift (span) tests were performed immediately preceding and following the test run before any adjustments to the measurement system ($\pm 3\%$ of span). All test runs were found to be within the system specifications and all zero and upscale calibrations were within the sampling system bias specifications.

5.4 Oxides of Nitrogen (NO_x) Sampling - EPA Method 7E

Nitrogen oxide (NO_x) was measured following the procedures set forth in Method 7E of 40 CFR 60, Appendix A. The NO_x analysis was performed with a TECO, Model 10AR, chemiluminescence NO_x analyzer manufactured by Thermo Environmental Instruments, Inc. The TECO 10AR blends the gas sample with O_3 in a reaction chamber. The resulting chemiluminescence is monitored through an optical filter by a high-sensitivity photomultiplier positioned at one end of the chamber. The filter/photomultiplier combination responds to light in a narrow-wave length band unique to the reaction of NO and O_3 . The output from the photomultiplier is linearly proportional to the NO concentration. To measure NO_x concentrations, the NO_x in the sample gas is converted to NO through a converter. The chemiluminescent response in the reaction chamber to the converter effluent is linearly proportional to the NO_x concentration entering the converter.

The electrical responses from the TECO 10AR were recorded on an Omega 5500 data logger. This data was digitized into 60-minute averages. The gas sample in the stack was drawn from the stack port with a Thomas Industries Model 107 diaphragm pump. The sample gas flow from the stack flowed through Teflon tubing to a glass condenser (ice bath) where the water vapor was removed. From the condenser, the gas flow was reduced by a valve before entering the pump. The gas sample was then pumped through the analyzer at a constant flow rate and pressure (Figure 5-3). Photocopies of the actual concentration readings recorded on the data logger recorder are presented in Appendix E.

The nitrogen oxide analyzer was calibrated using a three-point calibration consisting of a zero gas, and two additional test concentrations of nitrogen oxide (NO) consisting of 86.7 parts per million (ppm) and 151 ppm of NO. The NO_x analyzer was calibrated before and after the NO_x tests. The certifications for the calibration gases used during the test are presented in Appendix G.

5.5 Sampling Equipment and Procedures for Carbon Monoxide (CO) Sampling - EPA Method 10.

CO concentrations in the stack gas were monitored with a Horiba 331 CO Analyzer. This instrument utilizes gas filter correlation for CO measurement.

The gas sample was continuously drawn from the stack with a Thomas Industries Model 107 diaphragm pump. The gas flowed from the stack through Teflon tubing to a glass condenser where the majority of the water vapor was removed. From the condenser, the gas flow rate was reduced by a valve before entering the pump. The gas was then pumped through the analyzer at a constant flow rate and pressure (Figure 5-3). The CO analyzer was calibrated with known concentrations of certified N₂ for zero span and certified concentrations of CO for upscale span calibrations. The analyzer was calibrated before and after each test run. Photocopies of the actual CO concentration readings recorded on a data logger/chart recorder are presented in Appendix E. Protocol-1 calibration gas certificates are presented in Appendix G.

5.6 Sampling Equipment and Procedures for Total Hydrocarbon (THC) Determination EPA Method 25A

Total hydrocarbon concentrations (as propane) in the stack gas were continuously extracted and analyzed with a J.U. M. Model VE-7 heated total hydrocarbon analyzer. The analyzer utilizes a hydrogen flame ionization detector (FID) in a heated oven (190°C) to prevent the loss of high molecular weight hydrocarbons.




Figure 5-3
Continuous Emission Monitoring System

Stack gas was continuously extracted from the source through heated teflon sample lines (250°F) connected to suitable stainless steel sampling probes. The stack gas was introduced directly into the heated total hydrocarbon analyzer at a constant flow rate and pressure. The total hydrocarbon analyzer was calibrated before and after each of the tests with known concentrations of USEPA Protocol-1 propane calibration gases for upscale span calibrations and drift checks and zero gas for zero calibrations.

The total hydrocarbon analyzer's responses (as propane) were continuously recorded on an Omega Model 5500 data logger. Figure 5-4 illustrates a schematic diagram of the total hydrocarbon sampling train. Copies of the data logger records are presented in Appendix E. Calibration gas certifications for the USEPA Protocol-1 calibration gases are presented in Appendix G.

6.0 EMISSION RESULTS

The emissions results of the testing are presented in Tables 6-1 through 6-9. Example calculations for test run number 1, conducted on the kiln outlet on August 29, 1994, for total particulate matter are presented in Appendix F.

Tables 6-10 through 6-15 presents the emissions for NO_x , total hydrocarbons (THC), and carbon monoxide (CO) as measured utilizing the continuous emission monitors. There were no NO_x emissions detected on the north dryer No. 1 and no total hydrocarbon or NO_x emissions detected on the south dryer No. 2.

TABLE 6-1

PARTICULATE MATTER EMISSION SUMMARY.

PLANT: MARSEILLES BRICK
 CITY, STATE: MARSEILLES, ILL.
 STACK: KILN

PARTICULATE MATTER SUMMARY

	1	2	3	AVERAGE
Run Number	AUGUST 29, 1994			
Date of Run				
Starting Time (hours)	1048	1250	1451	
Ending Time (hours)	1154	1355	1556	
Net Time of Run (minutes)	60	60	60	
Number of Points	21	21	21	
Barometric Pressure (in. Hg)	30.24	30.24	30.24	
Static Pressure (in. H ₂ O)	-0.15	-0.15	-0.15	
Stack Pressure (in. Hg)	30.23	30.23	30.23	30.23
Average Delta H (in. H ₂ O)	4.1381	4.1286	4.3762	4.21
Average Delta P (in. H ₂ O)	0.3652	0.3567	0.3781	0.37
Meter Pressure (in. Hg)	30.54	30.54	30.56	30.55
Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Meter Box Number (STL#)	2	2	2	
Y-Factor	1.002	1.002	1.002	
Stack Length (in.)	41	41	41	
Stack Width (in.)	41	41	41	
Stack Cross Sectional Area (ft ²)	11.673611	11.673611	11.673611	11.67361
Nozzle Diameter (inches)	0.370	0.370	0.370	
Nozzle Area (ft ²)	0.00074667	0.0007467	0.000746674	0.000747
Meter Temperature (F)	92.667	89.952	97.952	93.524
Stack Temperature (F)	437.429	436.286	434.762	436.159
Ending DGM Volume (ACF)	321.647	397.72	479.652	
Beginning DGM Volume (ACF)	257.989	333.035	413.778	
Volume of Dry Gas Sample (acf)	63.6580	64.6850	65.8740	64.7390
Dry, Std. Gas Sample Volume (dscf)	62.2097	63.524	63.802	63.1785
Condensate Collected (mL)	81.10	79.30	60.20	73.53
Moisture Concentration (%)	5.78	5.55	4.25	5.19
Carbon Dioxide Concentration (%)	2.218	2.230	2.270	2.239
Oxygen Concentration (%)	16.730	18.300	19.385	18.138
Carbon Monoxide Concentration (%)	0.000	0.000	0.000	0.000
Nitrogen Conc. Dry (gas balance)	81.052	79.470	78.345	79.622
Molecular Weight, Dry (lb/lb-mole)	29.0241	29.0888	29.1386	29.0838
Molecular Weight, Wet (lb/lb-mole)	28.3867	28.4734	28.6649	28.5083
SQRT Delta P Avg., Pitot (in. H ₂ O)	0.598272	0.593871	0.611407	0.601183
Avg. Velocity, Stack Gas (ft/sec)	43.9364	43.5190	44.6161	44.0238
Actual Flow Rate (acfm)	30773.768	30481.418	31249.863	30835.016
Dry, Std. Vol. Flow Rate (dscfm)	17234.991	17135.054	17838.682	17402.909
% Isokinetic	94.11	96.66	93.25	94.67
Total Filter Catch (mg)	413.30	263.00	268.20	314.83
Total Wash Catch (mg)	175.50	55.20	119.10	116.60
Total Catch (mg)	588.80	318.20	387.30	431.43
Particulate Conc. (grams/dscf)	0.0092	0.0049	0.0059	0.0067
Particulate Conc. (grains/dscf)	0.1427	0.0759	0.0907	0.1031
Particulate Concentration (lb/dscf)	2.09E-05	1.10E-05	1.34E-05	1.51E-05
Particulate Emission Rate (lb/hr)	21.5814	11.3556	14.3264	15.7545

TABLE 6-2

SULFUR DIOXIDE EMISSION RESULTS
SO₂

PLANT: MARSEILLES BRICK
CITY, STATE: MARSEILLES, ILL.
STACK: KILN

SO₂ EMISSIONS SUMMARY

	1	2	3	AVERAGE
Run Number	AUGUST 29, 1994			
Date of Run				
Starting Time (hours)	1048	1250	1451	
Ending Time (hours)	1154	1355	1556	
Net Time of Run (minutes)	60	60	60	
Number of Points	21	21	21	
Barometric Pressure (in. Hg)	30.24	30.24	30.24	
Static Pressure (in. H ₂ O)	-0.15	-0.15	-0.15	
Stack Pressure (in. Hg)	30.23	30.23	30.23	30.23
Average Delta H (in. H ₂ O)	4.1381	4.1286	4.3762	4.21
Average Delta P (in. H ₂ O)	0.3652	0.3567	0.3781	0.37
Meter Pressure (in. Hg)	30.54	30.54	30.56	30.55
Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Meter Box Number (STL#)	2	2	2	
Y-Factor	1.002	1.002	1.002	
Stack Length (in.)	41	41	41	
Stack Width (in.)	41	41	41	
Stack Cross Sectional Area (ft ²)	11.673611	11.673611	11.673611	11.67361
Nozzle Diameter (inches)	0.370	0.370	0.370	
Nozzle Area (ft ²)	0.00074667	0.0007467	0.000746674	0.000747
Meter Temperature (F)	92.667	89.952	97.952	93.524
Stack Temperature (F)	437.429	436.286	434.762	436.159
Ending DGM Volume (ACF)	321.647	397.72	479.652	
Beginning DGM Volume (ACF)	257.989	333.035	413.778	
Volume of Dry Gas Sample (acf)	63.6580	64.6850	65.8740	64.7390
Dry, Std. Gas Sample Volume (dscf)	62.2097	63.524	63.802	63.1785
Condensate Collected (mL)	81.10	79.30	60.20	73.53
Moisture Concentration (%)	5.78	5.55	4.25	5.19
Carbon Dioxide Concentration (%)	2.218	2.230	2.270	2.239
Oxygen Concentration (%)	16.730	18.300	19.385	18.138
Carbon Monoxide Concentration (%)	0.000	0.000	0.000	0.000
Nitrogen Conc. Dry (gas balance)	81.052	79.470	78.345	79.622
Molecular Weight, Dry (lb/lb-mole)	29.0241	29.0888	29.1386	29.0838
Molecular Weight, Wet (lb/lb-mole)	28.3867	28.4734	28.6649	28.5083
SQRT Delta P Avg., Pitot (in. H ₂ O)	0.598272	0.593871	0.611407	0.601183
Avg. Velocity, Stack Gas (ft/sec)	43.9364	43.5190	44.6161	44.0238
Actual Flow Rate (acfm)	30773.768	30481.418	31249.863	30835.016
Dry, Std. Vol. Flow Rate (dscfm)	17234.991	17135.054	17838.682	17402.909
% Isokinetic	94.11	96.66	93.25	94.67
SO₂				
Total Catch (mg) SO ₂	3347.00	3411.00	3555.00	3437.67
SO ₂ Conc. (grams/dscf)	0.0526	0.0527	0.0540	0.0531
SO ₂ Conc. (grains/dscf)	0.8113	0.8137	0.8327	0.8192
SO ₂ Concentration (lb/dscf)	1.16E-04	1.16E-04	1.19E-04	1.17E-04
SO ₂ Emission Rate (lb/hr)	119.8874	119.5428	127.3644	122.2649

TABLE 6-3

SULFUR TRIOXIDE EMISSION SUMMARY.
SO₃

PLANT: MARSEILLES BRICK
CITY, STATE: MARSEILLES, ILL.
STACK: KILN

SO₃ SUMMARY

	1	2	3	AVERAGE
Run Number	AUGUST 29, 1994			
Date of Run				
Starting Time (hours)	1048	1250	1451	
Ending Time (hours)	1154	1355	1556	
Net Time of Run (minutes)	60	60	60	
Number of Points	21	21	21	
Barometric Pressure (in. Hg)	30.24	30.24	30.24	
Static Pressure (in. H ₂ O)	-0.15	-0.15	-0.15	
Stack Pressure (in. Hg)	30.23	30.23	30.23	30.23
Average Delta H (in. H ₂ O)	4.1381	4.1286	4.3762	4.21
Average Delta P (in. H ₂ O)	0.3652	0.3567	0.3781	0.37
Meter Pressure (in. Hg)	30.54	30.54	30.56	30.55
Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Meter Box Number (STL#)	2	2	2	
Y-Factor	1.002	1.002	1.002	
Stack Length (in.)	41	41	41	
Stack Width (in.)	41	41	41	
Stack Cross Sectional Area (ft ²)	11.673611	11.673611	11.673611	11.67361
Nozzle Diameter (inches)	0.370	0.370	0.370	
Nozzle Area (ft ²)	0.00074667	0.0007467	0.000746674	0.000747
Meter Temperature (F)	92.667	89.952	97.952	93.524
Stack Temperature (F)	437.429	436.286	434.762	436.159
Ending DGM Volume (ACF)	321.647	397.72	479.652	
Beginning DGM Volume (ACF)	257.989	333.035	413.778	
Volume of Dry Gas Sample (acf)	63.6580	64.6850	65.8740	64.7390
Dry, Std. Gas Sample Volume (dscf)	62.2097	63.524	63.802	63.1785
Condensate Collected (mL)	81.10	79.30	60.20	73.53
Moisture Concentration (%)	5.78	5.55	4.25	5.19
Carbon Dioxide Concentration (%)	2.218	2.230	2.270	2.239
Oxygen Concentration (%)	16.730	18.300	19.385	18.138
Carbon Monoxide Concentration (%)	0.000	0.000	0.000	0.000
Nitrogen Conc. Dry (gas balance)	81.052	79.470	78.345	79.622
Molecular Weight, Dry (lb/lb-mole)	29.0241	29.0888	29.1386	29.0838
Molecular Weight, Wet (lb/lb-mole)	28.3867	28.4734	28.6649	28.5083
SQRT Delta P Avg., Pitot (in. H ₂ O)	0.598272	0.593871	0.611407	0.601183
Avg. Velocity, Stack Gas (ft/sec)	43.9364	43.5190	44.6161	44.0238
Actual Flow Rate (acfm)	30773.768	30481.418	31249.863	30835.016
Dry, Std. Vol. Flow Rate (dscfm)	17234.991	17135.054	17838.682	17402.909
% Isokinetic	94.11	96.66	93.25	94.67
Total Catch (mg) SO ₃	34.33	44.14	79.69	52.720
SO ₃ Conc. (grams/dscf)	0.0005	0.0007	0.0012	0.0008
SO ₃ Conc. (grains/dscf)	0.0083	0.0105	0.0187	0.0125
SO ₃ Concentration (lb/dscf)	1.22E-06	1.53E-06	2.75E-06	1.83E-06
SO ₃ Emission Rate (lb/hr)	1.2583	1.5752	2.9478	1.9271

TABLE 6-4

PARTICULATE MATTER EMISSION SUMMARY.

PLANT: MARSEILLES BRICK
 CITY, STATE: MARSEILLES, ILL.
 STACK: DRYER STACK #1

PARTICULATE MATTER SUMMARY

	1	2	3	AVERAGE
Run Number				
Date of Run	AUGUST 30, 1994			
Starting Time (hours)	937	1133	1311	
Ending Time (hours)	1040	1236	1417	
Net Time of Run (minutes)	60	60	60	
Number of Points	24	24	24	
Barometric Pressure (in. Hg)	30.12	30.12	30.12	
Static Pressure (in. H ₂ O)	-0.12	-0.12	-0.12	
Stack Pressure (in. Hg)	30.11	30.11	30.11	30.11
Average Delta H (in. H ₂ O)	2.4458	2.4388	2.6500	2.51
Average Delta P (in. H ₂ O)	0.3363	0.3233	0.3463	0.34
Meter Pressure (in. Hg)	30.30	30.30	30.31	30.30
Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Meter Box Number (STL#)	2	2	2	
Y-Factor	1.002	1.002	1.002	
Stack Diameter (in.)	45	45	45	
Stack Cross Sectional Area (ft ²)	11.044662	11.044662	11.044662	11.04466
Nozzle Diameter (inches)	0.300	0.300	0.300	
Nozzle Area (ft ²)	0.00049087	0.0004909	0.000490874	0.000491
Meter Temperature (F)	72.417	77.417	78.375	76.069
Stack Temperature (F)	113.417	103.500	102.250	106.389
Ending DGM Volume (ACF)	537.987	598.745	659.159	
Beginning DGM Volume (ACF)	489.166	548.537	608.88	
Volume of Dry Gas Sample (acf)	48.8210	50.2080	50.2790	49.7693
Dry, Std. Gas Sample Volume (dscf)	49.1286	50.053	50.061	49.7475
Condensate Collected (mL)	72.00	89.00	87.70	82.90
Moisture Concentration (%)	6.45	7.72	7.62	7.26
Carbon Dioxide Concentration (%)	0.320	0.220	0.400	0.313
Oxygen Concentration (%)	20.300	20.420	20.450	20.390
Carbon Monoxide Concentration (%)	0.000	0.000	0.000	0.000
Nitrogen Conc. Dry (gas balance)	79.380	79.360	79.150	79.297
Molecular Weight, Dry (lb/lb-mole)	28.8632	28.8520	28.8820	28.8657
Molecular Weight, Wet (lb/lb-mole)	28.1622	28.0139	28.0530	28.0764
SQRT Delta P Avg., Pitot (in. H ₂ O)	0.569051	0.555836	0.581913	0.568934
Avg. Velocity, Stack Gas (ft/sec)	33.6035	32.6240	34.0929	33.4401
Actual Flow Rate (acfm)	22268.334	21619.287	22592.676	22160.099
Dry, Std. Vol. Flow Rate (dscfm)	19303.906	18812.170	19725.345	19280.473
% Isokinetic	95.49	99.83	95.23	96.85
Total Filter Catch (mg)	1.40	0.80	0.00	0.73
Total Wash Catch (mg)	11.00	2.50	8.60	7.37
Total Catch (mg)	12.40	3.30	8.60	8.10
Particulate Conc. (grams/dscf)	0.0003	0.0001	0.0002	0.0002
Particulate Conc. (grains/dscf)	0.0039	0.0010	0.0026	0.0025
Particulate Concentration (lb/dscf)	5.57E-07	1.45E-07	3.79E-07	3.60E-07
Particulate Emission Rate (lb/hr)	0.6446	0.1641	0.4483	0.4190

TABLE 6-5

SULFUR DIOXIDE EMISSION SUMMARY.
SO₂

PLANT: MARSEILLES BRICK
CITY, STATE: MARSEILLES, ILL.
STACK: DRYER STACK #1

SO₂ EMISSION SUMMARY

	1	2	3	AVERAGE
Run Number	AUGUST 30, 1994			
Date of Run	937	1133	1311	
Starting Time (hours)	1040	1236	1417	
Ending Time (hours)	60	60	60	
Net Time of Run (minutes)	24	24	24	
Number of Points	30.12	30.12	30.12	
Barometric Pressure (in. Hg)	-0.12	-0.12	-0.12	
Static Pressure (in. H ₂ O)	30.11	30.11	30.11	30.11
Stack Pressure (in. Hg)	2.4458	2.4388	2.6500	2.51
Average Delta H (in. H ₂ O)	0.3363	0.3233	0.3463	0.34
Average Delta P (in. H ₂ O)	30.30	30.30	30.31	30.30
Meter Pressure (in. Hg)	0.84	0.84	0.84	0.84
Pitot Tube Coefficient	2	2	2	
Meter Box Number (STL#)	1.002	1.002	1.002	
Y-Factor	45	45	45	
Stack Diameter (in.)	11.044662	11.044662	11.044662	11.04466
Stack Cross Sectional Area (ft ²)	0.300	0.300	0.300	
Nozzle Diameter (inches)	0.00049087	0.0004909	0.000490874	0.000491
Nozzle Area (ft ²)	72.417	77.417	78.375	76.069
Meter Temperature (F)	113.417	103.500	102.250	106.389
Stack Temperature (F)	537.987	598.745	659.159	
Ending DGM Volume (ACF)	489.166	548.537	608.88	
Beginning DGM Volume (ACF)	48.8210	50.2080	50.2790	49.7693
Volume of Dry Gas Sample (acf)	49.1286	50.053	50.061	49.7475
Dry, Std. Gas Sample Volume (dscf)	72.00	89.00	87.70	82.90
Condensate Collected (mL)	6.45	7.72	7.62	7.26
Moisture Concentration (%)	0.320	0.220	0.400	0.313
Carbon Dioxide Concentration (%)	20.300	20.420	20.450	20.390
Oxygen Concentration (%)	0.000	0.000	0.000	0.000
Carbon Monoxide Concentration (%)	79.380	79.360	79.150	79.297
Nitrogen Conc. Dry (gas balance)	28.8632	28.8520	28.8820	28.8657
Molecular Weight, Dry (lb/lb-mole)	28.1622	28.0139	28.0530	28.0764
Molecular Weight, Wet (lb/lb-mole)	0.569051	0.555836	0.581913	0.568934
SQRT Delta P Avg., Pitot (in. H ₂ O)	33.6035	32.6240	34.0929	33.4401
Avg. Velocity, Stack Gas (ft/sec)	22268.334	21619.287	22592.676	22160.099
Actual Flow Rate (acfm)	19303.906	18812.170	19725.345	19280.473
Dry, Std. Vol. Flow Rate (dscfm)	95.49	99.83	95.23	96.85
% Isokinetic	N/D	N/D	N/D	0.00
Total Catch (mg) SO ₂	N/D	N/D	N/D	0.0000
SO ₂ Conc. (grams/dscf)	N/D	N/D	N/D	0.0000
SO ₂ Conc. (grains/dscf)	N/D	N/D	N/D	0.00E+00
SO ₂ Concentration (lb/dscf)	N/D	N/D	N/D	0.0000
SO ₂ Emission Rate (lb/hr)				

N/D = NON-DETECT

TABLE 6-6

SULFUR TRIOXIDE EMISSION SUMMARY.
SO₃

PLANT: MARSEILLES BRICK
CITY, STATE: MARSEILLES, ILL.
STACK: DRYER STACK #1

SO₃ EMISSION SUMMARY

	1	2	3	AVERAGE
Run Number	AUGUST 30, 1994			
Date of Run				
Starting Time (hours)	937	1133	1311	
Ending Time (hours)	1040	1236	1417	
Net Time of Run (minutes)	60	60	60	
Number of Points	24	24	24	
Barometric Pressure (in. Hg)	30.12	30.12	30.12	
Static Pressure (in. H ₂ O)	-0.12	-0.12	-0.12	
Stack Pressure (in. Hg)	30.11	30.11	30.11	30.11
Average Delta H (in. H ₂ O)	2.4458	2.4388	2.6500	2.51
Average Delta P (in. H ₂ O)	0.3363	0.3233	0.3463	0.34
Meter Pressure (in. Hg)	30.30	30.30	30.31	30.30
Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Meter Box Number (STL#)	2	2	2	
Y-Factor	1.002	1.002	1.002	
Stack Diameter (in.)	45	45	45	
Stack Cross Sectional Area (ft ²)	11.044662	11.044662	11.044662	11.04466
Nozzle Diameter (inches)	0.300	0.300	0.300	
Nozzle Area (ft ²)	0.00049087	0.0004909	0.000490874	0.000491
Meter Temperature (F)	72.417	77.417	78.375	76.069
Stack Temperature (F)	113.417	103.500	102.250	106.389
Ending DGM Volume (ACF)	537.987	598.745	659.159	
Beginning DGM Volume (ACF)	489.166	548.537	608.88	
Volume of Dry Gas Sample (acf)	48.8210	50.2080	50.2790	49.7693
Dry, Std. Gas Sample Volume (dscf)	49.1286	50.053	50.061	49.7475
Condensate Collected (mL)	72.00	89.00	87.70	82.90
Moisture Concentration (%)	6.45	7.72	7.62	7.26
Carbon Dioxide Concentration (%)	0.320	0.220	0.400	0.313
Oxygen Concentration (%)	20.300	20.420	20.450	20.390
Carbon Monoxide Concentration (%)	0.000	0.000	0.000	0.000
Nitrogen Conc. Dry (gas balance)	79.380	79.360	79.150	79.297
Molecular Weight, Dry (lb/lb-mole)	28.8632	28.8520	28.8820	28.8657
Molecular Weight, Wet (lb/lb-mole)	28.1622	28.0139	28.0530	28.0764
SQRT Delta P Avg., Pitot (in. H ₂ O)	0.569051	0.555836	0.581913	0.568934
Avg. Velocity, Stack Gas (ft/sec)	33.6035	32.6240	34.0929	33.4401
Actual Flow Rate (acfm)	22268.334	21619.287	22592.676	22160.099
Dry, Std. Vol. Flow Rate (dscfm)	19303.906	18812.170	19725.345	19280.473
% Isokinetic	95.49	99.83	95.23	96.85
Total Catch (mg) SO ₃	0.18	0.25	10.67	3.70
SO ₃ Conc. (grams/dscf)	0.0000	0.0000	0.0002	0.0001
SO ₃ Conc. (grains/dscf)	0.0001	0.0001	0.0033	0.0011
SO ₃ Concentration (lb/dscf)	8.08E-09	1.10E-08	4.70E-07	1.63E-07
SO ₃ Emission Rate (lb/hr)	0.0094	0.0124	0.5562	0.1927

TABLE 6-7

PARTICULATE MATTER EMISSION SUMMARY.

PLANT: MARSEILLES BRICK
 CITY, STATE: MARSEILLES, ILL.
 STACK: DRYER STACK #2

PARTICULATE MATTER SUMMARY

	1	2	3	AVERAGE
Run Number	AUGUST 30, 1994			
Date of Run	1520	1733	1856	
Starting Time (hours)	1623	1838	1958	
Ending Time (hours)	60	60	60	
Net Time of Run (minutes)	24	24	24	
Number of Points	30.06	30.06	30.06	
Barometric Pressure (in. Hg)	-0.22	-0.22	-0.22	
Static Pressure (in. H ₂ O)	30.04	30.04	30.04	30.04
Stack Pressure (in. Hg)	2.3029	2.2613	2.2383	2.27
Average Delta H (in. H ₂ O)	0.2992	0.2917	0.2850	0.29
Average Delta P (in. H ₂ O)	30.23	30.23	30.22	30.23
Meter Pressure (in. Hg)	0.84	0.84	0.84	0.84
Pitot Tube Coefficient	2	2	2	
Meter Box Number (STL#)	1.002	1.002	1.002	
Y-Factor	45	45	45	
Stack Diameter (in.)	11.044662	11.044662	11.044662	11.04466
Stack Cross Sectional Area (ft ²)	0.300	0.300	0.300	
Nozzle Diameter (inches)	0.00049087	0.0004909	0.000490874	0.000491
Nozzle Area (ft ²)	75.500	79.750	83.625	79.625
Meter Temperature (F)	103.583	102.667	104.500	103.583
Stack Temperature (F)	714.134	774.13	832.62	
Ending DGM Volume (ACF)	667.141	726.747	785.615	
Beginning DGM Volume (ACF)	46.9930	47.3830	47.0050	47.1270
Volume of Dry Gas Sample (acf)	46.9073	46.919	46.211	46.6792
Dry, Std. Gas Sample Volume (dscf)	96.50	89.70	88.20	91.47
Condensate Collected (mL)	8.83	8.26	8.24	8.44
Moisture Concentration (%)	0.300	0.400	0.300	0.333
Carbon Dioxide Concentration (%)	20.380	20.430	20.300	20.370
Oxygen Concentration (%)	0.000	0.000	0.000	0.000
Carbon Monoxide Concentration (%)	79.320	79.170	79.400	79.297
Nitrogen Conc. Dry (gas balance)	28.8632	28.8812	28.8600	28.8681
Molecular Weight, Dry (lb/lb-mole)	27.9041	27.9829	27.9648	27.9506
Molecular Weight, Wet (lb/lb-mole)	0.532303	0.524855	0.516691	0.524616
SQRT Delta P Avg., Pitot (in. H ₂ O)	31.3416	30.8344	30.4141	30.8633
Avg. Velocity, Stack Gas (ft/sec)	20769.412	20433.348	20154.774	20452.511
Actual Flow Rate (acfm)	17813.572	17664.152	17369.102	17615.609
Dry, Std. Vol. Flow Rate (dscfm)	98.80	99.67	99.83	99.43
% Isokinetic	0.40	1.50	0.10	0.67
Total Filter Catch (mg)	4.90	3.80	3.70	4.13
Total Wash Catch (mg)	5.30	5.30	3.80	4.80
Total Catch (mg)	0.0001	0.0001	0.0001	0.0001
Particulate Conc. (grams/dscf)	0.0017	0.0017	0.0012	0.0016
Particulate Conc. (grains/dscf)	2.49E-07	2.49E-07	1.81E-07	2.27E-07
Particulate Concentration (lb/dscf)	0.2663	0.2640	0.1890	0.2397
Particulate Emission Rate (lb/hr)				

TABLE 6-8
SULFUR DIOXIDE EMISSION SUMMARY.
SO₂

PLANT: MARSEILLES BRICK
CITY, STATE: MARSEILLES, ILL.
STACK: DRYER STACK #2

SO₂ EMISSION SUMMARY

	1	2	3	AVERAGE
Run Number	AUGUST 30, 1994			
Date of Run				
Starting Time (hours)	1520	1733	1856	
Ending Time (hours)	1623	1838	1958	
Net Time of Run (minutes)	60	60	60	
Number of Points	24	24	24	
Barometric Pressure (in. Hg)	30.06	30.06	30.06	
Static Pressure (in. H ₂ O)	-0.22	-0.22	-0.22	
Stack Pressure (in. Hg)	30.04	30.04	30.04	30.04
Average Delta H (in. H ₂ O)	2.3029	2.2613	2.2383	2.27
Average Delta P (in. H ₂ O)	0.2992	0.2917	0.2850	0.29
Meter Pressure (in. Hg)	30.23	30.23	30.22	30.23
Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Meter Box Number (STL#)	2	2	2	
Y-Factor	1.002	1.002	1.002	
Stack Diameter (in.)	45	45	45	
Stack Cross Sectional Area (ft ²)	11.044662	11.044662	11.044662	11.04466
Nozzle Diameter (inches)	0.300	0.300	0.300	
Nozzle Area (ft ²)	0.00049087	0.0004909	0.000490874	0.000491
Meter Temperature (F)	75.500	79.750	83.625	79.625
Stack Temperature (F)	103.583	102.667	104.500	103.583
Ending DGM Volume (ACF)	714.134	774.13	832.62	
Beginning DGM Volume (ACF)	667.141	726.747	785.615	
Volume of Dry Gas Sample (acf)	46.9930	47.3830	47.0050	47.1270
Dry, Std. Gas Sample Volume (dscf)	46.9073	46.919	46.211	46.6792
Condensate Collected (mL)	96.50	89.70	88.20	91.47
Moisture Concentration (%)	8.83	8.26	8.24	8.44
Carbon Dioxide Concentration (%)	0.300	0.400	0.300	0.333
Oxygen Concentration (%)	20.380	20.430	20.300	20.370
Carbon Monoxide Concentration (%)	0.000	0.000	0.000	0.000
Nitrogen Conc. Dry (gas balance)	79.320	79.170	79.400	79.297
Molecular Weight, Dry (lb/lb-mole)	28.8632	28.8812	28.8600	28.8681
Molecular Weight, Wet (lb/lb-mole)	27.9041	27.9829	27.9648	27.9506
SQRT Delta P Avg., Pitot (in. H ₂ O)	0.532303	0.524855	0.516691	0.524616
Avg. Velocity, Stack Gas (ft/sec)	31.3416	30.8344	30.4141	30.8633
Actual Flow Rate (acfm)	20769.412	20433.348	20154.774	20452.511
Dry, Std. Vol. Flow Rate (dscfm)	17813.572	17664.152	17369.102	17615.609
% Isokinetic	98.80	99.67	99.83	99.43
Total Catch (mg) SO ₂	N/D	N/D	1.60	0.53
SO ₂ Conc. (grams/dscf)	N/D	N/D	0.0000	0.0000
SO ₂ Conc. (grains/dscf)	N/D	N/D	0.0005	0.0002
SO ₂ Concentration (lb/dscf)	N/D	N/D	7.63E-08	2.54E-08
SO ₂ Emission Rate (lb/hr)	N/D	N/D	0.0796	0.0265

N/D = NON-DETECT

TABLE 6-9

SULFUR TRIOXIDE EMISSION SUMMARY.
SO₃

PLANT: MARSEILLES BRICK
CITY, STATE: MARSEILLES, ILL.
STACK: DRYER STACK #2

SO₃ EMISSION SUMMARY

	1	2	3	AVERAGE
Run Number	AUGUST 30, 1994			
Date of Run				
Starting Time (hours)	1520	1733	1856	
Ending Time (hours)	1623	1838	1958	
Net Time of Run (minutes)	60	60	60	
Number of Points	24	24	24	
Barometric Pressure (in. Hg)	30.06	30.06	30.06	
Static Pressure (in. H ₂ O)	-0.22	-0.22	-0.22	
Stack Pressure (in. Hg)	30.04	30.04	30.04	30.04
Average Delta H (in. H ₂ O)	2.3029	2.2613	2.2383	2.27
Average Delta P (in. H ₂ O)	0.2992	0.2917	0.2850	0.29
Meter Pressure (in. Hg)	30.23	30.23	30.22	30.23
Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Meter Box Number (STL#)	2	2	2	
Y-Factor	1.002	1.002	1.002	
Stack Diameter (in.)	45	45	45	
Stack Cross Sectional Area (ft ²)	11.044662	11.044662	11.044662	11.04466
Nozzle Diameter (inches)	0.300	0.300	0.300	
Nozzle Area (ft ²)	0.00049087	0.0004909	0.000490874	0.000491
Meter Temperature (F)	75.500	79.750	83.625	79.625
Stack Temperature (F)	103.583	102.667	104.500	103.583
Ending DGM Volume (ACF)	714.134	774.13	832.62	
Beginning DGM Volume (ACF)	667.141	726.747	785.615	
Volume of Dry Gas Sample (acf)	46.9930	47.3830	47.0050	47.1270
Dry, Std. Gas Sample Volume (dscf)	46.9073	46.919	46.211	46.6792
Condensate Collected (mL)	96.50	89.70	88.20	91.47
Moisture Concentration (%)	8.83	8.26	8.24	8.44
Carbon Dioxide Concentration (%)	0.300	0.400	0.300	0.333
Oxygen Concentration (%)	20.380	20.430	20.300	20.370
Carbon Monoxide Concentration (%)	0.000	0.000	0.000	0.000
Nitrogen Conc. Dry (gas balance)	79.320	79.170	79.400	79.297
Molecular Weight, Dry (lb/lb-mole)	28.8632	28.8812	28.8600	28.8681
Molecular Weight, Wet (lb/lb-mole)	27.9041	27.9829	27.9648	27.9506
SQRT Delta P Avg., Pitot (in. H ₂ O)	0.532303	0.524855	0.516691	0.524616
Avg. Velocity, Stack Gas (ft/sec)	31.3416	30.8344	30.4141	30.8633
Actual Flow Rate (acfm)	20769.412	20433.348	20154.774	20452.511
Dry, Std. Vol. Flow Rate (dscfm)	17813.572	17664.152	17369.102	17615.609
% Isokinetic	98.80	99.67	99.83	99.43
Total Catch (mg) SO ₃	6.25	3.31	2.33	3.96
SO ₃ Conc. (grams/dscf)	0.0001	0.0001	0.0000	0.0001
SO ₃ Conc. (grains/dscf)	0.0021	0.0011	0.0008	0.0013
SO ₃ Concentration (lb/dscf)	2.94E-07	1.56E-07	1.11E-07	1.87E-07
SO ₃ Emission Rate (lb/hr)	0.3140	0.1649	0.1159	0.1982

TABLE 6-10

KILN OUTLET
EMISSION RATE CALCULATION
TOTAL HYDROCARBONS (THC)

En - TOTAL HYDROCARBONS (THC) Emission Rate; lb/hr
 Qsd - Volumetric Flow Rate of Stack Gas, Corrected to Dry,
 Standard Conditions; DSCF/min.
 Mw - Molecular Weight of TOTAL HYDROCARBONS (THC); 44.0 g/gmole
 Cn - Concentration of TOTAL HYDROCARBONS (THC); Dry Basis
 K1 - Conversion Factor; Part Per Million
 K2 - Conversion Factor; 385.3 g/gmole-lb/ft³
 K3 - Conversion Factor; 60 Minutes Per Hour

$$En = \frac{Cn \cdot Mw \cdot Qsd \cdot K3}{K1 \cdot K2}$$

TEST DATA
KILN OUTLET

RUN 1:	Cn =	7.800	Qsd =	17234.991
RUN 2:	Cn =	6.100	Qsd =	17135.054
RUN 3:	Cn =	6.200	Qsd =	17838.682
AVERAGE:	=	6.700		17402.91

TOTAL HYDROCARBONS (THC) Emission
CALCULATIONS:
KILN OUTLET

RUN 1:	7.8 *	44 *	17234.99 *	60
	(385.3 E6)			
		=	0.921108 LB/HR	
RUN 2:	6.1 *	44 *	17135.05 *	60
	(385.3 E6)			
		=	0.716177 LB/HR	
RUN 3:	6.2 *	44 *	17838.68 *	60
	(385.3 E6)			
		=	0.757808 LB/HR	
	AVERAGE: =		0.798364 LB/HR	

TABLE 6-11

**KILN OUTLET
EMISSION RATE CALCULATION
OXIDES OF NITROGEN (NO_x)**

- En - OXIDES OF NITROGEN (NO_x) Emission Rate; lb/hr
 Qsd - Volumetric Flow Rate of Stack Gas, Corrected to Dry,
 Standard Conditions; DSCF/min.
 Mw - Molecular Weight of OXIDES OF NITROGEN (NO_x) 46.0 g/gmole
 Cn - Concentration of OXIDES OF NITROGEN (NO_x); Dry Basis
 K1 - Conversion Factor; Part Per Million
 K2 - Conversion Factor; 385.3 g/gmole-lb/ft³
 k3 - Conversion Factor; 60 Minutes Per Hour

$$En = \frac{Cn \cdot Mw \cdot Qsd \cdot K3}{K1 \cdot k2}$$

**TEST DATA
KILN OUTLET**

RUN 1:	Cn =	16.3830	Qsd =	17234.99
RUN 2:	Cn =	15.6300	Qsd =	17135.05
RUN 3:	Cn =	7.2500	Qsd =	17838.68
AVERAGE:	=	13.088		17402.91

**OXIDES OF NITROGEN (NO_x) Emission
CALCULATIONS:
KILN OUTLET**

RUN 1:	16.383	*	46	*	17234.99	*	60
				(385.3 E6)			
				= 2.022621 LB/HR			
RUN 2:	15.63	*	46	*	17135.05	*	60
				(385.3 E6)			
				= 1.918468 LB/HR			
RUN 3:	7.25	*	46	*	17838.68	*	60
				(385.3 E6)			
				= 0.926426 LB/HR			
				AVERAGE: = 1.622505 LB/HR			

TABLE 6-12

**KILN OUTLET
EMISSION RATE CALCULATION
CARBON MONOXIDE (CO)**

En - Carbon monoxide Emission Rate; lb/hr
 Qsd - Volumetric Flow Rate of Stack Gas, Corrected to Dry,
 Standard Conditions; DSCF/min.
 Mw - Molecular Weight of Carbon Monoxide; 28.0 g/gmole
 Cn - Concentration of Carbon Monoxide; Dry Basis
 K1 - Conversion Factor; Part Per Million
 K2 - Conversion Factor; 385.3 g/gmole-lb/ft³
 K3 - Conversion Factor; 60 Minutes Per Hour

$$En = \frac{Cn \cdot Mw \cdot Qsd \cdot K3}{K1 \cdot K2}$$

TEST DATA

KILN OUTLET AUGUST 29, 1994

RUN 1:	Cn =	130.10	Qsd =	17234.99
RUN 2:	Cn =	125.98	Qsd =	17135.05
RUN 3:	Cn =	136.82	Qsd =	17838.68
AVE:		130.97		17402.91

**Carbon Monoxide (CO) Emissions
CALCULATIONS:
KILN OUTLET**

RUN 1:	130.1	*	28	*	17234.99	*	60	
					(385.3 E6)			
				=			9.776843	LB/HR
RUN 2:	125.98	*	28	*	17135.05	*	60	
					(385.3 E6)			
				=			9.412335	LB/HR
RUN 3:	136.816	*	28	*	17838.68	*	60	
					(385.3 E6)			
				=			10.64167	LB/HR
AVERAGE								9.943617 LB/HR

TABLE 6-13

**DRYER STACK 1 (NORTH)
EMISSION RATE CALCULATION
TOTAL HYDROCARBONS (THC)**

En - TOTAL HYDROCARBONS (THC) Emission Rate; lb/hr
 Qsd - Volumetric Flow Rate of Stack Gas, Corrected to Dry,
 Standard Conditions; DSCF/min.
 Mw - Molecular Weight of TOTAL HYDROCARBONS (THC); 44.0 g/gmole
 Cn - Concentration of TOTAL HYDROCARBONS (THC); Dry Basis
 K1 - Conversion Factor, Part Per Million
 K2 - Conversion Factor, 385.3 g/gmole-lb/ft³
 k3 - Conversion Factor, 60 Minutes Per Hour

$$En = \frac{Cn \cdot Mw \cdot Qsd \cdot K3}{K1 \cdot k2}$$

**TEST DATA
DRYER STACK 1 (NORTH)**

RUN 1:	Cn =	1.550	Qsd =	19303.906
RUN 2:	Cn =	0.000	Qsd =	18812.170
RUN 3:	Cn =	0.000	Qsd =	19725.345
AVERAGE:	=	0.517		19280.47

**TOTAL HYDROCARBONS (THC) Emission
CALCULATIONS:
DRYER 1 (NORTH)**

RUN 1:	1.55	*	44	*	19303.91	*	60
	(385.3 E6)				=	0.205013	LB/HR
RUN 2:	0	*	44	*	18812.17	*	60
	(385.3 E6)				=	0	LB/HR
RUN 3:	0	*	44	*	19725.35	*	60
	(385.3 E6)				=	0	LB/HR
	AVERAGE:				=	0.068338	LB/HR

TABLE 6-14

DRYER 1 (NORTH)
EMISSION RATE CALCULATION
CARBON MONOXIDE (CO)

En - Carbon monoxide Emission Rate; lb/hr
 Qsd - Volumetric Flow Rate of Stack Gas, Corrected to Dry,
 Standard Conditions; DSCF/min.
 Mw - Molecular Weight of Carbon Monoxide; 28.0 g/gmole
 Cn - Concentration of Carbon Monoxide; Dry Basis
 K1 - Conversion Factor, Part Per Million
 K2 - Conversion Factor; 385.3 g/gmole-lb/ft³
 K3 - Conversion Factor; 60 Minutes Per Hour

$$En = \frac{Cn \cdot Mw \cdot Qsd \cdot K3}{K1 \cdot K2}$$

TEST DATA

DRYER 1 (NORTH) AUGUST 30, 1994

RUN 1:	Cn =	5.50	Qsd =	19303.91
RUN 2:	Cn =	14.6	Qsd =	18812.17
RUN 3:	Cn =	5.40	Qsd =	19725.35
AVE:		8.50		19280.47

Carbon Monoxide (CO) Emissions
CALCULATIONS:
 DRYER 1 (NORTH)

RUN 1:	5.5	*	28	*	19303.91	*	60
					(385.3 E6)		
				=		0.462933	LB/HR
RUN 2:	14.6	*	28	*	18812.17	*	60
					(385.3 E6)		
				=		1.197573	LB/HR
RUN 3:	5.4	*	28	*	19725.35	*	60
					(385.3 E6)		
				=		0.464439	LB/HR
							AVERAGE 0.708345 LB/HR

TABLE 6-15

DRYER STACK 2 (SOUTH)
EMISSION RATE CALCULATION
CARBON MONOXIDE (CO)

- En - Carbon monoxide Emission Rate; lb/hr
 Qsd - Volumetric Flow Rate of Stack Gas, Corrected to Dry,
 Standard Conditions; DSCF/min.
 Mw - Molecular Weight of Carbon Monoxide; 28.0 g/gmole
 Cn - Concentration of Carbon Monoxide; Dry Basis
 K1 - Conversion Factor; Part Per Million
 K2 - Conversion Factor; 385.3 g/gmole-lb/ft³
 K3 - Conversion Factor; 60 Minutes Per Hour

$$En = \frac{Cn \cdot Mw \cdot Qsd \cdot K3}{K1 \cdot K2}$$

TEST DATA
DRYER STACK 2 (SOUTH)

RUN 1: Cn = 4.70

RUN 2: Cn = 3.00

RUN 3: Cn = 5.00

AVE: 4.23

17813.57
 Qsd = 19303.91

17664.15
 Qsd = 18812.17

17369.10
 Qsd = 19725.35

17615.61
 19280.47

*North
 Stack
 Flow
 Rates.
 Correct
 rates
 shown
 in
 red.*

Carbon Monoxide (CO) Emissions
CALCULATIONS:
DRYER STACK 2 (SOUTH)

RUN 1: 4.7 * 28 * 19303.91 * 60

(385.3 E6)

= 0.365
 0.395597 LB/HR

RUN 2: 3 * 28 * 18812.17 * 60

(385.3 E6)

= 0.231
 0.246077 LB/HR

RUN 3: 5 * 28 * 19725.35 * 60

(385.3 E6)

= 0.379
 0.430036 LB/HR

AVERAGE 0.325
 0.357237 LB/HR

APPENDIX A

Resumes



RESUME

Robert F. Folle
Air Quality Scientist

EDUCATION:

MBA, Business Management, Golden Gate University, San Francisco, California, 1979
BA, Business Administration, St. Leo College, St. Leo, Florida, 1977

QUALIFICATIONS:

Certified EPA Method 9 visual opacity observer, 40 CFR, Part 52, Appendix F, Air Pollution Control Board, St. Louis, MO, April 1993; Certified AHERA Asbestos Inspector #7ME0409920031R; Certified AHERA Asbestos Mgr. Planner #7ME040992003MPR; Certification of Completion, 40 Hr. Course in Hazardous Materials/Waste Site Investigation, 1989; Certification of Completion, Supervisors Course in Hazardous Materials/Waste Site Operations, 1990; Certification of Completion, Air Dispersion Modeling, 1990; Certification of Completion, Air Dispersion Modeling Laboratory, 1990.

EXPERIENCE:

Over 4 years experience in the performance and management of a diversified range of air quality projects. Performed as field team leader, project manager or group leader on over 200 source emissions projects involving the collection and analysis of air quality data for engineering design, permitting and compliance.

Project manager for numerous air dispersion modeling projects involving the use of the USEPA industrial source complex (ISC) short-term (ISCST) and long-term (ISCLT), complex-1 and screen models.

Extensive experience as field team leader and project manager for continuous emission monitoring system (CEMS) performance specification certification testing including CEMS relative accuracy (RA) certifications.

Participated and managed numerous projects involving asbestos sampling and asbestos air monitoring for facility and transactional environmental audits.

PROFESSIONAL AFFILIATIONS:

Member of the Air and Waste Management Association
Source Evaluation Society

RESUME



J. Todd Staley

Senior Environmental Technician

EDUCATION:

Community College of the Air Force
1983 - 1992 - Management and Construction Technology

QUALIFICATIONS:

Certified EPA Method 9 visual opacity observer
OSHA Hazardous Waste Operations and Emergency Response
RCRA Compliance & Hazardous Waste Management

EXPERIENCE:

Over nine years experience as an environmental technician. Responsible for ensuring compliance and providing technical assistance on waste disposal, UST remediation and air quality projects. Currently assigned to the Air Quality Group engaged in all technical aspects of Source Emissions testing. Participated in several source tests including projects at petroleum refineries, hazardous waste incinerators, chemical production facilities, explosive manufacturers and chemical transfer facilities.

Mr. Staley has served as an Air Quality Technician on several source emission testing projects and Continuous Emission Monitoring System (CEM) specification certifications.

He has provided technical support on several USEPA Method 5 projects including collection and analysis of Air Quality data for a major explosives plant in Missouri.

At a chemical production facility in West Virginia, he assisted in a USEPA Boiler and Industrial Furnace (BIF) project, providing Continuous Emission Monitoring (CEM) specification certifications on two CO and O₂ systems. Certifications included span drift and CEMS relative accuracy tests. (RA)

Mr. Staley is presently providing on-going monitoring services for two benzene transfer facilities in Illinois and Missouri. He is responsible for leak detection monitoring of all components at both facilities on a routine basis.

PROFESSIONAL AFFILIATIONS:

Air and Waste Management Association
Source Evaluation Society

RESUME



Daniel M. Cusac
Air Quality Technician

EDUCATION: Illinois Central College, 1989-1993, Metals Technology

QUALIFICATIONS: Certified EPA Method 9-Visual Plume Observer
OSHA Hazardous Waste Operations and Emergency Response

EXPERIENCE: Assigned to the Air Quality Division serving as a technician on several Source Emissions Testing projects. Provided technical support for Air Quality projects at petroleum refineries, waste incinerators, chemical production facilities and chemical transfer facilities.

While assigned to the Air Quality Group, Mr. Cusac has provided technical support on several source emission testing projects and Continuous Emission Monitoring (CEM) system certifications.

He has served as an Air Quality Technician on a wide variety of tests utilizing USEPA Methods 1, 2, 3, 4, 5, 9, and 12 for the collection and analysis of total particulate matter, visible opacity and lead.

Mr. Cusac has also performed multi-metals emission testing utilizing USEPA (Draft) Method 0012 at major industrial facilities. He has been involved in the collection and recovery of samples utilizing the procedures outlined in the draft method.

He has participated in conducting Continuous Emission Monitoring (CEM) system performance specification and relative accuracy testing following the guidelines published in the Boilers and Industrial Furnace (BIF) regulation.

PROFESSIONAL AFFILIATIONS: Air and Waste Management Association
Source Evaluation Society

APPENDIX B

Laboratory Analysis

Fugro - McClelland

Lab Name: Triangle Laboratories of RTP, Inc.

Client Project: Marscilles Brick

TLRTP Project Number: 29512

Date Received: September 9, 1994

Date Analyzed: October 3, 1994

Analysis Method: 40 CFR 60 App. A, Method 8

FIELD SAMPLES:

Client Sample I.D. Number:	TLI I.D. Number:	Total Sample Volume, mL:	Aliquot Volume, mL:	Normality BaCl ₂ , meq/mL:	Sample Titrant Volume used, mL:	Blank Titrant Volume, mL:	Sample Results in milligrams:
Run 1 K. Exht SO3	87-194-1	250 *	10	0.010	2.9	0.1	34.33
Run 1 K. Exht SO2	87-194-2	1000 *	2	0.010	21	0.1	3347
Run 2 K. Exht SO3	87-194-3	250 *	10	0.010	3.7	0.1	44.14
Run 2 K. Exht SO2	87-194-4	1000 *	2	0.010	21.4	0.1	3411
Run 3 K. Exht SO3	87-194-5	250 *	10	0.010	6.6	0.1	79.69
Run 3 K. Exht SO2	87-194-6	1000 *	2	0.010	22.3	0.1	3555
Run 1 N. Dryer SO3	87-194-7	250	100	0.010	0.25	0.1	0.18
Run 1 N. Dryer SO2	87-194-8	1000	10	0.010	0.1	0.1	ND
Run 2 N. Dryer SO3	87-194-9	250	100	0.010	0.3	0.1	0.25
Run 2 N. Dryer SO2	87-194-10	1000	10	0.010	0.1	0.1	ND
Run 3 N. Dryer SO3	87-194-11	250	100	0.010	8.8	0.1	10.67
Run 3 N. Dryer SO2	87-194-12	1000	10	0.010	0.1	0.1	ND
Run 1 S. Dryer SO3	87-194-13	250	100	0.010	5.2	0.1	6.25
Run 1 S. Dryer SO2	87-194-14	1000	10	0.010	0.1	0.1	ND
Run 2 S. Dryer SO3	87-194-15	250	100	0.010	2.8	0.1	3.31
Run 2 S. Dryer SO2	87-194-16	1000	10	0.010	0.1	0.1	ND
Run 3 S. Dryer SO3	87-194-17	250	100	0.010	2	0.1	2.33
Run 3 S. Dryer SO2	87-194-18	1000	10	0.010	0.15	0.1	1.60
80% IPA Blank	87-194-19	250	100	0.010	0.0	—	
3% H2O2 Blank	87-194-20	250	10	0.010	0.1	0.1	
Lab IPA Blank	—	100	100	0.010	0.1	—	

AUDIT SAMPLES:

Dry Gas Volume used, DSCM:	2.1E-02						mg/DSCM
Audit Vial # 1194	100	20	0.010	1.6	0.1		114.39

COMMENTS:

The true value of the audit used for this project was known (114.4 mg/DSCM), and the titration yielded a value within 5% of this value.

* A smaller aliquot was used for these samples due to high concentrations found during initial screening.

Triangle Laboratories of RTP, Inc.
801 Capitola Drive • Durham, NC 27713
Tele.: 919-544-5729 • Fax: 919-544-5491

Printed: 05:52 PM on 05-Oct-94

PARTICULATE LABORATORY ANALYSIS

Project Name: Marseilles Brook Date Sampled: 8-30-94

Project Number: 0894-8885-2 Date Analyzed: 9-7-94

Source: NOZEH DRYER Analyzed By: R77

Run No. <u>1</u>	Run No. <u>2</u>	Run No. <u>3</u>	Run No. _____
Beaker No. <u>94-140</u>	Beaker No. <u>94-141</u>	Beaker No. <u>94-142</u>	Beaker No. _____
Beaker Vol <u>100 ml</u>	Beaker Vol <u>100 ml</u>	Beaker Vol <u>100 ml</u>	Beaker Vol _____
Final Wt <u>63.9945 g</u>	Final Wt <u>62.5166 g</u>	Final Wt <u>60.8190 g</u>	Final Wt _____
Tare Wt <u>63.7832 g</u>	Tare Wt <u>62.5138 g</u>	Tare Wt <u>60.8101 g</u>	Tare Wt _____
Wt Gain <u>11.3 mg</u>	Wt Gain <u>2.8 mg</u>	Wt Gain <u>8.9 mg</u>	Wt Gain _____
Blk Corr <u>0.3 mg</u>	Blk Corr <u>0.3 mg</u>	Blk Corr <u>0.3 mg</u>	Blk Corr _____
Net Wt <u>11.0 mg</u>	Net Wt <u>2.5 mg</u>	Net Wt <u>8.6 mg</u>	Net Wt _____
Filter No. <u>940126</u>	Filter No. <u>940127</u>	Filter No. <u>940128</u>	Filter No. _____
Final Wt <u>0.3421 g</u>	Final Wt <u>0.3428 g</u>	Final Wt <u>0.3406 g</u>	Final Wt _____
Tare Wt <u>0.3407 g</u>	Tare Wt <u>0.3420 g</u>	Tare Wt <u>0.3406 g</u>	Tare Wt _____
Wt Gain <u>1.4 mg</u>	Wt Gain <u>0.8 mg</u>	Wt Gain <u>0 mg</u>	Wt Gain _____
Blk Gain <u>0.0 mg</u>	Blk Gain <u>0.0 mg</u>	Blk Gain <u>0 mg</u>	Blk Gain _____
Net Wt <u>1.4 mg</u>	Net Wt <u>0.8 mg</u>	Net Wt <u>0 mg</u>	Net Wt _____
TOTAL PARTICULATE WTS	TOTAL PARTICULATE WTS	TOTAL PARTICULATE WTS	TOTAL PARTICULATE WTS
Filter <u>1.4 mg</u>	Filter <u>0.8 mg</u>	Filter <u>0.0 mg</u>	Filter _____
Wash <u>11.0 mg</u>	Wash <u>2.5 mg</u>	Wash <u>8.6 mg</u>	Wash _____
Total <u>12.4 mg</u>	Total <u>3.3 mg</u>	Total <u>8.6 mg</u>	Total _____

PARTICULATE LABORATORY ANALYSIS

Project Name: Marseilles Brick Date Sampled: 8-30-94

Project Number: 0844-8885-2 Date Analyzed: 9-7-94

Source: SOIL DEVEER Analyzed By: RFF

Run No. <u>1</u>	Run No. <u>2</u>	Run No. <u>3</u>	Run No. _____
Beaker No. <u>94-143</u>	Beaker No. <u>94-144</u>	Beaker No. <u>94-145</u>	Beaker No. _____
Beaker Vol <u>100 ml</u>	Beaker Vol <u>100 ml</u>	Beaker Vol <u>100 ml</u>	Beaker Vol _____
Final Wt <u>63.4989 g</u>	Final Wt <u>63.7469 g</u>	Final Wt <u>62.4208 g</u>	Final Wt _____
Tare Wt <u>63.4937 g</u>	Tare Wt <u>63.7428 g</u>	Tare Wt <u>62.4568 g</u>	Tare Wt _____
Wt Gain <u>5.2 mg</u>	Wt Gain <u>4.1 mg</u>	Wt Gain <u>4.0 mg</u>	Wt Gain _____
Blk Corr <u>0.3 mg</u>	Blk Corr <u>0.3 mg</u>	Blk Corr <u>0.3 mg</u>	Blk Corr _____
Net Wt <u>4.9 mg</u>	Net Wt <u>3.8 mg</u>	Net Wt <u>3.7 mg</u>	Net Wt _____
Filter No. <u>940127</u>	Filter No. <u>940130</u>	Filter No. <u>940131</u>	Filter No. _____
Final Wt <u>0.3425 g</u>	Final Wt <u>0.3427 g</u>	Final Wt <u>0.3420 g</u>	Final Wt _____
Tare Wt <u>0.3421 g</u>	Tare Wt <u>0.3412 g</u>	Tare Wt <u>0.3419 g</u>	Tare Wt _____
Wt Gain <u>0.4 mg</u>	Wt Gain <u>1.5 mg</u>	Wt Gain <u>0.1 mg</u>	Wt Gain _____
Blk Gain <u>0.0 mg</u>	Blk Gain <u>0.0 mg</u>	Blk Gain <u>0.0 mg</u>	Blk Gain _____
Net Wt <u>0.4 mg</u>	Net Wt <u>1.5 mg</u>	Net Wt <u>0.1 mg</u>	Net Wt _____
TOTAL PARTICULATE WTS	TOTAL PARTICULATE WTS	TOTAL PARTICULATE WTS	TOTAL PARTICULATE WTS
Filter <u>0.4 mg</u>	Filter <u>1.5 mg</u>	Filter <u>0.1 mg</u>	Filter _____
Wash <u>4.9 mg</u>	Wash <u>3.8 mg</u>	Wash <u>3.7 mg</u>	Wash _____
Total <u>5.3 mg</u>	Total <u>5.3 mg</u>	Total <u>3.8 mg</u>	Total _____

PARTICULATE LABORATORY ANALYSIS

Project Name: Mareilles Brick

Date Sampled: 8-29-94

Project Number: 0894-8885-2

Date Analyzed: 8-31-94

Source: KILN EXHAUST

Analyzed By: SJS

Run No. <u>1</u> Beaker No. <u>94-137</u> Beaker Vol <u>100.41</u> ml Final Wt <u>62.7382</u> g Tare Wt <u>62.5624</u> g Wt Gain <u>175.8</u> mg Blk Corr <u>0.3</u> mg Net Wt <u>175.5</u> mg	Run No. <u>2</u> Beaker No. <u>94-138</u> Beaker Vol <u>100.41</u> ml Final Wt <u>64.1636</u> g Tare Wt <u>64.1081</u> g Wt Gain <u>55.5</u> mg Blk Corr <u>0.3</u> mg Net Wt <u>55.2</u> mg	Run No. <u>3</u> Beaker No. <u>94-139</u> Beaker Vol <u>100.41</u> ml Final Wt <u>64.4487</u> g Tare Wt <u>64.3255</u> g Wt Gain <u>119.4</u> mg Blk Corr <u>0.3</u> mg Net Wt <u>119.1</u> mg	Run No. <u>BLANK</u> Beaker No. <u>94-100</u> Beaker Vol <u>100.41</u> ml Final Wt <u>61.0087</u> g Tare Wt <u>61.0084</u> g Wt Gain <u>0.30</u> mg Blk Corr <u>0.30</u> mg Net Wt <u>0.30</u> mg
Filter No. <u>940123</u> Final Wt <u>0.7561</u> g Tare Wt <u>0.3428</u> g Wt Gain <u>413.3</u> mg Blk Gain <u>0</u> mg Net Wt <u>413.3</u> mg	Filter No. <u>940124</u> Final Wt <u>0.6057</u> g Tare Wt <u>0.3427</u> g Wt Gain <u>263.0</u> mg Blk Gain <u>0</u> mg Net Wt <u>263.0</u> mg	Filter No. <u>940125</u> Final Wt <u>0.6077</u> g Tare Wt <u>0.3345</u> g Wt Gain <u>268.2</u> mg Blk Gain <u>0</u> mg Net Wt <u>268.2</u> mg	Filter No. <u>940140 (BLANK)</u> Final Wt <u>0.3410</u> g Tare Wt <u>0.3410</u> g Wt Gain <u>0</u> mg Blk Gain <u>0</u> mg Net Wt <u>0</u> mg
TOTAL PARTICULATE WTS Filter <u>413.3</u> mg Wash <u>175.5</u> mg Total <u>588.80</u> mg	TOTAL PARTICULATE WTS Filter <u>263.0</u> mg Wash <u>55.2</u> mg Total <u>318.20</u> mg	TOTAL PARTICULATE WTS Filter <u>268.2</u> mg Wash <u>119.1</u> mg Total <u>387.30</u> mg	TOTAL PARTICULATE WTS Filter <u>0.0</u> mg Wash <u>0.3</u> mg Total <u>0.3</u> mg

APPENDIX C

Field Data Sheets

PLANT

Morrells BrickPROJECT 0894-8885

CITY, STATE

Morrells IL

TEST SERIES NO. _____

STACK

Kila Exhaust

DATE

8-29-91

VELOCITY TRAVERSE DATA

Run No. _____

Page _____ of _____

	Clock Time Cycles	Port # and Point	Stack Temp. °F	Δp in. H ₂ O	$\sqrt{\Delta p}$
1	0		435	.31	
2	0		440	.40	
3	0		443	.40	
4	0		443	.30	
5	0		445	.26	
6	0		445	.22	
7	0		445	.18	
8	0		444	.17	
9	0		447	.55	
10	0		449	.52	
11	0		450	.50	
12	0		451	.39	
13	0		452	.36	
14	0		453	.34	
15	0		447	.36	
16	0		452	.38	
17	0		455	.46	
18	0		457	.47	
19	0		458	.50	
20	0		459	.51	
21	0		460	.42	
22					
23					
24					
25					
AVERAGES			449	.40	.6324

PITOT TUBE

Number _____

Coefficient (C_p) _____

Calibration Date _____

PRESSURES

Barometric 30.24 in. HgStatic -.15 in. H₂OStack (P_s) _____ in. Hg

CALCULATIONS

Stack Area (A) _____ ft²Water Vapor Conc. 5 %

Dry Gas Fraction (DGF)

DGF = 1 - (XH₂O/100) = _____Carbon Dioxide Conc. 2.2 %Oxygen Concentration 16.7 %Molecular Weight, Wet (M_w) _____RMS $p = (\sqrt{\Delta p})^2$ _____ $\sqrt{\Delta p} =$ _____Stack Temp. _____ °F + 460 = (T_s) _____ °RStack Gas Velocity (V_s) $V_s = (\sqrt{T_s / (P_s \times K)} / \sqrt{\Delta p}) C$, 85.43V_s = _____ feet/secondActual Volumetric Flowrate (Q_a)Q_a = 3600 V_s AQ_a = _____ acf/hourQ_a/60 = _____ acf/min.Dry, Standard Volumetric Flowrate (Q_d)Q_d = 17.64 Q_a DGF P_s / T_sQ_d = _____ dscf/hourQ_d/60 = _____ dscf/min.

Signature _____

Company Marsalles Brick Project 0894-8885
 Test Location Marsalles 1C Date 8-29-97


Traverse Point Determination -- Rectangular Duct

Size of Duct 3.47 ft x 3.47 ft Equivalent Diameter ft
 (2LW/L+W)

Distance upstream from disturbance ft diameters

Distance downstream from disturbance ft diameters

Minimum Number of Traverse Points



Minimum number of traverse points 21

Matrix layout 3 ports x 7 traverse points


Distance between traverse points 5.86' ft
 (Depth of duct / Points at one port)

Distance from stack wall to first point 2.93 ft
 (Distance between points / 2)

Port Extension Length 20 inches

Point	Distances From (inches)	
	Stack Wall	End of Port
1	<u>2.93</u>	<u>22.9</u>
2	<u>8.78</u>	<u>28.8</u>
3	<u>14.64</u>	<u>34.6</u>
4	<u>20.5</u>	<u>40.5</u>
5	<u>26.36</u>	<u>46.36</u>
6	<u>32.21</u>	<u>52.21</u>
7	<u>38.07</u>	<u>58.07</u>

Cross Section





Company Marselles Back

Project 0894-8223

Test Location Marselles IL

Date 8-30-94

Traverse Point Determination — Circular Stacks

Stack Inside Diameter 3.75 feet

Is diameter greater than 12 inches? Yes/ No

Distance Upstream from Disturbance _____ ft _____ diameters


Distance Downstream from Disturbance _____ ft _____ diameters

Are the ports greater than two diameters downstream and one-half diameter upstream from disturbances? Yes/ No

Number of Traverse Points Required (as shown in 40CFR60, Appendix A, Method 1) 24 points

Number of Traverse Points per Diameter 24/12

Minimum Number of Traverse Points



Port Extension Length

6 inches

Point No.	% of ID From Wall	Distance To Inside Wall	Distance To Outside Port Edge
1	<u>2.1</u>	<u>0.94</u>	<u>6.94</u>
2	<u>6.7</u>	<u>3.0</u>	<u>9.0</u>
3	<u>11.8</u>	<u>5.3</u>	<u>11.3</u>
4	<u>17.7</u>	<u>8.0</u>	<u>14.0</u>
5	<u>25.0</u>	<u>11.25</u>	<u>17.25</u>
6	<u>33.6</u>	<u>16.0</u>	<u>22.0</u>
7	<u>44.1</u>	<u>29.0</u>	<u>32.0</u>
8	<u>55.0</u>	<u>33.7</u>	<u>39.7</u>
9	<u>67.3</u>	<u>37.0</u>	<u>43.0</u>
10	<u>80.2</u>	<u>39.7</u>	<u>45.7</u>
11	<u>93.3</u>	<u>42.0</u>	<u>48.0</u>
12	<u>97.9</u>	<u>44.0</u>	<u>50.0</u>

PLANT Marselles Brick PROJECT 0894-8885
 CITY, STATE Marselles IL TEST SERIES NO. —
 STACK NORTH DRYER DATE 8-30-94

VELOCITY TRAVERSE DATA

Run No. —
 Page — of —

	Clock Time	Port # and Point	Stack Temp. °F	Δp in. H ₂ O	$\sqrt{\Delta p}$
1	0		108	.71	
2	0		114	.65	
3	0		115	.55	
4	0		116	.35	
5	0		116	.27	
6	0		117	.15	
7	0		117	.14	
8	0		117	.20	
9	0		117	.21	
10	0		117	.11	
11	0		118	.21	
12	0		118	.21	
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
AVERAGES			116	.313	0.5595

PITOT TUBE

Number —
 Coefficient (C_p) .84
 Calibration Date —

PRESSURES

Barometric 30.12 in. Hg
 Static -.12 in. H₂O
 Stack (P_s) — in. Hg

CALCULATIONS

Stack Area (A) — ft²
 Water Vapor Conc. 5 %

Dry Gas Fraction (DGF)

$$DGF = 1 - (\%H_2O/100) = \underline{\hspace{2cm}}$$

Carbon Dioxide Conc. — %

Oxygen Concentration — %

Molecular Weight, Wet (M_w) —

$$RMS\ p = (\sqrt{\Delta p})^2 = \sqrt{\Delta p} = \underline{\hspace{2cm}}$$

Stack Temp. — °F + 460 = (T_s) — °R

Stack Gas Velocity (V_s)

$$V_s = \left(\sqrt{(T_s / (P_s \times 8.3)) / (\sqrt{\Delta p})} \right) C_p \times 85.49$$

$$V_s = \underline{\hspace{2cm}} \text{ feet/second}$$

Actual Volumetric Flowrate (Q_a)

$$Q_a = 3600 V_s A$$

$$Q_a = \underline{\hspace{2cm}} \text{ acf/hour}$$

$$Q_a / 60 = \underline{\hspace{2cm}} \text{ acf/min.}$$

Dry, Standard Volumetric Flowrate (Q_s)

$$Q_s = 17.64 Q_a DGF P_s / T_s$$

$$Q_s = \underline{\hspace{2cm}} \text{ dscf/hour}$$

$$Q_s / 60 = \underline{\hspace{2cm}} \text{ dscf/min.}$$

Signature —

Client: Morales BrackLocation: Morales 16Source ID: Kiln ExhaustProject No: 0891-0885Date: 6-29-94Run Number: 1Operator: JDHot Box No: 5722Cold Box No: 5722Console No: 5722

Plot No:

Plot Coefficient: .84DMC Factor: 1.002Meter & Hg: 1.887Barometric Pressure: 30.24Stack Diameter, in: 11.614Nozzle Diameter, in: .37Filter No: 740123Ambient Temp: 75Static Pressure: -15K Factor: 11.35

Port and Traverse Point No.	Sample Time	Dry Gas Meter Reading	Velocity		Orifice Pressure Difference		Stack Gas Temperature		Filter Box	Sample Train Temperature (°F)		Vacuum (in Hg)
			MP	AP	Calc	Actual	Temp (°F)	Temp (°F)		Impinger	Gas Meter	
1 (1)W	0	257.989	.30		0.5477	3.4	449	251	250	64	85	3
2	2.86	260.670	.41		0.6483	4.6	453	250	250	55	86	5
3	5.72	263.990	.35		0.5916	4.0	418	250	250	61	88	5
4	8.58	267.120	.30		0.5477	3.4	425	250	251	60	88	5
5	11.41	269.610	.25		0.5000	2.8	433	250	250	60	90	4
6	14.3	272.420	.21		0.4582	2.4	433	250	250	60	90	4
7	17.16	274.970	.15		0.3873	1.7	435	250	250	61	90	4
8 (2)	20.02	276.83	.45		0.6708	5.1	446	250	251	60	91	5
9	22.88	279.590	.51		0.7141	5.8	451	250	250	60	92	6
10	25.74	283.620	.50		0.7071	5.6	455	251	251	59	93	5
11	28.6	286.950	.30		0.5477	3.4	458	250	250	59	94	5
12	31.46	290.500	.35		0.5916	4.0	385	250	250	58	95	5
13	34.32	293.640	.35		0.5916	4.0	419	250	251	59	96	5
14	37.18	297.400	.25		0.5000	2.8	425	250	251	60	99	5
15 (3)	40.04	298.707	.35		0.5916	4.0	420	250	250	61	94	5
16	42.9	301.570	.40		0.6324	4.5	436	250	251	62	95	5
Total/Avg												

COMMENTS:

Start 1048Stop 1154

28.2475

Flue Gas Analysis

Total	O ₂		CO ₂		H ₂	
	1	2	1	2	1	2
1	16.73	2.28				
2	16.73	2.28				
3	16.73	2.28				
Avg						

Weight

Gained

Final Weights	Initial Weights	Weight Gained
00	100	0
140	100	40
110	100	10
250	250	31.1
Total/Avg	81.1	Total Condensate

Pretest Leak Check @ 10 "Hg for 0.00 CFMPosttest Leak Check @ 10 "Hg for 0.00 CFM

Portland Cement Sample Point No.	Sample Time	DR Gas Meter Reading	Velocity Head (H ₂ O)		Oil/Gas Pressure Differential (H ₂ O)		Stick (in)	Sample Oil Temperatures (°F)			Vacuum (Hg)	
			SP	VAP	CALC	Actual		Probe	Filter Box	Last Impinge		
17	45.76	303.970	.40	0.632d	4.540	4.5	443	280	250	62	76	5
18	48.62	307.990	.45	0.6708	5.1075	5.1	445	230	250	62	96	6
19	51.48	311.600	.51	0.7141	5.7685	5.8	448	250	250	63	97	6
20	54.34	315.000	.46	0.6782	5.221	5.2	452	251	250	64	98	6
21	57.2	318.980	.42	0.6480	4.767	4.8	457	250	250	64		
	60.06	321.647										
								</				



Client: *Marzelles Buck* Hot Box No.: *STLZ* Standard Pressure: *30.24*
Location: *Marzelles LC* Cold Box No.: *STLZ* Stack Diameter, in: *11.674*
Source I.D.: *Kiln Exhaust* Console No.: *STLZ* Horz. Diameter, in: *.37*
Project No.: *0894-885* Plot No.: *9/10/24*
Date: *8-29-94* Plot Coefficient: *.84* Ambient Temp.: *81*
Run Number: *2* DMC Factor: *1.002* Static Pressure: *-.15*
Operator: *JTS* Meter a No.: *1.887* K Factor: *11.52*

94.14

Port and Traverse Position	Sample Time	Dry Gas Meter Reading	Velocity Head (ft/10)		Orifice Pressure Differential (ft/10)		Stack Gas Temperature (°F)		Sample Train Temperatures (°F)			Vacuum (in. Hg)
			P	V/C	Calc.	Actual	Probe	Filter Box	Last Impinger	Dry Gas Meter		
1 (1E)	0	338.035	.32		3.6864	3.7	437	250	251	60	90	2
2	2.7	335.820	.41		4.7252	4.7	451	251	250	52	90	2
3	5.7	339.300	.35		4.032	4.0	455	250	250	52	91	2
4	8.6	342.321	.43		4.9536	4.9	423	250	251	53	92	2
5	11.4	345.410	.47		5.4144	5.4	414	250	250	53	92	2
6	14.3	349.016	.45		5.184	5.2	424	250	250	52	93	2
7	17.2	352.610	.35		4.032	4.0	428	250	251	52	94	2
8 (2)	20.0	355.700	.40		4.608	4.6	434	251	251	50	94	2
9	22.9	357.521	.40		4.608	4.6	435	251	250	51	95	2
10	25.7	361.600	.51		5.8752	5.9	443	250	250	54	95	4
11	28.6	365.520	.42		4.8384	4.8	448	251	250	52	95	4
12	31.5	369.120	.40		4.608	4.6	452	250	250	54	96	4
13	34.3	372.760	.25		3.3408	3.3	455	250	250	54	96	4
14	37.2	376.000	.35		4.032	4.0	460	250	250	56	97	3
15 (3)	40.0	378.582	.25		3.3408	3.3	411	250	251	57	97	3
16	42.9	380.840	.30		3.456	3.4	420	250	250	58		
Total/Av.												

COMMENTS:

Start 1250

Stop 1355

Flue Gas Analysis

Thal	O ₂			CO ₂			H ₂		
	1	2	3	1	2	3	1	2	3
1	18.3	2.33							
2	18.3	2.33							
3	18.3	2.33							
AVG									

Weight Gained

Final Weights	Initial Weights	Weight Gained
First Impinger	100	—
Second Impinger	100	40
Third Impinger	100	12
Silica Gel	250	27.3
79.3 Total Condensate		

Pretest Leak Check @ 15" Hg for .0002 CFM

Posttest Leak Check @ 15" Hg for .0002 CFM

[illegible]

Portland Cement Traverse Point No.	Sample Number	Dry Gas Meter Reading	Velocity Head (ft)		Orifice Pressure Difference (in H ₂ O)		Stick Temperature (°F)	Probe	Sample Train Temperature (°F)		Dry Gas Meter	Vacuum (in Hg)
			% P	ft/sec	Calc	Actual			Filler Box	Loss Impinger		
17	45.8	383.940	.30	2.3477	3.456	3.1	427	250	250	61	95	3
18	48.6	386.620	.25	0.5000	2.880	2.8	430	250	251	61	96	3
19	51.5	389.320	.30	0.5477	3.456	3.4	435	250	251	62	96	3
20	54.3	391.200	.32	0.5657	3.6864	3.7	439	250	251	63	97	3
21	57.2	395.800	.20	0.5099	2.9952	3.0	441	251	251	64	98	3
60.0	397.720											
Total			3.50			4.13	436					



Client: *Morales Back*
Location: *Morales Back*
Source I.D.: *Kila Exhaust*
Project No.: *0894-8885*
Date: *8-29-91*
Run Number: *3*
Operator: *JTS*

Hot Box No.: *5722*
Cold Box No.: *5722*
Console No.: *5722*
Pilot No.:
Pilot Coefficient: *.84*
DDMC Factor: *1.002*
Meter a.Hg: *1.887*
Barometric Pressure: *30.27*
Stack Diameter, in: *41*
Nozzle Diameter, in: *.57*
Filter No.: *94025*
Ambient Temp.: *85*
Static Pressure: *-.15*
K Factor: *11.65*

Port and Traverse Point No.	Sample Time	Dry Gas Meter Reading	Velocity Head (ft/Hr)		Orifice Pressure Differential (in.H ₂ O)		Stack Gas Temperature (°F)		Sample Train Temperature (°F)		Velocity (ft/Hr)	
			V.P.	Actual	Calc.	Actual	Temp.	Probe	Filter Box	Impinger Gas Meter		
1 (17W)	0	413.778	.30		3.456	3.4	423	250	251	52	95	2
2	2.7	416.240	.35		4.032	4.0	446	250	250	52	85	2
3	5.7	419.690	.35		4.032	4.0	447	250	250	52	95	2
4	8.6	421.930	.42		4.8384	4.8	449	250	250	53	96	2
5	11.4	426.300	.47		5.4755	5.5	453	250	250	53	96	2
6	14.3	429.721	.42		4.8384	4.8	455	250	251	54	96	2
7	17.2	432.410	.25		2.9125	2.9	400	250	250	55	96	2
8 (2)	20.0	435.142	.45		5.2425	5.2	420	250	250	58	97	2
9	22.7	438.810	.51		5.9415	5.9	426	250	250	57	97	4
10	25.7	442.200	.47		5.4755	5.5	432	250	250	59	97	3
11	28.6	445.000	.40		4.660	4.7	434	250	251	59	98	3
12	31.5	448.830	.40		4.660	4.7	439	250	250	60	98	3
13	34.3	452.160	.35		4.032	4.0	443	250	251	60	98	3
14	37.2	455.420	.20		2.3500	2.3	445	250	250	61	99	3
15 (3)	40.0	458.264	.30		3.456	3.4	449	251	250	60	99	3
16	42.9	459.990	.34		3.961	4.0	429	251	250	62	99	3
Total/Avg												

COMMENTS:

Start *1451*
Stop *1556*

Flue Gas Analysis

Thal	O ₂			CO ₂			H ₂		
	1	2	3	1	2	3	1	2	3
1	19.38	2.27							
2	19.38	2.27							
3	19.38	2.27							
Avg									

	Final Weights	Initial Weights	Weight Gained
First Impinger	100	100	0
Second Impinger	142	100	42
Third Impinger	110	100	10
Seica Od	258.2	250	8.2
Total/Avg	60.2	Total Condensate	

Pretest Leak Check @ *15* "Hg for *0.00* CFM
Posttest Leak Check @ *10* "Hg for *0.00* CFM

[illegible]



Client: Mercedes, Back

Hel. Box No.: 5722

Barometric Pressure: 30.12

Location: Marshall's IL

Cold Box No.: 5722

Block Diameter, in: 4.5

Source ID: NORTH PRYER

Console No.: 5722

Nozzle Diameter, in: .30

Project No.: 0894-8885

Plot No.:

Filter No.: 94026

Date: 8-30-94

Plot Coefficient: .84

Ambient Temp.: 65

Run Number: 1

DQMC Factor: 1.002

Static Pressure: -.12

Operator: JTS

Meter a/Hg: 1.887

K Factor: 7.27

Port and Traverse Point No.	Sample Time	Gas Meter Reading	Velocity Head (ftH ₂ O)		Orifice Pressure Difference (ftH ₂ O)		Stack Gas Temperature (°F)		Sample Train Temperature (°F)		Vacuum (ftH ₂ O)	
			XP	VAP	Calc	Actual			Probe	Filter Box	Impinger	By Gas Meter
1 (E)	0	489.166	.67	0.8185	4.8209	4.9	110		250	250	62	66
2	2.5	493.020	.56	0.7483	4.0712	4.1	112		250	249	52	66
3	5.0	495.020	.50	0.7071	3.635	3.6	113		250	248	52	66
4	7.5	497.120	.37	0.6083	2.6899	2.7	113		250	250	56	66
5	10.0	499.320	.31	0.5568	2.2537	2.2	113		250	250	60	66
6	12.5	501.390	.20	0.4472	1.454	1.4	114		250	250	61	67
7	15.0	502.900	.15	0.3880	1.0905	1.1	114		250	250	61	67
8	17.5	504.370	.25	0.5000	1.8175	1.8	114		250	250	60	70
9	20.0	506.300	.40	0.6324	2.908	2.9	114		250	250	60	72
10	22.5	508.220	.40	0.6324	2.908	2.9	114		250	253	60	74
11 *	25.0	510.220	.41	0.6403	3.0176	3.0	114		250	250	61	75
12	27.5	512.820	.40	0.6324	2.908	2.9	114		251	250	61	77
13 (N)	30.0	514.757	.32	0.5657	2.3552	2.3	109		250	248	61	77
14	32.5	516.7	.32	0.5657	2.3552	2.3	111		251	249	62	75
15	35.0	518.900	.33	0.5844	2.4208	2.4	111		250	248	63	74
16	37.5	520.750	.42	0.6481	3.0912	3.1	113		250	250	63	74
Total/Avg.												

28.0123

COMMENTS:

Start 0937

Stop 1040

* Change K-Factor 7.36

Pretest Leak Check @ 15" Hg for 0.000 CFM

Posttest Leak Check @ 15" Hg for 0.000 CFM

Fluo Gas Analysis

Tidal	O ₂	CO ₂	CO	H ₂
1	20.3	0.32		
2	20.3	0.32		
3	20.3	0.32		
Avg				

Weight

Initial

Weights

Total Condensate

Weight

Initial

Weights

Total Condensate

Gained

Initial

Weights

Total Condensate

Gained

Initial

Weights

Total Condensate

Gained

Initial

Weights

Total Condensate

Gained

Initial

Weights

Total Condensate

Gained

Initial

Weights

Total Condensate

Gained

Initial

Weights

Total Condensate

Gained

Initial

Weights

Total Condensate



Client: <u>MARSHALLS BAKERY</u>	Hot Box No.: <u>572.2</u>	Standard Pressure: <u>30.12</u>
Location: <u>MARSHALLS</u>	Cold Box No.: <u>572.2</u>	Block Diameter, in: <u>45</u>
Source I.D.: <u>NORTH DAVEN</u>	Console No.: <u>572.2</u>	Nozzle Diameter, in: <u>30</u>
Project No.: <u>0844-8885</u>	Pilot No.: <u></u>	Filter No.: <u>970128</u>
Date: <u>8-30-74</u>	Pilot Coefficient: <u>.84</u>	Ambient Temp.: <u>63</u>
Run Number: <u>2</u>	DDMC Factor: <u>1.022</u>	Static Pressure: <u>-12</u>
Operator: <u>JS</u>	Meter # HD: <u>1.887</u>	K Factor: <u>7.58</u>

Port and Traverse Point No.	Sample Time	Dry Gas Meter Reading	Velocity Head (H ₂ O)		Orifice Pressure Differential (H ₂ O)		Stack Gas Temperature (°F)	Sample Train Temperature (°F)		Vacuum (in Hg)	
			V.H.		O.P.			Probe	Temp.		
			P	VP	Gage	Actual			Filter Box		Impinger
1 (N)	0	548.537	.37	0.6093	2.8046	2.8	112	250	62	78	2
2	2.5	550.780	.39	0.6246	2.9562	2.7	112	250	46	76	2
3	5.0	553.300	.43	0.6357	3.2591	3.2	105	250	45	76	2
4	7.5	555.920	.47	0.6856	3.5626	3.6	103	250	45	76	2
5	10.0	557.900	.47	0.6856	3.5626	3.6	102	250	48	76	2
6	12.5	560.102	.30	0.5477	2.2741	2.3	102	250	49	77	2
7	15.0	562.400	.15	0.3873	1.137	1.1	103	250	49	77	2
8	17.5	564.990	.15	0.3873	1.137	1.1	103	250	50	78	2
9	20.0	566.320	.22	0.4690	1.6676	1.7	103	250	52	78	2
10	22.5	567.990	.22	0.4690	1.6676	1.7	102	250	54	77	2
11	25.0	569.480	.25	0.5000	1.895	1.7	102	250	54	77	2
12	27.5	571.920	.27	0.5196	2.0466	2.0	102	250	56	78	2
13 (E)	30.0	573.445	.65	0.8062	4.927	4.9	103	250	57	78	2
14	32.5	576.780	.54	0.7348	4.032	4.1	102	250	58	79	2
15	35.0	579.420	.45	0.6708	3.411	3.4	103	251	59	78	2
16	37.5	581.720	.44	0.6633	3.3352	3.3	103	250	60	78	2
Total/Avg											

Fluo Gas Analysis				
Final Weights	Initial Weights	Weight Gained		
First Impinger	100	0	O ₂	N ₂
Second Impinger	142	42	20.42	0.28
Third Impinger	118	18	20.42	0.28
Static Gas	277	250	20.42	0.28
89		Total Condensate		

COMMENTS:
Start 1133
Stop 1236

Pretest Leak Check @ 15" Hg for 0.000 CFM
Posttest Leak Check @ 15" Hg for 0.000 CFM



Client: Marselles Brick	Hot Box No.: ST-2	Atmospheric Pressure: 30.12
Location: Marselles Brick	Cold Box No.: ST-2	Stack Diameter, in: 45
Source ID: U02TH DNER	Console No.: 5166	Nozzle Diameter, in: .30
Project No.: 0894-8005	Pilot No.: 	Filter No.: 9/10/28
Date: 8-30-94	Pilot Coefficient: .84	Ambient Temp.: 72
Run Number: 3	DDMG Factor: 1.002	Static Pressure: -.12
Operator: STS	Meter & Hg: 1887	K Factor: 7.66

Port and Traveled Pointing	Sample Time	Dry Gas Meter Reading	Velocity Head (ft/H ₂ O)		Orifice Pressure Differential (ft/H ₂ O)		Stack Gas Temperature (°F)		Sample Train Temperature (°F)		Valving (H ₂ O)	
			P	V	Calc.	Actual	Temp.	Temp.	Probe	Filter Box	Impinger	Impinger
1 (E)	0	608.880	.63	0.737	4.8258	4.8	100	100	250	251	61	76
2	2.5	611.580	.45	0.6208	3.447	3.4	100	100	250	250	52	76
3	5.0	613.448	.47	0.6457	3.6002	3.6	101	101	250	250	51	77
4	7.5	615.620	.40	0.6324	3.064	3.1	99	99	250	250	52	78
5	10.0	617.850	.30	0.5477	2.298	2.3	98	98	250	251	52	77
6	12.5	619.240	.30	0.5477	2.298	2.3	103	103	250	251	53	77
7	15.0	622.620	.32	0.5657	2.4512	2.4	103	103	250	251	54	78
8	17.5	624.250	.27	0.5196	2.0682	2.1	103	103	250	251	55	78
9	20.0	627.240	.25	0.5000	1.915	1.9	103	103	250	250	56	78
10	22.5	628.250	.27	0.5196	2.4512	2.4	103	103	250	251	57	78
11	25.0	630.421	.37	0.6083	2.8342	2.8	104	104	251	250	58	79
12	27.5	632.207	.37	0.6083	2.8342	2.8	103	103	251	250	59	79
13	30.0	634.528	.34	0.5831	2.6044	2.6	99	99	250	250	60	78
14	32.5	636.710	.37	0.6083	2.8342	2.8	102	102	250	251	60	78
15	35.0	639.340	.38	0.6164	2.9108	2.9	102	102	250	250	60	79
16	37.5	641.120	.43	0.6557	3.2958	3.3	103	103	250	250	60	80
Total/Avg												

28.2194 Fluo Gas Analysis				
Tral	O ₂	CO ₂	CO	N ₂
1	20.45	4.0		
2	20.45	4.0		
3	20.45	4.0		
Avg				

28.2194 Fluo Gas Analysis			
Final Weights	Initial Weights	Weight Gained	
First Impinger	100	0	
Second Impinger	100	43	
Third Impinger	100	19	
Static Oil	275.7	25.7	
Total/Avg	275.7	25.7	

COMMENTS:

Start 1311

Stop 1417

Pretest Leak Check 0 12 "Hg for 0.000 CFM

Posttest Leak Check 0 "Hg for CFM

Port and Traverse Point No.	Sample Time	Dry Gas Meter Reading	Velocity Head (ft/d)		Orifice Pressure Difference (H ₂ O)		Suck Gas Temperature (°F)	Sample Train Temperatures (°F)			Vacuum (Hg)
			P	VAP	Calc	Actual		Probe	Filler Box	Last Impinger	
17	40.0	643.240	.45	0.6108	3.447	3.4	103	250	62	80	2
18	42.5	646.100	.47	0.6855	3.602	3.6	103	251	62	80	2
19	45.0	648.250	.32	0.5657	2.4512	2.4	103	250	60	80	2
20	47.5	650.440	.30	0.5477	2.298	2.3	104	250	61	80	2
21	50.0	652.630	.15	0.3873	1.149	1.1	104	250	60	77	2
22	52.5	654.270	.19	0.4359	1.4554	1.4	104	251	60	78	2
23	55.0	655.720	.25	0.5000	1.915	1.9	104	250	59	79	2
24	57.5	657.400	.26	0.5099	1.976	2.0	104	251	60	78	2
	60.0	659.159									
			</								



Client: *Marcellus Brick*
Location: *Marcellus Brick*
Source ID: *NO2TH DNER*
Project No.: *0894-8885*
Date: *8-30-94*
Run Number: *3*
Operator: *STS*

Hot Box No.: *5722*
Cold Box No.: *5722*
Console No.: *5110*
Plot No.:
Plot Coefficient: *-84*
DQMC Factor: *1.002*
Meter a No.: *1887*

Atmospheric Pressure: *30.12*
Stack Diameter, in: *4.5*
Nozzle Diameter, in: *.30*
Pitot No.: *910/28*
Ambient Temp.: *72*
Static Pressure: *-1.12*
K Factor: *7.66*

Port and Traverse Point No.	Sample Time	Dry Gas Meter Reading	Velocity Head (ft)		Orifice Pressure Differential (in H ₂ O)		Stack Gas Temperature (°F)		Sample Train Temperatures (°F)		Vacuum (in Hg)
			P	V	Calc	Actual	Temp	Probe	Filter Box	Impinger	
1 (E)	0	602.880	.63	0.737	4.8258	4.8	100	250	251	61	76 2
2	2.5	611.580	.45	0.6208	3.447	3.4	100	250	250	52	76 2
3	5.0	613.448	.47	0.6457	3.6002	3.6	101	250	250	51	77 2
4	7.5	615.620	.40	0.6324	3.064	3.1	99	250	250	52	78 2
5	10.0	617.850	.30	0.5477	2.298	2.2	98	250	251	52	77 2
6	12.5	619.240	.30	0.5477	2.298	2.3	103	250	251	53	77 2
7	15.0	622.620	.32	0.5657	2.4512	2.4	103	250	251	54	78 2
8	17.5	624.250	.27	0.5196	2.0682	2.1	103	250	251	55	78 2
9	20.0	627.240	.25	0.5000	1.915	1.9	103	250	250	56	78 2
10	22.5	628.250	.27	0.5196	2.0682	2.1	103	250	251	57	78 2
11	25.0	630.421	.37	0.6083	2.8342	2.8	104	251	250	58	79 2
12	27.5	632.207	.37	0.6083	2.8342	2.8	103	251	250	59	79 2
13	30.0	634.528	.34	0.5831	2.6044	2.6	99	250	250	60	78 2
14	32.5	636.770	.37	0.6083	2.8342	2.8	102	250	251	60	78 2
15	35.0	639.340	.38	0.6164	2.9108	2.9	102	250	250	60	79 2
16	37.5	641.120	.43	0.6557	3.2938	3.3	103	250	250	60	80 2
Total/Avg											

Flue Gas Analysis					
28.2194					
	O ₂	CO ₂	CO	N ₂	
1	20.45	40			
2	20.45	40			
3	20.45	40			
Avg					

Final Weights	Initial Weights	Weight Gained
101	100	0
143	100	43
119	100	19
275.7	250	25.7
Total Condensate		

COMMENTS:

Start 1311

Stop 1417

Pretest Leak Check @ 12 "Hg for 60.000 CFM

Posttest Leak Check @ "Hg for CFM

Portland Traverse Point No.	Sample Time	Dry Gas Meter Reading	Velocity Head (H ₂ O)		Orifice Pressure Difference (H ₂ O)		Suction Pressure (PS)	Sample Train Temperatures (°F)			Vacuum (Hg)	
			SP	VP	Orifice	Actual		Probe	Filter Box	Gas Impinger		Dry Gas Meter
17	40.0	583.620	.35	0.5916	2.653	2.6	103	251	250	62	77	2
18	42.5	585.920	.20	0.4472	1.516	1.5	103	250	251	62	78	2
19	45.0	588.120	.18	0.4243	1.3644	1.4	103	250	250	63	78	2
20	47.5	589.720	.20	0.4472	1.516	1.5	103	251	251	63	78	2
21	50.0	591.230	.25	0.5000	1.895	1.9	103	251	250	64	78	2
22	52.5	593.100	.35	0.5916	2.653	2.6	103	251	250	64	79	2
23	55.0	595.000	.38	0.5916	2.653	2.6	103	251	250	64	78	2
24	57.5	597.720	.11	0.3317	0.838	0.83	101	250	251	64	78	2
60.0		598.745										
										</		



Client: *Massey's Brick*
Location: *Marysville, IL*
Source ID: *South Dyer*
Project No.: *0004-8885*
Date: *8-30-94*
Run Number: *1*
Operator: *JTS*

Hot Box No.: *5727*
Cold Box No.: *5722*
Console No.: *5722*
Pilot No.:
Pilot Coefficient: *.84*
DOMC Factor: *1.002*
Meter a Hot: *1.887*
Barometric Pressure: *30.06*
Stack Diameter, in: *45*
Nozzle Diameter, in: *.30*
Fiter No.: *940129*
Ambient Temp.: *70*
Static Pressure: *-.22*
K Factor: *7.73*

Port and Traveler Position	Sample Time	Dry Gas Meter Reading	Velocity Head (ft/H ₂ O)		Orifice Diameter (in)		Stack Gas Temperature (°F)		Sample Temperature (°F)		Dry Volume (ft ³ /Hr)	
			AP	VP	Calc	Actual	Probe	Filter Box	Impinger	Dry Gas	Water	Volume (ft ³ /Hr)
1 IN1	0	668.141	.45	0.6708	3.4785	3.5	250	252	61	73	3	3
2	2.5	669.970	.45	0.6708	3.4785	3.5	250	250	52	73	3	3
3	5.0	670.250	.41	0.6708	3.1613	3.2	250	250	50	73	3	3
4	7.5	674.120	.32	0.5657	2.9736	2.5	251	249	51	74	3	3
5	10.0	676.521	.32	0.5657	2.9736	2.5	251	250	52	74	3	3
6	12.5	678.040	.28	0.5291	2.1644	2.2	251	249	53	74	3	3
7	15.0	680.120	.12	0.3464	0.9276	0.93	250	250	54	74	3	3
8	17.5	682.120	.39	0.6245	3.0147	3.0	251	248	55	74	3	3
9	20.0	684.230	.51	0.7141	3.9423	3.9	251	250	56	74	3	3
10	22.5	686.350	.51	0.7141	3.9423	3.9	250	250	57	74	3	3
11	25.0	689.430	.55	0.7416	4.2515	4.2	250	250	58	74	3	3
12	27.5	692.020	.50	0.7071	3.865	3.9	250	250	59	74	3	3
13 *	30.0	695.000	.26	0.5099	1.9942	2.0	250	250	59	74	3	3
14	32.5	696.850	.28	0.5291	2.1476	2.1	250	250	59	74	2	2
15	35.0	698.370	.21	0.4582	1.6107	1.6	250	250	60	75	2	2
16	37.5	700.650	.24	0.4899	1.8408	1.8	250	250	60	77	2	2
Total/Avg												

COMMENTS:

Start 1520

Stop 1623

* Change K-Factor - 7.67

Pretest Leak Check @ 15 "Hg for 0.000 CFM

Posttest Leak Check @ 15 "Hg for 0.000 CFM

Flue Gas Analysis

Total	O ₂	CO ₂	CO	H ₂
1	20.38	.30		
2	20.38	.30		
3	20.38	.30		
Avg				

Weight Gained

Final Weights	Initial Weights	Weight Gained
100	100	0
145	100	45
128	100	28
273.5	250	23.5
Total/Avg		



Client: <i>Mazatlan Brick</i>	Hot Box No: <i>5722</i>	Humidity Pressure: <i>30.06</i>
Location: <i>Marsailles 1C</i>	Cold Box No: <i>5722</i>	Stack Diameter, in: <i>45</i>
Source ID: <i>SOUTH DRYER</i>	Console No: <i>5722</i>	Nozzle Diameter, in: <i>.30</i>
Project No: <i>0894-8885</i>	Pilot No: <i></i>	Filter No: <i>940130</i>
Date: <i>8-30-94</i>	Pilot Coefficient: <i>.84</i>	Ambient Temp: <i>72</i>
Run Number: <i>2</i>	DMC Factor: <i>1.002</i>	Static Pressure: <i>-.22</i>
Operator: <i>JTS</i>	Water a HQ: <i>1.887</i>	K Factor: <i>7.74</i>

Port and Traversing Point No.	Sample Time	Dry Gas Meter Reading	Velocity Head (H ₂ O)		Orifice Pressure Differential (H ₂ O)		Stack Gas Temperature (°F)	Sampling Temperatures (°F)			Vacuum (H ₂ O)	
			AP	VP	Calc	Actual		Probe	Filter Box	Gas Impinger		Dry Gas Impinger
1 (E)	0	726.747	.31	0.5568	2.3994	2.4	104	250	250	63	78	3
2	2.5	729.050	.30	0.5477	2.322	2.3	100	251	251	50	74	3
3	5.0	730.900	.25	0.5000	1.935	1.9	100	251	251	51	75	3
4	7.5	732.520	.21	0.4582	1.6254	1.6	101	251	251	52	76	3
5	10.0	734.720	.15	0.3873	1.161	1.2	101	251	251	53	77	3
6	12.5	735.990	.12	0.3464	0.9288	.93	102	251	251	54	77	3
7	15.0	737.250	.12	0.3464	0.9288	.93	102	251	251	55	78	3
8	17.5	738.720	.12	0.3464	0.9288	.93	102	250	250	55	78	3
9	20.0	740.120	.15	0.3873	1.161	1.2	102	250	251	56	79	3
10	22.5	741.420	.25	0.5000	1.935	1.9	100	250	250	56	79	2
11	25.0	743.200	.28	0.5291	2.1672	2.2	103	251	250	57	80	2
12	27.5	745.280	.28	0.5291	2.1672	2.2	103	250	250	57	80	2
13	30.0	747.164	.39	0.6245	3.0186	3.0	103	250	250	56	79	2
14	32.5	749.550	.37	0.5477	2.8638	2.9	103	249	250	57	80	2
15	35.0	751.020	.40	0.6324	3.096	3.1	103	250	250	58	81	2
16	37.5	753.920	.30	0.5477	2.322	2.3	103	250	250	59	80	
Total/Avg												

COMMENTS:

Start 1733

Stop 1838

Flue Gas Analysis

Total	O ₂	CO ₂	CO	H ₂
1	20.43	0.4		
2	11	11		
3	11	11		
Avg				

Weight Gained

Final Weights	Initial Weights	Weight Gained
100	100	0
144	100	44
122	100	22
273.7	250	23.7
87.7	Total Condensate	

Pretest Leak Check @ 15" Hg for 0.000 CFM

Posttest Leak Check @ 15" Hg for 0.000 CFM



Client: <u>Worcestershire</u>	Hot Box No.: <u>5723</u>	Barometric Pressure: <u>30.06</u>
Location: <u>Worcestershire</u>	Cold Box No.: <u>5723</u>	Sick Diameter, in: <u>45</u>
Source ID: <u>SOUTH DEVER</u>	Console No.: <u>5723</u>	Nozzle Diameter, in: <u>.30</u>
Project No.: <u>0891-8885</u>	Pilot No.: <u></u>	Filter No.: <u>910151</u>
Date: <u>8-30-94</u>	Pilot Coefficient: <u>.84</u>	Ambient Temp.: <u>72</u>
Run Number: <u>3</u>	DOHC Factor: <u>1.002</u>	Static Pressure: <u>-.22</u>
Operator: <u>JTS</u>	Meter & Hg: <u>1.887</u>	K Factor: <u>7.80</u>

Portland Traverse Point No.	Sample Time	Dry Gas Meter Reading	Velocity Head (H ₂ O)		Orifice Pressure Difference (H ₂ O)		Stack Gas Temperature (°F)	Sample Train Temperatures (°F)		Filter Box	Dry Impinger Gas Meter	Vacuum (H ₂ O)
			W.P.	V.P.	Gate	Actual		Probe	Exhaust Manifold			
	0	785.615	.41	0.6403	3.198	3.2	102	250	251	52	82	2
	2.5	787.251	.41	0.6403	3.198	3.2	102	250	250	53	83	2
	5.0	790.300	.38	0.664	2.964	3.0	103	250	250	54	83	3
	7.5	793.250	.38	0.664	2.964	3.0	104	250	251	55	84	3
	10.0	795.320	.15	0.3813	1.170	1.2	104	250	250	56	85	3
	12.5	796.970	.13	0.3605	1.011	1.0	104	250	251	56	84	3
	15.0	798.720	.11	0.3317	0.858	0.86	104	251	250	57	84	3
	17.5	799.620	.49	0.7000	3.822	3.8	105	251	251	57	83	3
	20.0	802.320	.47	0.6324	3.666	3.7	105	251	251	58	84	3
	22.5	805.021	.51	0.7141	3.978	4.0	105	250	250	59	84	3
	25.0	807.030	.56	0.7483	4.368	4.4	105	250	250	60	85	3
	27.5	810.720	.53	0.7280	4.134	4.1	105	250	251	60	84	3
	30.0	812.853	.25	0.5000	1.95	2.0	105	250	250	61	85	3
	32.5	814.520	.20	0.4472	1.56	1.6	105	251	251	60	84	3
	35.0	816.270	.20	0.4472	1.56	1.6	105	251	251	60	82	3
	37.0	818.510	.15	0.3873	1.17	1.2	105	251	252	60	82	3
Total/Avg												

COMMENTS:

Start 1856

Stop 1958

Flue Gas Analysis

Total	O ₂	CO ₂	CO	H ₂
1	20.5	0.3		
2	20.3	0.3		
3	29.3	0.3		
Avg				

Weight

Initial

Final

Weights

Gained

First Impinger	147.0	100	0	
Second Impinger	121.147	100	47	
Third Impinger	121	100	21	
Since Oct	270.2	250.91	20.3	
Total Condensate	58.2			

Pretest Leak Check @ 15 "Hg for 0.000 CFM

Posttest Leak Check @ 15 "Hg for 0.000 CFM

[illegible]

CONTINUOUS EMISSIONS MONITORING DATA SHEET

 PLANT MARSEILLES BRICK

 DATE 8-29-94

 SOURCE KILN

 RUN # 1A

TIME	NOX (ppm-dry)	CO (ppm-dry)	SO2 (ppm-dry)	CO2 % (ppm-dry)	O2 % (ppm-dry)	VOC (ppm-dry)	OTHER (ppm-dry)
1 1048	12	131	500	2.2	16.6	7	
2 1049	15	134	500	2.0	17.1	7	
3 1050	10	133	500	2.1	16.8	7	
4 1051	10 15	133	505	1.8	17.3	7	
5 1052	10	136	410	1.9	16.8	9	
6 1053	4	78	490	0.8	19.1	9	
7 1054	17	154	495	1.8	17.7	7	
8 1055	22	127	490	2.6	16.2	7	
9 1056	14	122	495	2.3	16.4	7	
10 1057	15	125	500	2.3	16.6	7	
11 1058	22	125	500	2.5	16.3	7	
12 1059	17	124	505	2.4	16.3	7	
13 1100	15	124	505	2.4	16.2	7	
14 1101	20	128	505	2.1	16.9	7	
15 1102	18	124	505	2.6	16.0	7	
16 1103	17	127	510	2.1	16.7	7	
17 1104	22	124	510	2.9	15.6	7	
18 1105	20	128	515	2.1	16.7	7	
19 1106	16	126	520	2.5	16.2	7	
20 1107	24	129	520	2.5	16.2	7	
21 1108	18	124	525	2.4	16.1	7	
22 1109	14	120	525	2.3	16.0	7	Port Change
23 1112	22	131	525	2.3	16.5	7	
24 1113	20	135	525	2.4	16.7	7	
25 1114	22	131	525	2.3	16.5	7	
26 1115	25	135	530	2.4	16.4	7	
27 1116	17	135	535	2.0	16.9	7	
28 1117	30	137	530	2.3	16.8	7	
29 1118	23	136	540	1.9	17.2	7	
30 1119	21	136	535	2.6	16.3	7	
AVERAGE							

 continued
on Run # 1B

1 minute averages

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT Marseilles Brick

DATE 8-29-94

SOURCE KILN

RUN # 1B

TIME	NOX (ppm-dry)	CO (ppm-dry)	SO2 (ppm-dry)	CO2 % (ppm-dry)	O2 % (ppm-dry)	VOC (ppm-dry)	OTHER (ppm-dry)
1 1120	18	138	535	2.0	17.0	7	
2 1121	13	138	535	2.2	16.9	7	
3 1122	10	138	535	2.1	17.0	7	
4 1123	20	141	530	2.2	17.1	7	
5 1124	7	139	440	1.4	17.6	8	
6 1125	5	86	515	0.6	19.4	7	
7 1126	17	144	515	1.9	17.8	7	
8 1127	13	128	515	2.5	16.4	7	
9 1128	12	126	515	2.3	16.5	7	
10 1129	10	126	515	2.3	16.5	7	
11 1130	25	130	520	2.5	16.5	7	
12 1131	15	130	520	2.1	16.8	7	
13 1132	15	130	520	2.5	16.5	7	
14 1134	17	128	520	2.7	16.2	7	Port Change
15 1135	14	129	525	2.2	16.5	7	
16 1136	15	130	535	2.4	16.5	7	
17 1137	18	133	540	2.3	16.7	6	
18 1138	13	129	535	2.5	16.2	6	
19 1139	16	133	535	2.3	16.9	6	
20 1140	17	131	530	2.3	16.5	6	
21 1141	22	135	535	2.4	16.7	6	
22 1142	12	133	535	2.2	16.9	6	
23 1143	15	134	540	2.4	16.5	6	
24 1144	14	134	540	2.4	16.6	6	
25 1145	13	135	540	2.2	16.8	6	
26 1146	23	136	545	2.2	16.9	6	
27 1147	13	133	545	2.3	16.7	6	
28 1148	15	136	545	2.2	16.7	6	
29 1149	17	136	550	2.2	16.8	6	
30 1150	12	135	545	2.2	16.8	6	
AVERAGE	16.383	130.000	518.000	2.213	16.733	7.8	

1 MINUTE AVERAGES

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT MARSHALLS BRICK

DATE 8-29-84

SOURCE KILN

RUN # 2A

TIME	NOX _x (ppm dry)	CO (ppm dry)	SO ₂ (ppm dry)	CO ₂ % (ppm dry)	O ₂ % (ppm dry)	VOC (ppm dry)	OTHER (ppm dry)
1 1250	20	131	520	2.1	17.9	7	
2 1251	13	130	530	2.3	18.1	7	
3 1252	25	132	540	2.1	18.7	6	
4 1253	11	130	550	1.9	18.7	6	
5 1254	12	127	550	2.1	18.1	6	
6 1255	13	134	560	1.7	19.0	6	
7 1256	14	131	555	2.5	18.0	7	
8 1257	22	133	555	2.2	18.7	7	
9 1258	14	130	555	2.3	18.2	7	
10 1259	18	133	560	2.2	18.6	6	
11 1300	10	127	470	1.4	18.9	7	
12 1301	5	82	545	0.7	20.8	9	
13 1302	18	132	550	1.8	19.4	7	
14 1303	23	126	550	2.6	18.1	6	
15 1304	14	121	555	2.3	17.9	6	
16 1305	21	124	560	2.7	17.8	6	
17 1306	14	118	555	2.5	17.5	6	
18 1307	27	124	555	2.6	18.0	6	
19 1308	14	123	555	2.1	18.4	5	
20 1309	17	124	560	2.7	17.9	6	↑
21 1312	16	126	560	2.2	18.5	6	Perf ←
22 1313	15	125	550	2.5	17.9	6	Change
23 1314	18	127	555	2.4	18.2	6	
24 1315	16	125	550	2.5	17.8	6	
25 1316	18	126	550	2.4	18.2	6	
26 1317	14	125	545	2.4	18.1	6	
27 1318	13	126	545	2.2	18.1	6	
28 1319	23	128	540	2.3	18.3	6	
29 1320	15	127	540	2.3	18.3	6	
30 1321	14	127	540	2.2	18.3	6	
AVERAGE							

→ CONTINUED ON
Run # 2B

1 minute averages

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT Marsailles Brick

DATE 8-29-94

SOURCE KILN

RUN # 28

TIME	NOX (ppm dry)	CO (ppm dry)	SO2 (ppm dry)	CO2 % (ppm dry)	O2 % (ppm dry)	VOC (ppm dry)	OTHER (ppm dry)
1 1322	20	129	535	2.3	18.3	6	
2 1323	15	130	530	2.2	18.5	6	
3 1324	15	131	535	2.0	18.8	6	
4 1325	16	129	530	2.4	18.0	6	
5 1326	15	131	535	2.1	18.7	6	
6 1327	14	131	530	2.1	18.5	6	
7 1328	15	132	525	2.3	18.4	6	
8 1329	13	132	525	1.8	19.1	6	
9 1330	12	133	525	2.1	18.6	6	
10 1331	18	132	530	2.1	18.6	6	
11 1332	6	128	445	1.3	19.0	8	PORT
12 1333	14	152	515	2.0	19.4	6	Change
13 1333	16	118	515	2.4	17.9	6	
14 1336	14	118	515	2.4	17.9	6	
15 1337	16	119	515	2.4	18.0	6	
16 1338	18	120	520	2.6	17.8	6	
17 1339	15	117	520	2.4	17.8	6	
18 1340	16	119	525	2.5	17.9	6	
19 1341	15	124	530	2.2	18.5	6	
20 1342	13	124	535	2.4	18.3	6	
21 1343	15	122	530	2.5	17.7	6	
22 1344	15	123	535	2.3	18.1	6	
23 1345	17	123	535	2.4	17.9	6	
24 1346	13	122	540	2.3	17.9	6	
25 1347	17	126	545	2.2	18.5	6	
26 1348	14	122	545	2.5	17.8	6	
27 1349	18	125	550	2.4	18.1	6	
28 1350	14	123	550	2.4	17.8	6	
29 1351	19	125	550	2.4	18.0	6	
30 1352	13	124	555	2.2	18.0	6	
AVERAGE	15.63	125.97	537.76	2.23	18.303	6.1	

1 minute averages

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

 PLANT MARSEILLES BRICK

 DATE 8-29-84

 SOURCE KILN

 RUN # 3A

TIME	NOX (ppm dry)	CO (ppm dry)	SO2 (ppm dry)	CO2 % (ppm dry)	O2 % (ppm dry)	VOC (ppm dry)	OTHER (ppm dry)
1 1451	11	139	425	2.5	17.2	6	
2 1452	9	139	445	2.5	16.9	6	
3 1453	8	142	455	2.4	16.8	6	
4 1454	6	140	465	2.5	16.8	6	
5 1455	8	141	470	2.5	16.8	6	
6 1456	8	141	480	2.4	17.3	6	
7 1457	9	144	480	2.4	17.4	6	
8 1458	8	143	485	2.4	16.8	6	
9 1459	12	142	485	2.5	16.8	6	
10 1500	5	142	495	2.4	17.3	6	
11 1501	5	146	495	2.3	17.5	6	
12 1502	7	145	495	2.2	17.3	6	
13 1503	7	146	495	2.2	17.1	6	
14 1504	5	147	495	2.1	17.3	6	
15 1505	5	146	495	2.2	17.2	6	
16 1506	9	147	490	2.1	17.1	6	
17 1507	6	148	490	2.1	17.4	6	
18 1508	3	110	440	1.9	18.6	8	
19 1509	2	98	470	1.6	19.1	6	
20 1510	10	150	470	1.6	17.7	6	
21 1511	8	137	470	1.8	17.0	6	Port
22 1514	8	132	470	2.4	16.7	6	change
23 1515	8	135	475	2.4	16.4	6	
24 1516	8	133	470	2.5	16.1	6	
25 1517	6	132	470	2.5	16.2	6	
26 1518	8	135	475	2.5	16.6	6	
27 1519	6	135	475	2.5	16.4	6	
28 1520	8	138	480	2.4	17.0	6	
29 1521	9	137	480	2.4	16.4	6	
30 1522	5	133	480	2.5	16.2	6	
AVERAGE							

 CONTINUED
ON RUN #3B

1 minute average

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT MARSEILLES BRICK

DATE 8-29-94

SOURCE KILN

RUN # 3B

TIME	NOX (ppm-dry)	CO (ppm-dry)	SO2 (ppm-dry)	CO2 % (ppm-dry)	O2 % (ppm-dry)	VOC (ppm-dry)	OTHER (ppm-dry)
1 1523	9	137	480	2.4	16.8	6	
2 1524	10	138	485	2.4	16.9	6	
3 1525	7	137	480	2.4	16.3	6	
4 1526	6	137	480	2.5	16.4	6	
5 1527	5	138	480	2.4	16.6	6	
6 1528	7	139	485	2.3	16.8	6	
7 1529	6	141	485	2.3	16.5	6	
8 1530	5	141	485	2.3	16.6	6	
9 1531	5	141	490	2.3	16.9	6	
10 1532	10	141	490	2.3	16.6	6	
11 1533	6	140	490	2.3	16.7	6	
12 1534	5	141	485	2.2	16.8	6	Port change
13 1535	4	142	485	2.2	16.7	6	
14 1538	4	143	480	2.1	17.0	6	
15 1539	12	147	480	2.0	16.9	6	
16 1540	3	129	410	2.2	17.1	8	
17 1541	1	85	460	1.6	18.7	7	
18 1542	10	151	460	1.5	17.5	6	
19 1543	11	134	460	1.9	16.2	6	
20 1544	7	130	460	2.1	16.2	6	
21 1545	6	132	460	2.3	16.4	6	
22 1546	8	133	460	2.3	16.4	6	
23 1547	8	131	460	2.3	16.3	6	
24 1548	9	133	460	2.4	16.3	6	
25 1549	8	134	460	2.4	16.2	6	
26 1550	10	135	465	2.4	16.0	6	
27 1551	7	133	470	2.4	16.2	6	
28 1552	12	136	490	2.4	16.1	6	
29 1553	8	132	470	2.5	15.7	6	
30 1554	7	133	465	2.5	16.0	6	
AVERAGE	7.25	136.816	473.57	2.27	16.385	6.2	

CO2 AND O2 CONCENTRATIONS ARE IN (%)

1 MINUTE AVERAGES

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT Marseilles Brick

DATE 8-30-94

SOURCE Dryer 1 (North)

RUN # 1

TIME	NOX (ppm-dry)	CO (ppm-dry)	SO2 (ppm-dry)	CO2 % (ppm-dry)	O2 % (ppm-dry)	VOC (ppm-dry)	OTHER (ppm-dry)
1 0937	0	3	0	0.4	20.1	1	
2	0	3	0	.4	20.1	1	
3	0	4	0	.4	20.1	0	
4	0	4	0	.4	20.1	0	
5	0	5	0	.4	20.1	0	
6	0	5	0	.3	20.2	0	
7	0	5	0	.3	20.2	0	
8	0	3	0	.3	20.3	0	
9	0	3	0	.3	20.4	0	
10	0	4	0	.3	20.5	0	
11	0	5	0	.3	20.5	0	
12	0	6	0	.3	20.6	0	
13	0	6	0	.3	20.5	0	
14	0	7	0	.3	20.4	0	
15	0	7	0	.3	20.4	2	
16	0	8	0	.3	20.3	2	
17	0	8	0	.3	20.3	1	
18	0	9	0	.3	20.3	1	
19	0	9	0	.3	20.2	5	
20 1040	0	9	0	0.3	20.2	18	
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
AVERAGE	0	5.50	0	0.32	20.13	7.350	

3 minute averages

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT MARSEILLES Brick

DATE 8-30-99

SOURCE Dryer 1 (North)

RUN # 2

TIME	NOX (ppm dry)	CO (ppm dry)	SO2 (ppm dry)	CO2 % (ppm dry)	O2 % (ppm dry)	VOC (ppm dry)	OTHER (ppm dry)
1 1133	0	14	0	0.2	20.4	0	
2	0	14	0	.2	20.4	0	
3	0	16	0	.2	20.4	0	
4	0	15	0	.2	20.4	0	
5	0	15	0	.2	20.4	0	
6	0	15	0	.2	20.4	0	
7	0	15	0	.2	20.4	0	
8	0	14	0	.2	20.4	0	
9	0	14	0	.2	20.4	0	
10	0	14	0	.2	20.4	0	
11	0	15	0	.2	20.4	0	
12	0	15	0	.2	20.4	0	
13	0	15	0	.2	20.4	0	
14	0	15	0	.2	20.4	0	
15	0	15	0	.2	20.4	0	
16	0	15	0	.3	20.4	0	
17	0	15	0	.3	20.5	0	
18	0	15	0	.3	20.5	0	
19	0	15	0	0.3	20.5	0	
20 1236	0	15	0	0.3	20.5	0	
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
AVERAGE	0	14.60	0	0.22	20.490	0	

3 minute averages

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT MARSHALLS BRICK

DATE 8-30-94

SOURCE Dryer 1 (North)

RUN # 3

TIME	NOX (ppm dry)	CO (ppm dry)	SO2 (ppm dry)	CO2 % (ppm dry)	O2 % (ppm dry)	VOC (ppm dry)	OTHER (ppm dry)
1 1311	0	4	0	0.4	20.4	0	—
2	0	4	0	.4	20.4	0	
3	0	4	0	.4	20.4	0	
4	0	4	0	.4	20.4	0	
5	0	4	0	.4	20.4	0	
6	0	4	0	.4	20.4	0	
7	0	4	0	.4	20.4	0	
8	0	4	0	.4	20.5	0	
9	0	5	0	.4	20.5	0	
10	0	5	0	.4	20.5	0	
11	0	5	0	.4	20.5	0	
12	0	5	0	.4	20.5	0	
13	0	5	0	.4	20.5	0	
14	0	5	0	.4	20.4	0	
15	0	5	0	.4	20.4	0	
16	0	7	0	.4	20.4	0	
17	0	8	0	.4	20.4	0	
18	0	8	0	.4	20.5	0	
19	0	9	0	.4	20.5	0	
20 1426	0	9	0	0.4	20.5	0	
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
AVERAGE	0	5.40	0	0.4	20.48	0	

3 MINUTE AVERAGES

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT Marseilles Brick

DATE 8-30-94

SOURCE Dryer 2 (South)

RUN # 1

TIME	NOX (ppm dry)	CO (ppm dry)	SO2 (ppm dry)	CO2 % (ppm dry)	O2 % (ppm dry)	VOC (ppm dry)	OTHER (ppm dry)
1 1520	0	4	0	0.3	20.2	0	
2	0	4	0	0.3	20.2	0	
3	0	4	0	.3	20.2	0	
4	0	4	0	.3	20.2	0	
5	0	4	0	.3	20.2	0	
6	0	4	0	.3	20.2	0	
7	0	5	0	.3	20.2	0	
8	0	5	0	.3	20.2	0	
9	0	5	0	.3	20.5	0	
10	0	5	0	.3	20.5	0	
11	0	5	0	.3	20.5	0	
12	0	5	0	.3	20.5	0	
13	0	5	0	.3	20.5	0	
14	0	5	0	.3	20.5	0	
15	0	5	0	.3	20.5	0	
16	0	5	0	.3	20.5	0	
17	0	5	0	.3	20.5	0	
18	0	5	0	.3	20.5	0	
19	0	5	0	.3	20.5	0	
20 1624	0	5	0	0.3	20.5	0	
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
AVERAGE	0	4.70	0	0.3	20.370	0	

3 minute Averages

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT MARSEILLES BRICK

DATE 8-30-94

SOURCE Dryer 2 (Crayth)

RUN # 2

TIME	NOX (ppm dry)	CO (ppm dry)	SO2 (ppm dry)	CO2 % (ppm dry)	O2 % (ppm dry)	VOC (ppm dry)	OTHER (ppm dry)
1 1733	0	3	0	0.4	20.4	0	
2	0	3	0	.4	20.4	0	
3	0	3	0	.4	20.4	0	
4	0	3	0	.4	20.4	0	
5	0	3	0	.4	20.4	0	
6	0	3	0	.4	20.4	0	
7	0	3	0	.4	20.4	0	
8	0	3	0	.4	20.4	0	
9	0	3	0	.4	20.4	0	
10	0	3	0	.4	20.4	0	
11	0	3	0	.4	20.4	0	
12	0	3	0	.4	20.4	0	
13	0	3	0	.4	20.4	0	
14	0	3	0	.4	20.4	0	
15	0	3	0	.4	20.5	0	
16	0	3	0	.4	20.5	0	
17	0	3	0	.4	20.5	0	
18	0	3	0	.4	20.5	0	
19	0	3	0	.4	20.5	0	
20 1836	0	3	0	0.4	20.5	0	
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
AVERAGE	0	3	0	0.4	20.730	0	

3 minute AVERAGE

NOTES:

CONTINUOUS EMISSIONS MONITORING DATA SHEET

PLANT MAVSPILLES Brick

DATE 8-30-94

SOURCE Dryer 2 (South)

RUN # 3

TIME	NOX (ppm-dry)	CO (ppm-dry)	SO2 (ppm-dry)	CO2 % (ppm-dry)	O2 % (ppm-dry)	VOC (ppm-dry)	OTHER (ppm-dry)
1 1856	0	4	0	0.4	20.3	0	
2	0	4	0	.4	20.3	0	
3	0	4	0	.4	20.3	0	
4	0	4	0	.4	20.3	0	
5	0	4	0	.4	20.3	0	
6	0	4	0	.3	20.3	0	
7	0	4	0	.3	20.3	0	
8	0	4	0	.3	20.3	0	
9	0	5	0	.3	20.3	0	
10	0	5	0	.3	20.3	0	
11	0	5	0	.3	20.3	0	
12	0	5	0	.3	20.3	0	
13	0	6	0	.3	20.3	0	
14	0	6	0	.3	20.3	0	
15	0	6	0	.3	20.3	0	
16	0	6	0	.3	20.3	0	
17	0	6	0	.3	20.3	0	
18	0	6	0	.3	20.3	0	
19	0	6	0	0.4	20.3	0	
20 1959	0	6	0	0.4	20.3	0	
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
AVERAGE	0	5.0	0	0.335	20.3	0	

3 minute averages

NOTES:

APPENDIX D

Equipment Calibration Records



Dry Gas Meter and Orifice Calibration

Dry Gas Meter or Console Number STL2 Date 8-25-94
 Barometric Pressure(not corrected to sea level pressure), $P_b = 30.19$ in. Hg

ΔH	Dry Gas Meter					Wet Test Meter					Time ' & " min. θ	γ	$\Delta H @$	
	Volume, cu.ft.		Temp.		Press in.Hg P_m	Volume, cu.ft.		Temp.						
	Final	Init.	Δ	V_d		Δ	V_w	Δ	Δ					
	T_d	Δ	Δ	Δ		Δ	Δ	Δ						
.5	207.508	197.501	10.007	80	540	30.23	30.452	20.265	10.187	69	529	25.1	1.038	1.652
1.0	217.508	207.505	10.003	81	541	30.26	40.475	30.452	10.023	70	530	18.2	1.020	1.798
1.5	227.508	217.508	10.050	82	542	30.30	50.384	40.475	9.909	70	530	15.0	1.005	1.871
2.0	237.508	227.508	10.000	83	543	30.34	60.122	50.384	9.738	69	529	13.1	0.995	1.959
2.5	247.508	237.508	10.000	83	543	30.37	69.748	60.122	9.626	69	529	11.7	0.982	1.999
3.0	257.500	247.508	10.002	84	544	30.41	79.275	69.748	9.527	69	529	10.7	0.972	2.044
Average										1.002		1.887		
Signature <i>David M. [unclear]</i>														

Signature Daniel M. [Signature]

$$P_m = (\Delta H \div 13.6) + P_b$$


$$\Delta H @ = \left(\frac{T_w \theta}{V_w} \right)^2 \frac{0.0317 \Delta H}{P_b T_d}$$

$$\gamma = \frac{V_w P_b T_d}{V_d P_m T_w}$$

$$\Delta H @ = \left(\frac{T_w \theta}{V_w} \right)^2 \frac{0.0317 \Delta H}{P_b T_d}$$


γ is the ratio of accuracy of the wet test meter to the dry gas meter and its tolerance limits are ± 0.02 from 1.00.

$\Delta H @$ is the orifice differential pressure which gives an air flow rate of 0.75 cfm at 70°F and 29.92 inches of mercury. It had tolerance limits of ± 0.20 in. H₂O from 1.84.






TYPE 5 PITOT TUBE CALIBRATION

PITOT TUBE 5-155
DATE 4-11-94



Are a_1 and $a_2 < 10^\circ$? ☒ Yes ☐ No
Are B_1 and $B_2 < 5^\circ$? ☒ Yes ☐ No
Is $Z < 1/8$ inch? ☒ Yes ☐ No
Is $W < 1/32$ inch? ☒ Yes ☐ No



External tube diameter (D_c) .3705

Is D_c between $3/16$ and $3/8$ in.? ☒ Yes ☐ No

Base-to-opening plane distances:

P_A .401
 P_B .401

Does $P_A = P_B$? ☒ Yes ☐ No

Is $1.05 D_c \leq P \leq 1.50 D_c$?

.397 < .401 < .568

☒ Yes ☐ No

When pitot tube is part of an assembly:

Is the thermocouple 2 inches behind the pitot tube opening? ☒ Yes ☐ No

Does the pitot tube extend 3 inches beyond the compression fitting on the nozzle? ☒ Yes ☐ No

Is the distance between the nozzle and the pitot tube more than $3/4$ inch when a $1/4$ inch nozzle is in place? ☒ Yes ☐ No

If any answer is no, the pitot tube must be calibrated in a wind tunnel against a standard type pitot tube.

If all answers are yes, the pitot tube may be assigned a baseline coefficient of 0.84.

Assigned Baseline Coefficient 0.84

Signature Daniel M. [illegible]

STACK TEMPERATURE SENSOR CALIBRATION DATA FORM

Date 1-6-94 Thermocouple number 5-1

Ambient temperature 23.0 °C Barometric pressure 29.74 in. Hg

Calibrator D.M.C Reference: mercury-in-glass Fisher Scientific #15-041A
other _____

Reference point number	Source ^a (specify)	Reference thermometer temperature, °C	Thermocouple potentiometer temperature, °C	Temperature difference, % ^b
100°C	Water	100°C	97.78	0.006
0°C	Ice Water	0.000°C	0.000°C	0.000
—	Oil	219.44°C	219.44°C	0.000

^a Type of calibration system used.

^b
$$\left[\frac{(\text{ref temp, } ^\circ\text{C} + 273) - (\text{test thermom temp, } ^\circ\text{C} + 273)}{\text{ref temp, } ^\circ\text{C} + 273} \right] 100 \leq 1.5\%$$

METHOD 5: PROBE NOZZLE FIELD CALIBRATION DATA



Nozzle Identification Number: STL 3-10

Client: Marseilles Brick

Project No.: 0894-8885-2

Source: KILN

Date: 8-29-94

Analyst: RFF

Micrometer:

Scale:

Tolerance:

CALIBRATION DATA

Trial Number	Run	Run	Run	Run
1	0.368			
2	0.370			
3	0.370			
4	0.372			
5	0.370			
6				
7				
8				
9				
10				
AVERAGE	0.370			

Comments:

METHOD 5: PROBE NOZZLE FIELD CALIBRATION DATA



Nozzle Identification Number: *5+L 3-4*

Client: *Marseilles Brick*

Project No.: *0894-8885-2*

Source: *Dryer Stack*

Date: *8-30-94*

Analyst:

Micrometer:

Scale:

Tolerance:


CALIBRATION DATA

Trial Number	Run	Run	Run	Run
1	0.300			
2	0.299			
3	0.300			
4	0.300			
5	0.301			
6				
7				
8				
9				
10				
AVERAGE	0.300			


Comments:

APPENDIX E

Data Logger Strip Chart Recordings



12 - 0.0010
 06 - 0.494V
 05 - 0.001V
 04 - 0.001V
 03 - 0.278V
 01 - 0.005V
 2000 V/H




9-29-94


KLN STACK OUTLET

MAISELLES BRICK

OMEGA ENGINEERING INC. 3000 ZEEB RD. SUITE 100



12 8.05V
 06 0.036V
 05 0.004V
 04 0.004V
 03 0.011V
 01 -0.035V
 200 h/h
 Aug. 29 08:10



OMEGA ENGINEERING, INC. OMS500-ZFP

04 0.125V
 03 0.17V
 01 0.28V.6
 200mV
 Aug. 29 11:10

zero
 CO
 NO

300mV CO BIAS

300mV
 TRC
 BIAS

300mV
 TRC
 NOX BIAS

400mV
 TRC
 BIAS

10%
 COC BIAS


12.0%
 COC BIAS

END RUN
 #2 1153

ON
 CABLE
 OFF

12 5.347V
 06 0.653V
 06 0.067V
 04 0.261V
 03 0.676V
 01 0.737V
 200mV
 Aug. 29 11:10

06 0.706V
 05 0.072V
 04 0.245V
 03 0.648V
 01 0.658V
 200mm/h
 Aug. 29 13:10



12 5.952V
 06 0.807V
 05 0.807V

STACK 1442

① zero

① 20.9% 002

30PPM
TNC BIAS

470PPM 50%
BIAS

86PPM
NOT BIAS

60PPM
CO BIAS

① 10.0%
CO2 BIAS

12.0% 002 BIAS


① 20.9%
002

① END RUN #2
1354


12
06
03
03
01
200m h
Aug. 29 14:10

12 4.758V
 06 0.731V
 05 0.040V
 04 0.321V
 03 0.600V
 01 0.354V

200mm
 Aug. 29 15:00



12 1.869V
 06 0.000V
 05 0.270V
 04 0.004V
 03 0.000V
 01 0.000V
 200mV
 Aug. 29 1961



60PPM
CO BIAS

29PPM
PROPANE
TWC BIAS

10.0%
CO2 BIAS

SYSTEM
RESPONSE
TIME 212.5

129002 BIAS

489114
500 BIAS

36PPM
NOX
CAL

489PPM
SO2 CAL

151PPM
NOX CAL

12844502
CAL

60PPM
CO CAL

31PPM
PROPANE
TWC CAL
30800
CAL

49PPM PROPANE
TWC CAL

10.0% CO2 CAL

18%
CO2 CAL
82PPM PROPANE
TWC CAL

zero TWC
NOX
SO2
CO

NORTH DRYER STACK
MANIFOLD BRICK
8-30-94

12 0001V
06 00042V
05 00005V
04 00005V
03 -00042V
01 -00022V
200
Aug. 30 03110

12 -0.002V
06 0.020V
05 0.012V
04 0.010V
03 0.011V
01 0.039V
200mV
Aug. 30 10:10

zero 0.4% CO₂
CO = 3ppm

20.4% O₂

zero
NOx
SO₂
the
0.3%
CO₂
1ppm CO
3

20.5% O₂

0.4% O₂

20.1% O₂

NORTH START RUN #1
Dryer
STACK 0937
8-30-94

zero
NOx
CO 3ppm
the 1ppm
SO₂ 1ppm

0.2%
CO₂

20.5% O₂

STACK 0917

20.9% O₂

80ppm NOx BIAS

60ppm
CO BIAS

ZERO
NOX
TWC
SO2

CO 14 PPM
CO2 .2%

START RUN # Z 1133

O2 20.4%

20.9% O2

60 PPM
CO BIAS

80 PPM
NOX BIAS

10% O2 BIAS

12% O2 BIAS

31 PPM
TWC BIAS

489 SO2
BIAS

END RUN # 1040

CO = 10 PPM
28 PPM
TWC

CO = 9 PPM
CO2 = 0.3%

O2 20.2% O2

OTHC = 3 PPM

-0.020V
0.020V
0.012V
0.010V

20.8% O2

86ppm
NOX BIAS

60ppm CO
BIAS!

29ppm
Propene BIAS
TAC

48954.2
10.0% CO2 BIAS

0 END RUN #2
1236

20.9% O2
BIAS

20.5% O2

zero
CO = 15ppm
CO2 = .3%

12 -0.001V
06 0.0023V
05 0.003V
04 0.0055V
03 0.0055V
01 0.0080V

200mm
Aug. 30 12:10

CO = 16ppm

440074P

CO = 5 ppm
CO2 = 0.4%

20.4% O2

0.4% CO2
CO = 4 ppm

20.5% O2

- 12 -0.002V
- 06 0.023V
- 05 0.015V
- 04 0.010V
- 03 -0.034V
- 01 0.078V

START RUN #3
1311
NORTH DRYER STACK
8-30-74

20.8% O2

↑
86ppm
NOX BAS

START RUN# 1
1520

12 0.004V
06 0.006V
05 0.004V
04 -0.001V
03 -0.009V
01 -0.035V
200m/h
Aug. 30

0.3% CO₂

4 ppm CO

zero NOX, SO₂, etc

20.3% O₂

20.8% O₂

Moving to South
Dryer Stack 1455
8-30-94

86 ppm
NOX BIAS

60 ppm
CO BIAS

29 ppm
PIDANE
BIAS
The

10.0%
CO₂ BIAS

489
ppm
SO₂
12% O₂ BIAS

END RUN # 3
1426

12 -0.002V
06 0.000V
05 0.002V
04 0.002V
03 0.002V
01 0.003V
200m/h
Aug. 30

CO = 9 ppm

20.5% O₂

CO = 5 ppm
CO₂ = 0.4%

20.4% O₂

THE BAY
12.0%
02 BAY

486.1 PM
502 BAY

O-END RUN # 1624

12 -0.001V
6 0.0019V
5 0.001V
4 0.0015V
03 0.0009V
01 0.0008V
200mV
us.30 10

QASCO TECHNOLOGIES INC QASCO-ZFP

5 PPM CO

20.5% O2

0.3% CO2
4 PPM CO

20.2% O2

START RUN # 1
1520

12 0.001V
6 0.0006V
5 0.0004V
03 0.001V
01 0.000V

0.4% CO2

3 ppm CO

0.4% CO2
CO = 3 ppm

20.4% O2

20.4% O2

START RUN #2 1733

20.9% O2

zero
NOx
SO2
TWC

0.010V
0.0083V
0.004V
0.001V
-0.004V
-0.0033V
200 h
0.30 10

ONEA ENGINEERING, INC.
04500.ZIP

12

6

12

60 ppm
CO B.A.S

8 ppm
NOx B.A.S

10.0%
CO2 B.A.S

zero

29 ppm
Propane
TWC B.A.S

12.0%
O2 B.A.S

486 ppm
SO2 B.A.S

4 ppm CO
0.4% CO₂

20.3
20.3% O₂

START Run #3
1856
South, Oryor

86 ppm
NO_x BIAS

60 ppm
CO BIAS

29 ppm
NO_x BIAS

10.0%
O₂ BIAS

486 ppm CO₂ BIAS
END Run #2
1836

20.0%
O₂ BIAS

0.4% CO₂
3 ppm CO

20.5% O₂

12 -0.02V
06 0.02V
05 0.01V
04 0.07V
03 0.26V
01 0.44V
200
Run 30 10

0.4% CO₂
3 ppm CO

20.4% O₂

0.4% CO₂

20.4% O₂

CHROMA ENGINEERING INC. CH500ZFP

01 200mV 160 PPM
Aug. 30 20:10 CO BIAS

①
↑
30 PPM
PROPANE BIAS

↑
439 PPM SO₂ BIAS

↑
20.0%
O₂ BIAS

○ RUN 3 END 1959

ZERO
NO_x
SO₂
TUC

○ 0.3% CO₂
○ 6 PPM CO

20.3
○ 20.3% O₂

12 0.006V
06 0.014V
05 0.011V
04 0.011V
03 0.017V
01 0.018V
200mV
Aug. 30 19:10

○ 4 PPM CO
○ 0.4% CO₂

○ 20.3
○ 20.3% O₂

STRA Run #3

1856
South, Driver

Hand-drawn graph on grid paper showing various data points and trends. The graph includes handwritten labels for CO, NOx, SO2, and O2 concentrations, along with 'CAL' and 'BIAS' annotations. A dashed line connects several points, and a solid line connects others. The x-axis is labeled 'ORIN 3 END 1959'.

Key data points and labels:

- Top Left:** 60 PPM CO CAL.
- Top Center:** 86 PPM NOx CAL, 307 PPM CO CAL, 30 PPM PROPANE THE CAL.
- Top Right:** 151 PPM NOx CAL, 82 PPM PROPANE THE CAL.
- Middle Left:** 30 PPM PROPANE THE CAL.
- Middle Center:** 10.0% CO2 CAL, 4.9 PPM SO2 CAL, 12.1% O2 CAL.
- Middle Right:** 18.1% CO2 CAL, 844 PPM SO2 CAL, 20.0% O2 CAL.
- Bottom Left:** 60 PPM CO BIAS, 86 PPM NOx BIAS.
- Bottom Center:** 30 PPM PROPANE THE BIAS, 10.0% CO2 BIAS, 4.9 PPM SO2 BIAS.
- Bottom Right:** 20.0% O2 BIAS.

A dashed line connects points from the top left to the middle right. A solid line connects points from the bottom left to the bottom right. The x-axis is labeled 'ORIN 3 END 1959'.

APPENDIX F

Example Calculations

MOISTURE CONTENT DETERMINATION
EPA Method 4 Calculations
TEST RUN #1
KILN

Parameter	Definition	Unit
Pm	- Absolute Meter Pressure	in. Hg.
Po	- Average Meter Orifice Differential Pressure	in. H2O
Pstd	- Absolute Standard Barometric Pressure {29.92}	in. Hg.
Pb	- Absolute Barometric Pressure	in. Hg.
k	- Standard Volume H2O Vapor/Unit Weight Liquid Constant = 0.04715 cu. ft./g	ft./g
Tm(F)	- Average Meter Temperature Degrees F:	degrees (F)
Tm	- Average Meter Temperature Degrees R:	degrees (R)
Tstd	- Absolute Standard Temperature (528 R)	degrees (R)
Y	- Dry Gas Meter Correction Factor	dimensionless
Vicg	- Total condensate Collected	grams/ml H2O
Vm	- Metered Dry Sample Gas Volume	dcf
Vmstd	- Volume of Water Vapor Collected at Standard Conditions (528 R, 1 atmosphere)	scf
Bws	- Moisture Content (mole fraction)	mole fraction
Bwd	- Moisture Content (% Volume)	% volume

TEST DATA
RUN # 1

Pb	30.24	Y	1.002
Vm	63.658	Tm(F)	92.666667
Vicg	81.10	Tm	552.66667
Tstd	528.00	Po	4.138
Pstd	29.92	k	0.04715

MOISTURE DETERMINATION CALCULATIONS:

1. Meter Pressure:

$$P_m = (P_o/13.6) + P_b$$

$$P_m = 4.138095238 \text{ divided by } 13.6 + 30.24 = 30.5443 \text{ in. Hg.}$$

2. Standard Meter Volume:

$$V_{mstd} = \frac{17.64 \cdot V_m \cdot Y \cdot P_m}{T_m}$$

$$V_{mstd} = \frac{17.64 \cdot 63.658 \cdot 1.002 \cdot 30.5443}{552.6666667} = 62.1850 \text{ dscf}$$

3. Meter Temperature:

$$T_m = T_m(F) + 460$$

$$T_m = 92.66666667 + 460 = 552.6666667 \text{ Deg. (R)}$$

4. Standard Water Volume:

$$V_{wstd} = k \cdot V_{lwg}$$

$$V_{wstd} = 0.04715 \cdot 81.1 = 3.823865 \text{ scf}$$

5a. Moisture Content

$$B_{ws} = \frac{V_{wstd}}{V_{wstd} + V_{mstd}}$$

$$B_{ws} = \frac{3.823865}{3.823865 + 62.1850} = 0.0579 \text{ mole frac.}$$

$$B_{wd} = B_{ws} \cdot 100$$

$$B_{wd} = 0.057929548 \cdot 100 = 5.7930 \% \text{ H}_2\text{O}$$

5c. Dry Gas Fraction:

$$F_{dg} = 1 - B_{ws}$$

$$F_{dg} = 1 - 0.0579 = 0.9421 \text{ FDG}$$

VELOCITY AND VOLUMETRIC FLOWRATE DETERMINATION
EPA METHOD 2 CALCULATIONS
TEST RUN #1
KILN

Parameter	Definition	Units
Cp	- Pitot Tube Coefficient	dimensionless
Vs	- Gas Stream Velocity	ft./second
Qsd	- Volumetric Flow Rate at Standard Condition, Dry Basis	dscfm
Qact	- Actual Volumetric Flow Rate, Wet Basis	acfm
Bws	- Moisture Content	mole fraction
Dp	- Average Square Root of Velocity Head	in. H2O
Pb	- Absolute Barometric Pressure	in. Hg.
Kp	- Constant= $89.49(\text{ft})(\text{lb}/\text{b-mol})(\text{in. Hg}^{0.5})/(\text{s})(\text{R})$	in. H2O
Ts	- Absolute Stack Gas Temperature (R)	Degrees (R)
Ms	- Sample Gas Molecular Weight, Wet Basis	lb/lb-mole
Sp	- Static Pressure of Gas Stream	in. H2O
Abs	- Absolute Standard Temperature	528 degrees R
Sl	- Stack Length	in.
Sw	- Stack Width	in.
Csa	- Stack Cross-sectional Area	ft ²
Ps	- Absolute Stack Gas Pressure	in. Hg.
Sm	- Conversion Factor	60 sec/min
Pi	- Constant Ratio	3.1415927 dimensionless
Dn	- Nozzle Diameter	in.
An	- Nozzle Area	ft. ²
Tstd	- Absolute Standard Temperature (528) (R)	degrees R

TEST DATA
TEST RUN #1

Ms	28.3867	Cp	0.84
Bws	0.0579	Pb	30.24
Sp	-0.15	Ts	897.43
Sl	41.00	Dp	0.5983
Sw	41		
Tstd	528.00	Dn	0.3700

VELOCITY AND VOLUMETRIC FLOWRATE CALCULATIONS:

1. Stack Pressure:

$$P_s = P_b + (S_p / 13.6)$$

$$P_s = 30.24 + \frac{-0.15}{13.6} = 30.2290 \text{ in. Hg.}$$

2. Velocity of Stack Gas:

$$\frac{V_s = 85.49 \cdot C_p \cdot D_p \cdot \left[\frac{\text{SQRT}[(T_s)/(P_s \cdot M_s)]}{V_s = 85.49 \cdot 0.502548772 \cdot 1.022658579} \right]}{29.9571 \quad 29.2934} = 43.9364 \text{ ft./sec.}$$

3. Stack Cross-sectional Area:

$$\begin{aligned} C_{sa} &= (L \cdot W) / 144 \\ C_{sa} &= (41 \cdot 41) / 144 = 11.67361111 \text{ ft}^2 \end{aligned}$$

4a. Volumetric Flowrate, Wet Basis:

$$\begin{aligned} Q_{act} &= (V_s \cdot C_{sa}) \cdot 60 \\ Q_{act} &= 43.9364 \cdot 11.67361111 \cdot 60 = 30773.7677 \text{ acfm} \end{aligned}$$

4b. Volumetric Flowrate at Standard Conditions, Dry Basis:

$$\begin{aligned} Q_{sd} &= \frac{(Q_{act})(1 - B_{ws})}{(T_s)(29.92)} \cdot \frac{(T_{std})(P_s)}{P_{std}} \\ Q_{sd} &= \frac{30773.76769 \cdot 0.942070452}{26851.06286} = 15960.89647 \end{aligned}$$

$$Q_{sd} = 17232.9589 \text{ dscfm}$$

MOLECULAR WEIGHT DETERMINATION
EPA METHOD 3 CALCULATIONS
TEST RUN # 1
KILN

Parameter	Definition	Units
Md	- Sample Gas Molecular Weight, Dry Basis	lb/lb-mole
Ms	- Sample Gas Molecular Weight, Wet Basis	lb/lb-mole
Bws	- Moisture Content	mole fraction
%O2	- Oxygen (O2) Concentration, Dry Basis	% volume
%CO2	- Carbon Dioxide (CO2) Concentration, Dry Basis	% volume
%CO	- Carbon Monoxide (CO) Concentration, Dry Basis	% volume
%N2	- Nitrogen (N2) Concentration, Dry Basis (gas balance)	% volume
0.32	- Molecular Weight of Oxygen (O2) divided by 100	lb/lb-mole
0.44	- Molecular Weight of Carbon Dioxide (CO2) / by 100	lb/lb-mole
0.28	- Molecular Weight of Carbon Monoxide (CO) / by 100	lb/lb-mole
0.28	- Molecular Weight of Nitrogen (N2) divided by 100	lb/lb-mole
18.00	- Molecular Weight of Water	lb/lb-mole

TEST DATA
TEST RUN #1

Bws	0.0579	%N2	81.052
%O2	16.73		
%CO2	2.218		
%CO	0		

1. MOLECULAR WEIGHT, DRY:

$$\begin{aligned}
 \text{Md} &= 0.44 \cdot \% \text{CO}_2 + 0.32 \cdot \% \text{O}_2 + 0.28 \cdot \% \text{N}_2 + \% \text{CO} \\
 &= 0.97592 + 5.3536 + 22.69456 + 0 \\
 \text{Md} &= 29.0241 \text{ lb/lb-mole}
 \end{aligned}$$

2. MOLECULAR WEIGHT, WET:

$$\begin{aligned}
 \text{Ms} &= \text{Md} \cdot (1 - \text{Bws}) + 18.00 \cdot \text{Bws} \\
 &= 29.02408 \cdot 0.942070452 + 1.042731861 \\
 \text{Ms} &= 28.3855 \text{ lb/lb-mole}
 \end{aligned}$$

PARTICULATE MATTER EMISSION DETERMINATION
EPA METHOD 5 CALCULATIONS
TEST RUN # 1
KILN

Parameter	Definition	Units
Fdg	- (1-Bws)	fraction
I	- Percent of Isokinetic Sampling	%
Ts	- Absolute Average Stack Gas Temperature	degrees R
Vmstd	- Volume of Stack Gas Sampled, Corrected to Dry, Standard Conditions	dscf
Vs	- Stack Gas Velocity	ft./second
T	- Sample Time Interval	minutes
An	- Cross-Sectional Area of Sampling Nozzle	ft.2
Ps	- Absolute Stack Gas Pressure	in. Hg
Dn	- Sampling Nozzle Diameter	inches
Pi	- Constant (3.141592654)	dimensionless
K2	- Conversion Factor (144)	in.2/ft.2
K3	- Conversion Factor (0.002669)	in. Hg-ft.3/ml-R
K4	- Conversion Factor (17.64)	deg.R/in. Hg
1.67	- Conversion Factor	%-sec/min

TEST DATA
TEST RUN #1
KILN

Bws	0.0579	Ts	897.43
Vs	43.9364	Ps	30.2290
Vicg	81.1000	T	60
K3	0.0027	Dn	0.3700
K4	0.0945	Vmstd	62.1850
Fdg	0.9421		

1. Nozzle Area:

$$An = (Dn/24)^2 \cdot \pi$$

$$\frac{An}{An} = 0.000237674 \cdot 3.1415927 = 0.00074667 \text{ ft.2}$$

2. I = ISOKINETICS (%):

$$\frac{0.0945 \cdot Ts \cdot Vmstd}{Ps \cdot Vs \cdot An \cdot T \cdot Fdg} \quad An \cdot T \cdot Fdg = 0.042205152$$

$$\frac{0.0945 \cdot 897.4285714 \cdot 62.185022}{30.22897 \cdot 43.93637266 \cdot 0.0422052} = 94.08 \% I$$

PARTICULATE MATTER EMISSION DETERMINATION
EPA METHOD 5 CALCULATIONS
TEST RUN # 1
KILN

Parameter	Definition	Units
Pc	- Total Particulate Catch	mg
Pg	- Total Particulate Catch (mg/1000)	grams
Vmstd	- Volume of Stack Gas Sampled, Corrected to Dry, Standard Conditions	dscf
Cs	- Concentration of Particulate in Stack Gas, Corrected to Dry, Standard Conditions (grams/dscf)	gm/dscf
Cg	- Concentration of Particulate Matter (grains)	gr/dscf
Pcs	- Concentration of Particulate (lb/hour)	lb/hour
K3	- Conversion Factor (15.43)	gr/gm
Qsd	- Stack Gas Volumetric Flow Rate, Corrected to Dry, Standard Conditions	dscf/min
K2	- Conversion Factor (0.002205)	lb/gm
K1	- Conversion Factor (0.001)	gm/mg
K4	- Conversion Factor (60)	min/hour
Pe	- Particulate Matter Emission Rate	lb/hour

TEST DATA
TEST RUN #1
KILN

Pc	588.8	K4	60.00
Pg	0.5888	Qsd	17232.959
Vmstd	62.1850	K1	0.001000
K2	0.002205	K3	15.43

AUGUST 29, 1994
KILN STACK
PARTICULATE MATTER EMISSIONS CALCULATIONS:

1a. Total Particulate Catch :

$$Cs = \frac{Pg}{Vmstd} = \frac{0.5888}{62.1850224} = 0.0095 \text{ grams/dscf}$$

1b. Cg = K3 * Cs

$$Cg = 15.43 * 0.009468518 = 0.1461 \text{ grains/dscf}$$

1c. Pcs = K2 * Cs

$$Pcs = 0.002205 * 0.009468518 = 0.00002088 \text{ lb/dscf}$$

1d. Pe = K4

$$Pe = 60 * 0.000020878 * 17232.95892 = 21.5875 \text{ lbs/hour}$$

Pe = 21.5875 lbs/hour Total Particulate Emissions.

APPENDIX G

Calibration Gas Certifications



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(313) 589-2950 FAX: (313) 589-2134

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer
FURGO MCCLELLAND
CHRIS DAWDY
9921 ST CHARLES ROCK RD
ST ANN MO 63074

Assay Laboratory
Scott Specialty Gases, Inc.
1290 Combermere
Troy, MI 48083

Purchase Order H145-2
Scott Project # 547552

ANALYTICAL INFORMATION

Certified to exceed the minimum specifications of EPA Protocol 1 Procedure #G1, Section Number 3.0.4

Cylinder Number ALM020958
Cylinder Pressure 1900 psig

Certification Date 2-18-93
Previous Certification Dates None

Expiration Date 8-18-94

ANALYZED CYLINDER

Components
Propane

Certified Concentration
82.11 ppm

Analytical Uncertainty*
±1% NIST Directly Traceable

Balance Gas: Nitrogen

*Analytical uncertainty is inclusive of usual known error sources which at least includes reference standard error & precision of the measurement processes.

REFERENCE STANDARD

Type Expiration Date
SRM 2643A 10-14-95

Cylinder Number
SX-20305

Concentration
99.12 ppm Propane in N₂

INSTRUMENTATION

Instrument/Model/Serial #
Prop: Beckman/400/1002059

Last Date Calibrated
1-25-93

Analytical Principle
Flame Ionization Detector

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components
Propane

First Triad Analysis

Date: 2-18-93 Response Units: mv
Z1=0.00 R1=99.10 T1=82.10
R2=99.10 Z2=0.00 T2=82.10
Z3=0.00 T3=82.10 R3=99.10
Avg. Conc. of Cust. Cyl. 82.11 ppm

Second Triad Analysis


Calibration Curve

Concentration=A+Bx+Cx²+Dx³+Ex⁴
r=0.99999 SRM 2643A
Constants: A=-0.03442105
B=1.000549 C=0
D=0 E=0

Concentration=A+Bx+Cx²+Dx³+Ex⁴

Concentration=A+Bx+Cx²+Dx³+Ex⁴

Special Notes


Analyst Tim Sanderson



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(313) 589-2950 FAX: (313) 589-2134

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer
FURGO MCCLELLAND
CHRIS DAWDY
9921 ST CHARLES ROCK RD
ST ANN MO 63074

Assay Laboratory
Scott Specialty Gases, Inc.
1290 Combermere
Troy, MI 48083

Purchase Order H145-2
Scott Project # 547552

ANALYTICAL INFORMATION

Certified to exceed the minimum specifications of EPA Protocol 1 Procedure #G1, Section Number 3.0.4

Cylinder Number ALM030297
Cylinder Pressure 1900 psig

Certification Date 2-18-93
Previous Certification Dates None

Expiration Date 8-18-94

ANALYZED CYLINDER

Components
Propane

Certified Concentration
49.59 ppm

Analytical Uncertainty*
±1% NIST Directly Traceable

Balance Gas: Nitrogen

*Analytical uncertainty is inclusive of usual known error sources which at least includes reference standard error & precision of the measurement processes.

REFERENCE STANDARD

Type SRM 2643A
Expiration Date 10-14-95

Cylinder Number
SX-20305

Concentration
99.12 ppm Propane in N₂

INSTRUMENTATION

Instrument/Model/Serial #
Prop: Beckman/400/1002059

Last Date Calibrated
1-25-93

Analytical Principle
Flame Ionization Detector

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components
Propane

First Triad Analysis

Date: 2-18-93 Response Units: mv
Z1=0.00 R1=99.10 T1=49.60
R2=99.10 Z2=0.00 T2=49.60
Z3=0.00 T3=49.60 R3=99.10
Avg. Conc. of Cust. Cyl. 49.59 ppm

Second Triad Analysis

Calibration Curve

Concentration=A+Bx+Cx²+Dx³+Ex⁴
r=0.99999 SRM 2643A
Constants: A=-0.03442105
B=1.000549 C=0
D=0 E=0

Concentration=A+Bx+Cx²+Dx³+Ex⁴

Concentration=A+Bx+Cx²+Dx³+Ex⁴

Special Notes

Analyst Tim Sanderson



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(313) 589-2950 FAX: (313) 589-2134

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer
FURGO MCCLELLAND
CHRIS DAWDY
9921 ST CHARLES ROCK RD
ST ANN MO 63074

Assay Laboratory
Scott Specialty Gases, Inc.
1290 Combermere
Troy, MI 48083

Purchase Order H145-2
Scott Project # 547552

ANALYTICAL INFORMATION

Certified to exceed the minimum specifications of EPA Protocol 1 Procedure #G1, Section Number 3.0.4

Cylinder Number ALM030957
Cylinder Pressure 1900 psig

Certification Date 2-18-93
Previous Certification Dates None

Expiration Date 8-18-94

ANALYZED CYLINDER

Components
Propane

Certified Concentration
30.68 ppm

Analytical Uncertainty*
±1% NIST Directly Traceable

Balance Gas: Nitrogen

*Analytical uncertainty is inclusive of usual known error sources which at least includes reference standard error & precision of the measurement processes.

REFERENCE STANDARD

Type SRM 2643A
Expiration Date 10-14-95

Cylinder Number
SX-20305

Concentration
99.12 ppm Propane in N₂

INSTRUMENTATION

Instrument/Model/Serial #
Prop: Beckman/400/1002059

Last Date Calibrated
1-25-93

Analytical Principle
Flame Ionization Detector

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components
Propane

First Triad Analysis

Date: 2-18-93 Response Units: mv
Z1=0.00 R1=99.10 T1=30.70
R2=99.10 Z2=0.00 T2=30.70
Z3=0.00 T3=30.70 R3=99.10
Avg. Conc. of Cust. Cyl. 30.68 ppm

Second Triad Analysis


Calibration Curve

Concentration=A+Bx+Cx²+Dx³+Ex⁴
r=0.99999 SRM 2643A
Constants: A=-0.03442105
B=1.000549 C=0
D=0 E=0

Concentration=A+Bx+Cx²+Dx³+Ex⁴

Concentration=A+Bx+Cx²+Dx³+Ex⁴

Special Notes


Analyst Tim Sanderson



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALEMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER N/A

REFERENCE STANDARD

COMPONENT	NIST SRM NO.	CYLINDER NO.	CONCENTRATION
NITRIC OXIDE GMIS	vs 1685b	SA 5692	237 ppm

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	NITRIC OXIDE	GMIS	ANALYZER MAKE-MODEL-S/N	Beckman 951A	S/N 0101354		
ANALYTICAL PRINCIPLE		Chemiluminescence	LAST CALIBRATION DATE 03/03/93				
FIRST ANALYSIS DATE		04/16/93	SECOND ANALYSIS DATE 04/23/93				
Z 0	R 931	C 964	CONC. 245 ppm	Z 0	R 932	C 966	CONC. 246 ppm
R 932	Z 0	C 964	CONC. 245 ppm	R 933	Z 0	C 969	CONC. 246 ppm
Z 0	C 964	R 931	CONC. 245 ppm	Z 0	C 968	R 933	CONC. 246 ppm
U/M mV		MEAN TEST ASSAY 245 ppm		U/M mV		MEAN TEST ASSAY 246 ppm	

THIS CYLINDER NO. SA 6137
HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 2000 PSIG
CERTIFICATION DATE 04/23/93
EXPIRATION DATE 10/23/94

CERTIFIED CONCENTRATION
NITRIC OXIDE 246 ppm
NITROGEN BALANCE
NOX 248 ppm

ANALYZED BY

MARIA E. ROCHON

CERTIFIED BY

KWAN T. YOUNG



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALAMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER 102293-1

REFERENCE STANDARD

COMPONENT

NIST SRM NO.

CYLINDER NO.

CONCENTRATION

SULFUR DIOXIDE GMIS

vs. 1662a

SA 6240

1002 ppm

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT		SULFUR DIOXIDE		GMIS		ANALYZER MAKE-MODEL-S/N		Siemens Ultramat 5E		S/N C1-009					
ANALYTICAL PRINCIPLE				NDIR		LAST CALIBRATION DATE				08/17/93					
FIRST ANALYSIS DATE				11/08/93		SECOND ANALYSIS DATE				11/15/93					
Z 0		R 1002		C 845		CONC. 845 ppm		Z 0		R 1004		C 846		CONC. 844 ppm	
R 1002		Z 0		C 844		CONC. 844 ppm		R 1004		Z 0		C 847		CONC. 845 ppm	
Z 0		C 844		R 1002		CONC. 844 ppm		Z 0		C 846		R 1004		CONC. 844 ppm	
U/M		ppm		MEAN TEST ASSAY		844 ppm		U/M		ppm		MEAN TEST ASSAY		844 ppm	

THIS CYLINDER NO. SA 8427
HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 2000 PSIG
CERTIFICATION DATE 11/15/93
EXPIRATION DATE 11/15/96 TERM 36 MONTHS

CERTIFIED CONCENTRATION

SULFUR DIOXIDE 844 ppm
NITROGEN BALANCE

ANALYZED BY

Kelly Gallagher
KELLY GALLAGHER

CERTIFIED BY

Marta Rochon
MARTA ROCHON



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALEMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER 031993-4

REFERENCE STANDARD

COMPONENT	NIST SRM NO.	CYLINDER NO.	CONCENTRATION
NITRIC OXIDE GMIS	vs 1684b	SA 1395	85.2 ppm

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	NITRIC OXIDE	GMIS	ANALYZER MAKE-MODEL-S/N	Beckman 951A	S/N 0101354		
ANALYTICAL PRINCIPLE		Chemiluminescence		LAST CALIBRATION DATE	03/03/93		
FIRST ANALYSIS DATE		01/21/93		SECOND ANALYSIS DATE	03/24/93		
Z 0	R 967	C 822	CONC. 86.7 ppm	Z 0	R 862	C 870	CONC. 86.0 ppm
R 967	Z 0	C 822	CONC. 86.7 ppm	R 860	Z 0	C 869	CONC. 86.1 ppm
Z 0	C 822	R 967	CONC. 86.7 ppm	Z 0	C 869	R 860	CONC. 86.1 ppm
U/M mV		MEAN TEST ASSAY	86.7 ppm	U/M mV		MEAN TEST ASSAY	86.1 ppm

CHRONOLOGY: First Analysis vs GMIS SA 3057, 102 ppm NO/N2

THIS CYLINDER NO. SGAL 1074
HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0
OF TRACEABILITY PROTOCOL NO. 1
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 2000 PSIG
CERTIFICATION DATE 03/24/93
EXPIRATION DATE 09/24/94

CERTIFIED CONCENTRATION

NITRIC OXIDE	86.4 ppm
NITROGEN	BALANCE
NOX	88.7 ppm

ANALYZED BY

W. J. [Signature]
PART 1 - NOX

CERTIFIED BY

[Signature]
KUAN T. YOUNG



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALAMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER 102293-1

REFERENCE STANDARD

COMPONENT	NIST SRM NO.	CYLINDER NO.	CONCENTRATION
SULFUR DIOXIDE GHIS	vs. 1662a	SA 6240	1002 ppm

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	SULFUR DIOXIDE	GHIS	ANALYZER MAKE-MODEL-S/N	Siemens Ultramat 5E	S/N C1-009		
ANALYTICAL PRINCIPLE	NDIR			LAST CALIBRATION DATE	08/17/93		
FIRST ANALYSIS DATE	11/08/93			SECOND ANALYSIS DATE	11/15/93		
Z 0	R 1002	C 845	CONC. 845 ppm	Z 0	R 1004	C 846	CONC. 844 ppm
R 1002	Z 0	C 844	CONC. 844 ppm	R 1004	Z 0	C 847	CONC. 845 ppm
Z 0	C 844	R 1002	CONC. 844 ppm	Z 0	C 846	R 1004	CONC. 844 ppm
U/M ppm		MEAN TEST ASSAY	844 ppm	U/M ppm		MEAN TEST ASSAY	844 ppm

THIS CYLINDER NO. SA 8427
HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 2000 PSIG
CERTIFICATION DATE 11/15/93
EXPIRATION DATE 11/15/96 TERM 36 MONTHS

CERTIFIED CONCENTRATION
SULFUR DIOXIDE 844 ppm
NITROGEN BALANCE

ANALYZED BY

Kelly Gallagher
KELLY GALLAGHER

CERTIFIED BY

Marta Rochon
MARTA ROCHON



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALAMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER 102293-1

REFERENCE STANDARD

COMPONENT	NIST SRM NO.	CYLINDER NO.	CONCENTRATION
SULFUR DIOXIDE GMIS	vs 1662a	SA 3104	480 ppm

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	SULFUR DIOXIDE	GMIS	ANALYZER MAKE-MODEL-S/N	Siemens Ultramat 5E	S/N C1-009		
ANALYTICAL PRINCIPLE	NDIR			LAST CALIBRATION DATE	08/17/93		
FIRST ANALYSIS DATE	11/08/93			SECOND ANALYSIS DATE	11/15/93		
Z 0	R 480	C 489	CONC. 489 ppm	Z 0	R 480	C 489	CONC. 489 ppm
R 481	Z 0	C 488	CONC. 487 ppm	R 480	Z 0	C 489	CONC. 489 ppm
Z 0	C 488	R 481	CONC. 487 ppm	Z 0	C 488	R 480	CONC. 488 ppm
U/M ppm		MEAN TEST ASSAY	488 ppm	U/M ppm		MEAN TEST ASSAY	489 ppm

THIS CYLINDER NO. SA 6036
HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 2000 PSIG
CERTIFICATION DATE 11/15/93
EXPIRATION DATE 11/15/95 TERM 24 MONTHS

CERTIFIED CONCENTRATION
SULFUR DIOXIDE 489 ppm
NITROGEN BALANCE

ANALYZED BY

Kelly Gallagher
KELLY GALLAGHER

CERTIFIED BY

Marta Rochow
MARTA ROCHOW



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALAMEDA STREET • LOS ANGELES, CA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER ENV. & INDUSTRY, DIST.

P.O. NUMBER 022194-1

REFERENCE STANDARD

COMPONENT	NIST SRM NO.	CYLINDER NO.	CONCENTRATION
CARBON DIOXIDE GMIS	vs 1675b	438008	14.04 %

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	CARBON DIOXIDE	GMIS	ANALYZER MAKE-MODEL-S/N	Siemens Ultramat 5E	S/N A12-730
ANALYTICAL PRINCIPLE	NDIR			LAST CALIBRATION DATE	03/04/94
FIRST ANALYSIS DATE	03/17/94			SECOND ANALYSIS DATE	
Z 0.00	R 14.04	C 10.00	CONC. 10.00 %	Z	R C CONC.
R 14.04	Z 0.00	C 10.00	CONC. 10.00 %	R	Z C CONC.
Z 0.00	C 10.00	R 14.04	CONC. 10.00 %	Z	C R CONC.
U/M %		MEAN TEST ASSAY	10.00 %	U/M %	MEAN TEST ASSAY

THIS CYLINDER NO. CC 58016
HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 2000 PSIG
CERTIFICATION DATE 03/17/94
EXPIRATION DATE 03/17/97 TERM 36 MONTHS

CERTIFIED CONCENTRATION
CARBON DIOXIDE 10.00 %
NITROGEN BALANCE

ANALYZED BY

Marie E. Rochon
MARIE E. ROCHON

CERTIFIED BY

Ty Triplett
TY TRIPLETT



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALAMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER 102293-1

REFERENCE STANDARD

COMPONENT
CARBON DIOXIDE

NIST SRM NO.
2745

CYLINDER NO.
SX-20341

CONCENTRATION
15.75 %

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	CARBON DIOXIDE	ANALYZER MAKE-MODEL-S/N	Siemens Ultramat 5E	S/N A12-730			
ANALYTICAL PRINCIPLE	NDIR		LAST CALIBRATION DATE	09/03/93			
FIRST ANALYSIS DATE	11/10/93		SECOND ANALYSIS DATE				
Z 0.00	R 15.74	C 18.12	CONC. 18.13 %	Z	R	C	CONC.
R 15.76	Z 0.00	C 18.12	CONC. 18.11 %	R	Z	C	CONC.
Z 0.00	C 18.11	R 15.75	CONC. 18.11 %	Z	C	R	CONC.
U/M %		MEAN TEST ASSAY	18.12 %	U/M %		MEAN TEST ASSAY	

THIS CYLINDER NO. SA 8767

HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1

PROCEDURE G1

CERTIFIED ACCURACY ± 1 % NIST TRACEABLE

CYLINDER PRESSURE 2000 PSIG

CERTIFICATION DATE 11/10/93

EXPIRATION DATE 11/10/96 TERM 36 MONTHS

CERTIFIED CONCENTRATION

CARBON DIOXIDE	18.12 %
NITROGEN	BALANCE

ANALYZED BY

Maria Rochon
MARIA ROCHON

CERTIFIED BY

David Leon
DAVID LEON



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALAMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER 102293-1

REFERENCE STANDARD

COMPONENT	NIST SRM NO.	CYLINDER NO.	CONCENTRATION
CARBON MONOXIDE GHIS	vs 1680b	55251	452 ppm

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	CARBON MONOXIDE	GHIS	ANALYZER MAKE-MODEL-S/N	Siemens Ultramat 5E	S/N A12-729
ANALYTICAL PRINCIPLE	NDIR		LAST CALIBRATION DATE	09/02/93	
FIRST ANALYSIS DATE	11/8/93		SECOND ANALYSIS DATE	11/15/93	
Z 0	R 452	C 309	CONC. 309 ppm	Z 0	R 452
R 452	Z 0	C 309	CONC. 309 ppm	R 452	Z 0
Z 0	C 309	R 452	CONC. 309 ppm	Z 0	C 309
U/M ppm	MEAN TEST ASSAY	309 ppm	U/M ppm	MEAN TEST ASSAY	309 ppm

THIS CYLINDER NO. SA 8631
HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 1650 PSIG
CERTIFICATION DATE 11/15/93
EXPIRATION DATE 11/15/96 TERM 36 MONTHS

CERTIFIED CONCENTRATION

CARBON MONOXIDE	309 ppm
NITROGEN	BALANCE

ANALYZED BY *Maria E. Rochon*
MARIA E. ROCHON

CERTIFIED BY *David Leon*
DAVID LEON



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(313) 589-2950 FAX: (313) 589-2134

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer

FUGRO MCCLELLAND
MR. TODD SATLEY
9921 ST CHARLES ROCK RD
ST ANN MO 63074

Assay Laboratory
Scott Specialty Gases, Inc.
1290 Combermere
Troy, MI 48083

Purchase Order H145
Scott Project # 549824

ANALYTICAL INFORMATION

Certified to exceed the minimum specifications of EPA Protocol 1 Procedure # G1, Section Number 3.0.4

Cylinder Number ALM022588
Cylinder Pressure 1900 psig

Certification Date 4-19-93
Previous Certification Dates None

General Exp. Date 4-19-96
Acid Rain Exp. Date 10-19-94

ANALYZED CYLINDER

Components
Carbon Monoxide

Certified Concentration
60.08 ppm

Analytical Uncertainty*
±1% NIST Directly Traceable

Balance Gas: NITROGEN

*Analytical uncertainty is inclusive of usual known error sources which at least includes reference standard error & precision of the measurement processes.

REFERENCE STANDARD

Type CRM 1679
Expiration Date 12-20-94

Cylinder Number
AAL1355

Concentration
96.67 ppm CO in N₂

INSTRUMENTATION

Instrument/Model/Serial #
CO: Horiba/OPE 144E/560172153

Last Date Calibrated
4-6-93


Analytical Principle
Non-Dispersive Infrared

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components	First Triad Analysis	Second Triad Analysis	Calibration Curve
Carbon Monoxide	Date: 4-12-93 Response Units: mv Z1=0.00 R1=170.0 T1=106.4 R2=170.0 Z2=0.00 T2=106.4 Z3=0.00 T3=106.4 R3=170.0 Avg. Conc. of Cust. Cyl. 60.13 ppm	Date: 4-19-93 Response Units: mv Z1=0.00 R1=170.0 T1=106.2 R2=170.0 Z2=0.00 T2=106.2 Z3=0.00 T3=106.2 R3=170.0 Avg. Conc. of Cust. Cyl. 60.02 ppm	Concentration=A+Bx+Cx²+Dx³+Ex⁴ r=0.99999 CRM 1679 Constants: A=0.02233189 B=0.5597086 C=0.000053352 D=0 E=0
			Concentration=A+Bx+Cx²+Dx³+Ex⁴
			Concentration=A+Bx+Cx²+Dx³+Ex⁴

Special Notes

If this product is used for Acid Rain Rule Compliance, the Acid Rain Expiration Date noted above applies per 40 CFR Part 75, Appendix H. Otherwise, the General Expiration Date applies.


Analyst Frank P. Doran



Scott Specialty Gases, Inc.

1290 COMBERMERE STREET, TROY, MI 48083

(313) 589-2950 FAX: (313) 589-2134

CERTIFICATE OF ANALYSIS: EPA PROTOCOL GAS

Customer

FUGRO MCCLELLAND
MR. TODD SATLEY
9921 ST CHARLES ROCK RD
ST ANN MO 63074

Assay Laboratory

Scott Specialty Gases, Inc.
1290 Combermere
Troy, MI 48083

Purchase Order H145
Scott Project # 549824

ANALYTICAL INFORMATION

Certified to exceed the minimum specifications of EPA Protocol 1 Procedure # G1, Section Number 3.0.4

Cylinder Number ALM016785
Cylinder Pressure 1900 psig

Certification Date 4-19-93
Previous Certification Dates None

General Exp. Date 4-19-96
Acid Rain Exp. Date 10-19-94

ANALYZED CYLINDER

Components

Carbon Monoxide

Certified Concentration

30.47 ppm

Analytical Uncertainty*

±1% NIST Directly Traceable

Balance Gas: NITROGEN

*Analytical uncertainty is inclusive of usual known error sources which at least includes reference standard error & precision of the measurement processes.

REFERENCE STANDARD

Type Expiration Date
CRM 1679 12-20-94

Cylinder Number
AAL1355

Concentration
96.67 ppm CO in N₂

INSTRUMENTATION

Instrument/Model/Serial #
CO: Horiba/OPE 144E/560172153

Last Date Calibrated
4-6-93

Analytical Principle
Non-Dispersive Infrared

ANALYZER READINGS (Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

Components	First Triad Analysis	Second Triad Analysis	Calibration Curve
Carbon Monoxide	Date: 4-12-93 Response Units: mv Z1=0.00 R1=170.0 T1=54.20 R2=170.0 Z2=0.00 T2=54.20 Z3=0.00 T3=54.20 R3=170.0 Avg. Conc. of Cust. Cyl. 30.47 ppm	Date: 4-19-93 Response Units: mv Z1=0.00 R1=170.0 T1=54.20 R2=170.0 Z2=0.00 T2=54.20 Z3=0.00 T3=54.20 R3=170.0 Avg. Conc. of Cust. Cyl. 30.47 ppm	Concentration=A+Bx+Cx²+Dx³+Ex⁴ r=0.99999 CRM 1679 Constants: A=-0.02233189 B=0.5597086 C=0.000053352 D=0 E=0
			Concentration=A+Bx+Cx²+Dx³+Ex⁴
			Concentration=A+Bx+Cx²+Dx³+Ex⁴

Special Notes

If this product is used for Acid Rain Rule Compliance, the Acid Rain Expiration Date noted above applies per 40 CFR Part 75, Appendix H. Otherwise, the General Expiration Date applies.

Analyst Frank P. Doran



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALEMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS8U

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER 022293-3

REFERENCE STANDARD

COMPONENT	NIST SRM NO.	CYLINDER NO.	CONCENTRATION
OXYGEN GHIS	vs 2629a	632487	21.00 %

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	OXYGEN	GHIS	ANALYZER MAKE-MODEL-S/N	Siemens Oxymat 5E S/N A12-839
ANALYTICAL PRINCIPLE		Paramagnetic		LAST CALIBRATION DATE 12/08/92
FIRST ANALYSIS DATE		03/01/93		SECOND ANALYSIS DATE
Z 0.00	R 21.00	C 20.05	CONC. 20.05 %	Z R C CONC.
R 21.00	Z 0.00	C 20.00	CONC. 20.00 %	R Z C CONC.
Z 0.00	C 20.05	R 21.00	CONC. 20.05 %	Z C R CONC.
U/M %		MEAN TEST ASSAY	20.03 %	U/M % MEAN TEST ASSAY

THIS CYLINDER NO. SA-6957

HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1

PROCEDURE G1

CERTIFIED ACCURACY ± 1 % NIST TRACEABLE

CYLINDER PRESSURE 2000 PSIG

CERTIFICATION DATE 03/01/93

EXPIRATION DATE 09/01/94

CERTIFIED CONCENTRATION

OXYGEN	20.03 %
NITROGEN	BALANCE

ANALYZED BY

MARIA E. ROCHON

CERTIFIED BY

KWAN T. YOUNG



213-585-2154
FAX# 213-585-0582

LIQUID CARBONIC

CYLINDER GAS PRODUCTS

5700 SOUTH ALEMEDA STREET • LOS ANGELES, CALIFORNIA 90058

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS8U

CUSTOMER ENV. & INDUST. DIST.

P.O NUMBER 022293-3

REFERENCE STANDARD

COMPONENT		NIST SRM NO.	CYLINDER NO.	CONCENTRATION
OXYGEN	GHIS	vs 2629a	632487	21.00 %

ANALYZER READINGS

R=REFERENCE STANDARD

Z=ZERO GAS

C=GAS CANDIDATE

1. COMPONENT	OXYGEN	GHIS	ANALYZER MAKE-MODEL-S/N	Siemens Oxymat 5E	S/N A12-839
ANALYTICAL PRINCIPLE		Paramagnetic		LAST CALIBRATION DATE	12/08/92
FIRST ANALYSIS DATE		03/01/93		SECOND ANALYSIS DATE	
Z 0.00	R 21.00	C 20.05	CONC. 20.05 %	Z	R C CONC.
R 21.00	Z 0.00	C 20.00	CONC. 20.00 %	R	Z C CONC.
Z 0.00	C 20.05	R 21.00	CONC. 20.05 %	Z	C R CONC.
U/M %		MEAN TEST ASSAY	20.03 %	U/M %	MEAN TEST ASSAY

THIS CYLINDER NO. SA-6957
HAS BEEN CERTIFIED ACCORDING TO SECTION 3.0.4
OF TRACEABILITY PROTOCOL NO. 1
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 2000 PSIG
CERTIFICATION DATE 03/01/93
EXPIRATION DATE 09/01/94

CERTIFIED CONCENTRATION
OXYGEN 20.03 %
NITROGEN BALANCE

ANALYZED BY

MARIA E. ROCHON

CERTIFIED BY

KWAN T. YOUNG