

Note: This is a reference cited in *AP 42, Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP-42 Section 11.6
 Reference 32
 Report Sect. 4
 Reference 22

Source category: Portland Cement
 Plant name : Lehigh Portland Cement Co.
 Test date : 11/8 - 11/9/84
 Process : wet

Date: 01/12/93
 Location: Cementon, NY
 Ref. No.: 26
 Basis for process rate : kiln feed in GPM

Source	Type of control	Pollutant	Run No.	Emission rate, lb/hr	Process rate, ton/hr	Emission factor		Volumetric flow rate, DSCFM	Concen ppm
						kg/Mg	lb/ton		
rotary kiln (coal-fired)	ESP	BASED ON KILN FEED RATE IN GPM CONVERTED TO CLINKER PRODUCTION RAT							
		filt. PM	1	8.50	62.5	0.0680	0.136		
		filt. PM	2	8.60	62.5	0.0688	0.138		
		filt. PM	3	12.00	63.3	0.0948	0.190		
		AVERAGE				0.0772	0.154	RATING:	C
		SO2	1	1,256	62.5	10.0	20.1		
		SO2	2	1,196	62.5	9.57	19.1		
		SO2	3	980	63.3	7.74	15.5		
		AVERAGE				9.12	18.2	RATING:	C
		CO2	1	116,430	62.5	931	1,863	105,726	16.1
		CO2	2	96,904	62.5	775	1,550	99,072	14.3
		CO2	3	121,915	63.3	963	1,926	110,707	16.1
		AVERAGE				890	1,780	RATING:	C

Notes: 1. Data rated C because of uncertainty of process rates and poor documentation.

عدد

71500-2007

Reference SZ:
(1) Coal-fired wet
Process kiln w/ESP

**COMPLIANCE TEST
PARTICULATE AND SULFUR (**

CEMENTON KI

Date: Rating C
Process date unclear
(Gf not wt.)

**PREPARED FOR:
LEHIGH PORTLAND CEMENT COMPANY
CEMENTON FACILITY
CEMENTON, NEW YORK
GREENE COUNTY**

**PREPARED BY:
R. L. BAKER
KVB, INC .
ENGINEERING AND RESEARCH DIVISION**

DECEMBER 1984



CONTENTS

<u>Section</u>	<u>Page</u>
1.0 INTRODUCTION	1-1
2.0 SUMMARY OF TEST RESULTS	2-1
3.0 KILN DESCRIPTION	3-1
4.0 EMISSION SAMPLING AND ANALYSIS	4-1
4.1 Sampling Plane and Traverse Point Location	4-1
4.2 Velocity Traverse	4-1
4.3 Particulate Sampling Procedures	4-3
4.4 Laboratory Procedures	4-5
4.5 Data Reduction	4-6
4.6 Calibration Data	4-7
REFERENCES	R-1
APPENDICES:	
A. METHOD 5 COMPUTER REDUCED DATA	A-1
B. METHOD 5 RAW DATA	B-1
C. KILN OPERATIONAL DATA	C-1
D. ELECTROSTATIC PRECIPITATOR OPERATIONAL DATA	D-1
E. CYCLONIC FLOW DATA	E-1
F. LABORATORY SUMMARY	F-1
G. CALIBRATION DATA	G-1
H. KVB DATA REDUCITON FORMULAE	H-1
I. SAMPLE EMISSIONS CALCULATIONS	I-1
J. FUEL ANALYSIS	J-1
K. CHAIN OF CUSTODY FORMS	K-1
L. COMMUNICATIONS WITH NYS-DEC	L-1
M. SULFUR ANALYSIS DATA	M-1

FIGURES

<u>Figure</u>		<u>Page</u>
3-1	Lehigh Portland Cement, Cementon Facility - Kiln Exhaust Gas Path and Sampling Port Location	3-2
4-1	Stack Sample Plane and Sample Point Matrix	4-2
4-2	EPA Methods 5 and 6 Combined Emissions Train	4-4

<u>Table</u>		<u>Page</u>
2-1	Particulate Emissions Results	2-1
2-2	Sulfur Emissions Results	2-2
4-1	Weight and Volume Summary	4-6
4-2	Particulate Loadings and Percent Isokinetic	4-7

SECTION 1.0

INTRODUCTION

A series of particulate emission compliance tests was conducted by KVB Inc. on the kiln at the Lehigh Portland Cement Company located in Cementon, New York during November 8-9, 1984. The purpose of this program was to demonstrate compliance with the New York State Department of Environmental Conservation's particulate emissions limitation of 0.05 grains per dry standard cubic foot and the sulfur emissions limitation of 1.9 pounds per 10^6 Btu. Testing was completed within two months of the September start up during which extensive repairs were made to the electrostatic precipitator.

The compliance test series consisted of three EPA Method 5 tests with a Method 6 sulfur dioxide impinger train conducted at the kiln exhaust after an electrostatic precipitator. Throughout the testing, the facility was operating at its present maximum sustained output of approximately 1500 tons per day of clinker (400 GPM slurry input) while firing approximately 16.5 tons per hour of pulverized coal.

Visual opacity readings were taken throughout the two-day test period in accordance with EPA Method 9 procedures by a NYS DEC Region IV representative, Mr. Ronald Daoust. Particulate emissions testing at the stack was conducted by KVB, Inc. and observed by a NYS DEC representative, Mr. Bruce Gould. Mr. Richard Forgea of the NYS DEC Region IV reviewed the test protocol prior to the initial day of testing and was cognizant of all the test methods and procedures employed.

The particulate emissions test series was conducted by KVB, Inc. under the direction of Mr. R. L. Baker, Project Engineer, assisted by Mr. P. C. Coviello, Principal Technician and Mr. R. A. Parker, Senior Technician.

This report contains the results of the particulate emissions tests and associated documentation of the raw data, reduced data, and test conditions. Applicable pre-test data, field test data, operational data, and

reduced data are presented in the appendices. The fuel analysis presented in this report indicates the results of individual samples taken during each compliance test day.

SECTION 2.0

SUMMARY OF TEST RESULTS

The results of the particulate emission compliance test conducted on the kiln exhaust stack of Lehigh's Cementon facility in Cementon, New York, are presented in Table 2-1. This data represents the emission level of the kiln exhaust stack while firing pulverized coal to produce approximately 1500 tons per day of Portland cement. The applicable emissions limitation for this facility is 0.05 grains per dry standard cubic foot.

TABLE 2-1. PARTICULATE EMISSIONS RESULTS

Date	Test No.	Time Period (hr)	Particulate Emissions	
			Gr/DSCF*	lb/hr**
11/8/84	LC Comp 1	1525 - 1657	0.009	8.5
11/9/84	LC Comp 2	1316 - 1428	0.010	8.6
11/9/84	LC Comp 3	1610 - 1722	0.013	12.0
AVERAGE			0.011	9.7

*Standard conditions 68°F and 29.92 in Hg at stack oxygen level

**Based on stack velocity method of analysis

The emissions levels in Table 2-1 were computed through KVB's Emission Data Reduction Computer Program (See Appendix A and H) which is in accordance with the appropriate EPA methods. The raw test data taken during each test appears in Appendix B.

A representative of the NYS DEC Region IV was present at the test site during the initial compliance testing day and was fully cognizant of the testing procedures used. The results indicate that the particulate emission levels for the Cementon kiln are well below the 0.05 GR/DSCF limit. The compliance test filters are being preserved and are available for inspection by the NYS DEC upon request.

Visible opacity was recorded using EPA Method 9 and was conducted during each day of compliance testing by a NYS DEC Region IV representative.

The sulfur dioxide emissions testing was conducted to demonstrate compliance with the 1.9 pound per million Btu regulation. Results of the sulfur testing, run concurrently with the particulate testing, appears below in Table 2-2.

TABLE 2-2. SULFUR EMISSIONS RESULTS

Date	Test No.	Test Period	Sulfur Emissions		
			ppm at 3% as SO ₂	lb/hr S	lb/10 ⁶ Btu
11/8/84	LC Comp 1	1525 - 1657	1540	628	1.48
11/9/84	LC Comp 2	1316 - 1428	1537	598	1.42
11/9/84	LC Comp 3	1610 - 1722	1205	490	1.17
AVERAGE			1427	571	1.36

SECTION 3.0

KILN DESCRIPTION

The Lehigh Portland Cement facility consists of a single wet process kiln manufactured by Allis Chalmers. The original design capacity of the kiln was approximately 1500 tons of clinker production per day (TPD). The 550-foot long kiln is normally fired on pulverized coal. Pertinent kiln operational data taken during the compliance testing is included as Appendix C.

The exhaust gases exit the kiln and enter a western electrostatic precipitator (ESP) prior to entering a single 270-foot stack. The kiln gases are drawn from the clinker cooler by the use of an induced draft fan situated at the base of the stack. A schematic of the exhaust gas path and the location of the sampling plane is illustrated in Figure 3-1. Operational data documenting the power levels which existed in the ESP appear in Appendix D.




Figure 3-1. Lehigh Portland Cement, Cementon Facility - Kiln Exhaust Gas Path and Sampling Port Location

SECTION 4.0

EMISSION SAMPLING AND ANALYSIS

The various procedures used in stack sampling, laboratory analyses and data reduction are described and discussed in the following sections.

4.1 SAMPLING PLANE AND TRAVERSE POINT LOCATION

Testing was performed in the stack at test ports located 5.50 diameters downstream of the last flow disturbance and 14.0 diameters upstream of the stack exit. Figure 4-1 illustrates the sampling location at the Cementon facility. Twenty-four sampling points were specified by EPA Method 1. There are two ports installed 90 degrees apart in the stack, therefore, 12 points were sampled in each port. Sample point locations are presented in Figure 4-1.

4.2 VELOCITY TRAVERSE

The gas velocity was measured at the traverse points specified in Figure 4-1, using an "S" type pitot tube. The presence of cyclonic flow was quantified by the following procedure. The pitot tube was positioned at each of the traverse points such that the face openings are perpendicular to the stack cross-sectional plane. A null (zero) reading at "0° Reference" was construed to indicate the absence of cyclonic flow. If the reading was not zero, the pitot tube was rotated in increments until a null reading was obtained. The absolute angle of a null reading was recorded in degrees as a deviation from the perpendicular, and the summation of all the traverse points was calculated. The resultant overall average for the sampling plane averaged 1.4 degrees which is within the acceptable limit (10 degrees). The cyclonic flow check was performed at a steady state condition under normal production rate conditions. This data is included as Appendix E.




Figure 4-1. Stack Sample Plane and Sample Point Matrix

4.3 PARTICULATE SAMPLING PROCEDURES

Particulate sampling was in accordance with the EPA Method 5. Particulate matter was collected by out-of-stack filtration utilizing the basic configuration shown in Figure 4-2. A 14-foot heated inconcel probe was utilized for the sampling. The sampled gases passed directly from the probe into a glass housing which contained a preweighed 11 cm glass fiber filter. The glass filter material, Reeve Angel Grade 934 AH, had been previously shown to be chemically inert having a pH of seven. The filter housing was contained in a small oven thermostatically controlled to maintain a temperature no higher than 320°F.

After the filter, the flue gas sample was drawn through a flexible vacuum line to six Greenburg-Smith impingers maintained below 68°F. The first and second impingers each were filled with 100 ml of IPA 80 percent in water to serve as condensers. The third was left dry and the fourth and fifth contained approximately 100 ml of hydrogen peroxide, followed by a blank and finally 250 grains of weighed silica gel. The outlet of the last impinger was connected by an umbilical cord to a RAC Stacksampler meter/control box. The meter/control box contained a vacuum pump, regulation valves, instantaneous flow meter, integrating flowmeter, pitot tube, manometer and vacuum gauge. Flowrates were adjusted to obtain isokinetic sampling utilizing the RAC Stacksampler box and associated nomographs.

Sampling times of three minutes per traverse point were used for each test, yielding a total test time of 72 minutes. Prior to and after each test, the sampling train was checked for leakage. A seal was placed over the end of the sampling nozzle and a vacuum was drawn. For the pre-test check, a 15" Hg vacuum pressure was drawn for the post-test check, the vacuum was at least equal to the highest vacuum recorded during the testing. A leakage rate equal to or less than 0.02 cfm was considered acceptable. The pitot tubes were also checked before each test in accordance with the procedure outlined in the FEDERAL REGISTER.

At each point the various sample train parameters were recorded; the raw data are presented in Appendix B.




Figure 4-2. EPA Methods 5 and 6 Combined Emissions Train

Required O₂ measurements were obtained using a portable Teledyne analyzer, calibrated on ambient air which drew the sample from a tap located at the gas exit of the RAC box. The excellent correspondence between Teledyne and Orsat analysis has been witnessed by personnel from EPA, as well as the NYS DEC and was therefore, approved for use during the compliance testing, at the pre-test conference. Orsat analyses were run on a two-port composite sample collected in a Tedlar bag for each of the compliance tests.

A pulverized coal fuel sample was taken during each test day, and the analysis of a composite sample was used to reduce the data. The fuel analysis was performed by an independent laboratory (Warner Laboratories) and a copy is presented in Appendix J.

4.4 LABORATORY PROCEDURES

The reported particulate emissions are a combination of the particulate matter collected on the glass filter and the particulate matter deposited on the sampling nozzle, probe and upstream filter housing which are recovered with an acetone rinse.

Prior to testing a series of filters were held in a desiccator for 24 hours and weighed. Immediately following each test the filter was weighed and promptly transferred to a desiccator for a period not less than 24 hours prior to final weighing. The particulate matter upstream of the filter was collected by rinsing the sampling probe and all associated glassware with acetone, brushing the sampling probe to loosen adhered particles, rinsing the brush and probe again and collecting the entire rinse in a tared beaker. This acetone rinse was evaporated to dryness using a warm air flow. The sample handling history is summarized in the chain of custody forms in Appendix K.

The resultant collected samples were cooled in an ambient desiccator and weighed to the nearest 0.1 milligram. The tare and final weights for each test are presented in Appendix F.

The volumes of water from the flue gas samples were determined by measuring the volume in the flexible hose (filter housing to first impinger) and impingers plus the weight difference of the silica gel. A summary of the

filter weights, wash weights, condensate volumes and dry gas volumes are presented in Table 4-1.

TABLE 4-1. WEIGHT AND VOLUME SUMMARY

Test No.	Filter Wt. (mg)	Wash Wt. (mg)	Total Wt. (mg)	Condensate VOL. (ml)	Meter Sample VOL. (SCF)*
LC Comp 1	18.6	11.9	30.5	430.5	51.491
LC Comp 2	16.6	14.9	31.5	431.0	47.825
LC Comp 3	21.6	20.4	42.0	456.5	49.948

*Dry at 68°F and 29.92 Hg

4.5 DATA REDUCTION

The particulate data reduction technique utilized KVB's computerized particulate emissions data reduction program which uses the EPA "F Factor" method presented in the FEDERAL REGISTER of August 18, 1977 (Volume 42, Number 160) and June 11, 1979 (Volume 44, Number 113). The actual equations used by the KVB program are presented in Appendix H. Sample calculations for each compliance test appear in Appendix I.

Input to the computer program includes the raw sampling data, laboratory weights, kiln operational data and the fuel analysis. The computer output contains the final particulate mass loadings in various units, the fuel analysis, operational data and the percent of isokinetic sampling. The percent isokinetic samplings for the tests ranged from 102.3 to 106.7 percent. Included in the output is a listing of the individual sampling point raw data and the individual sampling point velocities. Average values for each variable are listed. The printed outputs are presented in Appendix A.

Table 4-2 contains a summary of the particulate mass loadings and percent isokinetic sampling for each of the compliance test runs.

TABLE 4-2. PARTICULATE LOADINGS AND PERCENT ISOKINETIC

Test No.	Particulate Mass Loadings		Percent of Isokinetic
	GR/DSCF	LB/HR	
LC Comp 1	0.009	8.5	105.3
LC Comp 2	0.010	8.6	106.7
LC Comp 3	0.013	12.0	102.3
AVERAGE	0.011	9.7	104.8

4.6 CALIBRATION DATA

Equipment for the testing was calibrated under the following conditions by KVB personnel. Appendix G presents the calibration data.

1. Precalibration of the dry gas meter and flow orifice. These calibrations were performed at KVB facility. The flow range covered 0.5 to 4.5 inches H₂O of orifice manometer setting (ΔH).
2. Postcalibration of the dry gas meter and flow orifice. These calibrations were performed at KVB facility as specified in the FEDERAL REGISTER (Volume 39, No. 177, September 11, 1974). A series of three post calibrations were performed on each metering system utilized for compliance testing at the average ΔH and at the maximum vacuum experienced during the testing.
3. Probe nozzle calibration. The 3/8" nominal size orifice was calibrated on site using a set of inside calipers. Four diameters were measured. The resultant mean diameter was 0.376 inches.
4. Pitot tube calibration. The pitot tubes were calibrated by Nutech Corporation outlined in the FEDERAL REGISTER, June 8, 1976, Volume 41, No. 111.

REFERENCES.

1. FEDERAL REGISTER, Vol. 36, No. 247, December 23, 1971, and Vol. 39, No. 177, September 11, 1974.
2. New York State Environmental Conservation Law 3-0301, 19-0301, Sec. 220.1, 220.2, and 225.0.
3. "Compliance Test Protocol - Particulate and Sulfur Oxide Emissions, Cementon Kiln," KVB, Inc., November 1984, KVB TM No. 71-71500-TP, R. Baker.

APPENDIX A

METHOD 5 - COMPUTER REDUCED DATA

KVB, INC. 18006 SKYPARK BLVD. IRVINE, C.A. 92714 (714) 250-6200

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH PORTLAND CEMENT
LOCATION - CEMENTON NY
UNIT(S) - KILN EXHAUST STACK
TEST DATE - 11-8-84
TEST NO. - COMPLIANCE 1
TEST SITE - STACK

***** FUEL ANALYSIS *****

COAL	PCT BY WT	MOLES/LB-FUEL
CARBON	69.39	5.783(-02)
HYDROGEN	4.73	4.730(-02)
SULFUR	2.66	8.313(-04)
OXYGEN	5.81	1.816(-03)
NITROGEN	1.26	4.500(-04)
ASH	16.15	

HIGH HEATING VALUE(BTU/LB)	12606.00
EPA 'F FACTOR'(DSCF/MBTU)	9702.0

***** ORSAT ANALYSIS *****

	PCT BY VOLUME
CARBON DIOXIDE	16.10
OXYGEN	8.00
CARBON MONOXIDE	0.02
NITROGEN	47.62
WATER	28.26

***** TEST CONDITIONS *****

KILN FEED(GPM)	400.0
TOTAL HEAT INPUT(KBTU/HR)	423561.6
FUEL FLOW(LB/HR)	33600.0
BAROMETRIC PRESSURE(IN. HG)	29.85
STACK GAS STATIC PRESS(IN H2O)	-0.55
NOZZLE DIAMETER(IN)	0.376
PITOT TUBE COEFFICIENT	0.840
DUCT AREA AT SAMPLING PLANE(SQ. FT)	122.7
PROBE LENGTH (FT)	14.0
PROBE MATERIAL	INCONEL

***** FLUE GAS PARAMETERS *****

MOLECULAR WEIGHT DRY(COMBINED)	31.60
MOLECULAR WEIGHT WET(COMBINED)	27.76
MOLECULAR WEIGHT DRY(ORSAT)	32.04
MOLECULAR WEIGHT WET(ORSAT)	28.07
PERCENT MOISTURE(MEASURED)	28.26
ACFM AT SAMPLING PLANE BASED ON:	
FUEL FLOW AND COMBUSTION CHEMISTRY	192765.2
STACK VELOCITY	237043.9

KVB, INC. 18006 SKYPARK BLVD. IRVINE, C.A. 92714 (714) 250-6200

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH PORTLAND CEMENT
LOCATION - CEMENTON NY
UNIT(S) - KILN EXHAUST STACK
TEST DATE - 11-8-84
TEST NO. - COMPLIANCE 1
TEST SITE - STACK

***** PARTICULATE DATA *****

PARTICULATE MASS(MG)	30.50
CONDENSATE VOLUME(ML)	430.50
CONDENSATE VOLUME(SCF)	20.279
DRY GAS METERED VOLUME(DSCF)	51.491
AVERAGE O2 MEASURED(%)	7.33
TOTAL DURATION OF TEST(MINUTES)	72.00

* EMISSIONS BASED ON VELOCITY AND FUEL FLOW METHOD *

LB/DSCF	1.306(-06)
LB/WSCF	9.369(-07)
GRAINS/ACF	4.166(-03)
GRAINS/DSCF	9.141(-03)
GRAINS/WSCF	6.558(-03)
LB/HR(BASED ON STACK VELOCITY)	8.465(00)
LB/HR(BASED ON FLUE GAS COMPOSITION)	6.883(00)
PERCENT ISOKINETIC SAMPLING	105.34

KVB, INC. 18006 SKYPARK BLVD. IRVINE, C.A. 92714 (714) 250-6200

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH PORTLAND CEMENT
LOCATION - CEMENTON NY
UNIT(S) - KILN EXHAUST STACK
TEST DATE - 11-8-84
TEST NO. - COMPLIANCE 1
TEST SITE - STACK

IDENT.	TIME (MIN)	VOLUME (CU FT)	O2 (%)	DEL P (IN H2O)	DEL H	T-METER (F)	T-STACK (F)	GAS VEL (FT/SEC)
N12	3.00	2.114	7.60	0.19	1.80	52.0	370.0	31.3
N11	3.00	2.030	7.60	0.19	1.80	55.0	370.0	31.3
N10	3.00	2.030	7.70	0.18	1.70	57.0	370.0	30.5
N9	3.00	2.100	7.70	0.20	1.90	58.0	370.0	32.1
N8	3.00	2.120	7.40	0.20	1.90	66.0	370.0	32.2
N7	3.00	2.220	7.50	0.23	2.10	65.0	370.0	34.5
N6	3.00	2.330	7.50	0.29	2.70	66.0	370.0	38.7
N5	3.00	2.230	7.50	0.23	2.10	67.0	371.0	34.5
N4	3.00	2.220	6.60	0.21	2.00	68.0	370.0	33.0
N3	3.00	2.150	6.50	0.20	1.85	67.0	371.0	32.2
N2	3.00	1.750	6.60	0.15	1.40	67.0	371.0	27.9
N1	3.00	2.038	6.60	0.14	1.30	67.0	365.0	26.9
W12	3.00	2.400	7.20	0.26	2.35	63.0	370.0	36.7
W11	3.00	2.250	7.20	0.26	2.35	66.0	370.0	36.7
W10	3.00	2.360	7.20	0.28	2.55	68.0	370.0	38.1
W9	3.00	2.390	7.40	0.27	2.50	70.0	370.0	37.4
W8	3.00	2.270	7.40	0.23	2.10	71.0	370.0	34.5
W7	3.00	2.230	7.40	0.22	2.05	71.0	369.0	33.7
W6	3.00	2.210	7.50	0.20	1.85	72.0	370.0	32.1
W5	3.00	2.090	7.60	0.16	1.45	72.0	365.0	28.7
W4	3.00	2.040	7.60	0.17	1.60	72.0	364.0	29.5
W3	3.00	1.960	7.50	0.15	1.40	73.0	362.0	27.7
W2	3.00	1.900	7.50	0.14	1.30	73.0	360.0	26.7
W1	3.00	1.795	7.60	0.13	1.20	73.0	357.0	25.7

TOTAL 72.00 51.227

AVERAGE 7.33 0.20 1.89 66.6 368.1 32.2

** NOTE ** AVERAGE OF DELTA P'S BY SUM OF SQUARE ROOTS **

KVB, INC. 18006 SKYPARK BLVD. IRVINE, C.A. 92714 (714) 250-6200

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH PORTLAND CEMENT
LOCATION - CEMENTON NY
UNIT(S) - KILN EXHAUST STACK
TEST DATE - 11-9-84
TEST NO. - COMPLIANCE 2
TEST SITE - STACK

***** FUEL ANALYSIS *****

COAL	PCT BY WT	MOLES/LB-FUEL
CARBON	70.68	5.890(-02)
HYDROGEN	4.83	4.830(-02)
SULFUR	2.40	7.500(-04)
OXYGEN	5.53	1.728(-03)
NITROGEN	1.30	4.643(-04)
ASH	15.26	

HIGH HEATING VALUE(BTU/LB)	12812.00
EPA 'F FACTOR'(DSCF/MBTU)	9727.0

***** ORSAT ANALYSIS *****

	PCT BY VOLUME
CARBON DIOXIDE	14.30
OXYGEN	7.80
CARBON MONOXIDE	0.07
NITROGEN	48.03
WATER	29.80

***** TEST CONDITIONS *****

KILN FEED(GPM)	400.0
TOTAL HEAT INPUT(KBTU/HR)	420233.6
FUEL FLOW(LB/HR)	32800.0
BAROMETRIC PRESSURE(IN. HG)	29.79
STACK GAS STATIC PRESS(IN H2O)	-0.70
NOZZLE DIAMETER(IN)	0.376
PITOT TUBE COEFFICIENT	0.840
DUCT AREA AT SAMPLING PLANE(SQ. FT)	122.7
PROBE LENGTH (FT)	14.0
PROBE MATERIAL	INCONEL

***** FLUE GAS PARAMETERS *****

MOLECULAR WEIGHT DRY(COMBINED)	31.00
MOLECULAR WEIGHT WET(COMBINED)	27.12
MOLECULAR WEIGHT DRY(ORSAT)	31.70
MOLECULAR WEIGHT WET(ORSAT)	27.62
PERCENT MOISTURE(MEASURED)	29.80
ACFM AT SAMPLING PLANE BASED ON:	
FUEL FLOW AND COMBUSTION CHEMISTRY	175733.0
STACK VELOCITY	223463.0

KVB, INC. 18006 SKYPARK BLVD. IRVINE, C.A. 92714 (714) 250-6200

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH PORTLAND CEMENT
LOCATION - CEMENTON NY
UNIT(S) - KILN EXHAUST STACK
TEST DATE - 11-9-84
TEST NO. - COMPLIANCE 2
TEST SITE - STACK

***** PARTICULATE DATA *****

PARTICULATE MASS(MG)	31.50
CONDENSATE VOLUME(ML)	431.00
CONDENSATE VOLUME(SCF)	20.302
DRY GAS METERED VOLUME(DSCF)	47.825
AVERAGE O2 MEASURED(%)	6.75
TOTAL DURATION OF TEST(MINUTES)	72.00

* EMISSIONS BASED ON VELOCITY AND FUEL FLOW METHOD *

LB/DSCF	1.452(-06)
LB/WSCF	1.019(-06)
GRAINS/ACF	4.504(-03)
GRAINS/DSCF	1.016(-02)
GRAINS/WSCF	7.135(-03)
LB/HR(BASED ON STACK VELOCITY)	8.627(00)
LB/HR(BASED ON FLUE GAS COMPOSITION)	6.784(00)

PERCENT ISOKINETIC SAMPLING	106.73
-----------------------------	--------

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH PORTLAND CEMENT
 LOCATION - CEMENTON NY
 UNIT(S) - KILN EXHAUST STACK
 TEST DATE - 11-9-84
 TEST NO. - COMPLIANCE 2
 TEST SITE - STACK

IDENT.	TIME (MIN)	VOLUME (CU FT)	O2 (%)	DEL P (IN H2O)	DEL H	T-METER (F)	T-STACK (F)	GAS VEL (FT/SEC)
N12	3.00	2.178	6.50	0.19	1.75	61.0	370.0	31.8
N11	3.00	2.100	6.40	0.20	1.85	62.0	370.0	32.6
N10	3.00	2.250	6.40	0.20	1.85	65.0	370.0	32.6
N9	3.00	1.790	6.60	0.18	1.20	67.0	370.0	30.9
N8	3.00	1.720	6.60	0.11	1.00	67.0	370.0	24.2
N7	3.00	1.640	7.20	0.11	1.00	67.0	370.0	24.1
N6	3.00	1.750	7.20	0.13	1.20	70.0	370.0	26.2
N5	3.00	1.700	7.10	0.10	0.95	71.0	370.0	23.0
N4	3.00	1.850	7.10	0.09	0.85	71.0	370.0	21.8
N3	3.00	1.250	7.00	0.11	1.00	72.0	370.0	24.1
N2	3.00	1.500	7.00	0.10	0.95	72.0	370.0	23.0
N1	3.00	1.550	7.00	0.10	0.95	72.0	370.0	23.0
W12	3.00	2.350	6.40	0.25	2.30	67.0	370.0	36.4
W11	3.00	2.300	6.40	0.25	2.30	69.0	370.0	36.4
W10	3.00	2.550	6.60	0.32	3.00	73.0	370.0	41.2
W9	3.00	2.550	6.60	0.30	2.80	75.0	375.0	40.0
W8	3.00	2.320	6.80	0.25	2.35	76.0	376.0	36.5
W7	3.00	2.380	6.80	0.25	2.35	74.0	376.0	36.5
W6	3.00	2.250	6.60	0.23	2.10	75.0	375.0	35.0
W5	3.00	2.180	6.60	0.20	1.85	77.0	375.0	32.7
W4	3.00	2.170	6.80	0.20	1.85	78.0	373.0	32.6
W3	3.00	2.130	6.80	0.18	1.70	79.0	373.0	31.0
W2	3.00	1.860	6.80	0.13	1.20	79.0	370.0	26.3
W1	3.00	1.836	6.80	0.13	1.20	79.0	370.0	26.3

TOTAL 72.00 48.154

AVERAGE 6.75 0.17 1.65 71.6 371.4 30.4

** NOTE ** AVERAGE OF DELTA P'S BY SUM OF SQUARE ROOTS **

KVB, INC. 18006 SKYPARK BLVD. IRVINE, C.A. 92714 (714) 250-6200

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH CEM COMP3
LOCATION - CEMENTON NY
UNIT(S) - KILN EXHAUST STACK
TEST DATE - 11-9-84
TEST NO. - COMPLIANCE 3
TEST SITE - STACK

***** FUEL ANALYSIS *****

COAL	PCT BY WT	MOLES/LB-FUEL
CARBON	70.68	5.890(-02)
HYDROGEN	4.83	4.830(-02)
SULFUR	2.40	7.500(-04)
OXYGEN	5.53	1.728(-03)
NITROGEN	1.30	4.643(-04)
ASH	15.26	

HIGH HEATING VALUE(BTU/LB)	12812.00
EPA 'F FACTOR'(DSCF/MBTU)	9727.0

***** ORSAT ANALYSIS *****

	PCT BY VOLUME
CARBON DIOXIDE	16.10
OXYGEN	7.50
CARBON MONOXIDE	0.03
NITROGEN	46.27
WATER	30.10

***** TEST CONDITIONS *****

KILN FEED(GPM)	405.0
TOTAL HEAT INPUT(KBTU/HR)	420233.6
FUEL FLOW(LB/HR)	32800.0
BAROMETRIC PRESSURE(IN. HG)	29.79
STACK GAS STATIC PRESS(IN H2O)	-0.80
NOZZLE DIAMETER(IN)	0.376
PITOT TUBE COEFFICIENT	0.840
DUCT AREA AT SAMPLING PLANE(SQ. FT)	122.7
PROBE LENGTH (FT)	14.0
PROBE MATERIAL	INCONEL

***** FLUE GAS PARAMETERS *****

MOLECULAR WEIGHT DRY(COMBINED)	31.58
MOLECULAR WEIGHT WET(COMBINED)	27.49
MOLECULAR WEIGHT DRY(ORSAT)	32.11
MOLECULAR WEIGHT WET(ORSAT)	27.87
PERCENT MOISTURE(MEASURED)	30.10
ACFM AT SAMPLING PLANE BASED ON:	
FUEL FLOW AND COMBUSTION CHEMISTRY	188154.5
STACK VELOCITY	243087.8

KVB, INC. 18006 SKYPARK BLVD. IRVINE, C.A. 92714 (714) 250-6200

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH CEM COMP3
LOCATION - CEMENTON NY
UNIT(S) - KILN EXHAUST STACK
TEST DATE - 11-9-84
TEST NO. - COMPLIANCE 3
TEST SITE - STACK

***** PARTICULATE DATA *****

PARTICULATE MASS(MG)	42.00
CONDENSATE VOLUME(ML)	456.50
CONDENSATE VOLUME(SCF)	21.504
DRY GAS METERED VOLUME(DSCF)	49.948
AVERAGE O2 MEASURED(%)	7.28
TOTAL DURATION OF TEST(MINUTES)	72.00

* EMISSIONS BASED ON VELOCITY AND FUEL FLOW METHOD *

LB/DSCF	1.854(-06)
LB/WSCF	1.296(-06)
GRAINS/ACF	5.759(-03)
GRAINS/DSCF	1.298(-02)
GRAINS/WSCF	9.071(-03)
LB/HR(BASED ON STACK VELOCITY)	1.200(01)
LB/HR(BASED ON FLUE GAS COMPOSITION)	9.287(00)

PERCENT ISOKINETIC SAMPLING	102.31
-----------------------------	--------

KVB, INC. 18006 SKYPARK BLVD. IRVINE, C.A. 92714 (714) 250-6200

***** PARTICULATE EMISSIONS DATA REDUCTION PROGRAM *****

COMPANY - LEHIGH CEM COMP3
LOCATION - CEMENTON NY
UNIT(S) - KILN EXHAUST STACK
TEST DATE - 11-9-84
TEST NO. - COMPLIANCE 3
TEST SITE - STACK

IDENT.	TIME (MIN)	VOLUME (CU FT)	O2 (%)	DEL P (IN H2O)	DEL H	T-METER (F)	T-STACK (F)	GAS VEL (FT/SEC)
N12	3.00	2.055	7.80	0.20	1.70	70.0	373.0	32.4
N11	3.00	2.030	7.80	0.20	1.70	73.0	373.0	32.4
N10	3.00	2.070	7.60	0.20	1.70	76.0	375.0	32.4
N9	3.00	2.040	7.60	0.20	1.70	77.0	368.0	32.3
N8	3.00	2.040	7.20	0.20	1.70	78.0	358.0	32.1
N7	3.00	2.120	7.20	0.23	1.90	75.0	355.0	34.4
N6	3.00	2.320	7.20	0.30	2.50	79.0	355.0	39.3
N5	3.00	2.330	7.20	0.29	2.45	80.0	355.0	38.6
N4	3.00	2.280	7.30	0.27	2.25	81.0	354.0	37.2
N3	3.00	2.190	6.50	0.22	1.90	82.0	357.0	33.7
N2	3.00	2.030	6.50	0.18	1.50	82.0	357.0	30.5
N1	3.00	1.933	6.70	0.18	1.50	82.0	356.0	30.5
W12	3.00	2.400	7.20	0.26	2.40	78.0	370.0	36.9
W11	3.00	2.360	7.20	0.26	2.40	70.0	370.0	36.9
W10	3.00	2.430	7.40	0.27	2.50	72.0	375.0	37.7
W9	3.00	2.360	7.40	0.25	2.30	75.0	377.0	36.3
W8	3.00	2.400	7.40	0.27	2.50	76.0	377.0	37.7
W7	3.00	2.390	7.30	0.25	2.30	77.0	375.0	36.3
W6	3.00	2.210	7.30	0.20	1.90	78.0	375.0	32.5
W5	3.00	2.030	7.30	0.18	1.60	78.0	371.0	30.7
W4	3.00	1.910	7.40	0.15	1.30	78.0	370.0	28.0
W3	3.00	1.850	7.40	0.15	1.30	78.0	369.0	28.0
W2	3.00	1.560	7.40	0.10	0.87	78.0	365.0	22.8
W1	3.00	1.445	7.30	0.10	0.87	78.0	365.0	22.8

TOTAL 72.00 50.783

AVERAGE 7.28 0.21 1.86 77.1 366.5 33.0

** NOTE ** AVERAGE OF DELTA P'S BY SUM OF SQUARE ROOTS **

APPENDIX B

METHOD 5 RAW DATA

Time	METER CONDITIONS			TEMPERATURES, °F				Impingers In	Impingers Out	Meter In	Meter Out	O ₂ , %	Vac.
	ΔPs	ΔH	Meter Reading	Stack	Probe	Oven							
1525	.19	1.8	205.056	380	295	299	50	50	54	50	7.6	4	
1528	.19	1.8	207.17	380	302	300	50	50	58	52	7.6	4	
1531	.18	1.7	209.20	380	305	300	50	50	62	52	7.7	4	
1534	.20	1.9	211.23	380	302	302	50	50	66	53	7.7	4	
1537	.20	1.9	213.33	380	301	305	50	50	70	54	7.4	4	
1540	.23	2.1	215.45	380	300	305	50	50	74	56	7.5	4	
1543	.24	2.7	217.67	380	301	298	50	50	76	56	7.5	5	
1546	.23	2.1	220.00	371	301	290	50	50	79	56	7.5	5	
1549	.21	2.0	222.23	370	299	302	50	50	80	56	6.6	5	
1552	.20	1.85	224.45	371	297	304	50	50	81	56	6.5	5	
1555	.15	1.4	226.60	371	295	305	50	50	81	56	6.6	5	
1558	.14	1.3	228.35	365	299	304	50	50	81	56	6.6	5	
1601			230.388										
			LPAK CH 4000		END OF RUN								
		1879		823.166								51.339	
												.112	
				81.3								51.227	

Percent O₂ = 7.3

MM stack gas = ~28

Velocity = 32.4 f/Sec

Total Sample Time = 72 min.

ISOKINETICS = 103.2%

Particulate Emissions

lbs/10 BT

COMMENTS: OK SAT
 CO₂ : 16.1%
 O₂ : 8.0%
 CO (x100) : 214 PPM

18 730617 1147

11

AMBIENT TEMPERATURE, °F

METER VOL. (START/END)

LOCATION _____
 U. _____ FUEL _____
 OPERATORS _____

RAC BOX #

FTER LEARN CHECK:

Before test; Vac=	In.Hg.
Water Leak Rate=	CFM
After test; Vac=	In.Hg.
Water Leak Rate=	CFM

Nomograph Setup

$P_{\text{meter}} =$	$C =$
$P_{\text{stack}} =$	$T_{\text{stack}} =$
$T_{\text{meter}} =$	$\Delta P =$
$\Delta H_Q =$	$\text{Noz (Ideal)} =$
$\% \text{ H}_2\text{O} =$	$\text{Noz (Actual)} =$
	$\Delta =$



A Research-Centric Company

Imp.	Vol. (End)	Vol. (Start)	Δ Vol. (ml)	Filter #	Particulate Wt	Filter m	Acetone m	Total m
#1	—	—	—	4				
#2	—	—	—					
#3	—	—	—					
#4	—	—	—					
#5	—	—	—					
(Silica Gel)	—	—	—					
Total Vol. H ₂ O			ml					

61		71	
tot	Stack Press. In. Hg-Gauge	Barometric Pressure	
TEST RESULTS			
Test Averages:			
	ΔP_s	Tstack	$^{\circ}F$
	ΔH	Tmeter	$^{\circ}F$

Boiling Time Point, Min.	Particulate Wt., mg	Condensate Vol., ml	Fuel Flow gal/hr	Load MW	C _{pi}
11		21	31	41	51

[illegible]

METER CONDITIONS				TEMPERATURES, °F				O ₂ , %		Vac.	
Time	ΔPs	ΔH	Meter Reading	Stack	Probe	Oven	Impingers In	Impingers Out	Meter In	Meter Out	
1621	.26	2.35	220.500	370	295	305		50	66	60	5
1624	.26	2.35	232.90	370	300	305		50	70	61	5
1627	.28	2.52	235.15	370	305	305		50	75	61	5
1630	.27	2.50	237.51	370	302	311		50	78	62	5
1633	.23	2.1	239.90	370	301	308		50	80	62	5
1636	.22	2.05	241.17	369	298	299		50	81	62	5
1639	.20	1.85	244.40	370	297	296		50	82	63	5
1642	.16	1.45	246.61	365	286	304		50	80	64	4
1645	.17	1.6	248.70	364	296	287		50	81	64	4
1648	.15	1.40	250.74	362	296	278		50	83	64	4
1651	.14	1.3	252.70	360	296	280		50	83	64	3
1654	.13	1.2	254.60	357	295	285		50	83	64	3
1657			256.395								

Percent O₂ = _____

MM stack gas = _____ (~28 ft/sec)

Velocity = _____

Total Sample Time = _____ min.

ISOKINETICS = _____

Particulate Emissions _____ lbs/10⁶ BT

COMMENTS:

DATE: 11-9-84
 AMBIENT TEMPERATURE, °F: 45
 METER VOL. (START/END): 262.222/310.396
 OPERATORS: RC
 FUEL: _____
 RAC BOX # 513-1
 FILTER: 2

WATER LEAK CHECK:
 before test; Vac=10 In.Hg.
 meter Leak Rate=.004CFM
 after test; Vac=5 In.Hg.
 meter Leak Rate=.003CFM

Nomograph Setup
 P_{meter} = 99 C = .70
 P_{stack} = 380 T_{stack} = 380
 T_{meter} = 70 ΔP = .2
 ΔH₀ = 1.96 Noz (Ideal) = .375
 H₂O = 29 Noz (Actual) = .376

Imp. Vol. (End) Vol. (Start) ΔVol. (ml)
 #1 190 - 100 190 = 390
 #2 117 - 100 117 = 17
 #3 111 - 100 111 = 11
 #4 0 - 0 =
 #5 213 - 200 13
 (Silica Gel)
 Total Vol. H₂O 431 ml

Particulate Wt: _____
 Filter mg _____
 Acetone mg _____
 Total mg _____
 Filter # 5



11	21	31	41	51	61	71
3		431		1600	0.04	29.79
Flow Time	Particulate	Condensate	Fuel Flow	Load	Stack Press.	Barometric
Point, Min.	Wt., mg	Vol., ml	gal/hr		In. Hg-Gauge	Pressure

METER CONDITIONS				TEMPERATURES, °F				O ₂ , %	
Start Time	ΔPs	ΔH	Meter Reading	Stack	Probe	Oven	Impingers In	Impingers Out	Vac.
0	.19	1.75	262.222	370	299	310		45	62
3	.20	1.82	264.40	370	305	310		45	62
6	.120	1.82	266.50	370	305	310		45	62
9	.13	1.18	268.75	370	302	308		45	62
12	.11	1.0	270.54	370	300	304		45	62
15	.11	1.0	272.26	370	300	297		45	62
18	.13	1.2	273.90	370	300	295		45	62
21	.10	0.95	275.65	370	300	296		45	62
24	.109	.85	277.35	370	298	290		45	62
27	.11	1.0	279.20	370	298	285		45	62
30	.10	.95	281.45	370	298	285		45	62
33	.10	.95	281.95	370	298	285		45	62
36			283.500						

TEST RESULTS
 Test Averages:
 ΔPs = 216 T_{stack} = 371 °F
 ΔH = 1.65 T_{meter} = 70 °F
 Sample Vol. = 431 Ft³
 Percent O₂ = _____
 MW_{stack} gas = _____ (~28)
 Velocity = _____ ft/sec
 Total Sample Time = 72 min.
 ISO KINETICS = _____
 Particulate Emissions _____ lbs/10⁶ BT

COMMENTS:
 ODSAT
 CO₂: 14.3%
 O₂: 7.0%
 CO (calc): 6.91 ppm

11-9-54

AMBIENT TEMPERATURE, °F

METER VOL. (START/END)

OPERATORS RC

FUEL

RAC BOX # 513-1

LEAK CHECK:

Pre test: Vac = In.Hg. P_{meter} = C =

Per Leak Rate = CFM P_{stack} = T_{stack} =

Pre test: Vac = In.Hg. T_{meter} = ΔP =

Per Leak Rate = CFM ΔH₀ = Noz (Ideal) =

ΔH₀ = Noz (Actual) =

H₂O =

Nomograph Setup

Imp.	Vol. (End)	Vol. (Start)	ΔVol. (ml)
#1			
#2			
#3			
#4			
#5			
(Silica Gel)			

Particulate Wts

Filter mc

Acetone mc

Total mc

Filter #

Total Vol. H₂O ml

TEST RESULTS

Test Averages:

ΔP_s = °F

ΔH = °F

T_{stack} = °F

T_{meter} = °F

Sample Vol. = Ft³

Percent O₂ =

M_{stack} gas = (~28)

Velocity = ft/sec

Total Sample Time = min.

ISOKINETICS =

Particulate Emissions

 lbs/10⁶ BTU

COMMENTS:

Time	Particulate Wt., mg	Condensate Vol., ml	Fuel Flow gal/hr	Load MW	C pitot	Stack Press.		Meter		O ₂ %	Vac.
						In.Hg-Gauge	Barometric Pressure	In	Out		

TEMPERATURES, °F											
Time	METER CONDITIONS		Stack		Probe		Oven		Impingers		O ₂ %
	ΔP _s	ΔH	Meter Reading	Stack	Probe	Probe	Oven	Oven	In	Out	
0	.25	2.3	283.60	370	302	302	302	302	45	68	6.4
3	.25	2.3	282.85	370	310	310	310	310	45	68	6.4
6	.25	3.0	288.15	370	306	310	310	310	45	68	6.6
9	.30	2.8	290.70	375	306	310	310	310	45	68	6.6
12	.25	2.35	293.25	376	304	310	310	310	45	68	6.8
15	.25	2.35	295.57	376	295	302	302	302	45	68	6.8
18	.23	2.1	297.95	375	305	301	301	301	45	68	6.6
21	.20	1.85	300.22	375	303	296	296	296	45	69	6.6
24	.20	1.85	303.70	373	299	297	297	297	45	70	6.8
27	.18	1.7	304.57	373	299	298	298	298	45	71	6.8
30	.13	1.2	306.70	370	298	298	298	298	45	71	6.8
33	.13	1.2	308.56	370	298	297	297	297	45	71	6.8
36			310.396								

ION
OP TORS
RAC BOX # 513-1

AMBIENT TEMPERATURE, °F
METER VOL. (START/END)
11 9-84
55
34.700/365.483

Page 1
OF 2

WATER LEAK CHECK:
Before test: Vac=10 In.Hg.
Meter Leak Rate=.005 CFM
After test: Vac=5 In.Hg.
Meter Leak Rate=.004 CFM

Nomograph Setup
P_{meter} = 99 C = .70
P_{stack} = 300
T_{meter} = 70 ΔP = .2
Noz (Ideal) = 320
ΔH₀ = 1.96
Noz (Actual) = 376
H₂O = 21 Y =

Imp. Vol. (End) Vol. (Start) ΔVol. (ml)
#1 515 - 100 115 = 415
#2 121 - 100 121 = 21
#3 106 - 100 106 = 6
#4 0 - 0 = 0
#5 204.5 - 2009 = 14.5
(Silica Gel)
Particulate Wts
Filter mg
Acetone mg
Total mg



A Research-Cordell Company

Time Point, Min.	Particulate Wt., mg	Condensate Vol., ml	Fuel Flow gal/hr	Load MW	C Pitot	Stack Press. In. Hg-Gauge	Barometric Pressure	Sample Vol. Ft ³
3		456.5		1600 MW	.84	-80" Hg	29.79	50.763

TEST RESULTS
Test Averages:
ΔPs = 0.21 Tstack = 366 °F
ΔH = 1.9 Tmeter = 70 °F

Time	METER CONDITIONS				TEMPERATURES, °F				O ₂ %	Vac.
	ΔPs	ΔH	Meter Reading	Stack	Probe	Ovan	Impingers In	Impingers Out		
12	.26	2.4	347.00	370	280	364		45	67	7.2
13	.26	2.4	347.10	370	280	303		45	71	7.2
14	.27	2.5	349.46	375	283	305		45	75	7.4
15	.25	2.3	341.89	377	300	306		45	79	7.4
16	.27	2.5	344.25	377	304	302		45	82	7.4
17	.25	2.3	346.65	375	302	301		45	85	7.3
18	.20	1.9	329.09	375	304	300		45	87	7.3
19	.18	1.6	331.25	371	300	302		45	87	7.3
20	.15	1.3	333.28	370	299	299		45	87	7.4
21	.15	1.3	335.19	369	299	289		45	87	7.4
22	.10	.87	337.04	365	299	292		45	87	7.4
23	.10	.87	338.60	365	298	295		45	87	7.3
24			340.045							3

Percent O₂ =
MW stack gas = (~28)
Velocity = ft/sec
Total Sample Time = 22 min.
ISOKINETICS =
Particulate Emissions lbs/10⁶ BTU
COMMENTS: ACSAT
O₂ = 16.1 %
O₂ = 7.5 %
O (rho) = 346 mm

RAC BOX # 513-1

Core test; Vac=	In.Hg.
Water Leak Rate=	CFM
Core test; Vac=	In.Hg.
Water Leak Rate=	CFM



TEST RESULTS

Test Averages:

$\Delta P_s =$	_____	Tstack =	_____ °F
$\Delta H =$	_____	Tmeter =	_____ °F

Sample Vol. = Ft³

Vac.	Percent O ₂	"	"
7	MW stack gas	"	(~28
4	Velocity	"	ft/sec
4	Total Sample	"	"
4	Time	"	min.
4	ISOKINETICS	"	"
2			

Particulate Emissions _____ lbs/10⁶ BTU

COMMENTS:

APPENDIX C

KILN OPERATIONAL DATA



LEHIGH PORTLAND CEMENT - CEMENTION - KILN OPERATIONAL DATA - PROJECT #71500

DATE	11/8/84	ID FAN AMPS ^{KW/21}	340/210	320/200
TIME	12:35 15:10	ID FAN DAMPER %	100	100
TEST No.	PRETEST COMP-1	BACKEND DRAFT	-0.8	-0.8
DESCRIPTION		HOOD DRAFT	-0.05	-0.05
	TEST START	UNDERGRATE PRESS	11.8	11.5
	15:18	COMPARTMENT 1&2	11.0 105/100	11.2 105/100
COAL FEED ^{TPH} (LB/HR) _{TRAVEL}	17.0 17.0	COMPARTMENT 3&4	6.5 120/115	6.5 120/115
KILN FEED (GPM)	400 400	COMPARTMENT 5&6	NA 108	NA 108
KILN SPEED (RPM)	1.2 1.2	COMPARTMENT 7&8	NA	NA
KILN DRIVE AMPS ^{KVA}	112 110	COOLER SPEED #1/2	10/10	10/9
KILN SHELL TEMP	880 890	COOLER BED DEPTH	NA	NA
TOTALIZER ^{12:45}	03233 04643	KILN EXIT 02 ^{LEAKS} _{KVB}	2.5/	2.3/2.5
COAL MILL FEED ^{TPH}	16.5 16.8	KILN EXIT CO2	0.6 SAT	0.6 SAT
MILL INLET TEMP	320 390	QUENCH AIR DAMP	100	100
MILL OUTLET TEMP	170 190	EXCESS AIR DAMP	NA	NA
COAL MILL AMPS	26 27	PRIMARY AIR DAMP	100	100
MILL 200 MESH	LAB LAB	PRIMARY ^{KW} DILUTION-AIR DAMP	240 NA	230
MILL 100 MESH	LAB LAB	6K3 AMPS/DAMP	NA	NA
		SEC AIR TEMP	1975	2000
SLURRY DENSITY	LAB LAB	ESP IN PRES.	1.8	1.4
BACK END TEMP	440 460	A/B/CN/CS	ESP	
PRECHAIN TEMP	1660 1620	EPS PRI VOLTS		
MATERIAL TEMP	1190 1160	EPS PRI AMPS		
BURN ZONE TEMP	2680 2620	EPS SEC MILLIAMP		
CLINKER TEMP	2200 2180			



LEHIGH PORTLAND CEMENT - CEMENTON - KILN OPERATIONAL DATA - PROJECT #71500

DATE	11/8/84	ID FAN AMPS ^{KW} /SET	340/204
TIME	16:48	ID FAN DAMPER %	100
TEST No.	Comp 1	BACKEND DRAFT	-0.9
DESCRIPTION	JTK TEST	HOOD DRAFT	-0.05
		UNDERGRATE PRESS	13.0
		COMPARTMENT 1&2	10/6.8 105/100
COAL FEED ^{TPH} (LB/HR) _{TUNER}	16.6	COMPARTMENT 3&4	110/115
KILN FEED (GPM)	400	COMPARTMENT 5&6	105
KILN SPEED (RPM)	1.2	COMPARTMENT 7&8	NA
KILN DRIVE AMPS ^{KVA}	105	COOLER SPEED #1/2	10/10
KILN SHELL TEMP	870	COOLER BED DEPTH	NA
TOTALIZER	16152 05591	KILN EXIT O2 ^{LEIGH} _{W/B}	1.8/2.6
COAL MILL FEED ^{TPH}	16.9	KILN EXIT CO2	ASAT
MILL INLET TEMP	340	QUENCH AIR DAMP	NA
MILL OUTLET TEMP	175	EXCESS AIR DAMP	NA
COAL MILL AMPS	27	PRIMARY AIR DAMP	100
MILL 200 MESH	LAB	^{PRIMARY} _{DILUTION} AIR DAMP ^{KW}	235
MILL 100 MESH	LAB	6K3 AMPS/DAMP	NA
		SEC AIR TEMP	2200
SLURRY DENSITY	LAB	ESP IN RES.	1.8
BACK END TEMP	450	A/B/CN/CS	ESP
PRECHAIN TEMP	1625	EPS PRI VOLTS	↓
MATERIAL TEMP	1160	EPS PRI AMPS	↓
BURN ZONE TEMP	2900	EPS SEC MILLIAMP	↓
CLINKER TEMP	2400	NOTE: 16:30 FUEL DEC. 16.8-16.8	
		16:40 FUEL DEC 16.6-16.4	
		17:00 ID FAN ADJ 204-202	



LEHIGH PORTLAND CEMENT - CEMENTON - KILN OPERATIONAL DATA - PROJECT #71500

DATE	11/9/84	ID FAN AMPS ^{N₂} /SET	330/212	335/214
TIME	13:12 14:50	ID FAN DAMPER %	100	100
TEST No.	COMP 2	BACKEND DRAFT ^{IN H₂O}	-0.9	-0.9
DESCRIPTION	STK TEST	HOOD DRAFT	-0.05 NF	-0.05 NF
	13:15 14:50	^{IN H₂O} UNDERGRATE PRESS	12.5	12.4
	COMP 2 END @ 15:15	COMPARTMENT 1&2	107/98	106/98
COAL FEED (LB/HR) ^{THRU #7}	16.5 16.3	COMPARTMENT 3&4	130/118	130/119
KILN FEED (GPM)	400 400	COMPARTMENT 5&6	112 -	112
KILN SPEED (RPM)	1.1 1.10	COMPARTMENT 7&8	-	-
KILN DRIVE AMPS ^{KVA}	105 110	COOLER SPEED 0/1/2	6.5/12.2	6.5/12
KILN SHELL TEMP	890 890	COOLER BED DEPTH	NA	NA
TOTALIZER ^{SLURRY FLOW}	13:19 15:12 03644 04680	KILN EXIT 02 ^{LENSH KVB}	2.0/2.5	2.1/2.4
COAL MILL FEED ^{TPH}	16.2 16.3	KILN EXIT CO2	NA	NA
MILL INLET TEMP	300 330	QUENCH AIR DAMP	100 100	100
MILL OUTLET TEMP	190 190	EXCESS AIR DAMP	NA	NA
COAL MILL AMPS	27 27.5	PRIMARY AIR DAMP	?	-
MILL 200 MESH	LAB LAB	^{PRIMARY} DILUTION AIR DAMP ^{KVA}	230	230
MILL 100 MESH	LAB LAB	6K3 AMP/DATE	NA	NA
		SEC AIR TEMP	2000	2000
SLURRY DENSITY	LAB LAB	^{IN H₂O} ESP IN PLES	-1.85	-1.80
BACK END TEMP	460 470	A/B/CN/CS		
PRECHAIN TEMP	1660 1620	EPS PRI VOLTS		
MATERIAL TEMP	1100 1130	EPS PRI AMPS		
BURN ZONE TEMP	3050 2650	EPS SEC MILLIAMP		
CLINKER TEMP	2000 2000			
1		COAL TRIP - WATER PRESSURE		
NOTE: KILN UPSET 7:58 - 11:45				



LEHIGH PORTLAND CEMENT - CEMENTON - KILN OPERATIONAL DATA - PROJECT #71500

DATE	11/9/04	ID FAN AMPS ^{kw} /SET	330/212	330/209
TIME	16:15 17:05	ID FAN DAMPER %	100	100
TEST No.	CAMP #3	BACKEND DRAFT ⁱⁿ / ₁₆₀	-0.9	-0.95
DESCRIPTION	STK TEST	HOOD DRAFT	-0.05	-0.05
	2nd ¹⁶⁰ PCT	UNDERGRATE PRESS	13.0	12.8
	16:15 17:05	COMPARTMENT 1&2	106/98	106/99
COAL FEED (LB/HR) ^{THRU}	16.8 16.8	COMPARTMENT 3&4	130/119	131/117
KILN FEED (GPM)	400 405	COMPARTMENT 5&6	108	111
KILN SPEED (RPM)	1.10 1.14	COMPARTMENT 7&8	—	—
KILN DRIVE AMPS ^{KVA}	105 103	COOLER SPEED 0/1/2	12.2/6.2	12.3/6.2
KILN SHELL TEMP	880 870	COOLER BED DEPTH	—	—
TOTALIZER ^{SLURRY} _{FEED} ^{TPH}	16:12 17:12 05252 05229	KILN EXIT O ₂ ^{LEHIGH} _{KILN}	1.9/2.3	22/2.7
COAL MILL FEED	16.3 16.5	KILN EXIT CO ₂	0.54	0.54
MILL INLET TEMP	330 325	QUENCH AIR DAMP	NA	100
MILL OUTLET TEMP	185 180	EXCESS AIR DAMP	NA	NA
COAL MILL AMPS	28.0 27.0	PRIMARY AIR DAMP	NA	NA
MILL 200 MESH	LAB LAB	^{PRIMARY} _{DILUTION} AIR DAMP ^{KVA}	230	228
MILL 100 MESH	LAB LAB	613 AMPS/DAMP	—	—
		SEC AIR TEMP	2015	2010
SLURRY DENSITY	LAB LAB	ESP IN. ^{IN H₂O}	-1.7	-1.8
BACK END TEMP	470 430	A/B/CN/CS	↓	
PRECHAIN TEMP	1620 1580	EPS PRI VOLTS		
MATERIAL TEMP	1130 1170	EPS PRI AMPS		
BURN ZONE TEMP	3050 2850	EPS SEC MILLIAMP		
CLINKER TEMP	1950 1970			
404-J	72 60			



LEHIGH PORTLAND CEMENT - CEMENTON - KILN OPERATIONAL DATA - PROJECT #71500

DATE	11/2/84	ID FAN AMPS ^{Kil/150T}	327/207
TIME	17:48	ID FAN DAMPER %	100
TEST No.	Comp 3	BACKEND DRAFT ^{in H₂O}	-0.8
DESCRIPTION	STK TEST	HOOD DRAFT	-0.05
		UNDERGRATE PRESS	12.5
	17:48	COMPARTMENT 1&2	116/49
COAL FEED (LB/HR) ^{THICKER}	17.0	COMPARTMENT 3&4	130/119
KILN FEED (GPM)	405	COMPARTMENT 5&6	112 -
KILN SPEED (RPM)	1.12	COMPARTMENT 7&8	-
KILN DRIVE AMPS	98	COOLER SPEED 0/1/2	11.9/
KILN SHELL TEMP ^{R/A}	860	COOLER BED DEPTH	NA
TOTALIZER ^{SLURRY FLOW TPA}	17.48 06/87	KILN EXIT O2 ^{LEAKAGE/KVA}	1.7/2.3
COAL MILL FEED ^{TPH}	16.7	KILN EXIT CO2	NA
MILL INLET TEMP	335	QUENCH AIR DAMP	100
MILL OUTLET TEMP	195	EXCESS AIR DAMP	NA
COAL MILL AMPS	27.5	PRIMARY AIR DAMP	NA
MILL 200 MESH	LAB	^{PRIMARY R/A} DILUTION AIR DAMP	230
MILL 100 MESH	LAB	6K3 AMPS/DAMP	-
		SEC AIR TEMP	1850
SLURRY DENSITY	LAB	ESP IN ^{in H₂O}	-1.75
BACK END TEMP	450	A/B/CN/CS	
PRECHAIN TEMP	1570	EPS PRI VOLTS	
MATERIAL TEMP	1130	EPS PRI AMPS	
BURN ZONE TEMP	2700	EPS SEC MILLIAMP	↓
CLINKER TEMP	1850		
404-T	64		
NOTE: SPEED CHANGE @ 17:56			
TEST COMPLETED 17:53			

2017-3045-DK
CEMENTON PLANT

DAILY KILN REPORT

DATE 11-8-84

TIME	KILN RPM/GPM	TEST TANK TIME	STURDY COUNTER	DIFFERENCE	ID FAN SPEED/02	ID FAN INLET TEMP	EXIT GAS TEMP	MATERIAL TEMP CHAIN	GAS TEMP CHAINS	MID KILN GAS	BURNING ZONE TEMP	COAL COUNTER	COAL MILL OUT TEMP	SECONDARY AIR	UNDERGRATE PRESSURE	HOOD DRAFT	DUST COLL DIFF	DUST RETURN RPM
8:00 AM	222-400	12.2	1315	572	370-25	450	485	1200	1600	2050	2650	7400	170	-	13.5	13	8.0	40
9:00 8	232-400	12.2	563	563	370-19	450	485	1200	1600	2050	2650	6910	170	-	13.6	12	8.2	40
0:00 9	222-400	12.2	1171	575	370-20	450	485	1200	1600	2050	2650	6910	170	1880	12.4	15	8.0	40
1:00 10	222-400	12.0	8	575	370-22	450	485	1193	1600	2050	2650	2600	170	2000	12.0	13	8.0	40
2:00 11	222-400	16.8	2270	1139	370-27	450	485	1193	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
1:00 12 PM	222-400	16.8	2824	554	370-30	450	485	1193	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
2:00 1	222-400	16.8	3390	566	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
3:00 2	222-400	16.8	3964	574	370-24	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
4:00 3	222-400	16.8	4518	557	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
5:00 4	222-400	16.8	5084	566	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
6:00 5	222-400	16.8	5660	576	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
7:00 6	222-400	17.2	6232	572	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
8:00 7	222-400	17.2	6805	573	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
9:00 8	222-400	17.0	7379	574	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
0:00 9	222-400	17.0	7949	570	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
1:00 10	222-400	16.8	8522	573	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
2:00 11 AM	222-400	16.9	9105	583	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
1:00 12 AM	222-400	16.9	9679	574	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
2:00 1	222-400	16.6	10254	575	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
3:00 2	222-400	16.4	10828	574	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
4:00 3	222-400	16.8	11401	573	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
5:00 4	222-400	16.8	11984	583	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
6:00 5	222-400	16.8	12540	556	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
7:00 6	222-400	16.8	13163	623	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40
8:00 7	222-400	16.8	13682	519	370-27	450	485	1200	1600	2050	2650	4150	170	2100	12.0	13	8.0	40

PRODUCTION REMARKS: (REASONS FOR SLOWDOWN, OIL USE, ETC.)
ALSO NOTE ALL STOPPAGES AND REASONS THEREFORE.

7:00 4:00 DUST 10000 TANK DUST
OFF AIR N BAKER REQUEST
241

FREE LIME	CaCO ₃	MOIST
.10		
.10	2.85	1.87 91.10
.06		
1.10		
.09		
.10	2.60	89.34

~~SOUTH - 245 - DR~~
CEMENTON PLANT

TIME	KILN RPM/GPM	TEST TANK	STOKRY COUNTER	DIFFERENCE	ID FAN SPEED/02	ID FAN INLET TEMP	EXIT GAS TEMP	MATERIAL TEMP CHAIN	GAS TEMP CHAINS	MID KILN GAS	BURNING ZONE TEMP	COAL COUNTER	COAL MILL OUT TEMP	SECONDARY AIR	UNDERGRATE PRESSURE	HOOD DRAFT	DUST COLL DIFF	DUST RETURN RPM
8:00 AM	212/400	16.8	1312	519	360/16	420	450	1095	1550	2000	2550	7077	150	1970	12.7	.15	4.9	40
9:00	212/400	17.0	1318		360/18	415	430	1100	1530	1925	2740	6454	160	1760	12.8	.13	6.2	40
10:00	212/400	17.5	1138	1138	365/-	405	430	1095	1510	1875	2640	6454	160	1980	13.6			40
11:00	212/400	17.5	1138	1138	365/-	405	430	1095	1510	1875	2640	6454	160	1980	13.6			40
12:00	212/400	16.0	2388	1150	355/-	470	520	1095	1690	2075	3000	3354	160	2020	14.6	.13	7.2	40
1:00 PM	210/390	16.2	2382	564	355/20	475	455	1095	1670	2075	3000	3354	180	1840	10.4	.14	11.8	40
2:00	215/390	16.4	3425	573	310/11	440	460	1095	1640	2045	2940	6438	205	2120	12.8	.14	10.8	40
3:00	220/420	16.4	4000	575	315/12	435	455	1165	1620	2025	2980	8036	190	1960	12.6	.13	10.8	40
4:00	220/400	16.2	4661	661	365/12	440	465	1130	1610	2050	2620	9995	175	2010	13.5	.14	10.8	40
5:00	210/400	16.2	5166	505	365/15	440	470	1130	1620	2050	2620	1260	160	2100	12.7	.14	10.8	40
6:00	224/410	16.1	5725	559	360/15	430	440	1130	1590	2000	3000	2721	165	2000	12.5	.14	11.4	40
7:00	190/355	16.2	6258	543	360/14	420	465	1130	1560	2000	2420	4425	175	1560	10.4	.14	10.2	40
8:00	205/395	16.6	6917	424	355/10	450	490	1130	1620	2050	2780	6001	160	1980	13.8	.13	10.4	40
9:00	215/350	16.4	7095	373	360/16	450	450	1130	1650	2050	2780	6001	160	2100	13.2	.13	10.0	40
10:00	210/400	16.9	7463	349	360/11	445	470	1130	1650	2050	2780	6001	160	2100	13.2	.13	10.0	40
11:00	210/400	16.2	7845	384	360/14	440	470	1130	1640	2050	2780	6001	160	2100	13.2	.13	10.0	40
12:00	220/400	16.2	8249	397	360/19	440	465	1150	1645	2050	2780	6001	160	2000	13.6	.13	10.2	40
1:00 PM	220/400	16.2	8633	384	370/7	435	465	1150	1640	2050	2780	6001	160	1980	13.0	.13	10.4	40
2:00	220/400	15.4	9023	350	370/0	435	465	1150	1620	2000	2780	6001	160	1940	13.0	.14	10.2	40
3:00	220/400	16.2	9410	387	370/5	435	465	1150	1585	2000	2780	6001	160	1830	12.5	.14	11.0	40
4:00	220/400	16.4	9798	388	370/8	435	465	1150	1590	2025	2780	6001	160	1800	13.5	.14	10.2	40
5:00	220/400	16.4	10186	388	370/11	435	465	1150	1590	2025	2780	6001	160	1630	12.0	.14	10.5	40
6:00	220/400	16.0	10573	387	370/17	435	465	1145	1590	2025	2780	6001	160	1940	13.5	.14	10.2	40
7:00	220/400	15.8	10960	387	370/15	435	465	1150	1620	2010	2780	6001	160	1850	13.0	.14	10.5	40
8:00	220/400	15.5	11341	384	370/15	440	465	1150	1620	2000	2780	6001	160	1840	12.75	.13	11.2	40

453	1150	1625	2000	2100	2476	160	1870	12.9
-----	------	------	------	------	------	-----	------	------

PRODUCTION REMARKS: (RESONS FOR SLOWDOWN, OIL ALSO NOTE ALL STOPPAGES AND REASONS THEREFORE.

753pm Lost Pri. On farm
ed by current. See
828pm Lost Pri. On again!
853pm

5/12
MOIST

LSF
CaCO₃

FREE LIME

25

112

103

11.

90.06

11.

03-700

2.60

812,075

0.

6 3/4 - Charge Basin

6 3/4 - Charge Basin

Pg. 4 of 4

C shift

2:40A DUST ON KILN
2:45A Coal 17.6 T.P.H.
3:25A Coal 17.2 T.P.H.
4:15A Coal 17.0 T.P.H.
5:25A Coal 17.2 T.P.H.

9:05A ALL DUST OFF AS PER MICK ASHPH 118 O₂ 2-37% CO 80- under

9:30A 1 Line CONT OFF 17.1
10:15A COAL to 16.8 T
10:50A ~~COAL~~ DUST To kiln 20%
11:50A ~~DUST OFF~~

13:00 TRIM 10 2 PTS

2-2.5 O₂

1:45 DUST OFF

Less Than 1700 cm

1:54 TRIM 11 2 PTS

2:21 " " 2 PTS

2:55 Coal to 17.0 T

2:40 PM COAL TO 16.8
4:30 PM COAL TO 16.6 - KILN WARM
4:40 PM COAL TO 16.4 -
4:45 PM 2 PTS 100 ID FAN - (204)
5:00 PM 2 PTS OFF 10 FAN - (202)
5:10 PM DUST TO KILN
5:15 PM COAL TO 16.6
5:25 PM COAL TO 16.8, 2 PTS 10 (204)
5:30 PM COAL TO 17.0
5:35 PM COAL TO 17.2

11/8/84 - 3-11 SHIFT

6:05 PM 2 PTS 10 FAN (206)
6:35 PM DUST OFF (KILN COOLING)
6:55 PM DUST ON

7:00 PM COAL 17.0
7:20 PM 2 PTS 10 FAN (208) 420 DUST SCREW DOWN TO REPAIR HANGER
7:30 PM 2 PTS 10 (210) OPENING DOORS ON SCREW
7:40 PM 2 PTS 10 (212)
7:45 PM 2 PM OFF 10 (210) - CLOSING 420 UP
7:50 PM COAL TO 16.8
7:55 PM 2 PTS OFF 10 (208)
8:00 PM COAL TO 16.9

11:00 PM Coal To 17.1

1:55 PM Coal To 16.9

3:30 PM Coal To 16.6

11-8-84 11-7

11/8/84 to 11/9/84
C

Pg. 54.

1:25A Coal To 16.4 C shift.

1:40A Coal To 16.3

2:00A Coal To 16.4

2:05A Coal To 16.6

2:40A Coal To 16.8

4-9-84
7:15A #5 COOLER FAN OPA 11/9/84 A
INCREASED #3+4
fan slightly

10:53AM lost primary airfan eddy current clutch. 3 Min.

7:00 AM COAL TO 17.0

8:20 AM lost primary airfan 30-45 sec

8:53 AM lost primary air fan.

8:57 AM lost primary air fan.

9:01 AM Adjusted dampers on cyclone

9:01 AM Slowed Kiln 10 Pts.

9:21 AM " " 10 Pts

9:30 AM " " 25 Pts

9:30 AM Slowed I.D. FAN 25 Pts.

9:44 AM Slowed Kiln 75 Pts to 100 on S.S.

9:45 AM TRIM ID FAN 10 Pts

9:50 AM Picked up Kiln 5 Pts

9:55 AM " " " 5 Pts

10:04 AM " " " 10 Pts

10:04 AM " " " 5 Pts

10:10 AM " " " 10 Pts.

10:11 AM " " " 5 Pts.

10:30 AM " " " 5 Pts.

10:57 AM Kiln driver picked off. - Back on immediately!

11:01 AM

11:50 AM #5 cooler fan on.

11/9/84

12:50 PM

5 pts on kiln.

1:45

2 LINES COAL INC

1:50

1 LINE COAL DEC 16.4

7 shift.

3:52 PM

2 PTS off ID FAN TO 212

4:22

ADDED 2 PTS TO KILN TO 222

4:22

2 PTS off ID FAN TO 210

4:42

ADDED 2 PTS TO KILN SPEED TO 224

4:42

1 LINE off COAL TO 16.1

5:00 PM

1 Pt off KILN SPEED TO 223

5:03 PM

Added 1 Line of COAL TO 16.3

5:03

Added 2 PTS to ID TO 209

5:15 AM

1 Pt off KILN

5:12

Added 2 Lines of COAL

5:15

Added 2 PTS to ID

5:30

Added 2 PTS + ID

5:40

Added 1 Line COAL

5:40

Added 1 Pt ID

5:55

Slowed KILN TO 190

TESTING COMPLETED 17:53

APPENDIX D

ELECTROSTATIC PRECIPITATOR OPERATIONAL DATA



PRECIPITATOR OPERATING DATA

DATE: 11/8/84

TIME: 11:20


TEST #: PC-

K9
ROAD RIVER
SIDE

FIELD	1-2A	1-2B	1-C	2-C			
TRANSFORMER							
PRIMARY VOLTS	370	340	180	240			
TRANSFORMER							
PRIMARY CURRENT	25	170	98	124			
PRECIPITATOR							
AVERAGE CURRENT							
SPARK RATE (GAUGE)							
(ACTUAL)	50	0	—	0			
POWER							
CONTROL	8	8	105	97			
MODE	M	A	M	D			
RAPPER							
PRIMARY VOLTAGE	70/70						
VIBRATOR							
CURRENT	84						
RAPPER							
VOLTAGE CONTROL							
VIBRATOR							
CONTROL							

NOTES :

FIELD CONFIGURATION





PRECIPITATOR OPERATING DATA

LEHIGH CEMENT - CEMENTON

DATE: 11/8/94

TIME: 15:35

TEST #: COMP-1

FIELD	1-2A	1-2B	1-C	2-C			
TRANSFORMER							
PRIMARY VOLTS	440	335	205	240			
TRANSFORMER							
PRIMARY CURRENT	65	185	125	125			
PRECIPITATOR							
AVERAGE CURRENT							
SPARK RATE (GAUGE)							
(ACTUAL)	10	0	—	0			
POWER							
CONTROL	100	8	100	96			
	m	A	m	A			
RAPPER							
PRIMARY VOLTAGE	70/70						
VIBRATOR							
CURRENT	83						
RAPPER							
VOLTAGE CONTROL							
VIBRATOR							
CONTROL							

NOTES :

FIELD CONFIGURATION



A Research-Cottrell Company

PRECIPITATOR OPERATING DATA

DATE: 11/8/84

TIME: 17:45

TEST #: Comp 1

FIELD	1-2A	1-2B	1-C	2-C			
TRANSFORMER PRIMARY VOLTS	340	340	200	240			
TRANSFORMER PRIMARY CURRENT	70	175	120	130			
PRECIPITATOR AVERAGE CURRENT							
SPARK RATE (GAUGE) (ACTUAL)	50	0	—	0			
POWER CONTROL	100	7	100	97			
	M	A	M	A			
RAPPER PRIMARY VOLTAGE	70/70						
VIBRATOR CURRENT	84						
RAPPER VOLTAGE CONTROL							
VIBRATOR CONTROL							

NOTES :

FIELD CONFIGURATION



PRECIPITATOR OPERATING DATA

DATE: 11/9/84

TIME: 7:45

TEST #: Comp 2 PRE

FIELD	1-2A	1-2B	1-C	2-C			
TRANSFORMER							
PRIMARY VOLTS	420	330	200	235			
TRANSFORMER							
PRIMARY CURRENT	75	100	125	130			
PRECIPITATOR							
AVERAGE CURRENT	0	—	—	—			
SPARK RATE (GAUGE)							
(ACTUAL)	0	0	—	0			
POWER							
CONTROL	90	6	100	97			
	M	A	M	A			
RAPPER							
PRIMARY VOLTAGE	70/70						
VIBRATOR							
CURRENT	84						
RAPPER							
VOLTAGE CONTROL							
VIBRATOR							
CONTROL							

NOTES :

FIELD CONFIGURATION




PRECIPITATOR OPERATING DATA

DATE: 11/9/84
 TIME: 13:48
 TEST #: COMP-2

FIELD	1-2A	1-2B	1-C	2-C			
TRANSFORMER							
PRIMARY VOLTS	400	320	190	235			
TRANSFORMER							
PRIMARY CURRENT	16	175	120	125			
PRECIPITATOR							
AVERAGE CURRENT	—	—	—	—			
SPARK RATE (GAUGE)							
(ACTUAL)	5	0	(95)?	0			
POWER							
CONTROL	92	7	105	96			
MODE	M	A	M	A			
RAPPER							
PRIMARY VOLTAGE	76 1/2 / 70						
VIBRATOR							
CURRENT <i>electrodes</i>	83						
RAPPER							
VOLTAGE CONTROL							
VIBRATOR							
CONTROL							

NOTES :

FIELD CONFIGURATION





PRECIPITATOR OPERATING DATA

DATE: 11/9/84

TIME: 16:30

TEST #: Comp #3

FIELD	1-2 A	1-2 B	1-C	2-C			
TRANSFORMER							
PRIMARY VOLTS	405	325	175	235			
TRANSFORMER							
PRIMARY CURRENT	65	165	115	125			
PRECIPITATOR							
AVERAGE CURRENT	—	—	—	—			
SPARK RATE (GAUGE)							
(ACTUAL)	25	0	(195)	0			
POWER							
CONTROL	93	6	105	97			
<i>mode</i>	<i>m</i>	<i>A</i>	<i>m</i>	<i>A</i>			
RAPPER							
PRIMARY VOLTAGE	70/70						
VIBRATOR							
CURRENT	83						
RAPPER							
VOLTAGE CONTROL							
VIBRATOR							
CONTROL							

NOTES :

FIELD CONFIGURATION:



A Research-Cottrell Company

PRECIPITATOR OPERATING DATA

DATE: 11/9/84

TIME: 18:10

TEST #: Comp 3

FIELD	1-2A	1-2B	1-C	2-C			
TRANSFORMER							
PRIMARY VOLTS	400	320	185	235			
TRANSFORMER							
PRIMARY CURRENT	55	175	120	124			
PRECIPITATOR							
AVERAGE CURRENT							
SPARK RATE (GAUGE)							
(ACTUAL)	25	0*	185	0			
POWER							
CONTROL	91	6	100	94			
	M	A	M	A			
RAPPER							
PRIMARY VOLTAGE	70/70						
VIBRATOR							
CURRENT	83						
RAPPER							
VOLTAGE CONTROL							
VIBRATOR							
CONTROL							

NOTES :

87 INTERMITTENT SPARK
OVER 25/min

FIELD CONFIGURATION



PRECIPITATOR OPERATING DATA

DATE: 11-9-84

TIME: 1727

TEST #: COMPLIANCE #3


FIELD	ROAD RIVER						
	1-2A	1-2B	1-C	2-C			
TRANSFORMER PRIMARY VOLTS	400	325	185	235			
TRANSFORMER PRIMARY CURRENT	55	170	120	124			
PRECIPITATOR AVERAGE CURRENT	—	—	—	—			
SPARK RATE (GAUGE) (ACTUAL)	40	25	190	—0—			
POWER CONTROL	91	6	100	94			
MODE	M	A	M	A			
RAPPER PRIMARY VOLTAGE	70 / 70						
VIBRATOR CURRENT	83						
RAPPER VOLTAGE CONTROL							
VIBRATOR CONTROL							

NOTES :

B-FIELD - INTERMITTENT
SPARKING
up to 25 sparks/min.

FIELD CONFIGURATION

APPENDIX E
CYCLONIC FLOW DATA



VELOCITY TRAVERSE AND CYCLONIC FLOW DATA

BAROMETRIC PRESSURE	<u>29.98</u>
STATIC PRESSURE	<u>-55</u>
PITOT TUBE IDENT. NO.	<u>55-4</u>
OPERATOR	<u>PC</u>

TRAVERSE POINT	VELOCITY DATA			CYCLONIC DATA	
	ΔP (in. H ₂ O)	STACK TEMP (°F)	O ₂ (%)	ΔP at 0° POSITION (in. H ₂ O)	ANGLE OF ZERO ΔP (degrees)
12	.13	352		.02	5
11	.15	353		.03	10
10	.18	353		.05	10
9	.17	353		0	—
8	.19	356	7.4	0	—
7	.19	359		0	—
6	.22	361		0	—
5	.21	363		0	—
4	.21	362		0	—
3	.19	361		0	—
2	.18	357		.03	5
1	.13	352		.02	5
12	.18	355		0	—
11	.22	355		0	—
10	.25	355		0	—
9	.21	354	7.3	0	—
8	.21	353		0	—
7	.22	352		0	—
6	.18	350		0	—
5	.14	350		0	—
4	.14	349		0	—
3	.12	347		0	—
2	.1	342		0	—
1	.09	342		0	—
AVERAGES	.175	353			+1.4°

APPENDIX F

LABORATORY SUMMARY



PARTICULATE LABORATORY SUMMARY

WEIGHTS

Plant LEHIGH-CEMENTON
Date 11/8/84
Test No. COMP 1

ITEM WEIGHTS	FILTER #4	ACETONE WASH #16	SILICA
Final Weight (g)	0.6557	03.8345	216.5
Initial Weight (g)	0.6367	03.8224	200.0
+ Blank Weight (g)	-0.0004	-0.0002	
Net Sample Weight (g)	0.0186	0.0119	16.5

Total Particulate Weight 18.6 mg. filter
+ 11.9 mg. wash
 30.5 mg. Total

MOISTURE VOLUMES

ITEM VOLUMES	CONDENSATE VOLUME
Final Volume ml	714
Initial Vol., ml	300
Net Sample Vol. ml	414

Total Moisture Volume:
 414 ml, condensate volume
+ 16.5 ml, silica gel *
 430.5 ml, Total

* 1 g/ml



PARTICULATE LABORATORY SUMMARY

WEIGHTS

Plant LEHIGH CEMENT CO.
Date 11/9/84
Test No. COMP 2

ITEM WEIGHTS	FILTER #5	ACETONE WASH #6	SILICA
Final Weight (g)	0.6140	109.3010	213.0
Initial Weight (g)	0.5970	109.2859	200.0
+ Blank Weight (g)	-0.0004	- 0.0002	
Net Sample Weight (g)	0.0166	0.0149	13.0

Total Particulate Weight

16.6 mg, filter
+ 14.9 mg, wash
31.5 mg, Total

MOISTURE VOLUMES

ITEM VOLUMES	CONDENSATE VOLUME
Final Volume ml	718
Initial Vol., ml	300
Net Sample Vol. ml	418

Total Moisture Volume:

418 ml, condensate volume
+ 13 ml, silica gel *
431 ml, Total

* 1 g/ml



PARTICULATE LABORATORY SUMMARY

WEIGHTS

Plant LEHIGH-CEMENTON

Date 1/9/84

Test No. COMP 3

ITEM WEIGHTS	FILTER #7	ACETONE WASH #4	SILICA
Final Weight (g)	0.6584	83.6452	214.5
Initial Weight (g)	0.6364	83.6246	200.0
+ Blank Weight (g)	-0.0004	-0.0002	
Net Sample Weight (g)	0.0216	0.0204	14.5

Total Particulate Weight

21.6 mg, filter
+ 20.4 mg, wash
42.0 mg, Total

MOISTURE VOLUMES

ITEM VOLUMES	CONDENSATE VOLUME
Final Volume ml	742
Initial Vol., ml	300
Net Sample Vol. ml	442

Total Moisture Volume:

442 ml, condensate volume
+ 14.5 ml, silica gel *
456.5 ml, Total

* 1 g/ml



PARTICULATE LABORATORY SUMMARY

WEIGHTS

Plant LEHIGH-CEMENTON
Date 11/9/04
Test No. BLANKS

ITEM WEIGHTS	FILTER #8	ACETONE WASH #44	SILICA
Final Weight (g)	0.6186	83.6246	—
Initial Weight (g)	0.6190	83.6248	—
+ Blank Weight (g)	—	—	X
Net Sample Weight (g)	-0.0004	-0.0002	—

Total Particulate Weight

— -0.4 — mg, filter
+ — -0.2 — mg, wash
— -0.6 — mg, Total

MOISTURE VOLUMES

ITEM VOLUMES	CONDENSATE VOLUME
Final Volume ml	—
Initial Vol., ml	—
Net Sample Vol. ml	—

Total Moisture Volume:

— — ml, condensate volume
+ — — ml, silica gel *
— — ml, Total

* 1 g/ml

November 1984

LEHIGH PORTLAND CEMENT

LABORATORY SUMMARY SHEET



71500

ID NUMBER	TEST NUMBER	TEST DATE	FILTER #4	FILTER #5	FILTER #6	FILTER #7	FILTER #8	SEALER #16	SEALER #6	SEALER #4	SEALER #44
			COMP1	COMP2	SAME	COMP3	BLANK	COMP1	COMP2	COMP3	BLANK
			11/6/84	11/6/84	11/6/84	11/6/84	11/6/84	11/6/84	11/6/84	11/6/84	11/6/84
			MS	MS	MS	MS	ARE	ARE	ARE	ARE	ARE
FINAL WEIGHT 1			.6555	.6146	UNUSABLE	.6583	.6186	83.8356	109.3010	83.6449	83.6246
2			.6556	.6136		.6575	.6180	83.8334	109.3016	83.6451	83.6248
3			.6559	.6130		.6593	.6185	83.8345	109.3003	83.6465	83.6244
AVERAGE FINAL WEIGHT			.6557	.6140		.6584	.6186	83.8345	109.3010	83.6452	83.6246
TARE WEIGHT 1			.6369	.5970	.5995	.6362	.6189	83.8224	109.2861	83.6247	83.6250
2			.6365	.5969	.5998	.6365	.6192	83.8222	109.2857	83.6244	83.6246
3			.6366	.5970	.5997	.6364	.6190	83.8225	109.2859	83.6247	83.6249
AVERAGE TARE WEIGHT			.6367	.5970	.5997	.6364	.6190	83.8224	109.2859	83.6246	83.6240
AVERAGE FINAL WEIGHT			.6557	.6140		.6584	.6186	83.8345	109.3010	83.6452	83.6246
AVERAGE TARE WEIGHT			.6367	.5970	.5997	.6364	.6190	83.8224	109.2859	83.6246	83.6248
PRELIM SAMPLE WEIGHT											
FINAL SAMPLE WEIGHT			19.0	17.0		22.0	-0.4	12.1	15.1	20.1	-0.2



METHOD 5 TRAIN ANALYTICAL PARTICULATE DATA

Plant LEHIGH - CEMENTON, NY Run No. COMP-1
Sample location KILN EXHAUST STACK
Relative humidity NOT RECORDED - CLEAR SKIES
Density of acetone (pa) LAB GRADE g/ml

Sample type	Sample identifiable	Liquid level marked and/or container sealed
Acetone rinse filter(s)	<u>#16 comp 1</u> <u>#4 comp 1</u>	<u>173 ml</u> <u>11/8/84</u>

Acetone rinse container no. #16
Acetone rinse volume (Vaw) 173 ml
Acetone blank residue concentration (Ca) 0.2 mg / 175 ml mg/g

Wa = Ca Vaw pa = () () () = mg

Date and time of wt 11/8/84 Gross wt mg

Date and time of wt 11/9/84 & 11/10/84 Gross wt mg

Average gross wt 83.8345 mg

Tare wt 83.8224 mg

Less acetone blank wt (Wa) 0.0002 mg

Weight of particulate in acetone rinse 11.9 mg

Filter(s) container no. #4 comp 1

Date and time of wt 11/9/84 Gross wt mg

Date and time of wt 11/10/84 Gross wt mg

Average gross wt 0.6557 mg

Tare wt 0.6367 mg

Weight of particulate on filter(s) 18.6 mg

Weight of particulate in acetone rinse 11.9 mg

Total weight of particulate 30.5 mg

Note: In no case shall a blank residue greater than (.01 mg/g) or .001% of the weight of acetone used be subtracted from the sample weight.

Remarks:

Signature of analyst

Signature of reviewer



Plant LEHIGH - CEMENTON, NY Run No. Comp-2
Sample location KILN EXHAUST STACK
Relative humidity NOT RECORDED - OVERCAST
Density of acetone (pa) LAB GRADE g/ml

Acetone rinse container no. # 6

Acetone rinse volume (Vaw) 184 ml

Acetone blank residue concentration (Ca) 0.2 mg / 175 ml mg/g

Wa = Ca Vaw pa = () () () = mg

Date and time of wt 11/2/04 Gross wt mg

Date and time of wt 11/10/04 Gross wt 10 mg

Average gross wt 109.3010 mg

Tare wt 109.2059 mg

Less acetone blank wt (Wa) 0.0002 mg

Weight of particulate in acetone rinse 14.9 mg

Filter(s) container no. # 5 Comp 2

Date and time of wt 11/9/04 Gross wt mg

Date and time of wt 11/10/04 Gross wt mg

Average gross wt 0.6140 mg

Tare wt 0.5970 mg

Weight of particulate on filter(s) 16.6 mg

Weight of particulate in acetone rinse 14.9 mg

Total weight of particulate 31.5 mg

Remarks: _____

Signature of reviewer



Plant LEHIGH-CEMENTON, NY Run No. CMP-3
Sample location KILN EXHAUST STACK
Relative humidity NOT REPORTED - OVERCAST
Density of acetone (pa) LAR GRADE g/ml

Acetone rinse container no. # 4
Acetone rinse volume (Vaw) 191 ml
Acetone blank residue concentration (Ca) 0.2 mg / 175 ml mg/g
Wa = Ca Vaw pa = () () () = mg

Weight of particulate in acetone rinse **20.4** mg

Total weight of particulate *42.0* mg

Remarks: _____

Signature of reviewer

APPENDIX G
CALIBRATION DATA

CALIBRATION SHEET

Customer IET Order No. _____

Date 10/31/84 Box No. EU-513-1 RAC Order No. _____

Pump ✓

Pump Oil ✓

Clean Quick Connects ✓ Valves ✓

Manometers ✓

Dry Test Meter ✓

Thermometers ✓

Lights _____ Buzzer _____

Electrical Check--Amphenol _____

Variac _____

Vacuum Gauge ✓

Leak Check at 27" Hg.--Leakage _____

Remarks LEHIGH CEMENT COMPLIANCE TESTING - Prod # 71500 0 CFM

Calibration--Orifice and Meter Date 10/31/84 Box No. EU-513-1 Pb 3d.09

Man Orifice	CF _w	CF _d	T _w	IT _d	OT _d	T _d avg.	Time t
0.5	5	4.979	63.5	74	62	69	13.6
1.0	5	5.013	62	75	58	65.5	9.2
2.0	10	10.011	63.5	85	65	75	13.5
4.0	10	9.968	63	87	64	75.5	9.7
6.0	10	9.950	63	90	68	79	7.25
8.0	10	10.080	63	90	68	79	6.7

Calculate Y & H@ at man. 2.0

$$\frac{CF_w}{CF_d} = \frac{P_b (T_d \text{ avg.} + 460)}{P_b (P_b + 0.147) (T_w + 460)}$$

$$H@ = \frac{0.0634}{P_b (OT_d + 460)} \left(\frac{(T_w + 460)}{CF_w} \right)^2$$

variances

$$0.99 - \frac{1.00}{1.84} = 1.01$$

$$1.6 - \frac{1.84}{2.1} = 2.1$$

$\frac{0.0317 (Max. Diff.)^2}{P_b (OT_d + 460)} \left(\frac{(T_w + 460)^t}{CF_w} \right)^2$	Max. ΔH @ H ₂ O	$\frac{CF_w P_b (T_d Avg. + 460)}{CF_d (P_b + 13.6 - \frac{Max. Diff.}{T_w + 460})}$	Cum. Y
$\frac{0.01585}{30.09 (\frac{62}{5} + 460)} \left(\frac{(\frac{62.5}{5} + 460) \frac{13.6}{5}}{5} \right)^2$	0.5	$\frac{5 \times 30.09 (\frac{69}{4.979} + 0.0368) (\frac{63.5}{4.979} + 460)}{4.979 (30.09 + 0.0368) (\frac{63.5}{4.979} + 460)}$	0.5
$\frac{0.0317}{30.09 (\frac{56}{5} + 460)} \left(\frac{(\frac{62}{5} + 460) \frac{9.2}{5}}{5} \right)^2$	1.0	$\frac{5 \times 30.09 (\frac{66.5}{5.013} + 460)}{5.013 (30.09 + 0.0737) (\frac{62}{5.013} + 460)}$	1.0
$\frac{0.06234}{30.09 (\frac{65}{10} + 460)} \left(\frac{(\frac{63.5}{10} + 460) \frac{13.5}{10}}{10} \right)^2$	2.0	$\frac{10.0 \times 30.09 (\frac{75}{10.01} + 460)}{10.01 (30.09 + 0.147) (\frac{63.5}{10.01} + 460)}$	2.0
$\frac{0.1268}{30.09 (\frac{64}{10} + 460)} \left(\frac{(\frac{63}{10} + 460) \frac{9.7}{10}}{10} \right)^2$	4.0	$\frac{10.0 \times 30.09 (\frac{75.5}{9.968} + 460)}{9.968 (30.09 + 0.294) (\frac{63}{9.968} + 460)}$	4.0
$\frac{0.1902}{30.09 (\frac{68}{10} + 460)} \left(\frac{(\frac{62}{10} + 460) \frac{7.2}{10}}{10} \right)^2$	6.0	$\frac{10.0 \times 30.09 (\frac{79}{9.95} + 460)}{9.95 (30.09 + 0.43) (\frac{63}{9.95} + 460)}$	6.0
$\frac{0.2536}{30.09 (\frac{68}{10} + 460)} \left(\frac{(\frac{63}{10} + 460) \frac{6.7}{10}}{10} \right)^2$	8.0	$\frac{10.0 \times 30.09 (\frac{79}{10.08} + 460)}{10.08 (30.09 + 0.588) (\frac{63}{10.08} + 460)}$	8.0
Avg. ΔH	1.916	Avg. Y	1.005

$\frac{0.0317 (Max. Diff.)}{P_b (OT_d + 460)} \left(\frac{(TW + 460)^t}{CF_w} \right)^2$	Max. "H ₂ O"	ΔH @	$\frac{CF_w P_b}{CF_d} \left(\frac{Max. Diff.}{P_b + 13.6} \right) (TW + 460)$	Y
$\frac{0.01585}{30.09} \left(\frac{62 + 460}{5} \right) \left(\frac{(62.5 + 460) 13.6}{5} \right)^2$	.5	2.00	$\frac{5}{4.979} \times 30.09 \left(\frac{69}{30.09 + 0.0368} \right) (63.5 + 460)$	.5 1.006
$\frac{0.0317}{30.09} \left(\frac{62 + 460}{5} \right) \left(\frac{(62 + 460) 9.2}{5} \right)^2$	1.0	1.876	$\frac{5}{5.013} \times 30.09 \left(\frac{66.5}{30.09 + 0.0737} \right) (62 + 460)$	1.0 1.00
$\frac{0.0634}{30.09} \left(\frac{65 + 460}{10} \right) \left(\frac{(63.5 + 460) 13.5}{10} \right)^2$	2.0	2.004	$\frac{10.0 \times 30.09}{10.01} \left(\frac{75}{30.09 + 0.147} \right) (63.5 + 460)$	2.0 1.01
$\frac{0.1268}{30.09} \left(\frac{63 + 460}{10} \right) \left(\frac{(63 + 460) 9.4}{10} \right)^2$	4.0	1.94	$\frac{10.0 \times 30.09}{9.968} \left(\frac{75.5}{30.09 + 0.294} \right) (63 + 460)$	4.0 1.007
$\frac{0.1902}{30.09} \left(\frac{63 + 460}{10} \right) \left(\frac{(63 + 460) 7.2}{10} \right)^2$	6.0	1.72	$\frac{10.0 \times 30.09}{9.95} \left(\frac{79}{30.09 + 0.43} \right) (63 + 460)$	6.0 1.008
$\frac{0.2536}{30.09} \left(\frac{63 + 460}{10} \right) \left(\frac{(63 + 460) 6.7}{10} \right)^2$	8.0	1.96	$\frac{10.0 \times 30.09}{10.08} \left(\frac{79}{30.09 + 0.588} \right) (63 + 460)$	8.0 1.002
Avg. ΔH	1.916		Avg. Y	1.005




DATE: 11/7/04

COMPANY: LEHIGH-PORTLAND

PLANT: CEMENTON, NY

UNIT NO.: KILN

NOZZLE CALIBRATION



MEASUREMENTS: A 0.376

B 0.375

C 0.376

D 0.377

AVERAGE DIAMETER: 0.376

PILOT TUBE SN # 046 $\frac{\text{COEFFICIENT}}{-0.84}$

[Signature]

POST TEST METER CALIBRATION

Date 11-26-84

Barometric pressure, $P_b = 30.29$ "Hg

Meter Box No. EN 513-1

Dry Gas Meter No. _____

Plant Lehigh Cement Co.

P/M _____

Project Manager Bob P. K. Co.

Pretest $V = 1.01 @ 2.0 \Delta H$

Test No.	Orifice monometer setting. ΔH , in H_2O	Gas volume wet test meter V_w , ft ³	Gas volume dry gas meter V_d , ft ³	Temperature					Time O ₂ min.	Vacuum setting in Hg	VI	VI
				Wet test Meter t_w , °F	Dry gas meter			Average t_d , °F				
					Inlet t_{di} , °F	Outlet t_{do} , °F						
1	1.9	10	9.72	65	81	69	75	13.6	6.0	1.04	$\frac{V_w P_b (t_d + 460)}{V_d (P_b + \frac{\Delta H}{13.6}) (t_w + 460)}$ $\frac{10 \times 30.29 \times (75 + 460)}{9.72 \times 30.29 + \frac{1.9}{13.6} \times (6.5 \times 1160)}$	
2	1.9	10	9.66	65	88	72	80	14.5	6.0	1.06	$\frac{10 \times 30.29 \times (80 + 460)}{9.66 \times 30.29 + \frac{1.9}{13.6} \times (6.5 \times 1160)}$	
3	1.9	10	9.75	65	88	74	81	13.8	6.0	1.03	$\frac{10 \times 30.29 \times (81 + 460)}{9.75 \times 30.29 + \frac{1.9}{13.6} \times (6.5 \times 1160)}$	
Post-test $\gamma = 1.043$												

• If there is only one thermometer on the dry gas meter record the temperature under t_d .

where:

V_w = Gas volume passing through the wet test meter, ft³.

V_d = Gas volume passing through the dry test meter, ft³.

t_w = Temperature of the gas in the wet test meter, °F.

t_{di} = Temperature of the inlet gas of the dry test meter, °F.

t_{do} = Temperature of the outlet gas of the dry test meter, °F.

t_d = Average temperature of the gas in the dry test meter, obtained by the average of t_{di} and t_{do} , °F.

ΔH = Pressure differential across orifice, in H_2O .

V = Ratio of accuracy of wet test meter to dry test meter for each run.

V = Average ratio of accuracy of wet test meter to dry test meter for all three runs.

Tolerance = Pretest ± 0.05 ft³.

P_b = Barometric pressure, in. Hg.

Δ = Time of calibration run, minutes.

Post-test $V = 1.04$

Calibrated by R. P. K. Co.
Signature

Calibration--Orifice and Meter

Date 10/31/84 Box No. ED-513-1 Pb 34.09

Customer IET

Date 10/31/84

Box No. EN-513-1

Order No

Pump ✓

RAC Order No.

Pump Oil ✓

Clean Quick Connects ✓

Valves ✓

Manometers ✓

Dry Test Meter ✓

Thermometers ✓

Lights —

Buzzer —

Electrical Check--Amphenol —

Variac —

Vacuum Gauge ✓

Leak Check at 27" Hg.--Leakage

Remarks

0 CFM

Man Orifice	CF _w	CF _d	T _w	IT _d	OT _d	Td avg.	Time t
0.5	5	4.979	63.5	76	62	69	13.6
1.0	5	5.013	62	75	58	65.5	9.2
2.0	10	10.011	63.5	85	65	75	13.5
4.0	10	9.968	63	87	64	75.5	9.7
6.0	10	9.950	63	90	68	79	7.25
8.0	10	10.080	63	90	68	79	6.7

Calculate Y & HQ at man. 2.0

$$CF_w P_b (T_d \text{ avg.} + 460) = CF_d (P_b + 0.147) (T_w + 460)$$

$$HQ = \frac{0.0634}{P_b (OT_d + 460)} \left(\frac{(T_w + 460)}{CF_w} \right)^2$$

tolerances

$$= 0.99 - 1.00 - 1.01$$

$$1 - 1.6 - 1.84 - 2.1$$

1150

$\frac{0.0317 \text{ (Max. Offset)}}{P_b (OT_d + 460)} \left(\frac{(T_w + 460)^2}{CF_w} \right)$	Max. "H ₂ O"	$\Delta H @$	$\frac{CF_w P_b (T_d \text{ Avg.} + 460)}{CF_d (P_b + 13.6 \text{ Max. Offset.}) (T_w + 460)}$	Mail. Y:
$\frac{0.01585}{30.09} \left(\frac{62 + 460}{5} \right) \left(\frac{(62.5 + 460) 13.6}{5} \right)^2$	0.5	2.00	$\frac{5 \times 30.09}{4.979} \left(\frac{69}{30.09 + 0.0368} \right) \left(\frac{63.5 + 460}{63.5 + 460} \right)$	0.5
$\frac{0.0317}{30.09} \left(\frac{62 + 460}{5} \right) \left(\frac{(62 + 460) 9.2}{5} \right)^2$	1.0	1.876	$\frac{5 \times 30.09}{5.013} \left(\frac{66.5}{30.09 + 0.0737} \right) \left(\frac{62 + 460}{62 + 460} \right)$	1.0
$\frac{0.0634}{30.09} \left(\frac{65 + 460}{10} \right) \left(\frac{(63.5 + 460) 13.5}{10} \right)^2$	2.0	2.004	$\frac{10.0 \times 30.09}{10.01} \left(\frac{75}{30.09 + 0.147} \right) \left(\frac{63.5 + 460}{63.5 + 460} \right)$	2.0
$\frac{0.1268}{30.09} \left(\frac{63 + 460}{10} \right) \left(\frac{(63 + 460) 9.7}{10} \right)^2$	4.0	1.94	$\frac{10.0 \times 30.09}{9.968} \left(\frac{75.5}{30.09 + 0.294} \right) \left(\frac{63 + 460}{63 + 460} \right)$	4.0
$\frac{0.1902}{30.09} \left(\frac{62 + 460}{10} \right) \left(\frac{(62 + 460) 7.2}{10} \right)^2$	6.0	1.72	$\frac{10.0 \times 30.09}{9.95} \left(\frac{79}{30.09 + 0.43} \right) \left(\frac{63 + 460}{63 + 460} \right)$	6.0
$\frac{0.2536}{30.09} \left(\frac{63 + 460}{10} \right) \left(\frac{(63 + 460) 6.7}{10} \right)^2$	8.0	1.96	$\frac{10.0 \times 30.09}{10.08} \left(\frac{79}{30.09 + 0.588} \right) \left(\frac{63 + 460}{63 + 460} \right)$	8.0
Avg. ΔH		1.94		

APPENDIX H

KVB DATA REDUCTION FORMULAE

DATA CONSTANTS

MW(1) = 44.0 Molecular Weight (lb/lbmole) CO₂
MW(2) = 32.0 Molecular Weight (lb/lbmole) O₂
MW(3) = 28.0 Molecular Weight (lb/lbmole) N₂
MW(4) = 64.0 Molecular Weight (lb/lbmole) SO₂
MW(5) = 12.0 Molecular Weight (lb/lbmole) C
MW(6) = 1.0 Molecular Weight (lb/lbmole) H
MW(7) = 32.0 Molecular Weight (lb/lbmole) S

PI = 3.141592654 = π

TSTD = 68 = Standard Temperature (Degrees F)

PSTD = 29.92 = Standard Pressure (Inches Hg)

Y = 1.0 = Dry Gas Calibration Factor

KP = 85.48 = Pitot Tube Constant $\frac{\text{ft}}{\text{sec}} \left[\frac{(\text{lb/lbmole})(\text{in Hg})}{(\text{Deg R (in H}_2\text{O)})} \right]^{\frac{1}{2}}$

R1 = 1544.3 = Gas Law Constant (ft-lb/(lb-mole Deg R))

RW = 62.31 = Density of H₂O @ 68°F (lb/ft³)

R = R1/7.0727E1 = conversion of Gas Law Constant to (ft³-in Hg/(lb-mole Deg R))

RHO = RW/28.316 x 10³ = Conversion of H₂O density to (lb/ml)

MOIS = RHO x R x (TSTD + 460)/(18 x PSTD) = $\frac{\text{ft}^3 \text{ H}_2\text{O Gas}}{\text{ml H}_2\text{O liquid}}$ at standard conditions

K3 = RHO x R/18 = Moisture Content Conversion (ft³ - in Hg/(ml Deg R))

STACK SAMPLING CALCULATIONS

SP = Stack Pressure [in Hg]

$$= \text{Barometric Pressure [in Hg]} + \frac{\text{Stack Gas Static Pressure, [in H}_2\text{O]}}{13.6}$$

Volume (DSCF) = meter volume (ft³) corrected to standard conditions

$$= \text{Meter volume} \times \text{dry gas calibration factor} \times \text{TSTD} \times (\text{PBARO} + \Delta H/13.6) / (\text{PSTD} \times \text{Stack Temp})$$

Stack Velocity [ft/sec] = KP x pitot tube coefficient x

$$\sqrt{(\text{Stack Temp} \times \Delta P) / (\text{Stack Pressure} \times \text{MW Wet})}$$

$$\text{Average } \Delta P \text{ for the stack} = \left(\frac{\text{Average Stack Velocity}}{\text{KP} \times \text{Pitot Tube Coefficient}} \right)^2 \times \text{Stack Pressure} \times \text{MW Wet/Stack Temp.}$$

$$\text{Isokinetics} = \frac{\text{Sampling Velocity}}{\text{Stack Velocity}} \times 100$$

$$= \frac{100 \times \text{stack temp} \left[K_3 \times \text{vol. H}_2\text{O} + \frac{(\text{meter volume})}{\text{meter temp}} \right] (\text{Baro. Press} + \Delta H/13.6)}{(60) (\text{sampling time}) (\text{stack velocity}) (\text{stack pressure}) (\text{area of nozzle})}$$

Volumetric Flow Rate Based On Stack Velocity (ACFM) = average stack velocity x area of stack

EMISSIONS CALCULATIONS

E = lb/MBTU based on combustion chemistry

$$= \frac{\text{Particulate [mg]} \times F \left[\frac{\text{DSCF}}{\text{MBTU}} \right]}{\text{Volume (DSCF)} \times 453.59 \text{E}3 \left[\frac{\text{mg}}{\text{lb}} \right]} \times \left(\frac{20.9}{20.9 - O_2} \right)$$

Where $\frac{20.9}{20.9 - O_2}$ is a correction of $\frac{1}{\text{Volume (DSCF)}}$ to 0% excess air.

E1 = lb/DSCF

$$= \frac{\text{Particulates [mg]}}{\text{Volume (DSCF)} \times 453.59 \text{E}3 \left[\frac{\text{mg}}{\text{lb}} \right]}$$

E2 = Grains/ACF

$$= \frac{\text{Particulates [mg]} \times 1.5432 \text{E}-2 \left[\frac{\text{grains}}{\text{mg}} \right]}{[\text{Volume (DSCF)} + \text{Volume H}_2\text{O}]} \times \left[\frac{\text{TSTD} \times \text{Stack Pressure}}{\text{PSTD} \times \text{Stack Temp.}} \right]$$

E3 = lb/hr based on Stack Velocity

$$= \text{Stack Velocity} \times \text{Stack Area} \times E1 \left[\frac{\text{lb}}{\text{DSCF}} \right] \times (1 - BWO) \times \frac{\text{TSTD} \times \text{Stack Press.}}{\text{PSTD} \times \text{Stack Temp.}}$$

E4 = Grains/DSCF at 77°F and 50% excess air (State of Maryland)

$$= E1 \left[\frac{\text{lb}}{\text{DSCF}} \right] \times 7000 \left[\frac{\text{grains}}{\text{lb}} \right] \times \frac{\text{TSTD}}{537^\circ\text{R}} \times \left(\frac{20.9 - M2}{20.9 - O_2} \right)$$

Where $\frac{20.9 - M2}{20.9 - O_2}$ is a correction of $\frac{1}{\text{Volume (DSCF)}}$ to 50% excess air.

EMISSIONS CALCULATIONS

E5 = E3 or Optionally

E5 = lb/hr based on combustion chemistry

$$E = \left[\frac{\text{lb}}{\text{MBTU}} \text{ (based on combustion chemistry)} \right] \times \text{HI} \left[\frac{\text{KBTU}}{\text{hour}} \right] \times \frac{10^3 \text{ KBTU}}{\text{MBTU}}$$

EE = lb/MBTU based on stack velocity and fuel flow

$$E = \frac{E3 \left[\frac{\text{lb}}{\text{hr}} \text{ based on stack velocity and fuel flow} \right]}{\text{HI} \left[\frac{\text{KBTU}}{\text{hour}} \right]} \times 10^3 \left[\frac{\text{KBTU}}{\text{MBTU}} \right]$$

CONVERSION OF CEMENT KILN EMISSIONS DATA

Conversion of cement kiln emission concentrations to $\text{lb}/10^6$ Btu using the F factor method (according to the Federal NSPS for utility boilers) requires correction for the CO_2 content evolved from the cement feed.

The standard dry basis NSPS procedure is:

$$E = C_d F_d \frac{20.9}{20.9 - \%O_{2d}}$$

where

E = pollutant emission rate, ng/J ($\text{lb}/10^6$ Btu)

C_d = pollutant concentration, ng/scm (lb/scf)

F_d = F factor, scm/J ($\text{scf}/10^6$ Btu)

Standard "default" F_d factors are tabulated in the NSPS for various fuels, such as:

$F_{d_{\text{natural gas}}}$	= 8740 $\text{dscf}/10^6$ Btu
$F_{d_{\text{oil}}}$	= 9220 $\text{dscf}/10^6$ Btu
$F_{d_{\text{coal}}}^*$	= 9820 $\text{dscf}/10^6$ Btu

*for bituminous and subbituminous coals.

For cement kilns (or any other process where feed material is evolved as gases into the stack gas) the F factor must be corrected for the evolved gas, i.e.,

$$F_d = F_{d_{\text{fuel}}} + F_{d_{\text{process}}}$$

For CO₂ from CaCO₃ in the cement feed:

$$F_{d_{CO_2}} = \frac{386.8 \text{ scf/mole}}{44 \text{ lb CO}_2/\text{mole}} \times \frac{\text{lb CO}_2}{\text{lb dry feed}} \times \frac{\text{lb dry feed}}{10^6 \text{ Btu}} = \frac{\text{scf CO}_2}{10^6 \text{ Btu}}$$

NOTE: 1 mole CaCO₃ = 1 mole CaO + 1 mole CO₂

$$100 \text{ lb CaCO}_3 = 56 \text{ lb CaO} + 44 \text{ lb CO}_2$$

lb CO₂/lb dry feed can be taken as the "ignition loss" from the dry feed analysis, typically 0.35.

lb dry feed/10⁶ Btu must be obtained from feed rate and fuel firing rate. This can be estimated roughly as:

$$\frac{\text{lb}_{df}}{10^6 \text{ Btu}} = \frac{2000}{B \frac{10^6 \text{ Btu}}{\text{Ton clinker}} \times (1 - \text{I.L.})}$$

where

B = 3-3.5 x 10⁶ Btu/Ton clinker for precalciner kilns

5-5.4 x 10⁶ Btu/Ton clinker for long kilns

I.L. = Ignition loss, dry feed

APPENDIX I

SAMPLE EMISSIONS CALCULATIONS

STACK GAS VELOCITY



DATE 11/8/84 TEST NUMBER COMP 1

LOCATION LEHIGH CEMENT-CEMENTON

UNIT KILN FUEL COAL

$$V_s = 85.48 (C_{\text{pitot}}) \left(\frac{(T_s) (\Delta P)}{(P_s) (MW_s)} \right)^{1/2} = 85.48 (.84) \left(\frac{(828) (.20)}{(29.81) (21.6)} \right)^{1/2} = \boxed{32.2}$$

Where: C_{pitot} = Pitot tube correction factor

T_s = Absolute average stack gas temperature °R.

ΔP = Average stack ΔP , inches H_2O .

P_s = Absolute stack gas pressure, inches H_g .

MW_s = Stack gas molecular weight

ISOKINETIC CALCULATION

$$I = \frac{123.76 (V_m)}{(D^2) (T_m) (\theta)} \left(\frac{T_s}{\Delta P} \right)^{1/2} \left[\frac{100}{100 - \% \text{ Moisture}} \right]$$

$$I = \frac{123.76 (51.227)}{(0.376)^2 (528) (72)} \left(\frac{828}{.20} \right)^{1/2} \left[\frac{100}{(1134)} \right] = \boxed{105.3}$$

Where:

I = Percent of isokinetic sampling

V_1 = Total volume of liquid collected in impingers and silica gel, ml.

V_m = Volume of gas sample through the dry gas meter (meter conditions), cu.ft.

T_m = Absolute average dry gas meter temperature °R

P_{bar} = Barometric pressure at sampling site, inches H_g .

ΔH = Average pressure drop across the orifice, inches H_2O .

θ = Total sampling time, min.

PARTICULATE CALCULATIONS

$$V_{\text{DSCF}} = \left(\frac{T_{\text{Std}}}{P_{\text{Std}}} \right) \left(\frac{V_m}{T_m} \right) \left[P_b + \left(\frac{\Delta H}{13.6} \right) \right] = \text{ @ 528 °R } 29.92 \text{ "Hg}$$

$$= 17.65 \left(\frac{51.227}{528} \right) \left[29.85 + \left(\frac{1.89}{13.6} \right) \right] = 51.491$$

$$V_{H_2O} = 0.047 (V_1) = 0.047 (430.5) = 20.23$$

$$\% \text{ Moisture} = \frac{(V_{H_2O})}{(V_{H_2O} + V_{\text{DSCF}})} \times 100 = \frac{(20.23)}{(20.23 + 51.491)} \times 100 = \boxed{28.26}$$

$$E \left[\frac{\text{GR}}{\text{DSCF}} \right] = \left[\frac{\text{Mg Samp}}{V_{\text{DSCF}}} \right] \left[\frac{15.43 \text{ GR/GM}}{1000 \text{ Mg/GM}} \right] = \left[\frac{30.5}{51.491} \right] 0.01543 = \boxed{0.0091}$$

$$E \left[\frac{\text{lb}}{\text{hr}} \right] = \left[\frac{\text{GR}}{\text{DSCF}} \right] \left[V_s \times A_{\text{STK}} \right] \left[\frac{528}{T_s} \right] \left[\frac{P_s}{29.92} \right] \left[\frac{1 \text{ lb}}{7000 \text{ GR}} \right] \left[\frac{3600 \text{ sec}}{\text{hr}} \right] \left[\frac{100 - \% M}{100} \right]$$

$$= \boxed{0.0091} \left[(32.2) (122.7) \right] \left[\frac{528}{828} \right] \left[\frac{29.88}{29.92} \right] \left[\frac{3600}{7000} \right] \left[\frac{100 - (28.26)}{100} \right] = 8.4$$

STACK GAS VELOCITY



LOCATION: LEHIGH CEMENT - CEMENTON

UNIT KILN

FUEL COAL

$$V_s = 85.48 (C_{\text{pitot}}) \left(\frac{(T_s) (\Delta P)}{(P_s) (MW_s)} \right)^{1/2} = 85.48 (.84) \left(\frac{(831.4) (0.17)}{(29.92) (23.12)} \right)^{1/2} = \boxed{30.4}$$

Where: C_{pitot} = Pitot tube correction factor
 T_s = Absolute average stack gas temperature °R.
 ΔP = Average stack ΔP , inches H_2O .
 P_s = Absolute stack gas pressure, inches H_g .
 MW_s = Stack gas molecular weight

ISO KINETIC CALCULATION

$$I = \frac{123.76 (V_m)}{(D^2) (T_m) (\theta)} \left(\frac{T_s}{\Delta P} \right)^{1/2} \left[\frac{100}{100 - \% \text{ Moisture}} \right]$$

$$I = \frac{123.76 (48.134)}{(0.376)^2 (531.6) (72)} \left(\frac{831.4}{0.17} \right)^{1/2} \left[\frac{100}{(72.0)} \right] = \boxed{104.75 \%}$$

Where:

I = Percent of isokinetic sampling
 V_1 = Total volume of liquid collected in impingers and silica gel, ml.
 V_m = Volume of gas sample through the dry gas meter (meter conditions), cu.ft.
 T_m = Absolute average dry gas meter temperature °R
 P_{bar} = Barometric pressure at sampling site, inches H_g .
 ΔH = Average pressure drop across the orifice, inches H_2O .
 θ = Total sampling time, min.

PARTICULATE CALCULATIONS

$$V_{\text{DSCF}} = \left(\frac{T_{\text{Std}}}{P_{\text{Std}}} \right) \left(\frac{V_m}{T_m} \right) \left[P_b + \left(\frac{\Delta H}{13.6} \right) \right] = \text{ @ 528 °R } 29.92 \text{ "Hg}$$

$$= 17.65 \left(\frac{48.134}{531.6} \right) \left[29.92 + \left(\frac{1.65}{13.6} \right) \right] = 47.825$$

$$V_{H_2O} = 0.047 (V_1) = 0.047 (431.00) = 20.26$$

$$\% \text{ Moisture} = \frac{(V_{H_2O})}{(V_{H_2O} + V_{\text{DSCF}})} \times 100 = \frac{(20.26)}{(20.26 + 47.825)} \times 100 = \boxed{29.80 \%}$$

$$E \left[\frac{\text{GR}}{\text{DSCF}} \right] = \left[\frac{\text{Mg Samp}}{V_{\text{DSCF}}} \right] \left[\frac{15.43 \text{ GR/GM}}{1000 \text{ Mg/GM}} \right] = \left[\frac{31.5}{47.825} \right] 0.01543 = \boxed{0.0102}$$

$$E \left[\frac{\text{lb}}{\text{hr}} \right] = \left[\frac{\text{GR}}{\text{DSCF}} \right] \left[V_s \times A_{\text{STK}} \right] \left[\frac{528}{T_s} \right] \left[\frac{P_s}{29.92} \right] \left[\frac{1 \text{ lb}}{7000 \text{ GR}} \right] \left[\frac{3600 \text{ sec}}{\text{hr}} \right] \left[\frac{100 - \% M}{100} \right]$$

$$= \left[0.0102 \right] \left[(30.4) (122.7) \right] \left[\frac{531.6}{831.4} \right] \left[\frac{29.92}{29.92} \right] \left[\frac{3600}{7000} \right] \left[\frac{100 - (29.80)}{100} \right] = 8.7$$

STACK GAS VELOCITY



Date: 11/1/04

W.H.R.

LOCATION: LEHIGH CEMENT-CEMENTON

UNIT: KILN FUEL: COAL

$$V_s = 85.48 (C_{\text{pitot}}) \left(\frac{T_s (\Delta P)}{(P_s) (MW_s)} \right)^{1/2} = 85.48 (.84) \left(\frac{(826.5) (.21)}{(29.73) (21.4)} \right)^{1/2} = \boxed{33.0}$$

Where: C_{pitot} = Pitot tube correction factor

T_s = Absolute average stack gas temperature °R.

ΔP = Average stack ΔP , inches H_2O .

P_s = Absolute stack gas pressure, inches H_g .

MW_s = Stack gas molecular weight

ISOKINETIC CALCULATION

$$I = \frac{123.76 (V_m)}{(D^2) (T_m) (\theta)} \left(\frac{T_s}{\Delta P} \right)^{1/2} \left[\frac{100}{100 - \% \text{ Moisture}} \right]$$

$$I = \frac{123.76 (50.783)}{(0.376)^2 (537.1) (72)} \left(\frac{826.5}{29.73} \right)^{1/2} \left[\frac{100}{(69.90)} \right] = \boxed{102.31 \%}$$

Where:

I = Percent of isokinetic sampling

V_1 = Total volume of liquid collected in impingers and silica gel, ml.

V_m = Volume of gas sample through the dry gas meter (meter conditions), cu.ft.

T_m = Absolute average dry gas meter temperature °R

P_{bar} = Barometric pressure at sampling site, inches H_g .

ΔH = Average pressure drop across the orifice, inches H_2O .

θ = Total sampling time, min.

PARTICULATE CALCULATIONS

$$V_{\text{DSCF}} = \left(\frac{T_{\text{Std}}}{P_{\text{Std}}} \right) \left(\frac{V_m}{T_m} \right) \left[P_b + \left(\frac{\Delta H}{13.6} \right) \right] = \text{ @ 528 °R } 29.92 \text{ "Hg}$$

$$= 17.65 \left(\frac{50.783}{537.1} \right) \left[29.79 + \left(\frac{1.86}{13.6} \right) \right] = 49.948$$

$$V_{H_2O} = 0.047 (V_1) = 0.047 (456.5) = 21.46$$

$$\% \text{ Moisture} = \frac{(V_{H_2O})}{(V_{H_2O} + V_{\text{DSCF}})} \times 100 = \frac{(21.46)}{(21.46 + 49.948)} \times 100 = \boxed{30.10 \%}$$

$$E \left[\frac{\text{GR}}{\text{DSCF}} \right] = \left[\frac{\text{Mg Samp}}{V_{\text{DSCF}}} \right] \left[\frac{15.43 \text{ GR/GM}}{1000 \text{ Mg/GM}} \right] = \left[\frac{42.0}{49.948} \right] 0.01543 = \boxed{0.0130}$$

$$E \left[\frac{\text{lb}}{\text{hr}} \right] = \left[\frac{\text{GR}}{\text{DSCF}} \right] \left[V_s \times A_{\text{STK}} \right] \left[\frac{528}{T_s} \right] \left[\frac{P_s}{29.92} \right] \left[\frac{1 \text{ lb}}{7000 \text{ GR}} \right] \left[\frac{3600 \text{ sec}}{\text{hr}} \right] \left[\frac{100 - \% M}{100} \right]$$

$$= \left[0.0130 \right] \left[(33.0) (122.7) \right] \left[\frac{528}{826.5} \right] \left[\frac{29.73}{29.92} \right] \left[\frac{3600}{7000} \right] \left[\frac{100 - (30.10)}{100} \right] = 12.0$$

APPENDIX J

FUEL ANALYSIS

WARNER LABORATORIES, INC.

EST. 1923

P.O. BOX 214

CRESSON, PA. 16630

PHONE (814) 886-7400

AS A MUTUAL PROTECTION TO CLIENTS, THE PUBLIC AND OURSELVES, ALL REPORTS ARE SUBMITTED AS THE CONFIDENTIAL PROPERTY OF CLIENTS, AND AUTHORIZATION FOR PUBLICATION OF STATEMENTS, CONCLUSIONS OR EXTRACTS FROM OR REGARDING OUR REPORTS IS RESERVED PENDING OUR WRITTEN APPROVAL.

DATE 11-16-84
WARNER NO. 627088

LEHIGH PORTLAND CEMENT CO.
P.O. BOX 117
CEMENTON, NEW YOR 12415

SAMPLE ID: COAL PIPE

OPERATING CO.:
SAMPLED BY: CUSTOMER PROVIDED
MINE:
LOCATION:

DATE SAMPLED: 11/8/84

DATE RECEIVED: 11/15/84

WEATHER:
GROSS WEIGHT:

OTHER ID: SAMPLE DRIED AND PULVERIZED WHEN SUBMITTED

CERTIFICATE OF ANALYSIS

	AS RECEIVED	DRY BASIS
MOISTURE	1.22%	XXX
VOLATILE MATTER	32.62%	33.02%
FIXED CARBON	50.21%	50.83%
ASH	15.95%	16.15%
SULFUR	2.63%	2.66%
CARBON	68.55%	69.39%
HYDROGEN	4.67%	4.73%
NITROGEN	1.24%	1.26%
OXYGEN	5.74%	5.81%
BTU/LB	12452	12606
MAF BTU/LB		15034

APPROVED BY [Signature]



WE SPECIALIZE IN:
Complete Analyses of Coal and Coke, Grindability and Washability Tests.
Ultimate Analyses of Ash, Analyses of Clay-Lime-Limestone.
Chemical and Bacteriological Analyses of Water Supplies and Analyses of Mine and Boiler Water.

WARNER LABORATORIES, INC.

EST. 1923

P.O. BOX 214

CRESSON, PA. 16630

PHONE (814) 886-7400

AS A MUTUAL PROTECTION TO CLIENTS, THE PUBLIC AND OURSELVES, ALL REPORTS ARE SUBMITTED AS THE CONFIDENTIAL PROPERTY OF CLIENTS, AND AUTHORIZATION FOR PUBLICATION OF STATEMENTS, CONCLUSIONS OR EXTRACTS FROM OR REGARDING OUR REPORTS IS RESERVED PENDING OUR WRITTEN APPROVAL.

DATE: 11-16-84

WARNER NO. 827089

LEHIGH PORTLAND CEMENT CO.
P O. BOX 117
CEMENTON, NEW YOR 12415

SAMPLE ID: COAL PIPE

OPERATING CO.:

SAMPLED BY: CUSTOMER PROVIDED

MINE:

LOCATION:

DATE SAMPLED: 11/9/84

DATE RECEIVED: 11/19/84

WEATHER:

GROSS WEIGHT:

OTHER ID: SAMPLE DRIED AND PULVERIZED WHEN SUBMITTED

CERTIFICATE OF ANALYSIS

AS RECEIVED

DRY BASIS

MOISTURE
VOLATILE MATTER
FIXED CARBON
ASH

1.03%	XXX
33.92%	33.88%
50.33%	50.86%
15.10%	15.26%

SULFUR

2.38%	2.40%
-------	-------

CARBON

69.94%	70.68%
--------	--------

HYDROGEN

4.78%	4.83%
-------	-------

NITROGEN

1.29%	1.30%
-------	-------

OXYGEN

5.46%	5.53%
-------	-------

BTU/LB

12678	12812
-------	-------

MAF BTU/LB

15118

APPROVED BY: *[Signature]*



WE SPECIALIZE IN:

Complete Analysis of Coal and Coke, Grindability and Washability Tests.
Ultimate Analysis of Ash, Analysis of Clay-Lime-Limestone.
Chemical and Bacteriological Analysis of Water Supplies and Analysis of Mine and Boiler Water.

APPENDIX K

CHAIN OF CUSTODY FORMS



METHOD 5

PARTICULATE SAMPLE RECOVERY AND INTEGRITY SHEET

Plant: LENIGH - CEMENTON Sample date: 11/8/84
Sample location: KILN EXHAUST STACK Run no.: Comp 1
Sample recovery person: P. COVIELLO Recovery date: 11/8/84
Filter(s) no.: #4

MOISTURE

Impingers Silica gel
Final volume (wt) 714 ml (gm) Final wt. 216.5 g _____
Initial volume (wt) 300 ml (gm) Initial wt. 200.0 g _____
Net volume (wt) 414 ml (gm) Net wt. 16.5 g _____
Total moisture 430.5 g
Color of silica gel BLUE/PINK
Description of impinger water CLEAR - MINIMUM
RESIDUE

RECOVERED SAMPLE

Filter container no. #4 sealed 11/8/84 RETRI
Description of particulate on filter CREAM / CHALKY

Acetone rinse Liquid level
container no. #16 marked 173 mL
Acetone blank Liquid level
container no. #44 marked 175 mL
Samples stored and locked 11/9/84
Remarks: EVAPORATED ON SITE - VENT HOOD

Date of laboratory custody 11/8/84
Laboratory personnel taking custody R. BAKER RLB
Remarks: 24 HR. - DESICCATED



METHOD 5

PARTICULATE SAMPLE RECOVERY AND INTEGRITY SHEET

Plant: LEHIGH-CEMENTON Sample date: 11/9/84
Sample location: KILN EXHAUST STACK Run no.: Comp 3
Sample recovery person: P. COVIELLO Recovery date: 11/9/84
Filter(s) no.: #7

MOISTURE

Impingers Silica gel
Final volume (wt) 742 ml(gm) Final wt. 214.5 g
Initial volume (wt) 300 ml(gm) Initial wt. 200.0 g
Net volume (wt) 442 ml(gm) Net wt. 14.5 g
Total moisture 456.5 g
Color of silica gel BLUE/PINK
Description of impinger water CLEAR - SLIGHTLY
CLOUDY @ BOTTOM - SOME VISIBLE SEDIMENT

RECOVERED SAMPLE

Filter container no. #7 sealed 11/9/84
Description of particulate on filter CREAM - CHALKY

Acetone rinse container no. #4 Liquid level marked 186

Acetone blank container no. #44 Liquid level marked 175

Samples stored and locked 11/9/84

Remarks: EVAPORATED ON SITE - NOT MOIST

Date of laboratory custody 11/9/84

Laboratory personnel taking custody R. BAKER RLB

Remarks: 24 hr ASSOCIATED



METHOD 5

PARTICULATE SAMPLE RECOVERY AND INTEGRITY SHEET

Plant: LEHIGH-CEMENTON Sample date: 11/9/84
Sample location: KILN EXHAUST STACK Run no.: CAMP 2
Sample recovery person: P. COVIELLO Recovery date: 11/9/84
Filter(s) no.: #5

MOISTURE

Impingers	Silica gel
Final volume (wt) <u>718</u> ml (gm)	Final wt. <u>213.0</u> g
Initial volume (wt) <u>300</u> ml (gm)	Initial wt. <u>200.0</u> g
Net volume (wt) <u>418</u> ml (gm)	Net wt. <u>13.0</u> g
Total moisture <u>431</u> g	
Color of silica gel <u>BLUE / PINK</u>	
Description of impinger water <u>CLEAR - SLIGHTLY</u> <u>CLOUDY AT BOTTOM - NO DETECTABLE SEDIMENT</u>	

RECOVERED SAMPLE

Filter container no. #5 sealed 11/9/84 RETN
Description of particulate on filter CREAM / CHALKY

Acetone rinse container no. <u>#6</u>	Liquid level marked <u>193</u>
Acetone blank container no. <u>#44</u>	Liquid level marked <u>175</u>
Samples stored and locked <u>11/10/84</u>	
Remarks: <u>EVAPORATED ON-SITE - VENT 9000</u>	

Date of laboratory custody 11/9/84
Laboratory personnel taking custody R. BAKER RLB
Remarks: 24 HR DESICCATED



METHOD 6 SAMPLE RECOVERY AND INTEGRITY DATA

PLANT LEHIGH CEMENT - CEMENTON SAMPLE LOCATION STACK (KILN)FIELD DATA CHECKS
SAMPLE RECOVERY PERSONNEL R.A. PARKER, P.C. COVIELLO
PERSON WITH DIRECT RESPONSIBILITY FOR RECOVERED SAMPLES R.L. BAKER

Sample no.	Sample identification no.	Date of recovery	Liquid level marked	Stored in locked container
1	LC-COMP-1	11/8/84	280 ML	11/8/84 RLB
2	LC-COMP-2	11/9/84	275 ML	11/9/84 RLB
3	LC-COMP-3	11/9/84	290 ML	11/9/84 RLB
4	_____			
5	_____			
6	_____			
Blank	LC-BLANK	11/8/84	250 ML	11/9/84 RLB

REMARKS _____

SIGNATURE OF FIELD SAMPLE TRUSTEE *[Signature]*

LABORATORY DATA CHECKS

LAB PERSON WITH DIRECT RESPONSIBILITY FOR RECOVERED SAMPLES R.A. PARKERDATE RECOVERED SAMPLES RECEIVED ANALYZED ON-SITE 11/8-11/10/84ANALYST R.A. PARKER

Sample no.	Sample identification no.	Date of analysis	Liquid at marked level	Sample identified
1	LC-COMP-1	11/8/84	280	R.A.P.
2	LC-COMP-2	11/9/84	275	R.A.P.
3	LC-COMP-3	11/10/84	290	R.A.P.
4	_____			
5	_____			
6	_____			
Blank	LC-BLANK	11/10/84	250	R.A.P.

REMARKS _____

SIGNATURE OF LAB SAMPLE TRUSTEE *[Signature]*

APPENDIX L

COMMUNICATIONS WITH NYS-DEC



A Research-Cottrell Company

18006 Skypark Blvd., P.O. Box 19518, Irvine, California 92714 (714) 250-6200

November 1, 1984

Mr. Richard Forgea
Senior Engineer
New York State -
Department of Environmental Conservation
Region IV
2176 Guilderland Avenue
Schenectady, New York 12306

Subject: Compliance Test Protocol - Particulate and Sulfur
Oxide Emissions -Lehigh Portland Cement - Cementon, NY

Dear Mr. Forgea:

At the request of Lehigh Portland Cement, I am forwarding four (4) copies of the test protocol prepared for the compliance series at Lehigh Cement's Cementon, New York portland cement facility. As we discussed during our telephone conversation last month, the testing will consist of a series of three Environmental Protection Agency method 5 particulate tests and a concurrent series of three method 6 sulfur oxide (SO₂) tests conducted at the kiln exhaust stack.

It appears that the tentative compliance testing schedule of November 8th and 9th remains most appropriate. I will await your review of this protocol. KVB will be on site at the plant the entire week of November 5th should you care to schedule a meeting with Mr. Sandbrook, plant manager, Mr. John Jones, Asst plant manager, and I to discuss the test program.

In any event, I will contact your office on Monday to confirm receipt of this test protocol. Perhaps a meeting can be scheduled then.

Thank you for your cooperation. KVB looks forward to again working with the State of New York.

cy: D. Sandbrook - Lehigh
J. Jones - Lehigh
S. Hunter - KVB
ATT: Compliance Test Protocol

Sincerely,
KVB Inc.

Ronald Baker

APPENDIX M

SULFUR ANALYSIS DATA



METHOD 6

SULFUR DIOXIDE ANALYTICAL DATA

PLANT LEHIGH - CEMENTON, NY DATE 11/8/84
SAMPLE LOCATION STACK (KILN) ANALYST R.A. PARKER

NORMALITY OF BARIUM PERCHLORATE
1 6.2 ml 0.016 N
2 6.3 ml 0.0159 N 0.016 N
3 6.2 ml 0.016 N

Run No.	Sample No.	Total* Volume of Sample	Sample Aliquot	Volume of Titrant V_t , ml			AVG.
				1st Titration	2nd Titration	3rd Average	
1	LC-COMP-1	280 ml	1.0 ml	8.8	8.7	8.8	8.8
2	LC-COMP-2	275 ml	1.0 ml	8.6	8.5	8.5	8.5
3	LC-COMP-3	290 ml	1.0 ml	6.7	6.8	6.7	6.7
4	—						
5	—						
6	—						

* STANDARDIZED TO 1000 ml

Blank Analysis - Volume of titrant 1st titration < 0.1 ml
2nd titration < 0.1 ml
Average < 0.1 ml

1st titration = 0.99 to 1.01 or 1st titration - 2nd titration = 0.2
2nd titration

Signature of Analyst R. Parker
Signature of Reviewer or Supervisor [Signature]

SO₂ EMISSIONS CALCULATION

Test # LC-CAMP-1

Station LEHIGH - CEMENTON, NY

Test Location STACK (KILN)

Date 11/8/84

N_{BaCl} 0.016 eq/l

V_{BaCl} 8.8, 8.7, 8.8 ml

V_{sample} 1000 ml

V_{aliquot} 1.0 ml

V_{dry gas} 51.227 ft³

ΔH 1.88 °H₂O

T_{meter} 528 °R

O₂ 7.3 %

P_{bar.} 29.85 "Hg

V_{H2O} 430.5 ml

Duct Area 122.7 ft²

3% H₂O₂ can absorb: 50 mg SO₂
ml 3% H₂O₂

$$\left(\frac{\text{g-moles SO}_2}{2 \text{ eq}} \right) \left(\frac{0.016 \text{ eq.}}{1} \right) \left(\frac{8.8 \text{ ml}}{\text{normality of BaCl}} \right) \left(\frac{1000}{1.0} \right) \left(\frac{1}{1000 \text{ ml}} \right) = \frac{0.0704}{\text{g-moles SO}_2}$$

$$\left(0.0704 \text{ g-moles SO}_2 \right) \left(\frac{64.06 \text{ g}}{\text{g-mole}} \right) = 4.510 \text{ grams SO}_2$$

Aliquot Factor = $\frac{V_{\text{sample}}}{V_{\text{aliquot}}}$

$$V_s = 2.42 \sqrt{T_s \Delta P} = 32.2 \text{ ft/sec} \quad \text{FROM METHOD 5 PRINT-OUT - APPENDIX A}$$

$$V_{\text{SO}_2 \text{ SCF}} = (0.8497) (0.0704 \text{ g-moles SO}_2) = 0.0598 \text{ SCF SO}_2$$

$$V_{\text{DSCF}} = (51.227 \text{ ft.}^3) \left(\frac{29.85 \text{ "Hg} + 1.88 \text{ "H}_2\text{O}}{29.92} \right) \left(\frac{528}{528 \text{ °R}} \right) = 51.343 \text{ DSCF}$$

$$\text{ppm SO}_2 = \left(\frac{0.0598 \text{ SCF SO}_2}{51.343 \text{ DSCF} + 0.0598 \text{ SCF SO}_2} \right) \left(\frac{1.8 \times 10^7}{21 - 7.3} \right) = 1540$$

dry, 3% O₂

$$\left(\frac{4.510 \text{ grams SO}_2}{\text{DSCF} + \text{SO}_2 \text{ scf} + \text{H}_2\text{O scf}} \right) \left(\frac{528}{T_s \text{ °R}} \right) \left(\frac{29.92}{P_{\text{bar}} + P_{\text{stack}}} \right)^4 \left(V_s \frac{\text{ft}}{\text{sec}} \right) \left(\text{Duct Area ft}^2 \right) = \frac{\text{grams}}{\text{second}}$$

$$\left(\frac{4.510}{51.343 + 0.0598 + 20.279} \right) \left(\frac{528}{828} \right) \left(\frac{29.92}{29.85 + 0.1} \right)^4 (32.2) (122.7) = 157.9 \text{ grams second}$$



SO₂ EMISSIONS CALCULATION

Test # LC-COMP-2

Station LEHIGH CEMENTON, NY

Test Location STACK (KILN)

Date 11/8/84

N_{BaCl} 0.016
V_{BaCl} 8.6, 8.5, 8.5
V_{sample} 1000
Valiquot 1.0
V_{dry gas} 48.154
ΔH 1.65
T meter 532
O₂ 6.75
P_{bar.} 29.79
V_{H2O} 431
Duct Area 122.7

3% H₂O₂ can absorb: 50 mg SO₂
ml 3% H₂O₂

$$\left(\frac{\text{g-moles SO}_2}{2 \text{ eq}} \right) \left(\frac{0.016 \text{ eq.}}{1 \text{ L.}} \right) \left(8.5 \text{ ml} \right) \left(\frac{1000}{1.0} \right) \left(\frac{1}{1000 \text{ ml}} \right) = 0.0680 \text{ g-moles SO}_2$$

normality of BaCl Volume of BaCl Aliquot Factor = $\frac{V_{\text{sample}}}{V_{\text{aliquot}}}$

$$(0.0680 \text{ g-moles SO}_2) \left(64.06 \frac{\text{g}}{\text{g-mole}} \right) = 4.356 \text{ grams SO}_2$$

$V_s = 2.42 \sqrt{T_s \Delta P} = 30.4 \text{ ft/sec}$ FROM METHOD 5 PRINTOUT - APPENDIX A

$$V_{\text{SO}_2 \text{ SCF}} = (0.8497) (0.0680 \text{ g-moles SO}_2) = 0.0578 \text{ SCF SO}_2$$

$$V_{\text{DSCF}} = (48.154 \text{ ft.}^3) \left(\frac{29.79 \text{ "Hg} + 1.65 \text{ "H}_2\text{O}}{29.92} \right) \frac{528}{532^\circ \text{R}} = 47.778 \text{ DSCF}$$

$$\text{ppm SO}_2 = \left(\frac{0.0578 \text{ SCF SO}_2}{47.778 \text{ DSCF} + 0.0578 \text{ SCF SO}_2} \right) \frac{1.8 \times 10^7}{21 - 6.75 \% \text{ O}_2} = 1537$$

$$\left(\frac{\text{grams SO}_2}{\text{DSCF} + \text{SO}_2 \text{ scf} + \text{H}_2\text{O scf}} \right) \left(\frac{528}{T_s^\circ \text{R}} \right) \left(\frac{29.92}{P_{\text{bar}} + P_{\text{stack}}} \right) \left(V_s \frac{\text{ft}}{\text{sec}} \right) \left(\text{Duct Area ft}^2 \right) = \frac{\text{GRAMS}}{\text{SECOND}}$$

$$\left(\frac{4.356}{47.778 + 0.0578 + 20.302} \right) \left(\frac{528}{831} \right) \left(\frac{29.92}{29.79 - 1.65}{13.6} \right) (30.4) (122.7) = 150.6 \frac{\text{GRAMS}}{\text{SECOND}}$$



SO₂ EMISSIONS CALCULATION

Test # LC-COMP-3

Station LEHIGH-CEMENTON, NY

Test Location STACK (KILN)

Date 11/2/64

N _{BaCl}	<u>0.016</u>	eq/l
V _{BaCl}	<u>6.7, 6.8, 6.7</u>	ml
V _{sample}	<u>1000</u>	ml
Valiquot	<u>1.0</u>	ml
V _{dry gas}	<u>50.703</u>	ft ³
ΔH	<u>1.86</u>	"H ₂ O
T meter	<u>537</u>	°R
O ₂	<u>7.3</u>	%
P bar.	<u>29.79</u>	"Hg
V _{H2O}	<u>456.5</u>	ml
Duct Area	<u>172.7</u>	ft ²

3% H₂O₂ can absorb: 50 mg SO₂
ml 3% H₂O₂

$$\left(\frac{\text{g-moles SO}_2}{2 \text{ eq}} \right) \left(\frac{0.016 \text{ eq.}}{1} \right) \left(\frac{6.7 \text{ ml}}{1} \right) \left(\frac{1000}{1.0} \right) \left(\frac{1}{1000 \text{ ml}} \right) = \frac{0.0536}{\text{g-moles SO}_2}$$

$$\left(0.0536 \text{ g-moles SO}_2 \right) \left(\frac{64.06 \text{ g}}{\text{g-mole}} \right) = \underline{3.434} \text{ grams SO}_2$$

$$V_s = 2.42 \sqrt{T_s \Delta P} = \text{ft/sec FROM METHOD 5 PRINTOUT - APPENDIX A}$$

$$V_{\text{SO}_2 \text{ SCF}} = (0.8497) (0.0536 \text{ g-moles SO}_2) = \underline{0.0455} \text{ SCF SO}_2$$

$$V_{\text{DSCF}} = (50.703 \text{ ft.}^3) \left(\frac{29.79 \text{ "Hg} + 1.86 \text{ "H}_2\text{O}}{29.92} \right) \frac{528}{537^\circ \text{R}} = \underline{49.943} \text{ DSCF}$$

$$\text{ppm SO}_2 = \left(\frac{0.0455 \text{ SCF SO}_2}{49.943 \text{ DSCF} + 0.0455 \text{ SCF SO}_2} \right) \frac{1.8 \times 10^7}{21 - 7.3} = \underline{1205}$$

$$\left(\frac{3.434 \text{ grams SO}_2}{\text{DSCF} + \text{SO}_2 \text{ scf} + \text{H}_2\text{O scf}} \right) \left(\frac{528}{T_s \text{ }^\circ \text{R}} \right) \left(\frac{29.92}{P_{\text{bar}} + P_{\text{stack}}} \right)^{-1} \left(V_s \frac{\text{ft}}{\text{sec}} \right) \left(\text{Duct Area ft}^2 \right) = \underline{\text{grams second}}$$

$$\left(\frac{3.434}{49.943 + 0.0455 + 21.804} \right) \left(\frac{528}{826} \right) \left(\frac{29.92}{29.79 - \frac{0.80}{13.6}} \right)^{-1} (33.0) (172.7) = \underline{123.5} \text{ grams second}$$

LEHIGH PORTLAND CEMENT COMPANY

LEHIGH

CEMENTON PLANT
BOX 117, CEMENTON, N. Y. 12418

512 943-5300

November 26, 1984


Mr. Ronald Baker
KVB, Engineering and Research Division
18006 Skypark Blvd.
P.O. Box 19518
Irvine, CA. 92714

Dear Mr. Baker,

SO
Enclosed are the chemical results for the kiln feed, clinker, coal and dust samples taken during your kiln testing at the Cementon Plant November 8th and 9th. I have also enclosed the coal analyses from Warner Laboratories.

If you have any further questions, do not hesitate to contact us.

Yours truly,



Cheryl McElroy
Quality Control Supervisor

CM:cw

ms
ond

CHEMICAL ANALYSIS

Sample Date Nov 9, 1984

CLINKER	Return		Waste		COAL	PIPE
	KILN FEED II	DUST 409 V	DUST 420 V			
23.08	23.46			Moist.	.58	
4.61	4.17			VOL.	34.22	
3.65	3.29			ASH	15.25	
65.67	67.10			F.C.	49.95	
1.73				S	2.29	
—	.16	3.75	1.95	BTU	12.558	
.78	—	—	—			
		.64	.48			
		7.12	3.60			
	35.27	24.37	22.19			
		5.32	2.84			

total Alk.

CHEMICAL ANALYSIS

Sample Date Nov 8, 1984

II	Return		Waste		COAL PIPE				
	KILN FEED	DUST 409 V	DUST 420 V						
CLINKER									
23.38	22.90			Moist.	.79				
4.98	4.48			Vol.	34.29				
3.70	3.38			Ash	16.02				
65.94	67.07			F.C.	48.90				
1.69	.88			S	2.58				
—	.14	2.86	3.75	BTU	12442				
.82	—	—	—						
		.52	.64						
		4.68	5.52						
	34.81	21.10	21.27						
		3.59	4.27						

102

203

203

10

50

203

203

20

20

loss

total

total Alk.

SULFUR EMISSIONS RESULTS

TEST NUMBER	LC-COMP-1	LC-COMP-2	LC-COMP-3	AVERAGE
DATE OF TEST	11/8/84	11/9/84	11/9/84	
TEST TIME				
START	15:25	13:16	16:10	
STOP	16:57	15:15	17:53	
KILN OPERATION				
RAW FEED (GPM)	400.00	400.00	405.00	401.67
% MOISTURE	35.00	35.00	35.00	35.00
COAL FLOW (TPH)	16.80	16.40	16.40	16.53
HEAT VAL (BTU/LB)	12606.00	12812.00	12812.00	12743.33
RATE (10 ⁶ BTU/HR)	423.56	420.23	420.23	421.34
DUST WASTED (TPH) ESTIM	21.00	21.00	21.00	21.00
KILN EXIT %O2	2.60	2.30	2.70	2.53
SAMPLING DATA				
TEST PERIOD (MIN)	72.00	72.00	72.00	72.00
VOLUME SAMPLED (DSCF)	51.49	47.83	49.95	49.75
STACK TEMP (F)	368.00	371.00	366.00	368.33
METER TEMP (F)	67.00	72.00	77.00	72.00
STACK %OXYGEN	7.30	6.80	7.30	7.13
STACK %MOISTURE	29.80	29.80	28.30	29.30
STACK PRES (IN HG)	29.81	29.74	29.73	29.76
MOLECULAR WT (WET)	27.76	27.12	27.49	27.46
MOLECULAR WT (DRY)	31.60	31.00	31.58	31.39
SULFUR DIOXIDE EMISSIONS				
STACK FLOW (ACFM)	237050.00	223460.00	243090.00	234533.33
(DSCFM)	105725.82	99071.60	110706.58	105168.00
SO2 - PPM 23% O2				
EPA METHOD #6	1540.00	1537.00	1205.00	1427.33
SO2 RATE (GM/SEC)	157.90	150.60	123.50	144.00
(LB/HR)	1253.17	1195.24	980.16	1142.86
SULFUR RATE (GM/SEC)	78.95	75.30	61.75	72.00
(LB/HR)	626.59	597.62	490.08	571.43
(LB/10 ⁶ BTU)	1.48	1.42	1.17	1.36
O2	2.60	2.30	2.70	2.53
CO	214.00	491.00	340.00	415.00
NOX	1486.00	1353.00	1454.00	1431.00
SO2	1276.00	1389.00	889.00	
	-1.82	-16.21	9.30	-2.91
SULFUR BALANCE				
RAW FEED %S03	.14	.16	.16	
XS EQUIV	.06	.064	.064	.06
SULFUR (TPH DRY)	.16	.17	.17	
COAL XS	2.58	2.29	2.29	
SULFUR (TPH DRY)	.43	.38	.38	
TOTAL SULFUR IN -TPH	.59	.55	.55	
CLINKER %S03	.82	.78	.78	
XS EQUIV	.33	.31	.31	
EST. PROD RATE (TPD)	1480.00	1480.00	1490.00	
SULFUR (TPH DRY)	.20	.19	.19	
ESP DUST %S03	2.86	3.75	3.75	
XS EQUIV	1.14	1.50	1.50	
SULFUR (TPH DRY)	.24	.32	.32	
STACK SULFUR (TPH)	.31	.30	.25	
TOTAL SULFUR OUT-TPH	.75	.81	.76	
XS ABSORPTION	.52	.55	.45	



A Research-Cottrell Company

18006 Skypark Boulevard
P.O. Box 19518, Irvine, CA 92714
(714) 250-6200