

The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

COMPLIANCE EVALUATION

OF

PARTICULATE EMISSIONS

FROM THE

COKE WORKS BOILER
BAGHOUSE OUTLET STACK


AT

WHEELING PITTSBURGH STEEL CORPORATION
STEUBENVILLE EAST COKE PLANT
FOLLANSBEE, WEST VIRGINIA

BCM PROJECT NO. 00-5167-02

JANUARY 1981

PREPARED BY:



Douglas E. Seely
Project Scientist

APPROVED BY:



Bernard M. Lalli
Regional Manager

BETZ•CONVERSE•MURDOCH•INC.
1200 CENTRE CITY TOWER
650 SMITHFIELD STREET
PITTSBURGH, PENNSYLVANIA 15222

AP-42 Section 12.2
Reference
Report Sect. 4
Reference 151

TABLE OF CONTENTS

	<u>PAGE</u>
.0 INTRODUCTORY SUMMARY	1
.0 SCOPE AND OBJECTIVES	1
.0 PROCEDURES	
3.1 Field Work	2
3.2 Equipment Calibration	3
3.3 Analytical Methods	3
3.4 Calculations	3
.0 SUMMARY OF RESULTS	
4.1 Particulate Results	4
.0 DISCUSSION OF RESULTS	
5.1 Particulate Results	6

PPENDICES

- .. BCM Proposal
- .. Field Sampling Procedures
- .. Laboratory Analysis and Calculations
- .. Process Data

1.0 INTRODUCTORY SUMMARY

Wheeling Pittsburgh Steel Corporation (WPSC) retained Betz•Converse•Murdoch•Inc. (BCM) to perform a compliance evaluation of the particulate emissions from the Coke Works Boiler Baghouse Outlet Stack at their Steubenville East Coke Plant in Follansbee, West Virginia. The program was conducted on December 22 and 23, 1980 and consisted of three (3) EPA Method Five particulate emission tests. The following Table 1 summarizes the results:

Table 1
Particulate Emissions

	<u>Date</u>	<u>Time</u>	<u>gr/DSCF</u>	<u>lbs/hr</u>	<u>Gas Volume (DSCF)</u>
Run 1	12/22/80	1313	.0325	23.29	83477
Run 2	12/23/80	0909	.0417	27.51	77033
Run 3	12/23/80	1316	.0367	24.50	77374

2.0 SCOPE AND OBJECTIVES

The scope of this project was defined in a letter dated December 8, 1980, BCM Proposal No. 18-8239-06, a copy of which appears as Appendix A of this report. In summary, sampling was conducted to determine:

1. Gas Flow - ACFM and SCFM
2. Volume Gas Sampled - DSCF
3. Gas Temperature - °F
4. Moisture Content - % by Volume
5. Gas Stream Molecular Weight - Orsat Analysis - Volume % CO₂, Volume % O₂, Volume % CO and Volume % N₂ (by difference)
6. Particulate Concentration - gr/DSCF
7. Particulate Emissions - lbs/hr

The project involved three (3) EPA Method Five particulate samples.

3.0 PROCEDURES

A description of the procedures used to conduct the sampling program is given below:

3.1 Field Work

All field work was performed on December ~~16~~²² and ~~17~~²³, 1980 by a BCM field crew consisting of the following personnel:

Douglas E. Seely - Project Scientist
Daniel R. Petrovay - Technician
Jeffrey P. Bishop - Technician

Coordination between BCM and WPSC was provided by:

T. S. Landon - Corporate Project Engineer

The following methods, using procedures established and approved by the U.S. EPA, were employed during the program:

1. Sampling and traverse locations were determined as per Method One of the Federal Register, Volume 44, April 19, 1979, as amended, which is outlined in Appendix B, page B-1.
2. Gas flow, gas temperature and static pressure measurements were made as per Method Two of the Federal Register, Volume 44, April 19, 1979, as amended, which is outlined in Appendix B, page B-1.
3. Excess air and molecular weight determinations were performed as per Method Three of the Federal Register, Volume 44, April 19, 1979, as amended, which is outlined in Appendix B, page B-1.

4. Particulate matter and associated gas stream moisture were collected according to procedures of EPA Method Five as presented in the Federal Register, Volume 44, April 19, 1979, as amended, which is outlined in Appendix B, pages B-2 through B-4.

3.2 Equipment Calibration

In accordance with accepted procedures published by the United States Environmental Protection Agency (EPA), all gas velocity measuring equipment, volume metering equipment, temperature measuring equipment and flow rate metering equipment had been calibrated within 60 days of the actual test date. Calibration data is listed in Appendix B, pages B-23 and B-24.

3.3 Analytical Methods

Samples collected during the test program were analyzed by the BCM Laboratory in Plymouth Meeting, Pennsylvania. Refer to Appendix C, page C-1 for a detailed description of the methodologies used in the analysis of the samples. Table C-1, page C-8 of Appendix C lists the breakdown of the laboratory results.

3.4 Calculations

All calculations were performed through the use of a Hewlett-Packard 3000 Series II computer. Raw data generated from the sampling program were combined with the laboratory results and developed through the use of the equations presented in Methods Two through Five of the Federal Register for all particulate samples. Computer input and all other reduced data appear in Appendix C, pages C-8 through C-10. Pages C-3 through C-8 list the equations employed in the calculation of test results.

4.0 SUMMARY OF RESULTS

4.1 Particulate Results

A detailed listing of all evaluated parameters of the particulate tests is found in Appendix C, page C-10. The following Tables II and III summarize the results:

Table II
Particulate Results

	<u>Run 1</u>	<u>Run 2</u>	<u>Run 3</u>
Date	12/22/80	12/23/80	12/23/80
Time	1313	0909	1316
Sample Volume (DSCF)	60.18	58.21	57.69
Moisture (%)	2.1	5.3	5.3
Gas Temperature (°F)	333	369	358
Gas Velocity (FPM)	1993	1986	1983
Gas Volume (DSCFM)	83477	77033	77874
Isokinetics (%)	96.18	100.82	98.83
Particulate Concentration (GR/DSCF)	.0325	.0417	.0367
Particulate Emissions (LBS/HR)	23.29	27.51	24.50

Table III
Opacity Results

<u>Run No.</u>	<u>Time</u>	<u>Emissions ≥ 20% (min.)</u>	<u>Emissions ≥ 60% (min.)</u>	<u>Average Opacity (%)</u>	<u>Maximum Opacity (%)</u>
1	1313-1343 1357-1427 1447-1517 1529-1559	0	0	0.1	5
2	0909-0939 0953-1023 1052-1122 1131-1201	0	0	3.1	5
3	1316-1346 1353-1423 1431-1501 1509-1539	0	0	3.8	5

5.0 DISCUSSION OF RESULTS

5.1 Particulate Sampling Results

All sampling and analysis was performed in accordance with the procedures and specifications established or approved by the United States Environmental Protection Agency (EPA). All isokinetic percentages fell within the permissible limits of 90% to 110% as prescribed. The following discussion describes relevant aspects of isokinetic sampling theory.

The isokinetic percentage is indicative of the precision with which the sample gas flow rate was adjusted to be identical to the actual stack gas flow rate. It is the best criterion in determining the validity of an individual test, presupposing all other test specifications were closely adhered to.

The dynamics of particulate motion is of interest in source sampling because particle motion does not always coincide with gas stream motion. Particles smaller than three to five microns in diameter will follow gas flow streamlines irrespective of changes in direction. However, larger particles can be expected to deviate from flow streamlines.

When the velocity of the gas stream into the sampling probe is different from that in the main stream, the size distribution and the total weight concentration of the particulate matter collected will be different from those in the main stream. The explanation lies in the behavior of particles having sufficient mass and velocity to possess appreciable momentum. At velocities less than main stream velocity, all large particles in the path of the nozzle will be projected into the sample opening, while a portion of the air or gas in this stream will be deflected around the nozzle. This results in a sample stream entering the nozzle that has more large particles than are in the main stream aerosol. When sampling velocity is greater

than main stream velocity, an excess of main stream air will enter the nozzle. Smaller particles will follow the stream lines into the nozzle, but larger particles, because of the inertia, will not be drawn in. Various investigators differ as to the magnitude of error produced by sampling at other than isokinetic velocity but agree that it is significant for particles greater than 5 μ m. Deviations from isokinetic sampling rates probably do not significantly affect results for particles below 1 μ m in size.

The average particulate emission for the three tests performed was .0370 gr/DSCF, with the highest concentration being .0417 gr/DSCF.

The average emission rate is 25.10 lbs/hr with the highest rate at 27.51 lbs/hr. Two of the three tests were below the compliance limit of 24.98 lbs/hr with one test, Run 2, over the compliance limit.

All three tests were well within the compliance limits for opacities, with all three tests showing 0 minutes $\geq$ 20% opacity, and no opacities greater than 5%.

BCM PROPOSAL

APPENDIX A

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

December 9, 1980

Wheeling-Pittsburgh Steel Corporation
P. O. Box 118
Pittsburgh, PA 15230

Attention Mr. Doug Mangus, Purchasing Department

Subject: Compliance Evaluation of
Coke Works Boiler at
Steubenville East Coke Works of
Wheeling-Pittsburgh Steel Co.
WP P.O. No. 265-931
BCM Proposal No. 18-~~8240~~-06

18-7241-06

Gentlemen:

This letter will serve as the proposal for the above mentioned project. Betz • Converse • Murdoch • Inc. (BCM) will supply two (2) men for two (2) days with the necessary equipment to sample, evaluate and report test parameters. The testing program is to be performed on the coke works boiler at Wheeling-Pittsburgh Steel Corporation's (WPSC) Steubenville East Coke Works in Follansbee, West Virginia. The lump sum cost of this project, if performed on weekdays, tentatively December 22 and 23, 1980, is If it is performed on one weekday and one weekend day, tentatively December 19 and 20, 1980, the lump sum cost will be Final scheduling is to be decided by Mr. D. L. Roush of WPSC and Mr. D. E. Seely of BCM on December 18, 1980.

Delays caused by conditions beyond BCM's control, such as unfavorable weather conditions, partial or complete plant shutdowns, strikes, floods or forces which delay the project's completion, will be billed at an additional charge of per delay hour for the field sampling crew.

Every effort will be made to obtain results and convey them to WPSC by December 24, 1980, as requested by Mr. Roush.

Should you have any questions concerning this proposal or otherwise, please advise.

Very truly yours,

BETZ • CONVERSE • MURDOCH • INC.

Douglas E. Seely

Douglas E. Seely
Project Scientist

ES/dc

cc: Messrs. P. R. Charrington, M. D. Mueller
B. M. Lalli, D. L. Roush, D. E. Seely

Three Rivers Group

FIELD SAMPLING PROCEDURES

APPENDIX B

0 SAMPLING PROCEDURES

1.1 Test Station and Traverse Location

The test platform was located on the Coke Works Boiler Baghouse Outlet Stack approximately 88 feet above grade, approximately 5 diameters downstream and at least 8 stack diameters upstream from the nearest flow disturbance. To meet the requirements of EPA Method One, the tests sampled 40 points, 20 along each of two perpendicular diameters.

1.2 Gas Flow and Gas Temperature Measurements

The flow rate and temperature profiles for the gas streams were measured by conducting simultaneous velocity and temperature traverses. Gas velocity heads were measured with a calibrated "S" type Pitot tube which was connected to an inclined manometer. The static pressure was measured using the same Pitot tube and manometer. A Chromel-Alumel thermocouple attached to a THERMO-ELECTRIC CORPORATION digital potentiometer was used to measure the gas temperature at each of the traverse points. The gas flow and gas temperature measurements followed Method Two of the Federal Register.

1.3 Molecular Weight Determination

A Fisher-type B No. 10-605 Orsat analyzer was used to determine the molecular weight of the flue gas. The following parameters were measured in order to calculate molecular weight: volume percent carbon dioxide (CO_2), volume percent oxygen (O_2), and volume percent carbon monoxide (CO); the volume percentage of nitrogen (N_2) was determined by difference. These parameters were measured using the principle of gas absorption in specific absorbing solutions. A 100 ml flue gas sample was drawn through the glass manifold to the sample chamber by the use of the leveling bottle following aspiration of the sampling line. The system was then closed by adjusting the stopcock at the inlet of the manifold.

The sample was bubbled through three absorbing solutions which selectively collected different gaseous components of the stack gas in the following manner: carbon dioxide was collected in a potassium hydroxide solution in the first absorber, oxygen was collected in a potassium pyrogallate solution in the second absorber, and carbon monoxide was collected in a saturated cupric chloride solution in the third absorber. The volume of a specific gaseous component collected in an individual absorbing solution was determined by the change in volume of sample gas in the sample chamber after the bubbling process through that solution was complete. Since the original sample volume was 100 ml, any change in volume was also the percentage of the specific gaseous component found in the stack gas stream. Temperature effects in the sample chamber were minimized by a water jacket which surrounded it, maintaining the temperature at a constant level throughout the duration of the Orsat analysis.

1.4 Moisture Content Sampling

Sampling was conducted employing the principles presented in EPA Method Four and concurrently with particulate sampling. Parameters evaluated in order to determine the gas stream moisture content were: sample gas volume, sample gas temperature, sample gas pressure, impinger moisture gain, and silica gel moisture gain. Some minor modifications were made to the Method Four train to allow concurrent particulate and moisture content sampling; these modifications involved no deviations from sampling principles. Such modifications as the substitution of a glass fiber filter for Pyrex wool as a filtering medium and the substitution of a calibrated orifice for a rotameter as a flow metering device were incorporated.

1.5 Particulate Sampling

All sampling procedures and equipment utilized in the test program were those outlined in Method Five of the Federal Register. The size of the nozzle required to maintain isokinetic sampling was calculated from the results of the initial temperature and velocity traverses through the use of a nomograph. The sampling train utilized a stainless steel probe which was heated to 250°F by an internal heating element contained within a stainless steel sleeve. A nozzle of the calculated size was attached to the end of the probe which was inserted into the stack. A calibrated "S" type Pitot tube and a Chromel-Alumel thermocouple were clamped to the probe and were used to monitor the velocity head and the temperature at the traverse points during the sampling period.

Sample gas passed through the nozzle and the probe to a glass fiber filter for the removal of the suspended particulates. The filter was housed in a heated chamber whose temperature was maintained at about 250°F. The sample gas then passed through a transition line to the impinger train. The first two impingers each contained 150 ml of deionized water. The third impinger contained no reagents and was the knockout impinger. The fourth impinger contained approximately 200 grams of coarse silica gel which collected any moisture and/or vapors which had not been captured in the preceding impingers.

The second impinger was a standard Greenburg Smith, while the other three were modified by replacing the tip with a 1/2-inch glass tube. It should be noted that the entire impinger train was maintained at less than 70°F for all sample runs.

The sample gas was conducted from the impinger train through an umbilical cord to the control console, a Model 2343 RAC Stack Sampler, which contained the following pieces of equipment (listed in the order in which sample gas passed through them): a main


valve, a by-pass valve for flow adjustment, an air-tight vacuum pump, a calibrated dry gas meter, and a calibrated orifice. The orifice was equipped with pressure taps which were connected across an inclined manometer used to insure that isokinetic sampling conditions were maintained during the test. A schematic diagram of the sampling train is on page B-5 of this Appendix.

The sampling train was subjected to an optional leak check prior to each sample run. The entire sampling system was assembled and the probe and filter heating systems were allowed to stabilize at the desired operating temperatures. The nozzle inlet was plugged and a 15-inch mercury vacuum was pulled. The system was then checked and a leakage rate of less than 0.02 cfm was insured.

Upon completion of the test or at any time when a system component change, e.g., filter, was necessary, the system was subjected to a mandatory leak check. The procedure was identical to that stated above except that the leak check vacuum equalled or exceeded the maximum vacuum obtained during the test run. If the leakage rate was no greater than 0.02 cfm or four percent of the average sampling rate, the results were acceptable and no volume corrections were necessary. However, if a higher leakage rate was found, a volume correction was performed utilizing the criteria of Method Five.

2.0 Field Data Sheets

The gas velocity head, gas temperature, inlet and outlet gas meter temperatures, orifice differential pressure, sample volume, time and opacity were recorded during the testing program. Copies of these data sheets follow on pages B-6 to B-22 of this Appendix.



EPA METHOD 5 (filter only)

Sample Port Location: Wp Follinsbee


12	21	90
----	----	----

Pressure: _____

Barometric Pressure: _____

Factor: _____

eer: _____



Pitot/Temperature Readings 12 | 27 | 80

nt	Distance (Inches) + 18"	Port <u>4</u>		Port <u>6</u>		Port <u>3</u>		Port <u> </u>		Port <u> </u>	
		ΔP	T	ΔP	T	ΔP	T	ΔP	T	ΔP	T
	19.4	.14	330	.18		.34					
	22.2	.18		.17		.35					
	25.2	.17		.18		.34					
	28.5	.18		.18		.34					
	31.9	.18		.19		.33					
	35.8	.16	330	.19		.32					
	40.0					.30					
	45.0					.24					
	51.0					.13					
	60.0					.02					
AL											
G.			.18								

NOMOGRAPH DATA

PLANT WP FehnsbeeDATE 12/21/80SAMPLING LOCATION Boiler

CALIBRATED PRESSURE DIFFERENTIAL ACROSS ORIFICE, in. H ₂ O	ΔH_o	1.99
AVERAGE METER TEMPERATURE (AMBIENT + 20°F), °F	$T_{m_{avg}}$	50°F
VOLUME PERCENT MOISTURE IN GAS	B_{wo}	10%
BAROMETRIC PRESSURE AT METER, in. Hg	P_m	
STACK STATIC PRESSURE, in. Hg ($P_m \pm 0.073 \times$ STACK GAUGE PRESSURE)	P_s	
PITOT CALIBRATION FACTOR	C_p	.81
AVERAGE STACK TEMPERATURE	T_s	330
AVERAGE VELOCITY HEAD, in. H ₂ O	ΔP_{avg}	.18
MAXIMUM VELOCITY HEAD, in. H ₂ O	ΔP_{max}	.20
C FACTOR		.90
CALCULATED NOZZLE DIAMETER, in.		.35
ACTUAL NOZZLE DIAMETER, in.		.32
REFERENCE ΔP , in. H ₂ O		.29



FIELD DATA SHEET

PLANT WP Collinsboro
DATE 12/22/80
SAMPLING LOCATION Boiler
SAMPLE TYPE Particulate
RUN NUMBER 1
OPERATOR DES/DRP
AMBIENT TEMPERATURE 30°F
BAROMETRIC PRESSURE -72"
STATIC PRESSURE, (P_s) P-49
FILTER NUMBER (S) 7
GEL NUMBER (S) +12.4

PROBE NUMBER AND TYPE 270
NOZZLE I.D. AND NO. 107%
ASSUMED MOISTURE % 1
SAMPLE BOX NUMBER 9
METER BOX NUMBER 1.99
METER ΔH_c .9
C FACTOR 100
PROBE HEATER SETTING 100
HEATER BOX SETTING 100
REFERENCE ΔH .56
PITOT C_p AND NO. 9.7 .81

ORSAT:

CO₂ 3.5%
O₂ 16.0%
CO

READ AND RECORD ALL DATA EVERY 3 MINUTES

.017 cfm @ 16 ± 15

TRAVERSE POINT NUMBER	SAMPLING TIME, min	CLOCK TIME (24-hr CLOCK)	GAS METER READING (V _m), ft ³	VELOCITY HEAD (ΔP _s), in. H ₂ O	ORIFICE PRESSURE DIFFERENTIAL (ΔH), in. H ₂ O		STACK TEMPERATURE (T _s), °F	DRY GAS METER TEMPERATURE		PUMP VACUUM, in. Hg	SAMPLE BOX TEMPERATURE, °F	IMPINGER TEMPERATURE, °F
					DESIRED	ACTUAL		INLET (T _{m in}), °F	OUTLET (T _{m out}), °F			
A-10	00	1313	391.850		1.1	1.1	371	30	29	4	225	33
	03	1316	393.5	.33	1.05	1.05	330	34	30	3.5	225	33
	06	1319	395.1	.32	1.15	1.15	332	40	30	4	225	33
	09	1322	396.7	.34	1.1	1.1	338	45	30	4	225	33
	12	1325	398.4	.33	1.0	1.0	330	48	31	3.5	230	34
	15	1328	399.9	.31	1.05	1.05	331	50	32	4	230	34
	18	1331	401.5	.32	.98	.98	330	53	33	3.5	230	34
	21	1334	403.0	.30	.76	.76	330	56	33	3.5	230	34
	24	1337	404.4	.23	.50	.50	315	56	35	3	235	34
	27	1340	405.5	.15	.33	.33	301	53	35	2	235	34
B-10	30	1343	406.627	.10								
	30	1357	406.629	chg. P _{ts}								
	33	1400	408.3	.32	1.05	1.05	372	40	35	4	235	34
	36	1403	409.9	.33	1.1	1.1	318	44	36	4	230	35
	39	1406	411.4	.33	1.1	1.1	327	49	36	4	230	34
	42	1409	413.1	.35	1.15	1.15	325	54	36	4	230	34
	45	1412	414.7	.31	1.0	1.0	321	56	37	4	235	34
	48	1415	416.2	.30	.98	.98	379	59	37	4	235	35
	51	1418	417.7	.27	.89	.89	379	62	39	4	235	35
	54	1421	419.0	.22	.71	.71	378	61	39	3	235	35
	57	1424	420.1	.14	.46	.46	355	59	40	2	235	35
	60	1427	420.935	.09	.30	.30	217	58	40	2	235	35

BCM

FIELD DATA SHEET

PLANT LVP Full.
 DATE 12/23/80
 SAMPLING LOCATION 330000 Stk
 SAMPLE TYPE Particulate
 RUN NUMBER 2
 OPERATOR DES / DRP
 AMBIENT TEMPERATURE 35°F
 BAROMETRIC PRESSURE 29.4"
 STATIC PRESSURE (P_s) D-53
 FILTER NUMBER (S) 12
 GEL NUMBER 157 +12

PROBE NUMBER AND TYPE 170
 NOZZLE I.D. AND NO. 10.16
 ASSUMED MOISTURE % 1
 SAMPLE BOX NUMBER 9
 METER BOX NUMBER 1.99
 METER ΔH 9
 C FACTOR 100
 PROBE HEATER SETTING 100
 HEATER BOX SETTING 100
 REFERENCE ΔP 56
 PITOT C_p AND NO. 81, 77

ORSAT:

CO₂ 3.0
 O₂ 17.0
 CO

READ AND RECORD ALL DATA EVERY 3 MINUTES

Soot Blow @ 900

TRAVERSE POINT NUMBER	SAMPLING TIME min	CLOCK TIME (24 hr CLOCK)	GAS METER READING (V _m) ft ³	VELOCITY HEAD (ΔP _s) in. H ₂ O	ORIFICE PRESSURE DIFFERENTIAL (ΔH) in. H ₂ O		STACK TEMPERATURE (T _s) °F	DRY GAS METER TEMPERATURE		PUMP VACUUM in. Hg	SAMPLE BOX TEMPERATURE °F	IMPIINGER TEMPERATURE °F
					DESIRED	ACTUAL		INLET (T _{m in}) °F	OUTLET (T _{m out}) °F			
B-10	03	0709	449.288	.29	.95	.95	372	35	34	3	215	34
	06	0715	452.4	.29	.95	.95	377	38	34	3	215	34
	09	0718	453.9	.28	.93	.93	376	43	34	3	210	32
	12	0721	455.4	.29	.95	.95	375	47	35	3	210	31
	15	0724	456.9	.28	.93	.93	375	50	35	3	215	30
	18	0727	458.4	.27	.89	.89	374	52	36	3	215	31
	21	0730	459.8	.26	.84	.84	373	53	36	3	215	31
	24	0733	461.2	.21	.83	.83	372	54	37	3	220	31
	27	0736	462.2	.14	.46	.46	365	54	38	2	225	31
	30	0739	463.114	.10	.34	.34	363	56	38	2	225	32
	30	0753	463.114	.089	.55	.55						
C-10	33	0956	464.7	.30	.98	.98	376	41	38	3	230	32
	36	0959	466.2	.29	.95	.95	379	44	39	3	235	33
	39	1002	467.8	.28	.93	.93	379	50	34	3	235	33
	42	1005	469.2	.27	.89	.89	378	54	40	3	235	33
	45	1008	470.7	.27	.89	.89	377	56	40	3	235	33
	48	1011	472.2	.25	.83	.83	379	56	40	3	235	34
	51	1014	473.6	.22	.72	.72	378	57	40	3	240	34
	54	1017	474.8	.19	.62	.62	377	57	41	2	235	34
	57	1020	475.9	.15	.50	.50	357	60	42	2	235	34
	60	1023	476.900	.10	.34	.34	329	58	43	2	235	34

Chq. fort3 + Soot Blow

POINT NUMBER	SAMPLING TIME		123 in CLOCK	W _m , in ³	HEAD W _g , in H ₂ O	DIFFERENTIAL (in H ₂ O)		TEMPERATURE (F) ₃	TEMPERATURE		in Hg	CF	CF
	min	sec				DESIRED	ACTUAL		INLET (F) _m	OUTLET (F) _m			
D-10	60	1052		476.900		1.1	1.1	355	43	42	4	230	37
	63	1055		478.6	.33	1.15	1.15	393	49	43	4	230	36
	66	1058		480.3	.35	.98	.98	378	56	44	4	230	35
	69	1101		481.8	.30	.43	.93	375	60	45	3	235	31
	72	1104		483.4	.28	.93	.93	375	64	46	3	235	31
	75	1107		484.9	.28	.84	.84	377	64	47	3	240	31
	78	1110		486.3	.26	.84	.84	376	67	47	3	240	31
	81	1113		487.8	.26	.69	.69	328	67	48	2	245	32
	84	1116		489.1	.21	.46	.46	356	67	48	2	255	32
	87	1119		490.2	.14	.30	.30	326	66	49	2		
90	1122		491.050	.09									
A-10	90	1131		491.050	Clg. fan	.98	.98	365	51	47	4	235	32
	93	1134		492.6	.30	1.1	1.1	375	58	48	4	240	33
	96	1137		494.3	.33	.98	.98	373	63	48	3	240	32
	99	1140		495.8	.30	.98	.98	372	68	49	3	240	37
	102	1143		497.4	.30	.98	.98	372	71	50	3	240	39
	105	1146		498.9	.30	.98	.98	374	72	51	3	240	41
	108	1149		500.6	.30	.98	.98	373	72	52	3	245	43
	111	1152		502.1	.26	.84	.84	369	72	53	3	245	45
	114	1155		503.4	.22	.72	.72	356	73	53	2	245	45
	117	1158		504.5	.14	.46	.46	337	73	54	2	245	45
120	1201		505.340	.09	.30	.30							
1019 cfm @ 12"													

BCM

FIELD DATA SHEET

PLANT W P Fullansbee
 DATE 12-23-80
 SAMPLING LOCATION Boiley stik.
 SAMPLE TYPE particulate
 RUN NUMBER 3
 OPERATOR DES/DRP
 AMBIENT TEMPERATURE 40
 BAROMETRIC PRESSURE -0.62"
 STATIC PRESSURE (P_s) D-58
 FILTER NUMBER (S) 14
 GEL NUMBER (S) +13

PROBE NUMBER AND TYPE 270
 NOZZLE I.D. AND NO. 10
 ASSUMED MOISTURE % 1
 SAMPLE BOX NUMBER 9
 METER BOX NUMBER 1.99
 METER ΔH₂ 9
 C FACTOR 104
 PROBE HEATER SETTING 104
 HEATER BOX SETTING 56
 REFERENCE ΔP 81
 PILOT C_P AND NO. 9.7

ORSAT:

CO₂ 3.0
 O₂ 16.5
 CO

READ AND RECORD ALL DATA EVERY 3 MINUTES

004 ch 0 17" +55

TRAVERSE POINT NUMBER	SAMPLING TIME min	CLOCK TIME (24 hr CLOCK)	GAS METER READING (V _m), ft ³	VELOCITY HEAD (SP _s), in. H ₂ O	ORIFICE PRESSURE DIFFERENTIAL (ΔH), in. H ₂ O		STACK TEMPERATURE (T _s), °F	DRY GAS METER TEMPERATURE		PUMP VACUUM, in. Hg	SAMPLE BOX TEMPERATURE, °F	IMPIPING TEMPERATURE, °F
					DESIRED	ACTUAL		INLET (T _{m in}), °F	OUTLET (T _{m out}), °F			
A-10	03	1316	505.846	.32	1.1	1.1	361	46	45	4	215	44
9	06	1322	509.1	.33	1.1	1.1	376	49	46	4	220	44
8	09	1325	510.7	.32	1.1	1.1	377	55	46	4	220	45
7	12	1328	512.4	.32	1.1	1.1	376	60	46	4	225	45
6	15	1331	513.9	.30	.98	.98	377	64	46	4	230	48
5	18	1334	515.5	.29	.95	.95	377	67	47	3	230	48
4	21	1337	517.0	.28	.93	.93	377	69	48	3	230	48
3	24	1340	518.4	.23	.76	.76	333	71	49	3	235	49
2	27	1343	519.5	.16	.53	.53	360	72	50	2	235	50
1	30	1346	520.478	.18	.40	.40	361	72	50	2	230	51
	30	1353	520.478	change								
D-10	33	1356	522.1	.32	1.1	1.1	351	55	49	4	235	50
9	36	1359	523.7	.31	1.0	1.0	377	60	51	4	235	50
8	39	1402	525.3	.30	.98	.98	377	64	50	4	240	50
7	42	1405	526.9	.30	.98	.98	378	67	51	4	240	50
6	45	1408	528.4	.29	.95	.95	379	70	51	4	240	51
5	48	1411	529.9	.27	.89	.89	377	72	51	3.5	235	53
4	51	1414	531.4	.25	.83	.83	377	74	52	3.5	235	53
3	54	1417	532.7	.22	.72	.72	376	73	52	3	235	54
2	57	1420	533.8	.15	.50	.50	351	72	52	2	235	51
1	60	1423	534.734	.10	.34	.34	336	72	52	2	230	47

Aug. Perts

[illegible]

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12/22/80

Location Name WHEELING - PITT. STEEL

Server J. BISHOP

Address FOLLANSBEE, W. VA.

Comments

Comments

on Point OLD COKE OVEN AREA

F ROILER STACK

Distance from 50m Height 2m

Direction W

Installation BOILER STACK

on Began 10:20 Ended 13:40

PARTLY CLOUDY SKY (20%)

READINGS START AGAIN AT 1315

W/ 50% CLOUD COVER

VIEW OF STACK OBSTRUCTED BY
STEAM PLUME

Smoke Density

	0	15	30	45		0	15	30	45
10:20	0	0	0	0	30	0	0	0	0
1	0	0	0	0	31	0	0	0	0
2	0	0	0	0	32	0	0	0	0
3	0	0	0	0	13:45 33	0	0	0	0
4	0	0	0	0	34	0	0	0	0
5	0	0	0	0	35	0	0	0	0
6	0	0	0	0	36	0	0	0	0
7	0	0	0	0	37	0	0	0	0
8	0	0	0	0	13:50 38	0	0	0	0
8	0	0	0	0	39	0	0	0	0
10	0	0	0	0	40	0	0	X	X
11	0	0	0	0	41	X	X	0	0
12	0	0	0	0	42	0	0	0	0
13	0	0	0	0	13:55 43	0	X	0	0
14	0	0	0	0	44	0	0	0	0
15	0	0	0	0	45	X	0	0	0
16	0	0	0	0	46	0	0	0	0
17	0	0	0	0	47	0	0	0	0
18	0	0	0	0	13:40 48	0	0	0	0
19	0	0	0	0	49	0	0	0	0
20	0	0	0	0	50	0	0	5	5
21	0	0	0	0	51	5	0	0	0
10:42 22	0	0	0	0	52	0	0	0	0
* 13:15 23	0	0	0	0	13:45 53	0	0	0	0
24	0	0	0	0	54	0	0	0	0
25	0	0	0	0	55	0	0	0	0
26	0	0	0	0	56	0	0	0	0
27	0	0	0	0	57	0	0	0	0
13:40 28	0	0	0	0	13:50 58	0	0	0	0
29	0	0	0	0	59	0	0	0	0

WHITE

Three Rivers Group

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12/22/80

Location Name WHEELING - PITT. STEEL

server J. BISHOP

Address FOLLANSBEE, W. VA.

Comments

Comments

on Point OLD COKE OVEN AREA

OF ROILER STACK

Distance from 150 yds Height 200'

ed 0-5 Direction

Installation ROILER STACK

AL

on Began 1352 Ended 1452

50% CLOUD COVER

X VIEW OBSTRUCTED BY STEAM PLUME

% Smoke Density

	0	15	30	45		0	15	30	45
1352	0	0	0	0	30	0	0	0	0
1	0	0	0	0	31	0	0	0	0
2	0	0	0	0	32	0	0	0	0
1355	3	X	X	0	1425	33	0	0	0
4	0	0	0	0	34	0	0	0	0
5	0	0	0	0	35	0	0	0	0
6	0	0	0	0	36	0	0	0	0
7	0	0	0	0	37	0	0	0	0
1400	8	0	X	X	1430	38	0	0	0
9	0	0	0	0	39	0	0	0	0
10	0	0	0	0	40	0	0	0	0
11	0	0	0	0	41	0	0	0	0
12	0	0	0	0	42	0	0	0	0
1405	13	0	0	0	1435	43	0	0	0
14	0	0	0	0	44	0	0	0	0
15	0	0	0	0	45	0	0	0	0
16	0	0	0	0	46	0	0	0	0
17	0	0	0	0	47	0	0	0	0
1410	18	0	0	0	1440	48	0	0	0
19	0	0	0	0	49	0	0	0	0
20	0	0	0	0	50	0	0	0	0
21	0	0	0	0	51	0	0	0	0
22	0	0	0	0	52	0	0	0	0
1415	23	0	0	0	1445	53	0	0	0
24	0	0	0	0	54	0	0	0	0
25	0	0	0	0	55	0	0	0	0
26	0	0	0	0	56	0	0	0	0
27	0	0	0	0	57	0	0	0	0
1420	28	0	0	0	1450	58	0	0	0
29	0	0	0	0	59	0	0	0	0

Three Rivers Group

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12/22/80

Location Name WHEELING-PITT STEEL

Server J. Bishop

Address FOLLANSBEE, W. VA.

Comments

Comments

Point OLD COKE OVEN AREA
OF BOILER STACK
 Distance from ISO Height 200'
 Direction SW
 Installation BOILER STACK
 Began 1452 Ended 1552

50% PARTLY CLOUDY

WHITE

	0	15	30	45		0	15	30	45
1452	0	0	0	0	30	0	0	0	0
1	0	0	0	0	31	0	0	0	0
2	0	0	0	0	32	0	0	0	0
1455	0	5	5	5	33	0	0	0	0
3	5	5	5	5	34	0	0	0	0
4	5	0	0	0	35	0	0	0	0
5	0	0	0	0	36	0	0	0	0
6	0	0	0	0	37	0	0	0	0
1500	0	0	0	0	38	0	0	0	0
7	0	0	0	0	39	0	0	0	0
8	0	0	0	0	40	0	0	0	0
9	0	0	0	0	41	0	0	0	0
10	0	0	0	0	42	0	0	0	0
11	0	0	0	0	43	0	0	0	0
12	0	0	0	0	44	0	0	0	0
1505	0	0	0	0	45	0	0	0	0
13	0	0	0	0	46	0	0	0	0
14	0	0	0	0	47	0	0	0	0
15	0	0	0	0	48	0	0	0	0
16	0	0	0	0	49	0	0	0	0
17	0	0	0	0	50	0	0	0	0
1510	0	0	0	0	51	0	0	0	0
18	0	0	0	0	52	0	0	0	0
19	0	0	0	0	53	0	0	0	0
20	0	0	0	0	54	0	0	0	0
21	0	0	0	0	55	0	0	0	0
22	0	0	0	0	56	0	0	0	0
1515	0	0	0	0	57	0	0	0	0
23	0	0	0	0	58	0	0	0	0
24	0	0	0	0	59	0	0	0	0
25	0	0	0	0					
26	0	0	0	0					
27	0	0	0	0					
1520	0	0	0	0					
28	0	0	0	0					
29	0	0	0	0					

Three Rivers Group

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12/23/80

Location Name WHEELING - PITT STEEL

Observer J. Bishop

Address FOLLANSBEE, W. VA.

Comments

Comments

ion Point OLD CREEK OVER AREA
H OF BOILER STACK
stance from 150 yds Height 100'
ed 0-5 Direction SW
Installation BOILER STACK

AL
ion Began 9/10 Ended 10/10

OVERCAST SKY

WHITE

LIGHT BROWN

) Smoke Density

LIGHT BROWN

	0	15	30	45		0	15	30	45
910	0	0	0	0	940	0	5	5	5
0	0	0	0	0	30	0	0	0	0
1	0	0	0	0	31	0	0	0	0
2	0	0	0	0	32	0	0	0	0
3	0	0	0	0	33	0	0	0	0
4	0	0	0	0	34	0	0	0	0
915	0	0	0	0	945	0	5	5	5
5	0	0	0	0	35	0	5	5	5
6	0	0	0	0	36	5	5	0	0
7	0	0	0	0	37	0	0	0	0
8	0	0	0	0	38	0	0	0	0
9	0	0	0	0	39	0	0	0	0
920	0	0	0	0	950	5	5	5	5
10	0	0	0	0	40	5	5	5	5
11	0	0	0	0	41	5	0	0	0
12	0	0	0	5	42	0	0	0	0
13	5	5	5	5	43	0	0	0	0
14	5	0	0	0	44	0	0	0	0
925	0	0	0	0	955	0	0	0	0
15	0	0	0	0	45	0	0	0	0
16	0	0	0	0	46	0	0	0	0
17	0	0	0	0	47	0	0	0	0
18	5	5	5	5	48	0	0	0	0
19	5	5	5	5	49	0	0	0	0
930	5	5	5	5	1000	0	0	0	0
20	5	5	5	5	50	0	0	0	0
21	5	5	5	5	51	5	5	5	5
22	5	5	5	5	52	5	5	5	5
23	5	5	0	0	53	0	0	5	5
24	0	0	0	0	54	5	5	5	5
935	0	0	0	0	1005	5	5	5	5
25	0	0	0	0	55	5	5	5	5
26	0	0	0	5	56	5	5	5	5
27	5	5	5	5	57	5	5	5	5
28	5	5	5	0	58	5	5	5	5
29	0	0	0	0	59	5	5	5	5

LIGHT BROWN

WHITE

Three Rivers Group

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12/23/80

Location Name WHEELING-PITT STEEL

Server J. Bishop

Address FOLLANSBEE, W. VA.

Comments

Comments

Point OLD COKE OVEN AREA
 F BOILER STACK
 ance from 500 Height 100'
 O-S Direction SW
 stallation BOILER STACK

Began 10/11 Ended 11/10

Partly cloudy (50%)

INTERFERENCE FROM STEAM PLUME

Smoke Density

	0	15	30	45		0	15	30	45		
WHITE	¹⁰¹⁰ 0	5	5	5	5	¹⁰¹⁰ 30	5	5	5	5	WHITE
	1	5	5	5	5	31	5	5	5	5	
	2	5	5	5	5	32	5	5	5	5	
	3	5	5	5	5	33	X	X	X	5	
	4	5	5	5	5	34	5	5	X	X	
	¹⁰¹⁵ 5	5	5	5	5	¹⁰¹⁵ 35	5	5	X	5	
	6	5	5	5	5	36	5	5	5	5	
	7	5	5	5	5	37	5	5	5	5	
	8	5	5	5	5	38	5	5	5	5	
	9	5	5	5	5	39	5	5	5	5	
	¹⁰²⁰ 10	5	5	5	5	¹⁰²⁰ 40	5	5	5	5	
	11	5	5	5	5	41	5	5	5	5	
	12	5	5	5	5	42	5	5	5	5	
	13	5	5	5	5	43	5	5	5	X	
	14	5	5	5	5	44	X	5	5	5	
	¹⁰²⁵ 15	5	5	5	5	¹⁰²⁵ 45	5	5	5	5	
	16	5	5	5	5	46	5	5	5	5	
	17	5	5	5	5	47	5	X	X	X	
	18	5	5	5	5	48	X	5	X	X	
	19	5	5	5	5	49	X	5	5	5	
	¹⁰³⁰ 20	5	5	5	5	¹⁰³⁰ 50	5	5	5	5	
	21	5	5	5	5	51	5	X	X	X	ByPASS
	22	5	5	5	5	52	X	5	5	5	BLACK END
	23	5	5	5	5	53	5	5	5	5	
	24	5	5	5	5	54	5	5	5	X	WHITE
	¹⁰³⁵ 25	5	5	5	5	¹⁰³⁵ 55	5	5	5	5	
	26	5	5	5	5	56	5	5	5	5	
	27	5	5	5	5	57	5	5	5	5	
	28	5	5	5	5	58	5	5	5	5	
	29	5	5	5	5	59	5	5	5	5	

Three Rivers Group

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12/23/80

Location Name WHEELING - PITT STEEL

server J. Bishop

Address FOLLANSBEE, W. VA

Comments

Comments

on Point OLD COKE OVER AREA
 AF BOILER STACK
 tance from 150 ft Height 20'
 d 0-10 Direction SW
 nstallation BOILER STACK

on Began 1110 Ended 1110

CLEAR SKY

INTERFERENCE FROM STEAM PLUME

) Smoke Density

	0	15	30	45		0	15	30	45
1110 0	5	5	5	5	1140 30	X	X	0	X
1	5	5	5	5	31	0	5	5	5
2	5	5	5	5	32	5	5	5	5
3	5	5	5	5	33	X	X	X	5
4	5	5	5	5	34	5	5	5	5
1115 5	5	5	5	5	1145 35	5	5	0	0
6	5	5	5	5	36	0	0	5	5
7	5	5	5	5	37	5	5	5	5
8	5	5	5	5	38	5	5	0	0
9	5	5	5	5	39	0	0	0	0
1120 10	5	5	5	5	1150 40	0	0	0	5
11	5	5	5	5	41	5	X	5	5
12	5	5	5	5	42	5	5	X	0
13	5	5	5	5	43	0	0	0	5
14	5	5	5	5	44	5	5	5	0
1125 15	5	5	5	5	1155 45	0	0	0	0
16	5	5	5	5	46	0	X	X	X
17	0	0	0	5	47	0	0	5	5
18	5	5	5	5	48	5	5	5	5
19	5	5	5	5	49	5	0	0	0
1130 20	5	5	X	5	1200 50	0	0	0	0
21	5	5	5	5	51	0	0	0	5
22	5	5	5	5	52	5	5	5	5
23	5	5	5	5	53	5	5	5	5
24	5	5	5	5	54				
1135 25	5	5	5	5	1205 55				
26	X	X	X	X	56				
27	X	X	5	5	57				
28	X	0	0	0	58				
29	X	5	X	X	59				

Three Rivers Group

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12/23/90

Location Name WHEELING-PITT STEEL

Server J. BISHOP

Address FOLLANSBEE, W. VA

Comments

Comments

on Point OLD COKE OVEN
 SOUTH OF BOILER STACK
 Distance from 150 yd Height 200'
 ID-10 Direction SW
 Installation BOILER STACK

on Began 1320 Ended 1420

GREY OVERCAST

INTERFERENCE FROM STEAM PLUME

) Smoke Density

	0	15	30	45		0	15	30	45	
120	0	0	0	0	150	5	5	5	5	Brown
1	0	0	0	0	31	5	5	5	5	HH
2	0	0	0	0	32	5	5	5	5	
3	0	0	0	0	33	5	5	5	5	
4	5	5	5	5	34	5	5	5	5	
125	5	5	5	5	155	5	5	5	5	
5	5	5	5	5	35	5	5	5	5	
6	5	5	5	5	36	5	5	X	X	
7	5	5	5	5	37	X	X	5	5	
8	5	5	5	5	38	5	X	X	5	
9	5	5	5	5	39	5	5	5	5	
130	0	0	0	0	200	5	5	5	5	
10	0	0	0	0	40	5	5	X	X	
11	0	0	0	0	41	5	5	5	5	
12	0	0	0	0	42	5	5	5	5	
13	0	0	0	0	43	5	5	5	5	
14	0	0	0	0	44	5	5	5	5	
135	0	0	0	0	205	5	5	5	5	
15	0	0	0	0	45	5	5	5	5	
16	0	0	0	5	46	5	5	5	5	
Brown	17	5	5	5	5	47	5	5	5	5
18	5	5	5	X	48	5	5	5	5	
19	X	5	5	5	49	5	5	5	5	
140	5	5	5	5	210	5	5	5	5	
20	5	5	5	5	50	5	5	5	5	
21	5	5	5	5	51	X	X	5	5	
22	5	5	5	5	52	5	5	5	5	
23	5	5	5	5	53	5	5	5	5	
24	5	5	5	5	54	5	5	5	5	
145	5	5	5	5	215	5	5	5	5	
25	5	5	5	5	55	5	5	5	5	
26	5	5	5	5	56	5	X	X	X	
27	5	5	5	5	57	5	5	5	5	
28	5	5	5	5	58	5	5	5	5	
29	5	5	5	5	59	X	5	X	X	

Three Rivers Group

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12/23/80

Location Name WHEELING-PITT STEEL

Server J. Bishop

Address FOLLENSBEE, W. VA

Comments

Comments

on Point OLD COKE AVEN
 SOUTH OF RAILER STACK
 Distance from 150yd Height 100'
 Direction SW
 Installation BOILER STACK

on Began 1420 Ended 1520

GREY OVERCAST

INTERFERENCE FROM STEAM PLUME

Smoke Density

	0	15	30	45		0	15	30	45	
1420	X	5	5	X	250	5	5	5	5	WHITE
1	5	5	5	5	31	5	5	5	5	
2	5	5	5	5	32	5	5	5	5	
3	5	5	5	5	33	5	5	5	5	
4	5	5	5	5	34	5	5	5	5	
225	5	5	5	5	35	5	5	5	5	
6	X	5	5	5	36	5	5	5	5	
7	5	5	X	5	37	5	5	5	5	
8	5	5	5	5	38	5	5	X	X	
9	5	5	X	X	39	5	5	5	5	
230	5	5	5	5	40	5	5	5	5	
11	X	5	X	5	41	5	5	5	5	
12	5	5	5	5	42	5	5	5	5	
13	5	5	5	5	43	5	5	5	5	
14	5	5	5	5	44	5	5	5	5	
235	5	X	X	X	45	5	5	X	X	
16	5	5	5	5	46	X	5	5	5	
17	5	5	5	5	47	5	5	5	5	
18	5	5	5	5	48	5	5	5	5	
19	5	5	5	5	49	5	X	X	X	
240	5	5	5	5	50	5	X	5	X	
21	5	5	5	5	51	X	5	5	5	
22	5	5	5	5	52	5	5	5	5	
23	5	5	5	5	53	X	5	5	X	
24	5	5	5	5	54	5	5	5	5	
245	5	5	5	5	55	5	X	X	X	
26	5	5	5	5	56	X	5	X	X	
27	5	5	5	5	57	X	X	X	X	
28	5	5	5	5	58	X	5	5	5	
29	5	5	5	5	59	5	5	5	5	

Three Rivers Group

Betz • Converse • Murdoch • Inc.

BCM

Consulting Engineers, Planners and Architects

Date 12-23-80

Location Name WHEELING-PITT STEEL

Observer J. Bishop

Address FOLLENSBEE, W. Va.

Comments

Comments

ion Point OLD COKE OVEN AREA

H OF BOILER STACK

Distance from 150 YD Height 200'

eed 0-10 Direction SW

Installation BOILER STACK

SAL

tion Began 520 Ended

GREY OVERCAST

X INTERFERENCE FROM STEAM PLUME

g) Smoke Density

WHITE

	0	15	30	45		0	15	30	45
320 0	5	X	X	5	30				
1	X	5	X	5	31				
2	5	5	5	5	32				
3	5	5	5	5	33				
4	X	X	5	5	34				
325 5	X	5	5	5	35				
6	5	X	X	X	36				
7	5	5	5	5	37				
8	5	X	X	5	38				
9	5	X	X	X	39				
330 10	X	X	5	5	40				
11	5	5	X	X	41				
12	5	5	5	5	42				
13	5	5	5	5	43				
14	X	X	X	5	44				
335 15	5	5	5	5	45				
16	5	5	X	X	46				
17	X	X	X	X	47				
18	X	X	X	X	48				
19	X	X	X	X	49				
340 20	X	X	X	X	50				
21					51				
22					52				
23					53				
24					54				
25					55				
26					56				
27					57				
28					58				
29					59				

Three Rivers Group

PITOT CALIBRATION

Pitot No. 9-7

Date 12/10/20

Engineer DRP. JFA

Range	Run No.	ΔP_{std}	A SIDE			B SIDE			DIF.
			ΔP	C_p	DEV.	ΔP	C_p	DEV.	
1	1	.025	.03			.03			
	2	.025	.03			.03			
	3	.025	.03			.03			
AVG.			.904			.904			.000

2	1	.17	.26	.801		.26	.801		
	2	.17	.25	.816		.26	.801		
	3	.17	.26	.801		.25	.816		
AVG.			.806			.806			.000

3	1	.42	.63	.808		.64	.802		
	2	.42	.63	.808		.63	.808		
	3	.43	.64	.811		.64	.811		
AVG.			.809			.807			.002

4	1	.59	.85	.825		.86	.820		
	2	.59	.85	.825		.85	.825		
	3	.59	.85	.825		.85	.825		
AVG.			.825			.823			.002

5	1	.83	1.30	.791		1.30	.791		
	2	.83	1.30	.791		1.30	.791		
	3	.83	1.31	.789		1.30	.791		
AVG.			.789			.791			.790

6	1	1.20	1.65	.844		1.65	.844		
	2	1.20	1.65	.844		1.66	.842		
	3	1.20	1.65	.844		1.65	.844		
AVG.			.844			.843			.001

7	1	1.30	1.90	.819		1.88	.823		
	2	1.30	1.91	.817		1.90	.819		
	3	1.30	1.91	.817		1.90	.819		
AVG.			.818			.820			.002

$$C_p = 0.99 \sqrt{\frac{\Delta P_{std}}{\Delta P \cdot S}}$$

$$DEV. = C_p - \bar{C}_p$$

$$DEV. \leq 0.01$$

$$DIF. = \bar{C}_{p(A)} - \bar{C}_{p(B)}$$

$$DIF. \leq 0.01$$

Date 10/25/80 Box No: 9 Inspector DES/DR/2
 Pump OK Oil OK Wick OK Pump Serial No. 1
 Manometers OK Knobs OK Oil OK Tubing OK
 Quick Connects OK Vacuum Gage OK Valves OK
 Dry Gas Motor ✓ Volume 865 Serial No.
 Thermometers ✓ In 58 of Out 58 of Ambient 58
 Amplionol OK Lights OK Switches OK Variac OK
 Leak Check - Max. Vacuum 23 In. Hg Leak Rate .000 CI
 Remarks

Pb 29.70 Tolerances:
 $Y = 0.99 - 1.00 - 1.$
 $\Delta H = 1.6 - 1.84 - 2.$

Man Orifice	CF _w	CF _d	T _w	IT _d	OT _d	Td Avg.	Time
0.5	4.978	5.088	58.6	67	59	63	13.50
1.0	4.997 5	5.190 4.997	58.6	83	64	73.5	9.50
2.0	10.002 10	10.556	58.6	97	72	84.5	14.13
4.0	10						
6.0	10						
8.0	10						

Man. Orifice	CF _w	Man. $\Delta H @$	CF _w P _b (T _d avg. + 460)	Man.	Y
0.0317 (Man. orifice) (T _w + 460) ^t					
P _b (OT _d + 460)			Man. orifice CF _d (P _b + 13.6 (T _w + 460)		
0.01505	(<u> </u> + 460) ²	.5 2.019	<u> </u> X <u> </u> (<u> </u> + 460)	.5	.989
	(<u> </u> + 460)		<u> </u> (<u> </u> + 0.0368) (<u> </u> + 460)		
0.0317	(<u> </u> + 460) ²	1.0 1.980	<u> </u> X <u> </u> (<u> </u> + 460)	1.0	.990
	(<u> </u> + 460)		<u> </u> (<u> </u> + 0.0737) (<u> </u> + 460)		
0.0631	(<u> </u> + 460) ²	2.0 2.156	<u> </u> X <u> </u> (<u> </u> + 460)	2.0	.990
	(<u> </u> + 460)		<u> </u> (<u> </u> + 0.147) (<u> </u> + 460)		

LABORATORY ANALYSIS AND CALCULATIONS

APPENDIX C

1.0 ANALYTICAL METHOD

The following is a discussion of the methods employed by the BCM Laboratory in analyzing all samples generated during the testing program.

1.1 Moisture Content

The total volume of the impinger solution minus the original volume of reagents in the impingers plus the volume of moisture and/or vapors collected by the silica gel equalled the total moisture gain of the sampling train. This volume was used as the basis for percent moisture by volume calculations. The laboratory results of the moisture analyses appear concurrently with the results of the particulate testing program.

1.2 Particulate Samples

All glass fiber filters used in the particulate sampling program had been tare-weighted following a 24 hour desiccation period prior to their use in the field. Upon their return to the laboratory, they were again desiccated for 24 hours and reweighed to a constant weight. The weight difference was the amount of sample collected on the filter.

Nozzle, probe, and front half filter holder acetone washings were evaporated to dryness in a tared beaker. Any residue was the amount of particulate matter collected at these locations in the sampling train.

Acetone blanks were evaporated to dryness in tared beakers. Any residue which remained was a contaminant in the reagents and was considered as a blank weight in subsequent calculations. Laboratory results of the particulate sampling program are listed on page C-8 of this Appendix.

2.0 COMPUTER INPUT SHEET

The reduced data calculated from the field data sheets were combined with the laboratory results on the following Computer Input Data Sheet to facilitate programming. See page C-9 of the Appendix.

3.0 CALCULATIONS

The following series of equations were utilized to facilitate the calculations leading to the results of the test program.

3.1 Particulate/Moisture

EQUATIONS FOR PARTICULATE/MOISTURE CALCULATIONS

1. No system leakage

$$V_m(\text{std}) = 17.647 (V_m)(Y)(P_{\text{bar}} + (\Delta H/13.6))/T_m$$

- 1a. Leakage with no component change, substitute for V_m in 1.

$$V_{m1} = V_m - ((L_p - L_a) \theta)$$

- 1b. Leakage with component change(s), substitute for V_m in 1.

$$V_{m2} = V_m - ((L_1 - L_a) \theta_1) - \sum_{i=2}^n ((L_i - L_a) \theta_i) - ((L_p - L_a) \theta_p)$$

2. $V_w(\text{std}) = 0.04707 (V_{1c})$

3. $B_{ws} = (V_w(\text{std})) / (V_m(\text{std}) + V_w(\text{std}))$

4. $C_a = (M_a) / ((V_a)(P_a))$

5. $W_a = (C_a) (V_{aw}) (P_a)$

6. $C_{sd} = 0.01543 (M_n) / (V_m(\text{std}))$

7. $C_{sw} = 0.01543 (M_n) / (V_m(\text{std}) + (V_w(\text{std})))$

8. $C_{sc} = 12 (C_{sd}) / (\%CO_2)$

9. $C_{ss} = (C_{sw})(528)(P_s) / ((T_s) (29.92))$

10. $\%EA = 100 (\%O_2 - 0.5(\%CO) / (0.264(\%N_2) - (\%O_2 - 0.5(\%CO))))$

11. $M_d = 0.44 (\%CO_2) + 0.32 (\%O_2) + 0.28 (\%CO + \%N_2)$

12. $M_s = M_d (1-B_{ws}) + 18 (B_{ws})$
13. $V_s = 85.49 (C_p) ((P)^{0.5})_{avg} ((T_s) / P_s M_s)^{0.5}$
14. $Q_{sa} = 60 (v_s) (A_s)$
15. $Q_{sd} = 1058.82 (1-B_{ws}) (v_s) (A_s) (P_s) / (T_s)$
16. $E_s = (Q_{sd}) (C_{sd}) (60) / (7000)$
17. $I = (0.0945 (T_s) (v_{m(std)})) / ((P_s)(v_s)(A_n)(0)(1-B_{ws}))$

LEGEND

A_s	= Cross-sectional area of stack	ft ²
A_n	= Cross-sectional area of nozzle	ft ²
B_{ws}	= Water vapor in gas stream, proportion by volume	%
C_a	= Acetone blank residue concentrations	mg/g
C_p	= Pitot tube coefficient, dimensionless	
C_{sd}	= Particulate concentration, dry basis	gr/DSCF
C_{sc}	= Particulate concentration, corrected to 12% CO ₂	gr/DSCF
C_{ss}	= Particulate concentration, stack conditions	gr/ACF
C_{sw}	= Particulate concentration, wet basis	gr/WSCF
E_s	= Particulate emission rate	lb./hr.
I	= Percent of isokinetic sampling	
L_1	= Individual leakage rate, from beginning of run until first component change	cfm
L_a	= Maximum acceptable leakage rate, 0.02 cfm or 4% average sampling rate, whichever is less	cfm
L_i	= Individual leakage rate, between two successive component changes, beginning with second component change	cfm

L_p	=	Post test leakage rate	cfm
M_a	=	Mass of acetone residue after evaporation	mg
M_d	=	Dry molecular weight of stack gas	lb/lb-mole
M_n	=	Total collected particulate matter	mg
M_s	=	Wet molecular weight of stack gas	lb./lb-mole
P_{bar}	=	Barometric pressure at sampling site	in Hg
P_s	=	Absolute stack gas pressure	in Hg
P_{std}	=	Standard atmospheric pressure	29.92 in Hg
ρ_a	=	Density of acetone	mg/ml
Q_{sa}	=	Stack gas volumetric flow, stack conditions	ACFM
Q_{sd}	=	Stack gas volumetric flow, dry basis, standard	SCFM
T_m	=	Absolute average dry gas meter temperature	$^{\circ}R$
T_s	=	Absolute average stack gas temperature	$^{\circ}R$
T_{std}	=	Absolute standard temperature	528 $^{\circ}R$
V_a	=	Volume of acetone blank	ml
V_{aw}	=	Volume of acetone used in wash	ml
V_{lc}	=	Total volume of liquid collected in impingers and silica gel	ml

V_m	=	Net test gas volume at gas meter	ft ³
$V_{m(std)}$	=	Net test gas volume at standard conditions	DSCF
V_s	=	Stack gas velocity	fps
$V_{w(std)}$	=	Volume of water vapor in gas sample, std. conditions	SCF
W_a	=	Weight of residue in acetone wash	mg
Y	=	Dry gas meter calibration factor	
%EA	=	Percent excess air	%
%CO	=	Percent carbon monoxide by volume, dry basis	%
%CO ₂	=	Percent carbon dioxide by volume, dry basis	%
%N ₂	=	Percent nitrogen by volume, dry basis	%
%O ₂	=	Percent oxygen by volume, dry basis	%
ΔH	=	Average orifice pressure differential	in H ₂ O
ΔP	=	Velocity head of stack gas	in H ₂ O
θ	=	Total sampling time	min.
θ_1	=	Sampling time interval, from beginning of run until first component change	min.
θ_i	=	Sampling time interval, between two successive component changes, beginning with interval between first and second changes	min.
θ_p	=	Sampling time interval, between last component change and end of test	min.

3.2 Equations for Sampling Equipment Calibration

Pitot Calibration

The pitot tubes were calibrated by measuring the velocity head in a duct with both a Type "S" pitot tube and a standard type pitot tube with a known coefficient. This was done at several different velocities. The pitot tube coefficient can be calculated:

$$C_{p \text{ test}} = (C_{p \text{ std}}) ((P_{\text{std}})/(P_{\text{test}}))^{0.5} \quad \text{eq. 1}$$

Where:

- $C_{p \text{ test}}$ = Pitot tube coefficient of Type "S" pitot tube
- $C_{p \text{ std}}$ = Pitot tube coefficient of standard type pitot tube
- P_{std} = Velocity head measured by standard type pitot tube
- P_{test} = Velocity head measured by type "S" pitot tube.

Dry Gas Meter and Orifice Meter

The dry gas meter and orifice were calibrated using a wet test meter. Gases were moved through the dry gas meter at ΔH 's of 0.5, 1.0 and 2.0 inches of water. With the information obtained, v , the ratio of the accuracy of the wet test meter to the dry test meter, and $\Delta H @$, the orifice differential that gives 0.75 cfm of air at 20°C and 29.92 inches of mercury, were calculated. The v has a tolerance of plus or minus 0.01 and the $\Delta H @$ has a tolerance of plus or minus 0.15.

$$v = ((V_w)(P_b)(t_d+460))/((V_d)(P_b+H/13.6)(t_w+460))$$

Where:

- P_b = Barometric Pressure
- V_w = Volume wet test meter
- t_d = Average temperature of dry gas meter in °F
- V_d = Volume dry gas meter
- t_w = Temperature wet test meter in °F
- $\Delta H @$ = $((t_w+460)(\theta)/(V_w)) ((0.0317)(\Delta H))/((P_b)(t_d+460))$

Where:

- θ = Time in minutes
- ΔH = Manometer orifice pressure drop

Potentiometer Calibration

The Thermo Electric Potentiometers were calibrated using a known voltage source.

Table C-1
Laboratory Results*

	<u>Run 1</u>	<u>Run 2</u>	<u>Run 3</u>
Filter Number	D-53	D-58	D-49
Filter Final Weight	.3039	.3261	.3258
Filter Tare Weight	.2112	.2166	.2150
Front Half Acetone Wash	.0345	.0480	.0267
Impinger Gain	15	57	55
Silica Gel Number	9	12	14
Silica Gel Final Weight	212.4	212.0	213.0
Silica Gel Tare Weight	200.0	200.0	200.0
Total Front Half Particulate	.1272	.1575	.1375
Total Moisture	27.4	69.0	68.0

* All results are corrected for blanks and weights in grams

3

Number of Tests

Test Identification

Stack Area, IN²

Stack Temperature, °F

Sample Volume, Dry, CF

Avg. Meter Temperature, °F

Avg. Orifice (ΔH) IN H₂O

Nozzle, Dia. IN

Duration of Test, Min.

CO₁

CO

O₂N₂

Stack Pressure, IN Hg

Barometric Pressure, IN Hg

Pitot Correction Factor

Pitot Traverse (Avg, $\sqrt{\Delta P}$) IN H₂OVolume, H₂O Collected, mlM₁, SO₂M₁, SO₂

Total Collected Weight, mg

Normality of SO₂Normality of SO₂

Motor Calibration Factor

CLIENT: WP Follansbee
 LOCATION: Coke Works Boiler
 JOB NO.: 00-5167-02
 NAME OF FILE: WP FOLL3, UNN

AIRPOL 1 INPUT DATA SHEET

PARAMETERS

	1	2	3
A OF BREACHING (SQ IN)	9161.00	9161.00	9161.00
PLE VOLUME(DRY) (STD CU FT)	60.18	58.21	57.69
STUKE (%)	2.0994	5.2877	5.2601
ECULAR WEIGHT	28.96	28.57	28.55
TEMPERATURE (F)	353	369	358
VELOCITY (FPM)	1993	1986	1483
VOLUME (SCFM)(DRY)	83477	77033	77874
VOLUME (ACFM)	126807	126556	126126
TICULATE CONC :			
GRAINS/STD CU.	.0325	.0417	.0367
GRAINS/STD CU.	.0319	.0395	.0348
GRAINS/STD CU.	.1116	.1667	.1468
GRAINS/STD CU.	.0214	.0254	.0227
POUNDS/HOUR	23.2860	27.5072	24.4978
AT ANALYSIS :			
CARBON DIOXIDE (VOL %)	3.50	3.00	3.00
CARBON MONOXIDE (VOL %)	.00	.00	.00
OXYGEN (VOL %)	16.00	17.00	16.50
NITROGEN (VOL %)	80.50	80.00	80.50
ESS AIR (%)	304.65	412.62	347.22
KINETIC (%)	96.18	100.82	98.83

PROCESS DATA

APPENDIX D

TEST	# 5	# 6	# 7			12/22/80	
CR. CAP.	15,000	55,000	55,000			START TEST @ 1:13 P.M.	
	14,000	50,000	50,000			@ 1:15 P.M.	
	19,000	49,000	49,000			@ 2:15 P.M.	
	2,500	49,000	49,000			@ 3:15	
	14,000	50,000	50,000			@ 4:15	
TEST	# 5	# 6	# 7			START TEST @ 9:10 A.M.	
CR. CAP.	15,000	55,000	55,000			@ 9:15	
	14,000	49,000	49,000			@ 10:15	
"	14,000	49,500	50,000			@ 11:15	
"	2,000	49,900	50,000			@ 12:15	
TEST	# 5	# 6	# 7			START TEST @ 1:22 P.M.	
CR. CAP.	15,000	55,000	55,000			@ 1:25	
"	14,000	51,000	52,000			@ 2:25	
"	14,500	52,000	52,000			@ 3:25	
"	14,000	50,000	52,000			@ 3:55	
"	14,000	49,000	50,000				

11-11-11