



Oil Country Tubular Goods
Line Pipe- Piling

10.1

September 29, 2000

Department for Environmental Protection
Division for Air Quality
803 Schenkel Lane
Frankfort, KY 40601-1403
Attn: Mr. Gerald Slucher

Re: Stack Test Results for EAF Exhaust/Brandt Baghouse
Air Quality Permit (F-98-014)

Dear Mr. Slucher,

Enclosed please find a copy of the, "Air Emissions Test Report – Brandt Baghouse, Newport Steel Corporation, Newport, Kentucky."

The first three particulate test runs constitute a complete test as required by Newport Steel's Air Quality Permit (F-98-014) for Brandt Baghouse particulate emissions and described in the NSPS for Electric Arc Furnaces (40 CFR 60.275a). The fourth test run was optional and was terminated when operating problems occurred in the EAF. We believe that the particulate test results are representative of normal baghouse emissions. The NOx and CO data, however, are not representative because manual oxygen lancing was being performed during much of the test which resulted in lower than normal production and higher than normal NOx and CO emission factors on a pound of pollutant per ton of steel produced basis. A follow-up test for Nox, CO, and SO2 emissions is scheduled for next week, October 2 for setup and October 3 and 4 for testing.

If you have any further questions, please feel free to contact me at 859/292-7236.

Sincerely,
Newport Steel Corporation

A handwritten signature in cursive script, reading 'Jennifer A. McDaniel'.

Jennifer A. McDaniel
Manager, Environmental and
Safety Compliance

Cc: Thom Golatzki

**AIR EMISSIONS TEST REPORT
BRANDT BAGHOUSE
NEWPORT STEEL CORPORATION
NEWPORT, KENTUCKY**

Prepared for:

Newport Steel Corporation
P.O. Box 1670
Ninth & Lowell Streets
Newport, Kentucky 41072

PN 050101.0011

Prepared by:

Environmental Quality Management, Inc.
1310 Kemper Meadow Drive
Cincinnati, Ohio 45240

September 2000

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Figures	iii
Tables	iv
Introduction	1-1
2 Summary of Test Results	2-1
Sampling Procedures	3-1
3.1 Measurement Sites	3-1
3.2 Velocity and Volumetric Flow Rate	3-1
3.3 Dry Molecular Weight	3-2
3.4 Moisture	3-2
3.5 Particulate Matter	3-2
3.6 Visible Emission Observations	3-4
3.7 SO ₂ Emissions	3-4
3.8 Nitrogen Oxides	3-4
3.9 Lead Emissions	3-4
3.10 CO Emissions	3-5
3.11 EAF Baghouse Operation Data	3-5
4 Process Description and Baghouse Operating Data	4-1
5 Quality Assurance and Quality Control	5-1
5.1 Calibration Procedures and Frequency	5-1
 <u>Appendix</u>	
A VE Emission Field Data	
B Production/Process Field Data	
C Production Heat Sheets	
D Emission Testing Field Data	
E Stack Test Calculations	
F Calibration Data	

FIGURES

<u>Number</u>		<u>Page</u>
3-1	Instrumental Analyzer Sampling System	3-3
4-1	Process Flow Diagram	4-2

TABLES

<u>Number</u>		<u>Page</u>
1-1	Sampling Requirements	1-1
2-1	Summary of Stack Gas Conditions for EAF Exhaust/Brandt Baghouse Inlet	2-1
2-2a	Summary of EAF NOX and CO Emissions	2-2
2-2b	Summary of PM/Sulfur Dioxide/Lead Emissions	2-2
2-3	Emission Factors Based on Brandt Baghouse Stack Test	2-3
2-4a	Relative Accuracy Test Audit - CO Monitor	2-4
2-4b	Relative Accuracy Test Audit - NOX Monitor	2-4
2-5	VE Readings and Rolling 6-minute VE Averages	2-5
2-6	VE Readings and Rolling 6-minute VE Averages	2-21
4-1	Baghouse Pressure Drop, Control System Fam Amps, and Damper Positions During Performance Testing	4-4
5-1	Field Equipment Calibration Summary	5-2
5-2	Field Checks on Sampling Equipment	5-2

SECTION 1

INTRODUCTION

On August 15 and 16, 2000 Environmental Quality Management, Inc. (EQ) and FBT Testing & Environmental Services (FBT) personnel conducted a compliance air emission program at Newport Steel Corporation. The air sampling program was performed on the Brandt Positive Pressure Baghouse servicing the electric arc furnace (EAF) and the EAF building. Sampling was performed in accordance with the requirements of operating Permit Number F-98-014 using EPA Reference Methods.. Table 1-1 presents the sampling conducted at the baghouse exhaust or the baghouse inlet.

TABLE 1-1. SAMPLING REQUIREMENTS

Test Point No.	Test Point Name	Parameter Tested	Test Method
1	Brandt Baghouse Inlet	Flow ¹ O ₂ /CO ₂ Moisture SO ₂ NO _x CO	EPA Method 1 for Velocity EPA Method 2 for Temperature EPA Method 3 EPA Method 4 EPA Method 6 EPA Method 7E EPA Method 10
2	Brandt Baghouse Outlet	PM Lead Visible Emissions	EPA Method 5D EPA Method 12 EPA Method 9

¹ Velocity profiles were conducted at the inlet before and after each outlet Method 5D sample. Inlet velocity data was be used to calculate the outlet sample rate.

Mr. Thom Golatzki of the NS Group, Ms. Jennifer McDaniel of Newport Steel, and Mr. Fred Hall of EQ monitored process operations for the purpose of testing. Mr. Tom Gerstle of EQ coordinated testing and process operations. Mr. John Jayne and Mr. John Allan of the Kentucky

Department of Environmental Protection observed process operations and sampling efforts.
Messrs. David Wetmore and Pete Hilty of FBT conducted sampling efforts.

SECTION 2

SUMMARY OF TEST RESULTS

Sampling of the Brandt baghouse was conducted on August 15 and 16, 2000. Three test runs, four to five hours in length, were conducted for velocity, moisture, O₂, and CO₂, particulate matter, SO₂, NO_x, CO, and lead. A fourth test run, for these same pollutants was aborted after 1 hour and 20 minutes due to EAF operating problems. Visible emission observations were also conducted at the baghouse and melt shop exhausts. Sampling was conducted following EPA Reference Methods 1-4, 5D, 6, 7E, 9, 10, and 12 (Table 1-1).

Table 2-1 summarizes the stack gas conditions measured for the three full sample periods at the inlet. Stack gas velocities averaged 67.2 feet per second (fps) at 148° F and 2.7 percent moisture. Stack gas composition averaged 0.4 percent CO, and 20.6 percent O₂. Volumetric flow rates averaged 775,735 actual cubic feet per minute (acfm) or 650,596 dry standard cubic feet minute (dscfm). Measurements were consistent for the three test runs.

**TABLE 2-1. SUMMARY OF STACK GAS CONDITIONS FOR
EAF EXHAUST/BRANDT BAGHOUSE INLET**

Run #	Date/Time	Exhaust Velocity (fps) ^a	Flow Rate		Exhaust Temp. ° F	H ₂ O %	O ₂ %	CO ₂ %
			(acfm) ^b	(dscf) ^c				
1	8/15/00	67.6	790,454	675,327	134	3.0	20.6	0.3
2	8/15/00	67.2	785,137	681,273	125	3.0	20.6	0.5
3	8/16/00	66.7	751,613	595,188	184	2.2	20.7	0.5
Average		67.2	775,735	650,596	148	2.7	20.6	0.4

^a Velocity in feet per second

^b Stack gas volumetric flow rate in actual cubic feet per minute

^c Stack gas volumetric flow rate in dry standard cubic feet minute

Tables 2-2a and 2-2b summarize the pollutant concentrations and mass emission rates for Runs 1 to 3. The filterable particulate concentration averaged 0.00084 grains per dry standard cubic foot (gr/dscf), with an average mass emission rate of 5.45 pounds per hour (lb/hr). The NO_x (as NO₂) concentration averaged 8.7 ppm with an average mass emission rate of 35.7 lb/hr. The CO concentration averaged 89 ppm with an average mass emission rate of 251 lb/hr.

TABLE 2-2a. SUMMARY OF EAF NO_x AND CO EMISSIONS

Run #	Date/Time	NO _x as NO ₂		CO	
		ppm ^a	(lb/hr) ^b	ppm ^a	(lb/hr) ^b
1	8/15/00 0814-1214	8.9	27.77	55	161.7
2	8/15/00 1532-1754	8.1	39.40	94	276.1
3	08/16/00 1355 - 1755	9.1	39.81	119	316.2
Average		8.7	35.66	89	251.3

^a Concentration in parts per million

^b Emission rate in pounds per hour

TABLE 2-2b. SUMMARY OF PM/SULFUR DIOXIDE/LEAD EMISSIONS

Run#	Date/Time	PM Concentration		PM Emission Rate (lb/hr) ^c	Sulfur Dioxide		Lead Concentration		Er (lb/hr) ^c
		(gr/dscf) ^a	(lb/dscf) ^b		Cs (ppm) ^d	Er(lb/hr)	(gr/dscf) ^a	(lb/dscf) ^b	
1	8/15/00 0414-1300	4.70E-04	6.91E-08	2.862	0.0	0.0	3.49E-06	4.98382E-10	204E-02
2	8/15/00 1345-1828	1.98E-03	295E-07	12.326	0.0	0.0	4.86E-06	6.95197E-10	290E-02
3	8/16/00 0754-1214	2.01E-04	2.98E-08	1.205	0.0	0.04	2.96E-06	4.22966E-10	1.71E-02
Average		8.84E-4	1.32E-7	5.45	0.0	0.013	3.77E-06	5.38848E-10	2.22E-02

^a Concentration in grains per dry standard cubic foot

^b Concentration in pounds per dry standard cubic foot

^c Emission rate in pounds per hour

^d Concentration in parts per million

Table 2-3 summarizes the melt shop production during the three test runs along with the calculated emission factors for NO_x, CO, SO₂, and lead (Pb). The emission factors for NO_x

ranged from 0.465 to 0.728 lb/ton produced with an average of 0.562 lb/NO_x/ton steel. The calculated emission factors for CO ranged from 2.71 to 5.10 lb/ton with an average of 3.96 lb CO/ton steel produced. The emission factors for SO₂ and Pb averaged 0.0 lb SO₂/ton steel produced and 0.0003 lb Pb/ton steel produced, respectively.

TABLE 2-3. EMISSION FACTORS BASED ON BRANDT BAGHOUSE STACK TEST

Date	Steel Production, Tons/Hr	Emissions, lb/hr				Emission Factors, lb/ton steel			
		NO _x	CO	SO ₂	Pb	NO _x	CO	SO ₂	Pb
Test 1	59.7	27.77	161.7	0.00	0.0204	0.465	2.709	0.000	0.0003
Test 2	54.1	39.40	276.1	0.00	0.0290	0.728	5.104	0.000	0.0005
Test 3	76.7	39.81	316.2	0.04	0.0171	0.519	4.123	0.001	0.0002
Average	63.5	35.66	251.3	0.013	0.0222	0.562	3.958	0.000	0.0003

Table 2-4a and 2-4b presents the test results comparing the NO_x and CO concentrations measured by the EPA Reference Methods (RM) 7E and 10, respectively, and the NO_x and CO concentrations concurrently measured by the CEMs.

EPA Reference Method 9, "Visible Determination of the Opacity of Emissions from Stationary Sources" was used to determine opacity from the baghouse exhaust as well as from the shop roof monitor. Observations were conducted simultaneously at each source in conjunction with the particulate sampling runs. The observations were recorded separately for the baghouse exhaust and melt shop roof monitor. The baghouse observation data are provided in Table 2-5. The melt shop observation data is provided in Table 2-6. Both tables also present the rolling 6 minute averages.

The data are presented as a comparison in relative concentration. The RM CO and NO_x data were collected at the Brandt baghouse inlet duct. The CEM CO and NO_x data were collected at the baghouse roof monitor, downstream of the bags.

TABLE 2-4a. DATA COMPARISON - CO (ppm)

Run #	Date	Time	Values	
			RM	CEMS
1	08/15/00	0814-1300	55.28	59.51
2	08/15/00	1345-1659	93.73	114.90
3	08/16/00	0754-1214	118.93	142.77
4	08/16/00	1309-1509	96.00	85.87
Averages:			90.99	100.76

RM - Data collected at **baghouse** inlet using EPA Reference Method 10.

CEMS - Continuous emission monitoring data collected at the **baghouse** exhaust.

TABLE 2-4b. DATA COMPARISON - NO_x (ppm)

Run #	Date	Time	Values	
			RM	CEMS
1	08/15/00	0814-1300	8.86	10.67
2	08/16/00	1345-1659	8.14	9.83
3	08/16/00	0754-1214	9.11	6.85
4	08/16/00	1309-1509	10.30	11.06
Averages:			9.10	9.60

RM - Data collected at **baghouse** inlet using EPA Reference Method 7E.

CEMS - Continuous emission monitoring data collected at the **baghouse** exhaust.

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6min Avg	Time	VE	6-min Avg	Time	VE	6min Avg	Time	VE	6-min Avg
8:15:00	0		13:55:00	0		7:55:00	0		12:40:00	0	
8:15:15	0		13:55:15	0		7:55:15	0		12:40:15	0	
8:15:30	0		13:55:30	0		7:55:30	0		12:40:30	0	
8:15:45	0		13:55:45	0		7:55:45	0		12:40:45	0	
8:16:00	0		13:56:00	0		7:56:00	0		12:41:00	0	
8:16:15	0		13:56:15	0		7:56:15	0		12:41:15	0	
8:16:30	0		13:56:30	0		7:56:30	0		12:41:30	0	
8:16:45	0		13:56:45	0		7:56:45	0		12:41:45	0	
8:17:00	0		13:57:00	0		7:57:00	0		12:42:00	0	
8:17:15	0		13:57:15	0		7:57:15	0		12:42:15	0	
8:17:30	0		13:57:30	0		7:57:30	0		12:42:30	0	
8:17:45	0		13:57:45	0		7:57:45	0		12:42:45	0	
8:18:00	0		13:58:00	0		7:58:00	0		12:43:00	0	
8:18:15	0		13:58:15	0		7:58:15	0		12:43:15	0	
8:18:30	0		13:58:30	0		7:58:30	0		12:43:30	0	
8:18:45	0		13:58:45	0		7:58:45	0		12:43:45	0	
8:19:00	0		13:59:00	0		7:59:00	0		12:44:00	0	
8:19:15	0		13:59:15	0		7:59:15	0		12:44:15	0	
8:19:30	0		13:59:30	0		7:59:30	0		12:44:30	0	
8:19:45	0		13:59:45	0		7:59:45	0		12:44:45	0	
8:20:00	0		14:00:00	0		8:00:00	0		12:45:00	0	
8:20:15	0		14:00:15	0		8:00:15	0		12:45:15	0	
8:20:30	0		14:00:30	0		8:00:30	0		12:45:30	0	
8:20:45	0	0.00	14:00:45	0	0.00	8:00:45	0	0.00	12:45:45	0	0.00
8:21:00	0	0.00	14:01:00	0	0.00	8:01:00	0	0.00	12:46:00	0	0.00
8:21:15	0	0.00	14:01:15	0	0.00	8:01:15	0	0.00	12:46:15	0	0.00
8:21:30	0	0.00	14:01:30	0	0.00	8:01:30	0	0.00	12:46:30	0	0.00
8:21:45	0	0.00	14:01:45	0	0.00	8:01:45	0	0.00	12:46:45	0	0.00
8:22:00	0	0.00	14:02:00	0	0.00	8:02:00	0	0.00	12:47:00	0	0.00
8:22:15	0	0.00	14:02:15	0	0.00	8:02:15	0	0.00	12:47:15	0	0.00
8:22:30	0	0.00	14:02:30	0	0.00	8:02:30	0	0.00	12:47:30	0	0.00
8:22:45	0	0.00	14:02:45	0	0.00	8:02:45	0	0.00	12:47:45	0	0.00
8:23:00	0	0.00	14:03:00	0	0.00	8:03:00	0	0.00	12:48:00	0	0.00
8:23:15	0	0.00	14:03:15	0	0.00	8:03:15	0	0.00	12:48:15	0	0.00
8:23:30	0	0.00	14:03:30	0	0.00	8:03:30	0	0.00	12:48:30	0	0.00
8:23:45	0	0.00	14:03:45	0	0.00	8:03:45	0	0.00	12:48:45	0	0.00
8:24:00	0	0.00	14:04:00	0	0.00	8:04:00	0	0.00	12:49:00	0	0.00
8:24:15	0	0.00	14:04:15	0	0.00	8:04:15	0	0.00	12:49:15	0	0.00
8:24:30	0	0.00	14:04:30	0	0.00	8:04:30	0	0.00	12:49:30	0	0.00
8:24:45	0	0.00	14:04:45	0	0.00	8:04:45	0	0.00	12:49:45	0	0.00
8:25:00	0	0.00	14:05:00	0	0.00	8:05:00	0	0.00	12:50:00	0	0.00
8:25:15	0	0.00	14:05:15	0	0.00	8:05:15	0	0.00	12:50:15	0	0.00
8:25:30	0	0.00	14:05:30	0	0.00	8:05:30	0	0.00	12:50:30	0	0.00
8:25:45	0	0.00	14:05:45	0	0.00	8:05:45	0	0.00	12:50:45	0	0.00
8:26:00	0	0.00	14:06:00	0	0.00	8:06:00	0	0.00	12:51:00	0	0.00
8:26:15	0	0.00	14:06:15	0	0.00	8:06:15	0	0.00	12:51:15	0	0.00
8:26:30	0	0.00	14:06:30	0	0.00	8:06:30	0	0.00	12:51:30	0	0.00
8:26:45	0	0.00	14:06:45	0	0.00	8:06:45	0	0.00	12:51:45	0	0.00
8:27:00	0	0.00	14:07:00	0	0.00	8:07:00	0	0.00	12:52:00	0	0.00
8:27:15	0	0.00	14:07:15	0	0.00	8:07:15	0	0.00	12:52:15	0	0.00
8:27:30	0	0.00	14:07:30	0	0.00	8:07:30	0	0.00	12:52:30	0	0.00
8:27:45	0	0.00	14:07:45	0	0.00	8:07:45	0	0.00	12:52:45	0	0.00
8:28:00	0	0.00	14:08:00	0	0.00	8:08:00	0	0.00	12:53:00	0	0.00
8:28:15	0	0.00	14:08:15	0	0.00	8:08:15	0	0.00	12:53:15	0	0.00
8:28:30	0	0.00	14:08:30	0	0.00	8:08:30	0	0.00	12:53:30	0	0.00
8:28:45	0	0.00	14:08:45	0	0.00	8:08:45	0	0.00	12:53:45	0	0.00
8:29:00	0	0.00	14:09:00	0	0.00	8:09:00	0	0.00	12:54:00	0	0.00
8:29:15	0	0.00	14:09:15	0	0.00	8:09:15	0	0.00	12:54:15	0	0.00
8:29:30	0	0.00	14:09:30	0	0.00	8:09:30	0	0.00	12:54:30	0	0.00
8:29:45	0	0.00	14:09:45	0	0.00	8:09:45	0	0.00	12:54:45	0	0.00
8:30:00	0	0.00	14:10:00	0	0.00	8:10:00	0	0.00	12:55:00	0	0.00
8:30:15	0	0.00	14:10:15	0	0.00	8:10:15	0	0.00	12:55:15	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
8:30:30	0	0.00	14:10:30	0	0.00	8:10:30	0	0.00	12:55:30	0	0.00
8:30:45	0	0.00	14:10:45	0	0.00	8:10:45	0	0.00	12:55:45	0	0.00
8:31:00	0	0.00	14:11:00	0	0.00	8:11:00	0	0.00	12:56:00	0	0.00
8:31:15	0	0.00	14:11:15	0	0.00	8:11:15	0	0.00	12:56:15	0	0.00
8:31:30	0	0.00	14:11:30	0	0.00	8:11:30	0	0.00	12:56:30	0	0.00
8:31:45	0	0.00	14:11:45	0	0.00	8:11:45	0	0.00	12:56:45	0	0.00
8:32:00	0	0.00	14:12:00	0	0.00	8:12:00	0	0.00	12:57:00	0	0.00
8:32:15	0	0.00	14:12:15	0	0.00	8:12:15	0	0.00	12:57:15	0	0.00
8:32:30	0	0.00	14:12:30	0	0.00	8:12:30	0	0.00	12:57:30	0	0.00
8:32:45	0	0.00	14:12:45	0	0.00	8:12:45	0	0.00	12:57:45	0	0.00
8:33:00	0	0.00	14:13:00	0	0.00	8:13:00	0	0.00	12:58:00	0	0.00
8:33:15	0	0.00	14:13:15	0	0.00	8:13:15	0	0.00	12:58:15	0	0.00
8:33:30	0	0.00	14:13:30	0	0.00	8:13:30	0	0.00	12:58:30	0	0.00
8:33:45	0	0.00	14:13:45	0	0.00	8:13:45	0	0.00	12:58:45	0	0.00
8:34:00	0	0.00	14:14:00	0	0.00	8:14:00	0	0.00	12:59:00	0	0.00
8:34:15	0	0.00	14:14:15	0	0.00	8:14:15	0	0.00	12:59:15	0	0.00
8:34:30	0	0.00	14:14:30	0	0.00	8:14:30	0	0.00	12:59:30	0	0.00
8:34:45	0	0.00	14:14:45	0	0.00	8:14:45	0	0.00	12:59:45	0	0.00
8:35:00	0	0.00	14:15:00	0	0.00	8:15:00	0	0.00	13:00:00	0	0.00
8:35:15	0	0.00	14:15:15	0	0.00	8:15:15	0	0.00	13:00:15	0	0.00
8:35:30	0	0.00	14:15:30	0	0.00	8:15:30	0	0.00	13:00:30	0	0.00
8:35:45	0	0.00	14:15:45	0	0.00	8:15:45	0	0.00	13:00:45	0	0.00
8:36:00	0	0.00	14:16:00	0	0.00	8:16:00	0	0.00	13:01:00	0	0.00
8:36:15	0	0.00	14:16:15	0	0.00	8:16:15	0	0.00	13:01:15	0	0.00
8:36:30	0	0.00	14:16:30	0	0.00	8:16:30	0	0.00	13:01:30	0	0.00
8:36:45	0	0.00	14:16:45	0	0.00	8:16:45	0	0.00	13:01:45	0	0.00
8:37:00	0	0.00	14:17:00	0	0.00	8:17:00	0	0.00	13:02:00	0	0.00
8:37:15	0	0.00	14:17:15	0	0.00	8:17:15	0	0.00	13:02:15	0	0.00
8:37:30	0	0.00	14:17:30	0	0.00	8:17:30	0	0.00	13:02:30	0	0.00
8:37:45	0	0.00	14:17:45	0	0.00	8:17:45	0	0.00	13:02:45	0	0.00
8:38:00	0	0.00	14:18:00	0	0.00	8:18:00	0	0.00	13:03:00	0	0.00
8:38:15	0	0.00	14:18:15	0	0.00	8:18:15	0	0.00	13:03:15	0	0.00
8:38:30	0	0.00	14:18:30	0	0.00	8:18:30	0	0.00	13:03:30	0	0.00
8:38:45	0	0.00	14:18:45	0	0.00	8:18:45	0	0.00	13:03:45	0	0.00
8:39:00	0	0.00	14:19:00	0	0.00	8:19:00	0	0.00	13:04:00	0	0.00
8:39:15	0	0.00	14:19:15	0	0.00	8:19:15	0	0.00	13:04:15	0	0.00
8:39:30	0	0.00	14:19:30	0	0.00	8:19:30	0	0.00	13:04:30	0	0.00
8:39:45	0	0.00	14:19:45	0	0.00	8:19:45	0	0.00	13:04:45	0	0.00
8:40:00	0	0.00	14:20:00	0	0.00	8:20:00	0	0.00	13:05:00	0	0.00
8:40:15	0	0.00	14:20:15	0	0.00	8:20:15	0	0.00	13:05:15	0	0.00
8:40:30	0	0.00	14:20:30	0	0.00	8:20:30	0	0.00	13:05:30	0	0.00
8:40:45	0	0.00	14:20:45	0	0.00	8:20:45	0	0.00	13:05:45	0	0.00
8:41:00	0	0.00	14:21:00	0	0.00	8:21:00	0	0.00	13:06:00	0	0.00
8:41:15	0	0.00	14:21:15	0	0.00	8:21:15	0	0.00	13:06:15	0	0.00
8:41:30	0	0.00	14:21:30	0	0.00	8:21:30	0	0.00	13:06:30	0	0.00
8:41:45	0	0.00	14:21:45	0	0.00	8:21:45	0	0.00	13:06:45	0	0.00
8:42:00	0	0.00	14:22:00	0	0.00	8:22:00	0	0.00	13:07:00	0	0.00
8:42:15	0	0.00	14:22:15	0	0.00	8:22:15	0	0.00	13:07:15	0	0.00
8:42:30	0	0.00	14:22:30	0	0.00	8:22:30	0	0.00	13:07:30	0	0.00
8:42:45	0	0.00	14:22:45	0	0.00	8:22:45	0	0.00	13:07:45	0	0.00
8:43:00	0	0.00	14:23:00	0	0.00	8:23:00	0	0.00	13:08:00	0	0.00
8:43:15	0	0.00	14:23:15	0	0.00	8:23:15	0	0.00	13:08:15	0	0.00
8:43:30	0	0.00	14:23:30	0	0.00	8:23:30	0	0.00	13:08:30	0	0.00
8:43:45	0	0.00	14:23:45	0	0.00	8:23:45	0	0.00	13:08:45	0	0.00
8:44:00	0	0.00	14:24:00	0	0.00	8:24:00	0	0.00	13:09:00	0	0.00
8:44:15	0	0.00	14:24:15	0	0.00	8:24:15	0	0.00	13:09:15	0	0.00
8:44:30	0	0.00	14:24:30	0	0.00	8:24:30	0	0.00	13:09:30	0	0.00
8:44:45	0	0.00	14:24:45	0	0.00	8:24:45	0	0.00	13:09:45	0	0.00
8:45:00	0	0.00	14:25:00	0	0.00	8:25:00	0	0.00	13:10:00	0	0.00
8:45:15	0	0.00	14:25:15	0	0.00	8:25:15	0	0.00	13:10:15	0	0.00
8:45:30	0	0.00	14:25:30	0	0.00	8:25:30	0	0.00	13:10:30	0	0.00
8:45:45	0	0.00	14:25:45	0	0.00	8:25:45	0	0.00	13:10:45	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
8:46:00	0	0.00	14:26:00	0	0.00	8:26:00	0	0.00	13:11:00	0	0.00
8:46:15	0	0.00	14:26:15	0	0.00	8:26:15	0	0.00	13:11:15	0	0.00
8:46:30	0	0.00	14:26:30	0	0.00	8:26:30	0	0.00	13:11:30	0	0.00
8:46:45	0	0.00	14:26:45	0	0.00	8:26:45	0	0.00	13:11:45	0	0.00
8:47:00	0	0.00	14:27:00	0	0.00	8:27:00	0	0.00	13:12:00	0	0.00
8:47:15	0	0.00	14:27:15	0	0.00	8:27:15	0	0.00	13:12:15	0	0.00
8:47:30	0	0.00	14:27:30	0	0.00	8:27:30	0	0.00	13:12:30	0	0.00
8:47:45	0	0.00	14:27:45	0	0.00	8:27:45	0	0.00	13:12:45	0	0.00
8:48:00	0	0.00	14:28:00	0	0.00	8:28:00	0	0.00	13:13:00	0	0.00
8:48:15	0	0.00	14:28:15	0	0.00	8:28:15	0	0.00	13:13:15	0	0.00
8:48:30	0	0.00	14:28:30	0	0.00	8:28:30	0	0.00	13:13:30	0	0.00
8:48:45	0	0.00	14:28:45	0	0.00	8:28:45	0	0.00	13:13:45	0	0.00
8:49:00	0	0.00	14:29:00	0	0.00	8:29:00	0	0.00	13:14:00	0	0.00
8:49:15	0	0.00	14:29:15	0	0.00	8:29:15	0	0.00	13:14:15	0	0.00
8:49:30	0	0.00	14:29:30	0	0.00	8:29:30	0	0.00	13:14:30	0	0.00
8:49:45	0	0.00	14:29:45	0	0.00	8:29:45	0	0.00	13:14:45	0	0.00
8:50:00	0	0.00	14:30:00	0	0.00	8:30:00	0	0.00	13:15:00	0	0.00
8:50:15	0	0.00	14:30:15	0	0.00	8:30:15	0	0.00	13:15:15	0	0.00
8:50:30	0	0.00	14:30:30	0	0.00	8:30:30	0	0.00	13:15:30	0	0.00
8:50:45	0	0.00	14:30:45	0	0.00	8:30:45	0	0.00	13:15:45	0	0.00
8:51:00	0	0.00	14:31:00	0	0.00	8:31:00	0	0.00	13:16:00	0	0.00
8:51:15	0	0.00	14:31:15	0	0.00	8:31:15	0	0.00	13:16:15	0	0.00
8:51:30	0	0.00	14:31:30	0	0.00	8:31:30	0	0.00	13:16:30	0	0.00
8:51:45	0	0.00	14:31:45	0	0.00	8:31:45	0	0.00	13:16:45	0	0.00
8:52:00	0	0.00	14:32:00	0	0.00	8:32:00	0	0.00	13:17:00	0	0.00
8:52:15	0	0.00	14:32:15	0	0.00	8:32:15	0	0.00	13:17:15	0	0.00
8:52:30	0	0.00	14:32:30	0	0.00	8:32:30	0	0.00	13:17:30	0	0.00
8:52:45	0	0.00	14:32:45	0	0.00	8:32:45	0	0.00	13:17:45	0	0.00
8:53:00	0	0.00	14:33:00	0	0.00	8:33:00	0	0.00	13:18:00	0	0.00
8:53:15	0	0.00	14:33:15	0	0.00	8:33:15	0	0.00	13:18:15	0	0.00
8:53:30	0	0.00	14:33:30	0	0.00	8:33:30	0	0.00	13:18:30	0	0.00
8:53:45	0	0.00	14:33:45	0	0.00	8:33:45	0	0.00	13:18:45	0	0.00
8:54:00	0	0.00	14:34:00	0	0.00	8:34:00	0	0.00	13:19:00	0	0.00
8:54:15	0	0.00	14:34:15	0	0.00	8:34:15	0	0.00	13:19:15	0	0.00
8:54:30	0	0.00	14:34:30	0	0.00	8:34:30	0	0.00	13:19:30	0	0.00
8:54:45	0	0.00	14:34:45	0	0.00	8:34:45	0	0.00	13:19:45	0	0.00
8:55:00	0	0.00	14:35:00	0	0.00	8:35:00	0	0.00	13:20:00	0	0.00
8:55:15	0	0.00	14:35:15	0	0.00	8:35:15	0	0.00	13:20:15	0	0.00
8:55:30	0	0.00	14:35:30	0	0.00	8:35:30	0	0.00	13:20:30	0	0.00
8:55:45	0	0.00	14:35:45	0	0.00	8:35:45	0	0.00	13:20:45	0	0.00
8:56:00	0	0.00	14:36:00	0	0.00	8:36:00	0	0.00	13:21:00	0	0.00
8:56:15	0	0.00	14:36:15	0	0.00	8:36:15	0	0.00	13:21:15	0	0.00
8:56:30	0	0.00	14:36:30	0	0.00	8:36:30	0	0.00	13:21:30	0	0.00
8:56:45	0	0.00	14:36:45	0	0.00	8:36:45	0	0.00	13:21:45	0	0.00
8:57:00	0	0.00	14:37:00	0	0.00	8:37:00	0	0.00	13:22:00	0	0.00
8:57:15	0	0.00	14:37:15	0	0.00	8:37:15	0	0.00	13:22:15	0	0.00
8:57:30	0	0.00	14:37:30	0	0.00	8:37:30	0	0.00	13:22:30	0	0.00
8:57:45	0	0.00	14:37:45	0	0.00	8:37:45	0	0.00	13:22:45	0	0.00
8:58:00	0	0.00	14:38:00	0	0.00	8:38:00	0	0.00	13:23:00	0	0.00
8:58:15	0	0.00	14:38:15	0	0.00	8:38:15	0	0.00	13:23:15	0	0.00
8:58:30	0	0.00	14:38:30	0	0.00	8:38:30	0	0.00	13:23:30	0	0.00
8:58:45	0	0.00	14:38:45	0	0.00	8:38:45	0	0.00	13:23:45	0	0.00
8:59:00	0	0.00	14:39:00	0	0.00	8:39:00	0	0.00	13:24:00	0	0.00
8:59:15	0	0.00	14:39:15	0	0.00	8:39:15	0	0.00	13:24:15	0	0.00
8:59:30	0	0.00	14:39:30	0	0.00	8:39:30	0	0.00	13:24:30	0	0.00
8:59:45	0	0.00	14:39:45	0	0.00	8:39:45	0	0.00	13:24:45	0	0.00
9:00:00	0	0.00	14:40:00	0	0.00	8:40:00	0	0.00	13:25:00	0	0.00
9:00:15	0	0.00	14:40:15	0	0.00	8:40:15	0	0.00	13:25:15	0	0.00
9:00:30	0	0.00	14:40:30	0	0.00	8:40:30	0	0.00	13:25:30	0	0.00
9:00:45	0	0.00	14:40:45	0	0.00	8:40:45	0	0.00	13:25:45	0	0.00
9:01:00	0	0.00	14:41:00	0	0.00	8:41:00	0	0.00	13:26:00	0	0.00
9:01:15	0	0.00	14:41:15	0	0.00	8:41:15	0	0.00	13:26:15	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
9:01:30	0	0.00	14:41:30	0	0.00	8:41:30	0	0.00	13:26:30	0	0.00
9:01:45	0	0.00	14:41:45	0	0.00	8:41:45	0	0.00	13:26:45	0	0.00
9:02:00	0	0.00	14:42:00	0	0.00	8:42:00	0	0.00	13:27:00	0	0.00
9:02:15	0	0.00	14:42:15	0	0.00	8:42:15	0	0.00	13:27:15	0	0.00
9:02:30	0	0.00	14:42:30	0	0.00	8:42:30	0	0.00	13:27:30	0	0.00
9:02:45	0	0.00	14:42:45	0	0.00	8:42:45	0	0.00	13:27:45	0	0.00
9:03:00	0	0.00	14:43:00	0	0.00	8:43:00	0	0.00	13:28:00	0	0.00
9:03:15	0	0.00	14:43:15	0	0.00	8:43:15	0	0.00	13:28:15	0	0.00
9:03:30	0	0.00	14:43:30	0	0.00	8:43:30	0	0.00	13:28:30	0	0.00
9:03:45	0	0.00	14:43:45	0	0.00	8:43:45	0	0.00	13:28:45	0	0.00
9:04:00	0	0.00	14:44:00	0	0.00	8:44:00	0	0.00	13:29:00	0	0.00
9:04:15	0	0.00	14:44:15	0	0.00	8:44:15	0	0.00	13:29:15	0	0.00
9:04:30	0	0.00	14:44:30	0	0.00	8:44:30	0	0.00	13:29:30	0	0.00
9:04:45	0	0.00	14:44:45	0	0.00	8:44:45	0	0.00	13:29:45	0	0.00
9:05:00	0	0.00	14:45:00	0	0.00	8:45:00	0	0.00	13:30:00	0	0.00
9:05:15	0	0.00	14:45:15	0	0.00	8:45:15	0	0.00	13:30:15	0	0.00
9:05:30	0	0.00	14:45:30	0	0.00	8:45:30	0	0.00	13:30:30	0	0.00
9:05:45	0	0.00	14:45:45	0	0.00	8:45:45	0	0.00	13:30:45	0	0.00
9:06:00	0	0.00	14:46:00	0	0.00	8:46:00	0	0.00	13:31:00	0	0.00
9:06:15	0	0.00	14:46:15	0	0.00	8:46:15	0	0.00	13:31:15	0	0.00
9:06:30	0	0.00	14:46:30	0	0.00	8:46:30	0	0.00	13:31:30	0	0.00
9:06:45	0	0.00	14:46:45	0	0.00	8:46:45	0	0.00	13:31:45	0	0.00
9:07:00	0	0.00	14:47:00	0	0.00	8:47:00	0	0.00	13:32:00	0	0.00
9:07:15	0	0.00	14:47:15	0	0.00	8:47:15	0	0.00	13:32:15	0	0.00
9:07:30	0	0.00	14:47:30	0	0.00	8:47:30	0	0.00	13:32:30	0	0.00
9:07:45	0	0.00	14:47:45	0	0.00	8:47:45	0	0.00	13:32:45	0	0.00
9:08:00	0	0.00	14:48:00	0	0.00	8:48:00	0	0.00	13:33:00	0	0.00
9:08:15	0	0.00	14:48:15	0	0.00	8:48:15	0	0.00	13:33:15	0	0.00
9:08:30	0	0.00	14:48:30	0	0.00	8:48:30	0	0.00	13:33:30	0	0.00
9:08:45	0	0.00	14:48:45	0	0.00	8:48:45	0	0.00	13:33:45	0	0.00
9:09:00	0	0.00	14:49:00	0	0.00	8:49:00	0	0.00	13:34:00	0	0.00
9:09:15	0	0.00	14:49:15	0	0.00	8:49:15	0	0.00	13:34:15	0	0.00
9:09:30	0	0.00	14:49:30	0	0.00	8:49:30	0	0.00	13:34:30	0	0.00
9:09:45	0	0.00	14:49:45	0	0.00	8:49:45	0	0.00	13:34:45	0	0.00
9:10:00	0	0.00	14:50:00	0	0.00	8:50:00	0	0.00	13:35:00	0	0.00
9:10:15	0	0.00	14:50:15	0	0.00	8:50:15	0	0.00	13:35:15	0	0.00
9:10:30	0	0.00	14:50:30	0	0.00	8:50:30	0	0.00	13:35:30	0	0.00
9:10:45	0	0.00	14:50:45	0	0.00	8:50:45	0	0.00	13:35:45	0	0.00
9:11:00	0	0.00	14:51:00	0	0.00	8:51:00	0	0.00	13:36:00	0	0.00
9:11:15	0	0.00	14:51:15	0	0.00	8:51:15	0	0.00	13:36:15	0	0.00
9:11:30	0	0.00	14:51:30	0	0.00	8:51:30	0	0.00	13:36:30	0	0.00
9:11:45	0	0.00	14:51:45	0	0.00	8:51:45	0	0.00	13:36:45	0	0.00
9:12:00	0	0.00	14:52:00	0	0.00	8:52:00	0	0.00	13:37:00	0	0.00
9:12:15	0	0.00	14:52:15	0	0.00	8:52:15	0	0.00	13:37:15	0	0.00
9:12:30	0	0.00	14:52:30	0	0.00	8:52:30	0	0.00	13:37:30	0	0.00
9:12:45	0	0.00	14:52:45	0	0.00	8:52:45	0	0.00	13:37:45	0	0.00
9:13:00	0	0.00	14:53:00	0	0.00	8:53:00	0	0.00	13:38:00	0	0.00
9:13:15	0	0.00	14:53:15	0	0.00	8:53:15	0	0.00	13:38:15	0	0.00
9:13:30	0	0.00	14:53:30	0	0.00	8:53:30	0	0.00	13:38:30	0	0.00
9:13:45	0	0.00	14:53:45	0	0.00	8:53:45	0	0.00	13:38:45	0	0.00
9:14:00	0	0.00	14:54:00	0	0.00	8:54:00	0	0.00	13:39:00	0	0.00
9:14:15	0	0.00	14:54:15	0	0.00	8:54:15	0	0.00	13:39:15	0	0.00
9:14:30	0	0.00	14:54:30	0	0.00	8:54:30	0	0.00	13:39:30	0	0.00
9:14:45	0	0.00	14:54:45	0	0.00	8:54:45	0	0.00	13:39:45	0	0.00
9:15:00	0	0.00	14:55:00	0	0.00	8:55:00	0	0.00	13:40:00	0	0.00
9:15:15	0	0.00	14:55:15	0	0.00	8:55:15	0	0.00	13:40:15	0	0.00
9:15:30	0	0.00	14:55:30	0	0.00	8:55:30	0	0.00	13:40:30	0	0.00
9:15:45	0	0.00	14:55:45	0	0.00	8:55:45	0	0.00	13:40:45	0	0.00
9:16:00	0	0.00	14:56:00	0	0.00	8:56:00	0	0.00	13:41:00	0	0.00
9:16:15	0	0.00	14:56:15	0	0.00	8:56:15	0	0.00	13:41:15	0	0.00
9:16:30	0	0.00	14:56:30	0	0.00	8:56:30	0	0.00	13:41:30	0	0.00
9:16:45	0	0.00	14:56:45	0	0.00	8:56:45	0	0.00	13:41:45	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
9:17:00	0	0.00	14:57:00	0	0.00	8:57:00	0	0.00	13:42:00	0	0.00
9:17:15	0	0.00	14:57:15	0	0.00	8:57:15	0	0.00	13:42:15	0	0.00
9:17:30	0	0.00	14:57:30	0	0.00	8:57:30	0	0.00	13:42:30	0	0.00
9:17:45	0	0.00	14:57:45	0	0.00	8:57:45	0	0.00	13:42:45	0	0.00
9:18:00	0	0.00	14:58:00	0	0.00	8:58:00	0	0.00	13:43:00	0	0.00
9:18:15	0	0.00	14:58:15	0	0.00	8:58:15	0	0.00	13:43:15	0	0.00
9:18:30	0	0.00	14:58:30	0	0.00	8:58:30	0	0.00	13:43:30	0	0.00
9:18:45	0	0.00	14:58:45	0	0.00	8:58:45	0	0.00	13:43:45	0	0.00
9:19:00	0	0.00	14:59:00	0	0.00	8:59:00	0	0.00	13:44:00	0	0.00
9:19:15	0	0.00	14:59:15	0	0.00	8:59:15	0	0.00	13:44:15	0	0.00
9:19:30	0	0.00	14:59:30	0	0.00	8:59:30	0	0.00	13:44:30	0	0.00
9:19:45	0	0.00	14:59:45	0	0.00	8:59:45	0	0.00	13:44:45	0	0.00
9:20:00	0	0.00	15:00:00	0	0.00	9:00:00	0	0.00	13:45:00	0	0.00
9:20:15	0	0.00	15:00:15	0	0.00	9:00:15	0	0.00	13:45:15	0	0.00
9:20:30	0	0.00	15:00:30	0	0.00	9:00:30	0	0.00	13:45:30	0	0.00
9:20:45	0	0.00	15:00:45	0	0.00	9:00:45	0	0.00	13:45:45	0	0.00
9:21:00	0	0.00	15:01:00	0	0.00	9:01:00	0	0.00	13:46:00	0	0.00
9:21:15	0	0.00	15:01:15	0	0.00	9:01:15	0	0.00	13:46:15	0	0.00
9:21:30	0	0.00	15:01:30	0	0.00	9:01:30	0	0.00	13:46:30	0	0.00
9:21:45	0	0.00	15:01:45	0	0.00	9:01:45	0	0.00	13:46:45	0	0.00
9:22:00	0	0.00	15:02:00	0	0.00	9:02:00	0	0.00	13:47:00	0	0.00
9:22:15	0	0.00	15:02:15	0	0.00	9:02:15	0	0.00	13:47:15	0	0.00
9:22:30	0	0.00	15:02:30	0	0.00	9:02:30	0	0.00	13:47:30	0	0.00
9:22:45	0	0.00	15:02:45	0	0.00	9:02:45	0	0.00	13:47:45	0	0.00
9:23:00	0	0.00	15:03:00	0	0.00	9:03:00	0	0.00	13:48:00	0	0.00
9:23:15	0	0.00	15:03:15	0	0.00	9:03:15	0	0.00	13:48:15	0	0.00
9:23:30	0	0.00	15:03:30	0	0.00	9:03:30	0	0.00	13:48:30	0	0.00
9:23:45	0	0.00	15:03:45	0	0.00	9:03:45	0	0.00	13:48:45	0	0.00
9:24:00	0	0.00	15:04:00	0	0.00	9:04:00	0	0.00	13:49:00	0	0.00
9:24:15	0	0.00	15:04:15	0	0.00	9:04:15	0	0.00	13:49:15	0	0.00
9:24:30	0	0.00	15:04:30	0	0.00	9:04:30	0	0.00	13:49:30	0	0.00
9:24:45	0	0.00	15:04:45	0	0.00	9:04:45	0	0.00	13:49:45	0	0.00
9:25:00	0	0.00	15:05:00	0	0.00	9:05:00	0	0.00	13:50:00	0	0.00
9:25:15	0	0.00	15:05:15	0	0.00	9:05:15	0	0.00	13:50:15	0	0.00
9:25:30	0	0.00	15:05:30	0	0.00	9:05:30	0	0.00	13:50:30	0	0.00
9:25:45	0	0.00	15:05:45	0	0.00	9:05:45	0	0.00	13:50:45	0	0.00
9:26:00	0	0.00	15:06:00	0	0.00	9:06:00	0	0.00	13:51:00	0	0.00
9:26:15	0	0.00	15:06:15	0	0.00	9:06:15	0	0.00	13:51:15	0	0.00
9:26:30	0	0.00	15:06:30	0	0.00	9:06:30	0	0.00	13:51:30	0	0.00
9:26:45	0	0.00	15:06:45	0	0.00	9:06:45	0	0.00	13:51:45	0	0.00
9:27:00	0	0.00	15:07:00	0	0.00	9:07:00	0	0.00	13:52:00	0	0.00
9:27:15	0	0.00	15:07:15	0	0.00	9:07:15	0	0.00	13:52:15	0	0.00
9:27:30	0	0.00	15:07:30	0	0.00	9:07:30	0	0.00	13:52:30	0	0.00
9:27:45	0	0.00	15:07:45	0	0.00	9:07:45	0	0.00	13:52:45	0	0.00
9:28:00	0	0.00	15:08:00	0	0.00	9:08:00	0	0.00	13:53:00	0	0.00
9:28:15	0	0.00	15:08:15	0	0.00	9:08:15	0	0.00	13:53:15	0	0.00
9:28:30	0	0.00	15:08:30	0	0.00	9:08:30	0	0.00	13:53:30	0	0.00
9:28:45	0	0.00	15:08:45	0	0.00	9:08:45	0	0.00	13:53:45	0	0.00
9:29:00	0	0.00	15:09:00	0	0.00	9:09:00	0	0.00	13:54:00	0	0.00
9:29:15	0	0.00	15:09:15	0	0.00	9:09:15	0	0.00	13:54:15	0	0.00
9:29:30	0	0.00	15:09:30	0	0.00	9:09:30	0	0.00	13:54:30	0	0.00
9:29:45	0	0.00	15:09:45	0	0.00	9:09:45	0	0.00	13:54:45	0	0.00
9:30:00	0	0.00	15:10:00	0	0.00	9:10:00	0	0.00	13:55:00	0	0.00
9:30:15	0	0.00	15:10:15	0	0.00	9:10:15	0	0.00	13:55:15	0	0.00
9:30:30	0	0.00	15:10:30	0	0.00	9:10:30	0	0.00	13:55:30	0	0.00
9:30:45	0	0.00	15:10:45	0	0.00	9:10:45	0	0.00	13:55:45	0	0.00
9:31:00	0	0.00	15:11:00	0	0.00	9:11:00	0	0.00	13:56:00	0	0.00
9:31:15	0	0.00	15:11:15	0	0.00	9:11:15	0	0.00	13:56:15	0	0.00
9:31:30	0	0.00	15:11:30	0	0.00	9:11:30	0	0.00	13:56:30	0	0.00
9:31:45	0	0.00	15:11:45	0	0.00	9:11:45	0	0.00	13:56:45	0	0.00
9:32:00	0	0.00	15:12:00	0	0.00	9:12:00	0	0.00	13:57:00	0	0.00
9:32:15	0	0.00	15:12:15	0	0.00	9:12:15	0	0.00	13:57:15	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
9:32:30	0	0.00	15:12:30	0	0.00	9:12:30	0	0.00	13:57:30	0	0.00
9:32:45	0	0.00	15:12:45	0	0.00	9:12:45	0	0.00	13:57:45	0	0.00
9:33:00	0	0.00	15:13:00	0	0.00	9:13:00	0	0.00	13:58:00	0	0.00
9:33:15	0	0.00	15:13:15	0	0.00	9:13:15	0	0.00	13:58:15	0	0.00
9:33:30	0	0.00	15:13:30	0	0.00	9:13:30	0	0.00	13:58:30	0	0.00
9:33:45	0	0.00	15:13:45	0	0.00	9:13:45	0	0.00	13:58:45	0	0.00
9:34:00	0	0.00	15:14:00	0	0.00	9:14:00	0	0.00	13:59:00	0	0.00
9:34:15	0	0.00	15:14:15	0	0.00	9:14:15	0	0.00	13:59:15	0	0.00
9:34:30	0	0.00	15:14:30	0	0.00	9:14:30	0	0.00	13:59:30	0	0.00
9:34:45	0	0.00	15:14:45	0	0.00	9:14:45	0	0.00	13:59:45	0	0.00
9:35:00	0	0.00	15:15:00	0	0.00	9:15:00	0	0.00	14:00:00	0	0.00
9:35:15	0	0.00	15:15:15	0	0.00	9:15:15	0	0.00	14:00:15	0	0.00
9:35:30	0	0.00	15:15:30	0	0.00	9:15:30	0	0.00	14:00:30	0	0.00
9:35:45	0	0.00	15:15:45	0	0.00	9:15:45	0	0.00	14:00:45	0	0.00
9:36:00	0	0.00	15:16:00	0	0.00	9:16:00	0	0.00	14:01:00	0	0.00
9:36:15	0	0.00	15:16:15	0	0.00	9:16:15	0	0.00	14:01:15	0	0.00
9:36:30	0	0.00	15:16:30	0	0.00	9:16:30	0	0.00	14:01:30	0	0.00
9:36:45	0	0.00	15:16:45	0	0.00	9:16:45	0	0.00	14:01:45	0	0.00
9:37:00	0	0.00	15:17:00	0	0.00	9:17:00	0	0.00	14:02:00	0	0.00
9:37:15	0	0.00	15:17:15	0	0.00	9:17:15	0	0.00	14:02:15	0	0.00
9:37:30	0	0.00	15:17:30	0	0.00	9:17:30	0	0.00	14:02:30	0	0.00
9:37:45	0	0.00	15:17:45	0	0.00	9:17:45	0	0.00	14:02:45	0	0.00
9:38:00	0	0.00	15:18:00	0	0.00	9:18:00	0	0.00	14:03:00	0	0.00
9:38:15	0	0.00	15:18:15	0	0.00	9:18:15	0	0.00	14:03:15	0	0.00
9:38:30	0	0.00	15:18:30	0	0.00	9:18:30	0	0.00	14:03:30	0	0.00
9:38:45	0	0.00	15:18:45	0	0.00	9:18:45	0	0.00	14:03:45	0	0.00
9:39:00	0	0.00	15:19:00	0	0.00	9:19:00	0	0.00	14:04:00	0	0.00
9:39:15	0	0.00	15:19:15	0	0.00	9:19:15	0	0.00	14:04:15	0	0.00
9:39:30	0	0.00	15:19:30	0	0.00	9:19:30	0	0.00	14:04:30	0	0.00
9:39:45	0	0.00	15:19:45	0	0.00	9:19:45	0	0.00	14:04:45	0	0.00
9:40:00	0	0.00	15:20:00	0	0.00	9:20:00	0	0.00	14:05:00	0	0.00
9:40:15	0	0.00	15:20:15	0	0.00	9:20:15	0	0.00	14:05:15	0	0.00
9:40:30	0	0.00	15:20:30	0	0.00	9:20:30	0	0.00	14:05:30	0	0.00
9:40:45	0	0.00	15:20:45	0	0.00	9:20:45	0	0.00	14:05:45	0	0.00
9:41:00	0	0.00	15:21:00	0	0.00	9:21:00	0	0.00	14:06:00	0	0.00
9:41:15	0	0.00	15:21:15	0	0.00	9:21:15	0	0.00	14:06:15	0	0.00
9:41:30	0	0.00	15:21:30	0	0.00	9:21:30	0	0.00	14:06:30	0	0.00
9:41:45	0	0.00	15:21:45	0	0.00	9:21:45	0	0.00	14:06:45	0	0.00
9:42:00	0	0.00	15:22:00	0	0.00	9:22:00	0	0.00	14:07:00	0	0.00
9:42:15	0	0.00	15:22:15	0	0.00	9:22:15	0	0.00	14:07:15	0	0.00
9:42:30	0	0.00	15:22:30	0	0.00	9:22:30	0	0.00	14:07:30	0	0.00
9:42:45	0	0.00	15:22:45	0	0.00	9:22:45	0	0.00	14:07:45	0	0.00
9:43:00	0	0.00	15:23:00	0	0.00	9:23:00	0	0.00	14:08:00	0	0.00
9:43:15	0	0.00	15:23:15	0	0.00	9:23:15	0	0.00	14:08:15	0	0.00
9:43:30	0	0.00	15:23:30	0	0.00	9:23:30	0	0.00	14:08:30	0	0.00
9:43:45	0	0.00	15:23:45	0	0.00	9:23:45	0	0.00	14:08:45	0	0.00
9:44:00	0	0.00	15:24:00	0	0.00	9:24:00	0	0.00	14:09:00	0	0.00
9:44:15	0	0.00	15:24:15	0	0.00	9:24:15	0	0.00	14:09:15	0	0.00
9:44:30	0	0.00	15:24:30	0	0.00	9:24:30	0	0.00	14:09:30	0	0.00
9:44:45	0	0.00	15:24:45	0	0.00	9:24:45	0	0.00	14:09:45	0	0.00
9:45:00	0	0.00	15:25:00	0	0.00	9:25:00	0	0.00	14:10:00	0	0.00
9:45:15	0	0.00	15:25:15	0	0.00	9:25:15	0	0.00	14:10:15	0	0.00
9:45:30	0	0.00	15:25:30	0	0.00	9:25:30	0	0.00	14:10:30	0	0.00
9:45:45	0	0.00	15:25:45	0	0.00	9:25:45	0	0.00	14:10:45	0	0.00
9:46:00	0	0.00	15:26:00	0	0.00	9:26:00	0	0.00	14:11:00	0	0.00
9:46:15	0	0.00	15:26:15	0	0.00	9:26:15	0	0.00	14:11:15	0	0.00
9:46:30	0	0.00	15:26:30	0	0.00	9:26:30	0	0.00	14:11:30	0	0.00
9:46:45	0	0.00	15:26:45	0	0.00	9:26:45	0	0.00	14:11:45	0	0.00
9:47:00	0	0.00	15:27:00	0	0.00	9:27:00	0	0.00	14:12:00	0	0.00
9:47:15	0	0.00	15:27:15	0	0.00	9:27:15	0	0.00	14:12:15	0	0.00
9:47:30	0	0.00	15:27:30	0	0.00	9:27:30	0	0.00	14:12:30	0	0.00
9:47:45	0	0.00	15:27:45	0	0.00	9:27:45	0	0.00	14:12:45	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
9:48:00	0	0.00	15:28:00	0	0.00	9:28:00	0	0.00	14:13:00	0	0.00
9:48:15	0	0.00	15:28:15	0	0.00	9:28:15	0	0.00	14:13:15	0	0.00
9:48:30	0	0.00	15:28:30	0	0.00	9:28:30	0	0.00	14:13:30	0	0.00
9:48:45	0	0.00	15:28:45	0	0.00	9:28:45	0	0.00	14:13:45	0	0.00
9:49:00	0	0.00	15:29:00	0	0.00	9:29:00	0	0.00	14:14:00	0	0.00
9:49:15	0	0.00	15:29:15	0	0.00	9:29:15	0	0.00	14:14:15	0	0.00
9:49:30	0	0.00	15:29:30	0	0.00	9:29:30	0	0.00	14:14:30	0	0.00
9:49:45	0	0.00	15:29:45	0	0.00	9:29:45	0	0.00	14:14:45	0	0.00
9:50:00	0	0.00	15:30:00	0	0.00	9:30:00	0	0.00	14:15:00	0	0.00
9:50:15	0	0.00	15:30:15	0	0.00	9:30:15	0	0.00	14:15:15	0	0.00
9:50:30	0	0.00	15:30:30	0	0.00	9:30:30	0	0.00	14:15:30	0	0.00
9:50:45	0	0.00	15:30:45	0	0.00	9:30:45	0	0.00	14:15:45	0	0.00
9:51:00	0	0.00	15:31:00	0	0.00	9:31:00	0	0.00	14:16:00	0	0.00
9:51:15	0	0.00	15:31:15	0	0.00	9:31:15	0	0.00	14:16:15	0	0.00
9:51:30	0	0.00	15:31:30	0	0.00	9:31:30	0	0.00	14:16:30	0	0.00
9:51:45	0	0.00	15:31:45	0	0.00	9:31:45	0	0.00	14:16:45	0	0.00
9:52:00	0	0.00	15:32:00	0	0.00	9:32:00	0	0.00	14:17:00	0	0.00
9:52:15	0	0.00	15:32:15	0	0.00	9:32:15	0	0.00	14:17:15	0	0.00
9:52:30	0	0.00	15:32:30	0	0.00	9:32:30	0	0.00	14:17:30	0	0.00
9:52:45	0	0.00	15:32:45	0	0.00	9:32:45	0	0.00	14:17:45	0	0.00
9:53:00	0	0.00	15:33:00	0	0.00	9:33:00	0	0.00	14:18:00	0	0.00
9:53:15	0	0.00	15:33:15	0	0.00	9:33:15	0	0.00	14:18:15	0	0.00
9:53:30	0	0.00	15:33:30	0	0.00	9:33:30	0	0.00	14:18:30	0	0.00
9:53:45	0	0.00	15:33:45	0	0.00	9:33:45	0	0.00	14:18:45	0	0.00
9:54:00	0	0.00	15:34:00	0	0.00	9:34:00	0	0.00	14:19:00	0	0.00
9:54:15	0	0.00	15:34:15	0	0.00	9:34:15	0	0.00	14:19:15	0	0.00
9:54:30	0	0.00	15:34:30	0	0.00	9:34:30	0	0.00	14:19:30	0	0.00
9:54:45	0	0.00	15:34:45	0	0.00	9:34:45	0	0.00	14:19:45	0	0.00
9:55:00	0	0.00	15:35:00	0	0.00	9:35:00	0	0.00	14:20:00	0	0.00
9:55:15	0	0.00	15:35:15	0	0.00	9:35:15	0	0.00	14:20:15	0	0.00
9:55:30	0	0.00	15:35:30	0	0.00	9:35:30	0	0.00	14:20:30	0	0.00
9:55:45	0	0.00	15:35:45	0	0.00	9:35:45	0	0.00	14:20:45	0	0.00
9:56:00	0	0.00	15:36:00	0	0.00	9:36:00	0	0.00	14:21:00	0	0.00
9:56:15	0	0.00	15:36:15	0	0.00	9:36:15	0	0.00	14:21:15	0	0.00
9:56:30	0	0.00	15:36:30	0	0.00	9:36:30	0	0.00	14:21:30	0	0.00
9:56:45	0	0.00	15:36:45	0	0.00	9:36:45	0	0.00	14:21:45	0	0.00
9:57:00	0	0.00	15:37:00	0	0.00	9:37:00	0	0.00	14:22:00	0	0.00
9:57:15	0	0.00	15:37:15	0	0.00	9:37:15	0	0.00	14:22:15	0	0.00
9:57:30	0	0.00	15:37:30	0	0.00	9:37:30	0	0.00	14:22:30	0	0.00
9:57:45	0	0.00	15:37:45	0	0.00	9:37:45	0	0.00	14:22:45	0	0.00
9:58:00	0	0.00	15:38:00	0	0.00	9:38:00	0	0.00	14:23:00	0	0.00
9:58:15	0	0.00	15:38:15	0	0.00	9:38:15	0	0.00	14:23:15	0	0.00
9:58:30	0	0.00	15:38:30	0	0.00	9:38:30	0	0.00	14:23:30	0	0.00
9:58:45	0	0.00	15:38:45	0	0.00	9:38:45	0	0.00	14:23:45	0	0.00
9:59:00	0	0.00	15:39:00	0	0.00	9:39:00	0	0.00	14:24:00	0	0.00
9:59:15	0	0.00	15:39:15	0	0.00	9:39:15	0	0.00	14:24:15	0	0.00
9:59:30	0	0.00	15:39:30	0	0.00	9:39:30	0	0.00	14:24:30	0	0.00
9:59:45	0	0.00	15:39:45	0	0.00	9:39:45	0	0.00	14:24:45	0	0.00
10:00:00	0	0.00	15:40:00	0	0.00	9:40:00	0	0.00	14:25:00	0	0.00
10:00:15	0	0.00	15:40:15	0	0.00	9:40:15	0	0.00	14:25:15	0	0.00
10:00:30	0	0.00	15:40:30	0	0.00	9:40:30	0	0.00	14:25:30	0	0.00
10:00:45	0	0.00	15:40:45	0	0.00	9:40:45	0	0.00	14:25:45	0	0.00
10:01:00	0	0.00	15:41:00	0	0.00	9:41:00	0	0.00	14:26:00	0	0.00
10:01:15	0	0.00	15:41:15	0	0.00	9:41:15	0	0.00	14:26:15	0	0.00
10:01:30	0	0.00	15:41:30	0	0.00	9:41:30	0	0.00	14:26:30	0	0.00
10:01:45	0	0.00	15:41:45	0	0.00	9:41:45	0	0.00	14:26:45	0	0.00
10:02:00	0	0.00	15:42:00	0	0.00	9:42:00	0	0.00	14:27:00	0	0.00
10:02:15	0	0.00	15:42:15	0	0.00	9:42:15	0	0.00	14:27:15	0	0.00
10:02:30	0	0.00	15:42:30	0	0.00	9:42:30	0	0.00	14:27:30	0	0.00
10:02:45	0	0.00	15:42:45	0	0.00	9:42:45	0	0.00	14:27:45	0	0.00
10:03:00	0	0.00	15:43:00	0	0.00	9:43:00	0	0.00	14:28:00	0	0.00
10:03:15	0	0.00	15:43:15	0	0.00	9:43:15	0	0.00	14:28:15	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	Gmin Avg
10:03:30	0	0.00	15:43:30	0	0.00	9:43:30	0	0.00	14:28:30	0	0.00
10:03:45	0	0.00	15:43:45	0	0.00	9:43:45	0	0.00	14:28:45	0	0.00
10:04:00	0	0.00	15:44:00	0	0.00	9:44:00	0	0.00	14:29:00	0	0.00
10:04:15	0	0.00	15:44:15	0	0.00	9:44:15	0	0.00	14:29:15	0	0.00
10:04:30	0	0.00	15:44:30	0	0.00	9:44:30	0	0.00	14:29:30	0	0.00
10:04:45	0	0.00	15:44:45	0	0.00	9:44:45	0	0.00	14:29:45	0	0.00
10:05:00	0	0.00	15:45:00	0	0.00	9:45:00	0	0.00	14:30:00	0	0.00
10:05:15	0	0.00	15:45:15	0	0.00	9:45:15	0	0.00	14:30:15	0	0.00
10:05:30	0	0.00	15:45:30	0	0.00	9:45:30	0	0.00	14:30:30	0	0.00
10:05:45	0	0.00	15:45:45	0	0.00	9:45:45	0	0.00	14:30:45	0	0.00
10:06:00	0	0.00	15:46:00	0	0.00	9:46:00	0	0.00	14:31:00	0	0.00
10:06:15	0	0.00	15:46:15	0	0.00	9:46:15	0	0.00	14:31:15	0	0.00
10:06:30	0	0.00	15:46:30	0	0.00	9:46:30	0	0.00	14:31:30	0	0.00
10:06:45	0	0.00	15:46:45	0	0.00	9:46:45	0	0.00	14:31:45	0	0.00
10:07:00	0	0.00	15:47:00	0	0.00	9:47:00	0	0.00	14:32:00	0	0.00
10:07:15	0	0.00	15:47:15	0	0.00	9:47:15	0	0.00	14:32:15	0	0.00
10:07:30	0	0.00	15:47:30	0	0.00	9:47:30	0	0.00	14:32:30	0	0.00
10:07:45	0	0.00	15:47:45	0	0.00	9:47:45	0	0.00	14:32:45	0	0.00
10:08:00	0	0.00	15:48:00	0	0.00	9:48:00	0	0.00	14:33:00	0	0.00
10:08:15	0	0.00	15:48:15	0	0.00	9:48:15	0	0.00	14:33:15	0	0.00
10:08:30	0	0.00	15:48:30	0	0.00	9:48:30	0	0.00	14:33:30	0	0.00
10:08:45	0	0.00	15:48:45	0	0.00	9:48:45	0	0.00	14:33:45	0	0.00
10:09:00	0	0.00	15:49:00	0	0.00	9:49:00	0	0.00	14:34:00	0	0.00
10:09:15	0	0.00	15:49:15	0	0.00	9:49:15	0	0.00	14:34:15	0	0.00
10:09:30	0	0.00	15:49:30	0	0.00	9:49:30	0	0.00	14:34:30	0	0.00
10:09:45	0	0.00	15:49:45	0	0.00	9:49:45	0	0.00	14:34:45	0	0.00
10:10:00	0	0.00	15:50:00	0	0.00	9:50:00	0	0.00	14:35:00	0	0.00
10:10:15	0	0.00	15:50:15	0	0.00	9:50:15	0	0.00	14:35:15	0	0.00
10:10:30	0	0.00	15:50:30	0	0.00	9:50:30	0	0.00	14:35:30	0	0.00
10:10:45	0	0.00	15:50:45	0	0.00	9:50:45	0	0.00	14:35:45	0	0.00
10:11:00	0	0.00	15:51:00	0	0.00	9:51:00	0	0.00	14:36:00	0	0.00
10:11:15	0	0.00	15:51:15	0	0.00	9:51:15	0	0.00	14:36:15	0	0.00
10:11:30	0	0.00	15:51:30	0	0.00	9:51:30	0	0.00	14:36:30	0	0.00
10:11:45	0	0.00	15:51:45	0	0.00	9:51:45	0	0.00	14:36:45	0	0.00
10:12:00	0	0.00	15:52:00	0	0.00	9:52:00	0	0.00	14:37:00	0	0.00
10:12:15	0	0.00	15:52:15	0	0.00	9:52:15	0	0.00	14:37:15	0	0.00
10:12:30	0	0.00	15:52:30	0	0.00	9:52:30	0	0.00	14:37:30	0	0.00
10:12:45	0	0.00	15:52:45	0	0.00	9:52:45	0	0.00	14:37:45	0	0.00
10:13:00	0	0.00	15:53:00	0	0.00	9:53:00	0	0.00	14:38:00	0	0.00
10:13:15	0	0.00	15:53:15	0	0.00	9:53:15	0	0.00	14:38:15	0	0.00
10:13:30	0	0.00	15:53:30	0	0.00	9:53:30	0	0.00	14:38:30	0	0.00
10:13:45	0	0.00	15:53:45	0	0.00	9:53:45	0	0.00	14:38:45	0	0.00
10:14:00	0	0.00	15:54:00	0	0.00	9:54:00	0	0.00	14:39:00	0	0.00
10:14:15	0	0.00	15:54:15	0	0.00	9:54:15	0	0.00	14:39:15	0	0.00
10:14:30	0	0.00	15:54:30	0	0.00	9:54:30	0	0.00	14:39:30	0	0.00
10:14:45	0	0.00	15:54:45	0	0.00	9:54:45	0	0.00	14:39:45	0	0.00
10:15:00	0	0.00	15:55:00	0	0.00	9:55:00	0	0.00	14:40:00	0	0.00
10:15:15	0	0.00	15:55:15	0	0.00	9:55:15	0	0.00	14:40:15	0	0.00
10:15:30	0	0.00	15:55:30	0	0.00	9:55:30	0	0.00	14:40:30	0	0.00
10:15:45	0	0.00	15:55:45	0	0.00	9:55:45	0	0.00	14:40:45	0	0.00
10:16:00	0	0.00	15:56:00	0	0.00	9:56:00	0	0.00	14:41:00	0	0.00
10:16:15	0	0.00	15:56:15	0	0.00	9:56:15	0	0.00	14:41:15	0	0.00
10:16:30	0	0.00	15:56:30	0	0.00	9:56:30	0	0.00	14:41:30	0	0.00
10:16:45	0	0.00	15:56:45	0	0.00	9:56:45	0	0.00	14:41:45	0	0.00
10:17:00	0	0.00	15:57:00	0	0.00	9:57:00	0	0.00	14:42:00	0	0.00
10:17:15	0	0.00	15:57:15	0	0.00	9:57:15	0	0.00	14:42:15	0	0.00
10:17:30	0	0.00	15:57:30	0	0.00	9:57:30	0	0.00	14:42:30	0	0.00
10:17:45	0	0.00	15:57:45	0	0.00	9:57:45	0	0.00	14:42:45	0	0.00
10:18:00	0	0.00	15:58:00	0	0.00	9:58:00	0	0.00	14:43:00	0	0.00
10:18:15	0	0.00	15:58:15	0	0.00	9:58:15	0	0.00	14:43:15	0	0.00
10:18:30	0	0.00	15:58:30	0	0.00	9:58:30	0	0.00	14:43:30	0	0.00
10:18:45	0	0.00	15:58:45	0	0.00	9:58:45	0	0.00	14:43:45	0	0.00

TABLE 2-5. VE READINGS AND ROLLING & MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
10:19:00	0	0.00	15:59:00	0	0.00	9:59:00	0	0.00	14:44:00	0	0.00
10:19:15	0	0.00	15:59:15	0	0.00	9:59:15	0	0.00	14:44:15	0	0.00
10:19:30	0	0.00	15:59:30	0	0.00	9:59:30	0	0.00	14:44:30	0	0.00
10:19:45	0	0.00	15:59:45	0	0.00	9:59:45	0	0.00	14:44:45	0	0.00
10:20:00	0	0.00	16:00:00	0	0.00	10:00:00	0	0.00	14:45:00	0	0.00
10:20:15	0	0.00	16:00:15	0	0.00	10:00:15	0	0.00	14:45:15	0	0.00
10:20:30	0	0.00	16:00:30	0	0.00	10:00:30	0	0.00	14:45:30	0	0.00
10:20:45	0	0.00	16:00:45	0	0.00	10:00:45	0	0.00	14:45:45	0	0.00
10:21:00	0	0.00	16:01:00	0	0.00	10:01:00	0	0.00	14:46:00	0	0.00
10:21:15	0	0.00	16:01:15	0	0.00	10:01:15	0	0.00	14:46:15	0	0.00
10:21:30	0	0.00	16:01:30	0	0.00	10:01:30	0	0.00	14:46:30	0	0.00
10:21:45	0	0.00	16:01:45	0	0.00	10:01:45	0	0.00	14:46:45	0	0.00
10:22:00	0	0.00	16:02:00	0	0.00	10:02:00	0	0.00	14:47:00	0	0.00
10:22:15	0	0.00	16:02:15	0	0.00	10:02:15	0	0.00	14:47:15	0	0.00
10:22:30	0	0.00	16:02:30	0	0.00	10:02:30	0	0.00	14:47:30	0	0.00
10:22:45	0	0.00	16:02:45	0	0.00	10:02:45	0	0.00	14:47:45	0	0.00
10:23:00	0	0.00	16:03:00	0	0.00	10:03:00	0	0.00	14:48:00	0	0.00
10:23:15	0	0.00	16:03:15	0	0.00	10:03:15	0	0.00	14:48:15	0	0.00
10:23:30	0	0.00	16:03:30	0	0.00	10:03:30	0	0.00	14:48:30	0	0.00
10:23:45	0	0.00	16:03:45	0	0.00	10:03:45	0	0.00	14:48:45	0	0.00
10:24:00	0	0.00	16:04:00	0	0.00	10:04:00	0	0.00	14:49:00	0	0.00
10:24:15	0	0.00	16:04:15	0	0.00	10:04:15	0	0.00	14:49:15	0	0.00
10:24:30	0	0.00	16:04:30	0	0.00	10:04:30	0	0.00	14:49:30	0	0.00
10:24:45	0	0.00	16:04:45	0	0.00	10:04:45	0	0.00	14:49:45	0	0.00
10:25:00	0	0.00	16:05:00	0	0.00	10:05:00	0	0.00	14:50:00	0	0.00
10:25:15	0	0.00	16:05:15	0	0.00	10:05:15	0	0.00	14:50:15	0	0.00
10:25:30	0	0.00	16:05:30	0	0.00	10:05:30	0	0.00	14:50:30	0	0.00
10:25:45	0	0.00	16:05:45	0	0.00	10:05:45	0	0.00	14:50:45	0	0.00
10:26:00	0	0.00	16:06:00	0	0.00	10:06:00	0	0.00	14:51:00	0	0.00
10:26:15	0	0.00	16:06:15	0	0.00	10:06:15	0	0.00	14:51:15	0	0.00
10:26:30	0	0.00	16:06:30	0	0.00	10:06:30	0	0.00	14:51:30	0	0.00
10:26:45	0	0.00	16:06:45	0	0.00	10:06:45	0	0.00	14:51:45	0	0.00
10:27:00	0	0.00	16:07:00	0	0.00	10:07:00	0	0.00	14:52:00	0	0.00
10:27:15	0	0.00	16:07:15	0	0.00	10:07:15	0	0.00	14:52:15	0	0.00
10:27:30	0	0.00	16:07:30	0	0.00	10:07:30	0	0.00	14:52:30	0	0.00
10:27:45	0	0.00	16:07:45	0	0.00	10:07:45	0	0.00	14:52:45	0	0.00
10:28:00	0	0.00	16:08:00	0	0.00	10:08:00	0	0.00	14:53:00	0	0.00
10:28:15	0	0.00	16:08:15	0	0.00	10:08:15	0	0.00	14:53:15	0	0.00
10:28:30	0	0.00	16:08:30	0	0.00	10:08:30	0	0.00	14:53:30	0	0.00
10:28:45	0	0.00	16:08:45	0	0.00	10:08:45	0	0.00	14:53:45	0	0.00
10:29:00	0	0.00	16:09:00	0	0.00	10:09:00	0	0.00	14:54:00	0	0.00
10:29:15	0	0.00	16:09:15	0	0.00	10:09:15	0	0.00	14:54:15	0	0.00
10:29:30	0	0.00	16:09:30	0	0.00	10:09:30	0	0.00	14:54:30	0	0.00
10:29:45	0	0.00	16:09:45	0	0.00	10:09:45	0	0.00	14:54:45	0	0.00
10:30:00	0	0.00	16:10:00	0	0.00	10:10:00	0	0.00	14:55:00	0	0.00
10:30:15	0	0.00	16:10:15	0	0.00	10:10:15	0	0.00	14:55:15	0	0.00
10:30:30	0	0.00	16:10:30	0	0.00	10:10:30	0	0.00	14:55:30	0	0.00
10:30:45	0	0.00	16:10:45	0	0.00	10:10:45	0	0.00	14:55:45	0	0.00
10:31:00	0	0.00	16:11:00	0	0.00	10:11:00	0	0.00	14:56:00	0	0.00
10:31:15	0	0.00	16:11:15	0	0.00	10:11:15	0	0.00	14:56:15	0	0.00
10:31:30	0	0.00	16:11:30	0	0.00	10:11:30	0	0.00	14:56:30	0	0.00
10:31:45	0	0.00	16:11:45	0	0.00	10:11:45	0	0.00	14:56:45	0	0.00
10:32:00	0	0.00	16:12:00	0	0.00	10:12:00	0	0.00	14:57:00	0	0.00
10:32:15	0	0.00	16:12:15	0	0.00	10:12:15	0	0.00	14:57:15	0	0.00
10:32:30	0	0.00	16:12:30	0	0.00	10:12:30	0	0.00	14:57:30	0	0.00
10:32:45	0	0.00	16:12:45	0	0.00	10:12:45	0	0.00	14:57:45	0	0.00
10:33:00	0	0.00	16:13:00	0	0.00	10:13:00	0	0.00	14:58:00	0	0.00
10:33:15	0	0.00	16:13:15	0	0.00	10:13:15	0	0.00	14:58:15	0	0.00
10:33:30	0	0.00	16:13:30	0	0.00	10:13:30	0	0.00	14:58:30	0	0.00
10:33:45	0	0.00	16:13:45	0	0.00	10:13:45	0	0.00	14:58:45	0	0.00
10:34:00	0	0.00	16:14:00	0	0.00	10:14:00	0	0.00	14:59:00	0	0.00
10:34:15	0	0.00	16:14:15	0	0.00	10:14:15	0	0.00	14:59:15	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1			TEST 2			TEST 3			TEST 4 (Incomplete)		
August 15, 2000			August 15, 2000			August 16, 2000			August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
10:34:30	0	0.00	16:14:30	0	0.00	10:14:30	0	0.00	14:59:30	0	0.00
10:34:45	0	0.00	16:14:45	0	0.00	10:14:45	0	0.00	14:59:45	0	0.00
10:35:00	0	0.00	16:15:00	0	0.00	10:15:00	0	0.00	15:00:00	0	0.00
10:35:15	0	0.00	16:15:15	0	0.00	10:15:15	0	0.00	15:00:15	0	0.00
10:35:30	0	0.00	16:15:30	0	0.00	10:15:30	0	0.00	15:00:30	0	0.00
10:35:45	0	0.00	16:15:45	0	0.00	10:15:45	0	0.00	15:00:45	0	0.00
10:36:00	0	0.00	16:16:00	0	0.00	10:16:00	0	0.00	15:01:00	0	0.00
10:36:15	0	0.00	16:16:15	0	0.00	10:16:15	0	0.00	15:01:15	0	0.00
10:36:30	0	0.00	16:16:30	0	0.00	10:16:30	0	0.00	15:01:30	0	0.00
10:36:45	0	0.00	16:16:45	0	0.00	10:16:45	0	0.00	15:01:45	0	0.00
10:37:00	0	0.00	16:17:00	0	0.00	10:17:00	0	0.00	15:02:00	0	0.00
10:37:15	0	0.00	16:17:15	0	0.00	10:17:15	0	0.00	15:02:15	0	0.00
10:37:30	0	0.00	16:17:30	0	0.00	10:17:30	0	0.00	15:02:30	0	0.00
10:37:45	0	0.00	16:17:45	0	0.00	10:17:45	0	0.00	15:02:45	0	0.00
10:38:00	0	0.00	16:18:00	0	0.00	10:18:00	0	0.00	Test Terminated		
10:38:15	0	0.00	16:18:15	0	0.00	10:18:15	0	0.00			
10:38:30	0	0.00	16:18:30	0	0.00	10:18:30	0	0.00			
10:38:45	0	0.00	16:18:45	0	0.00	10:18:45	0	0.00			
10:39:00	0	0.00	16:19:00	0	0.00	10:19:00	0	0.00			
10:39:15	0	0.00	16:19:15	0	0.00	10:19:15	0	0.00			
10:39:30	0	0.00	16:19:30	0	0.00	10:19:30	0	0.00			
10:39:45	0	0.00	16:19:45	0	0.00	10:19:45	0	0.00			
10:40:00	0	0.00	16:20:00	0	0.00	10:20:00	0	0.00			
10:40:15	0	0.00	16:20:15	0	0.00	10:20:15	0	0.00			
10:40:30	0	0.00	16:20:30	0	0.00	10:20:30	0	0.00			
10:40:45	0	0.00	16:20:45	0	0.00	10:20:45	0	0.00			
10:41:00	0	0.00	16:21:00	0	0.00	10:21:00	0	0.00			
10:41:15	0	0.00	16:21:15	0	0.00	10:21:15	0	0.00			
10:41:30	0	0.00	16:21:30	0	0.00	10:21:30	0	0.00			
10:41:45	0	0.00	16:21:45	0	0.00	10:21:45	0	0.00			
10:42:00	0	0.00	16:22:00	0	0.00	10:22:00	0	0.00			
10:42:15	0	0.00	16:22:15	0	0.00	10:22:15	0	0.00			
10:42:30	0	0.00	16:22:30	0	0.00	10:22:30	0	0.00			
10:42:45	0	0.00	16:22:45	0	0.00	10:22:45	0	0.00			
10:43:00	0	0.00	16:23:00	0	0.00	10:23:00	0	0.00			
10:43:15	0	0.00	16:23:15	0	0.00	10:23:15	0	0.00			
10:43:30	0	0.00	16:23:30	0	0.00	10:23:30	0	0.00			
10:43:45	0	0.00	16:23:45	0	0.00	10:23:45	0	0.00			
10:44:00	0	0.00	16:24:00	0	0.00	10:24:00	0	0.00			
10:44:15	0	0.00	16:24:15	0	0.00	10:24:15	0	0.00			
10:44:30	0	0.00	16:24:30	0	0.00	10:24:30	0	0.00			
10:44:45	0	0.00	16:24:45	0	0.00	10:24:45	0	0.00			
10:45:00	0	0.00	16:25:00	0	0.00	10:25:00	0	0.00			
10:45:15	0	0.00	16:25:15	0	0.00	10:25:15	0	0.00			
10:45:30	0	0.00	16:25:30	0	0.00	10:25:30	0	0.00			
10:45:45	0	0.00	16:25:45	0	0.00	10:25:45	0	0.00			
10:46:00	0	0.00	16:26:00	0	0.00	10:26:00	0	0.00			
10:46:15	0	0.00	16:26:15	0	0.00	10:26:15	0	0.00			
10:46:30	0	0.00	16:26:30	0	0.00	10:26:30	0	0.00			
10:46:45	0	0.00	16:26:45	0	0.00	10:26:45	0	0.00			
10:47:00	0	0.00	16:27:00	0	0.00	10:27:00	0	0.00			
10:47:15	0	0.00	16:27:15	0	0.00	10:27:15	0	0.00			
10:47:30	0	0.00	16:27:30	0	0.00	10:27:30	0	0.00			
10:47:45	0	0.00	16:27:45	0	0.00	10:27:45	0	0.00			
10:48:00	0	0.00	16:28:00	0	0.00	10:28:00	0	0.00			
10:48:15	0	0.00	16:28:15	0	0.00	10:28:15	0	0.00			
10:48:30	0	0.00	16:28:30	0	0.00	10:28:30	0	0.00			
10:48:45	0	0.00	16:28:45	0	0.00	10:28:45	0	0.00			
10:49:00	0	0.00	16:29:00	0	0.00	10:29:00	0	0.00			
10:49:15	0	0.00	16:29:15	0	0.00	10:29:15	0	0.00			
10:49:30	0	0.00	16:29:30	0	0.00	10:29:30	0	0.00			
10:49:45	0	0.00	16:29:45	0	0.00	10:29:45	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
10:50:00	0	0.00	16:30:00	0	0.00	10:30:00	0	0.00			
10:50:15	0	0.00	16:30:15	0	0.00	10:30:15	0	0.00			
10:50:30	0	0.00	16:30:30	0	0.00	10:30:30	0	0.00			
10:50:45	0	0.00	16:30:45	0	0.00	10:30:45	0	0.00			
10:51:00	0	0.00	16:31:00	0	0.00	10:31:00	0	0.00			
10:51:15	0	0.00	16:31:15	0	0.00	10:31:15	0	0.00			
10:51:30	0	0.00	16:31:30	0	0.00	10:31:30	0	0.00			
10:51:45	0	0.00	16:31:45	0	0.00	10:31:45	0	0.00			
10:52:00	0	0.00	16:32:00	0	0.00	10:32:00	0	0.00			
10:52:15	0	0.00	16:32:15	0	0.00	10:32:15	0	0.00			
10:52:30	0	0.00	16:32:30	0	0.00	10:32:30	0	0.00			
10:52:45	0	0.00	16:32:45	0	0.00	10:32:45	0	0.00			
10:53:00	0	0.00	16:33:00	0	0.00	10:33:00	0	0.00			
10:53:15	0	0.00	16:33:15	0	0.00	10:33:15	0	0.00			
10:53:30	0	0.00	16:33:30	0	0.00	10:33:30	0	0.00			
10:53:45	0	0.00	16:33:45	0	0.00	10:33:45	0	0.00			
10:54:00	0	0.00	16:34:00	0	0.00	10:34:00	0	0.00			
10:54:15	0	0.00	16:34:15	0	0.00	10:34:15	0	0.00			
10:54:30	0	0.00	16:34:30	0	0.00	10:34:30	0	0.00			
10:54:45	0	0.00	16:34:45	0	0.00	10:34:45	0	0.00			
10:55:00	0	0.00	16:35:00	0	0.00	10:35:00	0	0.00			
10:55:15	0	0.00	16:35:15	0	0.00	10:35:15	0	0.00			
10:55:30	0	0.00	16:35:30	0	0.00	10:35:30	0	0.00			
10:55:45	0	0.00	16:35:45	0	0.00	10:35:45	0	0.00			
10:56:00	0	0.00	16:36:00	0	0.00	10:36:00	0	0.00			
10:56:15	0	0.00	16:36:15	0	0.00	10:36:15	0	0.00			
10:56:30	0	0.00	16:36:30	0	0.00	10:36:30	0	0.00			
10:56:45	0	0.00	16:36:45	0	0.00	10:36:45	0	0.00			
10:57:00	0	0.00	16:37:00	0	0.00	10:37:00	0	0.00			
10:57:15	0	0.00	16:37:15	0	0.00	10:37:15	0	0.00			
10:57:30	0	0.00	16:37:30	0	0.00	10:37:30	0	0.00			
10:57:45	0	0.00	16:37:45	0	0.00	10:37:45	0	0.00			
10:58:00	0	0.00	16:38:00	0	0.00	10:38:00	0	0.00			
10:58:15	0	0.00	16:38:15	0	0.00	10:38:15	0	0.00			
10:58:30	0	0.00	16:38:30	0	0.00	10:38:30	0	0.00			
10:58:45	0	0.00	16:38:45	0	0.00	10:38:45	0	0.00			
10:59:00	0	0.00	16:39:00	0	0.00	10:39:00	0	0.00			
10:59:15	0	0.00	16:39:15	0	0.00	10:39:15	0	0.00			
10:59:30	0	0.00	16:39:30	0	0.00	10:39:30	0	0.00			
10:59:45	0	0.00	16:39:45	0	0.00	10:39:45	0	0.00			
11:00:00	0	0.00	16:40:00	0	0.00	10:40:00	0	0.00			
11:00:15	0	0.00	16:40:15	0	0.00	10:40:15	0	0.00			
11:00:30	0	0.00	16:40:30	0	0.00	10:40:30	0	0.00			
11:00:45	0	0.00	16:40:45	0	0.00	10:40:45	0	0.00			
11:01:00	0	0.00	16:41:00	0	0.00	10:41:00	0	0.00			
11:01:15	0	0.00	16:41:15	0	0.00	10:41:15	0	0.00			
11:01:30	0	0.00	16:41:30	0	0.00	10:41:30	0	0.00			
11:01:45	0	0.00	16:41:45	0	0.00	10:41:45	0	0.00			
11:02:00	0	0.00	16:42:00	0	0.00	10:42:00	0	0.00			
11:02:15	0	0.00	16:42:15	0	0.00	10:42:15	0	0.00			
11:02:30	0	0.00	16:42:30	0	0.00	10:42:30	0	0.00			
11:02:45	0	0.00	16:42:45	0	0.00	10:42:45	0	0.00			
11:03:00	0	0.00	16:43:00	0	0.00	10:43:00	0	0.00			
11:03:15	0	0.00	16:43:15	0	0.00	10:43:15	0	0.00			
11:03:30	0	0.00	16:43:30	0	0.00	10:43:30	0	0.00			
11:03:45	0	0.00	16:43:45	0	0.00	10:43:45	0	0.00			
11:04:00	0	0.00	16:44:00	0	0.00	10:44:00	0	0.00			
11:04:15	0	0.00	16:44:15	0	0.00	10:44:15	0	0.00			
11:04:30	0	0.00	16:44:30	0	0.00	10:44:30	0	0.00			
11:04:45	0	0.00	16:44:45	0	0.00	10:44:45	0	0.00			
11:05:00	0	0.00	16:45:00	0	0.00	10:45:00	0	0.00			
11:05:15	0	0.00	16:45:15	0	0.00						

TABLE 2-5. YE READINGS AND ROLLING 6-MINUTE YE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
11:05:30	0	0.00	16:45:30	0	0.00	10:45:30	0	0.00			
11:05:45	0	0.00	16:45:45	0	0.00	10:45:45	0	0.00			
11:06:00	0	0.00	16:46:00	0	0.00	10:46:00	0	0.00			
11:06:15	0	0.00	16:46:15	0	0.00	10:46:15	0	0.00			
11:06:30	0	0.00	16:46:30	0	0.00	10:46:30	0	0.00			
11:06:45	0	0.00	16:46:45	0	0.00	10:46:45	0	0.00			
11:07:00	0	0.00	16:47:00	0	0.00	10:47:00	0	0.00			
11:07:15	0	0.00	16:47:15	0	0.00	10:47:15	0	0.00			
11:07:30	0	0.00	16:47:30	0	0.00	10:47:30	0	0.00			
11:07:45	0	0.00	16:47:45	0	0.00	10:47:45	0	0.00			
11:08:00	0	0.00	16:48:00	0	0.00	10:48:00	0	0.00			
11:08:15	0	0.00	16:48:15	0	0.00	10:48:15	0	0.00			
11:08:30	0	0.00	16:48:30	0	0.00	10:48:30	0	0.00			
11:08:45	0	0.00	16:48:45	0	0.00	10:48:45	0	0.00			
11:09:00	0	0.00	16:49:00	0	0.00	10:49:00	0	0.00			
11:09:15	0	0.00	16:49:15	0	0.00	10:49:15	0	0.00			
11:09:30	0	0.00	16:49:30	0	0.00	10:49:30	0	0.00			
11:09:45	0	0.00	16:49:45	0	0.00	10:49:45	0	0.00			
11:10:00	0	0.00	16:50:00	0	0.00	10:50:00	0	0.00			
11:10:15	0	0.00	16:50:15	0	0.00	10:50:15	0	0.00			
11:10:30	0	0.00	16:50:30	0	0.00	10:50:30	0	0.00			
11:10:45	0	0.00	16:50:45	0	0.00	10:50:45	0	0.00			
11:11:00	0	0.00	16:51:00	0	0.00	10:51:00	0	0.00			
11:11:15	0	0.00	16:51:15	0	0.00	10:51:15	0	0.00			
11:11:30	0	0.00	16:51:30	0	0.00	10:51:30	0	0.00			
11:11:45	0	0.00	16:51:45	0	0.00	10:51:45	0	0.00			
11:12:00	0	0.00	16:52:00	0	0.00	10:52:00	0	0.00			
11:12:15	0	0.00	16:52:15	0	0.00	10:52:15	0	0.00			
11:12:30	0	0.00	16:52:30	0	0.00	10:52:30	0	0.00			
11:12:45	0	0.00	16:52:45	0	0.00	10:52:45	0	0.00			
11:13:00	0	0.00	16:53:00	0	0.00	10:53:00	0	0.00			
11:13:15	0	0.00	16:53:15	0	0.00	10:53:15	0	0.00			
11:13:30	0	0.00	16:53:30	0	0.00	10:53:30	0	0.00			
11:13:45	0	0.00	16:53:45	0	0.00	10:53:45	0	0.00			
11:14:00	0	0.00	16:54:00	0	0.00	10:54:00	0	0.00			
11:14:15	0	0.00	16:54:15	0	0.00	10:54:15	0	0.00			
11:14:30	0	0.00	16:54:30	0	0.00	10:54:30	0	0.00			
11:14:45	0	0.00	16:54:45	0	0.00	10:54:45	0	0.00			
11:15:00	0	0.00	16:55:00	0	0.00	10:55:00	0	0.00			
11:15:15	0	0.00	16:55:15	0	0.00	10:55:15	0	0.00			
11:15:30	0	0.00	16:55:30	0	0.00	10:55:30	0	0.00			
11:15:45	0	0.00	16:55:45	0	0.00	10:55:45	0	0.00			
11:16:00	0	0.00	16:56:00	0	0.00	10:56:00	0	0.00			
11:16:15	0	0.00	16:56:15	0	0.00	10:56:15	0	0.00			
11:16:30	0	0.00	16:56:30	0	0.00	10:56:30	0	0.00			
11:16:45	0	0.00	16:56:45	0	0.00	10:56:45	0	0.00			
11:17:00	0	0.00	16:57:00	0	0.00	10:57:00	0	0.00			
11:17:15	0	0.00	16:57:15	0	0.00	10:57:15	0	0.00			
11:17:30	0	0.00	16:57:30	0	0.00	10:57:30	0	0.00			
11:17:45	0	0.00	16:57:45	0	0.00	10:57:45	0	0.00			
11:18:00	0	0.00	16:58:00	0	0.00	10:58:00	0	0.00			
11:18:15	0	0.00	16:58:15	0	0.00	10:58:15	0	0.00			
11:18:30	0	0.00	16:58:30	0	0.00	10:58:30	0	0.00			
11:18:45	0	0.00	16:58:45	0	0.00	10:58:45	0	0.00			
11:19:00	0	0.00	16:59:00	0	0.00	10:59:00	0	0.00			
11:19:15	0	0.00	16:59:15	0	0.00	10:59:15	0	0.00			
11:19:30	0	0.00	16:59:30	0	0.00	10:59:30	0	0.00			
11:19:45	0	0.00	16:59:45	0	0.00	10:59:45	0	0.00			
11:20:00	0	0.00	17:00:00	0	0.00	11:00:00	0	0.00			
11:20:15	0	0.00	17:00:15	0	0.00	11:00:15	0	0.00			
11:20:30	0	0.00	17:00:30	0	0.00	11:00:30	0	0.00			
11:20:45	0	0.00	17:00:45	0	0.00	11:00:45	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
11:21:00	0	0.00	17:01:00	0	0.00	11:01:00	0	0.00			
11:21:15	0	0.00	17:01:15	0	0.00	11:01:15	0	0.00			
11:21:30	0	0.00	17:01:30	0	0.00	11:01:30	0	0.00			
11:21:45	0	0.00	17:01:45	0	0.00	11:01:45	0	0.00			
11:22:00	0	0.00	17:02:00	0	0.00	11:02:00	0	0.00			
11:22:15	0	0.00	17:02:15	0	0.00	11:02:15	0	0.00			
11:22:30	0	0.00	17:02:30	0	0.00	11:02:30	0	0.00			
11:22:45	0	0.00	17:02:45	0	0.00	11:02:45	0	0.00			
11:23:00	0	0.00	17:03:00	0	0.00	11:03:00	0	0.00			
11:23:15	0	0.00	17:03:15	0	0.00	11:03:15	0	0.00			
11:23:30	0	0.00	17:03:30	0	0.00	11:03:30	0	0.00			
11:23:45	0	0.00	17:03:45	0	0.00	11:03:45	0	0.00			
11:24:00	0	0.00	17:04:00	0	0.00	11:04:00	0	0.00			
11:24:15	0	0.00	17:04:15	0	0.00	11:04:15	0	0.00			
11:24:30	0	0.00	17:04:30	0	0.00	11:04:30	0	0.00			
11:24:45	0	0.00	17:04:45	0	0.00	11:04:45	0	0.00			
11:25:00	0	0.00	17:05:00	0	0.00	11:05:00	0	0.00			
11:25:15	0	0.00	17:05:15	0	0.00	11:05:15	0	0.00			
11:25:30	0	0.00	17:05:30	0	0.00	11:05:30	0	0.00			
11:25:45	0	0.00	17:05:45	0	0.00	11:05:45	0	0.00			
11:26:00	0	0.00	17:06:00	0	0.00	11:06:00	0	0.00			
11:26:15	0	0.00	17:06:15	0	0.00	11:06:15	0	0.00			
11:26:30	0	0.00	17:06:30	0	0.00	11:06:30	0	0.00			
11:26:45	0	0.00	17:06:45	0	0.00	11:06:45	0	0.00			
11:27:00	0	0.00	17:07:00	0	0.00	11:07:00	0	0.00			
11:27:15	0	0.00	17:07:15	0	0.00	11:07:15	0	0.00			
11:27:30	0	0.00	17:07:30	0	0.00	11:07:30	0	0.00			
11:27:45	0	0.00	17:07:45	0	0.00	11:07:45	0	0.00			
11:28:00	0	0.00	17:08:00	0	0.00	11:08:00	0	0.00			
11:28:15	0	0.00	17:08:15	0	0.00	11:08:15	0	0.00			
11:28:30	0	0.00	17:08:30	0	0.00	11:08:30	0	0.00			
11:28:45	0	0.00	17:08:45	0	0.00	11:08:45	0	0.00			
11:29:00	0	0.00	17:09:00	0	0.00	11:09:00	0	0.00			
11:29:15	0	0.00	17:09:15	0	0.00	11:09:15	0	0.00			
11:29:30	0	0.00	17:09:30	0	0.00	11:09:30	0	0.00			
11:29:45	0	0.00	17:09:45	0	0.00	11:09:45	0	0.00			
11:30:00	0	0.00	17:10:00	0	0.00	11:10:00	0	0.00			
11:30:15	0	0.00	17:10:15	0	0.00	11:10:15	0	0.00			
11:30:30	0	0.00	17:10:30	0	0.00	11:10:30	0	0.00			
11:30:45	0	0.00	17:10:45	0	0.00	11:10:45	0	0.00			
11:31:00	0	0.00	17:11:00	0	0.00	11:11:00	0	0.00			
11:31:15	0	0.00	17:11:15	0	0.00	11:11:15	0	0.00			
11:31:30	0	0.00	17:11:30	0	0.00	11:11:30	0	0.00			
11:31:45	0	0.00	17:11:45	0	0.00	11:11:45	0	0.00			
11:32:00	0	0.00	17:12:00	0	0.00	11:12:00	0	0.00			
11:32:15	0	0.00	17:12:15	0	0.00	11:12:15	0	0.00			
11:32:30	0	0.00	17:12:30	0	0.00	11:12:30	0	0.00			
11:32:45	0	0.00	17:12:45	0	0.00	11:12:45	0	0.00			
11:33:00	0	0.00	17:13:00	0	0.00	11:13:00	0	0.00			
11:33:15	0	0.00	17:13:15	0	0.00	11:13:15	0	0.00			
11:33:30	0	0.00	17:13:30	0	0.00	11:13:30	0	0.00			
11:33:45	0	0.00	17:13:45	0	0.00	11:13:45	0	0.00			
11:34:00	0	0.00	17:14:00	0	0.00	11:14:00	0	0.00			
11:34:15	0	0.00	17:14:15	0	0.00	11:14:15	0	0.00			
11:34:30	0	0.00	17:14:30	0	0.00	11:14:30	0	0.00			
11:34:45	0	0.00	17:14:45	0	0.00	11:14:45	0	0.00			
11:35:00	0	0.00	17:15:00	0	0.00	11:15:00	0	0.00			
11:35:15	0	0.00	17:15:15	0	0.00	11:15:15	0	0.00			
11:35:30	0	0.00	17:15:30	0	0.00	11:15:30	0	0.00			
11:35:45	0	0.00	17:15:45	0	0.00	11:15:45	0	0.00			
11:36:00	0	0.00	17:16:00	0	0.00	11:16:00	0	0.00			
11:36:15	0	0.00	17:16:15	0	0.00	11:16:15	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
11:36:30	0	0.00	17:16:30	0	0.00	11:16:30	0	0.00			
11:36:45	0	0.00	17:16:45	0	0.00	11:16:45	0	0.00			
11:37:00	0	0.00	17:17:00	0	0.00	11:17:00	0	0.00			
11:37:15	0	0.00	17:17:15	0	0.00	11:17:15	0	0.00			
11:37:30	0	0.00	17:17:30	0	0.00	11:17:30	0	0.00			
11:37:45	0	0.00	17:17:45	0	0.00	11:17:45	0	0.00			
11:38:00	0	0.00	17:18:00	0	0.00	11:18:00	0	0.00			
11:38:15	0	0.00	17:18:15	0	0.00	11:18:15	0	0.00			
11:38:30	0	0.00	17:18:30	0	0.00	11:18:30	0	0.00			
11:38:45	0	0.00	17:18:45	0	0.00	11:18:45	0	0.00			
11:39:00	0	0.00	17:19:00	0	0.00	11:19:00	0	0.00			
11:39:15	0	0.00	17:19:15	0	0.00	11:19:15	0	0.00			
11:39:30	0	0.00	17:19:30	0	0.00	11:19:30	0	0.00			
11:39:45	0	0.00	17:19:45	0	0.00	11:19:45	0	0.00			
11:40:00	0	0.00	17:20:00	0	0.00	11:20:00	0	0.00			
11:40:15	0	0.00	17:20:15	0	0.00	11:20:15	0	0.00			
11:40:30	0	0.00	17:20:30	0	0.00	11:20:30	0	0.00			
11:40:45	0	0.00	17:20:45	0	0.00	11:20:45	0	0.00			
11:41:00	0	0.00	17:21:00	0	0.00	11:21:00	0	0.00			
11:41:15	0	0.00	17:21:15	0	0.00	11:21:15	0	0.00			
11:41:30	0	0.00	17:21:30	0	0.00	11:21:30	0	0.00			
11:41:45	0	0.00	17:21:45	0	0.00	11:21:45	0	0.00			
11:42:00	0	0.00	17:22:00	0	0.00	11:22:00	0	0.00			
11:42:15	0	0.00	17:22:15	0	0.00	11:22:15	0	0.00			
11:42:30	0	0.00	17:22:30	0	0.00	11:22:30	0	0.00			
11:42:45	0	0.00	17:22:45	0	0.00	11:22:45	0	0.00			
11:43:00	0	0.00	17:23:00	0	0.00	11:23:00	0	0.00			
11:43:15	0	0.00	17:23:15	0	0.00	11:23:15	0	0.00			
11:43:30	0	0.00	17:23:30	0	0.00	11:23:30	0	0.00			
11:43:45	0	0.00	17:23:45	0	0.00	11:23:45	0	0.00			
11:44:00	0	0.00	17:24:00	0	0.00	11:24:00	0	0.00			
11:44:15	0	0.00	17:24:15	0	0.00	11:24:15	0	0.00			
11:44:30	0	0.00	17:24:30	0	0.00	11:24:30	0	0.00			
11:44:45	0	0.00	17:24:45	0	0.00	11:24:45	0	0.00			
11:45:00	0	0.00	17:25:00	0	0.00	11:25:00	0	0.00			
11:45:15	0	0.00	17:25:15	0	0.00	11:25:15	0	0.00			
11:45:30	0	0.00	17:25:30	0	0.00	11:25:30	0	0.00			
11:45:45	0	0.00	17:25:45	0	0.00	11:25:45	0	0.00			
11:46:00	0	0.00	17:26:00	0	0.00	11:26:00	0	0.00			
11:46:15	0	0.00	17:26:15	0	0.00	11:26:15	0	0.00			
11:46:30	0	0.00	17:26:30	0	0.00	11:26:30	0	0.00			
11:46:45	0	0.00	17:26:45	0	0.00	11:26:45	0	0.00			
11:47:00	0	0.00	17:27:00	0	0.00	11:27:00	0	0.00			
11:47:15	0	0.00	17:27:15	0	0.00	11:27:15	0	0.00			
11:47:30	0	0.00	17:27:30	0	0.00	11:27:30	0	0.00			
11:47:45	0	0.00	17:27:45	0	0.00	11:27:45	0	0.00			
11:48:00	0	0.00	17:28:00	0	0.00	11:28:00	0	0.00			
11:48:15	0	0.00	17:28:15	0	0.00	11:28:15	0	0.00			
11:48:30	0	0.00	17:28:30	0	0.00	11:28:30	0	0.00			
11:48:45	0	0.00	17:28:45	0	0.00	11:28:45	0	0.00			
11:49:00	0	0.00	17:29:00	0	0.00	11:29:00	0	0.00			
11:49:15	0	0.00	17:29:15	0	0.00	11:29:15	0	0.00			
11:49:30	0	0.00	17:29:30	0	0.00	11:29:30	0	0.00			
11:49:45	0	0.00	17:29:45	0	0.00	11:29:45	0	0.00			
11:50:00	0	0.00	17:30:00	0	0.00	11:30:00	0	0.00			
11:50:15	0	0.00	17:30:15	0	0.00	11:30:15	0	0.00			
11:50:30	0	0.00	17:30:30	0	0.00	11:30:30	0	0.00			
11:50:45	0	0.00	17:30:45	0	0.00	11:30:45	0	0.00			
11:51:00	0	0.00	17:31:00	0	0.00	11:31:00	0	0.00			
11:51:15	0	0.00	17:31:15	0	0.00	11:31:15	0	0.00			
11:51:30	0	0.00	17:31:30	0	0.00	11:31:30	0	0.00			
11:51:45	0	0.00	17:31:45	0	0.00	11:31:45	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
11:52:00	0	0.00	17:32:00	0	0.00	11:32:00	0	0.00			
11:52:15	0	0.00	17:32:15	0	0.00	11:32:15	0	0.00			
11:52:30	0	0.00	17:32:30	0	0.00	11:32:30	0	0.00			
11:52:45	0	0.00	17:32:45	0	0.00	11:32:45	0	0.00			
11:53:00	0	0.00	17:33:00	0	0.00	11:33:00	0	0.00			
11:53:15	0	0.00	17:33:15	0	0.00	11:33:15	0	0.00			
11:53:30	0	0.00	17:33:30	0	0.00	11:33:30	0	0.00			
11:53:45	0	0.00	17:33:45	0	0.00	11:33:45	0	0.00			
11:54:00	0	0.00	17:34:00	0	0.00	11:34:00	0	0.00			
11:54:15	0	0.00	17:34:15	0	0.00	11:34:15	0	0.00			
11:54:30	0	0.00	17:34:30	0	0.00	11:34:30	0	0.00			
11:54:45	0	0.00	17:34:45	0	0.00	11:34:45	0	0.00			
11:55:00	0	0.00	17:35:00	0	0.00	11:35:00	0	0.00			
11:55:15	0	0.00	17:35:15	0	0.00	11:35:15	0	0.00			
11:55:30	0	0.00	17:35:30	0	0.00	11:35:30	0	0.00			
11:55:45	0	0.00	17:35:45	0	0.00	11:35:45	0	0.00			
11:56:00	0	0.00	17:36:00	0	0.00	11:36:00	0	0.00			
11:56:15	0	0.00	17:36:15	0	0.00	11:36:15	0	0.00			
11:56:30	0	0.00	17:36:30	0	0.00	11:36:30	0	0.00			
11:56:45	0	0.00	17:36:45	0	0.00	11:36:45	0	0.00			
11:57:00	0	0.00	17:37:00	0	0.00	11:37:00	0	0.00			
11:57:15	0	0.00	17:37:15	0	0.00	11:37:15	0	0.00			
11:57:30	0	0.00	17:37:30	0	0.00	11:37:30	0	0.00			
11:57:45	0	0.00	17:37:45	0	0.00	11:37:45	0	0.00			
11:58:00	0	0.00	17:38:00	0	0.00	11:38:00	0	0.00			
11:58:15	0	0.00	17:38:15	0	0.00	11:38:15	0	0.00			
11:58:30	0	0.00	17:38:30	0	0.00	11:38:30	0	0.00			
11:58:45	0	0.00	17:38:45	0	0.00	11:38:45	0	0.00			
11:59:00	0	0.00	17:39:00	0	0.00	11:39:00	0	0.00			
11:59:15	0	0.00	17:39:15	0	0.00	11:39:15	0	0.00			
11:59:30	0	0.00	17:39:30	0	0.00	11:39:30	0	0.00			
11:59:45	0	0.00	17:39:45	0	0.00	11:39:45	0	0.00			
12:00:00	0	0.00	17:40:00	0	0.00	11:40:00	0	0.00			
12:00:15	0	0.00	17:40:15	0	0.00	11:40:15	0	0.00			
12:00:30	0	0.00	17:40:30	0	0.00	11:40:30	0	0.00			
12:00:45	0	0.00	17:40:45	0	0.00	11:40:45	0	0.00			
12:01:00	0	0.00	17:41:00	0	0.00	11:41:00	0	0.00			
12:01:15	0	0.00	17:41:15	0	0.00	11:41:15	0	0.00			
12:01:30	0	0.00	17:41:30	0	0.00	11:41:30	0	0.00			
12:01:45	0	0.00	17:41:45	0	0.00	11:41:45	0	0.00			
12:02:00	0	0.00	17:42:00	0	0.00	11:42:00	0	0.00			
12:02:15	0	0.00	17:42:15	0	0.00	11:42:15	0	0.00			
12:02:30	0	0.00	17:42:30	0	0.00	11:42:30	0	0.00			
12:02:45	0	0.00	17:42:45	0	0.00	11:42:45	0	0.00			
12:03:00	0	0.00	17:43:00	0	0.00	11:43:00	0	0.00			
12:03:15	0	0.00	17:43:15	0	0.00	11:43:15	0	0.00			
12:03:30	0	0.00	17:43:30	0	0.00	11:43:30	0	0.00			
12:03:45	0	0.00	17:43:45	0	0.00	11:43:45	0	0.00			
12:04:00	0	0.00	17:44:00	0	0.00	11:44:00	0	0.00			
12:04:15	0	0.00	17:44:15	0	0.00	11:44:15	0	0.00			
12:04:30	0	0.00	17:44:30	0	0.00	11:44:30	0	0.00			
12:04:45	0	0.00	17:44:45	0	0.00	11:44:45	0	0.00			
12:05:00	0	0.00	17:45:00	0	0.00	11:45:00	0	0.00			
12:05:15	0	0.00	17:45:15	0	0.00	11:45:15	0	0.00			
12:05:30	0	0.00	17:45:30	0	0.00	11:45:30	0	0.00			
12:05:45	0	0.00	17:45:45	0	0.00	11:45:45	0	0.00			
12:06:00	0	0.00	17:46:00	0	0.00	11:46:00	0	0.00			
12:06:15	0	0.00	17:46:15	0	0.00	11:46:15	0	0.00			
12:06:30	0	0.00	17:46:30	0	0.00	11:46:30	0	0.00			
12:06:45	0	0.00	17:46:45	0	0.00	11:46:45	0	0.00			
12:07:00	0	0.00	17:47:00	0	0.00	11:47:00	0	0.00			
12:07:15	0	0.00	17:47:15	0	0.00	11:47:15	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
12:07:30	0	0.00	17:47:30	0	0.00	11:47:30	0	0.00			
12:07:45	0	0.00	17:47:45	0	0.00	11:47:45	0	0.00			
12:08:00	0	0.00	17:48:00	0	0.00	11:48:00	0	0.00			
12:08:15	0	0.00	17:48:15	0	0.00	11:48:15	0	0.00			
12:08:30	0	0.00	17:48:30	0	0.00	11:48:30	0	0.00			
12:08:45	0	0.00	17:48:45	0	0.00	11:48:45	0	0.00			
12:09:00	0	0.00	17:49:00	0	0.00	11:49:00	0	0.00			
12:09:15	0	0.00	17:49:15	0	0.00	11:49:15	0	0.00			
12:09:30	0	0.00	17:49:30	0	0.00	11:49:30	0	0.00			
12:09:45	0	0.00	17:49:45	0	0.00	11:49:45	0	0.00			
12:10:00	0	0.00	17:50:00	0	0.00	11:50:00	0	0.00			
12:10:15	0	0.00	17:50:15	0	0.00	11:50:15	0	0.00			
12:10:30	0	0.00	17:50:30	0	0.00	11:50:30	0	0.00			
12:10:45	0	0.00	17:50:45	0	0.00	11:50:45	0	0.00			
12:11:00	0	0.00	17:51:00	0	0.00	11:51:00	0	0.00			
12:11:15	0	0.00	17:51:15	0	0.00	11:51:15	0	0.00			
12:11:30	0	0.00	17:51:30	0	0.00	11:51:30	0	0.00			
12:11:45	0	0.00	17:51:45	0	0.00	11:51:45	0	0.00			
12:12:00	0	0.00	17:52:00	0	0.00	11:52:00	0	0.00			
12:12:15	0	0.00	17:52:15	0	0.00	11:52:15	0	0.00			
12:12:30	0	0.00	17:52:30	0	0.00	11:52:30	0	0.00			
12:12:45	0	0.00	17:52:45	0	0.00	11:52:45	0	0.00			
12:13:00	0	0.00	17:53:00	0	0.00	11:53:00	0	0.00			
12:13:15	0	0.00	17:53:15	0	0.00	11:53:15	0	0.00			
12:13:30	0	0.00	17:53:30	0	0.00	11:53:30	0	0.00			
12:13:45	0	0.00	17:53:45	0	0.00	11:53:45	0	0.00			
12:14:00	0	0.00	17:54:00	0	0.00	11:54:00	0	0.00			
12:14:15	0	0.00	17:54:15	0	0.00	11:54:15	0	0.00			
12:14:30	0	0.00	17:54:30	0	0.00	11:54:30	0	0.00			
12:14:45	0	0.00	17:54:45	0	0.00	11:54:45	0	0.00			
VE Readings Completed			VE Readings Completed			VE Readings Completed					

TABLE 2-6. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL MELT SHOP

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	Cmin Avg
8:15:00	0		13:55:00	0		7:55:00	0		12:40:00	0	
8:15:15	0		13:55:15	0		7:55:15	0		12:40:15	0	
8:15:30	0		13:55:30	0		7:55:30	0		12:40:30	0	
8:15:45	0		13:55:45	0		7:55:45	0		12:40:45	0	
8:16:00	0		13:56:00	0		7:56:00	0		12:41:00	0	
8:16:15	0		13:56:15	0		7:56:15	0		12:41:15	0	
8:16:30	0		13:56:30	0		7:56:30	0		12:41:30	0	
8:16:45	0		13:56:45	0		7:56:45	0		12:41:45	0	
8:17:00	0		13:57:00	0		7:57:00	0		12:42:00	0	
8:17:15	0		13:57:15	0		7:57:15	0		12:42:15	0	
8:17:30	0		13:57:30	0		7:57:30	0		12:42:30	0	
8:17:45	0		13:57:45	0		7:57:45	0		12:42:45	0	
8:18:00	0		13:58:00	0		7:58:00	0		12:43:00	0	
8:18:15	0		13:58:15	0		7:58:15	0		12:43:15	0	
8:18:30	0		13:58:30	0		7:58:30	0		12:43:30	0	
8:18:45	0		13:58:45	0		7:58:45	0		12:43:45	0	
8:19:00	0		13:59:00	0		7:59:00	0		12:44:00	0	
8:19:15	0		13:59:15	0		7:59:15	0		12:44:15	0	
8:19:30	0		13:59:30	0		7:59:30	0		12:44:30	0	
8:19:45	0		13:59:45	0		7:59:45	0		12:44:45	0	
8:20:00	0		14:00:00	0		8:00:00	0		12:45:00	0	
8:20:15	0		14:00:15	0		8:00:15	0		12:45:15	0	
8:20:30	0		14:00:30	0		8:00:30	0		12:45:30	0	
8:20:45	0	0.00	14:00:45	0	0.00	8:00:45	0	0.00	12:45:45	0	0.00
8:21:00	0	0.00	14:01:00	0	0.00	8:01:00	0	0.00	12:46:00	0	0.00
8:21:15	0	0.00	14:01:15	0	0.00	8:01:15	0	0.00	12:46:15	0	0.00
8:21:30	0	0.00	14:01:30	0	0.00	8:01:30	0	0.00	12:46:30	0	0.00
8:21:45	0	0.00	14:01:45	0	0.00	8:01:45	0	0.00	12:46:45	0	0.00
8:22:00	0	0.00	14:02:00	0	0.00	8:02:00	0	0.00	12:47:00	0	0.00
8:22:15	0	0.00	14:02:15	0	0.00	8:02:15	0	0.00	12:47:15	0	0.00
8:22:30	0	0.00	14:02:30	0	0.00	8:02:30	0	0.00	12:47:30	0	0.00
8:22:45	0	0.00	14:02:45	0	0.00	8:02:45	0	0.00	12:47:45	0	0.00
8:23:00	0	0.00	14:03:00	0	0.00	8:03:00	0	0.00	12:48:00	0	0.00
8:23:15	0	0.00	14:03:15	0	0.00	8:03:15	0	0.00	12:48:15	0	0.00
8:23:30	0	0.00	14:03:30	0	0.00	8:03:30	0	0.00	12:48:30	0	0.00
8:23:45	0	0.00	14:03:45	0	0.00	8:03:45	0	0.00	12:48:45	0	0.00
8:24:00	0	0.00	14:04:00	0	0.00	8:04:00	0	0.00	12:49:00	0	0.00
8:24:15	0	0.00	14:04:15	0	0.00	8:04:15	0	0.00	12:49:15	0	0.00
8:24:30	0	0.00	14:04:30	0	0.00	8:04:30	0	0.00	12:49:30	0	0.00
8:24:45	0	0.00	14:04:45	0	0.00	8:04:45	0	0.00	12:49:45	0	0.00
8:25:00	0	0.00	14:05:00	0	0.00	8:05:00	0	0.00	12:50:00	0	0.00
8:25:15	0	0.00	14:05:15	0	0.00	8:05:15	0	0.00	12:50:15	0	0.00
8:25:30	0	0.00	14:05:30	0	0.00	8:05:30	0	0.00	12:50:30	0	0.00
8:25:45	0	0.00	14:05:45	0	0.00	8:05:45	0	0.00	12:50:45	0	0.00
8:26:00	0	0.00	14:06:00	0	0.00	8:06:00	0	0.00	12:51:00	0	0.00
8:26:15	0	0.00	14:06:15	0	0.00	8:06:15	0	0.00	12:51:15	0	0.00
8:26:30	0	0.00	14:06:30	0	0.00	8:06:30	0	0.00	12:51:30	0	0.00
8:26:45	0	0.00	14:06:45	0	0.00	8:06:45	0	0.00	12:51:45	0	0.00
8:27:00	0	0.00	14:07:00	0	0.00	8:07:00	0	0.00	12:52:00	0	0.00
8:27:15	0	0.00	14:07:15	0	0.00	8:07:15	0	0.00	12:52:15	0	0.00
8:27:30	0	0.00	14:07:30	0	0.00	8:07:30	0	0.00	12:52:30	0	0.00
8:27:45	0	0.00	14:07:45	0	0.00	8:07:45	0	0.00	12:52:45	0	0.00
8:28:00	0	0.00	14:08:00	0	0.00	8:08:00	0	0.00	12:53:00	0	0.00
8:28:15	0	0.00	14:08:15	0	0.00	8:08:15	0	0.00	12:53:15	0	0.00
8:28:30	0	0.00	14:08:30	0	0.00	8:08:30	0	0.00	12:53:30	0	0.00
8:28:45	0	0.00	14:08:45	0	0.00	8:08:45	0	0.00	12:53:45	0	0.00
8:29:00	0	0.00	14:09:00	0	0.00	8:09:00	0	0.00	12:54:00	0	0.00
8:29:15	0	0.00	14:09:15	0	0.00	8:09:15	0	0.00	12:54:15	0	0.00
8:29:30	0	0.00	14:09:30	0	0.00	8:09:30	0	0.00	12:54:30	0	0.00
8:29:45	0	0.00	14:09:45	0	0.00	8:09:45	0	0.00	12:54:45	0	0.00
8:30:00	0		14:10:00	0	0.00	8:10:00	0	0.00	12:55:00	0	0.00
8:30:15	0		14:10:15	0	0.00	8:10:15	0	0.00	12:55:15	0	0.00

TABLE 2-6. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL MELT SHOP

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
8:30:30	0	0.00	14:10:30	0	0.00	8:10:30	0	0.00	12:55:30	0	0.00
8:30:45	0	0.00	14:10:45	0	0.00	8:10:45	0	0.00	12:55:45	0	0.00
8:31:00	0	0.00	14:11:00	0	0.00	8:11:00	0	0.00	12:56:00	0	0.00
8:31:15	0	0.00	14:11:15	0	0.00	8:11:15	0	0.00	12:56:15	0	0.00
8:31:30	0	0.00	14:11:30	0	0.00	8:11:30	0	0.00	12:56:30	0	0.00
8:31:45	0	0.00	14:11:45	0	0.00	8:11:45	0	0.00	12:56:45	0	0.00
8:32:00	0	0.00	14:12:00	0	0.00	8:12:00	0	0.00	12:57:00	0	0.00
8:32:15	0	0.00	14:12:15	0	0.00	8:12:15	0	0.00	12:57:15	0	0.00
8:32:30	0	0.00	14:12:30	0	0.00	8:12:30	0	0.00	12:57:30	0	0.00
8:32:45	0	0.00	14:12:45	0	0.00	8:12:45	0	0.00	12:57:45	0	0.00
8:33:00	0	0.00	14:13:00	0	0.00	8:13:00	0	0.00	12:58:00	0	0.00
8:33:15	0	0.00	14:13:15	0	0.00	8:13:15	0	0.00	12:58:15	0	0.00
8:33:30	0	0.00	14:13:30	0	0.00	8:13:30	0	0.00	12:58:30	0	0.00
8:33:45	0	0.00	14:13:45	0	0.00	8:13:45	0	0.00	12:58:45	0	0.00
8:34:00	0	0.00	14:14:00	0	0.00	8:14:00	0	0.00	12:59:00	0	0.00
8:34:15	0	0.00	14:14:15	0	0.00	8:14:15	0	0.00	12:59:15	0	0.00
8:34:30	0	0.00	14:14:30	0	0.00	8:14:30	0	0.00	12:59:30	0	0.00
8:34:45	0	0.00	14:14:45	0	0.00	8:14:45	0	0.00	12:59:45	0	0.00
8:35:00	0	0.00	14:15:00	0	0.00	8:15:00	0	0.00	13:00:00	0	0.00
8:35:15	0	0.00	14:15:15	0	0.00	8:15:15	0	0.00	13:00:15	0	0.00
8:35:30	0	0.00	14:15:30	0	0.00	8:15:30	0	0.00	13:00:30	0	0.00
8:35:45	0	0.00	14:15:45	0	0.00	8:15:45	0	0.00	13:00:45	0	0.00
8:36:00	0	0.00	14:16:00	0	0.00	8:16:00	0	0.00	13:01:00	0	0.00
8:36:15	0	0.00	14:16:15	0	0.00	8:16:15	0	0.00	13:01:15	0	0.00
8:36:30	0	0.00	14:16:30	0	0.00	8:16:30	0	0.00	13:01:30	0	0.00
8:36:45	0	0.00	14:16:45	0	0.00	8:16:45	0	0.00	13:01:45	0	0.00
8:37:00	0	0.00	14:17:00	0	0.00	8:17:00	0	0.00	13:02:00	0	0.00
8:37:15	0	0.00	14:17:15	0	0.00	8:17:15	0	0.00	13:02:15	0	0.00
8:37:30	0	0.00	14:17:30	0	0.00	8:17:30	0	0.00	13:02:30	0	0.00
8:37:45	0	0.00	14:17:45	0	0.00	8:17:45	0	0.00	13:02:45	0	0.00
8:38:00	0	0.00	14:18:00	0	0.00	8:18:00	0	0.00	13:03:00	0	0.00
8:38:15	0	0.00	14:18:15	0	0.00	8:18:15	0	0.00	13:03:15	0	0.00
8:38:30	0	0.00	14:18:30	0	0.00	8:18:30	0	0.00	13:03:30	0	0.00
8:38:45	0	0.00	14:18:45	0	0.00	8:18:45	0	0.00	13:03:45	0	0.00
8:39:00	0	0.00	14:19:00	0	0.00	8:19:00	0	0.00	13:04:00	0	0.00
8:39:15	0	0.00	14:19:15	0	0.00	8:19:15	0	0.00	13:04:15	0	0.00
8:39:30	0	0.00	14:19:30	0	0.00	8:19:30	0	0.00	13:04:30	0	0.00
8:39:45	0	0.00	14:19:45	0	0.00	8:19:45	0	0.00	13:04:45	0	0.00
8:40:00	0	0.00	14:20:00	0	0.00	8:20:00	0	0.00	13:05:00	0	0.00
8:40:15	0	0.00	14:20:15	0	0.00	8:20:15	0	0.00	13:05:15	0	0.00
8:40:30	0	0.00	14:20:30	0	0.00	8:20:30	0	0.00	13:05:30	0	0.00
8:40:45	0	0.00	14:20:45	0	0.00	8:20:45	0	0.00	13:05:45	0	0.00
8:41:00	0	0.00	14:21:00	0	0.00	8:21:00	0	0.00	13:06:00	0	0.00
8:41:15	0	0.00	14:21:15	0	0.00	8:21:15	0	0.00	13:06:15	0	0.00
8:41:30	0	0.00	14:21:30	0	0.00	8:21:30	0	0.00	13:06:30	0	0.00
8:41:45	0	0.00	14:21:45	0	0.00	8:21:45	0	0.00	13:06:45	0	0.00
8:42:00	0	0.00	14:22:00	0	0.00	8:22:00	0	0.00	13:07:00	0	0.00
8:42:15	0	0.00	14:22:15	0	0.00	8:22:15	0	0.00	13:07:15	0	0.00
8:42:30	0	0.00	14:22:30	0	0.00	8:22:30	0	0.00	13:07:30	0	0.00
8:42:45	0	0.00	14:22:45	0	0.00	8:22:45	0	0.00	13:07:45	0	0.00
8:43:00	0	0.00	14:23:00	0	0.00	8:23:00	0	0.00	13:08:00	0	0.00
8:43:15	0	0.00	14:23:15	0	0.00	8:23:15	0	0.00	13:08:15	0	0.00
8:43:30	0	0.00	14:23:30	0	0.00	8:23:30	0	0.00	13:08:30	0	0.00
8:43:45	0	0.00	14:23:45	0	0.00	8:23:45	0	0.00	13:08:45	0	0.00
8:44:00	0	0.00	14:24:00	0	0.00	8:24:00	0	0.00	13:09:00	0	0.00
8:44:15	0	0.00	14:24:15	0	0.00	8:24:15	0	0.00	13:09:15	0	0.00
8:44:30	0	0.00	14:24:30	0	0.00	8:24:30	0	0.00	13:09:30	0	0.00
8:44:45	0	0.00	14:24:45	0	0.00	8:24:45	0	0.00	13:09:45	0	0.00
8:45:00	0	0.00	14:25:00	0	0.00	8:25:00	0	0.00	13:10:00	0	0.00
8:45:15	0	0.00	14:25:15	0	0.00	8:25:15	0	0.00	13:10:15	0	0.00
8:45:30	0	0.00	14:25:30	0	0.00	8:25:30	0	0.00	13:10:30	0	0.00
8:45:45	0	0.00		0	0.00	8:25:45	0	0.00	13:10:45	0	0.00

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6Cmin Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
10:50:00	0	0.00	16:30:00	0	0.00	10:30:00	0	0.00			
10:50:15	0	0.00	16:30:15	0	0.00	10:30:15	0	0.00			
10:50:30	0	0.00	16:30:30	0	0.00	10:30:30	0	0.00			
10:50:45	0	0.00	16:30:45	0	0.00	10:30:45	0	0.00			
10:51:00	0	0.00	16:31:00	0	0.00	10:31:00	0	0.00			
10:51:15	0	0.00	16:31:15	0	0.00	10:31:15	0	0.00			
10:51:30	0	0.00	16:31:30	0	0.00	10:31:30	0	0.00			
10:51:45	0	0.00	16:31:45	0	0.00	10:31:45	0	0.00			
10:52:00	0	0.00	16:32:00	0	0.00	10:32:00	0	0.00			
10:52:15	0	0.00	16:32:15	0	0.00	10:32:15	0	0.00			
10:52:30	0	0.00	16:32:30	0	0.00	10:32:30	0	0.00			
10:52:45	0	0.00	16:32:45	0	0.00	10:32:45	0	0.00			
10:53:00	0	0.00	16:33:00	0	0.00	10:33:00	0	0.00			
10:53:15	0	0.00	16:33:15	0	0.00	10:33:15	0	0.00			
10:53:30	0	0.00	16:33:30	0	0.00	10:33:30	0	0.00			
10:53:45	0	0.00	16:33:45	0	0.00	10:33:45	0	0.00			
10:54:00	0	0.00	16:34:00	0	0.00	10:34:00	0	0.00			
10:54:15	0	0.00	16:34:15	0	0.00	10:34:15	0	0.00			
10:54:30	0	0.00	16:34:30	0	0.00	10:34:30	0	0.00			
10:54:45	0	0.00	16:34:45	0	0.00	10:34:45	0	0.00			
10:55:00	0	0.00	16:35:00	0	0.00	10:35:00	0	0.00			
10:55:15	0	0.00	16:35:15	0	0.00	10:35:15	0	0.00			
10:55:30	0	0.00	16:35:30	0	0.00	10:35:30	0	0.00			
10:55:45	0	0.00	16:35:45	0	0.00	10:35:45	0	0.00			
10:56:00	0	0.00	16:36:00	0	0.00	10:36:00	0	0.00			
10:56:15	0	0.00	16:36:15	0	0.00	10:36:15	0	0.00			
10:56:30	0	0.00	16:36:30	0	0.00	10:36:30	0	0.00			
10:56:45	0	0.00	16:36:45	0	0.00	10:36:45	0	0.00			
10:57:00	0	0.00	16:37:00	0	0.00	10:37:00	0	0.00			
10:57:15	0	0.00	16:37:15	0	0.00	10:37:15	0	0.00			
10:57:30	0	0.00	16:37:30	0	0.00	10:37:30	0	0.00			
10:57:45	0	0.00	16:37:45	0	0.00	10:37:45	0	0.00			
10:58:00	0	0.00	16:38:00	0	0.00	10:38:00	0	0.00			
10:58:15	0	0.00	16:38:15	0	0.00	10:38:15	0	0.00			
10:58:30	0	0.00	16:38:30	0	0.00	10:38:30	0	0.00			
10:58:45	0	0.00	16:38:45	0	0.00	10:38:45	0	0.00			
10:59:00	0	0.00	16:39:00	0	0.00	10:39:00	0	0.00			
10:59:15	0	0.00	16:39:15	0	0.00	10:39:15	0	0.00			
10:59:30	0	0.00	16:39:30	0	0.00	10:39:30	0	0.00			
10:59:45	0	0.00	16:39:45	0	0.00	10:39:45	0	0.00			
11:00:00	0	0.00	16:40:00	0	0.00	10:40:00	0	0.00			
11:00:15	0	0.00	16:40:15	0	0.00	10:40:15	0	0.00			
11:00:30	0	0.00	16:40:30	0	0.00	10:40:30	0	0.00			
11:00:45	0	0.00	16:40:45	0	0.00	10:40:45	0	0.00			
11:01:00	0	0.00	16:41:00	0	0.00	10:41:00	0	0.00			
11:01:15	0	0.00	16:41:15	0	0.00	10:41:15	0	0.00			
11:01:30	0	0.00	16:41:30	0	0.00	10:41:30	0	0.00			
11:01:45	0	0.00	16:41:45	0	0.00	10:41:45	0	0.00			
11:02:00	0	0.00	16:42:00	0	0.00	10:42:00	0	0.00			
11:02:15	0	0.00	16:42:15	0	0.00	10:42:15	0	0.00			
11:02:30	0	0.00	16:42:30	0	0.00	10:42:30	0	0.00			
11:02:45	0	0.00	16:42:45	0	0.00	10:42:45	0	0.00			
11:03:00	0	0.00	16:43:00	0	0.00	10:43:00	0	0.00			
11:03:15	0	0.00	16:43:15	0	0.00	10:43:15	0	0.00			
11:03:30	0	0.00	16:43:30	0	0.00	10:43:30	0	0.00			
11:03:45	0	0.00	16:43:45	0	0.00	10:43:45	0	0.00			
11:04:00	0	0.00	16:44:00	0	0.00	10:44:00	0	0.00			
11:04:15	0	0.00	16:44:15	0	0.00	10:44:15	0	0.00			
11:04:30	0	0.00	16:44:30	0	0.00	10:44:30	0	0.00			
11:04:45	0	0.00	16:44:45	0	0.00	10:44:45	0	0.00			
11:05:00	0	0.00	16:45:00	0	0.00	10:45:00	0	0.00			
11:05:15	0	0.00	16:45:15	0	0.00	10:45:15	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
11:05:30	0	0.00	16:45:30	0	0.00	10:45:30	0	0.00			
11:05:45	0	0.00	16:45:45	0	0.00	10:45:45	0	0.00			
11:06:00	0	0.00	16:46:00	0	0.00	10:46:00	0	0.00			
11:06:15	0	0.00	16:46:15	0	0.00	10:46:15	0	0.00			
11:06:30	0	0.00	16:46:30	0	0.00	10:46:30	0	0.00			
11:06:45	0	0.00	16:46:45	0	0.00	10:46:45	0	0.00			
11:07:00	0	0.00	16:47:00	0	0.00	10:47:00	0	0.00			
11:07:15	0	0.00	16:47:15	0	0.00	10:47:15	0	0.00			
11:07:30	0	0.00	16:47:30	0	0.00	10:47:30	0	0.00			
11:07:45	0	0.00	16:47:45	0	0.00	10:47:45	0	0.00			
11:08:00	0	0.00	16:48:00	0	0.00	10:48:00	0	0.00			
11:08:15	0	0.00	16:48:15	0	0.00	10:48:15	0	0.00			
11:08:30	0	0.00	16:48:30	0	0.00	10:48:30	0	0.00			
11:08:45	0	0.00	16:48:45	0	0.00	10:48:45	0	0.00			
11:09:00	0	0.00	16:49:00	0	0.00	10:49:00	0	0.00			
11:09:15	0	0.00	16:49:15	0	0.00	10:49:15	0	0.00			
11:09:30	0	0.00	16:49:30	0	0.00	10:49:30	0	0.00			
11:09:45	0	0.00	16:49:45	0	0.00	10:49:45	0	0.00			
11:10:00	0	0.00	16:50:00	0	0.00	10:50:00	0	0.00			
11:10:15	0	0.00	16:50:15	0	0.00	10:50:15	0	0.00			
11:10:30	0	0.00	16:50:30	0	0.00	10:50:30	0	0.00			
11:10:45	0	0.00	16:50:45	0	0.00	10:50:45	0	0.00			
11:11:00	0	0.00	16:51:00	0	0.00	10:51:00	0	0.00			
11:11:15	0	0.00	16:51:15	0	0.00	10:51:15	0	0.00			
11:11:30	0	0.00	16:51:30	0	0.00	10:51:30	0	0.00			
11:11:45	0	0.00	16:51:45	0	0.00	10:51:45	0	0.00			
11:12:00	0	0.00	16:52:00	0	0.00	10:52:00	0	0.00			
11:12:15	0	0.00	16:52:15	0	0.00	10:52:15	0	0.00			
11:12:30	0	0.00	16:52:30	0	0.00	10:52:30	0	0.00			
11:12:45	0	0.00	16:52:45	0	0.00	10:52:45	0	0.00			
11:13:00	0	0.00	16:53:00	0	0.00	10:53:00	0	0.00			
11:13:15	0	0.00	16:53:15	0	0.00	10:53:15	0	0.00			
11:13:30	0	0.00	16:53:30	0	0.00	10:53:30	0	0.00			
11:13:45	0	0.00	16:53:45	0	0.00	10:53:45	0	0.00			
11:14:00	0	0.00	16:54:00	0	0.00	10:54:00	0	0.00			
11:14:15	0	0.00	16:54:15	0	0.00	10:54:15	0	0.00			
11:14:30	0	0.00	16:54:30	0	0.00	10:54:30	0	0.00			
11:14:45	0	0.00	16:54:45	0	0.00	10:54:45	0	0.00			
11:15:00	0	0.00	16:55:00	0	0.00	10:55:00	0	0.00			
11:15:15	0	0.00	16:55:15	0	0.00	10:55:15	0	0.00			
11:15:30	0	0.00	16:55:30	0	0.00	10:55:30	0	0.00			
11:15:45	0	0.00	16:55:45	0	0.00	10:55:45	0	0.00			
11:16:00	0	0.00	16:56:00	0	0.00	10:56:00	0	0.00			
11:16:15	0	0.00	16:56:15	0	0.00	10:56:15	0	0.00			
11:16:30	0	0.00	16:56:30	0	0.00	10:56:30	0	0.00			
11:16:45	0	0.00	16:56:45	0	0.00	10:56:45	0	0.00			
11:17:00	0	0.00	16:57:00	0	0.00	10:57:00	0	0.00			
11:17:15	0	0.00	16:57:15	0	0.00	10:57:15	0	0.00			
11:17:30	0	0.00	16:57:30	0	0.00	10:57:30	0	0.00			
11:17:45	0	0.00	16:57:45	0	0.00	10:57:45	0	0.00			
11:18:00	0	0.00	16:58:00	0	0.00	10:58:00	0	0.00			
11:18:15	0	0.00	16:58:15	0	0.00	10:58:15	0	0.00			
11:18:30	0	0.00	16:58:30	0	0.00	10:58:30	0	0.00			
11:18:45	0	0.00	16:58:45	0	0.00	10:58:45	0	0.00			
11:19:00	0	0.00	16:59:00	0	0.00	10:59:00	0	0.00			
11:19:15	0	0.00	16:59:15	0	0.00	10:59:15	0	0.00			
11:19:30	0	0.00	16:59:30	0	0.00	10:59:30	0	0.00			
11:19:45	0	0.00	16:59:45	0	0.00	10:59:45	0	0.00			
11:20:00	0	0.00	17:00:00	0	0.00	11:00:00	0	0.00			
11:20:15	0	0.00	17:00:15	0	0.00	11:00:15	0	0.00			
11:20:30	0	0.00	17:00:30	0	0.00	11:00:30	0	0.00			
11:20:45	0	0.00	17:00:45	0	0.00	11:00:45	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
11:21:00	0	0.00	17:01:00	0	0.00	11:01:00	0	0.00			
11:21:15	0	0.00	17:01:15	0	0.00	11:01:15	0	0.00			
11:21:30	0	0.00	17:01:30	0	0.00	11:01:30	0	0.00			
11:21:45	0	0.00	17:01:45	0	0.00	11:01:45	0	0.00			
11:22:00	0	0.00	17:02:00	0	0.00	11:02:00	0	0.00			
11:22:15	0	0.00	17:02:15	0	0.00	11:02:15	0	0.00			
11:22:30	0	0.00	17:02:30	0	0.00	11:02:30	0	0.00			
11:22:45	0	0.00	17:02:45	0	0.00	11:02:45	0	0.00			
11:23:00	0	0.00	17:03:00	0	0.00	11:03:00	0	0.00			
11:23:15	0	0.00	17:03:15	0	0.00	11:03:15	0	0.00			
11:23:30	0	0.00	17:03:30	0	0.00	11:03:30	0	0.00			
11:23:45	0	0.00	17:03:45	0	0.00	11:03:45	0	0.00			
11:24:00	0	0.00	17:04:00	0	0.00	11:04:00	0	0.00			
11:24:15	0	0.00	17:04:15	0	0.00	11:04:15	0	0.00			
11:24:30	0	0.00	17:04:30	0	0.00	11:04:30	0	0.00			
11:24:45	0	0.00	17:04:45	0	0.00	11:04:45	0	0.00			
11:25:00	0	0.00	17:05:00	0	0.00	11:05:00	0	0.00			
11:25:15	0	0.00	17:05:15	0	0.00	11:05:15	0	0.00			
11:25:30	0	0.00	17:05:30	0	0.00	11:05:30	0	0.00			
11:25:45	0	0.00	17:05:45	0	0.00	11:05:45	0	0.00			
11:26:00	0	0.00	17:06:00	0	0.00	11:06:00	0	0.00			
11:26:15	0	0.00	17:06:15	0	0.00	11:06:15	0	0.00			
11:26:30	0	0.00	17:06:30	0	0.00	11:06:30	0	0.00			
11:26:45	0	0.00	17:06:45	0	0.00	11:06:45	0	0.00			
11:27:00	0	0.00	17:07:00	0	0.00	11:07:00	0	0.00			
11:27:15	0	0.00	17:07:15	0	0.00	11:07:15	0	0.00			
11:27:30	0	0.00	17:07:30	0	0.00	11:07:30	0	0.00			
11:27:45	0	0.00	17:07:45	0	0.00	11:07:45	0	0.00			
11:28:00	0	0.00	17:08:00	0	0.00	11:08:00	0	0.00			
11:28:15	0	0.00	17:08:15	0	0.00	11:08:15	0	0.00			
11:28:30	0	0.00	17:08:30	0	0.00	11:08:30	0	0.00			
11:28:45	0	0.00	17:08:45	0	0.00	11:08:45	0	0.00			
11:29:00	0	0.00	17:09:00	0	0.00	11:09:00	0	0.00			
11:29:15	0	0.00	17:09:15	0	0.00	11:09:15	0	0.00			
11:29:30	0	0.00	17:09:30	0	0.00	11:09:30	0	0.00			
11:29:45	0	0.00	17:09:45	0	0.00	11:09:45	0	0.00			
11:30:00	0	0.00	17:10:00	0	0.00	11:10:00	0	0.00			
11:30:15	0	0.00	17:10:15	0	0.00	11:10:15	0	0.00			
11:30:30	0	0.00	17:10:30	0	0.00	11:10:30	0	0.00			
11:30:45	0	0.00	17:10:45	0	0.00	11:10:45	0	0.00			
11:31:00	0	0.00	17:11:00	0	0.00	11:11:00	0	0.00			
11:31:15	0	0.00	17:11:15	0	0.00	11:11:15	0	0.00			
11:31:30	0	0.00	17:11:30	0	0.00	11:11:30	0	0.00			
11:31:45	0	0.00	17:11:45	0	0.00	11:11:45	0	0.00			
11:32:00	0	0.00	17:12:00	0	0.00	11:12:00	0	0.00			
11:32:15	0	0.00	17:12:15	0	0.00	11:12:15	0	0.00			
11:32:30	0	0.00	17:12:30	0	0.00	11:12:30	0	0.00			
11:32:45	0	0.00	17:12:45	0	0.00	11:12:45	0	0.00			
11:33:00	0	0.00	17:13:00	0	0.00	11:13:00	0	0.00			
11:33:15	0	0.00	17:13:15	0	0.00	11:13:15	0	0.00			
11:33:30	0	0.00	17:13:30	0	0.00	11:13:30	0	0.00			
11:33:45	0	0.00	17:13:45	0	0.00	11:13:45	0	0.00			
11:34:00	0	0.00	17:14:00	0	0.00	11:14:00	0	0.00			
11:34:15	0	0.00	17:14:15	0	0.00	11:14:15	0	0.00			
11:34:30	0	0.00	17:14:30	0	0.00	11:14:30	0	0.00			
11:34:45	0	0.00	17:14:45	0	0.00	11:14:45	0	0.00			
11:35:00	0	0.00	17:15:00	0	0.00	11:15:00	0	0.00			
11:35:15	0	0.00	17:15:15	0	0.00	11:15:15	0	0.00			
11:35:30	0	0.00	17:15:30	0	0.00	11:15:30	0	0.00			
11:35:45	0	0.00	17:15:45	0	0.00	11:15:45	0	0.00			
11:36:00	0	0.00	17:16:00	0	0.00	11:16:00	0	0.00			
11:36:15	0	0.00	17:16:15	0	0.00	11:16:15	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
11:36:30	0	0.00	17:16:30	0	0.00	11:16:30	0	0.00			
11:36:45	0	0.00	17:16:45	0	0.00	11:16:45	0	0.00			
11:37:00	0	0.00	17:17:00	0	0.00	11:17:00	0	0.00			
11:37:15	0	0.00	17:17:15	0	0.00	11:17:15	0	0.00			
11:37:30	0	0.00	17:17:30	0	0.00	11:17:30	0	0.00			
11:37:45	0	0.00	17:17:45	0	0.00	11:17:45	0	0.00			
11:38:00	0	0.00	17:18:00	0	0.00	11:18:00	0	0.00			
11:38:15	0	0.00	17:18:15	0	0.00	11:18:15	0	0.00			
11:38:30	0	0.00	17:18:30	0	0.00	11:18:30	0	0.00			
11:38:45	0	0.00	17:18:45	0	0.00	11:18:45	0	0.00			
11:39:00	0	0.00	17:19:00	0	0.00	11:19:00	0	0.00			
11:39:15	0	0.00	17:19:15	0	0.00	11:19:15	0	0.00			
11:39:30	0	0.00	17:19:30	0	0.00	11:19:30	0	0.00			
11:39:45	0	0.00	17:19:45	0	0.00	11:19:45	0	0.00			
11:40:00	0	0.00	17:20:00	0	0.00	11:20:00	0	0.00			
11:40:15	0	0.00	17:20:15	0	0.00	11:20:15	0	0.00			
11:40:30	0	0.00	17:20:30	0	0.00	11:20:30	0	0.00			
11:40:45	0	0.00	17:20:45	0	0.00	11:20:45	0	0.00			
11:41:00	0	0.00	17:21:00	0	0.00	11:21:00	0	0.00			
11:41:15	0	0.00	17:21:15	0	0.00	11:21:15	0	0.00			
11:41:30	0	0.00	17:21:30	0	0.00	11:21:30	0	0.00			
11:41:45	0	0.00	17:21:45	0	0.00	11:21:45	0	0.00			
11:42:00	0	0.00	17:22:00	0	0.00	11:22:00	0	0.00			
11:42:15	0	0.00	17:22:15	0	0.00	11:22:15	0	0.00			
11:42:30	0	0.00	17:22:30	0	0.00	11:22:30	0	0.00			
11:42:45	0	0.00	17:22:45	0	0.00	11:22:45	0	0.00			
11:43:00	0	0.00	17:23:00	0	0.00	11:23:00	0	0.00			
11:43:15	0	0.00	17:23:15	0	0.00	11:23:15	0	0.00			
11:43:30	0	0.00	17:23:30	0	0.00	11:23:30	0	0.00			
11:43:45	0	0.00	17:23:45	0	0.00	11:23:45	0	0.00			
11:44:00	0	0.00	17:24:00	0	0.00	11:24:00	0	0.00			
11:44:15	0	0.00	17:24:15	0	0.00	11:24:15	0	0.00			
11:44:30	0	0.00	17:24:30	0	0.00	11:24:30	0	0.00			
11:44:45	0	0.00	17:24:45	0	0.00	11:24:45	0	0.00			
11:45:00	0	0.00	17:25:00	0	0.00	11:25:00	0	0.00			
11:45:15	0	0.00	17:25:15	0	0.00	11:25:15	0	0.00			
11:45:30	0	0.00	17:25:30	0	0.00	11:25:30	0	0.00			
11:45:45	0	0.00	17:25:45	0	0.00	11:25:45	0	0.00			
11:46:00	0	0.00	17:26:00	0	0.00	11:26:00	0	0.00			
11:46:15	0	0.00	17:26:15	0	0.00	11:26:15	0	0.00			
11:46:30	0	0.00	17:26:30	0	0.00	11:26:30	0	0.00			
11:46:45	0	0.00	17:26:45	0	0.00	11:26:45	0	0.00			
11:47:00	0	0.00	17:27:00	0	0.00	11:27:00	0	0.00			
11:47:15	0	0.00	17:27:15	0	0.00	11:27:15	0	0.00			
11:47:30	0	0.00	17:27:30	0	0.00	11:27:30	0	0.00			
11:47:45	0	0.00	17:27:45	0	0.00	11:27:45	0	0.00			
11:48:00	0	0.00	17:28:00	0	0.00	11:28:00	0	0.00			
11:48:15	0	0.00	17:28:15	0	0.00	11:28:15	0	0.00			
11:48:30	0	0.00	17:28:30	0	0.00	11:28:30	0	0.00			
11:48:45	0	0.00	17:28:45	0	0.00	11:28:45	0	0.00			
11:49:00	0	0.00	17:29:00	0	0.00	11:29:00	0	0.00			
11:49:15	0	0.00	17:29:15	0	0.00	11:29:15	0	0.00			
11:49:30	0	0.00	17:29:30	0	0.00	11:29:30	0	0.00			
11:49:45	0	0.00	17:29:45	0	0.00	11:29:45	0	0.00			
11:50:00	0	0.00	17:30:00	0	0.00	11:30:00	0	0.00			
11:50:15	0	0.00	17:30:15	0	0.00	11:30:15	0	0.00			
11:50:30	0	0.00	17:30:30	0	0.00	11:30:30	0	0.00			
11:50:45	0	0.00	17:30:45	0	0.00	11:30:45	0	0.00			
11:51:00	0	0.00	17:31:00	0	0.00	11:31:00	0	0.00			
11:51:15	0	0.00	17:31:15	0	0.00	11:31:15	0	0.00			
11:51:30	0	0.00	17:31:30	0	0.00	11:31:30	0	0.00			
11:51:45	0	0.00	17:31:45	0	0.00	11:31:45	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
11:52:00	0	0.00	17:32:00	0	0.00	11:32:00	0	0.00			
11:52:15	0	0.00	17:32:15	0	0.00	11:32:15	0	0.00			
11:52:30	0	0.00	17:32:30	0	0.00	11:32:30	0	0.00			
11:52:45	0	0.00	17:32:45	0	0.00	11:32:45	0	0.00			
11:53:00	0	0.00	17:33:00	0	0.00	11:33:00	0	0.00			
11:53:15	0	0.00	17:33:15	0	0.00	11:33:15	0	0.00			
11:53:30	0	0.00	17:33:30	0	0.00	11:33:30	0	0.00			
11:53:45	0	0.00	17:33:45	0	0.00	11:33:45	0	0.00			
11:54:00	0	0.00	17:34:00	0	0.00	11:34:00	0	0.00			
11:54:15	0	0.00	17:34:15	0	0.00	11:34:15	0	0.00			
11:54:30	0	0.00	17:34:30	0	0.00	11:34:30	0	0.00			
11:54:45	0	0.00	17:34:45	0	0.00	11:34:45	0	0.00			
11:55:00	0	0.00	17:35:00	0	0.00	11:35:00	0	0.00			
11:55:15	0	0.00	17:35:15	0	0.00	11:35:15	0	0.00			
11:55:30	0	0.00	17:35:30	0	0.00	11:35:30	0	0.00			
11:55:45	0	0.00	17:35:45	0	0.00	11:35:45	0	0.00			
11:56:00	0	0.00	17:36:00	0	0.00	11:36:00	0	0.00			
11:56:15	0	0.00	17:36:15	0	0.00	11:36:15	0	0.00			
11:56:30	0	0.00	17:36:30	0	0.00	11:36:30	0	0.00			
11:56:45	0	0.00	17:36:45	0	0.00	11:36:45	0	0.00			
11:57:00	0	0.00	17:37:00	0	0.00	11:37:00	0	0.00			
11:57:15	0	0.00	17:37:15	0	0.00	11:37:15	0	0.00			
11:57:30	0	0.00	17:37:30	0	0.00	11:37:30	0	0.00			
11:57:45	0	0.00	17:37:45	0	0.00	11:37:45	0	0.00			
11:58:00	0	0.00	17:38:00	0	0.00	11:38:00	0	0.00			
11:58:15	0	0.00	17:38:15	0	0.00	11:38:15	0	0.00			
11:58:30	0	0.00	17:38:30	0	0.00	11:38:30	0	0.00			
11:58:45	0	0.00	17:38:45	0	0.00	11:38:45	0	0.00			
11:59:00	0	0.00	17:39:00	0	0.00	11:39:00	0	0.00			
11:59:15	0	0.00	17:39:15	0	0.00	11:39:15	0	0.00			
11:59:30	0	0.00	17:39:30	0	0.00	11:39:30	0	0.00			
11:59:45	0	0.00	17:39:45	0	0.00	11:39:45	0	0.00			
12:00:00	0	0.00	17:40:00	0	0.00	11:40:00	0	0.00			
12:00:15	0	0.00	17:40:15	0	0.00	11:40:15	0	0.00			
12:00:30	0	0.00	17:40:30	0	0.00	11:40:30	0	0.00			
12:00:45	0	0.00	17:40:45	0	0.00	11:40:45	0	0.00			
12:01:00	0	0.00	17:41:00	0	0.00	11:41:00	0	0.00			
12:01:15	0	0.00	17:41:15	0	0.00	11:41:15	0	0.00			
12:01:30	0	0.00	17:41:30	0	0.00	11:41:30	0	0.00			
12:01:45	0	0.00	17:41:45	0	0.00	11:41:45	0	0.00			
12:02:00	0	0.00	17:42:00	0	0.00	11:42:00	0	0.00			
12:02:15	0	0.00	17:42:15	0	0.00	11:42:15	0	0.00			
12:02:30	0	0.00	17:42:30	0	0.00	11:42:30	0	0.00			
12:02:45	0	0.00	17:42:45	0	0.00	11:42:45	0	0.00			
12:03:00	0	0.00	17:43:00	0	0.00	11:43:00	0	0.00			
12:03:15	0	0.00	17:43:15	0	0.00	11:43:15	0	0.00			
12:03:30	0	0.00	17:43:30	0	0.00	11:43:30	0	0.00			
12:03:45	0	0.00	17:43:45	0	0.00	11:43:45	0	0.00			
12:04:00	0	0.00	17:44:00	0	0.00	11:44:00	0	0.00			
12:04:15	0	0.00	17:44:15	0	0.00	11:44:15	0	0.00			
12:04:30	0	0.00	17:44:30	0	0.00	11:44:30	0	0.00			
12:04:45	0	0.00	17:44:45	0	0.00	11:44:45	0	0.00			
12:05:00	0	0.00	17:45:00	0	0.00	11:45:00	0	0.00			
12:05:15	0	0.00	17:45:15	0	0.00	11:45:15	0	0.00			
12:05:30	0	0.00	17:45:30	0	0.00	11:45:30	0	0.00			
12:05:45	0	0.00	17:45:45	0	0.00	11:45:45	0	0.00			
12:06:00	0	0.00	17:46:00	0	0.00	11:46:00	0	0.00			
12:06:15	0	0.00	17:46:15	0	0.00	11:46:15	0	0.00			
12:06:30	0	0.00	17:46:30	0	0.00	11:46:30	0	0.00			
12:06:45	0	0.00	17:46:45	0	0.00	11:46:45	0	0.00			
12:07:00	0	0.00	17:47:00	0	0.00	11:47:00	0	0.00			
12:07:15	0	0.00	17:47:15	0	0.00	11:47:15	0	0.00			

TABLE 2-5. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL BRANDT BAGHOUSE

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
12:07:30	0	0.00	17:47:30	0	0.00	11:47:30	0	0.00			
12:07:45	0	0.00	17:47:45	0	0.00	11:47:45	0	0.00			
12:08:00	0	0.00	17:48:00	0	0.00	11:48:00	0	0.00			
12:08:15	0	0.00	17:48:15	0	0.00	11:48:15	0	0.00			
12:08:30	0	0.00	17:48:30	0	0.00	11:48:30	0	0.00			
12:08:45	0	0.00	17:48:45	0	0.00	11:48:45	0	0.00			
12:09:00	0	0.00	17:49:00	0	0.00	11:49:00	0	0.00			
12:09:15	0	0.00	17:49:15	0	0.00	11:49:15	0	0.00			
12:09:30	0	0.00	17:49:30	0	0.00	11:49:30	0	0.00			
12:09:45	0	0.00	17:49:45	0	0.00	11:49:45	0	0.00			
12:10:00	0	0.00	17:50:00	0	0.00	11:50:00	0	0.00			
12:10:15	0	0.00	17:50:15	0	0.00	11:50:15	0	0.00			
12:10:30	0	0.00	17:50:30	0	0.00	11:50:30	0	0.00			
12:10:45	0	0.00	17:50:45	0	0.00	11:50:45	0	0.00			
12:11:00	0	0.00	17:51:00	0	0.00	11:51:00	0	0.00			
12:11:15	0	0.00	17:51:15	0	0.00	11:51:15	0	0.00			
12:11:30	0	0.00	17:51:30	0	0.00	11:51:30	0	0.00			
12:11:45	0	0.00	17:51:45	0	0.00	11:51:45	0	0.00			
12:12:00	0	0.00	17:52:00	0	0.00	11:52:00	0	0.00			
12:12:15	0	0.00	17:52:15	0	0.00	11:52:15	0	0.00			
12:12:30	0	0.00	17:52:30	0	0.00	11:52:30	0	0.00			
12:12:45	0	0.00	17:52:45	0	0.00	11:52:45	0	0.00			
12:13:00	0	0.00	17:53:00	0	0.00	11:53:00	0	0.00			
12:13:15	0	0.00	17:53:15	0	0.00	11:53:15	0	0.00			
12:13:30	0	0.00	17:53:30	0	0.00	11:53:30	0	0.00			
12:13:45	0	0.00	17:53:45	0	0.00	11:53:45	0	0.00			
12:14:00	0	0.00	17:54:00	0	0.00	11:54:00	0	0.00			
12:14:15	0	0.00	17:54:15	0	0.00	11:54:15	0	0.00			
12:14:30	0	0.00	17:54:30	0	0.00	11:54:30	0	0.00			
12:14:45	0	0.00	17:54:45	0	0.00	11:54:45	0	0.00			
VE Readings Completed			VE Readings Completed			VE Readings Completed					

TABLE 2-6. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL MELT SHOP

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
8:15:00	0		13:55:00	0		7:55:00	0		12:40:15	0	
8:15:15	0		13:55:15	0		7:55:15	0		12:40:30	0	
8:15:30	0		13:55:30	0		7:55:30	0		12:40:45	0	
8:15:45	0		13:55:45	0		7:55:45	0		12:41:00	0	
8:16:00	0		13:56:00	0		7:56:00	0		12:41:15	0	
8:16:15	0		13:56:15	0		7:56:15	0		12:41:30	0	
8:16:30	0		13:56:30	0		7:56:30	0		12:41:45	0	
8:16:45	0		13:56:45	0		7:56:45	0		12:42:00	0	
8:17:00	0		13:57:00	0		7:57:00	0		12:42:15	0	
8:17:15	0		13:57:15	0		7:57:15	0		12:42:30	0	
8:17:30	0		13:57:30	0		7:57:30	0		12:42:45	0	
8:17:45	0		13:57:45	0		7:57:45	0		12:43:00	0	
8:18:00	0		13:58:00	0		7:58:00	0		12:43:15	0	
8:18:15	0		13:58:15	0		7:58:15	0		12:43:30	0	
8:18:30	0		13:58:30	0		7:58:30	0		12:43:45	0	
8:18:45	0		13:58:45	0		7:58:45	0		12:44:00	0	
8:19:00	0		13:59:00	0		7:59:00	0		12:44:15	0	
8:19:15	0		13:59:15	0		7:59:15	0		12:44:30	0	
8:19:30	0		13:59:30	0		7:59:30	0		12:44:45	0	
8:19:45	0		13:59:45	0		7:59:45	0		12:45:00	0	
8:20:00	0		14:00:00	0		8:00:00	0		12:45:15	0	
8:20:15	0		14:00:15	0		8:00:15	0		12:45:30	0	
8:20:30	0		14:00:30	0		8:00:30	0		12:45:45	0	0.00
8:20:45	0	0.00	14:00:45	0	0.00	8:00:45	0	0.00	12:46:00	0	0.00
8:21:00	0	0.00	14:01:00	0	0.00	8:01:00	0	0.00	12:46:15	0	0.00
8:21:15	0	0.00	14:01:15	0	0.00	8:01:15	0	0.00	12:46:30	0	0.00
8:21:30	0	0.00	14:01:30	0	0.00	8:01:30	0	0.00	12:46:45	0	0.00
8:21:45	0	0.00	14:01:45	0	0.00	8:01:45	0	0.00	12:47:00	0	0.00
8:22:00	0	0.00	14:02:00	0	0.00	8:02:00	0	0.00	12:47:15	0	0.00
8:22:15	0	0.00	14:02:15	0	0.00	8:02:15	0	0.00	12:47:30	0	0.00
8:22:30	0	0.00	14:02:30	0	0.00	8:02:30	0	0.00	12:47:45	0	0.00
8:22:45	0	0.00	14:02:45	0	0.00	8:02:45	0	0.00	12:48:00	0	0.00
8:23:00	0	0.00	14:03:00	0	0.00	8:03:00	0	0.00	12:48:15	0	0.00
8:23:15	0	0.00	14:03:15	0	0.00	8:03:15	0	0.00	12:48:30	0	0.00
8:23:30	0	0.00	14:03:30	0	0.00	8:03:30	0	0.00	12:48:45	0	0.00
8:23:45	0	0.00	14:03:45	0	0.00	8:03:45	0	0.00	12:49:00	0	0.00
8:24:00	0	0.00	14:04:00	0	0.00	8:04:00	0	0.00	12:49:15	0	0.00
8:24:15	0	0.00	14:04:15	0	0.00	8:04:15	0	0.00	12:49:30	0	0.00
8:24:30	0	0.00	14:04:30	0	0.00	8:04:30	0	0.00	12:49:45	0	0.00
8:24:45	0	0.00	14:04:45	0	0.00	8:04:45	0	0.00	12:50:00	0	0.00
8:25:00	0	0.00	14:05:00	0	0.00	8:05:00	0	0.00	12:50:15	0	0.00
8:25:15	0	0.00	14:05:15	0	0.00	8:05:15	0	0.00	12:50:30	0	0.00
8:25:30	0	0.00	14:05:30	0	0.00	8:05:30	0	0.00	12:50:45	0	0.00
8:25:45	0	0.00	14:05:45	0	0.00	8:05:45	0	0.00	12:51:00	0	0.00
8:26:00	0	0.00	14:06:00	0	0.00	8:06:00	0	0.00	12:51:15	0	0.00
8:26:15	0	0.00	14:06:15	0	0.00	8:06:15	0	0.00	12:51:30	0	0.00
8:26:30	0	0.00	14:06:30	0	0.00	8:06:30	0	0.00	12:51:45	0	0.00
8:26:45	0	0.00	14:06:45	0	0.00	8:06:45	0	0.00	12:52:00	0	0.00
8:27:00	0	0.00	14:07:00	0	0.00	8:07:00	0	0.00	12:52:15	0	0.00
8:27:15	0	0.00	14:07:15	0	0.00	8:07:15	0	0.00	12:52:30	0	0.00
8:27:30	0	0.00	14:07:30	0	0.00	8:07:30	0	0.00	12:52:45	0	0.00
8:27:45	0	0.00	14:07:45	0	0.00	8:07:45	0	0.00	12:53:00	0	0.00
8:28:00	0	0.00	14:08:00	0	0.00	8:08:00	0	0.00	12:53:15	0	0.00
8:28:15	0	0.00	14:08:15	0	0.00	8:08:15	0	0.00	12:53:30	0	0.00
8:28:30	0	0.00	14:08:30	0	0.00	8:08:30	0	0.00	12:53:45	0	0.00
8:28:45	0	0.00	14:08:45	0	0.00	8:08:45	0	0.00	12:54:00	0	0.00
8:29:00	0	0.00	14:09:00	0	0.00	8:09:00	0	0.00	12:54:15	0	0.00
8:29:15	0	0.00	14:09:15	0	0.00	8:09:15	0	0.00	12:54:30	0	0.00
8:29:30	0	0.00	14:09:30	0	0.00	8:09:30	0	0.00	12:54:45	0	0.00
8:29:45	0	0.00	14:09:45	0	0.00	8:09:45	0	0.00	12:55:00	0	0.00
8:30:00	0	0.00	14:10:00	0	0.00	8:10:00	0	0.00	12:55:15	0	0.00
8:30:15	0	0.00	14:10:15	0	0.00	8:10:15	0	0.00			

TABLE 2-6. VE READINGS AND ROLLING 6-MINUTE VE AVERAGES FOR NEWPORT STEEL MELT SHOP

TEST 1 August 15, 2000			TEST 2 August 15, 2000			TEST 3 August 16, 2000			TEST 4 (Incomplete) August 16, 2000		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
8:30:30	0	0.00	14:10:30	0	0.00	8:10:30	0	0.00	12:55:30	0	0.00
8:30:45	0	0.00	14:10:45	0	0.00	8:10:45	0	0.00	12:55:45	0	0.00
8:31:00	0	0.00	14:11:00	0	0.00	8:11:00	0	0.00	12:56:00	0	0.00
8:31:15	0	0.00	14:11:15	0	0.00	8:11:15	0	0.00	12:56:15	0	0.00
8:31:30	0	0.00	14:11:30	0	0.00	8:11:30	0	0.00	12:56:30	0	0.00
8:31:45	0	0.00	14:11:45	0	0.00	8:11:45	0	0.00	12:56:45	0	0.00
8:32:00	0	0.00	14:12:00	0	0.00	8:12:00	0	0.00	12:57:00	0	0.00
8:32:15	0	0.00	14:12:15	0	0.00	8:12:15	0	0.00	12:57:15	0	0.00
8:32:30	0	0.00	14:12:30	0	0.00	8:12:30	0	0.00	12:57:30	0	0.00
8:32:45	0	0.00	14:12:45	0	0.00	8:12:45	0	0.00	12:57:45	0	0.00
8:33:00	0	0.00	14:13:00	0	0.00	8:13:00	0	0.00	12:58:00	0	0.00
8:33:15	0	0.00	14:13:15	0	0.00	8:13:15	0	0.00	12:58:15	0	0.00
8:33:30	0	0.00	14:13:30	0	0.00	8:13:30	0	0.00	12:58:30	0	0.00
8:33:45	0	0.00	14:13:45	0	0.00	8:13:45	0	0.00	12:58:45	0	0.00
8:34:00	0	0.00	14:14:00	0	0.00	8:14:00	0	0.00	12:59:00	0	0.00
8:34:15	0	0.00	14:14:15	0	0.00	8:14:15	0	0.00	12:59:15	0	0.00
8:34:30	0	0.00	14:14:30	0	0.00	8:14:30	0	0.00	12:59:30	0	0.00
8:34:45	0	0.00	14:14:45	0	0.00	8:14:45	0	0.00	12:59:45	0	0.00
8:35:00	0	0.00	14:15:00	0	0.00	8:15:00	0	0.00	13:00:00	0	0.00
8:35:15	0	0.00	14:15:15	0	0.00	8:15:15	0	0.00	13:00:15	0	0.00
8:35:30	0	0.00	14:15:30	0	0.00	8:15:30	0	0.00	13:00:30	0	0.00
8:35:45	0	0.00	14:15:45	0	0.00	8:15:45	0	0.00	13:00:45	0	0.00
8:36:00	0	0.00	14:16:00	0	0.00	8:16:00	0	0.00	13:01:00	0	0.00
8:36:15	0	0.00	14:16:15	0	0.00	8:16:15	0	0.00	13:01:15	0	0.00
8:36:30	0	0.00	14:16:30	0	0.00	8:16:30	0	0.00	13:01:30	0	0.00
8:36:45	0	0.00	14:16:45	0	0.00	8:16:45	0	0.00	13:01:45	0	0.00
8:37:00	0	0.00	14:17:00	0	0.00	8:17:00	0	0.00	13:02:00	0	0.00
8:37:15	0	0.00	14:17:15	0	0.00	8:17:15	0	0.00	13:02:15	0	0.00
8:37:30	0	0.00	14:17:30	0	0.00	8:17:30	0	0.00	13:02:30	0	0.00
8:37:45	0	0.00	14:17:45	0	0.00	8:17:45	0	0.00	13:02:45	0	0.00
8:38:00	0	0.00	14:18:00	0	0.00	8:18:00	0	0.00	13:03:00	0	0.00
8:38:15	0	0.00	14:18:15	0	0.00	8:18:15	0	0.00	13:03:15	0	0.00
8:38:30	0	0.00	14:18:30	0	0.00	8:18:30	0	0.00	13:03:30	0	0.00
8:38:45	0	0.00	14:18:45	0	0.00	8:18:45	0	0.00	13:03:45	0	0.00
8:39:00	0	0.00	14:19:00	0	0.00	8:19:00	0	0.00	13:04:00	0	0.00
8:39:15	0	0.00	14:19:15	0	0.00	8:19:15	0	0.00	13:04:15	0	0.00
8:39:30	0	0.00	14:19:30	0	0.00	8:19:30	0	0.00	13:04:30	0	0.00
8:39:45	0	0.00	14:19:45	0	0.00	8:19:45	0	0.00	13:04:45	0	0.00
8:40:00	0	0.00	14:20:00	0	0.00	8:20:00	0	0.00	13:05:00	0	0.00
8:40:15	0	0.00	14:20:15	0	0.00	8:20:15	0	0.00	13:05:15	0	0.00
8:40:30	0	0.00	14:20:30	0	0.00	8:20:30	0	0.00	13:05:30	0	0.00
8:40:45	0	0.00	14:20:45	0	0.00	8:20:45	0	0.00	13:05:45	0	0.00
8:41:00	0	0.00	14:21:00	0	0.00	8:21:00	0	0.00	13:06:00	0	0.00
8:41:15	0	0.00	14:21:15	0	0.00	8:21:15	0	0.00	13:06:15	0	0.00
8:41:30	0	0.00	14:21:30	0	0.00	8:21:30	0	0.00	13:06:30	0	0.00
8:41:45	0	0.00	14:21:45	0	0.00	8:21:45	0	0.00	13:06:45	0	0.00
8:42:00	0	0.00	14:22:00	0	0.00	8:22:00	0	0.00	13:07:00	0	0.00
8:42:15	0	0.00	14:22:15	0	0.00	8:22:15	0	0.00	13:07:15	0	0.00
8:42:30	0	0.00	14:22:30	0	0.00	8:22:30	0	0.00	13:07:30	0	0.00
8:42:45	0	0.00	14:22:45	0	0.00	8:22:45	0	0.00	13:07:45	0	0.00
8:43:00	0	0.00	14:23:00	0	0.00	8:23:00	0	0.00	13:08:00	0	0.00
8:43:15	0	0.00	14:23:15	0	0.00	8:23:15	0	0.00	13:08:15	0	0.00
8:43:30	0	0.00	14:23:30	0	0.00	8:23:30	0	0.00	13:08:30	0	0.00
8:43:45	0	0.00	14:23:45	0	0.00	8:23:45	0	0.00	13:08:45	0	0.00
8:44:00	0	0.00	14:24:00	0	0.00	8:24:00	0	0.00	13:09:00	0	0.00
8:44:15	0	0.00	14:24:15	0	0.00	8:24:15	0	0.00	13:09:15	0	0.00
8:44:30	0	0.00	14:24:30	0	0.00	8:24:30	0	0.00	13:09:30	0	0.00
8:44:45	0	0.00	14:24:45	0	0.00	8:24:45	0	0.00	13:09:45	0	0.00
8:45:00	0	0.00	14:25:00	0	0.00	8:25:00	0	0.00	13:10:00	0	0.00
8:45:15	0	0.00	14:25:15	0	0.00	8:25:15	0	0.00	13:10:15	0	0.00
8:45:30	0	0.00	14:25:30	0	0.00	8:25:30	0	0.00	13:10:30	0	0.00
8:45:45	0	0.00	14:25:45	0	0.00	8:25:45	0	0.00	13:10:45	0	0.00

SECTION 3

SAMPLING PROCEDURES

The sampling and analytical procedures used conform to the most recent revisions of U.S. EPA Reference Methods for stationary sources. Specifically, U.S. EPA Reference Methods 1, 2, 3, 4, 5D, 6, 7E, 9, 10 and 12 were used. A brief description of each procedure is included below:

3.1 Measurement Sites

The location of measurement sites and the number of traverse points were determined as specified in U.S. EPA Reference Method 1, "Sample and Velocity Traverses for Stationary Sources."

Exhaust from the Brandt Baghouse is routed through 12 bag sections (cells). Following the guidelines presented in Method 5D, each sampling run consisted of six sample points per cell and four cells per test, for a total of 24 sample points per test run. At 10 minutes of sampling per point, this resulted in a net sampling time of 4 hours per test run. After three test runs, all 12 of the cells were sampled. Each test run was 240 minutes in length. Sampling point locations are detailed in Section 3. Isokinetic sampling rates were calculated from the measurement of volumetric flow rates at each inlet, as specified in Method 5D.

3.2 Velocity and Volumetric Flow Rates

The stack gas velocities and volumetric flow rates were determined using U.S. EPA Reference Method 2, "Determination of Stack Gas Velocity and Volumetric Flow Rate." Velocities were measured with an "s" type pitot tube and stack gas temperatures were measured with a calibrated Type "K" thermocouple.

3.3 Dry Molecular Weight (Method 3/3A)

Dry molecular weight was determined using U.S. EPA Method 3A, "Gas Analysis for Carbon Dioxide, Oxygen, Excess **Air**, and Dry Molecular Weight (Instrumental Analyzer Method)." A continuous sample was withdrawn and analyzed for O_2/CO_2 using instrumental analyzers. The instruments were calibrated with zero nitrogen and 2 span gases, in order to demonstrate linearity. Due to the amount of dilution air that the collection system receives, the dry molecular weight is essentially that of ambient air. Figure 3-1 depicts the sample train.

3.4 Moisture

Moisture content was determined using U.S. EPA Method 4 "Determination of Moisture Content of Stack Gases" in conjunction with the **RM/Lead** sampling.

3.5 Particulate Matter

EPA Reference Method 5D, "Determination of Particulate Matter Emissions from Positive Pressure Fabric Filters," was used to determine the particulate matter concentration and mass emission rates. The sample train consisted of a glass nozzle, glass probe and filter holder, glass fiber filter, and a series of **impingers** followed by a vacuum pump, dry gas meter, and calibrated orifice. The particulate sample will be withdrawn **isokinetically** and collected on the filter. Thermocouples will be used to monitor temperatures of the stack gas and **impinger** exit gas.

Exhaust from the Brandt Baghouse is routed through 12 bag sections (cells). Following the guidelines presented in Method 5D, each sampling run consisted of six sample points per cell and four cells per test, for a total of 24 sample points per test run. At 10 minutes of sampling per point, this resulted in a net sampling **time** of 4 hours per test run. After three test runs, all 12 of the cells were sampled. Each test run was approximately 240 minutes in length, and covered approximately three **EAF** heat cycles. Determination of measurement sites, number and location of traverse points, and velocity determination followed procedures in Method 5D. **Isokinetic** sampling rates were calculated from the measurement of volumetric flow rates at each inlet, as specified in Method 5D.




Figure 3-1. Instrumental Analyzer Sampling System

3.6 Visible Emission Observations

EPA Reference Method 9, "Visual Determination of the Opacity of Emissions from Stationary Sources," was used to determine opacity from the baghouse exhaust as well as from the shop roof monitor. Observations were conducted simultaneously with the particulate sampling runs.

3.7 SO₂ Emissions

The principles of EPA Method 6, "Determination of Sulfur Dioxide Emissions from Stationary Sources," were used for this test program. The first impinger contained 100 milliliters (ml) of an 80% isopropanol alcohol solution and the following two impingers of the impinger train contained a 3% hydrogen peroxide solution. The large impingers in a Method 5 sampling train were used in place of the midjet impingers. A gas sample was extracted from one sampling point in the stack. The sulfuric acid mist [including sulfur trioxide (SO₃)] and the SO₂ was separated. A separate pump was used to purge the sampling train. The SO₂ fraction was analyzed by the barium-thorin titration method. The average of three 240-minute sampling runs will constitute the test.

3.8 Nitrogen Oxides

NO_x emissions were determined using U.S. EPA Method 7E, "Determination of Nitrogen Oxide Emissions from Stationary Sources (Instrumental Analyzer Procedure)." A stack gas sample was withdrawn continuously from a single point and a portion directed to a chemiluminescent analyzer for NO_x measurement. All NO_x is converted to NO₂ in the analyzer and emission calculations are based upon the molecular weight of NO₂. U.S. EPA Protocol 1 calibration gases were used for instrument calibrations. Figure 3-1 depicts the sample

3.9 Lead Emissions

The principles of EPA Method 12, "Determination of Inorganic Lead Emissions from Stationary Sources," were used to measure lead emissions at the Brandt Baghouse. A gas sample

SECTION 4

PROCESS DESCRIPTION AND BAGHOUSE OPERATING DATA

The processes operating in the Newport Steel Corporation Melt Shop are the electric arc furnace (EAF), ladle metallurgy furnace (LMF), and continuous slab caster. The structure containing the EAF is referred to as the EAF building and the structure containing the LMF and the Caster is referred to as the Main Melt Shop Building. The Brandt baghouse vents emissions from the EAF and the EAF building.

Figure 4-1 shows the process flow for the Newport electric arc furnace (EAF). The EAF is a batch process. Each process cycle consists of four distinct phases: charging, melting, slagging, and tapping. After the furnace is charged with scrap and other additives, the meltdown phase comprises the period from charging to the complete meltdown of the solid material. Melting is accomplished by the heat supplied by direct radiation from the arcs formed between the electrodes and the scrap metal, by direct radiation from the furnace lining, and electric resistance of the metal between arc paths. The EAF also has oxy-fuel burners to provide additional heat input to enhance scrap meltdown and oxygen/carbon lances to enhance meltdown, refining, and foamy slag practice.

When the melting phase is complete, chemistry and temperature samples are taken. Based on these samples, the steel composition is adjusted and when the proper steel temperature has been reached, the foamy slag is poured off the furnace. For tapping, the power is shut off, the electrodes are raised to clear the molten steel bath, and the molten steel is tapped into a ladle and transferred to the LMF. After steel tapping is completed, the melting cycle begins again (i.e., the charging phase begins).

The Brandt baghouse exhausts the electric arc furnace (EAF) and the EAF building by an exhaust system consisting of (1) a direct evacuation control (DEC), and (2) a roof canopy hood. The DEC - also called a "fourth hole" system or direct shell evacuation (DSE) - captures emissions generated during scrap meltdown while the EAF roof is in place directly from the

was withdrawn from the gas stream and collected on a glass-lined probe, on a glass-fiber filter, and in a series of glass **impingers** containing 0.1 N nitric acid. The Method 12 sample was conducted utilizing the same train as the particulate sample. The **impinger** content volume was measured after sampling to **determine** the moisture pickup. The average of three 240-minute sample runs constituted the test.

3.10 CO Emissions

The principles of EPA Method 10, "**Determination** of Carbon Monoxide Emissions from Stationary Sources," were used for this program to determine CO emissions. A gas sample was continuously extracted from the **baghouse** inlet duct using the same conveying system as the NO_x and VOC analyzer. The CO analyzer measured the CO concentration using the principles of nondispersive infrared (NDIR) analysis. The sampling and data acquisition will be conducted simultaneously with and in the same manner as the NO_x sampling.

3.11 EAF and Baghouse Operation Data

EAF and Brandt Baghouse operation data included the following:

- EAF logs, including time and duration of each charge and tap, charge weights and tap weights;
- Calculations of average hourly steel production rate for each test run;
- Charge carbon sample analyses (for sulfur content);
- Baghouse pressure drops;
- Baghouse fan amperage and damper positions.

furnace vessel. The DEC is comprised of water-cooled **ductwork** to cool the hot EAF exhaust gases. Prior to the water-cooled section, a gap in the duct allows the entrainment of shop ambient air to assist in the combustion of carbon monoxide (CO) off-gases to carbon dioxide (CO₂). After passing sufficient distance to cool the exhaust, the DEC duct then merges with shop roof **ductwork** from the roof canopy hood. The overhead roof canopy hood collects fumes and gases that escape the furnace shell. The combined gas stream including EAF exhausts and melt shop ambient air is ducted to the Brandt baghouse.

Process information collected during the course of the sampling program included:

- A) Charge weights and materials, and tap weights and **materials**
- B) Heat times, including start and stop times, log of process operation including periods of no operation during testing
- C) Pressure drop across the baghouse, visual inspection of bags and control system fan amperes
- D) **Fan/duct** damper positions
- E) Fan amperes.

Data were recorded at 15-minute intervals during testing. Table 4-1 presents the baghouse pressure drops, fan amps, and damper positions during the test program.




Figure 4-1. Process Flow Diagram
Melt Shop - Electric Arc Furnace (EAF)

—> Material/Fuel Flow
 - - -> Emission Stream

Newport Steel, Inc.		E _O
Process Flow Diagram:		
Melt Shop - Electric Arc Furnace (EAF)		
Drawing No.:		
Scale: Not to Scale		
Drawn by: RJH	Revision: 0	
Checked by: FDH	Date: 2/9/98	

**TABLE 4-1. BAGHOUSE PRESSURE DROP, CONTROL SYSTEM FAN AMPS,
AND DAMPER POSITIONS DURING PERFORMANCE TESTS**

DATE	TIME	Baghouse Pressure Drop, in. WG	Fan 1 Amp	Fan 2 Amp	Fan 3 Amp	Total Amp
TEST 1						
8/15/00	8:15:00 AM	7.3	201	191	198	590
8/15/00	8:30:00 AM	7.5	202	193	199	594
8/15/00	8:45:00 AM	8.1	206	195	208	609
8/15/00	9:00:00 AM	7.6	214	201	210	625
8/15/00	9:15:00 AM	7.2	214	202	208	624
8/15/00	9:30:00 AM	7.2	219	208	214	641
8/15/00	9:45:00 AM	7.1	208	196	204	608
8/15/00	10:00:00 AM	7.5	199	190	197	586
8/15/00	10:15:00 AM	7.7	200	191	198	589
8/15/00	10:30:00 AM	7.8	210	200	206	616
8/15/00	10:45:00 AM	8.1	207	194	201	602
8/15/00	11:00:00 AM	7.6	218	205	212	635
8/15/00	11:15:00 AM	7.9	212	203	206	621
8/15/00	11:30:00 AM	7.7	214	200	207	621
8/15/00	11:45:00 AM	7.3	206	197	202	605
8/15/00	12:00:00 PM	8.0	208	196	204	608
8/15/00	12:15:00 PM	8.3	204	193	200	597
8/15/00	12:30:00 PM	8.3	211	199	206	616
8/15/00	12:45:00 PM	7.9	210	204	214	628
8/15/00	1:00:00 PM	8.3	197	188	196	581
Ampere Range Test 1 = 581 - 641						
Damper Positions During Test No. 1:						
EAF Exhaust = 100% Open						
Canopy = 68-70% Open						
TEST 2						
8/15/00	1:45:00 PM	7.6	213	199	206	618
8/15/00	2:00:00 PM	8.2	203	196	209	608
8/15/00	2:15:00 PM	7.7	213	200	206	619
8/15/00	2:30:00 PM	7.4	217	206	211	634
8/15/00	2:45:00 PM	7.1	215	208	221	644
8/15/00	3:00:00 PM	7.9	200	192	205	597
8/15/00	3:15:00 PM	8.0	215	203	207	625
8/15/00	3:30:00 PM	7.4	213	200	205	618
8/15/00	3:45:00 PM	7.2	209	194	205	608
8/15/00	4:00:00 PM	7.9	211	197	204	612
8/15/00	4:15:00 PM	7.7	206	192	200	598
8/15/00	4:30:00 PM	8.0	213	199	208	620
8/15/00	4:45:00 PM	6.9	214	207	220	641
8/15/00	5:00:00 PM	7.7	203	192	198	593
8/15/00	5:15:00 PM	7.4	207	192	201	600
8/15/00	5:30:00 PM	7.9	213	199	207	619
8/15/00	5:45:00 PM	7.2	208	195	202	605
8/15/00	6:00:00 PM	7.2	208	196	203	607
8/15/00	6:15:00 PM	7.3	214	202	208	624
8/15/00	6:30:00 PM	7.9	201	189	195	585
Ampere Range Test 3 = 585 - 644						
Damper Positions During Test No. 2:						
EAF Exhaust = 00% Open						
Canopy = 70% Open						

TABLE 4-1 (continued)

DATE	TIME	Baghouse Pressure Drop, in. WG	Fan 1 Amp	Fan 2 Amp	Fan 3 Amp	Total Amp
TEST 3						
8/16/00	7:55:00 AM	7.0	219	205	210	634
8/16/00	8:15:00 AM	7.6	211	198	205	614
8/16/00	8:30:00 AM	8.6	205	192	201	598
8/16/00	8:45:00 AM	8.1	206	193	199	598
8/16/00	9:00:00 AM	7.8	193	182	189	564
8/16/00	9:15:00 AM	7.7	199	187	195	581
8/16/00	9:30:00 AM	8.3	196	183	191	570
8/16/00	9:45:00 AM	8.4	198	185	194	577
8/16/00	10:00:00 AM	7.9	191	183	193	567
8/16/00	10:15:00 AM	7.9	214	201	207	622
8/16/00	10:30:00 AM	8.3	201	188	197	586
8/16/00	10:45:00 AM	8.2	202	187	196	585
8/16/00	11:00:00 AM	7.9	195	183	191	569
8/16/00	11:15:00 AM	7.7	210	197	204	611
8/16/00	11:30:00 AM	7.8	213	200	207	620
8/16/00	11:45:00 AM	7.6	200	190	199	589
8/16/00	12:00:00 PM	8.0	204	192	197	593
8/16/00	12:15:00 PM	7.6	201	191	197	589
Ampere Range Test 3 = 567 - 634						
Damper Positions During Test No. 3: EAF Exhaust = 00% Open Canopy = 70% Open						
Ampere Range All Complete Tests = 567 - 644						
Damper Positions During Tests No's 1 - 3: EAF Exhaust = 100% Open Canopy = 68-70% Open						

SECTION 5

QUALITY ASSURANCE AND QUALITY CONTROL

The field sampling quality assurance for this project includes the use of calibrated source sampling equipment, reference test methods, and traceability protocols for the recording and calculation of data. The analytical quality assurance includes use of validated analytical procedures, calibration of equipment, and analysis of control samples and blanks. The calibration and quality control procedures to be used for this test program are described in the following subsection.

5.1 Calibration Procedures and Frequency

All manual stack gas sampling equipment is calibrated before the test program in accordance with the procedures outlined in the Quality Assurance Handbook for Air Pollution Measurement Systems, Volume 111, EPA-600/4-72-027B. Summarized in Table 5-1 are the stack gas sampling equipment calibrations which will be performed in preparation for this project. The meter boxes will be re-calibrated after the test. Analyzer checks will be conducted directly to the instrument initially and then through the sampling system. Calibration checks will be conducted before and after each test run. EPA protocol gases will be used for calibrating the NO_x analyzer. The CO analyzer will be calibrated with Master Gas Certified calibration gases with a 2 percent accuracy.

Listed in Table 5-2 are the additional calibration checks which will be performed on the sampling equipment on site, just prior to the testing, to ensure that equipment was not damaged during transport. A copy of the calibration data and procedures is provided in Appendix F.

TABLE 5-1. FIELD EQUIPMENT CALIBRATION SUMMARY'

Equipment	Calibrated Against	Allowable Error
Method 5 meter box	Reference test meter	Y $\pm 0.02Y$ ▲H @ S.15 post-test Y $\pm 0.05 Y$
Orsat	Certified cylinder gas	$\pm 0.5\%$
Pitot tube	Geometric specifications	See EPA Method 2
Thermocouple	ASTM-3F thermometer	$\pm 1.5\%$
Impinger (or condenser thermometer)	ASTM-3F	$\pm 2^{\circ}\text{F}$
Dry gas thermometer	ASTM-3F	$\pm 5^{\circ}\text{F}$
Probe nozzles	Caliper	± 0.004 in.
Barometer	NBS traceable barometer	± 0.1 in. Hg

* As recommended in the Quality Assurance Handbook for Air Pollution Measurement Systems: Volume III. Stationary Source-Specific Methods. EPA-600/4-77-027b, August 1977.

TABLE 5-2. FIELD CHECKS OF SAMPLING EQUIPMENT

Equipment	Checked Against	Allowable Difference
Pitot tube	Inspection	No visible damage
Thermocouples	ASTM 2F or 3F	$\pm 1.5\%$
Probe Nozzles	Caliper	± 0.004 in.

FIELD CHECKS OF CO AND NO_x ANALYZER

	Instrument Check	Acceptable Limit
Initial Calibration	CO & NO _x Calibration Error, % Span	$\pm 2\%$
	Sampling System Bias	< 5% of Span
Daily Calibration	CO & NO _x Calibration Error, % Span	$\pm 2\%$
	CO & NO, Drift, % Span	< 3 of Span

APPENDIX B

PRODUCTION/PROCESS FIELD DATA

PRODUCTION WORKSHEET

Heats During Tests

Date	Heat No.	Tons	Tap-Tap Time, min	Operating Time, hr	Tons/Hr
TEST 1					
15-Aug	6004	95.4	96	1.6	59.6
	6005	94.6	96	1.6	59.1
	6006	95.2	110	1.8	51.9
	6007	105.8	91	1.5	69.8
	Totals	391.0	393	6.6	59.7 tons/hr
TEST 2					
15-Aug	6007	105.8	91	1.5	69.8
	6008	92.8	144	2.4	38.7
	6009	92.0	90	1.5	61.3
	6010	92.9	100	1.7	55.7
	Totals	383.5	425	7.1	54.1 tons/hr
TEST 3					
16-Aug	6018	93.3	85	1.4	65.9
	6019	93.6	60	1.0	93.6
	6020	94.5	88	1.5	64.4
	6021	94.2	61	1.0	92.7
	Totals	375.6	294	4.9	76.7 tons/hr
TEST 4					
16-Aug	6021	94.2	61	1.0	92.7
	6022	93.8	79	1.3	71.2
	6023	93.2	174	2.9	32.1
	Totals	281.2	314	5.2	53.7

Test stopped at 1:40 pm due to operating problems with automatic oxygen lance

**NEWPORT STEEL CORPORATION
BRANDT BAGHOUSE TEST PROCESS MONITORING FORM**

Date 8/15Run Number 2Start 1345
30 min

Time	Baghouse Fan Amperage			Baghouse Pressure Drop, in. WG	Damper Positions (Describe)	Notes (Heat No. and time; Other)
	1	2	3			
1345	213	199	206	7.6	13 ⁵⁰ 30% closed on canopy	6007 Melting Heat
14:00	203	196	209	8.2	100% open exhaust	14:15 Tapped 6007
14:15	213	200	206	7.7	14 ⁵⁰ 30 closed canopy	6008 14:55 Power On
14:30	217	206	211	7.4	100 open exhaust	Drum of dust in 15:22
14:45	215	208	221	7.1	15 ²² 30 closed canopy	2nd charge 15:32
15:00	200	192	205	7.9	100 open exhaust	Tap 16:37
15:15	215	203	207	8.0	16:30 30 closed canopy	6009
15:30	213	200	205	7.4	100 open exhaust	Began 16:51
15:45	209	194	205	7.2	17:30 30% closed Can	2nd charge 17:07
16:00	211	197	204	7.9	100% open exh.	Tap 18:07
16:15	206	192	200	7.7	18/ closed canopy	6010
16:30	213	199	208	8.0	30% canopy	Power 6:21 On
16:45	214	207	220	6.9	100% open exhaust	
17:00	203	192	198	7.7		
17:15	207	192	201	7.4		
17:30	213	199	207	7.9		
17:45	208	195	202	7.2		
18:00	208	196	203	7.2		
18:15	214	202	208	7.3		
18:25	201	189	195	7.9		

Note: Automatic oxygen lance in repair.
Manual lancing performed for heats during test

Gas (CO & NOx & SO₂)
ended 17:55

End 18:25

Date 8/16/00 Run Number 4 Start 12:40

END—

APPENDIX D

EMISSION TESTING FIELD DATA



Newport Steel
 Date 8/14/00
 Baylunze

(4.5')

(13.5')

54.75"

164.25"



793, 65L

0016 Ap


806, 75L

1.05

1.25

(178" + 11')

308"



251.67" (21')

150.91" (12.5')

50.33" (4')

219"
 (87" + 11')

Client :

Calculator :

Date : 8/14/00

Location :

Distance from *upstream* disturbance (u) :

~~1900~~ 1900

Distance from *downstream* disturbance (d) :

~~1200~~" 250"


Outside of port to ***far side*** of stack (a) :

197✓

Outside of port to **near side** of stack (b) :

Inside Stack Diameter (a-b) :

185.5

[illegible]

FBT

SAMPLE RECOVERY DATA

Date: 8-16-00
Client: Newport Steel
Plant: Newport
Location: Boghouse exhaust
Test Method: S
Run #: 4 TC #: _____

IMPINGER DATA

	#1	#2	#3	#4	#5	
Contents	DIN HNO ₃	DIN HNO ₃	MT	SG		Total
Final Wt.(g)	709	695	583	890		
Initial Wt.(g)	693	691	581	865		
Net Gain (g)	16	4	2		25	47

RECOVERED SAMPLES

Recovered by: _____

Date: - _____

Filter #: - _____

Silica Gel Color: _____

COMMENTS: _____

Client City: Newport SteelDate: 08/16/02 Run #:Location: Bayhouse Outlet

Sample Type: _____

Operator: PM, CW

Probe Length Type: _____

Nozzle Size: _____

Meter Box #: Apex 3 $\Delta H @$: _____

Y: _____

Assumed H_2O : _____ % T_s : _____

Cp: _____

 P_{BAR} : _____ Ambient Temperature: _____ °F

P: _____

Reference ΔP : _____

K-factor: _____

Pretest Leak Rate: .009 ft³ @ 8 "hg

Filter #: _____

Comments: 1/2 Post Leak .009 @ 13hgPosttest Leak Rate: _____ ft³ @ _____ "hg

Pitot Leak Check: _____

Orsat Leak Check: _____

Fyrite Data: _____

Moisture Data Total: _____

Traverse Schematic: _____

O₂: _____ml H₂O

g Sil. Gel

CO₂: _____

Page ____ of ____ Record data every ____ minutes

Trav. #	Sample Time	Clock Time	Meter Reading	Pitot #:		TC #s:		Probe	Stack	Tm In	Tm Out	Filter	Exit	Pump Vac.
				ΔP	$\Delta H(\text{calc})$	$\Delta H(\text{act})$								
		12:39	825.862		2.5				186	104	96	190	65	7
5-1	10								191	105	97	230	64	7
2	20								203	105	97	238	64	7
3	30								189	106	98	238	69	7
4	40								210	105	98	240	67	7
5	50								232	105	98	248	68	7
6	60		879.548											
6-1	10								167	101	99	210	65	7
2	20								175	105	99	226	67	7
3	30								183	108	99	228	67	7
4	40								175	109	100	228	69	7
5	50								175	109	101	228	69	7
6	60		933.487						170	109	101	227	67	7
12-1														
2														
3														
4														
5														
6														
11-1														
2														
3														
4														
5														
6														

O: _____ V_m: 107.625 avg $\sqrt{\Delta P}$: .04 avg ΔH : _____ T_s: 185 T_m: 102 Calculated By: _____ Checked By: _____

FBT

SAMPLE RECOVERY DATA

Date: 8/16/00
 Client: Newport Steel
 Plant: Newport, KY
 Location: Barghouse
 Test Method: M12
 Run #: 3 TC #:

IMPINGER DATA

	#1	#2	#3	#4	#5	
Contents	0.1 N HNO ₃	0.1 N HNO ₃	MT	SG		Total
Final Wt.(g)	760	530	554	802 843		
Initial Wt.(g)	617	606	551	850 875		
Net Gain (g)	143	- 76	3	8		

RECOVERED SAMPLES

Recovered by: U.I.H.
 Date: 8/16/00
 Filter #: 3705
 Silica Gel Color: 02

COMMENTS: _____

Probe Length / Type: 3' Tass

Date: 8-16-00 Run #: 3

Nozzle Size: _____, _____ = 1.125

Location: Bughouse Outlet

Meter Box #: Apex 3 ΔH@: 1-723 Y: 993

Sample Type: MS Operator: CWJRM Assumed H₂O: _____% T: _____ Cp: _____

P_{BAR} : _____ Ambient Temperature: 69 °F P_s : _____ Reference ΔP : _____ K-factor: _____

Pretest Leak Rate : .006 ft³ @ 22 "hg Filter #:

Comments:

Posttest Leak Rate : .003 ft³ @ 6.5"hg

Pitot Leak Check: _____ Orsat Leak Check: _____

Fyrite Data:

Moisture Data Total:

Traverse Schematic:

Q: .

ml H₂O

g Sil. Gel

CO₂: _____

Page of Record data every minutes

Trav. #	Sample Time	Clock Time	Meter Reading	Pitot #:		TC #s:		Probe	Stack	Tm In	Tm Out	Filter	Exit	Pump Vac.
				ΔP	$\Delta H(\text{calc})$	$\Delta H(\text{act})$								
	0	7:84	617.880											
1-1	10				2.5				135	90	86	229	62	3
2	20								140	90	87	233	67	3
3	30								145	93	86	232	69	3
4	40								150	95	84	237	60	3
5	50								160	96	83	239	65	3
6	60		670.529						160	95	83	240	65	3
2-1	10								155	92	83	210	67	3
2	20								183	92	83	241	68	3
3	30								180	86	84	242	64	3
4	40								180	93	83	242	68	3
5	50								175	98	85	244	68	3
6	60		718.215						175	99	86	243	68	3
3-1	10	1003							175	101	90	242	67	4
2	20								175	101	90	240	67	4
3	30								180	102	91	237	67	4
4	40								180	100	92	236	67	4
5	50								180	101	92	238	66	4
6	60		770.550						175	101	92	240	67	4
4-1	10								158	92	91	227	68	4
2	20								156	102	92	232	67	4
3	30								158	105	93	233	67	4
4	40								162	106	95	234	65	4
5	50								163	107	96	235	64	4
6	60	12:14	824.501						154	103	97	234	66	4

D: _____ V_m : 20% 621 $\text{avg} \sqrt{\Delta P}$: _____ $\text{avg} \Delta H$: _____ T_i : 165 T_o : 93 Calculated By: _____ Checked By: _____

FBT

SAMPLE RECOVERY DATA

Date: 8-15-00
Client: Newport Steel
Plant: Newport Ky
Location: Boghouse
Test Method: M12
Run #: 2 TC #: _____

IMPINGER DATA

	#1	#2	#3	#4	#5	Total
Contents	0.1N HNO ₃	0.1N HNO ₃	MT	SG		
Final Wt.(g)	577 726	697	585	892		
Initial Wt.(g)	677	686	581	863		
Net Gain (g)	49	11	4	29		93

RECOVERED SAMPLES

Recovered by: DW
Date: 8/15/00
Filter #: _____
Silica Gel Color. ok

COMMENTS: _____

Date: 08/15/00 Run #: 2

Location: Baghouse

Sample Type: _____ Operator: SM, CW

P_{BAR}: 30.02 Ambient Temperature: _____ °F P_i: _____

Pretest Leak Rate: .018 ft³ @ 10 "hg Filter #: _____

Posttest Leak Rate: .001 ft³ @ 20 "hg

Pitot Leak Check: _____ Orsat Leak Check: _____

Fyrite Data: _____ Moisture Data Total: _____

O₂: _____ ml H₂O g Sil. Gel

CO₂: _____

Page _____ of _____ Record data every _____ minutes

Probe Length / Type: _____

Nozzle Size: _____ = 1.13

Meter Box #: Apex 3AH@ 1.7234 Y: 9931

Assumed H₂O: _____ % T_s: _____ Cp: _____

Reference ΔP: _____ K-factor: _____

Comments: _____

Traverse Schematic: _____

Trav. #	Sample Time	Clock Time	Meter Reading	Pitot #:		TC #s:		Probe	Stack	Tm In	Tm Out	Filter	Exit	Pump Vac.
				ΔP	ΔH(calc)	ΔH(act)								
		<u>1:45</u>	<u>513.934</u>											
1	10			<u>.0016</u>	<u>2.53</u>				<u>135</u>	<u>109</u>	<u>103</u>	<u>230</u>	<u>53</u>	<u>11</u>
2	20								<u>135</u>	<u>111</u>	<u>105</u>	<u>239</u>	<u>53</u>	<u>11</u>
3	30								<u>135</u>	<u>112</u>	<u>107</u>	<u>243</u>	<u>44</u>	<u>11</u>
4	40								<u>135</u>	<u>118</u>	<u>113</u>	<u>242</u>	<u>46</u>	<u>11</u>
5	50								<u>131</u>	<u>108</u>	<u>111</u>	<u>239</u>	<u>47</u>	<u>11</u>
6	60								<u>130</u>	<u>111</u>	<u>109</u>	<u>239</u>	<u>46</u>	<u>11</u>
12-1	10								<u>135</u>	<u>108</u>	<u>108</u>	<u>237</u>	<u>51</u>	<u>12</u>
2	20								<u>135</u>	<u>103</u>	<u>103</u>	<u>236</u>	<u>44</u>	<u>12</u>
3	30								<u>140</u>	<u>115</u>	<u>108</u>	<u>240</u>	<u>42</u>	<u>13</u>
4	40								<u>142</u>	<u>114</u>	<u>110</u>	<u>239</u>	<u>45</u>	<u>13</u>
5	50								<u>140</u>	<u>114</u>	<u>110</u>	<u>238</u>	<u>50</u>	<u>13</u>
6	60		<u>503.417</u>						<u>140</u>	<u>116</u>	<u>111</u>	<u>238</u>	<u>45</u>	<u>13</u>
6-1									<u>150</u>	<u>110</u>	<u>111</u>	<u>208</u>	<u>52</u>	<u>12</u>
2									<u>150</u>	<u>122</u>	<u>113</u>	<u>217</u>	<u>52</u>	<u>12</u>
3									<u>150</u>	<u>136</u>	<u>123</u>	<u>224</u>	<u>52</u>	<u>12</u>
4									<u>146</u>	<u>134</u>	<u>127</u>	<u>228</u>	<u>46</u>	<u>12</u>
5									<u>145</u>	<u>132</u>	<u>127</u>	<u>221</u>	<u>40</u>	<u>12</u>
6			<u>560.342</u>						<u>145</u>	<u>128</u>	<u>124</u>	<u>229</u>	<u>44</u>	<u>12</u>
5-1									<u>145</u>	<u>108</u>	<u>113</u>	<u>210</u>	<u>44</u>	<u>13.5</u>
2									<u>145</u>	<u>125</u>	<u>120</u>	<u>217</u>	<u>44</u>	<u>13</u>
3									<u>160</u>	<u>122</u>	<u>117</u>	<u>244</u>	<u>46</u>	<u>13</u>
4									<u>150</u>	<u>125</u>	<u>119</u>	<u>244</u>	<u>46</u>	<u>14</u>
5									<u>162</u>	<u>118</u>	<u>116</u>	<u>230</u>	<u>47</u>	<u>14</u>
6		<u>6:28</u>	<u>616.726</u>						<u>151</u>	<u>116</u>	<u>114</u>	<u>229</u>	<u>48</u>	<u>14</u>

Θ: _____ V_m: 222.752 avg √ΔP: _____ avg ΔH: _____ T_s: 122 T_m: 113 Calculated By: _____ Checked By: _____

FBT



100

100

TPLES

TPLES

TPLES

Client / City: Newport Steel

Probe Length / Type: _____

Date: 08/15/02 Run #: 1Nozzle Size: _____ = 1.13Location: BaghouseMeter Box #: Aper 3 ΔH @: L2234 γ : .993Sample Type: _____ Operator: RM, CWAssumed H_2O : _____ % T_c : _____ Cp: _____ P_{BAR} : _____ Ambient Temperature: _____ °F P_s : _____Reference ΔP : _____ K-factor: _____Pretest Leak Rate: .008 ft³@ 15 "hg Filter #: _____

Comments: _____

Posttest Leak Rate: .003 ft³@ 10 "hg

Pilot Leak Check: _____ Orsat Leak Check: _____

Fyrite Data: _____ Moisture Data Total: _____

Traverse Schematic: _____

 O_2 : _____ ml H_2O g Sil. Gel CO_2 : _____

Page _____ of _____ Record data every _____ minutes

Trav. #	Sample Time	Clock Time	Meter Reading	Pilot #:		TC #s:		Probe	Stack	Tm In	Tm Out	Filter	Exit	Pump Vac.
				ΔP	ΔH (calc)	ΔH (act)								
		<u>8:34</u>	<u>157.717</u>					<u>X</u>						
7-1	10			<u>.0016</u>	<u>2.53</u>				<u>145</u>	<u>81</u>	<u>78</u>	<u>265</u>	<u>40</u>	<u>7.5</u>
2	20								<u>145</u>	<u>89</u>	<u>79</u>	<u>265</u>	<u>41</u>	<u>7.5</u>
3	30								<u>145</u>	<u>92</u>	<u>81</u>	<u>289</u>	<u>41</u>	<u>7.5</u>
4	40								<u>145</u>	<u>93</u>	<u>83</u>	<u>240</u>	<u>65</u>	<u>7.5</u>
5	50								<u>155</u>	<u>94</u>	<u>84</u>	<u>262</u>	<u>55</u>	<u>7.5</u>
6	60		<u>212.671</u>		<u>↓</u>				<u>155</u>	<u>94</u>	<u>85</u>	<u>255</u>	<u>55</u>	<u>7.5</u>
8-1	10								<u>140</u>	<u>89</u>	<u>87</u>	<u>255</u>	<u>61</u>	<u>6</u>
2	20								<u>140</u>	<u>96</u>	<u>88</u>	<u>255</u>	<u>53</u>	<u>6</u>
3	30								<u>155</u>	<u>100</u>	<u>90</u>	<u>280</u>	<u>52</u>	<u>6</u>
4	40								<u>165</u>	<u>101</u>	<u>93</u>	<u>281</u>	<u>51</u>	<u>6</u>
5	50								<u>165</u>	<u>104</u>	<u>94</u>	<u>275</u>	<u>50</u>	<u>6</u>
6	60		<u>274.486</u>						<u>165</u>	<u>104</u>	<u>96</u>	<u>277</u>	<u>51</u>	<u>6</u>
9-1	10								<u>150</u>	<u>98</u>	<u>99</u>	<u>260</u>	<u>49</u>	<u>5</u>
2	20								<u>150</u>	<u>105</u>	<u>100</u>	<u>261</u>	<u>49</u>	<u>5</u>
3	30								<u>130</u>	<u>111</u>	<u>100</u>	<u>260</u>	<u>50</u>	<u>5</u>
4	40								<u>130</u>	<u>112</u>	<u>105</u>	<u>260</u>	<u>62</u>	<u>5</u>
5	50								<u>130</u>	<u>112</u>	<u>105</u>	<u>260</u>	<u>49</u>	<u>5</u>
6	60		<u>330.452</u>						<u>130</u>	<u>112</u>	<u>105</u>	<u>260</u>	<u>54</u>	<u>5</u>
10-1	10								<u>135</u>	<u>105</u>	<u>106</u>	<u>240</u>	<u>52</u>	<u>5</u>
2	20								<u>135</u>	<u>108</u>	<u>104</u>	<u>241</u>	<u>56</u>	<u>5</u>
3	30								<u>135</u>	<u>100</u>	<u>104</u>	<u>241</u>	<u>65</u>	<u>5</u>
4	40								<u>135</u>	<u>110</u>	<u>105</u>	<u>242</u>	<u>55</u>	<u>5</u>
5	50								<u>135</u>	<u>109</u>	<u>105</u>	<u>244</u>	<u>68</u>	<u>5</u>
6	60		<u>385.860</u>						<u>135</u>	<u>108</u>	<u>104</u>	<u>237</u>	<u>56</u>	<u>5</u>

ϕ : _____ V_m : 226.143 avg $\sqrt{\Delta P}$: .04 avg ΔH : 2.53 T_c : 144 T_m : 96 Calculated By: _____ Checked By: _____

FBT

GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: Newport Steel

Date. 8/16/00

Sampling Location: CAF Exhaust / Brandt Inlet

Run #: 3 Clock Time: 0900

Barometric Pressure, in Hg: 29.85 Static Pressure, "H₂O: -4.1

Operators: PH / OW

TC #: Pitot Tube #: Pitot Leak Check:

Pitot Tube C_p : 0.84

Wet Bulb, °F: Dry Bulb, °F: A_g 185.5"

Fyrite 02: _____ CO₂: _____

Traverse Point #	ΔP in. H ₂ O	Stack Temp. °F	Cyclonic Flow °
1	0.89	190	
2	1.2	192	
3	1.3	194	
4	1.4	200	
5	1.2	200	
6	1.3	187	
7	1.1	180	
8	1.2	175	
1	0.98	195	
2	1.1	188	
3	1.0	163	
4	0.96	200	
5	1.3	231	
6	1.1	153	
3	1.1	153	
6	1.1	153	
Average:	$\sqrt{\Delta P} = 1.066$	T _s = 184	°C =

$$Md = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times N_2)$$

$$Md = (0.44 \times \underline{\hspace{2cm}}) + (0.32 \times \underline{\hspace{2cm}}) + (0.28 \times \underline{\hspace{2cm}})$$

$$Md =$$

$$M_s = M_d \times \left(1 - \frac{\%H_2O}{100}\right) + 18 \left(\frac{\%H_2O}{100}\right)$$

$$Ms = \underline{\hspace{1cm}} \times \left(1 - \frac{\hspace{1cm}}{100} \right) + 18 \left(\frac{\hspace{1cm}}{100} \right)$$

$$M_S =$$

$$T_s = \text{ } F + 460 = \text{ } R$$

$$P_s = P_{bar} + \frac{SP}{13.6} = \underline{\hspace{2cm}} + \frac{\underline{\hspace{2cm}}}{13.6}$$

$$P_s = \quad \text{in. Hg}$$

$$\sqrt{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s(R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times \underline{\hspace{1cm}} \times \underline{\hspace{1cm}} \times \sqrt{\frac{\underline{\hspace{1cm}}}{\underline{\hspace{1cm}} \times \underline{\hspace{1cm}}}}$$

$$V_s = \quad \text{ft/sec}$$

As = _____ **sq.ft**

$$Qa = Vs \times As \times 60s/m$$

$$Qa = \underline{\hspace{1cm}} \times \underline{\hspace{1cm}} \times 60$$

$Qa =$ _____ *acfm*

$$Q_{std} = Q_a \times 17.647 \times \frac{P_s}{T_s} \times \left(1 - \frac{\%H_2O}{100}\right)$$

$$Qstd = \underline{\hspace{2cm}} \times 17.647 \times \underline{\hspace{2cm}} \times \left(1 - \frac{\underline{\hspace{2cm}}}{100} \right)$$

$$Q_{std} = \underline{\hspace{2cm}} \text{ dscfm}$$

FBT

GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: Newport Steel

Date: 6/15/00

Sampling Location: EAF Exhaust / Brandt E In

Clock Time: 1540

Run #: 2

Operators: PH DW

Barometric Pressure, in Hg:

Static Pressure, "H₂O": - 4 -

TC #:

Pitot Tube #.:

Pitot Tube C_p : 0.64

Stack Dimension, in. ~~Diameter~~ or Side 1: 189"

Side 2:

Wet Bulb, $^{\circ}\text{F}$:

Dry Bulb, °F:

Fyrite 02: CO_2

Traverse Point #	Velocity Head in. H ₂ O	Stack Temp. °F	Cyclonic Flow °
1	0.92	125	
2	1.3	125	
3	1.2	126	
4	1.5	127	
5	1.3	125	
6	1.2	126	
7	1.2	125	
8	1.1	125	
1	0.95	120	
2	1.3	126	
3	1.3	126	
4	1.4	127	
5	1.5	121	
6	1.4	122	
7	1.5	122	
8	1.3	123	
Average: $\sqrt{\Delta P} =$	1.1257	T _s = 125	°C=

$$Md = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times N_2)$$

$$Md = (0.44 \times \text{-----}) + (0.32 \times \text{-----}) + (0.28 \times \text{-----})$$

$Md =$ _____

$$Ms = Md \times \left(1 - \frac{\%H_2O}{100}\right) + 18 \left(\frac{\%H_2O}{100}\right)$$

$$Ms = \text{-----} \times \left(1 - \frac{\text{-----}}{100}\right) + 18 \left(\frac{\text{-----}}{100}\right)$$

$$M_s =$$

$$T_s = \text{---} F + 460 = \text{---} R$$

$$P_s = P_{bar} + \frac{SP}{13.8} = \text{-----} + \frac{\text{-----}}{13.8}$$

$P_s =$ _____ in. Hg

$$\sqrt{\Delta P} = \underline{\hspace{2cm}}$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s(R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times \text{---} \times \text{---} \times \sqrt{\text{---} \times \text{---}}$$

$$V_s = \underline{\hspace{1cm}} \text{ ft / sec}$$

As = _____ sq. ft

$$Qa = Vs \times As \times 60s / m$$

$$Qa = \text{---} \times \text{---} \times 60$$

$Q_a =$ _____ acfm

$$Q_{std} = Q_a \times 17.647 \times \frac{P_s}{T_s} \times \left(1 - \frac{\%H_2O}{100}\right)$$

$$Q_{std} = \text{-----} \times 17.647 \times \frac{\text{-----}}{\text{-----}} \times \left(1 - \frac{\text{-----}}{100}\right)$$

$Q_{std} = \underline{\hspace{2cm}} \text{ dscfm}$

Average: $\sqrt{\Delta P} =$	1.1257	$T_s =$	125	$^{\circ}\text{C} =$
------------------------------	--------	---------	-----	----------------------

FBT

GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: Steel Date: 6/15/00
Sampling Location: Brandt Baghouse In Clock Time: 0900
Run #: 1 Operators: PH 10
Barometric Pressure, in Hg: 30.01 Static Pressure, "H₂O: -3.8
TC #: _____ Pitot Tube #: _____ Pitot Tube Cp: 0.84
Stack Dimension, in Diameter of Side 1: 149" Side 2: _____
Wet Bulb, OF: _____ Dry Bulb, OF: _____ Fyrite O₂: _____ CO₂: _____

Traverse Point #	Velocity Head in. H ₂ O	Stack Temp. °F	Cyclonic Flow °
1	1.592	128 135	
2	1.3	128 138	
3	1.4	128 142	
4	1.3 1.4	126 139	
5	1.3	136	
6	1.3	131	
7	1.4	131	
8	1.3	126	
1	0.96	128	
2	0.98 1.4	128 137	
3	0.96 1.3	129 134	
4	1.4	131	
5	1.3	135	
6	1.3	134	
7	1.2	131	
8	1.1	131	
Average:	$\sqrt{\Delta P} = 1.124$	T _s = 3	°C =

$$Md = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times N_2)$$

$$Md = (0.44 \times \underline{\hspace{1cm}}) + (0.32 \times \underline{\hspace{1cm}}) + (0.28 \times \underline{\hspace{1cm}})$$

$Md =$ _____

$$Ms = Md \times \left(1 - \frac{\%H_2O}{100}\right) + 18 \left(\frac{\%H_2O}{100}\right)$$

$$MS = \frac{\text{---}}{\text{---}} \times \left(1 - \frac{\text{---}}{100} \right) + 18 \left(\frac{\text{---}}{100} \right)$$

$$M_s = \underline{\hspace{2cm}}$$

$$T_s = \text{---} F + 460 = \text{---} R$$

$$P_s = P_{bar} + \frac{SP}{13.8} = \text{-----} + \frac{\text{-----}}{13.8}$$

$P_s = \text{-----in. Hg}$

$$\sqrt{\Delta P} = \underline{\hspace{2cm}}$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s(R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times \frac{1}{1000} \times \frac{1}{1000} \times \sqrt{\frac{1}{1000} \times \frac{1}{1000}}$$

$$V_s = \underline{\hspace{2cm}} \text{ ft / sec}$$

As = _____ sq. ft

$$Qa = Vs \times As \times 60s / m$$

$$Qa = \quad \times \quad \times 60$$

$Q_a =$ _____ *acfm*

$$Q_{std} = Q_a \times 17.647 \times \frac{Ps}{Ts} \times \left(1 - \frac{\%H_2O}{100}\right)$$

$$Qstd = \frac{\text{Area}_{std}}{\text{Area}_{int}} \times 17.647 \times \frac{\text{Conc}_{int}}{\text{Conc}_{std}} \times \left(\frac{1 - \frac{\text{Conc}_{int}}{100}}{\frac{\text{Conc}_{std}}{100}} \right)$$

$Q_{std} = \underline{\hspace{2cm}} \text{ dscfm}$

GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: Newport Steel

Date: 8/14/00

Sampling Location: Furnace Exhaust / Brandt Inlet

Clock Time: 1545

Run #: 00010

Operators: P4 / A...

Barometric Pressure, in Hg:

Static Pressure, "H₂O: - .44

TC #:

Pitot Tube #.:

Pitot Tube C_p : 0.64

Stack Dimension, in. Diameter or Side 1:

Side 2:

Wet Bulb, °F:

Dry Bulb, °F:

Fyrte 02:

CO₂:

Horizontal

Traverse Point #	Velocity Head in H ₂ O	Stack Temp. °F	Cyclonic Flow °
1	.91	158	
2	1.3	155	
3	1.5	160	
4	1.5	163	
5	1.3	156	
6	1.3	158	
7	1.2	148	
8	1.3	146	
Vertical			
1	1.2	151	
2	1.4	159	
3	1.4	165	
4	1.4	170	
5	1.4	174	
6	1.4	173	
7	1.5	174	
8	1.3	174	
Average: $\sqrt{\Delta P} = 1.1523$		Ts = 162	°C =

$$Md = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times N_2)$$

$$Md = (0.44 \times \underline{\hspace{1cm}}) + (0.32 \times \underline{\hspace{1cm}}) + (0.28 \times \underline{\hspace{1cm}})$$

$Md =$ _____

$$Ms = Md \times \left(1 - \frac{\%H_2O}{100}\right) + 18 \left(\frac{\%H_2O}{100}\right)$$

$$Ms = \text{-----} \times \left(1 - \frac{\text{-----}}{100}\right) + 18 \left(\frac{\text{-----}}{100}\right)$$

$$M_S =$$

$$T_s = \quad F + 460 = \quad R$$

$$P_s = P_{bar} + \frac{SP}{13.8} = \text{---} + \frac{\text{---}}{13.8}$$

$P_s = \text{-----in. Hg}$

$$\sqrt{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s(R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times \frac{1}{1000} \times \frac{1}{1000} \times \sqrt{\frac{1000}{1000}}$$

V_s _____ ft / sec

As = _____ sq. ft

$$Q_a = V_s \times A_s \times 60s / m$$

$Qa = \quad \times \quad \times 60$

$Q_a =$ $acfm$

$$Q_{std} = Q_a \times 17.647 \times \frac{P_s}{T_s} \times \left(1 - \frac{\%H_2O}{100}\right)$$

$$Q_{std} = \text{-----} \times 17.647 \times \text{-----} \times \left(1 - \frac{\text{-----}}{100}\right)$$

$$Q_{std} = \text{dscfm}$$

Average: $\sqrt{\Delta P} = 1.1523$	$T_s = 102$	$^{\circ}\text{C} =$
-------------------------------------	-------------	----------------------

FBT

MIDGET IMPINGER SAMPLING DATA SHEET

Company: Newport Steel Date: 8/16/00 DGM Orifice #: 5
 Sampling Site: BAF Exhaust / Brandt B.H. In Operator: PH DGM λ : 1.051
 Run #: 4 Leak $\checkmark$: Pre: / Probe Type:
 Sample Type: M6 / SO₂ Post: P_{BAR}: 30.02

SAMPLING PARAMETERS

* part @ 1501 / 70 min

Time		DGM (ft ³ or l)	Temp (°F)	Flow Rate	Time		(DGM)	T e e	Flow Rate
Clock	Sample				Clock	Sample			
1351	0	0	76	14/min	1501	70	2.516	76	14/min
	10	0.398	76	" "					
	20	0.764	76	" "					
	30	1.118	76	" "					
	40	1.511	77	" "					
	50	1.730	78	" "					
	60	2.101	78	" "					

Run Time: _____ (min) Meter Volume: _____ (ft³ or l) Average Meter Temp.: _____ (°F)

STACK GAS CONDITIONS DATA

Time: _____ Wet / Dry: _____ / _____ CO₂: _____ %
 P_s: _____ "H₂O Pitot # / C_s: _____ / _____ TC #: _____ O₂: _____ %

Point #	AP	T _s	Point #	ΔP	T _s

Avg. $\sqrt{\Delta P}$: _____ Average Stack Temp.: _____ (°F)

FBT

MIDGET IMPINGER SAMPLING DATA SHEET

Company: Newport Steel
Sampling Site: Bayhorse Inlet
Run#: 3
Sample Type: Sox Method 6

Date: 8-16-20 DGM/Orifice #: DGM #5

Operator: PH

DGM λ :

Leak ✓: Pre: ✓

Probe Type: TFE

Post:

P_{BAR}: 29.8

SAMPLING PARAMETERS

Time		DGM (ft ³ or l)	Temp (°F)	Flow Rate	Time		DGM (ft ³ or l)	Temp (°F)	Flow Rate
Clock	Sample				Clock	Sample			
0900	0	0.000	72	12pm	1010	70	3.244	72	12/min
	10	0.40	73	12pm	1020	80	3.446	72	12/min
	20	0.903	73	12pm		90	3.631	72	12/min
	30	1.220	73	12pm		100	3.863	72	12/min
	40	1.531	73	12pm		110	4.151	72	12/min
	50	1.750	73	12pm		120	4.057	73	11 min
1000	60	2.041	73	12/min					

Run Time: _____ (min) Meter Volume: _____ (ft³ or l) Average Meter Temp.: _____ (°F)

STACK GAS CONDITIONS DATA

Time:

Wet / Dry: /

CO₂: %

P,: ${}^2\text{H}_2\text{O}$

Pitot # / C_p: /

TC #: O₂: %

[illegible]

Avg. $\sqrt{\Delta P}$: _____ Average Stack Temp.: _____ (°F)

FBT

MIDGET IMPINGER SAMPLING DATA SHEET

Company: Newport Steel Date: 8-15-00 DGM/Orifice #: DGM #5
 Sampling Site: Bayhouse Inlet Operator: DW DGM λ : 1.051
 Run #: 2 Leak $\checkmark$: Pre: $\checkmark$ Probe Type: TFE
 Sample Type: SO₂ - Method 6 Post: _____ P_{BAR}: _____

SAMPLING PARAMETERS

Time		DGM (ft ³ or l)	Temp (°F)	Flow Rate	Time		DGM (ft ³ or l)	Temp (°F)	Flow Rate
Clock	Sample				Clock	Sample			
1501	0	0.000	84	12pm		70	2.57	86	12pm
	10	0.36	84	12pm		80	2.95	86	12pm
	20	0.73	85	12pm		90	3.31	86	12pm
	30	1.10	85	12pm		100	3.80	86	12pm
	40	1.45	86	12pm		110	4.08	86	12pm
	50	1.83	86	12pm		120	4.300	86	
	60	2.19	86	12pm					

Run Time: 120 (min) Meter Volume: 4.300 (A' or l) Average Meter Temp.: 85.6 (°F)

STACK GAS CONDITIONS DATA

Time: _____ Wet / Dry: I CO₂: _____ %
 P_S: _____ "H₂O Pitot # / C.: I TC #: _____ O₂: _____ %

Point #	ΔP	T _s	Point #	ΔP	T _s

Avg. $\sqrt{\Delta P}$: _____ Average Stack Temp.: _____ (°F)

FBT

MIDGET IMPINGER SAMPLING DATA SHEET

Company: Newport Steel Date: 8-15-00 DGM/Orifice #: DGM #5
 Sampling Site: Baghouse Inlet Operator: DW DGM λ: 1.051
 Run #: 1 Leak ✓: Pre: ☒ Probe Type: TFE
 Sample Type: SO₂ - Method 6 Post: _____ P_{BAR}: _____

SAMPLING PARAMETERS

Time		DGM	Temp	Flow	Time		DGM	Temp	Flow
Clock	Sample	(ft ³ or l)	(°F)	Rate	Clock	Sample	(ft ³ or l)	(°F)	Rate
1000	0	0.000	77	10pm		70	2.43	80	10pm
	10	0.400	79	10pm		80	2.83	80	10pm
	20	0.66	80	10pm		90	3.19	81	10pm
	30	1.00	81	10pm		100	3.54	82	10pm
	40	1.24	80	10pm		110	3.92	82	10pm
	50	1.60	80	10pm	1200	120	4.343	82	
	60	2.05	80	10pm					

Run Time: 120 (min) Meter Volume: 4.343 (ft³ or l) Average Meter Temp.: 80.3 (°F)

STACK GAS CONDITIONS DATA

Time: _____ Wet / Dry: _____ / _____ CO₂: _____ %
 P_s: _____ "H₂O Pitot # / C_s: _____ / _____ TC #: _____ O₂: _____ %

Point #	ΔP	T _s	Point #	ΔP	T _s

Avg. √ΔP: _____ Average Stack Temp.: _____ (°F)

FBT

APPENDIX E

STACK TEST CALCULATIONS

CLIENT/PROJECT #: Newport Steel
 SAMPLE LOCATION: Baghouse Exhaust
 DATE/TIME: 8/15/000814-1300
 RUN #: 1

STATIC PRESSURE("H ₂ O):	0	"HG	30.01
BAROMETRIC("Hg):	30.01		
SAMPLE TIME(min):	240	Vm(corr)	228.143
FINAL METER VOLUME:	228.143	DSCF	216.365
	0.040		
	2.53		
AVG STACK TEMP °F:	144.0	°R	604.0
AVG METER TEMP °F:	98.0		
Cp PITOT :	0.84		
NOZZLE DIA.(inches):	1.130	An(ft ²)	6.96--03
METER GAMMA:	0.993		
LEAK RATE(IF<0.02):			
CIRC STACK? 1=Y, 0=N:	0	As(ft ²)	5511.50
DIA OR DIM (inches):	793656.00		
% O ₂ :	20.58	Dry Mole Wt	28.8744
% CO ₂ :	0.32	Stack Mole Wt	28.6225099
VOL CONDENSATE(ml):	109	% H ₂ O	2.32
PARTICULATE(mg):	6.606		
LEAD(μg):	49.00		

***** CALCULATED RESULTS *****

STACK GAS CONDITIONS

Velocity (Vs):	24	ft/sec
Volumetric Flow Rate (Qa):	796.539	acfm
(Qstd):	682.227	dscfm
Stack Gas Temp :	144	° F
Moisture (%H ₂ O):	2.3	%
%O ₂ :	20.6	%
%CO ₂ :	0.3	%
Isokinetic Sampling Rate:	104.6	%

PARTICULATE EMISSIONS DATA

PM Concentration (Cs):	4.70E-04	gr/dscf
	6.72E-08	lb/dscf
PM Emission Rate (Er):	2.75E+00	lb/hr

LEAD EMISSIONS DATA

LEAD Concentration (Cs):	3.49E-06	gr/dscf
	4.98E-10	lb/dscf
LEAD Emission Rate (Er):	2.04E-02	lb/hr

Comments:

CLIENT/PROJECT #: Newport Steel
 SAMPLE LOCATION: Baghouse Exhaust
 DATE/TIME: 8/15/00 1345-1828
 RUN #: 2

STATIC PRESSURE("H ₂ O):	0	"HG	30.01
BAROMETRIC("Hg):	30.01		
SAMPLE TIME(min):	240	Vm(corr)	222.792
ACTUAL METER VOLUME:	222.792	DSCF	205.759
Average $\sqrt{\Delta P}$:	0.040		
AVG ORIFICE AH:	2.53		
AVG STACK TEMP °F:	122.0	°R	582.0
AVG METER TEMP °F:	113.0		
Cp PITOT :	0.84		
NOZZLE DIA.(inches):	1.130	An(ft ²)	6.96E-03
METER GAMMA:	0.993		
LEAK RATE(IF<0.02):			
CIRC STACK? 1=Y,0=N:	0	As(ft ²)	5511.50
DIA OR DIM (inches):	793656.00		
% O ₂ :	20.68	Dry Mole Wt	28.896
% CO ₂ :	0.43	Stack Mole Wt	28.6690172
VOL CONDENSATE(ml):	93	% H ₂ O	2.08
PARTICULATE(mg):	26.475		
LEAD(μg):	65.00		

***** CALCULATED RESULTS *****

STACK GAS CONDITIONS

Velocity (Vs):	24	ft/sec
Volumetric Flow Rate (Qa):	781,264	acfm
(Qstd):	696,096	dscfm
Stack Gas Temp :	122	°F
Moisture (%H ₂ O):	2.1	%
%O ₂ :	20.7	%
%CO ₂ :	0.4	%
Isokinetic Sampling Rate:	97.5	%

PARTICULATE EMISSIONS DATA

PM Concentration (Cs):	1.98E-03	gr/dscf
	2.83E-07	lb/dscf
PM Emission Rate (Er):	1.18E+01	lb/hr

LEAD EMISSIONS DATA

LEAD Concentration (Cs):	4.86E-06	gr/dscf
	6.95E-10	lb/dscf
LEAD Emission Rate (Er):	2.90E-02	lb/hr

Comments:

FBT

CLIENT/PROJECT #: Newport Steel
 SAMPLE LOCATION: Baghouse Exhaust
 DATE/TIME: 8/16/00 0754-1214
 RUN #: 3

STATIC PRESSURE("H ₂ O):	0	"HG	30.01
BAROMETRIC("Hg):	30.01		
SAMPLE TIME(min):	240	Vm(corr)	206.621
ACTUAL METER VOLUME:	206.621	DSCF	197.711
Average $\sqrt{\Delta P}$:	0.040		
AVG ORIFICE AH:	2.50		
AVG STACK TEMP °F:	165.0	°R	625.0
AVG METER TEMP °F:	93.0		
Cp PITOT :	0.84		
NOZZLE DIA.(inches):	1.130	An(ft ²)	6.96E-03
METER GAMMA:	0.993		
LEAK RATE(IF<0.02):			
CIRC STACK? 1=Y,0=N:	0	As(ft ²)	5511.50
DIA OR DIM (inches):	793656.00		
% O ₂ :	20.43	Dry Mole Wt	28.8716
% CO ₂ :	0.34	Stack Mole Wt	28.673397
VOL CONDENSATE(ml):	78	% H ₂ O	1.82
PARTICULATE(mg):	2.575		
LEAD(μg):	38.00		

***** CALCULATED RESULTS *****

STACK GAS CONDITIONS

Velocity (Vs):	24 ft/sec
Volumetric Flow Rate (Qa):	809,549 acfm
(Qstd):	673,456 dscfm
Stack Gas Temp :	165 °F
Moisture (%H ₂ O):	1.8 %
%O ₂ :	20.4 %
%CO ₂ :	0.3 %
Isokinetic Sampling Rate:	96.9 %

PARTICULATE EMISSIONS DATA

PM Concentration (Cs):	2.01E-04 gr/dscf
	2.87E-08 lb/dscf
PM Emission Rate (Er):	1.16E+00 lb/hr

LEAD EMISSIONS DATA

LEAD Concentration (Cs):	2.96E-06 gr/dscf
	4.23E-10 lb/dscf
LEAD Emission Rate (Er):	1.71E M lb/hr

Comments:

CLIENT/PROJECT #: Newport Steel
 SAMPLE LOCATION: Baghouse Exhaust
 DATE/TIME: 8/16/00 1239-1500
 RUN #: 4

STATIC PRESSURE("H ₂ O):	0	"HG	30.01
BAROMETRIC("Hg):	30.01		
SAMPLE TIME(min):	180	Vm(corr)	107.625
ACTUAL METER VOLUME:	107.625	DSCF	101.335
Average $\sqrt{\Delta P}$:	0.040		
AVG ORIFICE AH:	2.50		
AVG STACK TEMP °F:	188.0	*R	648.0
AVG METER TEMP °F:	102.0		
Cp PITOT :	0.84		
NOZZLE DIA.(inches):	1.130	An(ft ²)	6.96E-03
METER GAMMA:	0.993		
LEAK RATE(IF<0.02):			
CIRC STACK? 1=Y,0=N:	0	As(ft ²)	5511.50
DIA OR DIM (inches):	793656.00		
% O ₂ :	20.66	Dry Mole Wt	28.8872
% CO ₂ :	0.38	Stack Mole Wt	28.6545944
VOL CONDENSATE(ml):	47	% H ₂ O	2.14
PARTICULATE(mg):	0.55		
LEAD(μg):	13.00		

***** CALCULATED RESULTS *****

STACK GAS CONDITIONS

Velocity (Vs):	25	ft/sec
Volumetric Flow Rate (Qa):	824,580	acfm
(Qstd):	659,501	dscfm
Stack Gas Temp :	188	° F
Moisture (%H ₂ O):	2.1	%
%O ₂ :	20.7	%
%CO ₂ :	0.4	%
Isokinetic Sampling Rate:	67.6	%

PARTICULATE EMISSIONS DATA

PM Concentration (Cs):	8.36E-05	gr/dscf
	1.19E-08	lb/dscf
PM Emission Rate (Er):	4.73E-01	lb/hr

LEAD EMISSIONS DATA

LEAD Concentration (Cs):	1.98E-06	gr/dscf
	2.82E-10	lb/dscf
LEAD Emission Rate (Er):	1.12E-02	lb/hr

Comments:

CLIENT/PROJECT #: Newport Steel
 SAMPLE LOCATION: EAF Exhaust/Brandt Inlet
 DATE/TIME: 8/15/00 0814-1214
 RUN #: 1

DATA INPUT

STATIC PRESSURE("H ₂ O):	-3.80	"Hg	29.73
BAROMETRIC("Hg):	30.01		
Cp PITOT :	0.84		
AVG. $\sqrt{\Delta P}$:	1.124		
AVG STACK TEMP °F:	134.0	°R	594.0
CIRC STACK? 1=Y,0=N:	1		
DIA OR DIM (inches):	185.50	As(ft ²)	1.88E+02
% O ₂ :	20.54	Dry Mole Wt	28.83
% CO ₂ :	0.07	Stack Mole Wt	28.58

Moisture Data

ACTUAL METER VOLUME:	228.14		
AVG. METER TEMP (OF):	98.00	Volstd (dscf)	216.365
AVG ORIFICE AH:	2.53		
METER "γ":	0.99		
VOL CONDENSATE(ml):	109.00	H ₂ O %	2.32
DRY BULB TEMP:			
WET BULB TEMP:		VP ("Hg)	#N/A

NO_x as NO₂

CALIBRATION :	
PPM :	8.86
CALIBRATION :	Carbon Monoxide
PPM :	55.28

CALCULATED DATA

STACK GAS DATA

GAS VELOCITY (Vs):	67.48	ft/sec
STACK GAS FLOW (Qs):	759,930	acfm
	671,215	dscfm
STACK GAS TEMP :	134	° F
MOISTURE (%H ₂ O):	2.3	%

Emission Data for:

NO_x

CONCENTRATION (Cs):	6.89E-07	lbldscf
	9	ppm
EMISSION RATE (Er):	2.78E+01	lb/hr

Emission Data for:

CO

CONCENTRATION (Cs):	4.02E-06	lbldscf
	55	ppm
EMISSION RATE (Er):	1.62E+02	lb/hr

Comments:

CLIENT/PROJECT #:	Newport Steel
SAMPLE LOCATION:	EAF Exhaust/Brandt Inlet
DATE/TIME:	8/15/00 1532-1754
RUN #:	2

DATA INPUT

STATIC PRESSURE("H ₂ O):	-4.70	"Hg	29.66
BAROMETRIC("Hg):	30.01		
Cp PITOT :	0.84		
AVG. $\sqrt{\Delta P}$:	1.126		
AVG STACK TEMP °F:	125.0	°R	585.0
CIRC STACK? 1=Y,0=N:	1		
DIA OR DIM (inches):	185.50	As(ft ²)	1.88E+02
% O ₂ :	20.58	Dry Mole Wt	28.86
% CO ₂ :	0.24	Stack Mole Wt	28.64

Moisture Data

ACTUAL METER VOLUME:	222.79		
AVG. METER TEMP (°F):	113.00	Volstd (dscf)	205.759
AVG ORIFICE AH:	2.53		
METER "γ":	0.99		
VOL CONDENSATE(ml):	93.00	H ₂ O %	2.08
DRY BULB TEMP:			
WET BULB TEMP:		VP ("Hg)	#N/A

NO_x as NO₂

CALIBRATION:	8.14
PPM :	
CALIBRATION:	93.73
PPM :	

Carbon Monoxide

CALCULATED DATA

STACK GAS DATA

GAS VELOCITY (Vs):	67.09	ft/sec
STACK GAS FLOW (Qs):	755,427	acfm
	675,995	dscfm
STACK GAS TEMP :	125	° F
MOISTURE (%H ₂ O):	2.1	%

Emission Data for:

NO_x

CONCENTRATION (Cs):	9.72E-07	lbldscf
	8	ppm
EMISSION RATE (Er):	39.40	lb/hr

Emission Data for:

CO

CONCENTRATION (Cs):	6.81E-06	lb/dscf
	94	ppm
EMISSION RATE (Er):	276.13	lb/hr

Comments:

CLIENT/PROJECT #:	Newport Steel
SAMPLE LOCATION:	EAF Exhaust/Brandt Inlet
DATE/TIME:	8/16/00 0900
RUN #:	3

DATA INPUT

STATIC PRESSURE("H ₂ O):	-4.10	"Hg	29.71
BAROMETRIC("Hg):	30.01		
Cp PITOT:	0.84		
AVG. $\sqrt{\Delta P}$:	1.066		
AVG STACK TEMP °F:	184.0	°R	644.0
CIRC STACK? 1=Y,0=N:	1		
DIA OR DIM (inches):	185.50	As(ft ²)	1.88E+02
% O ₂ :	20.43	Dry Mole Wt	28.87
% CO ₂ :	0.34	Stack Mole Wt	28.67

Moisture Data

ACTUAL METER VOLUME:	206.62		
AVG. METER TEMP (OF):	93.00	Volstd (dscf)	197.711
AVG ORIFICE AH:	2.50		
METER "γ":	0.99		
VOL CONDENSATE(ml):	78.00	H ₂ O %	1.82
DRY BULB TEMP:			
WET BULB TEMP:		VP ("Hg)	#N/A

NO_x as NO₂

CALIBRATION:	
PPM:	9.11

Carbon Monoxide

CALIBRATION:	
PPM:	118.93

CALCULATED DATA

STACK GAS DATA

GAS VELOCITY (Vs):	66.56	ft/sec
STACK GAS FLOW (Qs):	749,516	acfrn
	610,165	dscfrn
STACK GAS TEMP:	184	°F
MOISTURE (%H ₂ O):	1.8	%

Emission Data for:

NO_x

CONCENTRATION (Cs):	1.09E-06	lbldscf
	9	ppm
EMISSION RATE (Er):	39.81	lb/hr

Emission Data for:

CO

CONCENTRATION (Cs):	8.64E-06	lbldscf
	119	ppm
EMISSION RATE (Er):	316.24	lb/hr

Comments:

CLIENT/PROJECT #:	Newport Steel
SAMPLE LOCATION:	EAF Exhaust/Brandt Inlet
DATE/TIME:	8/17/00 1309-1509
RUN #:	4

DATA INPUT

STATIC PRESSURE("H ₂ O):	-4.20	"Hg	29.70
BAROMETRIC("Hg):	30.01		
Cp PITOT :	0.84		
AVG. $\sqrt{\Delta P}$:	1.105		
AVG STACK TEMP °F:	148.0	°R	608.0
CIRC STACK? 1=Y,0=N:	1		
DIA OR DIM (inches):	185.50	As(ft ²)	1.88E+02
% O ₂ :	20.50	Dry Mole Wt	28.85
% CO ₂ :	0.20	Stack Mole Wt	28.63

Moisture Data

ACTUAL METER VOLUME:			
AVG. METER TEMP (OF):		Volstd (dscf)	0.000
AVG ORIFICE AH:			
METER "γ":			
VOL CONDENSATE(ml):		H ₂ O %	2.07
DRY BULB TEMP:			
WET BULB TEMP:		VP ("Hg)	#N/A

NO_x as NO₂

CALIBRATION :	
PPM :	10.30
CALIBRATION :	Carbon Monoxide
PPM :	96.00

CALCULATED DATA

STACK GAS DATA

GAS VELOCITY (Vs):	67.11	Wsec
STACK GAS FLOW (Qs):	755,747	acfm
	651,504	dscfm
STACK GAS TEMP :	148	° F
MOISTURE (%H ₂ O):	2.1	%

Emission Data for:

NO_x

CONCENTRATION (Cs):	1.23E-06	lbldscf
	10	ppm
EMISSION RATE (Er):	48.05	lb/hr

Emission Data for:

CO

CONCENTRATION (Cs):	6.97E-06	lbldscf
	96	ppm
EMISSION RATE (Er):	272.57	lb/hr

Comments:

CLIENT/PROJECT #: Newport Steel
 SAMPLE LOCATION: Baghouse Exhaust
 DATE/TIME: 8/15/00 0814-1300
 RUN #: 1

STATIC PRESSURE("H2O):	0	"HG	30.01
BAROMETRIC("HG):	30.01		
SAMPLE TIME(min):	240	Vm(corr)	228.143
ACTUAL METER VOLUME:	228.143	DSCF	216.365
SQ. ROOT AP:	0.040		
AVG ORIFICE AH:	2.53		
AVG STACK TEMP °F:	144.0	°R	604.0
AVG METER TEMP °F:	98.0		
Cp PITOT :	0.84		
NOZZLE DIA(inches):	1.130	An(ft^2)	6.96E-03
METER GAMMA:	0.993		
LEAK RATE(IF<0.02):			
CIRC STACK? 1=Y,0=N:	0	As(ft^2)	5511.50
DIA OR DIM (inches):	793656.00		
% O2 :	21.00	DRY MOLE WT	28.84
% CO2 :	0.00	ST MOLE WT	28.588907
VOL CONDENSATE(mi):	109	% H2O	2.32
FILTER GAIN (mg):			
RINSE GAIN(mg):		NET WT(mg)	0
F-FACTOR(DSCF/mmBtu):			
FUEL AS REC'D(Btu/lb):			
FUEL FEED RATE(lb/hr):			

SO2 DATA:

SAMPLE VOLUME(ml):	98.5
ALIQOT VOLUME(ml):	20
TITRANT NORMALITY:	0.1
SAMPLE TITRANT (ml):	0.1
BLANK TITRANT (ml):	0.1

*****CALCULATED RESULTS*****

Stack Gas Conditions

VELOCITY (Vs):	2.41	FT/SEC
VOLUMETRIC FLOW RATE(Qs):	797007.4	ACFM
	682628.1	DSCFM
TEMPERATURE :	144	Deg F
H2O:	2.3	%
O2:	21.0	%
CO2:	0.0	%
HEAT INPUT RATE:	#DIV/0!	mmBTU/hr
EXCESS AIR	0.00	%
ISOKINETIC SAMPLING RATE:	104.58	%

Particulate Matter Emissions

CONCENTRATION (Cs):	#N/A	gr/dscf
	#N/A	lb/dscf
EMISSION RATE (Er):	#N/A	lb/hr
	#N/A	lb/mmBTU
F-FACTOR EMISSIONS:	#N/A	lb/mmBTU

SO2 Emissions

CONCENTRATION (Cs):	0	ppm
	0.00E+00	lb/DSCF
EMISSION RATE (Er):	0.00	lb/hr
	#REF!	lb/mmBTU
COMMENTS:		

CLIENT/PROJECT #: 8/15/00 0814-1300
 SAMPLE LOCATION: Baghouse Exhaust
 DATE/TIME: 8/15/00 1345-1828
 RUN #: 2

STATIC PRESSURE("H2O):	0	"HG	30.01
BAROMETRIC("HG):	30.01		
SAMPLE TIME(min):	240	Vm(corr)	222.792
ACTUAL METER VOLUME:	222.792	DSCF	205.759
SQ. ROOT AP:	0.040		
AVG ORIFICE AH:	2.53		
AVG STACK TEMP °F:	122.0	°R	582.0
AVG METER TEMP °F:	113.0		
Cp PITOT:	0.84		
NOZZLE DIA.(inches):	1.130	An(R^2)	6.96E-03
METER GAMMA:	0.993		
LEAK RATE(IF<0.02):			
CIRC STACK? 1=Y,0=N:	0	As(R^2)	5511.50
DIA OR DIM (inches):	793656.00		
% O2:	21.00	DRY MOLE WT	28.84
% CO2:	0.00	ST MOLE WT	28.614184
VOL CONDENSATE(ml):	93	% H2O	2.08
FILTER GAIN (rng):			
RINSE GAIN(mg):		NET WT(mg)	0
F-FACTOR(DSCF/mmBtu):			
FUEL AS REC'D(Btu/lb):			
FUEL FEED RATE(lb/hr):			

SO2 DATA:

SAMPLE VOLUME(ml):	95.5
ALiquot VOLUME(ml):	20
TITRANT NORMALITY:	0.01
SAMPLE TITRANT (ml):	0.1
BLANK TITRANT (ml):	0.1

*****CALCULATED RESULTS*****

Stack Gas Conditions

VELOCITY (Vs):	2.36	FT/SEC
VOLUMETRIC FLOW RATE(Qs):	782012.1	ACFM
	696762.4	DSCFM
TEMPERATURE:	122	Deg F
H2O:	2.1	%
O2:	21.0	%
CO2:	0.0	%
HEAT INPUT RATE:	#DIV/0!	mmBTU/hr
EXCESS AIR	0.00	%
ISOKINETIC SAMPLING RATE:	97.43	%

Particulate Matter Emissions

CONCENTRATION(Cs):	#N/A	gr/dscf
	#N/A	lb/dscf
EMISSION RATE (Er):	#N/A	lb/hr
	#N/A	lb/mmBTU
F-FACTOR EMISSIONS:	#N/A	lb/mmBTU

SO2 Emissions

CONCENTRATION(Cs):	0	ppm
	0.00E+00	lb/DSCF
EMISSION RATE (Er):	0.00	lb/hr
	#REF!	lb/mmBTU

COMMENTS:

CLIENT/PROJECT #: Newport Steel
 SAMPLE LOCATION: Baghouse Exhaust
 DATE/TIME: 8/16/00 0754-1214
 RUN #: 3

STATIC PRESSURE("H2O): 0 "HG 30.01
 BAROMETRIC("HG): 30.01
 SAMPLE TIME(min): 240 Vm(corr) 206.621
 ACTUAL METER VOLUME: 206.621 DSCF 197.711
 SQ. ROOT AP: 0.040
 AVG ORIFICE AH: 2.50
 AVG STACK TEMP °F: 165.0 °R 625.0
 AVG METER TEMP °F: 93.0
 Cp PITOT : 0.84
 NOZZLE DIA.(inches): 1.130 An(ft²) 6.96E-03
 METER GAMMA: 0.993
 LEAK RATE(IF<0.02):
 CIRC STACK? 1=Y,0=N: 0 As(ft²) 5511.50
 DIA OR DIM (inches): 793656.00
 % O2 : 21.00 DRY MOL 28.84
 % CO2 : 0.00 OLE WT 28.642373
 VOL CONDENSATE(ml): 78 % H2O 1.82
 FILTER GAIN (mg):
 RINSE GAIN(mg): NET WT(mg) 0
 F-FACTOR(DSCF/mmBtu):
 FUEL AS REC'D(Btu/lb):
 FUEL FEED RATE(lb/hr):

SO2 DATA:

SAMPLE VOLUME(ml): 62
 ALIQUOT VOLUME(ml): 20
 TITRANT NORMALITY: 0.01
 SAMPLE TITRANT (ml): 0.2
 BLANK TITRANT (ml): 0.1

*****CALCULATED RESULTS*****

Stack Gas Conditions

VELOCITY (Vs): 2.45 FT/SEC
 VOLUMETRIC FLOW RATE(Qs): 809987.2 ACFM
 673820.5 DSCFM
 TEMPERATURE : 165 Deg F
 H2O: 1.8 %
 O2: 21.0 %
 CO2: 0.0 %
 HEAT INPUT RATE: #DIV/0! mBTU/hr
 EXCESS AIR #N/A %
 ISOKINETIC SAMPLING RATE: 96.81 %

Particulate Matter Emissions

CONCENTRATION (Cs): #N/A gr/dscf
 #N/A lb/dscf
 EMISSION RATE (Er): #N/A lb/hr
 #N/A lb/mmBTU
 F-FACTOR EMISSIONS: #N/A lb/mmBTU

SO2 Emissions

CONCENTRATION (Cs): 0 ppm
 1.11E-09 lb/DSCF
 EMISSION RATE (Er): 0.04 lb/hr
 #REF! lb/mmBTU
 COMMENTS:

CLIENT/PROJECT #: #REF!
 SAMPLE LOCATION: #REF!
 DATE/TIME: 8/16/00 1239-1500
 RUN #: 4

STATIC PRESSURE("H2O): 0 'HG 30.01
 BAROMETRIC("HG): 30.01
 SAMPLE TIME(min): 180 Vm(corr) 107.625
 ACTUAL METER VOLUME: 107.625 DSCF 101.335
 SQ. ROOT AP: 0.040
 AVG ORIFICE AH: 2.50
 AVG STACK TEMP °F: 188.0 °R 648.0
 AVG METER TEMP °F: 102.0
 Cp PITOT : 0.84
 NOZZLE DIA.(inches): 1.130 An(ft^2) 6.96E-03
 METER GAMMA: 0.993
 LEAK RATE(IF<0.02):
 CIRC STACK? 1=Y,0=N: 0 As(ft^2) 5511.50
 DIA OR DIM (inches): 793656.00
 % O2 : 21.00 DRY MOL 28.84
 % CO2 : 0.00 OLE WT 28.608403
 VOL CONDENSATE(ml): 47 % H2O 2.14
 FILTER GAIN (mg):
 RINSE GAIN(mg): NET WT(mg) 0
 F-FACTOR(DSCF/mmBtu):
 FUEL AS REC'D(Btu/lb):
 FUEL FEED RATE(lb/hr):

SO2 DATA:

SAMPLE VOLUME(ml): 65
 ALIQUOT VOLUME(ml): 20
 TITRANT NORMALITY: 0.01
 SAMPLE TITRANT (ml): 0.1
 BLANK TITRANT (ml):

*****CALCULATED RESULTS*****

Stack Gas Conditions

VELOCITY (Vs): 2.50 FT/SEC
 VOLUMETRIC FLOW RATE(Qs): 825245.9 ACFM
 660033.5 DSCFM
 TEMPERATURE : 188 Deg F
 H2O: 2.1 %
 O2: 21.0 %
 CO2: 0.0 %
 HEAT INPUT RATE: #DIV/0! mBTU/hr
 EXCESS AIR #N/A %
 ISOKINETIC SAMPLING RATE: 67.54 %

Particulate Matter Emissions

CONCENTRATION (Cs): #N/A gr/dscf
 #N/A lb/dscf
 EMISSION RATE (Er): #N/A lb/hr
 #N/A lb/mmBTU
 F-FACTOR EMISSIONS: #N/A lb/mmBTU

SO2 Emissions

CONCENTRATION (Cs): 0 ppm
 2.26E-09 lb/DSCF
 EMISSION RATE (Er): 0.09 lb/hr
 #REF! lb/mmBTU

COMMENTS:

APPENDIX B

Analytical Data

PROJECT ANALYTICAL SHEET FOR PARTICULATE MATTER

PROJECT NAME:

PROJECT DATE:

PROJECT MANAGER:

NUMBEROFSITES:

[illegible]

ANALYZED BY:

REVEIWD BY



A SOREINSON COMPANY

TEST REPORT
Page 1 of 2
9/6/00

Submitted To:

Pete Hilty
FBT Testing & Environmental Services
7419 Kingsgate Way, Suite D
West Chester, OH
45069

Reference Data:

SO₂
Sample Location: Newport Steel 531
Sample Type: Liquid
Client Sample No.: 591-6 through 591-10
PO #: 00-055
Method Reference: EPA Method 6
Sample Set ID#: 00-W-4623
DATACHEM Lab No.: 00-27029 through 00-27033
Analysis Date: 9/6/00

The samples were analyzed in accordance with EPA method 6.

The results are provided in the enclosed data table

Results relate only to the items tested.

This report shall not be reproduced except in full, without the written approval of the laboratory.

Rob Nieman
Analyst

Reviewer

CINCINNATI OFFICE
4388 GLENDALE-MILFORD ROAD
CINCINNATI, OHIO 45242-3706
513 733-5336, FAX 513 733-5347

WEST COAST OFFICE
11 SANTA YORBA COURT
NOVATO, CALIFORNIA 94945
800 280-0071, FAX 415 893 9469


TEST REPORT
Page 2 of 2
00-W-4623

SO₂ Results

Client #	DCL #	Sampler Vol. (mL)	Aliquot Vol. (mL)	Titrant Normality	Sample Titrant (mL)
591-6	00-27029	98.5	20	0.0100	0.1
591-7	00-27030	95.5	20	0.0100	0.1
591-8	00-27031	62.	20	0.0100	0.2
591-9	00-27032	65.	20	0.0100	0.1
591-10	00-27033	81.	20	0.0100	0.1

Note: Sample titrant used for prep blank = 0.1 mL.

Rob Nieman
Analyst



Reviewer

00-ww-4623
ANALYTICAL REQUEST &
CHAIN OF CUSTODY

FBT Testing & Environmental Services

7419 Kingsgate Way, Suite D

West Chester, Ohio 45069

(513)755-1717 Fax:(513) 755-1770

LABORATORY

Datachem Laboratories

4388 Glendale-Milford Road

Cincinnati, Ohio 45242-3706

DATE SHIPPED August 22, 2000	# OF SAMPLES 10 (14)	SAMPLE TYPE Mixed	PROJECT NAME & NUMBER Newport Steel 591
PO# 00-055	CONTACT PERSON Pete Hilty		

COMMENTS/SPECIAL INSTRUCTIONS:**PRIORITY****SAMPLE
RETURN**NORMAL
XXX

RUSH

EMERG
RUSH

YES

NO
XX

SAMPLE#	SAMPLE DATE	CONTAINER DESCRIPTION	ANALYSES REQUESTED
591-1A/B/C though 591-5A/C	8/15-17/00	Mixed	00-27024-27028 Lead by USEPA Method 12
591-6, 7, 8, 9, 10	8/15-17/00	250 ml HDPE	00-27029-33 SO ₂ by USEPA Method 6

CHAIN OF CUSTODY REQUESTSAMPLES DELIVERED BY: U.S. MAIL ____ FEDEX/UPS ____ COURIER X OTHER ____

DATE	PURPOSE FOR CUSTODY CHANGE	RELINQUISHED BY: (SIGNATURE)	RECEIVED BY: (SIGNATURE)
August 22, 2000	Analysis	<i>Chris L. Johnson</i>	<i>Chris L. Johnson</i> DCL

FBT



TEST REPORT
Page 1 of 2
9/15/00

Submitted To: Fete Hilty
FBT Testing & Environmental Services
7419 Kingsgate Way, Suite D
West Chester, OH 45069

Reference Data:	Lead
Client Sample No.:	591-1A/B/C through 591-5A/B/C
P.O. No.:	00-055
Sample Location:	Newport Steel 591
Sample Type:	Filter / Impinger / Rinse
Method Reference:	EPA Method 12
DCL Set ID No.:	00-S-4623
DCL Sample ID No.:	00-27024 through 00-27028
Sample Receipt Date:	3/23/2000
Preparation Date:	09/08/00
Analysis Date:	09/15/00

The samples were prepared and analyzed in accordance with EPA method 12 using a Perkin Elmer 3000XL (ICP) purged spectrometer.

Results relate only to the items tested.

The results are in the enclosed data table.

This report shall not be reproduced except in full, without the written approval of the Laboratory.

Chris Baugues
Analyst.

Reviewer

CINCINNATI OFFICE
4388 GLENDALE-MILFORD ROAD
CINCINNATI, OHIO 45242-3706
513 733-5306, FAX 513 733-5347

WEST COAST OFFICE
11 SANTA YRMA COURT
NOVATO, CALIFORNIA 94945
800 280 8071, FAX 415 893 9463

TEST REPORT
Page 2 of 2
00-S-4623


Lead Results
µg/Sample

Client #	DCL #	Pb
591-1A/B/C	00-27024	49.
591-2A/B/C	00-27025	65.
591-3A/B/C	00-27026	38.
591-4A/B/C	00-27027	13.
591-5A/B/C	00-27028	ND
	Prep Blank	ND
% Recovery	LCS	91.
Reporting Limit		5.

ND indicates the value is below the Reporting Limit.



Chris Baugues
Analyst



Reviewer

00-ww-4623

ANALYTICAL REQUEST & CHAIN OF CUSTODY



FBT Testing & Environmental Services 7419 Kingsgate Way, Suite D West Chester, Ohio 45060 (513) 755-1717 Fax: (513) 755-1770	LABORATORY Datachem Laboratories 4388 Glendale-Milford Road Cincinnati, Ohio 45242-3706
--	---

DATE SHIPPED August 22, 2000	# OF SAMPLES 10 (14)	SAMPLE TYPE Mixed	PROJECT NAME & NUMBER Newport Steel 591
PO# 00-055	CONTACT PERSON Pete Hilty		

COMMENTS/SPECIAL INSTRUCTIONS:	PRIORITY			SAMPLE RETURN	
	NORMAL XXX	RUSH	EMERG RUSH	YES	NO XX

SAMPLE #	SAMPLE DATE	CONTAINER DESCRIPTION	ANALYSES REQUESTED
591-1A/B/C though 591-5A/C	8/15-17/00	Mixed	00-27024-27028 Lead by USEPA Method 12
591-6, 7, 8, 9, 10	8/15-17/00	250 ml HDPE	00-27029-33 SO ₂ by USEPA Method 6

CHAIN OF CUSTODY REQUEST

SAMPLES DELIVERED BY: U.S. MAIL ___ FEDEX/UPS ___ COURIER <u>X</u> OTHER ___			
DATE	PURPOSE FOR CUSTODY CHANGE	RELINQUISHED BY: (SIGNATURE)	RECEIVED BY: (SIGNATURE)
August 22, 2000	Analysis		

FBT

APPENDIX F
CALIBRATION DATA

QUALITY ASSURANCE/QUALITY CONTROL

This section describes the specific QA/QC procedures employed by FBT in performing this series of tests. The goal of the QA/QC activities for this project are intended to ensure, to the highest degree possible, the accuracy of the data collected. The procedures contained in the "Quality Assurance Handbook for Air Pollution Measurement Systems," "Volume III, Stationary Source Specific Methods," EPA-600/77-027B serve as the basis for performance for all testing and related work activities.

CALIBRATION OF APPARATUS:

The preparation and calibration of source sampling equipment is essential in maintaining data quality. Brief descriptions of the calibration procedures used by FBT follow:

Barometers

FBT uses aneroid barometers which are calibrated against a National Weather Service-Type mercurial barometer.

Temperature Sensors

Bimetallic dial thermometers and Type "K" thermocouples are calibrated using the procedure described in Section 3.4.2 of the Quality Assurance Handbook. Each temperature sensor is calibrated over the expected range of use against an ASTM 3C or 3F thermometer.

Pitot Tubes

FBT uses Type "S" pitot tubes which are constructed according to EPA Method 2 specifications. Pitot tubes meeting these criteria are assigned a baseline coefficient of 0.84 and need not be calibrated.

Differential Pressure Gauges

FBT uses Dwyer inclined/vertical manometers to measure differential pressures. These include velocity pressure, static pressure, and meter orifice pressure. Manometers are selected with sufficient sensitivity to accurately measure pressures over the entire range of expected values. Manometers are primary standards and require no calibration.

Dry Gas Meters and Orifices

Dry gas meters and orifices are calibrated in accordance with Section 3.3.2 of the Quality Assurance Handbook. This procedure involves direct comparison of the dry gas meter to a reference wet test meter. The reference wet test meter is routinely calibrated against a bell prover. Before its initial use in the field, the metering system is calibrated over the entire range of operation. After each field use, the metering system is calibrated at a single intermediate setting based on the previous field test. Acceptable tolerances for the initial and final dry gas meter factors and orifice calibration factors are ± 0.02 and ± 0.20 from average, respectively.

QA/QC (cont.)

THE ON-SITE QA/QC ACTIVITIES INCLUDED:

Measurement Sites

Prior to sampling, all measurements were checked dimensionally to determine measurement site locations, location of test ports, and stack inside dimensions. Inside dimensions were checked through all available rest ports to ensure uniformity of the stack cross-sectional area.

Velocity Measurements

All velocity measurement apparatus was assembled, leveled, zeroed, and leak checked prior to each test run. The static pressure was determined at a single point near the center of the stack .

Flue Gas Component Sampling

During sampling, Fyrite combustion gas analyzers were used to determine percent concentrations of carbon dioxide and oxygen.

Moisture


Stack gas moisture was determined simultaneously with particulate matter. During sampling, the exit gas of the last impinger was maintained below 68°F to ensure complete condensation of the stack gas water vapor. The total moisture was determined gravimetrically.

Sample Trains


The sample trains were assembled, equilibrated to required temperatures and leak checked prior to testing. The nozzle size was determined in the field by making triplicate measurements along three different diameters using a dial caliper. The three measurements must vary no more than 0.004 inches between the high and low numbers.

At the conclusion of each test run, the sample trains were leak checked at the highest vacuum attained during the test run. Acceptable leakage rates are 0.02 cfm or 4 percent of the average sampling rate (whichever is less).

TEMPERATURE SENSOR CALIBRATION




TEMPERATURE SENSOR CALIBRATION



FBT

TEMPERATURE SENSOR CALIBRATION



FBT Testing & Environmental Services

METHOD 5 DRY GAS METER CALIBRATION USING CRITICAL ORIFICES

- 1) Select three critical orifices to calibrate the dry gas meter which bracket the expected operating range.
- 2) Record barometric pressure before and after calibration procedure.
- 3) Run at tested vacuum (from Orifice Calibration Report), for a period of time necessary to achieve a minimum total volume of 5 cubic feet.

CLIENT: Newport Steel

CRITICAL ORIFICE SET SERIAL #: 1355

DATE: 8/31/00

W E R BOX #: Apex 3

PERSON: Hilly

INITIAL Y: 02931

BAROMETRIC PRESSURE (In Hg): 29.6

INITIAL ΔH_g: 1.723

OFFICE #	RUN #	K' FACTOR (AVG)	TESTED VACUUM (In Hg)	DGM READINGS (FT ³)			TEMPERATURES °F					ELAPSED TIME (MIN) θ	DGM ΔH (in H ₂ O)	(1) V _m (STD)	(2) V _{cr} (STD)	(3) Y	Y VARIATION (%)	ΔH _g	
				INITIAL	FINAL	NET (V _m)	AMBIENT	DGM INLET		W M OUTLET									DGM AVG
								INITIAL	FINAL	INITIAL	FINAL								
24	1	0.6396	20	933.450	941.563	8.113	68	70	70	72	72	71	9.50	2.2	8.0260	7.8295	0.9755	1.8024	
24	2	0.6396	20	941.563	949.555	7.992	68	70	70	72	72	71	9.50	2.2	7.9063	7.8295	0.9903	1.8024	
																AVG =	0.9829	-1.03	
30	1	0.829	20	949.555	959.231	9.676	69	72	74	72	74	73	9.00	3.7	9.5716	9.6048	1.0035	1.8077	
30	2	0.829	20	959.231	968.904	9.673	69	72	74	72	74	73	9.00	3.7	9.5686	9.6048	1.0038	1.8077	
																AVG =	1.0036	1.06	
	1					.0						0			0.0	0.0	#DIV/0!	#DIV/0!	
	2					.0						0			0.0	0.0	#DIV/0!	#DIV/0!	
																AVG =	#DIV/0!	#DIV/0!	

SING THE CRITICAL ORIFICES AS CALIBRATION STANDARDS:

the following equations are used to calculate the standard volumes of air passed through the DGM, V_m (std), and the critical volume, V_{cr} (std), and the DGM calibration factor, Y. These equations are automatically calculated in the spreadsheet above.

AVERAGE DRY GAS METER CALIBRATION FACTOR, Y =

PRE-TEST/POST-TEST MUST BE ≤ 5.00% = 0.02%

AVERAGE ΔH_g = #DIV/0!

$$\Delta H_g = \frac{0.75 \theta}{V_{cr}(\text{std})}^2 \Delta H \frac{V_m(\text{std})}{V_m}$$

$$(1) V_m(\text{std}) = K_1 V_m \frac{P_{bar} + (AH113.6)}{T_m} = \text{Net volume of gas sample passed through DGM, corrected to standard conditions}$$

$K_1 = 17.64 \text{ } ^\circ\text{R/in. Hg (English), } 0.3858 \text{ } ^\circ\text{K/mm Hg (Metric)}$
 $T_m = \text{Absolute DGM avg. temperature (} ^\circ\text{R - English, } ^\circ\text{K - Metric)}$

$$(2) V_{cr}(\text{std}) = K' \sqrt{\frac{P_{bar} \theta}{T_{amb}}} = \text{Volume of gas sample passed through the critical orifice, corrected to standard conditions}$$

$T_{amb} = \text{Absolute ambient temperature (} ^\circ\text{R - English, } ^\circ\text{K - Metric)}$
 $K' = \text{Average K' factor from Critical Orifice Calibration}$

$$(3) Y = \frac{V_{cr}(\text{std})}{V_m(\text{std})} = \text{DGM calibration factor}$$

FBT


ORIFICE CAL.xls

S-type Pitot Tube Calibration


Identification: 1

Performed by: BW

Date: 1/4/00




$$\left\{ \begin{array}{l} P_A = P_B \\ 1.05D_t \leq P \leq 1.50D_t \end{array} \right\}$$




$$\alpha_1 = \underline{0}^\circ$$

$$\alpha_2 = \underline{1}^\circ$$



$$\beta_1 = \underline{1}^\circ$$

$$\beta_2 = \underline{0}^\circ$$



$$W = \underline{0} \text{ in.}$$


FBT

S-type Pitot Tube Calibration


Identification: 3

Performed by: BL

Date: 1/4/00




$$\left\{ \begin{array}{l} P_A = P_B \\ 1.05D_t \leq P \leq 1.50D_t \end{array} \right\}$$




$$\alpha_1 = \frac{I}{\theta}$$

$$\alpha_2 = \frac{0}{\theta}$$



$$\beta_1 = \frac{0}{\theta}$$

$$\beta_2 = \frac{0}{\theta}$$




$$W = \frac{6}{\theta} \text{ in.}$$

FBT



SPECTRA GASES INC.

3434 Route 22 West • Branchburg, NJ 08876 USA Tel (908) 252-9300 • (800) 932-0624 • Fax. (908) 252-0811
Shipped From 80 Industrial Drive • Alpha, NJ 08865



CERTIFICATE OF ANALYSIS

EPA PROTOCOL MIXTURE

PROCEDURE #: G1

CUSTOMER: FBT Testing & Environmental Services
SGI ORDER #: 152093
ITEM#: 3
P.O.#: 00-019

CYLINDER #: CC106973
CYLINDER PRES: 2000 PSIG
CGA OUTLET: 660

CERTIFICATION DATE: 3/22/2000

EXPIRATION DATE: 3/22/2002

CERTIFICATION HISTORY

COMPONENT	DATE OF ASSAY	MEAN CONCENTRATION	CERTIFIED CONCENTRATION	ANALYTICAL ACCURACY
Nitric Oxide	311412000 3/22/2000	89.13 ppm 89.51 ppm	89.3 ppm	+/- 1%
NOx			89.5 ppm	Reference Value Only

BALANCE Nitrogen

PREVIOUS CERTIFICATION DATES: None

REFERENCE STANDARDS

COMPONENT	SRM/NTRM#	CYLINDER#	CONCENTRATION
Nitric Oxide	NTRM-81684	CC79981	98.6 ppm

INSTRUMENTATION

COMPONENT	MAKE/MODEL	SERIAL #	DETECTOR	CALIBRATION DATE(S)
Nitric Oxide	Nicolet 560	ADL9600109	FTIR	311512000

THIS STANDARD WAS CERTIFIED ACCORDING TO THE EPA PROTOCOL PROCEDURES.
DO NOT USE THIS STANDARD IF THE CYLINDER PRESSURE IS LESS THAN 150 PSIG.

ANALYST: FP.
FRED PIKULA

DATE: 3/22/2000



SPECTRA GASES INC.

3434 Route 22 West • Branchburg, NJ 08876 USA Tel.: (908) 252-9300 • (800) 932-0624 • Fax: (908) 252-0811
Shipped From: 80 Industrial Drive • Alpha, NJ 08865



CERTIFICATE OF ANALYSIS

EPA PROTOCOL MIXTURE

PROCEDURE #: G1

CUSTOMER: FBT Testing & Environmental Services
SGI ORDER #: 142269
ITEM#: 5
P.O.#: 99-029

CYLINDER #: CC88515
CYLINDER PRES: 2000 PSIG
CGA OUTLET: 660

CERTIFICATION DATE: 5/12/99
EXPIRATION DATE: 5/12/2001

CERTIFICATION HISTORY

COMPONENT	DATE OF ASSAY	MEAN CONCENTRATION	CERTIFIED CONCENTRATION	ANALYTICAL ACCURACY
Nitric Oxide	5/4/99	92.03 ppm	91.5 ppm	+/- 1%
NOx	5/12/99	91.03 ppm	91.6 ppm	Reference Value Only

BALANCE Nitrogen

PREVIOUS CERTIFICATION DATES: None

REFERENCE STANDARDS

COMPONENT	SRM/NTRM#	CYLINDER#	CONCENTRATION
Nitric Oxide	GMIS-1	CC79984	98.6 ppm

INSTRUMENTATION

COMPONENT	MAKE/MODEL	SERIAL #	DETECTOR	CALIBRATION DATE(S)
Nitric Oxide	Teco 10	10AR-34979-249	Cheml	5/12/99

THIS STANDARD WAS CERTIFIED ACCORDING TO THE EPA PROTOCOL PROCEDURES.
DO NOT USE THIS STANDARD IF THE CYLINDER PRESSURE IS LESS THAN 150 PSIG.

ANALYST:

FRED PIKULA

DATE: 5/12/99



SPECTRA GASES INC.

3434 Route 22 West • Branchburg, NJ 08876 USA Tel (908) 252-9300 • (800) 932-0624 • Fax (908) 252-0811
Shipped From 80 Industrial Drive • Alpha NJ 08865



CERTIFICATE OF ANALYSIS

EPA PROTOCOL MIXTURE

PROCEDURE #: G1

CUSTOMER: FBT Testing & Environmental Services CYLINDER #: CC106772
SGI ORDER #: 139857 CYLINDER PRES: 2000 PSIG
ITEM#: 4 CGA OUTLET: 660
P.O.#: 99-005

CERTIFICATION DATE: 2/22/99
EXPIRATION DATE: 2/22/2001

CERTIFICATION HISTORY

COMPONENT	DATE OF ASSAY	MEAN CONCENTRATION	CERTIFIED CONCENTRATION	ANALYTICAL ACCURACY
Nitric Oxide	2/12/99	200.3 ppm	200 ppbn	+/- 1%
NOx	2/22/99	199.8 ppm	200 ppm	Reference Value Only

BALANCE Nitrogen

PREVIOUS CERTIFICATION DATES: None

REFERENCE STANDARDS

COMPONENT	SRM/NTRM#	CYLINDER#	CONCENTRATION
Nitric Oxide	NTRM-81685	LL2994	245.2 ppm

INSTRUMENTATION

COMPONENT	MAKE/MODEL	SERIAL #	DETECTOR	CALIBRATION DATE(S)
Nitric Oxide	Teco 10	10AR-34979-249	Cheml	2/5/99

THIS STANDARD WAS CERTIFIED ACCORDING TO THE EPA PROTOCOL PROCEDURES.
DO NOT USE THIS STANDARD IF THE CYLINDER PRESSURE IS LESS THAN 150 PSIG.

ANALYST: FR
FRED PIKULA

DATE: 2/22/99

**SPECTRA GASES**

3434 Route 22 West • Branchburg, NJ 08876 USA Tel: (908) 252-9303 • (800) 932-0624 • Fax: (908) 252-0811

SHIPPED FROM: 80 INDUSTRIAL DRIVE ALPHA, NJ. 08865 TEL: (908) 454-7455**SHIPPED TO:** FBT Testing & Environmental Services
7419 Kingsgate Way
West Chester, OH 45069**CERTIFICATE
OF
ANALYSIS****SGI ORDER # :** 152093
ITEM# : 1
CERTIFICATION DATE: 3/22/2000
P.O.# : 00-019
BLEND TYPE: CERTIFIED**CYLINDER # :** CC113935
CYLINDER PRES: 2000 psig
CYLINDER VALVE: CGA 350**ANALYTICAL ACCURACY: + / - 2%**

COMPONENT	REQUESTED GAS CONC	ANALYSIS
Carbon Monoxide	100 ppm	102 ppm
Carbon Dioxide	15.0 %	15.0 %
Nitrogen	Balance	Balance

ANALYST: 
Fred Pikula**DATE:** 3/22/2000

**SPECTRA GASES**

3434 Route 22 West • Branchburg, NJ 08876 USA Tel: (908) 252-9300 • (800) 932-0624 • Fax: (908) 252-0811

SHIPPED FROM: 80 INDUSTRIAL DRIVE ALPHA, NJ. 08865 TEL: (908) 454-7455

SHIPPED TO: FBT Testing & Environmental Services
7419 Kingsgate Way
West Chester. OH 45069


**CERTIFICATE
OF
ANALYSIS**

SGI ORDER # : 145753
ITEM# : 1
CERTIFICATION DATE: 8/25/99
P.O.# : 99-057
BLEND TYPE: CERTIFIED

CYLINDER # : CC90794
CYLINDER PRES: 2000 psig
CYLINDER VALVE: CGA 350

ANALYTICAL ACCURACY: + / - 2%

COMPONENT	REQUESTED GAS CONC	ANALYSIS
Carbon Monoxide	50.0 ppm	51.0 ppm
Carbon Dioxide	15.0 %	15.1 %
Nitrogen	Balance	Balance

ANALYST: 
Fred Pikula

DATE: 8/25/99

CLIENT: Newport Steel
SAMPLE LOCATION: EAF-Brandt Baghouse

RUN #:	1	2	3	4	5	6
Reference Method Data						
DATE:	08/15/00	08/15/00	08/16/00	08/16/00		
TIME:	0814-1300	1345-1659	0754-1214	1309-1509		
CO, ppmv	55.28	93.73	118.93	96.00	5.48	5.15
ppm NOx :	8.86	8.14	9.11	10.30	8.14	4.07
lb/MMbtu						
CEMS Data						
CO, ppmv	59.51	114.90	142.77	85.87	5.35	4.99
ppm NOx	10.67	9.83	6.85	11.06	9.50	6.90
lb/MMbtu	53.000	95.000	114.000	53.000	95.000	114.000
Reference Method Data						
RUN #:	7	8	9	10	11	12
Reference Method Data						
DATE:						
TIME:						
CO, ppmv	59.06	5.14	5.14	4.99	4.87	5.02
ppm NOx :	10.67	8.14	4.07	8.86	8.14	4.07
lb/MMbtu	55.280	93.730	118.930	55.280	93.730	118.930
CEMS Data						
% O ₂ :	5.08	5.05	5.05	4.92	4.86	5.07
ppm NOx :	9.80	9.50	6.90	9.80	9.50	6.90
lb/MMbtu						

Plant: Newport Steel
 Location: Baghouse Inlet
 Operator: P. Hilty
 Date/Time: 8/15/00 14:02:15

Final System Bias Check for Run 1

Analyte	O2	SO2	NOx	co2	CO
Units	%	ppm	ppm	%	ppm
Range	25	1000	100	20	200
Zero Gas Value	0	0	0	0	0
Calibration Zero	0.022	0.3	0.81	-0.267	-5.5
Final Bias Zero Avg	-0.086	-1.9	1.77	-0.301	-10
Zero Bias%	-0.3	-0.2	1.8	-1.5	-5.0
Zero Drift%	0.2	0.2	-1.1	0.4	4.0
Span Gas Value	20.9	400	50.5	8	50
Calibration Span	20.896	393.3	50.15	8.016	46.1
Final Bias Span Avg	20.824	399	51.43	7.992	39.5
Span Bias%	-0.3	-0.1	0.9	0.0	-5
Span Drift%	0.3	-0.7	-1.5	0.1	3.8
Initial Bias Zero	-0.032	0.2	0.69	-0.219	-2.1
Initial Bias Span	20.903	392.4	49.91	8.014	47.1
Run Avg	20.54	-1.43	9.9	0.07	48.51
Co	-0.059	-0.850	1.23	-0.26	-6.05
Cm	20.864	395.700	50.670	8.003	43.300
Correct Avg	20.58	-0.59	8.86	0.32	55.28

Plant: Newport Steel
 Location: Baghouse Inlet
 Operator: P. Hilty
 Date/Time: 8/15/00

Final System Bias Check for Run 2

Analyte	O2	SO2	NOx	co2	CO
Units	%	ppm	ppm	%	ppm
Range	25	1000	100	20	200
Zero Gas Value	0	0	0	0	0
Calibration Zero	0.022	0.3	0.81	-0.267	-5.5
Final Bias Zero Avg	-0.104	-3.3	2.67	-0.101	-4.2
Zero Bias%	-0.4	-0.3	2.7	-0.5	-2.1
Zero Drift%	0.1	0.1	-0.9	-1.0	2.1
Span Gas Value	20.9	400	50.5	8	50
Calibration Span	20.896	393.3	50.15	8.016	46.1
Final Bias Span Avg	20.769	390.3	50.22	7.918	46.1
Span Bias%	-0.5	-1.0	-0.3	-0.4	-2
Span Drift%	0.2	0.9	1.2	0.4	0.4
Initial Bias Zero	-0.086	-1.9	1.77	-0.301	0
Initial Bias Span	20.824	399	51.43	7.992	47
Run Avg	20.58		10.05	0.24	89.1
Co	-0.095	-2.600	2.22	-0.201	-2.1
Cm	20.797	394.650	50.825	7.955	46.550
Correct Avg	20.68	2.62	8.14	0.43	92.72

Plant: Newport Steel
 Location: Baghouse Inlet
 Operator: P. Hilty
 Date/Time: 8/16/00

Final System Bias Check for Run 3

Analyte	O2	SO2	NOx	co2	CO
Units	%	ppm	ppm	%	ppm
Range	25	1000	100	20	200
Zero Gas Value	0	0	0	0	0
Calibration Zero	0.022	0.3	0.81	-0.267	-5.5
Final Bias Zero Avg	-0.254		-0.79	0.016	2.2
Zero Bias%	-1.0	0.0	-0.8	0.1	1.1
Zero Drift%	0.6	-0.3	3.5	-0.6	-3.2
Span Gas Value	20.9	400	50.5	8	50
Calibration Span	20.896	393.3	50.15	8.016	46.1
Final Bias Span Avg	20.864		49.85	7.971	52.8
Span Bias%	-0.1	-40.0	-0.6	-0.1	1
Span Drift%	-0.4	39.0	0.4	-0.3	-3.4
Initial Bias Zero	-0.104	-3.3	2.67	-0.101	-4.2
Initial Bias Span	20.769	390.3	50.22	7.918	46.1
Run Avg	20.343		9.8	0.3	119
Co	-0.179	-1.650	0.94	-0.0425	-1
Gm	20.817	195.150	50.035	7.945	49.450
Correct Avg	20.43	3.35	9.11	0.34	118.93

Plant: Newport Steel
 Location: Baghouse Inlet
 Operator: P. Hilty
 Date/Time: 8/16/00 1309-1509

Final System Bias Check for Run 4

Analyte	O2	SO2	NOx	co2	CO
Units	%	ppm	ppm	%	ppm
Range	25	1000	100	20	200
Zero Gas Value	0	0	0	0	0
Calibration Zero	0.022	0.3	0.81	-0.267	-5.5
Final Bias Zero Avg	-0.256		-0.16	0.077	0
Zero Bias%	-1.0	0.0	-0.2	0.4	0.0
Zero Drift%	0.0	0.0	-0.6	-0.3	1.1
Span Gas Value	20.9	400	50.5	8	50
Calibration Span	20.896	393.3	50.15	8.016	46.1
Final Bias Span Avg	20.79		51.04	8	52.2
Span Bias%	-0.4	-40.0	0.5	0.0	1
Span Drift%	0.3	0.0	-1.2	-0.1	0.3
Initial Bias Zero	-0.254	0	-0.79	0.016	2.2
Initial Bias Span	20.864	0	49.85	7.971	52.8
Run Avg	20.58		9.91	0.42	99.79
Co	-0.255	0.000	-0.475	0.0465	1.1
Gm	20.827	0.000	50.445	7.986	52.500
Correct Avg	20.66	#DIV/0!	10.30	0.38	96.00

CEMS CO Data	RUN 1	CEMS Nox Data	Run 1
8/15/00 8:14	10.5	8/15/00 8:14	27.66
8/15/00 8:15	8.5	8/15/00 8:15	25.32
8/15/00 8:16	13	8/15/00 8:16	22.29
8/15/00 8:17	11.2	8/15/00 8:17	16.83
8/15/00 8:18	10.3	8/15/00 8:18	14.68
8/15/00 8:19	25.6	8/15/00 8:19	15.17
8/15/00 8:20	12.4	8/15/00 8:20	13.84
8/15/00 8:21	8.8	8/15/00 8:21	13.11
8/15/00 8:22	7.3	8/15/00 8:22	12.59
8/15/00 8:23	8.3	8/15/00 8:23	11.06
8/15/00 8:24	9.3	8/15/00 8:24	8.75
8/15/00 8:25	10.8	8/15/00 8:25	3.21
8/15/00 8:26	11.3	8/15/00 8:26	1.99
8/15/00 8:27	10.4	8/15/00 8:27	1.92
8/15/00 8:28	10.3	8/15/00 8:28	1.8
8/15/00 8:29	10.3	8/15/00 8:29	1.88
8/15/00 8:30	10.3	8/15/00 8:30	1.68
8/15/00 8:31	27.1	8/15/00 8:31	1.93
8/15/00 8:32	38.1	8/15/00 8:32	5.25
8/15/00 8:33	33.4	8/15/00 8:33	15.71
8/15/00 8:34	18.8	8/15/00 8:34	6.74
8/15/00 8:35	14.3	8/15/00 8:35	7.07
8/15/00 8:36	17.1	8/15/00 8:36	6.93
8/15/00 8:37	32.5	8/15/00 8:37	6.94
8/15/00 8:38	57.7	8/15/00 8:38	6.28
8/15/00 8:39	91.1	8/15/00 8:39	5.75
8/15/00 8:40	203.8	8/15/00 8:40	5.15
8/15/00 8:41	221.6	8/15/00 8:41	3.76
8/15/00 8:42	299.7	8/15/00 8:42	2.77
8/15/00 8:43	318.4	8/15/00 8:43	2.6
8/15/00 8:44	186.1	8/15/00 8:44	2.75
8/15/00 8:45	116.3	8/15/00 8:45	5.18
8/15/00 8:46	106	8/15/00 8:46	5.26
8/15/00 8:47	105.5	8/15/00 8:47	2.79
8/15/00 8:48	77.4	8/15/00 8:48	10.08
8/15/00 8:49	28.5	8/15/00 8:49	15.63
8/15/00 8:50	28.1	8/15/00 8:50	7.81
8/15/00 8:51	24.1	8/15/00 8:51	6.91
8/15/00 8:52	28.2	8/15/00 8:52	7.59
8/15/00 8:53	31.7	8/15/00 8:53	7.99
8/15/00 8:54	36.8	8/15/00 8:54	6.96
8/15/00 8:55	68.8	8/15/00 8:55	7.06
8/15/00 8:56	170.2	8/15/00 8:56	6.15
8/15/00 8:57	141	8/15/00 8:57	5.49
8/15/00 8:58	197.8	8/15/00 8:58	3.86
8/15/00 8:59	176.3	8/15/00 8:59	3.15

8/15/00 9:00	193.2
8/15/00 9:01	157
8/15/00 9:02	134.7
8/15/00 9:03	126.7
8/15/00 9:04	114.8
8/15/00 9:05	96.4
8/15/00 9:06	89.4
8/15/00 9:07	94
8/15/00 9:08	76
8/15/00 9:09	68.3
8/15/00 9:10	21.7
8/15/00 9:11	9.4
8/15/00 9:12	17.7
8/15/00 9:13	36.4
8/15/00 9:14	24.3
8/15/00 9:15	24.1
8/15/00 9:16	22.9
8/15/00 9:17	23.7
8/15/00 9:18	36
8/15/00 9:19	24.5
8/15/00 9:20	44.6
8/15/00 9:21	18.5
8/15/00 9:22	6.8
8/15/00 9:23	6.9
8/15/00 9:24	8.5
8/15/00 9:25	12.4
8/15/00 9:26	7.4
8/15/00 9:27	6.3
8/15/00 9:28	6.3
8/15/00 9:29	5.7
8/15/00 9:30	5.3
8/15/00 9:31	5.3
8/15/00 9:32	5.3
8/15/00 9:33	5.3
8/15/00 9:34	5.3
8/15/00 9:35	5.3
8/15/00 9:36	5.3
8/15/00 9:37	5.3
8/15/00 9:38	5.3
8/15/00 9:39	5.4
8/15/00 9:40	12
8/15/00 9:41	15.5
8/15/00 9:42	7.6
8/15/00 9:43	6.8
8/15/00 9:44	18.7
8/15/00 9:45	9.6
8/15/00 9:46	6.4

8/15/00 9:00	2.75
8/15/00 9:01	1.96
8/15/00 9:02	2.34
8/15/00 9:03	1.65
8/15/00 9:04	1.68
8/15/00 9:05	1.77
8/15/00 9:06	2.3
8/15/00 9:07	5.32
8/15/00 9:08	8.11
8/15/00 9:09	8.4
8/15/00 9:10	16.02
8/15/00 9:11	22.27
8/15/00 9:12	20.39
8/15/00 9:13	11.32
8/15/00 9:14	8.9
8/15/00 9:15	11.54
8/15/00 9:16	10.81
8/15/00 9:17	9.41
8/15/00 9:18	6.79
8/15/00 9:19	5.93
8/15/00 9:20	5.42
8/15/00 9:21	9.68
8/15/00 9:22	17.56
8/15/00 9:23	14.1
8/15/00 9:24	18.68
8/15/00 9:25	18.32
8/15/00 9:26	18.17
8/15/00 9:27	16.71
8/15/00 9:28	14.32
8/15/00 9:29	12.71
8/15/00 9:30	10.09
8/15/00 9:31	10
8/15/00 9:32	9.76
8/15/00 9:33	11.81
8/15/00 9:34	12.64
8/15/00 9:35	8.65
8/15/00 9:36	8.49
8/15/00 9:37	10.04
8/15/00 9:38	9.18
8/15/00 9:39	15.12
8/15/00 9:40	30.03
8/15/00 9:41	12.42
8/15/00 9:42	14.76
8/15/00 9:43	30.28
8/15/00 9:44	24.12
8/15/00 9:45	13.45
8/15/00 9:46	23.66

8/15/00 9:47	8.1	8/15/00 9:47	15.88
8/15/00 9:48	16.6	8/15/00 9:48	11.66
8/15/00 9:49	17.2	8/15/00 9:49	12.11
8/15/00 9:50	8.5	8/15/00 9:50	19.29
8/15/00 9:51	8.1	8/15/00 9:51	17.05
8/15/00 9:52	9	8/15/00 9:52	15.82
8/15/00 9:53	10	8/15/00 9:53	14.67
8/15/00 9:54	9.4	8/15/00 9:54	14.12
8/15/00 9:55	11.7	8/15/00 9:55	14.06
8/15/00 9:56	11.3	8/15/00 9:56	11.35
8/15/00 9:57	11.3	8/15/00 9:57	3.05
8/15/00 9:58	11.3	8/15/00 9:58	1.2
8/15/00 9:59	11.3	8/15/00 9:59	1.18
8/15/00 10:00	11.3	8/15/00 10:00	1.28
8/15/00 10:01	11.3	8/15/00 10:01	1.31
8/15/00 10:02	11	8/15/00 10:02	1.2
8/15/00 10:03	10.6	8/15/00 10:03	1.1
8/15/00 10:04	10.6	8/15/00 10:04	1.23
8/15/00 10:05	11.7	8/15/00 10:05	1.33
8/15/00 10:06	12.4	8/15/00 10:06	1.49
8/15/00 10:07	12.7	8/15/00 10:07	1.69
8/15/00 10:08	22.3	8/15/00 10:08	2.07
8/15/00 10:09	56.6	8/15/00 10:09	2.8
8/15/00 10:10	44	8/15/00 10:10	18.2
8/15/00 10:11	31.1	8/15/00 10:11	16.89
8/15/00 10:12	52.1	8/15/00 10:12	4.1
8/15/00 10:13	55.6	8/15/00 10:13	3.28
8/15/00 10:14	62.5	8/15/00 10:14	3.3
8/15/00 10:15	79.7	8/15/00 10:15	3.6
8/15/00 10:16	72	8/15/00 10:16	3.4
8/15/00 10:17	74.9	8/15/00 10:17	3.53
8/15/00 10:18	54.2	8/15/00 10:18	4.03
8/15/00 10:19	84.3	8/15/00 10:19	6.11
8/15/00 10:20	70.9	8/15/00 10:20	9.02
8/15/00 10:21	44.8	8/15/00 10:21	10.07
8/15/00 10:22	32.6	8/15/00 10:22	13.89
8/15/00 10:23	20.5	8/15/00 10:23	7.48
8/15/00 10:24	12.3	8/15/00 10:24	3.31
8/15/00 10:25	12.1	8/15/00 10:25	2.9
8/15/00 10:26	14.7	8/15/00 10:26	2.83
8/15/00 10:27	15.5	8/15/00 10:27	2.68
8/15/00 10:28	15.8	8/15/00 10:28	7.7
8/15/00 10:29	25.3	8/15/00 10:29	26.4
8/15/00 10:30	36.6	8/15/00 10:30	14.9
8/15/00 10:31	52.8	8/15/00 10:31	7.94
8/15/00 10:32	48.6	8/15/00 10:32	9.1
8/15/00 10:33	48.8	8/15/00 10:33	12.39

8/15/00 10:34	18.3	8/15/00 10:34	6.26
8/15/00 10:35	35.8	8/15/00 10:35	2.35
8/15/00 10:36	101.4	8/15/00 10:36	2.18
8/15/00 10:37	65.6	8/15/00 10:37	5.67
8/15/00 10:38	20.2	8/15/00 10:38	4.99
8/15/00 10:39	14	8/15/00 10:39	5.17
8/15/00 10:40	21.5	8/15/00 10:40	4.76
8/15/00 10:41	34.4	8/15/00 10:41	3.99
8/15/00 10:42	52	8/15/00 10:42	3.83
8/15/00 10:43	79.2	8/15/00 10:43	3.73
8/15/00 10:44	118.3	8/15/00 10:44	3.53
8/15/00 10:45	126.8	8/15/00 10:45	3.43
8/15/00 10:46	199.9	8/15/00 10:46	3.4
8/15/00 10:47	249	8/15/00 10:47	2.74
8/15/00 10:48	268	8/15/00 10:48	2.27
8/15/00 10:49	284	8/15/00 10:49	2.01
8/15/00 10:50	207	8/15/00 10:50	2.42
8/15/00 10:51	148.7	8/15/00 10:51	3.32
8/15/00 10:52	111.2	8/15/00 10:52	2.51
8/15/00 10:53	54.1	8/15/00 10:53	1.65
8/15/00 10:54	43.4	8/15/00 10:54	1.96
8/15/00 10:55	18.5	8/15/00 10:55	6.84
8/15/00 10:56	9.5	8/15/00 10:56	12.46
8/15/00 10:57	5.9	8/15/00 10:57	32.1
8/15/00 10:58	8.1	8/15/00 10:58	42.56
8/15/00 10:59	7.8	8/15/00 10:59	35.9
8/15/00 11:00	7.4	8/15/00 11:00	28.26
8/15/00 11:01	11.3	8/15/00 11:01	24.68
8/15/00 11:02	22	8/15/00 11:02	13.44
8/15/00 11:03	576.9	8/15/00 11:03	6.03
8/15/00 11:04	223	8/15/00 11:04	3.78
8/15/00 11:05	147.3	8/15/00 11:05	4.25
8/15/00 11:06	118.2	8/15/00 11:06	11.05
8/15/00 11:07	58.6	8/15/00 11:07	22.38
8/15/00 11:08	52.3	8/15/00 11:08	11.09
8/15/00 11:09	21.1	8/15/00 11:09	17.51
8/15/00 11:10	11.4	8/15/00 11:10	21.23
8/15/00 11:11	9.3	8/15/00 11:11	19.64
8/15/00 11:12	11.1	8/15/00 11:12	22.51
8/15/00 11:13	13.8	8/15/00 11:13	26.3
8/15/00 11:14	13.5	8/15/00 11:14	21.28
8/15/00 11:15	14.2	8/15/00 11:15	11.52
8/15/00 11:16	9.7	8/15/00 11:16	19.17
8/15/00 11:17	13.4	8/15/00 11:17	16.07
8/15/00 11:18	10.2	8/15/00 11:18	26.17
8/15/00 11:19	6.8	8/15/00 11:19	28.04
8/15/00 11:20	6.1	8/15/00 11:20	20.41

8/15/00 11:21	5.8	8/15/00 11:21	11.7
8/15/00 11:22	5.8	8/15/00 11:22	10
8/15/00 11:23	5.3	8/15/00 11:23	11.48
8/15/00 11:24	5.3	8/15/00 11:24	17
8/15/00 11:25	5.3	8/15/00 11:25	19.54
8/15/00 11:26	5.3	8/15/00 11:26	20.12
8/15/00 11:27	5.3	8/15/00 11:27	17.62
8/15/00 11:28	5.3	8/15/00 11:28	11.68
8/15/00 11:29	5	8/15/00 11:29	9.92
8/15/00 11:30	4.3	8/15/00 11:30	10.92
8/15/00 11:31	4.3	8/15/00 11:31	11.85
8/15/00 11:32	4.3	8/15/00 11:32	12.62
8/15/00 11:33	4.3	8/15/00 11:33	12.94
8/15/00 11:34	4.5	8/15/00 11:34	12.46
8/15/00 11:35	4.3	8/15/00 11:35	13.57
8/15/00 11:36	4.3	8/15/00 11:36	17.52
8/15/00 11:37	6	8/15/00 11:37	17.94
8/15/00 11:38	12.6	8/15/00 11:38	12.16
8/15/00 11:39	5.8	8/15/00 11:39	12.07
8/15/00 11:40	5.3	8/15/00 11:40	15.84
8/15/00 11:41	5	8/15/00 11:41	15.85
8/15/00 11:42	5.8	8/15/00 11:42	15.14
8/15/00 11:43	7.6	8/15/00 11:43	14.06
8/15/00 11:44	6.3	8/15/00 11:44	12.94
8/15/00 11:45	14.5	8/15/00 11:45	12.78
8/15/00 11:46	9.5	8/15/00 11:46	10.93
8/15/00 11:47	7	8/15/00 11:47	10.37
8/15/00 11:48	6.1	8/15/00 11:48	10.03
8/15/00 11:49	5.3	8/15/00 11:49	9.56
8/15/00 11:50	11.6	8/15/00 11:50	7.39
8/15/00 11:51	49.4	8/15/00 11:51	7.63
8/15/00 11:52	72.5	8/15/00 11:52	6.51
8/15/00 11:53	71.1	8/15/00 11:53	5.8
8/15/00 11:54	96.3	8/15/00 11:54	5.35
8/15/00 11:55	131.6	8/15/00 11:55	5.08
8/15/00 11:56	149	8/15/00 11:56	4.52
8/15/00 11:57	162.6	8/15/00 11:57	5.05
8/15/00 11:58	223.9	8/15/00 11:58	5.23
8/15/00 11:59	284.3	8/15/00 11:59	4.12
8/15/00 12:00	195.1	8/15/00 12:00	3.07
8/15/00 12:01	128.7	8/15/00 12:01	1.36
8/15/00 12:02	243.8	8/15/00 12:02	1.93
8/15/00 12:03	285.7	8/15/00 12:03	1.42
8/15/00 12:04	352.7	8/15/00 12:04	1.67
8/15/00 12:05	370.5	8/15/00 12:05	2.84
8/15/00 12:06	212.5	8/15/00 12:06	9.58
8/15/00 12:07	73.4	8/15/00 12:07	16.34

8/15/00 12:08	40.9
8/15/00 12:09	112.7
8/15/00 12:10	92.2
8/15/00 12:11	37.8
8/15/00 12:12	49.5
8/15/00 12:13	153.1
8/15/00 12:14	349.3
8/15/00 12:15	284.8
8/15/00 12:16	281.9
8/15/00 12:17	301.5
8/15/00 12:18	201.3
8/15/00 12:19	193.8
8/15/00 12:20	381.6
8/15/00 12:21	371.7
8/15/00 12:22	275.4
8/15/00 12:23	156.3
8/15/00 12:24	40.9
8/15/00 12:25	16.7
8/15/00 12:26	30.5
8/15/00 12:27	87
8/15/00 12:28	37
8/15/00 12:29	32.2
8/15/00 12:30	25.3
8/15/00 12:31	20.9
8/15/00 12:32	17.5
8/15/00 12:33	17.4
8/15/00 12:34	21.6
8/15/00 12:35	23.1
8/15/00 12:36	12.3
8/15/00 12:37	9.9
8/15/00 12:38	6.7
8/15/00 12:39	7.9
8/15/00 12:40	5.2
8/15/00 12:41	5.5
8/15/00 12:42	6.9
8/15/00 12:43	5.3
8/15/00 12:44	4.5
8/15/00 12:45	4.9
8/15/00 12:46	3.6
8/15/00 12:47	4.2
8/15/00 12:48	4.3
8/15/00 12:49	4.3
8/15/00 12:50	4.8
8/15/00 12:51	4.6
8/15/00 12:52	4.3
8/15/00 12:53	8.8
8/15/00 12:54	25.4

8/15/00 12:08	9.89
8/15/00 12:09	5.74
8/15/00 12:10	5.78
8/15/00 12:11	6.23
8/15/00 12:12	5.84
8/15/00 12:13	4.98
8/15/00 12:14	4.45
8/15/00 12:15	4.21
8/15/00 12:16	3.78
8/15/00 12:17	3.33
8/15/00 12:18	9.01
8/15/00 12:19	12.16
8/15/00 12:20	9.67
8/15/00 12:21	15.86
8/15/00 12:22	23.25
8/15/00 12:23	22.31
8/15/00 12:24	18.71
8/15/00 12:25	13
8/15/00 12:26	10.08
8/15/00 12:27	6.86
8/15/00 12:28	15.11
8/15/00 12:29	16.52
8/15/00 12:30	15.12
8/15/00 12:31	11.75
8/15/00 12:32	15.46
8/15/00 12:33	17.47
8/15/00 12:34	17.09
8/15/00 12:35	6.74
8/15/00 12:36	5.57
8/15/00 12:37	6.96
8/15/00 12:38	16.39
8/15/00 12:39	26.53
8/15/00 12:40	20.11
8/15/00 12:41	15.77
8/15/00 12:42	18.99
8/15/00 12:43	26.79
8/15/00 12:44	18.73
8/15/00 12:45	15.88
8/15/00 12:46	13.32
8/15/00 12:47	12.17
8/15/00 12:48	12.04
8/15/00 12:49	13.71
8/15/00 12:50	18.33
8/15/00 12:51	12.98
8/15/00 12:52	15.47
8/15/00 12:53	15.16
8/15/00 12:54	12.38

8/15/00 12:55	9.2
8/15/00 12:56	12.9
8/15/00 12:57	59.5
8/15/00 12:58	13.3
8/15/00 12:59	5.8
8/15/00 13:00	5.3

59.05575

8/15/00 12:55	17.05
8/15/00 12:56	13.77
8/15/00 12:57	8.58
8/15/00 12:58	18.49
8/15/00 12:59	21.12
8/15/00 13:00	15.99

10.67652

CEMS CO Data RUN2

8/15/00 13:45	8.3
8/15/00 13:46	8.3
8/15/00 13:47	8.3
8/15/00 13:48	25.1
8/15/00 13:49	77.1
8/15/00 13:50	56.8
8/15/00 13:51	34.4
8/15/00 13:52	25.6
8/15/00 13:53	29.2
8/15/00 13:54	69.3
8/15/00 13:55	177.1
8/15/00 13:56	121.7
8/15/00 13:57	100.9
8/15/00 13:58	97
8/15/00 13:59	115.8
8/15/00 14:00	104.1
8/15/00 14:01	92.4
8/15/00 14:02	105.2
8/15/00 14:03	103.2
8/15/00 14:04	125.1
8/15/00 14:05	155.4
8/15/00 14:06	159.8
8/15/00 14:07	175.1
8/15/00 14:08	113
8/15/00 14:09	61.2
8/15/00 14:10	56.9
8/15/00 14:11	89.3
8/15/00 14:12	105.9
8/15/00 14:13	21.5
8/15/00 14:14	9.4
8/15/00 14:15	9.3
8/15/00 14:16	9
8/15/00 14:17	8.7
8/15/00 14:18	11.8
8/15/00 14:19	18.2
8/15/00 14:20	21.6
8/15/00 14:21	21.8
8/15/00 14:22	21.3
8/15/00 14:23	21
8/15/00 14:24	22.7
8/15/00 14:25	15.8
8/15/00 14:26	13.3
8/15/00 14:27	13.3
8/15/00 14:28	13.2
8/15/00 14:29	10.5
8/15/00 14:30	27.9

CEMS Nox DATA RUN2

8/15/00 13:45	0.69
8/15/00 13:46	0.86
8/15/00 13:47	1.17
8/15/00 13:48	1.5
8/15/00 13:49	2.06
8/15/00 13:50	1.49
8/15/00 13:51	1.02
8/15/00 13:52	0.84
8/15/00 13:53	4.96
8/15/00 13:54	8.8
8/15/00 13:55	3.17
8/15/00 13:56	2.4
8/15/00 13:57	2.53
8/15/00 13:58	2.43
8/15/00 13:59	1.86
8/15/00 14:00	1.73
8/15/00 14:01	1.91
8/15/00 14:02	2.25
8/15/00 14:03	3.04
8/15/00 14:04	3.61
8/15/00 14:05	2.33
8/15/00 14:06	1.87
8/15/00 14:07	1.99
8/15/00 14:08	2.26
8/15/00 14:09	2.56
8/15/00 14:10	4.41
8/15/00 14:11	3.46
8/15/00 14:12	1.81
8/15/00 14:13	2.56
8/15/00 14:14	3.44
8/15/00 14:15	3.77
8/15/00 14:16	3.97
8/15/00 14:17	4.15
8/15/00 14:18	4.28
8/15/00 14:19	5.31
8/15/00 14:20	6.79
8/15/00 14:21	6.03
8/15/00 14:22	5.61
8/15/00 14:23	5.72
8/15/00 14:24	6.48
8/15/00 14:25	5.69
8/15/00 14:26	4.87
8/15/00 14:27	4.87
8/15/00 14:28	5.64
8/15/00 14:29	6.47
8/15/00 14:30	9.02

8/15/00 14:31	185.7
8/15/00 14:32	216.3
8/15/00 14:33	217.6
8/15/00 14:34	220.8
8/15/00 14:35	193
8/15/00 14:36	197.8
8/15/00 14:37	164
8/15/00 14:38	156.6
8/15/00 14:39	162
8/15/00 14:40	263.6
8/15/00 14:41	134.6
8/15/00 14:42	52.6
8/15/00 14:43	91.4
8/15/00 14:44	390.2
8/15/00 14:45	988.9
8/15/00 14:46	999.7
8/15/00 14:47	999.7
8/15/00 14:48	774.7
8/15/00 14:49	933.4
8/15/00 14:50	784
8/15/00 14:51	999.5
8/15/00 14:52	716.2
8/15/00 14:53	398.2
8/15/00 14:54	307.7
8/15/00 14:55	270.1
8/15/00 14:56	196.2
8/15/00 14:57	217.3
8/15/00 14:58	166.3
8/15/00 14:59	45.4
8/15/00 15:00	22.4
8/15/00 15:01	15
8/15/00 15:02	16.7
8/15/00 15:03	19.9
8/15/00 15:04	48.1
8/15/00 15:05	164.9
8/15/00 15:06	117.3
8/15/00 15:07	49.1
8/15/00 15:08	32.5
8/15/00 15:09	23.5
8/15/00 15:10	19.6
8/15/00 15:11	16.1
8/15/00 15:12	17.8
8/15/00 15:13	19.6
8/15/00 15:14	16.2
8/15/00 15:15	13
8/15/00 15:16	10.1
8/15/00 15:17	7.5

8/15/00 14:31	5.5
8/15/00 14:32	3.88
8/15/00 14:33	4.39
8/15/00 14:34	5.08
8/15/00 14:35	4.76
8/15/00 14:36	5.1
8/15/00 14:37	4.66
8/15/00 14:38	4.26
8/15/00 14:39	4.62
8/15/00 14:40	5.37
8/15/00 14:41	6.59
8/15/00 14:42	5.83
8/15/00 14:43	4.49
8/15/00 14:44	3.71
8/15/00 14:45	3.26
8/15/00 14:46	3.13
8/15/00 14:47	3.3
8/15/00 14:48	3.74
8/15/00 14:49	3.87
8/15/00 14:50	2.54
8/15/00 14:51	2.26
8/15/00 14:52	2.75
8/15/00 14:53	1.39
8/15/00 14:54	0.88
8/15/00 14:55	0.89
8/15/00 14:56	1.29
8/15/00 14:57	1.09
8/15/00 14:58	5.42
8/15/00 14:59	15.38
8/15/00 15:00	14.15
8/15/00 15:01	12.47
8/15/00 15:02	30.06
8/15/00 15:03	26.81
8/15/00 15:04	11.53
8/15/00 15:05	3.6
8/15/00 15:06	4.06
8/15/00 15:07	10.22
8/15/00 15:08	12.09
8/15/00 15:09	21.23
8/15/00 15:10	25.56
8/15/00 15:11	20.61
8/15/00 15:12	17.67
8/15/00 15:13	15.23
8/15/00 15:14	16.67
8/15/00 15:15	22.71
8/15/00 15:16	33.33
8/15/00 15:17	27.54

8/15/00 15:18	6.8	8/15/00 15:18	22.36
8/15/00 15:19	6.3	8/15/00 15:19	18.21
8/15/00 15:20	5.3	8/15/00 15:20	16.38
8/15/00 15:21	5.3	8/15/00 15:21	15.38
8/15/00 15:22	5.3	8/15/00 15:22	15.24
8/15/00 15:23	5.3	8/15/00 15:23	15.09
8/15/00 15:24	5.3	8/15/00 15:24	13.91
8/15/00 15:25	5.3	8/15/00 15:25	31.31
8/15/00 15:26	5.5	8/15/00 15:26	38.57
8/15/00 15:27	4.3	8/15/00 15:27	16.75
8/15/00 15:28	4.3	8/15/00 15:28	15.56
8/15/00 15:29	4.3	8/15/00 15:29	15.43
8/15/00 15:30	4.3	8/15/00 15:30	25.88
8/15/00 15:31	4.3	8/15/00 15:31	48.6
8/15/00 15:32	4.7	8/15/00 15:32	40.32
8/15/00 15:33	5.3	8/15/00 15:33	17.61
8/15/00 15:34	5	8/15/00 15:34	13.52
8/15/00 15:35	6.1	8/15/00 15:35	20.92
8/15/00 15:36	8.7	8/15/00 15:36	16.19
8/15/00 15:37	5.6	8/15/00 15:37	11.5
8/15/00 15:38	12.1	8/15/00 15:38	11.69
8/15/00 15:39	16.6	8/15/00 15:39	12.36
8/15/00 15:40	8.9	8/15/00 15:40	11.66
8/15/00 15:41	6.4	8/15/00 15:41	11.11
8/15/00 15:42	5.3	8/15/00 15:42	10.78
8/15/00 15:43	5.3	8/15/00 15:43	8.9
8/15/00 15:44	5.3	8/15/00 15:44	7.18
8/15/00 15:45	5.3	8/15/00 15:45	10.55
8/15/00 15:46	13.9	8/15/00 15:46	29.01
8/15/00 15:47	86	8/15/00 15:47	17.1
8/15/00 15:48	147.2	8/15/00 15:48	8.06
8/15/00 15:49	154.3	8/15/00 15:49	8.81
8/15/00 15:50	98.2	8/15/00 15:50	11.52
8/15/00 15:51	35.5	8/15/00 15:51	8.09
8/15/00 15:52	41.6	8/15/00 15:52	5.89
8/15/00 15:53	72.7	8/15/00 15:53	5.06
8/15/00 15:54	115.4	8/15/00 15:54	4.53
8/15/00 15:55	146.7	8/15/00 15:55	4.3
8/15/00 15:56	261.4	8/15/00 15:56	4.14
8/15/00 15:57	503.4	8/15/00 15:57	4.29
8/15/00 15:58	585.8	8/15/00 15:58	3.89
8/15/00 15:59	529	8/15/00 15:59	3.34
8/15/00 16:00	431.1	8/15/00 16:00	4.93
8/15/00 16:01	233.9	8/15/00 16:01	9.34
8/15/00 16:02	122.5	8/15/00 16:02	13.92
8/15/00 16:03	46.2	8/15/00 16:03	11.72
8/15/00 16:04	18	8/15/00 16:04	17.29

8/15/00 16:05	12.2
8/15/00 16:06	32
8/15/00 16:07	168.1
8/15/00 16:08	169.7
8/15/00 16:09	189
8/15/00 16:10	88.8
8/15/00 16:11	30.4
8/15/00 16:12	55.8
8/15/00 16:13	126.2
8/15/00 16:14	240.6
8/15/00 16:15	339.1
8/15/00 16:16	336.5
8/15/00 16:17	257.6
8/15/00 16:18	273.7
8/15/00 16:19	245.2
8/15/00 16:20	360.6
8/15/00 16:21	277.4
8/15/00 16:22	156.4
8/15/00 16:23	90.5
8/15/00 16:24	43.3
8/15/00 16:25	35.4
8/15/00 16:26	40.4
8/15/00 16:27	14.9
8/15/00 16:28	7.6
8/15/00 16:29	5.3
8/15/00 16:30	5.3
8/15/00 16:31	5.3
8/15/00 16:32	5.3
8/15/00 16:33	5.3
8/15/00 16:34	5.3
8/15/00 16:35	5.3
8/15/00 16:36	5.3
8/15/00 16:37	5.3
8/15/00 16:38	5.4
8/15/00 16:39	10.6
8/15/00 16:40	29.9
8/15/00 16:41	22.3
8/15/00 16:42	10.2
8/15/00 16:43	8.2
8/15/00 16:44	6.8
8/15/00 16:45	6.5
8/15/00 16:46	9.2
8/15/00 16:47	6.5
8/15/00 16:48	4.3
8/15/00 16:49	4.9
8/15/00 16:50	5.3
8/15/00 16:51	5.3

8/15/00 16:05	30.24
8/15/00 16:06	29.49
8/15/00 16:07	13.62
8/15/00 16:08	6.3
8/15/00 16:09	7.46
8/15/00 16:10	8.52
8/15/00 16:11	6.18
8/15/00 16:12	5.6
8/15/00 16:13	5.66
8/15/00 16:14	5.3
8/15/00 16:15	4.11
8/15/00 16:16	3.58
8/15/00 16:17	3.83
8/15/00 16:18	3.95
8/15/00 16:19	3.91
8/15/00 16:20	3.15
8/15/00 16:21	2.21
8/15/00 16:22	1.97
8/15/00 16:23	1.89
8/15/00 16:24	2.43
8/15/00 16:25	2.22
8/15/00 16:26	2.26
8/15/00 16:27	3.96
8/15/00 16:28	8.16
8/15/00 16:29	9.59
8/15/00 16:30	9.05
8/15/00 16:31	8.59
8/15/00 16:32	8.44
8/15/00 16:33	8.09
8/15/00 16:34	7.93
8/15/00 16:35	7.87
8/15/00 16:36	7.88
8/15/00 16:37	8.36
8/15/00 16:38	19.95
8/15/00 16:39	11.54
8/15/00 16:40	5.61
8/15/00 16:41	6.4
8/15/00 16:42	9.49
8/15/00 16:43	10.75
8/15/00 16:44	11.83
8/15/00 16:45	14.04
8/15/00 16:46	16.23
8/15/00 16:47	16.1
8/15/00 16:48	17.77
8/15/00 16:49	16.26
8/15/00 16:50	16.4
8/15/00 16:51	16.24

8/15/00 16:52	8.5	8/15/00 16:52	15.28
8/15/00 16:53	12	8/15/00 16:53	20.68
8/15/00 16:54	9.4	8/15/00 16:54	31.86
8/15/00 16:55	10.6	8/15/00 16:55	31.88
8/15/00 16:56	8.1	8/15/00 16:56	31.27
8/15/00 16:57	6.7	8/15/00 16:57	27.3
8/15/00 16:58	15.1	8/15/00 16:58	16.82
8/15/00 16:59	10.6	8/15/00 16:59	14.56
Average:	114.901		9.830256

CEMS CO Data Run3

8/16/00 7:54	12.3
8/16/00 7:55	12.3
8/16/00 7:56	19.8
8/16/00 7:57	28.1
8/16/00 7:58	43
8/16/00 7:59	26.1
8/16/00 8:00	39.3
8/16/00 8:01	56.1
8/16/00 8:02	58.1
8/16/00 8:03	54.1
8/16/00 8:04	170
8/16/00 8:05	85.2
8/16/00 8:06	125.2
8/16/00 8:07	186.4
8/16/00 8:08	187
8/16/00 8:09	198.5
8/16/00 8:10	137.5
8/16/00 8:11	65.8
8/16/00 8:12	29.9
8/16/00 8:13	32.5
8/16/00 8:14	25.8
8/16/00 8:15	15.1
8/16/00 8:16	15.9
8/16/00 8:17	44.3
8/16/00 8:18	106.3
8/16/00 8:19	102.6
8/16/00 8:20	166.7
8/16/00 8:21	169.2
8/16/00 8:22	182.1
8/16/00 8:23	187
8/16/00 8:24	160.7
8/16/00 8:25	157.6
8/16/00 8:26	146.4
8/16/00 8:27	134.9
8/16/00 8:28	189.7
8/16/00 8:29	235.7
8/16/00 8:30	202.9
8/16/00 8:31	256.4
8/16/00 8:32	272.9
8/16/00 8:33	114.3
8/16/00 8:34	56.5
8/16/00 8:35	118.2
8/16/00 8:36	128.1
8/16/00 8:37	141.8
8/16/00 8:38	139.7
8/16/00 8:39	172.4

CEMS Nox Data Run 3

8/16/00 7:54	14.23
8/16/00 7:55	11.84
8/16/00 7:56	10.18
8/16/00 7:57	9.39
8/16/00 7:58	6.96
8/16/00 7:59	6.63
8/16/00 8:00	6.48
8/16/00 8:01	5.91
8/16/00 8:02	5.49
8/16/00 8:03	4.93
8/16/00 8:04	3.9
8/16/00 8:05	3.33
8/16/00 8:06	3.24
8/16/00 8:07	3.23
8/16/00 8:08	3.06
8/16/00 8:09	3.1
8/16/00 8:10	3.44
8/16/00 8:11	6.66
8/16/00 8:12	8.78
8/16/00 8:13	5.64
8/16/00 8:14	5.14
8/16/00 8:15	5.78
8/16/00 8:16	6.39
8/16/00 8:17	6.19
8/16/00 8:18	5.67
8/16/00 8:19	5.5
8/16/00 8:20	6
8/16/00 8:21	6.42
8/16/00 8:22	5.37
8/16/00 8:23	4.32
8/16/00 8:24	3.2
8/16/00 8:25	3.11
8/16/00 8:26	3.41
8/16/00 8:27	4.94
8/16/00 8:28	5.44
8/16/00 8:29	3.64
8/16/00 8:30	2.75
8/16/00 8:31	2.29
8/16/00 8:32	3.88
8/16/00 8:33	14.93
8/16/00 8:34	18.25
8/16/00 8:35	6.42
8/16/00 8:36	4.18
8/16/00 8:37	4.09
8/16/00 8:38	3.59
8/16/00 8:39	3.5

8/16/00 8:40	219.6	8/16/00 8:40	3.27
8/16/00 8:41	206.9	8/16/00 8:41	2.81
8/16/00 8:42	267.3	8/16/00 8:42	2.71
8/16/00 8:43	278.8	8/16/00 8:43	2.93
8/16/00 8:44	126.6	8/16/00 8:44	7.26
8/16/00 8:45	87.3	8/16/00 8:45	11.16
8/16/00 8:46	88.2	8/16/00 8:46	6.18
8/16/00 8:47	36.1	8/16/00 8:47	13.1
8/16/00 8:48	26.5	8/16/00 8:48	20.2
8/16/00 8:49	24.6	8/16/00 8:49	18.18
8/16/00 8:50	22.1	8/16/00 8:50	16.91
8/16/00 8:51	28.1	8/16/00 8:51	15.96
8/16/00 8:52	18.1	8/16/00 8:52	14.68
8/16/00 8:53	14.8	8/16/00 8:53	14.03
8/16/00 8:54	13	8/16/00 8:54	13.12
8/16/00 8:55	18	8/16/00 8:55	10.36
8/16/00 8:56	24.2	8/16/00 8:56	8.9
8/16/00 8:57	27.5	8/16/00 8:57	6.07
8/16/00 8:58	18	8/16/00 8:58	6.24
8/16/00 8:59	25.2	8/16/00 8:59	6.87
8/16/00 9:00	67.6	8/16/00 9:00	5.57
8/16/00 9:01	61.8	8/16/00 9:01	4.26
8/16/00 9:02	79.3	8/16/00 9:02	4
8/16/00 9:03	80.6	8/16/00 9:03	2.96
8/16/00 9:04	68.3	8/16/00 9:04	2.75
8/16/00 9:05	92.6	8/16/00 9:05	2.97
8/16/00 9:06	118.1	8/16/00 9:06	3.23
8/16/00 9:07	159.7	8/16/00 9:07	2.8
8/16/00 9:08	170.5	8/16/00 9:08	2.3
8/16/00 9:09	111.2	8/16/00 9:09	2.68
8/16/00 9:10	125.9	8/16/00 9:10	3.92
8/16/00 9:11	169.7	8/16/00 9:11	4.88
8/16/00 9:12	200	8/16/00 9:12	5.01
8/16/00 9:13	195.2	8/16/00 9:13	5.65
8/16/00 9:14	135.1	8/16/00 9:14	5.6
8/16/00 9:15	201.5	8/16/00 9:15	4.62
8/16/00 9:16	158	8/16/00 9:16	4.02
8/16/00 9:17	151.4	8/16/00 9:17	3.89
8/16/00 9:18	134.2	8/16/00 9:18	4.05
8/16/00 9:19	103.4	8/16/00 9:19	3.59
8/16/00 9:20	93.9	8/16/00 9:20	3.54
8/16/00 9:21	95.4	8/16/00 9:21	3.62
8/16/00 9:22	94.4	8/16/00 9:22	3.57
8/16/00 9:23	95.5	8/16/00 9:23	3.63
8/16/00 9:24	99.4	8/16/00 9:24	3.44
8/16/00 9:25	83.7	8/16/00 9:25	3.3
8/16/00 9:26	86.5	8/16/00 9:26	3.2

8/16/00 9:27	95.2	8/16/00 9:27	3.28
8/16/00 9:28	101.2	8/16/00 9:28	3.25
8/16/00 9:29	80	8/16/00 9:29	3.19
8/16/00 9:30	84.5	8/16/00 9:30	3.48
8/16/00 9:31	97.2	8/16/00 9:31	3.11
8/16/00 9:32	127.1	8/16/00 9:32	5.23
8/16/00 9:33	38	8/16/00 9:33	5.96
8/16/00 9:34	25.2	8/16/00 9:34	4.69
8/16/00 9:35	111.8	8/16/00 9:35	4.55
8/16/00 9:36	296.4	8/16/00 9:36	4.61
8/16/00 9:37	295.5	8/16/00 9:37	4.92
8/16/00 9:38	335.1	8/16/00 9:38	5.62
8/16/00 9:39	217.8	8/16/00 9:39	6.41
8/16/00 9:40	242.1	8/16/00 9:40	6.45
8/16/00 9:41	374.5	8/16/00 9:41	6.31
8/16/00 9:42	666.5	8/16/00 9:42	5.72
8/16/00 9:43	463.6	8/16/00 9:43	5.34
8/16/00 9:44	334.5	8/16/00 9:44	4.35
8/16/00 9:45	220.9	8/16/00 9:45	3.29
8/16/00 9:46	202.4	8/16/00 9:46	3
8/16/00 9:47	189.4	8/16/00 9:47	2.94
8/16/00 9:48	156.4	8/16/00 9:48	2.34
8/16/00 9:49	141.4	8/16/00 9:49	2.43
8/16/00 9:50	124.6	8/16/00 9:50	3.08
8/16/00 9:51	75.4	8/16/00 9:51	8.3
8/16/00 9:52	103.1	8/16/00 9:52	6.25
8/16/00 9:53	98.1	8/16/00 9:53	2.81
8/16/00 9:54	150.3	8/16/00 9:54	2.48
8/16/00 9:55	160.8	8/16/00 9:55	2.71
8/16/00 9:56	147.7	8/16/00 9:56	3.08
8/16/00 9:57	146.4	8/16/00 9:57	3.86
8/16/00 9:58	86.5	8/16/00 9:58	4.35
8/16/00 9:59	68.6	8/16/00 9:59	3.97
8/16/00 10:00	64.2	8/16/00 10:00	7.48
8/16/00 10:01	38	8/16/00 10:01	17.3
8/16/00 10:02	84.1	8/16/00 10:02	5.38
8/16/00 10:03	58.3	8/16/00 10:03	4.55
8/16/00 10:04	18.7	8/16/00 10:04	15.92
8/16/00 10:05	13.2	8/16/00 10:05	17.67
8/16/00 10:06	11.2	8/16/00 10:06	15.15
8/16/00 10:07	10.1	8/16/00 10:07	14.34
8/16/00 10:08	9.6	8/16/00 10:08	13.48
8/16/00 10:09	8.6	8/16/00 10:09	13.35
8/16/00 10:10	8.3	8/16/00 10:10	13.3
8/16/00 10:11	8.3	8/16/00 10:11	13.22
8/16/00 10:12	7.3	8/16/00 10:12	13.33
8/16/00 10:13	7.3	8/16/00 10:13	13.08

8/16/00 10:14	7.3	8/16/00 10:14	12.85
8/16/00 10:15	8.2	8/16/00 10:15	12.79
8/16/00 10:16	20.1	8/16/00 10:16	13.31
8/16/00 10:17	13.7	8/16/00 10:17	13.17
8/16/00 10:18	24.5	8/16/00 10:18	14
8/16/00 10:19	19.5	8/16/00 10:19	13.76
8/16/00 10:20	10.1	8/16/00 10:20	13.16
8/16/00 10:21	7.8	8/16/00 10:21	12.78
8/16/00 10:22	7.3	8/16/00 10:22	12.86
8/16/00 10:23	7.3	8/16/00 10:23	13.02
8/16/00 10:24	8	8/16/00 10:24	12.95
8/16/00 10:25	7.1	8/16/00 10:25	12.75
8/16/00 10:26	6.3	8/16/00 10:26	12.55
8/16/00 10:27	6.3	8/16/00 10:27	12.51
8/16/00 10:28	6.3	8/16/00 10:28	12.37
8/16/00 10:29	6.3	8/16/00 10:29	11.79
8/16/00 10:30	7	8/16/00 10:30	9.45
8/16/00 10:31	8.2	8/16/00 10:31	9.12
8/16/00 10:32	8.3	8/16/00 10:32	9.04
8/16/00 10:33	8.8	8/16/00 10:33	8.96
8/16/00 10:34	8.3	8/16/00 10:34	8.78
8/16/00 10:35	8.4	8/16/00 10:35	9.02
8/16/00 10:36	9.2	8/16/00 10:36	9.15
8/16/00 10:37	8.3	8/16/00 10:37	9.35
8/16/00 10:38	33.7	8/16/00 10:38	10.69
8/16/00 10:39	60.2	8/16/00 10:39	9.14
8/16/00 10:40	106.1	8/16/00 10:40	6.58
8/16/00 10:41	159.4	8/16/00 10:41	6.99
8/16/00 10:42	62.6	8/16/00 10:42	6.64
8/16/00 10:43	45.6	8/16/00 10:43	6.12
8/16/00 10:44	65.6	8/16/00 10:44	5.33
8/16/00 10:45	86	8/16/00 10:45	4.69
8/16/00 10:46	118.8	8/16/00 10:46	4.56
8/16/00 10:47	110.3	8/16/00 10:47	3.9
8/16/00 10:48	99.8	8/16/00 10:48	3.5
8/16/00 10:49	117.6	8/16/00 10:49	3.89
8/16/00 10:50	255.6	8/16/00 10:50	4.62
8/16/00 10:51	464.7	8/16/00 10:51	4.27
8/16/00 10:52	562.2	8/16/00 10:52	3.92
8/16/00 10:53	364.9	8/16/00 10:53	2.78
8/16/00 10:54	242.9	8/16/00 10:54	2.29
8/16/00 10:55	199.9	8/16/00 10:55	2.41
8/16/00 10:56	97.2	8/16/00 10:56	5.72
8/16/00 10:57	44	8/16/00 10:57	8.11
8/16/00 10:58	94.7	8/16/00 10:58	6.78
8/16/00 10:59	70.8	8/16/00 10:59	4.87
8/16/00 11:00	84.8	8/16/00 11:00	4.56

8/16/00 11:01	192.4
8/16/00 11:02	57.5
8/16/00 11:03	30.8
8/16/00 11:04	85
8/16/00 11:05	188.9
8/16/00 11:06	267.8
8/16/00 11:07	205.8
8/16/00 11:08	199.4
8/16/00 11:09	229.3
8/16/00 11:10	241.7
8/16/00 11:11	269.1
8/16/00 11:12	474.1
8/16/00 11:13	484.4
8/16/00 11:14	231.8
8/16/00 11:15	156.8
8/16/00 11:16	162.3
8/16/00 11:17	160.8
8/16/00 11:18	184.2
8/16/00 11:19	190.6
8/16/00 11:20	152
8/16/00 11:21	75.6
8/16/00 11:22	143.6
8/16/00 11:23	234.7
8/16/00 11:24	215.2
8/16/00 11:25	199.1
8/16/00 11:26	209.8
8/16/00 11:27	259.3
8/16/00 11:28	232.6
8/16/00 11:29	288.1
8/16/00 11:30	391.2
8/16/00 11:31	150.9
8/16/00 11:32	35.8
8/16/00 11:33	23.7
8/16/00 11:34	17.7
8/16/00 11:35	20.8
8/16/00 11:36	17
8/16/00 11:37	42.7
8/16/00 11:38	36.9
8/16/00 11:39	17.6
8/16/00 11:40	12.9
8/16/00 11:41	12.3
8/16/00 11:42	14.8
8/16/00 11:43	44.6
8/16/00 11:44	57.1
8/16/00 11:45	37.5
8/16/00 11:46	55
8/16/00 11:47	87

8/16/00 11:01	5.36
8/16/00 11:02	6.07
8/16/00 11:03	5.41
8/16/00 11:04	5.16
8/16/00 11:05	5.25
8/16/00 11:06	5.08
8/16/00 11:07	5.25
8/16/00 11:08	5.09
8/16/00 11:09	5.3
8/16/00 11:10	5.16
8/16/00 11:11	5.04
8/16/00 11:12	4.42
8/16/00 11:13	4.01
8/16/00 11:14	3.41
8/16/00 11:15	4.41
8/16/00 11:16	3.24
8/16/00 11:17	2.38
8/16/00 11:18	2.32
8/16/00 11:19	2.63
8/16/00 11:20	8.6
8/16/00 11:21	12.05
8/16/00 11:22	4.18
8/16/00 11:23	2.98
8/16/00 11:24	3.19
8/16/00 11:25	3.25
8/16/00 11:26	3.11
8/16/00 11:27	3.12
8/16/00 11:28	3.41
8/16/00 11:29	3.73
8/16/00 11:30	4.04
8/16/00 11:31	9.82
8/16/00 11:32	22.8
8/16/00 11:33	28.79
8/16/00 11:34	19.73
8/16/00 11:35	17.1
8/16/00 11:36	15.6
8/16/00 11:37	16.03
8/16/00 11:38	14.84
8/16/00 11:39	13.84
8/16/00 11:40	13.72
8/16/00 11:41	13.67
8/16/00 11:42	11.3
8/16/00 11:43	11.47
8/16/00 11:44	7.3
8/16/00 11:45	5.35
8/16/00 11:46	5
8/16/00 11:47	4.72

8/16/00 11:48	126
8/16/00 11:49	191.5
8/16/00 11:50	189.8
8/16/00 11:51	196.3
8/16/00 11:52	191
8/16/00 11:53	210.1
8/16/00 11:54	283.8
8/16/00 11:55	263.2
8/16/00 11:56	221.1
8/16/00 11:57	172.5
8/16/00 11:58	138.1
8/16/00 11:59	100.8
8/16/00 12:00	40
8/16/00 12:01	53.2
8/16/00 12:02	133.4
8/16/00 12:03	53.3
8/16/00 12:04	79.3
8/16/00 12:05	256.8
8/16/00 12:06	580.9
8/16/00 12:07	515.8
8/16/00 12:08	556.5
8/16/00 12:09	436.8
8/16/00 12:10	323.2
8/16/00 12:11	347.7
8/16/00 12:12	387.4
8/16/00 12:13	502.4
8/16/00 12:14	358.5
Average	142.7695

8/16/00 11:48	4.43
8/16/00 11:49	4.26
8/16/00 11:50	3.9
8/16/00 11:51	3.23
8/16/00 11:52	2.9
8/16/00 11:53	3.4
8/16/00 11:54	3.64
8/16/00 11:55	2.73
8/16/00 11:56	2.17
8/16/00 11:57	1.91
8/16/00 11:58	1.89
8/16/00 11:59	4.69
8/16/00 12:00	14.79
8/16/00 12:01	6.3
8/16/00 12:02	7.49
8/16/00 12:03	7.31
8/16/00 12:04	6.26
8/16/00 12:05	5.1
8/16/00 12:06	4.79
8/16/00 12:07	4.42
8/16/00 12:08	3.51
8/16/00 12:09	2.96
8/16/00 12:10	2.54
8/16/00 12:11	3.19
8/16/00 12:12	3.28
8/16/00 12:13	3.13
8/16/00 12:14	2.83

6.845187

CEMS CO Data RUn4

8/16/00 13:09	110.9
8/16/00 13:10	42.4
8/16/00 13:11	11.9
8/16/00 13:12	8.6
8/16/00 13:13	31.5
8/16/00 13:14	57.9
8/16/00 13:15	52.8
8/16/00 13:16	24.4
8/16/00 13:17	6.23
8/16/00 13:18	6.09
8/16/00 13:19	152.3
8/16/00 13:20	246.2
8/16/00 13:21	298.7
8/16/00 13:22	204.8
8/16/00 13:23	248.6
8/16/00 13:24	310.6
8/16/00 13:25	274.9
8/16/00 13:26	170.5
8/16/00 13:27	168.5
8/16/00 13:28	107.6
8/16/00 13:29	28.5
8/16/00 13:30	17.7
8/16/00 13:31	52.4
8/16/00 13:32	66.9
8/16/00 13:33	25.3
8/16/00 13:34	8.4
8/16/00 13:35	9.5
8/16/00 13:36	6
8/16/00 13:37	17.2
8/16/00 13:38	45.9
8/16/00 13:39	99.7
8/16/00 13:40	68.1
8/16/00 13:41	46.1
8/16/00 13:42	50.5
8/16/00 13:43	81.2
8/16/00 13:44	40.2
8/16/00 13:45	18.2
8/16/00 13:46	12.1
8/16/00 13:47	13.1
8/16/00 13:48	10.9
8/16/00 13:49	12.7
8/16/00 13:50	60.2
8/16/00 13:51	36.2
8/16/00 13:52	9.2
8/16/00 13:53	7.3
8/16/00 13:54	9

CEMS Nox Data Run4

8/16/00 13:09	2.25
8/16/00 13:10	8.45
8/16/00 13:11	9.21
8/16/00 13:12	7.98
8/16/00 13:13	7.59
8/16/00 13:14	6.23
8/16/00 13:15	5.83
8/16/00 13:16	5.91
8/16/00 13:17	6.23
8/16/00 13:18	6.09
8/16/00 13:19	5.5
8/16/00 13:20	4.79
8/16/00 13:21	4.75
8/16/00 13:22	4.42
8/16/00 13:23	4.02
8/16/00 13:24	3.52
8/16/00 13:25	3.43
8/16/00 13:26	5.06
8/16/00 13:27	7.64
8/16/00 13:28	8.34
8/16/00 13:29	15.63
8/16/00 13:30	16.27
8/16/00 13:31	9.11
8/16/00 13:32	6.64
8/16/00 13:33	9.55
8/16/00 13:34	16.05
8/16/00 13:35	18.78
8/16/00 13:36	17.77
8/16/00 13:37	15.01
8/16/00 13:38	8.83
8/16/00 13:39	3.92
8/16/00 13:40	7.44
8/16/00 13:41	10.05
8/16/00 13:42	8.41
8/16/00 13:43	6.69
8/16/00 13:44	15.49
8/16/00 13:45	23.77
8/16/00 13:46	46.9
8/16/00 13:47	27.6
8/16/00 13:48	14.77
8/16/00 13:49	12.28
8/16/00 13:50	6.4
8/16/00 13:51	10.9
8/16/00 13:52	13.28
8/16/00 13:53	13.33
8/16/00 13:54	14.11

8/16/00 13:55	9.5	8/16/00 13:55	14.14
8/16/00 13:56	23.1	8/16/00 13:56	14.77
8/16/00 13:57	22.3	8/16/00 13:57	14.48
8/16/00 13:58	9.3	8/16/00 13:58	12.99
8/16/00 13:59	7.4	8/16/00 13:59	13.04
8/16/00 14:00	7.3	8/16/00 14:00	11.78
8/16/00 14:01	8.2	8/16/00 14:01	10.3
8/16/00 14:02	9.3	8/16/00 14:02	10.53
8/16/00 14:03	10	8/16/00 14:03	10.47
8/16/00 14:04	9.4	8/16/00 14:04	8.83
8/16/00 14:05	9.3	8/16/00 14:05	3.58
8/16/00 14:06	9.3	8/16/00 14:06	2.25
8/16/00 14:07	9.2	8/16/00 14:07	2.18
8/16/00 14:08	8.7	8/16/00 14:08	2.18
8/16/00 14:09	9.3	8/16/00 14:09	2.02
8/16/00 14:10	9.1	8/16/00 14:10	1.56
8/16/00 14:11	9.3	8/16/00 14:11	1.6
8/16/00 14:12	8.4	8/16/00 14:12	1.96
8/16/00 14:13	8.7	8/16/00 14:13	2.32
8/16/00 14:14	9.3	8/16/00 14:14	2.09
8/16/00 14:15	9.3	8/16/00 14:15	1.64
8/16/00 14:16	9.3	8/16/00 14:16	1.4
8/16/00 14:17	8.7	8/16/00 14:17	1.39
8/16/00 14:18	8.3	8/16/00 14:18	1.52
8/16/00 14:19	15.4	8/16/00 14:19	5.19
8/16/00 14:20	48.6	8/16/00 14:20	12.81
8/16/00 14:21	82.7	8/16/00 14:21	8.54
8/16/00 14:22	60.9	8/16/00 14:22	5.9
8/16/00 14:23	62.1	8/16/00 14:23	4.64
8/16/00 14:24	75.6	8/16/00 14:24	3.77
8/16/00 14:25	89.8	8/16/00 14:25	4.13
8/16/00 14:26	106.4	8/16/00 14:26	3.41
8/16/00 14:27	138	8/16/00 14:27	2.8
8/16/00 14:28	143.5	8/16/00 14:28	2.76
8/16/00 14:29	202.2	8/16/00 14:29	2.82
8/16/00 14:30	239.2	8/16/00 14:30	2.78
8/16/00 14:31	249	8/16/00 14:31	4.67
8/16/00 14:32	178	8/16/00 14:32	7.36
8/16/00 14:33	124.9	8/16/00 14:33	5.42
8/16/00 14:34	69.8	8/16/00 14:34	8.46
8/16/00 14:35	18.2	8/16/00 14:35	11.97
8/16/00 14:36	35.4	8/16/00 14:36	13.54
8/16/00 14:37	58.4	8/16/00 14:37	9.22
8/16/00 14:38	54.2	8/16/00 14:38	7.1
8/16/00 14:39	40.8	8/16/00 14:39	6.78
8/16/00 14:40	40.9	8/16/00 14:40	6.67
8/16/00 14:41	68.3	8/16/00 14:41	6.06

8/16/00 14:42	105	8/16/00 14:42	5.28
8/16/00 14:43	190.1	8/16/00 14:43	4.82
8/16/00 14:44	451.1	8/16/00 14:44	4.62
8/16/00 14:45	409.2	8/16/00 14:45	4.12
8/16/00 14:46	552	8/16/00 14:46	3.68
8/16/00 14:47	680.3	8/16/00 14:47	3.34
8/16/00 14:48	527.2	8/16/00 14:48	3.1
8/16/00 14:49	287.9	8/16/00 14:49	2.77
8/16/00 14:50	285.6	8/16/00 14:50	2.52
8/16/00 14:51	255.7	8/16/00 14:51	2.53
8/16/00 14:52	192.9	8/16/00 14:52	3.67
8/16/00 14:53	88.8	8/16/00 14:53	5.91
8/16/00 14:54	53.7	8/16/00 14:54	9.28
8/16/00 14:55	11.5	8/16/00 14:55	10.91
8/16/00 14:56	6.4	8/16/00 14:56	11.64
8/16/00 14:57	6.6	8/16/00 14:57	10.21
8/16/00 14:58	3	8/16/00 14:58	1.61
8/16/00 14:59	2.3	8/16/00 14:59	-0.02
8/16/00 15:00	2.3	8/16/00 15:00	-0.02
8/16/00 15:01	22.9	8/16/00 15:01	17.27
8/16/00 15:02	52.2	8/16/00 15:02	54.71
8/16/00 15:03	52.3	8/16/00 15:03	56.4
8/16/00 15:04	52.3	8/16/00 15:04	56.4
8/16/00 15:05	52.3	8/16/00 15:05	56.43
8/16/00 15:06	76.9	8/16/00 15:06	56.49
8/16/00 15:07	5.4	8/16/00 15:07	56.35
8/16/00 15:08	25.2	8/16/00 15:08	56.39
8/16/00 15:09	52.3	8/16/00 15:09	56.4
Average	85.86777		11.06488

Calibration Error Test, Run 1 STRATA Version 1.2.1

Operator: Peter Hilty
 Plant Name: Newport Steel
 Location: EAF Collector Exhaust

	Reference Cylinder Numbers			
	Zero	Low-range	Mid-range	High-range
O2	N2		CC84981	Air
CO2	N2		CC84981	CC113935
CO	N2	CC113985	CC113935	CC11790
NOx	N2	CC118512	CC106973	CC79974
SO2	N2	400&20%	400*60%	CC5784

Date/Time	08-14-2000		13:12:59		PASSED
Analyte	O2	CO2	CO	NOx	SO2
Units	%	%	ppm	ppm	ppm
Zero Ref Cyl	0.000	0.000	0.0	0.00	0.0
Zero Avg	0.018	-0.043	0.4	0.24	-0.2
Zero Error%	0.1%	0.2%	0.0%	0.0%	0.0%
Low Ref Cyl			50.0	50.50	
Low Avg			50.1	50.46	
Low Error%			0.0%	0.0%	
Mid Ref Cyl			100.0	89.30	
Mid Avg			98.2	88.74	
Mid Error%			0.2%	0.1%	
High Ref Cyl	20.900	15.000	152.0	197.40	400-0
High Avg	20.841	14.980	150.5	197.47	400.0
High Error%	0.2%	0.1%	0.2%	0.0%	0.0%

Calibration Error Test End

Calibration Error Test, Run 1 STRATA Version 1.2.1
 Operator: Peter Hilty
 Plant Name: Newport Steel
 Location: EAF Exhaust/Baghouse Inlet

	Reference Cylinder Numbers			
	Zero	Low - range	Mid - range	High - range
O2	N2		CC84981	Air
CO2	N2		CC84981	CC113935
CO	N2	CC113985	CC113935	CC94790
NOx	N2	CC118512	CC106973	CC79974
SO2	N2	400&20%	400*60%	CC5784

Date/Time	08-15-2000		07:39:45		PASSED
Analyte	O2	CO2	CO	NOx	SO2
Units	%	%	ppm	ppm	ppm
Zero Ref Cyl	0.000	0.000	0.0	0.00	0.0
Zero Avg	0.022	-0.267	-5.5	0.81	0.3
Zero Error%	0.1%	1.3%	0.6%	0.3%	0.0%
Low Ref Cyl			50.0	50.50	80.0
Low Avg			46.1	50.15	81.8
Low Error%			0.4%	0.1%	0.2%
Mid Ref Cyl	10.000	8.000	100.0	89.30	240.0
Mid Avg	9.934	8.016	94.7	89.22	227.0
Mid Error%	0.3%	0.1%	0.5%	0.0%	1.3%
High Ref Cyl	20.900	15.000	152.0	197.40	400.0
High Avg	20.896	14.993	147.1	197.68	393.3
High Error%	0.0%	0.0%	0.5%	0.1%	0.7%

Calibration Error **Test** End

Initial System Bias Check, Run 1 STRATA Version 1.2.1

Operator: Peter Hilty

Plant Name: Newport Steel

Location: EAF Exhaust/Baghouse Inlet

Reference Cylinder Numbers

	Zero	Span
O2	N2	Air
CO2	N2	CC84981
CO	N2	CC113985
NOx	N2	CC118512
SO2	N2	CC5784

Date/Time	08-15-2000	07:50:41	PASSED
Analyte	O2	CO2	CO
Units	%	%	ppm
Zero Ref Cyl	0.000	0.000	0.0
Zero Cal	0.022	-0.267	-5.5
Zero Avg	-0.032	-0.219	-2.1
Zero Bias%	0.2%	0.2%	0.3%
Zero Drift%			
Span Ref Cyl	20.900	8.000	50.0
Span Cal	20.896	8.016	46.1
Span Avg	20.903	8.014	47.1
Span Bias%	0.0%	0.0%	0.1%
Span Drift%			
System Bias Check End			

Final System Bias Check, Run 1 STRATA Version 1.2.1

Operator: Peter Hilty
 Plant Name: Newport Steel
 Location: EAF Exhaust/Baghouse Inlet

Reference Cylinder Numbers

	Zero	Span
O2	N2	Air
CO2	N2	CC84981
CO	N2	CC113985
NOx	N2	CC118512
SO2	N2	CC5784

Date/Time	08-15-2000		12:25:04		PASSED
Analyte	O2	CO2	CO	NOx	SO2
Units	%	%	ppm	ppm	ppm
Zero Ref Cyl	0.000	0.000	0.0	0.00	0.0
Zero Cal	0.022	-0.267	-5.5	0.81	0.3
Zero Avg	-0.086	-0.301	-10.0	1.77	-1.9
Zero Bias%	0.4%	0.28	0.4%	0.4%	0.2%
Zero Drift%	-0.2%	-0.48	-0.8%	0.4%	-0.2%
Span Ref Cyl	20.900	8.000	50.0	50.50	400.0
Span Cal	20.896	8.016	46.1	50.15	393.3
Span Avg	20.824	7.992	39.5	51.43	399.0
Span Bias%	0.3%	0.1%	0.7%	0.5%	0.6%
Span Drift%	-0.3%	-0.1%	-0.8%	0.6%	0.7%
Ini Zero Avg	-0.032	-0.219	-2.1	0.69	0.2
Ini Span Avg	20.903	8.014	47.1	49.91	392.4
Run Avg	20.597	0.267	97.5	10.23	31.9
Co	-0.059	-0.260	-6.0	1.23	-0.8
Cm	20.864	8.003	43.3	50.67	395.7
Correct Avg	20.633	0.510	105.0	9.19	33.1
System Bias Check End					

Test Run 2 STRATA Version 1.2.1

		O2 %	CO2 %	CO ppm	NOx ppm	SO2 ppm
08-15-2000	17:10:33	25.066*	13.097*	3289.2*	9.68*	1906.6*
08-15-2000	17:11:33	20.384	0.430	21.2	7.86	-3.1
08-15-2000	17:12:33	20.418	0.402	22.9	7.46	-3.1
08-15-2000	17:13:33	20.454	0.405	98.4	7.37	-3.1
08-15-2000	17:14:34	20.441	0.429	198.0	7.36	-3.2
08-15-2000	17:15:34	20.392	0.474	290.4	6.38	-3.2
08-15-2000	17:16:34	20.378	0.484	337.7	5.57	-3.3
08-15-2000	17:17:34	20.348	0.510	239.3	5.58	-3.3
08-15-2000	17:18:34	20.355	0.507	255.3	5.73	-3.3
08-15-2000	17:19:34	20.333	0.527	241.0	6.11	-3.3
08-15-2000	17:20:34	20.370	0.481	393.5	5.40	-3.3
08-15-2000	17:21:34	20.414	0.430	291.8	4.32	-3.3
08-15-2000	17:22:32	20.476	0.370	155.1	4.33	-3.3
08-15-2000	17:23:32	20.484	0.344	108.1	4.02	-3.3
08-15-2000	17:24:32	20.532	0.335	36.2	4.50	-3.3
08-15-2000	17:25:32	20.501	0.406	26.0	4.58	-3.2
08-15-2000	17:26:32	20.475	0.461	36.1	4.26	-3.2
08-15-2000	17:27:32	20.499	0.368	9.5	5.33	-3.2
08-15-2000	17:28:32	20.582	0.241	-2.1	8.22	-3.2
08-15-2000	17:29:33	20.662	0.156	-6.8	10.98	-3.2
08-15-2000	17:30:33	20.687	0.138	-6.8	10.41	-3.2
08-15-2000	17:31:33	20.700	0.119	-10.6	9.75	-3.2
08-15-2000	17:32:33	20.716	0.106	-7.1	9.56	-3.2
08-15-2000	17:33:33	20.721	0.102	-6.9	9.45	-3.2
08-15-2000	17:34:33	20.721	0.099	-6.5	9.25	-3.2
08-15-2000	17:35:33	20.724	0.093	-6.4	9.06	-3.2
08-15-2000	17:36:33	20.726	0.089	-5.9	9.13	-3.2
08-15-2000	17:37:33	20.726	0.087	-6.2	9.28	-3.2
08-15-2000	17:38:33	20.702	0.124	-6.7	14.05	-3.2
08-15-2000	17:39:33	20.580	0.281	-4.2	19.04	-3.2
08-15-2000	17:40:33	20.500	0.474	8.6	7.37	-3.2
08-15-2000	17:41:33	20.429	0.548	23.3	6.89	-3.2
08-15-2000	17:42:33	20.518	0.393	0.2	9.77	-3.2
08-15-2000	17:43:33	20.536	0.367	-2.7	11.42	-3.2
08-15-2000	17:44:33	20.517	0.415	-4.0	12.25	-3.2
08-15-2000	17:45:33	20.551	0.357	-5.1	13.58	-3.1
08-15-2000	17:46:33	20.554	0.357	-3.6	17.04	-3.1
08-15-2000	17:47:33	20.537	0.355	-2.6	15.46	-3.1
08-15-2000	17:48:33	20.593	0.293	-7.1	17.57	-3.1
08-15-2000	17:49:34	20.631	0.229	-7.1	16.94	-3.1
08-15-2000	17:50:34	20.640	0.202	-6.1	16.31	-3.1
08-15-2000	17:51:34	20.640	0.225	-5.6	16.46	-3.1
08-15-2000	17:52:34	20.620	0.255	-4.7	15.76	-3.2
08-15-2000	17:53:34	20.556	0.315	1.5	16.78	-3.2
08-15-2000	17:54:34	20.518	0.357	-0.3	25.06	-3.2

Test Run 2 STRATA Version 1.2.1

		02 g	C02 %	CO ppm	NOx ppm	SO2 ppm
08-15-2003	14:43:34	25.148*	24.468*	3674.7*	63.93*	1833.6*
08-15-2000	14:44:34	20.761	-0.012	2.9	2.90	-2.7
08-15-2000	14:45:34	20.760	-0.012	3.0	2.65	-2.7
08-15-2000	14:46:34	20.759	-0.013	3.3	2.66	-2.7
08-15-2000	14:47:32	20.760	-0.013	2.8	3.01	-2.7
08-15-2000	14:48:32	20.755	-0.002	5.1	3.17	-2.8
08-15-2000	14:49:32	20.619	0.155	75.4	3.72	-2.8
08-15-2000	14:50:32	20.697	0.036	71.7	3.33	-2.8
08-15-2000	14:51:32	20.734	0.013	36.7	3.11	-2.8
08-15-2000	14:52:32	20.743	0.005	24.3	2.73	-2.8
08-15-2000	14:53:32	20.746	0.009	21.1	2.66	-2.8
08-15-2000	14:54:32	20.592	0.141	49.4	12.48	-2.8
08-15-2000	14:55:33	20.539	0.163	134.2	4.66	-2.8
08-15-2000	14:56:33	20.499	0.211	123.2	3.91	-2.8
08-15-2000	14:57:33	20.472	0.233	101.8	4.05	-2.8
08-15-2000	14:58:33	20.478	0.233	86.3	4.31	-2.8
08-15-2000	14:59:33	20.436	0.277	109.9	3.60	-2.8
08-15-2000	15:00:33	20.430	0.285	105.7	3.41	-2.8
08-15-2000	15:01:33	20.435	0.274	88.2	3.52	-2.8
08-15-2000	15:02:33	20.401	0.338	92.6	3.89	-2.9
08-15-2000	15:03:33	20.426	0.311	103.3	4.24	-2.8
08-15-2000	15:04:33	20.431	0.317	102.8	5.31	-2.8
08-15-2000	15:05:33	20.439	0.320	138.9	4.29	-2.7
08-15-2000	15:06:33	20.438	0.311	150.8	3.50	-2.7
08-15-2000	15:07:33	20.433	0.355	174.3	3.71	-2.7
08-15-2000	15:08:34	20.436	0.316	105.3	3.92	-2.9
08-15-2000	15:09:34	20.522	0.251	59.6	3.95	-2.7
08-15-2000	15:10:34	20.593	0.228	47.1	6.43	-2.7
08-15-2000	15:11:34	20.490	0.323	87.6	5.06	-2.8
08-15-2000	15:12:34	20.370	0.448	123.0	3.38	-2.8
08-15-2000	15:13:34	20.506	0.255	29.8	3.83	-2.8
08-15-2000	15:14:34	20.644	0.163	0.4	4.88	-2.8
08-15-2000	15:15:34	20.664	0.142	1.3	5.29	-2.8
08-15-2000	15:16:34	20.654	0.126	1.1	5.35	-2.9
08-15-2000	15:17:34	20.689	0.123	0.3	5.48	-2.8
08-15-2000	15:18:32	20.689	0.121	3.3	5.63	-2.8
08-15-2000	15:19:32	20.698	0.099	10.8	5.70	-2.8
08-15-2000	15:20:32	20.629	0.176	17.0	8.76	-2.8
08-15-2000	15:21:32	20.657	0.143	18.9	8.14	-2.8
08-15-2000	15:22:32	20.662	0.127	16.9	7.32	-2.8
08-15-2000	15:23:33	20.667	0.120	17.4	7.42	-2.8
08-15-2000	15:24:33	30.662	0.137	18.9	7.80	-2.8
08-15-2000	15:25:33	20.661	0.129	10.7	7.29	-2.8
08-15-2000	15:26:33	20.686	0.101	6.2	6.17	-2.8
08-15-2000	15:27:33	20.689	0.095	5.9	5.87	-2.8
08-15-2000	15:28:33	20.644	0.147	6.7	6.81	-2.9
08-15-2000	15:29:33	20.598	0.164	3.5	7.00	-2.9
08-15-2000	15:30:33	20.584	0.199	4.2	10.55	-2.9
08-15-2000	15:31:33	20.531	0.263	156.4	8.68	-2.9

Test Run 2 Begin. STRATA Version 1.2.1
 Operator: Peter Hilty
 Plant Name: Newport Steel
 Location: EAF Exhaust/Baghouse Inlet

	02 %	CO2 %	CO ppm	NOx ppm	SO2 ppm
Begin calculating run averages					
8/15/00 13:55:32	20.484	0.401	7.8	13.59	-2.4
8/15/00 13:56:33	20.493	0.412	4.2	16.63	-2.4
8/15/00 13:57:33	20.442	0.563	63	8.05	-2.4
8/15/00 13:58:34	20.532	0.313	14.1	14.79	-2.4
8/15/00 14:01:34	20.657	0.203	0.9	14.64	-2.5
8/15/00 14:02:34	20.679	0.181	0.8	16.27	-2.5
8/15/00 14:03:34	20.699	0.152	0.6	18.43	-2.5
8/15/00 14:04:32	20.709	0.142	0.8	17.7	-2.5
8/15/00 14:05:32	20.702	0.139	1.6	16.99	-2.5
8/15/00 14:06:32	20.714	0.129	1.1	15.57	-2.5
8/15/00 14:10:33	20.509	0.422	12.6	16.07	-2.6
8/15/00 14:11:33	20.558	0.229	4.2	10.75	-2.6
8/15/00 14:12:33	20.654	0.144	1	15.57	-2.6
8/15/00 14:13:33	20.694	0.129	0.8	18.28	-2.6
8/15/00 14:14:33	20.678	0.146	7.5	15.81	-2.6
8/15/00 14:15:33	20.7	0.11	4.2	14.08	-2.6
8/15/00 14:16:33	20.729	0.086	2.4	13.61	-2.6
8/15/00 14:17:33	20.741	0.07	16.2	12.83	-2.6
8/15/00 14:18:34	20.764	0.056	8.1	11.72	-2.6
8/15/00 14:19:34	20.772	0.041	4	10.64	-2.6
8/15/00 14:20:34	20.755	0.014	3.6	3.39	-2.5
8/15/00 14:21:34	20.751	0.007	2.1	2.59	-2.5
8/15/00 14:22:34	20.752	0.004	1.8	2.52	-2.5
8/15/00 14:23:34	20.754	-0.001	1.2	2.61	-2.5
8/15/00 14:24:34	20.753	-0.002	1.2	2.67	-2.6
8/15/00 14:25:34	20.753	-0.002	1.4	2.54	-2.6
8/15/00 14:26:34	20.752	-0.002	1.4	2.73	-2.6
8/15/00 14:27:34	20.75	-0.002	1.4	3.26	-2.6
8/15/00 14:28:34	20.748	-0.003	2.3	3.26	-2.6
8/15/00 14:29:34	20.747	-0.003	2.6	2.92	-2.6
8/15/00 14:30:34	20.747	-0.003	2.5	2.81	-2.6
8/15/00 14:31:32	20.748	-0.003	2.3	2.88	-2.6
8/15/00 14:32:32	20.753	-0.009	2	2.76	-2.6
8/15/00 14:33:32	20.754	-0.01	2.4	2.71	-2.7
8/15/00 14:34:32	20.756	-0.011	3.2	2.65	-2.7
8/15/00 14:35:32	20.755	-0.012	3.4	2.64	-2.7
8/15/00 14:36:32	20.753	-0.011	3.9	2.69	-2.7
8/15/00 14:37:32	20.754	-0.011	3.8	2.83	-2.6
8/15/00 14:38:32	20.752	-0.011	3.1	2.98	-2.6
8/15/00 14:39:32	20.755	-0.011	2.8	2.9	-2.6
8/15/00 14:40:33	20.757	-0.011	3.5	2.79	-2.6
8/15/00 14:41:33	20.759	-0.011	2.7	2.79	-2.6
8/15/00 14:42:33	20.761	-0.011	3.3	2.67	-2.6

	02 8	C02 %	CO ppm	NOx ppm	SO2 ppm
Begin calculating run averages					
08-15-2000 13:55:32	20.484	0.401	7.8	13.59	-2.4
08-15-2000 13:56:33	20.493	0.412	4.2	16.63	-2.4
08-15-2000 13:57:33	20.442	0.563	63.0	8.05	-2.4
08-15-2000 13:58:34	20.532	0.313	14.1	14.79	-2.4
08-15-2000 13:59:33	22.057*	0.223"	1180.6*	20.39	-2.4
08-15-2000 14:00:34	23.347*	34.346"	1706.0"	44.26*	565.9*
08-15-2000 14:01:34	20.657	0.203	0.9	14.64	-2.5
08-15-2000 14:02:34	20.679	0.181	0.8	16.27	-2.5
08-15-2000 14:03:34	20.699	0.152	0.6	18.43	-2.5
08-15-2000 14:04:32	20.709	0.142	0.8	17.70	-2.5
08-15-2000 14:05:32	20.702	0.139	1.6	16.99	-2.5
08-15-2000 14:06:32	20.714	0.129	1.1	15.57	-2.5
08-15-2000 14:07:33	24.960"	59.026*	1768.8*	101.52*	1765.6*
08-15-2000 14:08:34	28.481*	35.464*	7072.4*	101.15*	4123.2*
08-15-2000 14:09:33	24.160*	12.020*	2357.9*	100.31*	2944.4*
08-15-2000 14:10:33	20.509	0.422	12.6	16.07	-2.6
08-15-2000 14:11:33	20.558	0.229	4.2	10.75	-2.6
08-15-2000 14:12:33	20.654	0.144	1.0	15.57	-2.6
08-15-2000 14:13:33	20.694	0.129	0.8	18.28	-2.6
08-15-2000 14:14:33	20.678	0.146	7.5	15.81	-2.6
08-15-2000 14:15:33	20.700	0.110	4.2	14.08	-2.6
08-15-2000 14:16:33	20.729	0.086	2.4	13.61	-2.6
08-15-2000 14:17:33	20.741	0.070	16.2	12.83	-2.6
08-15-2000 14:18:34	20.764	0.056	8.1	11.72	-2.6
08-15-2000 14:19:34	20.772	0.041	4.0	10.64	-2.6
08-15-2000 14:20:34	20.755	0.014	3.6	3.39	-2.5
08-15-2000 14:21:34	20.751	0.007	2.1	2.59	-2.5
08-15-2000 14:22:34	20.752	0.004	1.8	2.52	-2.5
08-15-2000 14:23:34	20.754	-0.001	1.2	2.61	-2.5
08-15-2000 14:24:34	20.753	-0.002	1.2	2.67	-2.6
08-15-2000 14:25:34	20.753	-0.002	1.4	2.54	-2.6
08-15-2000 14:26:34	20.752	-0.002	1.4	2.73	-2.6
08-15-2000 14:27:34	20.750	-0.002	1.4	3.26	-2.6
08-15-2000 14:28:34	20.748	-0.003	2.3	3.26	-2.6
08-15-2000 14:29:34	20.747	-0.003	2.6	2.92	-2.6
08-15-2000 14:30:34	20.747	-0.003	2.5	2.81	-2.6
08-15-2000 14:31:32	20.748	-0.003	2.3	2.88	-2.6
08-15-2000 14:32:32	20.753	-0.009	2.0	2.76	-2.6
08-15-2000 14:33:32	20.754	-0.010	2.4	2.71	-2.7
08-15-2000 14:34:32	20.756	-0.011	3.2	2.65	-2.7
08-15-2000 14:35:32	20.755	-0.012	3.4	2.64	-2.7
08-15-2000 14:36:32	20.753	-0.011	3.9	2.69	-2.7
08-15-2000 14:37:32	20.754	-0.011	3.8	2.83	-2.6
08-15-2000 14:38:32	20.752	-0.011	3.1	2.98	-2.6
08-15-2000 14:39:32	20.755	-0.011	2.8	2.90	-2.6
08-15-2000 14:40:33	20.757	-0.011	3.5	2.79	-2.6
08-15-2000 14:41:33	20.759	-0.011	2.7	2.79	-2.6
08-15-2000 14:42:33	20.761	-0.011	3.3	2.67	-2.6

Test Run 2 STRATA Version 1.2.1

		02 %	CO2 %	CO ppm	NOx ppm	SO2 ppm
08-15-2000 16:21:33	23.783*	12.823*	1269.5*	46.62*	1906.6*	
08-15-2000 16:22:33	20.708	0.164	-3.9	15.19	-3.1	
08-15-2000 16:23:33	20.679	0.176	-4.4	15.71	-3.1	
08-15-2000 16:24:33	20.708	0.151	-4.4	14.22	-3.1	
08-15-2000 16:25:33	20.707	0.143	-3.9	14.92	-3.1	
08-15-2000 16:26:33	20.648	0.138	-3.8	49.66	-3.0	
08-15-2000 16:27:33	20.692	0.125	-4.9	15.38	-3.0	
08-15-2000 16:28:33	20.753	0.080	-5.6	15.25	-2.9	
08-15-2000 16:29:34	20.761	0.077	-5.8	15.32	-2.9	
08-15-2000 16:30:34	20.757	0.089	-5.4	16.71	-2.9	
08-15-2000 16:31:34	20.674	0.190	-5.3	41.98	-2.9	
08-15-2000 16:32:34	20.682	0.164	-4.9	47.66	-2.9	
08-15-2000 16:33:34	20.763	0.083	-4.4	19.89	-2.8	
08-15-2000 16:34:32	20.776	0.076	-4.4	13.72	-2.8	
08-15-2000 16:35:32	20.771	0.071	-5.0	14.21	-2.8	
08-15-2000 16:36:32	20.716	0.094	2.3	23.88	-2.8	
08-15-2000 16:37:32	20.753	0.072	-3.0	13.05	-2.8	
08-15-2000 16:38:33	20.772	0.064	-3.9	12.43	-2.8	
08-15-2000 16:39:33	20.770	0.062	17.1	13.65	-2.8	
08-15-2000 16:40:33	20.795	0.054	2.2	12.29	-2.8	
08-15-2000 16:41:34	20.802	0.043	-2.8	12.01	-2.8	
08-15-2000 16:42:34	20.805	0.035	-3.7	11.58	-2.8	
08-15-2000 16:43:34	20.803	0.026	-4.6	11.02	-2.9	
08-15-2000 16:44:32	20.811	0.006	-4.1	8.78	-2.9	
08-15-2000 16:45:32	20.817	0.006	-3.9	9.81	-2.9	
08-15-2000 16:46:32	20.760	0.079	-4.1	25.64	-2.9	
08-15-2000 16:47:32	20.428	0.471	62.9	27.83	-2.9	
08-15-2000 16:48:32	20.536	0.263	147.9	8.78	-3.0	
08-15-2000 16:49:32	20.607	0.219	161.9	8.61	-3.0	
08-15-2000 16:50:33	20.576	0.263	127.6	10.81	-3.0	
08-15-2000 16:51:33	20.477	0.339	31.9	10.21	-3.0	
08-15-2000 16:52:33	20.504	0.340	25.7	7.72	-3.0	
08-15-2000 16:53:33	20.463	0.394	54.5	6.84	-3.0	
08-15-2000 16:54:33	20.479	0.373	104.7	6.09	-3.0	
08-15-2000 16:55:33	20.448	0.405	122.9	6.13	-3.0	
08-15-2000 16:56:33	20.407	0.449	212.6	5.74	-3.0	
08-15-2000 16:57:33	20.418	0.462	391.4	6.38	-3.0	
08-15-2000 16:58:33	20.374	0.498	513.7	5.80	-3.0	
08-15-2000 16:59:33	20.343	0.546	539.1	5.53	-3.1	
08-15-2000 17:00:33	20.371	0.581	413.9	5.76	-3.1	
08-15-2000 17:01:33	20.337	0.645	263.7	10.00	-3.1	
08-15-2000 17:02:33	20.375	0.562	148.0	15.06	-3.1	
08-15-2000 17:03:33	20.447	0.369	59.2	13.96	-3.1	
08-15-2000 17:04:34	20.609	0.208	7.2	13.23	-3.1	
08-15-2000 17:05:34	20.529	0.276	1.4	32.69	-3.1	
08-15-2000 17:06:34	20.523	0.289	1.3	34.40	-3.2	
08-15-2000 17:07:34	20.462	0.374	153.5	20.67	-3.2	
08-15-2000 17:08:34	20.509	0.303	191.5	8.21	-3.1	
08-15-2000 17:09:34	20.505	0.324	183.2	7.22	-3.1	

Test Run 2 STRATA Version 1.2.1

Run Averages

	O2 %	CO2 %	CO ppm	NOx ppm	SO2 ppm
38-15-2000 17:54:38	20.720*	1.003*	184.5*	11.66*	63.6*

Operator:

Peter Hilty

Plant Name:

Newport Steel

Location:

EAF Exhaust/Baghouse Inlet

Test Run 2 End

Final System Bias Check, Run 2 STRATA Version 1.2.1

Operator: Peter Hilty
 Plant Name: Newport Steel
 Location: EAF Exhaust/Baghouse Inlet

Reference Cylinder Numbers

	Zero	Span
O2	N2	Air
CO2	N2	CC84981
CO	N2	CC113985
NOx	N2	CC118512
SO2	N2	CC5784

Date/Time	08-15-2000		18:15:26	PASSED	
Analyte	O2	CO2	CO	NOx	SO2
Units	%	%	ppm	ppm	ppm
Zero Ref Cyl	0.000	0.000	0.0	0.00	0.0
Zero Cal	0.022	-0.267	-5.5	0.81	0.3
Zero Avg	-0.104	-0.101	-4.2	2.67	-3.3
Zero Bias%	0.5%	0.8%	0.1%	0.7%	0.4%
Zero Drift%	-0.1%	1.0%	0.6%	0.4%	-0.1%
Span Ref Cyl	20.900	8.000	50.0	50.50	400.0
Span Cal	20.896	8.016	46.1	50.15	393.3
Span Avg	20.769	7.918	46.2	50.22	390.3
Span Bias%	0.5%	0.5%	0.0%	0.0%	0.3%
Span Drift%	-0.2%	-0.4%	0.7%	-0.5%	-0.9%
Ini Zero Avg	-0.086	-0.301	-10.0	1.77	-1.9
Ini Span Avy	20.824	7.992	39.5	51.43	399.0
Run Avg	20.720	1.003	184.5	11.66	63.6
Co	-0.095	-0.201	-7.1	2.22	-2.6
Cm	20.796	7.955	42.8	50.83	394.7
Correct Avg	20.823	1.181	191.8	9.81	66.7

System Bias Check End

Final System Bias Check for Run 3
Operator: Peter Hilty
Plant Name: Newport Steel
Location: EAF Exhaust/Baghouse Inlet

Date/Time	8/16/00	12:07:23	PASSED		
Analyte	O2	CO2	CO	NOx	
Units	%	%	ppm	ppm	
Zero Ref Cyl	0	0	0	0	0
Zero Cal	-0.037	0.005	0.1	-1.24	
Zero Avg	-0.254	0.016	2.2	-0.79	
Zero Bids%	0.9	0.1	0.2	0.2	
Zero Drift%					
Span! Ref Cyl	20.9	8	50	50.5	
Span Cal	20.893	8	50.1	48.88	
Span Avg	20.864	7.971	52.8	49.85	
Span Bias%	0.1	0.1	0.3	0.4	
Span Drift%					

8/15/00 15:34:33	20.518	0.255	235.9	5.78	-3
8/15/00 15:35:33	20.537	0.222	200	5.69	-3
8/15/00 15:36:33	20.518	0.251	225.4	5.83	-3
8/15/00 15:37:33	20.524	0.243	197.5	5.81	-3
8/15/00 15:38:33	20.547	0.205	159.1	5.33	-3
8/15/00 15:40:32	20.479	0.286	239.6	5.72	-3.3
8/15/00 15:41:32	20.404	0.372	174.5	6.27	-3
8/15/00 15:42:32	20.293	0.465	48.8	7.24	-3
8/15/00 15:43:33	20.349	0.407	56.6	6.29	-3
8/15/00 15:44:33	20.431	0.361	190.9	5.34	-3
8/15/00 15:45:33	20.447	0.344	775	4.9	-3.1
8/15/00 15:46:33	20.381	0.419	1148.7	4.74	-3.1
8/15/00 15:47:33	20.346	0.483	1195.7	4.93	-3.1
8/15/00 15:48:33	20.26	0.586	841.3	4.89	-3.1
8/15/00 15:49:33	20.239	0.55	729	5.75	-3.1
8/15/00 15:50:33	20.328	0.506	588.9	4.65	-3.1
8/15/00 15:51:33	20.309	0.58	799.8	4.03	-3.1
8/15/00 15:52:34	20.316	0.554	811.7	4.44	-3.1
8/15/00 15:53:34	20.307	0.64	388.7	3.94	-3.1
8/15/00 15:54:34	20.224	0.67	341.1	3	-3.1
8/15/00 15:55:34	20.243	0.669	260.4	3.06	-3.1
8/15/00 15:56:34	20.26	0.622	232.8	3.33	-3.1
8/15/00 15:57:34	20.281	0.616	196.1	3.44	-3.1
8/15/00 15:58:34	20.284	0.615	212.2	3.39	-3.2
8/15/00 15:59:34	20.539	0.241	54.8	15.1	-3.1
8/15/00 16:00:32	20.639	0.165	21.1	15.72	-3.1
8/15/00 16:01:32	20.669	0.139	14.1	15.36	-3.1
8/15/00 16:02:32	20.645	0.203	11.3	20.75	-3.1
8/15/00 16:03:32	20.509	0.334	10.4	32.89	-3.1
8/15/00 16:04:32	20.461	0.454	20	14.04	-3.1
8/15/00 16:05:33	20.313	0.74	138.8	6.35	-3.1
8/15/00 16:06:33	20.25	0.746	156.1	4.7	-3.1
8/15/00 16:07:33	20.357	0.592	57.5	10.09	-3.1
8/15/00 16:08:33	20.394	0.553	32.4	13.15	-3.1
8/15/00 16:09:33	20.448	0.44	19.8	16.82	-3.2
8/15/00 16:10:33	20.573	0.269	15.7	24.45	-3.2
8/15/00 16:11:33	20.564	0.276	11.2	22.45	-3.2
8/15/00 16:12:33	20.534	0.313	8.8	19.22	-3.2
8/15/00 16:13:33	20.5	0.37	14.6	14.43	-3.2
8/15/00 16:14:33	20.502	0.37	10.7	16.24	-3.2
8/15/00 16:15:34	20.523	0.329	6	17.74	-3.2
8/15/00 16:16:34	20.591	0.24	2.3	39.01	-3.2
8/15/00 16:17:34	20.587	0.213	-1.3	30.47	-3.2
8/15/00 16:18:34	20.678	0.154	-1.7	22.09	-3.2
8/15/00 16:19:34	20.71	0.122	-2.9	18.33	-3.2
8/15/00 16:20:34	20.716	0.11	-3.5	16.73	-3.2
8/15/00 16:22:33	20.708	0.164	-3.9	15.19	-3.1
8/15/00 16:23:33	20.679	0.176	-4.4	15.71	-3.1
8/15/00 16:24:33	20.708	0.151	-4.4	14.22	-3.1
8/15/00 16:25:33	20.707	0.143	-3.9	14.92	-3.1

8/15/00 16:26:33	20.648	0.138	-3.8	49.66	-3
8/15/00 16:27:33	20.692	0.125	-4.9	15.38	-3
8/15/00 16:28:33	20.753	0.08	-5.6	15.25	-2.9
8/15/00 16:29:34	20.761	0.077	-5.8	15.32	-2.9
8/15/00 16:30:34	20.757	0.089	-5.4	16.71	-2.9
8/15/00 16:31:34	20.674	0.19	-5.3	41.98	-2.9
8/15/00 16:32:34	20.682	0.164	-4.9	47.66	-2.9
8/15/00 16:33:34	20.763	0.083	-4.4	19.89	-2.8
8/15/00 16:34:32	20.776	0.076	-4.4	13.72	-2.8
8/15/00 16:35:32	20.771	0.071	-5	14.21	-2.8
8/15/00 16:36:32	20.716	0.094	2.3	23.88	-2.8
8/15/00 16:37:32	20.753	0.072	-3	13.05	-2.8
8/15/00 16:38:33	20.772	0.064	-3.9	12.43	-2.8
8/15/00 16:39:33	20.77	0.062	17.1	13.65	-2.8
8/15/00 16:40:33	20.795	0.054	2.2	12.29	-2.8
8/15/00 16:41:34	20.802	0.043	-2.8	12.01	-2.8
8/15/00 16:42:34	20.805	0.035	-3.7	11.58	-2.8
8/15/00 16:43:34	20.803	0.026	-4.6	11.02	-2.9
8/15/00 16:44:32	20.811	0.006	-4.1	8.78	-2.9
8/15/00 16:45:32	20.817	0.006	-3.9	9.81	-2.9
8/15/00 16:46:32	20.76	0.079	-4.1	25.64	-2.9
8/15/00 16:47:32	20.428	0.471	62.9	27.83	-2.9
8/15/00 16:48:32	20.536	0.263	147.9	8.78	-3
8/15/00 16:49:32	20.607	0.219	161.9	8.61	-3
8/15/00 16:50:33	20.576	0.263	127.6	10.81	-3
8/15/00 16:51:33	20.477	0.339	31.9	10.21	-3
8/15/00 16:52:33	20.504	0.34	25.7	7.72	-3
8/15/00 16:53:33	20.463	0.394	54.5	6.84	-3
8/15/00 16:54:33	20.479	0.373	104.7	6.09	-3
8/15/00 16:55:33	20.448	0.405	122.9	6.13	-3
8/15/00 16:56:33	20.407	0.449	212.6	5.74	-3
8/15/00 16:57:33	20.418	0.462	391.4	6.38	-3
8/15/00 16:58:33	20.374	0.498	513.7	5.8	-3
8/15/00 16:59:33	20.343	0.546	539.1	5.53	-3.1
8/15/00 17:00:33	20.371	0.581	413.9	5.76	-3.1
8/15/00 17:01:33	20.337	0.645	263.7	10	-3.1
8/15/00 17:02:33	20.375	0.562	148	15.06	-3.1
8/15/00 17:03:33	20.447	0.369	59.2	13.96	-3.1
8/15/00 17:04:34	20.609	0.208	7.2	13.23	-3.1
8/15/00 17:05:34	20.529	0.276	1.4	32.69	-3.1
8/15/00 17:06:34	20.523	0.289	1.3	34.4	-3.2
8/15/00 17:07:34	20.462	0.374	153.5	20.67	-3.2
8/15/00 17:08:34	20.509	0.303	191.5	8.21	-3.1
8/15/00 17:09:34	20.505	0.324	183.2	7.22	-3.1
8/15/00 17:11:33	20.384	0.43	21.2	7.86	-3.1
8/15/00 17:12:33	20.418	0.402	22.9	7.46	-3.1
8/15/00 17:13:33	20.454	0.405	98.4	7.37	-3.1
8/15/00 17:14:34	20.441	0.429	198	7.36	-3.2
8/15/00 17:15:34	20.392	0.474	290.4	6.38	-3.2
8/15/00 17:16:34	20.378	0.484	337.7	5.57	-3.3

8/15/00 17:17:34	20.348	0.51	239.3	5.58	-3.3
8/15/00 17:18:34	20.355	0.507	255.3	5.73	-3.3
8/15/00 17:19:34	20.333	0.527	241	6.11	-3.3
8/15/00 17:20:34	20.37	0.481	393.5	5.4	-3.3
8/15/00 17:21:34	20.414	0.43	291.8	4.32	-3.3
8/15/00 17:22:32	20.476	0.37	155.1	4.33	-3.3
8/15/00 17:23:32	20.484	0.344	108.1	4.02	-3.3
8/15/00 17:24:32	20.532	0.335	36.2	4.5	-3.3
8/15/00 17:25:32	20.501	0.406	26	4.58	-3.2
8/15/00 17:26:32	20.475	0.461	36.1	4.26	-3.2
8/15/00 17:27:32	20.499	0.368	9.5	5.33	-3.2
8/15/00 17:28:32	20.582	0.241	-2.1	8.22	-3.2
8/15/00 17:29:33	20.662	0.156	-6.8	10.98	-3.2
8/15/00 17:30:33	20.687	0.138	-6.8	10.41	-3.2
8/15/00 17:31:33	20.7	0.119	-10.6	9.75	-3.2
8/15/00 17:32:33	20.716	0.106	-7.1	9.56	-3.2
8/15/00 17:33:33	20.721	0.102	-6.9	9.45	-3.2
8/15/00 17:34:33	20.721	0.099	-6.5	9.25	-3.2
8/15/00 17:35:33	20.724	0.093	-6.4	9.06	-3.2
8/15/00 17:36:33	20.726	0.089	-5.9	9.13	-3.2
8/15/00 17:37:33	20.726	0.087	-6.2	9.28	-3.2
8/15/00 17:38:33	20.702	0.124	-6.7	14.05	-3.2
8/15/00 17:39:33	20.58	0.281	-4.2	19.04	-3.2
8/15/00 17:40:33	20.5	0.474	8.6	7.37	-3.2
8/15/00 17:41:33	20.429	0.548	23.3	6.89	-3.2
8/15/00 17:42:33	20.518	0.393	0.2	9.77	-3.2
8/15/00 17:43:33	20.536	0.367	-2.7	11.42	-3.2
8/15/00 17:44:33	20.517	0.415	-4	12.25	-3.2
8/15/00 17:45:33	20.551	0.357	-5.1	13.58	-3.1
8/15/00 17:46:33	20.554	0.357	-3.6	17.04	-3.1
8/15/00 17:47:33	20.537	0.355	-2.6	15.46	-3.1
8/15/00 17:48:33	20.593	0.293	-7.1	17.57	-3.1
8/15/00 17:49:34	20.631	0.229	-7.1	16.94	-3.1
8/15/00 17:50:34	20.64	0.202	-6.1	16.31	-3.1
8/15/00 17:51:34	20.64	0.225	-5.6	16.46	-3.1
8/15/00 17:52:34	20.62	0.255	-4.7	15.76	-3.2
8/15/00 17:53:34	20.556	0.315	1.5	16.78	-3.2
8/15/00 17:54:34	20.518	0.357	-0.3	25.06	-3.2

Average of Test Run	O2 %	CO2 %	CO ppm	NOx ppm	SO2 ppm
8/15/00 17:54:34	20.58	0.24	89.10	10.05	-2.93

Test Run 2 End

Final System Bias Check for Run 2

Operator: Peter Hilty

Plant Name: Newport Steel

Location: EAF Exhaust/Baghouse Inlet

Date/Time 8/15/00 18:15:26 PASSED

Analyte	O2	CO2	CO	NOx	S02
Units	%	%	ppm	ppm	ppm
Zero Ref Cyl.	0	0	0	0	0
Zero Cal	0.022	-0.267	-5.5	0.81	0.3
Zero Avg	-0.104	-0.101	-4.2	2.67	-3.3
Zero Bias%	0.5	0.8	0.1	0.7	0.4
Zero Drift%	-0.1	1	0.6	0.4	-0.1
Span Ref Cyl	20.9	8	50	50.5	400
Span Cal.	20.896	8.016	46.1	50.15	393.3
Span Avg	20.769	7.918	46.2	50.22	390.3
Span Bias%	0.5	0.5	0	0	0.3
Span Drift%	-0.2	-0.4	0.7	-0.5	-0.9
Ini Zero Avg	-0.086	-0.301	-10	1.77	-1.9
Ini Span Avg	20.824	7.992	39.5	51.43	399
Run Avg	20.72	1.003	184.5	11.66	63.6
CO	-0.095	-0.201	-7.1	2.22	-2.6
Cm	20.796	7.955	42.8	50.83	394.7
Correct Avg	20.823	1.181	191.8	9.81	66.7

8/15/00 14:44:34	20.761	-0.012	2.9	2.9	-2.7
8/15/00 14:45:34	20.76	-0.012	3	2.65	-2.7
8/15/00 14:46:34	20.759	-0.013	3.3	2.66	-2.7
8/15/00 14:47:32	20.76	-0.013	2.8	3.01	-2.7
8/15/00 14:48:32	20.755	-0.002	5.1	3.17	-2.8
8/15/00 14:49:32	20.619	0.155	75.4	3.72	-2.8
8/15/00 14:50:32	20.697	0.036	71.7	3.33	-2.8
8/15/00 14:51:32	20.734	0.013	36.7	3.11	-2.8
8/15/00 14:52:32	20.743	0.005	24.3	2.73	-2.8
8/15/00 14:53:32	20.746	0.009	21.1	2.66	-2.8
8/15/00 14:54:32	20.592	0.141	49.4	12.48	-2.8
8/15/00 14:55:33	20.539	0.163	134.2	4.66	-2.8
8/15/00 14:56:33	20.499	0.211	123.2	3.91	-2.8
8/15/00 14:57:33	20.472	0.233	101.8	4.05	-2.8
8/15/00 14:58:33	20.478	0.233	86.3	4.31	-2.8
8/15/00 14:59:33	20.436	0.277	109.9	3.6	-2.8
8/15/00 15:00:33	20.43	0.285	105.7	3.41	-2.8
8/15/00 15:01:33	20.435	0.274	88.2	3.52	-2.8
8/15/00 15:02:33	20.401	0.338	92.6	3.89	-2.9
8/15/00 15:03:33	20.426	0.311	103.3	4.24	-2.8
8/15/00 15:04:33	20.431	0.317	102.8	5.31	-2.8
8/15/00 15:05:33	20.439	0.32	138.9	4.29	-2.7
8/15/00 15:06:33	20.438	0.311	150.8	3.5	-2.7
8/15/00 15:07:33	20.433	0.355	174.3	3.71	-2.7
8/15/00 15:08:34	20.436	0.316	105.3	3.92	-2.9
8/15/00 15:09:34	20.522	0.251	59.6	3.95	-2.7
8/15/00 15:10:34	20.593	0.228	47.1	6.43	-2.7
8/15/00 15:11:34	20.49	0.323	87.6	5.06	-2.8
8/15/00 15:12:34	20.37	0.448	123	3.38	-2.8
8/15/00 15:13:34	20.506	0.255	29.8	3.83	-2.8
8/15/00 15:14:34	20.644	0.163	0.4	4.88	-2.8
8/15/00 15:15:34	20.664	0.142	1.3	5.29	-2.8
8/15/00 15:16:34	20.654	0.126	1.1	5.35	-2.9
8/15/00 15:17:34	20.689	0.123	0.3	5.48	-2.8
8/15/00 15:18:32	20.689	0.121	3.3	5.63	-2.8
8/15/00 15:19:32	20.698	0.099	10.8	5.7	-2.8
8/15/00 15:20:32	20.629	0.176	17	8.76	-2.8
8/15/00 15:21:32	20.657	0.143	18.9	8.14	-2.8
8/15/00 15:22:32	20.662	0.127	16.9	7.32	-2.8
8/15/00 15:23:33	20.667	0.12	17.4	7.42	-2.8
8/15/00 15:24:33	20.662	0.137	18.9	7.8	-2.8
8/15/00 15:25:33	20.661	0.129	10.7	7.29	-2.8
8/15/00 15:26:33	20.686	0.101	6.2	6.17	-2.8
8/15/00 15:27:33	20.689	0.095	5.9	5.87	-2.8
8/15/00 15:28:33	20.644	0.147	6.7	6.81	-2.9
8/15/00 15:29:33	20.598	0.164	3.5	7	-2.9
8/15/00 15:30:33	20.584	0.199	4.2	10.55	-2.9
8/15/00 15:31:33	20.531	0.263	156.4	8.68	-2.9
8/15/00 15:32:32	20.512	0.279	-	4.97	-2.9
8/15/00 15:33:32	20.519	0.269	-	4.92	-2.9

Test Run 2 STRATA Version 1.2.1

		O2 %	CO2 %	CO ppm	NOx ppm	SO2 ppm
08-15-2000 15:32:32		20.512	0.279	220.6	4.97	-2.9
08-15-2000 15:33:32		20.519	0.269	228.5	4.92	-2.9
08-15-2000 15:34:33		20.518	0.255	235.9	5.78*	-3.0
08-15-2000 15:35:33		20.537	0.222	200.0	5.69	-3.0
08-15-2000 15:36:33		20.518	0.251	225.4	5.83	-3.0
08-15-2000 15:37:33		20.524	0.243	197.5	5.81	-3.0
08-15-2000 15:38:33		20.547	0.205	159.1	5.33	-3.0
08-15-2000 15:39:32		24.080*	0.251*	2511.1*	5.68*	1765.2*
08-15-2000 15:40:32		20.479	0.286	239.6	5.72	-3.3
08-15-2000 15:41:32		20.404	0.372	174.5	6.27	-3.0
08-15-2000 15:42:32		20.293	0.465	48.8	7.24	-3.0
08-15-2000 15:43:33		20.349	0.407	56.6	6.29	-3.0
08-15-2000 15:44:33		20.431	0.361	190.9	5.34	-3.0
08-15-2000 15:45:33		20.447	0.344	775.0*	4.90	-3.1
08-15-2000 15:46:33		20.381	0.419	1148.7*	4.74	-3.1
08-15-2000 15:47:33		20.346	0.483	1195.7*	4.93	-3.1
08-15-2000 15:48:33		20.260	0.586	841.3*	4.89	-3.1
08-15-2000 15:49:33		20.239	0.550	729.0*	5.75	-3.1
08-15-2000 15:50:33		20.328	0.506	588.9	4.65	-3.1
08-15-2000 15:51:33		20.309	0.580	799.8*	4.03	-3.1
08-15-2000 15:52:34		20.316	0.554	811.7*	4.44	-3.1
08-15-2000 15:53:34		20.307	0.640	388.7	3.94	-3.1
08-15-2000 15:54:34		20.224	0.670	341.1	3.00	-3.1
08-15-2000 15:55:34		20.243	0.669	260.4	3.06	-3.1
08-15-2000 15:56:34		20.260	0.622	232.8	3.33	-3.1
08-15-2000 15:57:34		20.281	0.616	196.1	3.44	-3.1
08-15-2000 15:58:34		20.284	0.615	212.2	3.39	-3.2
08-15-2000 15:59:34		20.539	0.241	54.8	15.10	-3.1
08-15-2000 16:00:32		20.639	0.165	21.1	15.72	-3.1
08-15-2000 16:01:32		20.669	0.139	14.1	15.36	-3.1
08-15-2000 16:02:32		20.645	0.203	11.3	20.75	-3.1
08-15-2000 16:03:32		20.509	0.334	10.4	32.89	-3.1
08-15-2000 16:04:32		20.461	0.454	20.0	14.04	-3.1
08-15-2000 16:05:33		20.313	0.740	138.8	6.35	-3.1
08-15-2000 16:06:33		20.250	0.746	156.1	4.70	-3.1
08-15-2000 16:07:33		20.357	0.592	57.5	10.09	-3.1
08-15-2000 16:08:33		20.394	0.553	32.4	13.15	-3.1
08-15-2000 16:09:33		20.448	0.440	19.8	16.82	-3.2
08-15-2000 16:10:33		20.573	0.269	15.7	24.45	-3.2
08-15-2000 16:11:33		20.564	0.276	11.2	22.45	-3.2
08-15-2000 16:12:33		20.534	0.313	8.8	19.22	-3.2
08-15-2000 16:13:33		20.500	0.370	14.6	14.43	-3.2
08-15-2000 16:14:33		20.502	0.370	10.7	16.24	-3.2
08-15-2000 16:15:34		20.523	0.329	6.0	17.74	-3.2
08-15-2000 16:16:34		20.591	0.240	2.3	39.01	-3.2
08-15-2000 16:17:34		20.587	0.213	-1.3	30.47	-3.2
08-15-2000 16:18:34		20.678	0.154	-1.7	22.09	-3.2
08-15-2000 16:19:34		20.710	0.122	-2.9	18.33	-3.2
08-15-2000 16:20:34		20.716		-3.5	16.73	-3.2

Test Run 4 Begin. STRATA Version 1.2.1

Operator: Peter Hilty

Plant Name: Newport Steel

Location: EAF Exhaust/Baghouse Inlet

	CO2 %	CO2 %	CO ppm	NOx ppm
Begin calculating run averages				
8/16/00 13:09:43	20.451	0.51	411.5	3.68
8/16/00 13:10:43	20.445	0.503	304.4	2.64
8/16/00 13:11:42	20.476	0.558	332.2	4
8/16/00 13:12:43	20.521	0.595	348.8	4.18
8/16/00 13:13:43	20.514	0.621	484.2	3.9
8/16/00 13:14:42	20.513	0.56	338.9	3.66
8/16/00 13:15:43	20.45	0.694	241.5	1.88
8/16/00 13:16:44	20.248	0.906	217.8	1.96
8/16/00 13:17:43	20.222	0.916	234.5	2.46
8/16/00 13:18:42	20.288	0.784	237.3	4.7
8/16/00 13:19:43	20.181	0.865	262.8	6.36
8/16/00 13:20:43	20.168	0.784	237.6	6.34
8/16/00 13:21:42	20.424	0.498	182	12.9
8/16/00 13:22:43	20.418	0.609	129.1	9.94
8/16/00 13:23:43	20.122	0.978	196.3	3.34
8/16/00 13:24:42	20.167	0.892	261	4.18
8/16/00 13:25:43	20.22	0.831	300.2	3.94
8/16/00 13:26:43	20.145	0.95	257.9	4.22
8/16/00 13:27:42	20.24	0.805	245.8	4.5
8/16/00 13:28:43	20.336	0.769	208.1	4.72
8/16/00 13:29:44	20.332	0.765	175.2	4.68
8/16/00 13:30:42	20.39	0.685	173.8	4.38
8/16/00 13:31:43	20.331	0.788	146.2	7.32
8/16/00 13:32:44	20.573	0.58	106.4	11.48
8/16/00 13:33:42	20.669	0.4	57.6	17.1
8/16/00 13:34:43	20.746	0.283	34.3	34.18
8/16/00 13:35:43	20.798	0.221	21.2	28.04
8/16/00 13:36:42	20.788	0.228	21.6	23.7
8/16/00 13:37:43	20.771	0.206	20.1	23.64
8/16/00 13:38:44	20.802	0.188	31.3	23.78
8/16/00 13:39:42	20.825	0.171	22.9	22.04
8/16/00 13:40:43	20.86	0.143	14.3	19.72
8/16/00 13:41:43	20.883	0.129	10.6	18.9
8/16/00 13:42:44	20.871	0.12	8.9	20.84
8/16/00 13:43:42	20.89	0.098	9.1	18.9
8/16/00 13:44:43	20.904	0.084	10	16.56
8/16/00 13:45:44	20.91	0.087	11.3	18.92
8/16/00 13:46:42	20.91	0.089	13.7	19.68
8/16/00 13:47:43	20.913	0.089	15.1	19.66

8/16/00 13:48:44	20.91	0.089	14.2	19.26
8/16/00 13:49:42	20.906	0.088	14.1	18.9
8/16/00 13:50:43	20.861	0.167	33.1	18.84
8/16/00 13:51:44	20.396	0.614	108.7	23.64
8/16/00 13:52:42	20.505	0.47	91.2	13.02
8/16/00 13:53:43	20.646	0.324	64.9	8.5
8/16/00 13:54:43	20.527	0.415	95.9	7.84
8/16/00 13:55:42	20.491	0.453	50.1	6.74
8/16/00 13:56:43	20.513	0.429	72.6	6.24
8/16/00 13:57:43	20.501	0.436	141.5	5.74
8/16/00 13:58:42	20.474	0.466	170.7	5.42
8/16/00 13:59:43	20.467	0.477	155.4	5.3
8/16/00 14:00:43	20.428	0.518	137.6	3.66
8/16/00 14:01:42	20.387	0.538	108.9	4.38
8/16/00 14:02:43	20.399	0.534	145.7	4.82
8/16/00 14:03:43	20.414	0.586	168.6	4.16
8/16/00 14:04:42	20.385	0.61	150.3	3.3
8/16/00 14:05:43	20.397	0.585	143.6	3.38
8/16/00 14:06:43	20.412	0.535	124.3	3.16
8/16/00 14:07:42	20.444	0.489	105.2	3.14
8/16/00 14:08:43	20.465	0.464	107.4	2.48
8/16/00 14:09:43	20.468	0.466	116.4	2.02
8/16/00 14:10:42	20.572	0.34	43.3	14.32
8/16/00 14:11:43	20.714	0.218	9.9	15
8/16/00 14:12:43	20.762	0.162	7.3	13.58
8/16/00 14:13:42	20.754	0.228	27.5	13.82
8/16/00 14:14:43	20.536	0.449	73.5	9.48
8/16/00 14:15:44	20.522	0.475	59.3	8.48
8/16/00 14:16:43	20.423	0.525	22.1	8.72
8/16/00 14:17:43	20.482	0.465	16.1	9.52
8/16/00 14:18:42	20.491	0.473	45.1	9.2
8/16/00 14:19:43	20.531	0.477	148.4	7.96
8/16/00 14:20:42	20.536	0.478	222.6	6.64
8/16/00 14:21:42	20.483	0.517	281.9	6.52
8/16/00 14:22:44	20.386	0.588	182.7	5.98
8/16/00 14:23:43	20.407	0.523	234.1	5.62
8/16/00 14:24:43	20.448	0.51	299.8	4.84
8/16/00 14:25:43	20.471	0.533	268.3	4.6
8/16/00 14:26:43	20.502	0.469	167.7	6.32
8/16/00 14:27:43	20.535	0.467	158.2	13.52
8/16/00 14:28:43	20.553	0.472	101.7	11.3
8/16/00 14:29:43	20.601	0.409	22.5	19.64
8/16/00 14:30:42	20.612	0.413	15.7	14.52
8/16/00 14:31:42	20.548	0.523	51.2	7
8/16/00 14:32:42	20.488	0.546	74.1	4.52
8/16/00 14:33:44	20.569	0.45	24	6.5

8/16/00 14:34:44	20.656	0.314	5.5	13.76
8/16/00 14:35:43	20.64	0.335	8.8	16.14
8/16/00 14:36:43	20.703	0.269	4.3	14.4
8/16/00 14:37:43	20.655	0.319	16.2	12.24
8/16/00 14:38:43	20.574	0.489	42.7	7.06
8/16/00 14:39:43	20.384	0.764	109.3	2.16
8/16/00 14:40:42	20.446	0.603	70.2	5.62
8/16/00 14:41:42	20.463	0.581	46.9	8.62
8/16/00 14:42:42	20.462	0.633	50.4	6.88
8/16/00 14:43:44	20.328	0.808	98.3	4.38
8/16/00 14:44:44	20.532	0.472	42.7	12
8/16/00 14:45:43	20.655	0.365	19	20.44
8/16/00 14:46:43	20.687	0.343	12.5	38.26
8/16/00 14:47:43	20.616	0.426	14	12.06
8/16/00 14:48:43	20.635	0.363	10.3	10.82
8/16/00 14:49:43	20.655	0.39	9.5	10.18
8/16/00 14:50:42	20.52	0.655	62.6	4.04
8/16/00 14:51:42	20.607	0.323	46.7	8.44
8/16/00 14:52:44	20.799	0.169	8	10.82
8/16/00 14:53:44	20.823	0.151	6.9	10.86
8/16/00 14:54:44	20.803	0.175	8.9	11.4
8/16/00 14:55:44	20.788	0.176	10.7	11.94
8/16/00 14:56:43	20.813	0.172	26.3	12.16
8/16/00 14:57:43	20.814	0.157	25.8	12.2
8/16/00 14:58:43	20.851	0.13	9.1	10.44
8/16/00 14:59:43	20.856	0.122	6.9	10.38
8/16/00 15:00:44	20.854	0.105	6.9	9.36
8/16/00 15:01:42	20.86	0.092	7.3	9.12
8/16/00 15:02:43	20.863	0.092	9.5	9.64
8/16/00 15:03:44	20.866	0.092	9.8	9.38
8/16/00 15:04:42	20.869	0.091	10.4	8.72
8/16/00 15:05:43	20.845	0.081	9.8	2.06
8/16/00 15:06:44	20.845	0.077	9.1	1.22
8/16/00 15:07:42	20.847	0.076	8.8	1.3
8/16/00 15:08:43	20.851	0.073	8.7	1.3
8/16/00 15:09:44	20.855	0.072	8.7	1.2
Average of Test Run	O2	CO2	CO	NOx
	%	%	ppm	ppm
8/16/00 15:10:36	20.58	0.42	99.79	9.91
Test Run 4 End				

Operator: Peter Hilty
 Plant Name: Newport Steel
 Location: EAF Exhaust/Baghouse Inlet

	Reference	Cylinder Numbers	Low-range	Mid-range	High-range
O2	N2			CC84981	Air
CO2	N2			CC84981	CC113935
CO	N2	CC113985		CC113935	CC94790
NOx	N2	CC118512		CC106973	CC79974

Date/Time 08-16-2000 15:35:41 PASSED

Analyte	O2	CO2	CO	NOx
Units	%	%	ppm	ppm
Zero Ref Cyl	0.000	0.000	0.0	0.00
Zero Avg	-0.256	0.077	0.0	-0.16
Zero Error%	1.0%	0.4%	0.0%	0.1%
Low Ref Cyl			50.0	50.50
Low Avg			52.2	51.04
Low Error%			0.2%	0.2%
Mid Ref Cyl			100.0	89.30
Mid Avg			101.7	91.59
Mid Error%			0.2%	0.9%
High Ref Cyl	20.900	15.000	152.0	197.40
High Avg	20.790	14.983	153.0	201.88
High Error&	0.4%	0.1%	0.1%	1.8%

Calibration Error Test End

Initial System Bias Check, Run 5 STRATA Version 1.2.1

Operator: Peter Hilty
 Plant Name: Newport Steel
 Location: EAF Exhaust/Baghouse Inlet

Reference Cylinder Numbers

	Zero	Span
O2	N2	Air
CO2	N2	CC113935
CO	N2	CC113985
NOx	N2	CC106973

Date/Time	08-17-2000	07:30:14	PASSED
Analyte	O2	CO2	CO NOx
Units	%	%	ppm ppm
Zero Ref Cyl	0.000	0.000	0.0 0.00
Zero Cal	-0.256	0.077	0.0 -0.16
Zero Avg	-0.163	0.104	1.3 0.21
Zero Bias%	0.4%	0.1%	0.1% 0.2%
Zero Drift%			
Span Ref Cyl	20.900	15.000	50.0 89.30
Span Cal	20.790	14.983	52.2 91.59
Span Avg	20.861	15.084	50.9 90.48
Span Bias%	0.3%	0.5%	0.1% 0.4%
Span Drift%			
System Bias Check End			

8/15/00	11:33:43	20.493	0.103	49.5	13.32	-2.3
8/15/00	11:34:43	20.639	-0.121	11.7	7.99	-2.2
8/15/00	11:35:43	20.707	-0.161	19.7	3.39	-2.2
8/15/00	11:36:43	20.708	-0.138	109.2	2.99	-2.1
8/15/00	11:37:41	20.686	-0.075	69.3	5.18	-2.1
8/15/00	11:38:41	20.506	0.11	11.7	5.36	-2.1
8/15/00	11:39:41	20.484	0.116	2.1	5.76	-2.1
8/15/00	11:40:41	20.505	0.08	9	5.76	-2
8/15/00	11:41:41	20.568	0.036	25.4	4.85	-2
8/15/00	11:42:42	20.588	0.008	31.7	4.69	-2
8/15/00	11:43:42	20.567	0.031	70.7	4.56	-1.9
8/15/00	11:44:42	20.567	0.016	101.3	4.4	-1.9
8/15/00	11:45:42	20.541	0.038	113.5	4.31	-1.9
8/15/00	11:46:42	20.517	0.062	166.9	4.44	-1.8
8/15/00	11:47:42	20.522	0.044	219.6	3.9	-1.8
8/15/00	11:48:42	20.56	0.017	228.2	3.52	-1.8
8/15/00	11:49:42	20.55	0.016	259.4	3.23	-1.8
8/15/00	11:50:42	20.541	0.017	193.2	3.22	-1.8
8/15/00	11:51:42	20.518	0.02	141.9	4.44	-1.8
8/15/00	11:52:42	20.488	0.066	108.2	3.84	-1.8
8/15/00	11:53:42	20.491	0.105	47.5	2.99	-1.8
8/15/00	11:54:42	20.514	0.13	34.1	2.89	-1.8
8/15/00	11:55:42	20.613	-0.049	0	8.32	-1.8
8/15/00	11:56:42	20.691	-0.114	-6.6	10.37	-1.8
8/15/00	11:57:42	20.672	-0.095	-6.7	20.81	-1.8
8/15/00	11:58:42	20.572	0.038	-4.2	41.27	-1.8
8/15/00	11:59:42	20.529	0.1	-3.2	33.25	-1.8
8/15/00	12:00:43	20.572	0.044	-3.1	25.42	-1.8
8/15/00	12:01:43	20.577	0.131	-2.1	23.3	-1.9
8/15/00	12:02:43	20.464	0.241	13.2	14.85	-1.9
8/15/00	12:04:43	19.956	0.65	191.6	4.43	-1.9
8/15/00	12:05:43	20.228	0.554	152.8	5.25	-1.9
8/15/00	12:06:43	20.27	0.437	138.9	7.41	-1.9
8/15/00	12:07:43	20.457	0.246	59.4	23.92	-1.9
8/15/00	12:08:43	20.424	0.285	54.5	9.26	-1.9
8/15/00	12:09:43	20.549	0.081	11.8	16.18	-1.9
8/15/00	12:10:42	20.626	-0.026	1.1	20.1	-1.9
8/15/00	12:11:42	20.649	-0.036	-1.3	18.59	-1.9
8/15/00	12:12:42	20.617	0.011	-0.3	20.7	-1.9
8/15/00	12:13:42	20.559	0.07	5	23.79	-1.9
8/15/00	12:14:42	20.535	0.139	3.9	23.45	-1.9
Average of Test Run		O2	CO2	CO	NOx	SO2
		%	%	ppm	ppm	ppm
8/15/00	12:14:42	20.54	0.07	48.51	9.90	-1.43

Test Run 1 End

8/15/00	10:40:42	20.584	-0.056	3	32.04	-1.9
8/15/00	10:42:42	20.594	-0.07	-0.5	12.48	-1.9
8/15/00	10:43:42	20.672	-0.114	-3.2	17.36	-1.9
8/15/00	10:44:42	20.488	-0.007	7.2	32.31	-2
8/15/00	10:45:42	20.531	0.008	2.4	9.18	-1.9
8/15/00	10:46:42	20.651	-0.091	-2.6	20.18	-1.9
8/15/00	10:47:42	20.551	0.001	-0.6	17.02	-1.9
8/15/00	10:48:42	20.507	0.126	5.7	12.08	-1.9
8/15/00	10:49:42	20.526	0.04	7.8	10.52	-1.9
8/15/00	10:50:42	20.661	-0.098	-1.6	19.6	-2
8/15/00	10:51:43	20.693	-0.128	-1.4	16.87	-2
8/15/00	10:52:43	20.707	-0.141	-1.1	14.76	-2
8/15/00	10:53:43	20.681	-0.133	2.9	14.54	-2
8/15/00	10:54:43	20.716	-0.169	0.2	13.35	-2.1
8/15/00	10:55:43	20.728	-0.182	3.7	13.45	-2.1
8/15/00	10:56:43	20.735	-0.195	3.3	12.59	-2.1
8/15/00	10:57:43	20.726	-0.239	2.7	4.55	-2.1
8/15/00	10:58:43	20.738	-0.252	2.4	2.26	-2.1
8/15/00	10:59:43	20.745	-0.257	1.9	2.39	-2.1
8/15/00	11:00:43	20.748	-0.26	2.3	2.43	-2.1
8/15/00	11:01:43	20.748	-0.263	1.8	2.48	-2.2
8/15/00	11:02:43	20.75	-0.265	1.4	2.4	-2.2
8/15/00	11:03:43	20.754	-0.267	1.3	2.33	-2.2
8/15/00	11:04:43	20.757	-0.272	1.1	2.38	-2.2
8/15/00	11:05:43	20.757	-0.274	3	2.49	-2.2
8/15/00	11:06:43	20.76	-0.275	4	2.66	-2.2
8/15/00	11:07:41	20.757	-0.276	5.2	2.89	-2.2
8/15/00	11:08:41	20.754	-0.272	5.2	3.16	-2.2
8/15/00	11:09:41	20.618	-0.096	53.5	3.88	-2.2
8/15/00	11:10:41	20.669	-0.178	51.9	6.75	-2.2
8/15/00	11:11:41	20.57	-0.09	15.4	24.71	-2.2
8/15/00	11:12:42	20.532	-0.058	43.5	4.7	-2.2
8/15/00	11:13:42	20.503	-0.036	49.2	3.97	-2.2
8/15/00	11:14:42	20.495	-0.013	47.9	4.16	-2.2
8/15/00	11:15:42	20.453	0.006	71.3	4.31	-2.3
8/15/00	11:16:42	20.421	0.029	67.1	4.29	-2.2
8/15/00	11:17:42	20.464	-0.001	69	4.37	-2.2
8/15/00	11:18:42	20.479	-0.007	42.1	4.63	-2.3
8/15/00	11:19:42	20.469	0.036	79.8	5.9	-2.3
8/15/00	11:20:42	20.478	0.045	73.9	8.48	-2.3
8/15/00	11:21:42	20.447	0.083	36.3	9.66	-2.3
8/15/00	11:22:42	20.38	0.155	26.8	13.29	-2.3
8/15/00	11:23:42	20.509	-0.028	14.5	9.43	-2.3
8/15/00	11:24:42	20.698	-0.156	2.9	4.22	-2.3
8/15/00	11:25:42	20.691	-0.168	1.2	4.02	-2.4
8/15/00	11:26:42	20.691	-0.164	5.3	3.87	-2.4
8/15/00	11:27:42	20.711	-0.163	5.1	3.76	-2.4
8/15/00	11:28:42	20.744	-0.179	5.3	3.56	-2.3
8/15/00	11:29:43	20.602	-0.007	13.6	23.26	-2.3
8/15/00	11:32:43	20.471	0.127	40.9	7.31	-2.3

8/15/00	9:49:42	20.567	0.068	21.3	21.48	-1.3
8/15/00	9:50:42	20.478	0.199	24.8	8.26	-1.3
8/15/00	9:51:42	20.352	0.307	22	7	-1.4
8/15/00	9:53:42	20.331	0.29	32.1	8.31	-1.4
8/15/00	9:54:42	20.356	0.304	31.4	7.21	-1.4
8/15/00	9:55:42	20.406	0.276	56	7.26	-1.4
8/15/00	9:56:42	20.345	0.255	159.1	6.39	-1.5
8/15/00	9:57:42	20.341	0.279	138.3	5.83	-1.5
8/15/00	9:58:42	20.349	0.257	196.2	4.76	-1.4
8/15/00	9:59:43	20.357	0.25	177.4	3.54	-1.4
8/15/00	10:00:43	20.372	0.295	246.6	3.86	-1.5
8/15/00	10:01:43	20.367	0.277	233.3	3.22	-1.5
8/15/00	10:02:43	20.381	0.285	133.6	3.41	-1.5
8/15/00	10:03:43	20.205	0.508	142.6	2.56	-1.5
8/15/00	10:04:43	20.195	0.507	135.6	2.53	-1.5
8/15/00	10:05:43	20.233	0.514	101.2	2.7	-1.5
8/15/00	10:06:43	20.196	0.593	100.6	2.98	-1.6
8/15/00	10:07:43	20.227	0.492	109.4	4.95	-1.6
8/15/00	10:08:43	20.344	0.34	82	9.01	-1.6
8/15/00	10:09:43	20.381	0.29	85.7	7.66	-1.6
8/15/00	10:10:43	20.421	0.173	21	13.9	-1.6
8/15/00	10:11:43	20.511	0.07	2.5	20.13	-1.6
8/15/00	10:12:43	20.528	0.078	5.2	21.86	-1.6
8/15/00	10:13:43	20.403	0.201	35.7	10.57	-1.7
8/15/00	10:14:43	20.416	0.215	19.2	8.38	-1.7
8/15/00	10:15:41	20.408	0.227	17.8	10.46	-1.7
8/15/00	10:16:41	20.406	0.246	18.8	11.09	-1.7
8/15/00	10:17:41	20.393	0.275	16.5	9.85	-1.7
8/15/00	10:18:41	20.36	0.339	34.8	7.05	-1.7
8/15/00	10:19:41	20.389	0.295	23.6	6.21	-1.7
8/15/00	10:20:41	20.323	0.364	47.5	5.73	-1.7
8/15/00	10:21:42	20.395	0.176	14.8	7.15	-1.7
8/15/00	10:22:42	20.558	-0.024	-0.4	16.46	-1.8
8/15/00	10:23:42	20.612	-0.026	-0.7	14.33	-1.7
8/15/00	10:24:42	20.597	-0.02	-0.2	13.96	-1.7
8/15/00	10:25:42	20.485	0.069	6.6	18.15	-1.7
8/15/00	10:26:42	20.566	-0.023	0.3	16.16	-1.7
8/15/00	10:27:42	20.657	-0.094	-0.7	15.55	-1.7
8/15/00	10:28:43	20.679	-0.119	-1.6	13.09	-1.7
8/15/00	10:29:43	20.691	-0.113	-1.9	12.59	-1.7
8/15/00	10:30:42	20.608	0.008	-2.3	9.75	-1.7
8/15/00	10:31:43	20.606	0.004	-2.9	9.87	-1.8
8/15/00	10:32:43	20.605	0.017	-2.4	9.48	-1.8
8/15/00	10:33:43	20.625	-0.046	-2.7	10.79	-1.8
8/15/00	10:34:43	20.684	-0.127	-2.6	12.94	-1.8
8/15/00	10:35:43	20.635	-0.039	-2.8	8.51	-1.8
8/15/00	10:36:43	20.633	-0.038	-3.5	7.98	-1.8
8/15/00	10:37:43	20.665	-0.09	-3	10.06	-1.8
8/15/00	10:38:41	20.644	-0.057	-3.6	8.92	-1.8
8/15/00	10:39:42	20.647	-0.074	-3	9.28	-1.9

8/15/00	8:58:43	20.7	-0.082	3.5	13.03	-0.7
8/15/00	8:59:43	20.72	-0.103	2.3	14.21	-0.7
8/15/00	9:00:43	20.737	-0.116	1.4	13.81	-0.7
8/15/00	9:01:43	20.668	-0.045	1.5	26.44	-0.7
8/15/00	9:02:43	20.617	0.064	6.2	18.29	-0.7
8/15/00	9:03:42	20.606	0.056	4.2	15.4	-0.7
8/15/00	9:04:42	20.708	-0.035	1.6	22.29	-0.7
8/15/00	9:05:42	20.73	-0.062	1.5	19.33	-0.7
8/15/00	9:06:42	20.741	-0.071	1.5	17.88	-0.8
8/15/00	9:07:42	20.735	-0.057	1.8	17.41	-0.7
8/15/00	9:08:42	20.715	-0.045	1.7	14.98	-0.7
8/15/00	9:09:42	20.657	0.025	1.3	12.65	-0.7
8/15/00	9:10:42	20.533	0.365	15.3	12.62	-0.8
8/15/00	9:11:42	20.024	1.195	163.6	6.38	-0.8
8/15/00	9:13:42	20.688	-0.062	11.5	23.24	-0.8
8/15/00	9:14:42	20.675	-0.039	5.6	24.52	-0.8
8/15/00	9:15:42	20.675	-0.057	4	21.51	-0.9
8/15/00	9:16:42	20.704	-0.066	7.3	20.38	-0.8
8/15/00	9:17:42	20.7	-0.102	10.6	15.56	-0.8
8/15/00	9:18:42	20.75	-0.145	3	13.54	-0.8
8/15/00	9:19:43	20.748	-0.135	29.4	14.59	-0.8
8/15/00	9:20:43	20.787	-0.168	9.7	12.73	-0.8
8/15/00	9:21:43	20.802	-0.184	5	11.8	-0.9
8/15/00	9:22:43	20.808	-0.19	3.3	11.61	-0.9
8/15/00	9:23:43	20.814	-0.196	3.5	10.06	-0.9
8/15/00	9:24:43	20.817	-0.206	4.4	8.44	-0.9
8/15/00	9:25:43	20.787	-0.235	5.6	3.53	-1
8/15/00	9:26:43	20.792	-0.24	6.7	2.54	-0.9
8/15/00	9:27:43	20.791	-0.24	5.8	2.59	-0.9
8/15/00	9:28:43	20.787	-0.241	5.9	2.42	-0.9
8/15/00	9:29:43	20.786	-0.241	6.2	2.58	-1
8/15/00	9:30:43	20.786	-0.246	5.8	2.45	-1
8/15/00	9:31:43	20.777	-0.172	23.6	2.31	-1
8/15/00	9:32:43	20.539	-0.022	40.7	3.23	-1
8/15/00	9:33:43	20.582	-0.035	32	15.72	-1.1
8/15/00	9:34:41	20.493	0.099	14.8	5.67	-1.1
8/15/00	9:35:41	20.381	0.204	9.9	7.09	-1.1
8/15/00	9:36:41	20.414	0.179	11	7.02	-1.1
8/15/00	9:37:41	20.421	0.171	23.1	7.15	-1.2
8/15/00	9:38:41	20.4	0.204	58.3	6.61	-1.2
8/15/00	9:39:41	20.34	0.25	70.2	6.17	-1.2
8/15/00	9:40:41	20.323	0.253	213.8	5.6	-1.2
8/15/00	9:41:42	20.299	0.269	212.2	4.65	-1.2
8/15/00	9:42:42	20.288	0.353	316.4	3.42	-1.3
8/15/00	9:43:42	20.291	0.393	358.6	3.35	-1.3
8/15/00	9:44:42	20.312	0.328	192.1	3.5	-1.3
8/15/00	9:45:42	20.331	0.275	120.4	6	-1.3
8/15/00	9:46:42	20.298	0.306	112.6	6.02	-1.3
8/15/00	9:47:42	20.286	0.315	119.7	3.25	-1.3
8/15/00	9:48:42	20.325	0.24	107.1	5.9	-1.3

Test Run 1 Begin STRATA Version 1.2.1
 Operator: Peter Hilty
 Plant Name: Newport Steel
 Location: EAF Exhaust/Baghouse Inlet

		O ₂ %	CO ₂ %	CO ppm	NO _x ppm	SO ₂ ppm	
Begin calculating run averages							
8/15/00	8:15:41	20.408	0.409	246.8	2.58	-0.2	
8/15/00	8:16:41	20.357	0.384	167.8	2.5	-0.2	
8/15/00	8:17:41	20.377	0.296	175	2.96	-0.2	
8/15/00	8:18:41	20.664	0.033	13.8	7.1	-0.2	
8/15/00	8:19:41	20.748	-0.07	7.2	7.28	-0.3	
8/15/00	8:20:41	20.747	-0.031	46.5	6.27	-0.3	
8/15/00	8:21:42	20.689	0.004	100.7	5.87	-0.3	
8/15/00	8:22:42	20.505	0.196	24.2	13.11	-0.3	
8/15/00	8:23:42	20.426	0.266	15.9	5.88	-0.3	
8/15/00	8:24:42	20.416	0.32	20.3	6.31	-0.3	
8/15/00	8:25:42	20.359	0.372	41.8	7.7	-0.4	
8/15/00	8:26:42	20.399	0.308	72.4	6.09	-0.4	
8/15/00	8:27:42	20.398	0.319	94.9	4.99	-0.4	
8/15/00	8:28:42	20.36	0.328	99	5.09	-0.4	
8/15/00	8:29:42	20.337	0.346	160.5	5.26	-0.4	
8/15/00	8:30:42	20.354	0.316	244.6	4.81	-0.4	
8/15/00	8:31:42	20.386	0.3	290.6	3.98	-0.4	
8/15/00	8:32:42	20.413	0.231	215.9	5.27	-0.4	
8/15/00	8:33:42	20.431	0.214	213.5	7.27	-0.4	
8/15/00	8:34:42	20.472	0.192	158.5	6.25	-0.4	
8/15/00	8:35:42	20.473	0.173	129.1	3.54	-0.4	
8/15/00	8:36:42	20.482	0.167	95.6	4.98	-0.4	
8/15/00	8:37:42	20.465	0.184	76.1	6.9	-0.5	
8/15/00	8:38:43	20.48	0.196	45.8	7.56	-0.5	
8/15/00	8:39:43	20.49	0.224	24.6	7.74	-0.5	
8/15/00	8:40:43	20.477	0.239	23.4	7.17	-0.5	
8/15/00	8:41:43	20.579	0.083	5.7	12.51	-0.5	
8/15/00	8:42:43	20.619	0.068	1.1	10.05	-0.5	
8/15/00	8:43:43	20.562	0.134	7	7.45	-0.5	
8/15/00	8:44:41	20.534	0.177	7.5	11.2	-0.5	
8/15/00	8:45:42	20.446	0.344	21.5	12.84	-0.5	
8/15/00	8:46:42	20.465	0.293	11.4	15.49	-0.5	
8/15/00	8:47:42	20.462	0.311	13.1	14.51	-0.6	
8/15/00	8:48:42	20.406	0.413	38.3	11.1	-0.6	
8/15/00	8:49:42	20.32	0.451	50.7	7.2	-0.6	
8/15/00	8:50:42	20.42	0.267	33.3	9.15	-0.7	
8/15/00	8:51:42	20.513	0.174	6.5	16.24	-0.7	
8/15/00	8:52:42	20.568	0.101	3	18.82	-0.7	
8/15/00	8:53:42	20.631	0.03	2.1	21.8	-0.7	
8/15/00	8:54:42	20.66	0.008	1.7	22.14	-0.7	
8/15/00	8:55:43	20.672	-0.016	1.1	19.82	-0.8	
8/15/00	8:56:43	20.703	-0.041	0.8	17.38	-0.7	
8/15/00	8:57:43	20.667	-0.003	3.3	10.71	-0.7	

Test Run 4 Begin. STRATA Version 1.2.1

Operator: Peter Hilty

Plant Name Newport Steel

Location: EAF Exhaust/Baghouse Inlet

	02	CO2	CO	NOx
	%	%	ppm	ppm
Begin calculating run averages				
8/16/00 13:09:43	20.451	0.51	411.5	1.84
8/16/00 13:10:43	20.245	0.503	304.4	1.32
8/16/00 13:11:43	20.471	0.458	332.2	2
8/16/00 13:12:43	20.921	0.495	348.8	2.09
8/16/00 13:13:43	20.514	0.621	484.2	1.95
8/16/00 13:14:42	20.513	0.56	338.9	1.83
8/16/00 13:15:43	20.45	0.694	241.5	0.94
8/16/00 13:16:44	20.248	0.906	217.8	0.98
8/16/00 13:17:43	20.222	0.916	234.5	1.23
8/16/00 13:18:42	20.288	0.784	237.3	2.35
8/16/00 13:19:43	20.181	0.865	262.8	3.18
8/16/00 13:20:43	20.168	0.784	237.6	3.17
8/16/00 13:21:42	20.424	0.498	182	6.45
8/16/00 13:22:43	20.418	0.609	129.1	4.97
8/16/00 13:23:43	20.122	0.978	196.3	1.67
8/16/00 13:24:42	20.167	0.892	261	2.09
8/16/00 13:25:43	20.22	0.831	300.2	1.97
8/16/00 13:26:43	20.145	0.95	257.9	2.11
8/16/00 13:27:42	20.24	0.805	245.8	2.25
8/16/00 13:28:43	20.336	0.769	208.1	2.36
8/16/00 13:29:44	20.332	0.765	175.2	2.34
8/16/00 13:30:42	20.39	0.685	173.8	2.19
8/16/00 13:31:43	20.331	0.788	146.2	3.66
8/16/00 13:32:44	20.573	0.58	106.4	5.74
8/16/00 13:33:42	20.669	0.4	57.6	8.55
8/16/00 13:34:43	20.746	0.283	34.3	17.09
8/16/00 13:35:43	20.798	0.221	21.2	14.02
8/16/00 13:36:42	20.788	0.228	21.6	11.85
8/16/00 13:37:43	20.771	0.206	20.1	11.82
8/16/00 13:38:44	20.802	0.188	31.3	11.89
8/16/00 13:39:42	20.825	0.171	22.9	11.02
8/16/00 13:40:43	20.86	0.143	14.3	9.86
8/16/00 13:41:43	20.883	0.129	10.6	9.45
8/16/00 13:42:44	20.871	0.12	8.9	10.42
8/16/00 13:43:42	20.89	0.098	9.1	9.45
8/16/00 13:44:43	20.904	0.084	10	8.28
8/16/00 13:45:44	20.91	0.087	11.3	9.46
8/16/00 13:46:42	20.91	0.089	13.7	9.84
8/16/00 13:47:43	20.913	0.089	15.1	9.83
8/16/00 13:48:44	20.91	0.089	14.2	9.63

FBT

8/16/00 13:49:42	20.906	0.088	14.1	9.45
8/16/00 13:50:43	20.861	0.167	33.1	9.42
8/16/00 13:51:44	20.396	0.614	108.7	11.82
8/16/00 13:52:42	20.505	0.47	91.2	6.51
8/16/00 13:53:43	20.646	0.324	64.9	4.25
8/16/00 13:54:43	20.527	0.415	95.9	3.92
8/16/00 13:55:42	20.491	0.453	50.1	3.37
8/16/00 13:56:43	20.513	0.429	72.6	3.12
8/16/00 13:57:43	20.501	0.436	141.5	2.87
8/16/00 13:58:42	20.474	0.466	170.7	2.71
8/16/00 13:59:43	20.467	0.477	155.4	2.65
8/16/00 14:00:43	20.428	0.518	137.6	1.83
8/16/00 14:01:42	20.387	0.538	108.9	2.19
8/16/00 14:02:43	20.399	0.534	145.7	2.41
8/16/00 14:03:43	20.414	0.586	168.6	2.08
8/16/00 14:04:42	20.385	0.61	150.3	1.65
8/16/00 14:05:43	20.397	0.585	143.6	1.69
8/16/00 14:06:43	20.412	0.535	124.3	1.58
8/16/00 14:07:42	20.444	0.489	105.2	1.57
8/16/00 14:08:43	20.465	0.464	107.4	1.24
8/16/00 14:09:43	20.468	0.466	116.4	1.01
8/16/00 14:10:42	20.572	0.34	43.3	7.16
8/16/00 14:11:43	20.714	0.218	9.9	7.5
8/16/00 14:12:43	20.762	0.162	7.3	6.79
8/16/00 14:13:42	20.754	0.228	27.5	6.91
8/16/00 14:14:43	20.536	0.449	73.5	4.74
8/16/00 14:15:44	20.522	0.475	59.3	4.24
8/16/00 14:16:43	20.423	0.525	22.1	4.36
8/16/00 14:17:43	20.482	0.465	16.1	4.76
8/16/00 14:18:42	20.491	0.473	45.1	4.6
8/16/00 14:19:43	20.531	0.477	148.4	3.98
8/16/00 14:20:42	20.536	0.478	222.6	3.32
8/16/00 14:21:42	20.483	0.517	281.9	3.26
8/16/00 14:22:44	20.386	0.588	182.7	2.99
8/16/00 14:23:43	20.407	0.523	234.1	2.81
8/16/00 14:24:43	20.448	0.51	299.8	2.42
8/16/00 14:25:43	20.471	0.533	268.3	2.3
8/16/00 14:26:43	20.502	0.469	167.7	3.16
8/16/00 14:27:43	20.535	0.467	158.2	6.76
8/16/00 14:28:43	20.553	0.472	101.7	5.65
8/16/00 14:29:43	20.601	0.409	22.5	9.82
8/16/00 14:30:42	20.612	0.413	15.7	7.26
8/16/00 14:31:42	20.548	0.523	51.2	3.5
8/16/00 14:32:42	20.488	0.546	74.1	2.26
8/16/00 14:33:44	20.569	0.45	24	3.25
8/16/00 14:34:44	20.656	0.314	5.5	6.88
8/16/00 14:35:43	20.64	0.335	8.8	8.07

8/16/00 14:36:43	20.703	0.269	4.3	7.2
8/16/00 14:37:43	20.655	0.319	16.2	6.12
8/16/00 14:38:43	20.574	0.489	42.7	3.53
8/16/00 14:39:43	20.384	0.764	109.3	1.08
8/16/00 14:40:42	20.446	0.603	70.2	2.81
8/16/00 14:41:42	20.463	0.581	46.9	4.31
8/16/00 14:42:42	20.462	0.633	50.4	3.44
8/16/00 14:43:44	20.328	0.808	98.3	2.19
8/16/00 14:44:44	20.532	0.472	42.7	6
8/16/00 14:45:43	20.655	0.365	19	10.22
8/16/00 14:46:43	20.687	0.343	12.5	19.13
8/16/00 14:47:43	20.616	0.426	14	6.03
8/16/00 14:48:43	20.635	0.363	10.3	5.41
8/16/00 14:49:43	20.655	0.39	9.5	5.09
8/16/00 14:50:42	20.52	0.655	62.6	2.02
8/16/00 14:51:42	20.607	0.323	46.7	4.22
8/16/00 14:52:44	20.799	0.169	8	5.41
8/16/00 14:53:44	20.823	0.151	6.9	5.43
8/16/00 14:54:44	20.803	0.175	8.9	5.7
8/16/00 14:55:44	20.788	0.176	10.7	5.97
8/16/00 14:56:43	20.813	0.172	26.3	6.08
8/16/00 14:57:43	20.814	0.157	25.8	6.1
8/16/00 14:58:43	20.851	0.13	9.1	5.22
8/16/00 14:59:43	20.856	0.122	6.9	5.19
8/16/00 15:00:44	20.854	0.105	6.9	4.68
8/16/00 15:01:42	20.86	0.092	7.3	4.56
8/16/00 15:02:43	20.863	0.092	9.5	4.82
8/16/00 15:03:44	20.866	0.092	9.8	4.69
8/16/00 15:04:42	20.869	0.091	10.4	4.36
8/16/00 15:05:43	20.845	0.081	9.8	1.03
8/16/00 15:06:44	20.845	0.077	9.1	0.61
8/16/00 15:07:42	20.847	0.076	8.8	0.65
8/16/00 15:08:43	20.851	0.073	8.7	0.65
8/16/00 15:09:44	20.855	0.072	8.7	0.6
Average of Test Run	O2	CO2	CO	NOx
	%	%	ppm	ppm
8/16/00 15:10:36	20.58	0.42	99.79	4.96
Test Run 4 End				

JAMES E. BICKFORD
SECRETARY



PAUL E. PATTON
GOVERNOR

COMMONWEALTH OF KENTUCKY
NATURAL RESOURCES AND ENVIRONMENTAL PROTECTION CABINET
DEPARTMENT FOR ENVIRONMENTAL PROTECTION
DIVISION FOR AIR QUALITY
803 SCHENKEL LN
FRANKFORT KY 40601-1403
October 23, 2000

Ms. Jennifer A. McDaniel
Manager, Environmental and
Safety Compliance
Newport Steel
Ninth & Lowell Streets, P.O. Box 1670
Newport, Kentucky 41072

Dear Ms. McDaniel:

On August 15 and 16, 2000, particulate, carbon monoxide, VOC, lead, NO_x, and SO₂ compliance tests were performed on the Electric Arc Furnace Brandt Baghouse at your Newport facility. FBT Testing and Environmental Services, Inc performed the testing. John Allen and John Jayne observed testing for the Division for Air Quality. Proper test methods were followed, and the test report was checked for completeness and accuracy. The results are summarized below.

PARAMETER	TEST RESULTS	PERMIT LIMIT
Particulate	0.00089 gr/dscf	0.0052 gr/dscf
Sulfur Dioxide	0.013 lb/hr	
Nitrogen Oxides (as NO ₂)	0.63lb/ton of steel	0.51 lb/ton of steel
Carbon Monoxide	251.3 lb/hr	
Lead	0.021 lb/hr	1.71 lb/hr

Therefore, this test report is accepted as proof of compliance for particulate, and lead. Nitrogen oxide emissions were above the permit level of 0.51 lbs/ton of steel produced. There is not a separate compliance limit for carbon monoxide and sulfur dioxide from the Brandt Baghouse. A copy of this letter is being sent to the Florence Regional Office for review. If you have any questions, please contact me at (502) 573-3382.

Sincerely,

Gerald Slucher, Supervisor
Source Testing Section
Technical Services Branch

NO_x = 14.8 lb/hr AVG
23.4 TON/HR

GHS

cc: Edd Frazier
W. A. Clements
Florence Regional Office
Pat Johnston



Printed on Recycled Paper
An Equal Opportunity Employer M/F/

bcc: File: ID# 21-037-00006

NEWPORT STEEL

Facility Newport Steel
Source Type Brandt Baghouse
Performed By FBT Req. by John Allen Rvwed. By Slucher
Date Performed 8/15/00 Received 10/13/00 Reviewed 10/19/00
=====

PARTICULATE

	Run #1	Run #2	Run #3
Cp	0.84	0.84	0.84
Theta,min.	180	180	180
As,ft2	176.7	176.7	176.7
Ts,degF	167	190	197
Ps,in.Hg.	28.92	29.43	29.43
DELPsqr	1.19	1.118	1.1458
Gamma	1.001	1.001	1.001
Tm,degF	96	81	89
Pbar,in.Hg.	29.2	29.68	29.68
Vlc,ml.	60.3	47.2	63.4
Vm.ft3.	121.805	120.239	120.635
DELH,in.H2O	1.4	1.4	1.4
CO2%	0.1	0.1	0.1
O2%	20.6	20.7	20.6
CO%	0	0	0
N2%	79.3	79.2	79.3
Vwstd,ft3	2.84013	2.22312	2.98614
Vmstd,ft3.	162.524936	153.197422	157.523896
Bws	0.01717491	0.0143039	0.01860407
Md	28.84	28.844	28.84
Ms	28.653824	28.6888885	28.6383319
vs1,ft/sec	74.3335538	70.4435271	72.6469049
Q1std,dscf/hr.	37826992.7	35291569.4	35850580.9

GASEOUS EMISSIONS

	Run #1	Run #2	Run #3
CARBON MONOXIDE			
Mol. Wt.	28.01		
ppm	100.3	89.4	115.1
lb/scf	7.28818E-06	6.4961E-06	8.3636E-06
lb/hr	275.6901151229	259287	299.840275
NITROGEN OXIDES			
Mol. Wt.	46.01	46.01	46.01
ppm	3.3	2.7	4.2
lb/scf	3.94006E-07	3.2237E-07	5.0146E-07

NEWPORT STEEL

lb/hr	14.90407448	11.3769014	17.9777255
SULFUR DIOXIDE			
Mol. Wt.	64.06	64.06	64.06
ppm	0.68	0.88	0.8
lb/scf	1.13049E-07	1.463E-07	1.33E-07
lb/hr	4.276297154	5.16310304	4.69373004
Average lb/hr:			
CO	268.2632255		
NOx	14.75290044		
Sulfur Dioxide	4.71104341		



36

10.2

COMMONWEALTH OF KENTUCKY
NATURAL RESOURCES AND ENVIRONMENTAL PROTECTION CABINET
DEPARTMENT FOR ENVIRONMENTAL PROTECTION
DIVISION FOR AIR QUALITY
803 SCHENKEL LN
FRANKFORT KY 40601 1403
November 9, 2000

Ms. Jennifer A. McDaniel
Manager, Environmental and
Safety Compliance
Newport Steel
Ninth & Lowell Streets, P.O. Box 1670
Newport, Kentucky 41072

Dear Ms. McDaniel:

On October 3 and 4, 2000, carbon monoxide, NO_x, and SO₂ compliance tests were performed on the Electric Arc Furnace Brandt Baghouse at your Newport facility. Pacific Environmental Services, Inc performed the testing. John Allen and John Jayne observed testing for the Division for Air Quality. Proper test methods were followed, and the test report was checked for completeness and accuracy. The results are summarized below.

PARAMETER	TEST RESULTS	PERMIT LIMIT
Sulfur Dioxide	4.24 lb/hr, 0.07 lb/ton steel	
Nitrogen Oxides (as NO ₂)	0.22 lb/ton of steel	0.51 lb/ton of steel
Carbon Monoxide	272.1 lb/hr, 4.0 lb/ton steel	

Therefore, this test report is accepted as proof of compliance for nitrogen oxide emissions. There is not a separate compliance limit for carbon monoxide and sulfur dioxide from the Brandt Baghouse. A copy of this letter is being sent to the Florence Regional Office for review. If you have any questions, please contact me at (502) 573-3382.

Sincerely,

Gerald Slucher, Supervisor
Source Testing Section
Technical Services Branch

GHS

cc: Edd Frazier
W. A. Clements
Florence Regional Office
Pat Johnston



bcc: File: ID# 21-037-00006



Printed on Recycled Paper
An Equal Opportunity Employer M



Oil Country Tubular Goods
Line Pipe • Piling

November 3, 2000

Department for Environmental Protection
Division for Air Quality
803 Schenkel Lane
Frankfort, KY 40601-1403
Attn: Mr. Gerald Slucher

Re: Stack Test Results for EAF Exhaust/Brandt Baghouse
Air Quality Permit (F-98-014)

Dear Mr. Slucher,

Enclosed please find a copy of the, "Air Emissions Test Report – Brandt Positive Pressure Baghouse, Newport Steel Corporation, Newport, Kentucky." The test was conducted October 3 – October 4, 2000.

If you have any further questions, please feel free to contact me at 859/292-7236.

Sincerely,
Newport Steel Corporation

A handwritten signature in cursive script, reading 'Jennifer A. McDaniel'.

Jennifer A. McDaniel
Manager, Environmental and
Safety Compliance

Cc: Thorn Goltzki

**AIR EMISSION TEST REPORT
BRANDT POSITIVE PRESSURE BAGHOUSE
NEWPORT STEEL
NEWPORT, KENTUCKY**

Prepared for

Newport Steel Corporation
P.O. Box 1670
Ninth & Lowell Streets
Newport, KY 41072

PN 050101.0013

Prepared by

Environmental Quality Management, Inc.
1310 Kemper Meadow Drive
Cincinnati, Ohio 45240
(513) 825-7500
Fax: (513) 825-7495

November 2000

TABLE OF CONTENTS

SECTION 1	INTRODUCTION	1-1
SECTION 2	SUMMARY OF TEST RESULTS	2-1
SECTION 3	SAMPLING AND ANALYTICAL PROCEDURES	3-1
	Location of Measurement Sites	3-1
	Stack Gas Volumetric Flow Rate	3-1
	Stack Gas Dry Molecular Weight	3-1
	Visible Emission Observation	3-2
	Stack Gas Moisture Content	3-2
	Nitrogen Oxides (NO _x)	3-2
	Carbon Monoxide	3-2
	Sulfur Dioxide (SO ₂)	3-2
SECTION 4	PROCESS DESCRIPTIONS/SAMPLING LOCATIONS . . .	4-1
SECTION 5	QUALITY ASSURANCE AND QUALITY CONTROL	5-1
	Calibration Procedures and Frequency	5-1
APPENDIX A	EXAMPLE CALCULATIONS	
APPENDIX B	FIELD DATA	
APPENDIX C	ANALYZER DATA	
APPENDIX D	PROCESS DATA	
APPENDIX E	CALIBRATION DATA	
APPENDIX F	VISIBLE EMISSION OBSERVATION FORMS	
APPENDIX G	CONTINUOUS EMISSION MONITORING DATA	

FIGURES

<u>Number</u>		<u>Page</u>
3-1	CEM Sample Flow and Calibration System Schematic	3-3
4-1	Brandt Baghouse Inlet Sampling Location Schmatic	4-2

TABLES

<u>Number</u>		<u>Page</u>
2-1	Summary of Stack Gas Conditions .	
	Brandt Baghouse Inlet	2-2
2-2	Summary of NO _x and CO Emissions .	
	Brandt Baghouse Inlet	2-3
2-3	Summary of SO ₂ Emissions	
	Brandt Baghouse Inlet	2-4
2-4	Data Comparison - CO (ppm)	2-5
2-5	Data Comparison - NO _x (ppm)	2-5
2-6	VE Readings and Rolling 6-Minute VE Averages for Newport Steel	
	Brandt Baghouse	2-6
2-7	VE Readings and Rolling 6-Minute VE Averages for Newport Steel	
	Melt Shop	2-25
5-1	Field Equipment Calibration Summary	5-2
5-2	Field Checks of Sampling Equipment	5-3
5-3	Field Checks of NO _x and CO Analyzers	5-3

SECTION 1

INTRODUCTION

Beginning on October 3, 2000 through October 4, 2000, Environmental Quality Management (EQ) and Pacific Environmental Services, Inc. (PES) personnel conducted an air emission evaluation at the Newport Steel Melt Shop in Newport, Kentucky. Sampling was conducted following the procedures of EPA reference methods. Nitrogen oxide, carbon monoxide and sulfur dioxide emissions were measured at the inlet of the Brandt fabric filter baghouse serving the electric arc furnace.

EQ utilized EPA Reference Methods 1-4 to determine stack gas velocity and temperature, molecular weight, and moisture. Nitrogen oxide emissions were measured following the procedures of EPA Reference Method 7E. Carbon monoxide emissions were measured following the procedures of EPA Reference Method 10. Sulfur dioxide emissions were measured following the procedures of EPA Reference Method 6. Visible emission observations were conducted at the Brandt Baghouse exhaust and furnace roof monitor. The visible emission observations were conducted according to the procedures in EPA Method 9.

Ms. Jennifer McDaniel of Newport Steel coordinated process operations with the test team. Mr. Fred Hall and Mr. Tom Gerstle of EQ monitored process operations for the purposes of testing. Messrs. Ron Kolde, Gary Gay and Bryan Boggs of PES conducted all field efforts as the PES test team.

SECTION 2

SUMMARY OF TEST RESULTS

Sampling of Brandt Baghouse was conducted beginning on October 3, 2000. Test runs were at least 180 minutes in duration. Results from all three test runs are presented.

Table 2-1 summarizes the stack gas conditions measured at the baghouse inlet location. Moisture content was measured at the inlet and is applied in calculations for actual molecular weight calculations. The baghouse inlet had an average stack gas velocity of 72.0 feet per second at 177°F and 2.3 percent moisture content. Volumetric flow rates averaged 763,477 actual cubic feet per minute (acfm) or 608,262 dry standard cubic feet per minute (dscfm). Composition of the stack gas was essentially ambient in nature (0.1% carbon dioxide and 21.0% oxygen).

Table 2-2 summarizes the NO_x and CO emissions measured at the baghouse inlet. The overall average NO_x concentration was 3.4 parts per million (ppm), for a corresponding mass emission rate of 14.6 pounds per hour (lb/hr). Based on steel production, the NO_x emission factor is 0.22 pound per ton of steel (lb/ton steel). The overall average CO concentration was 101.6 ppm, for a corresponding mass emission rate of 272.1 lb/hr, or 4.0 lb/ton steel.

Table 2-3 summarizes the SO₂ emissions for the three test runs. SO₂ concentrations averaged 0.79 ppm, for a corresponding mass emission rate of 4.82 lb/hr, or 0.07 lb/ton of steel produced.

Tables 2-4 and 2-5 present the test results comparing the NO_x and CO concentrations measured by the EPA Reference Methods (RM) 7E and 10, respectively, and the NO_x and CO concentrations concurrently measured by the CEMs.

EPA Reference Method 9, "Visible Determination of the Opacity of Emissions from Stationary Sources," was used to determine opacity from the baghouse exhaust as well as from the shop roof monitor. Observations were conducted simultaneously at each source in conjunction with the particulate sampling runs. The observations were recorded separately for the baghouse exhaust and melt shop roof monitor. The baghouse observation data is provided in Table 2-6. The melt shop observation data are provided

in Table 2-7. Both tables also present the rolling 6-minute averages. The visible emissions averaged 0% for the baghouse and furnace roof monitor.

The data are presented as a comparison in relative concentration. The RM CO and NO_x data were collected at the Brandt baghouse inlet duct. The CEM CO and NO_x data were collected at the baghouse roof monitor, downstream of the bags.

Field data is presented in Appendix B and CEM data is presented in Appendix C.

TABLE 2-1
SUMMARY OF STACK GAS CONDITIONS
BRANDT BAGHOUSE INLET

Dates: October 3-4, 2000

Plant: Newport Steel, Newport, Kentucky

Run No./ Date	Time	Stack Gas Velocity, fps ^a	Volumetric Flow Rate		Stack Temp, °F	Moisture, %
			acfm ^b	dscfm ^c		
BI-1 10/3/00	1620	72.6	769,801	642,495	146	2.4
	1920	72.5	768,488	602,864	185	2.4
Average		72.6	769,145	622,680	166	2.4
BI-2 10/4/00	0730	70.1	743,496	589,107	183	1.9
	1115	72.6	770,057	597,374	197	1.9
Average		71.4	756,777	593,241	190	1.9
BI-3 10/4/00	1115	72.7	770,918	594,384	197	2.5
	1510	71.5	758,099	623,348	155	2.5
Average		72.1	764,509	608,866	176	2.5
Overall Average		72.0	763,477	608,262	177	2.3

^aFeet per second.

^bActual cubic feet per minute.

^cDry standard cubic feet per minute

TABLE 2-2
SUMMARY OF NO_x AND CO EMISSIONS
BRANDT BAGHOUSE INLET

Dates: October 3-4, 2000

Plant: Newport Steel, Newport, Kentucky

Run No./ Time	Nitrogen Oxides			Carbon Monoxide			Steel Production, tons/hr ^(d)
	Conc., ^(a) ppm dry	Mass Rate lb/hr ^(b)	Mass Rate lb/ton Steel ^(c)	Conc., ppm dry ^(a)	Mass Rate lb/hr ^(b)	Mass Rate lb/ton Steel ^(c)	
October 3, 2000							
BI-1 1007 - 1051 1629 - 1928	3.6 2.9	15.94 12.74	0.25 0.20	125.2 75.3	340.0 204.6	5.43 3.27	87.5 83.6 40.5
Average	3.3	13.38 ^(b)	0.23	100.3	272.3 ^(b)	4.35	62.6
October 4, 2000							
BI-2 0800 - 0959 1045 - 1159	3.3 2.1	14.23 8.75	0.19 0.12	107.0 71.7	277.0 185.5	3.69 2.47	79.5 63.6 79.4 80.1
Average	2.7	12.13 ^(b)	0.15	89.4	231.3 ^(b)	3.08	75.0
BI-3 1245 - 1405 1422 - 1622	4.7 3.7	20.91 16.61	0.30 0.24	101.3 128.8	275.4 350.3	4.01 5.11	80.1 79.3 66.4 55.0
Average	4.2	18.33 ^(b)	0.27	115.1	312.9 ^(b)	4.56	68.6
Overall Average	3.4	14.61	0.22	101.6	272.1	4.00	68.7

^aPart per million, dry basis.

^bPound per hour: the average mass rate is a time weighted average (calculations are provided in Appendix A).

^cPound per ton of steel produced (average steel production used in calculation).

^dRate of steel production, tons per hour.

**TABLE 2-3
SUMMARY OF SULFUR DIOXIDE EMISSIONS
BRANDT BAGHOUSE INLET**

Run No./ Time	Concentration	Mass Rate		Steel Production tons/hr ^(d)
	ppm dry ^(a)	lb/hr ^(b)	lb/ton steel ^(c)	
BI-2	0.68	4.24	0.07	62.6
BI-3	0.88	5.22	0.07	75.0
BI-4	0.80	5.00	0.07	68.6
Average	0.79	4.82	0.07	68.7

^(a)Part per million, dry basis

^(b)Pounds per hour

^(c)Pounds per ton of steel

^(d)Rate of steel production, tons per hour

TABLE 2-4. DATA COMPARISON - CO (ppm)

Run #	Date	Time	Values	
			RM	CEMS
1	10/03/00	1007-1051	100.3	85.4
2	10/04/00	0800-0959	89.4	83.7
3	10/04/00	1245-1405	115.1	98.9
Averages:			101.6	89.3

RM - Data collected at baghouse inlet using EPA Reference Method 10.

CEMS - Continuous emission monitoring data collected at the baghouse exhaust.

TABLE 2-5. DATA COMPARISON - NO_x (ppm)

Run #	Date	Time	Values	
			RM	CEMS
1	10/03/00	1629-1928	3.3	3.7
2	10/04/00	1045-1159	2.7	4.2
3	10/04/00	1422-1622	4.2	5.7
Averages:			3.4	4.5

RM - Data collected at baghouse inlet using EPA Reference Method 7E.

CEMS - Continuous emission monitoring data collected at the baghouse exhaust.

SECTION 3

SAMPLING AND ANALYTICAL PROCEDURES

The sampling and analytical procedures used in this test program conform to EPA Reference Methods 1-4, 6, 7E, 9 and 10, as published in the Federal Register.

LOCATION OF MEASUREMENT SITES

EPA Method 1, "Sample Velocity Traverses for Stationary Sources," was used to select representative measurement sites. Sample locations are shown in Section 4.

STACK GAS VOLUMETRIC FLOW RATE

EPA Method 2, "Determination of Stack Gas Velocity and Volumetric Flow Rates," was used at each location to determine stack gas volumetric flow rates. Standard and Type "S" pitot tubes, meeting the EPA specifications, and an inclined manometer were used to measure velocity pressures. A calibrated Type "K" thermocouple, attached directly to the pitot tube, was used to measure stack gas temperature. The stack gas velocity was calculated from the average square root of the stack gas velocity pressure, average stack gas temperature, stack gas molecular weight, and absolute static pressure. The volumetric flow rate is the product of velocity and stack cross-sectional area.

STACK GAS DRY MOLECULAR WEIGHT

EPA Reference Method 3, "Gas Analysis for the Determination of Dry Molecular Weight," was used to determine stack gas dry molecular weight. Fyrite® gas analyzers were used to measure direct concentrations of stack gas for percent concentrations of carbon dioxide and oxygen, along with integrated Tedlar® bag samples collected during each measurement run which were analyzed with an Orsat® analyzer.

STACK GAS MOISTURE CONTENT

EPA Reference Method 4, "Determination of Moisture Content in Stack Gases," was used to determine stack gas moisture content. This method was conducted during each NO_x measurement run. The initial and final contents of all impingers are determined gravimetrically.

VISIBLE EMISSION OBSERVATIONS

EPA Reference Method 9, "Visual Determination of the Opacity of Emissions from Stationary Sources" was used to determine the opacity from the baghouse exhaust as well as from the melt shop roof monitor. Observations were conducted simultaneously with the emission measurement runs.

NITROGEN OXIDES (NO_x)

EPA Reference Method 7E, "Determination of Nitrogen Oxide Emissions from Stationary Sources" (Instrumental Analyzer Procedure) was used to measure NO_x emissions at the Brandt baghouse inlet. The sampling system consisted of a Teflon sampling line connected to a stainless steel condenser and stainless steel probe with a three-way valve. Stack gas was routed to a chemiluminescent analyzer through this system. Data was collected on both a Yokogawa strip chart recorder and Strata data logging system. The analyzer was calibrated with a zero gas and two Protocol One nitrogen oxides-in-nitrogen calibration gases. Calibrations were performed at the start of each sample run and at 2.5-hour intervals during each test run. Each sampling run was approximately 3 - 4 hours in length. Figure 3-1 is a schematic of the sampling system.

CARBON MONOXIDE (CO)

EPA Reference Method 10, "Determination of Carbon Monoxide Emissions from Stationary Sources," was used to measure CO emissions at the Brandt Baghouse inlet. The same sampling system for measuring NO_x emissions was used, with the exception of the CO instrument, which uses a non-dispersive infrared detection principle. The instrument was calibrated with a zero gas and three master gas certified calibration gases with concentrations of CO-in-nitrogen (balance). Figure 3-1 is a schematic of the sampling system.

SULFUR DIOXIDE (SO₂)

EPA Reference Method 6, "Determination of Sulfur Dioxide Emissions from Stationary Sources," was used to measure SO₂ emissions at the Brandt Baghouse inlet. A glass lined probe, filter assembly and series of four impingers containing 80% isopropanol (1st), 3% hydrogen peroxide (2nd and 3rd) and silica gel (4th) were used to collect SO₂ concentrations. The probe and filter assembly were maintained at

250°F, $\pm 25^\circ\text{F}$. Recovery of the sample trains consisted of a D.I. water rinse for impingers 2 and 3 after placing the contents in a sample recovery bottle. **Impinger** weights were recorded initially and at the end of each test run gravimetrically. Analysis of the samples was by barium perchlorate **titration** using thorin indicator. Figure 3-2 is a schematic of the SO₂ sampling train.




Figure 3-1. CEM Sample Flow and Calibration System Schematic (with THC analyzer)
Note: This study used the NO_x and CO analyzer.




Figure 3-2 Schematic of SO₂ Sampling System

SECTION 4

PROCESS DESCRIPTIONS/SAMPLING LOCATIONS

The processes operating in the Newport Steel Corporation Melt Shop are the electric arc furnace (EAF), ladle metallurgy furnace (LMF), and continuous slab caster. The structure containing the EAF is referred to as the EAF building, and the structure containing LMF and the Caster is referred to as the Main Melt Shop Building. The Brandt baghouse vents emissions from the EAF and the EAF building.

Figure 4-1 shows the process flow for the Newport electric arc furnace (EAF). The EAF is a batch process. Each process cycle consists of four distinct phases: charging, melting, slagging, and tapping. After the furnace is charged with scrap and other additives, the meltdown phase comprises the period from charging to the complete meltdown of the solid material. Melting is accomplished by the heat supplied by direct radiation from the arcs formed between the electrodes and the scrap metal, by direct radiation from the furnace lining, and electric resistance of the metal between arc paths. The EAF also has oxy-fuel burners to provide additional heat input to enhance scrap meltdown and oxygen/carbon lances to enhance meltdown, refining, and foamy slag practice.

When the melting phase is complete, chemistry and temperature samples are taken. Based on these samples, the steel composition is adjusted and when the proper steel temperature has been reached, the foamy slag is poured off the furnace. For tapping, the power is shut off, the electrodes are raised to clear the molten steel bath, and the molten steel is tapped into a ladle and transferred to the LMF. After steel tapping is completed, the melting cycle begins again (i.e., the charging phase begins).

The Brandt baghouse exhausts the electric arc furnace (EAF) and the EAF building by an exhaust system consisting of (1) a direct evacuation control (DEC), and (2) a roof canopy hood. The DEC - also called a "fourth hole" system or direct shell evacuation (DSE) - captures emissions generated during scrap meltdown while the EAF roof is in place directly from the furnace vessel. The DEC is comprised of water-cooled ductwork to cool the hot EAF exhaust gases. Prior to the water-cooled section, a gap in the duct allows the entrainment of shop ambient air to assist in the combustion of carbon monoxide (CO) off-gases to carbon dioxide (CO₂). After passing sufficient distance to cool the exhaust, the DEC duct then merges with shop roof ductwork from the roof canopy hood. The overhead roof canopy hood collects fumes and gases that escape the furnace shell. The combined gas stream including EAF exhausts and melt shop ambient air is ducted to the Brandt baghouse.


Process information was collected during the course of the sampling program and included:

- A) Charge weights and materials, and tap weights and materials
- B) Heat times, including start and stop times, log of process operation including periods of no operation during testing
- C) Pressure drop across the baghouse, visual inspection of bagsand control system fan amperes
- D) Fan/duct damper positions
- E) Fan amperes

Data was recorded at 15-minute intervals during testing. These data are provided in Appendix D.

EPA Reference Method 1 was used to determine representative measurement sites for stack gas velocity determinations on the baghouse inlet duct. The inlet of the baghouse consisted of a circular horizontal duct, 15 feet in diameter. Two sampling ports were located approximately 150 feet (10 duct diameters) downstream of a 45° elbow and 19 feet (1.3dd) upstream of the nearest disturbance. Eight points per port for a total of 16 points were used for the velocity traverse. A schematic of the baghouse inlet site is shown in Figure 4-2.

The NO_x, CO and SO_x sampling system collected data from this location.



Newport Steel, Inc.	EQ
Process Flow Diagram:	
Melt Shop - Electric Arc Furnace (EAF)	
Drawing No.:	
Scale: Not to Scale	
Drawn by: RJH	
Revision: 0	
Checked by: FDH	
Date: 2/9/98	

Figure 4-1 Schematic of Process Flow

Melt Shop - Electric Arc Furnace (EAF)






Figure 4-2 Schematic of Brandt Baghouse Inlet Sampling Location

SECTION 5

QUALITY ASSURANCE AND QUALITY CONTROL

The field sampling quality assurance for this project included the use of: calibrated source sampling equipment; reference test methods; and traceability protocols for the recording and calculation of data. The analytical quality assurance includes use of validated analytical procedures; calibration of analytical instruments; and analysis of control samples and blanks. The calibration and quality control procedures used for this test program are described in the following subsection:

CALIBRATION PROCEDURES AND FREQUENCY

All manual stack gas sampling equipment was calibrated before the test program in accordance with the procedures outlined in the *Quality Assurance Handbook for Air Pollution Measurement Systems, Volume III*, EPA-600/4-72-027B. Summarized in Table 5-1 are the stack gas sampling equipment calibrations which were performed in preparation for this project. The meter boxes were re-calibrated after the test.

Listed in Tables 5-2 and 5-3 are the additional calibration checks which were performed on the sampling equipment on-site, just prior to the testing, to ensure that equipment was not damaged during transport. Analyzer checks were conducted directly on the instrument initially and then through the sampling system. Calibration checks were conducted before and after each test run. Protocol One calibration gases were used for calibrating the NO, analyzer and master gas certified calibration gases for the CO analyzer.

TABLE 5-1
FIELD EQUIPMENT CALIBRATION SUMMARY*

Equipment	Calibrated against	Allowable error
Method 5 meter box	Reference test meter	Y k0.02 Y ▲H@ k0.20 ▲H@ post-test Y ±0.05 Y
Orsat®	Certified cylinder gas	±0.5%
Pitot tube	Geometric specifications	See EPA Method 2
Thermocouple	ASTM-3F thermometer	±1.5%
Impinger (or condenser thermome- ter)	ASTM-3F	±2°F
Dry gas meter thermometer	ASTM-3F	±5°F
Barometer	NBS traceable barometer	±0.1 in.Hg

*As recommended in the Quality Assurance Handbook for Air Pollution Measurement Systems: Volume III. Stationary Source-Specific Methods. EPA-600/4-77-027b, August 1977.

TABLE 5-2
FIELD CHECKS OF SAMPLING EQUIPMENT

Equipment	Checked against	Allowable difference
Pitot tube	Inspection	No visible damage
Thermocouples	ASTM 2F or 3F	$\pm 1.5\%$
Probe nozzles	Caliper	High-low 0.004 in.

TABLE 5-3
FIELD CHECKS OF NO_x ANALYZER

	Instrument Check	Acceptable Limit
Initial Calibration	CO & NO _x Calibration Error, % Span	$\pm 2\%$
	Sampling System Bias	< 5% of Span
Daily Calibration	CO & NO _x Calibration Error, % Span	$\pm 2\%$
	CO & NO _x Drift, % Span	< 3% of Span

Appendix A

Example Calculations

Example Calculations for Pollutant Emissions

1. Volume of dry gas sampled corrected to standard conditions, **ft³**.
Note: V_m must be corrected for leakage if any leakage rates exceed L_a .

$$V_{mstd} = 17.647 * V_m * \gamma * \frac{P_{bar} + \frac{AH}{13.6}}{T_m, ^\circ R}$$

2. Volume of water vapor at standard conditions, **ft³**.

$$V_{wstd} = 0.04707 * V_{lc} + 0.04715 * V_{sg}$$

3. Moisture content in stack gas, dimension less.

$$B_{ws} = \frac{V_{wstd}}{V_{wstd} + V_{mtd}}$$

4. Dry molecular weight of stack gas, **lb/lb-mole**.

$$M_d = 0.44 * \%CO_2 + 0.32 * \%O_2 + 0.28 * (\%N_2 + \%CO)$$

5. Molecular weight of stack gas, **lb/lb-mole**.

$$M_s = M_d (1 - B_{ws}) + 18 * B_{ws}$$

6. Stack velocity at stack conditions, **f/s**.

$$V_s = 85.49 * C_p * \alpha_{ve} \sqrt{\Delta P} * \sqrt{\frac{T_s, ^\circ R}{P_s * M_s}}$$

7. Stack gas volumetric flow rate at stack conditions, **cfm**.

$$Q_s = 60 * V_s * A_s$$

8. Dry stack gas volumetric flow rate at standard conditions, **cfm**.

$$Q_{sstd} = 17.647 * Q_s * \frac{P_s}{T_s, ^\circ R} * (1 - B_{ws})$$

Example Calculations for Pollutant Emissions

1. Volume of dry gas sampled corrected to standard conditions, **ft³**.
Note: V_m must be corrected for leakage if any leakage rates exceed L_a .

$$V_{mtd} = 17.647 * V_m * \gamma * \frac{P_{bar} + \frac{AH}{13.6}}{T_m, ^\circ R}$$

2. Volume of water vapor at standard conditions, **ft³**.

$$V_{wstd} = 0.04707 * V_{lc} + 0.04715 * V_{sg}$$

3. Moisture content in stack gas, dimension less.

$$B_{ws} = \frac{V_{wstd}}{V_{wstd} + V_{mtd}}$$

4. Dry molecular weight of stack gas, **lb/lb-mole**.

$$M_d = 0.44 * \%CO_2 + 0.32 * \%O_2 + 0.28 * (\%N_2 + \%CO)$$

5. Molecular weight of stack gas, **lb/lb-mole**.

$$M_s = M_d (1 - B_{ws}) + 18 * B_{ws}$$

6. Stack velocity at stack conditions, **f/s**.

$$V_s = 85.49 * C_p * \text{ave}\sqrt{\Delta P} * \sqrt{\frac{T_s, ^\circ R}{P_s * M_s}}$$

7. Stack gas volumetric flow rate at stack conditions, **cfm**.

$$Q_s = 60 * V_s * A_s$$

8. Dry stack gas volumetric flow rate at standard conditions, **cfm**.

$$Q_{sstd} = 17.647 * Q_s * \frac{P_s}{T_s, ^\circ R} * (1 - B_{ws})$$

9. Concentration in gr/dscf.

$$Cs = 0.01543 * \frac{Mn}{Vmstd}$$

10. Concentration in lb/dscf.

$$Cs, lb/dscf = \frac{gr/dscf}{7000}$$

11. Pollutant mass emission rate, lb/hr.

$$Pmr, lb/hr = lb/dscf * Qsstd * 60$$

12. Pollutant mass emission rate, lb/MMBtu.

$$pmr, lb/MMBtu = \frac{pmr, lb/hr}{MMBtu/hr}$$

13. F-factor, Fd.

$$Fd = \frac{10^6 * (3.64 * \%H) + (1.53 * \%C) + (0.57 * \%S) + (0.14 * \%N) - (0.46 * \%O_2)}{GCV (Btu/lb)}$$

14. F-factor, pollutant mass emission rate, lb/MMBtu.

$$= \frac{lb/dscf * Fd * 20.9}{(20.9 - \%O_2)}$$

15. Heat input, MMBtu/hr fuel.

$$= \frac{GVC (Btu/lb) * Feed Rate (lb/hr)}{10^6}$$

16. Heat input, MMBtu/hr, F-factor.

$$= \frac{Qsstd}{Fd} * ((20.9 - \%O_2) + 20.9) * 60$$

17. Volume of dry gas sampled corrected to standard conditions, m³.

$$Vmstd (m^3) = Vmstd (ft^3) * 0.02831$$

18. Concentration in **ug/dscm**.

$$ug/dscm = Target Catch, micrograms / Vmstd (m^3)$$

19. Concentration corrected to 7% oxygen.

$$ug/dscm @ 7\% O_2 = ug/dscm * (20.9-7) / (20.9-measured O_2)$$

20. Concentration, part per million, dry basis.

$$ppm, dry = ppm, wet basis \div (1 - \frac{BWS, \% }{Fd})$$

21. Pollutant Mass Emission Rate, pound per hour.

$$PMR, lb/hr = \frac{ppm, dry * Compound Molecular Weight}{(385.3 \times 10^6)} * dscfm * 60$$

Common Molecular Weights (MW)

Total Gaseous Organic Compound (TGO)	=	44.09
Sulfur Dioxide (SO ₂)	=	64.05
Nitrogen Oxides (NO _x)	=	46.00
Carbon Monoxide (CO)	=	28.01
Oxygen (O ₂)	=	32.00
Carbon Dioxide (CO ₂)	=	44.01

22. Removal Efficiency (RE), percent.

$$RE = (Inlet lb/hr - Outlet lb/hr / Inlet lb/hr) * 100$$

Nomenclature and Dimensions

A_n	=	Cross-sectional area of sampling nozzle, ft²
A_s	=	Cross-sectional area of stack, ft²
B_{ws}	=	Proportion by volume of water vapor in the gas stream, dimensionless
C_p	=	Pitot tube coefficient , dimensionless
C_s	=	Concentration of pollutant matter in stack gas-dry basis, grains per dry standard cubic foot (gr/dscf)
%CO	=	Percent of carbon monoxide by volume, dry basis
%CO₂	=	Percent of carbon dioxide by volume, dry basis
AH	=	Average pressure drop across the sampling meter flow office , inches of water (in. H₂O)
GCV	=	Gross calorific value, Btu/lb
I	=	Percent of isokinetic sampling
L_a	=	Maximum acceptable leakage rate for either a pretest leak check or for a leak check following a component change / equal to 0.020 cubic foot per minute or 4% of the average sampling rate, whichever is less
M_d	=	Dry molecular weight, lb/lb-mole
M_n	=	Total amount of pollutant matter collected, milligrams (mg)
M_s	=	Molecular weight of stack gas (wet basis), lb/lb-mole
%N₂	=	Percent of nitrogen by volume, dry basis
%O₂	=	Percent of oxygen by volume, dry basis
ΔP	=	Velocity head of stack gas, inches of water (in. H₂O)
P_{bar}	=	Barometric pressure, inches of mercury (in. Hg)
P_s	=	Absolute stack gas pressure, inches of mercury (in. Hg)
P_{std}	=	Gas pressure at standard conditions, inches of mercury (29.92 in. Hg)

p_{mr}	=	Pollutant matter emission rate, pounds per hour (lb/hr)
Q_s	=	Volumetric flow rate - wet basis at stack conditions, actual cubic feet per minute (acfm)
Q_{std}	=	Volumetric flow rate - dry basis at stack conditions, actual cubic feet per minute (dscfm)
T_m	=	Average temperature of dry gas meter, °R
T_s	=	Average temperature of stack gas, °R
T_{std}	=	Temperature at standard conditions, 528°R
V_{lc}	=	Total volume of liquid collected in impingers , ml
V_{sg}	=	Weight of moisture collected in silica gel, grams
V_m	=	Volume of dry gas sampled at meter conditions, ft³
V_{mstd}	=	Volume of dry gas sampled at standard conditions, ft³
V_s	=	Average stack gas velocity at stack conditions, ft/s
V_{wstd}	=	Volume of water vapor at standard conditions, scf
γ	=	Dry gas meter calibration factor, dimensionless
Θ	=	Total sampling time, minutes

NOTE: Standard conditions = 68°F and **29.92** in. Hg

Example Calculations for Pollutant Emissions

NIOSH/OSHA and EPA Method 18

1. Sample Volume Standard Liters (Evacuated Tank).

$$Liters_{std} = 17.647 * Total\ Tank\ Volume, L * \left(\frac{P_f}{T_f} - \frac{P_{in}}{T_{in}} \right)$$

P_f = Final tank pressure, in. Hg
P_{in} = Initial tank pressure, in. Hg
T_f = Final tank temperature, °R
T_{in} = Initial tank temperature, °R

2. Sample Volume, Standard Liters (VOST Meter).

$$Volume, Liters_{std} = 17.647 * Total\ Volume, L * Y * \left(\frac{Barometric, in. Hg}{Meter\ Temp., Rankin} \right)$$

3. Concentration, micrograms per liter.

$$pg/l = Total\ pg/sample \div V_{mstd}, liters$$

4. Concentration, part per million, wet basis.

$$ppm, wet = \left(\frac{\mu/l * 24.04\ Q/mole}{Molecular\ Weight\ of\ Analyte} \right)$$

5. Concentration, part per million, dry basis.

$$ppm, dry = ppm, wet \div \left(1 - \frac{H_2O, \%}{100} \right)$$

6. Mass Emission Rate, pound per hour.

$$MR, lb/hr = \left(\frac{ppm, dry * MW, analyte}{385.3 \times 10^6} \right) * dscfm * 60$$

MW	=	Molecular weight of target analyte
ppm	=	Part per million
dscfm	=	Volumetric flow rate, dry standard cubic feet per minute
MR, lb/hr	=	Mass emission rate, pound per hour
Molar Volume	=	385.3 ft³ / lb mole
ppm by volume	=	ft³ / 10⁶ ft³, volume ratio



PACIFIC ENVIRONMENTAL SERVICES, INC.

Project No. 5620.001	Page 1 of 1
Client EQM-Newport-Steel	
Location Newport, Kentucky	

Prepared By R. Holde	Date 10/30/00	Checked By D. Schaffer	Date 10/31	Sheet Title NOx/CO Mass Emission Rates
-------------------------	------------------	---------------------------	---------------	---

10/3/00 1007-1051 = 0.75 hrs
Run No. 1 1629-1928 = 3.00 hrs
Time-weighted averages
NOx Mass Rate,
$$\frac{(15.94 \text{ lb/hr} \times 0.75 \text{ hrs}) + (12.74 \text{ lb/hr} \times 3.00 \text{ hrs})}{3.75 \text{ hrs}} = 13.38 \text{ lb/hr}$$

CO Mass Rate
$$= \frac{(340.0 \text{ lb/hr} \times 0.75 \text{ hrs}) + (204.64 \text{ lb/hr} \times 3.00 \text{ hrs})}{3.75 \text{ hrs}} = 231.7 \text{ lb/hr}$$

10/4/00 0800-0959 = 1.98 hrs
Run No. 2 1045-1159 = 1.23 hrs
NOx Mass Rate,
$$= \frac{(14.23 \text{ lb/hr} \times 1.98 \text{ hrs}) + (8.75 \text{ lb/hr} \times 1.23 \text{ hrs})}{3.21 \text{ hrs}} = 12.13 \text{ lb/hr}$$

CO Mass Rate,
$$= \frac{(277.0 \text{ lb/hr} \times 1.98 \text{ hrs}) + (185.5 \text{ lb/hr} \times 1.23 \text{ hrs})}{3.21 \text{ hrs}} = 241.9 \text{ lb/hr}$$

Run No. 3 1245-1405 = 1.33 hrs
1422-1622 = 2.00 hrs
NOx Mass Rate,
$$= \frac{(20.91 \times 1.33 \text{ hrs}) + (16.61 \times 2.00 \text{ hrs})}{3.33 \text{ hrs}} = 18.33 \text{ lb/hr}$$

CO Mass Rate,
$$= \frac{(275.4 \text{ lb/hr} \times 1.33 \text{ hrs}) + (350.3 \text{ lb/hr} \times 2.00 \text{ hrs})}{3.33 \text{ hrs}} = 320.4 \text{ lb/hr}$$

Summary of Stack Gas Parameters and Test Results

Project

Plant Name & Location

US EPA Test Method 2 - Velocity

Baghouse Inlet

Page 1 of 1

RUN NUMBER RUN DATE RUN TIME	Velocity #2 10/03/2000 1620	Velocity #3 10/03/2000 1920	Velocity #4 10/04/2000 730	Average
MEASURED DATA				
P _{static} Stack Static Pressure, inches H ₂ O	-3.80	-3.60	-3.40	-3.60
P _{bar} Barometric Pressure, inches Hg	29.66	29.66	29.68	29.67
CO ₂ Carbon Dioxide content, % by volum	0.1	0.1	0.1	0.1
O ₂ Oxygen content, % by volume	20.6	20.6	20.6	20.6
N ₂ Nitrogen content, % by volume	79.4	79.4	79.3	79.3
C _p Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Circular Stack? 1=Y, 0=N:	1	1	1	1
As Diameter or Dimensions, inches:	180.00	180.00	180.00	180.00
A Stack Area, f ²	176.7	176.7	176.7	176.71
Temp. °F, WET				0.0
Temp. °F, DRY				0.0
Vapor Pressure Value, in. Hg. (Chart)				0.0000
B _{ws} Moisture, % by volume	2.40	2.40	1.90	2.23
Travers Point Number	Delta P Temp, °F	Delta P Temp, °F	Delta P Temp, °F	
	1.20 136.0	1.60 214.0	1.10 166.0	
	1.20 137.0	1.60 203.0	1.00 173.0	
	1.20 136.0	1.50 193.0	1.20 181.0	
	1.20 140.0	1.60 203.0	1.10 183.0	
	1.30 147.0	1.30 199.0	1.20 196.0	
	1.30 150.0	1.30 195.0	1.20 208.0	
	1.40 154.0	1.40 194.0	1.10 212.0	
	1.30 154.0	1.30 185.0	1.00 210.0	
	1.70 153.0	1.20 194.0	1.60 197.0	
	1.90 154.0	1.30 186.0	1.50 206.0	
	1.70 155.0	1.30 176.0	1.50 191.0	
	1.50 154.0	1.20 175.0	1.30 175.0	
	1.50 152.0	1.20 165.0	1.40 165.0	
	1.50 145.0	1.10 167.0	1.40 156.0	
	1.50 137.0	1.10 161.0	1.30 151.0	
	1.40 133.0	1.30 152.0	1.20 154.0	
Average	1.4250 146.1	1.3313 185.1	1.2563 182.8	
Square Root Average	1.1900	1.1517	1.1181	
CALCULATED DATA				
P _s Stack Pressure, inches Hg	29.38	29.40	29.43	29.40
M _d Molecular Weight (d.b.), lb/lb-mole	28.84	28.84	28.84	28.84
M _w Molecular Weight (w.b.), lb/lb-mole	28.58	28.58	28.63	28.60
V _s Stack Gas Velocity, ft/s	72.6	72.5	70.1	71.7
Q _s Stack Gas Volumetric flow, acfm	769,801	768,488	743,496	760,595
Q _w Stack Gas Volumetric flow, dscfm	642,495	602,864	589,107	611,489
Q _w Stack Gas Volumetric flow, dscmm	18,193	17,071	16,682	17,315

DS
10/31/00

Summary of Stack Gas Parameters and Test Results

Project

Plant Name & Location

US EPA Test Method 2 - Velocity

Baghouse Inlet

Page 1 of 1

RUN NUMBER RUN DATE RUN TIME	Velocity #5 10/04/2000 1115	Velocity #5B/6A 10/04/2000 1115	Velocity #6B 10/04/2000 1510	Average
MEASURED DATA				
P _{static} Stack Static Pressure, inches H ₂ O	-3.40	-3.40	-3.70	-3.50
P _{bar} Barometric Pressure, inches Hg	29.68	29.68	29.68	29.68
CO ₂ Carbon Dioxide content, % by volume	0.1	0.1	0.1	0.1
O ₂ Oxygen content, % by volume	20.6	20.6	20.6	20.6
N ₂ Nitrogen content, % by volume	79.4	79.4	79.3	79.3
C _p Pitot Tube Coefficient	0.84	0.84	0.84	0.84
Circular Stack? I=Y, O=N:	1	1	1	1
As Diameter or Dimensions, inches:	180.00	180.00	180.00	180.00
A Stack Area, ft ²	176.7	176.7	176.7	176.71
Temp. °F, WET				0.0
Temp. °F, DRY				0.0
Vapor Pressure Value, in. Hg. (Chad)				0.0000
B _{ws} Moisture, % by volume	1.90	2.50	2.50	2.30
Travers Point Number	Delta P Temp. °F	Delta P Temp. °F	Delta P Temp. °F	
	1.70 186.0	1.70 186.0	1.40 190.0	
	1.60 205.0	1.60 205.0	1.50 186.0	
	1.60 206.0	1.60 206.0	1.40 182.0	
	1.50 186.0	1.50 186.0	1.60 178.0	
	1.30 178.0	1.30 178.0	1.40 169.0	
	1.30 169.0	1.30 169.0	1.50 164.0	
	1.40 157.0	1.40 157.0	1.40 159.0	
	1.30 154.0	1.30 154.0	1.30 156.0	
	1.20 202.0	1.20 202.0	1.20 141.0	
	1.20 207.0	1.20 207.0	1.30 141.0	
	1.10 220.0	1.10 220.0	1.30 140.0	
	1.20 224.0	1.20 224.0	1.40 139.0	
	1.20 221.0	1.20 221.0	1.30 138.0	
	1.10 213.0	1.10 213.0	1.20 136.0	
	1.20 209.0	1.20 209.0	1.20 132.0	
	1.20 207.0	1.20 207.0	1.30 131.0	
Average	1.3188 196.5	1.3188 196.5	1.3563 155.1	
Square Root Average	1.1458	1.1458	1.1636	
CALCULATED DATA				
P _s Stack Pressure, inches Hg	29.43	29.43	29.41	29.42
M _d Molecular Weight (d.b.), lb/lb-mole	28.84	28.84	28.84	28.84
M _s Molecular Weight (w.b.), lb/lb-mole	28.63	28.57	28.57	28.59
V _s Stack Gas Velocity, ft/s	72.6	72.7	71.5	72.3
Q _s Stack Gas Volumetric flow, acfm	770,057	770,918	758,099	766,358
Q _s Stack Gas Volumetric flow, dscfm	597,374	594,384	623,348	605,035
Q _s Stack Gas Volumetric flow, dscmm	16,916	16,831	17,651	17,133

DS 10/31/10

Summary of Stack Gas Parameters and Test Results

5620.001

Newport Steel-Kentucky

US EPA Test Method 6 or 8 Sulfuric Acid and Acid Mists

Brandt Baghouse Inlet

Page 1 of 2

RUN NUMBER		BI-2	BI-3	BI-4	
RUN DATE		10/03/2000	10/04/2000	10/04/2000	Average
RUN TIME		16451945	0800-1100	1143-1443	
MEASURED DATA					
P _{static}	Stack Static Pressure, inches H ₂ O	-3.80	-3.40	-3.40	-3.53
y	Meter Box Correction Factor	1.001	1.001	1.001	1.001
P _{bar}	Barometric Pressure, inches Hg	29.20	29.68	29.68	29.52
V _m	Sample Volume, ft ³	121.805	120.239	120.635	120.893
Dp ^{1/2}	Average Square Root Dp, (in. H ₂ O) ^{1/2}	1.1900	1.1180	1.1458	1.1513
DH	Avg Meter Orifice Pressure, in. H ₂ O	1.40	1.40	1.40	1.40
T _m	Average Meter Temperature, °F	96	81	89	89
T _s	Average Stack Temperature, °F	167	190	197	185
V _{lc}	Condensate Collected, ml	60.3	47.2	63.4	57.0
CO ₂	Carbon Dioxide content, % by volume	0.1	0.1	0.1	0.1
O ₂	Oxygen content, % by volume	20.6	20.7	20.6	20.6
N ₂	Nitrogen content, % by volume	79.4	79.2	79.3	79.3
C _p	Pitot Tube Coefficient	0.84	0.84	0.84	0.84
	Circular Stack? 1=Y,0=N:	1	1	1	
As	Diameter or Dimensions, inches:	180.00	180.00	180.00	180.00
Q	Sample Run Duration, minutes	180	180	180	180
D _n	Nozzle Diameter, inches	0.000	0.000	0.000	0.000
CALCULATED DATA					
A _n	Nozzle Area, ft ²	0.000000	0.000000	0.000000	0.000000
V _{m(std)}	Standard Meter Volume, ft ³	113.353	116.882	115.558	115.265
V _{m(std)}	Standard Meter Volume, m ³	3.210	3.310	3.272	3.264
Q _m	Average Sampling Rate, dscfm	0.630	0.649	0.642	0.640
P _s	Stack Pressure, inches Hg	28.92	29.43	29.43	29.26
B _{ws}	Moisture, % by volume	2.4	1.9	2.5	2.3
B _{ws(sat)}	Moisture (at saturation), % by volume	39.3	64.5	74.8	59.5
V _{wstd}	Standard Water Vapor Volume, ft ³	2.838	2.222	2.984	2.681
1-B _{ws}	Dry Mole Fraction	0.976	0.981	0.975	0.977
M _d	Molecular Weight (d.b.), lb/lb•mole	28.84	28.84	28.84	28.84
M _s	Molecular Weight (w.b.), lb/lb•mole	28.57	28.64	28.57	28.59
V _s	Stack Gas Velocity, Ws	72.6	71.4	72.1	72.0
A	Stack Area, ft ²	176.7	176.7	176.7	176.71
Q _a	Stack Gas Volumetric flow, acfm	769,145	756,777	764,509	763,477
Q _s	Stack Gas Volumetric flow, dscfm	622,680	593,241	623,348	613,090
Q _s	Stack Gas Volumetric flow, dscmm	17,632	16,799	17,651	17,361
I	Isokinetic Sampling Ratio, %	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!

21

Summary of Stack Gas Parameters and Test Results

5620.001

Newport Steel-Kentucky

US EPA Test Method 6 or 8 Sulfuric Acid and Acid Mists

Brandt Baghouse Inlet

Page 2 of 2

<i>RUN NUMBER</i>	<i>BC2</i>	<i>BC3</i>	<i>BI-4</i>	
<i>RUN DATE</i>	<i>10/03/2000</i>	<i>10/04/2000</i>	<i>10/04/2000</i>	<i>Average</i>
<i>RUN TIME</i>	<i>1645-1945</i>	<i>0800-1100</i>	<i>1143-1443</i>	

EMISSIONS DATA

	<u>Sulfur Dioxide</u>				
	Titrant Normality, N	0.00973	0.00973	0.00973	0.00973
	Titrant Volume, ml	0.8	1.1	1.0	0.9
ppmdv	Parts Per Million, Dry Basis	6.83E-01 ✓	8.83141 ✓	8.04141	7.90E-01
E _{SO2}	Emission Rate, lb/hr	4.24E+00 ✓	5.22E+00 ✓	5.00E+00	4.82E+00

✓
DS

CEM Data Correction Data Sheet

Plant Name:	Newport Steel
Sampling Location:	Baghouse Inlet
Date:	10/3-10/4/00
Project Number:	5620.001
CEM Operator:	G. Gay
Pollutant:	NOx
Molecular Weight:	46.01

Run No.	Start-Stop Time	Raw Data (% or ppm)	Calibration Data			Source Information			Calibration Corrected Data (% or ppm)	Mass Emission Rate (lb/hr)	Steel Production, tons per hour	Mass Emission Rate lbs/ton steel
			Cma	Co	Cm	Stack Flow (dscfm)	Fd Factor (dscfl MMBtu)	Stack 0 2 Conc. (%)				
1	1007-1051	4.1	49.51	0.41	51.4	622,680			3.6	15.94		
2	1629-1928	3.2	49.5	0.2	52.2	622,680			2.9	12.74		
3	0800-0959	3.5	49.5	0.1	50.1	593,241			3.3	14.23		
4	1045-1159	2.2	49.5	0.2	49.2	593,241			2.1	8.75		
5	1245-1405	4.8	49.5	0.2	49.2	623,348			4.7	20.91		
6	1422-1622	3.8	49.5	0.2	48.6	623,348			3.7	16.61		
7												
8												
9												
10												
11												
12												
Average									3.4	14.86		

Calibration Error Correction

$$C_{gas} = (C_{obs} - C_o) * (C_{ma} / (C_m - C_o))$$

Oxygen Corrected Data

$$C = C_{gas} * ((20.9 - O_2 \text{ fact}) / (20.9 - O_2 \text{ obs}))$$

Mass Emission Rate (lb/hr)

$$E(\text{lb/hr}) = C_{gas} * MW_{gas} * Q_s(\text{dscfm}) * 60 / 385300000$$

Mass Emission Rate (lb/MMBtu)

$$E(\text{lb/MMBtu}) = C_{gas} * MW_{gas} * F_d * (20.9 / (20.9 - O_2 \text{ obs})) / 385300000$$

Pollutant	MWgas
CO	28.01
Propane	44.10
NOx	46.01
SO2	64.06

CEM Data Correction Data Sheet

Plant Name:	Newport Steel
Sampling Location:	Baghouse Inlet
Date:	1013-1014100
Project Number:	5620.001
CEM Operator:	G. Gay
Pollutant:	CO
Molecular Weight:	28.01

Run No.	Start-Stop Time	Raw Data (ppm)	Calibration Data			Source Information		Stack O ₂ Conc. (%)	Calibration Corrected Data (% or ppm)	Mass Emission Rate (lb/hr)	Steel Production tons per hour	Mass Emission Rate lbs/ton steel
			Cma	Co	Cm	(dscfm)	MMBtu)					
1	1007-1051	130.7	600.6	4.5	610.0	622,680			125.2	340.01		
1	1629-1928	77.5	600.6	1.0	610.8	622,680			75.3	204.64		
2	0800-0959	109.2	600.6	1.1	607.9	593,241			107.0	276.99		
2	1045-1159	74.1	600.6	1.1	613.0	593,241			71.7	185.52		
3	1245-1405	104.1	600.6	1.1	612.0	623,348			101.3	275.44		
3	1422-1622	132.4	600.6	0.5	615.4	623,348			128.8	350.27		
7												
8												
9												
10												
11												
12												
Average									101.6	#REF!	272.15	

Calibration Error Correction

$$C_{gas} = (C_{obs} - C_o) * (C_{ma} / (C_m - C_o))$$

Oxygen Corrected Data

$$C = C_{gas} * ((20.9 - O_2 \text{ fact}) / (20.9 - O_2 \text{ obs}))$$

Mass Emission Rate (lb/hr)

$$E(\text{lb/hr}) = C_{gas} * MW_{gas} * Q_s(\text{dscfm}) * 60 / 385300000$$

Mass Emission Rate (lb/MMBtu)

$$E(\text{lb/MMBtu}) = C_{gas} * MW_{gas} * F_d * (20.9 / (20.9 - O_2 \text{ obs})) / 385300000$$

Pollutant	MW _{gas}
CO	28.01
Propane	44.10
NO _x	46.01
SO ₂	64.06

Appendix B

Field Data

TRAVERSE POINT LOCATION FOR CIRCULAR DUCTS

Plant: Newport Steel

Date: 10, 2 00

Sampling Location: Brault Bayhouse Inlet

Inside of Far Wall to Outside of Nipple: _____

Inside of Near Wall to Outside of Nipple (Nipple Length): *

Stack I.O.: 15' - 180"


Distance Downstream from Flaw Disturbance (Distance B):

150" inches / Stack I.D. = 10.0 dd

Distance Upstream from Fbw Disturbance (Distance A):

19' inches / Stack I.D. = 1.3 dd

Calculated By: RH/10/10



Schematic of
Sampling Location

* marked for inside of post

Traverse Point Number	Fraction of Length	Length (inches)	Product of Columns 2 & 3 (To nearest 1/8")	Nipple Length (inches)	Traverse Point Location (Sum of Col. 4 & 5)
1	0.032	180"	5.76"	N/A	5.76"
2	0.105		18.9"		18.9"
3	0.194		34.92"		34.92"
	0.323		58.14"		58.14"
5	0.677		121.86"		121.86"
6	0.806		145.08"		145.04
7	0.895		161.11"		161.11"
8	0.969	*	174.24"	↓	174.24"

FIELD DATA SHEET

Plant: Newport Steel
 Sampling Location: Brant Bayshore Inlet
 Run Number: BA-2 Date: 10/3/00
 Pretest Leak Rate: 0.004 cfm @ 15 in. Hg.
 Pretest Leak Check: Pitot: ☒ Orsat: ☒
 Sample Type: SO₂ Operator: BB
 Pbar: 29.20 Ps: _____
 CO₂: 0 O₂: 20
 Probe Length/Type: 7' Glass Pitot #: _____
 Stack Diameter: 100" As: _____
 Nozzle ID: _____ Thermocouple #: _____
 Assumed Bws: _____ Filter #: _____
 Meter Box #: -1 Y: 1.001 ΔH@: 1795
 Post-Test Leak Rate: 0.004 cfm @ 15 in. Hg.
 Post-Test Leak Check: Pitot: _____ Orsat: _____

Traverse Point Number	Sampling Time (min)	Clock Time (24-hour clock)	Gas Meter Reading (Nm) ft ³	Velocity Head (Δp) in H ₂ O	Orifice Pressure Differential (Δh) in H ₂ O		Stack Temp. (T _s)	Temperature °F		Impinger Temp. °F	Dry Gas Meter Temp.		Pump Vacuum (in. Hg)	
					Desired	Actual		Probe	Filter		Inlet (T _m in °F)	Outlet (T _m out °F)	Inlet	Outlet
			137.243		1.4	1.4		256	256	58	94	93	3 1/2	
	0	1645	137.243		1.4	1.4		253	257	52	94	93	4	
	10	1655	143.94		1.4	1.4		253	258	50	97	93	4	
	20	1705	150.71		1.4	1.4		257	258	52	98	94	4	
	30	1715	157.49		1.4	1.4		255	259	52	99	94	4	
	40	1725	164.26		1.4	1.4		254	259	53	99	94	4	
	50	1735	171.035		1.4	1.4		255	259	54	97	94	4	
	60	1745	177.83		1.4	1.4		255	257	55	98	94	4 1/2	
	70	1755	184.6		1.4	1.4		254	255	55	98	94	4 1/2	
	80	1805	191.38		1.4	1.4		255	256	57	98	94	4 1/2	
	90	1815	198.24		1.4	1.4		257	260	59	98	94	4 1/2	
	100	1825	205.1		1.4	1.4		255	253	53	98	93	4 1/2	
	110	1835	211.89		1.4	1.4		256	257	53	98	93	5	
	120	1845	218.685		1.4	1.4		254	257	53	98	93	5	
	130	1855	225.4		1.4	1.4		255	256	53	98	93	6	
	140	1905	232.26		1.4	1.4		255	261	54	98	94	6.7	
	150	1915	238.96		1.4	1.4		256	255	56	98	94	7.2	
	160	1925	245.6		1.4	1.4		256	260	57	97	93	7.5	
	170	1935	252.37		1.4	1.4		253	258	59	97	93	8	
	180	1945	259.048		1.4	1.4								
				</										

NUM=	121.805	$\sqrt{\Delta p}$ =		$\overline{\Delta H}$ =	1.4	T_s =		PRGE	259.248	$\overline{T_m}$ =	96.9208	96
									269.225			



SAMPLE RECOVERY DATA

PLANT Newport Steel Run No. BI-2

DATE 10/3/00 Sample Box No. RN2 Job No. 5620.001

SAMPLE LOCATION Brundt Bayshore Tule Filter No. —

TRAIN PREPARER GG/BB

SAMPLE RECOVERY PERSON R Kall

COMMENTS SO₂ train

FRONT HALF

Acetone Liquid
Container No. — Level Marked — Sealed —

Filter
Container No. — Sealed —

Description of Filter —

Samples Stored and Locked —

BACK HALF/MOISTURE

Container No. —

Liquid Level Marked — Sealed —

IMP. NO.	CONTENTS	INITIAL VOL. (ml)	WEIGHT(grams)		
			INITIAL	FINAL	NET
1	IPA	100	530.1 ^{590.5}	551.7	-38.8
2	H ₂ O ₂	100	713.2	745.6	32.4
3	H ₂ O ₂	100	682.8	700.1	17.3
4	S/O	8250	821.3 ^{821.3}	866.9	49.4
5			817.5		
6					
'TOTAL					60.3

Description of Impinger Catch: clear

TUP.

STDe

Q_s std = ~~603,241~~ decim 603,307.72

21

GAS VELOCITY AND VOLUMETRIC FLOW RATE

FIELD DATA SHEET

Plant: Wingport Spool
Sampling Location: B3 north Bayshore
Run Number: BZ-3 Date: 10/4/50
Pretest Leak Rate: 2004 cfm @ 15 in. Hg.
Pretest Leak Check: Pilot: ✓ Orsat: ✓

Sample Type: 502 Operator: PS
Pbar: 29.68 Ps: _____
CO2: 0.1 O2: 20.7 _____
Probe Length/Type: 7' Glass Pitot #: _____
Stack Diameter: 180' As: _____

Nozzle ID: — Thermocouple #: —
Assumed Bws: — Filter #: —
Meter Box #: 1 Y: 1.001 $\Delta H@$: 1.795
Post-Test Leak Rate: $\frac{1.001}{\text{Pressure}}$ cfm @ 12 in. Hg
Post-Test Leak Check: Pitot: — Orsat: —

PLATE WITH
BROWN DUST
REMOVED.

[illegible]

Page- 390.970
401.314

上

40

170239

Tim



SAMPLE RECOVERY DATA

PLANT Newport Steel Run No. B2-3
DATE 10/4/00 Sample Box No. N9 Job No. 5620.001
SAMPLE LOCATION Bouldt Bayhead Filter No. —
TRAIN PREPARER GGIBB
SAMPLE RECOVERY PERSON RLK
COMMENTS S02 train

FRONT HALF

Acetone Liquid
Container No. _____ Level Marked _____ Sealed _____

Filter
Container No. _____ Sealed _____

Description of Filter _____

Samples Stored and Locked _____

BACK HALF/MOISTURE

Container No. _____

Liquid Level Marked _____ Sealed _____

IMP. NO.	CONTENTS	INITIAL VOL (ml)	WEIGHT (grams)		
			INITIAL	FINAL	NET
1	IPA	100	614.6	566.2	-48.4
2	H ₂ O ₂	100	731.2	759.1	27.9
3	H ₂ O ₂	100	611.4	618.0	6.6
4	S/G	250	832.5	893.6	61.1
5					
6					
TOTAL					47.2

Description of Impinger Catch: _____

FIELD DATA SHEET

Plant: Newport Steel
Sampling Location: Brandt Pyroline Inlet
Run Number: BZ-4 Date: 10/4/00
Pretest Leak Rate: 0.006 cfm @ 15 in. Hg.
Pretest Leak Check: Pitot: — Orsat: —

Sample Type: SO₂ Operator: BB
Pbar: 29.68 Ps: _____
CO₂: 0 O₂: 21
Probe Length/Type: 7' Glass Pitot #: _____
Stack Diameter: 180" As: _____

Nozzle ID: _____ Thermocouple #: _____
Assumed Bws: _____ Filter #: _____
Meter Box #: 1 Y: 1.001 ΔH @: 1.795
Post-Test Leak Rate: 0.01 cfm @ 16 in. Hg.
Post-Test Leak Check: Pitot: _____ Orsat: _____

Traverse Point Number	Sampling Time (min)	Clock Time (24-hour clock)	Gas Meter Reading (Vn) ft ³	Velocity Head (Δp) in H ₂ O	Orifice Pressure Differential (ΔH) in H ₂ O		Stack Temp. (Ts)	Temperature °F		Impinger Temp. °F	Dry Gas Meter Temp.		Pump Vacuum (in. Hg)
					Desired	Actual		Probe	Filter		Inlet (Tm in °F)	Outlet (Tm out °F)	
			401.524										
	0	1143	401.524		1.40	1.40		255	247	58	84.	84.	4 1/2
	10	1153	408.2		1.40	1.40		255	259	52	86.	83.	5
	20	1203	414.88		1.40	1.40		254	258	55	88.	83.	5
	30	1213	421.6		1.40	1.40		254	259	55	88.	84.	5 1/2
	40	1223	428.25		1.40	1.40		255	258	55	89.	84.	6
	50	1233	434.93		1.40	1.40		255	256	57	89.	84.	7
	60	1243	441.6		1.40	1.40		255	257	58	89.	84.	7.5
	70	1253	448.32		1.40	1.40		255	260	59	90.	85.	7.8
	80	1303	454.95		1.40	1.40		255	258	50	89.	85.	8
	90	1313	461.7		1.40	1.40		256	259	53	90.	85.	9
	100	1323	468.495		1.40	1.40		255	257	55	90.	85.	9
	110	1333	475.045		1.40	1.40		255	256	57	91.	86.	9.8
	120	1343	481.666		1.40	1.40		256	259	60	92.	87.	11
	130	1353	488.64		1.40	1.40		255	239	55	93.	88.	4.5
	140	1403	495.382		1.40	1.40		254	252	57	94.	89.	5
	150	1413	502.16		1.40	1.40		256	257	61	96	90.	5.2
	160	1423	508.946		1.40	1.40		255	259	63	98.	91.	5.5
	170	1433	515.6		1.40	1.40		255	256	64	99	92.	6.5
	180	1443	522.393		1.40	1.40		255	260	67	100	94.	7

ILTD KCH

 ΔV_i
$$\overline{AH} = 1.4$$

Figure 1

PAGE FOR 11 MINUTES. $\overline{T_m} = 8.9$



SAMPLE RECOVERY DATA

PLANT Newport Steel Run No. BT-4
DATE 6/4/00 Sample Box No. N-4 Job No. 5620.001
SAMPLE LOCATION Brands Bushouse Inlet Filter No. —
TRAIN PREPARER rk
SAMPLE RECOVERY PERSON rh
COMMENTS Spz Train

FRONT HALF

Acetone Liquid
Container No. _____ Level Marked _____ Sealed _____

Filter
Container No. _____ Sealed _____

Description of Filter _____

Samples Stored and Locked _____

BACK HALF/MOISTURE

Container No. _____

Liquid Level Marked _____ Sealed _____

IMP. NO.	CONTENTS	INITIAL VOL (ml)	WEIGHT (grams)		
			INITIAL	FINAL	NET
1	IPA	100	637.5	605.9	-31.6
2	H ₂ O ₂	100	627.9	660.1	32.2
3	H ₂ O ₂	100	643.1	663.1	20.0
4	CG	250	790.2	833.0	42.8
5					
6					
TOTAL					63.4

GAS VELOCITY AND VOLUMETRIC FLOW RATE

10/3/00 Newport Steel - O-set Data

Run No. BI-1 Page 1 1014-1114

CO₂

O₂

1 0.0

$$20.6 - 0.0 = 20.6$$

* VOIDED Run

2 0.0

$$20.8 - 0.0 = 20.8$$

0.0

$$20.7 - 0.0 = 20.7$$

Run No. BI-2 Page 2 1645-1945

CO₂

O₂

1 0.1

$$20.6 = 20.5$$

2 0.1

$$20.7 = 20.6$$

Run No. BI-3

10/4/00

0800-1100

CO₂

O₂

1 0.1

$$20.7 = 20.6$$

2 0.1

$$20.7 = 20.6$$

Run No. BI-4

1143-1443

CO₂

O₂

1 0.1

$$20.7 = 20.6$$

2 0.1

$$20.6 = 20.5$$



METHOD 6 SULFUR DIOXIDE ANALYTICAL DATA

Plant: Newport Steel Date: 10/24/00
Sample Location: Brandt Baghouse Filter Analyst: Ron Kohle

STANDARDIZATION OF TITRANT

	<u>BaClO₄)₂</u>		Volume of Titrant		Normality of Titrant
Titrant Used	<u>0.0100</u>	1	<u>20.6</u> ml		<u>0.00971</u> N
Normality of H ₂ SO ₄ Standard	<u>0.0100</u>	2	<u>20.6</u> ml		<u>0.00971</u> N <u>0.00973</u> N
Volume of Standard	<u>20 ml</u>	3	<u>20.5</u> ml		<u>0.00976</u> N (Avg., N ₂)

CONTROL SAMPLE ANALYSIS

			Volume of Titrant	
Normality of (NH ₄) ₂ SO ₄	(N ₁)	1	_____ ml	
Volume of (NH ₄) ₂ SO ₄	(V ₁)	2	_____ ml	_____ ml
Meq ₁ (NH ₄) ₂ SO ₄	(N ₁ × V ₁)	3	_____ ml	(Avg., V ₂)
Meq ₂ (NH ₄) ₂ SO ₄	(N ₂ × V ₂)			

$\frac{\text{Meq}_1}{\text{Meq}_2} = \text{_____} = 0.95 \text{ to } 1.05$

Run Number	Total Volume of Sample	Sample Aliquot	Volume of Titrant, Vt, ml			
			1st Titration	2nd Titration	3rd Titration	Average
BLANK		<u>20 ml</u>	<u>0.05</u>	<u>0.05</u>		<u>0.05</u>
AUDIT NO.						
B-2	<u>500</u>	<u>20 ml</u>	<u>0.80</u>	<u>0.80</u>		<u>0.80</u>
B-3	<u>500</u>	<u>20 ml</u>	<u>1.0</u>	<u>1.1</u>		<u>1.05</u>
B-4	<u>500</u>	<u>20 ml</u>	<u>1.0</u>	<u>0.9</u>		<u>0.95</u>

$$C_{\text{SO}_2} (\text{ppm, dry}) = \frac{(424.5)(V_t - V_{tb})(N)(V_{\text{soln}})}{(V_{\text{mstd.}})(V_a)}$$

$$E_{\text{SO}_2} (\text{lb/hr}) = \frac{(C_{\text{SO}_2})(\text{MW}_{\text{SO}_2})}{(385.3 \times 10^6)} (Q_{\text{sstd.}})(60)$$

Signature of Analyst: Ron Kohle

Signature of Reviewer: D. Schupp

Appendix C

Analyzer Data

CEM CALIBRATION DATA

Plant Name **Newport Steel**
 Sampling Location **Baghouse Inlet**
 Date **10/03/2000**
 Run Number **1**
 Start Time **1007**
 Stop Time **1051**

Plant Rep. **Jennifer Mcdaniels**
 Team Leader **Ron Kolde**
 CEM Operator **Gary Gay**
 Project Number **5620.001**

	Analyzer Number	Analyzer Span
CO		1015
CO2		25
O2		25
THC		100
NOx		100
ML THC		5000

	Calibration Gas Specification (% of Span)	CALIBRATION ERROR CHECK				SYSTEM CAL CHECK					Calibration Correction Factors
		Calibration Value (% or ppm)	Cylinder Number (1)	Analyzer Calibration Response	Difference (% of Span)	PRETEST		POST TEST			
						System Response	Syst. Bias (% of Span)	System Response	Syst. Bias (% of Span)	Drift (% of Span)	
CO Zero	0	0		4.6	0.5	4.5	4.5	4.5	0.0	0.0	Co=4.5
CO Low	~30	300.2		322.2	2.2						
CO Mid	~60	600.6		611.7	1.1	611.7	0.0	608.2	-0.3	-0.3	Cm=610.0
CO High	80-100 (2)	896.4		899.2	0.3						
CO2 Zero	0	0		1.8	7.2	1.8	0.0	1.8	0.0	0.0	Co=1.8
CO2 Low	NR										
CO2 Mid	40-60	10.12		11.1	3.9	11.1	0.0	11.1	0.0	0.0	Cm=11.1
CO2 High	80-100	19.97		20	0.1						
O2 Zero	0	0		0	0.0	0.1	0.4	0.1	0.4	0.0	Co=0.1
O2 Low	NR										
O2 Mid	40-60	12.91		12.9	0.0	12.9	0.0	12.8	-0.4	-0.4	Cm=12.9
O2 High	80-100	20.9		20.9	0.0						
THC Zero	0	0		0				0.1		0.1	
THC Low	25-35	29.76		31	4.2						
THC Mid	45-55	49		51.2	4.5			50.3		-0.9	
THC High	80-90	84.55		84.7							
NOx Zero	0	0		0	0.0	0.14	0.1	0.7	0.7	0.6	Co=0.4
NOx Low	20-30 (3)										
NOx Mid	45-55	49.49		50.27	0.8	50.27	0.0	52.5	2.2	2.2	Cm=51.4
NOx High	80-90	90.7		90.79	0.1						
ML THC Zer	0	0		899.2				31		-17.4	
ML THC Lo	25-35	867.9		850	-2.1						
ML THC Mi	45-55	2418		2436	0.7			2390		-0.9	
ML THC Hi	80-90	4467		4475							

CEM CALIBRATION DATA

Plant Name
Sampling Location
Date
Run Number
Start Time
Stop Time

Newport Steel
Baghouse Inlet
10/03/00
1
1629
1928

Plant Rep.
Team Leader
CEM Operator
Project Number

Jennifer Mcdaniels
Ron Kolde
Gary Gay
5620.001

Analyzer	Analyzer Number	Analyzer Span
CO		1015
CO2		25
O2		25
THC		100
NOx		100
SO2		5000

CALIBRATION ERROR CHECK			SYSTEM CAL CHECK				POST TEST		Calibration Correction Factors
Calibration Gas Specification (% of Span)	Calibration Value (% or ppm)	Cylinder Number (1)	Analyzer Calibration Response	Difference (% of Span)	PRETEST System Response	Syst. Bias (% of Span)	System Response	Syst. Bias (% of Span)	
CO Zero	0		4.6	0.5	1	-0.4	1	-0.4	Co=1.0
CO Low	~30		322.2	2.2					
CO Mid	~60		611.7	1.1	611.4	0.0	610.2	-0.1	Cm=610.8
CO High	80-100 (2)		899.2	0.3					
CO2 Zero	0		1.8	7.2	1.8	0.0	1.8	0.0	Co=1.8
CO2 Low	NR								
CO2 Mid	40-60		11.1	3.9	11.1	0.0	11.1	0.0	Cm=11.1
CO2 High	80-100		20	0.1					
O2 Zero	0		0	0.0	0.1	0.4	0	0.0	Co=0.1
O2 Low	NR								
O2 Mid	40-60		12.9	0.0	12.8	-0.4	12.8	-0.4	Cm=12.8
O2 High	80-100		20.9	0.0					
THC Zero	0		0				0.8	0.8	
THC Low	25-35		31	4.2					
THC Mid	45-55		51.2	4.5			49	-2.2	
THC High	80-90		84.7						
NOx Zero	0		0	0.0	0.2	0.2	0.2	0.2	Co=0.2
NOx Low	20-30 (3)								
NOx Mid	45-55		50.27	0.8	51.9	1.6	52.5	2.2	Cm=52.2
NOx High	80-90		90.79	0.1					
ML THC Zer	0		899.2		31		10	-17.8	
ML THC Lo	25-35		867.9	-2.1					
ML THC Mi	45-55		2418	0.7	2390		2455	0.4	
ML THC Hi	80-90		4467						

CEM CALIBRATION DATA

Plant Name
Sampling Location
Date
Run Number
Start Time
Stop Time

Newport Steel
Baghouse Inlet
10/04/00
2
0800
0959

Plant Rep.
Team Leader
CEM Operator
Project Number

Jennifer Mcdaniels
Ron Kolde
Gary Gay
5620.001

CO
CO2
O2
THC
NOx
SO2

Analyzer Number	Analyzer Span
	1015
	25
	25
	100
	100
	5000

	Calibration Gas Specification (% of Span)	CALIBRATION ERROR CHECK				SYSTEM CAL CHECK					Calibration Correction Factors
		Calibration Value (% or ppm)	Cylinder Number (1)	Analyzer Calibration Response	Difference (% of Span)	PRETEST		POST TEST			
						System Response	Syst. Bias (% of Span)	System Response	Syst. Bias (% of Span)	Drift (% of Span)	
CO Zero	0	0		1.1	0.1	1.1	0.0	1	0.0	0.0	Co=1.1
CO Low	~30	300.2		319.8	1.9						
CO Mid	~60	600.6		601.7	0.1	601.7	0.0	614	1.2	1.2	Cm=607.9
CO High	80-100 (2)	896.4		870.8	-2.5						
CO2 Zero	0	0		1.8	7.2	1.8	0.0	1.8	0.0	0.0	Co=1.8
CO2 Low	NR										
CO2 Mid	40-60	10.12		11.1	3.9	11.1	0.0	11	-0.4	-0.4	Cm=11.1
CO2 High	80-100	19.97		20	0.1						
O2 Zero	0	0		0	0.0	0	0.0	0	0.0	0.0	Co=0.0
O2 Low	NR										
O2 Mid	40-60	12.91		12.9	0.0	12.8	-0.4	12.7	-0.8	-0.4	Cm=12.8
O2 High	80-100	20.9		20.9	0.0						
THC Zero	0	0		0				0.3		0.3	
THC Low	25-35	29.76		31	4.2						
THC Mid	45-55	49		51.2	4.5			49.5		-1.7	
THC High	80-90	84.55		84.7							
NOx Zero	0	0		0.12	0.1	0.12	0.0	0.12	0.0	0.0	Co=0.1
NOx Low	20-30 (3)										
NOx Mid	45-55	49.49		51.1	1.6	51.06	0.0	49.1	-2.0	-2.0	Cm=50.1
NOx High	80-90	90.7		90.96	0.3						
ML THC Zer	0	0		899.2		10		24		-17.5	
ML THC Lo	25-35	867.9		850	-2.1						
ML THC Mi	45-55	2418		2436	0.7	2455		2510		1.5	
ML THC Hi	80-90	4467		4475							

CEM CALIBRATION DATA

Plant Name
Sampling Location
Date
Run Number
Start Time
Stop Time

Newport Steel
Baghouse Inlet
10/04/00
2B
1045
1159

Plant Rep.
Team Leader
CEM Operator
Project Number

Jennifer Mcdaniels
Ron Kolde
Gary Gay
5620.001

Analyzer Number	Analyzer Span
CO	1015
CO2	25
O2	25
THC	100
NOx	100
SO2	5000

	Calibration Gas Specification (% of Span)	CALIBRATION ERROR CHECK				SYSTEM CAL CHECK					Calibration Correction Factors
		Calibration Value (% or ppm)	Cylinder Number (1)	Analyzer Calibration Response	Difference (% of Span)	PRETEST		POST TEST			
						System Response	Syst. Bias (% of Span)	System Response	Syst. Bias (% of Span)	Drift (% of Span)	
CO Zero	0	0		1.1	0.1	1	0.0	1.1	0.0	0.0	Co=1.1
CO Low	~30	300.2		319.8	1.9						
CO Mid	~60	600.6		601.7	0.1	614	1.2	612	1.0	-0.2	Cm=613.0
CO High	80-100 (2)	896.4		870.8	-2.5						
CO2 Zero	0	0		1.8	7.2	1.8	0.0	1.8	0.0	0.0	Co=1.8
CO2 Low	NR										
CO2 Mid	40-60	10.12		11.1	3.9	11	-0.4	11	-0.4	0.0	Cm=11.0
CO2 High	80-100	19.97		20	0.1						
O2 Zero	0	0		0	0.0	0	0.0	0	0.0	0.0	Co=0.0
O2 Low	NR										
O2 Mid	40-60	12.91		12.9	0.0	12.7	-0.8	12.8	-0.4	0.4	Cm=12.8
O2 High	80-100	20.9		20.9	0.0						
THC Zero	0	0		0				0		0.0	
THC Low	25-35	29.76		31	4.2						
THC Mid	45-55	49		51.2	4.5			49.2		-2.0	
THC High	80-90	84.55		84.7							
NOx Zero	0	0		0.12	0.1	0.12	0.0	0.2	0.1	0.1	Co=0.2
NOx Low	20-30 (3)										
NOx Mid	45-55	49.49		51.1	1.6	49.1	-2.0	49.3	-1.8	0.2	Cm=49.2
NOx High	80-90	90.7		90.96	0.3						
ML THC Zer	0	0		899.2		24		25		-17.5	
ML THC Lo	25-35	867.9		850	-2.1						
ML THC Mi	45-55	2418		2436	0.7	2510		2550		2.3	
ML THC Hi	80-90	4467		4475							

CEM CALIBRATION DATA

Plant Name
Sampling Location
Date
Run Number
Start Time
Stop Time

Newport Steel
Baghouse Inlet
10/04/00
3
1245
1405

Plant Rep.
Team Leader
CEM Operator
Project Number

Jennifer Mcdaniels
Ron Kolde
Gary Gay
5620.001

Analyzer	Analyzer
Number	Span
CO	1015
CO2	25
O2	25
THC	100
NOx	100
SO2	5000

	Calibration Gas Specification (% of Span)	CALIBRATION ERROR CHECK				SYSTEM CAL CHECK					Calibration Correction Factors
		Calibration Value (% or ppm)	Cylinder Number (1)	Analyzer Calibration Response	Difference (% of Span)	PRETEST		POST TEST			
						System Response	Syst. Bias (% of Span)	System Response	Syst. Bias (% of Span)	Drift (% of Span)	
CO Zero	0	0		1.1	0.1	1.1	0.0	1	0.0	0.0	Co=1.1
CO Low	~30	300.2		319.8	1.9						
CO Mid	~60	600.6		601.7	0.1	612	1.0	612	1.0	0.0	Cm=612.0
CO High	80-100 (2)	896.4		870.8	-2.5						
CO2 Zero	0	0		1.8	7.2	1.8	0.0	2	0.8	0.8	Co=1.9
CO2 Low	NR										
CO2 Mid	40-60	10.12		11.1	3.9	11	-0.4	12.4	5.2	5.6	Cm=11.7
CO2 High	80-100	19.97		20	0.1						
O2 Zero	0	0		0	0.0	0	0.0	0	0.0	0.0	Co=0.0
O2 Low	NR										
O2 Mid	40-60	12.91		12.9	0.0	12.8	-0.4	12.9	0.0	0.4	Cm=12.9
O2 High	80-100	20.9		20.9	0.0						
THC Zero	0	0		0				0.3		0.3	
THC Low	25-35	29.76		31	4.2						
THC Mid	45-55	49		51.2	4.5			49.9		-1.3	
THC High	80-90	84.55		84.7							
NOx Zero	0	0		0.12	0.1	0.2	0.1	0.12	0.0	-0.1	Co=0.2
NOx Low	20-30 (3)										
NOx Mid	45-55	49.49		51.1	1.6	49.3	-1.8	49.1	-2.0	-0.2	Cm=49.2
NOx High	80-90	90.7		90.96	0.3						
ML THC Zer	0	0		899.2		25					
ML THC Lo	25-35	867.9		850	-2.1						
ML THC Mi	45-55	2418		2436	0.7	2550					
ML THC Hi	80-90	4467		4475							

12

CEM CALIBRATION DATA

Plant Name
 Sampling Location
 Date
 Run Number
 Start Time
 Stop Time

Newport Steel
Baghouse Inlet
10/04/00
3
1422
1621

Plant Rep.
 Team Leader
CEM Operator
 Project Number

Jennifer Mcdaniels
Ron Kolde
Gary Gay
5620.001

	Analyzer Number	Analyzer Span
CO		1015
CO2		25
O2		25
THC		100
NOx		100
SO2		5000

	Calibration Gas Specification (% of Span)	CALIBRATION ERROR CHECK				SYSTEM CAL CHECK					Calibration Correction Factors
		Calibration Value (% or ppm)	Cylinder Number (1)	Analyzer Calibration Response	Difference (% of Span)	PRETEST		POST TEST			
						System Response	Syst. Bias (% of Span)	System Response	Syst. Bias (% of Span)	Drift (% of Span)	
CO Zero	0	0		1.1	0.1	1	0.0	0.04	-0.1	-0.1	Co=0.5
CO Low	~30	300.2		319.8	1.9						
CO Mid	~60	600.6		601.7	0.1	612	1.0	618.7	1.7	0.7	Cm=615.4
CO High	80-100 (2)	896.4		870.8	-2.5						
CO2 Zero	0	0		1.8	7.2	2	0.8	2	0.8	0.0	Co=2.0
CO2 Low	NR										
CO2 Mid	40-60	10.12		11.1	3.9	12.4	5.2	12.5	5.6	0.4	Cm=12.5
CO2 High	80-100	19.97		20	0.1						
O2 Zero	0	0		0	0.0	0	0.0	0	0.0	0.0	Co=0.0
O2 Low	NR										
O2 Mid	40-60	12.91		12.9	0.0	12.9	0.0	12.9	0.0	0.0	Cm=12.9
O2 High	80-100	20.9		20.9	0.0						
THC Zero	0	0		0				0.5		0.5	
THC Low	25-35	29.76		31	4.2						
THC Mid	45-55	49		51.2	4.5			49.8		-1.4	
THC High	80-90	84.55		84.7							
NOx Zero	0	0		0.12	0.1	0.12	0.0	0.2	0.1	0.1	Co=0.2
NOx Low	20-30 (3)										
NOx Mid	45-55	49.49		51.1	1.6	49.1	-2.0	48.1	-3.0	-1.0	Cm=48.6
NOx High	80-90	90.7		90.96	0.3						
ML THC Zer	0	0		899.2		0					
ML THC Lo	25-35	867.9		850	-2.1						
ML THC Mi	45-55	2418		2436	0.7	0					
ML THC Hi	80-90	4467		4475							

CEM CALIBRATION DATA

Plant Name
Sampling Location
Date
Run Number
Start Time
Stop Time

Newport Steel
Baghouse Inlet
10/04/00
4

Plant Rep.
Team Leader
CEM Operator
Project Number

Jennifer Mcdaniels
Ron Kolde
Gary Gay
5620.001

	Analyzer Number	Analyzer Span
CO		1015
CO2		25
O2		25
THC		100
NOx		100
SO2		5000

	Calibration Gas Specification (% of Span)	CALIBRATION ERROR CHECK				SYSTEM CAL CHECK					Calibration Correction Factors
		Calibration Value (% or ppm)	Cylinder Number (1)	Analyzer Calibration Response	Difference (% of Span)	PRETEST System Response	Syst. Bias (% of Span)	POST TEST System Response	Syst. Bias (% of Span)	Drift (% of Span)	
CO Zero	0	0		1.1	0.1	0.04	-0.1				
CO Low	~30	300.2		319.8	1.9						
CO Mid	~60	600.6		601.7	0.1	618.7	1.7				
CO High	80-100 (2)	896.4		870.8	-2.5						
CO2 Zero	0	0		1.8	7.2	2	0.8				
CO2 Low	NR										
CO2 Mid	40-60	10.12		11.1	3.9	12.5	5.6				
CO2 High	80-100	19.97		20	0.1						
O2 Zero	0	0				0	#VALUE!				
O2 Low	NR										
O2 Mid	40-60	12.91		12.9	0.0	12.9	0.0				
O2 High	80-100	20.9		20.9	0.0						
THC Zero	0	0									
THC Low	25-35	29.76		31	4.2						
THC Mid	45-55	49		51.2	4.5						
THC High	80-90	84.55		84.7							
NOx Zero	0	0		0.12	0.1	0.2	0.1				
NOx Low	20-30 (3)										
NOx Mid	45-55	49.49		51.1	1.6	48.1	-3.0				
NOx High	80-90	90.7		90.96	0.3						
SO2 Zero	0	0		899.2	18.0						
SO2 Low	NR	867.9									
SO2 Mid	40-60	2418		2436	0.4						
SO2 High	80-100	4467		4475	0.2						

10/03/2000	9:33:27	-0.04	0.05	899.33
10/03/2000	9:34:27	-0.05	0.05	898.71
10/03/2000	9:35:27	-0.04	0.05	813.34
10/03/2000	9:36:27	-0.04	0.05	613.76
10/03/2000	9:37:27	-0.05	0.05	612.5
10/03/2000	9:38:27	-0.04	0.05	582.33
10/03/2000	9:39:27	-0.05	0.05	343.65
10/03/2000	9:40:27	-0.04	0.05	321.86
10/03/2000	9:41:27	-0.04	0.05	321.64
10/03/2000	9:42:27	-0.04	0.05	321.79
10/03/2000	9:43:27	-0.05	0.05	321.36
10/03/2000	9:44:27	-0.04	0.05	121.18
10/03/2000	9:45:27	-0.04	0.05	5.06
10/03/2000	9:46:27	-0.04	0.05	12.17
10/03/2000	9:47:27	-0.05	0.05	693.23
10/03/2000	9:48:27	-0.04	0.05	899.6
10/03/2000	9:49:27	-0.04	0.05	903.04
10/03/2000	9:50:27	-0.04	0.05	904.4
10/03/2000	9:51:27	-0.04	0.05	862.69
10/03/2000	9:52:27	-0.04	0.05	626.09
10/03/2000	9:53:27	-0.05	0.04	612.55
10/03/2000	9:54:27	-0.04	0.05	600.36
10/03/2000	9:55:27	-0.04	0.05	363.19
10/03/2000	9:56:27	-0.04	0.05	321.88
10/03/2000	9:57:27	-0.04	0.05	142.13
10/03/2000	9:58:27	-0.04	0.05	5.32
10/03/2000	9:59:27	-0.04	0.05	8.35
10/03/2000	10:00:27	17.08	0.05	33.36
10/03/2000	10:01:27	86.1	0.06	4.5
10/03/2000	10:02:27	93.91	0.06	4.56
10/03/2000	10:03:27	89.12	0.06	4.55
10/03/2000	10:04:27	37.83	0.05	4.45
10/03/2000	10:05:27	0.96	0.05	4.55
10/03/2000	10:06:27	0.44	0.05	63.15
Run 1	Start	NOX	CO	
10/03/2000	10:07:27	1.77	0.07	103.57
10/03/2000	10:08:27	3.98	0.05	31.04
10/03/2000	10:09:27	4.52	0.05	50.2
10/03/2000	10:10:27	2.99	0.05	111.01
10/03/2000	10:11:27	2.78	0.05	99.99
10/03/2000	10:12:27	5.28	0.05	84.54
10/03/2000	10:13:27	4.4	0.05	24.29
10/03/2000	10:14:27	3.2	0.05	36.24
10/03/2000	10:15:27	3	0.05	47.51
10/03/2000	10:16:27	2.81	0.05	68.29
10/03/2000	10:17:27	2.66	0.05	118.1
10/03/2000	10:18:27	2.78	0.05	256.99
10/03/2000	10:19:27	2.97	0.05	438.31
10/03/2000	10:20:27	2.95	0.05	359.94

10/03/2000	10:21:27	2.81	0.05	302.08
10/03/2000	10:22:27	2.74	0.05	351.92
10/03/2000	10:23:27	2.91	0.05	262.69
10/03/2000	10:24:27	2.72	0.05	332.79
10/03/2000	10:25:27	2.52	0.05	136.16
10/03/2000	10:26:27	2.08	0.05	164.99
10/03/2000	10:27:27	2.1	0.05	191.94
10/03/2000	10:28:27	2.1	0.05	165.78
10/03/2000	10:29:27	1.86	0.05	100.79
10/03/2000	10:30:27	1.69	0.05	148.07
10/03/2000	10:31:27	1.43	0.05	166.24
10/03/2000	10:32:27	1.32	0.05	131.12
10/03/2000	10:33:27	3.36	0.05	109.7
10/03/2000	10:34:27	8.95	0.05	35.31
10/03/2000	10:35:27	10.94	0.05	110.89
10/03/2000	10:36:27	2.97	0.05	131.22
10/03/2000	10:37:27	1.5	0.05	160.02
10/03/2000	10:38:27	1.71	0.05	211.42
10/03/2000	10:39:27	1.79	0.05	138.74
10/03/2000	10:40:27	1.82	0.05	120.64
10/03/2000	10:41:27	2.12	0.05	113.46
10/03/2000	10:42:27	2.95	0.05	92.22
10/03/2000	10:43:27	15.49	0.05	34.22
10/03/2000	10:44:27	12.87	0.05	70.81
10/03/2000	10:45:27	1.67	0.05	65.95
10/03/2000	10:46:27	3.54	0.05	34.31
10/03/2000	10:47:27	14.04	0.05	40.29
10/03/2000	10:48:27	4.86	0.05	60.84
10/03/2000	10:49:27	2.05	0.05	42.77
10/03/2000	10:50:27	8.6	0.05	13.12
10/03/2000	10:51:27	9.88	0.05	10.63
Average	End	4.1		130.7
10/03/2000	10:52:27	7.68	0.04	10.47
10/03/2000	10:53:27	7.26	0.04	15.16
10/03/2000	10:54:27	7.51	0.04	20.93
10/03/2000	10:55:27	7.16	0.04	25.76
10/03/2000	10:56:27	8.53	0.04	92.34
10/03/2000	10:57:27	7	0.04	25.41
10/03/2000	10:58:27	6.4	0.04	14.16
10/03/2000	10:59:27	6.66	0.04	12.45
10/03/2000	11:00:27	6.74	0.04	11.88
10/03/2000	11:01:27	6.56	0.04	11.54
10/03/2000	11:02:27	5.4	0.04	12.28
10/03/2000	11:03:27	4.82	0.04	37.71
10/03/2000	11:04:27	3.23	0.04	66.2
10/03/2000	11:05:27	2.33	0.04	57.98
10/03/2000	11:06:27	2.29	0.04	44.07
10/03/2000	11:07:27	2.43	0.04	43.52
10/03/2000	11:08:27	2.36	0.04	47.06

1010312000	16:10:48	1.4	-0.01	222.73
10/03/2000	16:11:48	1.61	-0.01	218.8
10/03/2000	16:12:48	1.7	-0.01	231.93
1010312000	16:13:48	1.6	-0.01	256.84
1010312000	16:14:48	1.49	-0.01	165.53
10/03/2000	16:15:48	0.39	-0.01	3.57
10/03/2000	16:16:48	0.01	-0.01	38.54
1010312000	16:17:48	0.01	-0.01	776.3
1010312000	16:18:48	0.01	-0.01	873.44
1010312000	16:19:48	0.01	-0.01	865.38
10/03/2000	16:20:48	0.01	-0.01	673.6
10/03/2000	16:21:48	0.01	-0.01	612.88
10/03/2000	16:22:48	0.01	-0.01	607.12
1010312000	16:23:48	0.01	-0.01	397.02
10/03/2000	16:24:48	0	-0.01	328.97
10/03/2000	16:25:48	0.01	-0.01	303.17
10/03/2000	16:26:48	0.01	-0.01	32.38
1010312000	16:27:48	0.01	-0.01	1
10/03/2000	16:28:48	0.26	-0.01	102.68

Run 1		NOX		CO
10/03/2000	16:29:48	2.3	-0.01	338.97
10/03/2000	16:30:48	3.3	-0.01	494
10/03/2000	16:31:48	2.93	-0.01	322.24
10/03/2000	16:32:48	2.19	-0.01	246.26
10/03/2000	16:33:48	1.82	-0.01	206.8
10/03/2000	16:34:48	1.61	-0.01	177.02
10/03/2000	16:35:48	1.36	-0.01	185.94
10/03/2000	16:36:48	1.32	-0.01	213.6
10/03/2000	16:37:48	1.99	-0.01	94.82
10/03/2000	16:38:48	7.91	-0.01	19.44
10/03/2000	16:39:48	5.1	-0.01	143.54
10/03/2000	16:40:48	2.05	-0.01	130.02
10/03/2000	16:41:48	1.51	-0.01	99.85
10/03/2000	16:42:48	1.5	-0.01	121.03
10/03/2000	16:43:48	1.58	-0.01	114.37
10/03/2000	16:44:48	1.55	-0.01	82.59
10/03/2000	16:45:48	1.34	-0.01	82.45
10/03/2000	16:46:48	1.34	-0.01	117.87
10/03/2000	16:47:48	1.5	-0.01	93.68
10/03/2000	16:48:48	1.44	-0.01	62.08
10/03/2000	16:49:48	1.63	-0.01	49.35
10/03/2000	16:50:48	1.92	-0.01	37.43
10/03/2000	16:51:48	4.48	-0.01	13.12
10/03/2000	16:52:48	6.08	-0.01	8.61
10/03/2000	16:53:48	4.52	-0.01	8.2
10/03/2000	16:54:48	4.16	-0.01	8.56
10/03/2000	16:55:48	3.91	-0.01	8.01
10/03/2000	16:56:48	9.66	-0.01	7.94
10/03/2000	16:57:48	26.26	-0.01	44.49

10/03/2000	16:58:48	3.17	-0.01	61.34
10/03/2000	16:59:48	3.61	-0.01	31.65
10/03/2000	17:00:48	7.34	-0.01	8
10/03/2000	17:01:48	5.69	-0.01	5.96
10/03/2000	17:02:48	5.46	-0.01	5.96
10/03/2000	17:03:48	5.32	-0.01	5.97
10/03/2000	17:04:48	4.96	-0.01	5.95
10/03/2000	17:05:48	5.21	-0.01	5.52
10/03/2000	17:06:48	5.09	-0.01	4.97
10/03/2000	17:07:48	4.31	-0.01	4.18
10/03/2000	17:08:48	4.61	-0.01	3.97
10/03/2000	17:09:48	4.77	-0.01	4.76
10/03/2000	17:10:48	4.94	-0.01	8.16
10/03/2000	17:11:48	5.39	-0.01	18.62
10/03/2000	17:12:48	5.92	-0.01	22.06
10/03/2000	17:13:48	8.12	-0.01	48.26
10/03/2000	17:14:48	5.86	-0.01	16.84
10/03/2000	17:15:48	5.22	-0.01	11.67
10/03/2000	17:16:48	5.48	-0.01	9.18
10/03/2000	17:17:48	5.7	-0.01	8.35
10/03/2000	17:18:48	5.53	-0.01	7.18
10/03/2000	17:19:48	5.21	-0.01	7.31
10/03/2000	17:20:48	5.16	-0.01	6.95
10/03/2000	17:21:48	4.31	-0.01	6.36
10/03/2000	17:22:48	1.9	-0.01	5.99
10/03/2000	17:23:48	1.35	-0.01	6.75
10/03/2000	17:24:48	1.22	-0.01	6.97
10/03/2000	17:25:48	1.41	-0.01	6.97
10/03/2000	17:26:48	1.54	-0.01	6.97
10/03/2000	17:27:48	1.59	-0.01	7.1
10/03/2000	17:28:48	1.6	-0.01	7.97
10/03/2000	17:29:48	1.67	-0.01	7.94
10/03/2000	17:30:48	1.69	-0.01	7.96
10/03/2000	17:31:48	1.6	-0.01	7.98
10/03/2000	17:32:48	1.55	-0.01	7.96
10/03/2000	17:33:48	1.54	-0.01	7.98
10/03/2000	17:34:48	1.6	-0.01	7.96
10/03/2000	17:35:48	1.47	-0.01	7.96
10/03/2000	17:36:48	1.57	-0.01	7.96
10/03/2000	17:37:48	1.53	-0.01	7.82
10/03/2000	17:38:48	1.42	-0.01	7.09
10/03/2000	17:39:48	2.48	-0.01	66.78
10/03/2000	17:40:48	3.65	-0.01	164.18
10/03/2000	17:41:48	2.53	-0.01	156.98
10/03/2000	17:42:48	2.28	-0.01	89.61
10/03/2000	17:43:48	1.91	-0.01	55.41
10/03/2000	17:44:48	4.32	-0.01	81.46
10/03/2000	17:45:48	6.76	-0.01	70.37
10/03/2000	17:46:48	2.26	-0.01	28.46

10/03/2000	17:47:48	1.87	-0.01	20.94
10/03/2000	17:48:48	1.76	-0.01	19.53
10/03/2000	17:49:48	1.98	-0.01	17
10/03/2000	17:50:48	2.01	-0.01	16.84
10/03/2000	17:51:48	1.84	-0.01	15.49
10/03/2000	17:52:48	1.76	-0.01	15.29
10/03/2000	17:53:48	1.77	-0.01	13.84
10/03/2000	17:54:48	1.58	-0.01	12.96
10/03/2000	17:55:48	1.43	-0.01	12.16
10/03/2000	17:56:48	1.4	-0.01	11
10/03/2000	17:57:48	1.46	-0.01	11.58
10/03/2000	17:58:48	1.63	-0.01	10.85
10/03/2000	17:59:48	1.37	-0.01	11.43
10/03/2000	18:00:48	1.76	-0.01	11.49
10/03/2000	18:01:48	1.78	-0.01	10.97
10/03/2000	18:02:48	1.67	-0.01	9.96
10/03/2000	18:03:48	1.66	-0.01	10.15
10/03/2000	18:04:48	1.64	-0.01	9.96
10/03/2000	18:05:48	1.45	-0.01	8.82
10/03/2000	18:06:48	1.55	-0.01	9.47
10/03/2000	18:07:48	1.61	-0.01	7.98
10/03/2000	18:08:48	1.53	-0.01	7.97
10/03/2000	18:09:48	1.6	-0.01	7.97
10/03/2000	18:10:48	1.6	-0.01	7.97
10/03/2000	18:11:48	1.52	-0.01	7.95
10/03/2000	18:12:48	1.58	-0.01	8.79
10/03/2000	18:13:48	1.77	-0.01	8.31
10/03/2000	18:14:48	1.7	-0.01	8.46
10/03/2000	18:15:48	1.7	-0.01	7.97
10/03/2000	18:16:48	1.74	-0.01	7.96
10/03/2000	18:17:48	1.54	-0.01	7.31
10/03/2000	18:18:48	1.25	-0.01	6.96
10/03/2000	18:19:48	1.15	-0.01	6.96
10/03/2000	18:20:48	1.06	-0.01	6.98
10/03/2000	18:21:48	1.01	-0.01	6.96
10/03/2000	18:22:48	1.1	-0.01	6.97
10/03/2000	18:23:48	1.01	-0.01	6.95
10/03/2000	18:24:48	1	-0.01	6.96
10/03/2000	18:25:48	1	-0.01	6.63
10/03/2000	18:26:48	0.97	-0.01	7.11
10/03/2000	18:27:48	18.45	-0.01	38.76
10/03/2000	18:28:48	9.56	-0.01	94.75
10/03/2000	18:29:48	2.74	-0.01	139.35
10/03/2000	18:30:48	3.59	-0.01	157.84
10/03/2000	18:31:48	3.72	-0.01	109.04
10/03/2000	18:32:48	4.07	-0.01	163.5
10/03/2000	18:33:48	3.53	-0.01	326.35
10/03/2000	18:34:48	2.34	-0.01	337.33
10/03/2000	18:35:48	1.82	-0.01	211.91

10/03/2000	18:36:48	1.62	-0.01	180.47
10/03/2000	18:37:48	1.35	-0.01	215.78
10/03/2000	18:38:48	1.35	-0.01	207.44
10/03/2000	18:39:48	2.91	-0.01	62.58
10/03/2000	18:40:48	4.56	-0.01	16.5
10/03/2000	18:41:48	3.65	-0.01	65.94
10/03/2000	18:42:48	2.54	-0.01	176.92
10/03/2000	18:43:48	2.23	-0.01	182.34
10/03/2000	18:44:48	2.96	-0.01	208.78
10/03/2000	18:45:48	10.43	-0.01	113.21
10/03/2000	18:46:48	3.92	-0.01	39.47
10/03/2000	18:47:48	3.79	-0.01	50.25
10/03/2000	18:48:48	3.61	-0.01	88.94
10/03/2000	18:49:48	3.55	-0.01	251.85
10/03/2000	18:50:48	3.68	-0.01	274.27
10/03/2000	18:51:48	3.59	-0.01	373.25
10/03/2000	18:52:48	3.42	-0.01	305.05
10/03/2000	18:53:48	3.61	-0.01	317.83
10/03/2000	18:54:48	3.45	-0.01	161.12
10/03/2000	18:55:48	3.12	-0.01	167.28
10/03/2000	18:56:48	2.34	-0.01	303.78
10/03/2000	18:57:48	1.67	-0.01	410.54
10/03/2000	18:58:48	1.62	-0.01	313.53
10/03/2000	18:59:48	2.4	-0.01	159.58
10/03/2000	19:00:48	4.28	-0.01	20.74
10/03/2000	19:01:48	3.99	-0.01	156.42
10/03/2000	19:02:48	1.25	-0.01	161.79
10/03/2000	19:03:48	1.27	-0.01	142.18
10/03/2000	19:04:48	1.53	-0.01	131.17
10/03/2000	19:05:48	1.44	-0.01	81.43
10/03/2000	19:06:48	1.48	-0.01	151.8
10/03/2000	19:07:48	1.6	-0.01	162.47
10/03/2000	19:08:48	1.65	-0.01	173.37
10/03/2000	19:09:48	1.71	-0.01	137.88
10/03/2000	19:10:48	2.08	-0.01	207.78
10/03/2000	19:11:48	1.98	-0.01	103.82
10/03/2000	19:12:48	1.62	-0.01	69.42
10/03/2000	19:13:48	1.55	-0.01	71.48
10/03/2000	19:14:48	2	-0.01	123.46
10/03/2000	19:15:48	2.27	-0.01	77.78
10/03/2000	19:16:48	2.52	-0.01	101.85
10/03/2000	19:17:48	1.95	-0.01	169.84
10/03/2000	19:18:48	2.88	-0.01	62.53
10/03/2000	19:19:48	2.43	-0.01	43.43
10/03/2000	19:20:48	6.88	-0.01	41.37
10/03/2000	19:21:48	2.15	-0.01	27.83
10/03/2000	19:22:48	7.66	-0.01	32.75
10/03/2000	19:23:48	8.99	-0.01	33.92
10/03/2000	19:24:48	10.2	-0.01	31.77

10/03/2000	19:25:48	4.02	-0.01	34.84
10/03/2000	19:26:48	5.54	-0.01	22.24
10/03/2000	19:27:48	9.24	-0.01	19.74
10/03/2000	19:28:48	9.62	-0.01	26.62
Average	End	3.2		77.5
10/03/2000	19:29:48	8.72	-0.01	40.26
10/03/2000	19:30:48	2.07	-0.01	2.99
10/03/2000	19:31:48	0.01	-0.01	0.94
10/03/2000	19:32:48	0	-0.01	0.93
10/03/2000	19:33:48	0	-0.01	133.87
10/03/2000	19:34:48	0	-0.01	844.51
10/03/2000	19:35:48	0	-0.01	869.89
10/03/2000	19:36:48	0	-0.01	872.03
10/03/2000	19:37:48	0	-0.01	830.36
10/03/2000	19:38:48	0	-0.01	620.64
10/03/2000	19:39:48	0	-0.01	608.92
10/03/2000	19:40:48	0	-0.01	477.09
10/03/2000	19:41:48	0	-0.01	329.39
10/03/2000	19:42:48	0	-0.01	312.37
10/03/2000	19:43:48	0	-0.01	41.1
10/03/2000	19:44:48	0	-0.01	0.93
10/03/2000	19:45:48	0.75	-0.01	28.14
10/03/2000	19:46:48	16.1	-0.01	162.72
10/03/2000	19:47:48	81.35	0	1.63
10/03/2000	19:48:48	95.23	0	-0.06
10/03/2000	19:49:48	95.09	0	-0.07
10/03/2000	19:50:48	71.6	0	0.92
10/03/2000	19:51:48	52.56	-0.01	0.93
10/03/2000	19:52:48	50.05	-0.01	0.92
10/03/2000	19:53:48	16.19	-0.01	0.94
10/03/2000	19:54:48	0.21	-0.01	0.92
10/03/2000	19:55:48	0.12	-0.01	11.61
10/03/2000	19:56:48	1.62	-0.01	106.57

Run 2	Start	NOX	CO
10/04/2000	8:00:54	2.99	0 71.76
10/04/2000	8:01:54	3.3	0 63.93
10/04/2000	8:02:54	2.91	0 75.6
10/04/2000	8:03:54	2.42	0 81.53
10/04/2000	8:04:54	2.13	0 78.54
10/04/2000	8:05:54	1.77	0 117.42
10/04/2000	8:06:54	1.42	0 90.15
10/04/2000	8:07:54	1.22	0 79.97
10/04/2000	8:08:54	1.01	0 79.35
10/04/2000	8:09:54	0.9	0 56.22
10/04/2000	8:10:54	2.56	0 21.68
10/04/2000	8:11:54	4.47	0 58.17
10/04/2000	8:12:54	2.34	0 128.05
10/04/2000	8:13:54	4.45	0 102.63
10/04/2000	8:14:54	5.27	0 32.49
10/04/2000	8:15:54	3.65	0 25.19
10/04/2000	8:16:54	3.27	0 63.59
10/04/2000	8:17:54	3.01	0 162.33
10/04/2000	8:18:54	2.94	0 288.95
10/04/2000	8:19:54	2.57	0 281.73
10/04/2000	8:20:54	1.39	0 243.78
10/04/2000	8:21:54	1.11	0 152.87
10/04/2000	8:22:54	1	0 96.73
10/04/2000	8:23:54	1.2	0 94.54
10/04/2000	8:24:54	1.36	0 136.06
10/04/2000	8:25:54	1.29	0.01 196.66
10/04/2000	8:26:54	1.21	0.01 222.75
10/04/2000	8:27:54	1.66	0.01 152.26
10/04/2000	8:28:54	4.6	0.01 46.08
10/04/2000	8:29:54	4.8	0.01 179.91
10/04/2000	8:30:54	1	0.01 227.91
10/04/2000	8:31:54	0.72	0.01 264.45
10/04/2000	8:32:54	0.66	0.01 249.98
10/04/2000	8:33:54	0.66	0.01 215.88
10/04/2000	8:34:54	0.73	0.01 190.05
10/04/2000	8:35:54	0.82	0.01 165.1
10/04/2000	8:36:54	0.83	0.01 128.68
10/04/2000	8:37:54	0.94	0.01 177.95
10/04/2000	8:38:54	1.11	0.01 192.53
10/04/2000	8:39:54	1.45	0.01 182.29
10/04/2000	8:40:54	1.77	0.01 160.74
10/04/2000	8:41:54	2.43	0.01 119.9
10/04/2000	8:42:54	10.2	0.01 67.14
10/04/2000	8:43:54	5.83	0.01 125.91
10/04/2000	8:44:54	10.87	0.01 28.13
10/04/2000	8:45:54	17.85	0.01 13.77
10/04/2000	8:46:54	10.89	0.01 53.47
10/04/2000	8:47:54	2.98	0.01 42.74

10/04/2000	8:48:54	11.94	0.01	13.11
10/04/2000	8:49:54	14.34	0.01	12.14
10/04/2000	8:50:54	11.39	0.01	20.72
10/04/2000	8:51:54	11.19	0.01	63.25
10/04/2000	8:52:54	8.48	0.01	12.29
10/04/2000	8:53:54	7.06	0.01	8.3
10/04/2000	8:54:54	7.04	0.01	6.56
10/04/2000	8:55:54	7.62	0.01	5.89
10/04/2000	8:56:54	6.86	0.01	5.88
10/04/2000	8:57:54	6.48	0.01	5.06
10/04/2000	8:58:54	6.24	0.01	5.1
10/04/2000	8:59:54	6.05	0.01	5.17
10/04/2000	9:00:54	6	0.01	5.14
10/04/2000	9:01:54	6.15	0.01	5.81
10/04/2000	9:02:54	5.96	0.01	7.09
10/04/2000	9:03:54	5.4	0.01	11.28
10/04/2000	9:04:54	5.34	0.01	12.81
10/04/2000	9:05:54	5.06	0.01	13.11
10/04/2000	9:06:54	5.36	0.01	13.82
10/04/2000	9:07:54	5.38	0.01	14.85
10/04/2000	9:08:54	5.28	0.01	15.1
10/04/2000	9:09:54	5.29	0.01	15.44
10/04/2000	9:10:54	5.4	0.01	16.54
10/04/2000	9:11:54	5.18	0.01	14.46
10/04/2000	9:12:54	5.11	0.01	14.7
10/04/2000	9:13:54	5.44	0.01	15.09
10/04/2000	9:14:54	5.25	0.01	15.06
10/04/2000	9:15:54	4.19	0.01	35.26
10/04/2000	9:16:54	3.05	0.01	46.94
10/04/2000	9:17:54	3.86	0.01	44.03
10/04/2000	9:18:54	6.81	0.01	78.76
10/04/2000	9:19:54	2.26	0.01	92.32
10/04/2000	9:20:54	1.62	0.01	98.76
10/04/2000	9:21:54	1.5	0.01	105.77
10/04/2000	9:22:54	1.42	0	103.81
10/04/2000	9:23:54	1.22	0.01	84.47
10/04/2000	9:24:54	1.12	0.01	63.85
10/04/2000	9:25:54	1.12	0	77.39
10/04/2000	9:26:54	1.12	0.01	85.09
10/04/2000	9:27:54	1.23	0.01	88.42
10/04/2000	9:28:54	1.22	0	103.34
10/04/2000	9:29:54	1.12	0	68.7
10/04/2000	9:30:54	1.12	0	106.78
10/04/2000	9:31:54	1.15	0	120.22
10/04/2000	9:32:54	1.83	0.01	14.15
10/04/2000	9:33:54	2.25	0.01	36.14
10/04/2000	9:34:54	1.77	0.01	165.54
10/04/2000	9:35:54	1.43	0.01	165.2
10/04/2000	9:36:54	1.42	0.01	156.18

10/04/2000	9:37:54	2.64	0.01	100.22
10/04/2000	9:38:54	3.72	0.01	49.98
10/04/2000	9:39:54	2.5	0.01	23.57
10/04/2000	9:40:54	2.22	0.01	37
10/04/2000	9:41:54	2.05	0.01	57.17
10/04/2000	9:42:54	1.95	0.01	74.1
10/04/2000	9:43:54	1.73	0.01	193.41
10/04/2000	9:44:54	1.85	0.01	238.66
10/04/2000	9:45:54	1.83	0.01	264.87
10/04/2000	9:46:54	2.3	0.01	200.5
10/04/2000	9:47:54	2.54	0.01	303.66
10/04/2000	9:48:54	2.87	0.01	369.16
10/04/2000	9:49:54	3.1	0.01	374.46
10/04/2000	9:50:54	2.74	0.01	323.52
10/04/2000	9:51:54	2.67	0.01	258.54
10/04/2000	9:52:54	1.82	0.01	217.47
10/04/2000	9:53:54	1.38	0.01	170.68
10/04/2000	9:54:54	1.27	0.01	192.72
10/04/2000	9:55:54	1.25	0.01	208.32
10/04/2000	9:56:54	1.05	0.01	321.44
10/04/2000	9:57:54	1.08	0.01	287.23
10/04/2000	9:58:54	1.04	0.01	237.59
10/04/2000	9:59:54	1.5	0.01	220.56
<i>Average</i> End		3.5		109.2
10/04/2000	10:00:54	4.14	0.01	68.86
10/04/2000	10:01:54	6.9	0.01	137.23
10/04/2000	10:02:54	1.59	0.01	25.01
10/04/2000	10:03:54	0.02	0.01	1.33
10/04/2000	10:04:54	0.02	0.01	233.9
10/04/2000	10:05:54	0.02	0.01	865.25
10/04/2000	10:06:54	0.02	0.01	873.58
10/04/2000	10:07:54	0.02	0.01	874.17
10/04/2000	10:08:54	0.02	0.01	811.41
10/04/2000	10:09:54	0.02	0.01	619.66
10/04/2000	10:10:54	0.02	0.01	614.25
10/04/2000	10:11:54	0.02	0.01	614.56
10/04/2000	10:12:54	1.39	0.01	262.14
10/04/2000	10:13:54	2.61	0.01	88
10/04/2000	10:14:54	0.87	0.01	302.7
10/04/2000	10:15:54	0.03	0.01	328.61
10/04/2000	10:16:54	0.02	0.01	87.47
10/04/2000	10:17:54	0.02	0.01	1.26
10/04/2000	10:18:54	0.02	0.01	1.23
10/04/2000	10:19:54	11.97	0.01	0.89
10/04/2000	10:20:54	74.66	0.02	0.14
10/04/2000	10:21:54	84.61	0.02	0.25
10/04/2000	10:22:54	84.94	0.02	0.12
10/04/2000	10:23:54	85.1	0.02	0.18
10/04/2000	10:24:54	85.45	0.02	0.19

10/04/2000	10:25:54	87.92	0.02	0.04
10/04/2000	10:26:54	91.36	0.02	0.17
10/04/2000	10:27:54	88.96	0.02	0.14
10/04/2000	10:28:54	69.85	0.02	0.2
10/04/2000	10:29:54	47.58	0.02	0.14
10/04/2000	10:30:54	47.65	0.02	0.21
10/04/2000	10:31:54	48.72	0.02	0.13
10/04/2000	10:32:54	49.11	0.02	0.17
10/04/2000	10:33:54	35.41	0.02	1.11
10/04/2000	10:34:54	3.35	0.01	1.18
10/04/2000	10:35:54	0.01	0.01	1.22
10/04/2000	10:36:54	2.89	0.01	5.26
10/04/2000	10:37:54	59.22	0.02	1.18
10/04/2000	10:38:54	84.5	0.02	0.19
10/04/2000	10:39:54	89.98	0.02	0.2
10/04/2000	10:40:54	82.47	0.02	0.58
10/04/2000	10:41:54	19.08	0.01	1.23
10/04/2000	10:42:54	0.12	0.01	1.16
10/04/2000	10:44:30	0.3	0	89.42

Run 2	Start	NOX	CO
10/04/2000	10:45:30	1.09	0 156.42
10/04/2000	10:46:30	0.95	0 147.98
10/04/2000	10:47:30	2.53	0 45.06
10/04/2000	10:48:30	4.34	0 58.15
10/04/2000	10:49:30	2.6	0 72.59
10/04/2000	10:50:30	3.56	0 66.05
10/04/2000	10:51:30	2.88	0 33.02
10/04/2000	10:52:30	2.12	0 57.27
10/04/2000	10:53:30	2.01	0 79.68
10/04/2000	10:54:30	1.86	0 108.2
10/04/2000	10:55:30	1.71	0 114.25
10/04/2000	10:56:30	1.71	0 109.75
10/04/2000	10:57:30	1.68	0 154.54
10/04/2000	10:58:30	1.68	0 176.84
10/04/2000	10:59:30	1.8	0 147.77
10/04/2000	11:00:30	1.45	0.01 161
10/04/2000	11:01:30	1.4	0 223.03
10/04/2000	11:02:30	1.48	0.01 223.73
10/04/2000	11:03:30	1.27	0 169.04
10/04/2000	11:04:30	0.9	0 99.98
10/04/2000	11:05:30	0.89	0 62.56
10/04/2000	11:06:30	1.11	0 26.09
10/04/2000	11:07:30	1.24	0 30.96
10/04/2000	11:08:30	2.45	0 28.48
10/04/2000	11:09:30	2.56	0 71.33
10/04/2000	11:10:30	0.93	0 115.27
10/04/2000	11:11:30	0.37	0 125.18
10/04/2000	11:12:30	0.32	0 176.78
10/04/2000	11:13:30	0.32	0 125.08

10/04/2000	11:14:30	0.63	0	102.07
10/04/2000	11:15:30	3.81	0	34.6
10/04/2000	11:16:30	7.85	0	59.2
10/04/2000	11:17:30	1.91	0	77.88
10/04/2000	11:18:30	0.71	0	76.19
10/04/2000	11:19:30	0.47	0	94.56
10/04/2000	11:20:30	0.44	0	98.73
10/04/2000	11:21:30	0.57	0	109.95
10/04/2000	11:22:30	1.3	0	89.42
10/04/2000	11:23:30	6.05	0	18.23
10/04/2000	11:24:30	8.36	0	31.53
10/04/2000	11:25:30	2.86	0	46.48
10/04/2000	11:26:30	3.48	0	23.2
10/04/2000	11:27:30	6.02	0	29.88
10/04/2000	11:28:30	2.12	0	47.38
10/04/2000	11:29:30	3.05	0	27.73
10/04/2000	11:30:30	6.43	0	7.78
10/04/2000	11:31:30	7	0	8.98
10/04/2000	11:32:30	6.4	0	13.79
10/04/2000	11:33:30	5.67	0	16.36
10/04/2000	11:34:30	5.36	0	43.47
10/04/2000	11:35:30	4.38	0	14.44
10/04/2000	11:36:30	4	0	6.54
10/04/2000	11:37:30	3.06	0	6.21
10/04/2000	11:38:30	3.06	0	8.73
10/04/2000	11:39:30	3.64	0	66.97
10/04/2000	11:40:30	2.32	0	75.52
10/04/2000	11:41:30	3.38	0	33.53
10/04/2000	11:42:30	2.88	0	43.72
10/04/2000	11:43:30	1.01	0	69.96
10/04/2000	11:44:30	0.79	0	66.81
10/04/2000	11:45:30	0.52	0	54.64
10/04/2000	11:46:30	0.51	0	69.33
10/04/2000	11:47:30	0.51	0	82.75
10/04/2000	11:48:30	0.59	0	105.83
10/04/2000	11:49:30	0.54	0	105.09
10/04/2000	11:50:30	0.5	0	101.05
10/04/2000	11:51:30	0.44	0	78.25
10/04/2000	11:52:30	0.44	0	80.62
10/04/2000	11:53:30	0.32	0	68.78
10/04/2000	11:54:30	0.32	0	49.61
10/04/2000	11:55:30	0.31	0	33.39
10/04/2000	11:56:30	0.32	0	28.49
10/04/2000	11:57:30	0.87	0	10.37
10/04/2000	11:58:30	2.02	0	17.33
10/04/2000	11:59:30	1.68	0	57.13
<i>Average</i> End		2.2		74.1
10/04/2000	12:00:30	1.03	0	62.17
10/04/2000	12:01:30	2.4	0	27.57

10/04/2000	12:02:30	1.54	0	10.39
10/04/2000	12:03:30	-0.04	0	0.82
10/04/2000	12:04:30	-0.19	0	492.54
10/04/2000	12:05:30	-0.19	0	891.43
10/04/2000	12:06:30	-0.19	0	870.71
10/04/2000	12:07:30	-0.19	0	864.93
10/04/2000	12:08:30	-0.19	0	248.15
10/04/2000	12:09:30	-0.19	0	1.42
10/04/2000	12:10:30	-0.19	0	1.07
10/04/2000	12:11:30	4.96	0	0.71
10/04/2000	12:12:30	57.78	0.01	-0.08
10/04/2000	12:13:30	75.28	0.01	0.17
10/04/2000	12:14:30	75.83	0.01	0.08
10/04/2000	12:15:30	77.21	0.01	0.04
10/04/2000	12:16:30	77.62	0.01	0.08
10/04/2000	12:17:30	78.43	0.01	0.08
10/04/2000	12:18:30	87.43	0.01	0.08
10/04/2000	12:19:30	99.78	0.01	0.07
10/04/2000	12:20:30	98.7	0.01	0.2
10/04/2000	12:21:30	94.4	0.01	0.03
10/04/2000	12:22:30	93.9	0.01	0.17
10/04/2000	12:23:30	93.74	0.01	0.04
10/04/2000	12:24:30	93.69	0.01	0.03
10/04/2000	12:25:30	93.58	0.01	0.07
10/04/2000	12:26:30	97.56	0.01	0.07
10/04/2000	12:27:30	98.8	0.01	-0.11
10/04/2000	12:28:30	90.79	0.01	0.08
10/04/2000	12:29:30	90.6	0.01	3.82
10/04/2000	12:30:30	49.81	0	570.02
10/04/2000	12:31:30	1.03	0	808.45
10/04/2000	12:32:30	0.05	0	810.71
10/04/2000	12:33:30	-0.05	0	805.59
10/04/2000	12:34:30	-0.09	0	836.62
10/04/2000	12:35:30	-0.09	0	854.57
10/04/2000	12:36:30	-0.09	0	155.94
10/04/2000	12:37:30	-0.09	0	1.74
10/04/2000	12:38:30	-0.09	0	3.43
10/04/2000	12:39:30	-0.09	0	569.02
10/04/2000	12:40:30	-0.17	0	868.41
10/04/2000	12:41:30	0.46	0	683.33
10/04/2000	12:42:30	9.45	0	29.8
10/04/2000	12:43:30	10.32	0	15.28
10/04/2000	12:44:52	8.06	0.01	23.86
Run 3	Start	NOX		CO
10/04/2000	12:45:52	8.32	0.01	52.26
10/04/2000	12:46:52	7.33	0.01	18.66
10/04/2000	12:47:52	6.34	0.01	10.3
10/04/2000	12:48:52	7.3	0.01	8.73
10/04/2000	12:49:52	7.02	0.01	7.46


10/04/2000	12:50:52	5.58	0.01	8.05
10/04/2000	12:51:52	5.36	0.01	10.51
10/04/2000	12:52:52	5.29	0.01	11.15
10/04/2000	12:53:52	5.84	0.01	17.75
10/04/2000	12:54:52	5.28	0.01	65.19
10/04/2000	12:55:52	7.81	0.01	33.08
10/04/2000	12:56:52	8.79	0.01	23.83
10/04/2000	12:57:52	11.92	0.01	24.25
10/04/2000	12:58:52	4.1	0.01	27.5
10/04/2000	12:59:52	3.44	0.01	28.77
10/04/2000	13:00:52	3.24	0	78.93
10/04/2000	13:01:52	4.91	0.01	107.31
10/04/2000	13:02:52	3.61	0.01	121.87
10/04/2000	13:03:52	1.85	0	143.19
10/04/2000	13:04:52	3.08	0	100.7
10/04/2000	13:05:52	2.38	0	103.97
10/04/2000	13:06:52	1.19	0	152.99
10/04/2000	13:07:52	0.77	0	273.18
10/04/2000	13:08:52	1.05	0	251.14
10/04/2000	13:09:52	6.47	0.01	50.96
10/04/2000	13:10:52	4.98	0	104.8
10/04/2000	13:11:52	2.13	0	110.73
10/04/2000	13:12:52	2.12	0	74.77
10/04/2000	13:13:52	2.21	0	60.27
10/04/2000	13:14:52	7.85	0.01	33.7
10/04/2000	13:15:52	5.6	0	30.25
10/04/2000	13:16:52	2.83	0	42.68
10/04/2000	13:17:52	2.39	0	43.5
10/04/2000	13:18:52	2.34	0.01	65.53
10/04/2000	13:19:52	2.23	0	104.86
10/04/2000	13:20:52	2.3	0	150.95
10/04/2000	13:21:52	2.38	0	110.44
10/04/2000	13:22:52	2.42	0.01	66.62
10/04/2000	13:23:52	2.11	0	234.46
10/04/2000	13:24:52	1.79	0	116.69
10/04/2000	13:25:52	2.48	0	200.68
10/04/2000	13:26:52	1.69	0	210.86
10/04/2000	13:27:52	0.86	0	273.48
10/04/2000	13:28:52	0.74	0	282.42
10/04/2000	13:29:52	0.87	0	212.32
10/04/2000	13:30:52	2.22	0	109.07
10/04/2000	13:31:52	7.04	0	14.9
10/04/2000	13:32:52	6.73	0	8.4
10/04/2000	13:33:52	8.21	0	59.28
10/04/2000	13:34:52	2.37	0	86.05
10/04/2000	13:35:52	1.28	0	156.73
10/04/2000	13:36:52	1.52	0	233.71
10/04/2000	13:37:52	1.41	0	246.61
10/04/2000	13:38:52	1.33	0	315.66

10/04/2000	13:39:52	1.55	0	372.27
10/04/2000	13:40:52	1.6	0	317.74
10/04/2000	13:41:52	1.67	0	267.81
10/04/2000	13:42:52	2.04	0	278.83
10/04/2000	13:43:52	2.22	0	347.09
10/04/2000	13:44:52	2.45	0	200.47
10/04/2000	13:45:52	7.85	0	56.9
10/04/2000	13:46:52	13.65	0	52.06
10/04/2000	13:47:52	3.64	0	171.55
10/04/2000	13:48:52	1.27	0	244.64
10/04/2000	13:49:52	2.23	0	188.82
10/04/2000	13:50:52	10.83	0	43.76
10/04/2000	13:51:52	17.13	0	21.6
10/04/2000	13:52:52	11.07	0	15.26
10/04/2000	13:53:52	11.76	0	17
10/04/2000	13:54:52	11.62	0	14.15
10/04/2000	13:55:52	12.99	0	46.97
10/04/2000	13:56:52	8.6	0	23.14
10/04/2000	13:57:52	7.87	0	14.61
10/04/2000	13:58:52	6.36	0	12.32
10/04/2000	13:59:52	5.26	0	11.11
10/04/2000	14:00:52	5.34	0	9.74
10/04/2000	14:01:52	6.44	0	9.45
10/04/2000	14:02:52	6.11	0	9.06
10/04/2000	14:03:52	4.41	0	11.35
10/04/2000	14:04:52	4.58	0	61.67
10/04/2000	14:05:52	1.75	0	118.64
<i>Average</i>	<i>End</i>	4.8		104.1
10/04/2000	14:06:52	0	0	1.72
10/04/2000	14:07:52	-0.13	0	1.02
10/04/2000	14:08:52	-0.19	0	356.43
10/04/2000	14:09:52	-0.19	0	869.25
10/04/2000	14:10:52	-0.19	0	869.39
10/04/2000	14:11:52	0.92	0	740.8
10/04/2000	14:12:52	55.92	0.01	34.32
10/04/2000	14:13:52	88.69	0.01	0.93
10/04/2000	14:14:52	90.11	0.01	0.83
10/04/2000	14:15:52	91.26	0.01	0.08
10/04/2000	14:16:52	80.62	0.01	0.61
10/04/2000	14:17:52	12.98	0	1.08
10/04/2000	14:19:40	0.33	0	57.31
10/04/2000	14:20:40	2.26	0	142.75
10/04/2000	14:21:40	3.5	0	42.1
Run 3		NOX		CO
10/04/2000	14:22:40	4.02	0	102.36
10/04/2000	14:23:40	2.68	0	129.08
10/04/2000	14:24:40	2.66	0	86.21
10/04/2000	14:25:40	5.13	0	47.83
10/04/2000	14:26:40	3.95	0	46.53

10/04/2000	14:27:40	3.6	0	38.14
10/04/2000	14:28:40	2.66	0	108.78
10/04/2000	14:29:40	2.01	0	206.05
10/04/2000	14:30:40	2.25	0	249.71
10/04/2000	14:31:40	2.41	0	184.63
10/04/2000	14:32:40	2.36	0	159.7
10/04/2000	14:33:40	2.09	0	262.44
10/04/2000	14:34:40	2.39	0	394.78
10/04/2000	14:35:40	1.62	0	449.89
10/04/2000	14:36:40	1.47	0	396.37
10/04/2000	14:37:40	0.91	0	289.74
10/04/2000	14:38:40	0.78	0	265.58
10/04/2000	14:39:40	0.62	0	279.13
10/04/2000	14:40:40	0.77	0	241.59
10/04/2000	14:41:40	0.81	0	292.94
10/04/2000	14:42:40	1.44	0	275.78
10/04/2000	14:43:40	5.58	0	97.55
10/04/2000	14:44:40	6.54	0	26.38
10/04/2000	14:45:40	7.74	0	14.28
10/04/2000	14:46:40	16.22	0	11.48
10/04/2000	14:47:40	5.54	0	8.67
10/04/2000	14:48:40	5.14	0	6.64
10/04/2000	14:49:40	6.39	0	6.39
10/04/2000	14:50:40	6.14	0	5.81
10/04/2000	14:51:40	5.08	0	5.01
10/04/2000	14:52:40	5.69	0	4.77
10/04/2000	14:53:40	5.39	0	4.4
10/04/2000	14:54:40	5.91	0	4.58
10/04/2000	14:55:40	6.98	0	5.16
10/04/2000	14:56:40	6.65	0	4.17
10/04/2000	14:57:40	5.26	0	3.63
10/04/2000	14:58:40	4.75	0	4.01
10/04/2000	14:59:40	5.87	0	3.92
10/04/2000	15:00:40	6.54	0	4.1
10/04/2000	15:01:40	9.34	0	6.31
10/04/2000	15:02:40	16.07	0	70.22
10/04/2000	15:03:40	1.48	0	79.81
10/04/2000	15:04:40	1.31	0	104.25
10/04/2000	15:05:40	1.36	0	147.98
10/04/2000	15:06:40	1.01	0	222.77
10/04/2000	15:07:40	0.81	0	173.86
10/04/2000	15:08:40	0.83	0	338.39
10/04/2000	15:09:40	1.17	0	224.19
10/04/2000	15:10:40	1.59	0	142.41
10/04/2000	15:11:40	1.6	0	153.41
10/04/2000	15:12:40	1.75	0	199.95
10/04/2000	15:13:40	4.29	0	76.72
10/04/2000	15:14:40	8.09	0	19.51
10/04/2000	15:15:40	13.73	0	10.42

10/04/2000	15:16:40	14.33	0	8.95
10/04/2000	15:17:40	12.71	0	9.18
10/04/2000	15:18:40	10.66	0	17.59
10/04/2000	15:19:40	9.41	0	29.55
10/04/2000	15:20:40	10.34	0	66.21
10/04/2000	15:21:40	6.62	0	22.37
10/04/2000	15:22:40	4.5	0	10.72
10/04/2000	15:23:40	4.44	0	7.48
10/04/2000	15:24:40	4.66	0	6.01
10/04/2000	15:25:40	4.38	0	5.52
10/04/2000	15:26:40	4.09	0	5.76
10/04/2000	15:27:40	5.09	0	9.15
10/04/2000	15:28:40	8.55	0	73.67
10/04/2000	15:29:40	6.73	0	111.02
10/04/2000	15:30:40	5.65	0	95.18
10/04/2000	15:31:40	6.61	0	65.19
10/04/2000	15:32:40	7.42	0	32.5
10/04/2000	15:33:40	2.79	0	77.58
10/04/2000	15:34:40	3.21	0	93.55
10/04/2000	15:35:40	3.05	0	109.49
10/04/2000	15:36:40	3.23	0	226.64
10/04/2000	15:37:40	3.57	0	292.95
10/04/2000	15:38:40	3.48	0	278.17
10/04/2000	15:39:40	2.81	0	220.99
10/04/2000	15:40:40	2.24	0	206.4
10/04/2000	15:41:40	2.29	0	231.99
10/04/2000	15:42:40	1.8	0	263.3
10/04/2000	15:43:40	1.13	0	263.46
10/04/2000	15:44:40	0.9	0	219.23
10/04/2000	15:45:40	2.96	0	24.24
10/04/2000	15:46:40	5.56	0	102.53
10/04/2000	15:47:40	2.54	0	198.53
10/04/2000	15:48:40	1.6	0	166.99
10/04/2000	15:49:40	1.41	0	144.6
10/04/2000	15:50:40	1.31	0	162.25
10/04/2000	15:51:40	1.35	0	196.34
10/04/2000	15:52:40	1.53	0	201.7
10/04/2000	15:53:40	4.01	0	69.85
10/04/2000	15:54:40	4.59	0	32.15
10/04/2000	15:55:40	2.22	0	34.05
10/04/2000	15:56:40	2.28	0	66.59
10/04/2000	15:57:40	2.15	0	125.86
10/04/2000	15:58:40	2.1	0	192.06
10/04/2000	15:59:40	1.8	0	276
10/04/2000	16:00:40	1.51	0	281.12
10/04/2000	16:01:40	1.54	0	312.21
10/04/2000	16:02:40	1.52	0	371.12
10/04/2000	16:03:40	1.75	0	382.28
10/04/2000	16:04:40	1.76	0	295.58

10/04/2000	16:05:40	0.83	0	204.22
10/04/2000	16:06:40	0.65	0	193.42
10/04/2000	16:07:40	0.55	0	264.4
10/04/2000	16:08:40	0.57	0	259.75
10/04/2000	16:09:40	0.81	0	227.64
10/04/2000	16:10:40	2.8	0	100.98
10/04/2000	16:11:40	3.79	0	10.84
10/04/2000	16:12:40	3.4	0	6.22
10/04/2000	16:13:40	5.01	0	6.54
10/04/2000	16:14:40	7.66	0	85.94
10/04/2000	16:15:40	0.91	0	118.32
10/04/2000	16:16:40	0.59	0	137.55
10/04/2000	16:17:40	0.61	0	183.17
10/04/2000	16:18:40	0.76	0	174.54
10/04/2000	16:19:40	0.77	0	204.67
10/04/2000	16:20:40	0.65	0	152.61
10/04/2000	16:21:40	0.74	0	165.48
<i>Average</i>	End	3.8		132.4



INITIAL CEM CALIBRATION AND PERFORMANCE EVALUATION

Plant: New Port Steel Parameter: SO₂, CO₂, O₂, (NO_x) THC
 Location: Bag House Filter Monitor: ppm or %
 Date: 10-3-01 Span Value: 100
 Operator: G. G. Chart Scale: 99.4
 Project #: 5620.001 Pbar, in. Hg.: 29.6

Cylinder #	Cal. Gas Conc., ppm or %	Chart Divisions		Concentration Predicted by Equation,* Direct System		Calibration Error,** % of Span	Sampling System Bias,*** % of Span
		Direct Injection to Monitor	Injection Through System				
	0	0	0	-16	-16	-	-
	49.49	50.2	50.20	49.8	49.8	-1.4	-
	90.7	91	91	90.5	90.5	-1.33	-1.56

- * Perform linear regression of pretest cal. gas concentration vs. chart divisions to determine the following equation:

$$y = mx + b \quad x = \text{ppm} \quad y = \text{chart divisions}$$

For Data Reduction:

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(CD - 16501)}{(1.009)}$$

$$\text{Correlation Coefficient} = .9999$$

Calculation concentration predicted by equation using actual chart response obtained from each calibration gas response.

$$** \text{ Analyzer cal. error, \% cal. gas value} = \frac{(\text{Cal. gas conc., ppm} - \text{conc. predicted, ppm}) \times 100}{\text{Cal. gas value, ppm}}$$

Acceptable limit = $\leq 2\%$ of calibration gas value ($\leq 5\%$ for THC)

$$*** \text{ Sampling system bias} = \frac{(\text{Direct inject. gas conc.} - \text{System inject. gas conc.}) \times 100}{\text{Span value}}$$

Acceptable limit $\leq 5\%$ of span

Minimum detectable limit = 2% of span or _____ ppm or % (circle one)

Rise time to 95% of response for high cal. gas injected through the system (return to zero after each injection): _____ s, _____ s, _____ s Average = _____ s

Precision, % scale = difference in chart division response for two repeated injections of the gas concentrations = _____ - _____ = _____ %
 (Clock time = _____)



DAILY CEM CALIBRATION AND PERFORMANCE EVALUATION

Plant: NEWPORT STEEL Parameter: SO₂, CO₂, O₂, NO_x, THC
 Location: BAG HOUSE INLET Monitor: ppm or %
 Date: 10-3-06 Span Value: 100 -
 Operator: GGM Chart Scale: 49.4
 Project #: 5620.001 Pbar, in. Hg.: 29.66
 Time, Pretest: _____ Post-test: _____ Ambient Temp., F: _____
 Run #: _____

Cyl. #	Cal. Gas Conc., ppm or %	Calibrations (Chart Divisions)				Concentration Predicted By Equation*				Analyzer Calibration Error,** % of Span	Drift,*** % of Span
		1235	1949								
	0	0	0	0	0	-1.6	-1.6	-1.6	-1.6	—	—
	49.4	50.2	52.5	52	53.0	49.85	52.1	51.6	52.6		
	98.7	91	95	91	95.5	90.5	94	90.5	99.9		

- Perform linear regression of pretest cal. gas concentration vs. chart divisions to determine the following equation:

$$y = mx + b \quad x = \text{ppm} \quad y = \text{chart divisions}$$

For Data Reduction:

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(CD - 16501)}{(1.0056)}$$

$$\text{Correlation Coefficient} = \underline{.9997}$$

$$** \text{ Analyzer cal. error, \% cal. gas value} = \frac{(\text{Cal. gas conc.} - \text{conc. predicted}) \times 100}{\text{Cal. gas value, ppm}}$$

Acceptable limit = $\leq 2\%$ of calibration gas value ($\leq 5\%$ for THC)

$$*** \text{ Drift, \% Span} = \frac{(\text{Post-test cal. response} - \text{initial cal. response}) \times 100}{\text{Span value}}$$


Acceptable limit $\leq 3\%$ of span

Minimum detectable limit = 2% of span or _____ ppm or % (circle one)

Maximum zero drift = _____ % of span or _____ ppm or % (circle one)

Maximum calibration drift = _____ % of span or _____ ppm or % (circle one)

COMMENTS: Pretest or post-test (circle one) calibration used to quantitate sample data. Post-test is used if drift exceeds limits and if post-test -



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: New Port Steel
Location: BAG House, F-207
Date: 10-3-00

Parameter: SO₂, CO₂, O₂, NO_x, THC
Operator: G. G. G.
Project #: _____

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} - 1.6501)}{(1.00367)}$$


Run #	Time** (24-Hr)	Average Chart Division	Concentration	Comments
1	1012 1022	3	2.8	
	1022 1032	2	1.8	
	1032 1042	2	1.8	
	1042 1052	8	7.8	
	1052 1102	8	7.8	
	1102 1112	2	1.8	
	1112 1122	2	1.8	
	1122 1132	3	2.82	
	1132 1142	4	3.82	
	1142 1152	4	3.82	3.60
	1152 1202			Process Power 45
	1202 1212			

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one. or describe alternate).

Calculated By: G. G. G.

Date: 10-3-00



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: NEW PORT STEEL
Location: BAG HOUSE INLET
Date: 10-3-00

Parameter: SO₂, CO₂, O₂, NO_x*, THC, CO
Operator: GGY
Project #: 5620.001


$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(CD - 1650)}{(1.00)}$$

Run #	Time** (24-Hr)	Average Chart Division	Concentration	comments
2	1629 1639	2	1.8	
	1639 1649	2	1.8	
	1649 1659	4	3.8	
	1659 1709	5	4.8	
	1709 1719	3	2.8	
	1719 1729	2	1.8	
	1729 1739	4	3.8	
	1739 1749	2	1.8	
	1749 1759	2	1.8	
	1759 1809	2	1.8	
	1809 1819	8	7.8	
	1819 1829	3	2.8	
	1829 1839	3	2.8	
	1839 1849	4	3.8	
	1849 1859	4	3.8	
	1859 1909	4	3.8	
	1909 1919	2	1.8	
	1919 1929	5	4.8	3.38 Ave

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one, or describe alternate).

Calculated By: GGY Date: 10-3-00



DAILY CEM CALIBRATION AND PERFORMANCE EVALUATION

Plant: Newport Steel Parameter: SO₂, CO₂, O₂, NO_x, THC
 Location: BAG House Filter Monitor: ppm or %
 Date: 10-4-00 Span Value: 100
 Operator: GGA Chart Scale: 99.1
 Project #: 5620001 Pbar, in. Hg.: 29.68
 Time, Pretest: _____ Post-test: _____ Ambient Temp., F: _____
 Run #: _____

Cyl. #	Cal. Gas Conc., ppm or %	Calibrations (Chart Divisions)					Concentration Predicted By Equation ^e	Analyzer Calibration Error,** % of Span	Drift,*** % of Span
		725	10	12	1405	1640			
	0	0	0	0			- .40		
	49.49	51				485	50.3		
	90.7	91	88	90	90	91	90.2		

- Perform linear regression of pretest cal. gas concentration vs. chart divisions to determine the following equation:

$$y = mx + b \quad x = \text{ppm} \quad y = \text{chart divisions}$$

For Data Reduction:

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} - .4066)}{(1.004)}$$

$$\text{Correlation Coefficient} = \underline{.9997}$$

$$\text{** Analyzer cal. error, \% cal. gas value} = \frac{(\text{Cal. gas conc.} - \text{conc. predicted}) \times 100}{\text{Cal. gas value, ppm}}$$

Acceptable limit = $\leq 2\%$ of calibration gas value ($\leq 5\%$ for THC)

$$\text{*** Drift, \% Span} = \frac{(\text{Post-test cal. response} - \text{initial cal. response}) \times 100}{\text{Span value}}$$


Acceptable limit $\leq 3\%$ of span

Minimum detectable limit = 2% of span or _____ ppm or % (circle one)

Maximum zero drift = _____ % of span or _____ ppm or % (circle one)

Maximum calibration drift = _____ % of span or _____ ppm or % (circle one)

COMMENTS: Pretest or post-test (circle one) calibration used to quantitate sample data. Post-test is used if drift exceeds limits and if post-test yields higher concentrations.



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: Newport Steel
Location: Bag House Inlet
Date: 10-9-00

Parameter: SO₂, CO₂, O₂, NO_x*, THC, CO
Operator: GGA
Project #: 5620.001

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} - 1.066)}{(1.004)}$$

Run #	Time** (24-Hr)	Average Chart Division	Concentration	Comments
4	1245 1255	6	5.65	
	1255 1305	3	2.5	
	1305 1315	4	3.57	
	1315 1325	3	2.5	
	1325 1335	4	3.57	
	1335 1345	2	1.58	
	1345 1355	11	10.5	
	1355 1405	6	5.56	
	1422 1432	3	2.5	
	1432 1442	2	1.58	
	1442 1452	6	5.56	
	1452 1502	5	4.5	
	1502 1512	2	1.58	
	1512 1522	7	6.56	
	1522 1532	7	6.56	
	1532 1542	4	3.57	
	1542 1552	2	1.58	
	1552 1602	2	1.58	

START TO
CAL

4.0

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one. or describe alternate).

Calculated By: GGA

Date: 10-9-00



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: New Port Steel
Location: BAG House Inlet
Date: 10-4-00

Parameter: SO₂, CO₂, O₂, NO_x, THC, CO
Operator: G. GAY
Project #: 5620.001

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} - .4066)}{(1.004)}$$

Run #	Time** (24-Hr)	Average Chart Division	Concentration	Comments
	1602 1612	5	4.57	
	1612 1622	1	1	
	1632			


3.78

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one, or describe alternate).

Calculated By: C. Brown

Date: 10-4-00



CEM DATA REDUCTION - 8AG ANALYSIS OR STEADY READINGS

Plant: Newport Steel

Parameter: SO₂, CO₂, O₂, (NO_x), THC, CO

Location: Bag House F-6

Operator: GGAY

Date: 10-4-00

Project #: _____

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD } 140667)}{(1.004)} = \frac{140667}{1.004}$$

Run #	Time** (24-Hr)	Average Chart Division	Concentration	Comments
3	800 810	2	1.5	
	810 820	3	2.5	
	820 830	3	2.5	
	830 840	3	2.5	
	840 850	8	7.5	
	850 900	6	5.5	
	900 910	6	5.5	
	910 920	3	2.5	
	920 930	2	1.5	
	930 940	2	1.5	
	940 950	2	1.5	
	950 1000	2	1.5	1.65 Ave
	1000 1010			

3.52


* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one, or describe alternate).

Calculated By: SSB

Date: 10-4-00

14



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: Newport Steel
Location: BAG House Inlet
Date: 10-4-00

Parameter: SO₂, CO₂, O₂, (NO_x)*, THC, CO
Operator: G G 14
Project #: 5620.001

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} - \frac{(\text{CD} - 4067)}{(1.004)}$$

Run #	Time** (24-Hr)	Average Chart Division	Concentration	comments
3	1045 1055	2.5	2.08	
	1055 1105	1.5	1.08	
	1105 1115	1.5	1.08	
	1115 1125	2.5	2.08	
	1125 1135	4	3.5	
	1135 1145	4	3.5	
	1145 1155	1.5	1.08	
	1155 1200	1.5	1.08	

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one. or describe alternate).

Calculated Av: Calc...

Date: 10-24-00



INITIAL GEM CALIBRATION AND PERFORMANCE EVALUATION

Plant: New Port Steel
 Location: BNC House, Fuli
 Date: 10-3-00
 Operator: Gene
 Project #: 5620.00

Parameter: SO₂, CO₂, O₂, NO_x, THC
 Monitor: ppm or %
 Span Value: 100
 Chart Scale: 999.7
 Pbar, in. Hg.: 29.66

Cylinder #	Cal. Gas ppm or	Chart Divisions		Concentration Predicted by Equation,* Direct System		Calibration Error,** % of Span	Sampling System % of Span
		Direct Injection to Monitor	Injection Through				
	0	0	0	-6.6	-6.6		
	300.2	31.5	31.5	309.8	309.8		
	600.6	60.5	60.5	601.2	601.2		
	896.4	89.5	89.5	892.7	892.7		

- * Perform linear regression of pretest cal. gas concentration vs. chart divisions to determine the following equation:

$$y = mx + b \quad x = \text{ppm} \quad y = \text{chart divisions}$$

For Data Reduction:

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(CD - 66.385)}{(1.099815)}$$

$$\text{Correlation Coefficient} = .9499$$

Calculation concentration predicted by equation using actual chart response obtained from each calibration gas response.

$$\text{** Analyzer cal. error. \% cal. gas value} = \frac{(\text{Cal. gas conc., ppm} - \text{conc. predicted. ppm}) \times 100}{\text{Cal. gas value, ppm}}$$

Acceptable limit = $\leq 2\%$ of calibration gas value ($\leq 5\%$ for THC)

$$\text{*** Sampling system bias} = \frac{(\text{Direct inject. gas conc.} - \text{System inject. gas conc.}) \times 100}{\text{Span value}}$$

Acceptable limit $\leq 5\%$ of span

Minimum detectable limit = 2% of span or _____ ppm or % (circle one)

Rise time to 95% of response for high cal. gas injected through the system

(return to zero after each injection): _____ s, _____ s, _____ s Average = _____ s

Precision, % scale = difference in chart division response for two repeated

injections of the gas concentrations = _____ = _____ %

(Clock time = _____)



DAILY CEM CALIBRATION AND PERFORMANCE EVALUATION

Plant: New Port Steel Parameter: SO₂, CO₂, O₂, NO_x, THC
 Location: BAL House FULC Monitor: ppm or %
 Date: 10-30-00 Span Value: 100 -
 Operator: nd Chart Scale: _____
 Project #: 5620.001 Pbar, in. Hg.: 39.64
 Time, Pretest: _____ Post-test: _____ Ambient Temp., F: _____
 Run #: _____

Cyl. #	Cal. Gas Conc., ppm or %	Calibrations (Chart Divisions)				Concentration Predicted By Equation*	Analyzer Calibration Error,** % of Span	Drift,*** % of Span
		1619	1932					
	0	0	0	0	0	-6.6		
	300.7	31.5	31.5	32.5	32.5	309.9		
	600.6	60.5	60.0	60.5	60.5	601.2		
	896.4	89.5	88	86.5	86.5	892.7		

- Perform linear regression of pretest cal. gas concentration vs. chart divisions to determine the following equation:

$$y = mx + b \quad x = \text{ppm} \quad y = \text{chart divisions}$$

For Data Reduction:

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} -)}{()}$$

Correlation Coefficient = _____

** Analyzer cal. error, % cal. gas value = $\frac{(\text{Cal. gas conc.} - \text{conc. predicted}) \times 100}{\text{Cal. gas value, ppm}}$

Acceptable limit = $\leq 2\%$ of calibration gas value ($\leq 5\%$ for THC)

*** Drift % Span = $\frac{(\text{Post-test cal. response} - \text{initial cal. response}) \times 100}{\text{Span value}}$


Acceptable limit $\leq 3\%$ of span

Minimum detectable limit = 2% of span or _____ ppm or % (circle one)

Maximum zero drift = _____ % of span or _____ ppm or % (circle one)

Maximum calibration drift = _____ % of span or _____ ppm or % (circle one)

COMMENTS: Pretest or post-test (circle one) calibration used to quantitate sample data. Post-test is used if drift exceeds limits and if post-test



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: NEW PORT STEEL
Location: Bag House Filter
Date: 10-3-00

Parameter: SO₂, CO₂, O₂, ~~NO_x~~, THC CO
Operator: G Gay
Project #: _____


$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} - 15)}{(1.5)} = \frac{166.285}{1.5} = 110.857$$

Run #	Time** (24-Hr)		Average Chart Division	Concentration	Comments
1	1012	1022	28	275	
	1022	1032	15	142	
	1032	1042	12	113	
	1042	1052	9	83	
	1052	1102	2	13.4	
	1102	1112	4	33.5	
	1112	1122	4	33.5	
	1122	1132	3	23.4	
	1132	1142	2	13.4	
	1142	1152	2	13.4	74.56
	1152	1202			Process Down 45
	1202	1212			

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one, or describe alternate).

Calculated By: G. Gay Date: 10-3-00



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: New Steel
Location: BAG House Filter
Date: 10.3.00

Parameter: SO₂, CO₂, O₂, NO_x*, THC, CO
Operator: G Gay
Project #: 5620.001

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} -)}{()}$$

Run #	Time** (24-Hr)	Average Chart Division	Concentration	Comments
2	1629 1639	11	97	
	1639 1649	11	97	
	1649 1659	6	45.1	
	1659 1709	2.0	3.5	
	1709 1719	2.0	3.5	
	1719 1729	1.0	1.0	
	1729 1739	1.5	1.5	
	1739 1749	5.8	430	
	1749 1759	1.0	1.0	
	1759 1809	1.5	1.5	
	1809 1819	1.2	1.2	
2	1819 1829	2	65.9	
	1829 1839	22	211	
	1839 1849	10	86.7	
	1849 1859	18	169.8	
	1859 1909	13	117	
	1909 1919	10	86.6	
	1919 1929	3	22.2	58.6 Ave

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one. or describe alternate).

Calculated By: G Gay

Date: 10.3.0.



DAILY CEM CALIBRATION AND PERFORMANCE EVALUATION

Plant: New Port Steel
Location: Bag House Filter
Date: 10-4-00
Operator: G. G. G.
Project #: 5620-001
Time, Pretest: _____
Post-test: _____
Run #: _____

Parameter: SO₂, CO₂, O₂, NO_x, THC
Monitor: ppm or %
Span Value: 100
Chart Scale: 1015
Pbar, in. Hg.: 29.68
Ambient Temp., F: _____

Cyl. #	Cal. Gas Conc., ppm or %	Calibrations (Chart Divisions)	Concentration Predicted By Equation*	Analyzer Calibration Error, % of Span**	Drift, % of Span***
	0	0	0	-12.0	
	300.2	32	333	316	
	600.6	60	615	604	
	896.4	81.5	82.5	86.5	888

* Perform linear regression of pretest cal. gas concentration vs. chart divisions to determine the following equation:

$$y = mx + b \quad x = \text{ppm} \quad y = \text{chart divisions}$$

For Data Reduction:

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{(CD - 1.1929)} = \frac{m}{(.09727)}$$

$$\text{Correlation Coefficient} = .9999$$

$$\text{** Analyzer cal. error, \% cal. gas value} = \frac{(\text{Cal. gas conc.} - \text{conc. predicted}) \times 100}{\text{Cal. gas value, ppm}}$$

Acceptable limit = $\leq 2\%$ of calibration gas value ($\leq 5\%$ for THC)

$$\text{*** Drift, \% Span} = \frac{(\text{Post-test cal. response} - \text{initial cal. response}) \times 100}{\text{Span value}}$$

Acceptable limit $\leq 3\%$ of span

Minimum detectable limit = 2% of span or _____ ppm or % (circle one)


Maximum zero drift = _____ % of span or _____ ppm or % (circle one)

Maximum calibration drift = _____ % of span or _____ ppm or % (circle one)

COMMENTS: Pretest or post-test (circle one) calibration used to quantitate

sample data. Post-test is used if drift exceeds limits and if post-test

yields higher concentrations.



CEM DATA REDUCTION - ~~BAG~~ ANALYSIS OR STEADY READINGS

Plant: New port Steel
Location: BAG House Filter
Date: 10-4-00

Parameter: SO₂, CO₂, O₂, NO_x*, THC, CO
Operator: GGH
Project #: 5620.001

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} - 1.1929)}{(1.09727)}$$


Run #	Time** (24-Hr)	Average Chart Division	Concentration	comments
3	800 810	8.5	75	
	810 820	15	141	
	820 830	15	141	
	830 840	17	162	
	840 850	9	80	
	850 900	1	1.9	
	900 910	1.5	3.1	
	910 920	4	28.8	
	920 930	8	69.9	
	930 940	8	69.9	
	940 950	20	193	
	950 1000	25	244	100
	1000 1010			

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one, or describe alternate).

Calculated By: GGH

Date: 10-4-00



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: Newport Steel
Location: Bldg House Inlet
Date: 10-4-00

Parameter: SO₂, CO₂, O₂, NO_x*, THC (CO)
Operator: SGM
Project #: 5620001

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(CD - 1.1925)}{(.09727)}$$

Run #	Time** (24-Hr)	Average Chart Division	Concentration	Comments
3	1045 1055	10	90	
	1055 1105	15	142	
	1105 1115	9	80	
	1115 1125	9	80	
	1125 1135	3	18.5	
	1135 1145	5	39	
	1145 1155	7	59.6	
	1155 1200	4	28	


* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one, or describe alternate).

Calculated By: SGM Date: 10-4-00

71.7

29



CEM DATA REDUCTION - BAG ANALYSIS OR STEADY READINGS

Plant: New Port Steel
Location: Bay House Inn
Date: 10-4-00

Parameter: SO₂, CO₂, O₂, NO_x*, THC, (CO)
Operator: G. Gar
Project #: 5620.001

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} = \frac{(\text{CD} - 1.1926)}{(109727)}$$

Run #	Time** (24-Hr)	Average Chart Division	Concentration	comments
4	1245 1255	15	3.15	
	1255 1305	8	70	
	1305 1315	15	141	
	1315 1325	10	90	
	1325 1335	13	121	
	1335 1345	25	244	
	1345 1355	12	111	
	1355 1405	2	8.2	
	1422 1432	15	141	
	1432 1442	32	316	
	1442 1452	2.0	8.2	
	1452 1502	1.5	1.5	
	1502 1512	20	193	
	1512 1522	2.0	8.2	
	1522 1532	4.5	33	
	1533 1542	15	141	
	1542 1552	15	141	
	1552 1602	15	141	

STOP
TO
CAL

103
103
103

* For NO_x Indicate whether NO, NO + NO₂, or NO₂ for specific interval.

** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one, or describe alternate).

Calculated By: G. Gar

Date: 10-4-00



Parameter: SO₂, CO₂, O₂, NO_x*, THC, CO
Operator: G Gay
Project #: 5620.001

$$\text{Pollutant, ppm/\%} = \frac{(\text{Chart Division} - b)}{m} - \frac{(\text{CD} - 1.1926)}{(.09727)}$$

[illegible]

**** Indicate whether time interval is from beginning of first time to beginning of second time or to end of second time (circle one, or describe alternate).**

Calculated By: Colby Date: 10-4-06

22

PES, Inc.
5209 E. Kemper Rd.
Cincinnati, OH **45249**
513.489.6611
www.pes.com

CEM Operator: GG44
Date: 10-4-00

[illegible]

CEM Calibration Data Sheet

PES, Inc.
5209 E. Kemper Rd.
Cincinnati, OH 45249
513.489.6611
www.pes.com

Company: NEW POST STEEL
Location: 3RD HOUSE TRWT
Project No.: 56 20.001

CEM Operator: G. G. M.
Date: 10-3-00

[illegible]



Scott Specialty Gases

1290 COMBERMERE STREET, TROY, MI 48083

RATA CLASS

Dual-Analyzed Calibration Standard

Phone: 248-589-2950

248-589-2134



CERTIFICATE OF ACCURACY: EPA Protocol Gas

Assay Laboratory

SCOTT SPECIALTY GASES
1290 COMBERMERE STREET
TROY, MI 48083

P.O. No.: 103-00-224
Project No.: 05-63123-001

Customer

PACIFIC ENVIRONMENTAL SERVICES, INC
DOUG ALLEN
7209 E. KEMPER RD
CINCINNATI OH 45249-1030

ANALYTICAL INFORMATION

This certification was performed according to EPA Traceability Protocol For Assay & Certification of Gaseous Calibration Standards; Procedure #G1, September, 1997.

Cylinder Number: **ALM058040** Certification Date: **6/23/00** Exp. Date: **6/23/2002**
Cylinder Pressure: **1900 PSIG**

COMPONENT

NITRIC OXIDE

NITROGEN - OXYGEN FREE

CERTIFIED CONCENTRATION (Moles)

49.49 PPM

BALANCE

ANALYTICAL

ACCURACY++

+/- 1%

TRACEABILITY

Direct NIST and NMI

TOTAL OXIDES OF NITROGEN

52.081 PPM

Reference Value Only

*** Do not use when cylinder pressure is below 150 psig.

** Analytical accuracy is based on the requirements of EPA Protocol procedure G1, September 1997.

Product certified as +/- 1% analytical accuracy is directly traceable to NIST or NMI standards.

REFERENCE STANDARD

TYPE/SRM NO.	EXPIRATION DATE	CYLINDER NUMBER	CONCENTRATION	COMPONENT
SRM 1683B	11/01/01	CAL013527	47.99 PPM	NITRIC OXIDE

INSTRUMENTATION

INSTRUMENT/MODEL/SERIAL#

HORIBA/OPE235/563956034

DATE LAST CALIBRATED

06/23/00

ANALYTICAL PRINCIPLE

CHEMILUMINESCENCE

ANALYZER READINGS

(Z=Zero Gas R=Reference Gas T=Test Gas r=Correlation Coefficient)

First Triad Analysis

Second Triad Analysis

Calibration Curve

NITRIC OXIDE

Date: 06/16/00	Response Unit: MV		
Z1 = 0.00000	R1 = 100.0000	T1 = 48.50000	
R2 = 100.0000	Z2 = 0.00000	T2 = 48.80000	
Z3 = 0.00000	T3 = 48.60000	R3 = 100.0000	
Avg. Concentration: 49.32 PPM			

Date: 06/23/00	Response Unit: MV		
Z1 = 0.00000	R1 = 100.0000	T1 = 48.90000	
R2 = 100.0000	Z2 = 0.00000	T2 = 48.90000	
Z3 = 0.00000	T3 = 49.10000	R3 = 100.0000	
Avg. Concentration: 49.66 PPM			

Concentration = A + Bx + Cx ² + Dx ³ + Ex ⁴	
r = .999997	16838
Constants:	A = -0.04993
B = 1.031701	C = -0.00034
D = 0	E = 0

APPROVED BY:



Praxair Distribution, Inc.
145 Shimersville Road
Bethlehem, PA 18015
Tel (610) 691-2474
Fax (610) 758-8384

CERTIFICATE OF ANALYSIS / EPA PROTOCOL GAS

CUSTOMER PRAXAIR CINCINNATI

P.O NUMBER 936353-00

REFERENCE STANDARD

COMPONENT	NIST SRM NO.	CYLINDER NO.	CONCENTRATION
NITRIC OXIDE 99.8 PPM VS	1684B	CAL-013252	97.8 PPM

ANALYZER READINGS

R = REFERENCE STANDARD

Z = ZERO GAS

C = GAS CANDIDATE

I. COMPONENT		NITRIC OXIDE 99.8 PPM VS.		ANALYZER MAKE-MODEL-S/N		TECO MODEL 42C 42CH-57352-312	
ANALYTICAL PRINCIPLE		Chemiluminescence		LAST CALIBRATION DATE		09/03/99	
FIRST ANALYSIS DATE		09/01/99		SECOND ANALYSIS DATE		09/08/99	
Z 0	R 99.9	C 90.9	CONC. 90.6	Z 0	R 100.0	C 90.9	CONC. 90.7
R 100.4	Z 0	C 91.0	CONC. 90.7	R 100.1	Z 0	C 91.0	CONC. 90.8
Z 0	C 90.9	R 100.2	CONC. 90.6	Z 0	C 91.0	R 100.0	CONC. 90.8
U/M	PPM	MEAN TEST ASSAY 90.6		U/M	PPM	MEAN TEST ASSAY 90.8	

VALUES NOT VALID BELOW 150 PSIG

UNCERTAINTY OF NITRIC OXIDE: ± 0.6 PPM

THIS CYLINDER NO. CC76285
HAS BEEN CERTIFIED ACCORDING TO SECTION 2.2
OF TRACEABILITY PROTOCOL NO. EPA-600/R97/121
PROCEDURE G1
CERTIFIED ACCURACY ± 1 % NIST TRACEABLE
CYLINDER PRESSURE 2000 PSIG
CERTIFICATION DATE 09/08/99
EXPIRATION DATE 09/08/01 TERM

CERTIFIED CONCENTRATION

NITRIC OXIDE	90.7 PPM
NITROGEN	BALANCE
NOx (FOR REFERENCE ONLY)	90.7 PPM

ANALYZED BY

JOHN PRIBISH

CERTIFIED BY

JASON BEARY



Praxair Distribution, Inc.
145 Shimersville Road
Bethlehem, PA 18015
Tel. (610) 691-2474
Fax (610) 758-8384

CERTIFICATE OF ANALYSIS .

PRODUCT NUMBER: NI COXP-AS

CUSTOMER: PRAXAIR CINCINNATI

PRODUCT DESCRIPTION: 300 PPM CARBON MONOXIDE, BALANCE NITROGEN-SIZE AS

CUSTOMER ORDER NUMBER: 987890-00

* PRIMARY STANDARD *

CYLINDER SERIAL NUMBER: CC103091

FILL DATE: JANUARY 23, 1999

COMPONENTS =====	REQUESTED CONCENTRATION =====	PREPARATION TOLERANCE =====	CERTIFIED CONCENTRATION =====
CARBON MONOXIDE	300 PPM	±5%	300.2 PPM
NITROGEN	BALANCE	-	BALANCE

ANALYTICAL ACCURACY: ±1%

CYLINDER VOLUME: 135 CUBIC FEET

CYLINDER PRESSURE: 2000 PSIG

CGA VALVE NUMBER: 350

METHOD OF ANALYSIS: SPECIFIC CARBON MONOXIDE ANALYZER

Certified concentrations were determined by individual analysis.

DATE: JANURAY 28, 1999

ANALYZED BY: DARLENE SANTIAGO

CERTIFIED MASTER CLASS

Single-Certified Calibration Standard



Scott Specialty Gases

1290 COMBERMERE STREET, TROY, MI 48063

Phone: 248-589-2950

Fax: 248-589-2134

CERTIFICATE OF ACCURACY: Certified Master Class Calibration Standard

Product information

Project No.: 05-63123-004

Item No.:

P.O. No.: 103-00-224

Cylinder Number: AAL9143

Cylinder Size: AL

Certification Date: 6/15/2000

Expiration Date: 6/15/2003

Customer

PACIFIC ENVIRONMENTAL SER

DON ALLEN

560 HERNDON PARKWAY

SUITE 200

HERNDON, VA 20170-5240

CERTIFIED CONCENTRATION

Component Name

Concentration
(Moles)

Accuracy
(+/-%)

CARBON MONOXIDE
NITROGEN

450. PPM
BALANCE

2

TRACEABILITY

Traceable To

NIST

APPROVED BY:

DATE:

6-16-00



Praxair Distribution, Inc.
145 Shimersville Road
Bethlehem, PA 18015
Tel. (610) 691-2474
Fax (610) 758-8384

CERTIFICATE OF ANALYSIS

PRODUCT NUMBER: NI COXP-AS CUSTOMER: PRAXAIR CINCINNATI
PRODUCT DESCRIPTION: 600 PPM CARBON MONOXIDE, BALANCE NITROGEN-SIZE AS
CUSTOMER ORDER NUMBER: 987890-00 * PRIMARY STANDARD *
CYLINDER SERIAL NUMBER: CC102910
FILL DATE: JANUARY 23, 1999

COMPONENTS =====	REQUESTED CONCENTRATION =====	PREPARATION TOLERANCE -----	CERTIFIED CONCENTRATION =====
CARBON MONOXIDE	600 PPM	±5%	600.6 PPM
NITROGEN	BALANCE	-	BALANCE

ANALYTICAL ACCURACY: ±1%
CYLINDER VOLUME: 135 CUBIC FEET
CYLINDER PRESSURE: 2000 PSIG
CGA VALVE NUMBER: 350
METHOD OF ANALYSIS: SPECIFIC CARBON MONOXIDE ANALYZER

Certified concentrations were determined by individual analysis.

DATE: JANURAY 28, 1999

ANALYZED BY: DARLENE SANTIAGO



Praxair Distribution, Inc.
145 Shimersville Road
Bethlehem, PA 18015
Tel (610) 691-2474
Fax (610) 758-8384

CERTIFICATE OF ANALYSIS

PRODUCT NUMBER: NI COXP-AS

CUSTOMER: PRAXAIR WHSE CINCINNATI

PRODUCT DESCRIPTION: 896 PPM CARBON MONOXIDE BALANCE NITROGEN - **SIZE** AS

CUSTOMER ORDER NUMBER: 212761-00

CYLINDER NUMBER: SA2558

• PRIMARY STANDARD*

FILL DATE: **JUNE** 07, 1999

<u>COMPONENTS</u>	<u>SPECIFICATIONS</u>	<u>PREPARATION TOLERANCE</u>	<u>CERTIFIED CONCENTRATION</u>
CARBON MONOXIDE	896 PPM	+/-5%	896.4 PPM
NITROGEN	BALANCE		BALANCE

Certified concentration ~~was~~ determined by individual analysis.

ANALYTICAL ACCURACY: +/-1%

CYLINDER VOLUME: 135 Cubic Feet

CGA VALVE NUMBER: 350

CYLINDER PRESSURE: 2000 psig

METHOD OF ANALYSIS: SPECIFIC CARBON MONOXIDE ANALYZER

CERTIFICATION DATE: JUNE 09, 1999


ANALYZED BY: DARLENE SANTIAGO


It is recommended that cylinders not be depleted below **50 psig** unless otherwise indicated.

14m80cm

CHART NO 892/AA/NN


(17) 11








CO DMS


14m80cm




















CHART NO. 28529A/NM

(17781)


[illegible]











WART No. 1000 JAA/ML











Appendix D

Process Data

PRODUCTION WORKSHEET

Heats During Tests

Date	Heat No.	Tons	Tap-Tap Time, min	Operating Time, hr	Tons/Hr
TEST 1					
3-Oct	6535	94.8	65	1.1	87.5
	6536	93.4	67	1.1	83.6
	6537	92.4	137	2.3	40.5
	Totals	280.6	269	4.5	62.6 tons/hr
TEST 2					
4-Oct	6548	92.8	70	1.2	79.5
	6549	94.4	89	1.5	63.6
	6550	95.3	72	1.2	79.4
	6551	94.8	71	1.2	80.1
	Totals	377.3	302	5.0	75.0 tons/hr
TEST 3					
4-Oct	6551	94.80	71	1.2	80.1
	6552	95.20	72	1.2	79.3
	6553	93.00	84	1.4	66.4
	6554	95.40	104	1.7	55.0
	Totals	378.4	331	5.5	68.6 tons/hr

1491
470

10-4-00, Daily Heat Report

1491
470

10-4-00, Daily Heat Report

Hit #	Grade	Melter	Tap Time	Tap Temp	Power on	KWH	Oxy.	Gas	Carb.	Tap " "	Tap C	Ladle	Scp chg	Tap wt	Heal wt	Tap se	Elect+	Al.	Carb	Sil.	Mn	Time	Delay	
6540	6545	LN3	11:32A	1:27	46.5	42.9	37.3	14.0	4140	3079	4.5	—	218	95.5	8+	130	1340	250	175	374	2472	2018	92	
6541	"	"	12:41	1:09	47.4	44.8	49.8	11.8	4220	3150	5.5	—	218	91.2	8+	125	—	250	150	374	2473	2022	92	
6542	UN80	"	1:59A	1:18	45.7	42.9	28.6	10.5	4260	3128	5.7	—	218	91.6	8+	125	—	250	75	382	2573	2019	91	
6543	"	"	3:03A	1:04	46.7	45.0	32.3	11.5	4120	3063	10.9	—	4	216.2	95.5	8+	125	—	250	0	375	2573	2021	91
6544	"	"	4:09A	1:02	46.1	43.9	31.4	11.1	4150	3090	10.1	—	2	218.1	92.2	10T	125	—	250	25	378	2575	2017	92
6545	"	"	5:25A	1:20	46.9	44.9	32.8	12.1	4160	3139	10.3	—	6	217.9	95.4	10T	125	—	250	0	350	2576	2000	11
6546	"	"	6:32A	1:07	43.7	42.4	23.2	8.8	4140	3030	10.0	—	8	217.2	94.1	10T	125	—	250	25	345	2580	2003	11
6547	"	"	7:40A	1:09	45.6	43.2	29.2	9.7	4130	3097	10.8	—	4	215.7	93.2	2T	120	—	250	0	356	2577	2009	12
6548	"	"	8:54A	1:10	44.0	40.9	40.1	15.2	4200	3031	10.2	—	6	215.2	92.8	3T	120	—	250	0	376	2572	2021	11
6549	"	"	10:21	1:09	49.2	45.9	29.8	9.7	4300	3105	0.91	—	3	218.2	94.4	5T	115	—	250	50	380	2371	2019	11
6550	355	45	11:31A	1:12	48.4	46.2	35.1	11.9	4260	3173	10.2	—	4	220.0	95.3	5T	115	—	250	0	0	1822	2016	11
6551	355	45	12:45A	1:11	46.9	44.8	26.6	10.1	4200	3083	9.8	—	8	218	94.8	5T	115	—	250	25	0	1932	2014	11
6552	355	45	1:35A	1:12	43.9	40.1	24.2	74.7	4200	3066	11.3	—	6	218	95.2	5T	115	—	250	50	0	1815	2013	11
6553	355	45	2:20A	1:24	43.4	39.9	29.9	13.0	4200	3065	10	—	3	218	93.0	4T	115	—	250	125	0	1816	2014	11
6554	355	45	3:04A	1:30	47.0	43.1	20.8	10.4	4200	3065	10	—	4	214	95.4	6T	—	—	300	175	0	1943	2015	11
6555	355	45	3:53A	1:31	44.8	42.0	19.2	10.9	4300	3081	0.9	—	6	217	92.4	9T	111	—	300	175	6	1931	2016	11
6556	355	45	4:41A	1:21	43.7	41.0	16.1	10.1	4200	3040	1.0	—	2	218	94.8	7T	111	—	300	200	0	1965	2013	11
6557	355	45	5:30A	1:15	42.1	39.5	15.7	10.4	4180	3049	0.9	—	4	217	95.5	7T	111	—	300	200	0	1941	2011	11
6558	355	45	6:22A	1:12	44.9	42.6	17.0	10.4	4180	306	1.0	—	8	218	95.4	6T	111	—	300	125	0	1967	2011	11

light shift info.

Elect. acids etc.

night shift info.

Day shift info.

Alt. Shift info.	
------------------	--

	Elect. add's etc...
--	---------------------

Acq	Series

5 Hyd.
6 Water
7 Elect.
8 Other

Sat. Pres. - 2.99 11:30 P

	Elect. add.	Stat. Pres.	Damp pos.
100			
200			
300			
400			
500			
600			
700			
800			
900			
1000			
1100			
1200			
1300			
1400			
1500			
1600			
1700			
1800			
1900			
2000			
2100			
2200			
2300			
2400			
2500			
2600			
2700			
2800			
2900			
3000			
3100			
3200			
3300			
3400			
3500			
3600			
3700			
3800			
3900			
4000			
4100			
4200			
4300			
4400			
4500			
4600			
4700			
4800			
4900			
5000			
5100			
5200			
5300			
5400			
5500			
5600			
5700			
5800			
5900			
6000			
6100			
6200			
6300			
6400			
6500			
6600			
6700			
6800			
6900			
7000			
7100			
7200			
7300			
7400			
7500			
7600			
7700			
7800			
7900			
8000			
8100			
8200			
8300			
8400			
8500			
8600			
8700			
8800			
8900			
9000			
9100			
9200			
9300			
9400			
9500			
9600			
9700			
9800			
9900			
10000			

15/4

	Elect. address	Stat. Pres.	Demo no:
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			

day	1	Sciap
di	11	2 Crane

5 Hyd.	
6 Water	
7 Elect.	
8 Other	

Amplitude	1	2
100	100	100
90	90	90
80	80	80
70	70	70
60	60	60
50	50	50
40	40	40
30	30	30
20	20	20
10	10	10
0	0	0

Damp pos.
Amor. "

•

Damp pos.

10

6 Water
7 Elect.
8 Other

08:09 651 751 402

6.11.17

Amps

Gun

Other

10-3-2011

HT #	Grade	Melter	Tap Time	Tap-Tap	Power on	KWH	Oxy.	Gas	Carb.	Tap "T"	Tap C	Tap S	Ladle	Scp chg	Tap wt	Heat wt	Tap se	Elect+	Al.	Carb	Sil.	Mn	Lime	Delay
6529	555	101	12:23	11:34	46.7	45.5	24.0	91.4	4100	3099	11.3	—	2	217.7	95.2	101	140	—	250	75	0	1863	2004	Auto
6530	"	"	12:28	1:05	45.9	45.0	30.9	108	4300	3025	9.3	—	4	217.7	94.6	101	140	—	250	75	0	1868	2007	"
6531	"	"	4:12	2:38	47.1	45.8	215	811	4100	3042	12.1	—	6	216.3	94.2	101	140	—	250	0	0	1868	2002	"
6532	"	"	5:12	1:02	48.4	49.9	288	892	4120	3060	10.0	—	2	218.7	95.6	101	140	—	250	50	0	1865	2000	"
6533	"	"	1:02	1:28	45.8	44.8	259	10.4	4600	3140	0.1	—	8	217.8	94.8	101	140	—	300	175	0	1867	2004	"
6534	"	RW	7:23	1:17	48.0	46.1	32.2	14.8	4100	3188	0.1	—	6	217.5	93.4	77	140	—	300	175	0	2018	2004	"
6535	"	"	10:53	3:07	50.2	45.6	216	2081	4040	2150	7.1	—	4	215.6	94.8	47	—	—	300	75	0	2023	2020	"
6536	"	RQ	5:31	—	44.3	41.8	387.0	2118.9	5120	3072	0.6	—	8	219.8	93.4	77	—	—	300	175	0	2020	1993	"
6537	"	"	7:31	2:15	48.9	46.7	587.0	856.7	4100	3023	0.6	—	2	22.0	92.4	87	—	—	400	175	0	2167	2019	"
6538	US-45	"	8:58	1:10	45.0	42.2	559.0	13183	4460	3026	0.5	—	4	219	94.8	87	135	—	300	75	28	2466	2019	MAN
6539	"	"	10:05	1:27	43.7	40.3	535.0	18274	4360	3053	0.5	—	2	219	93.6	87	137	—	200	125	371	2466	2019	"

10-3-2011

Elect. adds etc. ADD 350 ASUP 12 Day shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Sial. Pres. -3.41 3:30 AM

Damp pos.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Damp pos.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

Am. Shift info.

Am. Shift info.

Elect. adds etc. Sial. Pres. -1.38 8¹⁸

Am. Shift info.

Delay

1 Scrap

3 Hyd.

HEAT LOG

SEQ. No. 148034

DATE 10-3-00

GRADE J-85

CODE 84

HEAT No. D6535

CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS												L.S.	
TIME MELT	TO LAB.	REC'D	MADE	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Va	Cb	AL	FEO	
				26/28	95/28	015	008	08/15	30	15	12	03			029/040		
POWER				ACTUAL TIME													
ON	OFF			TAPPED PREVIOUS HEAT	BEGAN CHARGE	POWER ON	FINISH CHARGE	SLAG OFF START	SLAG OFF FINISH	TAPPED	TIME OF HEAT						
				7:47/A		9:50/A				10:55/A	1:05						
ELAPSED TIME																	
TEST	TEST	TEST	TEST	CK	3:50												
THERMOCOUPLE				TIME													
LOADING FURNACE																	
EST																	
TEST																	
TEST																	
CK																	
METALS CHARGED				WEIGHT													
NO. 1 STEEL																	
NO. 1 BUNDLESFACTORY																	
NO. 1 BUNDLES-DEALER				20040													
NO. 2 STEEL				31140													
BUSHLINGS				52240													
BROKEN MOULDS																	
PREPARED PIT SCRAP				8760													
COMPANY SCRAP-CARBON				30840													
COMPANY SCRAP-INGOTS & BUTTS																	
SHREDD				59600													
NO. 2 BUNDLES																	
BORING & TURNINGS																	
TIN PLATE																	
TOTAL				202620													
FURNACE AND LADLE ADDITIONS				WEIGHT													
MILL SCALE																	
NICKEL																	
COPPER																	
H. C. MANGANESE				2023													
FERRO PHOSPHORUS																	
75% FE. SILICON																	
ALUMINUM				39/300													
MOLYBDENUM																	
FE COLUMBIUM (CONT. WGT.)																	
LC. MANGANESE																	
FE. VANADIUM																	
CHROME																	
COKE				375													
CALCIUM				17													
TOTAL				3054													
PRODUCTION				29490													
WEIGHT																	
PRO- DUCT																	
NO. OF SLABS				6													
MOLD SIZE				8 1/2 x 28 1/2													
MOLD CODE																	
SLABS				176940													
SLABS																	
INGOTS																	
FRONT ENDCROPS																	
TAIL ENDCROPS																	
SKULL																	
TONS IN TUNDISH																	
PIT																	
TOTAL INGOT WEIGHT																	
TONNAGE				WEIGHT													
TOTAL CHARGED				102837													
TOTAL PRODUCED				88470													
YIELD				%													
FURNACE DELAYS AND REMARKS				TIME													
STRIPPING				ELAPSED TIME													
ip				TYPE													
me																	
WEIGHMASTER																	
CLOCK TIME OF RECARB OR DECARB																	

DATE 10-3-

CHARGE		WEIGHT	TYPE	HOW LOADED	TIME	CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS	C	M
					9:50/A	C.	TIME MELT	TO LAB.	REC'D	ORDERED	26/29	95
										MADE		
										Prelim.		
										Prelim.		
										Prelim.	071	
										Prelim.		
										Prelim.		
										Lollypop		
										Ladle Analysis		
ORDERED	FURNACE AND LADLE ALLOWANCE					POWER						
	ALLOYS	%	WEIGHT	TIME	After	ON	OFF					
	FE. MN. FURNACE				Before							
	FE. MN. FURNACE				Total Min.							
	FE. MN. FURNACE				% P. On							
	FE. MN. LADLE	80%	2023		THERMOCOUPLE READING FURNACE		TIME					
	FE. MN. LADLE				1st TEST							
	FE. SI. FURNACE				2nd TEST							
	FE. SI.	25%	0		3rd TEST							
	FE. SI.				4th TEST							
	MISCH ALLOY				BLOCK	3150						
	FE. VANADIUM				TAP							
	MOLYBDENUM				LADLE #1							
	AL. LADLE	8x19	300		LADLE #2							
	AL. MOULDS											
	COKE		25									
	A.K. FLUX											
	RIM. ACCEL. MOULDS											
	FE. COLUMBIUM											
	DESULFURIZER TAP	W-16	2020									
	DESULFURIZER LADLE											
	CALCIUM NO. OF FT.											
	POUNDS OF HOT TOP				Limestone							
	ELAPSED TIME OF TAP	secs	140		Lime							
	ARGON TIME				Lime							
	ARGON GAUGE READING				Coke							
		5002	500		Spar							
		5.6	300		Scale							
		5.6	50		Oxygen After							
					Meter Before							
					O ₂ Used							
ELECTRODE DATA												
PHASE	NO. ADDED	TIME	BY WHOM	SUPPLIER	METER AFTER							
No. 1					METER BEFORE							
No. 2				56L	METER AT MELT							
No. 3					K.W.H. USED TO MELT							
HEATS ON LINING:						ROOF No.						
WALLS						Used: GUN MIX						
						SYNDOLAG						
						COMMENTS						
TAP HOLE												
BANKS												
BOTTOM												
LADLE NO.						NO. HEATS						
STOPPER:						NOZ. SIZE						
						MOLD CONDITION:						
						Start Strip						
						Finish Strip						
						Lapsed Time						
						Delays						
BLEEDERS:												
POURED BY:						PIT FOREMAN						
TESTS: LAB.						JOMINY						
						GR. SIZE						
						Delivered						
MELTER						1st HELPER						
						WEIGHMASTER						
12-8						12-8						
8-4 GB						8-4						
4-12						4-12						
CLOCK TIME OF RECA												

TOTAL

Water Leak

METECH

HEAT LOG

SEQ. No. 113035

DATE 10-3-00 GRADE

CODE

89

HEAT No. 010536

CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS															
TIME MELT	TO-LAB.	REC'D		C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Va	Cb	AL	FEO	L.S.		
				ORDERED	20/28	93/05	015	008	08/15	30	15	12	03						
				MADE															
				Prelim.	.06														
				Prelim.															
				Prelim.	.19			.020											
				Prelim.															
				Lollypop															
				Ladle Analysis															
POWER				ACTUAL TIME															
ON				TAPPED PREVIOUS HEAT		BEGAN CHARGE		POWER ON		FINISH CHARGE		SLAG OFF START		SLAG OFF FINISH		TAPPED		TIME OF HEAT	
				10:55/A		11:05/A		405		421						512		6:10	
OFF				ELAPSED TIME															
				ACTUAL CHARGE TIME		CHARGE TO TAP		MAKE BOTTOMS		CHARGE TO CHARGE		DELAYS		FURNACE PATCH		K.W.H.		TAP TO TAP	
																		6:15	
				METALS CHARGED				WEIGHT				FURNACE AND LADLE ADDITIONS				WEIGHT			
E #1				NO. 1 STEEL								MILL SCALE							
E #2				NO. 1 BUNDLES-FACTORY								NICKEL							
				NO. 1 BUNDLES-DEALER				19120				COPPER							
				NO. 2 STEEL				30160				H. C. MANGANESE				2520			
				BUSHINGS				54400				FERRO PHOSPHORUS							
				BROKEN MOULDS								75% FE SILICON				180			
stone				PREPARED PIT SCRAP				9660				ALUMINUM 110/300				410			
				COMPANY SCRAP-CARBON				33340				MOLYBDENUM							
				COMPANY SCRAP-INGOTS & BUTTS								FE. COLUMBIUM (CONT. WGT.)							
				SHREDD				58820				LC. MANGANESE							
				NO. 2 BUNDLES								FE. VANADIUM							
en After				BORING & TURNINGS								CHROME							
r Before				TIN PLATE								COKE				175			
Used												CALCIUM				31			
				TOTAL				205500								400			
ER AFTER				PRODUCTION 29490				WEIGHT											
ER BEFORE				PRO- DUCT				NO. OF SLABS				MOLD SIZE				MOLD CODE			
ER AT MELT				SLABS				7 8 4 1/2 - 282				206430							
H. USED TO MELT				SLABS															
o.				INGOTS															
				FRONT ENDCROPS															
				TAIL ENDCROPS															
				SKULL															
				TONS IN TUNDISH															
				PIT															
				TOTAL INGOT WEIGHT															
STRIPPING				FURNACE DELAYS AND REMARKS										TONNAGE		WEIGHT			
				Shut-off for waiting for casters to start										11:05 - 405		5:00			
ip				F.D. won't open										455 500		:05		/	
me				Wait for Hecker to push ladle car												:10		/	
WEIGHMASTER																			
				CLOCK TIME OF RECARB OR DECARB															

10-2

[illegible]

HEAT LOG

SEQ. No. M3036DATE 10-3-00GRADE J55CODE 84HEAT No. 06537

CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Va	Cb	AL	FEO	LS.	
C.	TIME	TO LAB.	REC'D	ORDERED	26/28	95/105	0.05	0.08	0.08/15	35	15	12	0.3			0.20/0.40			
MADE																			
Prelim																			
Prelim																			
Prelim																			
Prelim																			
Prelim																			
Lollypop																			
Ladle Analysis																			
POWER																			
ON																			
OFF																			
fter																			
efore																			
otal Min.																			
P. On																			
THERMOCOUPLE																			
READING FURNACE																			
TEST																			
d TEST																			
d TEST																			
h TEST																			
LOCK																			
VP																			
DLE #1																			
DLE #2																			
nestone																			
ne																			
ne																			
ke																			
lar																			
ale																			
ygen After																			
eter Before																			
Used																			
EIER AFTER																			
ETER BEFORE																			
ETER AT MELT																			
W.H. USED TO MELT																			
No.																			
G																			
COMMENTS																			
STRIPPING																			
trip																			
Strip																			
Time																			
red																			
WEIGHMASTER																			
- 8																			
- 4																			
- 12																			

ACTUAL TIME									
TAPPED PREVIOUS HEAT	BEGAN CHARGE	POWER ON	FINISH CHARGE	SLAG OFF START	SLAG OFF RSMH	TAPPED	TIME OF HEAT		
512		545	646			729	1:25		

ELAPSED TIME									
ACTUAL CHARGE TIME	CHARGE TO TAP	MAKE BOTTOMS	CHARGE TO CHARGE	DELAYS	FURNACE PATCH	K.W.H.	TAP TO TAP		
							2:20		

METALS CHARGED		WEIGHT		FURNACE AND LADLE ADDITIONS		WEIGHT	
NO. 1 STEEL				MILL SCALE			
NO. 1 BUNDLESFACTORY				NICKEL			
NO. 1 BUNDLES-DEALER				COPPER			
NO. 2 STEEL				H. C. MANGANESE			229.
BUSHLINGS				FERRO PHOSPHORUS			
BROKEN MOULDS				75% FE. SILICON			
PREPARED PIT SCRAP				ALUMINUM	19/400		41.
COMPANY SCRAP-CARBON				MOLYBDENUM			
COMPANY SCRAP-INGOTS & BUTTS				FE. COLUMBIUM (CONT. WGT.)			
SHREDD				LC. MANGANESE			
NO. 2 BUNDLES				FE. VANADIUM			
BORING & TURNINGS				CHROME			
TIN PLATE				COKE			27.
TOTAL				CALCIUM			17
							40.

PRODUCTION 29490				WEIGHT			
PRO-DUCT	NO. OF SLABS	MOLD SIZE	MOLD CODE				
SLABS	3	8466-282					88470
SLABS	2	466-231					48300
INGOTS							
FRONT ENDCROPS							
TAIL ENDCROPS	16						1265
SKULL							
TONS IN TUNDISH	25	4.9					9800
PIT							5000
TOTAL INGOT WEIGHT							136770

TONNAGE		WEIGHT	
TOTAL CHARGED		104462	65.5
TOTAL PRODUCED		68385	YIELD %

FURNACE DELAYS AND REMARKS			
TIME	ELAPSED TIME	TYPE	
520/540	1:20	/	
540/545	1:05	/	
548/628	1:20	/	
	6:15		

STRIPPING	
trip	Gun F13, 56 Around Tee
Strip	Level 1st Charge
Time	Level roof / up and down limits
	Case 12 / 1st Temp

WEIGHMASTER	
- 8	
- 4	
- 12	

CLOCK TIME OF RECARB OR DECARB	

10-3-00

CHARGE		WEIGHT	TYPE	HOW LOADED	TIME	CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS		
						C.	TIME MELT.	TO LAB.	REC'D	ORDERED	C	Mn
										MADE		
										Prelim.		
										Prelim.		
										Prelim.		
										Prelim.		
										Prelim.		
										Lollypop		
										Ladle Analysis		
										TAPPED PREVIOUS HEAT		
										ACTUAL CHARGE TIME		
										METALS CHAIR		
										NO. 1 STEEL		
										NO. 1 BUNDLES-FACTOR		
										NO. 1 BUNDLESDEALER		
										NO. 2 STEEL		
										BUSHINGS		
										BROKEN MOULDS		
										PREPARED PIT SCRAP		
										COMPANY SCRAP-CARBON		
										COMPANY SCRAP-INGOT		
										SHREDD		
										NO. 2 BUNDLES		
										BORING & TURNINGS		
										TIN PLATE		
										PRODUCT		
										PRO- DUCT	NO. OF SLABS	MOLD
										SLABS	3	846%
										SLABS	2	46%
										INGOTS		
										FRONT END CROPS		
										TAIL END CROPS	1	46%
										SKULL		
										TONS IN TUNDISH	25	4%
										PIT		
										TOTAL IN		
										GUN FIB, SL		
										Level 1st		
										Level roof		
										Case 12/		
										CLOCK TIME OF RECARB		

HEAT LOG

SEQ. No. 113029

DATE 10-4-80 GRADE UN80

CODE 85

HEAT No. D6548

CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS												AL		FEO		L.S.	
C.	TIME MELT.	TO LAB.	REC'D	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Va	Cb	AL	FEO	L.S.				
				23/25	12.9/10	0.15	0.05	15/25	3.5	1.5	12	0.3				0.25/0.45					
MADE																					
Prelim.																					
Prelim.																					
Prelim.																					
Prelim.																					
Prelim.																					
Lollypop																					
Ladle Analysis																					
POWER																					
ON																					
OFF																					
THERMOCOUPLE LEADING FURNACE																					
TIME																					
TEST																					
TEST																					
TEST																					
TEST																					
CHECK																					
305																					
METALS CHARGED																					
NO. 1 STEEL																					
NO. 1 BUNDLES-FACTORY																					
NO. 1 BUNDLES-DEALER																					
NO. 2 STEEL																					
BUSHLINGS																					
BROKEN MOULDS																					
PREPARED PIT SCRAP																					
COMPANY SCRAP-CARBON																					
COMPANY SCRAP-INGOTS & BUTTS																					
SHREDD																					
NO. 2 BUNDLES																					
BORING & TURNINGS																					
TIN PLATE																					
TOTAL																					
PRODUCTION																					
WEIGHT																					
SLABS																					
SLABS																					
INGOTS																					
FRONT END CROPS																					
TAIL END CROPS																					
SKULL																					
TONS IN TUNDISH																					
PIT																					
TOTAL INGOT WEIGHT																					
FURNACE DELAYS AND REMARKS																					
TIME																					
ELAPSED TIME																					
TYPE																					
WEIGHMASTER																					
CLOCK TIME OF RECARB OR DECARB																					

DATE 10-4-5									
CHARGE	WEIGHT	TYPE	HOW LOADED	TIME	CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS
					C.	TIME MELT.	TO LAB.	REC'D	C
									ORDERED 23/25 12/2
									MADE
									Prelim.
									Prelim.
									Prelim. 10.2
									Prelim.
									Prelim.
									Lollypop
									Ladle Analysis
ORDERED	FURNACE AND LADLE ALLOWANCE				ON		OFF		
	ALLOYS	%	WEIGHT	TIME	After				
	FE. MN. FURNACE				Before				
	FE. MN. FURNACE				Total Min.				
	FE. MN. FURNACE				% P. On				
	FE. MN. LADLE	80%	2572		THERMOCOUPLE READING FURNACE		TIME		
	FE. MN. LADLE				1st TEST				
	FE. SI. FURNACE				2nd TEST				
	FE. SI.	25%	379		3rd TEST				
	FE. SI.				4th TEST				
	MISCH ALLOY				BLOCK		3051		
	FE. VANADIUM				TAP				
	MOLYBDENUM				LADLE #1				
	AL LADLE	8x19	250		LADLE #2				
	AL MOULDS								
	COKE								
	A.K. FLUX								
	RIM. ACCEL. MOULDS								
	FE. COLUMBIUM								
	DESULFURIZER TAP	10-16	2031						
	DESULFURIZER LADLE								
	CALCIUM NO. OF FT.				Limestone				
	POUNDS OF HOT TOP				Lime				
	ELAPSED TIME OF TAP				Lime				
	ARGON TIME				Coke				
	ARGON GAUGE READING				Spar				
		5050	300		Scale				
		512	200		Oxygen After				
		5010	50		Meter Before				
					O2 Used				
ELECTRODE DATA									
PHASE	NO. ADDED	TIME	BY WHOM	SUPPLIER	METER AFTER				
No. 1				S. G. L.	METER BEFORE				
No. 2					METER AT MELT				
No. 3					K.W.H. USED TO MELT				
HEATS ON LINING:									
WALLS				ROOF		ROOF No.			
Used: GUN MIX				SYNDOLAG		COMMENTS			
TAP HOLE									
BANKS									
BOTTOM									
LADLE NO.									
NO. HEATS		NOZ. SIZE		STRIPPING					
STOPPER:				MOLD CONDITION:		Start Strip			
						Finish Strip			
						Lapsed Time			
						Delays			
BLEEDERS:									
POURED BY:				PIT FOREMAN					
TESTS: LAB.				JOMINY		GR SIZE		Delivered	
MELTER		1st HELPER		WEIGHMASTER					
12-8		12-8		12-8					
8-4		8-4		8-4					
4-12		4-12		4-12					
CLOCK TIME OF RECAR									

HEAT LOG

SEQ. No. M 3030

DATE 10-21-90 GRADE 122FO

CODE 2.5

HEAT No. 06549

[illegible]

10-1

CHARGE		WEIGHT	TYPE	HOW LOADED	TIME	CARBON ANALYZER TESTS	TIME OF TEST		ANALYSIS C
						C.	TIME MELT.	TO LAB.	REC'D
									ORDERED 23/25
									MADE
									Prelim.
									Prelim.
									Prelim.
									Prelim.
									Lollypop
									Ladle Analysis
ORDERED	FURNACE AND LADLE ALLOWANCE					POWER			
	ALLOYS	%	WEIGHT	TIME	ON	OFF			
	FE. MN. FURNACE				After				
	FE. MN. FURNACE				Before				
	FE. MN. FURNACE				Total Min.				
	FE. MN. LADLE	80%	2371		% P. On				
	FE. MN. LADLE				THERMOCOUPLE READING FURNACE	TIME			
	FE. SI. FURNACE				1st TEST				
	FE. SI.	70%	380		2nd TEST				
	FE. SI.				3rd TEST				
	MISCH ALLOY				4th TEST				
	FE. VANADIUM				BLOCK	3165			
	MOLYBDENUM				TAP				
	AL LADLE	Brig.	250		LADLE #1				
	AL MOULDS				LADLE #2				
	COKE		50						
	A.K. FLUX								
	RIM. ACCEL. MOULDS								
	FE. COLUMBIUM								
	DESULFURIZER TAP	N-26	2019						
	DESULFURIZER LADLE								
	CALCIUM NO. OF FT.								
	POUNDS OF HOT TOP				Limestone				
	ELAPSED TIME OF TAP	Sess.	115		Lime				
	ARGON TIME				Lime				
	ARGON GAUGE READING				Coke				
		sarsa	300		Spar				
		side	200		Scale				
		calle			Oxygen Aher				
					Meter Before				
					O ₂ Used				
ELECTRODE DATA									
PHASE	NO. ADDED	TIME	BY WHOM	SUPPLIER	METER AFTER				
No. 1	1 stick A				METER BEFORE				
No. 2					METER AT MELT				
No. 3					K.W.H. USED TO MELT				
HEATS ON LINING:					ROOF	ROOF No.			
WALLS					Used: GUN MIX	SYNDOLAG	COMMENTS		
TAP HOLE									
BANKS									
BOTTOM									
UDDLE NO.					NO. HEATS	NOZ. SIZE	STRIPPING		
STOPPER:					MOLD CONDITION:		Start Strip		
							Finish Strip		
							Lapsed Time		
BLEEDERS:							Delays		
POURED BY:					PIT FOREMAN				
TESTS: LAB.					JOMINY	GR. SIZE	Delivered		
MELTER			1st HELPER			WEIGHMASTER			
12 - 8			12 - 8			12 - 8			
8 - 4 Bw			8 - 4 GB			8 - 4			
4 - 12			4 - 12			4 - 12			
									CLOCK TIME OF RE

HEAT LOG

SEQ. No. 6550

DATE 10-400

GRADE 555

CODE 84

HEAT No. D 10550

CARBON ANALYZER TESTS						TIME OF TEST									
TIME MELT.		TO LAB.		REC'D											
POWER															
ON						OFF									
THERMOCOUPLE LEADING FURNACE						TIME									
EST						TEST						EST		TEST	
CK						3173 ✓									
LE #1															
LE #2															
stone															
gen After															
er Before															
Used															
ER AFTER															
ER BEFORE															
ER AT MELT															
H. USED TO MELT															
o.															
COMMENTS															
STRIPPING															
WEIGHMASTER															
CLOCK TIME OF RECARB OR DECARB															

DATE 10-40

[illegible]

SEQ. No. 1551

DATE 10-4-06 GRADE 555 CODE 84 HEAT No. 06551

NSC-0108

[illegible]

HEAT LOG

SEQ. No. 4552

DATE 10-4-00

GRADE 755

CODE *Q 4*

HEAT No. 01552

[illegible]

DATE 10-4-61

[illegible]

HEAT LOG

SEQ. No. 3037

[illegible]

ANALYSIS	C	M-
----------	---	----

CLOCK TIME OF RECALL

HEAT LOG

SEQ. No. *M 3038*DATE *10/4/00*GRADE *J-55*CODE *84*HEAT No. *26534**020/076*

CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS													
C.	TIME MELT	TO LAB.	REC'D	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Va	Cb	AL	FEO	LS
				ORDERED	<i>28/30</i>	<i>100/110</i>	<i>015</i>	<i>010</i>	<i>04/15</i>	<i>35</i>	<i>15</i>	<i>12</i>	<i>03</i>				
				MADE													
				Prelim.	<i>07</i>												
				Prelim.													
				Prelim.	<i>2</i>	<i>90</i>		<i>028</i>									
				Prelim.													
				Lollypop													
				Ladle Analysis													

THERMOCOUPLE READING FURNACE		TIME	ACTUAL TIME							
st TEST			TAPPED PREVIOUS HEAT	BEGAN CHARGE	POWER ON	FINISH CHARGE	SLAG OFF START	SLAG OFF FINISH	TAPPED	TIME OF HEAT
<i>3077</i>			<i>320</i>		<i>333</i>	<i>355</i>			<i>504</i>	<i>1:30</i>
nd TEST										
rd TEST										
th TEST										
LOCK										
AP										

METALS CHARGED		WEIGHT		FURNACE AND LADLE ADDITIONS		WEIGHT	
ADLE #1		NO. 1 STEEL		MILL SCALE			
XDLE #2		NO. 1 BUNDLESFACTORY		NICKEL			
		NO. 1 BUNDLES-DEALER	<i>10820</i>	COPPER			
		NO. 2 STEEL	<i>35120</i>	H. C. MANGANESE			<i>194</i>
		BUSHLINGS		FERRO PHOSPHORUS			
		BROKEN MOULDS		75% FE SILICON			
		PREPARED PIT SCRAP	<i>9240</i>	ALUMINUM	<i>45/300</i>		<i>34</i>
estone		COMPANY SCRAP-CARBON	<i>112700</i>	MOLYBDENUM			
me		COMPANY SCRAP-INGOTS & BUTTS		FE COLUMBIUM (CONT WGT.)			
me		SHREDD	<i>27660</i>	LC MANGANESE			
oke		NO. 2 BUNDLES	<i>9780</i>	FE VANADIUM			
pa		BORING & TURNINGS		CHROME			
cale		TIN PLATE		COKE			<i>225</i>
xygen After		TOTAL	<i>205320</i>	CALCIUM			<i>23</i>
eter Before		PRODUCTION	<i>28080</i>	WEIGHT			<i>400</i>
2 Used							

ETER AFTER		ETER BEFORE		ETER AT MELT		W.H. USED TO MELT	
No.		No.		No.		No.	
CG	COMMENTS	CG	COMMENTS	CG	COMMENTS	CG	COMMENTS

STRIPPING		WEIGHMASTER	
rip		rip	
Strip		Strip	
Time		Time	

STRIPPING		WEIGHMASTER	
rip		rip	
Strip		Strip	
Time		Time	

CHARGE		WEIGHT	TYPE	HOW LOADED	TIME	CARBON ANALYZER TESTS		TIME OF TEST		ANALYSIS		
						C.	TIME MELT.	TO LAB.	REC'D	ORDERED	C	Mt
										MADE	28/30	100%
										Prelim.	107	
										Prelim.		
										Prelim.	25	90
										Prelim.		
										Prelim.		
										Lollypop		
										Ladle Analysis		
										TAPPED PREVIOUS HEAT	320	B
										ACTUAL CHARGE TIME		CF
										METALS CHAI		
										NO. 1 STEEL		
										NO. 1 BUNDLES-FACTOR		
										NO. 1 BUNDLES-DEALER		
										NO. 2 STEEL		
										BUSHLINGS		
										BROKEN MOULDS		
										PREPARED PIT SCRAP		
										COMPANY SCRAP-CARBON		
										COMPANY SCRAP-INGOT		
										SHREDD		
										NO. 2 BUNDLES		
										BORING & TURNINGS		
										TIN PLATE		
										PRODUCT		
										PRO-DUCT	NO. OF SLABS	MOLD
										SLABS	7	834/8
										INGOTS		
										FRONT END CROPS	1	34/8
										TAIL END CROPS		
										SKULL		
										TONS IN TUNDISH		
										PIT		
										TOTAL IN		
										STRIPPING		
										Start Strip		
										Finish Strip		
										Lapsed Time		
										Delays		
										WEIGHMASTER		
										CLOCK TIME OF RECARB		

23

[illegible]

NEWPORT STEEL CORPORATION
BRANDT BAGHOUSE TEST PROCESS MONITORING FORM

NEWPORT STEEL CORPORATION **BRANDT BAGHOUSE TEST PROCESS MONITORING FORM**

Date 10/4/00

Run Number 213

x6969

Time	Baghouse Fan Amperage			Baghouse Pressure Drop, in. WG	CEM DATA Damper Positions (Describe)	Notes (Heat No. and time; Other)
	1	2	3			
0800	220	212	218	6.22	NOx 3.5 ppm CO 101.2 ppm	1) 6548 CHARGE C 0755 - 2nd CHARGE C ON - FURNACE TAPPER #6547 C 0745
0830	204	191	195	6.79	NOx 0.88 CO 97.2	2) 6549 START 0855 LAST CHARGE C 0835 TAP C 1000 1020
0900	221	211	217	6.01	CO 34 ppm NOx 6 ppm	3) 6550 2nd CHARGE C 1048 HBI START TAP
0930	213	204	209	6.13	CO 49.3 NOx 2.9	4) 6551 START 1141 TAP C 1243
1000	203	193	198	6.47	CO 90.2 NOx 1.9	5) 6552 1255 START 2nd CHARGE C 1320 TAP C 1355
1030	210	198	206	6.92	CO 51.4 NOx 2.7	6) 6553 START 1402 TAP C 1510
1100	216	206	211	6.26	CO 229.29.3 NOx 8.3	7) 6554 START 1533 TAP C 1640 1630
1130	215	203	212	6.24	CO 239 NOx 2.6	
1200	214	202	208	6.15	CO 42 ppm NOx 8.2 ppm	
1230	219	210	215	6.28	CO 53 NOx 4.2	
1300	218	209	213	6.06	CO 78.2 NOx 2.8	
1330	217	205	207	6.23	CO 104 NOx 1.9	
1400	213	201	211	6.72	CO 87 NOx 0.98	
1430	211	198	211	6.31	CO 103 NOx 2.1	
1500	205	200	211	6.15		
1530	209	199	205	6.02		
1600	208	198	202	5.91		
1622	204	192	196	6.69		

uw2

uw3

IN
PLATE

Date _____ Run Number _____

[illegible]

Appendix E
Calibration Data

PACIFIC ENVIRONMENTAL SERVICES, INC.

CALIBRATION PROCEDURES AND RESULTS


All of the equipment used is calibrated in accordance with the procedures outlined in the Quality Assurance Handbook for Air Pollution Measurement Systems, Volume III.* The following pages describe these procedures and include the data sheets.

*EPA 600/4-77-027b

PACIFIC ENVIRONMENTAL SERVICES, INC.

Pitot Tube Calibration

Each **pitot** tube used in sampling meets all requirements of EPA Method 2, Section 4.1.** Therefore, a baseline coefficient of 0.84 is assigned to each **pitot** tube. The following pages show the alignment requirements of Method 2 and the **Pitot Tube Inspection Data Sheet(s)** for each **pitot** tube used during the test program.



**40 CFR 60, Appendix A, July 1995

PITOT TUBE CALIBRATIONS

Pitot ID	Date Calibrated	α_1	B_1	α_2	B_2	γ	θ	A	z	w	P_a	P_b	D_t	$A/2/D_t$	Accept/Reject
1	01/13/2000	1.8	0.1	1.4	0.1	0.1	0.8	0.948	0.002	0.010	0.474	0.474	0.375	1.264	ACCEPT
2-M-2	01/13/2000	0.8	1.4	2.8	0.7	1.1	1.7	0.955	0.018	0.028	0.477	0.478	0.375	1.273	ACCEPT
3-1	10/29/1999	1.3	1.6	3.8	3.7	2.1	0.3	1.077	0.039	0.008	0.538	0.539	0.364	1.479	ACCEPT
3-M-1	10/29/1999	1.1	1.8	0.9	0.1	1.4	1.7	0.948	0.023	0.028	0.474	0.474	0.375	1.264	ACCEPT
3-M-2	10/28/1999	1.8	0.8	0.8	0.8	0.7	0.8	0.954	0.012	0.013	0.477	0.477	0.375	1.272	ACCEPT
3-M-3	01/13/2000	0.7	0.2	1.6	0.2	2.6	1.6	0.945	0.043	0.026	0.473	0.472	0.375	1.260	ACCEPT
3-X-2	10/28/1999	0.4	0.4	0.7	0.7	0.7	0.9	0.945	0.012	0.015	0.472	0.473	0.375	1.260	ACCEPT
3-X-1	10/29/1999	0.4	0.6	0.8	0.6	0.1	0.2	0.945	0.002	0.003	0.473	0.472	0.375	1.260	ACCEPT
3-P-1	05/30/2000	1.0	1.0	1.0	1.0	1.0	0.1	0.748	0.013	0.001	0.374	0.374	0.250	1.496	ACCEPT
4-M-1	10/28/1999	0.3	0.6	0.5	0.4	0.6	0.4	0.949	0.010	0.007	0.474	0.475	0.375	1.265	ACCEPT
4-M-2	10/29/1999	0.7	0.4	0.2	1.4	1.1	0.4	0.958	0.018	0.007	0.479	0.479	0.375	1.277	ACCEPT
4-X-1	10/29/1999	4.7	1.2	4.4	0.4	2.7	0.4	0.945	0.045	0.007	0.472	0.473	0.375	1.260	ACCEPT
4-X-2	10/28/1999	0.2	0.9	1.6	1.3	0.1	0.1	0.949	0.002	0.002	0.474	0.475	0.375	1.265	ACCEPT
4-X-3	10/28/1999	0.2	0.6	0.2	0.5	0.2	0.4	0.956	0.003	0.007	0.478	0.478	0.375	1.275	ACCEPT
5' T/P	10/29/1999	1.9	3.5	1.0	1.4	1.8	1.6	0.937	0.029	0.026	0.468	0.469	0.375	1.249	ACCEPT
5-I-1	10/28/1999	1.8	0.8	1.0	0.8	0.1	0.7	0.968	0.002	0.012	0.484	0.484	0.375	1.291	ACCEPT
5-M-1	10/28/1999	0.2	0.3	0.2	0.2	1.0	0.6	0.896	0.016	0.009	0.448	0.448	0.375	1.195	ACCEPT
5-M-2	01/13/2000	0.9	0.1	3.9	3.9	1.3	1.2	0.921	0.021	0.019	0.461	0.460	0.375	1.228	ACCEPT
5-X-1	10/29/1999	0.3	0.0	0.3	0.5	1.8	0.3	0.950	0.027	0.005	0.475	0.475	0.373	1.273	ACCEPT
5-X-2	10/28/1999	1.8	1.4	1.2	0.7	0.7	0.7	0.947	0.012	0.012	0.474	0.473	0.372	1.273	ACCEPT
5-X-3	10/29/1999	0.4	0.4	0.1	0.3	1.0	0.9	0.948	0.017	0.015	0.474	0.474	0.375	1.264	ACCEPT
5-1	10/27/1999	1.4	1.3	1.0	1.4	0.7	0.8	1.042	0.013	0.015	0.521	0.521	0.375	1.389	ACCEPT
5-2	10/29/1999	0.4	1.8	3.7	2.9	1.4	0.9	0.971	0.024	0.015	0.485	0.486	0.375	1.295	ACCEPT
5-3	10/28/1999	0.8	0.2	0.9	1.0	0.2	0.3	1.009	0.004	0.005	0.504	0.505	0.375	1.345	ACCEPT
5-4	10/29/1999	2.3	1.2	0.5	0.7	2.7	1.0	0.625	0.029	0.011	0.312	0.313	0.250	1.250	ACCEPT
5-5	10/29/1999	1.0	0.8	0.8	0.5	0.5	0.6	1.022	0.009	0.011	0.511	0.511	0.375	1.363	ACCEPT
5-6	01/13/2000	1.3	0.1	1.2	1.4	2.5	0.7	0.938	0.041	0.011	0.469	0.469	0.375	1.251	ACCEPT
6-1	10/27/1999	1.6	1.5	1.7	1.3	0.2	0.2	0.956	0.003	0.003	0.478	0.478	0.375	1.275	ACCEPT
6-2	10/28/1999	0.1	0.2	0.7	1.7	0.4	0.3	1.097	0.008	0.006	0.548	0.549	0.375	1.463	ACCEPT
6-3	01/13/2000	1.9	2.1	2.6	1.7	1.5	0.1	1.041	0.027	0.002	0.520	0.521	0.375	1.388	ACCEPT
6-1-1	10/27/1999	1.4	2.7	1.3	0.6	2.2	0.4	0.986	0.038	0.007	0.493	0.493	0.375	1.315	ACCEPT
6-1-2	10/28/1999	0.8	0.8	1.3	1.8	0.8	0.3	0.968	0.010	0.005	0.484	0.484	0.375	1.291	ACCEPT
7-1	01/13/2000	0.7	1.5	1.3	1.0	0.6	0.9	0.975	0.010	0.015	0.487	0.488	0.375	1.300	ACCEPT
7-1-1	10/29/1999	0.1	1.9	0.6	1.0	0.9	0.3	0.948	0.015	0.005	0.474	0.474	0.375	1.264	ACCEPT
7-1-2	06/08/2000	0.4	0.4	0.8	0.3	0.5	0.4	0.920	0.008	0.006	0.474	0.474	0.375	1.227	ACCEPT
7-M-1	10/28/1999	1.1	1.1	0.2	0.2	1.1	0.9	0.957	0.018	0.015	0.478	0.479	0.375	1.276	ACCEPT
7-M-2	10/28/1999	0.4	1.2	1.9	1.8	0.7	0.8	0.923	0.011	0.013	0.462	0.461	0.375	1.231	ACCEPT
7-M-3	10/28/1999	1.6	1.8	0.5	0.4	0.7	0.1	0.923	0.011	0.002	0.461	0.462	0.375	1.231	ACCEPT
8-1	10/28/1999	0.8	0.8	1.9	1.8	0.3	0.1	0.934	0.005	0.002	0.467	0.467	0.375	1.245	ACCEPT
8-2	10/29/1999	0.9	0.8	0.4	0.5	2.1	1.6	0.941	0.034	0.026	0.470	0.471	0.375	1.255	ACCEPT
8-3	11/04/1999	1.1	0.6	0.3	1.4	0.1	0.4	0.918	0.002	0.006	0.459	0.459	0.374	1.227	ACCEPT
8-M-2	10/29/1999	0.2	2.4	0.3	1.2	0.5	0.7	0.938	0.008	0.011	0.469	0.469	0.375	1.251	ACCEPT
9-M-1	10/29/1999	0.1	1.7	0.2	0.8	1	1	0.882	0.017	0.017	0.491	0.491	0.375	1.309	ACCEPT
10-M-1	10/29/1999	2.2	2.8	0.3	0.5	0.2	0.4	0.949	0.003	0.007	0.475	0.474	0.374	1.269	ACCEPT
11-1	10/29/1999	0.8	1.9	2.5	1.8	1.3	1.5	0.970	0.022	0.025	0.485	0.485	0.351	1.382	ACCEPT
12-X-1	10/29/1999	0.4	1.5	0.9	1.9	2.9	1.4	0.921	0.047	0.023	0.461	0.46	0.372	1.238	ACCEPT
12-1	10/29/1999	0.3	0.4	1.1	0.6	1.2	1.2	1.125	0.024	0.024	0.563	0.562	0.375	1.500	ACCEPT

- 1 = Pitot Alone

- M-1 = Pitot/Thermo. Combination

- X-1 = Full Probe Assembly

- I-1 = Inkonel

- T-1 = Thermo. Alone

PACIFIC ENVIRONMENTAL SERVICES, INC.

Stack Thermocouples

Each thermocouple is calibrated by comparing it with an ASTM-3F thermometer at approximately **32°F**, ambient temperature, **212°F**, and **500°F**. The thermocouple reads within 1.5 percent (%) of the reference thermometer throughout the entire range when expressed in degrees **Rankine**. The thermocouples may be checked at ambient temperature at the test site to verify the calibration. Calibration data are included in the following Thermocouple Calibration Data **Sheet(s)**.

STACK THERMOCOUPLES

Thermo. ID	Therm.	Date Calibrated	Ambient Air	Diff., %	Cold Bath	Diff., %	Hot Bath	Diff., %	Hot Oil	Diff., %	Accept/Reject
1-T-1	Reference	0111312000	76	0.00	46	0.00	212	0.00	451	0.00	ACCEPT
	Pitot		76		46		212		451		
2-M-1	Reference	01/27/2000	75	0.00	42	0.00	210	0.00	410	0.00	ACCEPT
	Pitot		75		42		210		410		
2-M-2	Reference	01/27/2000	75	0.00	42	0.00	165	0.00	418	0.00	ACCEPT
	Pitot		75		42		165		418		
3-M-1	Reference	11/03/1999	65	1.14	35	0.00	201	0.00	423	0.00	ACCEPT
	Pitot		71		35		201		423		
3-M-2	Reference	1110211999	74	0.00	42	0.00	208	0.00	456	0.00	ACCEPT
	Pitot		74		42		208		456		
3-M-3	Reference	01/13/2000	75	0.00	36	0.00	192	0.00	410	0.00	ACCEPT
	Pitot		75		36		192		410		
3-M-4	Reference	01/27/2000	75	0.00	42	0.00	212	0.00	415	0.00	ACCEPT
	Pitot		75		42		212		415		
3-T-1	Reference	1012911999	77	0.19	42	0.00	214	0.00	393	0.23	ACCEPT
	Pitot		77		42		214		395		
3-T-2	Reference	1012911999	78	0.00	43	0.00	212	0.00	452	0.00	ACCEPT
	Pitot		77		43		212		452		
3-T-3	Reference	01/13/2000	75	0.00	46	0.00	207	0.00	423	0.00	ACCEPT
	Pitot		75		46		207		423		
3-T-4	Reference	01/13/2000	76	0.00	38	0.00	210	0.00	455	0.00	ACCEPT
	Pitot		76		38		210		455		
3-X-1	Reference	10/29/1999	77	0.00	42	0.20	211	0.00	500	0.10	ACCEPT
	Pitot		77		43		211		501		
3-X-2	Reference	1110311999	64	0.19	43	0.00	208	0.00	438	1.45	ACCEPT
	Pitot		65		43		208		425		
3-P-1	Reference	06/08/2000	73	0.00	38	0.00	118	0.17	429	0.45	ACCEPT
	Pitot		73		38		117		425		
4-M-1	Reference	1110211999	74	0.00	38	0.60	199	0.00	373	0.00	ACCEPT
	Pitot		74		41		199		373		
4-M-2	Reference	1110311999	74	0.00	58	0.00	192	0.31	411	0.00	ACCEPT
	Pitot		74		58		190		411		

PACIFIC ENVIRONMENTAL SERVICES

7209 East Kemper Rd.
Cincinnati, OH 45249
513.489.6611
513.489.6619 Fax
www.pes.com

STACK THERMOCOUPLES

Thermo. ID	Therm.	Date Calibrated	Ambient Air	Diff., %	Cold Bath	Diff., %	Hot Bath	Diff., %	Hot Oil	Diff., %	Accept/Reject
4-T-1	Reference	11/02/1999	74	0.00	42	0.00	199	0.00	402	0.58	ACCEPT
	Pitot		74		42		199		407		
4-T-2	Reference	11/02/1999	74	0.00	40	0.00	210	0.00	468	0.75	ACCEPT
	Pitot		74		40		210		475		
4-T-3	Reference	11/02/1999	74	0.00	41	0.00	204	0.00	410	0.00	ACCEPT
	Pitot		74		41		204		410		
4-X-1	Reference	11/03/1999	62	0.00	42	0.40	198	0.00	430	0.45	ACCEPT
	Pitot		62		44		198		426		
	Reference	01/27/2000	75	0.00	45	0.00	189	0.00	410	0.00	ACCEPT
	Pitot		75		45		189		410		
4-X-3	Reference	01/27/2000	75	0.00	44	0.00	206	0.00	418	0.00	ACCEPT
	Pitot		75		44		206		418		
5-M-1	Reference	11/02/1999	73	0.19	56	0.00	190	0.00	400	5.93	REJECT
	Pitot		74		56		190		349		
5-M-2	Reference	01/13/2000	75	0.00	44	0.00	210	0.00	438	0.00	ACCEPT
	Pitot		75		44		210		438		
5-T-1	Reference	10/29/1999	75	0.00	42	0.00	214	0.00	489	0.21	ACCEPT
	Pitot		75		42		214		491		
5-T-2	Reference	11/02/1999	74	0.00	40	0.00	210	0.15	410	0.00	ACCEPT
	Pitot		74		40		211		410		
5-X-1	Reference	10/29/1999	78	0.00	40	0.00	209	0.15	496	0.00	ACCEPT
	Pitot		78		40		208		496		
5-X-2	Reference	11/04/1999	66	0.38	39	0.00	206	0.30	438	0.78	ACCEPT
	Pitot		68		39		204		431		
5-X-3	Reference	10/29/1999	77	0.00	38	0.00	208	0.30	506	0.00	ACCEPT
	Pitot		77		38		210		506		
6-I-1	Reference	11/04/1999	66	0.00	43	0.00	210	0.00	449	0.00	ACCEPT
	Pitot		66		43		210		449		
6-I-2	Reference	11/02/1999	73	0.00	41	0.00	170	0.00	460	0.00	ACCEPT
	Pitot		73		41		170		460		
6-T-1	Reference	11/04/1999	66	0.38	43	0.00	212	0.00	459	0.00	ACCEPT
	Pitot		64		43		212		459		
6-T-2	Reference	11/04/1999	66	0.00	42	0.00	212	0.00	461	0.00	ACCEPT
	Pitot		66		42		212		461		

STACK THERMOCOUPLES

ID	Therm.	Date	Ambient Air	Diff., %	Cold Bath	Diff., %	Hot Bath	Diff., %	Hot Oil	Diff., %	Accept/Reject
6-T-3	Reference	Calibrated 10/29/1999	77	0.00	40	0.00	210	0.15	510	0.41	ACCEPT
	Pitot		77		40		211		514		
6-T-4	Reference	01/13/2000	75	0.00	44	0.00	210	0.00	438	0.00	ACCEPT
	Pitot		75		44		210		438		
7-M-1	Reference	11/03/1999	73	0.00	36	0.00	205	0.00	421	0.00	ACCEPT
	Pitot		73		36		205		421		
7-M-2	Reference	11/03/1999	72	0.00	37	0.00	209	0.00	454	0.00	ACCEPT
	Pitot		72		37		209		454		
7-M-3	Reference	11/03/1999	62	0.00	40	0.00	208	0.00	458	0.00	ACCEPT
	Pitot		62		40		208		458		
7-T-I-1	Reference	01/13/2000	75	0.00	48	0.00	209	0.00	435	0.00	ACCEPT
	Pitot		75		48		209		435		
7-T-I-2	Reference	01/13/2000	75	0.00	48	0.00	210	0.00	440	0.00	ACCEPT
	Pitot		75		48		210		440		
7-T-I-3	Reference	06/08/2000	73	0.00	40	0.00	120	0.00	420	0.00	ACCEPT
	Pitot		73		40		120		420		
8-M-2	Reference	11/03/1999	65	0.00	36	0.00	187	0.00	420	0.00	ACCEPT
	Pitot		65		36		187		378		
8-T-I	Reference	11/04/1999	67	0.38	42	0.00	212	0.00	459	0.00	ACCEPT
	Pitot		74		40		212		396		
8-T-2	Reference	11/02/1999	74	0.00	41	0.00	199	0.61	396	0.70	ACCEPT
	Pitot		74		41		195		396		
8-T-3	Reference	11/02/1999	74	0.00	41	0.00	195	0.00	446	0.00	ACCEPT
	Pitot		74		41		195		446		
8-T-4	Reference	11/04/1999	66	0.38	42	0.40	209	0.30	446	0.22	ACCEPT
	Pitot		68		44		207		446		
8-T-5	Reference	11/04/1999	66	0.00	39	0.80	206	0.15	446	0.00	ACCEPT
	Pitot		66		43		205		446		
10-M-1	Reference	11/04/1999	67	0.38	44	0.20	211	0.00	444	0.00	ACCEPT
	Pitot		69		45		211		417		
10-T-1	Reference	01/27/2000	75	0.00	42	0.00	185	0.00	384	0.00	ACCEPT
	Pitot		75		42		185		384		
12-X-1	Reference	11/04/1999	63	0.00	39	0.00	191	0.00	384	0.00	ACCEPT
	Pitot		63		39		191		384		

PACIFIC ENVIRONMENTAL SERVICES, INC.

Dry Gas Meter and Orifice Meter

Dry gas meters and orifices are calibrated in accordance with Section 3.3.2 of the QA Handbook. This procedure involves direct comparison of the dry gas meter to a reference dry test meter. The reference dry test meter is routinely calibrated using a liquid displacement technique. Before its initial use in the field, the metering system is calibrated over the entire range of operation. After each field use, the metering system is calibrated at a single intermediate setting based on the previous field test. Acceptable tolerances for the initial and final dry gas meter factors and orifice calibration factors are ± 0.02 and ± 0.20 from average, respectively.

Digital Indicators for Thermocouple Readout

A digital indicator is calibrated by feeding a series of millivolt signals to the input and comparing the indicator reading with the reading the signal should have generated. Errors did not exceed 0.5 percent (%) when the temperatures were expressed in degrees **Rankine**. Calibration data are included in the following Thermocouple Digital Indicator Calibration Data **Sheet(s)**.

Dry Gas Thermocouples

The dry gas thermocouples are calibrated by comparing them with an **ASTM-3** thermometer at approximately **32°F, ambient** temperature, and a higher temperature between approximately 100°F and **200°F**. The thermocouples agreed within 5°F of the reference thermometer.

11/19/1999

PACIFIC ENVIRONMENTAL SERVICES, INC.

7209 E. Kemper Rd
Cincinnati, Ohio 45249
Phone: 513.489.6611
Fax: 513.489.6619
www.pm.com

Meter Box No.: 1

Dry Gas Orifice Meter

Pb, in. Hg	29.36	RUN 1	RUN 2	RUN 3	RUN 4	RUN 5	RUN 6
DH	Delta H	0.50	0.75	1.00	1.50	2.00	4.00
in Hg	Vacuum	10	10	10	10	10	10
Vw ₁	Initial RTM	873.531	888.480	899.509	910.499	921.676	933.875
Vw ₂	Final RTM	888.088	899.083	910.341	921.430	933.245	947.460
Vd ₁	Initial DGM	809.724	824.702	835.775	846.827	858.032	870.262
Vd ₂	Final DGM	824.310	835.345	846.652	857.784	869.631	883.834
T _w	Ave. Temp RTM °	72	73	74	75	75	75
T _d	Ave. Temp DGM °	77	82	84	87	88	89
t	Time (min.)	36.1	21.4	19.0	15.9	15.0	12.4

$Vw_2 - Vw_1$	Net Volume RTM	14557	10.603	10.832	10.931	11.569	13.585
$Vd_2 - Vd_1$	Net Volume DGM	14586	10643	10.877	10.957	11.599	13.572
Y		1.006	1.011	1.012	1.016	1.017	1.017
dH@		1.747	1.724	1.732	1.793	1.896	1.876
AVERAGE Y	1.001	(Reference meter correction factor of 0.988)					ACCEPT
Average Y Range =		0.981	TO	1.021			
AVERAGE dH	1.795						ACCEPT
Average dH@ Range =		1.595	TO	1.995			
Calculations							
$Y = (Vw * Pb * (Td + 460)) / (Vd * (Pb + (dHd / 13.6)) * (Tw + 460))$							
$dH@ = 0.0317 * dHd / (Pb (Td + 460)) * (((Tw + 460) * 11) / Vw)^2$							

Digital Indicator for Thermocouple Readout

TEST POINT NO.	MILLIVOLT SIGNAL	EQUIVALENT TEMP. °F	DIGITAL INDICATOR TEMP. °F	DIFFERENCE. %
1	-0.692	0	-1	0.2
2	1.520	100	100	0.0
3	3.819	200	201	0.2
4	6.092	300	299	0.1
5	8.314	400	399	0.1
6	10.560	500	501	0.1
7	22.251	1000	1001	0.1
8	29.315	1300	1300	0.0
9	36.166	1600	1601	0.0
10	42.732	1900	1899	0.0

Percent difference must be less than or equal to 0.5 %

% difference: $\frac{(\text{Equivalent Temp., } ^\circ\text{R} - \text{Digital Indicator Temp., } ^\circ\text{R})}{(\text{Equivalent Temp., } ^\circ\text{R})} \times 100\%$

Where $^{\circ}\text{R} = ^\circ\text{F} + 460$

ACCEPT

Dry Gas Thermocouples

Reference point number	Source ^a (Specify)	Reference Thermometer Temperature, °F	Thermocouple Potentiometer Temperature, °F	Temperature Difference, °F
Inlet				
1	Ambient Air	73	74	1
2	Cold Bath	41	40	1
3	Hot Bath	138	137	1
Outlet				
1	Ambient Air	73	73	0
2	Cold Bath	42	42	0
3	Hot Bath	136	135	1

^a type of calibration used

^b allowable tolerance $\pm 5^\circ\text{F}$

ACCEPT

Calibrated By : da

PACIFIC ENVIRONMENTAL SERVICES, INC.

7209 E. Kemper Road
Cincinnati, Ohio 45249
Phone: 513.489.6611
Fax: 513.489.6619
www.pes.com

Box No.: MB-1 Bar. Press.(Pb): 29.12 in. Hg

Date: 1015100 Pretest Gamma: 1.001

Calibrated By : G Gay Pretest dH@: 1.795

Plant: Newport Steel

		RUN 1	RUN 2	RUN 3
DH	Delta H	1.80	1.80	1.80
in Hg	Vacuum	8.00	8.00	8.00
Vw ₁	Initial RTM	422.019	433.168	444.365
Vw ₂	Final RTM	433.168	444.365	456.724
Vd ₁	Initial DGM	532.859	544.132	555.480
Vd ₂	Final DGM	544.132	555.480	568.020
Tw	Ave. Temp RTM °F	69.0	70.0	71.0
Td	Ave. Temp DGM °F	72.0	73.0	74.0
t	Time (min.)	15.0	15.0	16.3

Vw ₂ - Vw ₁	Net Volume RTM	11.149	11.197	12.359
Vd ₂ - Vd ₁	Net Volume DGM	11.273	11.348	12.540
	Y	0.990	0.988	0.987
	dH@	1.866	1.853	1.800

AVERAGE Y = 0.980

% Difference from Yearly Y = -2.144

ACCEPT

AVERAGE dH@ = 1.840

Calculations

$$Y = (V_w * P_b * (T_d + 460)) / (V_d * (P_b + (dH_d / 13.6)) * (T_w + 460))$$

$$dH@ = 0.0317 * dH_d / (P_b (T_d + 460)) * (((T_w + 460) * time) / V_w)^2$$

PACIFIC ENVIRONMENTAL SERVICES, INC.

Impinger Thermocouples

The **impinger** thermocouples are checked in a similar manner at approximately 32°F and ambient temperature, and they agreed within **2°F**. **The** thermocouples may be checked at ambient temperature prior **to** the test series to verify calibration. Calibration data are included in the following Impinger Thermocouple Calibration Data **Sheet(s)**.

**TEMPERATURE SENSOR CALIBRATION DATA FORM
FOR SAMPLEHEADS****DATE:** 13-Jan-00

Reference point number	Source ^a (Specify)	Reference Thermometer Temperature, °F	Thermocouple Potentiometer Temperature, °F	Temperature Difference, ^b °F	
Sample Head No. 1					
1	Ambient Air	75	75	0	ACCEPT
2	Cold Bath	36	36	0	
Sample Head No. 2					
1	Ambient Air	76	76	0	ACCEPT-
2	Cold Bath	36	36	0	
Sample Head No. 3					
1	Ambient Air	76	76	0	ACCEPT
2	Cold Bath	38	38	0	
Sample Head No. 4					
1	Ambient Air	76	76	0	ACCEPT
2	Cold Bath	36	36	0	
Sample Head No. 5					
1	Ambient Air	76	78	2	ACCEPT
2	Cold Bath	36	36	0	
Sample Head No. 6					
1	Ambient Air	73	73	0	ACCEPT
2	Cold Bath	35	35	0	
Sample Head No. 7					
1	Ambient Air	74	74	0	ACCEPT
2	Cold Bath	35	35	0	
Sample Head No. 8					
1	Ambient Air	74	74	0	ACCEPT
2	Cold Bath	38	38	0	
Sample Head No. 9					
1	Ambient Air	75	75	0	ACCEPT
2	Cold Bath	40	40	0	

^aType of calibration used.

Calibrated By: ah

^bAllowable tolerance $\pm 2^{\circ}\text{F}$

Appendix G
Continuous Emission Monitoring Data

Run 1

Min001

Date	Hour	CO	NOX	COPPH	NOXPPH
1013100 0:00	9:14	68.9	3.33	176.64	14.05
1013100 0:00	9:15	83.5	3.14	214.15	13.24
1013100 0:00	9:16	122.2	2.99	313.40	12.60
1013100 0:00	9:17	250.0	3.10	641.33	13.06
1013100 0:00	9:18	421.8	3.19	1081.97	13.43
1013100 0:00	9:19	417.8	3.08	1071.72	12.98
1013100 0:00	9:20	331.6	3.00	850.58	12.66
1013100 0:00	9:21	374.3	2.74	960.03	11.55
1013100 0:00	9:22	268.1	2.96	687.80	12.47
1013100 0:00	9:23	380.4	2.96	975.68	12.48
1013100 0:00	9:24	174.1	2.57	446.50	10.84
1013100 0:00	9:25	145.1	1.97	372.17	8.32
10/3/00 0:00	9:26	170.9	1.92	438.37	8.09
1013100 0:00	9:27	159.5	1.88	409.23	7.91
1013100 0:00	9:28	112.3	1.71	288.19	7.21
1013100 0:00	9:29	121.0	1.55	310.39	6.52
1013100 0:00	9:30	155.9	1.34	399.86	5.66
1013100 0:00	9:31	129.2	1.30	331.50	5.47
1013100 0:00	9:32	116.3	3.92	298.43	16.49
1013100 0:00	9:33	59.8	10.71	153.43	45.11
1013100 0:00	9:34	102.0	12.95	261.68	54.54
1013100 0:00	9:35	124.0	3.00	318.16	12.65
10/3/00 0:00	9:36	137.0	1.44	351.50	6.08
1013100 0:00	9:37	184.6	1.70	473.50	7.16
1013100 0:00	9:38	141.8	1.71	363.75	7.21
10/3/00 0:00	9:39	118.0	1.81	302.69	7.63
1013100 0:00	9:40	117.5	2.21	301.52	9.33
1013100 0:00	9:41	104.3	3.17	267.49	13.36
1013100 0:00	9:42	60.2	15.50	154.31	65.28
1013100 0:00	9:43	79.2	12.49	203.28	52.63
1013100 0:00	9:44	80.3	2.09	205.98	8.80
1013100 0:00	9:45	58.3	3.87	149.48	16.31
1013100 0:00	9:46	50.6	12.10	129.74	50.96
1013100 0:00	9:47	70.8	4.00	181.67	16.86
1013100 0:00	9:48	60.8	1.99	155.95	8.39
1013100 0:00	9:49	41.0	7.73	105.14	32.56
1013100 0:00	9:50	36.7	8.37	94.24	35.27
1013100 0:00	9:51	36.3	7.16	93.09	30.17
1013100 0:00	9:52	38.0	6.64	97.54	27.95
1013100 0:00	9:53	43.6	6.77	111.96	28.52
1013100 0:00	9:54	44.1	6.63	113.19	27.93
1013100 0:00	9:55	98.9	7.72	253.79	32.52
1013100 0:00	9:56	55.7	6.69	142.75	28.19
1013100 0:00	9:57	39.9	6.07	102.42	25.57
10/3/00 0:00	9:58	37.5	5.89	96.08	24.80
1013100 0:00	9:59	37.4	5.91	95.83	24.91
1013100 0:00	10:00	36.3	6.01	93.08	25.32
1013100 0:00	10:01	37.1	4.96	95.14	20.88
1013100 0:00	10:02	52.3	4.70	134.04	19.82
1013100 0:00	10:03	74.9	3.03	192.13	12.76
1013100 0:00	10:04	75.1	2.41	192.66	10.13

10/3/00 0:00	10:05	62.6	2.40	160.69	10.10
10/3/00 0:00	10:06	59.0	2.37	151.33	9.99
10/3/00 0:00	10:07	59.0	2.19	151.22	9.24
10/3/00 0:00	10:08	59.5	2.21	152.60	9.30
10/3/00 0:00	10:09	61.3	2.34	157.21	9.87
10/3/00 0:00	10:10	61.6	2.34	157.97	9.85
10/3/00 0:00	10:11	63.9	2.22	163.79	9.37
10/3/00 0:00	10:12	63.8	2.24	163.69	9.46
10/3/00 0:00	10:13	61.9	2.10	158.66	8.86
10/3/00 0:00	10:14	64.1	1.91	164.31	8.05
10/3/00 0:00	10:15	60.8	1.88	156.07	7.94
10/3/00 0:00	10:16	59.0	1.93	151.30	8.14
10/3/00 0:00	10:17	58.9	2.22	150.97	9.36
10/3/00 0:00	10:18	57.5	2.46	147.54	10.36
10/3/00 0:00	10:19	60.4	2.48	154.90	10.43
10/3/00 0:00	10:20	62.2	2.32	159.52	9.77
10/3/00 0:00	10:21	61.9	2.11	158.76	8.89
10/3/00 0:00	10:22	59.3	2.14	152.07	9.03
10/3/00 0:00	10:23	62.5	2.31	160.20	9.73
10/3/00 0:00	10:24	59.3	2.56	152.06	10.78
10/3/00 0:00	10:25	63.0	2.56	161.71	10.78
10/3/00 0:00	10:26	61.9	2.49	158.70	10.47
10/3/00 0:00	10:27	56.0	2.58	143.74	10.86
10/3/00 0:00	10:28	50.6	2.86	129.87	12.05
10/3/00 0:00	10:29	48.8	2.69	125.15	11.31
10/3/00 0:00	10:30	46.5	3.09	119.40	13.00
10/3/00 0:00	10:31	48.7	2.94	124.94	12.36
10/3/00 0:00	10:32	51.2	3.18	131.37	13.38
10/3/00 0:00	10:33	50.4	3.37	129.21	14.19
10/3/00 0:00	10:34	47.6	3.60	121.98	15.17
10/3/00 0:00	10:35	48.1	3.72	123.45	15.66
10/3/00 0:00	10:36	48.2	4.02	123.68	16.95
10/3/00 0:00	10:37	46.2	3.83	118.53	16.14
10/3/00 0:00	10:38	46.5	3.53	119.19	14.88
10/3/00 0:00	10:39	45.8	3.58	117.48	15.07
10/3/00 0:00	10:40	46.3	3.67	118.75	15.47
10/3/00 0:00	10:41	46.3	3.94	118.75	16.59
10/3/00 0:00	10:42	47.0	3.65	120.67	15.40
10/3/00 0:00	10:43	47.5	2.84	121.91	11.94
10/3/00 0:00	10:44	44.7	2.84	114.56	11.97
10/3/00 0:00	10:45	43.3	3.35	111.07	14.12
10/3/00 0:00	10:46	43.3	3.74	111.06	15.75
10/3/00 0:00	10:47	44.1	3.75	113.03	15.80
10/3/00 0:00	10:48	44.3	3.95	113.62	16.63
10/3/00 0:00	10:49	44.6	3.85	114.32	16.23
10/3/00 0:00	10:50	44.7	3.67	114.64	15.47
10/3/00 0:00	10:51	44.1	3.74	113.21	15.76
10/3/00 0:00	10:52	43.4	3.70	111.22	15.59
10/3/00 0:00	10:53	47.5	3.17	121.74	13.34
10/3/00 0:00	10:54	45.7	2.60	117.30	10.96
10/3/00 0:00	10:55	43.1	3.01	110.54	12.66
10/3/00 0:00	10:56	42.3	3.42	108.50	14.43

Min001

10/3/00 0:00	10:57	42.3	3.33	108.49	14.02
10/3/00 0:00	10:58	42.2	3.26	108.23	13.72
10/3/00 0:00	10:59	42.1	3.05	107.88	12.85
10/3/00 0:00	11:00	41.8	3.58	107.21	15.09
10/3/00 0:00	11:01	42.0	3.82	107.79	16.10
10/3/00 0:00	11:02	41.3	3.73	105.93	15.73
10/3/00 0:00	11:03	40.7	3.88	104.38	16.35
10/3/00 0:00	11:04	41.2	4.13	105.76	17.40
10/3/00 0:00	11:05	41.1	4.13	105.49	17.41
10/3/00 0:00	11:06	41.3	3.89	105.92	16.39
10/3/00 0:00	11:07	41.3	3.96	105.93	16.70
10/3/00 0:00	11:08	42.1	4.14	107.94	17.42
10/3/00 0:00	11:09	41.5	4.32	106.46	18.19
10/3/00 0:00	11:10	41.9	4.21	107.50	17.72
10/3/00 0:00	11:11	42.6	4.09	109.24	17.23
10/3/00 0:00	11:12	42.8	4.00	109.90	16.83
10/3/00 0:00	11:13	41.5	3.69	106.49	15.54
10/3/00 0:00	11:14	41.3	3.61	105.92	15.19

81.2 3.8

Date	Hour	CO	NOX	COPPH	NOXPPH
10/3/00 0:00	15:29	328.2	3.67	841.76	15.44
10/3/00 0:00	15:30	340.5	3.35	873.40	14.10
10/3/00 0:00	15:31	238.0	2.76	610.42	11.61
10/3/00 0:00	15:32	197.6	2.20	506.96	9.26
10/3/00 0:00	15:33	174.4	1.92	447.34	8.10
10/3/00 0:00	15:34	147.6	1.64	378.65	6.89
10/3/00 0:00	15:35	166.1	1.44	426.14	6.08
10/3/00 0:00	15:36	154.3	1.46	395.91	6.13
10/3/00 0:00	15:37	61.0	6.31	156.45	26.57
10/3/00 0:00	15:38	54.0	8.12	138.41	34.21
10/3/00 0:00	15:39	132.1	3.14	338.73	13.22
10/3/00 0:00	15:40	102.1	1.78	262.02	7.51
10/3/00 0:00	15:41	89.6	1.58	229.84	6.65
10/3/00 0:00	15:42	93.7	1.62	240.41	6.81
10/3/00 0:00	15:43	86.8	1.67	222.70	7.05
10/3/00 0:00	15:44	69.6	1.47	178.48	6.19
10/3/00 0:00	15:45	81.2	1.38	208.34	5.83
10/3/00 0:00	15:46	88.6	1.53	227.16	6.46
10/3/00 0:00	15:47	76.1	1.49	195.10	6.28
10/3/00 0:00	15:48	56.1	1.59	143.86	6.69
10/3/00 0:00	15:49	51.4	1.80	131.91	7.58
10/3/00 0:00	15:50	41.8	3.74	107.11	15.75
10/3/00 0:00	15:51	30.8	7.13	78.93	30.03
10/3/00 0:00	15:52	30.3	5.62	77.64	23.66
10/3/00 0:00	15:53	29.3	4.74	75.07	19.98
10/3/00 0:00	15:54	29.8	4.50	76.34	18.95
10/3/00 0:00	15:55	29.3	5.16	75.07	21.74
10/3/00 0:00	15:56	36.6	26.91	93.86	113.36
10/3/00 0:00	15:57	63.7	10.39	163.50	43.79
10/3/00 0:00	15:58	58.6	2.71	150.26	11.40
10/3/00 0:00	15:59	35.9	7.61	92.17	32.05
10/3/00 0:00	16:00	28.6	7.23	73.36	30.44
10/3/00 0:00	16:01	28.3	6.81	72.52	28.68
10/3/00 0:00	16:02	28.3	6.64	72.50	27.99
10/3/00 0:00	16:03	28.3	6.42	72.52	27.03
10/3/00 0:00	16:04	28.3	6.20	72.51	26.12
10/3/00 0:00	16:05	27.9	5.84	71.67	24.59
10/3/00 0:00	16:06	27.3	5.39	69.96	22.71
10/3/00 0:00	16:07	27.3	5.12	69.95	21.57
10/3/00 0:00	16:08	27.3	5.18	69.95	21.82
10/3/00 0:00	16:09	27.5	5.32	70.42	22.41
10/3/00 0:00	16:10	32.9	5.42	84.39	22.85
10/3/00 0:00	16:11	32.7	5.61	83.88	23.65
10/3/00 0:00	16:12	47.6	7.02	122.12	29.59
10/3/00 0:00	16:13	41.9	7.23	107.60	30.46
10/3/00 0:00	16:14	32.9	6.10	84.35	25.69
10/3/00 0:00	16:15	30.8	6.10	78.89	25.68
10/3/00 0:00	16:16	29.7	6.16	76.30	25.93
10/3/00 0:00	16:17	29.3	6.03	75.08	25.41
10/3/00 0:00	16:18	29.3	5.88	75.08	24.77
10/3/00 0:00	16:19	28.9	5.77	74.19	24.32

Min001

10/3/00 0:00	16:20	28.3	5.12	72.52	21.57
10/3/00 0:00	16:21	28.3	2.84	72.51	11.95
10/3/00 0:00	16:22	28.3	1.56	72.51	6.58
10/3/00 0:00	16:23	28.3	1.30	72.52	5.49
10/3/00 0:00	16:24	28.3	1.44	72.51	6.05
10/3/00 0:00	16:25	28.3	1.67	72.52	7.04
10/3/00 0:00	16:26	28.8	1.68	73.84	7.07
10/3/00 0:00	16:27	29.3	1.68	75.08	7.07
10/3/00 0:00	16:28	29.3	1.70	75.07	7.18
10/3/00 0:00	16:29	29.3	1.78	75.08	7.49
10/3/00 0:00	16:30	29.3	1.74	75.07	7.32
10/3/00 0:00	16:31	29.3	1.67	75.08	7.03
10/3/00 0:00	16:32	29.3	1.61	75.08	6.77
10/3/00 0:00	16:33	29.3	1.68	75.07	7.07
10/3/00 0:00	16:34	29.3	1.64	75.09	6.89
10/3/00 0:00	16:35	29.3	1.62	75.07	6.84
10/3/00 0:00	16:36	29.3	1.72	75.08	7.24
10/3/00 0:00	16:37	29.3	1.52	75.05	6.40
10/3/00 0:00	16:38	34.4	1.89	88.32	7.95
10/3/00 0:00	16:39	85.3	3.78	218.79	15.94
10/3/00 0:00	16:40	117.3	2.84	300.82	11.95
10/3/00 0:00	16:41	90.3	2.38	231.52	10.01
10/3/00 0:00	16:42	63.4	2.04	162.67	8.59
10/3/00 0:00	16:43	51.6	2.43	132.34	10.22
10/3/00 0:00	16:44	72.8	7.13	186.68	30.04
10/3/00 0:00	16:45	47.4	2.96	121.56	12.46
10/3/00 0:00	16:46	37.0	2.06	94.81	8.66
10/3/00 0:00	16:47	34.7	1.77	89.07	7.45
10/3/00 0:00	16:48	33.7	1.92	86.50	8.07
10/3/00 0:00	16:49	33.3	2.01	85.31	8.46
10/3/00 0:00	16:50	33.3	1.97	85.30	8.31
10/3/00 0:00	16:51	32.7	1.80	83.92	7.56
10/3/00 0:00	16:52	32.3	1.85	82.76	7.80
10/3/00 0:00	16:53	32.2	1.64	82.66	6.91
10/3/00 0:00	16:54	31.3	1.49	80.21	6.28
10/3/00 0:00	16:55	31.2	1.38	80.10	5.81
10/3/00 0:00	16:56	30.5	1.42	78.18	6.00
10/3/00 0:00	16:57	31.1	1.64	79.66	6.89
10/3/00 0:00	16:58	30.5	1.48	78.18	6.22
10/3/00 0:00	16:59	31.3	1.60	80.22	6.76
10/3/00 0:00	17:00	30.4	1.85	77.93	7.79
10/3/00 0:00	17:01	30.3	1.70	77.63	7.16
10/3/00 0:00	17:02	30.3	1.69	77.65	7.12
10/3/00 0:00	17:03	30.3	1.75	77.65	7.38
10/3/00 0:00	17:04	30.1	1.54	77.09	6.49
10/3/00 0:00	17:05	29.8	1.51	76.48	6.35
10/3/00 0:00	17:06	29.4	1.67	75.39	7.05
10/3/00 0:00	17:07	29.3	1.58	75.07	6.67
10/3/00 0:00	17:08	29.3	1.63	75.08	6.85
10/3/00 0:00	17:09	29.3	1.73	75.07	7.27
10/3/00 0:00	17:10	29.3	1.64	75.08	6.89
10/3/00 0:00	17:11	29.3	1.54	75.07	6.50

Min001

10/3/00 0:00	17:12	29.3	1.81	75.08	7.61
10/3/00 0:00	17:13	29.3	1.75	75.08	7.38
10/3/00 0:00	17:14	29.3	1.68	75.08	7.07
10/3/00 0:00	17:15	29.3	1.76	75.08	7.41
10/3/00 0:00	17:16	29.3	1.69	75.07	7.10
10/3/00 0:00	17:17	28.4	1.36	72.78	5.71
10/3/00 0:00	17:18	28.3	1.22	72.51	5.12
10/3/00 0:00	17:19	28.3	1.12	72.52	4.70
10/3/00 0:00	17:20	28.3	1.08	72.52	4.55
10/3/00 0:00	17:21	28.3	1.08	72.53	4.55
10/3/00 0:00	17:22	28.3	1.08	72.51	4.55
10/3/00 0:00	17:23	28.3	1.08	72.53	4.55
10/3/00 0:00	17:24	28.3	1.02	72.51	4.28
10/3/00 0:00	17:25	28.3	0.98	72.53	4.12
10/3/00 0:00	17:26	31.9	12.17	81.91	51.26
10/3/00 0:00	17:27	62.3	17.87	159.69	75.27
10/3/00 0:00	17:28	82.7	3.59	212.13	15.13
10/3/00 0:00	17:29	108.7	3.33	278.78	14.03
10/3/00 0:00	17:30	113.1	4.28	290.13	18.01
10/3/00 0:00	17:31	96.4	4.51	247.24	18.98
10/3/00 0:00	17:32	152.3	4.24	390.60	17.87
10/3/00 0:00	17:33	258.9	3.31	663.98	13.94
10/3/00 0:00	17:34	197.1	2.66	505.71	11.21
10/3/00 0:00	17:35	151.3	1.94	387.99	8.15
10/3/00 0:00	17:36	135.2	1.63	346.79	6.88
10/3/00 0:00	17:37	145.8	1.46	374.11	6.16
10/3/00 0:00	17:38	119.2	2.26	305.78	9.53
10/3/00 0:00	17:39	40.8	4.53	104.55	19.07
10/3/00 0:00	17:40	39.4	4.25	101.15	17.89
10/3/00 0:00	17:41	89.7	2.87	230.15	12.08
10/3/00 0:00	17:42	120.7	2.28	309.62	9.62
10/3/00 0:00	17:43	131.8	2.10	338.03	8.83
10/3/00 0:00	17:44	140.8	8.65	361.08	36.43
10/3/00 0:00	17:45	64.0	6.05	164.15	25.47
10/3/00 0:00	17:46	51.6	4.33	132.33	18.24
10/3/00 0:00	17:47	59.4	4.21	152.42	17.75
10/3/00 0:00	17:48	122.3	4.10	313.67	17.25
10/3/00 0:00	17:49	192.2	4.23	493.10	17.82
10/3/00 0:00	17:50	240.3	4.23	616.35	17.82
10/3/00 0:00	17:51	262.6	4.10	673.63	17.26
10/3/00 0:00	17:52	217.7	4.13	558.45	17.40
10/3/00 0:00	17:53	184.7	4.13	473.89	17.40
10/3/00 0:00	17:54	112.8	3.90	289.26	16.42
10/3/00 0:00	17:55	137.9	3.01	353.78	12.69
10/3/00 0:00	17:56	294.5	2.16	755.47	9.11
10/3/00 0:00	17:57	261.0	1.86	669.44	7.85
10/3/00 0:00	17:58	192.5	2.26	493.73	9.53
10/3/00 0:00	17:59	65.1	3.45	167.11	14.52
10/3/00 0:00	18:00	65.8	7.51	168.90	31.62
10/3/00 0:00	18:01	140.9	2.60	361.55	10.97
10/3/00 0:00	18:02	108.5	1.33	278.19	5.60
10/3/00 0:00	18:03	107.7	1.48	276.19	6.25

Min001

10/3/00 0:00	18:04	78.2	1.53	200.52	6.44
10/3/00 0:00	18:05	85.9	1.51	220.32	6.38
10/3/00 0:00	18:06	112.6	1.61	288.76	6.80
10/3/00 0:00	18:07	108.9	1.70	279.37	7.15
10/3/00 0:00	18:08	117.8	1.85	302.10	7.78
10/3/00 0:00	18:09	114.6	1.99	294.06	8.36
10/3/00 0:00	18:10	120.0	2.28	307.92	9.59
10/3/00 0:00	18:11	73.8	1.89	189.31	7.97
10/3/00 0:00	18:12	59.8	1.69	153.36	7.14
10/3/00 0:00	18:13	75.9	2.02	194.69	8.53
10/3/00 0:00	18:14	84.9	2.30	217.76	9.69
10/3/00 0:00	18:15	60.1	3.20	154.25	13.48
10/3/00 0:00	18:16	101.3	2.22	259.87	9.35
10/3/00 0:00	18:17	100.6	2.86	258.14	12.05
10/3/00 0:00	18:18	52.5	2.56	134.55	10.78
10/3/00 0:00	18:19	50.6	6.31	129.69	26.59
10/3/00 0:00	18:20	45.6	5.25	116.94	22.10
10/3/00 0:00	18:21	41.0	3.65	105.27	15.37
10/3/00 0:00	18:22	44.3	13.61	113.57	57.33
10/3/00 0:00	18:23	41.7	9.89	106.92	41.68
10/3/00 0:00	18:24	46.3	10.57	118.74	44.52
10/3/00 0:00	18:25	42.4	4.18	108.88	17.61
10/3/00 0:00	18:26	36.0	11.13	92.24	46.89
10/3/00 0:00	18:27	37.5	11.22	96.21	47.29
10/3/00 0:00	18:28	40.9	10.27	104.95	43.28
10/3/00 0:00	18:29	46.6	9.86	119.42	41.55
		71.9	3.6		

Run 2

Min001

Date	Hour	CO	NOX	COPPH	NOXPPH
1014100 0:00	7:00	60.8	3.64	155.90	15.33
1014100 0:00	7:01	63.4	3.56	162.75	15.01
1014100 0:00	7:02	73.9	3.08	189.50	12.99
1014100 0:00	7:03	67.1	2.73	172.14	11.50
1014100 0:00	7:04	78.0	2.31	200.08	9.74
1014100 0:00	7:05	88.7	1.85	227.60	7.81
1014100 0:00	7:06	72.4	1.49	185.63	6.27
1014100 0:00	7:07	68.9	1.31	176.75	5.53
1014100 0:00	7:08	67.3	1.03	172.75	4.33
1014100 0:00	7:09	51.2	1.62	131.22	6.83
10/4/00 0:00	7:10	41.4	4.51	106.23	19.01
1014100 0:00	7:11	70.8	3.18	181.50	13.40
1014100 0:00	7:12	89.4	2.62	229.36	11.04
1014100 0:00	7:13	62.2	4.86	159.59	20.49
1014100 0:00	7:14	40.0	4.09	102.64	17.22
10/4/00 0:00	7:15	45.3	3.90	116.09	16.45
10/4/00 0:00	7:16	81.7	3.70	209.61	15.61
10/4/00 0:00	7:17	133.1	3.28	341.36	13.81
10/4/00 0:00	7:18	192.2	2.94	492.90	12.38
1014100 0:00	7:19	174.9	1.95	448.67	8.23
1014100 0:00	7:20	149.6	1.26	383.76	5.31
1014100 0:00	7:21	100.4	1.10	257.41	4.64
1014100 0:00	7:22	74.8	1.18	191.92	4.95
10/4/00 0:00	7:23	90.0	1.47	230.76	6.18
1014100 0:00	7:24	103.8	1.55	266.28	6.54
1014100 0:00	7:25	138.5	1.37	355.25	5.77
1014100 0:00	7:26	147.1	1.48	377.24	6.23
1014100 0:00	7:27	85.7	3.57	219.87	15.04
1014100 0:00	7:28	80.7	8.06	206.91	33.96
1014100 0:00	7:29	139.1	3.46	356.71	14.56
1014100 0:00	7:30	164.2	0.97	421.11	4.07
1014100 0:00	7:31	170.4	0.78	436.97	3.27
1014100 0:00	7:32	159.4	0.69	408.97	2.90
1014100 0:00	7:33	134.6	0.78	345.24	3.28
1014100 0:00	7:34	134.1	0.86	343.87	3.60
1014100 0:00	7:35	106.1	0.88	272.10	3.70
1014100 0:00	7:36	102.5	0.95	262.87	4.00
1014100 0:00	7:37	124.8	1.11	320.21	4.66
1014100 0:00	7:38	124.2	1.36	318.61	5.74
1014100 0:00	7:39	122.1	1.71	313.19	7.20
1014100 0:00	7:40	102.8	2.13	263.64	8.99
1014100 0:00	7:41	78.8	8.39	202.04	35.36
1014100 0:00	7:42	79.6	10.91	204.27	45.97
1014100 0:00	7:43	80.1	9.19	205.39	38.72
10/4/00 0:00	7:44	37.3	20.89	95.58	88.02
1014100 0:00	7:45	37.2	19.62	95.41	82.66
1014100 0:00	7:46	60.5	4.91	155.24	20.69
1014100 0:00	7:47	41.6	9.03	106.61	38.05
10/4/00 0:00	7:48	33.4	15.65	85.58	65.92
1014100 0:00	7:49	31.9	13.10	81.76	55.20
10/4/00 0:00	7:50	56.5	12.52	144.98	52.73

Min001

10/4/00 0:00 7:51	46.0	11.10	117.90	46.77
10/4/00 0:00 7:52	32.2	9.22	82.67	38.86
10/4/00 0:00 7:53	30.4	8.45	77.90	35.60
10/4/00 0:00 7:54	29.5	8.37	75.70	35.25
10/4/00 0:00 7:55	29.3	8.13	75.09	34.24
10/4/00 0:00 7:56	29.3	7.85	75.07	33.08
10/4/00 0:00 7:57	28.9	7.94	74.01	33.46
10/4/00 0:00 7:58	28.3	8.04	72.50	33.89
10/4/00 0:00 7:59	28.3	8.05	72.53	33.91
10/4/00 0:00 8:00	28.7	7.98	73.58	33.62
10/4/00 0:00 8:01	29.3	7.49	75.08	31.56
10/4/00 0:00 8:02	30.5	6.27	78.29	26.43
10/4/00 0:00 8:03	32.4	6.21	82.99	26.15
10/4/00 0:00 8:04	33.3	5.83	85.32	24.55
10/4/00 0:00 8:05	33.3	5.82	85.32	24.51
10/4/00 0:00 8:06	33.7	6.15	86.40	25.90
10/4/00 0:00 8:07	33.9	6.02	87.00	25.35
10/4/00 0:00 8:08	34.3	6.04	87.89	25.46
10/4/00 0:00 8:09	34.5	6.11	88.51	25.74
10/4/00 0:00 8:10	34.4	6.04	88.32	25.46
10/4/00 0:00 8:11	33.3	5.65	85.32	23.79
10/4/00 0:00 8:12	34.0	6.10	87.25	25.70
10/4/00 0:00 8:13	34.2	6.04	87.66	25.44
10/4/00 0:00 8:14	36.5	5.45	93.58	22.96
10/4/00 0:00 8:15	47.0	3.44	120.54	14.48
10/4/00 0:00 8:16	47.6	3.33	122.18	14.01
10/4/00 0:00 8:17	60.8	7.48	156.01	31.49
10/4/00 0:00 8:18	81.1	5.59	208.12	23.56
10/4/00 0:00 8:19	88.7	2.33	227.52	9.81
10/4/00 0:00 8:20	90.7	1.95	232.70	8.22
10/4/00 0:00 8:21	95.8	1.83	245.81	7.70
10/4/00 0:00 8:22	87.4	1.69	224.12	7.11
10/4/00 0:00 8:23	70.1	1.35	179.87	5.69
10/4/00 0:00 8:24	69.4	1.28	177.95	5.38
10/4/00 0:00 8:25	69.3	1.31	177.69	5.52
10/4/00 0:00 8:26	72.9	1.39	186.93	5.87
10/4/00 0:00 8:27	78.2	1.46	200.60	6.17
10/4/00 0:00 8:28	76.3	1.30	195.66	5.47
10/4/00 0:00 8:29	60.5	1.28	155.23	5.39
10/4/00 0:00 8:30	102.7	1.26	263.55	5.32
10/4/00 0:00 8:31	64.7	1.70	165.91	7.18
10/4/00 0:00 8:32	33.2	2.43	85.24	10.23
10/4/00 0:00 8:33	72.7	2.18	186.56	9.18
10/4/00 0:00 8:34	117.8	1.55	302.11	6.51
10/4/00 0:00 8:35	111.8	1.38	286.89	5.81
10/4/00 0:00 8:36	108.3	1.68	277.81	7.07
10/4/00 0:00 8:37	70.7	5.46	181.24	23.01
10/4/00 0:00 8:38	49.7	3.21	127.51	13.53
10/4/00 0:00 8:39	42.6	3.08	109.34	12.97
10/4/00 0:00 8:40	56.1	2.85	143.83	11.99
10/4/00 0:00 8:41	64.3	2.68	164.97	11.29
10/4/00 0:00 8:42	94.2	2.35	241.73	9.88

10/4/00 0:00	8:43	167.3	2.35	429.15	9.88
10/4/00 0:00	8:44	186.0	2.38	477.20	10.02
10/4/00 0:00	8:45	188.8	2.71	484.30	11.43
10/4/00 0:00	8:46	169.2	3.26	434.09	13.74
10/4/00 0:00	8:47	253.4	3.55	649.96	14.94
10/4/00 0:00	8:48	287.8	3.86	738.12	16.27
10/4/00 0:00	8:49	254.7	3.41	653.45	14.38
10/4/00 0:00	8:50	237.1	3.54	608.16	14.91
10/4/00 0:00	8:51	172.3	2.62	441.85	11.02
10/4/00 0:00	8:52	156.7	1.98	401.93	8.36
10/4/00 0:00	8:53	116.5	1.49	298.94	6.30
10/4/00 0:00	8:54	142.0	1.51	364.20	6.37
10/4/00 0:00	8:55	158.0	1.28	405.39	5.37
10/4/00 0:00	8:56	208.6	1.18	535.17	4.97
10/4/00 0:00	8:57	176.2	1.21	452.06	5.11
10/4/00 0:00	8:58	158.5	1.26	406.62	5.30
10/4/00 0:00	8:59	124.2	3.36	318.50	14.14
10/4/00 0:00	9:00	58.5	7.67	150.04	32.31
10/4/00 0:00	9:01	115.5	5.47	296.28	23.06
10/4/00 0:00	9:02	94.2	1.34	241.53	5.65
10/4/00 0:00	9:03	125.3	1.33	321.47	5.60
10/4/00 0:00	9:04	136.3	1.40	349.61	5.88
10/4/00 0:00	9:05	105.6	1.38	270.82	5.81
10/4/00 0:00	9:06	77.2	1.46	197.96	6.17
10/4/00 0:00	9:07	84.6	1.70	216.91	7.14
10/4/00 0:00	9:08	76.3	2.21	195.72	9.31
10/4/00 0:00	9:09	64.3	2.47	165.06	10.39
10/4/00 0:00	9:10	50.4	7.80	129.26	32.86
10/4/00 0:00	9:11	39.4	16.27	100.98	68.55
10/4/00 0:00	9:12	64.2	8.30	164.62	34.97
10/4/00 0:00	9:13	60.1	3.14	154.29	13.23
10/4/00 0:00	9:14	52.4	4.41	134.39	18.59
10/4/00 0:00	9:15	41.0	16.25	105.08	68.47
10/4/00 0:00	9:16	53.0	6.22	135.84	26.19
10/4/00 0:00	9:17	34.2	9.43	87.81	39.72
10/4/00 0:00	9:18	32.1	15.18	82.41	63.95
10/4/00 0:00	9:19	32.6	14.24	83.51	59.99
10/4/00 0:00	9:20	57.0	14.21	146.08	59.88
10/4/00 0:00	9:21	54.4	11.89	139.64	50.10
10/4/00 0:00	9:22	33.5	9.43	86.05	39.72
10/4/00 0:00	9:23	30.5	8.94	78.13	37.67
10/4/00 0:00	9:24	29.6	8.49	75.97	35.78
10/4/00 0:00	9:25	29.3	8.07	75.07	34.00
10/4/00 0:00	9:26	28.4	6.89	72.95	29.02
10/4/00 0:00	9:27	29.9	6.14	76.75	25.88
10/4/00 0:00	9:28	30.3	6.05	77.63	25.48
10/4/00 0:00	9:29	31.4	6.54	80.56	27.56
10/4/00 0:00	9:30	37.6	10.78	96.37	45.41
10/4/00 0:00	9:31	57.7	10.59	147.89	44.60
10/4/00 0:00	9:32	55.9	5.75	143.45	24.23
10/4/00 0:00	9:33	50.9	5.05	130.62	21.28
10/4/00 0:00	9:34	51.8	4.30	132.90	18.13

Min001

10/4/00 0:00 9:35	77.5	4.00	198.92	16.87
10/4/00 0:00 9:36	80.0	3.03	205.27	12.76
10/4/00 0:00 9:37	99.3	2.09	254.77	8.81
10/4/00 0:00 9:38	109.8	1.15	281.56	4.86
10/4/00 0:00 9:39	100.1	0.96	256.71	4.03
10/4/00 0:00 9:40	100.7	0.96	258.33	4.02
10/4/00 0:00 9:41	112.0	1.24	287.39	5.22
10/4/00 0:00 9:42	123.4	1.27	316.44	5.36
10/4/00 0:00 9:43	114.7	1.16	294.26	4.87
10/4/00 0:00 9:44	107.5	1.02	275.87	4.31
10/4/00 0:00 9:45	112.2	1.05	287.84	4.42
10/4/00 0:00 9:46	72.6	2.62	186.16	11.05
10/4/00 0:00 9:47	49.1	4.93	125.93	20.78
10/4/00 0:00 9:48	62.6	3.14	160.52	13.24
10/4/00 0:00 9:49	67.7	4.44	173.76	18.72
10/4/00 0:00 9:50	52.4	3.72	134.47	15.67
10/4/00 0:00 9:51	55.4	2.88	142.15	12.15
10/4/00 0:00 9:52	77.2	2.70	198.15	11.37
10/4/00 0:00 9:53	92.6	2.48	237.41	10.46
10/4/00 0:00 9:54	108.2	2.34	277.58	9.85
10/4/00 0:00 9:55	93.4	2.28	239.56	9.60
10/4/00 0:00 9:56	120.7	2.26	309.63	9.53
10/4/00 0:00 9:57	149.2	2.37	382.66	9.97
10/4/00 0:00 9:58	124.9	2.38	320.31	10.02
10/4/00 0:00 9:59	132.7	2.02	340.38	8.52
10/4/00 0:00 10:00	171.7	2.06	440.34	8.68
10/4/00 0:00 10:01	181.8	2.05	466.41	8.62
10/4/00 0:00 10:02	161.8	1.75	415.11	7.39
10/4/00 0:00 10:03	106.1	1.47	272.10	6.20
10/4/00 0:00 10:04	84.6	1.49	216.97	6.27
10/4/00 0:00 10:05	48.8	2.02	125.28	8.51
10/4/00 0:00 10:06	45.2	2.86	115.86	12.06
10/4/00 0:00 10:07	43.9	5.60	112.60	23.61
10/4/00 0:00 10:08	72.0	5.05	184.74	21.26
10/4/00 0:00 10:09	98.8	1.74	253.39	7.32
10/4/00 0:00 10:10	96.4	0.95	247.24	3.98
10/4/00 0:00 10:11	124.3	0.84	318.77	3.53
10/4/00 0:00 10:12	98.5	0.82	252.75	3.46
10/4/00 0:00 10:13	85.3	2.16	218.76	9.11
10/4/00 0:00 10:14	48.9	9.36	125.41	39.45
10/4/00 0:00 10:15	60.8	11.62	155.84	48.93
10/4/00 0:00 10:16	75.6	2.80	193.85	11.78
10/4/00 0:00 10:17	71.2	1.60	182.65	6.76
10/4/00 0:00 10:18	78.8	1.10	202.04	4.64
10/4/00 0:00 10:19	81.1	1.01	207.96	4.24
10/4/00 0:00 10:20	83.9	1.29	215.19	5.42
10/4/00 0:00 10:21	82.2	3.33	210.76	14.01
10/4/00 0:00 10:22	38.4	13.71	98.48	57.75
10/4/00 0:00 10:23	41.8	17.95	107.11	75.63
10/4/00 0:00 10:24	53.5	4.99	137.28	21.02
10/4/00 0:00 10:25	41.5	9.52	106.34	40.09
10/4/00 0:00 10:26	42.8	17.18	109.69	72.36

Min001

10/4/00 0:00	10:27	55.9	4.19	143.37	17.64
10/4/00 0:00	10:28	44.6	7.95	114.49	33.48
10/4/00 0:00	10:29	30.9	12.17	79.18	51.25
10/4/00 0:00	10:30	30.7	11.49	78.76	48.41
10/4/00 0:00	10:31	33.3	10.72	85.31	45.15
10/4/00 0:00	10:32	33.5	9.54	86.01	40.19
10/4/00 0:00	10:33	49.9	9.61	128.07	40.49
10/4/00 0:00	10:34	35.4	8.64	90.79	36.42
10/4/00 0:00	10:35	29.6	8.30	75.86	34.98
10/4/00 0:00	10:36	29.3	7.40	75.07	31.19
10/4/00 0:00	10:37	30.0	5.76	76.88	24.25
10/4/00 0:00	10:38	59.0	6.00	151.37	25.29
10/4/00 0:00	10:39	69.5	3.74	178.20	15.76
10/4/00 0:00	10:40	51.2	9.75	131.30	41.06
10/4/00 0:00	10:41	60.8	6.77	155.85	28.53
10/4/00 0:00	10:42	86.4	2.91	221.69	12.24
10/4/00 0:00	10:43	86.4	2.13	221.63	8.98
10/4/00 0:00	10:44	71.9	1.49	184.44	6.28
10/4/00 0:00	10:45	84.3	1.36	216.27	5.73
10/4/00 0:00	10:46	93.1	1.34	238.74	5.65
10/4/00 0:00	10:47	112.6	1.39	288.73	5.86
10/4/00 0:00	10:48	109.2	1.36	280.00	5.71
10/4/00 0:00	10:49	109.4	1.23	280.75	5.20
10/4/00 0:00	10:50	81.2	1.18	208.31	4.96
10/4/00 0:00	10:51	85.2	1.06	218.45	4.45
10/4/00 0:00	10:52	82.5	0.95	211.51	3.98
10/4/00 0:00	10:53	64.9	0.88	166.48	3.72
10/4/00 0:00	10:54	53.3	0.85	136.76	3.58
10/4/00 0:00	10:55	44.0	1.01	112.89	4.24
10/4/00 0:00	10:56	33.1	2.76	84.92	11.61
10/4/00 0:00	10:57	34.1	4.01	87.34	16.89
10/4/00 0:00	10:58	55.6	2.80	142.71	11.78
10/4/00 0:00	10:59	67.8	2.55	173.89	10.75
10/4/00 0:00	11:00	49.7	6.93	127.38	29.20
		80.5	4.5		

Run 3

Min001

Date	Hour	CO	NOX	COPPH	NOXPPt zero	avg	
10/4/00 0:00	11:00	49.7	6.93	127.38	29.20	26.3	0
10/4/00 0:00	11:01	34.6	4.05	88.63	17.04	26.3	0
10/4/00 0:00	11:02	38.0	3.43	97.38	14.43	26.3	0
10/4/00 0:00	11:03	83.6	2.77	214.38	11.65	26.3	0
10/4/00 0:00	11:04	129.4	2.67	331.87	11.26	26.3	0
10/4/00 0:00	11:05	128.2	2.75	328.88	11.58	26.3	0
10/4/00 0:00	11:06	229.2	2.76	588.02	11.61	26.3	0
10/4/00 0:00	11:07	224.4	2.93	575.63	12.34	26.3	0
10/4/00 0:00	11:08	240.7	2.63	617.55	11.07	26.3	0
10/4/00 0:00	11:09	290.4	2.02	744.88	8.49	26.3	0
10/4/00 0:00	11:10	293.9	1.73	753.93	7.28	26.3	0
10/4/00 0:00	11:11	227.9	1.84	584.49	7.75	26.3	0
10/4/00 0:00	11:12	188.3	2.28	483.12	9.62	26.3	0
10/4/00 0:00	11:13	71.7	5.72	184.03	24.11	26.3	0
10/4/00 0:00	11:14	45.0	11.56	115.49	48.72	26.3	0
10/4/00 0:00	11:15	76.8	13.63	197.02	57.41	26.3	0
10/4/00 0:00	11:16	59.8	18.77	153.27	79.06	26.3	0
10/4/00 0:00	11:17	43.3	17.00	111.14	71.59	26.3	0
10/4/00 0:00	11:18	43.7	12.88	112.10	54.25	26.3	0
10/4/00 0:00	11:19	46.9	10.92	120.38	45.99	26.3	0
10/4/00 0:00	11:20	45.1	9.40	115.71	39.58	26.3	0
10/4/00 0:00	11:21	66.1	5.21	169.58	21.94	26.3	0
10/4/00 0:00	11:22	98.6	1.33	252.80	5.60	26.3	0
10/4/00 0:00	11:23	92.4	1.18	236.89	4.97	26.3	0
10/4/00 0:00	11:24	94.1	2.75	241.27	11.58	26.3	0
10/4/00 0:00	11:25	45.2	7.62	115.82	32.08	26.3	0
10/4/00 0:00	11:26	34.6	10.86	88.65	45.74	26.3	0
10/4/00 0:00	11:27	32.5	13.03	83.44	54.90	26.3	0
10/4/00 0:00	11:28	36.7	13.93	94.14	58.67	26.3	0
10/4/00 0:00	11:29	93.6	8.27	239.98	34.84	26.3	0
10/4/00 0:00	11:30	182.7	1.71	468.76	7.21	26.3	0
10/4/00 0:00	11:31	217.5	1.01	557.79	4.26	26.3	0
10/4/00 0:00	11:32	136.0	0.99	348.92	4.19	26.3	0
10/4/00 0:00	11:33	117.0	1.15	300.21	4.83	26.3	0
10/4/00 0:00	11:34	106.4	2.20	272.86	9.25	26.3	0
10/4/00 0:00	11:35	51.5	10.01	132.12	42.19	26.3	0
10/4/00 0:00	11:36	34.2	12.82	87.65	53.99	26.3	0
10/4/00 0:00	11:37	32.5	12.93	83.41	54.48	26.3	0
10/4/00 0:00	11:38	33.2	13.40	85.07	56.44	26.3	0
10/4/00 0:00	11:39	34.4	13.03	88.31	54.90	26.3	0
10/4/00 0:00	11:40	48.0	5.61	123.14	23.65	26.3	0
10/4/00 0:00	11:41	33.9	9.51	87.04	40.08	26.3	0
10/4/00 0:00	11:42	31.5	11.50	80.84	48.44	26.3	0
10/4/00 0:00	11:43	32.5	9.41	83.42	39.66	26.3	0
10/4/00 0:00	11:44	46.3	8.71	118.86	36.71	26.3	0
10/4/00 0:00	11:45	46.3	8.70	118.66	36.64	26.3	0
10/4/00 0:00	11:46	33.6	8.41	86.16	35.44	26.3	0
10/4/00 0:00	11:47	30.5	8.01	78.28	33.74	26.3	0
10/4/00 0:00	11:48	29.5	7.76	75.72	32.71	26.3	0
10/4/00 0:00	11:49	29.3	7.48	75.08	31.50	26.3	0
10/4/00 0:00	11:50	29.9	6.14	76.62	25.85	26.3	0

Min001

10/4/00 0:00	11:51	30.8	6.00	78.91	25.27	26.3	0
10/4/00 0:00	11:52	31.0	5.93	79.62	24.98	26.3	0
10/4/00 0:00	11:53	40.1	6.27	102.84	26.43	26.3	0
10/4/00 0:00	11:54	59.3	5.45	152.00	22.96	26.3	0
10/4/00 0:00	11:55	46.1	15.29	118.30	64.41	26.3	0
10/4/00 0:00	11:56	39.9	11.72	102.34	49.36	26.3	0
10/4/00 0:00	11:57	43.6	13.72	111.90	57.78	26.3	0
10/4/00 0:00	11:58	44.7	6.14	114.57	25.87	26.3	0
10/4/00 0:00	11:59	51.0	7.24	130.71	30.51	26.3	0
10/4/00 0:00	12:00	82.8	6.12	212.45	25.78	26.3	0
10/4/00 0:00	12:01	94.2	6.32	241.69	26.62	26.3	0
10/4/00 0:00	12:02	104.7	3.56	268.51	14.99	26.3	0
10/4/00 0:00	12:03	106.7	2.91	273.65	12.25	26.3	0
10/4/00 0:00	12:04	77.4	4.11	198.63	17.30	26.3	0
10/4/00 0:00	12:05	86.0	2.19	220.67	9.23	26.3	0
10/4/00 0:00	12:06	124.3	1.32	318.84	5.54	26.3	0
10/4/00 0:00	12:07	180.2	0.96	462.23	4.02	26.3	0
10/4/00 0:00	12:08	131.1	4.76	336.26	20.05	26.3	0
10/4/00 0:00	12:09	57.0	7.88	146.10	33.20	26.3	0
10/4/00 0:00	12:10	85.8	3.43	219.98	14.46	26.3	0
10/4/00 0:00	12:11	81.3	2.29	208.55	9.66	26.3	0
10/4/00 0:00	12:12	61.8	2.35	158.47	9.88	26.3	0
10/4/00 0:00	12:13	58.1	5.19	149.09	21.88	26.3	0
10/4/00 0:00	12:14	44.8	17.39	115.01	73.27	26.3	0
10/4/00 0:00	12:15	48.1	5.27	123.27	22.19	26.3	0
10/4/00 0:00	12:16	51.5	3.70	132.03	15.60	26.3	0
10/4/00 0:00	12:17	57.3	3.21	146.88	13.53	26.3	0
10/4/00 0:00	12:18	79.4	3.34	203.62	14.08	26.3	0
10/4/00 0:00	12:19	109.0	3.14	279.65	13.22	26.3	0
10/4/00 0:00	12:20	118.6	3.96	304.16	16.68	26.3	0
10/4/00 0:00	12:21	82.3	3.30	211.00	13.91	26.3	0
10/4/00 0:00	12:22	93.6	3.05	240.02	12.85	26.3	0
10/4/00 0:00	12:23	184.4	2.58	472.93	10.89	26.3	0
10/4/00 0:00	12:24	142.3	3.90	365.06	16.42	26.3	0
10/4/00 0:00	12:25	163.9	3.92	420.51	16.52	26.3	0
10/4/00 0:00	12:26	192.7	2.16	494.25	9.08	26.3	0
10/4/00 0:00	12:27	202.4	1.09	519.20	4.57	26.3	0
10/4/00 0:00	12:28	192.4	1.19	493.56	5.01	26.3	0
10/4/00 0:00	12:29	148.0	1.74	379.57	7.31	26.3	0
10/4/00 0:00	12:30	68.0	6.99	174.45	29.44	26.3	0
10/4/00 0:00	12:31	33.7	11.83	86.35	49.82	26.3	0
10/4/00 0:00	12:32	32.0	11.08	82.03	46.69	26.3	0
10/4/00 0:00	12:33	71.2	10.27	182.54	43.26	26.3	0
10/4/00 0:00	12:34	79.6	2.22	204.09	9.33	26.3	0
10/4/00 0:00	12:35	125.0	1.74	320.63	7.32	26.3	0
10/4/00 0:00	12:36	159.6	1.89	409.30	7.96	26.3	0
10/4/00 0:00	12:37	168.7	1.81	432.65	7.63	26.3	0
10/4/00 0:00	12:38	220.3	1.91	565.17	8.05	26.3	0
10/4/00 0:00	12:39	233.2	2.17	598.16	9.13	26.3	0
10/4/00 0:00	12:40	197.0	2.27	505.27	9.58	26.3	0
10/4/00 0:00	12:41	173.6	2.52	445.39	10.63	26.3	0
10/4/00 0:00	12:42	187.3	2.83	480.40	11.92	26.3	0

Min001

10/4/00 0:00	12:43	204.2	2.68	523.89	11.27	26.3	0
10/4/00 0:00	12:44	115.1	6.18	295.35	26.02	26.3	0
10/4/00 0:00	12:45	48.8	13.23	125.06	55.71	26.3	0
10/4/00 0:00	12:46	64.4	11.12	165.24	46.84	26.3	0
10/4/00 0:00	12:47	134.6	2.21	345.31	9.32	26.3	0
10/4/00 0:00	12:48	157.7	1.95	404.47	8.23	26.3	0
10/4/00 0:00	12:49	105.8	5.80	271.50	24.42	26.3	0
10/4/00 0:00	12:50	45.9	17.56	117.72	73.97	26.3	0
10/4/00 0:00	12:51	37.8	17.10	97.02	72.02	26.3	0
10/4/00 0:00	12:52	33.0	14.98	84.73	63.12	26.3	0
10/4/00 0:00	12:53	34.6	13.51	88.63	56.91	26.3	0
10/4/00 0:00	12:54	33.1	14.17	84.80	59.69	26.3	0
10/4/00 0:00	12:55	52.2	12.75	133.87	53.71	26.3	0
10/4/00 0:00	12:56	36.1	9.70	92.49	40.85	26.3	0
10/4/00 0:00	12:57	32.8	8.55	84.12	36.03	26.3	0
10/4/00 0:00	12:58	31.6	8.23	81.10	34.68	26.3	0
10/4/00 0:00	12:59	31.1	8.21	79.83	34.60	26.3	0
10/4/00 0:00	13:00	30.3	7.95	77.63	33.48	26.3	0
10/4/00 0:00	13:01	30.3	7.57	77.65	31.90	26.3	0
10/4/00 0:00	13:02	30.3	6.54	77.63	27.54	26.3	0
10/4/00 0:00	13:03	32.2	5.74	82.56	24.17	26.3	0
10/4/00 0:00	13:04	58.0	4.37	148.68	18.41	26.3	0
10/4/00 0:00	13:05	63.1	7.59	161.89	31.97	26.3	0
10/4/00 0:00	13:06	63.2	7.44	162.08	31.34	26.3	0
10/4/00 0:00	13:07	69.9	3.86	179.27	16.27	26.3	0
10/4/00 0:00	13:08	78.7	3.60	201.77	15.15	26.3	0
10/4/00 0:00	13:09	77.3	3.13	198.39	13.18	26.3	0
10/4/00 0:00	13:10	68.3	3.85	175.11	16.24	26.3	0
10/4/00 0:00	13:11	77.8	4.12	199.58	17.36	26.3	0
10/4/00 0:00	13:12	75.3	3.36	193.18	14.16	26.3	0
10/4/00 0:00	13:13	90.3	3.32	231.59	13.99	26.3	0
10/4/00 0:00	13:14	98.0	2.66	251.47	11.22	26.3	0
10/4/00 0:00	13:15	97.4	2.57	249.96	10.83	26.3	0
10/4/00 0:00	13:16	103.0	2.21	264.10	9.32	26.3	0
10/4/00 0:00	13:17	99.0	1.99	254.06	8.36	26.3	0
10/4/00 0:00	13:18	95.2	2.34	244.25	9.85	26.3	0
10/4/00 0:00	13:19	115.9	2.87	297.20	12.07	26.3	0
10/4/00 0:00	13:20	75.1	3.06	192.57	12.89	26.3	0
10/4/00 0:00	13:21	60.2	4.61	154.55	19.43	26.3	0
10/4/00 0:00	13:22	85.7	3.25	219.91	13.70	26.3	0
10/4/00 0:00	13:23	99.0	2.98	254.07	12.54	26.3	0
10/4/00 0:00	13:24	83.1	5.56	213.06	23.42	26.3	0
10/4/00 0:00	13:25	50.3	6.33	128.91	26.65	26.3	0
10/4/00 0:00	13:26	50.1	5.88	128.50	24.76	26.3	0
10/4/00 0:00	13:27	68.6	5.00	175.91	21.05	26.3	0
10/4/00 0:00	13:28	132.4	3.59	339.52	15.12	26.3	0
10/4/00 0:00	13:29	221.8	3.45	568.94	14.52	26.3	0
10/4/00 0:00	13:30	181.7	3.88	465.96	16.34	26.3	0
10/4/00 0:00	13:31	129.4	3.51	331.84	14.80	26.3	0
10/4/00 0:00	13:32	154.3	3.02	395.89	12.73	26.3	0
10/4/00 0:00	13:33	198.6	2.85	509.55	12.02	26.3	0
10/4/00 0:00	13:34	297.3	2.46	762.48	10.38	26.3	0

Min001

10/4/00 0:00	13:35	291.4	1.97	747.52	8.31	26.3	0
10/4/00 0:00	13:36	245.3	1.49	629.16	6.29	26.3	0
10/4/00 0:00	13:37	179.3	1.22	459.94	5.15	26.3	0
10/4/00 0:00	13:38	189.0	1.02	484.80	4.28	26.3	0
10/4/00 0:00	13:39	163.2	1.07	418.59	4.50	26.3	0
10/4/00 0:00	13:40	168.0	1.18	430.90	4.96	26.3	0
10/4/00 0:00	13:41	185.8	1.40	476.69	5.90	26.3	0
10/4/00 0:00	13:42	146.6	5.19	375.99	21.87	26.3	0
10/4/00 0:00	13:43	57.1	8.74	146.47	36.81	26.3	0
10/4/00 0:00	13:44	36.8	8.86	94.47	37.33	26.3	0
10/4/00 0:00	13:45	32.4	30.29	83.10	127.58	26.3	0
10/4/00 0:00	13:46	31.4	15.75	80.57	66.33	26.3	0
10/4/00 0:00	13:47	30.2	7.91	77.58	33.32	26.3	0
10/4/00 0:00	13:48	29.3	7.63	75.07	32.14	26.3	0
10/4/00 0:00	13:49	29.2	7.92	75.02	33.37	26.3	0
10/4/00 0:00	13:50	28.3	8.30	72.51	34.95	26.3	0
10/4/00 0:00	13:51	28.3	7.65	72.52	32.23	26.3	0
10/4/00 0:00	13:52	28.3	7.47	72.53	31.49	26.3	0
10/4/00 0:00	13:53	28.3	7.72	72.51	32.53	26.3	0
10/4/00 0:00	13:54	28.3	7.91	72.52	33.34	26.3	0
10/4/00 0:00	13:55	28.3	8.23	72.51	34.67	26.3	0
10/4/00 0:00	13:56	27.6	8.15	70.77	34.32	26.3	0
10/4/00 0:00	13:57	27.3	7.52	69.97	31.68	26.3	0
10/4/00 0:00	13:58	27.3	7.11	69.94	29.97	26.3	0
10/4/00 0:00	13:59	27.3	7.29	69.97	30.71	26.3	0
10/4/00 0:00	14:00	27.3	7.97	69.94	33.56	26.3	0
10/4/00 0:00	14:01	45.1	20.78	115.66	87.53	26.3	0
10/4/00 0:00	14:02	73.8	7.54	189.39	31.77	26.3	0
10/4/00 0:00	14:03	77.8	2.31	199.49	9.73	26.3	0
10/4/00 0:00	14:04	98.1	2.30	251.58	9.68	26.3	0
10/4/00 0:00	14:05	122.8	1.80	315.09	7.59	26.3	0
10/4/00 0:00	14:06	143.7	1.30	368.55	5.49	26.3	0
10/4/00 0:00	14:07	143.7	1.23	368.64	5.18	26.3	0
10/4/00 0:00	14:08	192.8	1.37	494.59	5.78	26.3	0
10/4/00 0:00	14:09	123.2	1.85	315.92	7.78	26.3	0
10/4/00 0:00	14:10	111.0	2.33	284.67	9.81	26.3	0
10/4/00 0:00	14:11	130.5	2.03	334.81	8.54	26.3	0
10/4/00 0:00	14:12	110.6	3.82	283.65	16.11	26.3	0
10/4/00 0:00	14:13	48.1	8.52	123.44	35.91	26.3	0
10/4/00 0:00	14:14	33.3	13.91	85.34	58.60	26.3	0
10/4/00 0:00	14:15	30.4	17.10	77.97	72.04	26.3	0
10/4/00 0:00	14:16	30.3	14.39	77.64	60.64	26.3	0
10/4/00 0:00	14:17	31.3	11.71	80.28	49.34	26.3	0
10/4/00 0:00	14:18	35.1	9.76	90.02	41.13	26.3	0
10/4/00 0:00	14:19	57.2	11.12	146.85	46.82	26.3	0
10/4/00 0:00	14:20	48.4	9.17	124.17	38.64	26.3	0
10/4/00 0:00	14:21	33.6	8.22	86.26	34.63	26.3	0
10/4/00 0:00	14:22	30.3	7.77	77.82	32.74	26.3	0
10/4/00 0:00	14:23	29.3	7.53	75.07	31.73	26.3	0
10/4/00 0:00	14:24	28.4	7.30	72.81	30.76	26.3	0
10/4/00 0:00	14:25	28.3	6.64	72.52	27.96	26.3	0
10/4/00 0:00	14:26	28.8	5.70	73.92	24.00	26.3	0

Min001

10/4/00 0:00	14:27	41.2	8.70	105.60	36.67	26.3	0
10/4/00 0:00	14:28	75.0	8.66	192.33	36.50	26.3	0
10/4/00 0:00	14:29	77.5	6.55	198.84	27.58	26.3	0
10/4/00 0:00	14:30	72.1	6.93	185.07	29.19	26.3	0
10/4/00 0:00	14:31	54.4	11.87	139.59	49.98	26.3	0
10/4/00 0:00	14:32	55.3	6.63	141.93	27.93	26.3	0
10/4/00 0:00	14:33	80.0	4.00	205.19	16.83	26.3	0
10/4/00 0:00	14:34	80.2	4.36	205.80	18.38	26.3	0
10/4/00 0:00	14:35	128.9	4.56	330.59	19.22	26.3	0
10/4/00 0:00	14:36	187.9	4.55	482.06	19.15	26.3	0
10/4/00 0:00	14:37	213.2	4.85	546.97	20.41	26.3	0
10/4/00 0:00	14:38	172.2	4.33	441.66	18.24	26.3	0
10/4/00 0:00	14:39	149.0	3.08	382.25	12.97	26.3	0
10/4/00 0:00	14:40	143.2	2.93	367.37	12.34	26.3	0
10/4/00 0:00	14:41	171.8	2.86	440.78	12.06	26.3	0
10/4/00 0:00	14:42	168.7	2.05	432.74	8.62	26.3	0
10/4/00 0:00	14:43	194.0	1.31	497.65	5.53	26.3	0
10/4/00 0:00	14:44	95.6	2.46	245.12	10.37	26.3	0
10/4/00 0:00	14:45	42.8	6.42	109.83	27.05	26.3	0
10/4/00 0:00	14:46	109.9	4.43	281.93	18.67	26.3	0
10/4/00 0:00	14:47	126.8	2.18	325.24	9.20	26.3	0
10/4/00 0:00	14:48	109.0	1.83	279.70	7.70	26.3	0
10/4/00 0:00	14:49	102.9	1.73	263.89	7.27	26.3	0
10/4/00 0:00	14:50	119.0	1.68	305.35	7.07	26.3	0
10/4/00 0:00	14:51	132.3	1.77	339.33	7.44	26.3	0
10/4/00 0:00	14:52	120.5	4.10	309.01	17.28	26.3	0
10/4/00 0:00	14:53	53.3	11.46	136.70	48.29	26.3	0
10/4/00 0:00	14:54	47.6	4.41	122.08	18.58	26.3	0
10/4/00 0:00	14:55	54.2	3.88	138.99	16.34	26.3	0
10/4/00 0:00	14:56	93.6	3.71	240.14	15.63	26.3	0
10/4/00 0:00	14:57	133.1	3.70	341.31	15.57	26.3	0
10/4/00 0:00	14:58	226.3	3.49	580.38	14.69	26.3	0
10/4/00 0:00	14:59	267.1	2.88	685.07	12.12	26.3	0
10/4/00 0:00	15:00	254.1	2.89	651.91	12.19	26.3	0
10/4/00 0:00	15:01	269.6	2.65	691.65	11.15		
10/4/00 0:00	15:02	352.8	2.92	904.98	12.30		
10/4/00 0:00	15:03	280.8	3.11	720.35	13.10		
10/4/00 0:00	15:04	182.5	1.66	468.09	6.97		
10/4/00 0:00	15:05	161.5	1.25	414.26	5.25		
10/4/00 0:00	15:06	166.4	1.22	426.87	5.15		
10/4/00 0:00	15:07	186.8	1.08	479.20	4.54		
10/4/00 0:00	15:08	169.2	1.24	434.14	5.20		
10/4/00 0:00	15:09	143.6	3.33	368.34	14.01		
10/4/00 0:00	15:10	51.0	6.51	130.83	27.41		
10/4/00 0:00	15:11	31.0	6.13	79.56	25.84		
10/4/00 0:00	15:12	29.3	5.88	75.08	24.77		
10/4/00 0:00	15:13	40.8	13.80	104.75	58.12		
10/4/00 0:00	15:14	90.0	5.71	230.76	24.07		
10/4/00 0:00	15:15	88.9	1.06	228.03	4.47		
10/4/00 0:00	15:16	111.5	0.98	286.10	4.12		
10/4/00 0:00	15:17	122.1	1.12	313.25	4.71		
10/4/00 0:00	15:18	124.8	1.18	320.08	4.96		

Min001

10/4/00 0:00	15:19	120.9	1.07	310.25	4.52
10/4/00 0:00	15:20	114.3	1.02	293.15	4.31
10/4/00 0:00	15:21	107.7	1.44	276.29	6.06
10/4/00 0:00	15:22	110.0	1.77	282.04	7.44
10/4/00 0:00	15:23	89.6	1.56	229.95	6.59
10/4/00 0:00	15:24	94.6	1.48	242.76	6.23
10/4/00 0:00	15:25	113.6	1.45	291.47	6.10
10/4/00 0:00	15:26	99.5	6.95	255.18	29.30
10/4/00 0:00	15:27	47.3	16.09	121.30	67.78
10/4/00 0:00	15:28	43.6	21.99	111.89	92.64
10/4/00 0:00	15:29	87.6	9.40	224.60	39.60
10/4/00 0:00	15:30	55.2	3.89	141.48	16.39
10/4/00 0:00	15:31	39.8	11.57	101.98	48.73
10/4/00 0:00	15:32	30.7	16.94	78.83	71.38
10/4/00 0:00	15:33	29.3	17.28	75.24	72.78
10/4/00 0:00	15:34	29.3	16.30	75.07	68.66
10/4/00 0:00	15:35	29.3	15.85	75.06	66.75
10/4/00 0:00	15:36	29.3	15.50	75.08	65.30
10/4/00 0:00	15:37	29.3	12.50	75.07	52.66
10/4/00 0:00	15:38	29.3	10.34	75.07	43.58
10/4/00 0:00	15:39	29.3	8.79	75.08	37.03
10/4/00 0:00	15:40	29.3	7.93	75.08	33.42
10/4/00 0:00	15:41	29.3	7.39	75.07	31.12
10/4/00 0:00	15:42	29.3	6.91	75.08	29.12
10/4/00 0:00	15:43	29.3	6.68	75.07	28.14
10/4/00 0:00	15:44	29.3	6.96	75.08	29.34
10/4/00 0:00	15:45	30.8	7.08	78.95	29.81
		93.4	6.1		