

11.1

**AIR EMISSIONS TEST REPORT
TOTAL PARTICULATE MATTER EMISSIONS
HARSELL POSITIVE PRESSURE BAGHOUSE
KENTUCKY ELECTRIC STEEL, INC.
ASHLAND, KENTUCKY**

Prepared for

**Kentucky Electric Steel, Inc.
P.O. Box 3500
Ashland, Kentucky 41105**

July 2000

Submitted by


**Environmental Quality Management, Inc.
1310 Kemper Meadow Drive, Suite 100
Cincinnati, Ohio 45240
(513) 825-7500
Fax: (513) 825-7495**

PN: 050163.0009

ENVIRONMENTAL QUALITY MANAGEMENT, INC.
1310 Kemper Meadow Drive • Suite 100
Cincinnati, Ohio 45240
(513) 825-7500
FAX (513) 825-7495

July 6, 2000

Mr. Gerald Slucher
Commonwealth of Kentucky
Natural Resources and Environmental Protection Cabinet
Department of Environmental Protection
Division of Air Quality
803 Schenkel Lane
Frankfort, Kentucky 40601



Dear Mr. Slucher:

On behalf of our client, Kentucky Electric Steel, Inc. (KESI), we are pleased to submit the Air Emissions Test Report for Total Particulate Matter Emissions for KESI's Harsell Positive Pressure Baghouse. This test was required as a condition of KESI's Title V Operating Permit (Permit Number V-98-031).

Please contact Mr. Travis Bailey, KESI, at (606) 929-1330 with any questions or comments.

Sincerely,
ENVIRONMENTAL QUALITY MANAGEMENT, INC.

Thomas C. Gerstle /sub

Thomas C. Gerstle, P.E.
Project Manager

Cc: Mr. Travis Bailey, KESI
Ms. Sheri Bussard, EQ
Mr. Fred Hall, EQ
Ms. Tina Wise, EQ
050163.0009

Attachment



Meeting America's Needs for Experienced and Comprehensive Environmental Management

TABLE OF CONTENTS

SECTION 1	INTRODUCTION	1-1
SECTION 2	SUMMARY OF TEST RESULTS	2-1
SECTION 3	SAMPLING AND ANALYTICAL PROCEDURES ..	3-1
	Location of Measurement Sites	3-1
	Stack Gas Volumetric Flow Rate	3-1
	Stack Gas Dry Molecular Weight	3-1
	Stack Gas Moisture Content	3-1
	Particulate Matter	3-2
	Visible Emission Observations	3-2
SECTION 4	PROCESS DESCRIPTION/SAMPLING LOCATIONS	4-1
SECTION 5	QUALITY ASSURANCE AND QUALITY CONTROLS	5-1
SECTION 6	CALIBRATION PROCEDURES AND FREQUENCY	6-1
APPENDIX A	VISIBLE EMISSION FIELD DATA	
APPENDIX B	PRODUCTION/PROCESS FIELD DATA	
APPENDIX C	PRODUCTION HEAT SHEETS (PRIVILEGED AND CONFIDENTIAL)	
APPENDIX D	EMISSION TESTING FIELD DATA	
APPENDIX E	EXAMPLE CALCULATIONS	
APPENDIX F	CALIBRATION DATA	

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
3.1	Schematic of EPA Method 5 Sampling Train - Baghouse Outlet 3-3
4.1	Process Flow Diagram 4-2
5.1	Baghouse Inlet Sampling Location 5-2
5.2	Baghouse Outlet Sampling Location 5-3

LIST OF TABLES

<u>Table</u>	<u>Page</u>
2.1	Summary of Stack Gas Conditions Harsell Baghouse Inlet and Outlet 2-3
2.2	Summary of Stack Gas Conditions Harsell Baghouse Outlet 2-4
2.3	Summary of Total Particulate Matter Emissions Harsell Baghouse Outlet 2-5
2.4	Visible Emission Observation Summary, Melt Shop Roof Monitor . . . 2-6
2.5	Visible Emission Observation Summary, Baghouse Exhaust 2-36
4.2	Control System Fan Amperes During Performance 4-5
5.1	Field Equipment Calibration Summary 5-2
5.2	Field Checks of Sampling Equipment 5-2
6.1	Field Equipment Calibration Summary 6-2
6.2	Field Checks of Sampling Equipment 6-2

SECTION 1

INTRODUCTION

On May 11 and 12, 2000, Environmental Quality Management, Inc. (EQ) and Pacific Environmental Services, Inc. (PES) personnel conducted a compliance air emission program at the Kentucky Electric Steel, Inc. facility in Ashland, Kentucky. Sampling was conducted following the procedures of EPA Reference Methods. Total particulate matter emissions were measured from the Harsell positive pressure baghouse outlet sampling location.

EQ utilized EPA Reference Methods 1 and 2 to determine the inlet stack gas velocity and temperature. EPA Method 3 was used to determine the stack gas molecular weight. Moisture, particulate matter, and visible emissions were measured following the procedures of EPA Reference Methods 4, 5D, and 9, respectively at the baghouse outlet. In addition, visible emission observations were conducted via EPA Method 9 at the melt shop roof monitor.

Mr. Eddie Hall of Kentucky Electric Steel, Inc. and Messrs. Tom Gerstle and Fred Hall of EQ monitored process operations for the purposes of testing. Mr. John Jayne and Mr. Rick Seelhorst, of the Kentucky Division of Environmental Protection observed process operations and sampling efforts. Messrs. Ron Kolde, Dan Scheffel, and Gary Gay of PES and Ms. Tina Wise of EQ conducted sampling efforts.

SECTION 2

SUMMARY OF TEST RESULTS

Sampling of the Harsell baghouse was conducted on May 11 and 12, 2000. Three test runs, four to five hours in length, were conducted for velocity, moisture, O₂, and CO₂ and particulate matter. Visible emission observations were also conducted at the baghouse and melt shop exhausts. Sampling was conducted following EPA Reference Methods 1-4, 5D, and 9.

Table 2.1 summarizes the stack gas conditions measured for the three sample periods at the inlet. Stack gas velocities averaged 81.5 feet per second (fps) at 154°F and 2.1 percent moisture. Stack gas composition averaged zero percent CO₂ and 21 percent O₂. Volumetric flow rates averaged 622,736 actual cubic feet per minute (acfm) or 522,102 dry standard cubic feet per minute (dscfm). Measurements were consistent for the three test runs.

Table 2.2 summarizes the stack gas conditions measured for the three sample periods at the outlet. Stack gas velocities averaged 1.9 feet per second (fps) at 159°F and 2.1 percent moisture. Stack gas composition averaged zero percent CO, and 21 percent O₂. Volumetric flow rates averaged 603,900 actual cubic feet per minute (acfm) or 497,700 dry standard cubic feet per minute (dscfm). Measurements were consistent for the three test runs.

Table 2.3 summarizes the filterable particulate concentrations and mass emission rates and metal production and baghouse pressure drop. The filterable particulate concentration averaged 0.0019 grains per dry standard cubic foot (gr/dscf), with an average mass emission rate of 8.13 pounds per hour (lb/hr). The molton metal production averaged 45 tons/hr (total for both furnaces) and the baghouse pressure drop averaged 5.5 inches of water.

EPA Reference Method 9, "Visual Determination of the Opacity of Emissions from Stationary Sources" was used to determine opacity from the baghouse exhaust as well as from the shop roof monitor. Observations were conducted simultaneously at each source in conjunction with the particulate sampling runs. The observations were recorded separately for the baghouse exhaust and melt shop roof monitor. The raw emission observation data was entered into a computer spreadsheet to calculate the melting, charging and tapping

averages. These data are provided in Table 2.4. The baghouse observation data is provided in Table 2.5.

The melting periods are summarized into rolling 6 minute averages. The charges were averaged for the time period commencing at the moment the EAF starts to open and ending either three minutes after the EAF roof is returned to the closed position or six minutes after commencement of opening of the roof whichever is longer. The tapping periods were averaged for the time period commencing at the moment the EAF begins to tilt and ending either three minutes after steel ceases to flow or six minutes after steel begins to flow, whichever is longer.

TABLE 2.1
SUMMARY OF STACK GAS CONDITIONS
HARSELL BAGHOUSE INLET

Date: May 11 and 12, 2000

Plant: Kentucky Electric Steel, Ashland, Kentucky

Site/ Run No.	Time	Stack Gas Velocity, fps ^a	Volumetric Flow Rate		Temp, °F	Moisture, %	CO ₂ , %	O ₂ , %
			acfm ^b	dscfm ^c				
I-1	5/11 1355-1945	80.4	614,725	538,404	136	1.2	0.0	21.0
I-2	5/12 0630-1050	82.3	629,190	522,645	157	2.6	0.0	21.0
I-3	5/12 1050-1619	81.7	624,292	505,257	169	2.7	0.0	21.0
Average		81.5	622,736	522,102	154	2.1	0.0	21.0

^aFeet per second.

^bActual cubic feet per minute.

^cDry standard cubic feet per minute.

Note: Stack gas conditions presented are the average of pre and post-test velocity measurements conducted at the inlet sampling location.

TABLE 2.2
SUMMARY OF STACK GAS CONDITIONS
HARSELL BAGHOUSE OUTLET

Date: May 11 and 12, 2000

Plant: Kentucky Electric Steel, Ashland, Kentucky

Site/ Run No.	Time	Stack Gas Velocity, fps ^a	Volumetric Flow Rate		Temp, °F	Moisture, %	CO ₂ , %	O ₂ , %
			acfm ^b	dscfm ^c				
O-1	5/11 1355-1945	2.0	630,570	536,400	146	1.2	0.0	21.0
O-2	5/12 0630-1050	1.9	628,030	511,300	162	2.5	0.0	21.0
O-3	5/12 1050-1619	1.7	553,010	445,500	168	2.6	0.0	21.0
Average		1.9	603,900	497,700	159	2.1	0.0	21.0

^aFeet per second.

^bActual cubic feet per minute.

^cDry standard cubic feet per minute.

NOTE: Volumetric flow rates were taken at the inlet and applied to the outlet per Method 5D. Other parameters were measured at the outlet location.

TABLE 2.3
SUMMARY OF FILTERABLE PARTICULATE EMISSIONS
HARSELL BAGHOUSE OUTLET

Dates: May 11 and 12, 2000

Plant: Kentucky Electric Steel, Ashland, Kentucky

Run No.	Date/Time	Filterable Particulate Matter				Production, Tons/hr.	Baghouse Pressure Drop Inches Water (Range)
		Concentration		Mass Rate			
		gr/dscf ^a	lb/dscf ^b	lb/hr ^c	lb/ton ^d		
0-1	5/11 1355-1945	2.07E-03	2.96E-07	9.54	0.25	38.8	5.4 (5 -6.1)
0-2	5/12 0630-1050	2.16E-03	3.09E-07	9.48	0.20	48	5.5 (5 -5.8)
0-3	5/12 1050-1619	1.41E-03	2.01E-07	5.37	0.11	48	5.6 (5.2 -5.8)
Average		1.88E-03	2.69E-07	8.13	0.19	45	5.5 (5 - 6.1)
^a Grains per dry standard cubic foot ^b Pounds per dry standard cubic foot ^c Pound per hour ^d Pounds per ton of steel produced							

**TABLE 2.4. VISIBLE EMISSION OBSERVATION SUMMARY, MELT SHOP
ROOF MONITOR**

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
13:59:00	0		Charge	7:15:00	0		Melt	12:18:00	5		Melt
13:59:15	0		Charge	7:15:15	0		Melt	12:18:15	15		Melt
13:59:30	0		Charge	7:15:30	0		Melt	12:18:30	15		Melt
13:59:45	0		Charge	7:15:45	0		Melt	12:18:45	15		Melt
14:00:00	5		Charge	7:16:00	0		Melt	12:19:00	30		Melt
14:00:15	5		Charge	7:16:15	0		Melt	12:19:15	30		Melt
14:00:30	5		Charge	7:16:30	0		Melt	12:19:30	30		Melt
14:00:45	5		Charge	7:16:45	0		Melt	12:19:45	30		Melt
14:01:00	5		Charge	7:17:00	0		Melt	12:20:00	35		Melt
14:01:15	0		Charge	7:17:15	0		Melt	12:20:15	35		Melt
14:01:30	0		Charge	7:17:30	0		Melt	12:20:30	40		Melt
14:01:45	0		Charge	7:17:45	0		Melt	12:20:45	40		Melt
14:02:00	0		Charge	7:18:00	0		Melt	12:21:00	40		Melt
14:02:15	0		Charge	7:18:15	0		Melt	12:21:15	40		Melt
14:02:30	0		Charge	7:18:30	0		Melt	12:21:30	35		Melt
14:02:45	0		Charge	7:18:45	0		Melt	12:21:45	35		Melt
14:03:00	0		Charge	7:19:00	0		Melt	12:22:00	30		Melt
14:03:15	0		Charge	7:19:15	0		Melt	12:22:15	30		Melt
14:03:30	0		Charge	7:19:30	0		Melt	12:22:30	30		Melt
14:03:45	0		Charge	7:19:45	0		Melt	12:22:45	25		Melt
14:04:00	0		Charge	7:20:00	0		Melt	12:23:00	25		Melt
14:04:15	0		Charge	7:20:15	0		Melt	12:23:15	15		Melt
14:04:30	0		Charge	7:20:30	0		Melt	12:23:30	15		Melt
14:04:45	0		Charge	7:20:45	0	0.00	Melt	12:23:45	15	27.29	Melt
14:05:00	0		Charge	7:21:00	0	0.00	Melt	12:24:00	15	27.71	Melt
14:05:15	10		Charge	7:21:15	0	0.00	Melt	12:24:15	15	27.71	Melt
14:05:30	10		Charge	7:21:30	0	0.00	Melt	12:24:30	10	27.50	Melt
14:05:45	5		Charge	7:21:45	0	0.00	Melt	12:24:45	5	27.08	Melt
14:06:00	5		Charge	7:22:00	0	0.00	Melt	12:25:00	5	26.04	Melt
14:06:15	5		Charge	7:22:15	0	0.00	Melt	12:25:15	5	25.00	Melt
14:06:30	0		Charge	7:22:30	0	0.00	Melt	12:25:30	5	23.96	Melt
14:06:45	0		Charge	7:22:45	0	0.00	Melt	12:25:45	5	22.92	Melt
14:07:00	0		Charge	7:23:00	0	0.00	Melt	12:26:00	5	21.67	Melt
14:07:15	0		Charge	7:23:15	0	0.00	Melt	12:26:15	0	20.21	Melt
14:07:30	0		Charge	7:23:30	0	0.00	Melt	12:26:30	0	18.54	Melt
14:07:45	0		Charge	7:23:45	0	0.00	Melt	12:26:45	0	16.88	Melt
14:08:00	0		Charge	7:24:00	0	0.00	Melt	12:27:00	0	15.21	Melt

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
14:08:15	0		Charge	7:24:15	0	0.00	Melt	12:27:15	0	13.54	Melt
14:08:30	0		Charge	7:24:30	0	0.00	Melt	12:27:30	0	12.08	Melt
14:08:45	0		Charge	7:24:45	0	0.00	Melt	12:27:45	0	10.63	Melt
14:09:00	0		Charge	7:25:00	0	0.00	Melt	12:28:00	0	9.38	Melt
14:09:15	0		Charge	7:25:15	0	0.00	Melt	12:28:15	0	8.13	Melt
14:09:30	0		Charge	7:25:30	0	0.00	Melt	12:28:30	0	6.88	Melt
14:09:45	0		Charge	7:25:45	0	0.00	Melt	12:28:45	0	5.83	Melt
14:10:00	0		Charge	7:26:00	0	0.00	Melt	12:29:00	0	4.79	Melt
14:10:15	0		Charge	7:26:15	0	0.00	Melt	12:29:15	0	4.17	Melt
14:10:30	0		Charge	7:26:30	0	0.00	Melt	12:29:30	0	3.54	Melt
14:10:45	0		Charge	7:26:45	0	0.00	Melt	12:29:45	0	2.92	Melt
14:11:00	0		Charge	7:27:00	0	0.00	Melt	12:30:00	0	2.29	Melt
14:11:15	0		Charge	7:27:15	0	0.00	Melt	12:30:15	0	1.67	Melt
14:11:30	0		Charge	7:27:30	0	0.00	Melt	12:30:30	0	1.25	Melt
14:11:45	0		Charge	7:27:45	0	0.00	Melt	12:30:45	0	1.04	Melt
14:12:00	0		Charge	7:28:00	0	0.00	Melt	12:31:00	0		Charge
14:12:15	0		Charge	7:28:15	0	0.00	Melt	12:31:15	0		Charge
14:12:30	0		Charge	7:28:30	0	0.00	Melt	12:31:30	0		Charge
14:12:45	0		Charge	7:28:45	0	0.00	Melt	12:31:45	0		Charge
14:13:00	0		Charge	7:29:00	0	0.00	Melt	12:32:00	0		Charge
14:13:15	0		Charge	7:29:15	0	0.00	Melt	12:32:15	0		Charge
14:13:30	0		Charge	7:29:30	0	0.00	Melt	12:32:30	0		Charge
14:13:45	0		Charge	7:29:45	0	0.00	Melt	12:32:45	0		Charge
14:14:00	0		Charge	7:30:00	0		Tap	12:33:00	10		Charge
14:14:15	0		Charge	7:30:15	0		Tap	12:33:15	5		Charge
14:14:30	0		Charge	7:30:30	0		Tap	12:33:30	10		Charge
14:14:45	0		Charge	7:30:45	10		Tap	12:33:45	15		Charge
14:15:00	0		Charge	7:31:00	0		Tap	12:34:00	5		Charge
14:15:15	0		Charge	7:31:15	0		Tap	12:34:15	5		Charge
14:15:30	5		Charge	7:31:30	0		Tap	12:34:30	5		Charge
14:15:45	5		Charge	7:31:45	10		Tap	12:34:45	5		Charge
14:16:00	5		Charge	7:32:00	10		Tap	12:35:00	0		Charge
14:16:15	5		Charge	7:32:15	5		Tap	12:35:15	0		Charge
14:16:30	5		Charge	7:32:30	5		Tap	12:35:30	5		Charge
14:16:45	10		Charge	7:32:45	0		Tap	12:35:45	5		Charge
14:17:00	10		Charge	7:33:00	0		Tap	12:36:00	5		Charge
14:17:15	5		Charge	7:33:15	0		Tap	12:36:15	10		Charge
14:17:30	5		Charge	7:33:30	0		Tap	12:36:30	15		Charge
14:17:45	5		Charge	7:33:45	0		Tap	12:36:45	15		Charge
14:18:00	5		Charge	7:34:00	0		Tap	12:37:00	20		Charge
14:18:15	5		Charge	7:34:15	0		Tap	12:37:15	20		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
14:18:30	5		Charge	7:34:30	0		Tap	12:37:30	20		Charge
14:18:45	0		Charge	7:34:45	0		Tap	12:37:45	20	6.96	Charge
14:19:00	0		Charge	7:35:00	0		Tap	12:38:00	20		Melt
14:19:15	0		Charge	7:35:15	0		Tap	12:38:15	20		Melt
14:19:30	0		Charge	7:35:30	0		Tap	12:38:30	20		Melt
14:19:45	0		Charge	7:35:45	0		Tap	12:38:45	15		Melt
14:20:00	0		Charge	7:36:00	0		Tap	12:39:00	15		Melt
14:20:15	0		Charge	7:36:15	5		Tap	12:39:15	15		Melt
14:20:30	0		Charge	7:36:30	5		Tap	12:39:30	15		Melt
14:20:45	0		Charge	7:36:45	0	1.79	Tap	12:39:45	10		Melt
14:21:00	0		Charge	7:37:00	5		Charge	12:40:00	15		Melt
14:21:15	0		Charge	7:37:15	5		Charge	12:40:15	15		Melt
14:21:30	0		Charge	7:37:30	0		Charge	12:40:30	10		Melt
14:21:45	0		Charge	7:37:45	0		Charge	12:40:45	20		Melt
14:22:00	0		Charge	7:38:00	5		Charge	12:41:00	20		Melt
14:22:15	0		Charge	7:38:15	0		Charge	12:41:15	20		Melt
14:22:30	0		Charge	7:38:30	0		Charge	12:41:30	20		Melt
14:22:45	5		Charge	7:38:45	0		Charge	12:41:45	15		Melt
14:23:00	5		Charge	7:39:00	0		Charge	12:42:00	15		Melt
14:23:15	5		Charge	7:39:15	10		Charge	12:42:15	15		Melt
14:23:30	10		Charge	7:39:30	5		Charge	12:42:30	5		Melt
14:23:45	10		Charge	7:39:45	5		Charge	12:42:45	5		Melt
14:24:00	5		Charge	7:40:00	0		Charge	12:43:00	5		Melt
14:24:15	0		Charge	7:40:15	10		Charge	12:43:15	5		Melt
14:24:30	0		Charge	7:40:30	5		Charge	12:43:30	10		Melt
14:24:45	0		Charge	7:40:45	5		Charge	12:43:45	0	13.54	Melt
14:25:00	0		Charge	7:41:00	5		Charge	12:44:00	0	12.71	Melt
14:25:15	5		Charge	7:41:15	5		Charge	12:44:15	0	11.88	Melt
14:25:30	5		Charge	7:41:30	5		Charge	12:44:30	5	11.25	Melt
14:25:45	5		Charge	7:41:45	0		Charge	12:44:45	15	11.25	Melt
14:26:00	5		Charge	7:42:00	0		Charge	12:45:00	15	11.25	Melt
14:26:15	0		Charge	7:42:15	0		Charge	12:45:15	15	11.25	Melt
14:26:30	0		Charge	7:42:30	0		Charge	12:45:30	10	11.04	Melt
14:26:45	0		Charge	7:42:45	0		Charge	12:45:45	5	10.83	Melt
14:27:00	0		Charge	7:43:00	0		Charge	12:46:00	10		Tap
14:27:15	0		Charge	7:43:15	0		Charge	12:46:15	10		Tap
14:27:30	0		Charge	7:43:30	10		Charge	12:46:30	10		Tap
14:27:45	0		Charge	7:43:45	15		Charge	12:46:45	15		Tap
14:28:00	0		Charge	7:44:00	25		Charge	12:47:00	15		Tap
14:28:15	0		Charge	7:44:15	35		Charge	12:47:15	10		Tap
14:28:30	0		Charge	7:44:30	35		Charge	12:47:30	15		Tap

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
14:28:45	0		Charge	7:44:45	35		Charge	12:47:45	30		Tap
14:29:00	0		Charge	7:45:00	35		Charge	12:48:00	25		Tap
14:29:15	0		Charge	7:45:15	40		Charge	12:48:15	25		Tap
14:29:30	0		Charge	7:45:30	35		Charge	12:48:30	25		Tap
14:29:45	0		Charge	7:45:45	35		Charge	12:48:45	30		Tap
14:30:00	0		Charge	7:46:00	30		Charge	12:49:00	30		Tap
14:30:15	0		Charge	7:46:15	30		Charge	12:49:15	25		Tap
14:30:30	0		Charge	7:46:30	30		Charge	12:49:30	25		Tap
14:30:45	0		Charge	7:46:45	25		Charge	12:49:45	25		Tap
14:31:00	0		Charge	7:47:00	25		Charge	12:50:00	30		Tap
14:31:15	5		Charge	7:47:15	20		Charge	12:50:15	25		Tap
14:31:30	10		Charge	7:47:30	20		Charge	12:50:30	25		Tap
14:31:45	10		Charge	7:47:45	15		Charge	12:50:45	20		Tap
14:32:00	5		Charge	7:48:00	15		Charge	12:51:00	15		Tap
14:32:15	5		Charge	7:48:15	10		Charge	12:51:15	15		Tap
14:32:30	5		Charge	7:48:30	20		Charge	12:51:30	10		Tap
14:32:45	0		Charge	7:48:45	25		Charge	12:51:45	5		Tap
14:33:00	0		Charge	7:49:00	20		Charge	12:52:00	5		Tap
14:33:15	0		Charge	7:49:15	5		Charge	12:52:15	10		Tap
14:33:30	0		Charge	7:49:30	5		Charge	12:52:30	5		Tap
14:33:45	0		Charge	7:49:45	5		Charge	12:52:45	5		Tap
14:34:00	0		Charge	7:50:00	5		Charge	12:53:00	0		Tap
14:34:15	0		Charge	7:50:15	5		Charge	12:53:15	0		Tap
14:34:30	0		Charge	7:50:30	0		Charge	12:53:30	0		Tap
14:34:45	0		Charge	7:50:45	0		Charge	12:53:45	0	15.47	Tap
14:35:00	0		Charge	7:51:00	0		Charge	12:54:00	0		Charge
14:35:15	5		Charge	7:51:15	30		Charge	12:54:15	0		Charge
14:35:30	5		Charge	7:51:30	30		Charge	12:54:30	0		Charge
14:35:45	0		Charge	7:51:45	40		Charge	12:54:45	0		Charge
14:36:00	0		Charge	7:52:00	35		Charge	12:55:00	0		Charge
14:36:15	0		Charge	7:52:15	25		Charge	12:55:15	25		Charge
14:36:30	0		Charge	7:52:30	20		Charge	12:55:30	35		Charge
14:36:45	0		Charge	7:52:45	20		Charge	12:55:45	30		Charge
14:37:00	5		Charge	7:53:00	10		Charge	12:56:00	30		Charge
14:37:15	0		Charge	7:53:15	0		Charge	12:56:15	25		Charge
14:37:30	0		Charge	7:53:30	0		Charge	12:56:30	30		Charge
14:37:45	0	1.60	Charge	7:53:45	0		Charge	12:56:45	30		Charge
14:38:00	0		Tap	7:54:00	10		Charge	12:57:00	30		Charge
14:38:15	0		Tap	7:54:15	10		Charge	12:57:15	35		Charge
14:38:30	0		Tap	7:54:30	10		Charge	12:57:30	35		Charge
14:38:45	0		Tap	7:54:45	10		Charge	12:57:45	30		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
14:39:00	0		Tap	7:55:00	10		Charge	12:58:00	25		Charge
14:39:15	0		Tap	7:55:15	0		Charge	12:58:15	25		Charge
14:39:30	0		Tap	7:55:30	0		Charge	12:58:30	20		Charge
14:39:45	0		Tap	7:55:45	0		Charge	12:58:45	20		Charge
14:40:00	0		Tap	7:56:00	0		Charge	12:59:00	10		Charge
14:40:15	0		Tap	7:56:15	0		Charge	12:59:15	10		Charge
14:40:30	0		Tap	7:56:30	0		Charge	12:59:30	5		Charge
14:40:45	5		Tap	7:56:45	15		Charge	12:59:45	5		Charge
14:41:00	5		Tap	7:57:00	15		Charge	13:00:00	0		Charge
14:41:15	5		Tap	7:57:15	10		Charge	13:00:15	0		Charge
14:41:30	10		Tap	7:57:30	0		Charge	13:00:30	0		Charge
14:41:45	10		Tap	7:57:45	0		Charge	13:00:45	0		Charge
14:42:00	5		Tap	7:58:00	0		Charge	13:01:00	0		Charge
14:42:15	5		Tap	7:58:15	15		Charge	13:01:15	0		Charge
14:42:30	5		Tap	7:58:30	10		Charge	13:01:30	0		Charge
14:42:45	0		Tap	7:58:45	10		Charge	13:01:45	0		Charge
14:43:00	0		Tap	7:59:00	10		Charge	13:02:00	0		Charge
14:43:15	10		Tap	7:59:15	5		Charge	13:02:15	0		Charge
14:43:30	10		Tap	7:59:30	0		Charge	13:02:30	0		Charge
14:43:45	15		Tap	7:59:45	0	11.20	Charge	13:02:45	0		Charge
14:44:00	15		Tap	8:00:00	0		Melt	13:03:00	0		Charge
14:44:15	15		Tap	8:00:15	0		Melt	13:03:15	0		Charge
14:44:30	15		Tap	8:00:30	0		Melt	13:03:30	0		Charge
14:44:45	10	5.00	Tap	8:00:45	0		Melt	13:03:45	0	11.38	Charge
14:45:00	10		Charge	8:01:00	0		Melt	13:04:00	0		Melt
14:45:15	15		Charge	8:01:15	0		Melt	13:04:15	0		Melt
14:45:30	15		Charge	8:01:30	0		Melt	13:04:30	0		Melt
14:45:45	15		Charge	8:01:45	0		Melt	13:04:45	0		Melt
14:46:00	15		Charge	8:02:00	0		Melt	13:05:00	0		Melt
14:46:15	20		Charge	8:02:15	0		Melt	13:05:15	0		Melt
14:46:30	20		Charge	8:02:30	0		Melt	13:05:30	0		Melt
14:46:45	20		Charge	8:02:45	0		Melt	13:05:45	0		Melt
14:47:00	20		Charge	8:03:00	0		Melt	13:06:00	0		Melt
14:47:15	15		Charge	8:03:15	0		Melt	13:06:15	0		Melt
14:47:30	15		Charge	8:03:30	0		Melt	13:06:30	0		Melt
14:47:45	15		Charge	8:03:45	0		Melt	13:06:45	0		Melt
14:48:00	10		Charge	8:04:00	0		Melt	13:07:00	0		Melt
14:48:15	10		Charge	8:04:15	0		Melt	13:07:15	0		Melt
14:48:30	5		Charge	8:04:30	0		Melt	13:07:30	0		Melt
14:48:45	5		Charge	8:04:45	0		Melt	13:07:45	0		Melt
14:49:00	5		Charge	8:05:00	0		Melt	13:08:00	0		Melt

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
14:49:15	5		Charge	8:05:15	0		Melt	13:08:15	0		Melt
14:49:30	10		Charge	8:05:30	0		Melt	13:08:30	0		Melt
14:49:45	15		Charge	8:05:45	0	0.00	Melt	13:08:45	0		Melt
14:50:00	10		Charge	8:06:00	0	0.00	Melt	13:09:00	0		Melt
14:50:15	10		Charge	8:06:15	0	0.00	Melt	13:09:15	0		Melt
14:50:30	10		Charge	8:06:30	0	0.00	Melt	13:09:30	0		Melt
14:50:45	15		Charge	8:06:45	0	0.00	Melt	13:09:45	0	0.00	Melt
14:51:00	15		Charge	8:07:00	0	0.00	Melt	13:10:00	0	0.00	Melt
14:51:15	10		Charge	8:07:15	0	0.00	Melt	13:10:15	0	0.00	Melt
14:51:30	5		Charge	8:07:30	0	0.00	Melt	13:10:30	0	0.00	Melt
14:51:45	5		Charge	8:07:45	0	0.00	Melt	13:10:45	0	0.00	Melt
14:52:00	5		Charge	8:08:00	0	0.00	Melt	13:11:00	0	0.00	Melt
14:52:15	10		Charge	8:08:15	0	0.00	Melt	13:11:15	0	0.00	Melt
14:52:30	15		Charge	8:08:30	0	0.00	Melt	13:11:30	0	0.00	Melt
14:52:45	20		Charge	8:08:45	0	0.00	Melt	13:11:45	0	0.00	Melt
14:53:00	15		Charge	8:09:00	0	0.00	Melt	13:12:00	0	0.00	Melt
14:53:15	10		Charge	8:09:15	0	0.00	Melt	13:12:15	0	0.00	Melt
14:53:30	10		Charge	8:09:30	0	0.00	Melt	13:12:30	0	0.00	Melt
14:53:45	5		Charge	8:09:45	0	0.00	Melt	13:12:45	0	0.00	Melt
14:54:00	5		Charge	8:10:00	0	0.00	Melt	13:13:00	0	0.00	Melt
14:54:15	5		Charge	8:10:15	0	0.00	Melt	13:13:15	0	0.00	Melt
14:54:30	5		Charge	8:10:30	0	0.00	Melt	13:13:30	0	0.00	Melt
14:54:45	5		Charge	8:10:45	0	0.00	Melt	13:13:45	0	0.00	Melt
14:55:00	5		Charge	8:11:00	0	0.00	Melt	13:14:00	0	0.00	Melt
14:55:15	0		Charge	8:11:15	0	0.00	Melt	13:14:15	0	0.00	Melt
14:55:30	0		Charge	8:11:30	0	0.00	Melt	13:14:30	0	0.00	Melt
14:55:45	0	10.34	Charge	8:11:45	0	0.00	Melt	13:14:45	0	0.00	Melt
14:56:00	0		Melt	8:12:00	0	0.00	Melt	13:15:00	0	0.00	Melt
14:56:15	0		Melt	8:12:15	0	0.00	Melt	13:15:15	0	0.00	Melt
14:56:30	0		Melt	8:12:30	0	0.00	Melt	13:15:30	0	0.00	Melt
14:56:45	0		Melt	8:12:45	0	0.00	Melt	13:15:45	0	0.00	Melt
14:57:00	0		Melt	8:13:00	0	0.00	Melt	13:16:00	0	0.00	Melt
14:57:15	0		Melt	8:13:15	0	0.00	Melt	13:16:15	0	0.00	Melt
14:57:30	0		Melt	8:13:30	0	0.00	Melt	13:16:30	0	0.00	Melt
14:57:45	0		Melt	8:13:45	0	0.00	Melt	13:16:45	0	0.00	Melt
14:58:00	0		Melt	8:14:00	0	0.00	Melt	13:17:00	0	0.00	Melt
14:58:15	0		Melt	8:14:15	0	0.00	Melt	13:17:15	0	0.00	Melt
14:58:30	0		Melt	8:14:30	0	0.00	Melt	13:17:30	0	0.00	Melt
14:58:45	0		Melt	8:14:45	0	0.00	Melt	13:17:45	0	0.00	Melt
14:59:00	0		Melt	8:15:00	0	0.00	Melt	13:18:00	0	0.00	Melt
14:59:15	0		Melt	8:15:15	0	0.00	Melt	13:18:15	0	0.00	Melt

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
14:59:30	0		Melt	8:15:30	0	0.00	Melt	13:18:30	0	0.00	Melt
14:59:45	10		Melt	8:15:45	0	0.00	Melt	13:18:45	0	0.00	Melt
15:00:00	10		Melt	8:16:00	0	0.00	Melt	13:19:00	0	0.00	Melt
15:00:15	5		Melt	8:16:15	0	0.00	Melt	13:19:15	0	0.00	Melt
15:00:30	5		Melt	8:16:30	0	0.00	Melt	13:19:30	0	0.00	Melt
15:00:45	5		Melt	8:16:45	0	0.00	Melt	13:19:45	0	0.00	Melt
15:01:00	5		Melt	8:17:00	0	0.00	Melt	13:20:00	0	0.00	Melt
15:01:15	0		Melt	8:17:15	0	0.00	Melt	13:20:15	0	0.00	Melt
15:01:30	0		Melt	8:17:30	0	0.00	Melt	13:20:30	0	0.00	Melt
15:01:45	0	1.67	Melt	8:17:45	0	0.00	Melt	13:20:45	0	0.00	Melt
15:02:00	0	1.67	Melt	8:18:00	0	0.00	Melt	13:21:00	0	0.00	Melt
15:02:15	0	1.67	Melt	8:18:15	0	0.00	Melt	13:21:15	0	0.00	Melt
15:02:30	0	1.67	Melt	8:18:30	0	0.00	Melt	13:21:30	0	0.00	Melt
15:02:45	0	1.67	Melt	8:18:45	0	0.00	Melt	13:21:45	0	0.00	Melt
15:03:00	0	1.67	Melt	8:19:00	0	0.00	Melt	13:22:00	0	0.00	Melt
15:03:15	0	1.67	Melt	8:19:15	0	0.00	Melt	13:22:15	0	0.00	Melt
15:03:30	0	1.67	Melt	8:19:30	0	0.00	Melt	13:22:30	0	0.00	Melt
15:03:45	0	1.67	Melt	8:19:45	0	0.00	Melt	13:22:45	0	0.00	Melt
15:04:00	0	1.67	Melt	8:20:00	0	0.00	Melt	13:23:00	0	0.00	Melt
15:04:15	0	1.67	Melt	8:20:15	0	0.00	Melt	13:23:15	0	0.00	Melt
15:04:30	0	1.67	Melt	8:20:30	0	0.00	Melt	13:23:30	0	0.00	Melt
15:04:45	0	1.67	Melt	8:20:45	0	0.00	Melt	13:23:45	0	0.00	Melt
15:05:00	0	1.67	Melt	8:21:00	0	0.00	Melt	13:24:00	0	0.00	Melt
15:05:15	0	1.67	Melt	8:21:15	0	0.00	Melt	13:24:15	0	0.00	Melt
15:05:30	0	1.67	Melt	8:21:30	0	0.00	Melt	13:24:30	0	0.00	Melt
15:05:45	0	1.25	Melt	8:21:45	0	0.00	Melt	13:24:45	0	0.00	Melt
15:06:00	0	0.83	Melt	8:22:00	0	0.00	Melt	13:25:00	0		Tap
15:06:15	0	0.63	Melt	8:22:15	0	0.00	Melt	13:25:15	0		Tap
15:06:30	0	0.42	Melt	8:22:30	0	0.00	Melt	13:25:30	0		Tap
15:06:45	0	0.21	Melt	8:22:45	0	0.00	Melt	13:25:45	0		Tap
15:07:00	0	0.00	Melt	8:23:00	0	0.00	Melt	13:26:00	15		Tap
15:07:15	0	0.00	Melt	8:23:15	0	0.00	Melt	13:26:15	15		Tap
15:07:30	0	0.00	Melt	8:23:30	0	0.00	Melt	13:26:30	10		Tap
15:07:45	0	0.00	Melt	8:23:45	0	0.00	Melt	13:26:45	5		Tap
15:08:00	0	0.00	Melt	8:24:00	0	0.00	Melt	13:27:00	10		Tap
15:08:15	5	0.21	Melt	8:24:15	0	0.00	Melt	13:27:15	5		Tap
15:08:30	5	0.42	Melt	8:24:30	0	0.00	Melt	13:27:30	0		Tap
15:08:45	5	0.63	Melt	8:24:45	0	0.00	Melt	13:27:45	10		Tap
15:09:00	5	0.83	Melt	8:25:00	0	0.00	Melt	13:28:00	5		Tap
15:09:15	0	0.83	Melt	8:25:15	0	0.00	Melt	13:28:15	5		Tap
15:09:30	0	0.83	Melt	8:25:30	0	0.00	Melt	13:28:30	0		Tap

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
15:09:45	0	0.83	Melt	8:25:45	0	0.00	Melt	13:28:45	0		Tap
15:10:00	0		Tap	8:26:00	0	0.00	Melt	13:29:00	0		Tap
15:10:15	0		Tap	8:26:15	0	0.00	Melt	13:29:15	0		Tap
15:10:30	0		Tap	8:26:30	0	0.00	Melt	13:29:30	0		Tap
15:10:45	5		Tap	8:26:45	0	0.00	Melt	13:29:45	0		Tap
15:11:00	5		Tap	8:27:00	0	0.00	Melt	13:30:00	0		Tap
15:11:15	10		Tap	8:27:15	0	0.00	Melt	13:30:15	0		Tap
15:11:30	20		Tap	8:27:30	0	0.00	Melt	13:30:30	0		Tap
15:11:45	15		Tap	8:27:45	0	0.00	Melt	13:30:45	0		Tap
15:12:00	15		Tap	8:28:00	0	0.00	Melt	13:31:00	0		Tap
15:12:15	15		Tap	8:28:15	0	0.00	Melt	13:31:15	0		Tap
15:12:30	10		Tap	8:28:30	0	0.00	Melt	13:31:30	0		Tap
15:12:45	10		Tap	8:28:45	0	0.00	Melt	13:31:45	0		Tap
15:13:00	15		Tap	8:29:00	0	0.00	Melt	13:32:00	0		Tap
15:13:15	15		Tap	8:29:15	0	0.00	Melt	13:32:15	0		Tap
15:13:30	15		Tap	8:29:30	0	0.00	Melt	13:32:30	0		Tap
15:13:45	15		Tap	8:29:45	0	0.00	Melt	13:32:45	0	2.50	Tap
15:14:00	10		Tap	8:30:00	0		Charge	13:33:00	0		Charge
15:14:15	5		Tap	8:30:15	0		Charge	13:33:15	0		Charge
15:14:30	5		Tap	8:30:30	25		Charge	13:33:30	0		Charge
15:14:45	5		Tap	8:30:45	30		Charge	13:33:45	0		Charge
15:15:00	5		Tap	8:31:00	25		Charge	13:34:00	0		Charge
15:15:15	0		Tap	8:31:15	25		Charge	13:34:15	0		Charge
15:15:30	0		Tap	8:31:30	10		Charge	13:34:30	0		Charge
15:15:45	0		Tap	8:31:45	40		Charge	13:34:45	0		Charge
15:16:00	0		Tap	8:32:00	30		Charge	13:35:00	0		Charge
15:16:15	0		Tap	8:32:15	25		Charge	13:35:15	0		Charge
15:16:30	10		Tap	8:32:30	20		Charge	13:35:30	0		Charge
15:16:45	10	7.68	Tap	8:32:45	15		Charge	13:35:45	0		Charge
15:17:00	5		Charge	8:33:00	5		Charge	13:36:00	0		Charge
15:17:15	5		Charge	8:33:15	0		Charge	13:36:15	0		Charge
15:17:30	5		Charge	8:33:30	0		Charge	13:36:30	0		Charge
15:17:45	0		Charge	8:33:45	0		Charge	13:36:45	0		Charge
15:18:00	0		Charge	8:34:00	0		Charge	13:37:00	0		Charge
15:18:15	0		Charge	8:34:15	0		Charge	13:37:15	0		Charge
15:18:30	0		Charge	8:34:30	0		Charge	13:37:30	0		Charge
15:18:45	0		Charge	8:34:45	0		Charge	13:37:45	0		Charge
15:19:00	0		Charge	8:35:00	0		Charge	13:38:00	0		Charge
15:19:15	0		Charge	8:35:15	0		Charge	13:38:15	0		Charge
15:19:30	0		Charge	8:35:30	0		Charge	13:38:30	0		Charge
15:19:45	0		Charge	8:35:45	0	10.42	Charge	13:38:45	0		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
15:20:00	0		Charge	8:36:00	0		Melt	13:39:00	0		Charge
15:20:15	0		Charge	8:36:15	0		Melt	13:39:15	0		Charge
15:20:30	0		Charge	8:36:30	0		Melt	13:39:30	0		Charge
15:20:45	0		Charge	8:36:45	0		Melt	13:39:45	0		Charge
15:21:00	0		Charge	8:37:00	0		Melt	13:40:00	20		Charge
15:21:15	0		Charge	8:37:15	0		Melt	13:40:15	35		Charge
15:21:30	0		Charge	8:37:30	0		Melt	13:40:30	35		Charge
15:21:45	0		Charge	8:37:45	0		Melt	13:40:45	30		Charge
15:22:00	0		Charge	8:38:00	0		Melt	13:41:00	30		Charge
15:22:15	0		Charge	8:38:15	0		Melt	13:41:15	25		Charge
15:22:30	0		Charge	8:38:30	0		Melt	13:41:30	30		Charge
15:22:45	0		Charge	8:38:45	0		Melt	13:41:45	20		Charge
15:23:00	0		Charge	8:39:00	0		Melt	13:42:00	25		Charge
15:23:15	0		Charge	8:39:15	0		Melt	13:42:15	25		Charge
15:23:30	0		Charge	8:39:30	0		Melt	13:42:30	30		Charge
15:23:45	0		Charge	8:39:45	0		Melt	13:42:45	20		Charge
15:24:00	0		Charge	8:40:00	0		Melt	13:43:00	20		Charge
15:24:15	10		Charge	8:40:15	0		Melt	13:43:15	20		Charge
15:24:30	10		Charge	8:40:30	0		Melt	13:43:30	15		Charge
15:24:45	5		Charge	8:40:45	0		Melt	13:43:45	20		Charge
15:25:00	5		Charge	8:41:00	0		Melt	13:44:00	20		Charge
15:25:15	5		Charge	8:41:15	0		Melt	13:44:15	20		Charge
15:25:30	5		Charge	8:41:30	0		Melt	13:44:30	15		Charge
15:25:45	10		Charge	8:41:45	0	0.00	Melt	13:44:45	15		Charge
15:26:00	10		Charge	8:42:00	0	0.00	Melt	13:45:00	20		Charge
15:26:15	10		Charge	8:42:15	0	0.00	Melt	13:45:15	15		Charge
15:26:30	5		Charge	8:42:30	0	0.00	Melt	13:45:30	15		Charge
15:26:45	5		Charge	8:42:45	0	0.00	Melt	13:45:45	10		Charge
15:27:00	5		Charge	8:43:00	0	0.00	Melt	13:46:00	10		Charge
15:27:15	0		Charge	8:43:15	0	0.00	Melt	13:46:15	10		Charge
15:27:30	0		Charge	8:43:30	0	0.00	Melt	13:46:30	10		Charge
15:27:45	0		Charge	8:43:45	0	0.00	Melt	13:46:45	15		Charge
15:28:00	0		Charge	8:44:00	0	0.00	Melt	13:47:00	15		Charge
15:28:15	0		Charge	8:44:15	0	0.00	Melt	13:47:15	15		Charge
15:28:30	0		Charge	8:44:30	0	0.00	Melt	13:47:30	15		Charge
15:28:45	0		Charge	8:44:45	0	0.00	Melt	13:47:45	5		Charge
15:29:00	0		Charge	8:45:00	15		Tap	13:48:00	10		Charge
15:29:15	0		Charge	8:45:15	15		Tap	13:48:15	5		Charge
15:29:30	0		Charge	8:45:30	15		Tap	13:48:30	5		Charge
15:29:45	0		Charge	8:45:45	20		Tap	13:48:45	10		Charge
15:30:00	0		Charge	8:46:00	15		Tap	13:49:00	10		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
15:30:15	0		Charge	8:46:15	15		Tap	13:49:15	5		Charge
15:30:30	0		Charge	8:46:30	20		Tap	13:49:30	0		Charge
15:30:45	0		Charge	8:46:45	20		Tap	13:49:45	0		Charge
15:31:00	0		Charge	8:47:00	20		Tap	13:50:00	0		Charge
15:31:15	0		Charge	8:47:15	20		Tap	13:50:15	0		Charge
15:31:30	5		Charge	8:47:30	25		Tap	13:50:30	0		Charge
15:31:45	10		Charge	8:47:45	30		Tap	13:50:45	10		Charge
15:32:00	10		Charge	8:48:00	25		Tap	13:51:00	10		Charge
15:32:15	5		Charge	8:48:15	25		Tap	13:51:15	10		Charge
15:32:30	5		Charge	8:48:30	30		Tap	13:51:30	15		Charge
15:32:45	5		Charge	8:48:45	25		Tap	13:51:45	15		Charge
15:33:00	0		Charge	8:49:00	25		Tap	13:52:00	20		Charge
15:33:15	0		Charge	8:49:15	25		Tap	13:52:15	20		Charge
15:33:30	0		Charge	8:49:30	25		Tap	13:52:30	15		Charge
15:33:45	0		Charge	8:49:45	20		Tap	13:52:45	15		Charge
15:34:00	0		Charge	8:50:00	15		Tap	13:53:00	10		Charge
15:34:15	0		Charge	8:50:15	10		Tap	13:53:15	10		Charge
15:34:30	0		Charge	8:50:30	10		Tap	13:53:30	5		Charge
15:34:45	0		Charge	8:50:45	5	19.58	Tap	13:53:45	5		Charge
15:35:00	0		Charge	8:51:00	0		Charge	13:54:00	5		Charge
15:35:15	0		Charge	8:51:15	0		Charge	13:54:15	0		Charge
15:35:30	0		Charge	8:51:30	0		Charge	13:54:30	0		Charge
15:35:45	0		Charge	8:51:45	0		Charge	13:54:45	0		Charge
15:36:00	0		Charge	8:52:00	0		Charge	13:55:00	0		Charge
15:36:15	0		Charge	8:52:15	10		Charge	13:55:15	0		Charge
15:36:30	0		Charge	8:52:30	10		Charge	13:55:30	0		Charge
15:36:45	0		Charge	8:52:45	5		Charge	13:55:45	0		Charge
15:37:00	0		Charge	8:53:00	0		Charge	13:56:00	0		Charge
15:37:15	0		Charge	8:53:15	0		Charge	13:56:15	0		Charge
15:37:30	0		Charge	8:53:30	0		Charge	13:56:30	0		Charge
15:37:45	0		Charge	8:53:45	0		Charge	13:56:45	0		Charge
15:38:00	0		Charge	8:54:00	0		Charge	13:57:00	0		Charge
15:38:15	0		Charge	8:54:15	0		Charge	13:57:15	0		Charge
15:38:30	0		Charge	8:54:30	0		Charge	13:57:30	0		Charge
15:38:45	0		Charge	8:54:45	0		Charge	13:57:45	0		Charge
15:39:00	0		Charge	8:55:00	0		Charge	13:58:00	0		Charge
15:39:15	5		Charge	8:55:15	0		Charge	13:58:15	0		Charge
15:39:30	5		Charge	8:55:30	0		Charge	13:58:30	0		Charge
15:39:45	5		Charge	8:55:45	0		Charge	13:58:45	0		Charge
15:40:00	5		Charge	8:56:00	0		Charge	13:59:00	0		Charge
15:40:15	0		Charge	8:56:15	0		Charge	13:59:15	0		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
15:40:30	0		Charge	8:56:30	0		Charge	13:59:30	0		Charge
15:40:45	0		Charge	8:56:45	0		Charge	13:59:45	0		Charge
15:41:00	0		Charge	8:57:00	0		Charge	14:00:00	0		Charge
15:41:15	0		Charge	8:57:15	0		Charge	14:00:15	0		Charge
15:41:30	0		Charge	8:57:30	0		Charge	14:00:30	0		Charge
15:41:45	0		Charge	8:57:45	0		Charge	14:00:45	0		Charge
15:42:00	0		Charge	8:58:00	0		Charge	14:01:00	0		Charge
15:42:15	0		Charge	8:58:15	0		Charge	14:01:15	0		Charge
15:42:30	0		Charge	8:58:30	0		Charge	14:01:30	0		Charge
15:42:45	0	1.54	Charge	8:58:45	0		Charge	14:01:45	0		Charge
15:43:00	0		Melt	8:59:00	10		Charge	14:02:00	0		Charge
15:43:15	0		Melt	8:59:15	15		Charge	14:02:15	0		Charge
15:43:30	0		Melt	8:59:30	15		Charge	14:02:30	0		Charge
15:43:45	0		Melt	8:59:45	0		Charge	14:02:45	0		Charge
15:44:00	0		Melt	9:00:00	0		Charge	14:03:00	10		Charge
15:44:15	0		Melt	9:00:15	0		Charge	14:03:15	15		Charge
15:44:30	0		Melt	9:00:30	0		Charge	14:03:30	20		Charge
15:44:45	0		Melt	9:00:45	0		Charge	14:03:45	20		Charge
15:45:00	0		Melt	9:01:00	0		Charge	14:04:00	20		Charge
15:45:15	0		Melt	9:01:15	0		Charge	14:04:15	20		Charge
15:45:30	0		Melt	9:01:30	0		Charge	14:04:30	15		Charge
15:45:45	0		Melt	9:01:45	0		Charge	14:04:45	15		Charge
15:46:00	0		Melt	9:02:00	0		Charge	14:05:00	15		Charge
15:46:15	0		Melt	9:02:15	0		Charge	14:05:15	15		Charge
15:46:30	0		Melt	9:02:30	0		Charge	14:05:30	20		Charge
15:46:45	0		Melt	9:02:45	0		Charge	14:05:45	25		Charge
15:47:00	0		Melt	9:03:00	0		Charge	14:06:00	30		Charge
15:47:15	0		Melt	9:03:15	0		Charge	14:06:15	30		Charge
15:47:30	0		Melt	9:03:30	0		Charge	14:06:30	35		Charge
15:47:45	0		Melt	9:03:45	0	1.25	Charge	14:06:45	40		Charge
15:48:00	LMF Cond		Melt	9:04:00	0		Melt	14:07:00	40		Charge
15:48:15	LMF Cond		Melt	9:04:15	0		Melt	14:07:15	40		Charge
15:48:30	LMF Cond		Melt	9:04:30	0		Melt	14:07:30	50		Charge
15:48:45	LMF Cond		Melt	9:04:45	0		Melt	14:07:45	40		Charge
15:49:00	LMF Cond		Melt	9:05:00	0		Melt	14:08:00	40		Charge
15:49:15	LMF Cond		Melt	9:05:15	0		Melt	14:08:15	30		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
15:49:30	LMF Cond		Melt	9:05:30	0		Melt	14:08:30	40		Charge
15:49:45	LMF Cond		Melt	9:05:45	0		Melt	14:08:45	30		Charge
15:50:00	LMF Cond		Melt	9:06:00	10		Melt	14:09:00	30		Charge
15:50:15	0		Melt	9:06:15	0		Melt	14:09:15	30		Charge
15:50:30	0		Melt	9:06:30	0		Melt	14:09:30	30		Charge
15:50:45	0		Melt	9:06:45	0		Melt	14:09:45	30		Charge
15:51:00	0		Melt	9:07:00	0		Melt	14:10:00	25		Charge
15:51:15	0		Melt	9:07:15	0		Melt	14:10:15	25		Charge
15:51:30	5		Melt	9:07:30	0		Melt	14:10:30	25		Charge
15:51:45	5		Melt	9:07:45	10		Melt	14:10:45	25		Charge
15:52:00	5		Melt	9:08:00	0		Melt	14:11:00	15		Charge
15:52:15	5		Melt	9:08:15	0		Melt	14:11:15	10		Charge
15:52:30	5		Melt	9:08:30	0		Melt	14:11:30	10		Charge
15:52:45	0		Melt	9:08:45	0		Melt	14:11:45	10		Charge
15:53:00	0		Melt	9:09:00	0		Melt	14:12:00	5		Charge
15:53:15	0		Melt	9:09:15	0		Melt	14:12:15	5		Charge
15:53:30	0		Melt	9:09:30	0		Melt	14:12:30	0		Charge
15:53:45	10		Melt	9:09:45	0	0.83	Melt	14:12:45	15		Charge
15:54:00	15		Melt	9:10:00	0	0.83	Melt	14:13:00	15		Charge
15:54:15	10		Melt	9:10:15	0	0.83	Melt	14:13:15	20		Charge
15:54:30	25		Melt	9:10:30	0	0.83	Melt	14:13:30	20		Charge
15:54:45	70		Melt	9:10:45	0	0.83	Melt	14:13:45	20		Charge
15:55:00	75		Melt	9:11:00	0	0.83	Melt	14:14:00	20		Charge
15:55:15	80		Melt	9:11:15	0	0.83	Melt	14:14:15	25		Charge
15:55:30	70		Melt	9:11:30	0	0.83	Melt	14:14:30	25		Charge
15:55:45	65	19.35	Melt	9:11:45	0	0.83	Melt	14:14:45	20		Charge
15:56:00	75	21.67	Melt	9:12:00	0	0.42	Melt	14:15:00	15		Charge
15:56:15	90	25.42	Melt	9:12:15	0	0.42	Melt	14:15:15	15		Charge
15:56:30	85	28.96	Melt	9:12:30	0	0.42	Melt	14:15:30	15		Charge
15:56:45	80	32.29	Melt	9:12:45	0	0.42	Melt	14:15:45	10		Charge
15:57:00	70	35.21	Melt	9:13:00	0	0.42	Melt	14:16:00	10		Charge
15:57:15	50	37.29	Melt	9:13:15	0	0.42	Melt	14:16:15	20		Charge
15:57:30	50	39.17	Melt	9:13:30	0	0.42	Melt	14:16:30	20		Charge
15:57:45	50	41.04	Melt	9:13:45	0	0.00	Melt	14:16:45	10		Charge
15:58:00	60	43.33	Melt	9:14:00	0	0.00	Melt	14:17:00	20		Charge
15:58:15	60	45.63	Melt	9:14:15	0	0.00	Melt	14:17:15	15		Charge
15:58:30	70	48.33	Melt	9:14:30	0	0.00	Melt	14:17:30	15		Charge
15:58:45	65	51.04	Melt	9:14:45	0	0.00	Melt	14:17:45	15	11.81	Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
15:59:00	65	53.75	Melt	9:15:00	0	0.00	Melt	14:18:00	10		Melt
15:59:15	65	56.46	Melt	9:15:15	0	0.00	Melt	14:18:15	10		Melt
15:59:30	60	58.96	Melt	9:15:30	0	0.00	Melt	14:18:30	10		Melt
15:59:45	50	60.63	Melt	9:15:45	0	0.00	Melt	14:18:45	15		Melt
16:00:00	40	61.67	Melt	9:16:00	0	0.00	Melt	14:19:00	15		Melt
16:00:15	35	62.71	Melt	9:16:15	0	0.00	Melt	14:19:15	15		Melt
16:00:30	25	62.71	Melt	9:16:30	0	0.00	Melt	14:19:30	15		Melt
16:00:45	20	60.63	Melt	9:16:45	0	0.00	Melt	14:19:45	15		Melt
16:01:00	20	58.33	Melt	9:17:00	0	0.00	Melt	14:20:00	15		Melt
16:01:15	15	55.63	Melt	9:17:15	0	0.00	Melt	14:20:15	15		Melt
16:01:30	15	53.33	Melt	9:17:30	0	0.00	Melt	14:20:30	15		Melt
16:01:45	15	51.25	Melt	9:17:45	0	0.00	Melt	14:20:45	15		Melt
16:02:00	15	48.75	Melt	9:18:00	0	0.00	Melt	14:21:00	15		Melt
16:02:15	10	45.42	Melt	9:18:15	0	0.00	Melt	14:21:15	15		Melt
16:02:30	10	42.29	Melt	9:18:30	0	0.00	Melt	14:21:30	15		Melt
16:02:45	5	39.17	Melt	9:18:45	0	0.00	Melt	14:21:45	15		Melt
16:03:00	5	36.46	Melt	9:19:00	0	0.00	Melt	14:22:00	15		Melt
16:03:15	5	34.58	Melt	9:19:15	0	0.00	Melt	14:22:15	15		Melt
16:03:30	10	32.92	Melt	9:19:30	0	0.00	Melt	14:22:30	15		Melt
16:03:45	15	31.46	Melt	9:19:45	0	0.00	Melt	14:22:45	15		Melt
16:04:00	15	29.58	Melt	9:20:00	0	0.00	Melt	14:23:00	15		Melt
16:04:15	15	27.71	Melt	9:20:15	0	0.00	Melt	14:23:15	15		Melt
16:04:30	15	25.42	Melt	9:20:30	0	0.00	Melt	14:23:30	15		Melt
16:04:45	5	22.92	Melt	9:20:45	0	0.00	Melt	14:23:45	15	14.38	Melt
16:05:00	5	20.42	Melt	9:21:00	0	0.00	Melt	14:24:00	15	14.58	Melt
16:05:15	5	17.92	Melt	9:21:15	0	0.00	Melt	14:24:15	20	15.00	Melt
16:05:30	5	15.63	Melt	9:21:30	0	0.00	Melt	14:24:30	20	15.42	Melt
16:05:45	0	13.54	Melt	9:21:45	0	0.00	Melt	14:24:45	30	16.04	Melt
16:06:00	0	11.88	Melt	9:22:00	0	0.00	Melt	14:25:00	30	16.67	Melt
16:06:15	0	10.42	Melt	9:22:15	0	0.00	Melt	14:25:15	25	17.08	Melt
16:06:30	0	9.38	Melt	9:22:30	0	0.00	Melt	14:25:30	20	17.29	Melt
16:06:45	0	8.54	Melt	9:22:45	0	0.00	Melt	14:25:45	20	17.50	Melt
16:07:00	0	7.71	Melt	9:23:00	0	0.00	Melt	14:26:00	20	17.71	Melt
16:07:15	0	7.08	Melt	9:23:15	0	0.00	Melt	14:26:15	15	17.71	Melt
16:07:30	0	6.46	Melt	9:23:30	0	0.00	Melt	14:26:30	15	17.71	Melt
16:07:45	0	5.83	Melt	9:23:45	0	0.00	Melt	14:26:45	15	17.71	Melt
16:08:00	0	5.21	Melt	9:24:00	0	0.00	Melt	14:27:00	15	17.71	Melt
16:08:15	0	4.79	Melt	9:24:15	0	0.00	Melt	14:27:15	15	17.71	Melt
16:08:30	0	4.38	Melt	9:24:30	10	0.42	Melt	14:27:30	15	17.71	Melt
16:08:45	0	4.17	Melt	9:24:45	10	0.83	Melt	14:27:45	15	17.71	Melt
16:09:00	0	3.96	Melt	9:25:00	10	1.25	Melt	14:28:00	15	17.71	Melt

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
16:09:15	0	3.75	Melt	9:25:15	10	1.67	Melt	14:28:15	15	17.71	Melt
16:09:30	0	3.33	Melt	9:25:30	10	2.08	Melt	14:28:30	15	17.71	Melt
16:09:45	0	2.71	Melt	9:25:45	5	2.29	Melt	14:28:45	15	17.71	Melt
16:10:00	0	2.08	Melt	9:26:00	0	2.29	Melt	14:29:00	15	17.71	Melt
16:10:15	0	1.46	Melt	9:26:15	0	2.29	Melt	14:29:15	15	17.71	Melt
16:10:30	0	0.83	Melt	9:26:30	0	2.29	Melt	14:29:30	15	17.71	Melt
16:10:45	0	0.63	Melt	9:26:45	0	2.29	Melt	14:29:45	10	17.50	Melt
16:11:00	0	0.42	Melt	9:27:00	0	2.29	Melt	14:30:00	10	17.29	Melt
16:11:15	0	0.21	Melt	9:27:15	0	2.29	Melt	14:30:15	10	16.88	Melt
16:11:30	0	0.00	Melt	9:27:30	0	2.29	Melt	14:30:30	10	16.46	Melt
16:11:45	0	0.00	Melt	9:27:45	0	2.29	Melt	14:30:45	10	15.63	Melt
16:12:00	0	0.00	Melt	9:28:00	0	2.29	Melt	14:31:00	15	15.00	Melt
16:12:15	10	0.42	Melt	9:28:15	0	2.29	Melt	14:31:15	15	14.58	Melt
16:12:30	5	0.63	Melt	9:28:30	0	2.29	Melt	14:31:30	15	14.38	Melt
16:12:45	5	0.83	Melt	9:28:45	0	2.29	Melt	14:31:45	15	14.17	Melt
16:13:00	5	1.04	Melt	9:29:00	0	2.29	Melt	14:32:00	15	13.96	Melt
16:13:15	5	1.25	Melt	9:29:15	0	2.29	Melt	14:32:15	15	13.96	Melt
16:13:30	0	1.25	Melt	9:29:30	0	2.29	Melt	14:32:30	15	13.96	Melt
16:13:45	0	1.25	Melt	9:29:45	0	2.29	Melt	14:32:45	10	13.75	Melt
16:14:00	0	1.25	Melt	9:30:00	0	2.29	Melt	14:33:00	10	13.54	Melt
16:14:15	0	1.25	Melt	9:30:15	0	2.29	Melt	14:33:15	10	13.33	Melt
16:14:30	0	1.25	Melt	9:30:30	0	1.88	Melt	14:33:30	10	13.13	Melt
16:14:45	0	1.25	Melt	9:30:45	0	1.46	Melt	14:33:45	10	12.92	Melt
16:15:00	0	1.25	Melt	9:31:00	0		Charge	14:34:00	10	12.71	Melt
16:15:15	0	1.25	Melt	9:31:15	10		Charge	14:34:15	10	12.50	Melt
16:15:30	0	1.25	Melt	9:31:30	10		Charge	14:34:30	10	12.29	Melt
16:15:45	0	1.25	Melt	9:31:45	15		Charge	14:34:45	10	12.08	Melt
16:16:00	0	1.25	Melt	9:32:00	25		Charge	14:35:00	10		Tap
16:16:15	5	1.46	Melt	9:32:15	30		Charge	14:35:15	10		Tap
16:16:30	10	1.88	Melt	9:32:30	30		Charge	14:35:30	10		Tap
16:16:45	10	2.29	Melt	9:32:45	40		Charge	14:35:45	10		Tap
16:17:00	5	2.50	Melt	9:33:00	45		Charge	14:36:00	15		Tap
16:17:15	5	2.71	Melt	9:33:15	45		Charge	14:36:15	20		Tap
16:17:30	5	2.92	Melt	9:33:30	35		Charge	14:36:30	20		Tap
16:17:45	0	2.92	Melt	9:33:45	40		Charge	14:36:45	20		Tap
16:18:00	0	2.92	Melt	9:34:00	40		Charge	14:37:00	15		Tap
16:18:15	0	2.50	Melt	9:34:15	30		Charge	14:37:15	15		Tap
16:18:30	10	2.71	Melt	9:34:30	25		Charge	14:37:30	15		Tap
16:18:45	20	3.33	Melt	9:34:45	20		Charge	14:37:45	15		Tap
16:19:00	10	3.54	Melt	9:35:00	20		Charge	14:38:00	15		Tap
16:19:15	5	3.54	Melt	9:35:15	15		Charge	14:38:15	15		Tap

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
16:19:30	5	3.75	Melt	9:35:30	15		Charge	14:38:30	15		Tap
16:19:45	0	3.75	Melt	9:35:45	15		Charge	14:38:45	15		Tap
16:20:00	0		Charge	9:36:00	15		Charge	14:39:00	15		Tap
16:20:15	0		Charge	9:36:15	10		Charge	14:39:15	10		Tap
16:20:30	0		Charge	9:36:30	10		Charge	14:39:30	10		Tap
16:20:45	0		Charge	9:36:45	5	22.71	Charge	14:39:45	10		Tap
16:21:00	0		Charge	9:37:00	0		Melt	14:40:00	10		Tap
16:21:15	0		Charge	9:37:15	0		Melt	14:40:15	10		Tap
16:21:30	0		Charge	9:37:30	0		Melt	14:40:30	10		Tap
16:21:45	0		Charge	9:37:45	0		Melt	14:40:45	10		Tap
16:22:00	0		Charge	9:38:00	5		Melt	14:41:00	10		Tap
16:22:15	0		Charge	9:38:15	5		Melt	14:41:15	10		Tap
16:22:30	5		Charge	9:38:30	5		Melt	14:41:30	10		Tap
16:22:45	5		Charge	9:38:45	10		Melt	14:41:45	10		Tap
16:23:00	10		Charge	9:39:00	15		Melt	14:42:00	10		Tap
16:23:15	10		Charge	9:39:15	15		Melt	14:42:15	10		Tap
16:23:30	5		Charge	9:39:30	15		Melt	14:42:30	10		Tap
16:23:45	5		Charge	9:39:45	20		Melt	14:42:45	5	12.34	Tap
16:24:00	0		Charge	9:40:00	25		Melt	14:43:00	5		Charge
16:24:15	0		Charge	9:40:15	25		Melt	14:43:15	5		Charge
16:24:30	5		Charge	9:40:30	25		Melt	14:43:30	5		Charge
16:24:45	5		Charge	9:40:45	20		Melt	14:43:45	5		Charge
16:25:00	5		Charge	9:41:00	10		Melt	14:44:00	10		Charge
16:25:15	5		Charge	9:41:15	10		Melt	14:44:15	10		Charge
16:25:30	5		Charge	9:41:30	5		Melt	14:44:30	15		Charge
16:25:45	0	2.71	Charge	9:41:45	0		Melt	14:44:45	15		Charge
16:26:00	0		Melt	9:42:00	10		Charge	14:45:00	15		Charge
16:26:15	0		Melt	9:42:15	10		Charge	14:45:15	10		Charge
16:26:30	0		Melt	9:42:30	10		Charge	14:45:30	10		Charge
16:26:45	0		Melt	9:42:45	5		Charge	14:45:45	10		Charge
16:27:00	0		Melt	9:43:00	0		Charge	14:46:00	10		Charge
16:27:15	0		Melt	9:43:15	0		Charge	14:46:15	10		Charge
16:27:30	0		Melt	9:43:30	5		Charge	14:46:30	10		Charge
16:27:45	0		Melt	9:43:45	5		Charge	14:46:45	10		Charge
16:28:00	0		Melt	9:44:00	0		Charge	14:47:00	10		Charge
16:28:15	0		Melt	9:44:15	0		Charge	14:47:15	10		Charge
16:28:30	0		Melt	9:44:30	10		Charge	14:47:30	10		Charge
16:28:45	0		Melt	9:44:45	0		Charge	14:47:45	10		Charge
16:29:00	0		Melt	9:45:00	0		Charge	14:48:00	10		Charge
16:29:15	0		Melt	9:45:15	0		Charge	14:48:15	10		Charge
16:29:30	0		Melt	9:45:30	0		Charge	14:48:30	10		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
16:29:45	0		Melt	9:45:45	0		Charge	14:48:45	10		Charge
16:30:00	0		Melt	9:46:00	0		Charge	14:49:00	10		Charge
16:30:15	0		Melt	9:46:15	5		Charge	14:49:15	5		Charge
16:30:30	0		Melt	9:46:30	10		Charge	14:49:30	5		Charge
16:30:45	0		Melt	9:46:45	0		Charge	14:49:45	5		Charge
16:31:00	0		Melt	9:47:00	15		Charge	14:50:00	5		Charge
16:31:15	0		Melt	9:47:15	20		Charge	14:50:15	5		Charge
16:31:30	0		Melt	9:47:30	35		Charge	14:50:30	5		Charge
16:31:45	0	0.00	Melt	9:47:45	35	7.29	Charge	14:50:45	0		Charge
16:32:00	0	0.00	Melt	9:48:00	35		Melt	14:51:00	0		Charge
16:32:15	0	0.00	Melt	9:48:15	40		Melt	14:51:15	0		Charge
16:32:30	0	0.00	Melt	9:48:30	35		Melt	14:51:30	0		Charge
16:32:45	0	0.00	Melt	9:48:45	40		Melt	14:51:45	0		Charge
16:33:00	0	0.00	Melt	9:49:00	40		Melt	14:52:00	0		Charge
16:33:15	0	0.00	Melt	9:49:15	40		Melt	14:52:15	0		Charge
16:33:30	0	0.00	Melt	9:49:30	40		Melt	14:52:30	0		Charge
16:33:45	0	0.00	Melt	9:49:45	35		Melt	14:52:45	0		Charge
16:34:00	0	0.00	Melt	9:50:00	35		Melt	14:53:00	0		Charge
16:34:15	0	0.00	Melt	9:50:15	30		Melt	14:53:15	0		Charge
16:34:30	0	0.00	Melt	9:50:30	25		Melt	14:53:30	0		Charge
16:34:45	0	0.00	Melt	9:50:45	30		Melt	14:53:45	0		Charge
16:35:00	0	0.00	Melt	9:51:00	30		Melt	14:54:00	0		Charge
16:35:15	0	0.00	Melt	9:51:15	30		Melt	14:54:15	0		Charge
16:35:30	0	0.00	Melt	9:51:30	25		Melt	14:54:30	0		Charge
16:35:45	0	0.00	Melt	9:51:45	20		Melt	14:54:45	0		Charge
16:36:00	0	0.00	Melt	9:52:00	20		Melt	14:55:00	0		Charge
16:36:15	0	0.00	Melt	9:52:15	20		Melt	14:55:15	0		Charge
16:36:30	0	0.00	Melt	9:52:30	5		Melt	14:55:30	15		Charge
16:36:45	0	0.00	Melt	9:52:45	15		Melt	14:55:45	25		Charge
16:37:00	0	0.00	Melt	9:53:00	10		Melt	14:56:00	25		Charge
16:37:15	0	0.00	Melt	9:53:15	10		Melt	14:56:15	30		Charge
16:37:30	0	0.00	Melt	9:53:30	10		Melt	14:56:30	30		Charge
16:37:45	0	0.00	Melt	9:53:45	5	26.04	Melt	14:56:45	30		Charge
16:38:00	0	0.00	Melt	9:54:00	15	25.21	Melt	14:57:00	30		Charge
16:38:15	0	0.00	Melt	9:54:15	20	24.38	Melt	14:57:15	30		Charge
16:38:30	0	0.00	Melt	9:54:30	20	23.75	Melt	14:57:30	25		Charge
16:38:45	5	0.21	Melt	9:54:45	20	22.92	Melt	14:57:45	25		Charge
16:39:00	5	0.42	Melt	9:55:00	15		Tap	14:58:00	25		Charge
16:39:15	5	0.63	Melt	9:55:15	20		Tap	14:58:15	20		Charge
16:39:30	0	0.63	Melt	9:55:30	20		Tap	14:58:30	20		Charge
16:39:45	0	0.63	Melt	9:55:45	20		Tap	14:58:45	15		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
16:40:00	0	0.63	Melt	9:56:00	20		Tap	14:59:00	15		Charge
16:40:15	0	0.63	Melt	9:56:15	20		Tap	14:59:15	15		Charge
16:40:30	0	0.63	Melt	9:56:30	15		Tap	14:59:30	15		Charge
16:40:45	0	0.63	Melt	9:56:45	15		Tap	14:59:45	15		Charge
16:41:00	0	0.63	Melt	9:57:00	10		Tap	15:00:00	15		Charge
16:41:15	0	0.63	Melt	9:57:15	10		Tap	15:00:15	15		Charge
16:41:30	0	0.63	Melt	9:57:30	10		Tap	15:00:30	10		Charge
16:41:45	0	0.63	Melt	9:57:45	10		Tap	15:00:45	10		Charge
16:42:00	0	0.63	Melt	9:58:00	5		Tap	15:01:00	10		Charge
16:42:15	0	0.63	Melt	9:58:15	0		Tap	15:01:15	10		Charge
16:42:30	0	0.63	Melt	9:58:30	0		Tap	15:01:30	10		Charge
16:42:45	0	0.63	Melt	9:58:45	0		Tap	15:01:45	5	10.07	Charge
16:43:00	0		Tap	9:59:00	0		Tap	15:02:00	5		Melt
16:43:15	0		Tap	9:59:15	0		Tap	15:02:15	5		Melt
16:43:30	5		Tap	9:59:30	0		Tap	15:02:30	5		Melt
16:43:45	10		Tap	9:59:45	0		Tap	15:02:45	5		Melt
16:44:00	5		Tap	10:00:00	0		Tap	15:03:00	5		Melt
16:44:15	5		Tap	10:00:15	0		Tap	15:03:15	5		Melt
16:44:30	10		Tap	10:00:30	0		Tap	15:03:30	5		Melt
16:44:45	15		Tap	10:00:45	0		Tap	15:03:45	5		Melt
16:45:00	15		Tap	10:01:00	0		Tap	15:04:00	5		Melt
16:45:15	15		Tap	10:01:15	0		Tap	15:04:15	0		Melt
16:45:30	15		Tap	10:01:30	0		Tap	15:04:30	0		Melt
16:45:45	10		Tap	10:01:45	0		Tap	15:04:45	0		Melt
16:46:00	10		Tap	10:02:00	0		Tap	15:05:00	0		Melt
16:46:15	10		Tap	10:02:15	0		Tap	15:05:15	0		Melt
16:46:30	10		Tap	10:02:30	0		Tap	15:05:30	0		Melt
16:46:45	15		Tap	10:02:45	0		Tap	15:05:45	0		Melt
16:47:00	20		Tap	10:03:00	0		Tap	15:06:00	0		Melt
16:47:15	20		Tap	10:03:15	0	5.59	Tap	15:06:15	0		Melt
16:47:30	15		Tap	10:03:30	0		Charge	15:06:30	0		Melt
16:47:45	15		Tap	10:03:45	0		Charge	15:06:45	0		Melt
16:48:00	15		Tap	10:04:00	0		Charge	15:07:00	0		Melt
16:48:15	15		Tap	10:04:15	0		Charge	15:07:15	0		Melt
16:48:30	15		Tap	10:04:30	0		Charge	15:07:30	0		Melt
16:48:45	15		Tap	10:04:45	15		Charge	15:07:45	0	1.88	Melt
16:49:00	20		Tap	10:05:00	10		Charge	15:08:00	0	1.67	Melt
16:49:15	20		Tap	10:05:15	10		Charge	15:08:15	0	1.46	Melt
16:49:30	20		Tap	10:05:30	10		Charge	15:08:30	0	1.25	Melt
16:49:45	15	12.68	Tap	10:05:45	20		Charge	15:08:45	0	1.04	Melt
16:50:00	15		Charge	10:06:00	5		Charge	15:09:00	0	0.83	Melt

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
16:50:15	10		Charge	10:06:15	5		Charge	15:09:15	0	0.63	Melt
16:50:30	10		Charge	10:06:30	10		Charge	15:09:30	0	0.42	Melt
16:50:45	10		Charge	10:06:45	15		Charge	15:09:45	0	0.21	Melt
16:51:00	10		Charge	10:07:00	20		Charge	15:10:00	0	0.00	Melt
16:51:15	5		Charge	10:07:15	25		Charge	15:10:15	0	0.00	Melt
16:51:30	5		Charge	10:07:30	25		Charge	15:10:30	0	0.00	Melt
16:51:45	5		Charge	10:07:45	25		Charge	15:10:45	0	0.00	Melt
16:52:00	5		Charge	10:08:00	20		Charge	15:11:00	0	0.00	Melt
16:52:15	0		Charge	10:08:15	20		Charge	15:11:15	0	0.00	Melt
16:52:30	0		Charge	10:08:30	15		Charge	15:11:30	0	0.00	Melt
16:52:45	0		Charge	10:08:45	15		Charge	15:11:45	0	0.00	Melt
16:53:00	5		Charge	10:09:00	25		Charge	15:12:00	0	0.00	Melt
16:53:15	15		Charge	10:09:15	20		Charge	15:12:15	0	0.00	Melt
16:53:30	15		Charge	10:09:30	20		Charge	15:12:30	0	0.00	Melt
16:53:45	10		Charge	10:09:45	15		Charge	15:12:45	0	0.00	Melt
16:54:00	10		Charge	10:10:00	10		Charge	15:13:00	0	0.00	Melt
16:54:15	5		Charge	10:10:15	15		Charge	15:13:15	0	0.00	Melt
16:54:30	5		Charge	10:10:30	15		Charge	15:13:30	0	0.00	Melt
16:54:45	5		Charge	10:10:45	15		Charge	15:13:45	0	0.00	Melt
16:55:00	5		Charge	10:11:00	15		Charge	15:14:00	0	0.00	Melt
16:55:15	5		Charge	10:11:15	15		Charge	15:14:15	0	0.00	Melt
16:55:30	0		Charge	10:11:30	10		Charge	15:14:30	0	0.00	Melt
16:55:45	0		Charge	10:11:45	10		Charge	15:14:45	0	0.00	Melt
16:56:00	0		Charge	10:12:00	10		Charge	15:15:00	5	0.21	Melt
16:56:15	0		Charge	10:12:15	10		Charge	15:15:15	10	0.63	Melt
16:56:30	0		Charge	10:12:30	5		Charge	15:15:30	10	1.04	Melt
16:56:45	0		Charge	10:12:45	0		Charge	15:15:45	5	1.25	Melt
16:57:00	0		Charge	10:13:00	0		Charge	15:16:00	5	1.46	Melt
16:57:15	0		Charge	10:13:15	0		Charge	15:16:15	5	1.67	Melt
16:57:30	0		Charge	10:13:30	0		Charge	15:16:30	0	1.67	Melt
16:57:45	0		Charge	10:13:45	0		Charge	15:16:45	0	1.67	Melt
16:58:00	0		Charge	10:14:00	0		Charge	15:17:00	0	1.67	Melt
16:58:15	5		Charge	10:14:15	0		Charge	15:17:15	0	1.67	Melt
16:58:30	5		Charge	10:14:30	0		Charge	15:17:30	0	1.67	Melt
16:58:45	5		Charge	10:14:45	0	10.33	Charge	15:17:45	0	1.67	Melt
16:59:00	5		Charge	10:15:00	0		Melt	15:18:00	0	1.67	Melt
16:59:15	5		Charge	10:15:15	0		Melt	15:18:15	0	1.67	Melt
16:59:30	5		Charge	10:15:30	0		Melt	15:18:30	10	2.08	Melt
16:59:45	5		Charge	10:15:45	0		Melt	15:18:45	10	2.50	Melt
17:00:00	5		Charge	10:16:00	0		Melt	15:19:00	5	2.71	Melt
17:00:15	0		Charge	10:16:15	0		Melt	15:19:15	5	2.92	Melt

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
17:00:30	0		Charge	10:16:30	0		Melt	15:19:30	10	3.33	Melt
17:00:45	0		Charge	10:16:45	0		Melt	15:19:45	10	3.75	Melt
17:01:00	0		Charge	10:17:00	0		Melt	15:20:00	10	4.17	Melt
17:01:15	0		Charge	10:17:15	0		Melt	15:20:15	10	4.58	Melt
17:01:30	0		Charge	10:17:30	0		Melt	15:20:30	5	4.79	Melt
17:01:45	0		Charge	10:17:45	0		Melt	15:20:45	5	5.00	Melt
17:02:00	0		Charge	10:18:00	0		Melt	15:21:00	5	5.00	Melt
17:02:15	0		Charge	10:18:15	0		Melt	15:21:15	10	5.00	Melt
17:02:30	0		Charge	10:18:30	0		Melt	15:21:30	10	5.00	Melt
17:02:45	0		Charge	10:18:45	0		Melt	15:21:45	10	5.21	Melt
17:03:00	0		Charge	10:19:00	0		Melt	15:22:00	15	5.63	Melt
17:03:15	0		Charge	10:19:15	0		Melt	15:22:15	20	6.25	Melt
17:03:30	0		Charge	10:19:30	0		Melt	15:22:30	20	7.08	Melt
17:03:45	0		Charge	10:19:45	0		Melt	15:22:45	20	7.92	Melt
17:04:00	0		Charge	10:20:00	0		Melt	15:23:00	15	8.54	Melt
17:04:15	0		Charge	10:20:15	0		Melt	15:23:15	15	9.17	Melt
17:04:30	0		Charge	10:20:30	0		Melt	15:23:30	15	9.79	Melt
17:04:45	0		Charge	10:20:45	0	0.00	Melt	15:23:45	15	10.42	Melt
17:05:00	0		Charge	10:21:00	0	0.00	Melt	15:24:00	15	11.04	Melt
17:05:15	10		Charge	10:21:15	0	0.00	Melt	15:24:15	15	11.67	Melt
17:05:30	10		Charge	10:21:30	0	0.00	Melt	15:24:30	15	11.88	Melt
17:05:45	15		Charge	10:21:45	0	0.00	Melt	15:24:45	15	12.08	Melt
17:06:00	15		Charge	10:22:00	0	0.00	Melt	15:25:00	15	12.50	Melt
17:06:15	10		Charge	10:22:15	0	0.00	Melt	15:25:15	15	12.92	Melt
17:06:30	5		Charge	10:22:30	0	0.00	Melt	15:25:30	15	13.13	Melt
17:06:45	5		Charge	10:22:45	0	0.00	Melt	15:25:45	15	13.33	Melt
17:07:00	5		Charge	10:23:00	0	0.00	Melt	15:26:00	15	13.54	Melt
17:07:15	0		Charge	10:23:15	0	0.00	Melt	15:26:15	10	13.54	Melt
17:07:30	0		Charge	10:23:30	0	0.00	Melt	15:26:30	10	13.75	Melt
17:07:45	0		Charge	10:23:45	0	0.00	Melt	15:26:45	10	13.96	Melt
17:08:00	0		Charge	10:24:00	0	0.00	Melt	15:27:00	10	14.17	Melt
17:08:15	0		Charge	10:24:15	0	0.00	Melt	15:27:15	10	14.17	Melt
17:08:30	0		Charge	10:24:30	0	0.00	Melt	15:27:30	5	13.96	Melt
17:08:45	0		Charge	10:24:45	0	0.00	Melt	15:27:45	5	13.75	Melt
17:09:00	0		Charge	10:25:00	0	0.00	Melt	15:28:00	5	13.33	Melt
17:09:15	0		Charge	10:25:15	0	0.00	Melt	15:28:15	5	12.71	Melt
17:09:30	0		Charge	10:25:30	0	0.00	Melt	15:28:30	5	12.08	Melt
17:09:45	0		Charge	10:25:45	0	0.00	Melt	15:28:45	5	11.46	Melt
17:10:00	0		Charge	10:26:00	0	0.00	Melt	15:29:00	5	11.04	Melt
17:10:15	0		Charge	10:26:15	0	0.00	Melt	15:29:15	5	10.63	Melt
17:10:30	0		Charge	10:26:30	0	0.00	Melt	15:29:30	5	10.21	Melt

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
17:10:45	0		Charge	10:26:45	0	0.00	Melt	15:29:45	0	9.58	Melt
17:11:00	0		Charge	10:27:00	0	0.00	Melt	15:30:00	0	8.96	Melt
17:11:15	0		Charge	10:27:15	0	0.00	Melt	15:30:15	0	8.33	Melt
17:11:30	0		Charge	10:27:30	0	0.00	Melt	15:30:30	5	7.92	Melt
17:11:45	0		Charge	10:27:45	0	0.00	Melt	15:30:45	10	7.71	Melt
17:12:00	0		Charge	10:28:00	0	0.00	Melt	15:31:00	10	7.50	Melt
17:12:15	0		Charge	10:28:15	0	0.00	Melt	15:31:15	10	7.29	Melt
17:12:30	0		Charge	10:28:30	0	0.00	Melt	15:31:30	15	7.29	Melt
17:12:45	0		Charge	10:28:45	0	0.00	Melt	15:31:45	15	7.29	Melt
17:13:00	0		Charge	10:29:00	0	0.00	Melt	15:32:00	15	7.29	Melt
17:13:15	0		Charge	10:29:15	0	0.00	Melt	15:32:15	20	7.71	Melt
17:13:30	0		Charge	10:29:30	0	0.00	Melt	15:32:30	20	8.13	Melt
17:13:45	0		Charge	10:29:45	0	0.00	Melt	15:32:45	15	8.33	Melt
17:14:00	0		Charge	10:30:00	0	0.00	Melt	15:33:00	15	8.54	Melt
17:14:15	0		Charge	10:30:15	0	0.00	Melt	15:33:15	10	8.54	Melt
17:14:30	0		Charge	10:30:30	0	0.00	Melt	15:33:30	10	8.75	Melt
17:14:45	0		Charge	10:30:45	0	0.00	Melt	15:33:45	5	8.75	Melt
17:15:00	0		Charge	10:31:00	0		Tap	15:34:00	5	8.75	Melt
17:15:15	0		Charge	10:31:15	15		Tap	15:34:15	5	8.75	Melt
17:15:30	0		Charge	10:31:30	25		Tap	15:34:30	5	8.75	Melt
17:15:45	0		Charge	10:31:45	25		Tap	15:34:45	5	8.75	Melt
17:16:00	0		Charge	10:32:00	20		Tap	15:35:00	5	8.75	Melt
17:16:15	10		Charge	10:32:15	20		Tap	15:35:15	5	8.75	Melt
17:16:30	15		Charge	10:32:30	25		Tap	15:35:30	5	8.75	Melt
17:16:45	15		Charge	10:32:45	25		Tap	15:35:45	5	8.96	Melt
17:17:00	10		Charge	10:33:00	25		Tap	15:36:00	5		Charge
17:17:15	10		Charge	10:33:15	30		Tap	15:36:15	10		Charge
17:17:30	10		Charge	10:33:30	30		Tap	15:36:30	10		Charge
17:17:45	10		Charge	10:33:45	25		Tap	15:36:45	15		Charge
17:18:00	5		Charge	10:34:00	25		Tap	15:37:00	15		Charge
17:18:15	5		Charge	10:34:15	15		Tap	15:37:15	15		Charge
17:18:30	5		Charge	10:34:30	15		Tap	15:37:30	20		Charge
17:18:45	5		Charge	10:34:45	5		Tap	15:37:45	20		Charge
17:19:00	0		Charge	10:35:00	5		Tap	15:38:00	20		Charge
17:19:15	0		Charge	10:35:15	0		Tap	15:38:15	15		Charge
17:19:30	0		Charge	10:35:30	0		Tap	15:38:30	15		Charge
17:19:45	0		Charge	10:35:45	0		Tap	15:38:45	15		Charge
17:20:00	0		Charge	10:36:00	0		Tap	15:39:00	15		Charge
17:20:15	0		Charge	10:36:15	0		Tap	15:39:15	15		Charge
17:20:30	0		Charge	10:36:30	0		Tap	15:39:30	10		Charge
17:20:45	0		Charge	10:36:45	0	13.75	Tap	15:39:45	10		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
17:21:00	0		Charge	10:37:00	0		Charge	15:40:00	10		Charge
17:21:15	0		Charge	10:37:15	0		Charge	15:40:15	10		Charge
17:21:30	0		Charge	10:37:30	0		Charge	15:40:30	10		Charge
17:21:45	0		Charge	10:37:45	0		Charge	15:40:45	5		Charge
17:22:00	0		Charge	10:38:00	0		Charge	15:41:00	5		Charge
17:22:15	0		Charge	10:38:15	0		Charge	15:41:15	5		Charge
17:22:30	0		Charge	10:38:30	0		Charge	15:41:30	5		Charge
17:22:45	0		Charge	10:38:45	0		Charge	15:41:45	5		Charge
17:23:00	0		Charge	10:39:00	0		Charge	15:42:00	5		Charge
17:23:15	0		Charge	10:39:15	0		Charge	15:42:15	0		Charge
17:23:30	0		Charge	10:39:30	0		Charge	15:42:30	0		Charge
17:23:45	0		Charge	10:39:45	0		Charge	15:42:45	0	10.18	Charge
17:24:00	0		Charge	10:40:00	0		Charge	15:43:00	0		Tap
17:24:15	0		Charge	10:40:15	0		Charge	15:43:15	10		Tap
17:24:30	0		Charge	10:40:30	0		Charge	15:43:30	10		Tap
17:24:45	0	2.64	Charge	10:40:45	0		Charge	15:43:45	15		Tap
17:25:00	0		Melt	10:41:00	0		Charge	15:44:00	15		Tap
17:25:15	0		Melt	10:41:15	0		Charge	15:44:15	15		Tap
17:25:30	0		Melt	10:41:30	0		Charge	15:44:30	20		Tap
17:25:45	0		Melt	10:41:45	0		Charge	15:44:45	20		Tap
17:26:00	0		Melt	10:42:00	0		Charge	15:45:00	15		Tap
17:26:15	0		Melt	10:42:15	0		Charge	15:45:15	15		Tap
17:26:30	0		Melt	10:42:30	0		Charge	15:45:30	10		Tap
17:26:45	0		Melt	10:42:45	0		Charge	15:45:45	10		Tap
17:27:00	0		Melt	10:43:00	0		Charge	15:46:00	10		Tap
17:27:15	0		Melt	10:43:15	0		Charge	15:46:15	10		Tap
17:27:30	0		Melt	10:43:30	0		Charge	15:46:30	10		Tap
17:27:45	0		Melt	10:43:45	0		Charge	15:46:45	10		Tap
17:28:00	0		Melt	10:44:00	0		Charge	15:47:00	10		Tap
17:28:15	0		Melt	10:44:15	0		Charge	15:47:15	10		Tap
17:28:30	0		Melt	10:44:30	0		Charge	15:47:30	10		Tap
17:28:45	0		Melt	10:44:45	0		Charge	15:47:45	10		Tap
17:29:00	0		Melt	10:45:00	0		Charge	15:48:00	10		Tap
17:29:15	0		Melt	10:45:15	0		Charge	15:48:15	10		Tap
17:29:30	0		Melt	10:45:30	0		Charge	15:48:30	5		Tap
17:29:45	0		Melt	10:45:45	0		Charge	15:48:45	5		Tap
17:30:00	0		Melt	10:46:00	0		Charge	15:49:00	5		Tap
17:30:15	0		Melt	10:46:15	0		Charge	15:49:15	15		Tap
17:30:30	0		Melt	10:46:30	0		Charge	15:49:30	15		Tap
17:30:45	0	0.00	Melt	10:46:45	0		Charge	15:49:45	20	11.43	Tap
17:31:00	0	0.00	Melt	10:47:00	0		Charge	15:50:00	20		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
17:31:15	0	0.00	Melt	10:47:15	0		Charge	15:50:15	25		Charge
17:31:30	0	0.00	Melt	10:47:30	0		Charge	15:50:30	25		Charge
17:31:45	0	0.00	Melt	10:47:45	0		Charge	15:50:45	25		Charge
17:32:00	0	0.00	Melt	10:48:00	0		Charge	15:51:00	25		Charge
17:32:15	0	0.00	Melt	10:48:15	0		Charge	15:51:15	25		Charge
17:32:30	0	0.00	Melt	10:48:30	0		Charge	15:51:30	25		Charge
17:32:45	0	0.00	Melt	10:48:45	0		Charge	15:51:45	30		Charge
17:33:00	0	0.00	Melt	10:49:00	0		Charge	15:52:00	35		Charge
17:33:15	0	0.00	Melt	10:49:15	0		Charge	15:52:15	40		Charge
17:33:30	0	0.00	Melt	10:49:30	0		Charge	15:52:30	40		Charge
17:33:45	0	0.00	Melt	10:49:45	0		Charge	15:52:45	40		Charge
17:34:00	0	0.00	Melt	10:50:00	0		Charge	15:53:00	40		Charge
17:34:15	0	0.00	Melt	10:50:15	0		Charge	15:53:15	40		Charge
17:34:30	0	0.00	Melt	10:50:30	0		Charge	15:53:30	40		Charge
17:34:45	0	0.00	Melt	10:50:45	0		Charge	15:53:45	40		Charge
17:35:00	0	0.00	Melt	10:51:00	0		Charge	15:54:00	40		Charge
17:35:15	0	0.00	Melt	10:51:15	0		Charge	15:54:15	35		Charge
17:35:30	0	0.00	Melt	10:51:30	0		Charge	15:54:30	30		Charge
17:35:45	0	0.00	Melt	10:51:45	0		Charge	15:54:45	30		Charge
17:36:00	0	0.00	Melt	10:52:00	0		Charge	15:55:00	30		Charge
17:36:15	0	0.00	Melt	10:52:15	0		Charge	15:55:15	25		Charge
17:36:30	0	0.00	Melt	10:52:30	0		Charge	15:55:30	25		Charge
17:36:45	0	0.00	Melt	10:52:45	0		Charge	15:55:45	25		Charge
17:37:00	0	0.00	Melt	10:53:00	0		Charge	15:56:00	25		Charge
17:37:15	0	0.00	Melt	10:53:15	0		Charge	15:56:15	25		Charge
17:37:30	0	0.00	Melt	10:53:30	0		Charge	15:56:30	20		Charge
17:37:45	0	0.00	Melt	10:53:45	0		Charge	15:56:45	20		Charge
17:38:00	0	0.00	Melt	10:54:00	0		Charge	15:57:00	20		Charge
17:38:15	0	0.00	Melt	10:54:15	0		Charge	15:57:15	20		Charge
17:38:30	0	0.00	Melt	10:54:30	0		Charge	15:57:30	15		Charge
17:38:45	0	0.00	Melt	10:54:45	0		Charge	15:57:45	15		Charge
17:39:00	0	0.00	Melt	10:55:00	0		Charge	15:58:00	15		Charge
17:39:15	0	0.00	Melt	10:55:15	0		Charge	15:58:15	15		Charge
17:39:30	0	0.00	Melt	10:55:30	0		Charge	15:58:30	10		Charge
17:39:45	0	0.00	Melt	10:55:45	0		Charge	15:58:45	10		Charge
17:40:00	0	0.00	Melt	10:56:00	0		Charge	15:59:00	10		Charge
17:40:15	0	0.00	Melt	10:56:15	0		Charge	15:59:15	10		Charge
17:40:30	0	0.00	Melt	10:56:30	0		Charge	15:59:30	10		Charge
17:40:45	0	0.00	Melt	10:56:45	0		Charge	15:59:45	10		Charge
17:41:00	0	0.00	Melt	10:57:00	0		Charge	16:00:00	10		Charge
17:41:15	0	0.00	Melt	10:57:15	0		Charge	16:00:15	5		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
17:41:30	0	0.00	Melt	10:57:30	0		Charge	16:00:30	5		Charge
17:41:45	0	0.00	Melt	10:57:45	0		Charge	16:00:45	5		Charge
17:42:00	0		Charge	10:58:00	0		Charge	16:01:00	5		Charge
17:42:15	0		Charge	10:58:15	0		Charge	16:01:15	5		Charge
17:42:30	5		Charge	10:58:30	0		Charge	16:01:30	5		Charge
17:42:45	15		Charge	10:58:45	0		Charge	16:01:45	15		Charge
17:43:00	15		Charge	10:59:00	0		Charge	16:02:00	15		Charge
17:43:15	10		Charge	10:59:15	0		Charge	16:02:15	20		Charge
17:43:30	35		Charge	10:59:30	0		Charge	16:02:30	20		Charge
17:43:45	50		Charge	10:59:45	0		Charge	16:02:45	20		Charge
17:44:00	40		Charge	11:00:00	0		Charge	16:03:00	20		Charge
17:44:15	40		Charge	11:00:15	0		Charge	16:03:15	20		Charge
17:44:30	30		Charge	11:00:30	0		Charge	16:03:30	20		Charge
17:44:45	20		Charge	11:00:45	0		Charge	16:03:45	20		Charge
17:45:00	20		Charge	11:01:00	0		Charge	16:04:00	20		Charge
17:45:15	15		Charge	11:01:15	0		Charge	16:04:15	20		Charge
17:45:30	10		Charge	11:01:30	0		Charge	16:04:30	15		Charge
17:45:45	10		Charge	11:01:45	0		Charge	16:04:45	15		Charge
17:46:00	5		Charge	11:02:00	0		Charge	16:05:00	15		Charge
17:46:15	5		Charge	11:02:15	0		Charge	16:05:15	15		Charge
17:46:30	10		Charge	11:02:30	0		Charge	16:05:30	15		Charge
17:46:45	10		Charge	11:02:45	0		Charge	16:05:45	15		Charge
17:47:00	10		Charge	11:03:00	0		Charge	16:06:00	15		Charge
17:47:15	10		Charge	11:03:15	0		Charge	16:06:15	15		Charge
17:47:30	15		Charge	11:03:30	0		Charge	16:06:30	15		Charge
17:47:45	15		Charge	11:03:45	0		Charge	16:06:45	15		Charge
17:48:00	10		Charge	11:04:00	0		Charge	16:07:00	15		Charge
17:48:15	5		Charge	11:04:15	0		Charge	16:07:15	15		Charge
17:48:30	5		Charge	11:04:30	0		Charge	16:07:30	15		Charge
17:48:45	5		Charge	11:04:45	0		Charge	16:07:45	15		Charge
17:49:00	5		Charge	11:05:00	10		Charge	16:08:00	15		Charge
17:49:15	0		Charge	11:05:15	10		Charge	16:08:15	15		Charge
17:49:30	0		Charge	11:05:30	10		Charge	16:08:30	15		Charge
17:49:45	0		Charge	11:05:45	10	0.34	Charge	16:08:45	15		Charge
17:50:00	0		Charge	11:06:00	5		Melt	16:09:00	15		Charge
17:50:15	0		Charge	11:06:15	0		Melt	16:09:15	15		Charge
17:50:30	0		Charge	11:06:30	0		Melt	16:09:30	10		Charge
17:50:45	10		Charge	11:06:45	0		Melt	16:09:45	10		Charge
17:51:00	20		Charge	11:07:00	0		Melt	16:10:00	10		Charge
17:51:15	35		Charge	11:07:15	0		Melt	16:10:15	10		Charge
17:51:30	30		Charge	11:07:30	0		Melt	16:10:30	10		Charge

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
17:51:45	25		Charge	11:07:45	0		Melt	16:10:45	5		Charge
17:52:00	15		Charge	11:08:00	0		Melt	16:11:00	5		Charge
17:52:15	15		Charge	11:08:15	0		Melt	16:11:15	5		Charge
17:52:30	10		Charge	11:08:30	0		Melt	16:11:30	5		Charge
17:52:45	5	13.41	Charge	11:08:45	0		Melt	16:11:45	10		Charge
17:53:00	5		Melt	11:09:00	0		Melt	16:12:00	15		Charge
17:53:15	5		Melt	11:09:15	0		Melt	16:12:15	15		Charge
17:53:30	0		Melt	11:09:30	0		Melt	16:12:30	15		Charge
17:53:45	0		Melt	11:09:45	0		Melt	16:12:45	15		Charge
17:54:00	0		Melt	11:10:00	0		Melt	16:13:00	15		Charge
17:54:15	0		Melt	11:10:15	0		Melt	16:13:15	15		Charge
17:54:30	0		Melt	11:10:30	0		Melt	16:13:30	15		Charge
17:54:45	0		Melt	11:10:45	0		Melt	16:13:45	15		Charge
17:55:00	0		Melt	11:11:00	0		Melt	16:14:00	15		Charge
17:55:15	0		Melt	11:11:15	0		Melt	16:14:15	20		Charge
17:55:30	0		Melt	11:11:30	0		Melt	16:14:30	25		Charge
17:55:45	0		Melt	11:11:45	0	0.21	Melt	16:14:45	25		Charge
17:56:00	0		Melt	11:12:00	0	0.00	Melt	16:15:00	25		Charge
17:56:15	5		Melt	11:12:15	0	0.00	Melt	16:15:15	25		Charge
17:56:30	10		Melt	11:12:30	0	0.00	Melt	16:15:30	25		Charge
17:56:45	10		Melt	11:12:45	0	0.00	Melt	16:15:45	25		Charge
17:57:00	5		Melt	11:13:00	0	0.00	Melt	16:16:00	25		Charge
17:57:15	5		Melt	11:13:15	0	0.00	Melt	16:16:15	25		Charge
17:57:30	0		Melt	11:13:30	0	0.00	Melt	16:16:30	25		Charge
17:57:45	0		Melt	11:13:45	0	0.00	Melt	16:16:45	20		Charge
17:58:00	0		Melt	11:14:00	0	0.00	Melt	16:17:00	20		Charge
17:58:15	0		Melt	11:14:15	0	0.00	Melt	16:17:15	15		Charge
17:58:30	0		Melt	11:14:30	10	0.42	Melt	16:17:30	15		Charge
17:58:45	0	1.88	Melt	11:14:45	10	0.83	Melt	16:17:45	15		Charge
17:59:00	0	1.67	Melt	11:15:00	0	0.83	Melt	16:18:00	15		Charge
17:59:15	0	1.46	Melt	11:15:15	0	0.83	Melt	16:18:15	15		Charge
17:59:30	0	1.46	Melt	11:15:30	0	0.83	Melt	16:18:30	15		Charge
17:59:45	0	1.46	Melt	11:15:45	0	0.83	Melt	16:18:45	15		Charge
18:00:00	0	1.46	Melt	11:16:00	0	0.83	Melt	16:19:00	15		Charge
18:00:15	10	1.88	Melt	11:16:15	0	0.83	Melt	16:19:15	20		Charge
18:00:30	10	2.29	Melt	11:16:30	0	0.83	Melt	16:19:30	20		Charge
18:00:45	5	2.50	Melt	11:16:45	0	0.83	Melt	16:19:45	20	18.63	Charge
18:01:00	5	2.71	Melt	11:17:00	0	0.83	Melt				
18:01:15	5	2.92	Melt	11:17:15	0	0.83	Melt				
18:01:30	0	2.92	Melt	11:17:30	0	0.83	Melt				
18:01:45	0	2.92	Melt	11:17:45	0	0.83	Melt				

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
18:02:00	0	2.92	Melt	11:18:00	0	0.83	Melt				
18:02:15	0	2.71	Melt	11:18:15	0	0.83	Melt				
18:02:30	0	2.29	Melt	11:18:30	0	0.83	Melt				
18:02:45	10	2.29	Melt	11:18:45	0	0.83	Melt				
18:03:00	20	2.92	Melt	11:19:00	0	0.83	Melt				
18:03:15	20	3.54	Melt	11:19:15	0	0.83	Melt				
18:03:30	20	4.38	Melt	11:19:30	0	0.83	Melt				
18:03:45	15	5.00	Melt	11:19:45	0	0.83	Melt				
18:04:00	15	5.63	Melt	11:20:00	0	0.83	Melt				
18:04:15	15	6.25	Melt	11:20:15	0	0.83	Melt				
18:04:30	15	6.88	Melt	11:20:30	0	0.42	Melt				
18:04:45	10	7.29	Melt	11:20:45	0	0.00	Melt				
18:05:00	10	7.71	Melt	11:21:00	0	0.00	Melt				
18:05:15	5	7.92	Melt								
18:05:30	5	8.13	Melt								
18:05:45	5	8.33	Melt								
18:06:00	5	8.54	Melt								
18:06:15	0	8.13	Melt								
18:06:30	0	7.71	Melt								
18:06:45	0	7.50	Melt								
18:07:00	0	7.29	Melt								
18:07:15	5	7.29	Melt								
18:07:30	5	7.50	Melt								
18:07:45	10	7.92	Melt								
18:08:00	10	8.33	Melt								
18:08:15	10	8.75	Melt								
18:08:30	5	8.96	Melt								
18:08:45	5	8.75	Melt								
18:09:00	5	8.13	Melt								
18:09:15	5	7.50	Melt								
18:09:30	5	6.88	Melt								
18:09:45	0	6.25	Melt								
18:10:00	0	5.63	Melt								
18:10:15	15	5.63	Melt								
18:10:30	15	5.63	Melt								
18:10:45	10	5.63	Melt								
18:11:00	10	5.63	Melt								
18:11:15	15	6.04	Melt								
18:11:30	15	6.46	Melt								
18:11:45	15	6.88	Melt								
18:12:00	20	7.50	Melt								

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
18:12:15	20	8.33	Melt								
18:12:30	15	8.96	Melt								
18:12:45	15	9.58	Melt								
18:13:00	15	10.21	Melt								
18:13:15	10	10.42	Melt								
18:13:30	10	10.63	Melt								
18:13:45	15	10.83	Melt								
18:14:00	15	11.04	Melt								
18:14:15	15	11.25	Melt								
18:14:30	10	11.46	Melt								
18:14:45	10	11.67	Melt								
18:15:00	10	11.88	Melt								
18:15:15	10	12.08	Melt								
18:15:30	5	12.08	Melt								
18:15:45	5	12.29	Melt								
18:16:00	5	12.50	Melt								
18:16:15	5	12.08	Melt								
18:16:30	5	11.67	Melt								
18:16:45	0	11.25	Melt								
18:17:00	0	10.83	Melt								
18:17:15	0	10.21	Melt								
18:17:30	0	9.58	Melt								
18:17:45	0	8.96	Melt								
18:18:00	0	8.13	Melt								
18:18:15	0	7.29	Melt								
18:18:30	0	6.67	Melt								
18:18:45	0	6.04	Melt								
18:19:00	0	5.42	Melt								
18:19:15	0	5.00	Melt								
18:19:30	0	4.58	Melt								
18:19:45	0	3.96	Melt								
18:20:00	0	3.33	Melt								
18:20:15	0	2.71	Melt								
18:20:30	0	2.29	Melt								
18:20:45	0	1.88	Melt								
18:21:00	0	1.46	Melt								
18:21:15	0	1.04	Melt								
18:21:30	0	0.83	Melt								
18:21:45	0	0.63	Melt								
18:22:00	0	0.42	Melt								
18:22:15	0	0.21	Melt								

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
18:22:30	0	0.00	Melt								
18:22:45	0	0.00	Melt								
18:23:00	0	0.00	Melt								
18:23:15	0	0.00	Melt								
18:23:30	0	0.00	Melt								
18:23:45	0	0.00	Melt								
18:24:00	0	0.00	Melt								
18:24:15	0	0.00	Melt								
18:24:30	0	0.00	Melt								
18:24:45	0	0.00	Melt								
18:25:00	0	0.00	Melt								
18:25:15	0	0.00	Melt								
18:25:30	0	0.00	Melt								
18:25:45	0	0.00	Melt								
18:26:00	0	0.00	Melt								
18:26:15	0	0.00	Melt								
18:26:30	0	0.00	Melt								
18:26:45	0	0.00	Melt								
18:27:00	0	0.00	Melt								
18:27:15	0	0.00	Melt								
18:27:30	0	0.00	Melt								
18:27:45	0	0.00	Melt								
18:28:00	0	0.00	Melt								
18:28:15	0	0.00	Melt								
18:28:30	0	0.00	Melt								
18:28:45	0	0.00	Melt								
18:29:00	0		Tap								
18:29:15	0		Tap								
18:29:30	10		Tap								
18:29:45	15		Tap								
18:30:00	15		Tap								
18:30:15	10		Tap								
18:30:30	10		Tap								
18:30:45	5		Tap								
18:31:00	5		Tap								
18:31:15	5		Tap								
18:31:30	5		Tap								
18:31:45	5		Tap								
18:32:00	5		Tap								
18:32:15	10		Tap								
18:32:30	10		Tap								

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
18:32:45	15		Tap								
18:33:00	25		Tap								
18:33:15	20		Tap								
18:33:30	15		Tap								
18:33:45	15		Tap								
18:34:00	10		Tap								
18:34:15	10		Tap								
18:34:30	15		Tap								
18:34:45	20		Tap								
18:35:00	25		Tap								
18:35:15	25		Tap								
18:35:30	20		Tap								
18:35:45	15		Tap								
18:36:00	15		Tap								
18:36:15	10		Tap								
18:36:30	5		Tap								
18:36:45	5	11.72	Tap								
18:37:00	5		Melt								
18:37:15	5		Melt								
18:37:30	5		Melt								
18:37:45	0		Melt								
18:38:00	0		Melt								
18:38:15	0		Melt								
18:38:30	0		Melt								
18:38:45	0		Melt								
18:39:00	0		Melt								
18:39:15	0		Melt								
18:39:30	0		Melt								
18:39:45	0		Melt								
18:40:00	0		Melt								
18:40:15	0		Melt								
18:40:30	0		Melt								
18:40:45	0		Melt								
18:41:00	0		Charge								
18:41:15	0		Charge								
18:41:30	0		Charge								
18:41:45	0		Charge								
18:42:00	0		Charge								
18:42:15	0		Charge								
18:42:30	0		Charge								
18:42:45	0		Charge								

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
18:43:00	0		Charge								
18:43:15	0		Charge								
18:43:30	0		Charge								
18:43:45	0		Charge								
18:44:00	0		Charge								
18:44:15	0		Charge								
18:44:30	0		Charge								
18:44:45	0		Charge								
18:45:00	0		Charge								
18:45:15	0		Charge								
18:45:30	0		Charge								
18:45:45	0		Charge								
18:46:00	0		Charge								
18:46:15	0		Charge								
18:46:30	0		Charge								
18:46:45	0		Charge								
18:47:00	0		Charge								
18:47:15	0		Charge								
18:47:30	0		Charge								
18:47:45	0		Charge								
18:48:00	0		Charge								
18:48:15	0		Charge								
18:48:30	10		Charge								
18:48:45	15		Charge								
18:49:00	10		Charge								
18:49:15	10		Charge								
18:49:30	5		Charge								
18:49:45	5		Charge								
18:50:00	5		Charge								
18:50:15	0		Charge								
18:50:30	0		Charge								
18:50:45	5		Charge								
18:51:00	5		Charge								
18:51:15	10		Charge								
18:51:30	10		Charge								
18:51:45	5		Charge								
18:52:00	5		Charge								
18:52:15	5		Charge								
18:52:30	0		Charge								
18:52:45	0		Charge								
18:53:00	0		Charge								

Table 2.4. Visible Emission Observation Summary, Melt Shop Roof Monitor (continued)

TEST 1				TEST 2				TEST 3			
Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity	Time	VE	6-min Avg	Activity
18:53:15	0		Charge								
18:53:30	0		Charge								
18:53:45	0		Charge								
18:54:00	0		Charge								
18:54:15	0		Charge								
18:54:30	0		Charge								
18:54:45	0	1.88	Charge								
18:55:00	0		Melt								
18:55:15	0		Melt								
18:55:30	0		Melt								
18:55:45	0		Melt								
18:56:00	0		Melt								
18:56:15	0		Melt								
18:56:30	0		Melt								
18:56:45	0		Melt								
18:57:00	0		Melt								
18:57:15	0		Melt								
18:57:30	0		Melt								
18:57:45	0		Melt								
18:58:00	0		Melt								
18:58:15	0		Melt								
18:58:30	0		Melt								
18:58:45	0		Melt								
18:59:00	Too dark for VE's										

TABLE 2.5. VISIBLE EMISSION OBSERVATION SUMMARY, BAGHOUSE EXHAUST

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
13:59:00	0		7:15:00	0		12:18:00	0	
13:59:15	0		7:15:15	0		12:18:15	0	
13:59:30	0		7:15:30	0		12:18:30	0	
13:59:45	0		7:15:45	0		12:18:45	15	
14:00:00	0		7:16:00	0		12:19:00	0	
14:00:15	0		7:16:15	0		12:19:15	0	
14:00:30	0		7:16:30	10		12:19:30	0	
14:00:45	0		7:16:45	0		12:19:45	0	
14:01:00	0		7:17:00	0		12:20:00	0	
14:01:15	0		7:17:15	0		12:20:15	0	
14:01:30	0		7:17:30	0		12:20:30	0	
14:01:45	0		7:17:45	10		12:20:45	0	
14:02:00	0		7:18:00	0		12:21:00	0	
14:02:15	0		7:18:15	0		12:21:15	0	
14:02:30	0		7:18:30	0		12:21:30	0	
14:02:45	0		7:18:45	0		12:21:45	0	
14:03:00	0		7:19:00	0		12:22:00	0	
14:03:15	0		7:19:15	0		12:22:15	0	
14:03:30	0		7:19:30	0		12:22:30	0	
14:03:45	0		7:19:45	0		12:22:45	0	
14:04:00	0		7:20:00	0		12:23:00	0	
14:04:15	0		7:20:15	5		12:23:15	0	
14:04:30	0		7:20:30	0		12:23:30	10	
14:04:45	0	0.00	7:20:45	0	1.04	12:23:45	0	1.04
14:05:00	0	0.00	7:21:00	0	1.04	12:24:00	0	1.04
14:05:15	0	0.00	7:21:15	15	1.67	12:24:15	0	1.04
14:05:30	0	0.00	7:21:30	0	1.67	12:24:30	10	1.46
14:05:45	0	0.00	7:21:45	0	1.67	12:24:45	0	0.83
14:06:00	0	0.00	7:22:00	0	1.67	12:25:00	0	0.83
14:06:15	0	0.00	7:22:15	20	2.50	12:25:15	0	0.83
14:06:30	0	0.00	7:22:30	0	2.08	12:25:30	0	0.83
14:06:45	0	0.00	7:22:45	0	2.08	12:25:45	0	0.83
14:07:00	0	0.00	7:23:00	0	2.08	12:26:00	0	0.83
14:07:15	0	0.00	7:23:15	0	2.08	12:26:15	0	0.83
14:07:30	0	0.00	7:23:30	0	2.08	12:26:30	0	0.83
14:07:45	0	0.00	7:23:45	0	1.67	12:26:45	0	0.83
14:08:00	0	0.00	7:24:00	0	1.67	12:27:00	0	0.83

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
14:08:15	0	0.00	7:24:15	0	1.67	12:27:15	0	0.83
14:08:30	0	0.00	7:24:30	0	1.67	12:27:30	0	0.83
14:08:45	0	0.00	7:24:45	15	2.29	12:27:45	0	0.83
14:09:00	0	0.00	7:25:00	0	2.29	12:28:00	0	0.83
14:09:15	0	0.00	7:25:15	0	2.29	12:28:15	0	0.83
14:09:30	0	0.00	7:25:30	0	2.29	12:28:30	0	0.83
14:09:45	0	0.00	7:25:45	0	2.29	12:28:45	0	0.83
14:10:00	0	0.00	7:26:00	0	2.29	12:29:00	20	1.67
14:10:15	0	0.00	7:26:15	0	2.08	12:29:15	0	1.67
14:10:30	0	0.00	7:26:30	0	2.08	12:29:30	0	1.25
14:10:45	0	0.00	7:26:45	0	2.08	12:29:45	0	1.25
14:11:00	0	0.00	7:27:00	10	2.50	12:30:00	0	1.25
14:11:15	0	0.00	7:27:15	0	1.88	12:30:15	0	1.25
14:11:30	0	0.00	7:27:30	0	1.88	12:30:30	0	0.83
14:11:45	0	0.00	7:27:45	0	1.88	12:30:45	0	0.83
14:12:00	0	0.00	7:28:00	0	1.88	12:31:00	0	0.83
14:12:15	0	0.00	7:28:15	0	1.04	12:31:15	0	0.83
14:12:30	0	0.00	7:28:30	0	1.04	12:31:30	0	0.83
14:12:45	0	0.00	7:28:45	0	1.04	12:31:45	0	0.83
14:13:00	0	0.00	7:29:00	0	1.04	12:32:00	0	0.83
14:13:15	0	0.00	7:29:15	0	1.04	12:32:15	0	0.83
14:13:30	0	0.00	7:29:30	0	1.04	12:32:30	0	0.83
14:13:45	0	0.00	7:29:45	0	1.04	12:32:45	0	0.83
14:14:00	0	0.00	7:30:00	0	1.04	12:33:00	0	0.83
14:14:15	0	0.00	7:30:15	0	1.04	12:33:15	0	0.83
14:14:30	0	0.00	7:30:30	0	1.04	12:33:30	0	0.83
14:14:45	0	0.00	7:30:45	0	0.42	12:33:45	25	1.88
14:15:00	0	0.00	7:31:00	0	0.42	12:34:00	0	1.88
14:15:15	0	0.00	7:31:15	0	0.42	12:34:15	0	1.88
14:15:30	0	0.00	7:31:30	20	1.25	12:34:30	0	1.88
14:15:45	0	0.00	7:31:45	0	1.25	12:34:45	0	1.88
14:16:00	0	0.00	7:32:00	0	1.25	12:35:00	20	1.88
14:16:15	0	0.00	7:32:15	0	1.25	12:35:15	0	1.88
14:16:30	0	0.00	7:32:30	0	1.25	12:35:30	0	1.88
14:16:45	0	0.00	7:32:45	10	1.67	12:35:45	0	1.88
14:17:00	0	0.00	7:33:00	0	1.25	12:36:00	0	1.88
14:17:15	0	0.00	7:33:15	0	1.25	12:36:15	0	1.88

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
14:17:30	0	0.00	7:33:30	0	1.25	12:36:30	0	1.88
14:17:45	0	0.00	7:33:45	0	1.25	12:36:45	0	1.88
14:18:00	0	0.00	7:34:00	0	1.25	12:37:00	0	1.88
14:18:15	0	0.00	7:34:15	0	1.25	12:37:15	0	1.88
14:18:30	0	0.00	7:34:30	0	1.25	12:37:30	0	1.88
14:18:45	0	0.00	7:34:45	0	1.25	12:37:45	0	1.88
14:19:00	0	0.00	7:35:00	0	1.25	12:38:00	0	1.88
14:19:15	0	0.00	7:35:15	0	1.25	12:38:15	0	1.88
14:19:30	0	0.00	7:35:30	0	1.25	12:38:30	0	1.88
14:19:45	0	0.00	7:35:45	0	1.25	12:38:45	0	1.88
14:20:00	0	0.00	7:36:00	0	1.25	12:39:00	0	1.88
14:20:15	0	0.00	7:36:15	0	1.25	12:39:15	0	1.88
14:20:30	0	0.00	7:36:30	0	1.25	12:39:30	0	1.88
14:20:45	0	0.00	7:36:45	0	1.25	12:39:45	0	0.83
14:21:00	0	0.00	7:37:00	0	1.25	12:40:00	0	0.83
14:21:15	0	0.00	7:37:15	0	1.25	12:40:15	0	0.83
14:21:30	0	0.00	7:37:30	0	0.42	12:40:30	0	0.83
14:21:45	0	0.00	7:37:45	0	0.42	12:40:45	0	0.83
14:22:00	0	0.00	7:38:00	0	0.42	12:41:00	0	0.00
14:22:15	0	0.00	7:38:15	0	0.42	12:41:15	0	0.00
14:22:30	0	0.00	7:38:30	0	0.42	12:41:30	0	0.00
14:22:45	0	0.00	7:38:45	0	0.00	12:41:45	10	0.42
14:23:00	0	0.00	7:39:00	0	0.00	12:42:00	0	0.42
14:23:15	0	0.00	7:39:15	0	0.00	12:42:15	0	0.42
14:23:30	0	0.00	7:39:30	0	0.00	12:42:30	0	0.42
14:23:45	0	0.00	7:39:45	0	0.00	12:42:45	0	0.42
14:24:00	0	0.00	7:40:00	0	0.00	12:43:00	10	0.83
14:24:15	0	0.00	7:40:15	0	0.00	12:43:15	0	0.83
14:24:30	0	0.00	7:40:30	0	0.00	12:43:30	0	0.83
14:24:45	0	0.00	7:40:45	0	0.00	12:43:45	0	0.83
14:25:00	0	0.00	7:41:00	0	0.00	12:44:00	0	0.83
14:25:15	0	0.00	7:41:15	0	0.00	12:44:15	0	0.83
14:25:30	0	0.00	7:41:30	0	0.00	12:44:30	0	0.83
14:25:45	0	0.00	7:41:45	0	0.00	12:44:45	0	0.83
14:26:00	0	0.00	7:42:00	0	0.00	12:45:00	0	0.83
14:26:15	0	0.00	7:42:15	0	0.00	12:45:15	0	0.83
14:26:30	0	0.00	7:42:30	0	0.00	12:45:30	0	0.83

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
14:26:45	0	0.00	7:42:45	0	0.00	12:45:45	0	0.83
14:27:00	0	0.00	7:43:00	0	0.00	12:46:00	0	0.83
14:27:15	0	0.00	7:43:15	0	0.00	12:46:15	0	0.83
14:27:30	0	0.00	7:43:30	0	0.00	12:46:30	10	1.25
14:27:45	0	0.00	7:43:45	0	0.00	12:46:45	0	1.25
14:28:00	0	0.00	7:44:00	0	0.00	12:47:00	0	1.25
14:28:15	0	0.00	7:44:15	0	0.00	12:47:15	0	1.25
14:28:30	0	0.00	7:44:30	0	0.00	12:47:30	0	1.25
14:28:45	0	0.00	7:44:45	0	0.00	12:47:45	20	1.67
14:29:00	0	0.00	7:45:00	0	0.00	12:48:00	0	1.67
14:29:15	0	0.00	7:45:15	0	0.00	12:48:15	0	1.67
14:29:30	0	0.00	7:45:30	15	0.63	12:48:30	0	1.67
14:29:45	0	0.00	7:45:45	0	0.63	12:48:45	0	1.67
14:30:00	0	0.00	7:46:00	0	0.63	12:49:00	0	1.25
14:30:15	0	0.00	7:46:15	0	0.63	12:49:15	0	1.25
14:30:30	0	0.00	7:46:30	0	0.63	12:49:30	0	1.25
14:30:45	0	0.00	7:46:45	0	0.63	12:49:45	0	1.25
14:31:00	0	0.00	7:47:00	0	0.63	12:50:00	15	1.88
14:31:15	0	0.00	7:47:15	0	0.63	12:50:15	0	1.88
14:31:30	0	0.00	7:47:30	10	1.04	12:50:30	0	1.88
14:31:45	0	0.00	7:47:45	0	1.04	12:50:45	0	1.88
14:32:00	0	0.00	7:48:00	0	1.04	12:51:00	0	1.88
14:32:15	10	0.42	7:48:15	0	1.04	12:51:15	0	1.88
14:32:30	0	0.42	7:48:30	0	1.04	12:51:30	0	1.88
14:32:45	0	0.42	7:48:45	0	1.04	12:51:45	0	1.88
14:33:00	0	0.42	7:49:00	0	1.04	12:52:00	20	2.71
14:33:15	0	0.42	7:49:15	0	1.04	12:52:15	0	2.71
14:33:30	0	0.42	7:49:30	0	1.04	12:52:30	0	2.29
14:33:45	0	0.42	7:49:45	15	1.67	12:52:45	0	2.29
14:34:00	0	0.42	7:50:00	0	1.67	12:53:00	0	2.29
14:34:15	0	0.42	7:50:15	0	1.67	12:53:15	0	2.29
14:34:30	0	0.42	7:50:30	0	1.67	12:53:30	0	2.29
14:34:45	0	0.42	7:50:45	0	1.67	12:53:45	0	1.46
14:35:00	0	0.42	7:51:00	0	1.67	12:54:00	0	1.46
14:35:15	0	0.42	7:51:15	0	1.67	12:54:15	0	1.46
14:35:30	0	0.42	7:51:30	0	1.04	12:54:30	0	1.46
14:35:45	15	1.04	7:51:45	0	1.04	12:54:45	0	1.46

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
14:36:00	0	1.04	7:52:00	0	1.04	12:55:00	0	1.46
14:36:15	0	1.04	7:52:15	0	1.04	12:55:15	0	1.46
14:36:30	0	1.04	7:52:30	0	1.04	12:55:30	0	1.46
14:36:45	0	1.04	7:52:45	0	1.04	12:55:45	0	1.46
14:37:00	0	1.04	7:53:00	0	1.04	12:56:00	0	0.83
14:37:15	0	1.04	7:53:15	0	1.04	12:56:15	0	0.83
14:37:30	0	1.04	7:53:30	0	0.63	12:56:30	0	0.83
14:37:45	0	1.04	7:53:45	0	0.63	12:56:45	0	0.83
14:38:00	0	1.04	7:54:00	0	0.63	12:57:00	0	0.83
14:38:15	0	0.63	7:54:15	0	0.63	12:57:15	0	0.83
14:38:30	0	0.63	7:54:30	15	1.25	12:57:30	0	0.83
14:38:45	0	0.63	7:54:45	0	1.25	12:57:45	0	0.83
14:39:00	0	0.63	7:55:00	0	1.25	12:58:00	0	0.00
14:39:15	0	0.63	7:55:15	0	1.25	12:58:15	0	0.00
14:39:30	0	0.63	7:55:30	0	1.25	12:58:30	0	0.00
14:39:45	0	0.63	7:55:45	0	0.63	12:58:45	0	0.00
14:40:00	0	0.63	7:56:00	0	0.63	12:59:00	0	0.00
14:40:15	0	0.63	7:56:15	0	0.63	12:59:15	0	0.00
14:40:30	0	0.63	7:56:30	0	0.63	12:59:30	0	0.00
14:40:45	0	0.63	7:56:45	0	0.63	12:59:45	0	0.00
14:41:00	0	0.63	7:57:00	0	0.63	13:00:00	0	0.00
14:41:15	0	0.63	7:57:15	0	0.63	13:00:15	0	0.00
14:41:30	0	0.63	7:57:30	0	0.63	13:00:30	0	0.00
14:41:45	0	0.00	7:57:45	0	0.63	13:00:45	0	0.00
14:42:00	0	0.00	7:58:00	0	0.63	13:01:00	0	0.00
14:42:15	0	0.00	7:58:15	0	0.63	13:01:15	0	0.00
14:42:30	0	0.00	7:58:30	0	0.63	13:01:30	0	0.00
14:42:45	0	0.00	7:58:45	0	0.63	13:01:45	0	0.00
14:43:00	0	0.00	7:59:00	0	0.63	13:02:00	0	0.00
14:43:15	0	0.00	7:59:15	0	0.63	13:02:15	0	0.00
14:43:30	0	0.00	7:59:30	0	0.63	13:02:30	0	0.00
14:43:45	0	0.00	7:59:45	0	0.63	13:02:45	0	0.00
14:44:00	0	0.00	8:00:00	0	0.63	13:03:00	0	0.00
14:44:15	0	0.00	8:00:15	0	0.63	13:03:15	0	0.00
14:44:30	0	0.00	8:00:30	0	0.00	13:03:30	0	0.00
14:44:45	0	0.00	8:00:45	0	0.00	13:03:45	0	0.00
14:45:00	0	0.00	8:01:00	0	0.00	13:04:00	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
14:45:15	0	0.00	8:01:15	0	0.00	13:04:15	0	0.00
14:45:30	0	0.00	8:01:30	0	0.00	13:04:30	0	0.00
14:45:45	0	0.00	8:01:45	0	0.00	13:04:45	0	0.00
14:46:00	0	0.00	8:02:00	0	0.00	13:05:00	0	0.00
14:46:15	0	0.00	8:02:15	0	0.00	13:05:15	0	0.00
14:46:30	0	0.00	8:02:30	0	0.00	13:05:30	0	0.00
14:46:45	0	0.00	8:02:45	0	0.00	13:05:45	0	0.00
14:47:00	0	0.00	8:03:00	0	0.00	13:06:00	0	0.00
14:47:15	0	0.00	8:03:15	0	0.00	13:06:15	0	0.00
14:47:30	0	0.00	8:03:30	0	0.00	13:06:30	0	0.00
14:47:45	0	0.00	8:03:45	0	0.00	13:06:45	0	0.00
14:48:00	0	0.00	8:04:00	0	0.00	13:07:00	0	0.00
14:48:15	0	0.00	8:04:15	0	0.00	13:07:15	0	0.00
14:48:30	0	0.00	8:04:30	0	0.00	13:07:30	0	0.00
14:48:45	0	0.00	8:04:45	0	0.00	13:07:45	0	0.00
14:49:00	0	0.00	8:05:00	0	0.00	13:08:00	0	0.00
14:49:15	0	0.00	8:05:15	0	0.00	13:08:15	0	0.00
14:49:30	0	0.00	8:05:30	0	0.00	13:08:30	0	0.00
14:49:45	0	0.00	8:05:45	0	0.00	13:08:45	0	0.00
14:50:00	0	0.00	8:06:00	0	0.00	13:09:00	0	0.00
14:50:15	0	0.00	8:06:15	0	0.00	13:09:15	0	0.00
14:50:30	0	0.00	8:06:30	0	0.00	13:09:30	0	0.00
14:50:45	0	0.00	8:06:45	0	0.00	13:09:45	0	0.00
14:51:00	0	0.00	8:07:00	0	0.00	13:10:00	0	0.00
14:51:15	0	0.00	8:07:15	10	0.42	13:10:15	0	0.00
14:51:30	0	0.00	8:07:30	0	0.42	13:10:30	0	0.00
14:51:45	0	0.00	8:07:45	0	0.42	13:10:45	0	0.00
14:52:00	0	0.00	8:08:00	0	0.42	13:11:00	0	0.00
14:52:15	0	0.00	8:08:15	0	0.42	13:11:15	0	0.00
14:52:30	0	0.00	8:08:30	15	1.04	13:11:30	0	0.00
14:52:45	0	0.00	8:08:45	0	1.04	13:11:45	0	0.00
14:53:00	0	0.00	8:09:00	0	1.04	13:12:00	0	0.00
14:53:15	0	0.00	8:09:15	0	1.04	13:12:15	0	0.00
14:53:30	0	0.00	8:09:30	0	1.04	13:12:30	0	0.00
14:53:45	0	0.00	8:09:45	0	1.04	13:12:45	0	0.00
14:54:00	0	0.00	8:10:00	0	1.04	13:13:00	0	0.00
14:54:15	0	0.00	8:10:15	0	1.04	13:13:15	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
14:54:30	0	0.00	8:10:30	0	1.04	13:13:30	0	0.00
14:54:45	0	0.00	8:10:45	5	1.25	13:13:45	0	0.00
14:55:00	0	0.00	8:11:00	0	1.25	13:14:00	0	0.00
14:55:15	0	0.00	8:11:15	0	1.25	13:14:15	0	0.00
14:55:30	0	0.00	8:11:30	0	1.25	13:14:30	0	0.00
14:55:45	0	0.00	8:11:45	0	1.25	13:14:45	0	0.00
14:56:00	0	0.00	8:12:00	0	1.25	13:15:00	0	0.00
14:56:15	0	0.00	8:12:15	0	1.25	13:15:15	0	0.00
14:56:30	0	0.00	8:12:30	0	1.25	13:15:30	0	0.00
14:56:45	20	0.83	8:12:45	0	1.25	13:15:45	0	0.00
14:57:00	0	0.83	8:13:00	15	1.88	13:16:00	0	0.00
14:57:15	0	0.83	8:13:15	0	1.46	13:16:15	0	0.00
14:57:30	0	0.83	8:13:30	0	1.46	13:16:30	0	0.00
14:57:45	0	0.83	8:13:45	0	1.46	13:16:45	0	0.00
14:58:00	0	0.83	8:14:00	0	1.46	13:17:00	0	0.00
14:58:15	0	0.83	8:14:15	0	1.46	13:17:15	0	0.00
14:58:30	0	0.83	8:14:30	0	0.83	13:17:30	0	0.00
14:58:45	0	0.83	8:14:45	0	0.83	13:17:45	0	0.00
14:59:00	0	0.83	8:15:00	0	0.83	13:18:00	0	0.00
14:59:15	0	0.83	8:15:15	0	0.83	13:18:15	0	0.00
14:59:30	0	0.83	8:15:30	0	0.83	13:18:30	0	0.00
14:59:45	0	0.83	8:15:45	0	0.83	13:18:45	0	0.00
15:00:00	0	0.83	8:16:00	0	0.83	13:19:00	0	0.00
15:00:15	0	0.83	8:16:15	0	0.83	13:19:15	0	0.00
15:00:30	0	0.83	8:16:30	0	0.83	13:19:30	0	0.00
15:00:45	0	0.83	8:16:45	0	0.63	13:19:45	0	0.00
15:01:00	0	0.83	8:17:00	0	0.63	13:20:00	0	0.00
15:01:15	0	0.83	8:17:15	0	0.63	13:20:15	0	0.00
15:01:30	0	0.83	8:17:30	0	0.63	13:20:30	0	0.00
15:01:45	0	0.83	8:17:45	20	1.46	13:20:45	0	0.00
15:02:00	0	0.83	8:18:00	0	1.46	13:21:00	0	0.00
15:02:15	0	0.83	8:18:15	0	1.46	13:21:15	0	0.00
15:02:30	0	0.83	8:18:30	0	1.46	13:21:30	0	0.00
15:02:45	0	0.00	8:18:45	15	2.08	13:21:45	0	0.00
15:03:00	0	0.00	8:19:00	0	1.46	13:22:00	0	0.00
15:03:15	0	0.00	8:19:15	0	1.46	13:22:15	0	0.00
15:03:30	0	0.00	8:19:30	0	1.46	13:22:30	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
15:03:45	0	0.00	8:19:45	0	1.46	13:22:45	0	0.00
15:04:00	0	0.00	8:20:00	0	1.46	13:23:00	0	0.00
15:04:15	0	0.00	8:20:15	0	1.46	13:23:15	0	0.00
15:04:30	0	0.00	8:20:30	0	1.46	13:23:30	0	0.00
15:04:45	0	0.00	8:20:45	0	1.46	13:23:45	0	0.00
15:05:00	0	0.00	8:21:00	0	1.46	13:24:00	0	0.00
15:05:15	0	0.00	8:21:15	10	1.88	13:24:15	0	0.00
15:05:30	0	0.00	8:21:30	0	1.88	13:24:30	0	0.00
15:05:45	25	1.04	8:21:45	0	1.88	13:24:45	0	0.00
15:06:00	0	1.04	8:22:00	0	1.88	13:25:00	0	0.00
15:06:15	0	1.04	8:22:15	0	1.88	13:25:15	0	0.00
15:06:30	0	1.04	8:22:30	0	1.88	13:25:30	0	0.00
15:06:45	10	1.46	8:22:45	0	1.88	13:25:45	0	0.00
15:07:00	0	1.46	8:23:00	0	1.88	13:26:00	0	0.00
15:07:15	0	1.46	8:23:15	0	1.88	13:26:15	0	0.00
15:07:30	0	1.46	8:23:30	0	1.88	13:26:30	0	0.00
15:07:45	0	1.46	8:23:45	0	1.04	13:26:45	0	0.00
15:08:00	0	1.46	8:24:00	0	1.04	13:27:00	0	0.00
15:08:15	0	1.46	8:24:15	0	1.04	13:27:15	0	0.00
15:08:30	0	1.46	8:24:30	0	1.04	13:27:30	0	0.00
15:08:45	0	1.46	8:24:45	0	0.42	13:27:45	0	0.00
15:09:00	0	1.46	8:25:00	0	0.42	13:28:00	0	0.00
15:09:15	0	1.46	8:25:15	0	0.42	13:28:15	0	0.00
15:09:30	0	1.46	8:25:30	0	0.42	13:28:30	0	0.00
15:09:45	0	1.46	8:25:45	0	0.42	13:28:45	0	0.00
15:10:00	0	1.46	8:26:00	0	0.42	13:29:00	0	0.00
15:10:15	0	1.46	8:26:15	0	0.42	13:29:15	0	0.00
15:10:30	0	1.46	8:26:30	0	0.42	13:29:30	0	0.00
15:10:45	0	1.46	8:26:45	0	0.42	13:29:45	0	0.00
15:11:00	0	1.46	8:27:00	0	0.42	13:30:00	0	0.00
15:11:15	0	1.46	8:27:15	0	0.00	13:30:15	0	0.00
15:11:30	0	1.46	8:27:30	0	0.00	13:30:30	0	0.00
15:11:45	0	0.42	8:27:45	0	0.00	13:30:45	0	0.00
15:12:00	0	0.42	8:28:00	0	0.00	13:31:00	0	0.00
15:12:15	0	0.42	8:28:15	0	0.00	13:31:15	0	0.00
15:12:30	0	0.42	8:28:30	0	0.00	13:31:30	0	0.00
15:12:45	0	0.00	8:28:45	0	0.00	13:31:45	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
15:13:00	0	0.00	8:29:00	0	0.00	13:32:00	0	0.00
15:13:15	0	0.00	8:29:15	0	0.00	13:32:15	0	0.00
15:13:30	0	0.00	8:29:30	0	0.00	13:32:30	0	0.00
15:13:45	0	0.00	8:29:45	0	0.00	13:32:45	0	0.00
15:14:00	0	0.00	8:30:00	0	0.00	13:33:00	0	0.00
15:14:15	0	0.00	8:30:15	10	0.42	13:33:15	0	0.00
15:14:30	0	0.00	8:30:30	0	0.42	13:33:30	0	0.00
15:14:45	0	0.00	8:30:45	0	0.42	13:33:45	0	0.00
15:15:00	0	0.00	8:31:00	0	0.42	13:34:00	0	0.00
15:15:15	0	0.00	8:31:15	0	0.42	13:34:15	0	0.00
15:15:30	0	0.00	8:31:30	0	0.42	13:34:30	0	0.00
15:15:45	0	0.00	8:31:45	0	0.42	13:34:45	0	0.00
15:16:00	0	0.00	8:32:00	0	0.42	13:35:00	0	0.00
15:16:15	0	0.00	8:32:15	0	0.42	13:35:15	0	0.00
15:16:30	0	0.00	8:32:30	0	0.42	13:35:30	0	0.00
15:16:45	0	0.00	8:32:45	0	0.42	13:35:45	0	0.00
15:17:00	0	0.00	8:33:00	0	0.42	13:36:00	0	0.00
15:17:15	0	0.00	8:33:15	0	0.42	13:36:15	0	0.00
15:17:30	0	0.00	8:33:30	0	0.42	13:36:30	0	0.00
15:17:45	0	0.00	8:33:45	0	0.42	13:36:45	0	0.00
15:18:00	0	0.00	8:34:00	0	0.42	13:37:00	0	0.00
15:18:15	0	0.00	8:34:15	0	0.42	13:37:15	0	0.00
15:18:30	0	0.00	8:34:30	0	0.42	13:37:30	0	0.00
15:18:45	0	0.00	8:34:45	0	0.42	13:37:45	0	0.00
15:19:00	0	0.00	8:35:00	0	0.42	13:38:00	0	0.00
15:19:15	0	0.00	8:35:15	0	0.42	13:38:15	0	0.00
15:19:30	0	0.00	8:35:30	0	0.42	13:38:30	0	0.00
15:19:45	0	0.00	8:35:45	0	0.42	13:38:45	0	0.00
15:20:00	0	0.00	8:36:00	0	0.42	13:39:00	0	0.00
15:20:15	0	0.00	8:36:15	0	0.00	13:39:15	0	0.00
15:20:30	0	0.00	8:36:30	0	0.00	13:39:30	0	0.00
15:20:45	0	0.00	8:36:45	0	0.00	13:39:45	0	0.00
15:21:00	0	0.00	8:37:00	0	0.00	13:40:00	0	0.00
15:21:15	0	0.00	8:37:15	0	0.00	13:40:15	0	0.00
15:21:30	0	0.00	8:37:30	0	0.00	13:40:30	0	0.00
15:21:45	0	0.00	8:37:45	0	0.00	13:40:45	0	0.00
15:22:00	0	0.00	8:38:00	0	0.00	13:41:00	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
15:22:15	0	0.00	8:38:15	0	0.00	13:41:15	0	0.00
15:22:30	0	0.00	8:38:30	0	0.00	13:41:30	0	0.00
15:22:45	0	0.00	8:38:45	0	0.00	13:41:45	0	0.00
15:23:00	0	0.00	8:39:00	0	0.00	13:42:00	0	0.00
15:23:15	0	0.00	8:39:15	0	0.00	13:42:15	0	0.00
15:23:30	0	0.00	8:39:30	0	0.00	13:42:30	0	0.00
15:23:45	0	0.00	8:39:45	0	0.00	13:42:45	0	0.00
15:24:00	0	0.00	8:40:00	0	0.00	13:43:00	0	0.00
15:24:15	0	0.00	8:40:15	0	0.00	13:43:15	0	0.00
15:24:30	0	0.00	8:40:30	0	0.00	13:43:30	0	0.00
15:24:45	0	0.00	8:40:45	0	0.00	13:43:45	0	0.00
15:25:00	0	0.00	8:41:00	0	0.00	13:44:00	0	0.00
15:25:15	0	0.00	8:41:15	0	0.00	13:44:15	0	0.00
15:25:30	0	0.00	8:41:30	0	0.00	13:44:30	0	0.00
15:25:45	0	0.00	8:41:45	0	0.00	13:44:45	0	0.00
15:26:00	0	0.00	8:42:00	0	0.00	13:45:00	0	0.00
15:26:15	0	0.00	8:42:15	0	0.00	13:45:15	0	0.00
15:26:30	0	0.00	8:42:30	0	0.00	13:45:30	0	0.00
15:26:45	0	0.00	8:42:45	0	0.00	13:45:45	0	0.00
15:27:00	0	0.00	8:43:00	0	0.00	13:46:00	0	0.00
15:27:15	0	0.00	8:43:15	0	0.00	13:46:15	0	0.00
15:27:30	0	0.00	8:43:30	0	0.00	13:46:30	0	0.00
15:27:45	0	0.00	8:43:45	0	0.00	13:46:45	0	0.00
15:28:00	0	0.00	8:44:00	0	0.00	13:47:00	0	0.00
15:28:15	0	0.00	8:44:15	0	0.00	13:47:15	0	0.00
15:28:30	0	0.00	8:44:30	0	0.00	13:47:30	0	0.00
15:28:45	0	0.00	8:44:45	0	0.00	13:47:45	0	0.00
15:29:00	0	0.00	8:45:00	0	0.00	13:48:00	0	0.00
15:29:15	0	0.00	8:45:15	0	0.00	13:48:15	0	0.00
15:29:30	0	0.00	8:45:30	0	0.00	13:48:30	0	0.00
15:29:45	0	0.00	8:45:45	0	0.00	13:48:45	0	0.00
15:30:00	0	0.00	8:46:00	0	0.00	13:49:00	0	0.00
15:30:15	0	0.00	8:46:15	0	0.00	13:49:15	0	0.00
15:30:30	0	0.00	8:46:30	0	0.00	13:49:30	0	0.00
15:30:45	0	0.00	8:46:45	0	0.00	13:49:45	0	0.00
15:31:00	0	0.00	8:47:00	0	0.00	13:50:00	0	0.00
15:31:15	0	0.00	8:47:15	0	0.00	13:50:15	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
15:31:30	0	0.00	8:47:30	0	0.00	13:50:30	0	0.00
15:31:45	0	0.00	8:47:45	0	0.00	13:50:45	0	0.00
15:32:00	0	0.00	8:48:00	0	0.00	13:51:00	0	0.00
15:32:15	0	0.00	8:48:15	0	0.00	13:51:15	0	0.00
15:32:30	0	0.00	8:48:30	0	0.00	13:51:30	0	0.00
15:32:45	0	0.00	8:48:45	0	0.00	13:51:45	0	0.00
15:33:00	0	0.00	8:49:00	0	0.00	13:52:00	0	0.00
15:33:15	0	0.00	8:49:15	0	0.00	13:52:15	0	0.00
15:33:30	0	0.00	8:49:30	0	0.00	13:52:30	0	0.00
15:33:45	0	0.00	8:49:45	0	0.00	13:52:45	0	0.00
15:34:00	0	0.00	8:50:00	0	0.00	13:53:00	0	0.00
15:34:15	0	0.00	8:50:15	0	0.00	13:53:15	0	0.00
15:34:30	0	0.00	8:50:30	0	0.00	13:53:30	0	0.00
15:34:45	0	0.00	8:50:45	0	0.00	13:53:45	0	0.00
15:35:00	0	0.00	8:51:00	0	0.00	13:54:00	0	0.00
15:35:15	0	0.00	8:51:15	0	0.00	13:54:15	0	0.00
15:35:30	0	0.00	8:51:30	0	0.00	13:54:30	0	0.00
15:35:45	0	0.00	8:51:45	0	0.00	13:54:45	0	0.00
15:36:00	0	0.00	8:52:00	0	0.00	13:55:00	0	0.00
15:36:15	0	0.00	8:52:15	0	0.00	13:55:15	0	0.00
15:36:30	0	0.00	8:52:30	0	0.00	13:55:30	0	0.00
15:36:45	0	0.00	8:52:45	0	0.00	13:55:45	0	0.00
15:37:00	0	0.00	8:53:00	0	0.00	13:56:00	0	0.00
15:37:15	0	0.00	8:53:15	0	0.00	13:56:15	0	0.00
15:37:30	0	0.00	8:53:30	0	0.00	13:56:30	0	0.00
15:37:45	0	0.00	8:53:45	0	0.00	13:56:45	0	0.00
15:38:00	0	0.00	8:54:00	0	0.00	13:57:00	0	0.00
15:38:15	0	0.00	8:54:15	0	0.00	13:57:15	0	0.00
15:38:30	0	0.00	8:54:30	0	0.00	13:57:30	0	0.00
15:38:45	0	0.00	8:54:45	0	0.00	13:57:45	0	0.00
15:39:00	0	0.00	8:55:00	0	0.00	13:58:00	0	0.00
15:39:15	0	0.00	8:55:15	0	0.00	13:58:15	0	0.00
15:39:30	0	0.00	8:55:30	0	0.00	13:58:30	0	0.00
15:39:45	0	0.00	8:55:45	0	0.00	13:58:45	0	0.00
15:40:00	0	0.00	8:56:00	0	0.00	13:59:00	0	0.00
15:40:15	0	0.00	8:56:15	0	0.00	13:59:15	0	0.00
15:40:30	0	0.00	8:56:30	0	0.00	13:59:30	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
15:40:45	0	0.00	8:56:45	0	0.00	13:59:45	0	0.00
15:41:00	0	0.00	8:57:00	0	0.00	14:00:00	0	0.00
15:41:15	0	0.00	8:57:15	0	0.00	14:00:15	0	0.00
15:41:30	0	0.00	8:57:30	0	0.00	14:00:30	20	0.83
15:41:45	0	0.00	8:57:45	0	0.00	14:00:45	0	0.83
15:42:00	0	0.00	8:58:00	0	0.00	14:01:00	0	0.83
15:42:15	0	0.00	8:58:15	0	0.00	14:01:15	0	0.83
15:42:30	0	0.00	8:58:30	0	0.00	14:01:30	0	0.83
15:42:45	0	0.00	8:58:45	0	0.00	14:01:45	10	1.25
15:43:00	0	0.00	8:59:00	0	0.00	14:02:00	0	1.25
15:43:15	0	0.00	8:59:15	0	0.00	14:02:15	0	1.25
15:43:30	0	0.00	8:59:30	0	0.00	14:02:30	0	1.25
15:43:45	0	0.00	8:59:45	0	0.00	14:02:45	0	1.25
15:44:00	0	0.00	9:00:00	0	0.00	14:03:00	0	1.25
15:44:15	0	0.00	9:00:15	0	0.00	14:03:15	0	1.25
15:44:30	0	0.00	9:00:30	0	0.00	14:03:30	0	1.25
15:44:45	0	0.00	9:00:45	0	0.00	14:03:45	0	1.25
15:45:00	0	0.00	9:01:00	0	0.00	14:04:00	0	1.25
15:45:15	0	0.00	9:01:15	0	0.00	14:04:15	0	1.25
15:45:30	0	0.00	9:01:30	0	0.00	14:04:30	0	1.25
15:45:45	0	0.00	9:01:45	0	0.00	14:04:45	0	1.25
15:46:00	0	0.00	9:02:00	0	0.00	14:05:00	0	1.25
15:46:15	0	0.00	9:02:15	0	0.00	14:05:15	0	1.25
15:46:30	0	0.00	9:02:30	0	0.00	14:05:30	0	1.25
15:46:45	0	0.00	9:02:45	0	0.00	14:05:45	0	1.25
15:47:00	0	0.00	9:03:00	0	0.00	14:06:00	0	1.25
15:47:15	0	0.00	9:03:15	0	0.00	14:06:15	0	1.25
15:47:30	0	0.00	9:03:30	0	0.00	14:06:30	0	0.42
15:47:45	0	0.00	9:03:45	0	0.00	14:06:45	0	0.42
15:48:00	0	0.00	9:04:00	0	0.00	14:07:00	0	0.42
15:48:15	0	0.00	9:04:15	0	0.00	14:07:15	0	0.42
15:48:30	0	0.00	9:04:30	0	0.00	14:07:30	0	0.42
15:48:45	0	0.00	9:04:45	0	0.00	14:07:45	0	0.00
15:49:00	0	0.00	9:05:00	0	0.00	14:08:00	0	0.00
15:49:15	0	0.00	9:05:15	0	0.00	14:08:15	0	0.00
15:49:30	0	0.00	9:05:30	0	0.00	14:08:30	15	0.63
15:49:45	0	0.00	9:05:45	0	0.00	14:08:45	0	0.63

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
15:50:00	0	0.00	9:06:00	0	0.00	14:09:00	0	0.63
15:50:15	0	0.00	9:06:15	0	0.00	14:09:15	0	0.63
15:50:30	0	0.00	9:06:30	0	0.00	14:09:30	0	0.63
15:50:45	0	0.00	9:06:45	0	0.00	14:09:45	0	0.63
15:51:00	0	0.00	9:07:00	0	0.00	14:10:00	0	0.63
15:51:15	0	0.00	9:07:15	0	0.00	14:10:15	0	0.63
15:51:30	0	0.00	9:07:30	0	0.00	14:10:30	0	0.63
15:51:45	0	0.00	9:07:45	0	0.00	14:10:45	0	0.63
15:52:00	0	0.00	9:08:00	0	0.00	14:11:00	0	0.63
15:52:15	0	0.00	9:08:15	0	0.00	14:11:15	0	0.63
15:52:30	0	0.00	9:08:30	0	0.00	14:11:30	0	0.63
15:52:45	0	0.00	9:08:45	0	0.00	14:11:45	0	0.63
15:53:00	0	0.00	9:09:00	0	0.00	14:12:00	0	0.63
15:53:15	0	0.00	9:09:15	0	0.00	14:12:15	0	0.63
15:53:30	0	0.00	9:09:30	0	0.00	14:12:30	0	0.63
15:53:45	0	0.00	9:09:45	0	0.00	14:12:45	0	0.63
15:54:00	0	0.00	9:10:00	0	0.00	14:13:00	0	0.63
15:54:15	0	0.00	9:10:15	0	0.00	14:13:15	15	1.25
15:54:30	0	0.00	9:10:30	0	0.00	14:13:30	0	1.25
15:54:45	0	0.00	9:10:45	0	0.00	14:13:45	0	1.25
15:55:00	0	0.00	9:11:00	0	0.00	14:14:00	0	1.25
15:55:15	0	0.00	9:11:15	0	0.00	14:14:15	0	1.25
15:55:30	0	0.00	9:11:30	0	0.00	14:14:30	0	0.63
15:55:45	0	0.00	9:11:45	0	0.00	14:14:45	0	0.63
15:56:00	0	0.00	9:12:00	0	0.00	14:15:00	0	0.63
15:56:15	0	0.00	9:12:15	0	0.00	14:15:15	0	0.63
15:56:30	0	0.00	9:12:30	0	0.00	14:15:30	0	0.63
15:56:45	0	0.00	9:12:45	0	0.00	14:15:45	0	0.63
15:57:00	0	0.00	9:13:00	0	0.00	14:16:00	0	0.63
15:57:15	0	0.00	9:13:15	0	0.00	14:16:15	0	0.63
15:57:30	0	0.00	9:13:30	0	0.00	14:16:30	10	1.04
15:57:45	0	0.00	9:13:45	0	0.00	14:16:45	0	1.04
15:58:00	0	0.00	9:14:00	0	0.00	14:17:00	0	1.04
15:58:15	0	0.00	9:14:15	0	0.00	14:17:15	0	1.04
15:58:30	0	0.00	9:14:30	0	0.00	14:17:30	0	1.04
15:58:45	0	0.00	9:14:45	0	0.00	14:17:45	0	1.04
15:59:00	0	0.00	9:15:00	0	0.00	14:18:00	0	1.04

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
15:59:15	0	0.00	9:15:15	0	0.00	14:18:15	0	1.04
15:59:30	0	0.00	9:15:30	0	0.00	14:18:30	0	1.04
15:59:45	0	0.00	9:15:45	0	0.00	14:18:45	0	1.04
16:00:00	0	0.00	9:16:00	0	0.00	14:19:00	0	1.04
16:00:15	0	0.00	9:16:15	0	0.00	14:19:15	0	0.42
16:00:30	0	0.00	9:16:30	0	0.00	14:19:30	0	0.42
16:00:45	0	0.00	9:16:45	0	0.00	14:19:45	0	0.42
16:01:00	0	0.00	9:17:00	0	0.00	14:20:00	0	0.42
16:01:15	0	0.00	9:17:15	0	0.00	14:20:15	0	0.42
16:01:30	0	0.00	9:17:30	0	0.00	14:20:30	0	0.42
16:01:45	0	0.00	9:17:45	0	0.00	14:20:45	0	0.42
16:02:00	0	0.00	9:18:00	0	0.00	14:21:00	0	0.42
16:02:15	0	0.00	9:18:15	0	0.00	14:21:15	0	0.42
16:02:30	0	0.00	9:18:30	0	0.00	14:21:30	0	0.42
16:02:45	0	0.00	9:18:45	0	0.00	14:21:45	0	0.42
16:03:00	0	0.00	9:19:00	0	0.00	14:22:00	0	0.42
16:03:15	0	0.00	9:19:15	0	0.00	14:22:15	0	0.42
16:03:30	0	0.00	9:19:30	0	0.00	14:22:30	0	0.00
16:03:45	0	0.00	9:19:45	0	0.00	14:22:45	0	0.00
16:04:00	0	0.00	9:20:00	0	0.00	14:23:00	0	0.00
16:04:15	0	0.00	9:20:15	0	0.00	14:23:15	0	0.00
16:04:30	0	0.00	9:20:30	0	0.00	14:23:30	0	0.00
16:04:45	0	0.00	9:20:45	0	0.00	14:23:45	0	0.00
16:05:00	0	0.00	9:21:00	0	0.00	14:24:00	0	0.00
16:05:15	0	0.00	9:21:15	0	0.00	14:24:15	0	0.00
16:05:30	0	0.00	9:21:30	0	0.00	14:24:30	0	0.00
16:05:45	0	0.00	9:21:45	0	0.00	14:24:45	0	0.00
16:06:00	0	0.00	9:22:00	5	0.21	14:25:00	0	0.00
16:06:15	0	0.00	9:22:15	0	0.21	14:25:15	0	0.00
16:06:30	0	0.00	9:22:30	0	0.21	14:25:30	0	0.00
16:06:45	0	0.00	9:22:45	0	0.21	14:25:45	0	0.00
16:07:00	0	0.00	9:23:00	0	0.21	14:26:00	0	0.00
16:07:15	0	0.00	9:23:15	0	0.21	14:26:15	0	0.00
16:07:30	0	0.00	9:23:30	0	0.21	14:26:30	0	0.00
16:07:45	0	0.00	9:23:45	0	0.21	14:26:45	0	0.00
16:08:00	0	0.00	9:24:00	0	0.21	14:27:00	0	0.00
16:08:15	0	0.00	9:24:15	10	0.63	14:27:15	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
16:08:30	0	0.00	9:24:30	0	0.63	14:27:30	0	0.00
16:08:45	0	0.00	9:24:45	0	0.63	14:27:45	0	0.00
16:09:00	0	0.00	9:25:00	0	0.63	14:28:00	0	0.00
16:09:15	0	0.00	9:25:15	0	0.63	14:28:15	0	0.00
16:09:30	0	0.00	9:25:30	0	0.63	14:28:30	0	0.00
16:09:45	0	0.00	9:25:45	0	0.63	14:28:45	0	0.00
16:10:00	0	0.00	9:26:00	0	0.63	14:29:00	0	0.00
16:10:15	0	0.00	9:26:15	0	0.63	14:29:15	0	0.00
16:10:30	0	0.00	9:26:30	0	0.63	14:29:30	0	0.00
16:10:45	0	0.00	9:26:45	0	0.63	14:29:45	0	0.00
16:11:00	0	0.00	9:27:00	0	0.63	14:30:00	0	0.00
16:11:15	0	0.00	9:27:15	0	0.63	14:30:15	0	0.00
16:11:30	0	0.00	9:27:30	0	0.63	14:30:30	0	0.00
16:11:45	0	0.00	9:27:45	0	0.63	14:30:45	0	0.00
16:12:00	0	0.00	9:28:00	0	0.42	14:31:00	0	0.00
16:12:15	0	0.00	9:28:15	0	0.42	14:31:15	0	0.00
16:12:30	0	0.00	9:28:30	0	0.42	14:31:30	0	0.00
16:12:45	0	0.00	9:28:45	0	0.42	14:31:45	0	0.00
16:13:00	0	0.00	9:29:00	0	0.42	14:32:00	0	0.00
16:13:15	0	0.00	9:29:15	0	0.42	14:32:15	0	0.00
16:13:30	0	0.00	9:29:30	0	0.42	14:32:30	0	0.00
16:13:45	0	0.00	9:29:45	0	0.42	14:32:45	0	0.00
16:14:00	0	0.00	9:30:00	0	0.42	14:33:00	0	0.00
16:14:15	0	0.00	9:30:15	0	0.00	14:33:15	0	0.00
16:14:30	0	0.00	9:30:30	0	0.00	14:33:30	0	0.00
16:14:45	0	0.00	9:30:45	0	0.00	14:33:45	15	0.63
16:15:00	0	0.00	9:31:00	0	0.00	14:34:00	0	0.63
16:15:15	0	0.00	9:31:15	0	0.00	14:34:15	0	0.63
16:15:30	0	0.00	9:31:30	0	0.00	14:34:30	0	0.63
16:15:45	20	0.83	9:31:45	0	0.00	14:34:45	0	0.63
16:16:00	0	0.83	9:32:00	0	0.00	14:35:00	0	0.63
16:16:15	0	0.83	9:32:15	0	0.00	14:35:15	0	0.63
16:16:30	0	0.83	9:32:30	15	0.63	14:35:30	0	0.63
16:16:45	10	1.25	9:32:45	0	0.63	14:35:45	0	0.63
16:17:00	0	1.25	9:33:00	0	0.63	14:36:00	0	0.63
16:17:15	0	1.25	9:33:15	0	0.63	14:36:15	0	0.63
16:17:30	0	1.25	9:33:30	0	0.63	14:36:30	0	0.63

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
16:17:45	0	1.25	9:33:45	0	0.63	14:36:45	0	0.63
16:18:00	0	1.25	9:34:00	0	0.63	14:37:00	0	0.63
16:18:15	0	1.25	9:34:15	0	0.63	14:37:15	0	0.63
16:18:30	0	1.25	9:34:30	0	0.63	14:37:30	0	0.63
16:18:45	0	1.25	9:34:45	0	0.63	14:37:45	0	0.63
16:19:00	0	1.25	9:35:00	0	0.63	14:38:00	0	0.63
16:19:15	0	1.25	9:35:15	0	0.63	14:38:15	0	0.63
16:19:30	0	1.25	9:35:30	0	0.63	14:38:30	0	0.63
16:19:45	0	1.25	9:35:45	0	0.63	14:38:45	0	0.63
16:20:00	0	1.25	9:36:00	0	0.63	14:39:00	0	0.63
16:20:15	0	1.25	9:36:15	0	0.63	14:39:15	0	0.63
16:20:30	0	1.25	9:36:30	0	0.63	14:39:30	0	0.63
16:20:45	0	1.25	9:36:45	0	0.63	14:39:45	0	0.00
16:21:00	0	1.25	9:37:00	0	0.63	14:40:00	0	0.00
16:21:15	0	1.25	9:37:15	0	0.63	14:40:15	0	0.00
16:21:30	0	1.25	9:37:30	0	0.63	14:40:30	0	0.00
16:21:45	0	0.42	9:37:45	0	0.63	14:40:45	0	0.00
16:22:00	0	0.42	9:38:00	0	0.63	14:41:00	0	0.00
16:22:15	0	0.42	9:38:15	0	0.63	14:41:15	0	0.00
16:22:30	0	0.42	9:38:30	0	0.00	14:41:30	0	0.00
16:22:45	0	0.00	9:38:45	0	0.00	14:41:45	0	0.00
16:23:00	0	0.00	9:39:00	0	0.00	14:42:00	0	0.00
16:23:15	0	0.00	9:39:15	0	0.00	14:42:15	0	0.00
16:23:30	0	0.00	9:39:30	0	0.00	14:42:30	0	0.00
16:23:45	0	0.00	9:39:45	0	0.00	14:42:45	0	0.00
16:24:00	0	0.00	9:40:00	0	0.00	14:43:00	0	0.00
16:24:15	0	0.00	9:40:15	0	0.00	14:43:15	0	0.00
16:24:30	0	0.00	9:40:30	0	0.00	14:43:30	0	0.00
16:24:45	0	0.00	9:40:45	0	0.00	14:43:45	0	0.00
16:25:00	0	0.00	9:41:00	0	0.00	14:44:00	0	0.00
16:25:15	0	0.00	9:41:15	0	0.00	14:44:15	0	0.00
16:25:30	0	0.00	9:41:30	0	0.00	14:44:30	0	0.00
16:25:45	0	0.00	9:41:45	0	0.00	14:44:45	0	0.00
16:26:00	0	0.00	9:42:00	0	0.00	14:45:00	0	0.00
16:26:15	0	0.00	9:42:15	0	0.00	14:45:15	0	0.00
16:26:30	0	0.00	9:42:30	0	0.00	14:45:30	0	0.00
16:26:45	0	0.00	9:42:45	0	0.00	14:45:45	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
16:27:00	0	0.00	9:43:00	0	0.00	14:46:00	0	0.00
16:27:15	0	0.00	9:43:15	0	0.00	14:46:15	0	0.00
16:27:30	0	0.00	9:43:30	0	0.00	14:46:30	0	0.00
16:27:45	0	0.00	9:43:45	0	0.00	14:46:45	0	0.00
16:28:00	0	0.00	9:44:00	10	0.42	14:47:00	0	0.00
16:28:15	15	0.63	9:44:15	0	0.42	14:47:15	0	0.00
16:28:30	0	0.63	9:44:30	0	0.42	14:47:30	0	0.00
16:28:45	0	0.63	9:44:45	0	0.42	14:47:45	0	0.00
16:29:00	0	0.63	9:45:00	0	0.42	14:48:00	0	0.00
16:29:15	0	0.63	9:45:15	0	0.42	14:48:15	0	0.00
16:29:30	10	1.04	9:45:30	0	0.42	14:48:30	0	0.00
16:29:45	0	1.04	9:45:45	0	0.42	14:48:45	0	0.00
16:30:00	0	1.04	9:46:00	0	0.42	14:49:00	0	0.00
16:30:15	0	1.04	9:46:15	0	0.42	14:49:15	0	0.00
16:30:30	0	1.04	9:46:30	0	0.42	14:49:30	0	0.00
16:30:45	0	1.04	9:46:45	0	0.42	14:49:45	0	0.00
16:31:00	0	1.04	9:47:00	0	0.42	14:50:00	0	0.00
16:31:15	0	1.04	9:47:15	0	0.42	14:50:15	0	0.00
16:31:30	20	1.88	9:47:30	0	0.42	14:50:30	0	0.00
16:31:45	0	1.88	9:47:45	0	0.42	14:50:45	0	0.00
16:32:00	0	1.88	9:48:00	0	0.42	14:51:00	0	0.00
16:32:15	0	1.88	9:48:15	0	0.42	14:51:15	0	0.00
16:32:30	0	1.88	9:48:30	0	0.42	14:51:30	0	0.00
16:32:45	0	1.88	9:48:45	0	0.42	14:51:45	0	0.00
16:33:00	0	1.88	9:49:00	0	0.42	14:52:00	0	0.00
16:33:15	0	1.88	9:49:15	0	0.42	14:52:15	0	0.00
16:33:30	0	1.88	9:49:30	0	0.42	14:52:30	0	0.00
16:33:45	0	1.88	9:49:45	0	0.42	14:52:45	0	0.00
16:34:00	0	1.88	9:50:00	0	0.00	14:53:00	0	0.00
16:34:15	0	1.25	9:50:15	0	0.00	14:53:15	0	0.00
16:34:30	0	1.25	9:50:30	0	0.00	14:53:30	0	0.00
16:34:45	0	1.25	9:50:45	0	0.00	14:53:45	0	0.00
16:35:00	0	1.25	9:51:00	0	0.00	14:54:00	0	0.00
16:35:15	0	1.25	9:51:15	0	0.00	14:54:15	0	0.00
16:35:30	0	0.83	9:51:30	0	0.00	14:54:30	0	0.00
16:35:45	0	0.83	9:51:45	0	0.00	14:54:45	0	0.00
16:36:00	0	0.83	9:52:00	0	0.00	14:55:00	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
16:36:15	0	0.83	9:52:15	0	0.00	14:55:15	0	0.00
16:36:30	0	0.83	9:52:30	0	0.00	14:55:30	0	0.00
16:36:45	0	0.83	9:52:45	0	0.00	14:55:45	0	0.00
16:37:00	0	0.83	9:53:00	0	0.00	14:56:00	0	0.00
16:37:15	0	0.83	9:53:15	0	0.00	14:56:15	0	0.00
16:37:30	0	0.00	9:53:30	0	0.00	14:56:30	0	0.00
16:37:45	0	0.00	9:53:45	0	0.00	14:56:45	0	0.00
16:38:00	0	0.00	9:54:00	0	0.00	14:57:00	0	0.00
16:38:15	0	0.00	9:54:15	0	0.00	14:57:15	0	0.00
16:38:30	0	0.00	9:54:30	0	0.00	14:57:30	0	0.00
16:38:45	20	0.83	9:54:45	0	0.00	14:57:45	0	0.00
16:39:00	0	0.83	9:55:00	0	0.00	14:58:00	0	0.00
16:39:15	0	0.83	9:55:15	0	0.00	14:58:15	0	0.00
16:39:30	0	0.83	9:55:30	0	0.00	14:58:30	0	0.00
16:39:45	0	0.83	9:55:45	0	0.00	14:58:45	0	0.00
16:40:00	0	0.83	9:56:00	0	0.00	14:59:00	0	0.00
16:40:15	0	0.83	9:56:15	0	0.00	14:59:15	0	0.00
16:40:30	0	0.83	9:56:30	0	0.00	14:59:30	0	0.00
16:40:45	0	0.83	9:56:45	0	0.00	14:59:45	0	0.00
16:41:00	0	0.83	9:57:00	10	0.42	15:00:00	0	0.00
16:41:15	0	0.83	9:57:15	0	0.42	15:00:15	0	0.00
16:41:30	0	0.83	9:57:30	0	0.42	15:00:30	0	0.00
16:41:45	0	0.83	9:57:45	0	0.42	15:00:45	0	0.00
16:42:00	0	0.83	9:58:00	0	0.42	15:01:00	0	0.00
16:42:15	0	0.83	9:58:15	0	0.42	15:01:15	0	0.00
16:42:30	0	0.83	9:58:30	0	0.42	15:01:30	0	0.00
16:42:45	0	0.83	9:58:45	0	0.42	15:01:45	0	0.00
16:43:00	0	0.83	9:59:00	0	0.42	15:02:00	0	0.00
16:43:15	0	0.83	9:59:15	0	0.42	15:02:15	0	0.00
16:43:30	0	0.83	9:59:30	0	0.42	15:02:30	0	0.00
16:43:45	0	0.83	9:59:45	0	0.42	15:02:45	0	0.00
16:44:00	0	0.83	10:00:00	0	0.42	15:03:00	0	0.00
16:44:15	0	0.83	10:00:15	0	0.42	15:03:15	0	0.00
16:44:30	0	0.83	10:00:30	0	0.42	15:03:30	0	0.00
16:44:45	0	0.00	10:00:45	0	0.42	15:03:45	0	0.00
16:45:00	0	0.00	10:01:00	0	0.42	15:04:00	0	0.00
16:45:15	0	0.00	10:01:15	0	0.42	15:04:15	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
16:45:30	0	0.00	10:01:30	0	0.42	15:04:30	0	0.00
16:45:45	0	0.00	10:01:45	0	0.42	15:04:45	0	0.00
16:46:00	0	0.00	10:02:00	0	0.42	15:05:00	0	0.00
16:46:15	0	0.00	10:02:15	0	0.42	15:05:15	0	0.00
16:46:30	0	0.00	10:02:30	0	0.42	15:05:30	0	0.00
16:46:45	0	0.00	10:02:45	0	0.42	15:05:45	0	0.00
16:47:00	0	0.00	10:03:00	0	0.00	15:06:00	0	0.00
16:47:15	0	0.00	10:03:15	0	0.00	15:06:15	0	0.00
16:47:30	0	0.00	10:03:30	0	0.00	15:06:30	0	0.00
16:47:45	0	0.00	10:03:45	0	0.00	15:06:45	0	0.00
16:48:00	0	0.00	10:04:00	0	0.00	15:07:00	0	0.00
16:48:15	0	0.00	10:04:15	0	0.00	15:07:15	0	0.00
16:48:30	0	0.00	10:04:30	0	0.00	15:07:30	0	0.00
16:48:45	0	0.00	10:04:45	0	0.00	15:07:45	0	0.00
16:49:00	0	0.00	10:05:00	0	0.00	15:08:00	0	0.00
16:49:15	0	0.00	10:05:15	15	0.63	15:08:15	0	0.00
16:49:30	0	0.00	10:05:30	0	0.63	15:08:30	0	0.00
16:49:45	0	0.00	10:05:45	0	0.63	15:08:45	0	0.00
16:50:00	0	0.00	10:06:00	0	0.63	15:09:00	0	0.00
16:50:15	0	0.00	10:06:15	0	0.63	15:09:15	0	0.00
16:50:30	0	0.00	10:06:30	0	0.63	15:09:30	0	0.00
16:50:45	0	0.00	10:06:45	0	0.63	15:09:45	0	0.00
16:51:00	0	0.00	10:07:00	0	0.63	15:10:00	0	0.00
16:51:15	10	0.42	10:07:15	0	0.63	15:10:15	0	0.00
16:51:30	0	0.42	10:07:30	0	0.63	15:10:30	0	0.00
16:51:45	0	0.42	10:07:45	0	0.63	15:10:45	0	0.00
16:52:00	0	0.42	10:08:00	0	0.63	15:11:00	0	0.00
16:52:15	0	0.42	10:08:15	0	0.63	15:11:15	0	0.00
16:52:30	25	1.46	10:08:30	0	0.63	15:11:30	0	0.00
16:52:45	0	1.46	10:08:45	0	0.63	15:11:45	0	0.00
16:53:00	0	1.46	10:09:00	0	0.63	15:12:00	0	0.00
16:53:15	0	1.46	10:09:15	0	0.63	15:12:15	0	0.00
16:53:30	0	1.46	10:09:30	0	0.63	15:12:30	0	0.00
16:53:45	0	1.46	10:09:45	0	0.63	15:12:45	0	0.00
16:54:00	0	1.46	10:10:00	0	0.63	15:13:00	0	0.00
16:54:15	0	1.46	10:10:15	0	0.63	15:13:15	0	0.00
16:54:30	0	1.46	10:10:30	0	0.63	15:13:30	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
16:54:45	0	1.46	10:10:45	0	0.63	15:13:45	0	0.00
16:55:00	0	1.46	10:11:00	0	0.63	15:14:00	0	0.00
16:55:15	0	1.46	10:11:15	0	0.00	15:14:15	0	0.00
16:55:30	0	1.46	10:11:30	0	0.00	15:14:30	0	0.00
16:55:45	0	1.46	10:11:45	0	0.00	15:14:45	0	0.00
16:56:00	0	1.46	10:12:00	15	0.63	15:15:00	0	0.00
16:56:15	0	1.46	10:12:15	0	0.63	15:15:15	0	0.00
16:56:30	0	1.46	10:12:30	0	0.63	15:15:30	0	0.00
16:56:45	20	2.29	10:12:45	0	0.63	15:15:45	0	0.00
16:57:00	0	2.29	10:13:00	0	0.63	15:16:00	0	0.00
16:57:15	0	1.88	10:13:15	10	1.04	15:16:15	0	0.00
16:57:30	0	1.88	10:13:30	0	1.04	15:16:30	0	0.00
16:57:45	0	1.88	10:13:45	0	1.04	15:16:45	0	0.00
16:58:00	0	1.88	10:14:00	0	1.04	15:17:00	0	0.00
16:58:15	0	1.88	10:14:15	0	1.04	15:17:15	0	0.00
16:58:30	0	0.83	10:14:30	0	1.04	15:17:30	0	0.00
16:58:45	0	0.83	10:14:45	0	1.04	15:17:45	0	0.00
16:59:00	0	0.83	10:15:00	0	1.04	15:18:00	0	0.00
16:59:15	0	0.83	10:15:15	0	1.04	15:18:15	0	0.00
16:59:30	0	0.83	10:15:30	0	1.04	15:18:30	0	0.00
16:59:45	0	0.83	10:15:45	0	1.04	15:18:45	0	0.00
17:00:00	0	0.83	10:16:00	0	1.04	15:19:00	0	0.00
17:00:15	0	0.83	10:16:15	0	1.04	15:19:15	0	0.00
17:00:30	0	0.83	10:16:30	0	1.04	15:19:30	0	0.00
17:00:45	0	0.83	10:16:45	10	1.46	15:19:45	0	0.00
17:01:00	0	0.83	10:17:00	0	1.46	15:20:00	0	0.00
17:01:15	0	0.83	10:17:15	0	1.46	15:20:15	0	0.00
17:01:30	0	0.83	10:17:30	0	1.46	15:20:30	0	0.00
17:01:45	0	0.83	10:17:45	0	1.46	15:20:45	0	0.00
17:02:00	0	0.83	10:18:00	15	1.46	15:21:00	0	0.00
17:02:15	0	0.83	10:18:15	0	1.46	15:21:15	0	0.00
17:02:30	0	0.83	10:18:30	0	1.46	15:21:30	0	0.00
17:02:45	0	0.00	10:18:45	0	1.46	15:21:45	0	0.00
17:03:00	0	0.00	10:19:00	0	1.46	15:22:00	0	0.00
17:03:15	0	0.00	10:19:15	0	1.04	15:22:15	0	0.00
17:03:30	0	0.00	10:19:30	0	1.04	15:22:30	0	0.00
17:03:45	0	0.00	10:19:45	0	1.04	15:22:45	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
17:04:00	0	0.00	10:20:00	0	1.04	15:23:00	0	0.00
17:04:15	0	0.00	10:20:15	10	1.46	15:23:15	0	0.00
17:04:30	0	0.00	10:20:30	0	1.46	15:23:30	0	0.00
17:04:45	0	0.00	10:20:45	0	1.46	15:23:45	0	0.00
17:05:00	0	0.00	10:21:00	0	1.46	15:24:00	0	0.00
17:05:15	0	0.00	10:21:15	0	1.46	15:24:15	0	0.00
17:05:30	0	0.00	10:21:30	0	1.46	15:24:30	0	0.00
17:05:45	0	0.00	10:21:45	0	1.46	15:24:45	0	0.00
17:06:00	0	0.00	10:22:00	0	1.46	15:25:00	0	0.00
17:06:15	0	0.00	10:22:15	15	2.08	15:25:15	0	0.00
17:06:30	0	0.00	10:22:30	0	2.08	15:25:30	0	0.00
17:06:45	0	0.00	10:22:45	0	1.67	15:25:45	0	0.00
17:07:00	0	0.00	10:23:00	0	1.67	15:26:00	0	0.00
17:07:15	0	0.00	10:23:15	0	1.67	15:26:15	0	0.00
17:07:30	0	0.00	10:23:30	0	1.67	15:26:30	0	0.00
17:07:45	0	0.00	10:23:45	0	1.67	15:26:45	0	0.00
17:08:00	0	0.00	10:24:00	0	1.04	15:27:00	0	0.00
17:08:15	0	0.00	10:24:15	0	1.04	15:27:15	0	0.00
17:08:30	20	0.83	10:24:30	0	1.04	15:27:30	0	0.00
17:08:45	0	0.83	10:24:45	0	1.04	15:27:45	0	0.00
17:09:00	0	0.83	10:25:00	0	1.04	15:28:00	0	0.00
17:09:15	0	0.83	10:25:15	0	1.04	15:28:15	0	0.00
17:09:30	0	0.83	10:25:30	0	1.04	15:28:30	0	0.00
17:09:45	0	0.83	10:25:45	0	1.04	15:28:45	0	0.00
17:10:00	0	0.83	10:26:00	0	1.04	15:29:00	0	0.00
17:10:15	0	0.83	10:26:15	0	0.63	15:29:15	0	0.00
17:10:30	0	0.83	10:26:30	0	0.63	15:29:30	0	0.00
17:10:45	0	0.83	10:26:45	0	0.63	15:29:45	0	0.00
17:11:00	0	0.83	10:27:00	15	1.25	15:30:00	0	0.00
17:11:15	0	0.83	10:27:15	0	1.25	15:30:15	0	0.00
17:11:30	0	0.83	10:27:30	0	1.25	15:30:30	0	0.00
17:11:45	0	0.83	10:27:45	0	1.25	15:30:45	0	0.00
17:12:00	0	0.83	10:28:00	0	1.25	15:31:00	0	0.00
17:12:15	0	0.83	10:28:15	15	1.25	15:31:15	0	0.00
17:12:30	0	0.83	10:28:30	0	1.25	15:31:30	0	0.00
17:12:45	0	0.83	10:28:45	0	1.25	15:31:45	0	0.00
17:13:00	0	0.83	10:29:00	0	1.25	15:32:00	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
17:13:15	0	0.83	10:29:15	0	1.25	15:32:15	0	0.00
17:13:30	0	0.83	10:29:30	0	1.25	15:32:30	0	0.00
17:13:45	0	0.83	10:29:45	0	1.25	15:32:45	0	0.00
17:14:00	0	0.83	10:30:00	0	1.25	15:33:00	0	0.00
17:14:15	0	0.83	10:30:15	0	1.25	15:33:15	0	0.00
17:14:30	25	1.04	10:30:30	0	1.25	15:33:30	0	0.00
17:14:45	0	1.04	10:30:45	0	1.25	15:33:45	0	0.00
17:15:00	0	1.04	10:31:00	0	1.25	15:34:00	0	0.00
17:15:15	0	1.04	10:31:15	0	1.25	15:34:15	0	0.00
17:15:30	20	1.88	10:31:30	0	1.25	15:34:30	0	0.00
17:15:45	0	1.88	10:31:45	0	1.25	15:34:45	0	0.00
17:16:00	0	1.88	10:32:00	0	1.25	15:35:00	0	0.00
17:16:15	0	1.88	10:32:15	0	1.25	15:35:15	0	0.00
17:16:30	0	1.88	10:32:30	0	1.25	15:35:30	0	0.00
17:16:45	0	1.88	10:32:45	0	1.25	15:35:45	0	0.00
17:17:00	0	1.88	10:33:00	0	0.63	15:36:00	0	0.00
17:17:15	0	1.88	10:33:15	0	0.63	15:36:15	0	0.00
17:17:30	0	1.88	10:33:30	0	0.63	15:36:30	0	0.00
17:17:45	0	1.88	10:33:45	0	0.63	15:36:45	0	0.00
17:18:00	0	1.88	10:34:00	0	0.63	15:37:00	0	0.00
17:18:15	0	1.88	10:34:15	0	0.00	15:37:15	0	0.00
17:18:30	0	1.88	10:34:30	0	0.00	15:37:30	0	0.00
17:18:45	0	1.88	10:34:45	0	0.00	15:37:45	0	0.00
17:19:00	0	1.88	10:35:00	15	0.63	15:38:00	0	0.00
17:19:15	0	1.88	10:35:15	0	0.63	15:38:15	0	0.00
17:19:30	0	1.88	10:35:30	0	0.63	15:38:30	0	0.00
17:19:45	0	1.88	10:35:45	0	0.63	15:38:45	0	0.00
17:20:00	0	1.88	10:36:00	0	0.63	15:39:00	0	0.00
17:20:15	0	1.88	10:36:15	10	1.04	15:39:15	0	0.00
17:20:30	0	0.83	10:36:30	0	1.04	15:39:30	0	0.00
17:20:45	0	0.83	10:36:45	0	1.04	15:39:45	0	0.00
17:21:00	0	0.83	10:37:00	0	1.04	15:40:00	0	0.00
17:21:15	0	0.83	10:37:15	0	1.04	15:40:15	0	0.00
17:21:30	0	0.00	10:37:30	0	1.04	15:40:30	0	0.00
17:21:45	0	0.00	10:37:45	0	1.04	15:40:45	0	0.00
17:22:00	0	0.00	10:38:00	0	1.04	15:41:00	0	0.00
17:22:15	0	0.00	10:38:15	0	1.04	15:41:15	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
17:22:30	0	0.00	10:38:30	0	1.04	15:41:30	0	0.00
17:22:45	0	0.00	10:38:45	0	1.04	15:41:45	25	1.04
17:23:00	0	0.00	10:39:00	5	1.25	15:42:00	0	1.04
17:23:15	0	0.00	10:39:15	0	1.25	15:42:15	0	1.04
17:23:30	0	0.00	10:39:30	0	1.25	15:42:30	0	1.04
17:23:45	0	0.00	10:39:45	0	1.25	15:42:45	0	1.04
17:24:00	0	0.00	10:40:00	10	1.67	15:43:00	0	1.04
17:24:15	0	0.00	10:40:15	0	1.67	15:43:15	0	1.04
17:24:30	0	0.00	10:40:30	0	1.67	15:43:30	0	1.04
17:24:45	0	0.00	10:40:45	0	1.67	15:43:45	0	1.04
17:25:00	0	0.00	10:41:00	10	1.46	15:44:00	0	1.04
17:25:15	0	0.00	10:41:15	0	1.46	15:44:15	0	1.04
17:25:30	0	0.00	10:41:30	0	1.46	15:44:30	0	1.04
17:25:45	0	0.00	10:41:45	0	1.46	15:44:45	0	1.04
17:26:00	0	0.00	10:42:00	0	1.46	15:45:00	0	1.04
17:26:15	0	0.00	10:42:15	0	1.04	15:45:15	0	1.04
17:26:30	0	0.00	10:42:30	0	1.04	15:45:30	0	1.04
17:26:45	0	0.00	10:42:45	0	1.04	15:45:45	0	1.04
17:27:00	0	0.00	10:43:00	0	1.04	15:46:00	0	1.04
17:27:15	0	0.00	10:43:15	10	1.46	15:46:15	0	1.04
17:27:30	0	0.00	10:43:30	0	1.46	15:46:30	0	1.04
17:27:45	0	0.00	10:43:45	0	1.46	15:46:45	0	1.04
17:28:00	0	0.00	10:44:00	0	1.46	15:47:00	0	1.04
17:28:15	0	0.00	10:44:15	0	1.46	15:47:15	0	1.04
17:28:30	0	0.00	10:44:30	0	1.46	15:47:30	0	1.04
17:28:45	0	0.00	10:44:45	0	1.46	15:47:45	0	0.00
17:29:00	0	0.00	10:45:00	0	1.25	15:48:00	0	0.00
17:29:15	0	0.00	10:45:15	0	1.25	15:48:15	0	0.00
17:29:30	0	0.00	10:45:30	15	1.88	15:48:30	0	0.00
17:29:45	0	0.00	10:45:45	0	1.88	15:48:45	0	0.00
17:30:00	0	0.00	10:46:00	0	1.46	15:49:00	0	0.00
17:30:15	0	0.00	10:46:15	0	1.46	15:49:15	0	0.00
17:30:30	0	0.00	10:46:30	0	1.46	15:49:30	0	0.00
17:30:45	0	0.00	10:46:45	0	1.46	15:49:45	0	0.00
17:31:00	0	0.00	10:47:00	0	1.04	15:50:00	0	0.00
17:31:15	0	0.00	10:47:15	0	1.04	15:50:15	0	0.00
17:31:30	0	0.00	10:47:30	0	1.04	15:50:30	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
17:31:45	0	0.00	10:47:45	0	1.04	15:50:45	0	0.00
17:32:00	0	0.00	10:48:00	0	1.04	15:51:00	0	0.00
17:32:15	0	0.00	10:48:15	0	1.04	15:51:15	0	0.00
17:32:30	0	0.00	10:48:30	0	1.04	15:51:30	0	0.00
17:32:45	0	0.00	10:48:45	0	1.04	15:51:45	0	0.00
17:33:00	0	0.00	10:49:00	0	1.04	15:52:00	0	0.00
17:33:15	0	0.00	10:49:15	0	0.63	15:52:15	0	0.00
17:33:30	0	0.00	10:49:30	0	0.63	15:52:30	0	0.00
17:33:45	0	0.00	10:49:45	0	0.63	15:52:45	0	0.00
17:34:00	0	0.00	10:50:00	15	1.25	15:53:00	0	0.00
17:34:15	0	0.00	10:50:15	0	1.25	15:53:15	0	0.00
17:34:30	0	0.00	10:50:30	0	1.25	15:53:30	0	0.00
17:34:45	0	0.00	10:50:45	0	1.25	15:53:45	0	0.00
17:35:00	0	0.00	10:51:00	0	1.25	15:54:00	0	0.00
17:35:15	0	0.00	10:51:15	10	1.67	15:54:15	0	0.00
17:35:30	0	0.00	10:51:30	0	1.04	15:54:30	0	0.00
17:35:45	0	0.00	10:51:45	0	1.04	15:54:45	0	0.00
17:36:00	0	0.00	10:52:00	0	1.04	15:55:00	0	0.00
17:36:15	0	0.00	10:52:15	0	1.04	15:55:15	0	0.00
17:36:30	0	0.00	10:52:30	0	1.04	15:55:30	0	0.00
17:36:45	0	0.00	10:52:45	0	1.04	15:55:45	0	0.00
17:37:00	0	0.00	10:53:00	0	1.04	15:56:00	0	0.00
17:37:15	0	0.00	10:53:15	0	1.04	15:56:15	0	0.00
17:37:30	0	0.00	10:53:30	0	1.04	15:56:30	0	0.00
17:37:45	0	0.00	10:53:45	0	1.04	15:56:45	0	0.00
17:38:00	0	0.00	10:54:00	0	1.04	15:57:00	0	0.00
17:38:15	0	0.00	10:54:15	0	1.04	15:57:15	0	0.00
17:38:30	0	0.00	10:54:30	0	1.04	15:57:30	0	0.00
17:38:45	0	0.00	10:54:45	0	1.04	15:57:45	0	0.00
17:39:00	0	0.00	10:55:00	0	1.04	15:58:00	0	0.00
17:39:15	0	0.00	10:55:15	0	1.04	15:58:15	0	0.00
17:39:30	0	0.00	10:55:30	0	1.04	15:58:30	0	0.00
17:39:45	0	0.00	10:55:45	0	1.04	15:58:45	0	0.00
17:40:00	0	0.00	10:56:00	0	0.42	15:59:00	0	0.00
17:40:15	0	0.00	10:56:15	0	0.42	15:59:15	0	0.00
17:40:30	0	0.00	10:56:30	0	0.42	15:59:30	0	0.00
17:40:45	0	0.00	10:56:45	0	0.42	15:59:45	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
17:41:00	0	0.00	10:57:00	0	0.42	16:00:00	0	0.00
17:41:15	0	0.00	10:57:15	0	0.00	16:00:15	0	0.00
17:41:30	0	0.00	10:57:30	0	0.00	16:00:30	0	0.00
17:41:45	0	0.00	10:57:45	0	0.00	16:00:45	0	0.00
17:42:00	0	0.00	10:58:00	0	0.00	16:01:00	0	0.00
17:42:15	0	0.00	10:58:15	0	0.00	16:01:15	0	0.00
17:42:30	0	0.00	10:58:30	0	0.00	16:01:30	0	0.00
17:42:45	0	0.00	10:58:45	0	0.00	16:01:45	0	0.00
17:43:00	0	0.00	10:59:00	0	0.00	16:02:00	0	0.00
17:43:15	0	0.00	10:59:15	0	0.00	16:02:15	0	0.00
17:43:30	0	0.00	10:59:30	0	0.00	16:02:30	0	0.00
17:43:45	0	0.00	10:59:45	0	0.00	16:02:45	0	0.00
17:44:00	0	0.00	11:00:00	0	0.00	16:03:00	0	0.00
17:44:15	0	0.00	11:00:15	0	0.00	16:03:15	0	0.00
17:44:30	0	0.00	11:00:30	0	0.00	16:03:30	0	0.00
17:44:45	0	0.00	11:00:45	0	0.00	16:03:45	0	0.00
17:45:00	0	0.00	11:01:00	0	0.00	16:04:00	0	0.00
17:45:15	0	0.00	11:01:15	0	0.00	16:04:15	0	0.00
17:45:30	0	0.00	11:01:30	0	0.00	16:04:30	0	0.00
17:45:45	0	0.00	11:01:45	0	0.00	16:04:45	0	0.00
17:46:00	0	0.00	11:02:00	0	0.00	16:05:00	0	0.00
17:46:15	0	0.00	11:02:15	0	0.00	16:05:15	0	0.00
17:46:30	0	0.00	11:02:30	0	0.00	16:05:30	0	0.00
17:46:45	0	0.00	11:02:45	0	0.00	16:05:45	0	0.00
17:47:00	0	0.00	11:03:00	0	0.00	16:06:00	0	0.00
17:47:15	0	0.00	11:03:15	0	0.00	16:06:15	0	0.00
17:47:30	0	0.00	11:03:30	0	0.00	16:06:30	0	0.00
17:47:45	0	0.00	11:03:45	0	0.00	16:06:45	0	0.00
17:48:00	0	0.00	11:04:00	0	0.00	16:07:00	0	0.00
17:48:15	0	0.00	11:04:15	0	0.00	16:07:15	0	0.00
17:48:30	0	0.00	11:04:30	0	0.00	16:07:30	0	0.00
17:48:45	0	0.00	11:04:45	0	0.00	16:07:45	0	0.00
17:49:00	0	0.00	11:05:00	0	0.00	16:08:00	0	0.00
17:49:15	0	0.00	11:05:15	0	0.00	16:08:15	0	0.00
17:49:30	0	0.00	11:05:30	0	0.00	16:08:30	0	0.00
17:49:45	0	0.00	11:05:45	0	0.00	16:08:45	0	0.00
17:50:00	0	0.00	11:06:00	0	0.00	16:09:00	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
17:50:15	0	0.00	11:06:15	0	0.00	16:09:15	0	0.00
17:50:30	0	0.00	11:06:30	0	0.00	16:09:30	0	0.00
17:50:45	0	0.00	11:06:45	0	0.00	16:09:45	0	0.00
17:51:00	0	0.00	11:07:00	0	0.00	16:10:00	0	0.00
17:51:15	0	0.00	11:07:15	0	0.00	16:10:15	0	0.00
17:51:30	0	0.00	11:07:30	0	0.00	16:10:30	0	0.00
17:51:45	0	0.00	11:07:45	0	0.00	16:10:45	0	0.00
17:52:00	0	0.00	11:08:00	0	0.00	16:11:00	0	0.00
17:52:15	0	0.00	11:08:15	0	0.00	16:11:15	0	0.00
17:52:30	0	0.00	11:08:30	0	0.00	16:11:30	0	0.00
17:52:45	0	0.00	11:08:45	0	0.00	16:11:45	0	0.00
17:53:00	0	0.00	11:09:00	0	0.00	16:12:00	0	0.00
17:53:15	0	0.00	11:09:15	0	0.00	16:12:15	0	0.00
17:53:30	0	0.00	11:09:30	0	0.00	16:12:30	0	0.00
17:53:45	0	0.00	11:09:45	0	0.00	16:12:45	0	0.00
17:54:00	0	0.00	11:10:00	0	0.00	16:13:00	0	0.00
17:54:15	0	0.00	11:10:15	0	0.00	16:13:15	0	0.00
17:54:30	0	0.00	11:10:30	0	0.00	16:13:30	0	0.00
17:54:45	0	0.00	11:10:45	0	0.00	16:13:45	0	0.00
17:55:00	0	0.00	11:11:00	0	0.00	16:14:00	0	0.00
17:55:15	0	0.00	11:11:15	0	0.00	16:14:15	0	0.00
17:55:30	0	0.00	11:11:30	0	0.00	16:14:30	0	0.00
17:55:45	0	0.00	11:11:45	0	0.00	16:14:45	0	0.00
17:56:00	0	0.00	11:12:00	0	0.00	16:15:00	0	0.00
17:56:15	0	0.00	11:12:15	0	0.00	16:15:15	0	0.00
17:56:30	0	0.00	11:12:30	0	0.00	16:15:30	0	0.00
17:56:45	0	0.00	11:12:45	0	0.00	16:15:45	0	0.00
17:57:00	0	0.00	11:13:00	0	0.00	16:16:00	0	0.00
17:57:15	0	0.00	11:13:15	0	0.00	16:16:15	0	0.00
17:57:30	0	0.00	11:13:30	0	0.00	16:16:30	0	0.00
17:57:45	0	0.00	11:13:45	0	0.00	16:16:45	0	0.00
17:58:00	0	0.00	11:14:00	0	0.00	16:17:00	0	0.00
17:58:15	0	0.00	11:14:15	0	0.00	16:17:15	0	0.00
17:58:30	0	0.00	11:14:30	0	0.00	16:17:30	0	0.00
17:58:45	0	0.00	11:14:45	0	0.00	16:17:45	0	0.00
17:59:00	0	0.00	11:15:00	0	0.00	16:18:00	0	0.00
17:59:15	0	0.00	11:15:15	0	0.00	16:18:15	0	0.00

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
17:59:30	0	0.00	11:15:30	0	0.00	16:18:30	0	0.00
17:59:45	0	0.00	11:15:45	0	0.00	16:18:45	0	0.00
18:00:00	0	0.00	11:16:00	0	0.00	16:19:00	0	0.00
18:00:15	0	0.00	11:16:15	0	0.00	16:19:15	0	0.00
18:00:30	0	0.00	11:16:30	0	0.00	16:19:30	0	0.00
18:00:45	0	0.00	11:16:45	0	0.00	16:19:45	0	0.00
18:01:00	0	0.00	11:17:00	0	0.00			
18:01:15	0	0.00	11:17:15	0	0.00			
18:01:30	0	0.00	11:17:30	0	0.00			
18:01:45	0	0.00	11:17:45	0	0.00			
18:02:00	0	0.00	11:18:00	0	0.00			
18:02:15	0	0.00	11:18:15	0	0.00			
18:02:30	0	0.00	11:18:30	0	0.00			
18:02:45	0	0.00	11:18:45	0	0.00			
18:03:00	0	0.00	11:19:00	0	0.00			
18:03:15	0	0.00	11:19:15	0	0.00			
18:03:30	0	0.00	11:19:30	0	0.00			
18:03:45	0	0.00	11:19:45	0	0.00			
18:04:00	0	0.00	11:20:00	0	0.00			
18:04:15	0	0.00	11:20:15	0	0.00			
18:04:30	0	0.00	11:20:30	0	0.00			
18:04:45	0	0.00	11:20:45	0	0.00			
18:05:00	0	0.00	11:21:00	0	0.00			
18:05:15	0	0.00						
18:05:30	0	0.00						
18:05:45	0	0.00						
18:06:00	0	0.00						
18:06:15	0	0.00						
18:06:30	0	0.00						
18:06:45	0	0.00						
18:07:00	0	0.00						
18:07:15	0	0.00						
18:07:30	0	0.00						
18:07:45	0	0.00						
18:08:00	0	0.00						
18:08:15	0	0.00						
18:08:30	0	0.00						

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
18:08:45	0	0.00						
18:09:00	0	0.00						
18:09:15	0	0.00						
18:09:30	0	0.00						
18:09:45	0	0.00						
18:10:00	0	0.00						
18:10:15	0	0.00						
18:10:30	0	0.00						
18:10:45	0	0.00						
18:11:00	0	0.00						
18:11:15	0	0.00						
18:11:30	0	0.00						
18:11:45	0	0.00						
18:12:00	0	0.00						
18:12:15	0	0.00						
18:12:30	0	0.00						
18:12:45	0	0.00						
18:13:00	0	0.00						
18:13:15	0	0.00						
18:13:30	0	0.00						
18:13:45	0	0.00						
18:14:00	0	0.00						
18:14:15	0	0.00						
18:14:30	25	1.04						
18:14:45	0	1.04						
18:15:00	0	1.04						
18:15:15	0	1.04						
18:15:30	0	1.04						
18:15:45	0	1.04						
18:16:00	0	1.04						
18:16:15	0	1.04						
18:16:30	0	1.04						
18:16:45	0	1.04						
18:17:00	0	1.04						
18:17:15	0	1.04						
18:17:30	0	1.04						
18:17:45	0	1.04						

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
18:18:00	0	1.04						
18:18:15	0	1.04						
18:18:30	0	1.04						
18:18:45	0	1.04						
18:19:00	0	1.04						
18:19:15	0	1.04						
18:19:30	0	1.04						
18:19:45	0	1.04						
18:20:00	0	1.04						
18:20:15	0	1.04						
18:20:30	0	0.00						
18:20:45	0	0.00						
18:21:00	0	0.00						
18:21:15	25	1.04						
18:21:30	5	1.25						
18:21:45	0	1.25						
18:22:00	0	1.25						
18:22:15	0	1.25						
18:22:30	0	1.25						
18:22:45	0	1.25						
18:23:00	0	1.25						
18:23:15	0	1.25						
18:23:30	0	1.25						
18:23:45	0	1.25						
18:24:00	0	1.25						
18:24:15	0	1.25						
18:24:30	0	1.25						
18:24:45	0	1.25						
18:25:00	0	1.25						
18:25:15	0	1.25						
18:25:30	0	1.25						
18:25:45	0	1.25						
18:26:00	0	1.25						
18:26:15	0	1.25						
18:26:30	0	1.25						
18:26:45	0	1.25						
18:27:00	0	1.25						

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
18:27:15	0	0.21						
18:27:30	0	0.00						
18:27:45	0	0.00						
18:28:00	0	0.00						
18:28:15	0	0.00						
18:28:30	0	0.00						
18:28:45	0	0.00						
18:29:00	0	0.00						
18:29:15	0	0.00						
18:29:30	0	0.00						
18:29:45	0	0.00						
18:30:00	0	0.00						
18:30:15	0	0.00						
18:30:30	0	0.00						
18:30:45	0	0.00						
18:31:00	0	0.00						
18:31:15	0	0.00						
18:31:30	0	0.00						
18:31:45	0	0.00						
18:32:00	0	0.00						
18:32:15	0	0.00						
18:32:30	0	0.00						
18:32:45	0	0.00						
18:33:00	0	0.00						
18:33:15	15	0.63						
18:33:30	0	0.63						
18:33:45	0	0.63						
18:34:00	0	0.63						
18:34:15	0	0.63						
18:34:30	20	1.46						
18:34:45	0	1.46						
18:35:00	0	1.46						
18:35:15	0	1.46						
18:35:30	30	2.71						
18:35:45	0	2.71						
18:36:00	0	2.71						
18:36:15	0	2.71						

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
18:36:30	0	2.71						
18:36:45	0	2.71						
18:37:00	0	2.71						
18:37:15	0	2.71						
18:37:30	0	2.71						
18:37:45	0	2.71						
18:38:00	0	2.71						
18:38:15	0	2.71						
18:38:30	0	2.71						
18:38:45	0	2.71						
18:39:00	0	2.71						
18:39:15	0	2.08						
18:39:30	0	2.08						
18:39:45	30	3.33						
18:40:00	0	3.33						
18:40:15	0	3.33						
18:40:30	0	2.50						
18:40:45	0	2.50						
18:41:00	0	2.50						
18:41:15	0	2.50						
18:41:30	0	1.25						
18:41:45	0	1.25						
18:42:00	0	1.25						
18:42:15	0	1.25						
18:42:30	0	1.25						
18:42:45	0	1.25						
18:43:00	0	1.25						
18:43:15	0	1.25						
18:43:30	0	1.25						
18:43:45	0	1.25						
18:44:00	0	1.25						
18:44:15	0	1.25						
18:44:30	0	1.25						
18:44:45	0	1.25						
18:45:00	0	1.25						
18:45:15	0	1.25						
18:45:30	25	2.29						

**Table 2.5. Visible Emission Observation Summary,
Baghouse Exhaust (continued)**

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
18:45:45	5	1.25						
18:46:00	0	1.25						
18:46:15	0	1.25						
18:46:30	0	1.25						
18:46:45	0	1.25						
18:47:00	0	1.25						
18:47:15	0	1.25						
18:47:30	0	1.25						
18:47:45	0	1.25						
18:48:00	0	1.25						
18:48:15	0	1.25						
18:48:30	0	1.25						
18:48:45	0	1.25						
18:49:00	0	1.25						
18:49:15	0	1.25						
18:49:30	0	1.25						
18:49:45	0	1.25						
18:50:00	0	1.25						
18:50:15	0	1.25						
18:50:30	0	1.25						
18:50:45	0	1.25						
18:51:00	0	1.25						
18:51:15	0	1.25						
18:51:30	0	0.21						
18:51:45	0	0.00						
18:52:00	0	0.00						
18:52:15	0	0.00						
18:52:30	0	0.00						
18:52:45	0	0.00						
18:53:00	0	0.00						
18:53:15	0	0.00						
18:53:30	0	0.00						
18:53:45	0	0.00						
18:54:00	0	0.00						
18:54:15	0	0.00						
18:54:30	0	0.00						
18:54:45	0	0.00						

TEST 1			TEST 2			TEST 3		
Time	VE	6-min Avg	Time	VE	6-min Avg	Time	VE	6-min Avg
18:55:00	0	0.00						
18:55:15	0	0.00						
18:55:30	0	0.00						
18:55:45	0	0.00						
18:56:00	0	0.00						
18:56:15	0	0.00						
18:56:30	0	0.00						
18:56:45	0	0.00						
18:57:00	0	0.00						
18:57:15	0	0.00						
18:57:30	0	0.00						
18:57:45	0	0.00						
18:58:00	0	0.00						
18:58:15	0	0.00						
18:58:30	0	0.00						
18:58:45	0	0.00						
18:59:00	Too dark for VE's							

SECTION 3

SAMPLING AND ANALYTICAL PROCEDURES

The sampling and analytical procedures used in this test program conform to **EPA** Reference Methods 1-4, 5D, and 9, as published in the Federal Register.

LOCATION OF MEASUREMENT SITES

EPA Method 1, "Sample Velocity Traverses for Stationary Sources," was used to select representative measurement sites. Sample locations are shown in Section 4.

STACK GAS VOLUMETRIC FLOW RATE

EPA Method 2, "Determination of Stack Gas Velocity and Volumetric Flow Rates," was used at each location to determine stack gas volumetric flow rates. Standard and Type "S" pitot tubes, meeting the **EPA** specifications, and an inclined manometer were used to measure velocity pressures. A calibrated Type "K" thermocouple, attached directly to the pitot tube, was used to measure stack gas temperature. The stack gas velocity was calculated from the average square root of the stack gas velocity pressure, average stack gas temperature, stack gas molecular weight, and absolute static pressure. The volumetric flow rate is the product of velocity and stack cross-sectional area.

STACK GAS DRY MOLECULAR WEIGHT

EPA Reference Method 3A, "Gas Analysis for the Determination of Dry Molecular Weight," was used to determine stack gas dry molecular weight. Bag samples were collected and analyzed for each measurement run using **Orsat** combustion analyzers.

STACK GAS MOISTURE CONTENT

EPA Reference Method 4, "Determination of Moisture Content in Stack Gases," was used to determine outlet stack gas moisture content. This method was conducted as

part of each total particulate matter measurement run. The initial and final contents of all impingers are determined gravimetrically.

PARTICULATE MATTER

EPA Reference Method 5D, "Determination of Particulate Matter Emissions from Positive Pressure Fabric Filter Baghouses," was used to determine the total particulate matter concentration and mass emission rates. The sample train consisted of a stainless steel nozzle, glass probe and filter holder, glass fiber filter, and a series of impingers followed by a vacuum pump, dry gas meter, and calibrated orifice. The particulate sample was withdrawn isokinetically and collected on the filter. Thermocouples were used to monitor temperatures of the stack gas and impinger exit gas. A schematic of the sample train is shown in Figure 3.1.

VISIBLE EMISSION OBSERVATIONS

EPA Reference Method 9, "Visual Determination of the Opacity of Emissions from Stationary Sources," was used to determine opacity from the baghouse exhaust as well as from the melt shop roof monitor. Observations were conducted simultaneously with the particulate sampling runs.




Figure 3.1. Schematic of EPA Method 5 Sampling Train - Baghouse Outlet

SECTION 4

PROCESS DESCRIPTION/SAMPLING LOCATIONS

Kentucky Electric Steel, Inc. owns and operates an electric arc furnace (EAF) melt shop and bar steel rolling facility located on U.S. Route 60 approximately 12 miles west of **Ashland**, Kentucky.

Kentucky Electric Steel, Inc. has two EAFs for steel production. Scrap steel is delivered by rail and truck and is stored in open piles. Scrap steel and various fluxing agents are weighed and charged to the EAF. The charge material is melted by electrical current flowing among three graphite electrodes lowered into the furnace. Slag (melt impurities) is separated from the product metal and is transferred to slag storage and processing using an endloader. Molten metal is tapped from the EAF into preheated transfer ladles by tilting the furnace, allowing the metal to flow through a hole in the side.

Molten metal is then transferred to the ladle metallurgy furnace (LMF). Raw materials (bulk alloys and fluxes) are added to the molten metal in the LMF to further purify it. The metal is heated during refining using electrodes. After metal treatment is complete, the transfer ladle is removed from the LMF and carried to the continuous casting machine.

At the continuous caster, molten metal is poured into a preheated **tundish** and then flows into molds and is allowed to partially cool. The strips of metal are cut into pieces at the caster to form **billets**. Cooled billets are later reheated in a reheat furnace and rolled to the desired dimensions. The bar steel is descaled using water sprays and the ends of the bars are sheared off. The final product is bound into bundles and stored until shipped **offsite**.

Emissions **from** the EAFs and LMF are vented to the Harsell Positive Pressure Baghouse. A general process flow diagram is provided in Figure 4-1.

Throughout the test program the following process data was collected:

- A) Charge weights and materials and tap weights and materials (these are provided on the heat sheets in Appendix **C**).
- B) Heat times, including start and stop times, log off process operation including periods of no operation during testing (These are

provided on the heat sheets and production field data in Appendices C and B respectively.)

- C)** **Pressure** Drop across the baghouse. (Shown in Table 2.3 and in Appendix B) A visual inspection of the baghouse was made prior to testing.
- D)** Fan/duct damper position (shown in Table 4.1).
- E)** Fan amperes (shown in Table 4.2).

Fan and damper data was monitored continuously electronically and manually every 15 minutes. Ranges of the data are provided in Table 4.1. The fan amperes are summarized in Table 4.2.




Figure 4.1. Process Flow Diagram

TABLE 4.1. DAMPER POSITIONS (PERCENT OPEN DURING ACTIVITY)

Damper	Melting A&B	Charging A Melting B	Charging B Melting A	Tapping A Melting B	Tapping B Melting A	Charging A Charging B
West Blower	100	100	100	100	100	100
East Blower	100	100	100	100	100	100
A Furnace Plenum	0-100	0	0	0	0	0
B Furnace Plenum	0-100	0-100	0	0	0	0
A Water Cooled	100	100	100	0	100	0-100
B Water Cooled	100	100	0	100	0	0-100
Furnace Blower Inlet	100	99-100	100	100	100	62-78
Furnace Blower Outlet	100	99-100	100	100	100	62-79

TABLE 4.2. CONTROL SYSTEM FAN AMPERES DURING PERFORMANCE

DATE	TIME	Baghouse Pressure	Baghouse Temp, F	East Blower Amp	West Blower Amp	4th Port Blower Amp	Total Amp	Activity
TEST 1								
5/11/00	1:50:00 pm	5.18	105.61	191.26	182.86	110.83	484.95	Charge
5/11/00	1:55:00 pm	5.25	107.18	192.25	183.88	102.22	478.36	Charge
5/11/00	2:00:00 pm	5.34	106.86	192.88	184.60	108.64	486.13	Charge
5/11/00	2:05:00 pm	5.42	109.05	192.61	184.13	109.03	485.78	Charge
5/11/00	2:10:00 pm	5.55	108.11	192.77	184.45	114.93	492.15	Charge
5/11/00	2:15:00 pm	5.57	110.93	190.26	182.00	110.00	482.25	Charge
5/11/00	2:20:00 pm	5.56	113.74	187.18	178.96	98.54	464.68	Charge
5/11/00	2:25:00 pm	5.68	118.74	189.67	181.19	102.56	473.41	Charge
5/11/00	2:30:00 pm	5.72	118.11	189.57	181.30	100.84	471.72	Charge
5/11/00	2:35:00 pm	5.98	116.55	189.80	181.28	103.36	474.44	Charge
5/11/00	2:40:00 pm	5.79	123.74	186.04	177.65	95.06	458.75	Tap
5/11/00	2:45:00 pm	5.95	122.18	188.28	179.99	103.20	471.47	Charge
5/11/00	2:50:00 pm	5.72	125.92	186.09	177.62	107.68	471.39	Charge
5/11/00	2:55:00 pm	5.58	130.92	186.23	177.87	113.44	477.54	Charge
5/11/00	3:00:00 pm	5.58	131.24	186.85	178.80	100.66	466.32	Melt
5/11/00	3:05:00 pm	5.53	121.24	188.97	181.03	104.24	474.25	Melt
5/11/00	3:10:00 pm	5.67	120.30	188.85	180.85	104.44	474.14	Tap
5/11/00	3:15:00 pm	5.40	124.99	187.43	179.53	100.01	466.98	Tap
5/11/00	3:20:00 pm	5.11	129.67	187.82	179.80	101.75	469.37	Charge
5/11/00	3:25:00 pm	5.23	128.74	186.99	179.28	115.40	481.67	Charge
5/11/00	3:30:00 pm	5.25	129.05	188.68	180.67	119.89	489.23	Charge
5/11/00	3:35:00 pm	5.19	131.55	188.67	180.68	119.47	488.82	Charge
5/11/00	3:40:00 pm	5.27	128.42	187.31	179.55	117.74	484.61	Charge
5/11/00	3:45:00 pm	5.31	129.05	185.60	177.84	117.19	480.63	Melt
5/11/00	3:50:00 pm	5.37	127.49	185.26	177.81	106.01	469.08	Melt
5/11/00	3:55:00 pm	5.47	121.86	188.41	180.55	111.56	480.52	Melt
5/11/00	4:00:00 pm	5.40	121.86	186.83	178.71	106.62	472.17	Melt
5/11/00	4:05:00 pm	5.60	139.99	185.83	177.70	102.44	465.97	Melt
5/11/00	4:10:00 pm	5.71	126.86	186.80	178.58	104.67	470.04	Melt
5/11/00	4:15:00 pm	5.80	124.99	187.43	179.26	106.16	472.85	Melt
5/11/00	4:20:00 pm	5.90	123.74	186.24	177.98	102.40	466.63	Charge
5/11/00	4:25:00 pm	5.81	133.11	185.66	177.22	98.16	461.04	Charge
5/11/00	4:30:00 pm	5.74	141.55	186.16	178.07	96.92	461.15	Melt
5/11/00	4:35:00 pm	6.06	127.49	187.27	178.92	106.01	472.20	Melt
5/11/00	4:40:00 pm	5.99	123.74	185.43	177.31	104.76	467.49	Melt
5/11/00	4:45:00 pm	5.98	122.49	185.59	177.50	103.66	466.75	Tap

TABLE 4.2. CONTROL SYSTEM FAN AMPERES DURING PERFORMANCE

DATE	TIME	Baghouse Pressure	Baghouse Temp, F	East Blower Amp	West Blower Amp	4th Port Blower Amp	Total Amp	Activity
5/11/00	4:50:00 pm	5.63	124.99	186.08	178.12	100.93	465.13	Charge
5/11/00	4:55:00 pm	5.63	135.30	185.14	176.86	107.49	469.48	Charge
5/11/00	5:00:00 pm	5.56	143.42	183.01	174.74	108.04	465.79	Charge
5/11/00	5:05:00 pm	5.66	144.67	182.62	174.43	106.29	463.35	Charge
5/11/00	5:10:00 pm	5.60	141.55	183.78	175.71	112.58	472.07	Charge
5/11/00	5:15:00 pm	5.47	138.42	185.67	177.72	116.59	479.99	Charge
5/11/00	5:20:00 pm	5.45	129.05	187.51	179.48	119.62	486.60	Charge
5/11/00	5:25:00 pm	5.15	127.17	188.01	180.29	116.02	484.32	Melt
5/11/00	5:30:00 pm	5.16	122.18	188.71	181.27	107.98	477.96	Melt
5/11/00	5:35:00 pm	5.20	119.99	189.59	181.73	106.69	478.02	Melt
5/11/00	5:40:00 pm	5.26	119.05	190.03	182.18	108.86	481.08	Melt
5/11/00	5:45:00 pm	5.30	117.80	189.98	182.11	107.08	479.18	Charge
5/11/00	5:50:00 pm	5.33	120.61	190.06	181.90	116.29	488.25	Charge
5/11/00	5:55:00 pm	5.44	122.80	189.02	181.06	111.80	481.88	Melt
5/11/00	6:00:00 pm	5.42	134.05	186.34	178.07	107.04	471.44	Melt
5/11/00	6:05:00 pm	5.59	127.80	187.92	179.83	105.48	473.23	Melt
5/11/00	6:10:00 pm	5.61	123.74	186.67	178.55	103.74	468.95	Melt
5/11/00	6:15:00 pm	5.66	125.92	185.65	177.55	101.66	464.87	Melt
5/11/00	6:20:00 pm	5.75	142.17	183.17	174.96	91.86	449.98	Melt
5/11/00	6:25:00 pm	6.18	132.17	186.10	177.77	104.77	468.64	Melt
5/11/00	6:30:00 pm	5.94	128.42	185.77	177.51	104.12	467.41	Tap
5/11/00	6:35:00 pm	5.72	133.42	187.82	179.58	104.74	472.14	Tap
5/11/00	6:40:00 pm	5.62	130.61	188.37	180.10	109.18	477.66	Melt
5/11/00	6:45:00 pm	5.51	132.17	187.76	179.55	117.02	484.34	Charge
5/11/00	6:50:00 pm	5.56	133.11	186.92	178.73	119.72	485.37	Charge
5/11/00	6:55:00 pm	5.18	138.11	186.96	178.97	118.18	484.11	Melt
5/11/00	7:00:00 pm	5.13	127.80	191.11	183.23	116.67	491.01	Melt
5/11/00	7:05:00 pm	3.57	119.68	191.09	183.28	118.52	492.89	Melt
5/11/00	7:10:00 pm	5.11	116.24	191.10	183.28	118.67	493.05	Melt
5/11/00	7:15:00 pm	5.22	118.43	187.44	179.67	112.43	479.55	Melt
5/11/00	7:20:00 pm	5.30	120.93	188.02	180.29	108.55	476.87	Melt
5/11/00	7:25:00 pm	5.40	120.30	188.79	180.98	109.84	479.61	Melt
5/11/00	7:30:00 pm	5.46	118.43	189.95	182.06	114.58	486.58	Tap
5/11/00	7:35:00 pm	5.41	120.61	189.14	181.04	118.52	488.71	Melt
Ampere Range Test 1							450.0 - 493.1	
TEST 2								
5/12/00	7:15:00 am	6.01	122.49	184.39	176.08	108.11	468.58	Melt

TABLE 4.2. CONTROL SYSTEM FAN AMPERES DURING PERFORMANCE

BATE	TIME	Baghouse Pressure	Baghouse Temp, F	East Blower Amp	West Blower Amp	4th Port Blower Amp	Total Amp	Activity
5/12/00	7:20:00 am	5.93	123.43	182.48	174.69	102.06	459.23	Melt
5/12/00	7:25:00 am	5.93	127.17	183.56	175.60	102.78	461.95	Melt
5/12/00	7:30:00 am	5.83	125.92	184.12	176.12	104.52	464.76	Melt
5/12/00	7:35:00 am	5.75	126.55	184.77	176.59	103.55	464.91	Tap
5/12/00	7:40:00 am	5.51	129.36	182.62	174.52	107.87	465.00	Charge
5/12/00	7:45:00 am	5.56	137.80	182.80	174.61	111.13	468.54	Charge
5/12/00	7:50:00 am	5.54	145.92	180.58	172.27	113.15	466.00	Charge
5/12/00	7:55:00 am	5.64	145.92	182.07	173.82	109.02	464.91	Charge
5/12/00	8:00:00 am	5.54	142.17	182.68	174.65	107.36	464.69	Melt
5/12/00	8:05:00 am	5.42	135.30	183.34	175.59	101.44	460.37	Melt
5/12/00	8:10:00 am	5.49	134.05	184.70	176.75	100.91	462.36	Melt
5/12/00	8:15:00 am	5.51	131.24	187.42	179.35	104.49	471.26	Melt
5/12/00	8:20:00 am	5.60	130.92	188.65	180.68	101.73	471.06	Melt
5/12/00	8:25:00 am	5.41	129.67	186.62	178.78	101.53	466.93	Melt
5/12/00	8:30:00 am	5.34	127.80	187.04	179.26	103.55	469.85	Charge
5/12/00	8:35:00 am	5.17	133.74	185.84	177.98	103.54	467.36	Charge
5/12/00	8:40:00 am	5.05	139.36	183.50	175.98	90.88	450.35	Melt
5/12/00	8:45:00 am	5.22	133.11	185.59	177.92	99.66	463.16	Tap
5/12/00	8:50:00 am	5.30	129.36	186.58	178.60	110.92	476.11	Tap
5/12/00	8:55:00 am	5.30	133.74	185.07	177.01	108.79	470.87	Charge
5/12/00	9:00:00 am	5.34	142.49	183.30	175.17	112.74	471.22	Charge
5/12/00	9:05:00 am	5.44	138.11	184.50	176.44	106.16	467.09	Melt
5/12/00	9:10:00 am	5.45	138.11	183.98	175.96	89.91	449.84	Melt
5/12/00	9:15:00 am	5.56	143.74	184.61	176.58	88.04	449.23	Melt
5/12/00	9:20:00 am	5.65	149.36	183.85	175.71	88.16	447.72	Melt
5/12/00	9:25:00 am	5.75	154.36	181.69	173.52	83.69	438.90	Melt
5/12/00	9:30:00 am	5.94	158.73	181.59	173.28	82.96	437.83	Melt
5/12/00	9:35:00 am	5.85	158.42	180.08	171.74	85.14	436.96	Charge
5/12/00	9:40:00 am	5.71	173.42	178.99	170.68	82.48	432.15	Melt
5/12/00	9:45:00 am	5.55	179.04	178.82	170.69	81.55	431.06	Charge
5/12/00	9:50:00 am	5.58	179.67	179.32	171.17	84.21	434.69	Melt
5/12/00	9:55:00 am	5.68	173.42	180.81	172.64	85.84	439.28	Tap
5/12/00	10:00:00 am	5.93	159.36	180.85	172.58	89.26	442.68	Tap
5/12/00	10:05:00 am	6.15	150.61	181.85	173.61	94.68	450.13	Charge
5/12/00	10:10:00 am	5.80	152.48	178.76	170.50	98.88	448.14	Charge
5/12/00	10:15:00 am	5.67	161.86	179.92	171.75	99.68	451.35	Melt
5/12/00	10:20:00 am	5.66	147.17	182.66	174.85	94.22	451.73	Melt

TABLE 4.2. CONTROL SYSTEM FAN AMPERES DURING PERFORMANCE

DATE	TIME	Baghouse Pressure	Baghouse Temp, F	East Blower Amp	West Blower Amp	4th Port Blower Amp	Total Amp	Activity
5/12/00	10:25:00 am	5.62	139.05	184.06	176.18	98.75	458.99	Melt
5/12/00	10:30:00 am	5.70	137.80	183.37	175.34	100.02	458.72	
5/12/00	10:35:00 am	5.58	142.49	182.80	174.83	105.90	463.54	
5/12/00	10:40:00 am	5.53	142.17	184.73	176.54	112.82	474.09	Charge
5/12/00	10:45:00 am	5.54	140.92	185.22	177.00	117.72	479.94	Charge
5/12/00	10:50:00 am	5.54	138.11	185.74	177.76	118.92	482.42	Charge
5/12/00	10:55:00 am	5.37	134.99	185.01	177.23	118.87	481.11	Charge
5/12/00	11:00:00 am	4.10	139.36	184.16	176.62	116.86	477.63	Charge
5/12/00	11:05:00 am	4.96	136.86	182.18	174.61	112.10	468.89	Charge
5/12/00	11:10:00 am	5.01	147.17	181.42	173.99	88.53	443.94	Melt
5/12/00	11:15:00 am	5.25	143.11	183.39	175.88	97.84	457.11	Melt
5/12/00	11:20:00 am	5.31	141.24	184.73	176.81	91.53	453.07	Melt
Ampere Range Test 3							431.1 - 482.4	
TEST 3								
5/12/00	12:15:00 pm	5.75	141.86	182.26	174.32	96.45	453.03	Melt
5/12/00	12:20:00 pm	5.58	140.61	181.30	173.39	94.98	449.68	Melt
5/12/00	12:25:00 pm	5.67	145.92	181.37	173.17	94.76	449.29	Melt
5/12/00	12:30:00 pm	5.69	138.74	182.55	174.60	102.35	459.50	Melt
5/12/00	12:35:00 pm	5.69	146.55	179.73	171.72	92.39	443.84	Charge
5/12/00	12:40:00 pm	5.41	154.05	179.63	171.59	91.08	442.31	Melt
5/12/00	12:45:00 pm	5.38	156.23	178.94	170.99	87.19	437.13	Melt
5/12/00	12:50:00 pm	5.55	149.05	181.39	173.38	105.59	460.36	Tap
5/12/00	12:55:00 pm	5.47	150.30	180.21	172.03	105.26	457.49	Charge
5/12/00	1:00:00 pm	5.37	167.48	177.73	169.61	103.05	450.39	Charge
5/12/00	1:05:00 pm	5.31	149.67	181.85	174.09	93.37	449.31	Melt
5/12/00	1:10:00 pm	5.38	142.49	182.55	174.92	97.73	455.20	Melt
5/12/00	1:15:00 pm	5.44	143.11	183.52	175.58	98.84	457.94	Melt
5/12/00	1:20:00 pm	5.48	142.80	179.21	171.04	92.13	442.38	Melt
5/12/00	1:25:00 pm	5.53	143.42	181.98	173.89	94.20	450.07	Tap
5/12/00	1:30:00 pm	5.60	142.80	185.83	177.74	105.50	469.07	Tap
5/12/00	1:35:00 pm	5.58	144.05	184.46	176.18	114.02	474.67	Charge
5/12/00	1:40:00 pm	5.60	152.17	179.87	171.87	112.09	463.83	Charge
5/12/00	1:45:00 pm	5.65	155.92	180.41	172.08	108.83	461.32	Charge
5/12/00	1:50:00 pm	5.73	156.86	182.60	174.23	120.38	477.21	Charge
5/12/00	1:55:00 pm	5.72	150.61	182.46	174.34	118.11	474.91	Charge
5/12/00	2:00:00 pm	5.76	151.23	181.12	172.91	105.79	459.82	Charge
5/12/00	2:05:00 pm	6.10	150.30	180.47	172.16	106.30	458.93	Charge

TABLE 4.2. CONTROL SYSTEM FAN AMPERES DURING PERFORMANCE

DATE	TIME	Baghouse Pressure	Baghouse Temp, F	East Blower Amp	West Blower Amp	4th Port Blower Amp	Total Amp	Activity
5/12/00	2:10:00 pm	5.94	152.17	180.64	172.20	109.75	462.59	Charge
5/12/00	2:15:00 pm	5.88	155.92	179.96	171.57	105.78	457.31	Charge
5/12/00	2:20:00 pm	5.58	167.48	177.04	168.82	86.96	432.81	Melt
5/12/00	2:25:00 pm	5.78	159.05	179.85	171.82	85.72	437.38	Melt
5/12/00	2:30:00 pm	5.66	152.17	181.16	173.02	90.60	444.78	Melt
5/12/00	2:35:00 pm	5.55	150.30	181.06	172.99	89.98	444.03	Tap
5/12/00	2:40:00 pm	5.59	149.36	181.21	173.07	91.86	446.14	Tap
5/12/00	2:45:00 pm	5.65	148.74	180.42	172.33	99.97	452.72	Charge
5/12/00	2:50:00 pm	5.70	161.23	178.84	170.48	104.23	453.55	Charge
5/12/00	2:55:00 pm	5.52	163.11	179.57	171.24	104.59	455.41	Charge
5/12/00	3:00:00 pm	5.49	157.48	180.41	171.99	107.59	459.99	Charge
5/12/00	3:05:00 pm	5.28	161.86	180.53	172.55	103.84	456.93	Melt
5/12/00	3:10:00 pm	5.34	148.42	182.78	174.95	98.14	455.88	Melt
5/12/00	3:15:00 pm	5.43	144.05	182.86	175.06	101.12	459.04	Melt
5/12/00	3:20:00 pm	5.39	149.36	180.02	172.17	91.81	444.00	Melt
5/12/00	3:25:00 pm	5.46	155.61	178.57	170.81	85.76	435.14	Melt
5/12/00	3:30:00 pm	5.59	159.98	179.49	171.56	87.08	438.13	Melt
5/12/00	3:35:00 pm	5.77	149.05	180.78	172.95	97.74	451.47	Melt
5/12/00	3:40:00 pm	5.75	147.80	179.93	171.93	93.32	445.18	Charge
5/12/00	3:45:00 pm	6.02	151.23	178.71	170.62	97.24	446.56	Tap
5/12/00	3:50:00 pm	6.03	148.74	179.11	170.79	89.64	439.54	Charge
5/12/00	3:55:00 pm	5.69	152.17	178.54	170.27	92.06	440.87	Charge
5/12/00	4:00:00 pm	5.71	163.11	177.17	168.79	101.94	447.89	Charge
5/12/00	4:05:00 pm	5.80	155.61	180.95	172.68	114.82	468.45	Charge
5/12/00	4:10:00 pm	5.71	150.61	178.69	170.47	107.68	456.83	Charge
5/12/00	4:15:00 pm	5.72	167.80	177.92	169.57	108.94	456.43	Charge
5/12/00	4:20:00 pm	3.34	162.17	178.96	170.58	98.81	448.35	Charge
Ampere Range Test 3							432.8 - 477.2	
Ampere Range All Tests							431.1 - 493.0	

SECTION 5

SAMPLING LOCATIONS

The **baghouse** inlet sampling location was in a section of rectangular duct approximately 193 inches downstream of a bend and 165 inches upstream of a reduction in duct size. The duct dimensions were 131.5 inches by 144 inches. Six ports on the top of the duct were sampled with a total of 48 sampling points, eight per port. Figure 5.1 is a schematic of the **baghouse** inlet sampling location.

Figure 5.2 is a schematic of the **baghouse** outlet compartments **sampled** for the particulate emissions. A **sampling** matrix of four by two points, eight points per compartment, was used for sampling purposes.

A total of **32** points within four compartments was sampled at a **minimum** during each test run. Of the twenty compartments present, a total of **13** compartments were sampled during the course of the sampling program




Figure 5.1. Baghouse Inlet Sampling Location




Figure 5-2. Schematic of Baghouse Outlet

SECTION 6

QUALITY ASSURANCE AND QUALITY CONTROL

The field sampling quality assurance for this project included the use of: calibrated source sampling equipment; reference test methods; and traceability protocols for the recording and calculation of data. The analytical quality assurance includes use of validated analytical procedures; calibration of equipment; and analysis of control samples and blanks. The calibration and quality control procedures used for this test program are described in the following subsection:

CALIBRATION PROCEDURES AND FREQUENCY

All manual stack gas sampling equipment is calibrated before the test program in accordance with the procedures outlined in the ***Quality Assurance Handbook for Air Pollution Measurement Systems, Volume III***, EPA-600/4-72-027B. Summarized in Table 5.1 are the stack gas sampling equipment calibrations which are performed in preparation for this project. The meter boxes are re-calibrated after the test.

Listed in Table 6.2 are the additional calibration checks which are performed on the sampling equipment **onsite**, just prior to the testing, to ensure that equipment was not damaged during transport.

TABLE 6.1
FIELD EQUIPMENT CALIBRATION SUMMARY*

Equipment	Calibrated against	Allowable error
Method 5 meter box	Reference test meter	Y $\pm$ 0.02 Y Δ H@ $\pm$ 0.20 Δ H@ post-test Y $\pm$ 0.05 Y
Pitot tube	Geometric specifications	See EPA Method 2
Thermocouple	ASTM-3F thermometer	$\pm$ 1.5%
Impinger (or condenser thermometer)	ASTM-3F	$\pm$ 2°F
Dry gas meter thermometer	ASTM-3F	$\pm$ 5°F
Probe nozzles	Caliper	$\pm$ 0.004 in.
Barometer	NBS traceable barometer	$\pm$ 0.1 in.Hg

*As recommended in the Quality Assurance Handbook for Air Pollution Measurement Systems: Volume 111. Stationary Source-Specific Methods. EPA-600/4-77-027b, August 1977.

TABLE 6.2
FIELD CHECKS OF SAMPLING EQUIPMENT

Equipment	Checked against	Allowable difference
Pitot tube	Inspection	No visible damage
Thermocouples	ASTM 2F or 3F	$\pm$ 1.5%
Probe nozzles	Caliper	$\pm$ 0.004 in.

Appendix A
Visible Emission Field Data

VISIBLE EMISSION OBSERVATION FORM

No. 1 of 10

COMPANY NAME
Kentucky Electric Steel, Inc.

STREET ADDRESS
U.S. 60 West - Coalton

CITY
Ashland

STATE
KY

ZIP
41102

PHONE (KEY CONTACT) Plant
(606) 929-1320 Guard

SOURCE ID NUMBER
103-0340-0020

PROCESS EQUIPMENT
Melt Shop

OPERATING MODE
Charge/Melt/Tap

CONTROL EQUIPMENT
Harsell Baghouse

OPERATING MODE
On line

DESCRIBE EMISSION POINT
Middle of Melt shop

HEIGHT ABOVE GROUND LEVEL
60'

HEIGHT RELATIVE TO OBSERVER
Start 10' End ✓

DISTANCE FROM OBSERVER
in 600' End ✓

DIRECTION FROM OBSERVER
Start North End North

DESCRIBE EMISSIONS
Start BP End ✓

EMISSION COLOR
in white End ✓

IF WATER DROPLET PLUME
Attached ☒ N/A Detached ☐

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED
in 10' over release monitor End

DESCRIBE PLUME BACKGROUND
Start Trees End ✓


BACKGROUND COLOR
in Green End ✓

WIND SPEED
in 5-10 MPH End ✓

WIND DIRECTION
Start South East End West

WET BULB TEMP
N/A

RH, percent
N/A



ADDITIONAL INFORMATION
1st Helper -
2nd Helper -

OBSERVATION DATE		START TIME		END TIME	
5-11-00		1359		1429	
SEC	0	15	30	45	COMMENTS
MIN					
1359	0	0	0	0	Melt shop
2	5	5	5	5	
3	5	0	0	0	
4	0	0	0	0	
5	0	0	0	0	25/24 = 1.04%
1404	0	0	0	0	
1405	0	10	10	10	Should have been on
8	5	5	0	0	baghouse VES.
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	35/24 = 1.46%
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	5	5	
16	5	5	5	10	
17	10	5	5	5	75/24 = 3.13%
18	5	5	5	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	5	40/24 = 1.67%
23	5	10	10	5	
24	5	0	0	0	
25	0	5	5	5	
26	5	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	20/24 = 0.83%
30	0	0	0	0	

OBSERVER'S NAME (PRINT)
Bryan Brunfield

OBSERVER'S SIGNATURE
Bryan Brunfield

DATE
5-11-00

ORGANIZATION
Environmental Quality Management

CERTIFIED BY
ETA

DATE
3-22-00

CONTINUED ON VEO FORM NUMBER
0307

VISIBLE EMISSION OBSERVATION FORM

No. 2 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard		SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT Middle, East + West End of Melt Shop	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <i>Letting</i> End ✓	
EMISSION COLOR Start <i>White</i> End ✓	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 10' out + above monitor End ✓	

DESCRIBE PLUME BACKGROUND Start <i>Trees</i> End <i>Baghouse + Trees</i>	
BACKGROUND COLOR Start <i>Green</i> End <i>Brown + Green</i>	SKY CONDITIONS Start <i>Scattered</i> End ✓
WIND SPEED Start 5-10 mph End ✓	WIND DIRECTION Start <i>Southwest</i> End ✓
AMBIENT TEMP Start 80° End ✓	WET BULB TEMP N/A
	RH, percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow
---------------------------------	--

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-11-00					START TIME 1429	END TIME 1459
SEC MIN	0	15	30	45	COMMENTS	
1429	0	0	0	0	Melt Shop	
2	0	0	0	0		
3	0	5	10	10	Charge A	
4	10	5	5	0		
5	0	0	0	0	45/24 = 1.88%	
1434	0	0	0	0		
1435	0	5	5	0		
6	0	0	0	0		
7	0	0	0	0		
10	0	0	0	0	Tap B	
11	0	0	0	0	15/24 = 0.63%	
12	0	0	0	5		
1440	5	5	10	10		
13	5	5	10	10		
1441	5	5	10	10		
14	5	5	5	0		
15	0	10	10	15		
16	15	15	15	10	Charge B	
17	10	15	15	15	265/24 = 11.04%	
18	15	20	20	20		
1446	20	15	15	15		
19	10	10	5	5		
1447	5	5	10	15		
20	10	10	10	15		
21	15	10	5	5	260/24 = 10.83%	
22	5	10	15	20		
23	15	10	10	5		
24	5	10	15	20		
1452	15	10	10	5		
25	5	5	5	5		
1453	5	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0	65/24 = 2.71%	
30	0	0	0	0		
1458	0	0	0	0		

OBSERVER'S NAME (PRINT) Bryan Brunfield	
OBSERVER'S SIGNATURE <i>Bryan Brunfield</i>	DATE 5-11-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00
CONTINUED ON VEO FORM NUMBER 03 02	

VISIBLE EMISSION OBSERVATION FORM

No. 3 of 10


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant 606) 929-1320 Guard		SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT Same	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 100' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start Low Puff End ✓	
EMISSION COLOR tan End ✓	IF WATER DROPLET PLUME Attached () N/A Detached ()
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Baghouse & Trees End ✓		
BACKGROUND COLOR tan End ✓	SKY CONDITIONS Start Scattered End ✓	
WIND SPEED Start 5-10 End ✓	WIND DIRECTION Start South End ✓	
AMBIENT TEMP Start 80 End 85°	WET BULB TEMP N/A	REL. percent N/A



ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-11-00				START TIME 1459	END TIME 1529
SEC	0	15	30	45	COMMENTS
1459	0	0	0	10	Melter charge
2	10	5	5	5	
3	5	0	0	0	
4	0	0	0	0	
5	0	0	0	0	30/24 = 1.25%
6	0	0	0	0	
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	5	5	5	
11	5	0	0	0	25/24 = 1.04%
12	0	0	0	5	Tap A
13	5	10	20	15	
14	15	15	10	10	
15	15	15	15	15	
16	10	5	5	5	
17	5	0	0	0	210/24 = 8.75%
18	0	0	10	10	
19	5	5	5	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	15/24 = 0.63%
24	0	0	0	0	
25	0	0	0	0	
26	0	10	10	5	
27	5	5	5	10	
28	10	10	5	5	
29	5	0	0	0	85/24 = 3.54%
30	0	0	0	0	

OBSERVER'S NAME (PRINT) Bryan Brunfield	
OBSERVER'S SIGNATURE Bryan Brunfield	DATE 5-11-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00
CONTINUED ON VEO FORM NUMBER 0403	

VISIBLE EMISSION OBSERVATION FORM

No. 4 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard		SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baphouse	OPERATING MODE On line

DESCRIBE EMISSION POINT Middle + East end of Melt Shop	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start Lofting End ✓	
EMISSION COLOR Start White End ✓	IF WATER DROPLET Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Same End ✓	
BACKGROUND COLOR Start Same End ✓	SKY CONDITIONS Start Partly Cloudy End ✓
WIND SPEED Start 10 End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 85° End	WET BULB TEMP N/A
	RH. percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-11-00				START TIME 1529	END TIME 1559
SEC MIN	0	15	30	45	COMMENTS
1529	0	0	0	0	Melt Shop
2	0	0	0	0	
3	0	0	5	10	
4	10	5	5	5	
5	0	0	0	0	
6	0	0	0	0	40/24 = 1.67%
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	5	5	5	0.83%
12	5	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	0/24 = 0%
18	0	0	0	0	
19	0	0	0	0	
20	1	1	1	1	Could not read due to
21	1	1	1	1	L.M.F. Emissions
22	1	0	0	0	
23	0	0	5	5	25/24 = 1.048
24	5	5	5	0	
25	0	0	0	10	
26	15	10	25	70	Line test Front end
27	75	80	70	65	Loader at Carrier
28	75	90	85	80	
29	70	50	50	50	12 25/24 = 51.04%
30	60	60	70	65	

OBSERVER'S NAME (PRINT) Bryan Brunfield	
OBSERVER'S SIGNATURE Bryan Brunfield	DATE 5-11-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00
CONTINUED ON VEO FORM NUMBER 0504	

VISIBLE EMISSION OBSERVATION FORM

No. 5 of 12

COMPANY NAME
Kentucky Electric Steel, Inc.

STREET ADDRESS
U.S. 60 West - Coalton

CITY
Ashland

STATE
KY

ZIP
41102

PHONE (KEY CONTACT) Plant
606) 929-1320 Guard

SOURCE ID NUMBER
103-0340-0020

PROCESS EQUIPMENT
Melt Shop

OPERATING MODE
Charge/Melt/Tap

CONTROL EQUIPMENT
Harsell Baghouse

OPERATING MODE
On line

DESCRIBE EMISSION POINT
East, West + middle of Melt shop

HEIGHT ABOVE GROUND LEVEL
60'

HEIGHT RELATIVE TO OBSERVER
Start 10' End ✓

DISTANCE FROM OBSERVER
Start 600' End ✓

DIRECTION FROM OBSERVER
Start North End North

DESCRIBE EMISSIONS
Start Lofony End ✓

EMISSION COLOR
Start White End ✓

IF WATER DROPLET PLUME
Attached () N/A Detached ()

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED
Start Same End ✓

DESCRIBE PLUME BACKGROUND
Start Same End ✓

BACKGROUND COLOR
Start Same End ✓

SKY CONDITIONS
Start Scattered End Scattered


WIND SPEED
Start 5-10 End ✓

WIND DIRECTION
Start SW End ✓

AMBIENT TEMP
Start 85° End ✓

WET BULB TEMP
N/A

PH, percent
N/A



ADDITIONAL INFORMATION
Mr. Halper -

OBSERVATION DATE			START TIME		END TIME
5-11-00			1559		1629
SEC	0	15	30	45	COMMENTS
1	65	65	60	50	Melt shop
2	40	35	25	20	
3	20	15	15	15	
4	15	10	10	5	
5	5	5	10	15	550/24 = 22.92%
6	15	15	15	5	
7	5	5	5	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	15/24 = 0.63
12	0	0	0	0	
13	0	0	0	0	
14	0	10	5	5	
15	5	5	0	0	
16	0	0	0	0	
17	0	0	0	0	55/24 = 2.29%
18	0	5	10	10	
19	5	5	5	0	
20	0	0	10	20	
21	10	5	5	0	
22	0	0	0	0	
23	0	0	0	0	75/24 = 3.13
24	0	0	5	5	
25	10	10	5	5	
26	0	0	5	5	
27	5	5	5	0	
28	0	0	0	0	
29	0	0	0	0	2.29% = 55/24
30	0	0	0	0	

OBSERVER'S NAME (PRINT)
Bryan Brunfield

OBSERVER'S SIGNATURE
Bryan Brunfield

DATE
5-11-00

ORGANIZATION
Environmental Quality Management

CERTIFIED BY
ETA

DATE
3-22-00

CONTINUED ON VEO FORM NUMBER
0605

VISIBLE EMISSION OBSERVATION FOR

No. 6 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard		SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT Same	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start 60°F End ✓	
EMISSION COLOR Start White End ✓	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Same End ✓	
BACKGROUND COLOR Start Same End ✓	SKY CONDITIONS Start Scattered Clouds End ✓
WIND SPEED Start 5-10 End ✓	WIND DIRECTION Start South End ✓
AMBIENT TEMP Start 85° End ✓	WET BULB TEMP N/A
	RH, percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-11-00					START TIME 1629	END TIME 1658 1659
SEC MIN	0	15	30	45	COMMENTS	
1625	0	0	0	0	Melt Shop	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
1634	0	0	0	0		
1635	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	5		
11	5	5	0	0	15/24 = 0.63%	
12	0	0	0	0		
1634	0	0	0	0		
1641	0	0	0	0		
14	0	0	0	0		
15	0	0	5	10	Tap A BB Tap B	
16	5	5	10	15		
17	15	15	15	10	150/24 = 6.25%	
18	10	10	10	15	Tap B BB	
19	20	20	15	15		
20	15	15	15	15		
21	20	20	20	15		
22	15	10	10	10		
23	10	5	5	5	280/24 = 11.67%	
24	5	0	0	0		
25	5	15	15	10		
26	10	5	5	5		
27	5	5	0	0		
28	0	0	0	0		
29	0	0	0	0	95/24 = 3.96%	
30	0	5	5	5		

OBSERVER'S NAME (PRINT) Bryan Brunfield	
OBSERVER'S SIGNATURE Bryan Brunfield	DATE 5-11-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00

CONTINUED ON VEO FORM NUMBER

07

VISIBLE EMISSION OBSERVATION FORM

No. 2 of 10

COMPANY NAME
Kentucky Electric Steel, Inc.

STREET ADDRESS
U.S. 60 West - Coalton

CITY
Ashland

STATE
KY

ZIP
41102

PHONE (KEY CONTACT) Plant
606) 929-1320 Guard

SOURCE ID NUMBER
103_0340_0020

PROCESS EQUIPMENT
Melt Shop

OPERATING MODE
Charge/Melt/Tap

CONTROL EQUIPMENT
Harsell Baghouse

OPERATING MODE
On line

DESCRIBE EMISSION POINT
Same

HEIGHT ABOVE GROUND LEVEL
60'

HEIGHT RELATIVE TO OBSERVER
Start 10' End ✓

DISTANCE FROM OBSERVER
Start 600' End ✓

DIRECTION FROM OBSERVER
Start North End North

DESCRIBE EMISSIONS
Start Lofry End ✓

EMISSION COLOR
Start White End ✓

IF WATER DROPLET PLUME
Attached ☒ N/A Detached ☐

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED
Start Same End ✓

DESCRIBE PLUME BACKGROUND
Start Same End ✓

BACKGROUND COLOR
Start Same End ✓

SKY CONDITIONS
Start Partly Cloudy End ✓

WIND SPEED
Start 1-5 End ✓

WIND DIRECTION
Start South End ✓

AMBIENT TEMP
Start 85° End ✓

WET BULB TEMP
N/A

RH, percent
N/A

SOURCE LAYOUT SKETCH

Draw North Arrow

Observer's Position

Sun Location Line

140°

ADDITIONAL INFORMATION
Lester Helper -

OBSERVATION DATE					START TIME	END TIME
5-11-00					1659	1729
SEC	0	15	30	45	COMMENTS	
1659	5	5	5	5	Melt Shop	
2	5	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0	25/24 = 1.04%	
6	0	0	0	0		
7	0	10	10	15		
8	15	10	5	5		
9	5	0	0	0		
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0	75/24 = 3.13%	
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0	40/24 = 1.67%	
18	0	10	15	15	Change B	
19	10	10	10	10		
20	5	5	5	5		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0	60/24 = 2.50%	
24	0	0	0	0		
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0	0/24 = 0%	
30	0	0	0	0		

OBSERVER'S NAME (PRINT)
Bryan Brumfield

OBSERVER'S SIGNATURE
Bryan Brumfield

DATE
5-11-00

ORGANIZATION
Environmental Quality Management

CERTIFIED BY
ETA

DATE
3-22-00

VISIBLE EMISSION OBSERVATION FORM

No. 8 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard	SOURCE ID NUMBER 103-0340-0020	

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT <u>Same</u>	
HEIGHT ABOVE GROUND LEVEL <u>60'</u>	HEIGHT RELATIVE TO OBSERVER Start <u>10'</u> End ☒
DISTANCE FROM OBSERVER Start <u>600'</u> End ☒	DIRECTION FROM OBSERVER Start <u>North</u> End <u>North</u>

DESCRIBE EMISSIONS Start <u>White</u> End ☒	
EMISSION COLOR Start <u>Leaky</u> End ☒	IF WATER DROPLET PLUME Attached ☒ <u>N/A</u> Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>Same</u> End ☒	

DESCRIBE PLUME BACKGROUND Start <u>Same</u> End ☒	
BACKGROUND COLOR Start <u>Same</u> End ☒	SKY CONDITIONS Start <u>Scattered</u> End <u>Broken</u>
WIND SPEED Start <u>1-5</u> End <u>1-10 MPH</u>	WIND DIRECTION Start <u>South</u> End <u>SE</u>
AMBIENT TEMP Start <u>85'</u> End ☒	WET BULB TEMP <u>N/A</u>
	RH, percent <u>N/A</u>

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION <u>1st Helper -</u> <u>Melter -</u>
--

OBSERVATION DATE 5-11-00				START TIME 1729	END TIME 1859
SEC	0	15	30	45	COMMENTS
1	0	0	0	0	Melt Shop
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	5	15	Charge B
15	15	10	35	50	
16	40	40	30	20	
17	20	15	10	10	$345/24 = 14.38\%$
18	5	5	10	10	
19	10	10	15	15	
20	10	5	5	5	
21	5	0	0	0	
22	0	0	0	10	
23	20	35	30	25	$245/24 = 10.21\%$
24	15	15	10	5	
25	5	5	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	5	10	10	
29	5	5	0	0	$45/24 = 1.88\%$
30	0	0	0	0	

OBSERVER'S NAME (PRINT) <u>Bryan Brunfield</u>	
OBSERVER'S SIGNATURE <u>Bryan Brunfield</u>	DATE <u>5-11-00</u>
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE <u>3-22-00</u>

CONTINUED ON VEO FORM NUMBER

09

SIBLE EMISSION OBSERVATION FORM

No. 9 of 10

COMPANY NAME Kentucky Electric Steel, Inc.	
STREET ADDRESS U.S. 60 West - Coalton	
CITY Ashland	STATE KY
ZIP 41102	
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard	SOURCE ID NUMBER 103-0340-0020
PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line
DESCRIBE EMISSION POINT Middle of Melt shop	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End ✓	DIRECTION FROM OBSERVER Start North End North
DESCRIBE EMISSIONS Start <u>Leaky</u> End ✓	
EMISSION COLOR Start <u>White</u> End ✓	IF WATER DROPLET PLUME Attached () <u>N/A</u> Detached ()
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>Same</u> End ✓	
DESCRIBE PLUME BACKGROUND Start <u>Trees</u> End ✓	
BACKGROUND COLOR Start <u>Green</u> End ✓	SKY CONDITIONS Start <u>Broke</u> End ✓
WIND SPEED Start <u>1-10 MPH</u> End ✓	WIND DIRECTION Start <u>South-east</u> End <u>SE</u>
AMBIENT TEMP Start <u>85°</u> End <u>80°</u>	WET BULB TEMP <u>N/A</u>
	RH, percent <u>N/A</u>
Stack with Plume Start End SOURCE LAYOUT SKETCH 1802 1800-1801	
ADDITIONAL INFORMATION 57 Helper-	

OBSERVATION DATE 5-11-00		START TIME 1759		END TIME	
SEC	0	15	30	45	COMMENTS
MIN					
1759	0	0	0	0	Melt shop
2	0	10	10	5	
3	5	5	0	0	
4	0	0	0	10	
5	20	20	30	15	175/24 = 7.29%
6	15	15	15	10	
7	10	5	5	5	
8	5	0	0	0	
9	0	5	5	10	
10	10	10	5	5	
11	5	5	5	0	135/24 = 5.63%
12	0	15	15	10	
13	10	15	15	15	
14	20	20	15	15	
15	15	10	10	15	
16	15	15	10	10	
17	10	10	5	5	270/24 = 11.25%
18	5	5	5	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	
OBSERVER'S NAME (PRINT) Bryan Brunfield					
OBSERVER'S SIGNATURE Bryan Brunfield					DATE 5-11-00
ORGANIZATION Environmental Quality Management					
CERTIFIED BY ETA					DATE 3-22-00

VISIBLE EMISSION OBSERVATION FORM

No. 12 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard		SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT West end of Melt Shop	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 100' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start Lifting End ✓	
EMISSION COLOR Start White End ✓	IF WATER DROPLET PLUME Attached () N/A Detached ()
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Trees End ✓	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Broken End ✓
WIND SPEED Start 1-10 mph End ✓	WIND DIRECTION Start SE End ✓
AMBIENT TEMP Start 80° End ✓	WET BULB TEMP N/A
	REL. percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION 1st Helper -
--

OBSERVATION DATE 5-11-00		START TIME 1829		END TIME 1859	
SEC	0	15	30	45	COMMENTS
MIN					
1829	0	0	10	15	Tap A Melt Shop
2	15	10	10	5	
3	5	5	5	5	
4	5	10	10	15	
5	25	20	15	15	255/24 = 10.63%
1834	10	10	15	20	
1835	25	25	20	15	
6	15	10	5	5	
7	5	5	5	0	
8	0	0	0	0	
9	0	0	0	0	135/24 = 5.63%
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	
19	0	0	0	0	
20	0	0	10	15	
21	10	10	5	5	
22	5	0	0	5	
23	5	10	10	5	105/24 = 4.38%
24	5	5	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	

OBSERVER'S NAME (PRINT) Bryan Brunfield	
OBSERVER'S SIGNATURE Bryan Brunfield	DATE 5-11-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00

VISIBLE EMISSION OBSERVATION FORM

No. 1 of 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust <u>Roof Monitor EAST END OF Building</u>	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <u>COFFING</u> End ✓	
EMISSION COLOR Start <u>White</u> End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Monitor</u> End	

DESCRIBE PLUME BACKGROUND Start <u>BAGHOUSE/TREES</u> End ✓	
BACKGROUND COLOR Start <u>Gray</u> End ✓	SKY CONDITIONS Start <u>Clear</u> End
WIND SPEED Start <u>4-6 mph</u> End ✓	WIND DIRECTION Start <u>W</u> End <u>From</u>
AMBIENT TEMP Start <u>70</u> End ✓	WET BULB TEMP <u>NA</u> RH, percent <u>NA</u>



ADDITIONAL INFORMATION <u>Lot Helper - Jim Hall Woody Hill</u> <u>Melter - Bruce Moore</u>
--

OBSERVATION DATE <u>5/12/00</u>					START TIME <u>0715</u>	END TIME <u>1121</u>
SEC MIN	0	15	30	45	COMMENTS	
1	0	0	0	0		
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
6	0	0	0	0	<u>avg 0/24 = 0%</u>	
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0	<u>avg 0/24 = 0%</u>	
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	10	<u>TAP A</u>	
17	0	0	0	10		
18	10	5	5	0	<u>avg 30/24 = 1.25%</u>	
19	0	0	0	0	<u>end tap</u>	
20	0	0	0	0		
21	0	10	0	0	<u>change A</u>	
22	0	5	5	0		
23	5	5	0	0		
24	5	0	0	0	<u>avg 25/24 = 1.04%</u>	
25	0	10	5	5		
26	0	10	5	5		
27	5	5	5	0		
28	0	0	0	0		
29	0	0	10	15	<u>Change B avg 10/24 = 0.42%</u>	
30	35	35	35	35	<u>end change B 8.75%</u>	

OBSERVER'S NAME (PRINT) <u>George Hensley</u>	
OBSERVER'S SIGNATURE <u>George Hensley</u>	DATE <u>5/12/00</u>
ORGANIZATION <u>Environmental Quality Management</u>	
CERTIFIED BY <u>ETA</u>	DATE <u>3/29/00</u>
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 2 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT

OF Building

HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS

Start LOFTING End ✓

EMISSION COLOR
Start White End ✓

IF WATER DROPLET PLUME
Attached ☒ NA Detached ☐

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED
Start 5' to 10' Above Melt Shop End

DESCRIBE PLUME BACKGROUND

Start BAGHOUSE/TREES End ✓

BACKGROUND COLOR
Start Green End ✓

WIND SPEED
Start 4-6 mph End ✓

AMBIENT TEMP
Start 20 End ✓

SKY CONDITIONS
Start Overcast End ✓

WIND DIRECTION
Start W End

WET BULB TEMP
NA

RH. percent
NA

SOURCE LAYOUT SKETCH

Draw North Arrow

Stack with Plume (X)

Sun (circle with dot)

Wind (arrow)

MCH SHOP

Observer's Position

Sun Location Line

140°

ADDITIONAL INFORMATION

1st Helper - Jim Hall Wally Hall

Melter - Bruce

OBSERVATION DAY					START TIME	END TIME
5/12/00					0715	1121
SEC	0	15	30	45	COMMENTS	
1	35	40	35	35		
2	30	30	30	25		
3	25	20	20	15		
4	15	10	20	25		
5	20	5	5	5		
6	5	5	0	0	avg ⁴⁵⁵ / 24 = 18.96	
7	0	30	30	40		
8	35	25	20	20		
9	10	0	0	0		
10	10	10	10	10	end change A	
11	10	0	0	0		
12	0	0	0	15	avg ²⁷⁸ / 24 = 11.46	
13	15	10	0	0		
14	0	15	10	10		
15	10	5	0	0		
16	0	0	0	0		
17	0	0	0	0		
18	0	0	0	0	avg ⁷⁵ / 24 = 3.13	
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0		
24	0	0	0	0	avg ⁰ / 24 = 0%	
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0		
30	0	0	0	0	avg ⁰ / 24 = 0%	

OBSERVER'S NAME (PRINT)
George Hensley

OBSERVER'S SIGNATURE
George Hensley

DATE
5/12/00

ORGANIZATION
Environmental Quality Management

CERTIFIED BY
ETA

DATE
3/29/00

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 3 of 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust <u>Roof Manifold EAST END OF Building</u>	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <u>COFTing</u> End -	
EMISSION COLOR Start <u>White</u> End -	IF WATER DROPLET PLUME Attached () <u>NA</u> Detached ()
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Manifold End</u>	

DESCRIBE PLUME BACKGROUND Start <u>BAGHOUSE/TREES</u> End ✓	
BACKGROUND COLOR Start <u>Brown</u> End ✓	SKY CONDITIONS Start <u>Overcast</u> End ✓
WIND SPEED Start <u>4-6 mph</u> End ✓	WIND DIRECTION <u>FROM</u> Start <u>W</u> End ✓
AMBIENT TEMP Start <u>70</u> End ✓	WET BULB TEMP <u>NA</u> RH. percent <u>NA</u>



OBSERVATION DATE 5/12/00					START TIME 0715	END TIME 1121
SEC MIN	0	15	30	45	COMMENTS	
1	0	0	0	0		
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
6	0	0	0	0	avg 0/24 = 0.20	
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0	avg 0/24 = 0.20	
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	10	25	30	Change A	
17	25	25	10	40	end change	
18	30	25	20	15	avg 25/24 = 10.212	
19	5	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0		
24	0	0	0	0	Avg 5/24 = 0.212	
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0		
30	0	0	0	0	avg 0/24 = 0.20	

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00

ADDITIONAL INFORMATION

Lot Helper - Jim Hall Woody Hill

Melter - Bruce Moore

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 4 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust <u>Roof Monitor EAST END</u> <u>OF Building</u>	
HEIGHT ABOVE GROUND LEVEL <u>60'</u>	HEIGHT RELATIVE TO OBSERVER Start <u>10'</u> End <u>✓</u>
DISTANCE FROM OBSERVER Start <u>600'</u> End <u>600'</u>	DIRECTION FROM OBSERVER Start <u>North</u> End <u>North</u>

DESCRIBE EMISSIONS Start <u>LOFTING</u> End <u>✓</u>	
EMISSION COLOR Start <u>White</u> End <u>✓</u>	IF WATER DROPLET PLUME Attached <u>✓</u> <u>NA</u> Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Monitor</u> End <u>✓</u>	

DESCRIBE PLUME BACKGROUND Start <u>BAGHOUSE/TREES</u> End <u>✓</u>	
BACKGROUND COLOR Start <u>Clear</u> End <u>✓</u>	SKY CONDITIONS Start <u>Overcast</u> End <u>✓</u>
WIND SPEED Start <u>6-8 mph</u> End <u>✓</u>	WIND DIRECTION Start <u>W</u> End <u>From</u>
AMBIENT TEMP Start <u>72</u> End <u>✓</u>	WET BULB TEMP <u>NA</u>
	RH. percent <u>NA</u>

Stack with Plume

Sun

Wind

SOURCE LAYOUT SKETCH

Observer's Position

Sun Location Line

Draw North Arrow

ADDITIONAL INFORMATION <u>Lot Helper - Jim Hall, Woody Hill</u> <u>Melter - Bruce Ward</u>	
--	--

OBSERVATION DATE <u>5/12/00</u>		START TIME <u>0715</u>		END TIME <u>1121</u>	COMMENTS
SEC MIN	0	15	30	45	
1	15	15	15	20	TAP B
2	15	15	20	20	
3	20	20	25	30	end tap B
4	25	25	30	25	
5	25	25	25	20	thru B
6	15	10	10	5	avg 40/24 = 19.58
7	0	0	0	10	Charge A
8	0	10	10	5	
9	0	0	0	0	end Charge A
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	avg 35/24 = 1.469
13	0	0	0	10	Charge B
14	0	0	0	0	
15	10	15	15	0	end Charge B
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	avg 40/24 = 1.679
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	10	0	0	0	
23	0	0	0	10	
24	0	0	0	0	avg 20/24 = 0.833
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	avg 0/24 = 0%

OBSERVER'S NAME (PRINT) <u>George Hensley</u>	
OBSERVER'S SIGNATURE <u>George Hensley</u>	DATE <u>5/12/00</u>
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE <u>3/29/00</u>
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 5 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust <u>Roof Monitor EAST END</u> <u>OF Building</u>	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <u>COFFING</u> End ✓	
EMISSION COLOR Start <u>White</u> End ✓	IF WATER DROPLET PLUME Attached () <u>NA</u> Detached ()
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Monitor</u> End	

DESCRIBE PLUME BACKGROUND Start <u>BAGHOUSE TREES</u> End ✓	
BACKGROUND COLOR Start <u>Green</u> End ✓	SKY CONDITIONS Start <u>Overcast</u> End ✓
WIND SPEED Start <u>6-8 mph</u> End ✓	WIND DIRECTION Start <u>W</u> End ✓
AMBIENT TEMP Start <u>72</u> End	WET BULB TEMP <u>NA</u>
	RH, percent <u>NA</u>

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH
---------------------------------	--------------------------

ADDITIONAL INFORMATION 1st Helper - <u>Jim Hall Woody Hill</u> Melter - <u>Prince Marshall</u>	
--	--

OBSERVATION DATE 5/12/00		START TIME 0715		END TIME 1121	
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	avg 0/24 = 0.00
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	10	10	
11	10	10	10	5	
12	0	0	0	0	avg 55/24 = 2.29
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	10	10	15	change B avg 15/24 = 0.625
18	25	30	30	40	end change
19	45	45	35	40	
20	40	30	25	20	
21	20	15	15	15	
22	15	10	10	5	
23	0	0	0	0	
24	5	5	5	10	avg 410/24 = 17.08
25	15	15	15	20	
26	25	25	25	20	
27	10	10	5	0	
28	10	10	10	5	
29	0	0	5	5	
30	0	0	10	0	avg 240/24 = 10.0

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00

CONTINUED ON VEO FORM NUMBER	
------------------------------	--

VISIBLE EMISSION OBSERVATION FORM

No. 6 of 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320	SOURCE ID NUMBER 103-0340-0020	

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust ROOF MANITON EAST END OF Building	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS	
Start COFFING	End ✓
EMISSION COLOR Start White End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Manifold End	

DESCRIBE PLUME BACKGROUND	
Start BAGHOUSE/TREES	End ✓
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start broken End Scattered
WIND SPEED Start 10-12 mph End ✓	WIND DIRECTION Start SW End From
AMBIENT TEMP Start 75 End ✓	WET BULB TEMP NA
	RH, percent NA



OBSERVATION DAY 5/12/00		START TIME 0715		END TIME 1121	
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	5	10	0	
3	15	20	35	35	
4	35	40	35	40	
5	40	40	40	35	
6	35	30	25	30	avg 545/24 = 22.71
7	30	30	25	20	
8	20	20	5	15	
9	10	10	10	5	
10	15	20	20	20	
11	15	20	20	20	TAP A
12	20	20	15	15	avg 429/24 = 17.50
13	10	10	10	10	
14	5	0	0	0	
15	0	0	0	0	end top
16	10	0	0	0	change 100
17	0	0	0	0	end change
18	0	0	0	0	avg 45/24 = 1.88%
19	0	0	0	0	change A
20	0	0	0	15	
21	10	10	10	20	
22	5	5	10	15	
23	20	25	25	25	
24	20	20	15	15	avg 265/24 = 11.04%
25	25	20	20	15	
26	10	15	15	15	end change
27	15	15	10	10	
28	10	10	5	0	
29	0	0	0	0	
30	0	0	0	0	avg 210/24 = 8.75%

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE <i>George Hensley</i>	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00

ADDITIONAL INFORMATION
1st Helper - Jim Hall Woody Hall
Melter - Bruce Moore

VISIBLE EMISSION OBSERVATION FORM

No. 2 of 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust <u>Roof Monitor East End</u> <u>of Building</u>	
HEIGHT ABOVE GROUND LEVEL <u>60'</u>	HEIGHT RELATIVE TO OBSERVER Start <u>10'</u> End <u>✓</u>
DISTANCE FROM OBSERVER Start <u>600'</u> End <u>600'</u>	DIRECTION FROM OBSERVER Start <u>North</u> End <u>North</u>

DESCRIBE EMISSIONS Start <u>Cooling</u> End <u>✓</u>	
EMISSION COLOR Start <u>White</u> End <u>✓</u>	IF WATER DROPLET PLUME Attached <u>✓</u> Detached <u>□</u>
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Monitor</u> End <u>✓</u>	

DESCRIBE PLUME BACKGROUND Start <u>BAGHOUSE / TREES</u> End <u>✓</u>	
BACKGROUND COLOR Start <u>Green</u> End <u>✓</u>	SKY CONDITIONS Start <u>Scattered</u> End <u>✓</u>
WIND SPEED Start <u>8-10</u> End <u>✓</u>	WIND DIRECTION Start <u>SW</u> End <u>✓</u>
AMBIENT TEMP Start <u>75</u> End <u>✓</u>	WET BULB TEMP <u>NA</u>
	RH, percent <u>NA</u>



ADDITIONAL INFORMATION <u>1st Helper - Jim Hall Wood, Hill</u> <u>Melter - Bruce Moore</u>	
--	--

OBSERVATION DATE <u>5/12/00</u>					START TIME <u>0715</u>	END TIME <u>1121</u>
SEC	0	15	30	45	COMMENTS	
1	0	0	0	0		
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
6	0	0	0	0	<u>avg 0/24 = 0.70</u>	
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0	<u>avg 0/24 = 0.90</u>	
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	<u>10</u>	<u>15</u>	<u>25</u>	<u>25</u>	<u>TAP B</u>	
18	<u>20</u>	<u>20</u>	<u>25</u>	<u>25</u>	<u>End TAP</u>	
19	<u>25</u>	<u>30</u>	<u>30</u>	<u>25</u>	<u>avg 15/24 = 6.46%</u>	
20	<u>25</u>	<u>15</u>	<u>15</u>	<u>5</u>		
21	<u>5</u>	<u>0</u>	<u>0</u>	<u>0</u>		
22	<u>10</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>Check B</u>	
23	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>		
24	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>avg 12/24 = 5.04%</u>	
25	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>		
26	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>		
27	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>		
28	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>		
29	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>		
30	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>avg 0/24 = 0.90</u>	

OBSERVER'S NAME (PRINT) <u>George Hensley</u>	
OBSERVER'S SIGNATURE <u>George Hensley</u>	DATE <u>5/12/00</u>
ORGANIZATION <u>Environmental Quality Management</u>	
CERTIFIED BY <u>ETA</u>	DATE <u>3/29/00</u>
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 8 of 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust ROOF MANIFOLD EAST END OF Building	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start Leaking End ✓	
EMISSION COLOR Start White End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Manifold End	

DESCRIBE PLUME BACKGROUND Start BAGHOUSE/TREES End ✓	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 10-12 mph End ✓	WIND DIRECTION FROM Start SW End ✓
AMBIENT TEMP Start 80 End 84	WET BULB TEMP NA
	REL. percent NA

Stack with Plume  Sun  Wind 	SOURCE LAYOUT SKETCH 
--	---

ADDITIONAL INFORMATION Lot Helper - Jim Hall Woody Hill Melter - Bruce Moore	
--	--

OBSERVATION DATE 5/12/00					START TIME 0715	END TIME 1121
SEC MIN	0	15	30	45	COMMENTS	
1	0	0	0	0		
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
6	0	0	0	0	avg 0/24 = 0%	
7	0	0	0	0		
8	10	0	0	0	Change A	
9	0	0	0	0		
10	0	0	0	0	end change	
11	0	0	0	0		
12	0	0	0	0	avg 0/24 = 0%	
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	10	0	0	Change B	
18	0	0	0	0	end Change B	
19	0	0	0	0	avg 0/24 = 0%	
20	0	0	0	0		
21	10	10	10	10		
22	5	0	0	0		
23	0	0	0	0		
24	0	0	0	0	avg 40/24 = 1.67%	
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0		
30	0	0	10	10	avg 20/24 = 0.8%	

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 9 OF 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust <u>Roof Manifold EAST END OF Building</u>	
HEIGHT ABOVE GROUND LEVEL <u>60'</u>	HEIGHT RELATIVE TO OBSERVER Start <u>10'</u> End <u>✓</u>
DISTANCE FROM OBSERVER Start <u>600'</u> End <u>600'</u>	DIRECTION FROM OBSERVER Start <u>North</u> End <u>North</u>

DESCRIBE EMISSIONS Start <u>None</u> End <u>✓</u>	
EMISSION COLOR Start <u>None</u> End <u>✓</u>	IF WATER DROPLET PLUME Attached <u>✓</u> <u>NA</u> Detached <u>□</u>
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Manifold</u> End <u>✓</u>	

DESCRIBE PLUME BACKGROUND Start <u>BAGHOUSE/TREES</u> End <u>✓</u>	
BACKGROUND COLOR Start <u>Brown</u> End <u>✓</u>	SKY CONDITIONS Start <u>Scattered</u> End <u>✓</u>
WIND SPEED Start <u>10-12 mph</u> End <u>✓</u>	WIND DIRECTION Start <u>SW</u> End <u>✓</u>
AMBIENT TEMP Start <u>84</u> End <u>✓</u>	WET BULB TEMP <u>NA</u>
	RH, percent <u>NA</u>



OBSERVATION DATE 5/12/00					START TIME 0715	END TIME 1121
SEC MIN	0	15	30	45	COMMENTS	
1	0	0	0	0		
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
6	0	0	0	0	Avg 0/24 = 0.20	
7					end Run	
8						
9						
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VEO FORM NUMBER	

ADDITIONAL INFORMATION 1st Helper - Jim Hall Noddy Hill Melter - Bruce Moore
--

2



VISIBLE EMISSION OBSERVATION FORM

No. 1 OF 9


COMPANY NAME Kentuck Electric Steel, Inc.		
U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust ROOF MANIFOLD EAST END OF Building	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start LIFTING End ✓	
EMISSION COLOR Start white End ✓	IF WATER DROPLET PLUME Attached? NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Manifold End	

DESCRIBE PLUME BACKGROUND Start BAG HOUSE / TREES End ✓	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Broken End ✓
WIND SPEED Start 8-10 mph End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 85 End ✓	WET BULB TEMP Start NA End NA

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow 
---------------------------------	---

ADDITIONAL INFORMATION 1st Helper - Jim Hall Hardy Hill Melter - Bruce Moore
--

OBSERVATION DATE 5/12/00					START TIME 1218	END TIME
SEC MIN	0	15	30	45	COMMENTS	
1	5	15	15	15	Only 20 sec white	
2	30	30	30	30	from where tap on B	
3	35	35	40	40	comes out sometime during on top B	
4	40	40	35	35		
5	30	30	30	25	655/1 = 27.29	
6	25	15	15	15	avg 1/4 = 27.29	
7	15	15	10	5		
8	5	5	5	5		
9	5	0	0	0		
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0	avg 70/24 = 2.922	
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	10	5	10	1.5	Change A	
17	5	5	5	5	and change	
18	0	0	5	5	avg 70/24 = 2.922	
19	5	10	15	15		
20	20	20	20	20		
21	20	20	20	15		
22	15	15	15	10		
23	15	15	10	20		
24	20	20	20	15	avg 390/24 = 16.25	
25	15	15	5	5		
26	5	5	10	0		
27	0	0	5	15		
28	15	15	10	5		
29	10	10	10	15	avg 230/24 = 9.58	
30	15	10	15	30	TAP B	

OBSERVER'S NAME (PRINT) George Hensley		DATE 5/12/00
OBSERVER'S SIGNATURE George Hensley		
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 3/29/00
CONTINUED ON VEO FORM NUMBER		

VISIBLE EMISSION OBSERVATION FORM

No. 2 OF 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust <u>Roof Monitor EAST END OF Building</u>	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <u>LOFTING</u> End ✓	
EMISSION COLOR Start <u>White</u> End ✓	IF WATER DROPLET PLUME Attached () <u>NA</u> Detached ()
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Monitor</u> End	

DESCRIBE PLUME BACKGROUND Start <u>BAG HOUSE / TREES</u> End ✓	
BACKGROUND COLOR Start <u>Green</u> End ✓	SKY CONDITIONS Start <u>Scattered</u> End ✓
WIND SPEED Start <u>10-12 mph</u> End ✓	WIND DIRECTION Start <u>SW</u> End ✓
AMBIENT TEMP Start <u>85</u> End ✓	WET BULB TEMP <u>NA</u>
	RH. percent <u>NA</u>

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow 
---------------------------------	---

OBSERVATION DATE 5/12/00					START TIME 1218	END TIME
SEC MIN	0	15	30	45	COMMENTS	
1	25	25	25	30		
2	30	25	25	25	and top B	
3	30	25	25	20		
4	15	15	10	5		
5	5	10	5	5		
6	0	0	0	0	avg 380/24 = 15.83	
7	0	0	0	0	change B	
8	0	25	35	30		
9	30	25	30	30	end change B	
10	30	35	35	30		
11	25	25	20	20		
12	10	10	5	5	avg 455/24 = 18.96	
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0		
18	0	0	0	0	avg 0/24 = 0%	
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0		
24	0	0	0	0	avg 0/24 = 0%	
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0		
30	0	0	0	0	avg 0/24 = 0%	

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00

ADDITIONAL INFORMATION 1st Helper - Jim Hall waddy fill Melter - Bruce more

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 3 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320	SOURCE ID NUMBER 103-0340-0020	
Guard		

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust ROOF MONITOR EAST END OF Building	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start COPTING End ✓	
EMISSION COLOR Start White End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED SUN 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND Start BAGHOUSE TREES End ✓	
BACKGROUND COLOR Start Gray End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 10-12 End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 87 End ✓	WET BULB TEMP NA
	RH. percent NA

Stack with Plume

Sun

Wind

SOURCE LAYOUT SKETCH

Observer's Position

Sun location line

Draw North Arrow

ADDITIONAL INFORMATION 1st Helper - Jamell Hardy Hail	
Melter - Bruce Moore	

OBSERVATION DATE			START TIME		END TIME
5/12/00			1218		
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	avg 0/24 = 0%
7	0	0	0	0	
8	0	0	0	10	top A
9	15	15	10	5	
10	10	5	0	10	
11	5	5	0	0	
12	0	0	10	0	end top A avg 80/24 = 3.3%
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	avg 0/24 = 0%
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	20	35	35	30	step B
24	30	25	30	20	avg 225/24 = 9.38%
25	25	25	30	20	
26	20	20	15	20	
27	120	20	15	15	change B
28	20	15	15	10	
29	10	10	10	15	
30	15	15	15	5	avg 400/24 = 16.67%

OBSERVERS NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VEO FORM NUMBER	

..VISIBLE EMISSION OBSERVATION FORM

No. 4 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust <u>Roof Monitor EAST END</u> <u>of Building</u>	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER LO' Ed ✓
DISTANCE FROM OBSERVER Start 600' W 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <u>CORTING</u> End	
EMISSION COLOR Start <u>white</u> End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Monitor</u> End	

DESCRIBE PLUME BACKGROUND Start <u>BAGHOUSE/TREES</u> End ✓		
BACKGROUND COLOR Start <u>Green</u> End ✓	SKY CONDITIONS Start <u>Scattered</u> End ✓	
WIND SPEED Start <u>8-10 mph</u> End ✓	WIND DIRECTION <u>From</u> Start <u>SW</u> End ✓	
AMBIENT TEMP Start <u>88</u> End ✓	WET BULB TEMP NA	RH. percent NA

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION 1st Helper - <u>Jim Hall</u> <u>Wally Hill</u> Melter - <u>Bruce Moore</u>	
---	--

OBSERVATION DATE 5/12/00					START TIME 1218	END TIME
SEC	0	15	30	45	COMMENTS	
1	10	5	5	10		
2	10	5	0	0		
3	0	0	0	10		
4	10	10	15	15		
5	20	20	15	15	end change B	
6	10	10	5	5	avg 205/24 = 8.54%	
7	5	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0	avg 5/24 = 0.21%	
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	10		
16	10	15	20	20		
17	20	20	15	15	stop in B	
18	15	15	20	25	avg 220/24 = 9.17%	
19	30	30	35	40		
20	40	40	50	40		
21	40	30	40	30		
22	30	30	30	30		
23	25	25	25	25		
24	15	10	10	10	avg 210/24 = 29.58%	
25	5	5	10	15	Change A	
26	15	20	20	20		
27	20	25	25	20	end change A	
28	15	15	15	10		
29	10	20	20	10		
30	20	15	15	15	avg 310/24 = 15.42%	

OBSERVER'S NAME (PRINT) George Hensley		DATE 5/12/00
OBSERVER'S SIGNATURE <i>George Hensley</i>		
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 3/29/00
CONTINUED ON VEO FORM NUMBER		

VISIBLE EMISSION OBSERVATION FORM

No. 5 OF 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust ROOF MANIFOLD EAST END OF Building	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End 600'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start COPTING End ✓	
EMISSION COLOR Start White End ✓	IF WATER DROPLET PLUME Attached ☒ Attached ☐ Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Manifold End	

DESCRIBE PLUME BACKGROUND Start BAGHOUSE/TREES End ✓		
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Scattered End ✓	
WIND SPEED Start 10-12 mph End ✓	WIND DIRECTION Start SW End ✓	
AMBIENT TEMP Start 88 End ✓	WET BULB TEMP Nil-	REL. percent NA



ADDITIONAL INFORMATION 1st Helper - Jim Hall Woody Hill Melter - Bruce Moore
--

OBSERVATION DATA					START TIME	END TIME
5/12/00						
SEC	0	15	30	45	COMMENTS	
MIN						
1	10	10	10	15		
2	15	15	15	15		
3	15	15	15	10		
4	5	15	15	10		
5	10	10	10	15		
6	15	15	15	5	avg 310/24 = 12.92%	
7						
8						
9						
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VED FORM NUMBER	

VISIBLE EMISSION OBSERVATION FOR

No. 6 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard		SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harcell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT Middle, East + West end of Meltshop	
HEIGHT ABOVE LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <u>Top of Baghouse</u> End	
EMISSION COLOR Start <u>White</u> End ✓	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 10' out to above monitor End ✓	

DESCRIBE PLUME BACKGROUND Start <u>Baghouse + Trees</u> End ✓	
BACKGROUND COLOR Start <u>Brown + Green</u> End ✓	SKY CONDITIONS Start <u>Scattered</u> End
WIND SPEED Start <u>7-15 MPH</u> End ✓	WIND DIRECTION Start <u>Southwest</u> End ✓
AMBIENT TEMP Start <u>85-90</u> End ✓	WET BULB TEMP N/A
	RH, percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION 1st Helper -
--

OBSERVATION DATE				START TIME	END TIME	
5-12-90				1420	1450	
MIN	SEC	0	15	30	45	COMMENTS
1	1420	15	15	15	15	Melt shop
2		15	15	15	15	
3		15	15	15	15	
4		15	15	15	15	
5		15	20	20	30	420/24 = 17.50%
6	1425	30	25	20	20	
7	1426	20	15	15	15	
8		15	15	15	15	
9		15	15	15	15	
10		15	15	15	10	
11		10	10	10	10	340/24 = 14.17%
12	1431	15	15	15	15	
13	1432	15	15	15	10	
14		10	10	10	10	
15		10	10	10	10	
16		10	10	10	10	Tap B
17		15	20	20	20	310/24 = 12.92%
18	1437	15	15	15	15	
19	1438	15	15	15	15	
20		15	10	10	10	End Tap
21		10	10	10	10	
22		10	10	10	10	
23		10	10	10	5	240/24 = 10.00%
24	1443	5	5	5	5	Charge A
25		10	10	15	15	
26		15	10	10	10	
27		10	10	10	10	
28		10	10	10	10	
29		10	10	10	10	240/24 = 10.00%
30		10	5	5	5	

OBSERVER'S NAME (PRINT) Bryan Brunfield	
OBSERVER'S SIGNATURE Bryan Brunfield	DATE 5-12-90
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 2 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard		SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT
East end + Middle of Melt shop

HEIGHT ABOVE GROUND LEVEL <u>60'</u>	HEIGHT RELATIVE TO OBSERVER Start <u>10'</u> End ☒
DISTANCE FROM OBSERVER Start <u>600'</u> End ☒	DIRECTION FROM OBSERVER Start <u>North</u> End <u>North</u>

DESCRIBE EMISSIONS
Start with Loke End ☒

EMISSION COLOR Start <u>White</u> End ☒	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>10' out above main</u> End ☒	

DESCRIBE PLUME BACKGROUND
Start Same End ☒

BACKGROUND COLOR Start <u>Same</u> End ☒	SKY CONDITIONS Start <u>Scattered</u> End ☒
WIND SPEED Start <u>7-15</u> End ☒	WIND DIRECTION Start <u>SW</u> End ☒
AMBIENT TEMP Start <u>85-90</u> End ☒	WET BULB TEMP <u>N/A</u>
	REL. percent <u>N/A</u>

SOURCE LAYOUT SKETCH Draw North Arrow

Stack with Plume
Sun
Wind

X Emission Point

Melt Shop

Observer's Position

140°

Sun Location Line

ADDITIONAL INFORMATION
1st Helper -

OBSERVATION DATE 5-12-09		START TIME 1450				END TIME 1520
SEC MIN	0	15	30	45	COMMENTS	
1450	5	5	5	0	Melt shop	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0	$35/24 = 2.29\%$	
1455	0	0	15	25	Charge B	
1456	25	30	30	30	End Charge	
6	30	30	25	25		
7	25	20	20	15		
8	15	15	15	15		
11	15	15	10	10	$45/24 = 18.75\%$	
12	10	10	10	5		
13	5	5	5	5		
14	5	5	5	5		
15	5	0	0	0		
16	0	0	0	0		
17	0	0	0	0	$45/24 = 1.88$	
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0	$0/24 = 0\%$	
24	0	0	0	0		
25	0	0	0	0		
26	5	10	10	5		
27	5	5	0	0		
28	0	0	0	0		
29	0	0	10	10	$20/24 = 3.75\%$	
30	5	5	10	10		

OBSERVER'S NAME (PRINT) Bryan Brunfield	
OBSERVER'S SIGNATURE Bryan Brunfield	DATE 5-12-09
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00

VISIBLE EMISSION OBSERVATION FORM

No. 8 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard		SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT Middle, East + West end of Melt shop	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start 2.0 ft/m End ✓	
EMISSION COLOR Start White End ✓	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Same End ✓	
BACKGROUND COLOR Start Same End ✓	SKY CONDITIONS Start Good End ✓
WIND SPEED Start 2-15 End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 85-90 End ✓	WET BULB TEMP N/A RH, percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow
---------------------------------	--

Stack with Plume
Sun
Wind

SOURCE LAYOUT SKETCH
Draw North Arrow

TAPA

X X X X

X Emission Point

⊙ ⊙

Melt Shop

SW

Observer's Position

140°

Sun Location Line

ADDITIONAL INFORMATION L. H. Holper -
--

OBSERVATION DATE 5-12-00					START TIME 1520	END TIME 1550
SEC	0	15	30	45	COMMENTS	
1530	10	10	5	5	Melt shop	
2	5	10	10	10		
3	15	20	20	20		
4	15	15	15	15		
5	15	15	15	15	320/24 = 13.33%	
1535	15	15	15	15		
1536	15	10	10	10		
8	10	10	5	5		
9	5	5	5	5		
10	5	5	5	0		
11	0	0	5	10	175/24 = 7.29%	
1537	10	10	15	15		
1538	15	20	20	15		
14	15	10	10	5		
15	5	5	5	5		
16	5	5	5	5	260/24 = 10.83%	
17	5	10	10	15	Charge B	
1539	15	15	20	20		
1540	20	15	15	15		
20	15	15	10	10		
21	10	10	10	5		
22	5	5	5	5		
23	5	0	0	0	210/24 = 8.75%	
1541	0	10	10	15	Tap A	
1544	15	15	20	20		
26	15	15	10	10		
27	10	10	10	10		
28	10	10	10	10		
29	10	10	5	5	285/24 = 11.88%	
1549	5	15	15	20		

OBSERVER'S NAME (PRINT) Bryan Brumfield	
OBSERVER'S SIGNATURE Bryan Brumfield	DATE 5-12-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00

SIBL EMISSION OBSERVATION FOR

No. 9 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320 Guard	SOURCE ID NUMBER 103-0340-0020	

PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT Middle + East End of Melt Shop

HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start Same End ✓	
EMISSION COLOR Start Same End ✓	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Same End ✓	
BACKGROUND COLOR Start Same End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 7-15 End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 85-90 End ✓	WET BULB TEMP N/A
	REL. percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow
---------------------------------	--

The sketch shows a rectangular building labeled 'Melt Shop' with an 'X' marking the 'Emission Point'. Below the building is a point labeled 'Observer's Position'. A dashed line labeled 'Sun Location Line' extends from the observer's position. An angle of 140° is indicated between the line to the emission point and the sun location line. A north arrow is shown in the top right corner.

ADDITIONAL INFORMATION 1st Helper -
--

OBSERVATION DATE 5-12-90		START TIME 1550				END TIME 1620
SEC MIN	0	15	30	45	COMMENTS	
1	20	25	25	25	Melt Shop	
2	25	25	25	30		
3	35	40	40	40		
4	40	40	40	40		
5	40	35	30	30	755/24 = 31.46%	
6	30	25	25	25		
7	25	25	20	20		
8	20	15	15	15		
9	15	15	10	10		
10	10	10	10	10		
11	10	5	5	5	300/24 = 12.50%	
12	5	5	5	15		
13	15	20	20	20		
14	20	20	20	20		
15	20	20	15	15		
16	15	15	15	15	405/24 = 16.88%	
17	15	15	15	15	Pour back From LMP	
18	15	15	15	15		
19	15	15	15	15		
20	15	15	10	10		
21	10	10	10	5		
22	5	5	5	10		
23	15	15	15	15	280/24 = 11.67%	
24	15	15	15	15		
25	15	20	25	25		
26	25	25	25	25		
27	25	25	25	20		
28	20	15	15	15		
29	15	15	15	15	480/24 = 20.00	
30	15	20	20	20		

OBSERVER'S NAME (PRINT) Bryan Brumfield		DATE 5-12-00
OBSERVER'S SIGNATURE Bryan Brumfield		DATE 3-22-00
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 3-22-00

1

VISIBLE EMISSION OBSERVATION FORM

No. 1 of 1

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant 606) 929-1320 Guard	SOURCE ID NUMBER 103-0340-0020	


PROCESS EQUIPMENT Melt Shop	OPERATING MODE Charge/Melt/Tap
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On line

DESCRIBE EMISSION POINT East, West + middle of Melt Shop	
HEIGHT ABOVE GROUND LEVEL 60'	HEIGHT RELATIVE TO OBSERVER Start 10' End ✓
DISTANCE FROM OBSERVER Start 600' End ✓	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start L. Ferry End	
EMISSION COLOR Start White End	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 10' out + 650' + 100' End ✓

DESCRIBE PLUME BACKGROUND Start Baghouse + Trans End ✓	
BACKGROUND COLOR Start Brown End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 7-15 mph End ✓	WIND DIRECTION Start South West End ✓
AMBIENT TEMP Start 90° End ✓	WET BULB TEMP N/A
	RH, percent N/A



ADDITIONAL INFORMATION St Holper - elver -
--

OBSERVATION DATE 5-12-00					START TIME 081518 1718	END TIME 1742
SEC MIN	0	15	30	45	COMMENTS	
1718	10	10	10	15	Melt shop (600 HP fan turned off)	
2	15	15	15	20	Tap A 1718	
3	25	25	25	25		
4	25	25	25	20	End Tap	
5	20	15	15	25	475/24 = 19.79%	
1722	25	25	25	20		
1724	20	15	15	15		
6	15	15	10	10		
7	10	10	10	10		
10	10	10	10	15	Charge A	
11	15	15	10	10	290/24 = 12.08%	
1729	10	10	10	10	End Charge	
13	10	5	5	10		
1730	10	5	5	10		
14	10	15	20	25		
15	25	15	15	15		
16	10	10	15	20		
17	20	20	20	25	385/24 = 16.04%	
18	25	20	15	15		
19	15	15	20	20		
1736	20	20	25	15		
20	10	5	5	10		
21	10	15	15	20		
22	10	10	15	25	350/24 = 14.58%	
23	15	15	15	15		
24	15	15	15	15		
1742						

OBSERVER'S NAME (PRINT) Bryan Brunfield	
OBSERVER'S SIGNATURE Bryan Brunfield	DATE 5-12-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FC

No. 1 of 1

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT
Baghouse Exhaust

HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ✓
DISTANCE FROM OBSERVER Start 700' End ✓	DIRECTION FROM OBSERVER Start North End ✓

DESCRIBE EMISSIONS

Start None End ✓

EMISSION COLOR
Start N/A End ✓

IF WATER DROPLET PLUME
Attached ☒ N/A Detached ☐

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED
Start 10' out above manway End ✓

DESCRIBE PLUME BACKGROUND

Start Trees End ✓

BACKGROUND COLOR
Start Green End ✓

WIND SPEED
Start 7-15 mph End ✓

WIND DIRECTION
Start Southeast End ✓

AMBIENT TEMP
Start 90° End ✓

WET BULB TEMP
N/A

REL. percent
N/A

SOURCE LAYOUT SKETCH

Stack with Plume

Sun

Wind

Draw North Arrow

Emission Point

Observer's Position

140°

Sun Location Line

OBSERVATION DATE				START TIME	END TIME
5-12-90				1718	1742
SEC	0	15	30	45	COMMENTS
MIN					
1718	0	0	0	0	Baghouse
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	$\%24 = 0\%$
1722	0	0	0	0	
1724	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	$\%24 = 0\%$
1728	0	0	0	0	
1730	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	$\%24 = 0\%$
1735	0	0	0	0	
1736	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	$\%24 = 0\%$
24	0	0	0	0	
1741	0	0	0	0	
25					
1742					
26					
27					
28					
29					
30					
1743					

OBSERVER'S NAME (PRINT)
Bryan Brumfield

OBSERVER'S SIGNATURE
Bryan Brumfield

DATE
5-12-90

ORGANIZATION
Environmental Quality Management

CERTIFIED BY
ETA

DATE
3-22-00

ADDITIONAL INFORMATION
St. Helper

VISIBLE EMISSION OBSERVATION FORM

No. 1 of 10

COMPANY NAME <u>Kentucky Electric Steel, Inc.</u>		
STREET ADDRESS <u>U.S. 60 West - Coalton</u>		
CITY <u>Ashland</u>	STATE <u>KY</u>	ZIP <u>41102</u>
PHONE (KEY CONTACT) <u>(606) 929-1320</u>	Plant <u>Guard</u>	SOURCE ID NUMBER <u>103-0340-0020</u>

PROCESS EQUIPMENT <u>Melt Shop</u>	OPERATING MODE <u>On Line</u>
CONTROL EQUIPMENT <u>Harsell Baghouse</u>	OPERATING MODE <u>On Line</u>

DESCRIBE EMISSION POINT <u>Baghouse Exhaust</u>	
HEIGHT ABOVE GROUND LEVEL <u>75'</u>	HEIGHT RELATIVE TO OBSERVER Start <u>25'</u> End ☒
DISTANCE FROM OBSERVER Start <u>700'</u> End ☒	DIRECTION FROM OBSERVER Start <u>North</u> End ☒

DESCRIBE EMISSIONS Start <u>None</u> End ☒	
EMISSION COLOR Start <u>N/A</u> End ☒	IF WATER DROPLET PLUME Attached ☒ <u>N/A</u> Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>10' out before main stack</u> End ☒	

DESCRIBE PLUME BACKGROUND Start <u>Trees</u> End ☒	
BACKGROUND COLOR Start <u>Green</u> End ☒	SKY CONDITIONS Start <u>Scattered</u> End ☒
WIND SPEED Start <u>5-10 MPH</u> End ☒	WIND DIRECTION Start <u>Southwest</u> End <u>West</u>
AMBIENT TEMP Start <u>80</u> End ☒	WET BULB TEMP <u>N/A</u>
	REL. percent <u>N/A</u>

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION <u>1st Helper -</u> <u>M. L. ...</u>

OBSERVATION DATE <u>5-11-00</u>				START TIME <u>1359</u>	END TIME <u>1429</u>
SEC	0	15	30	45	COMMENTS
MIN					
12:59	0	0	0	0	Baghouse
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	0/24 = 0%
6	0	0	0	0	
7	0	0	0	0	Should have been a
8	0	0	0	0	Melt shop VBS
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	0/24 = 0%
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	0/24 = 0%
18	0	0	0	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	0/24 = 0%
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	

OBSERVER'S NAME (PRINT) <u>Bryan Brumfield</u>	
OBSERVER'S SIGNATURE <u>Bryan Brumfield</u>	DATE <u>5-11-00</u>
ORGANIZATION <u>Environmental Quality Management</u>	
CERTIFIED BY <u>ETA</u>	OFF <u>NNNNNN</u>
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 2 of 10

COMPANY NAME Kentucky Electric Steel, Inc.	
STREET ADDRESS U.S. 60 West - Coalton	
CITY Ashland	STATE KY
ZIP 41102	
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard
SOURCE ID NUMBER 103-0340-0020	

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ☒
DISTANCE FROM OBSERVER Start 700' End ☒	DIRECTION FROM OBSERVER Start North End ☒

DESCRIBE EMISSIONS Start Orange End ☒	
EMISSION COLOR Start Orange End ☒	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ☒	

DESCRIBE PLUME BACKGROUND Start Trans End ☒	
BACKGROUND COLOR Start Green End ☒	SKY CONDITIONS Start Scattered End ☒
WIND SPEED Start 5-10 mph End ☒	WIND DIRECTION Start South End ☒
AMBIENT TEMP Start 80° End ☒	WET BULB TEMP N/A
RH. percent N/A	

Stack with Plume 	SOURCE LAYOUT SKETCH 10 15 X Emission Point Observer's Position 140° Sun Location Line	Draw North Arrow
----------------------	--	----------------------

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-11-00					START TIME 1429	END TIME 1459
SEC	0	15	30	45	COMMENTS	
1929	0	0	0	0	Baghouse	
2	0	0	0	0		
3	0	0	0	0		
4	0	10	0	0		
5	0	0	0	0	10/24 = 0.42%	
1434	0	0	0	0		
7 1435	0	0	0	15		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0	15/24 = 0.63%	
12 1440	0	0	0	0		
13 1441	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0		
18 1446	0	0	0	0		
19 1447	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0		
24 1452	0	0	0	0		
25 1453	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	20	0		
29	0	0	0	0	20/24 = 0.83%	
30 1458	0	0	0	0		

OBSERVER'S NAME (PRINT) Bryan Brumfield	
OBSERVER'S SIGNATURE 	DATE 5-11-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 5-22-00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 3 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ✓
DISTANCE FROM OBSERVER Start 700' End ✓	DIRECTION FROM OBSERVER Start North End ✓

DESCRIBE EMISSIONS Start <u>Leaky</u> End <u>None</u>	
EMISSION COLOR Start <u>Orange</u> End <u>N/A</u>	IF WATER DROPLET PLUME Attached ☒ Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>Same</u> End ✓	

DESCRIBE PLUME BACKGROUND Start <u>Traces</u> End ✓	
BACKGROUND COLOR Start <u>Green</u> End ✓	SKY CONDITIONS Start <u>Scattered</u> End ✓
WIND SPEED Start <u>5-10 mph</u> End ✓	WIND DIRECTION Start <u>South</u> End ✓
AMBIENT TEMP Start <u>80</u> End <u>85</u>	WET BULB TEMP <u>N/A</u>
	RH. percent <u>N/A</u>

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH 10 Draw North Arrow
---------------------------------	---

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-11-00					START TIME 1459	END TIME 1529
SEC MIN	0	15	30	45	COMMENTS	
1459	0	0	0	0	Baghouse	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0	Ø	
1504	0	0	0	0		
1505	0	0	0	25		
8	0	0	0	10		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0	25/24 = 1.04%	
12	0	0	0	0		
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0	Ø	
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0	Ø	
24	0	0	0	0		
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0	Ø	
30	0	0	0	0		

OBSERVER'S NAME (PRINT) Bryan Brumfield		DATE 5-11-00
OBSERVER'S SIGNATURE <i>Bryan Brumfield</i>		DATE 5-11-00
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 3-22-00
CONTINUED ON VEO FORM NUMBER		

VISIBLE EMISSION OBSERVATION F M

No. 4 of 10

COMPANY NAME Kentucky Electric Steel, Inc.	
STREET ADDRESS U.S. 60 West - Coalton	
STATE Ashland	ZIP KY 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT
Baghouse Exhaust

HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ☒
DISTANCE FROM OBSERVER Start 700' End ☒	DIRECTION FROM OBSERVER Start North End ☒

DESCRIBE EMISSIONS	
Start None End ☒	
EMISSION COLOR Start N/A End ☒	IF WATER DROPLET PLUME Attached ☒ Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ☒	

DESCRIBE PLUME BACKGROUND	
Start Fine End ☒	
BACKGROUND COLOR Start Green End ☒	SKY CONDITIONS Start Scattered End ☒
WIND SPEED Start 5-10 End ☒	WIND DIRECTION Start SW End ☒
AMBIENT TEMP Sun 85' End ☒	WET BULB TEMP N/A
	RH, percent N/A

Stack with Plume 	SOURCE LAYOUT SKETCH	Draw North Arrow
Sun 		
Wind 		

OBSERVATION DATE 5-11-00				START TIME 1529	END TIME 1559
SEC	0	15	30	45	COMMENTS
1	0	0	0	0	Baghouse
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	Ø
6	0	0	0	0	
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	Ø
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	Ø
18	0	0	0	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	Ø
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	Ø
30	0	0	0	0	

OBSERVER'S NAME (PRINT) Bryan Brum Field		DATE 5-11-00
OBSERVER'S SIGNATURE 		
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 3-22-01
CONTINUED ON VEO FORM NUMBER		

ADDITIONAL INFORMATION

1st Helper -

M. 1-2-3-

VISIBLE EMISSION OBSERVATION FORM

No. 5 of 12

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ☒
DISTANCE FROM OBSERVER Start 700' End ☒	DIRECTION FROM OBSERVER Start North End ☒

DESCRIBE EMISSIONS	
Start None	End Lat+ig
EMISSION COLOR Start White End Orange	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ☒	

DESCRIBE PLUME BACKGROUND	
Start Same	End ☒
BACKGROUND COLOR Start Same End ☒	SKY CONDITIONS Start Scattered End Scattered + Heavy
WIND SPEED Start 5-10 End ☒	WIND DIRECTION Start SW End ☒
AMBIENT TEMP Start 85° End ☒	WET BULB TEMP N/A
	RM. percent N/A

Stack with Plume 	SOURCE LAYOUT SKETCH	Draw North Arrow
Sun 	15 20 30 45 60 75 90 105 120 135 150 165 180 195 210 225 240 255 270 285 300 315 330 345	
Wind 		

ADDITIONAL INFORMATION 1st Helper - M. L. H.
--

OBSERVATION DATE 5-11-00				START TIME 1559	END TIME 1629
SEC	0	15	30	45	COMMENTS
1	0	0	0	0	Baghouse
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	20	30/24 = 1.25%
18	0	0	0	10	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	15/24 = 0.63%
30	0	15	0	0	

OBSERVER'S NAME (PRINT) Bryan Brumfield		DATE 5-11-00
OBSERVER'S SIGNATURE 		
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 5-22-00

CONTINUED ON VED FORM NUMBER

VISIBLE EMISSION OBSERVATION F IM

No. 6 of 10

COMPANY NAME <u>Kentucky Electric Steel, Inc.</u>		
STREET ADDRESS <u>U.S. 60 West - Coalton</u>		
CITY <u>Ashland</u>	STATE <u>KY</u>	ZIP <u>41102</u>
PHONE (KEY CONTACT) <u>(606) 929-1320</u>	Plant <u>Guard</u>	SOURCE ID NUMBER <u>103-0340-0020</u>

PROCESS EQUIPMENT <u>Melt Shop</u>	OPERATING MODE <u>On Line</u>
CONTROL EQUIPMENT <u>Harsell Baghouse</u>	OPERATING MODE <u>On Line</u>

DESCRIBE EMISSION POINT <u>Baghouse Exhaust</u>	
HEIGHT ABOVE GROUND LEVEL <u>75'</u>	HEIGHT RELATIVE TO OBSERVER <u>S 5</u> End ☒
DISTANCE FROM OBSERVER Start <u>700'</u> End	DIRECTION FROM OBSERVER Start <u>North</u> End ☒

DESCRIBE Start <u>L. from</u> End ☒	
EMISSION COLOR Start <u>Orange</u>	IF WATER DROPLET PLUME Attached ☒ <u>N/A</u> Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>End</u> End ☒	

DESCRIBE PLUME BACKGROUND Start <u>Trace</u> End ☒	
BACKGROUND COLOR Start <u>Green</u> End ☒	SKY CONDITIONS Start <u>Scattered</u> End ☒
WIND SPEED Start <u>8-10</u> End ☒	WIND DIRECTION Start <u>South</u> End ☒
AMBIENT TEMP Start <u>85°</u> End ☒	WET BULB TEMP <u>N/A</u>
	REL. percent <u>N/A</u>

Stack with Plume 	WIND
SOURCE LAYOUT SKETCH Draw North Arrow	

ADDITIONAL INFORMATION <u>1st Helper</u>

OBSERVATION DATE <u>5-11-00</u>					START TIME <u>1629</u>	END TIME <u>1805</u>
SEC	0	15	30	45	COMMENTS	
MIN						
1629	0	0	10	0	<u>By house</u>	
2	0	0	0	0		
3	0	0	20	0		
4	0	0	0	0		
5	0	0	0	0	<u>30/24 = 1.25%</u>	
6	0	0	0	0		
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	20		
11	0	0	0	0	<u>20/24 = 0.83%</u>	
12	0	0	0	0		
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0		
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	10	0	0	<u>35/24 = 1.46%</u>	
24	0	0	25	0		
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	20		
29	0	0	0	0	<u>20/24 = 0.83%</u>	
30	0	0	0	0		

OBSERVER'S NAME (PRINT) <u>Bryan Brumfield</u>	
OBSERVER'S SIGNATURE <u>Bryan Brumfield</u>	DATE <u>5-11-00</u>
ORGANIZATION <u>Environmental Quality Management</u>	
CERTIFIED BY <u>ETA</u>	DATE <u>3-22-01</u>

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 2 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320	Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ✓
DISTANCE FROM OBSERVER Start 700' End ✓	DIRECTION FROM OBSERVER Start North End ✓

DESCRIBE EMISSIONS	
Start <u>Leaky</u> End ✓	IF WATER DROPLET PLUME
EMISSION COLOR Start <u>Brown</u> End ✓	Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>Same</u> End ✓	

DESCRIBE PLUME BACKGROUND	
Start <u>Same</u> End ✓	SKY CONDITIONS Start <u>Scattered</u> End <u>Scattered</u>
BACKGROUND COLOR Start <u>Same</u> End ✓	WIND DIRECTION Start <u>South</u> End ✓
WIND SPEED Start <u>1-5</u> End ✓	WET BULB TEMP N/A
AMBIENT TEMP Start <u>85°</u> End ✓	RH. percent N/A

Slack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow
---------------------------------	---

ADDITIONAL INFORMATION <u>1st Helper -</u> <u>Melter -</u>
--

OBSERVATION DATE <u>5-11-00</u>					START TIME <u>1659</u>	END TIME <u>1729</u>
SEC MIN	0	15	30	45	COMMENTS	
1659	0	0	0	0	Baghouse	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
6	0	0	0	0		
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	20	0		
11	0	0	0	0	$20/24 = 0.83\%$	
12	0	0	0	0		
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	25	0		
17	0	0	20	0	$45/24 = 1.88\%$	
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0		
24	0	0	0	0		
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0		
30	0	0	0	0		

OBSERVER'S NAME (PRINT) <u>Bryan Brumfield</u>	
OBSERVER'S SIGNATURE <u>Bryan Brumfield</u>	DATE <u>5-11-00</u>
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE <u>3-22-00</u>

CONTINUED ON VEO FORM NUMBER

018

VISIBLE EMISSION OBSERVATION FORM

No. 8 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ✓
DISTANCE FROM OBSERVER Start 700' End ✓	DIRECTION FROM OBSERVER Start North End ✓

DESCRIBE EMISSIONS Start None End ✓	
EMISSION COLOR Start N/A End ✓	IF WATER DROPLET PLUME Attached () N/A Detached ()
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Trees End ✓	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Partly Cloudy End Broken
WIND SPEED Start 1-5 End 1-10 MPH	WIND DIRECTION Start SE End SE
AMBIENT TEMP Start 85° End ✓	WET BULB TEMP N/A
	RH. percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow
---------------------------------	--

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-11-00					START TIME 1729	END TIME 1759
SEC MIN	0	15	30	45	COMMENTS	
1739	0	0	0	0	Baghouse	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0	Ø	
6	0	0	0	0		
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0	Ø	
12	0	0	0	0		
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0	Ø	
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0	Ø	
24	0	0	0	0		
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0	Ø	
30	0	0	0	0		

OBSERVER'S NAME (PRINT) Bryan Brumfield		DATE 5-11-00
OBSERVER'S SIGNATURE Bryan Brumfield		DATE 5-11-00
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 3-22-00
CONTINUED ON VEO FORM NUMBER		

VISIBLE EMISSION OBSERVATION FORM

No. 9 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ✓
DISTANCE FROM OBSERVER Start 700' End ✓	DIRECTION FROM OBSERVER Start North End ✓

DESCRIBE EMISSIONS Start None End <u>Loopy</u>	
EMISSION COLOR Start N/A End Orange	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Trees End ✓	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Broken End ✓
WIND SPEED Start 1-10 mph End ✓	WIND DIRECTION Start Southeast End SE
AMBIENT TEMP Start 85° End 80°	WET BULB TEMP N/A
	RH. percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow
---------------------------------	--

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-11-00					START TIME 1759	END TIME
SEC MIN	0	15	30	45	COMMENTS	
1759	0	0	0	0	Baghouse	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0	0	
1804	0	0	0	0		
1805	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0	0	
1810	0	0	0	0		
1811	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	25	0		
17	0	0	0	0	25/24 = 1.04%	
1816	0	0	0	0		
1817	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	25	5	0	30/24 = 1.25%	
24	0	0	0	0		
1822	0	0	0	0		
25	0	0	0	0		
1823	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0	0	
30	0	0	0	0		
1828	0	0	0	0		

OBSERVER'S NAME (PRINT) Bryan Brumfield		DATE 5-11-00
OBSERVER'S SIGNATURE Bryan Brumfield		
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 3-22-00

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 12 of 10

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ☒
DISTANCE FROM OBSERVER Start 700' End ☒	DIRECTION FROM OBSERVER Start North End ☒

DESCRIBE EMISSIONS Start Letting End ☒	
EMISSION COLOR Start Orange End ☒	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ☒	

DESCRIBE PLUME BACKGROUND Start Trees End ☒	
BACKGROUND COLOR Start Green End ☒	SKY CONDITIONS Start Broken End ☒
WIND SPEED Start 1-10 mph End ☒	WIND DIRECTION Start South east End ☒
AMBIENT TEMP Start 80° End ☒	WET BULB TEMP N/A
	RH. percent N/A

Slack with Plume ☒ Sun ☒ Wind ☒	SOURCE LAYOUT SKETCH
---	---------------------------------

ADDITIONAL INFORMATION 1st Helper -

OBSERVATION DATE 5-11-00					START TIME 1829	END TIME 1859
SEC	0	15	30	45	COMMENTS	
1	0	0	0	0	Baghouse	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	15	0	0	75/24 = 1.46%	
6	0	0	20	0		
7	0	0	30	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	30	60/24 = 2.50%	
12	0	0	0	0		
13	0	0	0	0		
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	25	5	30/24 = 1.25%	
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0	Φ	
24	0	0	0	0		
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0	Φ	
30	0	0	0	0		

OBSERVER'S NAME (PRINT) Bryan Brumfield	
OBSERVER'S SIGNATURE <i>Bryan Brumfield</i>	DATE 5-11-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 1 OF 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) Plant (606) 929-1320	SOURCE ID NUMBER 103-0340-0020	
Guard		

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start COFTing End ✓	
EMISSION COLOR Start Orange End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND Start TREES End ✓	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Overcast End ✓
WIND SPEED Start 4-bush End ✓	WIND DIRECTION From Start W End ✓
AMBIENT TEMP Start 70 End ✓	WET BULB TEMP NA
	RH, percent NA

Stack with Plume  Sun  Wind 	SOURCE LAYOUT SKETCH 	Draw North Arrow 
---	--	---

ADDITIONAL INFORMATION 1st HELPER Tony Hall / nearby tell
MEITER

OBSERVATION DATE 5/12/00				START TIME 0715	END TIME 1121
SEC	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	0	10	0	#1R
3	0	0	0	10	#1L
4	0	0	0	0	
5	0	0	0	0	
6	0	5	0	0	#2L
7	0	15	0	0	#3R
8	0	20	0	0	3L
9	0	0	0	0	
10	0	0	0	15	4L
11	0	0	0	0	
12	0	0	0	0	
13	10	0	0	0	5L
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	20	0	#RN
18	0	0	0	10	3LN
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE 	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 2 OF 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <u>COFFING</u> End <u>✓</u>	
EMISSION COLOR Start <u>Orange</u> End <u>✓</u>	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Monitor</u> End	

DESCRIBE PLUME BACKGROUND Start <u>TREES</u> End <u>✓</u>		
BACKGROUND COLOR Start <u>Green</u> End <u>✓</u>	SKY CONDITIONS Start <u>Overcast</u> End <u>✓</u>	
WIND SPEED Start <u>4-6 mph</u> End <u>✓</u>	WIND DIRECTION Start <u>W</u> End	
AMBIENT TEMP Start <u>70</u> End <u>✓</u>	WET BULB TEMP <u>NA</u>	REL. percent <u>NA</u>

Slack with Plume ☒ Sun ☒ Wind ☒	SOURCE LAYOUT SKETCH 	Draw North Arrow
---	--------------------------	------------------

ADDITIONAL INFORMATION 1st HELPER <u>Jim Hall Woody Hall</u> MELTER <u>Bruce M. Hall</u>
--

OBSERVATION DATE 5/12/00		START TIME 0715		END TIME 1121	
SEC MIN	0	15	30	45	COMMENTS
1	0	0	15	0	#3L
2	0	0	0	0	
3	0	0	10	0	4L
4	0	0	0	0	
5	0	0	0	15	5L
6	0	0	0	0	
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	15	0	#4RN
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	10	0	0	3R
24	0	0	15	0	3L
25	0	0	0	0	
26	0	0	0	5	4R
27	0	0	0	0	
28	0	0	0	0	
29	15	0	0	0	#5L
30	0	0	0	0	

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 3 OF 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start COFFING End ☒	
EMISSION COLOR Start Orange End ☒	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND Start TREES End ☒	
BACKGROUND COLOR Start Green End ☒	SKY CONDITIONS Start overcast End ☒
WIND SPEED Start 4-6 End ☒	WIND DIRECTION Start W End ☒
AMBIENT TEMP Start 70 End ☒	WET BULB TEMP NA
	RH, percent NA



OBSERVATION DATE 5/12/00				START TIME 0715	END TIME 1121
SEC	0	15	30	45	COMMENTS
MIN					
1	0	0	0	0	
2	0	0	0	0	
3	0	0	0	20	4 RN
4	0	0	0	15	3 LW
5	0	0	0	0	
6	0	0	0	0	
7	0	10	0	0	#2 NR
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	10	0	0	#3 R
17	0	0	0	0	
18	0	0	0	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE <i>George Hensley</i>	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00

ADDITIONAL INFORMATION 1ST HELPER Jim Hall Woody Hill	
MELTER Bruce mmm	

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 4 OF 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS	
Start none	End ☒
EMISSION COLOR Start none End ☒	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND	
Start TREES	End ☒
BACKGROUND COLOR Start Green End ☒	SKY CONDITIONS Start overcast End ☒
WIND SPEED Start 6-8 mph End ☒	WIND DIRECTION Start W End ☒
AMBIENT TEMP Start 72 End ☒	WET BULB TEMP NA RH, percent NA

Stack with Plume ☒ Sun ☒ Wind ☒	SOURCE LAYOUT SKETCH Draw North Arrow
---	--

ADDITIONAL INFORMATION 1st HELPER Jim Hall Woody Hill MELTER Bruce Hall

OBSERVATION DATE 5/12/00				START TIME 0715	END TIME 1121
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	

OBSERVER'S NAME (PRINT) George Hensley	DATE 5/12/00
OBSERVER'S SIGNATURE George Hensley	
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00

CONTINUED ON VED FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 5 OF 9

COMPANY NAME
Kentucky Electric Steel, Inc.

STREET ADDRESS
U.S. 60 West - Coalton

CITY
Ashland

STATE
KY

ZIP
41102

PHONE (KEY CONTACT) Plant
(606) 929-1320

Guard
103-0340-0020

SOURCE ID NUMBER

PROCESS EQUIPMENT
Melt Shop

OPERATING MODE
On Line

CONTROL EQUIPMENT
Harsell Baghouse

OPERATING MODE
On Line

DESCRIBE EMISSION POINT
Baghouse Exhaust

HEIGHT ABOVE GROUND LEVEL
75'

HEIGHT RELATIVE TO ~ ~ E W E R
SON as (End as)

DISTANCE FROM OBSERVER
Start 700' End 700'

DIRECTION FROM OBSERVER
Start North End North

DESCRIBE EMISSIONS
Start COFFING End ✓

EMISSION COLOR
Start Orange End ✓

IF WATER DROPLET PLUME
Attached () NA

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED
Start 5' to 10' Above Monitor End

DESCRIBE PLUME BACKGROUND
Start TREES End ✓

BACKGROUND COLOR
Start Green End ✓

SKY CONDITIONS
Start Overcast End ✓

WIND SPEED
Start 6-8 mph End ✓

WIND DIRECTION
Start W End ✓

AMBIENT TEMP
Start 72 End ✓

WET BULB TEMP
NA

REL. percent
NA

Stack with Plume

Sun

Wind

SOURCE LAYOUT SKETCH
N. S. S. S. S.

Draw North Arrow

BAGHOUSE

Observer's Position

140°

Sun Location Line

OBSERVATION DATE			START TIME		END TIME
5/12/00			0715		1121
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	
7	0	0	0	0	
8	5	0	0	0	#3 L
9	0	0	0	0	
10	0	10	0	0	4 R
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	15	0	#3 LN
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	10	0	0	0	#3 R

OBSERVER'S NAME (PRINT)
George Hensley

OBSERVER'S SIGNATURE
George Hensley

DATE
5/12/00

ORGANIZATION
Environmental Quality Management

CERTIFIED BY
ETA

DATE
3/29/00

CONTINUED ON VEO FORM NUMBER

ADDITIONAL INFORMATION
1ST HELPER Jim Hall Woody Hall

MELTER Bruce Moore

VISIBLE EMISSION OBSERVATION FORM

No. 7 OF 9

COMPANY NAME
Kentucky Electric Steel, Inc.

STREET ADDRESS
U.S. 60 West - Coalton

CITY
Ashland

STATE
KY

ZIP
41102

PHONE (KEY CONTACT) Plant
(606) 929-1320

Guard
103-0340-0020

PROCESS EQUIPMENT
Melt Shop

OPERATING MODE
On Line

CONTROL EQUIPMENT
Harsell Baghouse

OPERATING MODE
On Line

DESCRIBE EMISSION POINT
Baghouse Exhaust

HEIGHT ABOVE GROUND LEVEL
75'

HEIGHT RELATIVE TO OBSERVER
Start 25' End 25'

DISTANCE FROM OBSERVER
Start 700' End 700'

DIRECTION FROM OBSERVER
Start North End North

DESCRIBE EMISSIONS
Start COFFING End ✓

EMISSION COLOR
Start Orange End ✓

IF WATER DROPLET PLUME
Attached ☒ NA Detached ☐

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED
Start 5' to 10' Above Monitor End

DESCRIBE PLUME BACKGROUND
Start TREES End ✓

BACKGROUND COLOR
Start Green End ✓

SKY CONDITIONS
Start Scattered End ✓

WIND SPEED
Start 8-10 mph End ✓

WIND DIRECTION
Start SW End ✓

AMBIENT TEMP
Start 5 End ✓

WET BULB TEMP
NA

RH, percent
NA

Slack with Plume ☒

Sun ☒

Wind ☒

SOURCE LAYOUT SKETCH
N Side

Draw North Arrow

BAGHOUSE

Observer's Position

140°

Sun Location Line

ADDITIONAL INFORMATION
1st HELPER Jim Hall Woody Hall

MELTER Bruce Moore

OBSERVATION DATE 5/12/00					START TIME 0715	END TIME 1121
SEC MIN	0	15	30	45	COMMENTS	
1	0	0	0	0		
2	0	0	0	10	3R	
3	0	0	0	0		
4	15	0	0	0	3L	
5	0	0	0	0		
6	0	10	0	0	4L	
7	0	0	0	0		
8	0	15	0	0	5L	
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0		
13	15	0	0	0	4RN	
14	0	15	0	0	3LN	
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0		
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	15	0	0	0	1R	
22	0	10	0	0	1L	
23	0	0	0	0		
24	0	0	0	0		
25	5	0	0	0	2L	
26	10	0	0	0	3R	
27	10	0	0	0	3L	
28	0	0	0	0		
29	0	10	0	0	4L	
30	0	0	0	0		

OBSERVER'S NAME (PRINT)
George Hensley

OBSERVER'S SIGNATURE
George Hensley

DATE
5/12/00

ORGANIZATION
Environmental Quality Management

CERTIFIED BY
ETA

DATE
3/29/00

CONTINUED ON VEO FORM NUMBER

VISIBLE EMISSION OBSERVATION FORM

No. 8 of 9


COMPANY NAME Kentucky Electric Steel, Inc.	
STREET ADDRESS U.S. 60 West - Coalton	
CITY Ashland	STATE KY
ZIP 41102	
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start COFFING End ✓	
EMISSION COLOR Start Orange End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND Start TREES End ✓	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 10-12 mph End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 80 End 84	WET BULB TEMP NA
	RH. percent NA



OBSERVATION DATE 5/12/00				START TIME 0715	END TIME 1121
SEC MIN	0	15	30	45	COMMENTS
1	0	0	15	0	5 L
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	15	0	0	0	4 RN
7	0	10	0	0	3 RN
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VED FORM NUMBER	

ADDITIONAL INFORMATION 1st HELPER Jim Hall Woody Hill	
MELTER Bruce...	

VISIBLE EMISSION OBSERVATION FORM

No. 9 OF 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT
Baghouse Exhaust

HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS

Start **None** End ☒

EMISSION COLOR
Start **None** End ☒

POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED
Start **5' to 10' Above Monitor** End

DESCRIBE PLUME BACKGROUND

Start **TREES** End ☒

BACKGROUND COLOR
Start **Green** End ☒

WIND SPEED
Start **10-12 mph** End ☒


AMBIENT TEMP
Start **84** End

SKY CONDITIONS
Start **Scattered** End ☒

WIND DIRECTION
Start **SW** End ☒

WET BULB TEMP
NA

RH, percent
NA



ADDITIONAL INFORMATION

1st HELPER *Jim Hall Woody Hall*

MELTER *Bruce Morris*

OBSERVATION DATE		START TIME				END TIME
5/12/00		0715				1121
SEC	0	15	30	45	COMMENTS	
MIN						
1	0	0	0	0		
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
6	0	0	0	0	avg 0/24 = 0%	
7					end Run	
8						
9						
10						
11						
12						
13						
14						
15						
16						
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						

OBSERVER'S NAME (PRINT) George Hensley		DATE 5/12/00
OBSERVER'S SIGNATURE <i>George Hensley</i>		
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		DATE 3/29/00
CONTINUED ON VEO FORM NUMBER		

VISIBLE EMISSION OBSERVATION FORM

No. 1 OF 1

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start <u>LOFTING</u> End <u>✓</u>	
EMISSION COLOR Start <u>Orange</u> End <u>✓</u>	IF WATER DROPLET PLUME Attached <u>1</u> <u>NA</u> Detached <u>0</u>
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start <u>5' to 10' Above Monitor</u> End	

DESCRIBE PLUME Start <u>TREES</u> End	
BACKGROUND COLOR Start <u>Green</u> End <u>✓</u>	SKY CONDITIONS Start <u>Stationary</u> End <u>✓</u>
WIND SPEED Start <u>8-10 mph</u> End <u>✓</u>	WIND DIRECTION <u>From</u> Start <u>SW</u> End <u>✓</u>
AMBIENT TEMP Start <u>85</u> End <u>✓</u>	WET BULB TEMP <u>NA</u>
	RH, percent <u>NA</u>

Slack with Plume <u>✓</u> Sun <u>+</u> Wind <u>→</u>	SOURCE LAYOUT SKETCH
--	--------------------------

ADDITIONAL INFORMATION <u>1st HELPER Jim Hall Woody Hall</u>
<u>MELTER Bruce Mink</u>

OBSERVATION DATE 5/12/00		START TIME 1218		END	
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	15	#1R
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	10	0	3R Avg 25/24 = 1.04
7	0	0	10	0	3L
8	0	0	0	0	
9	0	0	0	10	4R
10	0	0	0	0	
11	0	0	0	0	
12	20	0	0	0	5L Avg 40/24 = 1.67
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	25	4RN
17	0	0	0	0	
18	20	0	0	0	3LN Avg 45/24 = 1.88
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	10	1R Avg 10/24 = 0.42
25	0	0	0	0	
26	10	0	0	0	1L
27	0	0	0	0	
28	0	0	0	0	
29	0	0	10	0	3R
30	0	0	0	20	3L Avg 40/24 = 1.67

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE <u>George Hensley</u>	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FC 1

No. 2 OF 1

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS	
Start COPTing	End ✓
EMISSION COLOR Start Orange End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND	
Start TREES	End ✓
BACKGROUND COLOR Start Grey End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 10-12 mph ✓	WIND DIRECTION FROM Start SW End ✓
AMBIENT TEMP Start 85 End ✓	WET BULB TEMP NA
	RH. percent NA

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH	Draw North Arrow
	Observer's Position 140° Sun Location Line	

ADDITIONAL INFORMATION
1st HELPER Jim Hael newly hired
MELTER Bruce Moore

OBSERVATION DATE 5/12/00				START TIME 1218	END TIME
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	0	0	0	
3	15	0	0	0	4L
4	0	0	0	0	
5	20	0	0	0	5L
6	0	0	0	0	avg ³⁵ / ₂₄ = 1.462
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	avg ⁰ / ₂₄ = 0%
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	avg ⁰ / ₂₄ = 0%
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	avg ⁰ / ₂₄ = 0%
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	avg ⁰ / ₂₄ = 0%

OBSERVER'S NAME (PRINT) George Hensley	DATE 5/12/00
OBSERVER'S SIGNATURE George Hensley	
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 3 OF 1


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End d ~
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start none End ✓	
EMISSION COLOR Start none End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND Start TREES End	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 10-12 End ✓	WIND DIRECTION FROM Start SW End ✓
AMBIENT TEMP Start 87 End ✓	WET BULB TEMP NA RH, percent NA

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow 
---------------------------------	---

ADDITIONAL INFORMATION 1st HELPER Jim Hall Wendy Hall MELTER Bruce Moore	
--	--

OBSERVATION DATE				START TIME	END TIME
5/12/00				1218	
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	avg 0/24 = 0%
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	avg 0/24 = 0%
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	avg 0/24 = 0%
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	avg 0/24 = 0%
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	avg 0/24 = 0%

OBSERVERS NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FC

No. 4 OF 1

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Sun 25' End
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start COPTING End ✓	
EMISSION COLOR Start Orange End ✓	IF WATER DROPLET PLUME Attached () NA Detached ()
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND Start TREES End ✓	
BACKGROUND COLOR Start Blue End ✓	SKY CONDITIONS - a Scatter End ✓
WIND SPEED Start 8-10 mph End ✓	WIND DIRECTION FROM Start SW End ✓
AMBIENT TEMP Start 88 End ✓	WET BULB TEMP NA
	RH, percent NA

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow
---------------------------------	---

ADDITIONAL INFORMATION 1st HELPER Jim Hall Wendy Hill
MELTER Bruce Moore

OBSERVATION DATE 5/12/00					START TIME 1218	END TIME
SEC	0	15	30	45	COMMENTS	
1	0	0	0	0		
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0		
6	0	0	0	0	Avg 0/24 = 0%	
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0	Avg 0/24 = 0%	
13	0	0	20	0	4 RN	
14	0	0	0	10	3 LN	
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0		
18	0	0	0	0	Avg 30/24 = 1.25%	
19	0	0	0	0		
20	0	0	0	0		
21	0	0	15	0	# 1 R	
22	0	0	0	0		
23	0	0	0	0		
24	0	0	0	0	Avg 15/24 = 0.63%	
25	0	0	0	0		
26	0	15	0	0	3 R	
27	0	0	0	0		
28	0	0	0	0		
29	0	0	10	0	4 C	
30	0	0	0	0	Avg 25/24 = 1.04%	

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FC

No. 5 OF 1

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End 25'
DISTANCE FROM OBSERVER Start 700' End 700'	DIRECTION FROM OBSERVER Start North End North

DESCRIBE EMISSIONS Start none End ✓	
EMISSION COLOR Start None End ✓	IF WATER DROPLET PLUME Attached ☒ NA Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 5' to 10' Above Monitor End	

DESCRIBE PLUME BACKGROUND Start TREES End ✓	
BACKGROUND COLOR Start Green End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 10-12 mph End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 88 End ✓	WET BULB TEMP NA RH, percent NA

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION 1st HELPER Jim Hall Waddy Hill MELTER Bruce Moore
--

OBSERVATION DATE 5/12/00		START TIME		END TIME	
SEC MIN	0	15	30	45	COMMENTS
1	0	0	0	0	
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	avg 0/24 = 090
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					

OBSERVER'S NAME (PRINT) George Hensley	
OBSERVER'S SIGNATURE George Hensley	DATE 5/12/00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3/29/00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 6 of 9


COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ☒
DISTANCE FROM OBSERVER Start 700' End ☒	DIRECTION FROM OBSERVER Start North End ☒

DESCRIBE EMISSIONS Start Lofting End None	
EMISSION COLOR Start Orange End N/A	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start 10' out above main burner End ☒	

DESCRIBE PLUME BACKGROUND Start Trees End ☒	
BACKGROUND COLOR Start Green End ☒	SKY CONDITIONS Start Scattered End ☒
WIND SPEED Start 7-15 MPH End ☒	WIND DIRECTION Start Southwest End ☒
AMBIENT TEMP Start 85-90 End ☒	WET BULB TEMP N/A
	RH, percent N/A

Stack with Plume ☒ Sun 4 Wind ☒	SOURCE LAYOUT SKETCH Draw North Arrow  
--	---

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-12-00					START TIME 1420	END TIME 1459
SEC	0	15	30	45	COMMENTS	
MIN						
14 ³⁰	0	0	0	0	baghouse	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0	Ø	
6	0	0	0	0		
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0		
10	0	0	0	0		
11	0	0	0	0	Ø	
12	0	0	0	0		
13	0	0	0	0		
14	0	0	0	15		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0	15/24 = 0.63%	
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0		
22	0	0	0	0		
23	0	0	0	0	Ø	
24	0	0	0	0		
25	0	0	0	0		
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0	Ø	
30	0	0	0	0		

OBSERVER'S NAME (PRINT) Bryan Brumfield	
OBSERVER'S SIGNATURE Bryan Brumfield	DATE 5-12-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 2 of 2

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ✓
DISTANCE FROM OBSERVER Start 700' End ✓	DIRECTION FROM OBSERVER Start North End ✓

DESCRIBE EMISSIONS Start None End ✓	
EMISSION COLOR Start N/A End ✓	IF WATER DROPLET PLUME Attached () N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Same End ✓	
BACKGROUND COLOR Start Same End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 2-15 End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 85-90 End ✓	WET BULB TEMP N/A
	RH. percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH 	Draw North Arrow
---------------------------------	--------------------------	----------------------

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-12-00				START TIME 1450	END TIME 1520
SEC MIN	0	15	30	45	COMMENTS
14:50	0	0	0	0	Baghouse
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	0
14:55	0	0	0	0	
15:00	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	0
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	0
18	0	0	0	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	0
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	0
30	0	0	0	0	

OBSERVER'S NAME (PRINT) Bryan Brumfield	
OBSERVER'S SIGNATURE 	DATE 5-12-00
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00
CONTINUED ON VEO FORM NUMBER	

VISIBLE EMISSION OBSERVATION FORM

No. 8 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ✓
DISTANCE FROM OBSERVER Start 700' End ✓	DIRECTION FROM OBSERVER Start North End ✓

DESCRIBE EMISSIONS	
Start None	End 2:00 PM
EMISSION COLOR Start N/A End Orange	IF WATER DROPLET PLUME Attached ✓ Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND	
Start Same	End ✓
BACKGROUND COLOR Start Same End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 2-15 mph End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 85-90 End ✓	WET BULB TEMP N/A
	RH. percent N/A

SOURCE LAYOUT SKETCH	
Draw North Arrow	

ADDITIONAL INFORMATION 1st Help - Melter -
--

OBSERVATION DATE 5-12-90					START TIME 1520	END TIME 1550
SEC MIN	0	15	30	45	COMMENTS	
1	0	0	0	0	Baghouse	
2	0	0	0	0		
3	0	0	0	0		
4	0	0	0	0		
5	0	0	0	0	Ø	
6	0	0	0	0		
7	0	0	0	0		
8	0	0	0	0		
9	0	0	0	0	Ø	
10	0	0	0	0		
11	0	0	0	0		
12	0	0	0	0		
13	0	0	0	0	Ø	
14	0	0	0	0		
15	0	0	0	0		
16	0	0	0	0		
17	0	0	0	0	Ø	
18	0	0	0	0		
19	0	0	0	0		
20	0	0	0	0		
21	0	0	0	0	25/24 = 1.04%	
22	0	0	0	25		
23	0	0	0	0		
24	0	0	0	0		
25	0	0	0	0	Ø	
26	0	0	0	0		
27	0	0	0	0		
28	0	0	0	0		
29	0	0	0	0	Ø	
30	0	0	0	0		

OBSERVER'S NAME (PRINT) Bryan Brumfield		DATE 5-12-90
OBSERVER'S SIGNATURE <i>Bryan Brumfield</i>		
ORGANIZATION Environmental Quality Management		
CERTIFIED BY ETA		ME. 3-22-00
CONTINUED ON VEO FORM NUMBER 1 1 1 1 1		

VISIBLE EMISSION OBSERVATION FORM

No. 9 of 9

COMPANY NAME Kentucky Electric Steel, Inc.		
STREET ADDRESS U.S. 60 West - Coalton		
CITY Ashland	STATE KY	ZIP 41102
PHONE (KEY CONTACT) (606) 929-1320	Plant Guard	SOURCE ID NUMBER 103-0340-0020

PROCESS EQUIPMENT Melt Shop	OPERATING MODE On Line
CONTROL EQUIPMENT Harsell Baghouse	OPERATING MODE On Line

DESCRIBE EMISSION POINT Baghouse Exhaust	
HEIGHT ABOVE GROUND LEVEL 75'	HEIGHT RELATIVE TO OBSERVER Start 25' End ✓
DISTANCE FROM OBSERVER Start 700' End ✓	DIRECTION FROM OBSERVER Start North End ✓

DESCRIBE EMISSIONS Start None End ✓	
EMISSION COLOR Start N/A End ✓	IF WATER DROPLET PLUME Attached ☒ N/A Detached ☐
POINT IN THE PLUME AT WHICH OPACITY WAS DETERMINED Start Same End ✓	

DESCRIBE PLUME BACKGROUND Start Same End ✓	
BACKGROUND COLOR Start Same End ✓	SKY CONDITIONS Start Scattered End ✓
WIND SPEED Start 7-15 End ✓	WIND DIRECTION Start SW End ✓
AMBIENT TEMP Start 85-90 End ✓	WET BULB TEMP N/A
	RH. percent N/A

Stack with Plume Sun Wind	SOURCE LAYOUT SKETCH Draw North Arrow

ADDITIONAL INFORMATION 1st Helper - Melter -
--

OBSERVATION DATE 5-12-99				START TIME 1559	END TIME 1620
SEC MIN	0	15	30	45	COMMENTS
1550	0	0	0	0	Baghouse
2	0	0	0	0	
3	0	0	0	0	
4	0	0	0	0	
5	0	0	0	0	
6	0	0	0	0	
7	0	0	0	0	
8	0	0	0	0	
9	0	0	0	0	
10	0	0	0	0	
11	0	0	0	0	
12	0	0	0	0	
13	0	0	0	0	
14	0	0	0	0	
15	0	0	0	0	
16	0	0	0	0	
17	0	0	0	0	
18	0	0	0	0	
19	0	0	0	0	
20	0	0	0	0	
21	0	0	0	0	
22	0	0	0	0	
23	0	0	0	0	
24	0	0	0	0	
25	0	0	0	0	
26	0	0	0	0	
27	0	0	0	0	
28	0	0	0	0	
29	0	0	0	0	
30	0	0	0	0	

OBSERVER'S NAME (PRINT) Bryan Brumfield	DATE 5-12-00
OBSERVER'S SIGNATURE Bryan Brumfield	
ORGANIZATION Environmental Quality Management	
CERTIFIED BY ETA	DATE 3-22-00
CONTINUED ON VEO FORM NUMBER	

Appendix B

Production/Process Field Data

2

343

**KENTUCKY ELECTRIC STEEL
BAGHOUSE TEST PROCESS MONITORING FORM**

Date

5/12/08

START - 07:15

Time	Baghouse Fan Amperage			Lmp	Baghouse Pressure Drop, in. WG	Damper Positions (Describe)	Notes (Heat No. and time; Charge and Tap Times)
	A	B	C				
7:15	176	181	99	101	5.8	All open except Fresh Air	A+B Melting
7:30	179	187	115	108	5.8		W1359 W1363
7:50	178	187	120	109	5.5		X1274 X1278
8:05	176	186	103	107	5.5		A Tap 7:31-7:35
8:20	176	184	100	101	5.5		A Charge 7:37-7:56
8:35	179	188	101	112	5.3		B Charge 7:45-7:47
8:50	175	184	109	110	5.3		A Charge 8:31-8:33
9:10	174	181	81	104	5.5		B Tap 8:47-8:50
9:25	171	179	77	78	5.6		B Charge 8:51-9:01
9:45	173	174	89	111	5.7		A Charge 8:54-8:55
10:05	171	179	101	110	5.7	W1365	B Charge 9:43-9:45
10:20	169	173	94	110	5.7		A Tap 9:57-10:02
10:40	177	185	117	110	5.6		Charge 10:05-10:13
11:00	172	186	95	111	5.0		B Tap 10:32-10:36
11:20	173	181	87	115	5.4		B Charge 10:38-11:04
						X-1280	A Charge 10:54-10:56
							Tapped W1365
							@ 11:45 am

a) Prior to tap, cave in around electrodes - high smoke in Bldg

End 11:20

**KENTUCKY ELECTRIC STEEL
BAGHOUSE TEST PROCESS MONITORING FORM**

Date

5/12/00

Test #3

Start

12:19

12:15

Time	Baghouse Fan Amperage			LMF	Baghouse Pressure Drop, in. WG	Damper Positions (Describe)	Notes (Heat No. and time; Charge and Tap Times)
	A	B	C				
12:19	169	177	93	110	5.5	All open except cooling air	X-1280
12:35	175	184	97	103	5.7		W-1366
12:52	169	177	105	109	5.5		A Charge 12:31 - 12:33
1:10	176	182	104	108	5.5		B Tap 12:46 - 12:51
1:25	179	186	103	110	5.7		Charging B 12:52 - 12:58
1:45	173	181	121	107	5.7		Tapping A 1:27 - 1:32
2:00	173	179	102	109	5.8	X-1281	Charging A 1:33 - 2:15
2:15	173	182	97	108	5.8		13:41 slip on B, clouds of dust
2:30	166	176	111	107	5.8		Charging B 1:46 - 1:53
2:50	172	181	107	106	5.4		Tapping B 2:39 - 2:43
3:10	176	184	102	106	5.4		Charging B 2:45 - 3:01
3:25	172	182	86	108	5.5		Charging A 2:47 - 2:49
3:40	168	175	90	110	5.5	Ladle	Charging B 3:40 - 3:42
4:00	169	177	110	112	5.2		Tapping A 3:48 - 3:52
4:20	172	183	93	114	5.2 ^{LMF} 5.3		Charging A 3:53 - 4:13

3:58 B furnace smoking badly. Cut electricity
4:11 charging A w/LMF ladle

RUN END 4:20 p.m.

PRODUCTION WORKSHEET

Heats During Tests

Date	Heat No.	Tons	Previous Tap	Time Tap	Operating Time, min	Tons/Hr
TEST 1						
	X-1269	51.7	NA	14:40	96	
11-May	W-1355	0		15:11		Begin operations at 13:40
	X-1270	44.7	14:40	16:45	125	No cast, completed as W-1357
	W-1356	47.7	15:11	18:33	202	
	X-1271	56.4	16:45	19:25	160	
	W-1357	50	18:33	20:19	197	Return of heat W-1355, add times
	W or A Furnace	97.7	W or A Furnace		399	14.7
	X or B Furnace	152.8	X or B Furnace		381	24.1
	Totals	250.5				38.8 tons/hr

TESTS 2 and 3

12-May						
	W-1363	48.3	5:51	7:34	103	
	W-1364	52.2	7:34	9:59	145	
	W-1365	52.1	9:59	11:41	102	
	W-1366	55.6	11:41	13:28	107	
	W-1367	46.7	13:28	15:46	138	
	W-1368	50.2	15:46	17:18	205	Return of heat X-1281 add times
	X-1278	49.9	6:39	8:46	127	
	X-1279	50.6	8:46	10:31	105	
	X-1280	51.9	10:31	12:47	136	
	X-1281	0	12:47	14:40		No cast, completed as W-1368
	X-1282	50.9	14:40	16:37	117	
	W or A Furnace	305.1	W or A Furnace		800	22.9
	X or B Furnace	203.3	X or B Furnace		485	25.2
	Totals	508.4				48.0 tons/hr

1

KENTUCKY ELECTRIC STEEL

BAGHOUSE TEST PROCESS MONITORING FORM

Date

5/11/00

Start

1:55 p.m.

Heat

W1356

X1269

Time	Baghouse Fan Amperage 500 HP			LMF	Baghouse Pressure Drop, in. WG	Damper Positions (Describe)	Notes (Heat No. and time; Charge and Tap Times)
	West A	East B	C				
1:55	181	185	105	125	5.6	Dampers fully open	Heat Melting Both
2:10	174	177	102	126	5.6		Charging A 1:30
2:25	183	191	107	125	6.0	Fresh air dampers closed	Tap B 1:42-1:47
2:42	177	185	106	129	5.6		Charge B 1:52-2:55
2:57	174	182	100	116	5.6	During Charging	Heat X1270
3:13	179	187	100	117	5.0	Damper on furnace charging closed.	Tap A 3:15-3:19
3:29	174	183	122	111	5.2		Charge A 3:21-3:40
3:44	177	181	112	117	5.3		Heat W1356
4:00	169	180	110	113	5.5	Others open	Charge B 3:29-3:35
4:15	179	188	102	115	5.8		Adjusting oxygen burner
4:30	181	190	104	117	6.1		(High VE's) ~ 4:00 p.m.
4:45	175	184	101	112	5.9		Charging A 4:22-4:24
5:00	175	181	116	109	5.5		
5:15	178	188	120	113	5.5		Tapping B 4:50-4:55
5:30	181	188	107	110	5.1		Heat X1271
5:45	177	189	111	111	5.3		Charge B 5:00-5:21
6:00	179	188	107	121	5.6		Charge B 5:46-5:49
6:19	173	184	90	98	6.0		Tap A 6:36-6:41
6:30	178	186	92	109	5.8		Charge A 6:43-6:53
6:50	172	180	94	115	5.1		by heat from LMF
7:15	180	188	111	111	5.3		Tap B 7:29-7:33

a) Also, Front end loader moving slag @ end of caster. Lime dust.

7:35 181 189 119 108 5.40 -

Time End 19:35

Appendix C

Production Heat Sheets (Privileged and Confidential)

Kentucky Electric Steel

P.O. Box 3500
Ashland KY 41105-3500

May 22, 2000

Dear Fred:

Here is the Raw Data you may need for our report..

Sincerely,

A handwritten signature in cursive script that reads "Eddie Hall".

Eddie Hall
Supervisor of Safety and Environmental Affairs

DATE	5-12-00
SHIFT	11-7
SUPERVISOR	CR 7711

MELTER'S LOG

Additional Comments:

HEAT #	GRADE	TIME (minutes) TAP/1 2nd 3rd CHG:CHG:CHG	TAP / TAP	TIME of TAP	POWER (minutes) ON/OFF	LAG FCE DIFF. @ TAP	# CAST (Ex: 4/2)	TONS/ HEAT	T/A	FURNACE ONLY DELAYS	DELAYS CAUSING CASTER DELAYS
1	W-1359	17.5 5	120.0	0:02	58.8 43.7	8	3	55.0		19.0	Kw 22830 13603 35201
2	X-1274	12 2	123.5	0:57	36.0 54.3	10	3	41.0		Sub No 2 Elect	Kw 19710 15437 40265
3	W-1360	12.8 5	120.3	2:00	54.5 53.0	2	1	55.2		11.5	Kw 21480 15035 36370
4	X-1275	34.5 2	128.5	3:05	56.0 38.0	7	3	51.1		Repaired bottom El 47.5 t. t 7.000 Pw. Set	Kw 22100 10717 31593
5	W-1361	4.5 15	123.0	4:02	56.8 61.9	8	3	54.1		Set 13388 Elect	Kw 21590 13152 31420
6	X-1276	19.0 2	116.3	5:00	52.5 44.8	10	4	46.7		12.500 6.000 Sub. 1.000	Kw 20830 15538 49047
7	W-1362	12.8 3	108.8	5:51	52.0 44.0	2	4	50.0		22.0	Kw 20470 12303 35395
8	X-1277	2				7	4	43.2			Kw 19820 13271 47462
9											
10											
11											

Document No. MS-015

Revision Date: 02-15-99

Revision Level: D

WHITE - CLERK • CANARY - MELT SHOP OFFICE • PINK - FURNACE PULPIT

SHIFT	7-2
SUPERVISOR	H. W. Salinas

MELTER'S LOG

Additional Comments:

"H" FURNACE DOWN WAITING ON 1ST CHARGE FROM 13:35 TO 14:11

HEAT #	GRADE	TIME (minutes) TAP/ 2nd / 3rd	CHG: CHG: CHG	TAP	TIME of TAP	POWER (minutes) ON: OFF	LAG FACE DIFF.	CAST (EX: 4/2)	TONS/ HEAT	T/A	FURNACE ONLY DELAYS	DELAYS CAUSING CASTER DELAYS
1	110	18	2	12/0	07:34	53:36	2	3	48.3	7/4		23.8
2	110	19	2	131.5	8:46	120:48	10	3	49.9			18.3
3	110	21	4	2	147.3	9:59	59:65	7	3/4	52.2		27.0
4	110	6	2	105.0	12:31	52:42	2	4	50.1			19.5
5	110	12		102.8	11:41	57:39	8	4	52.1			0.5
6	110	29	2	135.5	12:47	128:42	10	4	51.9		GUN B-4 HENT SET H-2 OFFCT	18.8
7	110	13	2	104.8	13:28	54:51	5	7	4/3	55.1		23.3
8	110	7	9	2	141.3	14:40	125:42	2			SEA 1-3.1000	21.4
9	110											
10	110											
11												

DATE 5-12-00
SHIFT 3-11
SUPERVISOR M. NICHOLS

MELTER'S LOG

Additional Comments: LMF down after W-1368. Replace 2 heat shields. Ship straight to caster

HEAT #	GRADE	TIME (minutes) TAP/ 2nd 3rd CHG: CHG: CHG	TAP I TAP	TIME of TAP	POWER (minutes) ON/OFF	LAG FCE DIFF @ TAP	# CAST (EX 4/2)	TONS/ HEAT	T/A	FURNACE ONLY DELAYS	DELAYS CAUSING CASTER DELAYS
1	W-1367	110 45.5 a -	140.5	15:46	58.5 8.20	45.2 10	4	46.7	(T/A)		21.900 PD 15.3
2	X-1282	110 17.3 2 -	123.0	16:37	58.8 64.2	46.1	4	50.9		TA 84 tap to no cast	K 21.760 PD 19.8
3	W-1368	110 101850 39.5 Return Heat	93.0	17:18	14.8 68.5	45.1				Return X-1281, came through plates.	K 5.010 PD 1.3
4	X-1283	"	140.8	19:00	63.0 77.8	45.9 10	4	61.1		1st heat straight to caster.	K 22.400 PD 1.5
5	W-1369	" 9.0 2 a	157.0	19:55	63.8 93.2	46.1	No cast			slide gate went shut off hold over fce.	K 22.740 PD 10.0
6	X- + ! IT ~	" 2 -									K PD
7	W-1370										K PD
8											
9											
10											
11											

Document No MS-015

Revision Date 02-15-99

Revision Level D

WHITE - CLERK • CANARY - MELT SHOP OFFICE • PINK - FURNACE PULPIT

MELTER'S LOG

DATE 5-11-00
SHIFT 11-7
SUPERVISOR

Additional Comments: 23:12 - 23:25 Adj. Barbin

Bottom 10" Low 6-7 lines

HEAT #	GRADE	TIME (minutes)			TAP / TAP	TIME of TAP	POWER (minutes)		LAG FCE DIFF @ TAP	# CAST (Ex: 4/2)	TONS/ HEAT	T/A	FURNACE ONLY DELAYS	DELAYS CAUSING CASTER DELAYS	
		TAP/1 CHG/CHG	2nd CHG/CHG	3rd CHG/CHG			ON	OFF							
1	X-1264	112	24	2		106.5	23:20	57.5	3:28	#6	4/3	44.5	Fly Furnish	10	KW 17360
															G 14473
														13.5	G 42862
2	W-1350	921		2		144.0	0:51	57.8	23:5	#10	3	48.6	Set #1 to 2 E. Deck		KW 22310
															G 11899
													88 Carbon Bottom 10" Low	14.8	G 48678
3	X-1265	921	8	2		117.8	1:17	56.5	4:12	#8	3	47.4			KW 2170
															G 1370
														20.5	G 40853
4	W-1351	120	10	2		92.3	2:23	57.5	3:33	#6	3	51.7			KW 22350
															G 12887
														4.5	G 41597
5	X-1266	413	20	2		117.3	3:14	56.5	4:02	#10	3	53.0	Delay 1st Charge Change to Furn		KW 21600
															G 12151
														23	G 42644
6	W-1352	413	25	3		114.5	4:16	55.0	5:20	#8	3	49.7	Repaired Bottom B-4 this heat		KW 21610
															G 13790
														8.8	G 38751
7	X-1267	413	15	2		115.0	5:02	55.5	5:55	#2	3	46.3			KW 20910
															G 15713
														22.5	G 41824
8	W-1353	147	6	5		110.8	6:06	56.0	6:58	#6	3	41.2			KW 21320
															G 13338
														21.0	G 34298
9	X-1268	147		2		107.8	6:55	55.5	7:48	#10	3	44.4			KW 19490
															G 16567
														26	G 41876
10															
11															

Document No. MS-015

Revision Date: 02-15-99

Revision Level: D

WHITE - CLERK • CANARY - MELT SHOP OFFICE •

PINK - FURNACE PULPIT

DATE 5-11-00
 SHIFT 7-3
 SUPERVISOR H.W. SALYERS

MELTER'S LOG

Additional Comments: ① MAIN FAN DOWN FROM 0800 TO 13:40.

HEAT #	GRADE	TIME (minutes)			TAP / TAP	TIME of TAP	POWER (minutes)		LAG FCE DIFF. @ TAP	# CAST (Ex 4/2)	TONS/ HEAT	T/A	FURNACE ONLY DELAYS	DELAYS CAUSING CASTER DELAYS	
		TAP/ CHG	2nd CHG	3rd CHG			ON	OFF							
1 W-1354	147	7.9	2	-	120.0	8:06	58.3	54.2	# 8	3/2	38.0			14.3	E 22090 K 13245 O 33667
2 X-1269	147	25	2	-	4713	14:40	678	4615	2	3	57.7	(T/A)	See 1-2	7.0	K 25830 E 22321 O 63,014
3 W-1355	147														K G O K G P
4															
5															
6															
7															
8															
9															
10															
11															

DATE	5-11-00	MELTER'S LOG
SHIFT	3-11	Additional Comments: Burners in hold on X-1270 20,400 KWH-2846°
SUPERVISOR	Nichols	No Thermocouples for Keith preheater. Put gas pipe in ladle.

HEAT #	GRADE	TIME (minutes)			TAP / TAP	TIME of TAP	POWER (minutes)		LAG FCE DIFF @ TAP	# CAST (Ex: 4/2)	TONS/ HEAT	T/A	FURNACE ONLY DELAYS	DELAYS CAUSING CASTER DELAYS
		TAP/	2nd	3rd			ON	OFF						
1	W-1355	147	9.7	2	-	430.0	15.11	55.8	3782	8	459	0	wouldn't open, return to fcs.	K 24,230 PD 12.8 G 22,371 O 63,014
2	X-1270	756	6.3	9	-	125.3	16:45	67.8	525	10	461	3/4	44.7	T/A K 26,410 PD 13.3 G 11,984 O 32,715
3	W-1356	521	25.8	2	-	201.8	18:33	69.3	1335	2	451	4	47.7	T.A. B4 Tap. K 26,800 PD 25.5 G 14,289 O 32,839
4	X-1271	278	22.8	2	-	160.8	19:25	58.3	1025	7	459	4	56.4	Gun fcs. 9,500 lbs. in slag pot after this heat. K 33,090 PD 2.5 G 12,961 O 33,255
5	W-1357	147	300	Heat	Return	106.5	20:19	11.3	952	8	461	4	50.0	Return W-1355, wouldn't open. K 4,160 PD 0 G 5,883 O 12,233
6	X-1272	412	7.5	5	-	99.3	21:05	66.9	325	10	451	4	48.9	10,500 lbs. in pot. K 23,150 PD 0 G 9,757 O 38,255
7	W-1358	408	0.7	2	-	99.0	21:56	57.0	420	2	459			8,500 lbs. in pot. K 21,520 PD 19.3 G 13,594 O 40,926
8	X-1273	"	2	-		98.3	22:58	53.0	413	7	461			K 18,560 PD 17.0 G 15,031 O 50,540
9														
10														
11														

Document No MS-015

Revision Date 02-15-99

Revision Level D

WHITE - CLERK • CANARY - MELT SHOP OFFICE • PINK - FURNACE PULPIT

EAF Melting Log (time)

	Start	Stop	Scrap Wt.
Last Tap		19:35	
1st Chg.	19:40	20:05	75,000
2nd Chg.	20:10		40,000
3rd Chg.			
Tapping	21:05	21:10	
Tap Temp.	3030	Totals:	
Total Time of Heat.			

LMF Treatment Log (time)

Car Number	2
Last Heal - Treatment Stop	21:21
Current Heat - Treatment Start	21:28
Preparation Time	
Current Heal - Treatment Stop	22:16
Total Time of Heat	14:43

Power & Supply Consumption

	Amount Used	
	At Furnace	At LMF
Power Meter	73050	3075
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Delta	18	
Wall Heat	18	
Thermocouples		
Samplers		
Oxygen Probes		

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon	4-15		40		Carbon	
Cal Al						75% FeSi		150	25	25	Cal Sil	150
Spar			5-15			SiMn		1400			FeCb	
Cal C			5-15			HC FeMn			105		FeB	
Lime	4000		1000			MC FeMn				100	FeTi	
DoloLime						FeCr					FeV	
NI	1	200				Moly Oxide					Nitrovan	25-18
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	21:30	21:50	22:00	22:14	22:15						Final N ₂ (ppm):	
Temp. (°F)	2845	2856	2910	2908	2912						Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice:	412	Roll No:	044	Chemistry:								V
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al ^{II}	
Spec.	14	110	20	25	22	35	30	20	0.4			
Prelim.	7	11	4	55	-	27	10	10	0.2			
Prelim	9	51	7	45	22	28	27	13	2	13	0.65	
Prelim	14	103	7	40	22	28	27	13	2	13	0.6	
Prelim												
Prelim												
Prelim												
Final	.15	1.11	.011	.010	.26	.30	.32	.13	.03	.014		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	555	112
Final	.004	.066	.001	.000	.000	.0000	.0008	+ .0015		Sample Type:		

Heat No.	2-1272	Product Code	21H
Split	B.O. #	Billet Size	Length
A	5978	5.00X7.00	229
B	0	0	0.0
C	0	0	0.0
D	0	0	0.0
E	0	0	0.0
F	0	0	0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
912	233	451	10		6	6	5-11-2004	3-11	2-1272

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

2-1272-0150

EAF Melting Log (time)

	Start	Stop	Wt
Last	18:50	18:35	
1st Chg.			
2nd Chg.			
3rd Chg.			
Tapping	20:20	20:25	
Tap Temp.	2987	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)

Car Number	1
Last Heat - Treatment Stop	20:40
Current Heat - Treatment Start	20:42
Preparation Time	
Current Heat - Treatment Stop	21:21
Total Time of Heat	38:06

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.
50 tons	
couldn't get open	

Power & Supply Consumption

	At Furnace	At LMF
Power Meter	Amount	21.2
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Delta	17	
Wall Heat	17	
Thermocouples		
Samplers		
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon			200	20	Carbon	
Cal Al						75% FeSi			50		Cal Sil	150
Spar			2.13			SiMn					FeCo	2-18
Cal C			K-C			HC FeMn					FeB	
Lime			300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil		413				copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	20:15	20:52	21:00	21:19							Final N ₂ (ppm):	
Temp. (°F)	2880	2796	2825	2815							Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice:	147	Roll No:	044	Chemistry:	N/A						
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	95	57	20	25	17	35	20	15	0.6		
Prelim.	84	58	11	2	12	21	8	12	0.2		
Prelim.	74	55	14	19	16	21	8	13	0.1	9	0.26
Prelim.	87	55	15	17	16	21	8	13	2	10	0.26
Prelim.											
Prelim.											
Prelim.											
Final	.96	.55	.014	.017	.16	.21	.08	.13	.02	.009	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	147
Final	.004	.006	.026	.000	.000	.0000	.0006	.0013		Sample Type:	555

GRADE

1095 MOD

Heat No. W1357

Product Code 21H

Split 8.0. # Billet Size Length Count Tons Stack #Scrap Tons

A 5972 5.00X7.00 202 51 50.0 11-3 0 0.0

B 0 0 0.0 0 0.0

C 0 0 0.0 0 0.0

D 0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
712	235	461	8		35	10	5-11-2020	3-11	W-1357

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption		
	Start	Stop	Scrap Wt.	Car Number	2	Amount Used		
Last Tap		14:46		Last Heat - Treatment Stop	19:55	At Furnace	At LMF	
1st Chg.	17:20	17:53	75,000	Current Heat - Treatment Start	20:--	Power Meter	23090	242
2nd Chg.	17:55		40,000	Preparation Time		Electrode #1		
3rd Chg.				Current Heat - Treatment Stop	20:20	Electrode #2		
Tapping	19:30	19:35		Total Time of Heat	38:12	Electrode #3		
Tap Temp.	3020	Totals:		Reason for Return to LMF / Furnace		Lance Sections		
Total Time of Heat:				Est. Return Wgt.	Added Scrap Wgt.	Roof Delta	17	
LMF	Ladle Weight					Wall Heat	17	
Steel	Tare Weight	49,000 #				Thermocouples		
Weight	Steel Weight					Samplers		
						Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
slag Cond.		1000				Carbon			140	40	Carbon	
Cal Al						75% FeSi		10		25	Cal Sil	150
Spar			3-13			SiMn		1600			FeCb	
Cal C			K-C			HC FeLin			20		FeB	10-15
Lime	4000		400			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	18:17	19:21	20:14	20:17							Final N ₂ (ppm):	
Temp. (°F)	2815	2966	2830	2855							Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice: 278

Roll No: 044

Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^u	Al
Spec.	31	125	20	25	22	35	20	20	0		
Prelim.	17	17	4	47	-	19	8	13	02		
Prelim	14	107	12	36	24	19	8	14	2	10	
Prelim	36	121	13	29	22						
Prelim											
Prelim											
Final	.30	1.22	.013	.025	.21	.19	.08	.16	.02	.010	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	555
Final	.004	.002	.000	.000	.000	.0018	.0011	.0013		Sample Type:	
GRADE 15B28 SQ											

Heat No. X1271		Product Code 23K	
Split	B.O. 1	Billet Size	Length Count Tons Stack #Scrap Tons
A	5975	5.00X7.00	228 47 52.0 003 4 4.4
B	0		0 0 0.0 0 0.0
C	0		0 0 0.0 0 0.0
D	0		0 0 0.0 0 0.0
Melter	LMF Operator	Ladleman	Ladle No.
912	435	459	7
Gale No.	Heels on Ladle	Heels on Plug	Date
	33	1	5-11-2000
Shift	Heat Number		
3-11	X-1271		
Document No: MS-013			
Revision Date: 04-19-1999			
Revision Level: F			
Remarks: 304 Furnace			
A 20 - 117.1.1			

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number		Amount Used	
Last Tap		17:15		Last Heat - Treatment Stop		At Furnace	At LMF
1st Chg.	15:43	16:21	000	Current Heat - Treatment Start		21,800	2725
2nd Chg.	16:23		53,060	Preparation Time			
3rd Chg.				Current Heat - Treatment Stop			
Tapping	18:30	18:35		Total Time of Heat			
Tap Temp.	3040	Totals:		48:25			
Total Time of Heat				Reason for Return to LMF / Furnace		Lance Sections	
				Est. Return Wgt.		Roof Della	16
				Added Scrap Wgt.		Wall Heat	16
						Thermocouples	
						Samplers	
						Oxygen Probes	

LMF	Ladle Weight	
Steel	Tare Weight	49.000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	Carbon
Slag Cond.		11:00				Carbon	4-B	4-B	20		Cal Sil	150
Cal Al						75% FeSi		200		25	FeCb	3-15
Spar			3-11			SiMn		900			FeB	
Cal C			4-C			HC FeMn					FeTi	
Lime	4000	900				MC FeMn					FeV	
DoloLime						FeCr		1000	25		Nitrovan	
NI						Moly Oxide		9-C			FeS	
Cal Sil						Copper						

Argon Log

Argon Flow										Rinse Flow:

Temperatures and Times

Time	17:05	18:17	18:49	19:18	19:26	19:30	19:44	19:52	19:55	Final N ₂ (ppm):
Temp. (°F)	2803	2815	2899	2789	2849	2906	2891	2874	2882	Final Temp (°F):
Oxygen (ppm)										Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	521	Roll No:	044	Chemistry:							112 412
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	50	88	20	25	22	30	20	95	20		
Prelim.	38	20	18	55	1	18	4	14	02		
Prelim	43	90	23	36	25	19	9	86	20	10	028
Prelim	30	20	24	19	23	19	9	92	20	9	028
Prelim											
Prelim											
Prelim											
Final	.50	.91	+.025	.015	.26	.19	.09	.94	.21	.010	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	521
Final	.004	+.007	.029	.000	.000	.0000	.0007	+.0029		Sample Type:	555
GRADE 4150											

Heat No. W1356

Product Code 2B1

Split B.O. # Billet Size Length Count Tons Stack #Scrap Tons

A 5974 5.00X7.00 197 42 40.1 003 8 7.6

B 0 0 0 0 0 0 0 0 0.0

C 0 0 0 0 0 0 0 0 0.0

D 0 0 0 0 0 0 0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heals on Ladle	Heals on Plug	Date	Shift	Heat Number
912	233	452			12	17	5-11-2000	3-11	W-1356

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)

	Start	Stop	Scrap Wt.
Last Tap	14:55	15:25	80000
1st Chg.	15:34		30000
2nd Chg.			
3rd Chg.			
Tapping	16:45	16:50	
Tap Temp.	3020	Totals:	
Total Time of Heat:			

LMF Treatment Log (time)

Car Number	2
Last Heat - Treatment Stop	17:28
Current Heat - Treatment Start	17:25
Preparation Time	
Current Heat - Treatment Stop	19:04
Total Time of Heat	99:34

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption

	Amount Used	
	At Furnace	At LMF
Power Meter	26410	6772
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Delta	16	
Wall Heat	16	
Thermocouples		
Samplers		
Oxygen Probes		

LMF
Steel
Weight

Ladle Weight	
Tare Weight	49,000 #
Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					We Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon		100	20		Carbon	
CalAl						75% FeSi		200			CalSi	150
Spar			3-13			Si in		1000			FeCb	
Cal C			1-0			HC FeMn			10		FeB	
Lime	4000		300			MC FeMn					FeTi	
DoloLime						FeCr		1000	500	150	FeV	150
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	16:15	16:23	16:29	16:43	18:16	18:36	18:46	18:53	19:00		Final N ₂ (ppm):
Temp (°F)	2844	2872	2942	2995	2768	2898	2876	2895	2893		Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice: 756 Roll No: 044 Chemistry: V

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	AT
Spec.	50	85	20	25	22	30	20	100	06		
Prelim.	19	16	7	48	-	18	7	11	02		
Prelim	39	24	10	15	25	18	9	22	2	8	181
Prelim	48	82	11	12	25	16	9	84	2	9	182
Prelim											
Prelim											
Prelim											
Final	.52	.83	.012	.010	.27	.18	.09	.95	.02	.009	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	756
Final	.004	.185	.001	.000	.000	.0000	.0010	+.0015	4.29	Sample Type:	555
GRADE 6150H											no message defined

Heat No. X-1270

Product Code 20W

Split B.B. I Billet Size Length Count Tons Stack # Scrap Tons

A 0973 5.00X7.00 174 53 44.7 113 0 9.0

B 0 0 0 0 0 0 0 0.0

C 0 0 0 0 0 0 0 0.0

D 0 0 0 0 0 0 0 0.0

Matter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
912	235	461	10		5	5	5-11-00	3/11	X-1270

Document No: MS-013

Revision Due: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption			
	Start	Stop	Scrap Wt.	Car Number	1	If Used At Furnace At LMF			
Last Tap				Last Heat - Treatment Stop	16:11	Power Meter	29.0		
1st Chg.	11:38	12:32	80000	Current Heat - Treatment Start	16:13	Electrode d1			
2nd Chg.	14:34		35	Preparation Time		Electrode d2			
3rd Chg.				Current Heat - Treatment Stop	17:22	Electrode #3			
Tapping	15:10	15:25		Total Time of Heat	16:52	Lance Sections			
Tap Temp.	3020	Totals:		Reason for Return to LMF / Furnace		Roof Delta	15		
Total Time of Heat:				Est. Return Wgt.	Added Scrap Wgt.	Wall Heat	15		
						Thermocouples			
						Samplers			
						Oxygen Probes			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon		4-B	300	450	Carbon	
Cal Al						75% FeSi			1:15	50	Cal Si	150
Spar			7-B			SiMn		500			FeCl	3-15
Cal C			4-C			HC FeMn			100	100	FeB	
Lime	4000		900			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni	1					Moly Oxide					Nitrovan	
Cal Sil		4-B				Copper					FeS	

Argon Log

Argon Flow										Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	15:07	16:33	16:53	17:53	18:02	18:04				Final N ₂ (ppm):	
Temp. (°F)	2961	2754	2818	2844	2872	2885				Final Temp (°F):	
Oxygen (ppm)										Final O ₂ (ppm):	

Chemistry and Billet Information

Practice:	147	Roll No:	044	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}		
Spec.	95	57	20	25	17	3.5	20	15	0.3			
Prelim.	10	11	4	39	-	22	7	8	0.2			
Prelim.	14	11	4	19	11	22	7	10	2	9	0.25	
Prelim.	70	10.6	7	16	18	23	5	11	2	14	0.27	
Prelim.	88	5.5	5	13	20	0.1	7	10	2	9	0.24	
Prelim.	88	5.1	5	11	20	0.1	7	10	2	9	0.23	
Prelim.												
Final	.00	.00	.000	.000	.00	.00	.00	.00	.00	.000		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	147	
Final	.000	.000	.000	.000	.000	.0000	.0000	.0000		Sample Type:	898	
GRADE 1095 MOD												NU CAST

Heat No. W-1355

Product Code 21H

Split B.O. # Billet Size Length Count Tons Stack #Scrap Tons

A	5972	5.00X7.00	202	0	0.0	0	0.0
B	0		0	0	0.0	0	0.0
C	0		0	0	0.0	0	0.0
D	0		0	0	0.0	0	0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
912	235	459	8		34	9	5-11-00	3/1	W-1355

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

Delay 0805-1345 big blower out on bog house

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number	X	Amount Used	
Last Tap		0657		Last Heat - Treatment Stop		At Furnace	At LMF
1st Chg.	0722	0758	60000	Current Heat - Treatment Start	14:51	Power Meter	25291 21/20
2nd Chg.	11:32		55000	Preparation Time		Electrode #1	1
3rd Chg.				Current Heat - Treatment Stop	16:11	Electrode #2	1
Tapping	14:40	14:45		Total Time of Heat	79:40	Electrode #3	
Tap Temp.	3271	Totals:		Reason for Return to LMF / Furnace		Lance Sections	
Total Time of Heat:				Est. Return Wgt.	Added Scrap Wgt.	Roof Delta	15
LMF	Ladle Weight					Wall Heal	15
Steel	Tare Weight	49,000 #				Thermocouples	3
Weight	Steel Weight					Samplers	
						Oxygen Probes	

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						Alloys Added (lbs.)					r Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Contd		1000				Carbon		6-B	400	750	Carbon	
Cal Al						75% FeSi		200			Cal Si	150
Spar			2-B			SiMn		400			FeCb	3-B
Cal C						HC FeMn			150	150	FeB	
Lime	4000		700			MC FeMn				50	FeTi	
DoloLime						FeCr					FeV	
Ni	1					Moly Oxide					Nitrovan	
Cal Si		4-B				Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	1430	1436	1439	15:05	15:24	15:44	15:55	16:01	16:08	Final N ₂ (ppm):
Temp. (°F)	2999	2964	3071	2833	2833	2837	2837	2840	2839	Final Temp (°F):
Oxygen (ppm)										Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	147	Roll No:	044	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al ^{III}	
Spec.	95	57	20	25	17	35	20	15	06			
Prelim.	4	7	5	40	0	24	8	6	2	10		
Prelim	83	30	5	10	21	15	8	2	2	10	025	
Prelim	84	31	5	21	20	23	8	7	2	10	025	
Prelim	80	52	6	12	20	23	8	7	2	10	025	
Prelim	91	52	6	11	20	23	6	7	2	10	025	
Prelim												
Final	1.01	.57	.007	.010	.21	.23	.08	.08	.02	.010		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	147	
Final	.004	.004	.026	.000	.000	.0000	.0003	.0016		Sample Type:	555	

GRADE

1095 MOD

Heat No. X-1269

Product Code 215

Split R.O. 1 Billet Size Length Count Tons Stack #Scrap Tons

A 5971 5.00X7.00 213 50 51.7 11-3 0 0.0

B 0 0 0 0 0.0 0 0.0

C 0 0 0 0 0.0 0 0.0

D 0 0 0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
919	235	114	2		16	16	5-11-00	13	X-1269

Document No. MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

Let #1 & 2 eld. Delay 0758-13:40 scrap crane down & big from on bay house

EAF Melting Log (ti)			
	Start	Stop	Scrap Wt.
Last Tap		06:08	
1st Chg.	06:15	07:02	61400
2nd Chg.	07:02		54
3rd Chg.			
Tapping	08:00	08:05	
Tap Temp.	3066	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)	
Car Number	825
Last Heat - Treatment Slog	839
Current Heat - Treatment Start	
Preparation Time	96.3
Current Heat - Treatment Stop	932
Total Time of Heat	

Reason for Return to LMF / Furnace	
Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption		
	Amount Used	
	At Furnace	At LMF
Power Meter	22090	2875
Electrode #1		
Electrode #2		
Electrode #3	1	
Lance Sections		
Roof Delta	014	
Wall Heat	014	
Thermocouples	3	
Samplers		
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon					Carbon	
Cal Al						75% FeSi		100			Cal Sil	
Spar						SiMn		300			FeCb	3-13
Cal C						HC FeMn					FeB	
Lime	4000					MC FeMn					FeTi	
DoloLime						FeCr					FeV	
NI	1					Moly Oxide					Nitrovan	
Cal Sil		4-15				Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	08:46	07:56									Final N ₂ (ppm):	
Temp (°F)	2848	2998	3264								Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice:	147	Roll No:	044	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al	
Spec.	45	62	20	25	12	35	20	15	06			
Prelim.	19	15	6	54	1	26	8	12	2	10		
Prelim	34	38		32	6							
Prelim	78	54		22	16							
Prelim												
Prelim												
Prelim												
Final	.90	.55	.008	.015	.23	.25	.07	.14	.02	.010		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code	147	
Final	.003	.004	.025	.000	.000	.0000	.0003	.0014		Sample Type:	555	

GRADE

1095 MOD

Heat No.	W-1354	Product Code	21F									
Split	B.O. #	Billet Size	Length	Count	Tons	Stack	#Scrap	Tons				
A	5969	4.75X8.00	200	36	38.0	11-3	0	0.0				
B	0		0	0	0.0		0	0.0				
C	0		0	0	0.0		0	0.0				
D	0		0	0	0.0		0	0.0				

Melter	LMF Operator	Lademan	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
919		185	8		32	8	5-11-00	7/3	20-1354

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks: 2103 elect.

EAF Melting Log (time)			
	Start	Stop	Scrap Wt.
Last Tap		05:10	
1st Chg.	05:20	06:03	64700
2nd Chg.	06:03		461
3rd Chg.			
Tapping	06:12	06:57	
Tap Temp.	2624	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)	
Car Number	
Last Heat - Treatment Stop	07:16
Current Heat - Treatment Start	07:19
Preparation Time	6321
Current Heat - Treatment Stop	08:25
Total Time of Heat	

Reason for Return to LMF / Furnace	
Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption		
	Amount Used	
	At Furnace	At LMF
Power Meter	19490	1925
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Della	14	
Wall Heat	14	
Thermocouples	2	
Samplers		
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		4000				Carbon			500		Carbon	
Cal Al						75% FeSi		100	125		Cal Sil	150
Spar						SiMn		350			FeCb	30
Cal C						HC FeMn			400		FeB	
Lime	4000					MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	05:58	06:45									Final N ₂ (ppm):	
Temp. (°F)	2941	3024									Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice:	147	Roll No:	044	Chemistry:	5							
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al	
Spec.	95	57	0020	025	17	35	20	15	06	20		
Prelim.	7	60	4	49	0	7		9	1	9		
Prelim	11	23		36	18							
Prelim	20	57		18	18							
Prelim												
Prelim												
Prelim												
Final	.92	.56	.006	.014	.22	.22	.07	.11	.02	.009		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	147	
Final	.003	.003	.030	.000	.000	.0000	.0007	.0013		Sample Type:	555	

GRADE

1095 MOD

Heat No. X-1268	Product Code 21F										
Billet R.O. #	Billet Size	Length	Count	Tons	Stack	*Scrap	Tons				
6	4.75X8.00	200	42	44.4	11-3	0	0.0	0	0.0	0	0.0
"	0	0	0	0.0	0	0.0	0	0.0	0	0.0	0
"	0	0	0	0.0	0	0.0	0	0.0	0	0.0	0
"	0	0	0	0.0	0	0.0	0	0.0	0	0.0	0

Melter	LMF Operator	Ladleman	Ladle No.	Gale No.	Heels on Laffs	Hoots on Plug	Date	Shift	Heat Number
613		232	10		4		5-11-01	147	X-1268

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)			LMF Treatment Log (time)		Power Supply Consumption	
Start	Stop	Scrap Wt.	Car Number	2	Amount Used	
Last Tap	04:20		Last Heat - Treatment Stop	06:14	At Furnace	At LMF
1st Chg.	04:25	75200	Current Heat - Treatment Start	06:16	Power Meter	214/10 2115
2nd Chg.	05:13	40,	Preparation Time	60.31	Electrode #1	
3rd Chg.			Current Heat - Treatment Stop	7:14	Electrode #2	
Tapping	06:03	06:08	Total Time of Heat		Electrode #3	
Tap Temp.	30.55	Totals:			Lance Sections	
Total Time of Heat:			Reason for Return to LMF / Furnace		Roof Delta	0/3
			Est. Return Wgt.		Wall Heat	0/3
			Added Scrap Wgt.		Thermocouples	
					Samplers	
					Oxygen Probes	

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1,000	60/40			Carbon		8-3	300		Carbon	
Cal Al			3-B			75% FeSi		100	50		Cal Sil	
Spar			4-C			SiMn		300			FeCb	3-L
Cal C						HC FeMn			150		FeB	
Lime	4,000		300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
NI	1					Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow										Rinse Flow:

Temperatures and Times

Time	06:26	06:48								Final N ₂ (ppm):
Temp. (°F)	2833	2890								Final Temp (°F):
Oxygen (ppm)										Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	147	Roll No:	044	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al	
Spec.	95	57	020	025	17	35	20	15	06	20		
Prelim.	23	18	9	47		19	7	14	2	8		
Prelim	57	36		24	21	28						
Prelim	83	48										
Prelim	71	47										
Prelim												
Prelim												
Final	.96	.49	.007	.010	.20	.20	.07	.14	.02	.009		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	147	
Final	.004	.003	.029	.000	.000	.0000	.0005	.0013		Sample Type:	555	

GRADE

1095 MOD

Heat No. W-1353

Product Code 11F

Selling B.O. # Billet Size Length Count Tons Stack # Scrap Tons

5989 4.75X8.00 200 39 41.2 11-3 0 0.0

0 0 0 0 0.0 0 0.0

0 0 0 0 0.0 0 0.0

0 0 0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
973	215	461	6		31	31	5-11-00	11-7	20-1353

Document No. MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)		
Start	Stop	Scrap Wt.
1st Tap	03:15	
1st Chg.	03:30	04:13
2nd Chg.	04:17	44
3rd Chg.		
4th Chg.	05:05	05:10
5th Chg.	05:55	Totals:
Total Time of Heat:		

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)	
Car Number	1
Last Heat - Treatment Stop	05:22
Current Heat - Treatment Start	05:24
Preparation Time	50:11
Current Heat - Treatment Stop	06:14
Total Time of Heat	

Reason for Return to LMF / Furnace	
Est. Return Wgt.	Added Scrap Wgt.

Power Supply Consumption		
	Amount Used	
	At Furnace	At LMF
Power Meter	20900	2450
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Delta	13	
Wall Heat	13	
Thermocouples		2
Samplers		2
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		4000	60/40			Carbon			40		Carbon	
Cal Al			2-B			75% FeSi		125	30		Cal Sil	300
Spar			2-C			SiMn		1300			FeCb	
Cal C						HC FeMn			120		FeB	
Lime	4000		300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
NI		220				Moly Oxide					Nitrovan	3B
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow	
------------	--	--	--	--	--	--	--	--	--	--	------------	--

Temperatures and Times

Time	05:38	05:58									Final N ₂ (ppm):
Temp. (°F)	2891	2915									Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	413	Roll No:	044	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^h	Al	
Spec.	14	110	020	025	22	25	30	20	06	20		
Prelim.	9	11	4	49	2	22	8	8	2	8		
Prelim	9	91		28	22		26	149				
Prelim	13			17								
Prelim												
Prelim												
Prelim												
Final	.13	1.02	.008	.014	.24	.24	.27	.12	.02	.010		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	413	
Final	+.006	.050	.000	.000	.001	.0000	.0013	+.0017		Sample Type:	555	
GRADE A572-GR/60 CV												

Heat No. X-1267

Product Code 12K

Split	R.O. #	Billet Size	Length	Count	Tons	Slack	#Scrap	Tons
A	5982	4.75X8.00	209	42	46.3	11-3	0	0.0
B	0		0	0	0.0		0	0.0
C	0		0	0	0.0		0	0.0
D	0		0	0	0.0		0	0.0

Melter	LMF Operator	Ledlemen	Ladle NO.	Gale NO.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
973	215	419	2		15	15	5-11-00	11-7	X-1267

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)			
	Start	Stop	Scrap Wt
asl Tap	---	02:25	
1st Chg.	02:56	03:20	71,200
2nd Chg.	03:23		44
3rd Chg.			
Tapping	04:15	04:20	
ap Temp.	3055	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)	
Car Number	2
Last Heat - Treatment Stop	04:21
Current Heat - Treatment Start	04:23
Preparation Time	53:57
Current Heat - Treatment Stop	05:22
Total Time of Heat	

Reason for Return to LMF / Furnace	
Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption		
	Amount Used	
	At Furnace	At LMF
Power Meter	21150	3000
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Delta	012	
Wall Heat	012	
Thermocouples		3
Samplers		2
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000	60/40			Carbon			30		Carbon	
Cal Al			3-B			75% FeSi		125			Cal Sil	
Spar			3-C			SiMn		1300				
Cal C						HC FeMn			100		FeB	
Time	4000		300			MC FeMn					FeTi	
Dolo/Lime						FeCr					FeV	
NI	1	220		100		Moly Oxide					Nitrovan	3B
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow	
------------	--	--	--	--	--	--	--	--	--	--	------------	--

Temperatures and Times

Time	04:33	04:51	05:09								Final N ₂ (ppm):
Temp (°F)	2875	2716	2880								Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	4/13	Roll No:	044	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al	
Spec.	14	110	020	025	22	25	30	20	06			
Prelim.	6	9	1	40		28	8	8	2	12		
Prelim	10	96		23	24		18	154				
Prelim	14	102		14	22		27	153				
Prelim												
Prelim												
Prelim												
Final	.15	1.05	.007	.010	.22	.28	.27	.10	.02	.014		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	413	
Final	+.004	.054	.000	.000	.000	.0000	.0010	+.0015		Sample Type:	555	
GRADE A572-GR/60 CV												

Heat No. W-1352

Product Code 22K

5-Lit B.O. # Billet Size Length Count Tons Stack #Scrap Tons

A	5982	4.75X8.00	209	45	49.7	II-3	0	0.0
B	0		0	0	0.0		0	0.0
C	0		0	0	0.0		0	0.0
D	0		0	0	0.0		0	0.0

Moller	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
973	215	232	8		32	32	5-11-00	11-7	W-1352

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

High Carbon

EAF Melting Log (time)

	Start	Stop	Scrap Wt.
Last Tap		01:20	
1st Chg.	01:40	02:20	73260
2nd Chg.	02:22		421
3rd Chg.			
Tapping	03:10	03:15	
Tap - e	3050	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49.000 #
Weight	Steel Weight	

Car Number

Last Heat - Treatment Stop	03:18
Current Heat - Treatment Start	03:20
Preparation Time	60:22
Current Heat - Treatment Stop	04:19
Total Time of Heat	

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption

	Amount Used	
	At Furnace	At LMF
Power Meter	20120	2775
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Della	12	
Wall Heat	12	
Thermocouples		2
Samplers		1
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)					Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1,000	60/40		Carbon			40		Carbon	
Cal Al			3-B		75% FeSi		125	30		Cal Sil	150
Spar			4-C		SiMn		1300			FeCb	
Cal C					HC FeMn			125		FeB	
Lime	4,000		300		MC FeMn					FeTi	
DoloLime					FeCr					FeV	
Ni		220			Moly Oxide					Nitrovan	3-13
Cal Sil					Copper					FeS	

Argon Log

Argon Flow										Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	03:30	04:08								Final N ₂ (ppm):	
Temp. (°F)	2928	2913								Final Temp (°F):	
Oxygen (ppm)										Final O ₂ (ppm):	

Chemistry and Billet Information

Practice: 413 Roll No: 044 Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	14	110	020	025	22	25	30	20	06		
Prelim	9	11	3	45	—	21	9	9	2	9	
Prelim	9	91		29	22		28	175			
Prelim											
Prelim											
Prelim											
Prelim	14	1.01	.007	.011	21	21	20	10	02	.010	
Final											

Element	0.04	Al	+.075	V	.000	Nb	.000	Ti	.000	Zr	.0000	B	.0010	Ca	.0014	Zn	DI	Grade Code:
Final	GRADE				A572-GR/60		CV											Sample Type: 555

Heat No. X-1266	Product Code 22K
Split B.O. #	Billet Size Length Count Tons Stack #Scrap Tons
6900	4.75X8.00 207 45 49.7 11-3 3 3.3
I:	0 0 0.0 0 0.0
C	0 0 0.0 0 0.0
n	0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
973	215	461	10		5	3	5-11-00	11-9	X-1266

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)			
	Start	Stop	Scrap Wt.
Last Tap		00:55	
1st Chg.	01:03	01:25	71200
2nd Chg.	01:30		45
3rd Chg.			
Tapping	02:20	02:25	
Tap Temp.	3055	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)	
Car Number	2
Last Heat - Treatment Stop	02:25
Current Heat - Treatment Start	02:28
Preparation Time	47:47
Current Heat - Treatment Stop	03:18
Total Time of Heat	

Reason for Return to LMF / Furnace	
Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption		
	Amount Used	
	At Furnace	At LMF
Power Meter	22390	20000
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Delta	011	
Wall Heat	011	
Thermocouples		3
Samplers		2
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond		4000	60/40			Carbon			110	30	Carbon	
Cal Al			2-B			75% FeSi		250			Cal Sil	3.50
Spar			2-C			SiMn		100			FeCb	
Cal C						HC FeMn					FeB	
Lime	4000		300			MC FeMn					FeTi	
Dolo/Lma						FeCr					FeV	
NI						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log											
Argon Flow											Rinse Flow:

Temperatures and Times											
Time	02:44	02:49	03:02								Final N ₂ (ppm):
Temp. (°F)	2931	2963	2903								Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	120	Roll No:	044	Chemistry:										
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al			
Spec.	34	.20	0.26	0.25	22	35	20	14	06	20				
Prelim.	17	15	14	57		20	7	14	2	8				
Prelim	22	63		19	28									
Prelim	30			15										
Prelim														
Prelim														
Prelim														
Final	.33	.64	.009	.012	.29	.20	.07	.14	.02	.009				
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	120			
Final	.005	.003	.000	.000	.000	.0000	.0021	.0013		Sample Type:	555			
GRADE 1035 SQ														

Heat No. W-1351	Product Code 220													
Split B.O. #	Billet Size	Length	Count	Tons	Stark	#	Scrap	Tons						
A 5976	4.75X8.00	228	34	40.9	11-3			2	10.8					
B 0		0	0	0.0				0	0.0					
C 0		0	0	0.0				0	0.0					
D 0		0	0	0.0				0	0.0					

Moller	LMF Operator	Ladleman	Ladle No.	Gate No.	He-is on Ladle	He-is on ; ; ; ; ;	Date	Shift	Heat Number
973	215	419	Q		30	30	5-11-0011-7	10-1351	

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
Start	Stop	Scrap Wt.		Car Number	1	Amount Used	
Last Tap	23:20			Last Heat - Treatment Stop	01:22	At Furnace	At LMF
1st Chg.	23:43	00:19	62,400	Current Heat - Treatment Stop	01:25	Power Meter	2170
2nd Chg.	00:23		53	Preparation Time	60:18	Electrode #1	
3rd Chg.				Current Heat - Treatment Stop	02:25	Electrode #2	
Tapping	01:15	01:20		Total Time of Heat		Electrode #3	
Tap Temp.	3035	Totals:				Lance Sections	
Total Time of Heat:				Reason for Return to LMF / Furnace		Roof Delta	011
LMF	Ladle Weight			Est. Return Wgt.	Added Scrap Wgt.	Wall Heat	011
Steel	Tare Weight	49,000 #				Thermocouples	4
Weight	Steel Weight					Samplers	2
						Oxygen Probes	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1,000	60/40			Carbon			100	30	Carbon	
Cal Al			2-B			75% FeSi		250	40	35	Cal Sil	
Spar			3-0			SiMn		700			FeCb	
Cal C						HC FeMn			200		FeB	
Lime	4,000		300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
NI	I					Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow								Rinse Flow

Temperatures and Times

Time	01:35	01:41	02:11	02:24						Final N ₂ (ppm):
Temp. (°F)	2915	2925	2892	2929						Final Temp (°F):
Oxygen (ppm)										Final O ₂ (ppm):

Chemistry and Billet Information

Practice: 921 Roll No: 044 Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^h	Al
Spec.	19	80	0.35	0.30	22	35	20	20	0.6	20	—
Prelim.	6	8	5	37	—	20	6	7	1	8	—
Prelim	7	52		28	19						
Prelim	16	67		21	20						
Prelim											
Prelim											
Prelim											
Final	.20	.68	.007	.013	.22	.20	.06	.10	.01	.008	

Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	Bi	Grade Code:	921
Final	.003	.002	.000	.000	.000	.0000	.0014	.0013		Sample Type:	555

GRADE A36

Heat No.	X-1265	Product Code	20C
Split	R.O. #	Billet Size	Length Count Tons
A	5977	4.75X8.00	214 41 47.4 00-3 0 0.0
B	0		0 0 0.0 0 0.0
C	0		0 0 0.0 0 0.0
D	0		0 0 0.0 0 0.0

Molter	LMF Operator	Ladleman	Ladle No	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
973	215	232	8		31	31	5-11-00	11-7	X-1265

Remarks:

EAF Melting Log (time)			
	Start	Stop	Scrap Wt.
1st Tap		22:25	
1st Chg.	22:42	23:28	83.00
2nd Chg.	23:35		33.1
3rd Chg.			
4th Chg.			
5th Chg.			
6th Chg.			
7th Chg.			
8th Chg.			
9th Chg.			
10th Chg.			
11th Chg.			
12th Chg.			
13th Chg.			
14th Chg.			
15th Chg.			
16th Chg.			
17th Chg.			
18th Chg.			
19th Chg.			
20th Chg.			
21st Chg.			
22nd Chg.			
23rd Chg.			
24th Chg.			
25th Chg.			
26th Chg.			
27th Chg.			
28th Chg.			
29th Chg.			
30th Chg.			
31st Chg.			
32nd Chg.			
33rd Chg.			
34th Chg.			
35th Chg.			
36th Chg.			
37th Chg.			
38th Chg.			
39th Chg.			
40th Chg.			
41st Chg.			
42nd Chg.			
43rd Chg.			
44th Chg.			
45th Chg.			
46th Chg.			
47th Chg.			
48th Chg.			
49th Chg.			
50th Chg.			
51st Chg.			
52nd Chg.			
53rd Chg.			
54th Chg.			
55th Chg.			
56th Chg.			
57th Chg.			
58th Chg.			
59th Chg.			
60th Chg.			
61st Chg.			
62nd Chg.			
63rd Chg.			
64th Chg.			
65th Chg.			
66th Chg.			
67th Chg.			
68th Chg.			
69th Chg.			
70th Chg.			
71st Chg.			
72nd Chg.			
73rd Chg.			
74th Chg.			
75th Chg.			
76th Chg.			
77th Chg.			
78th Chg.			
79th Chg.			
80th Chg.			
81st Chg.			
82nd Chg.			
83rd Chg.			
84th Chg.			
85th Chg.			
86th Chg.			
87th Chg.			
88th Chg.			
89th Chg.			
90th Chg.			
91st Chg.			
92nd Chg.			
93rd Chg.			
94th Chg.			
95th Chg.			
96th Chg.			
97th Chg.			
98th Chg.			
99th Chg.			
100th Chg.			
101st Chg.			
102nd Chg.			
103rd Chg.			
104th Chg.			
105th Chg.			
106th Chg.			
107th Chg.			
108th Chg.			
109th Chg.			
110th Chg.			
111st Chg.			
112nd Chg.			
113rd Chg.			
114th Chg.			
115th Chg.			
116th Chg.			
117th Chg.			
118th Chg.			
119th Chg.			
120th Chg.			
121st Chg.			
122nd Chg.			
123rd Chg.			
124th Chg.			
125th Chg.			
126th Chg.			
127th Chg.			
128th Chg.			
129th Chg.			
130th Chg.			
131st Chg.			
132nd Chg.			
133rd Chg.			
134th Chg.			
135th Chg.			
136th Chg.			
137th Chg.			
138th Chg.			
139th Chg.			
140th Chg.			
141st Chg.			
142nd Chg.			
143rd Chg.			
144th Chg.			
145th Chg.			
146th Chg.			
147th Chg.			
148th Chg.			
149th Chg.			
150th Chg.			
151st Chg.			
152nd Chg.			
153rd Chg.			
154th Chg.			
155th Chg.			
156th Chg.			
157th Chg.			
158th Chg.			
159th Chg.			
160th Chg.			
161st Chg.			
162nd Chg.			
163rd Chg.			
164th Chg.			
165th Chg.			
166th Chg.			
167th Chg.			
168th Chg.			
169th Chg.			
170th Chg.			
171st Chg.			
172nd Chg.			
173rd Chg.			
174th Chg.			
175th Chg.			
176th Chg.			
177th Chg.			
178th Chg.			
179th Chg.			
180th Chg.			
181st Chg.			
182nd Chg.			
183rd Chg.			
184th Chg.			
185th Chg.			
186th Chg.			
187th Chg.			
188th Chg.			
189th Chg.			
190th Chg.			
191st Chg.			
192nd Chg.			
193rd Chg.			
194th Chg.			
195th Chg.			
196th Chg.			
197th Chg.			
198th Chg.			
199th Chg.			
200th Chg.			
201st Chg.			
202nd Chg.			
203rd Chg.			
204th Chg.			
205th Chg.			
206th Chg.			
207th Chg.			
208th Chg.			
209th Chg.			
210th Chg.			
211st Chg.			
212nd Chg.			
213rd Chg.			
214th Chg.			
215th Chg.			
216th Chg.			
217th Chg.			
218th Chg.			
219th Chg.			
220th Chg.			
221st Chg.			
222nd Chg.			
223rd Chg.			
224th Chg.			
225th Chg.			
226th Chg.			
227th Chg.			
228th Chg.			
229th Chg.			
230th Chg.			
231st Chg.			
232nd Chg.			
233rd Chg.			
234th Chg.			
235th Chg.			
236th Chg.			
237th Chg.			
238th Chg.			
239th Chg.			
240th Chg.			
241st Chg.			
242nd Chg.			
243rd Chg.			
244th Chg.			
245th Chg.			
246th Chg.			
247th Chg.			
248th Chg.			
249th Chg.			
250th Chg.			
251st Chg.			
252nd Chg.			
253rd Chg.			
254th Chg.			
255th Chg.			
256th Chg.			
257th Chg.			
258th Chg.			
259th Chg.			
260th Chg.			
261st Chg.			
262nd Chg.			
263rd Chg.			
264th Chg.			
265th Chg.			
266th Chg.			
267th Chg.			
268th Chg.			
269th Chg.			
270th Chg.			
271st Chg.			
272nd Chg.			
273rd Chg.			
274th Chg.			
275th Chg.			
276th Chg.			
277th Chg.			
278th Chg.			
279th Chg.			
280th Chg.			
281st Chg.			
282nd Chg.			
283rd Chg.			
284th Chg.			
285th Chg.			
286th Chg.			
287th Chg.			
288th Chg.			
289th Chg.			
290th Chg.			
291st Chg.			
292nd Chg.			
293rd Chg.			
294th Chg.			
295th Chg.			
296th Chg.			
297th Chg.			
298th Chg.			
299th Chg.			
300th Chg.			
301st Chg.			
302nd Chg.			
303rd Chg.			
304th Chg.			
305th Chg.			
306th Chg.			
307th Chg.			
308th Chg.			
309th Chg.			
310th Chg.			
311st Chg.			
312nd Chg.			
313rd Chg.			
314th Chg.			
315th Chg.			
316th Chg.			
317th Chg.			
318th Chg.			
319th Chg.			
320th Chg.			
321st Chg.			
322nd Chg.			
323rd Chg.			
324th Chg.			
325th Chg.			
326th Chg.			
327th Chg.			
328th Chg.			
329th Chg.			
330th Chg.			
331st Chg.			
332nd Chg.			
333rd Chg.			
334th Chg.			
335th Chg.			
336th Chg.			
337th Chg.			
338th Chg.			
339th Chg.			
340th Chg.			
341st Chg.			
342nd Chg.			
343rd Chg.			
344th Chg.			
345th Chg.			
346th Chg.			
347th Chg.			
348th Chg.			
349th Chg.			
350th Chg.			
351st Chg.			
352nd Chg.			
353rd Chg.			
354th Chg.			
355th Chg.			
356th Chg.			
357th Chg.			
358th Chg.			
359th Chg.			
360th Chg.			
361st Chg.			
362nd Chg.			
363rd Chg.			
364th Chg.			
365th Chg.			
366th Chg.			
367th Chg.			
368th Chg.			
369th Chg.			
370th Chg.			
371st Chg.			
372nd Chg.			
373rd Chg.			
374th Chg.			
375th Chg.			
376th Chg.			
377th Chg.			
378th Chg.			
379th Chg.			
380th Chg.			
381st Chg.			
382nd Chg.			
383rd Chg.			
384th Chg.			
385th Chg.			
386th Chg.			
387th Chg.			
388th Chg.			
389th Chg.			
390th Chg.			
391st Chg.			
392nd Chg.			
393rd Chg.			
394th Chg.			
395th Chg.			
396th Chg.			
397th Chg.			
398th Chg.			
399th Chg.			
400th Chg.			
401st Chg.			
402nd Chg.			
403rd Chg.			
404th Chg.			
405th Chg.			
406th Chg.			
407th Chg.			
408th Chg.			
409th Chg.			
410th Chg.			
411st Chg.			
412nd Chg.			
413rd Chg.			
414th Chg.			
415th Chg.			
416th Chg.			
417th Chg.			
418th Chg.			
419th Chg.			
420th Chg.			
421st Chg.			
422nd Chg.			
423			

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
Start	Stop	Scrap Wt.		Car Number	1	Amount Used	
1st Tap	21:35			Last Heat - Treatment Stop	23:22	Al Furnace	Al LMF
1st Chg.	21:37	22:33	75,640	Current Heat - Treatment Start	23:26	Power Meter	18830 2775
2nd Chg.	22:35		35,600	Preparation Time	55:13	Electrode #1	
3rd Chg.				Current Heat - Treatment Stop	00:21	Electrode #2	
4th Chg.				Total Time of Heat		Electrode #3	
5th Chg.						Lance Sections	
6th Chg.						Roof Della	610
7th Chg.						Wall Heat	010
8th Chg.						Thermocouples	2
9th Chg.						Samplers	2
10th Chg.						Oxygen Probes	
11th Chg.							
12th Chg.							
13th Chg.							
14th Chg.							
15th Chg.							
16th Chg.							
17th Chg.							
18th Chg.							
19th Chg.							
20th Chg.							
21st Chg.							
22nd Chg.							
23rd Chg.							
24th Chg.							
25th Chg.							
26th Chg.							
27th Chg.							
28th Chg.							
29th Chg.							
30th Chg.							
31st Chg.							
32nd Chg.							
33rd Chg.							
34th Chg.							
35th Chg.							
36th Chg.							
37th Chg.							
38th Chg.							
39th Chg.							
40th Chg.							
41st Chg.							
42nd Chg.							
43rd Chg.							
44th Chg.							
45th Chg.							
46th Chg.							
47th Chg.							
48th Chg.							
49th Chg.							
50th Chg.							
51st Chg.							
52nd Chg.							
53rd Chg.							
54th Chg.							
55th Chg.							
56th Chg.							
57th Chg.							
58th Chg.							
59th Chg.							
60th Chg.							
61st Chg.							
62nd Chg.							
63rd Chg.							
64th Chg.							
65th Chg.							
66th Chg.							
67th Chg.							
68th Chg.							
69th Chg.							
70th Chg.							
71st Chg.							
72nd Chg.							
73rd Chg.							
74th Chg.							
75th Chg.							
76th Chg.							
77th Chg.							
78th Chg.							
79th Chg.							
80th Chg.							
81st Chg.							
82nd Chg.							
83rd Chg.							
84th Chg.							
85th Chg.							
86th Chg.							
87th Chg.							
88th Chg.							
89th Chg.							
90th Chg.							
91st Chg.							
92nd Chg.							
93rd Chg.							
94th Chg.							
95th Chg.							
96th Chg.							
97th Chg.							
98th Chg.							
99th Chg.							
100th Chg.							
101st Chg.							
102nd Chg.							
103rd Chg.							
104th Chg.							
105th Chg.							
106th Chg.							
107th Chg.							
108th Chg.							
109th Chg.							
110th Chg.							
111st Chg.							
112nd Chg.							
113th Chg.							
114th Chg.							
115th Chg.							
116th Chg.							
117th Chg.							
118th Chg.							
119th Chg.							
120th Chg.							
121st Chg.							
122nd Chg.							
123rd Chg.							
124th Chg.							
125th Chg.							
126th Chg.							
127th Chg.							
128th Chg.							
129th Chg.							
130th Chg.							
131st Chg.							
132nd Chg.							
133rd Chg.							
134th Chg.							
135th Chg.							
136th Chg.							
137th Chg.							
138th Chg.							
139th Chg.							
140th Chg.							
141st Chg.							
142nd Chg.							
143rd Chg.							
144th Chg.							
145th Chg.							
146th Chg.							
147th Chg.							
148th Chg.							
149th Chg.							
150th Chg.							
151st Chg.							
152nd Chg.							
153rd Chg.							
154th Chg.							
155th Chg.							
156th Chg.							
157th Chg.							
158th Chg.							
159th Chg.							
160th Chg.							
161st Chg.							
162nd Chg.							
163rd Chg.							
164th Chg.							
165th Chg.							
166th Chg.							
167th Chg.							
168th Chg.							
169th Chg.							
170th Chg.							
171st Chg.							
172nd Chg.							
173rd Chg.							
174th Chg.							
175th Chg.							
176th Chg.							
177th Chg.							
178th Chg.							
179th Chg.							
180th Chg.							
181st Chg.							
182nd Chg.							
183rd Chg.							
184th Chg.							
185th Chg.							
186th Chg.							
187th Chg.							
188th Chg.							
189th Chg.							
190th Chg.							
191st Chg.							
192nd Chg.							
193rd Chg.							
194th Chg.							
195th Chg.							
196th Chg.							
197th Chg.							
198th Chg.							
199th Chg.							
200th Chg.							
201st Chg.							
202nd Chg.							
203rd Chg.							
204th Chg.							
205th Chg.							
206th Chg.							
207th Chg.							
208th Chg.							
209th Chg.							
210th Chg.							
211st Chg.							
212nd Chg.							
213rd Chg.							
214th Chg.							
215th Chg.							
216th Chg.							
217th Chg.							
218th Chg.							
219th Chg.							
220th Chg.							
221st Chg.							
222nd Chg.							
223rd Chg.							
22							

EAF Melting Log (time)			LMF Treatment Log (time)		Power & Supply Consumption	
Start	Stop	Scrap Wt.	Car Number		Amount Used	
Last Tap	20:00		Last Heat - Treatment Stop	22:44	At Furnace	At LMF
1st Chg.	21:10	98000	Current Heat - Treatment Start	22:37	Power Meter	19310 2150
2nd Chg.	21:49	39000	Preparation Time	45:17	Electrode #1	
3rd Chg.			Current Heat - Treatment Stop	23:22	Electrode #2	
Tapping	22:20	23:25	Total Time of Heat		Electrode #3	
ap Temp.	5720	Totals:			Lance Sections	
Total Time of Heat:			Reason for Return to LMF / Furnace		Roof Delta	009
LMF	Ladle Weight		Est. Return Wgt.	Added Scrap Wgt.	Wall Heat	009
Steel	Tare Weight	49,000 #			Thermocouples	2
Weight	Steel Weight				Samplers	1
					Oxygen Probes	

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						23:25 Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1006				Carbon	4-0		20		Carbon	
Cal Al						75% FeSi		200			Cal Sil	150
Spar			2-13			SiMn		1100			FeCb	
Cal C			4-2			HC FeMn			150		FeB	
Lime	4000		300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni	1					Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argo											
Vgon Flow											Rinse Flow: =

Temperature and Times											
Time	22:15	22:46	22:57	23:11							Final N ₂ (ppm):
Temp. (°F)	1822	2879	2927	2905							Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	490	Roll No:	B11	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al	
Spec.	14	90	25	15	22	35	20	20	05			
Prelim.	9	13	2	28	-	19	7	10	00			
Prelim	12	80		18	2.5							
Prelim												
Prelim												
Prelim												
Final	.13	.91	.006	.012	26	20	07	.13	.02	.008		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	490	
Final	.004	.002	.000	.000	.000	.0000	.0010	.0015		Sample Type:	.555	

GRADE SAE Y45 GRA

Heat No. W-1349 Product Code 993

Split B.O. + Billet Size Length Count Tons Stack #Scrap Tons

A	5968	4.75X8.00	177	54	50.5	HH-2	0	0.0
B	0		0	0	0.0		0	0.0
C	0		0	0	0.0		0	0.0
D	0		0	0	0.0		0	0.0

Miller	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
712	235	461	2		14	14	5-10-2000	3-11	W-1349

Document No: MS-011

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF / LMF Combined Heat Sheet

EAF Melting Log (time)			
	Start	Stop	Scrap Wt.
Last Tap	_____	1249	_____
1st Chg.	1256	1342	640 lb
2nd Chg.	1351	1405	3240 lb
3rd Chg.	1407		19
Tapping	14:36	14:41	
Tap Temp.	2945	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)	
Car Number	2
Last Heat - Treatment Stop	14:45
Current Heat - Treatment Start	14:50
Preparation Time	
Current Heat - Treatment Stop	15:34
Total Time of Heat	48:45
Reason for Return to LMF / Furnace	
Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption		
	Amount Used	
	At Furnace	At LMF
Power Meter	21800	2875
Electrode #1	1	
Electrode #2		
Electrode #3	1	
Lance Sections		
Roof Delta	27	
Wall Heat	27	
Thermocouples	2	
Samplers		
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						15:40	Alloys Added (lbs.)				Wire Added (ft.)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1500				Carbon			60	10	Carbon	
Cal Al						75% FeSi		250	75	90	Cal Sil	150
Spar			9-B			SiMn		600			FeCb	
Cal C			4-C			HC FeMn			150	200	FeB	
Lime	4000		700			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
NI	1					Moly Oxide					Nitrovan	
Cat Sil						Copper					FeS	

Argon Log

[illegible]

Temperatures and Times

Time	1453	1456	1458	1501	1504	1507	1510	1513	1516	1519	1522	1525	1528	1531	1534	1537	1540	1543	1546	1549	1552	1555	1558	1601	1604	1607	1610	1613	1616	1619	1622	1625	1628	1631	1634	1637	1640	1643	1646	1649	1652	1655	1658	1701	1704	1707	1710	1713	1716	1719	1722	1725	1728	1731	1734	1737	1740	1743	1746	1749	1752	1755	1758	1801	1804	1807	1810	1813	1816	1819	1822	1825	1828	1831	1834	1837	1840	1843	1846	1849	1852	1855	1858	1901	1904	1907	1910	1913	1916	1919	1922	1925	1928	1931	1934	1937	1940	1943	1946	1949	1952	1955	1958	2001	2004	2007	2010	2013	2016	2019	2022	2025	2028	2031	2034	2037	2040	2043	2046	2049	2052	2055	2058	2101	2104	2107	2110	2113	2116	2119	2122	2125	2128	2131	2134	2137	2140	2143	2146	2149	2152	2155	2158	2201	2204	2207	2210	2213	2216	2219	2222	2225	2228	2231	2234	2237	2240	2243	2246	2249	2252	2255	2258	2301	2304	2307	2310	2313	2316	2319	2322	2325	2328	2331	2334	2337	2340	2343	2346	2349	2352	2355	2358	2401	2404	2407	2410	2413	2416	2419	2422	2425	2428	2431	2434	2437	2440	2443	2446	2449	2452	2455	2458	2501	2504	2507	2510	2513	2516	2519	2522	2525	2528	2531	2534	2537	2540	2543	2546	2549	2552	2555	2558	2601	2604	2607	2610	2613	2616	2619	2622	2625	2628	2631	2634	2637	2640	2643	2646	2649	2652	2655	2658	2701	2704	2707	2710	2713	2716	2719	2722	2725	2728	2731	2734	2737	2740	2743	2746	2749	2752	2755	2758	2801	2804	2807	2810	2813	2816	2819	2822	2825	2828	2831	2834	2837	2840	2843	2846	2849	2852	2855	2858	2901	2904	2907	2910	2913	2916	2919	2922	2925	2928	2931	2934	2937	2940	2943	2946	2949	2952	2955	2958	3001	3004	3007	3010	3013	3016	3019	3022	3025	3028	3031	3034	3037	3040	3043	3046	3049	3052	3055	3058	3101	3104	3107	3110	3113	3116	3119	3122	3125	3128	3131	3134	3137	3140	3143	3146	3149	3152	3155	3158	3201	3204	3207	3210	3213	3216	3219	3222	3225	3228	3231	3234	3237	3240	3243	3246	3249	3252	3255	3258	3301	3304	3307	3310	3313	3316	3319	3322	3325	3328	3331	3334	3337	3340	3343	3346	3349	3352	3355	3358	3401	3404	3407	3410	3413	3416	3419	3422	3425	3428	3431	3434	3437	3440	3443	3446	3449	3452	3455	3458	3501	3504	3507	3510	3513																																																																																																																																																																																																																																																																																																																																																																															
Temp. (°F)	2880	2945	2861	2914	2915																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		

Chemistry and Billet Information

Practice: 110 Roll No: 0421 Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	116	70	20	25	22	35	20	15	06		
Prelim.	8	8	12	49	0	27	7	10	1	11	
Prelim	8	24	10	10							
Prelim	15	53	10	30	19	25	7	10	1	10	
Prelim											
Prelim											
Prelim											
Final	- .00	- .00	.000	.000	- .00	.00	.00	.00	.00	.000	

Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110
Final	.000	.000	.000	.000	.000	.0000	.0000	.0000		Sample Type:	89

GRADE	1018 SQ
-------	---------

Heat No. X1281

Product Code 30X

Split	L.O. #	Billet Size	Length	Count	Tons	Stack	#Scrap	Tons
A	5989	5.00X7.00	175	0	0.0		0	0.0
B	0		0	0	0.0		0	0.0
C	0		0	0	0.0		0	0.0
D	0		0	0	0.0		0	0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
909	235	114	2		22	22	5-12-00	2/3	X-1281

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: 5

Remarks:

lot 2 / 3 shot

EAF Melting Log (time)		
	Start	Stop
Last Tap	<u> </u>	<u>17:30</u>
1st Chg.	<u>17:32</u>	<u>18:23</u>
2nd Chg.	<u>18:25</u>	<u>18:43</u>
3rd Chg.	<u>18:45</u>	<u> </u>
Tapping	<u>19:55</u>	<u>20:00</u>
Tap Temp.	<u>3040</u>	<u>Totals:</u>
Total Time of Heat:		

LMF Treatment Log (time)	
Car Number	
Last Heat - Treatment Stop	
Current Heat - Treatment Start	
Preparation Time	
Current Heat - Treatment Stop	
Total Time of Heat	

Reason for Return to LMF / Furnace	
Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption		
	Amount Used	
	At Furnace	At LMF
Power Meter	<u>12140</u>	
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections	<u>29</u>	
Roof Delta	<u>29</u>	
Wall Heat		
Thermocouples		
Samplers		
Oxygen Probes		

LMF Steel Weight		
Ladle Weight		
Tare Weight	<u>49,000 #</u>	
Steel Weight		

Additions To The Furnace and Ladle												
Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Sleg Cond.		1000				Carbon		2-13			Carbon	
Cal Al						75% FeSi		250			Cal Sil	
Spar						SiMn		900			FeCb	
Cal C						HC FeMn					FeB	
Lime	4000					MC FeMn					FeTi	
DoloLime						FeCr					FeV	
NI	I					Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

[illegible]

Temperatures and Times									
Time	19:10	19:57							Final N ₂ (ppm):
Temp. (°F)	2906	2863							Final Temp (°F):
Oxygen (ppm)									Final O ₂ (ppm):

Chemistry and Billet Information

Practice: 110		Roll No: 044		Chemistry:							
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	70	20	25	22	35	20	15	02		
Prelim.	14	19	6	30	-	26	7	11	01		
Prelim	13	19	4	30	-	25	7	10	01		
Prelim											
Prelim											
Prelim											
Prelim											
Final	- .00	- .00	.000	.000	- .00	.00	.00	.00	.00	.000	

Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110
Final	.000	.000	.000	.000	.000	.0000	.0000	.0000		Sample Type:	898

NO CAUTION

Heat No. W1369		Product Code 32W							
Split	R.O. #	Billet Size	Length	Count	Tons	Stack	#Scrap	Tons	
A	5991	5.00X7.00	221	0	0.0		0	0.0	
B	0		0	0	0.0		0	0.0	
C	0		0	0	0.0		0	0.0	
D	0		0	0	0.0		0	0.0	
				0	0.0		0	0.0	

W1369
NOT
SPLIT
OFF

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats On Ladle	Heats Off Aug	Weld	0	0.0
912		461	10		12	12	5-12-2000	3-21	W-1369

Remarks:

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
Last Tap	Start	Stop	Scrap Wt.	Car Number		Amount Used	
1st Chg.	16:54	17:23	70,000	Last Heat - Treatment Stop		At Furnace	At LMF
2nd Chg.	17:23		35,000	Current Heat - Treatment Start		Power Meter	
3rd Chg.				Preparation Time		Electrode #1	
Tapping	19:00	19:05		Current Heat - Treatment Stop		Electrode #2	
Tap Temp.	3055	Totals:		Total Time of Heat		Electrode #3	
Total Time of Heat:				Reason for Return to LMF / Furnace		Lance Sections	
				Est. Return Wgt.		Roof Delta	219
				Added Scrap Wgt.		Wall Heal	219
						Thermocouples	
						Samplers	
						Oxygen Probes	

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle											
Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur
Slag Cond.		1000				Carbon	-13				Carbon
Cal Al						75% FeSi		250			Cal Sil
Spar						SiMn		1000			FeCb
Cal C						HC FeMn					FeB
Lime	4000					MC FeMn					FeTi
DoloLime						FeCr					FeV
Ni	1					Moly Oxide					Nitrovan
Cal Sil						Copper					FeS

Argon Log											
Argon Flow											Rinse Flow:

Temperatures and Times											
Time	18:19	18:35									Final N (ppm):
Temp. (°F)	2921	2920									Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information											
Practice:	110		Roll No:	044		Chemistry:					
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	70	20	25	22	35	20	15	15		
Prelim.	6	9	9	35	-	22	7	9	01		
Prelim.	5	8	6	32	-	22	7	8	01		
Prelim.											
Prelim.											
Prelim.											
Prelim.											
Final	.15	.61	.008	.027	.26	.23	.07	.08	.01	.009	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110
Final	.003	.000	.000	.000	.000	.0000	.0000	.0012		Sample Type:	555

GRADE 1018 SQ

Heat No. X1283 Product Code 32W											
Split	E.O. #	Billet Size	Length	Count	Tons	Stack	#Scrap	Tons			
A	5991	5.00X7.00	221	57	61.1	DD1	0	0.0			
E	0		0	0	0.0		0	0.0			
C	0		0	0	0.0		0	0.0			
Ti	0		0	0	0.0		0	0.0			

Melter	LMF Operator	Ladleman	Leak No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
912		459	8		41	16	5-12-2000	3-11	X-1283

Document No: MS-013 Revision Date: 04-19-1999 Revision Level: F

Remarks: Delay Smelter

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
Last Tap	Start	Slop	Scrap Wt	Car Number		Amount Used	
1st Chg	16:14	15:50		Last Heat - Treatment Slop	17:37	At Furnace	At LMF
2nd Chg				Current Heat - Treatment Start	17:51	Power Meter	5010
3rd Chg				Preparation Time		Electrode #1	
Tapping	17:20			Current Heat - Treatment Slop	18:17	Electrode #2	
Tap Temp	3020	Totals		Total Time of Heat	79:1	Electrode #3	
Total Time of Heat.				Reason for Return to LMF / Furnace		Lance Sections	
LMF	Ladle Weight			Est. Return Wgt.	Added Scrap Wgt.	Roof Delta	28
Steel	Tare Weight	49,000 #		1 Heat		Wall Heat	28
Weight	Steel Weight			Slide gate		Thermocouples	
						Samplers	
						Oxygen Probes	

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						Alloys Added (lbs.)					Wire Added (n)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond		1000				Carbon	5-15				Carbon	
Cal Al						75% FeSi		300	50		Cal Sil	50
spar			2-15			SiMn		200			FeCb	
Cal C			4.0			HC FeMn					FeR	
Lime			100			MC FeMn			200		FeTi	
DoloLime						FeCr					FeV	
Ni	1					Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	16:38	16:02	18:15								Final H ₂ (ppm):	
Temp. (°F)	2940	2925	2920								Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Info

Practice:	Roil No:	144	Chemistry:									
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al	
Spec.	16	70	20	25	22	35	20	15	0.6			
Prelim.	15	40	14	39	2	26	7	13	0.1			
Prelim	16	19	15	29	19	26	7	14	1			
Prelim	17	65	14	20	20	26						
Prelim												
Prelim												
Prelim												
Final	.17	.65	0.1	.017	.20	25	.07	.14	.01	.010		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	Dr	Grade Code:	110	
Final	.004	.001	.000	.000	.000	.0000	.0011	.0012		Sample Type:	555	

GRADE 1018 SQ

Heat No. W1368 Product Code 230

Split	B.O. #	Billet Size	Length	Count	Tons	Stack #	Scrap Tons
A	5990	5.00X7.00	167	62	50.2	EE1	0 0.0
B	0			0	0	0.0	0 0.0
C	0			0	0	0.0	0 0.0
Ti	0			0	0	0.0	0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
912	W.C.	451	2		23	23	5-12-2000	3-1	W-1368

Document No. MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)			LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number	Amount Used	
Last Tap	14:58	15:38	72.02N	Last Heat - Treatment Stop	At Furnace	At LMF
1st Chg.	15:40		48.22	Current Heat - Treatment Start	21530	2775
2nd Chg.				Preparation Time		
3rd Chg.				Current Heat - Treatment Stop		
Tapping	16:40	16:45		Total Time of Heat	47:15	
Tap Temp	3	0	Totals	Reason for Return to LMF / Furnace		
Total Time of Heat.				Est. Return Wgt.	Added Scrap Wgt.	
LMF	Ladle Weight					
Steel	Tare Weight	49,000 #				
Weight	Steel Weight					

Addition The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs)					Wire Added (it)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1700				Carbon			80	20	Carbon	
Cal Al						75% FeSi		250	100	25	Cal Si	150
Spar			2.19			SiMn		700			FeCb	
Cal C			1.2			HC FeMn			900		FeB	
Lime	4100		200			MC FeMn				60	FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow	
------------	--	--	--	--	--	--	--	--	--	--	------------	--

Temperatures and Times

Time	16:25	16:32	17:08	17:18	17:24	17:31	17:38				Final N ₂ (ppm):
Temp. (°F)	2800	3005	2920	2908	2920	2901	2920				Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	110	Roll No:	04	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^h	Al	
Spec.	16	70	20	25	22	35	20	15	64			
Prelim.	7	8	22	40	-	21	2	10	01			
Prelim.	8	22	12	35	15	21	-	10	1	?		
Prelim.	14	63	23	25	20	21						
Prelim.												
Prelim.												
Prelim.												
Final	.16	.66	.023	.016	.21	.22	.06	.11	.01	.009		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110	
Final	.004	.004	.000	.000	.000	.0000	.0009	.0012		Sample Type:	555	

GRADE 1018 SQ

Heat No.	X-1282	Product Code	230									
Split	B.O. #	Billet Size	Length	Count	Tons	Stack	Scrap	Tons				
A	5989	5.00X7.00	175	60	50.9	EE1		0	0.0			
B	0			0	0	0.0		0	0.0			
C	0			0	0	0.0		0	0.0			
D	0			0	0	0.0		0	0.0			

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
912	235	441	10		11	11	5-12-2000	3-11	X-1282

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

Additions To The Furnace and Ladle

August

Temperatures and Times	
------------------------	--

Chemistry and Billet Information

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
---------	---	----	---	---	----	----	----	----	----	------------------	----

Heat No. W1367 Product Code 230

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Num
--------	--------------	----------	-----------	----------	----------------	---------------	------	-------	----------

Document No: MS-013 Revision Date: 04-19-1999 Revision Level: F

Remarks: No Hockey 13:28 - 14:05 - 4 - 4 - 4 - 4 - 4 - 4

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
Last Tap	Start	Stop	Scrap Wt.	Car Number		Amount Used	
1st Chg	11:56	12:37	26301	Last Heat - Treatment Stop	63-45	At Furnace	At LMF
2nd Chg	12:37		49	Current Heat - Treatment Start	63-48	Power Meter	20910 1123
3rd Chg				Preparation Time	2-1:31	Electrode #1	
Tapping	13:23	13:28		Current Heat - Treatment Stop	14:03	Electrode #2	
Tap Temp	3148	Totals		Total Time of Heat		Electrode #3	
Total Time of Heat				Reason for Return to LMF / Furnace		Lance Sections	
				Est. Return Wgt.	Added Scrap Wgt.	Roof Delta	26
						Wall Heat	24
						Thermocouples	1
						Samplers	
						Oxygen Probes	

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle												
Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cont.		1000				Carbon			80	20	Carbon	
Cal A						75% FeSi		250			Cal Sil	150
Spar						SiMn		600			FeCb	
Cal C						HC FeMn					FeB	
Lime	4000		350			MC FeMn					FeTi	
DoloLine						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log												
Argon Flow												Rinse Flow:

Temperatures and Times												
Time	12:37											Final N ₂ (ppm):
Temp. (F)	3148											Final Temp (F):
Oxygen (ppm)												Final O ₂ (ppm):

Chemistry and Billet Information												
Practice:	110	Roll No:	044	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al	
Spec.	16	20	20	25	22	35	20	15	06			
Prelim	9	10	5	31	0	27	9	13	2	9		
Prelim	11	64		10	21							
Prelim												
Prelim												
Prelim												
Prelim												
Final	.16	.67	.009	.013	.22	.27	.10	.17	.02	.010		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI		Grade Code:	110
Final	.004	.002	.000	.000	.000	.0000	.0012	.0015			Sample Type:	555

Product Code 30X												
Roll	110	Billet Size	Length	Count	Tons	Stack	#Scrap	Tons				
A	5988	5.60X7.00	170	19	15.7	EE1		0	0.0			
B	5989	5.60X7.00	175	47	39.5	EE1		0	0.0			
C	0		0	0	0.0			0	0.0			
D	0		0	0	0.0			0	0.0			

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
911		185	7		38	4	5-12-00	7/3	10-1366

Document ID: MS-013 Revision Date: 04-19-1999 Revision Level: F

Remarks:

EAF / LMF Combined Heat Sheet

EAf Melting Log (time):

	Start	Stop	Scrap Wt.
Last Tap	_____	10:34	_____
1st Chg.	11:03	11:47	68.60
2nd Chg.	11:49		42
3rd Chg.			
Tapping	12:44	12:49	
Top Temp.	3023	Totals:	
Total Time of Heat:			

LMF Treatment Log (time)

Car Number	
Last Heal - Treatment Stop	1258
Current Heal - Treatment Start	1258
Preparation Time	43.11
Current Heal - Treatment Stop	1345
Total Time of Heal	

Power & Supply Consumption

	Amount Used	
	Al Furnace	Al LMF
Power Meter	23630	1975
Electrode #1		
Electrode #2	1	
Electrode #3		
Lance Sections		
Roof Delta	26	
Wall Heat	26	
Thermocouples	13	
Samplers		
Oxygen Probes		

LMF

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)
Time	Furnace	Ledie	LMF	LMF	LMF	Time	Furnace	Ledie	LMF	LMF	Sulfur
Slag Cond.		1000				Carbon			80		Carbon
Cal Al						75% FeSi		250	100		Cal Sil 150
Spar			2-3			SiMn		600			FeCb
Cal C						HC FeMn			350		FeB
Lime	4000		330			MC FeMn					FeTi
DoloLime						FeCr					FeV
Ni	1					Moly Oxide					Nitrovan
Cal Sil						Copper					FeS

Argon Log

[illegible]

Temperatures and Times

[illegible]

Chemistry and Billet Information

Practice: 110 Roll No: 044 Chemistry: 10.1.11

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	70	50	25	22	35	20	15	06		
Prelim.	8	9	25	54	0	24	8	14	2	11	
Prelim.	5	61		33	22						
Prelim.	15	64		24	21						
Prelim.											
Prelim.											
Prelim.											
Final	.17	.69	.020	.017	.25	.25	.08	.14	.02	.009	

Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code	110
Final	.004	.002	.000	.000	.000	.0000	.0013	.0013		Sample Type	555

GRADE	1018 SQ
-------	---------

Heat No. X-1280

Product Code 30X

Split	R.O. %	Billet Size	Length	Count	Tons	Stack	Scraper	Tons
A	55.98	5.00X7.00	170	63	51.9	EE-1	0	0.0
B	0	5.00X7.00	0	0	0.0		0	0.0
C	0		0	0	0.0		0	0.0
D	0		0	0	0.0		0	0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
979		452	10		10	10	5-12-00	2/3	X-1280

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

from fur. Set no 3 electroly

Additions To The Furnace and Ladle

Argon Log

Temperatures and Times

Chemistry and Billet Information

GRADE	1018 50
-------	---------

Heat No. W-1365		Product Code 30X						
Split	R.O. #	Billet Size	Length	Count	Tons	Stack	#Scrap	Tons
	5987	5.00X7.00	197	20	19.1	EE-1	0	0.0
E	5988	5.00X7.00	170	40	33.0	EE-1	0	0.0
F	0		0	3	0.0		0	0.0
H	0		0	0	0.0		0	0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate NO.	Heels on Ladle	Heels on Plug	Date	Shift	Heat Number
919		114	8			13	5-12-00	T/3	W-1365

Document No. MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)

	Start	Stop	Scrap Wt.
Last Tap		0849	
1st Chg.	0905	0931	63000
2nd Chg.	0935		52
3rd Chg.			
Tapping	1025	1039	
Tap Temp.	3093	Totals:	
Total Time of Heat:			

LMF Treatment Log (time)

Car Number	
Last Heat - Treatment Stop	
Current Heat - Treatment Start	
Preparation Time	45
Current Heat - Treatment Stop	620
Total Time of Heat	

Power & Supply Consumption

	Amount Used	
	At Furnace	At LMF
Power Meter	19630	2000
Electrode #1		
Electrode #2		
Electrode #3		✓
Lance Sections		
Roof Delta	25	
Wall Heat	25	
Thermocouples	2	
Samplers		
Oxygen Probes		

LMF
Steel
Weight

Ladle Weight	
Tare Weight	49,000 #
Steel Weight	

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond		000				Carbon					Carbon	
Cal Al						75% FeSi		250	100	50	Cal Sil	150
Spar			0-			SIMn		600	985		FeCb	
Cal C						HC FeMn					FeB	
Time	400		300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow	
------------	--	--	--	--	--	--	--	--	--	--	------------	--

Temperatures and Times

Time	1015	1034									Final N ₂ (ppm):
Temp. (°F)	3187	3023									Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice:

110

Roll No:

044

Chemistry:

10 W F 400

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec	16	10	20	25	22	35	20	20	06		
Prelim	4	8	2	28	0	23	9	5	2	9	
Prelim	5	40		43	18						
Prelim	16	68		30	20						
Prelim											
Prelim											
Prelim											
Final	.16	.69	.008		24	23	09	01	.02	.009	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110
Final	.004	.002	.000	.000	.000	.0000	.0013	.0014		Sample Type:	555

GRADE

1018 SQ

Heat No. X-1279

Product Code 30X

Split B.O. # Billet Size Length Count Tons Stack # Scrap Tons

A 5987 5.00X7.00 197 53 50.6 EE-1 0 0.0

B 0 5.00X7.00 0 0 0.0 0 0.0

C 0 0 0.0 0 0.0

D 0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
719		1185	2		21	21	5-12-00	7/3	X-1279

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

Set phase electrolyte @ Cmf

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number		Amount Used	
Last Tap		07:34		Last Heat - Treatment Stop	1000	Al Furnace	Al LMF
1st Chg.	07:55	08:28	45000	Current Heat - Treatment Start	1005	Power Meter	27620
2nd Chg.	08:32	08:54	48400	Preparation Time	09:13	Electrode #1	
3rd Chg.	08:58		22	Current Heat - Treatment Stop	1105	Electrode #2	
Tapping	09:54	09:59		Total Time of Heat		Electrode #3	
Tap Temp.	3002	Totals:				Lance Sections	
Total Time of Heat:				Reason for Return to LMF / Furnace		Roof Delta	24
				Est. Return Wgt.	Added Scrap Wgt.	Wall Heal	24
						Thermocouples	4
						Samplers	
						Oxygen Probes	

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon					Carbon	
Cal Al						75% FeSi		250			Cal Sil	150
Spar						SiMn		600			FeCb	
Cal C						HC FeMn					FeB	
Lime	4000		6000			MC FeMn					FeTi	
Dolo/Lime						FeCr					FeV	
NI						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow												Rinse Flow	
------------	--	--	--	--	--	--	--	--	--	--	--	------------	--

Temperatures and Times

Time	09:30	09:35	09:45	09:59	10:41	10:53						Final N ₂ (ppm):
Temp. (°F)	2865	3013	3010	3002	2873	2901						Final Temp (°F):
Oxygen (ppm)												Final O ₂ (ppm):

Chemistry and Billet Information

Practice:	110	Roll No:	044	Chemistry:	10 AFT						
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	20	20	25	22	35	20	15	06		
Prelim.	14	16	5	46	0	21	6	12	1	8	
Prelim.	7	13		46	17						
Prelim.	15	69		300	25						
Prelim.											
Prelim.											
Prelim.											
Final	.16	.71	.009	.022	.24	.20	.07	.14	.02	.008	
Element	Al	V	Nb	Ti	Zr	B	Co	Zn	DI	Grade Code:	110
Final	.004	.002	.000	.000	.000	.0000	.0005	.0012		Sample Type:	555

GRADE

1018 SQ

Heat No. W-1364		Product Code 32W	
Split	100.0	Billet Size	Length
A	5786	5.00X7.00	189
B	0	5.00X7.00	0
C	0		0
D	0		0
E	0		0
F	0		0
G	0		0
H	0		0
I	0		0
J	0		0
K	0		0
L	0		0
M	0		0
N	0		0
O	0		0
P	0		0
Q	0		0
R	0		0
S	0		0
T	0		0
U	0		0
V	0		0
W	0		0
X	0		0
Y	0		0
Z	0		0
AA	0		0
AB	0		0
AC	0		0
AD	0		0
AE	0		0
AF	0		0
AG	0		0
AH	0		0
AI	0		0
AJ	0		0
AK	0		0
AL	0		0
AM	0		0
AN	0		0
AO	0		0
AP	0		0
AQ	0		0
AR	0		0
AS	0		0
AT	0		0
AU	0		0
AV	0		0
AW	0		0
AX	0		0
AY	0		0
AZ	0		0
BA	0		0
BB	0		0
BC	0		0
BD	0		0
BE	0		0
BF	0		0
BG	0		0
BH	0		0
BI	0		0
BJ	0		0
BK	0		0
BL	0		0
BM	0		0
BN	0		0
BO	0		0
BP	0		0
BQ	0		0
BR	0		0
BS	0		0
BT	0		0
BU	0		0
BV	0		0
BW	0		0
BX	0		0
BY	0		0
BZ	0		0
CA	0		0
CB	0		0
CC	0		0
CD	0		0
CE	0		0
CF	0		0
CG	0		0
CH	0		0
CI	0		0
CJ	0		0
CK	0		0
CL	0		0
CM	0		0
CN	0		0
CO	0		0
CP	0		0
CQ	0		0
CR	0		0
CS	0		0
CT	0		0
CU	0		0
CV	0		0
CW	0		0
CX	0		0
CY	0		0
CZ	0		0
DA	0		0
DB	0		0
DC	0		0
DD	0		0
DE	0		0
DF	0		0
DG	0		0
DH	0		0
DI	0		0
DJ	0		0
DK	0		0
DL	0		0
DM	0		0
DN	0		0
DO	0		0
DP	0		0
DQ	0		0
DR	0		0
DS	0		0
DT	0		0
DU	0		0
DV	0		0
DW	0		0
DX	0		0
DY	0		0
DZ	0		0
EA	0		0
EB	0		0
EC	0		0
ED	0		0
EE	0		0
EF	0		0
EG	0		0
EH	0		0
EI	0		0
EJ	0		0
EK	0		0
EL	0		0
EM	0		0
EN	0		0
EO	0		0
EP	0		0
EQ	0		0
ER	0		0
ES	0		0
ET	0		0
EU	0		0
EV	0		0
EW	0		0
EX	0		0
EY	0		0
EZ	0		0
FA	0		0
FB	0		0
FC	0		0
FD	0		0
FE	0		0
FF	0		0
FG	0		0
FH	0		0
FI	0		0
FJ	0		0
FK	0		0
FL	0		0
FM	0		0
FN	0		0
FO	0		0
FP	0		0
FQ	0		0
FR	0		0
FS	0		0
FT	0		0
FU	0		0
FV	0		0
FW	0		0
FX	0		0
FY	0		0
FZ	0		0
GA	0		0
GB	0		0
GC	0		0
GD	0		0
GE	0		0
GF	0		0
GG	0		0
GH	0		0
GI	0		0
GJ	0		0
GK	0		0
GL	0		0
GM	0		0
GN	0		0
GO	0		0
GP	0		0
GQ	0		0
GR	0		0
GS	0		0
GT	0		0
GU	0		0
GV	0		0
GW	0		0
GX	0		0
GY	0		0
GZ	0		0
HA	0		0
HB	0		0
HC	0		0
HD	0		0
HE	0		0
HF	0		0
HG	0		0
HH	0		0
HI	0		0
HJ	0		0
HK	0		0
HL	0		0
HM	0		0
HN	0		0
HO	0		0
HP	0		0
HQ	0		0
HR	0		0
HS	0		0
HT	0		0
HU	0		0
HV	0		0
HW	0		0
HX	0		0
HY	0		0
HZ	0		0
IA	0		0
IB	0		0
IC	0		0
ID	0		0
IE	0		0
IF	0		0
IG	0		0
IH	0		0
II	0		0
IJ	0		0
IK	0		0
IL	0		0
IM	0		0
IN	0		0
IO	0		0
IP	0		0
IQ	0		0
IR	0		0
IS	0		0
IT	0		0
IU	0		0
IV	0		0
IW	0		0
IX	0		0
IY	0		0
IZ	0		0
JA	0		0
JB	0		0
JC	0		0
JD	0		0
JE	0		0
JF	0		

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
Last Tap	Start	Stop	Scrap Wt.	Car Number		Amount Used	
1st Chg.	0658	0735	65000	Last Heat - Treatment Stop	900	At Furnace	At LMF
2nd Chg.	0737		50	Current Heat - Treatment Start	906	Power Meter	24820 2575
3rd Chg.				Preparation Time	55.13	Electrode #1	
Tapping	0844	0849		Current Heat - Treatment Stop	1000	Electrode #2	
Tap Temp.	3028	Totals:		Total Time of Heat		Electrode #3	
Total Time of Heat:				Reason for Return to LMF / Furnace		Lance Sections	
				Est. Return Wgt.	Added Scrap Wgt.	Roof Delta	24
						Wall Heat	24
						Thermocouples	4
						Samplers	
						Oxygen Prpbcs	

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon		10			Carbon	
Cal Al						75% FeSi		250	100	40	Cal Sil	150
Spur			4.3			SiMn			380		FeCb	
Cal C						HC FeMn					FeB	
Lime	4000					MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:-	
------------	--	--	--	--	--	--	--	--	--	--	--------------	--

Temperatures and Times

Time	0820	0825	0839	0843							Final N ₂ (ppm):	
Temp. (°F)	2801	2835	2899	3008							Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice:	110	Roll No:	044	Chemistry:	2 AFTER							
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al	
Spec.	16	70	20	25	20	35	20	15	4			
Prelim.	7	7	6	75	0	21	12	8	3	10		
Prelim.	7	41		57	18							
Prelim.	15	21		24	23							
Prelim.												
Prelim.												
Prelim.												
Final	.15	.70	.008	.016	.24	.21	.11	.10	.03	.010		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110	
Final	.004	.002	.000	.000	.000	.0000	.0015	.0014		Sample Type:	555	

Heat No. X-1278

Product Code 341

Split P.O. # Billet Size Length Count Tons Stack # Scrap Tons

A 5925 5.00X7.00 166 62 49.8 EE-1 0 0.0

B 0 5.00X7.00 0 0 0.0 0 0.0

C 0 0 0 0 0.0 0 0.0

D 0 0 0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gale NO.	Heck on Ladle	Heats or Plug	Date	Shift	Heat Number
919		114	10		9	4	6-12-00	7/3	X-1278

Document No: MS-013

Revision Date: 04/19/99

revi-inn Level F

Remarks:

EAF Melting Log (time)

	Start	Stop	Scrap Wt.
Last Tap		05:55	
1st Chg.	06:05	06:45	86,460
2nd Chg.	06:48		29
3rd Chg.			
Tapping	07:29	07:39	
Tap Temp.	3017	Totals:	
Total Time of Heat:			

LMF Treatment Log (time)

Car Number	
Last Heat - Treatment Stop	725
Current Heat - Treatment Start	735
Preparation Time	77:31
Current Heat - Treatment Stop	900
Total Time of Heat	

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption

	Amount Used	
	At Furnace	At LMF
Power Meter	20700	2775
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Delta	23	
Wall Heat	23	
Thermocouples	2	
Samplers		
Oxygen Probes		

LMF

Steel

Weight

Ladle Weight	
Tare Weight	49,000 #
Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon			90		Carbon	
Cal Al						75% FeSi		250	100		Cal Sil	
Spar			653			SiMn		400			FeCb	
Cal C						HC FeMn			400		FeB	
Lime	4000		1000			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	07:23	07:27									Final N ₂ (ppm):
Temp. (°F)	2922	3017									Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice: 110

Roll No: 044

Chemistry: 15. AF12R

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^h	Al
Spec.	16	70	020	025	22	35	20	15	06		
Prelim.	6	7	3	81	0	19	11	9	2	9	
Prelim.	5	39		64	13						
Prelim.	13	20		57							
Prelim.	17			44							
Prelim.	10			32							
Prelim.											
Final	.17	.74	.009	.013	.18	.21	.13	.13	.03	.011	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code	110
Final	.004	.002	.001	.000	.000	.0001	.0007	.0015		Sample Type:	555

GRADE:

1018 SQ

Heat No. W-1363

Product Code 341

Split Billet # Billet Size Length Count Tons Stack 1 Scrap Tons

A 5985 5.00X7.00 166 60 48.3 EE-1 0 0.0

B 0 5.00X7.00 0 0 0.0 0 0.0

C 0 0 0 0 0.0 0 0.0

D 0 0 0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
914		185	8		38	13	5-13-00	1/3	20-1363

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number		Amount Used	
Last Tap		05:00		Last Heat - Treatment Stop	650	At Furnace	At LMF
1st Chg.	05:12	05:53	66	Current Heat - Treatment Start	1:55	Power Meter	1985 2071
2nd Chg.	05:55		49	Preparation Time	59.3	Electrode #1	
3rd Chg.				Current Heat - Treatment Stop		Electrode 12	
Tapping	06:34	06:39		Total Time of Heat		Electrode #3	
Tap Temp.	3055	Totals:		Reason for Return to LMF / Furnace		Lance Sections	
Total Time of Heat:				Est. Return Wgt.	Added Scrap Wgt.	Roof Delta	23
LMF	Ladle Weight					Wall Heat	23
Steel	Tare Weight	49,000 #				Thermocouples	1
Weight	Steel Weight					Samplers	
						Oxygen Probes	

Additions To The Furnace and Ladle											
Fluxes Added (lbs.)						Alloys Added (lbs.)					Wire Added (ft)
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur
Slag Cond.		4,000				Carbon					Carbon
Cal Al						75% FeSi		250			Cal Sil
Spar						SIMn		1000			FeCb
Cal C						HC FeMn					FeB
Lime	4,000					MC FeMn					FeTi
DoloLime						FeCr					FeV
Ni						Moly Oxide					Nitrovan
Cal Sil						Copper					FeS

Argon Log											
Argon Flow											Rinse Flow:

Temperatures and Times											
Time	06:30										Final N ₂ (ppm):
Temp. (°F)	2984										Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information											
Practice:	110	Roll No:	044	Chemistry:	25						
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	70	020	025	22	35	20	15	06		
Prelim.	6	41		80							
Prelim.	9										
Prelim.	12										
Prelim.											
Prelim.											
Prelim.											
Final	-.15	+ .86	.010	.029	+.31	.18	13	UY	03	008	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110
Final	.004	.003	.000	.000	.000	.0000	.0019	.0014		Sample Type:	555

Heat No. X-1277 Product Code 341																															
Split	R.O.	Billet Size	Length	Count	Tons	Steel	Scrap	Tons																							
A	5984	5.00X7.00	191	31	28.7	EE-1	0	0.0																							
B	5985	5.00X7.00	166	18	14.5	EE-1	0	0.0																							
C	0		0	0	0.0		0	0.0																							
D	0		0	0	0.0		0	0.0																							
<table border="1"> <thead> <tr> <th>Melter</th> <th>LMF Operator</th> <th>Ladleman</th> <th>Ladle No.</th> <th>Gate No.</th> <th>Heats on Ladle</th> <th>Heats on Plug</th> <th>Date</th> <th>Shift</th> <th>Heat Number</th> </tr> </thead> <tbody> <tr> <td>917</td> <td></td> <td>323</td> <td>7</td> <td></td> <td>36</td> <td>4</td> <td>5-12-00</td> <td>11-7</td> <td>X-1277</td> </tr> </tbody> </table>												Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number	917		323	7		36	4	5-12-00	11-7	X-1277
Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number																						
917		323	7		36	4	5-12-00	11-7	X-1277																						
Document No: MS-013 Revision Date: 04-19-1999 Revision Level: F																															
Remarks:																															

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number		Amount Used	
Last Tap		04:03		Last Heat - Treatment Stop	0554	At Furnace	At LMF
1st Chg.	04:16	05:00	66400	Current Heat - Treatment Start	0557	Power Meter	20910
2nd Chg.	05:05		49	Preparation Time	53.00	Electrode #1	
3rd Chg.				Current Heat - Treatment Stop	650	Electrode #2	
Tapping	05:50	05:55		Total Time of Heat		Electrode #3	
Tap Temp.	3855	Totals:		Reason for Return to LMF / Furnace		Lance Sections	
Total Time of Heat:				Est. Return Wgt.	Added Scrap Wgt.	Roof Delta	21
LMF	Ladle Weight			10-TIL		Wall Heat	22
Steel	Tare Weight	49,000 #				Thermocouples	
Weight	Steel Weight					Samplers	
						Oxygen Probes	

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon			70	50	Carbon	
Cal Al						75% FeSi		250	60	50	Cal Sil	
Spar			5-5			SiMn		1000			FeCb	
Cal C			8-2			AlC FeMn			300		FeB	
Lime	4000		550			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow	
------------	--	--	--	--	--	--	--	--	--	--	------------	--

Temperatures and Times

Time	06:05	06:27	06:40								Final N ₂ (ppm):
Temp. (°F)	2873	2889	2912								Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice: 110

Roll No: 044

Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	70	020	025	23	35	20	15	06	20	
Prelim	6	7	4	85	-	20	16	8	3	9	
Prelim	7	46	7	70	20						
Prelim	12	68	7	40	20						
Prelim	14			30							
Prelim											
Prelim	19	69	007	021	.26	.20	.16	.09	.03	.009	
Final											110
Element	Al	V	Nb	000	000	0000	0025	0015	DI	Grade Code:	555
Final	GRADE		1018 SQ							Sample Type:	

Heat No. W-1362

Product Code 341

S-Jit R.O. # Billet Size Length Count Tons Stack #Scrap Tons

A 5984 5.00X7.00 191 54 50.0 EE-1 0 0.0

B 0 0 0 0.0 0 0.0

C 0 0 0 0.0 0 0.0

D 0 0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
917	367	470	2		27	27	5-12-00	11-720	1362

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)			
	Start	Stop	Scrap Wt.
Last Tap		03:06	
1st Chg.	03:13	04:07	79400
2nd Chg.	04:09		29
3rd Chg.			
Tapping	04:53	05:00	
Tap Temp.	3053	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)	
Car Number	2
Last Heat - Treatment Stop	05:10
Current Heat - Treatment Start	05:12
Preparation Time	4:46
Current Heat - Treatment Stop	05:54
Total Time of Heat	

Reason for Return to LMF / Furnace	
Est. Return Wgt.	6500
Added Scrap Wgt.	4000
Total P.R.	
3-9.12	

Power & Supply Consumption		
	Amount Used	
	At Furnace	At LMF
Power Meter	21240	2525
Electrode #1		
Electrode #2		
Electrode #3		
Crane Sections		
Roof Delta	22	
Wall Heat	22	
Thermocouples		
Samplers		
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)				Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur
Slag Cond.		1,000				Carbon			100	40	Carbon
Cal Al						75% FeSi					Cal Sil
Spar			3-B			SiMn		250	80	50	FeCh
Cal C			6-C			HC FeMn		1000	300		FeB
Lime	4,000		300			MC FeMn					FeTi
DoloLime						FeCr					FeV
NI						Moly Oxide					Nitrovan
Cal Sil						Copper					FeS

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	05:21	05:46									Final N ₂ (ppm):
Temp. (°F)	2571	2893									Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice: 11A Roll No: 044 Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	70	0.20	0.25	22	35	20	15	0.6	20	
Prelim.	5	7	3	65	2	22	11	6	3	9	
Prelim.	5	44	4	55	17						
Prelim.	13	75	8	36	19						
Prelim.											
Prelim.											
Prelim.											
Final	.18	+.76	.007	.022	.24	.22	.11	.09	.03	.009	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	Ol	Grade Code:	110
Final	.004	.005	.000	.000	.000	.0000	.0018	.0015		Sample Type:	555

GRADE 1018 SQ

Heat No. X-1276

Product Code 21H

Solid R.O. # Billet Size Length Count Tons Stack 1 Scrap Tons

4 5983 5.00X7.00 169 57 46.7 EE-1 0 0.0

1 0 0 0 0.0 0 0.0

1 0 0 0 0.0 0 0.0

1 0 0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
917	367	453	10		8	8	5-12-00	11-7	X-1276

Document No: MS-011

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)

	Start	Stop	Snap Wt.
Last Tap	02:10	02:00	
1st Chg.	03:10	03:00	75,200
2nd Chg.	03:17		40
3rd Chg.			
Tapping	03:58	04:03	
Tap Temp.	3055	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)

Car Number	1
Last Heat - Treatment Stop	04:24
Current Heat - Treatment Start	04:31
Preparation Time	3932
Current Heat - Treatment Stop	05:10
Total Time of Heat	
Reason for Return to LMF / Furnace	
Est. Return Wgt.	Added Scrap Wgt.
15 - AFTER	

Power & Supply Consumption

	Amount Used	
	At Furnace	At LMF
Power Meter	10940	2500
Electrode #1	1	
Electrode #2	1	
Electrode #3	1	
Lance Sections		
Roof Delta	21	
Wall Heat	21	
Thermocouples		
Samplers		
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon			60		Carbon	
Cal Al						75% FeSi		250			Cal Sil	
Spar						SIMn		600			FeCb	
Cal C			2-C			HC FeMn			250		FeB	
Lima	4000		300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	04:01	04:59									Final N ₂ (ppm):	
Temp. (°F)	2845	2894									Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice: 110

Roll No: 044

Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^h	Al
Spec.	16	70	020	025	22	35	20	15	06	20	—
Prelim.	6	7	10	30	—	20	10	7	2	7	
Prelim	10	49	6	36	24						
Prelim	15	65	6	26	24						
Prelim											
Prelim											
Prelim											
Final	.16	.65	.007	.026	.24	.22	.12	.12	.03	.010	

Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110
Final	.006	.002	.000	.001	.000	.0000	.0002	.0168		Sample Type:	555

GRADE

1018 SQ

Heat No. W-1361	Product Code 21H
Split R.O. #	Billet Size Length Count Tons Stack #Scrap Tons
A 5983	5.00X7.00 169 66 54.1 EE-1 0 0.0
B 0	0 0 0.0 0 0.0
C 0	0 0 0.0 0 0.0
D 0	0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No	Gate No.	Heats O: Ladle	Heats on Plug	Date	Shift	Heat Numbe.
917	3027	322	8		37	12	5-12-00	11-7	W-1361

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

Set A-B-C elect

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
Last Tap	Start	Stop	Scrap Wt.	Car Number	2	Amount Used	
1st Chg.	01:33	01:18	83400	Last Heat - Treatment Stop	0325	At Furnace	At LMF
2nd Chg.	02:20		32	Current Heat - Treatment Start	0327	Power Meter	2240 6778
3rd Chg.				Preparation Time	5825	Electrode #1	
Tapping	03:00	03:05		Current Heat - Treatment Stop	0424	Electrode #2	
Tap Temp.	3055	Totals:		Total Time of Heat		Electrode #3	
Total Time of Heat:				Reason for Return to LMF / Furnace		Lance Sections	
LMF	Ladle Weight			Est. Return Wgt.	Added Scrap Wgt.	Roof Della	21
Steel	Tare Weight	49,000 #		25 - AFTER		Wall Heat	21
Weight	Steel Weight					Thermocouples	
						Samplers	
						Oxygen Probes	

Fluxes Added (lbs)						Alloys Added (lbs.)				Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur
Slag Cond.						Carbon			80	70	Carbon
Cal Al						75% FeSi		250		50	Cal Sil
Spar			2-0			SiMn		1000			FeCb
Cal C			4	2-0		HC FeMn			350		FeB
Lime	4000		300	150		MC FeMn					FeTi
DoloLime						FeCr					FeV
NI						Moly Oxide					Nitrovan
Cal Sil						Copper					FeS

Argon Log											
Argon Flow											Rinse Flow:

Temperatures and Times											
Time	0341	0403	0416	0422							Final N ₂ (ppm):
Temp. (°F)	2849	2871	2880	2926							Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information											
Practice:	110	Roll No:	044	Chemistry:							
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	70	020	025	22	35	20	15	06	-	-
Prelim.	9	10	5	55	0	20	12	8	3	9	-
Prelim	5	42	8	30	16						
Prelim	13	72	8	35	19						
Prelim											
Prelim											
Prelim											
Final	.18	+.76	.008	.020	.24	.23	.12	.10	.03	.010	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	110
Final	.004	.003	.000	.000	.000	.0000	.0018	.0016		Sample Type:	555
GRADE 1018 SQ											

Heat No.	X-1275	Product Code	21H
Split	B.O. #	Billet Size	Length Count Tons Stack #Scrap Tons
A	5981	5.00X7.00	170 62 51.1 NN-3 0 0.0
B	0		0 0 0.0 0 0.0
C	0		0 0 0.0 0 0.0
D	0		0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on LMF	Heats on Plug	Date	Shift	Heat Number
9/7	867	470	7		35	3	5-12-00	11-7	X-1275

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number		Amount Used	
Last Tap		00:05		Last Heat - Treatment Stop	0224	At Furnace	At LMF
1st Chg.	00:15	00:55	73300	Current Heat - Treatment Start		Power Meter	21400 5325
2nd Chg.	01:19		421	Preparation Time		Electrode #1	
3rd Chg.				Current Heat - Treatment Stop	0224	Electrode #2	
Tapping	01:55	02:00		Current Heat - Treatment Start	0226	Electrode #3	
Tap Temp.	3050	Totals:		Preparation Time	5825	Lance Sections	
Total Time of Heat:				Current Heat - Treatment Stop	0325	Roof Delta	210
				Total Time of Heat		Wall Heat	20
				Thermocouples			
				Samplers			
				Oxygen Probes			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs.)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	Carbon
Slag Cond		4000				Carbon			40			
Cal Al						75% FeSi		250				
Spar						SiMn		600				
Cal C			4-e			HC FeMn			500			
Lime	4000		500			MC FeMn						
DoloLime						FeCr						
Ni						Moly Oxide						
Cal Sil						Copper						

Argon Log

Argon Flow										Rinse Flow:

Temperatures and Times

Time	0234	0245	0302	0325						Final N ₂ (ppm):
Temp. (°F)	2888	2853	2890	2927						Final Temp (°F):
Oxygen (ppm)										Final O ₂ (ppm):

Practice: 110 Roll No: 044 Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	70	020	025	22	35	20	15	06	20	
Prelim.	10	10	4	53	-	22	70	9	2	10	
Prelim	10	47	5	30	24						
Prelim	17	68	6	17	25						
Prelim											
Prelim											
Prelim											
Final	.17	.72	.008	.010	.25	.22	.10	.11	.02	.012	

Element	Al	V	Nb	Ti	Zr	B	Ca	Zn		Grade Code:	110
Final	.005	.003	.001	.000	.001	.0000	.0014	.0014		Sample Type:	555

GRADE

1018 SQ

Heat No. W-1360		Product Code 21H	
Split	B.O. #	Billet Size	Length Count Tons Stack # Scrap Tons
A	5981	5.00X7.00	170 61 50.3 NN-3 6 4.7
B	0		0 0 0.0 0 0.0
C	0		0 0 0.0 0 0.0
D	0		0 0 0.0 0 0.0

Melter	LMF Operator	Ladleman	Ladle No	Gate No.	Heats on Ladle	Heels on Plug	Date	Shift	Heat Number
917	307	453	2		19	19	5-12-00	11-7	W-1360

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)

	Start	Stop	Scrap Wt
Last Tap		22:55	
1st Chg	23:15	00:05	73200
2nd Chg	00:07		271
3rd Chg			
Tapping	00:55	01:00	
Tap Temp.	30:55	Totals:	
Total Time of Heat:			

LMF Treatment Log (time)

Car Number	2
Last Heat - Treatment Stop	0121
Current Heat - Treatment Start	0123
Preparation Time	6103
Current Heat - Treatment Stop	0224
Total Time of Heat	

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.

25-ARTEL

Power & Supply Consumption

	Amount Used	
	At Furnace	At LMF
Power Meter	19910	2875
Electrode #1		
Electrode #2		
Electrode #3	1	
Lance Sections		
Roof Delta	20	
Wall Heat	20	
Thermocouples		
Samplers		
Oxygen Probes		

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	Carbon
Slag Cond.		1000				Carbon			140	60	Carbon	
Cal Al						75% FeSi		110	100		Cal Sil	
Spar			1-5			SiMn		1300			FeCb	
Cal C			4-2			HC FeMn			350		FeB	
Lime	4000		500			MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni	1					Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	0131	0157	0207								Final N ₂ (ppm):
Temp. (°F)	2884	2936	2914								Final Temp (°F):
Oxygen (ppm)											Final O ₂ (ppm):

Chemistry and Billet Information

Practice: 9:30

Roll No: 044

Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^u	Al
Spec.	23	110	0.25	0.30	22	40	30	30	06	—	
Prelim.	5	7	6	55	—	21	8	7	2	11	—
Prelim.	5	79	11	52	19						
Prelim.	16	114	11	28	23						
Prelim.											
Prelim.											
Prelim.											
Final	.23	1.12	.011	.020	.24	.22	.60	.09	.02	.010	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code: 930	
Final	.004	.005	.000	.000	.000	.0000	.0013	.0012		Sample Type:	555

GRADE

A529 GR 50

Heat No. X-1274

Product Code 21H

Split B.O. # Billet Size Length Count Tons Stack 1 Scrap Tons

A 5980 5.00X7.00 180 47 41.0 NN-3 0 0.0

B 0 0 0 0 0 0 0 0 0 0

C 0 0 0 0 0 0 0 0 0 0

D 0 0 0 0 0 0 0 0 0 0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
917	307	323	10		7	8	5-12-00	11-7	X-1274

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

Set C - elect

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number		Amount Used	
Last Tap		22:00		Last Heat - Treatment Stop	0019	At Furnace	At LMF
1st Chg.	22:19	23:00	78,000	Current Heat - Treatment Start	0021	Power Meter	23870 2025
2nd Chg.	23:05		32,000	Preparation Time	5136	Electrode #1	
3rd Chg.				Current Heat - Treatment Stop	0121	Electrode #2	
Tapping	24:00	00:05		Total Time of Heat		Electrode #3	
Tap Temp.	30.55	Totals:		Reason for Return to LMF / Furnace		Lance Sections	
Total Time of Heat:				Est. Return Wgt.	Added Scrap Wgt.	Roof Delta	19
LMF	Ladle Weight			22-125720		Wall Heat	19
Steel	Tare Weight	49,000 #				Thermocouples	
Weight	Steel Weight					Samplers	
						Oxygen Probes	

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1,000				Carbon	4-15		70		Carbon	
Cal Al						75% FeSi		110			Cal Sil	
Spar						SiMn		1200			FeCb	
Cal C						HC FeMn			250		FeB	
Lime	4,000					MC FeMn					FeTi	
DoloLime						FeCr					FeV	
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	00:30	01:35	01:01								Final N ₂ (ppm):	
Temp. (°F)	2876	1922	2719								Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice: 930

Roll No: 044

Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{li}	Al
Spec.	23	110	025	030	22	40	20	20	06		
Prelim.	10	13	6	45	—	25	10	14	3	12	—
Prelim.	13	84	8	27	24						
Prelim.	21	105	12	22	27						
Prelim.											
Prelim.											
Prelim.											
Prelim.	21	1.02	.010	.018	.27	.23	.10	.16	.03	.011	
Final											930
Element	Al	V	Nb	000	000	0000	0011	20012	DI	Grade Code:	555
Final	GRADE			A529 GR 50						Sample Type:	

Heat No. W-1359

Product Code 21H

Split B.O. # Billet Size Length Count Tons Stack # Scrap Tons

A 5980 5.00X7.00 180 57 49.8 NN-3 6 5.2

B 0 0 0 0 0 0 0 0 0

C 0 0 0 0 0 0 0 0 0

D 0 0 0 0 0 0 0 0 0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
9/17	367	470	8		56	36	5-12-00	11-7	W-1359

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:

EAF Melting Log (time)				LMF Treatment Log (time)		Power & Supply Consumption	
	Start	Stop	Scrap Wt.	Car Number		Amount Used	
Last Top		21:10		Last Heat - Treatment Stop	2320	At Furnace	At LMF
1st Chg.	21:30	22:09	78,000	Current Heat - Treatment Start	2335	Power Meter	17420 5325
2nd Chg.	22:10		30,000	Preparation Time	4337	Electrode 111	
3rd Chg.				Current Heat - Treatment Stop	0019	Electrode 112	
Tapping	22:40	22:55		Total Time of Heat		Electrode #3	
Tap Temp.	3020	Totals:				Lance Sections	
Total Time of Heat:				Reason for Return to LMF / Furnace		Roof Delta	19
						Wall Heat	19
						Thermocouples	
						Samplers	
						Oxygen Probes	

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

Est. Return Wgt.		Added Scrap Wgt.	

20-ASTEX

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon	4-B		60		Carbon	
Cal Al						75% FeSi		780	100		Cal Sil	
Spar			1-B			SiMn		1300			FeCb	
Cal C			4-C			HC FeMn			200		FeB	
Lime	4000		300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	4-B
Ni						Moly Oxide					Nitrovan	
Cal Sil						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	22:31	22:40	23:40	23:53	24:08						Final N ₂ (ppm):	
Temp. (°F)	2819	3008	2808	2846	2883						Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice:	408	Roll No:	644	Chemistry:								
Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^b	Al	
Spec.	16	100	20	25	22	35	20	20	06			
Prelim.	4	7	4	50	-	22	9	4	12			
Prelim		82	7	38	16							
Prelim	13	99	8	32	25							
Prelim												
Prelim												
Prelim												
Final	.16	1.02	.009	.021	.26	23	.09	10	.02	.011		
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	DI	Grade Code:	408	
Final	+.004	.048	.000	.000	.000	.0000	.0017	.0016		Sample Type:	555	
GRADE A572-GR/50												

Heat No. X-1273

Product Code 21H

Split R.O. #

Billet Size Length Count Tons Stack # Scrap Tons

A	5979	5.00X7.00	172	63	52.6	NN-3	0	0.0
B	0		0	0	0.0		0	0.0
C	0		0	0	0.0		0	0.0
D	0		0	0	0.0		0	0.0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat number
912	367	461	7		34	2	5-11-2000	3-11	X-1273

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks: Set #2+3-Elect.

EAF Melting Log (time)

	Start	Stop	Scrap Wt.
Carl Tap		18:35	
1st Chg	2 30	21:13	73,000
2nd Chg	21:15		98
3rd Chg			
Tapping	21:55	22:40	
Tap Temp.	3020	Totals:	
Total Time of Heat:			

LMF	Ladle Weight	
Steel	Tare Weight	49,000 #
Weight	Steel Weight	

LMF Treatment Log (time)

Car Number	1
Last Heat - Treatment Stop	22:16
Current Heat - Treatment Start	22:19
Preparation Time	6:24
Current Heat - Treatment Stop	23:19
Total Time of Heat	

Reason for Return to LMF / Furnace

Est. Return Wgt.	Added Scrap Wgt.

Power & Supply Consumption

	Amount Used	
	At Furnace	At LMF
Power Meter	21490	5750
Electrode #1		
Electrode #2		
Electrode #3		
Lance Sections		
Roof Delta	18	
Wall Heat	18	
Thermocouples		
Samplers		
Oxygen Probes		

Additions To The Furnace and Ladle

Fluxes Added (lbs)						Alloys Added (lbs.)					Wire Added (ft)	
Time	Furnace	Ladle	LMF	LMF	LMF	Time	Furnace	Ladle	LMF	LMF	Sulfur	
Slag Cond.		1000				Carbon	4-B				Carbon	
Cal Al						75% FeSi		200			Cal Si	
Spar			2-11			SiMn		1200			FeCb	
Cal C			4-2			HC FeMn					FeB	
Lime	4000		300			MC FeMn					FeTi	
DoloLime						FeCr					FeV	4-B
Ni	1					Moly Oxide					Nitrovan	
Cal Si						Copper					FeS	

Argon Log

Argon Flow											Rinse Flow:	
------------	--	--	--	--	--	--	--	--	--	--	-------------	--

Temperatures and Times

Time	21:51	22:29	22:47	22:51	23:14						Final N ₂ (ppm):	
Temp. (°F)	2929	2832	2866	2924	2919						Final Temp (°F):	
Oxygen (ppm)											Final O ₂ (ppm):	

Chemistry and Billet Information

Practice: 1, 8 Roll No: 044 Chemistry:

Element	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn ^{II}	Al
Spec.	16	100	20	25	22	35	20	20	04		
Prelim.	28	21	7	40	-	20	8	14	02		
Prelim											
Prelim											
Prelim											
Prelim											
Prelim											
Final	.18	.98	.011	.009	.28	.20	.10	.19	.02	.009	
Element	Al	V	Nb	Ti	Zr	B	Ca	Zn	Di	Grade Code:	555
Final	+.004	+.051	.000	.000	.000	.0000	.0011	.0013		Sample Type:	

GRADE

A572-GR/50

Heat No. W-1358

Product Code 21H

Split R.O. # Billet Size Length Count Tons Stack #Scrap Tons

A 5979 5.00X7.00 172 56 46.7 NN-3 5 4.2

B 0 0 0 0 0 0 0 0 0 0 0 0

C 0 0 0 0 0 0 0 0 0 0 0 0

D 0 0 0 0 0 0 0 0 0 0 0 0

Melter	LMF Operator	Ladleman	Ladle No.	Gate No.	Heats on Ladle	Heats on Plug	Date	Shift	Heat Number
712	235	459	2		18	18	5-11-2000	3-71	W-1358

Document No: MS-013

Revision Date: 04-19-1999

Revision Level: F

Remarks:



Appendix D

Emission Testing Field Data



TRAVERSE POINT LOCATION FOR RECTANGULAR DUCTS

Plant: Kentucky SFO

Date: 5/10/00

Sampling Location: Bayhouse inlet

Duct Width, inches: 132"

Inside of Far Wall to Outside of Nipple: 142"

Inside of Near Wall to Outside of Nipple (Nipple Length): 3"

Duct Length, inches: 134"

Equivalent Diameter = $2 \times L \times W / (L + W) =$ 134"

Distance Downstream from Flow Disturbance (Distance B):

192 inches / Equivalent Diameter = 1.4 dd

Distance Upstream from Flow Disturbance (Distance A):

165 inches / Equivalent Diameter = 1.22 dd

Calculated By: 26/76

Schematic of
Sampling Location

Traverse Point Number	Fraction of Length	Length (inches)	Product of Columns 2 & 3* (To nearest 1/8")	Nipple Length (inches)	Traverse Point Location (Sum of Col. 4 & 5)
1	0.062	139"	8.6	3"	11.6
2	0.188		26.13		29.73
3	0.312		43.37		46.37
4	0.438		60.09		63.88
5	0.562		78.12		81.11
6	0.688		95.63		98.63
7	0.812		112.87		115.87
8	0.938		130.38		133.38
			5		

If No Ports. Calculate Distances From Stack Walls For Port Locations

Number of Ports	Fraction of Width	Width (inches)	Port Location Product of Col. 2 & 3* (To Nearest 1/83)

* All points or ports should be an equal distance from each other (D) and 1/2 of that distance from the stack walls (D/2), where $D = \text{Width} / \# \text{ of points or ports}$




Figure 3-2. Inlet Velocity Measurement Location



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KENTUCKY ELECTRIC STEEL Date: 5/10/00
Sampling Location: BAGMOOSE INLET Clock Time: 13.14
Run #: PRELIM Operators: TG/RK/TW
Barometric Pressure, in. Hg: 29.46 Static Pressure, in. H₂O: +4.7
Moisture, %: 1 Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
Stack Dimension, in. Diameter or Side 1: 139 Side 2: 132
Wet Bulb, °F: — Dry Bulb, °F: —

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
1	1.1	219.1
2	1.1	214.2
3	1.6	215.3
4	1.8	217.9
5	1.9	214.9
6	1.9	195.6
7	2.1	168.6
8	2.1	144.2
1	1.3	150.0
2	1.2	191.0
3	1.5	211.3
4	1.7	217.3
5	1.7	207.3
6	1.9	192.5
7	2.1	175.9
8	2.1	160.1
1	0.88	154.7
2	1.2	193.0
3	1.5	206.7
4	1.6	194.2
5	1.7	172.2
6	1.8	162.2
7	2.0	148.4
8	2.1	131.7
$\sqrt{\Delta P} =$		$T_s = 158$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d =$$

$$M_s = M_d \times \left(1 - \frac{\%H_2O}{100}\right) + 18 \left(\frac{\%H_2O}{100}\right)$$

$$M_s = (\quad) \times \left(1 - \frac{\quad}{100}\right) + 18 \left(\frac{\quad}{100}\right)$$

$$M_s =$$

$$T_s = \quad ^\circ F = \quad ^\circ R \quad (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = \quad \text{in. Hg}$$

$$\sqrt{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times \left(1 - \frac{\%H_2O}{100}\right)$$

$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times \left(1 - \frac{\quad}{100}\right)$$

$$Q_{s, \text{std}} = \quad \text{dscfm}$$

1862



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KENTUCKY ELECTRIC STEEL Date: 5/10/00
 Sampling Location: BOATHOUSE INLET Clock Time: 13:15
 Run #: PRELIM Operators: RK/TG/TW
 Barometric Pressure, in. Hg: _____ Static Pressure, in. H₂O: +4.7
 Moisture, %: _____ Molecular wt., Dry: _____ Pitot Tube, Cp: _____
 Stack Dimension, in. Diameter or Side 1: _____ Side 2: _____
 Wet Bulb, °F: _____ Dry Bulb, °F: _____

D

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
1	1.7	127.3
2	1.6	157.9
3	1.5	159.5
4	1.4	155.9
5	1.6	149.3
6	1.6	145.1
7	2.3	136.1
8	2.1	130.2
	2.1	118.3
1	↓	↓
2	1.6	125.0
3	1.6	126.3
4	1.6	127.0
5	1.8	127.8
6	1.7	128.0
7	2.4	126.7
8	2.3	124.0
1	1.9	115.4
2	1.6	117.4
3	1.4	118.4
4	1.7	119.2
5	1.8	119.8
6	2.2	119.9
7	2.0	118.5
8	1.9	118.9

E

F

134724

$\Delta P = 1.7433$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times) + (0.32 \times) + (0.28 \times)$$

$$M_d = 28.04$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = () \times (1 - \frac{ }{100}) + 18 (\frac{ }{100})$$

$$M_s = 28.73$$

$$T_s = 158 ^\circ F = 618 ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = () + \frac{ }{13.6}$$

$$P_s = 29.81 \text{ in. Hg}$$

$$\sqrt{\Delta P} = 1.3140$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times () \times () \times \sqrt{ }$$

$$V_s = 80.16 \text{ ft/s}$$

$$A_s = \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \times \times 60$$

$$Q_s = 612821 \text{ acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \times 17.647 \times \times (1 - \frac{ }{100})$$

$$Q_{s, \text{std}} = 516355 \text{ dscfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: Kentucky Electric Steel Date: 5/10/00
Sampling Location: BAHOUSE INLET Clock Time:
Run #: Calim = 2/3 Fans.* Operators: RK/TC/TH
Barometric Pressure, in. Hg: 29.46 Static Pressure, in. H₂O: +2.3
Moisture, %: 1 Molecular wt., Dry: 28.9 Pitot Tube, Cp: 0.84
Stack Dimension, in. Diameter or Side 1: 139" Side 2: 132"
Wet Bulb, °F: Dry Bulb, °F:

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
1	0.52	145.9
2	0.42	157.2
3	0.40	170.3
4	0.70	178.8
5	0.84	182.3
6	0.72	183.5
7	0.65	176.7
8	0.64	169.7
1	0.52	152.3
2	0.49	156.3
3	0.50	161.6
4	0.70	169.6
5	0.88	175.5
6	0.88	176.7
7	0.77	175.7
8	0.59	162.7
1	0.65	148.2
2	0.59	152.3
3	0.68	160.3
4	0.82	165.8
5	0.92	171.3
6	0.98	172.3
7	0.85	171.4
8	0.72	166.3
$\overline{\Delta P}$ =		T_s =

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d =$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s =$$

$$T_s = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = \quad \text{in. Hg}$$

$$\overline{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\overline{\Delta P}} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/min}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s, \text{std}} = \quad \text{dscfm}$$

one
* 900# Fan shut down during flow measurement



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: Kenrock U Electric Steel Date: 5/10/00
 Sampling Location: USE TANKET Clock Time: 15:15
 Run #: PRELIM w/ 2/2 Operators: RK/TC/TN
 Barometric Pressure, in. Hg: 29.46 Static Pressure, in. H₂O: +2.3
 Moisture, %: i Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
 Stack Dimension, in. Diameter or Side 1: 139" Side 2: 132"
 Wet Bulb, °F: — Dry Bulb, °F: —

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
1	0.70	140.6
2	0.62	141.9
3	0.61	143.8
4	0.64	144.0
5	0.72	146.3
6	1.0	148.8
7	0.98	149.6
8	0.85	149.1
1	0.49	139.6
2	0.50	141.5
3	0.48	143.4
4	0.56	144.1
5	0.66	145.0
6	0.78	145.4
7	0.85	145.2
8	0.77	144.4
1	0.35	139.0
2	0.43	140.6
3	0.44	142.7
4	0.46	145.4
5	0.54	148.8
6	0.65	149.9
7	0.66	150.6
8	0.82	150.8
$\sqrt{\Delta P} = 0.8112$		$T_s = 156$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d = 28.84$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s = 28.73$$

$$T_s = 156 \text{ } ^\circ F = 616 \text{ } ^\circ R \text{ (} ^\circ F + 460 \text{)}$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = 29.63 \text{ in. Hg}$$

$$\sqrt{\Delta P} = 0.8112$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = 49.55 \text{ ft/s}$$

$$A_s = \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = 378,835 \text{ acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s, \text{std}} = 318,343 \text{ dscfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KES Date: 5/24/07
 Sampling Location: BAGHOUSE WCEI Clock Time: 1730
 Run #: 500 HP Fan off Operators: GC/TC/TW
 Barometric Pressure, in. Hg: 29.45 Static Pressure, in. H₂O: +4.1
 Moisture, %: Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
 Stack Dimension, in. Diameter or Side 1: 139 Side 2: 132
 Wet Bulb, °F: Dry Bulb, °F:

A

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
1	0.78	135.3
2	0.91	146.7
3	0.88	153.1
4	0.82	156.7
5	0.95	159.7
6	1.4	162.6
7	1.5	164.6
8	1.6	166.6
B		
1	0.87	167.0
2	0.86	168.5
3	0.84	169.4
4	0.83	169.9
5	0.99	170.0
6	1.5	170.4
7	1.6	171.0
8	1.4	171.3
C		
1	0.98	168.7
2	0.94	169.2
3	0.88	169.9
4	0.99	170.3
5	1.0	170.6
6	1.6	171.1
7	1.7	171.3
8	1.6	171.5
$\overline{\Delta P} =$		$\overline{T_s} =$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d = 28.84$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s =$$

$$\overline{T_s} = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = \quad \text{in. Hg}$$

$$\overline{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\overline{\Delta P}} \times \sqrt{\frac{\overline{T_s} (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{\overline{T_s}} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s, \text{std}} = \quad \text{dscfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KES Date: 5/12/00
 Sampling Location: BAGHOUSE INLET Clock Time: 1730
 Run #: SOOT HP FOR Operators: GG/TG/TA
 Barometric Pressure, in. Hg: _____ Static Pressure, in. H₂O: 14.1
 Moisture, %: _____ Molecular wt., Dry: _____ Pitot Tube, Cp: _____
 Stack Dimension, in. Diameter or Side 1: _____ Side 2: _____
 Wet Bulb, °F: _____ Dry Bulb, °F: _____

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
1	1.0	171.7
2	1.0	172.6
3	1.0	173.3
4	0.95	173.7
5	1.1	174.0
6	1.7	174.5
7	1.8	175.2
8	1.8	175.0
1	1.6	175.8
2	1.6	175.9
3	1.0	176.0
4	1.2	176.0
5	1.5	176.2
6	1.8	176.2
7	1.9	176.9
8	1.8	177.2
1	1.5	173.3
2	0.90	172.8
3	0.90	172.7
4	1.4	173.7
5	1.5	174.4
6	1.6	178.1
7	1.5	184.5
8	1.4	186.6
$\overline{\Delta P} = 1.1153$		$\overline{T}_s = 170$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d =$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s =$$

$$\overline{T}_s = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_a - \quad \text{In. Hg}$$

$$\overline{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \overline{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$


$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$


$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s, \text{std}} = \quad \text{dscfm}$$



Proposed KES, Inc. Outlet Sampling Points

Figure 3-3. Schematic of Baghouse Outlet

$12.5' + 23' + 23'$
 $23' + 23' + 23'$


20 compartments total
 10 compartments per side

TRAVERSE POINT LOCATION FOR RECTANGULAR DUCTS

Plant: AES

Date: _____

Sampling Location: Bygone Outlet

Duct Width, inches: _____

Inside of Far Wall to Outside of Nipple: _____

Inside of Near Wall to Outside of Nipple (Nipple Length): _____

Duct Length, inches: _____

Equivalent Diameter = $2 \times L \times W / (L + W) =$ _____


Distance Downstream from Flow Disturbance (Distance B): _____

_____ inches / Equivalent Diameter = _____ dd

Distance Upstream from Flow Disturbance (Distance A): _____

_____ inches / Equivalent Diameter = _____ dd

Calculated By: TW/RK



Traverse Point Number	Fraction of Length	Length (inches)	Product of Columns 2 & 3* (To nearest 1/83)	Nipple Length (inches)	Traverse Point Location (Sum of Col. 4 & 5)

~~736,000 ft~~
~~1360,000 ft~~
 5381 ft²

If No Ports. Calculate Distances From Stack Walls For Port Locations

Number of Ports	Fraction of Width	Width (inches)	Port Location Product of Col. 2 & 3* (To Nearest 1/87)

* All points or ports should be an equal distance from each other (O) and 1/2 of that distance from the stack walls (D/2), when $D = \text{Width} / \# \text{ of points or ports}$

27' 3"

STACK TEST REVIEW

NAME ky Electric Steel TEST NO. _____
 SOURCE TYPE Harsco Products Process Bayhous RUN NO. 24
 MODEL OR NAME _____ DATE OF TEST 5-12, 2000 0630
 TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>148</u> °F P_s , Stack pressure <u>27.83</u> in.Hg T_m , Meter temperature _____ °F P_m , Meter pressure _____ in.Hg M_w , Condensed water _____ gm V_{DGM} , Volume of sample (meter conditions) <u>8</u> cf	V_{H_2O} , Volume of water _____ cf B_{H_2O} , Moisture of content <u>1</u> V_{ne} , Volume of sample _____ cf at stack cond. _____ cf M_{dry} , Molecular wt dry <u>28.84</u> M_{wet} , Molecular wt wet <u>28.73</u> Velocity <u>82.20</u> fps <u>32,293,420 DSCF/hr</u>
CO_2 <u>0.0</u> % O_2 <u>21.0</u> % CO_2 <u>0.0</u> % N_2 <u>79.0</u> %	Isokinetic Ratio _____ gr/scf @ 12% CO_2 _____
AP , Velocity head <u>1.5713</u> in. H_2O (traverse points) C_p , Pitot tube coeff. <u>0.84</u> _____ min x 60 Θ , Sampling time _____ sec. A_n , area of nozzle $D =$ _____ ft ² $D^2 \times 0.005454$	Lb/Hr _____ Lb/mm BTU _____
Weight of collected _____ gm pollutant CO_2 , Waste only _____ %	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
A_s , Area of stack $D =$ ft $\frac{D^2}{4} \pi$ <u>131.50</u> ft ² <u>10'11 1/2" x 12'</u> <u>132 x 139</u> Boiler Heat Capacity <u>12742</u> mmBTU/Hr.	

REMARKS

STACK TEST REVIEW

NAME ky Electric Steel TEST NO. _____

SOURCE TYPE Harsco Products Inc. Baghouse RUN NO. BI 20-3A

MODEL OK NAME _____ DATE OF TEST 5-14, 2000 10:57

TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>141.0</u> °F P_s , Stack pressure <u>29.78</u> in. Hg. T_m , Meter temperature _____ °F P_m , Meter pressure _____ in. Hg. M_w , Condensed water _____ gm V_{DGM} , Volume of sample (meter conditions) <u>8</u> cf	V_{H_2O} , Volume of water _____ cf B_{wo} , Moisture of content <u>170 assumed</u> V_{ne} , Volume of sample at stack cond. _____ cf M_{dry} , Molecular wt dry <u>28.94</u> M_{wet} , Molecular wt wet _____ Velocity <u>81.92</u> fps <u>Q₃₀ 33,296,079 DSCF/hr</u>
CO_2 _____ % O_2 _____ % CO_2 _____ % N_2 _____ %	Isokinetic Ratio _____ gr/scf @ 12% CO_2
AP, Velocity head <u>1.83743</u> in. H_2O <u>1.35552</u> (traverse points) C_p , Pitot tube coeff. <u>0.84</u>	Lb/Hr _____ Lb/mm BIU _____
_____ min x 60 θ , Sampling time _____ sec. A_n , area of nozzle D= _____ ft ² D ² x 0.005454	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
Weight of collected _____ gm pollutant CO_2 , Waste only _____ %	
A_s , Area of stack D= ft <u>D2</u> π <u>131.50</u> ft ² <u>101 x 112" 4</u> <u>132 x 139</u> <u>127.42</u>	
Boiler Heat Capacity _____ mmBTU/Hr.	

REMARKS

STACK TEST REVIEW

NAME ky Electric Steel TEST NO. _____
 SOURCE TYPE Hassell Pouchier 10000 Bingham RUN NO. 1A
 MODEL OR NAME _____ DATE OF TEST 5-11, 2000 07:30
 TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>142</u> °F P_s , Stack pressure <u>29.98</u> in. Hg. T_m , Meter temperature _____ °F P_m , Meter pressure _____ in. Hg. M_w , Condensed water _____ gm V_{DGM} , Volume of sample (meter conditions) <u>8</u> cf	V_{H_2O} , Volume of water _____ cf B , Moisture of content <u>+70 assumed</u> V_{ne} , Volume of sample at stack cond. _____ cf M_{dry} , Molecular wt dry <u>28.84</u> M_{wet} , Molecular wt wet <u>28.73</u> Velocity <u>81.62</u> fms <u>QSD 33,615,682 DSCF/W</u>
CO_2 <u>0.0</u> % O_2 <u>21.0</u> % CO_2 <u>0.0</u> % N_2 <u>79.0</u> %	Isokinetic Ratio gr/scf @ 12% CO_2
AP , Velocity head <u>1.84</u> in. H ₂ O (traverse points) C_p , Pitot tube coeff. <u>0.84</u>	Lb/Hr $Lb/mm\ BTU$
_____ min x 60 θ , Sampling time _____ sec. A_n , area of nozzle $D =$ " _____ ft^2 $D^2 \times 0.005454$	
Weight of collected _____ gm pollutant CO_2 , Waste only _____ %	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
A_s , Area of stack $D =$ ft $\frac{D^2}{4} \pi$ <u>131.50</u> ft^2 <u>10'11 1/2" x 12'</u> <u>132 x 139</u> <u>127.42</u> Boiler Heat Capacity <u>mmBTU/Hr.</u>	

REMARKS

STACK TEST REVIEW

NAME ky Electric Steel

TEST NO. _____

SOURCE TYPE Haskell Products Pressure Bayhous

RUN NO. 1B

MODEL OR NAME _____

DATE OF TEST 5-11, 2000 0705

TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>130</u> °F P_s , Stack pressure <u>24.43</u> in. Hg T_m , Meter temperature _____ °F P_m , Meter pressure _____ in. Hg M_w , Condensed water _____ gm V_{DGM} , Volume of sample (meter conditions) <u>8</u> cf	V_{H_2O} , Volume of water _____ cf B_{mo} , Moisture of content <u>1</u> % V_{ne} , Volume of sample at stack cond. _____ cf M_{dry} , Molecular wt dry <u>28.84</u> M_{wet} , Molecular wt wet <u>28.73</u> Velocity <u>79.12</u> fps <u>Qsd 33.496 528 DSCF/hr</u>
CO_2 <u>0.0</u> % O_2 <u>21.0</u> % CO_2 <u>0.0</u> % N_2 <u>79.0</u> %	Isokinetic Ratio _____ gr/scf @ 12% CO_2 _____
AP, Velocity head <u>1.70913</u> in. H_2O ^{1.33007} (traverse points) C_p , Pitot tube coeff. <u>0.84</u>	Lb/Hr _____ Lb/mm BIU _____
_____ min x 60 θ , Sampling' time _____ sec. A_n , area of nozzle D= _____ ft ² D ² x <u>0.005454</u>	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
Weight of collected _____ gm pollutant CO_2 , Waste only _____ %	
A_s , Area of stack D= ft <u>D2</u> π <u>131.5</u> ft ² <u>10'11 1/2" x 12'</u> <u>132 134</u> <u>127.42</u> Boiler Heat Capacity _____ mmBTU/Hr.	

REMARKS

STACK TEST REVIEW

NAME Kentucky Electric Steel TEST NO. _____


SOURCE TYPE Harsco Pittman Pressure Baghouse RUN NO. BF 5B

MODEL OR NAME _____ DATE OF TEST 5-12-06 16 °F

TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>191</u> °F P_s , Stack pressure <u>29.79</u> in. Hg. T_m , Meter temperature _____ °F P_m , Meter pressure _____ in. Hg. M_w , Condensed water _____ gm V_{DGM} , Volume of sample (meter conditions) _____ cf	V_{H_2O} , Volume of water _____ cf B_{wo} , Moisture of content <u>1</u> % (wt) <u>7.5</u> % V_{ne} , Volume of sample at stack cond. _____ cf M_{dry} , Molecular wt dry <u>29.5</u> M_{wet} , Molecular wt wet _____ Velocity <u>80.89</u> f/s <u>QSD 30,612,842</u>
CO_2 _____ % O_2 _____ % CO_2 _____ % N_2 _____ %	Isokinetic Ratio _____ gr/scf @ 12% CO_2
AP , Velocity head <u>1.66800</u> in. H_2O <u>1.29151</u> (traverse points) C_p , Pitot tube coeff. _____	Lb/Hr _____
_____ min x 60 θ , Sampling time _____ sec. A_n , area of nozzle $D=$ " _____ ft^2 $D^2 \times 0.005454$	Lb/mm BTU _____
Weight of collected _____ gm pollutant CO_2 , Waste only _____ %	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
A_s , Area of stack $D=$ ft <u>D2</u> π <u>131.50</u> ft^2 <u>10'11.5" x 12' 4"</u> <u>132" x 139"</u> <u>127.42</u> Boiler Heat Capacity _____ mmBTU/Hr.	

REMARKS



82.5

631,123

510,407



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KENTUCKY ELECTRIC STEEL Date: 5/11/00
 Sampling Location: BAGHOUSE INLET Clock Time: 0720
 Run #: Run 1A Operators: GA/TG/WD
 Barometric Pressure, in. Hg: _____ Static Pressure, in. H₂O: +5.1
 Moisture, %: _____ Molecular wt., Dry: _____ Pitot Tube, Cp: _____
 Stack Dimension, in. Diameter or Side 1: _____ Side 2: _____
 Wet Bulb, °F: _____ Dry Bulb, °F: _____

Traverse Point Numkr	Velocity Head In. H ₂ O	Stack Temp. °F
1	1.7	120.1
2	1.9	133.0
3	1.7	133.9
4	1.5 1.5	133.2
5	1.9	123.5
6	2.0	118.0
7	2.2	109.7
8	2.1	105.9
1	2.1	96.6
2	2.3	98.3
3	1.6	97.9
4	1.7	97.9
5	2.0	97.7
6	2.0	96.8
7	2.4	94.6
8	2.4	92.7
1	1.2	87.2
2	1.5	87.1
3	1.7	87.0
4	2.0	87.0
5	2.1	87.1
6	2.2	86.9
7	2.1	86.3
8	2.1	85.9
$\sqrt{\Delta P} = 1.3594$		$T_s = 142$

avg $\Delta P = 1.864$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d = 28.84$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s = 28.75 \quad 28.71 \text{ g/g}$$

$$T_s = \quad ^\circ F = 602 ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = 29.97 \text{ in. Hg}$$

$$\sqrt{\Delta P} = 1.3594$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = 81.62 \text{ ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/min}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = 623962 \text{ acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s, \text{std}} = 542784 \text{ dscfm}$$

65.2535



page 1 of 2

GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: Honolulu Electric Steel Date: 5/11/60
Sampling Location: Bughouse inlet Clock Time: 1900
Run #: 1B Operators: AK/TG/66
Barometric Pressure, in. Hg: 29.60 Static Pressure, in. H₂O: +
Moisture, %: 1.2 Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
Stack Dimension, in. Diameter or Side 1: 139" Side 2: 132"
Wet Bulb, °F: _____ Dry Bulb, °F: _____

204 A

B

C

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
1	2.1 1.1	146
2	1.2	155
3	1.45	159
4	1.75	159
5	1.9	152
6	2.1	141
7	2.1	131
8	1.9	127
1	1.3	141
2	1.0	149
3	1.6	135
4	1.7	156
5	1.8	147
6	1.9	140
7	1.9	130
8	2.0	125
1	1.0	134
2	1.1	143
3	1.6	149
4	1.8	147
5	1.8	139
6	1.9	132
7	2.2	125
8	2.1	120
	$\overline{\Delta P}$ =	$\overline{T_s}$ =

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d =$$

$$M_a = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_a = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_a =$$

$$\overline{T_s} = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_a = P_b + \frac{SP.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_a = \quad \text{in. Hg}$$

$$\overline{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\overline{\Delta P}} \times \sqrt{\frac{\overline{T_s} (^\circ R)}{P_a \times M_a}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/min}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_a}{\overline{T_s}} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s, \text{std}} = \quad \text{scfm}$$



page 2 of 2

GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: Kentucky Electric Steel Date: 5/11/00
Sampling Location: Bygonne Outlet Clock Time: 0705
Run #: 1B Operators: RK/TG
Barometric Pressure, in. Hg: 29.60 Static Pressure, in. H₂O: +4.5
Moisture, %: 1.2 Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
Stack Dimension, in. Diameter or Side 1: 139" Side 2: 132"
Wet Bulb, °F: — Dry Bulb, °F: —

Traverse Point Numkr	Velocity Head In. H ₂ O	Stack Temp. °F
1	2.0	122
2	1.8	126
3	1.8	130
4	1.9	130
5	1.7	128
6	1.8	125
7	2.0	121
8	2.1	118
1	1.9	115
2	1.7	116
3	1.5	117
4	1.8	118
5	1.9	118
6	2.1	117
7	2.2	116
8	2.2	115
1	1.8	113
2	1.5	114
3	1.6	114
4	1.6	114
5	2.1	114
6	2.2	113
7	2.2	113
8	2.1	113
$\sqrt{\Delta P} = 1.3305$		$T_s = 120$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times) + (0.32 \times) + (0.28 \times)$$

$$M_d = 28.84$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = () \times (1 - \frac{ }{100}) + 18 (\frac{ }{100})$$

$$M_s = 28.73 \quad 28.71 \quad RK$$

$$T_s = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_a = P_b + \frac{S.P.}{13.6} = () + - 13.6$$

$$P_s = 29.78 \text{ in. Hg}$$

$$\sqrt{\Delta P} = 1.3305$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times () \times () \times \sqrt{ }$$

$$V_s = 79.339 \text{ ft/s}$$

$$A_s = \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \times \times 60$$

$$Q_s = 606,547 \text{ acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \times 17.647 \times \times (1 - \frac{ }{100})$$

$$Q_{s, \text{std}} = 534,879 \text{ acfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KES Date: 5/12/00
Sampling Location: BARHOUSE INLET Clock Time: 0630
Run #: 2A operators: GC/TC/TW
Barometric Pressure, in. Hg: 29.45 Static Pressure, in. H₂O: +5.2
Moisture, %: Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.9
Stack Dimension, in. Diameter or Side 1: 139 Side 2: 132
Wet Bulb, °F: Dry Bulb, °F:

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
1	1.6	254.8
2	1.1	254.8
3	1.7	260.1
4	1.9	258.6
5	2.0	246.3
6	1.9	227.8
7	2.1	205.7
8	2.1	185.7
1	1.1	179.1
2	1.1	193.7
3	1.6	204.3
4	1.7	207.0
5	1.8	201.9
6	2.0	191.7
7	2.1	178.7
8	2.1	164.4
1	1.1	156.8
2	1.3	178.3
3	1.7	188.5
4	1.7	186.1
5	1.8	176.1
6	1.9	166.9
7	2.2	151.3
8	2.1	146.5
$\overline{\Delta P} = 1.3372$		$\overline{T_s} = 168$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d =$$

$$M_s = M_d \times \left(1 - \frac{\%H_2O}{100}\right) + 18 \left(\frac{\%H_2O}{100}\right)$$

$$M_s = (\quad) \times \left(1 - \frac{\quad}{100}\right) + 18 \left(\frac{\quad}{100}\right)$$

$$M_s =$$

$$T_s = \quad ^\circ F = \quad ^\circ R \quad (^\circ F + 460)$$

$$P_a = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = \quad \text{in. Hg}$$

$$\overline{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\overline{\Delta P}} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s \text{ std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times \left(1 - \frac{\%H_2O}{100}\right)$$

$$Q_{s \text{ std}} = \quad \times 17.647 \times \quad \times \left(1 - \frac{\quad}{100}\right)$$

$$Q_{s \text{ std}} = \quad \text{dscfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KES Date: 5/12/00
Sampling Location: BAGHOUSE INLET Clock Time: 0630
Run #: 2A Operators: GA/TA/TW
Barometric Pressure, in. Hg: 29.45 Static Pressure, in. H₂O: +5.2
Moisture, %: _____ Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
Stack Dimension, in. Diameter or Side 1: 139 Side 2: 132
Wet Bulb, °F: _____ Dry Bulb, °F: _____

Traverse Point Number	Velocity Head h. H ₂ O	Stack Temp. °F
1	1.9	150.6
2	1.8	160.0
3	1.6	166.1
4	1.7	166.3
5	1.7	160.0
6	1.8	148.9
7	2.1	143.3
8	2.1	137.7
1	2.0	130.5
2	1.7	131.3
3	1.6	131.2
4	1.5	131.4
5	2.0	131.2
6	2.1	130.9
7	2.3	129.3
8	2.2	127.6
1	1.9	125.0
2	1.5	125.8
3	1.6	126.1
4	1.7	126.5
5	1.9	126.7
6	2.1	126.6
7	2.1	126.3
8	1.9	125.9
$\sqrt{\Delta P}$ =		T_s =

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d = 28.84$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s = 1$$

$$T_s = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.8} = (\quad) + \frac{\quad}{13.8}$$

$$P_s = 29.83 \text{ in. Hg}$$

$$\sqrt{\Delta P} = 1.3372$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s \text{ std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s \text{ std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s \text{ std}} = \quad \text{dscfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KES Date: 5/12/00
Sampling Location: BT-3 BARNHOUSE INLET Clock Time: 1050
Run #: BT-28/3A Operators: TG/GG/TW
Barometric Pressure, in. Hg: 29.45 Static Pressure, in. H₂O: _____
Moisture, %: 1 Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
Stack Dimension, in. Diameter or Side 1: 139" Side 2: 132"
Wet Bulb, °F: --- Dry Bulb, °F: ---

Traverse Point Number	Velocity in. H ₂ O	Stack Temp. °F
A 1	1.0	147.4
2	1.2	147.9
3	1.4	148.2
4	1.7	147.6
5	1.9	146.7
6	2.0	145.7
7	2.1	143.4
8	2.1	140.4
B 1	1.2	155.2
2	1.1	159.3
3	1.5	166.7
4	1.8	168.1
5	1.8	165.2
6	1.9	158.2
7	2.1	150.3
8	2.1	143.6
C 1	1.7	142.6
2	1.4	161.4
3	1.6	170.9
4	1.6	171.6
5	1.7	165.5
6	2.0	157.0
7	2.2	150.5
8	1.7	147.3
$\sqrt{\Delta P} =$		$T_s =$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d =$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s =$$

$$T_s = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = \quad \text{in. Hg}$$

$$\sqrt{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s, \text{std}} = \quad \text{dscfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KES Date: 5/12/00
 Sampling Location: BARHOUSE INLET Clock Time: 1050
 Run #: BI-2B/3A Operators: GG/TG/TW
 Barometric Pressure, in. Hg: 29.45 Static Pressure, in. H₂O: +4.5
 Moisture, %: _____ Molecular wt., Dry: 28.84 Pitot Tube. Cp: 0.84
 Stack Dimension, in. Diameter or Side 1: 139 Side 2: 132
 Wet Bulb, °F: _____ Dry Bulb, °F: _____

Traverse Point Numkr	Velocity Head in. H ₂ O	Shck Tamp. °F
1	2.0	147.0
2	1.7	152.7
3	1.7	153.7
4	1.6	153.7
5	1.8	149.8
6	1.8	146.0
7	2.2	143.3
8	2.3	138.8
1	1.8	134.2
2	1.9	135.0
3	1.5	135.1
4	1.6	135.7
5	1.9	136.9
6	2.1	136.4
7	2.9	134.7
8	2.3	137.1
1	1.6	130.2
2	1.5	130.2
3	1.8	130.3
4	2.0	130.7
5	2.3	130.5
6	2.4	130.4
7	2.8	130.0
8	2.3	129.9
$\overline{\Delta P} = 1.3596$		$T_s = 146$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times) + (0.32 \times) + (0.28 \times)$$

$$M_d =$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = () \times (1 - \frac{ }{100}) + 18 (\frac{ }{100})$$

$$M_s =$$

$$T_s = \text{°F} = \text{°R} (\text{°F} + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = () + \frac{ }{13.6}$$

$$P_s = 29.45 \text{ in. Hg}$$

$$\sqrt{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (\text{°R})}{P_s \times M_s}}$$

$$V_s = 85.49 \times () \times () \times \sqrt{ }$$

$$V_s = 81.92 \text{ ft/s}$$

$$A_s = \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \text{ } \times \text{ } \times 60$$

$$Q_s = 6263.2 \text{ acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \text{ } \times 17.647 \times \text{ } \times (1 - \frac{ }{100})$$

$$Q_{s, \text{std}} = 5377.28 \text{ dscfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KES Date: 5/12/00
Sampling Location: BANKSIDE INLET Clock Time: 1619
Run #: RI-3B Operators: GG/TC/TM
Barometric Pressure, in. Hg: 29.45 Static Pressure, in. H₂O: +4.6
Moisture, %: _____ Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
Stack Dimension, in. Diameter or Side 1: 139 Side 2: 132
Wet Bulb, °F: _____ Dry Bulb, °F: _____

Traverse Point Number	Velocity Head in. H ₂ O	Stack Temp. °F
A 1	1.3	233.4
2	0.98	232.7
3	1.6	232.6
4	1.7	232.6
5	1.9	228.7
6	1.8	217.0
7	2.1	203.3
8	2.0	193.1
B 1	1.1	214.5
2	1.1	219.9
3	1.6	224.3
4	1.6	223.0
5	1.7	211.0
6	1.7	197.9
7	2.2	185.9
8	2.0	177.8
C 1	1.3	219.8
2	1.3	235.2
3	1.5	240.2
4	1.4	233.1
5	1.5	218.9
6	1.7	206.2
7	2.0	194.1
8	2.0	188.4
$\overline{\Delta P} = 1.2915$		$\overline{T_s} = 191$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d =$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s =$$

$$\overline{T_s} = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = \quad \text{in. Hg}$$

$$\overline{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \overline{\Delta P} \times \sqrt{\frac{\overline{T_s} (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{scfm}$$

$$Q_{s_{std}} = Q_s \times 17.647 \times \frac{P_s}{\overline{T_s}} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s_{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s_{std}} = \quad \text{dscfm}$$



GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: KES Date: 5/12/00
Sampling Location: KES BATHHOUSE INLET Clock Time: 4:16:19
Run #: BI-3B Operators: GC/TG/TW
Barometric Pressure, in. Hg: 29.45 Static Pressure, in. H₂O: +4.6
Moisture, %: _____ Molecular wt., Dry: 28.84 Pitot Tube, Cp: 0.84
Stack Dimension, in. Diameter or Side 1: 139" Side 2: 132"
Wet Bulb, °F: _____ Dry Bulb, °F: _____

Traverse Point Number	Velocity Head In. H ₂ O	Stack Temp. °F
1	1.9	184.5
2	1.5	189.3
3	1.5	188.4
4	1.4	189.0
5	1.6	185.2
6	1.6	181.1
7	2.0	175.2
8	2.1	170.0
1	1.8	168.7
2	1.5	166.8
3	1.4	167.5
4	1.6	167.9
5	1.9	167.4
6	2.0	165.4
7	2.1	162.6
8	2.1	161.0
1	1.6	155.4
2	1.2	155.1
3	1.4	154.8
4	1.5	154.5
5	1.9	154.6
6	2.0	154.5
7	2.2	154.1
8	1.9	153.6
	$\sqrt{\Delta P} =$	$T_s =$

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$M_d = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

$$M_d =$$

$$M_s = M_d \times (1 - \frac{\%H_2O}{100}) + 18 (\frac{\%H_2O}{100})$$

$$M_s = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_s =$$

$$T_s = \quad ^\circ F = \quad ^\circ R (^\circ F + 460)$$

$$P_s = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.6}$$

$$P_s = \quad \text{in. Hg}$$

$$\sqrt{\Delta P} =$$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^\circ R)}{P_s \times M_s}}$$

$$V_s = 85.49 \times (\quad) \times (\quad) \times \sqrt{\quad}$$

$$V_s = \quad \text{ft/s}$$

$$A_s = \quad \text{ft}^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$$Q_s = \quad \times \quad \times 60$$

$$Q_s = \quad \text{acfm}$$

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times (1 - \frac{\%H_2O}{100})$$

$$Q_{s, \text{std}} = \quad \times 17.647 \times \quad \times (1 - \frac{\quad}{100})$$

$$Q_{s, \text{std}} = \quad \text{dscfm}$$



PACIFIC ENVIRONMENTAL SERVICES, INC.

Project No. 5700.000		Page of	
Client KES / Equi			
Location Ashland, Kentucky			
Prepared By RWH	Date 5/10/00	Checked By DA	Sheet Title Nozzle Calculation

Prelim 5/10/00

Total Bayhouse inlet, acfm = 612,821 acfm

$$\frac{612,821 \text{ acfm}}{538 \text{ ft}^2 \times 60} = 1.898 \text{ feet/second}$$

$$1.898 \text{ fps} = 85.49 \times .84 \times \sqrt{\Delta P} \sqrt{\frac{618.92}{28.73 \times 29.81}}$$

$$\left(\frac{1.898}{85.49 \times .84 \times 0.8495} \right)^2 = (0.031113)^2 = 0.000968 = \Delta P$$

$$M. Box \Delta T = 1.721$$

1.100" Nozzle (used 1.050")
160° F static

5/11/00

Total Bayhouse inlet, acfm = 623,962 acfm

$$\frac{623,962 \text{ acfm}}{538 \text{ ft}^2 \times 60} = 1.933 \text{ fps}$$

$$1.933 \text{ fps} = 85.49 \times .84 \times \sqrt{\Delta P} \sqrt{\frac{602}{28.73 \times 29.87}}$$

$$\left(\frac{1.933 \text{ fps}}{85.49 \times .84 \times 0.8362} \right)^2 = (0.03219)^2 = 0.001036 \Delta P$$



PACIFIC ENVIRONMENTAL SERVICES, INC.

Project No.	4700,000	Page	of
Client			
Location			

Prepared By	Date	Checked By	Date	Sheet Title
nle	5/12	DA		

Kingman Inlet action = 606,547

$$\frac{606,547}{5381 \times 60} = 1.879 \text{ fps}$$

$$1.879 = 85.49 \times .84 \times \sqrt{\Delta P} \sqrt{\frac{510}{28.73 \times 29.78}}$$

↓
0.8304

$$\left(\frac{1.879}{85.49 \times .84 \times 0.8304} \right)^2 = \left(0.0315097 \right)^2 = 0.000993 \text{ L.P.}$$

Fun down at 0000...
waiting on replacement!

FIELD DATA SHEET

K = 101...
K = 1231.7

Plant: KES
Sampling Location: Highway
Run Number: B0-1 Date: 5/11/00
Pretest Leak Rate: 0.002 cfm @ 12 in. Hg.
Pretest Leak Check: Pitot: ✓ Orsat: 118.747

Sample Type: Part. Operator: TW/A
Pbar: 29.60 Ps: - .10
CO2: 0 O2: 21
Probe Length/Type: 2' Glass Pitot #:
Stack Diameter: AS:

Nozzle ID: 000 Thermocouple #:
Assumed Bws: 1 Filter #: 300 304
Meter Box #: 2 Y: 0.988 ΔH: 1.74
Post-Test Leak Rate: cfm @ in. Hg.
Post-Test Leak Check: Pitot: Orsat:

Traverse Point Number	Sampling Time (min)	Clock Time (24-hour clock)	Gas Meter Reading (Vn) ft ³	Velocity Head (Δp) In H2O	Orifice Pressure Differential (ΔH) in H2O		Stack Temp. (Ts)	Temperature °F		Impinger Temp. °F (4)	Dry Gas Meter Temp.		Pump Vacuum (in. Hg)
					Desired	Actual		Probe	Filter		Inlet (Tm in °F)	Outlet (Tm out °F)	
0 →	0	1355	117.628										
1	7.5	1402		0.000968	0.98	0.95	121	256	257	67	82	82	18
2	15.0	1400	126.565	0.001036	0.98	0.95	123	256	253	65	83	84	18
3	22.5	1402	133.545	0.001036	0.98	1.00	127	256	230	73	90	87	1
4	30.0	1507	137.628	0.001036	0.97	0.97	137	258	252	73	91	88	1
5	37.5	1515	142.204	0.001036	0.96	0.96	140	258	253	74	92	89	1
6	45.0	1522	146.41	0.001036	0.97	0.97	139	257	251	73	94	90	1
7	52.5	1530	150.91	0.001036	0.97	0.97	138	257	255	71	95	91	1
8	60.0	1537	155.22	0.001036	0.97	0.97	136	257	253	71	95	91	1
5-1	107.5	1545	159.77	0.001036	0.96	0.96	145	258	253	75	96	92	1
2	115.0	1552	163.88	0.001036	0.95	0.95	153	258	254	77	97	92	1
3	122.5	1560	168.34	0.001036	0.94	0.94	156	257	252	81	96	92	1
4	130.0	1607	172.69	0.001036	0.93	0.93	169	257	253	78	97	93	1
5	137.5	1615	176.99	0.001036	0.93	0.93	169	257	254	76	97	92	1
6	145.0	1622	181.34	0.001036	0.93	0.93	164	258	253	78	98	93	1
7	152.5	1630	185.67	0.001036	0.96	0.96	150	258	252	77	97	94	1
8	200.0	1637	190.05	0.001036	0.90	0.98	139	258	255	77	98	94	1
4-1	207.5	1645	194.49	0.001036	0.98	0.98	135	257	250	76	98	94	1
2	215.0	1652	198.99	0.001036	0.93	0.93	167	258	254	76	97	94	1
3	222.5	1700	203.23	0.001036	0.93	0.93	165	258	254	78	98	94	1
4	230.0	1708	207.55	0.001036	0.92	0.92	174	257	253	82	97	94	1
5	237.5	1715	211.88	0.001036	0.93	0.93	169	256	252	84	97	94	1
6	245.0	1722	216.21	0.001036	0.95	0.95	150	258	254	73	96	93	1
7	252.5	1730	220.58	0.001036	0.95	0.95	155	257	253	73	94	96	1
8	300.0	1737	224.62	0.001036	0.94	0.94	159	257	254	72	97	94	1
3-1	307.5	1745	229.44	0.001036	0.99	1.00	127	258	252	72	97	93	1

Compt #20
* stopped
shortened
unofficial
and
started at
0 12697069
stop @
1443
12060000
start @
1452
13020000
@ comparison
6

-3.744

Bws = 1.2
ΔVn = Δp = 0.03219 ΔH = Ts = Tm =
avg Δp = 0.001036

FIELD DATA SHEET

Plant:

Sampling Location: BAGHD USE DORET
Run Number: B - 1 Date: 5/11/00

Pretest Leak Rate: 0.002 cfm @ 1/2 in. Hg.

Pretest Leak Check: Pitot: Orsat:

Sample Type: PART. Operator: DS/BK

Pbar: 29.6 Ps: -0.10

CO2: 0 02: 21

Probe Length/Type: _____ Pilot #: _____

Stack Diameter: _____ As: _____

Nozzle ID: 1-000 Thermocouple #:

Assumed Bws: 1 Filter #: 300307

Meter Box #: 2 Y: 0988ΔH@: 174

Post-Test Leak Rate: 0.002 cfm @ 20 in. Hg.

Post-Test Leak Check: Pitot: _____ Orsat: _____

Comp 3

2

Vol. 99
10.

2523

7

Traverse Point Number	Sampling Time (min)	Clock Time (24-hour clock)	Gas Meter Reading (Nm) ft ³	Velocity Head (Δp) In H ₂ O	Orifice Pressure Differential (ΔH) in H ₂ O		Stack Temp. (T _s)	Temperature °F		Impinger Temp. °F	Dry Gas Meter Temp.		Pump Vacuum (in. Hg)
					Desired	Actual		Probe	Filter		Inlet (T _{in} in °F)	Outlet (T _{out} in °F)	
2	315	1752											
1	↓	↓	233.69	0.001036	0.99	0.99	127	257	253	72	98	94	1
2	325	1800	238.15	0.001036	0.98	0.98	133	258	252	74	98	94	1
3	330	1807	242.43	0.001036	0.99	0.99	128	256	252	77	98	94	1
4	338	1815	247.44	0.001036	0.99	0.99	129	256	256	77	98	94	1
5	345	1822	251.51	0.001036	0.97	0.97	140	257	254	81	98	94	1
6	352.5	1830	256.50	0.001036	0.95	0.95	152	258	253	78	98	94	1
7	400.0	1837	260.62	0.001036	0.95	0.95	157	257	252	80	99	95	1
8	407.5	1845	265.28	0.001036	0.96	0.96	151	256	253	80	99	94	1
9	415.0	1900	269.24	0.001036	0.97	0.97	145	257	256	80	99	96	1
10	422.5	1907	273.62	0.001036	0.97	0.97	143	257	253	79	100	96	1
11	430.0	1915	278.08	0.001036	0.99	0.99	130	258	253	79	99	95	1
12	437.5	1922	282.53	0.001036	0.98	0.98	138	257	254	80	98	95	1
13	445.0	1930	286.98	0.001036	0.95	0.95	156	256	251	74	97	94	1
14	452.5	1937	291.39	0.001036	0.96	0.96	147	258	253	75	95	93	1
15	5:00.0	1945	295.810	0.001036	0.96	0.96	140	259	253	78	94	93	1

177.063-
3.744

$$\begin{array}{r} 0.9 \\ 0.9 \end{array}$$
$$\overline{T}_B = 146$$

94



SAMPLE RECOVERY DATA

PLANT KENT. EL Steel Run No. BD-1
DATE 5/11/00 Sample Box No. N-4 Job No. 5700.000
SAMPLE LOCATION Bag House Outlet Filter No. 300304

TRAIN PREPARER AN

SAMPLE RECOVERY PERSON Gray

COMMENTS Very light loading

FRONT HALF

Acetone Liquid
Container No. _____ Level Marked _____ Sealed _____

Filter
Container No. _____ Sealed _____

Description of Filter _____

Samples Stored and Locked _____

Container No. _____

Liquid Level Marked _____ Sealed _____

IMP. NO.	CONTENTS	INITIAL VOL (ml)	WEIGHT (grams)		
			INITIAL	FINAL	NET
1	DI WATER	100	697.4	698.1	.7
2	DI WATER	100	714.5	720.4	5.9
3	—	—	615.2	618.4	3.2
4	Silica Gel	250	752.7	796.4	337
5					
6					
TOTAL			a 779.8	2823.3	43.5

FIELD DATA SHEET

K = 2415.8

Plant: KES Sample Type: Paint Operator: alc Nozzle ID: 1.240 Thermocouple #: 219
 Sampling Location: Englewood Pbar: 26.43 Ps: -0.1 Assumed Bws: 1 Filter #: 30382
 Run Number: 60-2 Date: 9/16/00 CO2: 0 O2: 2.1 Meter Box #: 2 Y: 988 ΔH@: 1.72
 Pretest Leak Rate: 0.002 cfm @ 15 in. Hg. Post-Test Leak Rate: cfm @ in. Hg.
 Pretest Leak Check: Pitot: NA Orsat: alc Stack Diameter: 102 As: Pitot #: 21
 Stack Temperature: °F Impinger Temp: °F Dry Gas Meter Temp: °F

Traverse Point Number	Sampling Time (min)	Clock Time (24-hour clock)	Gas Meter Reading (Nm) ft ³	Velocity Head (Δp) in H ₂ O	Orifice Pressure Differential (ΔH) in H ₂ O		Stack Temp. (T _s)	Temperature °F		Impinger Temp. °F	Dry Gas Meter Temp.		Pump Vacuum (in. Hg)
					Desired	Actual		Probe	Filter		Inlet (T _m in °F)	Outlet (T _m out °F)	
0	0	0715	296.400										
1	7.1	0722	303.604	0.000993	2.1	2.1	146	252	252	83	78	78	3
2	15.1	0730	309.72	0.000993	2.1	2.1	147	256	251	80	82	79	3
3	23.1	0737	315.88	0.000993	2.2	2.2	143	254	252	80	83	80	3
4	31.1	0745	322.01	0.000993	2.1	2.1	140	256	250	80	84	81	3
5	39.1	0752	328.12	0.000993	2.1	2.1	154	256	253	80	87	82	3
6	47.1	0800	334.26	0.000993	2.1	2.1	150	255	252	80	87	82	3
7	55.1	0807	340.36	0.000993	2.1	2.1	151	256	251	80	89	82	3
8	63.1	0815	346.22	0.000993	2.1	2.1	153	256	251	80	89	84	3
9	71.1	0823	351.99	0.000993	2.1	2.1	157	256	250	78	90	84	3
10	79.1	0830	358.37	0.000993	2.1	2.1	158	256	252	79	90	84	3
11	87.1	0837	364.53	0.000993	2.1	2.1	157	256	251	80	90	85	3
12	95.1	0845	371.22	0.000993	2.1	2.1	167	256	251	80	91	86	3
13	103.1	0852	376.74	0.000993	2.1	2.1	159	255	251	85	91	86	3
14	111.1	0905	382.34	0.000993	2.1	2.1	156	257	250	85	91	86	3
15	119.1	0912	388.51	0.000993	2.1	2.1	156	256	253	82	91	86	3
16	127.1	0920	394.49	0.000993	2.1	2.1	166	256	252	79	92	87	3
17	135.1	0927	400.55	0.000993	2.1	2.1	172	256	252	80	92	86	3
18	143.1	0935	406.71	0.000993	2.1	2.1	177	257	251	85	93	88	3
19	151.1	0942	413.32	0.000993	2.1	2.1	183	256	251	87	92	87	3
20	159.1	0950	418.10	0.000993	2.0	2.0	190	256	252	90	93	89	3
21	167.1	0958	424.65	0.000993	2.0	2.0	193	257	252	95	93	88	3
22	175.1	1005	430.02	0.000993	2.1	2.1	180	257	252	100	93	88	3
23	183.1	1012	436.49	0.000993	2.1	2.1	172	256	253	95	94	90	3
24	191.1	1020	443.98	0.000993	2.1	2.1	175	256	251	88	95	90	3

UMP 10

UMP 9

STOP -
372.37
initial leak

UMP 13

*
KESSIE
SNACK
TEMP. 7
PITOT 9.17
BAG WASTE

ΔV_m = $\sqrt{\Delta p}$ = ΔH = T_s = T_m =

FIELD DATA SHEET

Plant: KCS

Sampling Location: REGHOUSE OUTLET
Run Number: 602 Date: 5/12/05
Pretest Leak Rate: 0.002 cfm @ 15 in. Hg
Pretest Leak Check: Pilot: Y/N Orsat: N/A

Sample Type: REG. Operator: RK/m
Pbar: 29.45 Ps: -0.1
CO2: 0 O2: 21
Probe Length/Type: 2' WSS Pilot #: 2 M
Stack Diameter: 5381 ft² As:

Nozzle ID: 1240 Thermocouple #: 2 M
Assumed Bws: 1 Filter #: 500382
Meter Box #: 2 Y: .983 ΔH@: 1.72
Post-Test Leak Rate: .001 cfm @ 5 in. Hg
Post-Test Leak Check: Pilot: N/A Orsat: N/A

Traverse	Point	Sampling Time (min)	Clock Time (24-hour)	Gas Meter Reading (Nm ³)	Velocity Head (Δp) in H2O	Office Pressure Differential (ΔH) in H2O	Actual	Stack Temp. (T _s)	Temperature of Probe	Filter	Impinger Temp. of	Dry Gas Meter Temp. Inlet (T _m in° F)	Outlet (T _m out° F)	Pump Vacuum (in. Hg)
----------	-------	---------------------	----------------------	--------------------------------------	---------------------------	--	--------	-------------------------------	----------------------	--------	-------------------	--	--------------------------------	----------------------

1		3:01:30	1027	449.04	0.000993	2.1	2.1	170	257	258	90	94	90	3
2		3:15:00	1035	455.54	0.000993	2.1	2.1	164	254	254	82	95	91	3
3		3:22:30	1042	461.59	0.000993	2.1	2.1	165	251	253	75	95	92	3
4		3:30:00	1050	468.4	0.000993	2.2	2.2	157	257	253	74	95	91	3
5		3:37:30	1057	474.45	0.000993	2.2	2.2	147	257	253	72	95	92	3
6		3:45:00	1105	480.91	0.000993	2.2	2.2	145	252	523	74	95	91	3
7		3:52:30	1112	487.37	0.000993	2.2	2.2	157	257	252	80	95	91	3
8		4:00:00	1120	493.79	0.000993	2.1	2.1	162	256	253	83	95	92	3

14 cmf

ΔV_m = 197.399 Δp = 0.0315 ΔH = 2.11 T_s = 162 T_m = 89



SAMPLE RECOVERY DATA

PLANT KES Run No. B0-2
DATE 5/12/00 Sample Box No. N-3 Job No. 5700.000
SAMPLE LOCATION Baghouse Outlet Filter No. 200.382
TRAIN PREPARER AH
SAMPLE RECOVERY PERSON G. Gay
COMMENTS Clear

FRONT HALF

Acetone Liquid
Container No. _____ Level Marked _____ Sealed _____
Filter
Container No. _____ Sealed _____
Description of Filter _____

Samples Stored and Locked _____

BACK HALF/MOISTURE

Container No. _____
Liquid Level Marked _____ Sealed _____

IMP. NO.	CONTENTS	INITIAL VOL (ml)	WEIGHT (grams)		
			INITIAL	FINAL	NET
1	DI WATER	100	657.5	692.4	34.9
2	DI WATER	100	628.7	653.0	24.3
3	—	—	510.8	515.6	4.8
4	Silica Gel	250	768.4	805.5	37.1
5					
6					
TOTAL			2566.4	2666.5	100.1

K=2391.1

FIELD DATA SHEET

Plant: KES Sample Type: Leak Operator: TW/KE Nozzle ID: 1.240 Thermocouple #: 2m
 Sampling Location: Boymise Outlet Pbar: 29.45 Psi: -0.1 Assumed Bws: 1 Filler #: 300251
 Run Number: 603 Date: 5/12/00 CO2: 0 O2: 21 Meter Box #: 2 Y: 0.980 ΔH@: 1.721
 Pretest Leak Rate: 0.003 cfm @ 15 in. Hg. Post-Test Leak Rate: 0.03 cfm @ 5 in. Hg.
 Pretest Leak Check: Pilot: — Orsat: — Post-Test Leak Check: Pilot: NH Orsat: W1

Traverse Point Number	Sampling Time (min)	Clock Time (24-hour clock)	Gas Meter Reading (Nm) ft ³	Velocity Head (Δp) in H ₂ O	Orifice Pressure Differential (ΔH) in H ₂ O		Stack Temp. (Ts)	Temperature °F		Impinger Temp. °F	Dry Gas Meter Temp. (Tm in/°F)		Pump Vacuum (in. Hg)
					Desired	Actual		Probe	Filler		Inlet	Outlet	
0	0	1210	494.320										
1	7.5	1225	499.87	0.000763	1.66	1.66	145	257	252	65	90	90	2
2	15.0	1232	505.51	0.000763	1.62	1.62	160	257	252	72	92	90	2
3	22.5	1240	511.15	0.000763	1.61	1.7	167	257	252	76	93	91	2
4	30.0	1248	516.74	0.000763	1.60	1.6	172	257	254	79	95	91	2
5	37.5	1255	521.55	0.000763	1.61	1.7	169	258	254	70	95	92	2
6	45.0	1303	527.85	0.000763	1.59	1.6	174	258	255	66	95	92	2
7	52.5	1310	533.41	0.000763	1.61	1.7	168	258	254	67	96	92	2
8	60.0	1318	539.96	0.000763	1.62	1.7	162	256	254	68	96	92	2
9	1:07:30	1325	544.74	0.000763	1.62	1.7	165	258	255	73	98	92	2
10	1:15:00	1333	550.17	0.000763	1.64	1.6	160	258	254	72	98	94	2
11	1:22:30	1340	555.81	0.000763	1.63	1.7	156	257	253	75	99	93	2
12	1:30:00	1348	561.33	0.000763	1.63	1.6	164	257	254	75	98	95	2
13	1:37:30	1355	566.89	0.000763	1.64	1.6	161	257	254	75	99	95	2
14	1:45:00	1403	572.57	0.000763	1.64	1.6	159	258	254	75	99	96	2
15	1:52:30	1410	577.86	0.000763	1.64	1.6	160	256	251	77	100	95	2
16	2:00:00	1418	583.41	0.000763	1.63	1.6	164	256	254	66	100	95	2
17	2:07:30	1425	588.96	0.000763	1.62	1.6	175	258	252	64	100	97	2
18	2:15:00	1433	594.51	0.000763	1.59	1.6	180	258	254	70	101	97	2
19	2:22:30	1440	600.06	0.000763	1.60	1.6	177	257	253	73	100	97	2
20	2:30:00	1448	605.64	0.000763	1.61	1.6	175	256	252	75	101	97	2
21	2:37:30	1455	611.22	0.000763	1.60	1.6	177	257	252	82	102	97	2
22	2:45:00	1503	616.78	0.000763	1.61	1.6	175	257	253	83	103	98	2
23	2:52:30	1510	622.41	0.000763	1.61	1.6	175	258	254	83	102	98	2
24	3:00:00	1518	627.92	0.000763	1.62	1.6	171	257	254	77	102	98	2

Comp 18

Comp 17

Comp 19

 $\Delta Vm = 0.02162$
 $\Delta H = 1.62$
 $Tm = 97$

FIELD DATA SHEET

FIELD DATA SHEET

Pretest Leak Check: Pitot: — Orsat: —

Pretest Leak Check: Pitot: — Orsat: —

Pretest Leak Check: Pitot: — Orsat: —

Pretest Leak Check: Pitot: — Orsat: —

Prestab Leak Check:	—	Orgat:	—
Stack Diameter:	—		

Pretest Leak Check: Pitot: — Orsat: —
Stack Diameter: —

Pretest Leak Check: Pitot: — Orsat: —
Stack Diameter: — As: —

Pretest Leak Check: Pitot: — Orgat: —
Stack Diameter: As:

Pretest Leak Check: Pitot: — Orsat: —
Slack Diameter: — As: —

Pretest Leak Check: Pilot: — Orgat: — Stack Diameter: As: Post-Test

Pretest Leak Check: Pitot: — Orgat: —
Stack Diameter: As: Post-Test Leak C

Pretest Leak Check: — Orsat: —
 Stack Diameter: As:
 Post-Test Leak Check: —

Pretest Leak Check: Pilot: As:
 Stack Diameter: Post-Test Leak Check: Pilot:

Pretest Leak Check: Pilot: As:
 Stack Diameter:
 Post-Test Leak Check: Pilot: As:

Pretest Leak Check: Pilot: _____ Orsal: _____
 Stack Diameter: _____ As: _____
 Post-Test Leak Check: Pilot: _____ Orsal: _____

Traverse Point Number	Sampling Time (min)	Clock Time (24-hour clock)	Gas Meter Reading (Nm ³)	Velocity Head (Δp) in H ₂ O	Orifice Pressure Differential (ΔH) in H ₂ O		Stack Temp. (T _s)	Temperature °F		Impinger Temp. °F	Dry Gas Meter Temp.		Pump Vacuum (in. Hg)
					Desired	Actual		Probe	Filter		Inlet (T _m in °F)	Outlet (T _m out °F)	
			627.92										
1	3:01:30	1525	623.48	0.000763	1.61	1.6	175	258	254	75	104	98	2
2	3:15:00	1533	639.03	0.000763	1.60	1.6	179	257	255	76	104	99	2
3	3:22:30	1540	644.57	0.000763	1.62	1.6	171	258	253	80	104	99	2
4	3:30:00	1548	650.19	0.000762	1.62	1.6	170	256	251	85	103	99	2
5	3:31:30	1555	655.62	0.000762	1.63	1.6	169	257	253	86	102	99	2
6	3:45:00	1603	661.45	0.000762	1.61	1.6	175	258	254	72	103	99	2
7	3:52:30	1610	666.7	0.000762	1.63	1.6	169	256	252	69	103	99	2
8	4:00:00	1618	672.67	0.000763	1.63	1.6	169	252	251	72	104	100	2

$\Delta v_{\text{m}} =$	$\bar{r} =$	$\bar{T}_8 =$
178.352	0.02762	168

$$\overline{Im} = 97$$



SAMPLE RECOVERY DATA

PLANT Kentucky Electric Steel Run No. 60-3
DATE 5/12/60 Sample Box No. N-7 Job No. 5700.000
SAMPLE LOCATION Bayhouse Outlet Filter No. 300251
TRAIN PREPARER AH
SAMPLE RECOVERY PERSON _____
COMMENTS Particulate iron

FRONT HALF

Acetone Liquid
Container No. _____ Level Marked _____ Sealed _____

Filter
Container No. _____ Sealed _____

Description of Filter _____

Samples Stored and Locked _____

BACK HALF/MOISTURE

Container No. _____

Liquid Level Marked _____ Sealed _____

IMP. NO.	CONTENTS	INITIAL VOL (ml)	WEIGHT (grams)		
			INITIAL	FINAL	NET
1	DI WATER	100	659.5	692.1	32.6
2	DI WATER	100	689.1	714.8	25.7
3	—	—	582.4	585.8	3.4
4	Silica gel	250	705.3	736.6	31.3
5					
6					
TOTAL			2626.3	2729.3	93.0

☐ ☐ ☐
☐ ☐ ☐
☐ ☐ ☐

NAME: KES

PROJECT NUMBER: 5700-000

PROJECT MANAGER: R. Kolde

PROJECT DATE: 5-12-00

METHOD: M5

NUMBER OF SITES: 1

[illegible]



PROJECT ANALYTICAL SHEET

SITE: _____ RUN NO.: 130-1

FILTER NO.: 300304 I.D. NO.: 00-511

FINAL MASS: _____ TARE MASS: 351.95

DATE/TIME	NAME	MASS
#1 <u>5/23 0724</u>	<u>AH</u>	<u>356.0</u>
#2 <u>5/23 1500</u>	<u>AH</u>	<u>355.7</u> ↓
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 355.85

NET GAIN: 3.9 375

F/H BEAKER NO.: 2028 I.D. NO.: 00-512

FINAL MASS: _____ TARE MASS: 108441.4

DATE/TIME	NAME	MASS
#1 <u>5/23 0724</u>	<u>AH</u>	<u>108,450.5</u>
#2 <u>5/23 1502</u>	<u>AH</u>	<u>108,450.0</u> *
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 108,450.25

NET GAIN: 8.85 806


B/H BEAKER NO.: 2011 I.D. NO.: 00-5-13

FINAL MASS: _____ TARE MASS: 110701.6

DATE/TIME	NAME	MASS
#1 <u>5/24/00 1620</u>	<u>DA</u>	<u>110710.8</u>
#2 <u>5/25/00 820</u>	<u>DA</u>	<u>110710.4</u> *
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 110710.6

NET GAIN: 9.0 8.8



PROJECT ANALYTICAL SHEET

SITE: _____ RUN NO.: 1302

FILTER NO.: 300382 I.D. NO.: 00-514

FINAL MASS: _____ TARE MASS: 351.45

DATE/TIME	NAME	MASS
#1 <u>5/23 0726</u>	<u>AH</u>	<u>367.2</u>
#2 <u>5/23 1501</u>	<u>AH</u>	<u>361.8</u>
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 362.0

NET GAIN: 10.55 10.35

F/H BEAKER NO.: 2037 I.D. NO.: 00-515

FINAL MASS: _____ TARE MASS: 107717.75

DATE/TIME	NAME	MASS
#1 <u>5/23 0726</u>	<u>AH</u>	<u>107,725.3</u>
#2 <u>5/23 1501</u>	<u>AH</u>	<u>107,724.8</u> ★
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 107,725.05

NET GAIN: 7.3 7.05

B/H BEAKER NO.: 2005 I.D. NO.: 00-516

FINAL MASS: _____ TARE MASS: 105952.05

DATE/TIME	NAME	MASS
#1 <u>5/24/00 1620</u>	<u>DA</u>	<u>105960.08</u> 4
#2 <u>5/25/00 820</u>	<u>DA</u>	<u>105960.10</u> ★
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 105960.2

NET GAIN: 8.15 7.95



PROJECT ANALYTICAL SHEET

SITE: _____ RUN NO.: 130-3

FILTER NO.: 300251 I.D. NO.: 00-517

FINAL MASS: _____ TARE MASS: 250.55

DATE/TIME	NAME	MASS
#1 <u>5/23 0727</u>	<u>AH</u>	<u>352.0</u>
#2 <u>5/23 1501</u>	<u>AH</u>	<u>351.5 *</u>
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 351.75

NET GAIN: 1.2 0.95

F/H BEAKER NO.: 2020 I.D. NO.: 00-5-18'

FINAL MASS: _____ TARE MASS: 107984.1

DATE/TIME	NAME	MASS
#1 <u>5/23 0727</u>	<u>AH</u>	<u>107,990.7</u>
#2 <u>5/23 1502</u>	<u>AH</u>	<u>107,990.2 *</u>
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 107,990.45

NET GAIN: 6.35 6.1

B/H BEAKER NO.: 1996 I.D. NO.: 00-519

FINAL MASS: _____ TARE MASS: 109868.65

DATE/TIME	NAME	MASS
#1 <u>5/24/00 1620</u>	<u>DA</u>	<u>109876.4</u>
#2 <u>5/25/00 820</u>	<u>DA</u>	<u>109875.9 *</u>
#3 _____	_____	_____
#4 _____	_____	_____

AVG. MASS: 109876.15

NET GAIN: 7.50 7.25

Appendix E
Example Calculations

Nomenclature and Dimensions

A_n	=	Cross-sectional area of sampling nozzle, ft²
A_s	=	Cross-sectional area of stack, ft²
B_{ws}	=	Proportion by volume of water vapor in the gas stream, dimensionless
C_p	=	Pitot tube coefficient, dimensionless
C_s	=	Concentration of pollutant matter in stack gas-dry basis, grains per dry standard cubic foot (gr/dscf)
%CO	=	Percent of carbon monoxide by volume, dry basis
%CO₂	=	Percent of carbon dioxide by volume, dry basis
ΔH	=	Average pressure drop across the sampling meter flow orifice , inches of water (in. H₂O)
GCV	=	Gross calorific value, Btu/lb
I	=	Percent of isokinetic sampling
L_a	=	Maximum acceptable leakage rate for either a pretest leak check or for a leak check following a component change/ equal to 0.020 cubic foot per minute or 4% of the average sampling rate, whichever is less
Md	=	Dry molecular weight, lb/lb-mole
Mn	=	Total amount of pollutant matter collected, milligrams (mg)
Ms	=	Molecular weight of stack gas (wet basis), lb/lb-mole
%N₂	=	Percent of nitrogen by volume, dry basis
%O₂	=	Percent of oxygen by volume, dry basis
ΔP	=	Velocity head of stack gas, inches of water (in. H₂O)
P_{bar}	=	Barometric pressure, inches of mercury (in. Hg)
P_s	=	Absolute stack gas pressure, inches of mercury (in. Hg)
P_{std}	=	Gas pressure at standard conditions, inches of mercury (29.92 in. Hg)

p_{mr}	=	Pollutant matter emission rate, pounds per hour (lb/hr)
Q_s	=	Volumetric flow rate - wet basis at stack conditions, actual cubic feet per minute (acfm)
Q_{std}	=	Volumetric flow rate - dry basis at stack conditions, actual cubic feet per minute (dscfm)
T_m	=	Average temperature of dry gas meter, °R
T_s	=	Average temperature of stack gas, °R
T_{std}	=	Temperature at standard conditions, 528°R
V_{lc}	=	Total volume of liquid collected in impingers, ml
v_{sg}	=	Weight of moisture collected in silica gel, grams
V_m	=	Volume of dry gas sampled at meter conditions, ft³
V_{mstd}	=	Volume of dry gas sampled at standard conditions, ft³
v_s	=	Average stack gas velocity at stack conditions, ft/s
V_{wstd}	=	Volume of water vapor at standard conditions, scf
Y	=	Dry gas meter calibration factor, dimensionless
Θ	=	Total sampling time, minutes

NOTE: Standard conditions = **68°F** and **29.92** in. Hg

Example Calculations for Pollutant Emissions

1. Volume of dry gas sampled corrected to standard conditions, ft³.
Note: V_m must be corrected for leakage if any leakage rates exceed L_a .

$$V_{wstd} = 17.647 * V_m * \gamma * \frac{P_{bar} + \frac{AH}{13.6}}{T_m, ^\circ R}$$

2. Volume of water vapor at standard conditions, ft³.

$$V_{mstd} = 0.04707 * V_{lc} + 0.04715 * V_{sg}$$

3. Moisture content in stack gas, dimension less.

$$B_{ws} = \frac{V_{wstd}}{V_{wstd} + V_{mstd}}$$

4. Dry molecular weight of stack gas, lbhb -mole.

$$M_d = 0.44 * \%CO_2 + 0.32 * \%O_2 + 0.28 * (\%N_2 + \%CO)$$

5. Molecular weight of stack gas, lbhb-mole.

$$M_s = M_d(1 - B_{ws}) + 18 * B_{ws}$$

6. Stack velocity at stack conditions, f/s.

$$V_s = 85.49 * C_p * \text{ave}\sqrt{\Delta P} * \sqrt{\frac{T_s, ^\circ R}{P_s * M_s}}$$

7. Stack gas volumetric flow rate at stack conditions, cfm.

$$Q_s = 60 * V_s * A_s$$

8. Dry stack gas volumetric flow rate at standard conditions, cfm.

$$Q_{sstd} = 17.647 * Q_s * \frac{P_s}{T_s, ^\circ R} * (1 - B_{ws})$$

9. Concentration in gr/dscf.

$$Cs = 0.01543 * \frac{Mn}{Vmstd}$$

10. Concentration in lb/dscf.

$$Cs, lb/dscf = \frac{gr/dscf}{7000}$$

11. Pollutant mass emission rate, lb/hr.

$$Pmr, lb/hr = lb/dscf * Qsstd * 60$$

12. Pollutant mass emission rate, lb/MMBtu.

$$pmr, lb/MMBtu = \frac{pmr, lb/hr}{MMBtu/hr}$$

13. F-factor, Fd.

$$Fd = \frac{10^6 * (3.64 * \%H) + (1.53 * \%C) + (0.57 * \%S) + (0.14 * \%N) - (0.46 * \%O_2)}{GCV (Btu/lb)}$$

14. F-factor, pollutant mass emission rate, lb/MMBtu.

$$= \frac{lb/dscf * Fd * 20.9}{(20.9 - \%O_2)}$$

15. Heat input, MMBtu/hr fuel.

$$= \frac{GVC (Btu/lb) * Feed Rate (lb/hr)}{10^6}$$

16. Heat input, MMBtu/hr, F-factor.

$$= \frac{Qsstd}{Fd} * ((20.9 - \%O_2) + 20.9) * 60$$

17. Volume of dry gas sampled corrected to standard conditions, m³.

$$Vmstd (m^3) = Vmstd (ft^3) * 0.02831$$

18. Concentration in ugldscm.

$$ugldscm = Target\ Catch, micrograms / Vmstd (m^3)$$

19. **Concentration** corrected to 7% oxygen.

$$ugldscm @ 7\% O_2 = ugldscm * (20.9-7) / (20.9-measured O_2)$$

20. Concentration, part per million, dry basis.

$$ppm, dry = ppm, wet basis \div (1 - \frac{BWS, \%}{Fd})$$

21. Pollutant Mass Emission Rate, pound per hour.

$$PMR, lb/hr = \frac{ppm, dry * Compound\ Molecular\ Weight}{(385.3 \times 10^6)} * dscfm * 60$$

Common Molecular Weights (MW)

Total Gaseous Organic Compound (TGOC)	=	44.09
Sulfur Dioxide (SO ₂)	=	64.05
Nitrogen Oxides (NO _x)	=	46.00
Carbon Monoxide (CO)	=	28.01
Oxygen (O₂)	=	32.00
Carbon Dioxide (CO ₂)	=	44.01

22. Removal Efficiency (RE), percent.

$$RE = (Inlet\ lb/hr - Outlet\ lb/hr / Inlet\ lb/hr) * 100$$

Summary of Stack Gas Parameters and Test Results

5700.000

Kentucky Electric Steel, INC
US EPA Test Method 2 - Velocity
Harsell Baghouse Inlet

Page 1 of 1

RUN NUMBER	1A	1B	2A	2B	3A	3B	
RUN DATE	5/11/00		5/12/00		5/12/00		Average
RUN TIME	730	705	630	1050	1050	1619	
MEASURED DATA							
P _{static} Stack Static Pressure, inches H ₂ O	5.10	4.50	5.20	4.50	4.50	4.60	4.73
P _{bar} Barometric Pressure, inches Hg	29.60	29.60	29.45	29.45	29.45	29.45	29.50
CO ₂ Carbon Dioxide content, % by volu	0.0	0.0	0.0	0.0	0.0	0.0	0.00
O ₂ Oxygen content, % by volume	21.0	21.0	21.0	21.0	21.0	21.0	21.00
N ₂ Nitrogen content, % by volume	79.0	79.0	79.0	79.0	79.0	79.0	79.00
C _p Pitot Tube Coefficient	0.84	0.84	0.84	0.84	0.84	0.84	0.84
Circular Stack? 1=Y,0=N:	0	0	0	0	0	0	0.00
As Diameter or Dimensions, inches:	18348.00	18348.00	18348.00	18348.00	18348.00	18348.00	18348.00
A Stack Area, ft ²	127.4	127.4	127.4	127.4	127.4	127.4	127.42
B _{ws} Moisture, % by volume	1.20	1.20	2.50	2.60	2.60	2.70	2.13
Square root Delta P	1.36	1.3	1.34	1.4	1.4	1.3	1.34
Ts Stack Temp	142.00	130.0	168.00	146.0	146.0	191.0	153.83
CALCULATED DATA							
P _s Stack Pressure, inches Hg	29.98	29.93	29.83	29.78	29.78	29.79	29.85
M _d Molecular Weight (d.b.), lb/lb•mole	28.84	28.84	28.84	28.84	28.84	28.84	28.84
M _s Molecular Weight (w.b.), lb/lb•mole	28.71	28.71	28.57	28.56	28.56	28.55	28.61
V _s Stack Gas Velocity, ft/s	81.6	79.2	82.4	82.2	82.2	81.1	81.46
Q _a Stack Gas Volumetric flow, acfm	624,197	605,253	630,169	628,212	628,212	620,372	622735.84
Q _s Stack Gas Volumetric flow, dscfm	541,677	535,131	514,859	530,431	530,431	487,222	523291.69
Q _s Stack Gas Volumetric flow, dscmm	15,339	15,153	14,579	15,020	15,020	13,797	14817.97

139" x 132"

Summary of Stack Gas Parameters and Test Results

5700.000

Kentucky Electric Steel, INC.

US EPA Test Method 5 - Particulate Matter

Harsell Baghouse Outlet

Page 1 of 2

RUN NUMBER		BO-1	BO-2	BO-3	Average
RUN DATE		5/11/00	5/12/00	5/12/00	
RUN TIME		1355-1945	0715-1120	1218-1618	
MEASURED DATA					
P _{static}	Stack Static Pressure, inches H ₂ O	-0.10	-0.10	-0.10	-0.10
y	Meter Box Correction Factor	0.988	0.988	0.988	0.988
P _{bar}	Barometric Pressure, inches Hg	29.60	29.45	29.45	29.50
V _m	Sample Volume, ft ³	173.319	197.399	178.352	183.023
Dp ^{1/2}	Average Square Root Dp, (in. H ₂ O) ^{1/2}	0.0322	0.0315	0.0276	0.0304
DH	Avg Meter Orifice Pressure, in. H ₂ O	0.96	2.11	1.62	1.56
T _m	Average Meter Temperature, °F	94	89	97	93
T _s	Average Stack Temperature, °F	146	162	168	159
V _{lc}	Condensate Collected, ml	43.5	101.1	93.0	79.2
CO ₂	Carbon Dioxide content, % by volume	0.0	0.0	0.0	0.0
O ₂	Oxygen content, % by volume	21.0	21.0	21.0	21.0
N ₂	Nitrogen content, % by volume	79.0	79.0	79.0	79.0
C _p	Pitot Tube Coefficient	0.84	0.84	0.84	0.84
	Circular Stack? 1=Y,0=N:	0	0	0	
As	Diameter or Dimensions, inches:	774862.95	774862.95	774862.95	774862.95
Q	Sample Run Duration, minutes	300	240	240	260
D _n	Nozzle Diameter, inches	1.000	1.240	1.240	1.160
CALCULATED DATA					
A _n	Nozzle Area, ft ²	0.005454	0.008386	0.008386	0.007408
V _{m(std)}	Standard Meter Volume, ft ³	161.778	185.522	165.012	170.771
V _{m(std)}	Standard Meter Volume, m ³	4.581	5.253	4.673	4.836
Q _m	Average Sampling Rate, dscfm	0.539	0.773	0.688	0.667
P _s	Stack Pressure, inches Hg	29.59	29.44	29.44	29.49
B _{ws}	Moisture, % by volume	1.2	2.5	2.6	2.1
B _{ws(sat)}	Moisture (at saturation), % by volume	23.1	34.3	39.5	32.3
V _{wstd}	Standard Water Vapor Volume, ft ³	2.048	4.759	4.378	3.728
1-B _{ws}	Dry Mole Fraction	0.988	0.975	0.974	0.979
M _d	Molecular Weight (d.b.), lb/lb•mole	28.84	28.84	28.84	28.84
M _s	Molecular Weight (w.b.), lb/lb•mole	28.70	28.57	28.56	28.61
V _s	Stack Gas Velocity, ft/s	2.0	1.9	1.7	1.9
A	Stack Area, ft ²	5381.0	5381.0	5381.0	5380.99
Q _a	Stack Gas Volumetric flow, acfm	630,570	628,028	553,007	603,868
Q _s	Stack Gas Volumetric flow, dscfm	536,390	511,287	445,529	497,735
Q _s	Stack Gas Volumetric flow, dscmm	15,189	14,478	12,616	14,004
I	Isokinetic Sampling Ratio, %	99.2	97.0	99.0	98.4

Summary of Stack Gas Parameters and Test Results

5700.000

Kentucky Electric Steel, INC.

US EPA Test Method 5 - Particulate Matter

Harsell Baghouse Outlet

Page 2 of 2

RUN NUMBER		BO-1	BO-2	BO-3	Average
RUN DATE		5/11/00	5/12/00	5/12/00	
RUN TIME		1355-1945	0715-1120	1218-1618	
EMISSIONS DATA					
Particulate Matter					
PM	Filter Weight Gain, mg	3.9 //	10.55 //	1.2 //	
PM	Beaker Weight Gain, mg	17.85 //	15.45 //	13.85 //	
PM	Total Catch, g	0.0218	0.0260	0.0151	0.0209
C _{PM}	Concentration,grldscf	2.07E-03	2.16E-03	1.41E-03	1.88E-03
C _{PM}	Concentration,lbldscf	2.96E-07	3.09E-07	2.01E-07	2.69E-07
E _{PM}	Emission Rate, lb/hr	9.54	9.48	5.37	8.13

SA

Appendix F
Calibration Data

PACIFIC ENVIRONMENTAL SERVICES, INC.

CALIBRATION PROCEDURES AND RESULTS

All of the equipment used is calibrated in accordance with the procedures outlined in the Quality Assurance Handbook for Air Pollution Measurement Systems. Volume III.* The following pages describe these procedures and include the data sheets.

***EPA 600/4-77-027b**

PACIFIC ENVIRONMENTAL SERVICES, INC.


Nozzle Diameter

Each nozzle used in these tests is calibrated by making three separate measurements and calculating the average. If a deviation of more than 0.004 of an inch is found between any two measurements, the nozzle is either discarded or reamed out and remeasured. A micrometer is used for measuring. These calibration data are shown in the following Nozzle Calibration data **sheet(s)**.


PACIFIC ENVIRONMENTAL SERVICES, INC.

Pitot Tube Calibration

Each **pitot** tube used in sampling meets all requirements of EPA Method 2, Section 4.1.** Therefore, a baseline coefficient of 0.84 is assigned to each **pitot** tube. The following pages show the alignment requirements of Method 2 and the **Pitot** Tube Inspection Data **Sheet(s)** for each **pitot** tube used during the test program.



(a) side view: both legs of equal length and centerlines coincident, when viewed from both sides. Baseline coefficient values of 0.84 may be assigned to pitot tubes constructed this way.



The types of face-apening misalignment shown above will not affect the baseline value of $C_p(s)$ so long as α_1 and α_2 is less than or equal to 10° , β_1 and β_2 is less than or equal to 5° , z is less than or equal to 0.32 cm (1/8 in.), and w is less than or equal to 0.08 cm (1/32 in.) (reference 1.0 in Section 16.0).

PITOT TUBE CALIBRATIONS

Pitot ID	Date Calibrated	α_1	B_1	α_2	B_2	γ	θ	A	z	w	P_α	P_β	D_t	A/2/D _t	Accept/Reject
2-M-1	11/13/00	1.8	0.1	1.4	0.1	0.1	0.6	0.948	0.002	0.010	0.474	0.474	0.375	1.264	ACCEPT
2-M-2	1/13/00	0.6	1.4	2.8	0.7	1.1	1.7	0.955	0.018	0.028	0.477	0.478	0.375	1.273	ACCEPT
3-1	10/29/99	1.3	1.6	3.8	3.7	2.1	0.3	1.077	0.039	0.006	0.538	0.539	0.364	1.479	ACCEPT
3-M-1	10/29/99	1.1	1.8	0.9	0.1	1.4	1.7	0.948	0.023	0.028	0.474	0.474	0.375	1.264	ACCEPT
3-M-2	10/28/99	1.6	0.8	0.8	0.6	0.7	0.8	0.954	0.012	0.013	0.477	0.477	0.375	1.272	ACCEPT
3-M-3	1/13/00	0.7	0.2	1.6	0.2	2.6	1.6	0.945	0.043	0.026	0.473	0.472	0.375	1.260	ACCEPT
3-X-2	10/28/99	0.4	0.4	0.7	0.7	0.7	0.9	0.945	0.012	0.015	0.472	0.473	0.375	1.260	ACCEPT
3-X-1	10/29/99	0.4	0.6	0.8	0.6	0.1	0.2	0.945	0.002	0.003	0.473	0.472	0.375	1.260	ACCEPT
4-M-1	10/28/99	0.3	0.6	0.5	0.4	0.6	0.4	0.949	0.010	0.007	0.474	0.475	0.375	1.265	ACCEPT
4-M-2	10/29/99	0.7	0.4	0.2	1.4	1.1	0.4	0.958	0.018	0.007	0.479	0.479	0.375	1.277	ACCEPT
4-X-1	10/29/99	4.7	1.2	4.4	0.4	2.7	0.4	0.945	0.045	0.007	0.472	0.473	0.375	1.260	ACCEPT
4-X-2	10/28/99	0.2	0.9	1.6	1.3	0.1	0.1	0.949	0.002	0.002	0.474	0.475	0.375	1.265	ACCEPT
4-X-3	10/28/99	0.2	0.6	0.2	0.5	0.2	0.4	0.956	0.003	0.007	0.478	0.478	0.375	1.275	ACCEPT
5-TIP	10/29/99	1.9	3.5	1.0	1.4	1.8	1.6	0.937	0.029	0.026	0.468	0.469	0.375	1.249	ACCEPT
5-I-1	10/28/99	1.6	0.8	1.0	0.8	0.1	0.7	0.968	0.002	0.012	0.484	0.484	0.375	1.291	ACCEPT
5-M-1	10/28/99	0.2	0.3	0.2	0.2	1.0	0.6	0.896	0.016	0.009	0.448	0.448	0.375	1.195	ACCEPT
5-M-2	1/13/00	0.9	0.1	3.9	3.9	1.3	1.2	0.921	0.021	0.019	0.461	0.460	0.375	1.228	ACCEPT
5-X-1	10/29/99	0.3	0.0	0.3	0.5	1.6	0.3	0.950	0.027	0.005	0.475	0.475	0.373	1.273	ACCEPT
5-X-2	10/28/99	1.6	1.4	1.2	0.7	0.7	0.7	0.947	0.012	0.012	0.474	0.473	0.372	1.273	ACCEPT
5-X-3	10/29/99	0.4	0.4	0.1	0.3	1.0	0.9	0.948	0.017	0.015	0.474	0.474	0.375	1.264	ACCEPT
5-1	10/27/99	1.4	1.3	1.0	1.4	0.7	0.8	1.042	0.013	0.015	0.521	0.521	0.375	1.389	ACCEPT
5-2	10/29/99	0.4	1.8	3.7	2.9	1.4	0.9	0.971	0.024	0.015	0.485	0.486	0.375	1.295	ACCEPT
5-3	10/28/99	0.8	0.2	0.9	1.0	0.2	0.3	1.009	0.004	0.005	0.504	0.505	0.375	1.345	ACCEPT
5-4	10/29/99	2.3	1.2	0.5	0.7	2.7	1.0	0.625	0.029	0.011	0.312	0.313	0.250	1.250	ACCEPT
5-5	10/29/99	1.0	0.8	0.8	0.5	0.5	0.6	1.022	0.009	0.011	0.511	0.511	0.375	1.363	ACCEPT
5-6	1/13/00	1.3	0.1	1.2	1.4	2.5	0.7	0.938	0.041	0.011	0.469	0.469	0.375	1.251	ACCEPT
6-1	10/27/99	1.6	1.5	1.7	1.3	0.2	0.2	0.956	0.003	0.003	0.478	0.478	0.375	1.275	ACCEPT
6-2	10/28/99	0.1	0.2	0.7	1.7	0.4	0.3	1.097	0.008	0.006	0.548	0.549	0.375	1.463	ACCEPT
6-3	1/13/00	1.9	2.1	2.6	1.7	1.5	0.1	1.041	0.027	0.002	0.520	0.521	0.375	1.388	ACCEPT
6-I-1	10/27/99	1.4	2.7	1.3	0.6	2.2	0.4	0.986	0.038	0.007	0.493	0.493	0.375	1.315	ACCEPT
6-I-2	10/28/99	0.8	0.8	1.3	1.8	0.6	0.3	0.968	0.010	0.005	0.484	0.484	0.375	1.291	ACCEPT
7-1	1/13/00	0.7	1.5	1.3	1.0	0.6	0.9	0.975	0.010	0.015	0.487	0.488	0.375	1.300	ACCEPT
7-I-1	10/29/99	0.1	1.9	0.6	1.0	0.9	0.3	0.948	0.015	0.005	0.474	0.474	0.375	1.264	ACCEPT
7-M-1	10/28/99	1.1	1.1	0.2	0.2	1.1	0.9	0.957	0.018	0.015	0.478	0.479	0.375	1.276	ACCEPT
7-M-2	10/28/99	0.4	1.2	1.9	1.8	0.7	0.8	0.923	0.011	0.013	0.462	0.461	0.375	1.231	ACCEPT
7-M-3	10/29/99	1.6	1.8	0.5	0.4	0.7	0.1	0.923	0.011	0.002	0.461	0.462	0.375	1.231	ACCEPT
8-1	10/28/99	0.6	0.8	1.9	1.6	0.3	0.1	0.934	0.005	0.002	0.467	0.467	0.375	1.245	ACCEPT
8-2	10/29/99	0.9	0.8	0.4	0.5	2.1	1.6	0.941	0.034	0.026	0.470	0.471	0.375	1.255	ACCEPT
8-3	11/4/99	1.1	0.6	0.3	1.4	0.1	0.4	0.918	0.002	0.006	0.459	0.459	0.374	1.227	ACCEPT
8-M-2	10/29/99	0.2	2.4	0.3	1.2	0.5	0.7	0.938	0.008	0.011	0.469	0.469	0.375	1.251	ACCEPT
9-M-1	10/29/99	0.1	1.7	0.2	0.8	1	1	0.982	0.017	0.017	0.491	0.491	0.375	1.309	ACCEPT
10-M-1	10/29/99	2.2	2.8	0.3	0.5	0.2	0.4	0.949	0.003	0.007	0.475	0.474	0.374	1.269	ACCEPT
11-1	10/29/99	0.8	1.9	2.5	1.8	1.3	1.5	0.970	0.022	0.025	0.485	0.485	0.351	1.382	ACCEPT
12-X-1	10/29/99	0.4	1.5	0.9	1.9	2.9	1.4	0.921	0.047	0.023	0.461	0.46	0.372	1.238	ACCEPT
12-1	10/29/99	0.3	0.4	1.1	0.6	1.2	1.2	1.125	0.024	0.024	0.563	0.562	0.375	1.500	ACCEPT

- 1 = Pitot Alone

- M - 1 = Pitot/Thermo. Combination

- X - 1 = Full Probe Assembly

- I - 1 = Inkonel

- T - 1 = Thermo. Alone

PACIFIC ENVIRONMENTAL SERVICES, INC.

Dry Gas Meter and Orifice Meter

Dry gas meters and orifices are calibrated in accordance with Section **3.3.2** of the QA Handbook. This procedure involves direct comparison of the dry gas meter to a reference dry test meter. The reference dry test meter is routinely calibrated using a liquid displacement technique. Before its initial use in the field, the metering system is calibrated over the entire range of operation. After each field use, the metering system is calibrated at a single intermediate setting based on the previous field test. Acceptable tolerances for the initial and final dry gas meter factors and orifice calibration factors are ± 0.02 and ± 0.20 from average, respectively.

Digital Indicators for Thermocouple Readout

A digital indicator is calibrated by feeding a series of millivolt signals to the input and comparing the indicator reading with the reading the signal should have generated. Errors did not exceed **0.5** percent (%) when the temperatures were expressed in degrees **Rankine**. Calibration data are included in the following Thermocouple Digital Indicator Calibration Data **Sheet(s)**.

Dry Gas Thermocouples

The dry gas thermocouples are calibrated by comparing them with an **ASTM-3** thermometer at approximately **32°F**, ambient temperature, and a higher temperature between approximately **100°F** and **200°F**. The thermocouples agreed within **5°F** of the reference thermometer.

11/19/1999

PACIFIC ENVIRONMENTAL SERVICES, INC.

7209 E. Kemper Rd.
Cincinnati, Ohio 45249
Phone: 513.489.6611
Fax: 513.489.6619
wmv.pes.com

Meter Box No.: 2

Dry Gas Orifice Meter

Pb, in. Hg	29.36	RUN 1	RUN 2	RUN 3	RUN 4	RUN 5	RUN 6
DH	Delta H	0.50	0.75	1.00	1.50	2.00	4.00
in Hg	Vacuum	10	10	10	10	10	10
Vw ₁	Initial RTM	956.527	966.320	974.057	985.406	996.985	1009.901
Vw ₂	Final RTM	965.863	973.878	985.114	996.606	#####	1022.371
Vd ₁	Initial DGM	59.856	69.667	77.458	88.899	100.602	113.680
Vd ₂	Final DGM	69.216	77.274	88.604	100.217	112.825	126.334
Tw	Ave. Temp RTM °	75	76	78	78	79	79
Td	Ave. Temp DGM °	78	81	84	87	88	89
	Time (min.)	22.3	15.0	19.0	16.0	15.0	11.0

Vw ₂ - Vw ₁	Net Volume RTM	9.336	7.558	11.057	11.200	12.071	12.470
Vd ₂ - Vd ₁	Net Volume DGM	9.360	7.607	11.146	11.318	12.223	12.654
Y		1.002	1.001	1.001	1.002	0.999	0.994
dH@		1.634	1.694	1.696	1.749	1.775	1.778

AMRAGE Y	0.988	(Reference meter correction factor of 0.988)			ACCEPT
Average Y Range =		0.968	TO	1.008	
AMRAGE dH	1.721				ACCEPT
Average dH@ Range =		1.521	TO	1.921	

Calculations							
$Y = (Vw - Pb * (Td + 460)) / (Vd * (Pb + (dHd / 13.6)) * (Tw + 460))$							
$dH@ = 0.0317 * dHd * (Pb * (Td + 460)) * (((Tw + 460) * t) / Vw)^2$							

Digital Indicator for Thermocouple Readout

DIGITAL				
TEST POINT NO.	MILLIVOLT SIGNAL	EQUIVALENT TEMP, °F	INDICATOR TEMP °F	DIFFERENCE, %
			READING, °F	
1	4.692	0	1	0.2
2	1.520	100	100	0.0
3	3.819	200	201	0.2
4	6.092	300	299	0.1
5	8.314	400	399	0.1
6	10.560	500	501	0.1
7	22.251	1000	1001	0.1
8	29.315	1300	1300	0.0
9	36.166	1600	1601	0.0
10	42.732	1900	1899	0.0

Percent difference must be less than or equal to 0.5 %

% difference: $\frac{(\text{Equivalent Temp., } ^\circ\text{R} - \text{Digital Indicator Temp., } ^\circ\text{R}) * (100\%)}{(\text{Equivalent Temp., } ^\circ\text{R})}$

Where $^\circ\text{R} = ^\circ\text{F} + 460$

ACCEPT

Dry Gas Thermocouples

Reference point number	Source* (Specify)	Reference Thermometer Temperature, °F	Thermocouple Potentiometer Temperature, °F	Temperature Difference, °F
Inlet				
1	Ambient Air	73	74	1
2	Cold Bath	42	43	1
3	Hot Bath	139	138	1
Outlet				
1	Ambient Air	73	73	0
2	Cold Bath	42	43	1
3	Hot Bath	138	137	1

*Type of calibration used.

Allowable tolerance $\pm 5^\circ\text{F}$

ACCEPT

Calibrated By : da

PACIFIC ENVIRONMENTAL SERVICES, INC.

4700 Duke Drive,
Suite 150
Mason, Ohio 45040
Phone: (513)398-2556
Fax: (513)398-3342
www.pes.com

Box No.:	MB -2	Bar. Press.(Ps):	29.23	in. Hg
Date:	MAY 25,2000	Pretest Gamma:	0.988	
Calibrated By :	G GAY	Pretest dH@:	1.721	
Plant:	KES			
		RUN 1	RUN 2	RUN 3
DH	Delta H	2.00	2.00	2.00
in Hg	Vaccum	5.00	5.00	5.00
Vw ₁	Initial RTM	803.015	815.118	827.233
Vw ₂	Final RTM	815.118	827.233	839.345
Vd ₁	Initial DGM	673.120	685.278	697.516
Vd ₂	Final DGM	685.278	697.516	709.789
Tw	Ave. Temp RTM °F	76.0	76.0	77.0
Td	Ave. Temp DGM °F	82.0	84.0	86.0
	Time (min.)	15.0	15.0	15.0

Vw ₂ - Vw ₁	Net Volume RTM	12.103	12.115	12.112
Vd ₂ - Vd ₁	Net Volume DGM	12.158	12.238	12.273
	Y	1.002	1.000	0.998
	dH@	1.766	1.756	1.757

AVERAGE Y = 1.000

% Difference from Yearly Y = 1.204 ACCEPT

AVERAGE dH@ = 1.760

Calculations

$$Y = (Vw * Pb * (Td + 460)) / ((Vd * (Pb + (dHd / 13.6)) * (Tw + 460)))$$

$$dH@ = 0.0317 * dHd / (Pb * (Td + 460)) * (((Tw + 460) * time) / Vw)^2$$

PACIFIC ENVIRONMENTAL SERVICES, INC.

Stack Thermocouples

Each thermocouple is calibrated by comparing it with an ASTM-3F thermometer at approximately **32°F**, ambient temperature, **212°F**, and 500°F. The thermocouple reads within 1.5 percent (%) of the reference thermometer throughout the entire range when expressed in degrees **Rankine**. The thermocouples may be checked at ambient temperature at the test site to verify the calibration. Calibration data are included in the following Thermocouple Calibration Data **Sheet(s)**.

STACK THERMOCOUPLES

Thermo. ID	Therm.	Date Calibrated	Ambient Air	Diff., %	Cold Bath	Diff., %	Hot Bath	Diff., %	Hot Oil	Diff., %	Accept/Reject
1-T-1	Reference	1/13/00	76	0.00	46	0.00	212	0.00	451	0.00	ACCEPT
	Pitot		76		46		212		451		
2-M-1	Reference	1/27/00	75	0.00	42	0.00	210	0.00	410	0.00	ACCEPT
	Pitot		75		42		210		410		
2-M-2	Reference	1/27/00	75	0.00	42	0.00	165	0.00	418	0.00	ACCEPT
	Pitot		75		42		165		418		
3-M-1	Reference	11/3/99	65	1.14	35	0.00	201	0.00	423	0.00	ACCEPT
	Pitot		71		35		201		423		
3-M-2	Reference	11/2/99	74	0.00	42	0.00	208	0.00	456	0.00	ACCEPT
	Pitot		74		42		208		456		
3-M-3	Reference	1/13/00	75	0.00	36	0.00	192	0.00	410	0.00	ACCEPT
	Pitot		75		36		192		410		
3-M-4	Reference	1/27/00	75	0.00	42	0.00	212	0.00	415	0.00	ACCEPT
	Pitot		75		42		212		415		
3-T-1	Reference	10/29/99	77	0.19	42	0.00	214	0.00	393	0.23	ACCEPT
	Pitot		78		42		214		395		
3-T-2	Reference	10/29/99	77	0.00	43	0.00	212	0.00	452	0.00	ACCEPT
	Pitot		77		43		212		452		
3-T-3	Reference	1/13/00	75	0.00	46	0.00	207	0.00	423	0.00	ACCEPT
	Pitot		75		46		207		423		
3-T-4	Reference	1/13/00	76	0.00	38	0.00	210	0.00	455	0.00	ACCEPT
	Pitot		76		38		210		455		
3-X-1	Reference	10/29/99	77	0.00	42	0.20	211	0.00	500	0.10	ACCEPT
	Pitot		77		43		211		501		
3-X-2	Reference	11/3/99	64	0.19	43	0.00	208	0.00	438	1.45	ACCEPT
	Pitot		65		43		208		425		
4-M-1	Reference	11/2/99	74	0.00	38	0.60	199	0.00	373	0.00	ACCEPT
	Pitot		74		41		199		373		
4-M-2	Reference	11/3/99	74	0.00	58	0.00	192	0.31	411	0.00	ACCEPT
	Pitot		74		58		190		411		

PACIFIC ENVIRONMENTAL SERVICES, INC.

Impinger Thermocouples

The impinger thermocouples are checked in a similar manner at approximately 32°F and ambient temperature, and they agreed within 2°F. The thermocouples may be checked at ambient temperature prior to the test series to verify calibration. Calibration data are included in the following Impinger Thermocouple Calibration Data Sheet(s).

PACIFIC ENVIRONMENTAL SERVICES, INC.

7209 E. Kemper Rd.
Cincinnati, OH 45249
Phone: 513.489.6611
Fax: 513.489.6619

**TEMPERATURE SENSOR CALIBRATION DATA FORM
FOR SAMPLEHEADS****DATE:** 13-Jan-00

Reference point number	source ^a (Specify)	Reference Thermometer Temperature, °F	Thermocouple Potentiometer Temperature, °F	Temperature Difference, ^b °F	
Sample Head No. 1					
1	Ambient Air	75	75	0	ACCEPT
2	Cold Bath	36	36	0	
Sample Head No. 2					
1	Ambient Air	76	76	0	ACCEPT
2	Cold Bath	36	36	0	
Sample Head No. 3					
1	Ambient Air	76	76	0	ACCEPT
2	Cold Bath	38	38	0	
Sample Head No. 4					
1	Ambient Air	76	76	0	ACCEPT
2	Cold Bath	36	36	0	
Sample Head No. 5					
1	Ambient Air	76	78	2	ACCEPT
2	Cold Bath	36	36	0	
Sample Head No. 6					
1	Ambient Air	73	73	0	ACCEPT
2	Cold Bath	35	35	0	
Sample Head No. 7					
1	Ambient Air	74	74	0	ACCEPT
2	Cold Bath	35	35	0	
Sample Head No. 8					
1	Ambient Air	74	74	0	ACCEPT
2	Cold Bath	38	38	0	

"Type of calibration used.

Calibrated By: ah

^b Allowable tolerance $\pm 2^{\circ}\text{F}$ **SAMPLEHEAD****2000 Yearly Calibration**

SECTION B - EMISSION POINTS, EMISSIONS UNITS, APPLICABLE REGULATIONS, AND OPERATING CONDITIONS

02 (01) - Electric arc furnaces(EAFs), Ladle metallurgy furnace (LMF) and the associated Dust handling equipment

Description:

The two Leco Inert electric arc furnaces A and B have maximum capacities of 34 tons/hr, each. The emissions are vented by direct shell evacuation through side draft hoods and overhead canopy hood system to the baghouse. This emission point covers emissions due to charging, melting, and tapping. The (6) six oxy-fuel burners operate on natural gas and oxygen and are capable of firing at up to 10 million Btu/hr, each. The LMF is a steel purification and refining process. The emissions from the LMF are captured by a hooding system and vented to the same Harsell baghouse. The LMF has the capacity to refine 68 tons per hour of molten steel. The emissions from the associated dust handling equipment are also vented to the same Harsell baghouse.

Construction commenced: EAFs - 1981;
LMF- June, 1995;
Baghouse - 1976

APPLICABLE REGULATIONS:

401 KAR 59:570 - Standards of performance for steel plants: electric arc furnaces constructed after October 21, 1974, and on or before August 17, 1983, is governed by 40 CFR 60, Subpart AA.

STATE-ORIGIN APPLICABLE REGULATIONS:

401 KAR 63:021 - Existing sources emitting toxic air pollutants.

1. Operating Limitations:

- 1- The total steel production from both furnaces shall not exceed 403,200 tons/yr, with each furnace producing no more than 34 tons/hr. (Self imposed to preclude the applicability of 401 KAR 51:052, Review of new sources in or impacting upon nonattainment areas)
- 2- The control system fan amperes shall fall within the same range of values recorded during the latest performance test (See testing requirements). However, the permittee have the option of installing , calibrating, and maintaining a monitoring device that continuously records the volumetric flow rate at the baghouse inlet. A shop opacity compliance demonstration shall be performed to establish volumetric flow rate and damper positions. [60.274 (b) and (c)]
- 3- The static pressure in the free space inside the EAFs shall not exceed the levels established during the latest performance test. The owner or operator shall install, calibrate and maintain a monitoring device that continuously records the pressure in the free space inside the EAF. The pressure shall be recorded as 15-minute integrated averages. The pressure monitoring device shall have an accuracy of plus or minus 5 mm of water gauge over its normal operating range and shall be calibrated according to the manufacturer's instructions (See testing requirements). However, the permittee have the option to conduct daily visual emissions observations as an alternative to furnace static pressure monitoring. Under the alternative, the permittee shall perform shop opacity observations once per day during a meltdown and refining period.[60.274 (b) and (c)]

Commonwealth of Kentucky
Natural Resources and Environmental Protection Cabinet
Department for Environmental Protection
Division for Air Quality
803 Schenkel Lane
Frankfort, Kentucky 40601
(502) 573-3382

AIR QUALITY PERMIT

Permittce Name: Kentucky Electric Steel, Incorporated
Mailing Addrsss: P. O. Box 3500, **Ashland**, Kentucky 41105

Source Name: Kentucky **Electric** Steel, Incorporated
Mailing Addrsss: Same as above

Source Location: 12 miles **west** of **Ashland** on U.S. 60, **Coalton**, Kentucky

PERMIT TYPE: Federally-Enforceable Title V
Review **Type**: Operating, Synthetic Minor

Permit Number: **V-98-031**
Log Number: **E982**
Application
Complete Date: February 14, 1997
KYEIS ID #: 103-0340-0020
AFS Plant ID: 21-019-00020
SIC Code: 3312

Region: **Huntington/Ashland**
County: Boyd

Issuance Date: June 2, 1999
Expiration Date: June 2, 2004

John E. Hornback, Director
Division for Air Quality

TABLE OF CONTENTS

<u>SECTION</u>		<u>DATE OF ISSUANCE</u>	<u>PAGE</u>
SECTION A	PERMIT AUTHORIZATION	June 2, 1999	1
SECTION B	EMISSION POINTS, EMISSION UNITS APPLICABLE REGULATIONS, AND OPERATING CONDITIONS	June 2, 1999	2
SECTION C	INSIGNIFICANT ACTIVITIES	June 2, 1999	14
SECTION D	SOURCE EMISSION LIMITATIONS AND TESTING REQUIREMENTS	June 2, 1999	15
SECTION E	SOURCE CONTROL EQUIPMENT OPERATING REQUIREMENTS	June 2, 1999	15
SECTION F	MONITORING, RECORD KEEPING, AND REPORTING REQUIREMENTS	June 2, 1999	16
SECTION G	GENERAL CONDITIONS	June 2, 1999	19
SECTION H	COMPLIANCE SCHEDULE	June 2, 1999	23

SECTION A - PERMIT AUTHORIZATION

Pursuant to a duly submitted application which was determined to be complete on February 14, 1997, the Kentucky Division for Air Quality hereby authorizes the operation of the equipment described herein in accordance with the terms and conditions of this permit. This permit has been issued under the provisions of Kentucky Revised Statutes Chapter 224 and regulations promulgated pursuant thereto.

The permittee shall not construct, reconstruct, or modify any affected facilities without first having submitted a complete application and receiving a permit for the planned activity from the permitting authority, except as provided in this permit or in the Regulation 401 KAR 50:035, Pennits.

Issuance of this permit does not relieve the pennittee from the responsibility of obtaining any other permits, licenses, or approvals required by this Cabinet or any other federal, staie, or local agency.

JAMES E. BICKFORD
SECRETARY



PAUL E. PATTON
GOVERNOR

33

11 08

COMMONWEALTH OF KENTUCKY
NATURAL RESOURCES AND ENVIRONMENTAL PROTECTION CABINET
DEPARTMENT FOR ENVIRONMENTAL PROTECTION
DIVISION FOR AIR QUALITY
803 SCHENKEL LN
FRANKFORT KY 40601-1403

August 14, 2000

Travis Bailey
Kentucky Electric Steel
P. O. Box 3500
Ashland, KY 41105

Dear Sir:

On May 10-12, 2000, personnel from the Kentucky Division for Air Quality observed particulate compliance tests on Kentucky Electric Steel's Harsell Open Top Baghouse. Testing was performed by PES and EQ of Cincinnati, Ohio, in a satisfactory manner. The test report was complete and acceptable. Results were as follows:

Run	Date	Time	gr/DSCF	lb/hr
1	5-11	13:55 – 19:45	0.0012	4.80
2	5-12	7:15 – 11:20	0.0014	5.51
3	5-12	12:18 – 16:18	<u>0.0007</u>	<u>2.43</u>
			0.0011	4.25

The emissions stated in the report include the back half catch, which is not used in Kentucky. The allowable emission rate for this source is .0052 gr/DSCF. The baghouse was in compliance at the time of the test.

Sincerely,

Gerald Slucher, Chief
Source Test Section

GS/JJ/mlp

Cc: Facility File 21-019-00020
Ashland Regional Office



Printed on Recycled Paper
An Equal Opportunity Employer M/F/D

**AIR EMISSIONS SOURCE TESTING PROTOCOL
COMPLIANCE SAMPLING PROGRAM
KENTUCKY ELECTRIC STEEL, INC.
ASHLAND, KENTUCKY**

Prepared for:

Kentucky Electric Steel, Inc.
P.O. Box 3500
Ashland, Kentucky 41105

PN 050163.0009

Prepared by:

800 229 7495

Environmental Quality Management, Inc.
1310 Kemper Meadow Drive
Cincinnati, Ohio 45240

April 2000

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Figures	iii
Tables	iv
1 Introduction	1-1
2 Sampling and Analytical Procedures	2-1
Location of Measurement Sites	2-1
Stack Gas Volumetric Flow Rate	2-1
Stack Gas Molecular Weight	2-1
Stack Gas Moisture Content	2-2
Particulate Matter	2-2
Visible Emission Observations	2-4
3 Process Description/Sampling Locations	3-1
4 Quality Assurance/Quality Control	4-1
Calibration Procedures and Frequency	4-1
5 Project Schedule	5-1
6 Final Report Format	6-1
 <u>Appendix</u>	
A Compliance Test Protocol Forms	
B Example Data Sheets	

FIGURES

<u>Number</u>		<u>Page</u>
2-1	Schematic of EPA Method 5 Sampling Train - Baghouse Outlet	2-3
3-1	Process Flow Diagram	3-2
3-2	Inlet Velocity Measurement Location	3-4
3-3	Schematic of Baghouse Outlet	3-5

TABLES

<u>Number</u>		<u>Page</u>
1-1	Sampling Requirement	1-1
4-1	Field Equipment Calibration Summary	4-2
4-2	Field Checks of Sampling Equipment	4-2

SECTION 1

INTRODUCTION

Environmental Quality Management, Inc. (EQ) has been retained by Kentucky Electric Steel, Inc. (KES) to plan and conduct a compliance particulate sampling evaluation from the Harsell Positive Pressure Baghouse servicing LECTROMELT Electric Arc Furnaces A and B and Ladle Metallurgy Furnace. Sampling is being performed in accordance with the requirements of operating Permit Number V-98-031. Table 1-1 presents the sampling efforts to be performed at the baghouse exhaust.

The test program is scheduled to be conducted May 11 and 12, 2000.

TABLE 1-1. SAMPLING REQUIREMENTS

Test Point No.	Test Point Name	Parameter Tested	Test Method
1	Harsell Baghouse Inlet	Flow ¹	EPA Method 1 for Velocity EPA Method 2 for Temperature
2	Harsell Baghouse Outlet	O ₂ /CO ₂ Moisture PM Visible Emissions	EPA Method 3 EPA Method 4 EPA Method 5D EPA Method 9

¹ Velocity profiles will be conducted at the inlet before and after each outlet Method 5D sample. Inlet velocity data **will** be used to sample the outlet.

The plant contact is:

Mr. Travis Bailey
Kentucky Electric Steel, Inc.
P.O. Box 3500
Ashland, Kentucky 41105
(606) 929-1330

The EQ contact is:

Mr. Tom Gerstle
Environmental Quality Management, Inc.
1310 Kemper Meadow Drive, Suite 100
Cincinnati, Ohio 45240
(513) 825-7500
tgerstle@eqm.com

SECTION 2

SAMPLING AND ANALYTICAL PROCEDURES

The sampling and analytical procedures to be used in this test program conform to **EPA** Reference Method 1-4, 5D, and 9 as published in the Federal Register. A brief description of each method follows:

LOCATION OF MEASUREMENT SITES

EPA Method 1, "Sample Velocity Traverses for Stationary Sources," will be used to select representative measurement sites. Sample locations are shown in Section 3. Exact measurements will be made **onsite**. Selection of cells to be sampled and location of sampling points within the **baghouse** will follow guidelines in **EPA** Method 5D. A schematic of the **baghouse** outlet is shown in Figure 3-3.

STACK GAS VOLUMETRIC FLOW RATE

EPA Method 2, "Determination of Stack Gas Velocity and Volumetric Flow Rates," will be used at each location to determine stack gas volumetric flow rates at the **baghouse** inlet. Standard and Type "S" pitot tubes, meeting the **EPA** specifications, and an inclined manometer will be used to measure velocity pressures. A calibrated Type "K" thermocouple, attached directly to the pitot tube, **will** be used to measure stack gas temperature. The stack gas velocity will be calculated from the average square root of the stack gas velocity pressure, average stack gas temperature, stack gas molecular weight, and absolute static pressure. The volumetric flow rate is the product of velocity and stack cross-sectional area.


STACK GAS DRY MOLECULAR WEIGHT

EPA Reference Method 3, "Gas Analysis for the Determination of Dry Molecular Weight," will be used to determine stack gas dry molecular weight. Bag samples will be collected



Kentucky Electric Steel, Inc.

P. O. Box 3500 • Ashland, Kentucky 41105-3500 • (606) 929-1200



April 24, 2000

Mr. Gerald Slucher
Commonwealth of Kentucky
Natural Resources and Environmental
Protection Cabinet
Department for Environmental Protection
Division of Air Quality
803 Schenkel Lane
Frankfort, KY 40601

Dear Mr. Slucher:

Please find attached copies of Kentucky Electric Steel, Inc.'s Emission Testing Protocol for the test dates of May 11th and May 12th, 2000.

If you have any questions regarding the enclosed or need additional information, please feel free to contact me at (606) 929-1330.

Sincerely,

Travis A. Bailey
Manager
Human Resources & Risk Control

TAB:jla

Enclosures

and analyzed for each measurement run using **Orsat** combustion gas analyzers which read 0.1 percent concentrations of carbon dioxide and oxygen.

STACK GAS MOISTURE CONTENT

EPA Reference Method 4, "Determination of Moisture Content in Stack Gases," will be used to determine stack gas moisture content. This method will be conducted as part of each particulate measurement run. The initial and final contents of all impingers will be determined gravimetrically.

PARTICULATE MATTER

EPA Reference Method 5D, "Determination of Particulate Matter Emissions from Positive Pressure Fabric Filters," will be used to determine the particulate matter concentration and mass emission rates. The sample train will consist of a glass nozzle, glass probe and filter holder, glass fiber filter, and a series of impingers followed by a vacuum pump, dry gas meter, and calibrated orifice. The particulate sample will be withdrawn isokinetically and collected on the filter. Thermocouples will be used to monitor temperatures of the stack gas and impinger exit gas. A schematic of the sample train is shown in Figure 2-1.

Exhaust from the Harsell **Baghouse** is routed through 20 bag sections. Following the guidelines presented in Method **5D**, each sampling run will consist of six sample points per cell and four cells per test, for a total of 24 sample points per test run. At ten minutes of sampling per point, this will result in a net sampling time of four hours per test run. After three test runs, 12 of the 20 cells will have been sampled. Each test run will be approximately 240 minutes in length, and will cover approximately three **EAF** heat cycles. Exact sampling point locations are detailed in Section **3**. Determination of measurement sites, number and location of traverse points, and velocity determination will follow procedures in Method 5D. Isokinetic **sampling** rates will be calculated from the measurement of volumetric flow rates at each inlet, as specified in Method **5D**.




Figure 2-1. Schematic of EPA Method 5 Sampling Train - Baghouse Outlet

VISIBLE EMISSION OBSERVATIONS

EPA Reference Method 9, "Visual Determination of the Opacity of Emissions from Stationary Sources" will be used to determine opacity from the **baghouse** exhaust as well as from the shop roof monitor. Observations will be conducted simultaneously with the particulate sampling runs.

SECTION 3

PROCESS DESCRIPTION/SAMPLING LOCATIONS

Kentucky Electric Steel, Inc. owns and operates an electric arc furnace (EAF) melt shop and bar steel rolling facility located on U.S. Route 60 approximately 12 miles west of Ashland, Kentucky.

Kentucky Electric Steel, Inc. has two EAFs for steel production. Scrap steel is delivered by rail and truck and is stored in open piles. Scrap steel and various fluxing agents are weighed and charged to the EAF. The charge material is melted by electrical current flowing among three graphite electrodes lowered into the furnace. Slag (melt impurities) is separated from the product metal and is transferred to slag storage and processing using an endloader. Molten metal is tapped from the EAF into preheated transfer ladles by tilting the furnace, allowing the metal to flow through a hole in the side.

Molten metal is then transferred to the ladle metallurgy furnace (LMF). Raw materials (bulk alloys and fluxes) are added to the molten metal in the LMF to further purify it. The metal is heated during refining using electrodes. After metal treatment is complete, the transfer ladle is removed from the LMF and carried to the continuous casting machine.

At the continuous caster, molten metal is poured into a preheated tundish and then flows into molds and is allowed to partially cool. The strips of metal are cut into pieces at the caster to form billets. Cooled billets are later reheated in a reheat furnace and rolled to the desired dimensions. The bar steel is descaled using water sprays and the ends of the bars are sheared off. The final product is bound into bundles and stored until shipped offsite.


Emissions from the EAFs and LMF are vented to the Harsell Positive Pressure Baghouse. A general process flow diagram is provided in Figure 3-1.

The baghouse flue gas flow rate will be measured at an inlet location in a section of rectangular duct approximately 193 inches downstream of a bend in the duct and 165 inches upstream of a reduction in duct size. Dimensions of this area of the duct are 131.5 inches by 144

LADLE METALLURGICAL FURNACE



SCRAP



CONTINUOUS CASTER



AUTOMATIC
BANDER

54"
SHEAR





Figure 3-1. Pro

KES, Inc.

EQ

Process Flow Diagram:

Plant Process Flow

Drawing No: 0

Revision: 0

Date: 1/9/98

inches. Six ports on the top of the duct will be sampled, eight points per port, for a total of 48 points. A schematic is shown in Figure 3-2.

Figure 3-3 is a schematic of the baghouse outlet compartments to be sampled for the particulate emissions. A sampling matrix of three by two points, six points per compartment, will be used for sampling purposes. Each compartment will be sampled for 60 minutes. Four compartments will be sampled per test run.

Process information will be collected during the course of the sampling program and will include:

- A) Charge weights and materials, and tap weights and materials
- B)** Heat times, including start and stop times, log of process operation including periods of no operation during testing
- C) Pressure drop across the baghouse, visual inspection of bags and control system fan amperes
- D) Fan/duct damper positions
- E) Fan amperes.

Fan and damper data is monitored continuously electronically. Data will be recorded at 15 minute intervals **during** testing.





Figure 3-2. Inlet Velocity Measurement Location



Proposed KES, Inc. Outlet Sampling Points

Figure 3-3. Schematic of Baghouse Outlet

SECTION 4

QUALITY ASSURANCE AND QUALITY CONTROL

The field sampling quality assurance for this project includes the use of: calibrated source sampling equipment; reference test methods; and traceability protocols for the recording and calculation of data. The analytical quality assurance includes use of validated analytical procedures; calibration of equipment; and analysis of control samples and blanks. The calibration and quality control procedures to be used for this test program are described in the following subsection.

CALIBRATION PROCEDURES AND FREQUENCY

All manual stack gas sampling equipment is calibrated before the test program in accordance with the procedures outlined in the Quality Assurance Handbook for Air Pollution Measurement Systems, Volume 111, EPA-600/4-72-027B. Summarized in Table 4-1 are the stack gas sampling equipment calibrations which are performed in preparation for this project. The meter boxes are re-calibrated after the test.

Listed in Table 4-2 is the additional calibration checks which are performed on the sampling equipment onsite, just prior to the testing, to ensure that equipment was not damaged during transport.

TABLE 4-1. FIELD EQUIPMENT CALIBRATION SUMMARY"

Equipment	Calibrated against	Allowable error
Method 5 meter box	Reference test meter	Y ± 0.02 Y $\Delta H @ \pm 0.15$ post-test Y B.05 Y
Orsat	Certified cylinder gas	$\pm 0.5\%$
Pitot tube	Geometric specifications	See EPA Method 2
Thermocouple	ASTM-3F thermometer	$\pm 1.5\%$
Impinger (or condenser thermometer)	ASTM-3F	$\pm 2^{\circ}\text{F}$
Dry gas thermometer	ASTM-3F	$\pm 5^{\circ}\text{F}$
Probe nozzles	Caliper	k0.004 in.
Barometer	NBS traceable barometer	± 0.1 in. Hg

* As recommended in the Quality Assurance Handbook for Air Pollution Measurement Systems: Volume III. Stationary Source-Specific Methods. EPA-600/4-77-027b, August 1977.

TABLE 4-2. FIELD CHECKS OF SAMPLING EQUIPMENT

Equipment	Checked against	Allowable difference
Pitot tube	Inspection	No visible damage
Thermocouples	ASTM 2F or 3F	$\pm 1.5\%$
Probe Nozzles	Caliper	± 0.004 in.

SECTION 5
PROJECT SCHEDULE

The following tentative schedule outlines the daily activities for this project. The order of sampling events may change based on production schedules.

SCHEDULE			
Day 1	May 10	Arrival at Plant / Safety Orientation / Set up equipment	
Day 2	May 11	Conduct 4 hour particulate sampling	2 Runs
Day 3	May 12	Conduct 4 hour particulate sampling	1 Run

SECTION 6
FINAL REPORT FORMAT

TABLE OF CONTENTS

SECTION 1	INTRODUCTION
SECTION 2	SUMMARY OF TEST RESULTS
SECTION 3	SAMPLING AND ANALYTICAL PROCEDURES
	Location of Measurement Sites
	Stack Gas Volumetric Flow Rate
	Stack Gas Dry Molecular Weight
	Stack Gas Moisture Content
	Particulate Concentration and Mass Emission Rates
SECTION 4	PROCESS DESCRIPTION/SAMPLING LOCATIONS
SECTION 5	QUALITY ASSURANCE/QUALITY CONTROL

APPENDICES

A	CALCULATIONS
B	RAW FIELD DATA
C	ANALYTICAL DATA
D	PROCESS DATA
E	QUALITY ASSURANCE/QUALITY CONTROL

APPENDIX A

COMPLIANCE TEST PROTOCOL FORMS

Commonwealth of Kentucky
Natural Resources and Environmental Protection Cabinet
Department for Environmental Protection
Division for Air Quality
803 Schenkel Lane
Frankfort, Kentucky 40601

COMPLIANCE TEST PROTOCOL

I. SOURCE INFORMATION

A. GENERAL INFORMATION

PLANT NAME Kentucky Electric Steel, Inc. PLANT ID# 21-019-00020
ADDRESS P.O. Box 3500 Ashland, Kentucky 41105 PERMIT ID# V-98-031
PLANT CONTACT Travis Bailey TELEPHONE NO: 6061929-1330
AFFECTED FACILITIES TO BE TESTED Electric Arc Furnaces A and B, Ladle
Metallurgy Furnace and Associated Dust Handling Equipment

TENTATIVE TEST DATE May 11 and 12, 2000

B. PROCESS INFORMATION

MAXIMUM RATED CAPACITY 68 tons/hr (Hot Metal Production from both EAFs)
RATE TO BE RUN DURING TEST Approximately 40 tons/hr
(Permitted rate will be no more than 10% of average test rate)
METHOD OF DETERMINING RATE Records of charge weights and materials, and
tap weights and materials

NORMAL OPERATING CYCLES *(e.g. S hear/day, soot blowing, etc.)* Approximately 20 heats/day
(24 hours/day)

OPERATING CONDITIONS THAT TEND TO CAUSE "WORST CASE" POLLUTION EMISSIONS _____
Attempt to maximize hot metal production

NORMAL MAINTENANCE SCHEDULE FOR EQUIPMENT AFFECTING EMISSIONS _____
Monitor baghouse pressure drop, inspect bags, and monitor control
system fan amperes

INCLUDE A SIMPLIFIED PROCESS FLOW DIAGRAM

COMPLIANCE TEST PROTOCOL CONTINUED

C. CONTROL EQUIPMENT DATA

TYPE AND MANUFACTURER OR ALL CONTROL EQUIPMENT

Harsell Positive Pressure Baghouse, Harsell Engineering Corp.,
Harsell 2400 Bag, 20DW120

DATA TO BE MONITORED AND RECORDED TO ENSURE REPRESENTATIVE OPERATION DURING TEST. AND THEIR OPTIMUM VALUES.

Baghouse Pressure Drop - 5" W.C. (Typical)

Furnace Blower Fan Amperage - 103 Amps (Approximate)

West Fan Amperage - 182 Amps (Approximate)

East Fan Amperage - 183 Amps (Approximate)

OPERATIONAL CYCLES Bags are cleaned with reverse air and via shaking
on an hourly cycle

CONTINUOUS MONITORS None

NORMAL MAINTENANCE SCHEDULE ON CONTROL EQUIPMENT, AND LAST TIME THIS MAINTENANCE WAS PERFORMED.

Maintenance is conducted as needed

COMPLIANCE TEST PROTOCOL CONTINUED

II. SAMPLING DATA

TESTING FIRM NAME Environmental Quality Management, Inc.
 ADDRESS 1310 Kemper Meadow Drive Cincinnati, Ohio 45240
 PERSON TO CONTACT Tom Gerstle TELEPHONE NO: 513/825-7500

LIST ALL AFFECTED FACILITIES TO BE SAMPLED AND GIVE THE INFORMATION REQUIRED BELOW:

Affected Facility	Pollutants	Total Time Per Test	No. of Tests (minimum of 3)	Test Methods To be Used
EAF, LMF EAF, LMF	particulate Matter	240 minutes 240 minutes	3	EPA Methods 1-4 5D, 9

INCLUDE A DIAGRAM OF THE SAMPLING LOCATION WITH DIMENSIONS, PORT LOCATIONS, NUMBER AND LOCATION OF TRAVERSE POINTS, DISTANCES FROM FLOW DISTURBANCES, AND ANY OTHER PHYSICAL OBSTACLES, IN OR AROUND THE STACK

SEE ATTACHED SAMPLING PLAN

A SAMPLING TRAIN INFORMATION

GIVE A DETAILED DESCRIPTION OF ANY SAMPLING OR SAMPLE RECOVERY AND TRANSPORT PROCEDURES WHICH DO NOT COMPLY WITH THE SPECIFIED PROCEDURES AND JUSTIFICATION FOR DEVIATION.

LENGTH OF SAMPLING PROBE 4 ft

PROBE LINER MATERIAL OF CONSTRUCTION Borosilicate Glass

MANUFACTURER OF SAMPLING EQUIPMENT Nutech

AMOUNT OF - L E A KOR-ANALYSIS TO BE DONE ON-SITE Front-half, back-half, and filter recovery will be performed on site

COMPLIANCE TEST PROTOCOL **CONTINUED**

STACK TEMPERATURE 130° F STACK % MOISTURE 2%
STACK GAS VELOCITY 70 FPM

STACK GAS COMPOSITION, INCLUDING APPROXIMATE CONCENTRATION OF ORGANICS _____
O₂ - 20.3%, CO - 0%, CO₂ - 0%, N₂ - 79.7%

FOR INSTRUMENTAL METHODS LIST EXPECTED CONCENTRATIONS, ALLOWABLE CONCENTRATIONS,
INSTRUMENT SPANS, AND CAL GAS CONCENTRATIONS _____

B. LABORATORY ANALYSIS

GIVE DETAILED DESCRIPTION OF ANY ANALYTICAL PROCEDURE AND/OR EQUIPMENT WHICH
DOES NOT COMPLY WITH THE SPECIFIED PROCEDURES AND JUSTIFICATION FOR DEVIATION.

HAVE YOU PARTICIPATED IN ANY EPA INTER-LAB SOURCE AUDITS IN THE LAST YEAR? No
IF SO, LIST THE TYPE OF AUDIT, THE DATE, AND THE RESULT _____

WHAT ARE YOUR CHAIN OF CUSTODY PROCEDURES AND METHOD OF DOCUMENTATION?

All samples will be maintained with a chain of custody form. A
sample form is provided in the attached Sampling Plan

ALL LABORATORY PROCEDURES SHALL HAVE PERTINENT QA DATA SUBMITTED WHETHER OR NOT
THE WORK IS PERFORMED IN-HOUSE OR BY A THIRD PARTY.

C DATA SHEETS SEE ATTACHED SAMPLING PLAN
SUBMIT EXAMPLES OF ALL DATA SHEETS TO BE USED.

APPENDIX B

EXAMPLE DATA SHEETS

FIELD DATA SHEET

Plant: _____

Sample Type: Operator:

Nozzle ID: Thermocouple #:

Sampling Location

Pbar: _____ **Ps:** _____

Assumed Bws: Filter #:

Run Number: _____ Date: _____

C02: **02:**

Meter Box #: Y: ΔH@:

Pretest Leak Rate: cfm @ in. Hg.

Probe Length/Type: Pit #:

Post-Test Leak Rate: cfm @ in. Hg.

Pretest Leak Check: Pitot: Orsat:

Stack Diameter: _____ As: _____

Post-Test Leak Check: Pitot: Orsat:

[illegible]
$$\Delta V_m = \quad \sqrt{\Delta p} = \quad \Delta H = \quad T_a =$$

Tmc _____

GAS VELOCITY AND VOLUMETRIC FLOW RATE

Plant: _____ Date: _____

Sampling Location: _____ Clock Time: _____

Run #: _____ Operators: _____

Barometric Pressure, in. Hg: _____ Static Pressure, in. H₂O: _____

Moisture, %: _____ Molecular wt., Dry: _____ Pitot Tube, Cp: _____

Stack Dimension, in. Diameter or Side 1: _____ Side 2: _____

Wet Bulb, °F: _____ Dry Bulb, °F: _____

[illegible]

$$M_d = (0.44 \times \%CO_2) + (0.32 \times \%O_2) + (0.28 \times \%N_2)$$

$$Md = (0.44 \times \quad) + (0.32 \times \quad) + (0.28 \times \quad)$$

Md =

$$M_s = M_d \times \left(1 - \frac{\% H_2O}{100}\right) + 18 \left(\frac{\% H_2O}{100}\right)$$

$$Ms = (\quad) \times (1 - \frac{\quad}{100}) + 18 (\frac{\quad}{100})$$

$$M_0 =$$

$$\overline{T_B} = \quad {}^\circ F = \quad {}^\circ R \quad ({}^\circ F + 460)$$

$$P_a = P_b + \frac{S.P.}{13.6} = (\quad) + \frac{\quad}{13.8}$$

$P_B =$ _____ in. Hg

$\sqrt{\Delta P} =$

$$V_s = 85.49 \times C_p \times \sqrt{\Delta P} \times \sqrt{\frac{T_s (^{\circ}R)}{P_s \times M_s}}$$

$$V_B = 85.49 \times (\quad) \times (\quad) \times \sqrt{ \quad }$$

$V_8 =$ ft/s

$$A_8 = \pi^2$$

$$Q_s = V_s \times A_s \times 60 \text{ s/m}$$

$\dot{Q}_8 = \quad \times \quad \times 60$

Q8 = actm

$$Q_{s, \text{std}} = Q_s \times 17.647 \times \frac{P_s}{T_s} \times \left(1 - \frac{\% \text{H}_2\text{O}}{100}\right)$$

$$Q_{std} = \quad \times 17.647 \times \frac{\quad}{\quad} \times \left(1 - \frac{\quad}{100}\right)$$

Qs_{std}= dactm

Pacific Environmental Services, Inc.

Dry Molecular Weight Determination

Client/Project: _____

Orsat No. _____

Date/Time: _____

Operator _____

Sample Type: _____

Comments: _____

Ambient Temp. °F _____

Site Location: _____

Run No.(s)	Gas	Run 1		Run 2		Run 3		Average Net Volume %	Multiplier	Molecular Weight of Stack Gas, Md (lb/Mole)
		Actual	Net	Actual	Net	Actual	Net			
	CO ₂								0.44	
	O ₂ ^a								0.32	
	CO ^b								0.28	
	N ₂ ^c								0.28	
									Md =	

Run No.(s)	Gas	Run 1		Run 2		Run 3		Average Net Volume %	Multiplier	Molecular Weight of Stack Gas, Md (lb/Mole)
		Actual	Net	Actual	Net	Actual	Net			
	CO ₂								0.44	
	O ₂ ^a								0.32	
	CO ^b								0.28	
	N ₂ ^c								0.28	
									Md =	

Run No.(s)	Gas	Run 1		Run 2		Run 3		Average Net Volume %	Multiplier	Molecular Weight of Stack Gas, Md (lb/Mole)
		Actual	Net	Actual	Net	Actual	Net			
	CO ₂								0.44	
	O ₂ ^a								0.32	
	CO ^b								0.28	
	N ₂ ^c								0.28	
									Md =	

^a O₂ Net Volume is O₂ actual reading minus CO₂ actual reading.

^b CO Net Volume is CO actual reading minus O₂ actual reading.

^c N₂ Net Volume is 100 minus CO actual reading.

Francis Bailey
Kentucky Electric Steel
PO Box 3500

Ashland, Ky 41105

Dear Sir,

On May 10-12, 2000, personnel from the Kentucky Division of Air Quality
performed particulate compliance tests on Kentucky Electric Steel's Hotwell Open Top
Baghouse. Testing was performed by PES and EPA, of Cincinnati, Ohio, in a satisfactory
manner. The test report was complete and acceptable. Results were as follows

Run	Date	Time	g/dscf	lb/hr
1	5-11	1355-1358	0.0012	4.80
2	5-12	715-1120	0.0014	5.51
3	5-12	1218-1618	0.0007	2.43
			0.0011	4.25

The emissions stated in the report include the break half catch, which is
not used in Kentucky. The allowable emission rate for this source
is 0.052 g/dscf. The baghouse was ~~not~~ in compliance at the time of the test.

CL memo to 24-019-00020
Ashland Regional Office

to Mary Lou
Aug 14 00

EQ Tom Gerette
 PES Dan Schuffel

Shus

May 11 Ky Electric Steel-Eddie Hall 606 929 1200

start 7⁵⁵ V_m 118.747 pt 1 2 3 4 5 6 7 8 dust
 stop 7³⁵ V_m 295.810 Δp .0010% $\rightarrow$ all same baseline vehicle po

On 1100 T_s 130°F final llk $\sqrt{0.001}$ @ 5 mHg pitot llk ✓ ok

fugitives from ^{melt} shop roof at 2:44 p, 3:55 p, 5:51 p

line handling taghome emissions at 3:56 p

May 12 2000 J.E.

start 7¹⁵ V_m 296.400 ^{port @ 100m top} 1 2 3 4 5 6 7 8
 1.8 1.9 1.5 1.6 1.9 2.1 2.9 2.3

stop 11²⁰ V_m 443.789 0.000993 $\rightarrow$ all same baseline


T_s ~160°F D 1.240 final llk $\sqrt{0.001}$ @ 4 mHg pitot llk ✓ ok

opacity from shop roof at 8:44^A 9:45^A

start 12¹⁸ V_m 404.320 pt ^A 1 2 3 4 5 6 7 8
 stop 4⁰⁰ V_m 672.672 Δp ^{bottom} 1.3 1.8 1.0 1.7 1.9 1.8 2.1 2.0

On T_s final llk $\sqrt{0.003}$ @ 5 mHg pitot llk ✓ ok

fugitives from melt shop roof 1:37 p, 2:03 p, 3:58 p, 4:04 p, 4:13 p



F A X

Date of Transmittal: 7/28/00

Time of Transmittal: 0645

Number of Pages (including cover): 4

To Verify Receipt, Call: (513) 825 7500

To: JOHN JAYNE Phone No: _____

Company: KY DAO

Fax No: 502-573-3787

From: TOM GARSTLE


Message:


SCHEMATIC OF KES DIRT LAYOUT. THIS IS A COPY OF THE LARGER
DRAWING I HAD. THE CORRECT OVERLAP TO MAKE A CARRIER
FIGURE.


PLEASE CALL IF YOU NEED ANYTHING ELSE.

Tom

Environmental Quality Management, Inc.
1310 Kemper Meadow Drive, Cincinnati, Ohio 45240
Tel: (513) 825-7500, Fax: (513) 825 7495







STACK TEST REVIEW

NAME Ky Electric Steel TEST NO. _____

SOURCE TYPE Hassell Positive Pressure Baghouse RUN NO. B0-3

MODEL OR NAME _____ DATE OF TEST 5-12-00 12:18-16:18

TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>29.45</u> °F P_s , Stack pressure <u>29.44</u> in. Hg T_m , Meter temperature <u>97</u> °F P_m , Meter pressure <u>29.57</u> in. Hg M_w , Condensed water <u>93.0</u> gm V_{DGM} , Volume of sample (meter conditions) <u>178.352</u> cf <u>80.988</u>	V_{H_2O} , Volume of water <u>4.378</u> cf B_{wo} , Moisture of content <u>2.6%</u> V_{ne} , Volume of sample at stack cond. <u>165.017</u> cf M_{dry} , Molecular wt dry <u>28.84</u> M_{wet} , Molecular wt wet <u>28.56</u> Velocity <u>1.65</u> f/s <u>25,754.736</u> DSCF/hr
CO_2 <u>0.0</u> % O_2 <u>21.0</u> % CO_2 <u>0.0</u> % N_2 <u>79.0</u> %	Isokinetic Ratio <u>1.03</u> gr/scf <u>8.0007</u>
AP , Velocity head <u>0.00763</u> in. H ₂ O (traverse points) C_p , Pitot tube coeff. <u>0.84</u>	Lb/Hr $Lb/mm BTU$
240 min x 60 θ , Sampling time _____ sec. A_n , area of nozzle $D=1.240"$ <u>0.00839</u> ft ² D^2_x <u>0.005454</u>	
Weight of collected pollutant <u>7.05 mg</u> gm CO_2 , Waste only _____ %	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
A_s , Area of stack $D=$ ft $\frac{D^2}{4} \pi$ <u>5381</u> ft ²	
Boiler Heat Capacity _____ mmBTU/Hr.	

REMARKS

$$F = \frac{0.0945 V_{m,s} (460 + T_s)}{(1 - B_{w,s}) P_s D_n V_s \theta}$$

$$\frac{7.05 \text{ mg}}{165.017 \text{ DSCF}} \frac{\text{gm}}{1000 \text{ mg}} \frac{7000 \text{ gr}}{\text{lb}} \frac{\text{lb}}{453.59 \text{ gm}}$$

$$V = \frac{Q_s}{A_o} \frac{T_o}{T_s}$$

$$1.65 = \frac{(33296.079 + 39612.842)}{5381} \frac{(460 + 168)}{(460 + \frac{146 + 191}{2})} \frac{\text{hr}}{3600 \text{ sec}}$$

STACK TEST REVIEW

NAME Kentucky Electric Steel TEST NO. _____

SOURCE TYPE Hand Positive Pressure Baghouse RUN NO. B0-1

MODEL OR NAME _____ DATE OF TEST 5-11-00 1355- 1945

TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>29.60</u> <u>145</u> °F P_s , Stack pressure <u>29.59</u> in.Hg. T_m , Meter temperature <u>94</u> °F P_m , Meter pressure <u>29.7</u> in.Hg. M_w , Condensed water <u>43.5</u> gm V_{DGM} , Volume of sample (meter conditions) <u>173.319</u> cf <u>28 0.988</u>	V_{H_2O} , Volume of water <u>2.048</u> cf B_{wo} , Moisture of content <u>1.320</u> V_{ne} , Volume of sample at stack cond. <u>161.774</u> cf M_{dry} , Molecular wt dry <u>28.84</u> M_{wet} , Molecular wt wet <u>28.70</u> Velocity <u>1.76</u> fps <u>29,017,380 DSCF/hr</u>
CO_2 <u>0.0</u> % O_2 <u>21.6</u> % CO_2 <u>0.0</u> % N_2 <u>24.0</u> %	Isokinetic Ratio <u>1.10</u> gr/scf <u>0.0012</u> <u>no back buff</u>
AP, Velocity head <u>0.001036</u> in.H ₂ O <u>0.032187</u> (traverse points) C_p , Pitot tube coeff. <u>0.84</u>	Lb/Hr Lb/mm BTU
<u>300</u> min x 60 ϕ , Sampling time _____ sec. A_n , area of nozzle $D=1.00$ " <u>0.005454</u> ft ² $D^2 \times 0.005454$	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
Weight of collected <u>30304</u> <u>12.15</u> gm pollutant CO_2 , Waste only _____ %	
A_s , Area of stack $D=$ ft <u>18.5</u> " $\frac{D^2}{4} \pi$ <u>538.1</u> ft ² <u>18.5</u> " x <u>15.45</u> "	
Boiler Heat Capacity _____ mmBTU/Hr.	

REMARKS

$$\bar{V} = \frac{Q_L}{A_0} \frac{T_0}{T_1} \quad Q_L = Q_{10} + 10$$

$$1.76 \frac{ft}{sec} = \frac{67112.210 \frac{(460+145)}{5381 ft^2 (460+136)_{avg}}}{3600 sec}$$

STACK TEST REVIEW

NAME Kentucky Electric Steel TEST NO. _____

SOURCE TYPE Harsell Positive Pressure Baghouse RUN NO. 130-2

MODEL OR NAME _____ DATE OF TEST 5-12-00 7¹⁵ 11²⁰

TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>29.45</u> °F P_s , Stack pressure <u>16.2</u> in. Hg. T_m , Meter temperature <u>29.44</u> °F P_m , Meter pressure <u>87</u> in. Hg. M_w , Condensed water <u>29.67</u> gm V_{DGM} , Volume of sample (meter conditions) <u>101.1</u> cf <u>192.399</u> cf <u>80.988</u>	V_{H_2O} , Volume of water <u>4.754</u> cf B_{wo} , Moisture of content <u>2.5%</u> V_{ne} , Volume of sample at stack cond. <u>186.787</u> cf M_{dry} , Molecular wt dry <u>28.84</u> M_{wet} , Molecular wt wet <u>28.57</u> Velocity <u>1.70</u> fps <u>QSD 26,818,676 DSCF/hr</u>
CO_2 <u>0.0</u> % O_2 <u>21.0</u> % CO_2 <u>0.0</u> % N_2 <u>79.0</u> %	Isokinetic Ratio <u>1.09</u> gr/scf <u>REMOVED</u> <u>0.0014</u>
AP , Velocity head <u>0.000993</u> in. H ₂ O (traverse points) <u>0.03151</u> C_p , Pitot tube coeff. <u>0.84</u>	Lb/Hr Lb/mm BIU
<u>240</u> min x 60 Θ , Sampling time _____ sec. A_n , area of nozzle D=1.240 " <u>0.00839</u> ft ² D^2_x 0.005454	
Weight of collected <u>300382</u> <u>17.40</u> gm pollutant CO_2 , Waste only _____ %	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
A_s , Area of stack D= ft <u>D2</u> π <u>5381</u> ft ² <u>4</u>	
Boiler Beat Capacity _____ mmBTU/Hr.	

REMARKS

$$\bar{U} = \frac{Q_n}{A_o} \frac{T_o}{T_n}$$

$$1.70 \frac{ft}{sec} = \frac{(32,293,420 + 332,96,079) \frac{lb}{hr}}{5381} \frac{(460 + 162)}{(460 + (\frac{460 + 162}{2}))} \frac{1}{3600 sec}$$

STACK TEST REVIEW

NAME Key Electric Steel TEST NO. _____
 SOURCE TYPE Harsco Products Process Control RUN NO. Prelim 2/3 fans; one 900amps fan off
 MODEL OR NAME _____ DATE OF TEST 5-10, 2000 15:15
 TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>156</u> °F P_s , Stack pressure <u>29.63</u> in.Hg. T_m , Meter temperature _____ °F P_m , Meter pressure _____ in.Hg. M_w , Condensed water _____ gm V_{DGM} , Volume of sample (meter conditions) <u>8</u> cf	$V_{w,0}$, Volume of water _____ cf $B_{w,0}$, Moisture of content <u>1% assumed</u> V_{ne} , Volume of sample at stack cond. _____ cf M_{dry} , Molecular wt dry <u>28.84</u> M_{wet} , Molecular wt wet <u>28.73</u> Velocity <u>49.55</u> fps <u>Asp 19,711, 920 DSCF/in</u>
CO_2 _____ % O_2 _____ % CO_2 _____ % N_2 _____ %	Isokinetic Ratio _____ gr/scf @ 12% CO_2 _____
AP , Velocity head <u>0.658039</u> in.H ₂ O (traverse points) <u>811.196</u> C_p , Pitot tube coeff. <u>0.84</u>	Lb/Hr _____ Lb/mm BTU _____
_____ min x 60 θ , Sampling time _____ sec. A_0 , area of nozzle D= " _____ ft ² $D^2 \times 0.005454$	
Weight of collected _____ gm pollutant CO_2 , Waste only _____ %	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
A_3 , Area of stack $D = \frac{ft}{4} \frac{D2}{4} \pi$ <u>131.5</u> ft ² <u>10'11 1/2" x 12'</u>	
Boiler Heat Capacity _____ mmBTU/Hr.	

REMARKS

$$\bar{V} = \frac{Q_1}{A_0} \cdot \frac{T_0}{T_1}$$

STACK TEST REVIEW

NAME Ky Electric Steel TEST NO. _____

SOURCE TYPE Hassell Products Inc. Baghouse RUN NO. 2000

MODEL OR NAME _____ DATE OF TEST 5-10, 2000

TEST PERFORMED BY EQ/PES

DATA REQUIRED		RESULTS	
T_s , Stack temperature	<u>155</u> °F	V_{H_2O} , Volume of water	_____ cf
P_s , Stack pressure	<u>29.87</u> in. Hg.	R_{wo} , Moisture of content	<u>12%</u>
T_m , Meter temperature	_____ °F	V_s , Volume of sample	_____ cf
P_m , Meter pressure	_____ in. Hg.	at stack cond.	_____ cf
M_w , Condensed water	_____ gm	M_{dry} , Molecular wt dry	<u>28.84</u>
V_{DGM} , Volume of sample (meter conditions)	_____ cf	M_{wet} , Molecular wt wet	<u>28.73</u>
		Velocity	<u>79.96</u> fms
			<u>32,054,867</u> DSCF/hr
CO_2	%	Isokinetic Ratio	_____
O_2	%		_____
CO_2	%		gr/scf @ 12% CO_2
N_2	%		_____
AP, Velocity head	<u>172648</u> in. H_2O	Lb/Hr	_____
(traverse points)			_____
C_p , Pitot tube coeff.	<u>0.84</u>	Lb/mm BIU	_____

	_____ min x 60		
θ , Sampling time	_____ sec.		
A_n , area of nozzle	$D = \frac{1}{4}$ ft		
$D^2 \times 0.005454$			
Weight of collected pollutant	_____ gm	REQUESTED BY	_____
CO_2 , Waste only	_____ %	REVIEWED BY	_____
		DATE	_____
A_s , Area of stack		RECOMMENDATION	_____
$D = \frac{ft}{4} \pi$	<u>131.5</u> ft ²		_____
$10'11\frac{1}{2}'' \times 12'$			
Boiler Heat Capacity	_____ mmBTU/Hr.		

REMARKS

STACK TEST REVIEW

NAME ky Electric Steel

TEST NO. _____

SOURCE TYPE Haskell Products Inc. B.

RUN NO. pidem^{id} 2/3 fans, 900amp fan down

MODEL OR NAME _____

DATE OF TEST 5-12, 1930

TEST PERFORMED BY EQ/PES

DATA REQUIRED	RESULTS
T_s , Stack temperature <u>29.45</u> °F P_s , Stack pressure <u>29.75</u> in. Hg T_m , Meter temperature _____ °F P_m , Meter pressure _____ in. Hg M_w , Condensed water _____ gm V_{DGM} , Volume of sample (meter conditions) <u>8</u> cf	V_{H_2O} , Volume of water _____ cf B_{wo} , Moisture of content <u>18.5%</u> V_{ne} , Volume of sample at stack cond. _____ cf M_{dry} , Molecular wt dry <u>28.84</u> M_{wet} , Molecular wt wet <u>28.73</u> Velocity <u>68.82</u> fps <u>Q_{SD} 26,835,310 DSCF/hr</u>
CO_2 _____ % O_2 _____ % CO_2 _____ % N_2 _____ %	Isokinetic Ratio _____ gr/scf @ 12% CO_2 _____
AP, Velocity head <u>1.24393</u> in. H_2O (traverse points) C_p , Pitot tube coeff. <u>0.84</u> _____ min x 60 θ , Sampling time _____ sec. A_n , area of nozzle D= _____ ft ² $D^2 \times 0.005454$	Lb/Hr _____ Lb/mm BIU _____
Weight of collected _____ gm pollutant CO_2 , Waste only _____ % A_s , Area of stack D= ft $\frac{D^2}{4} \pi$ <u>131.5</u> ft ² <u>10'11 1/2" x 12'</u>	REQUESTED BY _____ REVIEWED BY _____ DATE _____ RECOMMENDATION _____
Boiler Heat Capacity _____ mmBTU/Hr.	

REMARKS